


SEDIMENT NOTE:

1. NO STOCKPILING OF MATERIALS IS PERMITTED ON THE VERGE BETWEEN KERB & PROPERTY BOUNDARY.
2. NO VEHICLE CROSSING OR STOCKPILING OF MATERIAL ON VEGETATION BUFFER.
3. ALL SEDIMENT RETAINING STRUCTURES TO BE CLEANED ON REACHING 50% STORAGE CAPACITY.
4. ALL EXISTING VEGETATION WILL BE RETAINED OUTSIDE THE CONSTRUCTION SITE.
5. ROOF DRAINAGE IS TO BE CONNECTED TO THE STORMWATER SYSTEM AS SOON AS PRACTICABLE.
6. DEPRESSIONS LEFT IN THE FOOTPATH BY HEAVY TRUCKS ARE TO BE FILLED AS SOON AS POSSIBLE.
7. ONLY ONE EXIT POINT SHOULD BE USED & SHOULD BE CONSTRUCTED SO AS TO PREVENT SOIL REACHING THE ROAD & TO STOP BOGGING.
8. DRAINAGE DITCHES ABOVE & BELOW CUT & FILLED AREAS ARE TO REDUCE EROSION FROM DISTURBED GROUND.



TEMPORARY CONSTRUCTION FENCE
SEDIMENT CONTROL FENCE



40°06'10"
20.22

Colorbond Fence
6.095
129°57'30"

SP 61769



Ridge
30.91
2 STY
BRICK DUPLEX
RESIDENCE
(tile roof)
No 12

Balcony
Garage

O'head Wire
3.9m clear
of Ground

BENCH MARK
DRILL HOLE
IN VC
RL 23.24 (AHD)

RAINE

RD

SEDIMENT CONTROL PLAN

OWNER(S) ACCEPTANCE

I/WE HEREBY APPROVE OUR BUILDING PLANS TO BE BUILT ON OUR LAND.

I/WE HAVE STUDIED THE PLANS AND HAVE HAD THEM EXPLAINED TO US AND ACCEPT AND APPROVE THE FRONT/REAR/SIDE SETBACKS AND CUT/FILL LEVELS AS SHOWN ON THE PLAN.

I/WE ACCEPT NO CHANGES CAN BE MADE.

I/WE HAVE HAD THE DRIVEWAY GRADIENT EXPLAINED.

I/WE HAVE HAD THE BASIX WATER TANK OR THE DUAL WATER PLUMBING EXPLAINED.

I/WE HAVE HAD OUR CHOSEN ALTERATIONS/VARIATIONS EXPLAINED TO US.

I/WE HEREBY APPROVE OUR PLANS AND GIVE CONSENT TO ALLCASTLE HOMES P/L TO LODGE OUR PLANS TO APPROVING AUTHORITY FOR A DEVELOPMENT APPLICATION.

I/WE UNDERSTAND THAT NO FURTHER PHYSICAL CHANGES CAN BE MADE I/WE UNDERSTAND THAT DUE TO CONSTRUCTION CONSTRAINTS, THE BUILDER MAY VARY PLANS ON SITE TO SUIT.

I/WE UNDERSTAND ANY SURFACE DRAINAGE OR RETAINING WALLS REQUIRED BY APPROVING AUTHORITY ARE TO BE COMPLETED WITH LANDSCAPING BY OWNER

OWNER _____ OWNER _____ DATE _____

05.05.26JD	D	DA SET
15.04.26JD	C	SUBDIVISION LINE AMENDED + DWELLING LEVEL DROPPED
07.04.26JD	B (T04)	VAR. 15-21 + HI SLAB
05.03.26	A (T03)	FIRST DRAW

DATE ISSUE REVISION

NOTE: ALL WORKS TO COMPLY WITH BCA 2022 AND RELEVANT AUSTRALIAN STANDARDS
- NOTE: ALL WALLS WITHIN 900mm OF BOUNDARY TO BE 60/60/60 - ALL DIMENSIONS ARE IN MILLIMETRES - ALL DIMENSIONS ARE FRAME TO FRAME DO NOT SCALE - USE WRITTEN DIMENSIONS - THIS DRAWING IS SUBJECT TO COPYRIGHT LAWS AND MAY NOT BE COPIED WITHOUT THE WRITTEN PERMISSION OF ALLCASTLE HOMES PTY LTD.
- ABN 12057 761 378

ALLCASTLE HOMES PTY LTD WILL TAKE NO RESPONSIBILITY FOR ANY VERBAL DISCUSSIONS OR INSTRUCTIONS. ALL CHANGES AND SPECIAL INCLUSIONS MUST BE DOCUMENTED IN WRITING. IT IS THE RESPONSIBILITY OF THE OWNER TO ENSURE THAT THE LAYOUT AND ALL SPECIAL INCLUSIONS ARE CORRECT. NOTE: WET AREA SYMBOLS ARE STRICTLY SYMBOLIC, OWNERS TO CONFIRM WET AREA ITEMS WITH SELECTIONS.

PROPOSED RESIDENCE		CUSTOM DUPLEX	
MODIFIED STELLA FACADE			
FOR: Mr. B KATBAY	DATE: 04.03.26	SCALE: 1:200	
	DRAWN: DI	CHECKED:	
AT: LOT B (#14) RAINE ROAD, PADSTOW	SHEET NO: 10	JOB NO: 8058	

SALES: PHONE: (02) 9629 4772
FAX: (02) 9629 5813
HEAD 96-100 TOONGABBIE ROAD,
OFFICE: GIRRAWEEN NSW 2145
PHONE: (02) 9672 7055
FAX: (02) 9672 7033
ABN: 12057761378 BLDG.LIC.39371

Allcastle Homes

Make it Home

allcastlehomes.com.au