

**PLANNING PROPOSAL FOR  
MIXED USE DEVELOPMENT**  
**311 HUME HIGHWAY, LIVERPOOL**  
*Assessment of Traffic and  
Parking Implications*

January 2015  
(Rev D)

Reference 14303

TRANSPORT AND TRAFFIC PLANNING ASSOCIATES  
Transportation, Traffic and Design Consultants  
Suite 502, Level 5  
282 Victoria Avenue  
CHATSWOOD 2067  
Telephone (02) 9411 5660  
Facsimile (02) 9904 6622  
Email: ross@ttpa.com.au

TABLE OF CONTENTS

|    |                                                  |    |
|----|--------------------------------------------------|----|
| 1. | INTRODUCTION .....                               | 1  |
| 2. | PROPOSED PLANNING PROPOSAL .....                 | 2  |
|    | 2.1 Site, Context and Existing Use .....         | 2  |
|    | 2.2 Approved Development .....                   | 2  |
|    | 2.3 Envisaged Development .....                  | 3  |
| 3. | ROAD NETWORK AND TRAFFIC CONTROLS .....          | 4  |
|    | 3.1 Road Network.....                            | 4  |
|    | 3.2 Traffic Controls.....                        | 4  |
|    | 3.3 Traffic Conditions .....                     | 5  |
|    | 3.4 Transportation Services .....                | 5  |
| 4. | TRAFFIC .....                                    | 7  |
| 5. | ACCESS, INTERNAL CIRCULATION AND SERVICING ..... | 9  |
| 6. | PARKING .....                                    | 10 |
| 7. | CONCLUSION .....                                 | 13 |

|            |                                |
|------------|--------------------------------|
| APPENDIX A | APPROVED PLANS                 |
| APPENDIX B | PLANS OF ENVISAGED DEVELOPMENT |
| APPENDIX C | EXTRACTS FROM TRAFFIC REPORT   |
| APPENDIX D | INTERSECTION PLAN              |

LIST OF ILLUSTRATIONS

|          |                                       |
|----------|---------------------------------------|
| FIGURE 1 | LOCATION                              |
| FIGURE 2 | SITE                                  |
| FIGURE 3 | ROAD NETWORK                          |
| FIGURE 4 | TRAFFIC CONTROLS                      |
| FIGURE 5 | APPROXIMATE INTERSECTION TRAFFIC FLOW |
| FIGURE 6 | TRAFFIC DISTRIBUTION                  |

# 1. INTRODUCTION

This report has been prepared to accompany a Planning Proposal to Liverpool City Council to permit an envisaged residential apartment based mixed use development on a site at 311 Hume Highway in the southern sector of the Liverpool City Centre (Figure 1).

Development activity in Liverpool CBD in recent times has largely been focused on the northern sector, while development in the western and southern sectors has been limited and many sites remain underutilised. The Liverpool City Centre offers considerable advantages for major residential based development of underutilised sites due to:


- \* the close proximity of primary public transport services (rail and buses)
- \* the convenient proximity to employment, shopping and entertainment facilities available in the centre along with the nearby educational and hospital/medical services

There have been two previous consents granted for development on the site and the now envisaged development scheme, subject to approval of the Planning Proposal, comprises:

- 304 residential apartments
- Retail floor space (163 m<sup>2</sup>)
- Basement parking

The purpose of this report is to:

- \* describe the proposed development
- \* describe the road network serving the site and the prevailing traffic conditions
- \* assess the adequacy of the proposed parking provision
- \* assess the potential traffic implications
- \* assess the proposed vehicle access, internal circulation and servicing arrangements





2. PROPOSED PLANNING PROPOSAL

2.1 SITE, CONTEXT AND EXISTING USE

The site (Figure 2), being Lot 71 of DP 1004792, occupies an area irregular shaped all with frontages to Hume Highway, Hoxton Park Road and Gillespie Street located on the southern edge of the CBD.

The site is cleared and partially excavated while the surrounding landuses comprise:

- \* the Collingwood Hotel which adjoins to the south
- \* the vacant commercial building which adjoins to the west
- \* the commercial uses which extend along the highway and the residential areas extending to the south and west
- \* the Liverpool CBD and medical precinct which is located just to the north-east

2.2 APPROVED DEVELOPMENT

Two Consents have been previously granted for proposed developments on the site with the most recent (which was substantially commenced with basement excavation) comprising:

|             |                                                |
|-------------|------------------------------------------------|
| Retail      | 3,036m <sup>2</sup> GLFA (supermarket & shops) |
| Commercial  | 800m <sup>2</sup>                              |
| Residential | 124 apartments                                 |
| Parking     | 277 spaces                                     |

Vehicle access was located on Gillespie Street and there was a Consent Condition for the provision of traffic signals at the Hoxton Park Road and Gillespie Street intersection.









Details of the approved development are provided on the architectural plans provided in part in Appendix A.

2.3 ENVISAGED DEVELOPMENT

It would be proposed to complete the excavation of the site to provide for basement car parking and a level building platforms to enable construction of a 30 storey tower and two 7 storey buildings.

The envisaged development comprises:

|                               |                       |
|-------------------------------|-----------------------|
| <b>Residential Apartments</b> |                       |
| <b>Tower</b>                  |                       |
| One-bedroom apartments x 34   |                       |
| Two-bedroom apartments x 233  |                       |
| Three-bedroom apartments x 37 |                       |
| <b>Total:</b>                 | <b>304 apartments</b> |
|                               |                       |
| Retail Floor Space            | 163 m <sup>2</sup>    |
| Carpark                       | 348 spaces            |

Vehicle access will be located on the Gillespie Street frontage.

Architectural details of the development scheme are shown on the plans prepared by Design Workshop Australia which accompany the Development Application and are reproduced in part in Appendix B.

3. ROAD NETWORK AND TRAFFIC CONTROLS

3.1 ROAD NETWORK

The road network serving the site (Figure 3) comprises:

- \* *South-western (M5) Motorway* – a State Road and arterial route
- \* *Hume Highway* – a State Road and arterial route
- \* *Cumberland Highway* – a State Road and arterial route
- \* *Elizabeth Drive* – a State Road and arterial route
- \* *Newbridge Road/Terminus Street/Macquarie Street* – a State Road and arterial route
- \* *Hoxton Park Road* – a State Road and sub-arterial route linking between Hume Highway and Cowpasture Road
- \* *Gill Avenue and Reilly Street* – minor collector road routes connecting to Hoxton Park Road and Hume Highway

Gillespie Street and Pearce Avenue are local access roads being some 13m wide.

3.2 TRAFFIC CONTROLS

The existing traffic controls on the road system in the vicinity of the site (Figure 4) comprise:

- \* the traffic control signals at the Macquarie Street/Hume Highway/Hoxton Park Road intersections
- \* the traffic control signals at the Macquarie Street/Terminus Street and Bathurst Street/Memorial Avenue intersections






#### LEGEND

- ARTERIAL
- SUB-ARTERIAL
- COLLECTOR



### ROAD NETWORK

FIG 3



#### LEGEND

- TRAFFIC SIGNAL CONTROL
- ROUNDABOUT
- RESTRICTED TURNING MOVEMENT



### TRAFFIC CONTROLS

FIG 4



- \* the central median island along the Hume Highway which restricts movements to left-turn IN/OUT of Atkinson Street and Passefield Street
- \* the traffic signal control at the Hoxton Park Road and Gill Avenue intersection
- \* the roundabouts along Gill Avenue at the Atkinson Street, Rose Street and Reilly Street intersections
- \* the GIVEWAY sign controls at the Gill Avenue and Pearce Street intersection
- \* the NO STOPPING and CLEARWAY restrictions along Hume Highway and Hoxton Park Road
- \* the 50 km/h speed restriction within the local road network and 60 kmph on Hume Highway and Hoxton Park Road

3.3 TRAFFIC CONDITIONS

An indication of the traffic conditions on the road system serving the site is provided by the most recently published Roads and Maritime Services (RMS) traffic data. The data is expressed in Average Annual Daily Traffic (AADT) and is provided as follows:

|                                          | AADT   |
|------------------------------------------|--------|
| Copeland Street, West of Memorial Avenue | 72,450 |
| Hoxton Park Road, West of Hume Highway   | 27,150 |
| Terminus Street, East of Hume Highway    | 30,222 |


Available traffic surveys of intersections in the vicinity of the site provide the generalised peak traffic flows at intersections as indicated on Figure 5.

3.4 TRANSPORTATION SERVICES

The development site is ideally located in relation to high capacity and frequent public transport services. Liverpool City Centre (CBD) is the transport ‘hub’ for south-west Sydney comprising extensive railway and bus network connections and the development site is located within easy walking distance to bus services connecting to the CBD.

Numerous bus services including Westbus, Busabout and Liverpool Transport pass the site along Hume Highway while other services along the transitway are only a short distance away to the west.





## 4. TRAFFIC

The Roads and Maritime Services Development Guidelines<sup>1</sup> provide indicative traffic generation rates in relation to specific landuse types based on surveys of a wide range of locations and circumstances which are aggregated.

The recent RMS Technical Direction (TDT 2013-4b) in relation to 'high density' residential apartments with good access to public transport services specify a traffic generation characteristic of 0.19 and 0.15 vph per unit during the on-street peak periods (AM and PM respectively). Application of these rates to the proposed residential element of the envisaged development scheme (304 apartments) would indicate a traffic generation during the peak traffic periods of some 58 vph and 46 vph during the AM and PM peaks respectively.

The RMS rate for retail traffic generation is for retail centres and therefore is not appropriate to the retail floorspace and it is only envisaged that there will be 2 retail parking spaces utilised by tenants indicating an arrival/departure rate of only 1 vph in the peak periods.

Application of these factors to the development scheme indicates generation of:

|               | AM        |           | PM        |           |
|---------------|-----------|-----------|-----------|-----------|
|               | IN        | OUT       | IN        | OUT       |
| Residential   | 11        | 47        | 37        | 9         |
| Retail        | 1         | -         | -         | 1         |
| <b>Total:</b> | <b>12</b> | <b>47</b> | <b>37</b> | <b>10</b> |

<sup>1</sup> RMS Technical Direction TDT-2013 (4b)




Prior to the demolition of existing buildings for the previously approved development there was a mixture of commercial uses on the site which generated a moderate level of vehicle activity. The traffic assessment<sup>2</sup> undertaken for the most recently approved development on the site established projected peak generation rates of 113 vph in the morning and 451 vph in the afternoon (see extracts in Appendix C).

Consent for the previous development involved the provision of traffic signals at the Hoxton Park Road and Gillespie Street intersection as indicated on the design plan which incorporates peak period right turn prohibition (refer to Appendix D). Recent discussions with Council in relation to the now envisaged development indicate that Council (and presumably RMS) would prefer to formerly prohibit the right turn movements to/from Gillespie on this basis:

- \* vehicles departing the site to travel north, south or east will either access the highway via Rose Street or Reilly Street or access Hoxton Park Road via Gill Avenue
- \* vehicles approaching the site from the west will turn into Gill Avenue from Hoxton Park Road

The distribution of the projected 59 vph in the morning and 47 vph in the afternoon (two way) as indicated on Figure 6 will be diverse and will not result in any adverse traffic implications (particularly when compared with that of the previously approved development on the site).

2 Proposed Residential and Retail Development  
Cnr Hume Highway and Hoxton Park Road, Liverpool  
Traffic and Parking Assessment  
Traffic Solutions, Sept 2002



5. ACCESS, INTERNAL CIRCULATION AND SERVICING

ACCESS

Vehicle access for the site will be provided by a combined ingress/egress driveway on the Gillespie Street frontage. This access point will be located where there are excellent sight distances and will comply with the design requirements of AS2890.1.

INTERNAL CIRCULATION

A simple and efficient one way access ramp and aisle circulation system will be provided through the carpark levels. The aisles, ramps, parking bays and manoeuvring areas will be designed to accord with AS2890.1 and 6.

SERVICING

Refuse will be removed from the street by Council’s collection service. Small vehicles (eg service personnel/couriers etc) will be able to use the visitor parking spaces while occasional needs of larger service vehicles (eg furniture pantechnicons etc) will be accommodated on the available on-street kerbspace as is normal for a residential apartment development of this nature.

6. PARKING

Car Parking

Car parking for retail and commercial developments within the Liverpool CBD are subject to the Liverpool Local Environmental Plan (LLEP) 2008 while Liverpool Development Control Plan (LDCP) 2008 applies to residential components of all developments.

The LLEP specifies a minimum parking provision for development as follows:

*‘Development consent must not be granted to development on land in the Liverpool city centre that is in Zone B3 Commercial Core or B4 Mixed Use that involves the erection of a new building or an alteration to an existing building that increases the gross floor area of the building unless:*

- (a) at least one car parking space is provided for every 200 m<sup>2</sup> of any new gross floor area that is on the ground floor level of the building, and*
- (b) in respect of any other part of the building:*
  - at least one car parking space is provided for every 100 m<sup>2</sup> of any new gross floor area that is to be used for the purposes of retail premises, and*
  - at least one car parking space is provided for every 150 m<sup>2</sup> of any new gross floor area that is to be used for any other purpose.’*

Application of the above criteria to the retail component would indicate a minimum parking requirement as follows:

|                              | Minimum Requirement |
|------------------------------|---------------------|
| Retail (163 m <sup>2</sup> ) | 2 spaces            |



The residential component of the development is subject to LDCP control, which is provided in the following:

|       | Minimum Requirement |
|-------|---------------------|
| 1-bed | 1 space per unit    |
| 2-bed | 1 space per unit    |
| 3-bed | 1.5 space per unit  |

Application of the above criteria indicates the following requirements:

|              | No. of spaces     |
|--------------|-------------------|
| 34 x 1-bed   | 34 spaces         |
| 233 x 2-bed  | 233 spaces        |
| 37 x 3-bed   | 56 spaces         |
| <b>Total</b> | <b>323 spaces</b> |

The quantum of visitor spaces becomes skewed in larger developments and significant urban renewal and infrastructure developments within the Liverpool CBD have resulted in similar ‘city’ characteristics to the Sydney CBD, in particular the convenience of public transport services along with increased reliance on these services. It is therefore proposed to provide visitors’ parking in accordance with the Sydney LEP rates which largely reflect a CBD locality and accessibility.

The City of Sydney LEP 2012 rate for visitor parking are as follows:

|                         | Rate                 |
|-------------------------|----------------------|
| 0-30 apartments         | 0.167 space per unit |
| 30-70 apartments        | 0.1 space per unit   |
| 70 and above apartments | 0.05 space per unit  |

Application of the above criteria to the proposed 304 apartments would indicate a requirement of 21 visitor spaces.

Having regard to both the LLEP and LDCP requirements along with the ‘CBD’ nature of the site location it is proposed to provide a total of 348 car parking spaces within the car park with the following composition:

|              |                   |
|--------------|-------------------|
| Residents    | 323 spaces        |
| Visitors     | 23 spaces         |
| Retail       | 2 spaces          |
| <b>Total</b> | <b>348 spaces</b> |

The proposed provision of 23 spaces for visitors in a conveniently located site with close proximity to city centre and excellent transport services is considered to be satisfactory and will not result in adverse parking implications. It is apparent that the overall provision of 348 spaces will essentially provide a balanced outcome which will be adequate for the proposed development.

**Bicycles and Motorcycles**

There is no specification for bicycle provision within the LLEP therefore assessment in relation to the appropriate provision for motorcycles and bicycles is made with reference to LDCP 2008 as follows:

|                  | Bicycles                       | Motorcycles         |
|------------------|--------------------------------|---------------------|
| All developments | - 1 per 200 m <sup>2</sup> GFA | 1 per 20 car spaces |

It is proposed to provide 134 bicycle storage spaces (residents bicycles could be in store areas) and 18 motorbike spaces in the basement carpark and this will be entirely compliant with Council’s code.

7. CONCLUSION

---

The envisaged development (subject to approval of the Planning Proposal) reflects a contemporary outcome for the Liverpool CBD reflecting other nearby current development processes. The development scheme will take advantage of the excellent public transport services which are available and the convenient access available to the arterial road system.

The assessment provided in this report confirms that:

- \* the potential traffic generation of the development will be satisfactorily accommodated on the road system (and will be substantially less than that of the previously approved development on the site)
- \* the envisaged vehicle access, internal circulation and turning arrangements will be satisfactory
- \* there will not be any unacceptable road safety and traffic related environmental implications
- \* a suitable and appropriate parking provision can be made in relation to the needs of the development

Appendix A

APPROVED PLANS

---





01 EAST ELEVATION  
ALONG HUME HIGHWAY

As signed dimensions are to be checked prior to commencement of work. Larger scale single hole provisions are smaller. Figure dimensions are scaled, immediately notify the architect of any discrepancy.

This drawing is copyright and the property of the architect and must not be copied, copied or used without the authority of O'Brien, Harris, Watt, Henderson Pty Limited. 400 99 000 363 376, trading as O'Brien Architects.

This construction drawing is based upon the approved design and development application prepared by O'Brien Architects. It is the responsibility of the architect to ensure that the design, including the construction of the building, complies with the requirements of the Quality Plan. Where the Quality Plan is not included in the information on this drawing, it is intended for preliminary purposes only as it is unapproved.

QUALITY RECORD

| REV      | NAME | SIGNATURE | DATE |
|----------|------|-----------|------|
| DRAWN    | JAM  |           |      |
| CHECKED  |      |           |      |
| APPROVED | JR   |           |      |

DD DESIGN DEVELOPMENT  
DA DEVELOPMENT APPLICATION  
CC CONSTRUCTION CERTIFICATE  
TO TENDER DRAWING  
WD WORKING DRAWING  
AS AS BUILT

| REV. | AMENDMENTS                                                                                   | BY |
|------|----------------------------------------------------------------------------------------------|----|
| A    | 19.04.07 - TENDER ISSUE                                                                      |    |
| B    | 17.05.07 - LEVELS REVISED, O/A HEIGHT OF BUILDING MAINTAINED<br>NOTES ADDED, AUTO DOOR ADDED |    |

CONSULTANTS

**SUPERINTENDENT**

**CAVERSTOCK GROUP**

SYDNEY OFFICE: Level 1, The Cornmarket Offices, 180 Liverpool Street, SYDNEY NSW 2000  
PH: (612) 9284 3188 FX: (612) 9284 9386

NEWCASTLE OFFICE: 5/28-31 Level 1, 438 Hunter Street, NEWCASTLE NSW 2300  
PH: (612) 4929 8338 FX: (612) 4929 8337

**CONSULTANTS**

STRUCTURAL - CIVIL: **COSTIN ROE Consulting** Tel: 9251 7090 - Fax 9241 3731

HYDRAULIC - FFE: **ROZ Engineering** Tel: 9417 8400 - Fax 9417 8337

FIRE ENGINEER: **RAWFIRE** Tel: 9906 8239 - Fax 9906 6284

ELECTRICAL - MECHANICAL: **EMF Griffiths** Tel: 9283 8445 - Fax 9283 2331

KEY PLAN

DRAWING STATUS

**FOR TENDER PURPOSES ONLY**

**NOT FOR CONSTRUCTION**

CLIENT

**CITADEL** property group

**OPR ARCHITECTS**

87 Cooper Street, Surry Hills  
Email: opa@opra.com.au

PO Box 87 Blighway Hills NSW 2012  
ph (02) 9519 4322 fax (02) 9519 4386  
ABN 69 090 393 376

PROJECT

**RETAIL - RESIDENTIAL DEVELOPMENT**  
311 HUME HIGHWAY cnr. HOXTON PARK RD- LIVERPOOL


DRAWING TITLE: **EAST ELEVATION**

SCALE: 1:100 PLOT DATE: 17.05.07 JOB No: STATUS: **B16 TD**

DWG No: **A.16** REV: **B**







01 SITE PLAN

All figure dimensions are to be checked prior to commencement of work. Larger figure apply. Size, dimensions and position. Right dimensions are shown. Immediately notify the Architect of any discrepancy.

This drawing is copyright and the property of the author and must not be revised, copied, altered, or used without the authority of Citadel. Pyramid, both Registered Pty Limited, ABN 89 080 563 276, trading as OPR Architects.

This construction drawing is based upon the approved design and development application prepared by OPR Architects Pty Limited, ABN 89 080 563 276, trading as OPR Architects. Copyright and moral rights to the design remain with the original author.

Completion of the Quality Record is evidence that the design and drawing have been verified in accordance with the requirements of the Quality Plan. Before the drawing is used for construction, the drawing must be checked for preliminary purposes only as it is unclassified.

| REV. | AMENDMENTS                             | BY |
|------|----------------------------------------|----|
| A    | 28.03.07 - SECTION 98 ISSUE TO CITADEL |    |
| B    | 22.10.07 - QUEST TENANCY D.A. ISSUE    |    |

| REV.     | NAME | SIGNATURE | DATE |
|----------|------|-----------|------|
| REVIEW   | GER  |           |      |
| DRAWN    | GER  |           |      |
| CHECKED  | .    |           |      |
| APPROVED | GR   |           |      |

| STATUS | DESIGN DEVELOPMENT APPLICATION | CONSTRUCTION CERTIFICATE | TO TENDER DRAWING | WORKING DRAWING | AS BUILT |
|--------|--------------------------------|--------------------------|-------------------|-----------------|----------|
| DA     |                                |                          |                   |                 |          |
| CC     |                                |                          |                   |                 |          |
| TD     |                                |                          |                   |                 |          |
| WD     |                                |                          |                   |                 |          |
| AS     |                                |                          |                   |                 |          |

CONSULTANTS

STRUCTURAL - CIVIL - STORMWATER  
**COSTIN ROE Consulting** Tel. 9251 7889 - Fax 9241 3731

HYDRAULIC - FIRE - ELECTRICAL - MECHANICAL  
**PYRAMID CONSULTING ENGINEERS** Tel. 9460 2888 - Fax 9460 3222

FIRE ENGINEER  
**RAWFIRE** Tel. 9906 8239 - Fax 9906 6394

KEY PLAN

DRAWING STATUS

**ISSUED FOR SECTION 98 APPLICATION APPROVAL**  
**NOT FOR CONSTRUCTION**

CLIENT

**CITADEL** property group

**OPR ARCHITECTS**

67 Cooper Street, Bury Hills  
Email: opa@opra.com.au

PO Box 57, Sharnbrook Hills NSW 2012  
ph (02) 9519 4332 fax (02) 9519 4388  
John 95 095 393 976

PROJECT

**RETAIL - RESIDENTIAL DEVELOPMENT**  
311 HUME HIGHWAY cnr. HOXTON PARK RD- LIVERPOOL.

DRAWING TITLE

**OVERALL SITE PLAN**

DWG No

**A01**

SCALE

**1:200**

PLOT DATE

**22.10.07**

JOB No

**B16**

STATUS

**S96**

REV

**B**

Appendix B

PLANS OF ENVISAGED DEVELOPMENT

















PLAN - BASEMENT LEVEL 4  
1:250

CONSULTANT ISSUE

|                                                                                                                                                                                                                                                     |                    |                               |  |                                                                                       |                                                                                                                                                             |                                                                                                                                                       |                                                                                       |                                                                                                                                                                  |                                                            |                                        |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------|-------------------------------|--|---------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------|----------------------------------------|
| REF.<br>E                                                                                                                                                                                                                                           | DATE<br>13.01.2015 | AMENDMENT<br>CONSULTANT ISSUE |  |  | <b>Wollongong</b><br>81a Princes Highway, Fairy Meadow<br>Tel: (02) 4227 1661<br>Email: info@designworkshop.com.au<br>Web: http://www.designworkshop.com.au | <b>Sydney</b><br>Suite 704, 31 Market St. Sydney<br>Tel: (02) 4227 1661<br>Email: info@designworkshop.com.au<br>Web: http://www.designworkshop.com.au |  | CLIENT:<br>HUME DEVELOPMENTS<br>MKED USE DEVELOPMENT<br>ADDRESS:<br>LOT NO. AND D.P.1004792<br>311 HUME HIGHWAY, LIVERPOOL<br>DRAWING NAME:<br>PLAN - BASEMENT 4 | DATE:<br>DEC 14<br>DRAWN:<br>SWG<br>SCALE:<br>1:250<br>QA: | PROJECT No.<br>1086<br>DWG No.<br>07-E |
| DISCLAIMER<br><small>© 2015 Design Workshop Australia. All rights reserved. This drawing is the property of Design Workshop Australia and is not to be used for any other purpose without the written consent of Design Workshop Australia.</small> |                    |                               |  |                                                                                       |                                                                                                                                                             |                                                                                                                                                       |                                                                                       |                                                                                                                                                                  |                                                            |                                        |



UNIT BEDROOM NUMBERS

| TOWER             |       | BUILDING A |      |
|-------------------|-------|------------|------|
| 1 BED             | = 31  | 1 BED      | = 4  |
| 2 BED             | = 176 | 2 BED      | = 33 |
| 3 BED             | = 30  |            |      |
|                   | = 237 | BUILDING B |      |
|                   |       | 1 BED      | = 1  |
|                   |       | 2 BED      | = 29 |
|                   |       |            | = 30 |
| TOTAL UNITS = 305 |       |            |      |

CONSULTANT ISSUE





**Appendix C**

**EXTRACTS FROM TRAFFIC REPORT**

---



**TRAFFIC PLANNING & ENGINEERING CONSULTANTS**

**PROPOSED RESIDENTIAL AND RETAIL  
DEVELOPMENT CORNER HUME HIGHWAY  
AND HOXTON PARK ROAD, LIVERPOOL**

---

**TRAFFIC AND PARKING  
ASSESSMENT**

September 2002

Ref: 01.02.110

## 1. INTRODUCTION

This report has been prepared to accompany a development application to Liverpool City Council for a proposed residential and retail development located on the corner of Hume Highway and Hoxton Park Road, Liverpool. (Figure 1)

The development proposes a Coles shopping centre, 9 specialty shops, 4 offices and 124 residential units, comprising 96 x 2 and 28 x 3 bedroom units. Parking for 277 cars is proposed on 5 basement levels. Vehicle access to/from the development is to be via a shared entry/exit driveway off Gillespie Street.

This report examines the traffic and parking implications of the proposed development and will assess the:

- Adequacy of the off-street parking provision.
- The proposed access arrangements.
- Estimated traffic generation of the proposal.
- Impacts on the existing road network of the estimated traffic generation.
- Loading arrangements.

The supermarket and specialty shops have been the subject of a previous development application approval. This approval included the provision of Traffic Signals at the intersection of Hoxton Park Road and Gillespie Street. Recent correspondence with the Roads and Traffic Authority indicates that the traffic signals approval is still current.

therefore have less parking requirements.

The proposed development is located on the fringe of the Liverpool CBD midway between Liverpool Railway Station and the proposed Transitway Station adjacent Liverpool City Council. The development is approximately 960m from Liverpool Rail Station and 600m from the Transitway Station. Consequently, it is considered appropriate to use the RTA's car parking rates at this location.

Accordingly, the proposed residential development exceeds the RTA's suggested parking requirements with the provision of 277 off-street parking spaces.

## LOADING FACILITIES

A loading dock is proposed for the sole use of the proposed supermarket (Coles) and is unchanged from the previously approved application. Access to the dock is via a separate driveway off Gillespie Street. The proposed loading dock is sufficient to cater for up to two (2) large rigid vehicles simultaneously. This number of docks is considered sufficient by Coles to adequately service the proposed supermarket.

An additional service vehicle dock is proposed directly off Hume Highway for the collection of refuse generated by the residential, shopping and office components of this development. The garbage collection will be by private contractor and due to the location on the highway will be carried out in the early hours of the morning prior to peak Clearway hours. In this regard the applicant has held discussions with contractors SITA who have provided details of their dock dimension requirements.

Notwithstanding, the previous approval of the supermarket loading docks, an assessment of the supermarket loading dock has been undertaken to determine if they are sufficient in size to enable a large rigid vehicle to manoeuvre on site and enter/exit in a forward direction. This assessment is achieved by overlaying the "Australian Standard Off-Street parking – Part 2 – Commercial vehicle facilities, AS 2890.2 – 1989" service area manoeuvring template upon the design plans. This procedure indicates that the subject vehicles can access the loading area from Gillespie Street and leave the site in a forward direction.

## TRAFFIC

An estimation of the traffic generation of the proposed development can be calculated by again referring to the Roads and Traffic Authority's 'Guide to Traffic Generating Developments, Section 3 - Landuse Traffic Generation' of December 1993. The guide specifies 0.24 peak hour vehicle trips per unit for high density residential flat buildings in Metropolitan Regional (CBD) Centres.



In addition the RTA guidelines provide the following evening peak hour generation formula for retail and commercial developments:

**Shopping Centres**

$$V(P) = 20 A(S) + 51 A(F) + 155 A(SM) + 46 A(SS) + 22 A(OM)$$

(vehicle trips per 1000m)

where:

- A(S):** Slow Trade gross leasable floor area (Gross Leasable Floor Area in square metres) includes major department stores such as David Jones and Grace Bros., furniture, electrical and whitegoods stores.
- A(F):** Faster Trade GLFA - includes discount department stores such as K-Mart and Target, together with larger specialist stores such as Fosseys.
- A(SM):** Supermarket GLFA - includes stores such as Franklins and large fruit markets.
- A(SS):** Specialty shops, secondary retail GLFA - includes speciality shops and take-away stores such as McDonalds. These stores are grouped as they tend to not be primary attractors to the centre.
- A(OM):** Office, medical GLFA: includes medical centres and general business offices.

Accordingly, the estimated residential traffic generation of this development calculates as:

$$124 \text{ units @ } 0.24 \text{ trips/unit} = 30 \text{ am \& pm peak hour trips}$$

And the commercial/retail component of the development calculates as:

$$\begin{aligned} V(P) &= 20 A(S) + 51 A(F) + 155 A(SM) + 46 A(SS) + 22 A(OM) \\ &\quad \text{(vehicle trips per 1000m}^2\text{)} \\ &= 20 A(S) + 51 A(F) + 155 (2419\text{m}^2) + 46 (616.5\text{m}^2) + 22 (798.2\text{m}^2)/1000\text{m}^2 \\ &= 374.9 + 28.4 + 17.6 \\ &= 421 \text{ evening peak hour vehicle trips} \end{aligned}$$

As the RTA does not provide a morning peak hour traffic generation, it will be assumed that the office, shop and 10% of the supermarket (estimated morning staff) component of the evening peak hour traffic generation will approach the site in the morning peak hour.

Accordingly, the estimated potential traffic generation of the proposed development is **113 morning and 451 evening peak hour trips.**

## Appendix D

## INTERSECTION PLAN

DO NOT AMEND MANUALLY

DRAWN BY CADD




A PHASE

B & D PHASES  
(Z+ introduces D Phase)

C PHASE

MOVEMENTS



DETECTOR SPECIFICATION

| Detector | Specifications |                |                |                          |
|----------|----------------|----------------|----------------|--------------------------|
|          | FN             | A(L)           | A(E1)          |                          |
| A        | SG/PS          | A              | A              |                          |
| A-B-D1   | DS             | B(PR)          | D(PR)          | B(E4)                    |
|          | Approach       | A              | A              | B                        |
| A-B-D1   | FN             | Z-             | Z+             | D(NEXT)                  |
|          | Approach       | A(L)B(L)       | A/B/D          | A(E2)                    |
| A-B-D1   | DS             | B(E2)          | Z+             | A-B-D1(PR)B(NEXT)D(NEXT) |
|          | Approach       | A(NEXT)D(NEXT) | A(NEXT)B(NEXT) | D(E2)                    |
| A-B-D2   | FN             | A(L)           | A(E3)          | B(E3)                    |
|          | Approach       | A              | A              | B                        |
| A-B-D2   | DS             | B(NEXT)D(NEXT) | A(NEXT)D(NEXT) | A(NEXT)D(NEXT)           |
|          | Approach       | D              | D              | D                        |
| B-C-D    | DS             | B(NEXT)D(NEXT) | B(NEXT)C(NEXT) |                          |
|          | Approach       | C              | C              | C                        |
| A        | DS             | A(PR)          | C(L)           | C(L)                     |
|          | Approach       | A(NEXT)A(WALK) | A(NEXT)A(WALK) | B, C, D                  |
| C1       | DS             | C(PR)          | A(L)           | A(L)                     |
|          | Approach       | C(C)C(WALK)    | C(C)C(WALK)    | A, B, D                  |
| C2       | DS             | C(PR)          | A(L)           | A(L)                     |
|          | Approach       | C(C)C(WALK)    | C(C)C(WALK)    | A, B, D                  |

SPECIAL SIGNAL GROUP DISPLAY SEQUENCE

| SIGNAL GROUP    | TABLE TYPE | REMARKS                                    |
|-----------------|------------|--------------------------------------------|
| A/B/D           | 3          |                                            |
| B/D (RT)        | 39         | Z-signal allows right turn filter movement |
| B/C COND/D (LT) | 14         | Timed R.A. protection for 'A' pedestrian   |
| C (LT)          | 73         | Timed R.A. protection for 'C1' pedestrian  |
| C (LS)          | 23         | Timed protection for 'C2' pedestrian       |

| POST TYPE | LENGTH | REMARKS |
|-----------|--------|---------|
| 1         | 2      | 4.1 New |
| 2         | 2      | 4.1 New |
| 3         | 5XL    | - New   |
| 4         | 2      | 4.1 New |
| 5         | 5XL    | - New   |
| 6         | 2      | 3.2 New |

NOTES

1. This site is SCATS linked.
2. Special STOP sign (R1-4) attached to post 1.
3. All push buttons are audio tactile.
4. Kerb Ramps to be constructed at all pedestrian crossings in accordance with Model Drawing MDR173 B&T A.
5. Supply to be determined on site by Class 2/3 service provider.

A ORIGINAL ISSUE

|                                                                                                                                                       |                                                                                                                                                                 |                                                                                                            |                                                                                                                     |                                                                                             |                                    |                         |
|-------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------|------------------------------------|-------------------------|
| <b>PUBLIC UTILITY LEGEND</b><br>PROGENT<br>STOP VALVE<br>WATER MAIN<br>SEWER MAIN<br>TELEPHONE POLE<br>STAY POLE<br>TELEPHONE BOX<br>TELEPHONE CLOSET | <b>REFERENCE PLANS</b><br>SYMBOLS/REMARKS: 10001-5<br>STOP POST<br>WATER MAIN<br>SEWER MAIN<br>TELEPHONE POLE<br>STAY POLE<br>TELEPHONE BOX<br>TELEPHONE CLOSET | <b>DESIGN APPROVAL</b><br>APPROVED<br>DATE<br>POSITION<br>DESIGNED BY<br>CHECKED BY<br>PLANNING ASSOCIATES | <b>TRAFFIC SIGNALS AT THE INTERSECTION OF HOXTON PARK ROAD AND GILLESPIE STREET</b><br>DESIGN LAYOUT<br>TCS No. 000 | <b>CAAD FILE: 10000-00A.DGN</b><br>SCALE<br>FILE<br>RECON.<br>000 75 000<br>0000.000.W.0000 | <b>EXISTING</b><br><b>PROPOSED</b> | <b>ISSUE</b><br>A<br>00 |
|-------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------|------------------------------------|-------------------------|