



Dulconghi Investments Pty Ltd

Dulconghi Heights
Planning Proposal - Lot 3 DP 1164661,
Neville Morton Drive, Crescent Head

October 2016

Table of contents

1.	Introduction.....	1
1.1	Overview	1
1.2	Background	1
1.3	Purpose of report	1
1.4	Structure of report	2
1.5	Landowner consent.....	2
2.	Site description.....	3
2.1	Site locality	3
2.2	Existing development.....	3
2.3	Access	3
2.4	Current site zoning and minimum lot size.....	3
2.5	Topography	3
2.6	Development history	3
3.	Environmental assessment	5
3.1	Ecology assessment	5
3.2	Bushfire assessment.....	6
3.3	Cultural heritage.....	10
3.4	Wastewater and servicing.....	12
3.5	Traffic assessment.....	15
3.6	Visual assessment	16
4.	Planning Proposal	18
4.1	Part 1 - Statement of objectives of proposed LEP	18
4.2	Part 2 – Explanation of provisions to be included in proposed LEP	18
4.3	Part 3 – Justification of proposal.....	18
4.4	Part 4 – Mapping.....	30
4.5	Part 5 – Community consultation	31
4.6	Part 6 – Project timeline.....	31
5.	Conclusion.....	32
6.	Disclaimer.....	33
7.	References	34

Table index

Table 3-1	APZ compliance assessment	7
Table 3-2	Design parameters.....	14
Table 4-1	Proposed rezoning	18

Table 4-2	SWOT analysis	19
Table 4-3	Project timeline	31

Plate index

Plate 1	Rural residential land strategy identified lands	4
Plate 2	Location of visual assessment photo	16
Plate 3	View line towards site	17

Figure index

Figure 1	Site location	37
Figure 2	Existing site conditions	38
Figure 3	Existing zoning plan	39
Figure 4	Proposed zoning plan	40
Figure 5	1:100 year flood level	43
Figure 6	Proposed dwelling locations and APZs	44

Appendices

Appendix A - Figures

Appendix B - Ecology assessment

Appendix C - Previous reports

1. Introduction

1.1 Overview

GHD has been engaged by Dulconghi Investments Pty Ltd to prepare a Planning Proposal for the rezoning of Lot 3 DP 1164661, Neville Morton Drive, Crescent Head NSW.

This Planning Proposal has been prepared to provide justification for the rezoning of the site by Kempsey Shire Council (Council), as the relevant planning authority, in accordance with Clause 55 of the *Environmental Planning and Assessment Act 1979* (EP&A Act).

1.2 Background

The site has been identified in Council's Rural Residential Land Release Strategy 2014 (the strategy) and is therefore eligible for consideration for rezoning and subdivision for rural residential development. Before any land identified in the strategy can be subdivided or developed the land use zones and minimum lot sizes need to be amended in the Kempsey Local Environmental Plan (KLEP 2013). Amending the KLEP 2013 requires the preparation of a Planning Proposal. The subject site was identified as a Stage 1 site for future rezoning within the strategy.

The Rural Residential Land Strategy (Kempsey Shire Council 2014) determined that biodiversity was a constraint to the development of rural residential subdivisions in the Crescent Head locality. In regards to lands that are the subject of this planning proposal, GHD have completed an ecology assessment (included as Appendix B) of the site's biodiversity values and potential impacts associated with the future development of the site. This report concluded that the land subject to the planning proposal is suitable for rezoning to R5.

1.3 Purpose of report

Pursuant to Clause 55 of the EP&A Act, Council, as the relevant planning authority, is required to prepare a document that provides the justification for and explains the intended effect and purpose of a proposed amendment to KLEP 2013. This Planning Proposal addresses this requirement.

The main issues used to form the basis of this report are outlined in the former NSW Department of Planning and Infrastructure (2012) *Guide to Preparing Planning Proposals*. A site meeting was also held on 3 February 2016 with representatives from the Department of Planning and Environment (DPE), the NSW Office of Environment and Heritage (OEH) and Kempsey Shire Council (KSC) to discuss the proposed rezoning applicable. The outcomes of this meeting have also informed the final zoning changes proposed. This Planning Proposal supports the following changes to the current zoning at the site:

- Rezoning of 4.6 ha of RU2 Rural Landscape to R5 Large Lot Residential (mostly cleared lands with scattered trees only).

- Rezoning of 7.7 ha of E3 Environmental Management to R5 Large Lot Residential (contains vegetation in a modified state with the mid storey largely removed and ground covers dominated in locations by introduced pastures).
- Rezoning of 37.9 ha of E3 Environmental Management to E2 Environmental Conservation.

1.4 Structure of report

This report has been structured as follows:

Chapter 1 – Introduction and background information.

Chapter 2 – Site description and development history.

Chapter 3 – Environmental assessment of the site.

Chapter 4 – Justification for the Planning Proposal.

Chapter 5 – Concluding statement.

1.5 Landowner consent

Dulconghi Investments Pty Ltd as the owner of Lot 3 DP 1164661, Neville Morton Drive, Crescent Head has provided consent to submit this Planning Proposal.

2. Site description

2.1 Site locality

The subject site is known as Lot 3 DP 1164661, Neville Morton Drive, Crescent Head and is located on the north side of Crescent Head Road, less than 3 kms to the north west of the Crescent Head town centre.

Figure 1 in Appendix A shows the regional location of the site. The site encompasses an area of approximately 54 hectares as identified in the strategy.

2.2 Existing development

Approximately half of the site has been cleared of vegetation and has been subjected to intensive livestock grazing. With the exception of stock fencing and a stock yard in the eastern portion of the site there are no other improvements or infrastructure.

Figure 2 in Appendix A shows the existing condition of the site.

2.3 Access

The site is accessed from an existing rural residential estate known as Dulconghi Heights. This estate is serviced by a central bitumen sealed access road (Neville Morton Drive) and associated services which extend to the boundary of the subject site.

2.4 Current site zoning and minimum lot size

The proposed site is currently zoned RU2 Rural Landscape, E2 Environmental Conservation and E3 Environmental Management under the KLEP 2013.

Figure 3 in Appendix A shows the current zoning of the site.

The minimum lot size for any subdivision of the site is currently 40 hectares.

The western portion of the site has also been mapped under KLEP 2013 as being scenic protection land. Accordingly, development consent must not be granted to development unless the consent authority is satisfied that measures will be taken, including in relation to the location and design of the development, to minimise the visual impact of the development from major roads and other public places.

2.5 Topography

The site has a gently sloping topography with an easterly aspect. The site is traversed by one small ephemeral drainage line in the north western portion associated with the existing farm dam. The eastern portion of the site drains towards the east to an unnamed wetland.

2.6 Development history

2.6.1 Nearby development

The site lies directly adjacent to and is accessed from an existing rural residential estate known as Dulconghi Heights. This estate currently has a central access road (Neville Morton Drive) and associated services which extend to the boundary of the site. The rezoning of the site for rural residential development would simply lead to an extension of the existing estate and associated infrastructure and services.

2.6.2 Subject site identified as a potential Rural Residential area

The Background Report for the draft Rural Residential Strategy (Insite, 2013) examined the environmental conditions affecting each investigation area. Crescent Head is discussed on page 38 of this document and states that the subject site is suitable for rural residential land use as shown below;

“Another pocket of land at the northern end of Neville Morton Drive could form an extension to the rural residential subdivision to which this road provides access; noting this small area contains class 2 a & 2b koala habitat. Some of the land is however cleared and appears suitable for rural residential use.

Areas where extension or intensification could be considered....., is the land accessed from..... the northern end of Neville Morton Drive”.

(Page 38/ 39 Background Report for the Rural Residential Strategy (Insite ,2013)

The Strategy (KSC, 2014) describes the suitability of the subject site for rural residential zoning as:

“Some potential also exists for an extension of the R5 zoned area immediately to the north of the Dulconghi Estate, subject to visual impacts, ecological impacts, flooding and the presence of a SEPP 14 wetland being addressed.”

Map 18: Crescent Head Land Release Staging




Plate 1 Rural residential land strategy identified lands

3. Environmental assessment

This chapter provides an assessment into the environmental, social and economic impacts of the Planning Proposal.

3.1 Ecology assessment

GHD completed a specialist ecology assessment to support this rezoning application (Appendix B). It describes the ecological values at the site, with particular emphasis on threatened ecological communities, populations and species listed under the *Threatened Species Conservation Act 1995* (TSC Act), *Fisheries Management Act 1994* (FM Act), and Matters of National Environmental Significance (MNES) listed under the Commonwealth *Environmental Protection and Biodiversity Conservation Act 1999* (EPBC Act).

The complete report is provided as Appendix B with a summary of key findings below.

A review of existing literature and site surveys indicate the main constraint to future development is the management of biodiversity, including Koala habitat. Constraints to be considered and how they would be managed during future approvals include:

- Impacts to approximately 7.34 ha of modified Blackbutt Tallowwood grassy open forest vegetation, comprising the removal of 2.36 ha of vegetation for residential dwellings and associated infrastructure and partial clearing of 4.98 ha to accommodate bushfire protection areas. This vegetation type is in a degraded state with the canopy already 'thinned' in the majority of the western portion of the site due to previous tree clearing and the mid storey largely removed due to the impacts of constant grazing. This vegetation type is not listed as an EEC in NSW and such an impact would likely not be considered a 'significant' impact.
- Removal of approximately three remnant Paperbark trees (*Melaleuca quinquinervia*) associated with the construction of the proposed access road.
- Impacts to habitat for potential threatened fauna as listed in Table 4-2. These impacts are considered minor due to the following:
 - The existing condition of the vegetation being impacted
 - The limited total clearing of 2.36 ha required
 - Limited tree removal in Asset Protection Zones (large areas of the western portion of the site already have a discontinuous canopy and cleared understorey)
 - The retention of almost all PFTs for the Koala
 - The retention of the majority of hollow-bearing trees within Asset Protections Zones and via the sighting of dwelling locations
 - The protection of habitat trees via Tree Preservation Orders (or other agreed planning mechanism)
 - Preparation of a Construction Environmental Management Plan (CEMP), including appropriate avoidance and mitigation measures, associated with native biota.

- Presence of Secondary (Class A) Preferred Koala habitat (Blackbutt Tallowood grassy open forest). This vegetation type at the site includes scattered individuals of the 'primary food trees (PFTs)', Tallowood and Grey Gum (Biolink 2011). The proposed subdivision would remove only four PFTs. Impacts to PFTs have been minimised through protection via a planning instrument (such as Tree Preservation Order), retaining in APZ's, determining building footprints within lots and gazetting biodiversity offsets for conservation if required. Impacts to Koala habitat have been assessed in accordance with the Comprehensive Koala Plan of Management (Kempsey CKPoM), as detailed in Section 5.2.3 of the ecology assessment, and the EPBC Act.
- SEPP 44. As mentioned above, the development would also be subject to detailed ecological impact assessment, including assessments of significance (7-part test) through the provisions of Section 5A of the EPA Act or a biobanking statement under Part 7A of the TSC Act.

The Planning Proposal includes the rezoning of approximately 37.9 ha of Lot 3 DP 1164661, to the west and south west of the subject site as shown in Figure 4, to offset impacts to native vegetation at the site. This approach was discussed with representatives of the DPE and OEH during the site visit on 3 February 2016 and it was agreed this would be a suitable offset activity for the proposals impacts. OEH indicated they were supportive of the avoidance and mitigation measures proposed within the planning proposal however these actions alone were not considered adequate leading to the proposed rezoning of the additional 37.9 ha as E2 Environmental Conservation. This area will also be used to provide the required offsets under the Kempsey CKPoM.

The Rural Residential Land Strategy (Kempsey Shire Council 2014) determined that biodiversity was a constraint to the development of rural residential subdivisions in the Crescent Head locality. In regards to lands that are the subject of this report, GHD have completed an analysis of biodiversity constraints and impacts associated with the proposed rezoning and conclude that the land subject to the planning proposal is suitable for rezoning to R5. Any impacts to threatened biota would be further addressed in greater detail at the DA stage. It should be remembered that the indicative subdivision plan presented in the planning proposal has been provided to show how a potential subdivision may apply to the land and the considerations associated with reducing impacts to biodiversity as well as accommodating bushfire protection measures. This layout may be subject to change (either through the realignment of lot boundaries or repositioning/ reduction in dwellings) depending on decisions made by approval authorities and/or the applicant.

3.2 Bushfire assessment

Council has identified the site to be bushfire prone. As a result, an assessment of the site has been undertaken in accordance with *Planning for Bushfire Protection* (PBP 2006) (NSWRFS, 2006).

The development is considered a rural residential subdivision. Accordingly, the planning controls outlined in Chapter 4.1 of PBP 2006 apply. These controls specify that the proposal should:

- *Minimise perimeters of the subdivision exposed to the bushfire hazard. Hourglass shapes, which maximise perimeters and bottlenecks, should be avoided.*
- *Minimise bushland corridors that permit the passage of bush fire.*

- *Provide for the siting of future dwellings away from ridge tops and steep slopes – particularly upslopes, within saddle and narrow ridge crests.*
- *Ensure that Asset Protection Zones (APZs) between a bushfire hazard and future dwellings enable conformity with the deemed-to-satisfy requirements of the Building Code of Australia (BCA).*
- *Provide and locate, where the scale of development permits, open space and public recreation area as accessible public refuge areas or buffers.*
- *Ensure the ongoing maintenance of asset protection zones.*
- *Provide clear and ready access from all properties to the public road system for residents and emergency services.*
- *Ensure the provision of and adequate supply of water and other services to facilitate effective firefighting.*

To achieve the above objectives, Section 4.1.3 of PBP 2006 outlines the intent, various performance criteria and acceptable solutions for various bush fire protection measures required for residential subdivisions in bushfire prone areas. The following sections assess compliance with these requirements.

3.2.1 Asset Protection Zones

The intent of the APZs are *“To provide sufficient space and maintain reduced fuel loads, so as to ensure radiant heat levels at buildings are below critical limits and to prevent direct flame contact with a building”* (NSWRFS 2006).

The slope, vegetation and associated APZs have been calculated for each potential dwelling site, in accordance with PBP 2006. The results of the bushfire hazard assessment in regard to dominant vegetation type, slope and required APZs are shown in Table 3-1.

As shown on Figure 6 and in Table 3-1, adequate space is available to meet the APZ requirements in all directions, however some vegetation would need to be cleared. In this regard, dwelling locations have been sited to limit the impacts to native vegetation. This includes the location of dwellings in the proposed eastern lots so that there is no potential impact from dwellings, APZ's and other infrastructure on the mapped SEPP 14 area. Indicative building envelopes and associated infrastructure have also been located outside the existing 1:100 year flood event allowing suitable distance to establish an APZ between any future structures and the SEPP 14 (E2 zone) boundary.

Table 3-1 APZ compliance assessment

Dwelling	Transect Direction	Predominant Vegetation	Effective Slope	Required APZ (m) (PBP 2006)	Sufficient APZ Available
1	North	Forest	Upslope/flat	20	Yes but thinning required
	East	Forest	>0-5° downslope	20	Yes but thinning required
	South	Forest	>0-5° downslope	20	Yes but thinning required
	West	Forest	Upslope/flat	20	Yes but thinning required

Dwel ling	Transect Direction	Predominant Vegetation	Effective Slope	Required APZ (m) (PBP 2006)	Sufficient APZ Available
2	North	Forest	Upslope/flat	20	Yes but thinning required
	East	Forest	>0-5° downslope	20	Yes but thinning required
	South	Forest	>0-5° downslope	20	Yes but thinning required
	West	Forest	Upslope/flat	20	Yes but thinning required
3	North	Forest	Upslope/flat	20	Yes but thinning required
	East	Forest	>0-5° downslope	20	Yes but thinning required
	South	Forest	>0-5° downslope	20	Yes but thinning required
	West	Forest	Upslope/flat	20	Yes but thinning required
4	North	Forest	Upslope/flat	20	Yes but thinning required
	East	Forest	>0-5° downslope	20	Yes but thinning required
	South	Forest	>0-5° downslope	20	Yes but thinning required
	West	Forest	Upslope/flat	20	Yes but thinning required
5	North	Forest	Upslope/flat	20	Yes
	East	Cleared	>0-5° downslope	10	Yes
	South	Cleared	>0-5° downslope	10	Yes
	West	Forest	Upslope/flat	20	Yes but minor clearing may be required
6	North	Forest	Upslope/flat	20	Yes
	East	Cleared	>0-5° downslope	10	Yes
	South	Cleared	>0-5° downslope	10	Yes
	West	Forest	Upslope/flat	20	Yes but minor clearing may be required
7	North	Forest	Upslope/flat	20	Yes
	East	Cleared	>0-5° downslope	10	Yes
	South	Cleared	>0-5° downslope	10	Yes
	West	Forest	Upslope/flat	20	Yes but minor clearing may be required
8	North	Cleared	Upslope/flat	10	Yes

Dwel ling	Transect Direction	Predominant Vegetation	Effective Slope	Required APZ (m) (PBP 2006)	Sufficient APZ Available
	East	Cleared	>0-5° downslope	10	Yes
	South	Cleared	>0-5° downslope	10	Yes
	West	Cleared	Upslope/flat	10	Yes
9	North	Cleared	Upslope/flat	10	Yes
	East	Forest	>0-5° downslope	20	Yes
	South	Cleared	>0-5° downslope	10	Yes
	West	Cleared	Upslope/flat	10	Yes
10	North	Cleared	Upslope/flat	10	Yes
	East	Forest	>0-5° downslope	20	Yes
	South	Forest	>0-5° downslope	20	Yes but clearing may be required
	West	Rainforest*	Upslope/flat	10	Yes but clearing may be required
11	North	Cleared	Upslope/flat	10	Yes
	East	Cleared	>0-5° downslope	10	Yes
	South	Rainforest*	>0-5° downslope	10	Yes
	West	Cleared	Upslope/flat	10	Yes
12	North	Cleared	Upslope/flat	10	Yes
	East	Cleared	>0-5° downslope	10	Yes
	South	Rainforest*	>0-5° downslope	10	Yes
	West	Cleared	Upslope/flat	10	Yes
13	North	Cleared	Upslope/flat	10	Yes
	East	Forest	>0-5° downslope	20	Yes
	South	Forest	>0-5° downslope	20	Yes
	West	Cleared	Upslope/flat	10	Yes
14	North	Forest	Upslope/flat	20	Yes
	East	Forest	>0-5° downslope	20	Yes
	South	Cleared	>0-5° downslope	10	Yes
	West	Cleared	Upslope/flat	10	Yes

* PBP (2006) states areas less than 1 hectare can be assessed as rainforest

3.2.2 Access

PBP 2006 provides a range of Performance Criteria and Acceptable Solutions for Public Roads, Property Access and Fire Trails, the site contains sufficient area and conditions to achieve the PBP 2006 acceptable solutions. However, the current indicative layout does not meet the following acceptable solutions:

- The requirement for the public road to be a through road, or less than 200 metres in length.
- Alternative property access roads for individual dwellings that are located more than 200 metres from a public through road.

Despite the current layout not meeting the PBP 2006 requirements, given the relatively cleared nature of the site, it is considered the intent of PBP 2006 in relation to Public Roads, Property Access and Fire Trails can still be achieved.

This non-compliance has been discussed with RFS, who have provided advice to suggest the proposal would be acceptable providing some amendments to the proposed subdivision layout are incorporated. The RFS advice is contained in an email dated 18 February 2016 and the subdivision layout has been amended to reflect the RFS recommendations.

3.2.3 Services

PBP 2006 provides a range of Performance Criteria and Acceptable Solutions for water, electricity and gas. The site contains sufficient area and conditions to achieve the PBP 2006 acceptable solutions.

3.2.4 Summary

The potential subdivision layout and dwelling locations have considered the implications associated with bushfire protection while minimising impacts to biodiversity. The subdivision would see approximately 4.98 ha of vegetation requiring only partial clearing to establish and maintain appropriate APZ's. Vegetation being impacted has already been modified with the understorey largely removed with the site being subjected to active grazing for a long time. Due to the existing condition of vegetation, impacts to establish APZs would be limited to 'thinning' of trees to ensure a discontinuous canopy. APZs would also maintain the cleared understorey.

Future dwellings would need to be constructed to relevant building standards associated with bushfire protection which would be determined during development applications.

Proposed dwelling locations have been sited to limit the impacts to native vegetation. This includes the location of indicative building envelopes and associated APZ's, in the proposed eastern lots so that there is no potential construction activities within the mapped SEPP 14 boundary (E2 zone).

3.3 Cultural heritage

3.3.1 Literature review

A survey of the proposed development site was originally undertaken in 1996 by the Kempsey Local Aboriginal Land Council (LALC). The report, titled *Survey of Proposed Development on Lots 1, 2 & 3 – DP 794159*, documented the works undertaken including a thorough site inspection and consultation with Aboriginal elders of the Macleay Valley.

No surface relics noted and there was no recollection of the site having contemporary Aboriginal significance or occupation.

A letter from the NSW National Parks and Wildlife Service is attached to the above report, documenting the results of an inspection to verify an Aboriginal site which was listed on the NPWS Aboriginal Sites register. The Senior Aboriginal sites officer attending the inspection stated he had no knowledge of any Aboriginal sites occurring directly on Lots 1, 2 and 3 DP 794159. In addition, no Aboriginal relics were detected during the survey.

In addition to the above inspection reports, GHD also reviewed local narratives of occupation of the Crescent Head area and basic cultural heritage site information prepared by a post graduate student of University of New England.

The above information is included as Appendix C.

3.3.2 Site inspection

A site inspection was undertaken by Graham Quinlan and Fred Kelly from Kempsey LALC and Tim Hill from Everick Heritage Consultants on 27 March 2015.

As a result of the site inspection one Aboriginal site was identified comprising two artefacts; one chert flake and a greywacke (beach cobble) flake piece. The site has not yet been recorded on the Aboriginal Heritage Management Information System (AHIMS).

The ridgeline/crest on the site fits the criteria for a Potential Archaeological Deposit – being broad, flat and immediately adjacent to a large waterbody/ resource area (in this case the wetland). Observed disturbance across the site includes the original/ historic forestry and the remains of a house on part of the ridge nearby to the location of the flakes.

The letter report produced describing the site inspection found that based on the previous survey (Kempsey LALC, 1996) and the knowledge of the area the Aboriginal site is likely to be of low to moderate significance however additional investigation would be required during preparation of a DA before making a definite statement on the site's significance.

The report recommended that based on the potential to harm Aboriginal objects across the ridgeline, an Aboriginal Cultural Heritage Assessment should be undertaken prior to ground disturbing works taking place on the ridgeline. However, based on the results of the site inspection Kempsey LALC had no significant objections to the proposal to rezone the land.

The letter produced by Kempsey LALC describing the site inspection is included as Appendix C.

3.3.3 Summary

The results of the literature review and site inspection confirmed that the site is likely to have low to moderate Aboriginal heritage significance. Kempsey LALC have undertaken a site inspection and confirmed they had no significant objections to this planning proposal. Any future DA that may result in ground disturbance would include an Aboriginal Cultural Heritage Assessment.

3.4 Wastewater and servicing

The purpose of the assessment is to determine the suitability of the soil at the proposed rezoning site for on-site disposal of sewage effluent and sullage comprising liquid waste from dwellings.

This report has been prepared in general compliance with the *Kempsey Development Control Plan 2013* (Kempsey DCP), *Environment and Health Protection Guidelines – On-site Sewage Management for Single Households* (NSW Government, 1998) and AS/NZS 1547-2012 *On-site Domestic-Wastewater Management*.

3.4.1 Site evaluation

The site evaluation outlines the information relevant to the assessment of the capability of the proposed site to accept wastewater. This was achieved through desktop research.

Flood potential

GHD were advised by Kempsey Shire Council (Tony Castle, personal communication, 02 April 2015) that the calculated 1 in 100 year flood level for the site is 4.21 mAHD as depicted in Figure 5, Appendix A. As required by the Kempsey DCP, the site has adequate room for the treatment system to be located above the 100 Year flood level.

Slope

The slope at the proposed location of the disposal fields was from 0 to 10%, less than the 12% guideline in the Kempsey DCP and will therefore not require terracing. No evidence of instability was observed during the site inspection hence slope is not considered to be a limitation for on-site sewerage disposal.

Surface water

An unnamed tributary of Killick Creek runs through the site and a wetland is located to the east. Sufficient area is available to achieve the required 100m buffer from waterways or wetlands.

Groundwater

Limited information is available in relation to groundwater in the locality. The depth to groundwater is uncertain at the site. Analysis of existing development in the estate suggests that biocycle systems installed at the same elevations and soil types would be suitable for future development on the site.

The NSW NR Atlas shows one groundwater bore within the eastern portion of the site but there is no information on what it is used for. It is not used as a domestic water supply.

Overland surface flow

Due to the slope of the site it is anticipated that there would be overland surface flow across the disposal field during periods of high rainfall. However, this would be minimised by providing surface diversion drains to divert upslope run-on water clear of the field.

Erosion potential

There were no signs of erosion observed at the site during the site inspection and the nature of the vegetation established on-site, at present, indicates that suitable grasses can be established and maintained to provide protection against erosion.

Surface dampness

No surface dampness was noted during the site investigation.

Aspect

The disposal areas would face east and exposure to sun and wind in these locations are suitable for effluent disposal.

Surface rocks

Rocks or rock outcrops are not considered to present a limitation to the disposal of wastewater at the site.

3.4.2 Treatment system

Tank

It is assumed a biocycle system (or similar) is the most likely form of treatment system to be used at the site. These systems are used widely throughout the existing estate and provide the environmental performance required in this type of landscape. Septic tanks may achieve the minimum performance criteria (see below) but the use of a more environmentally friendly system such as the biocycle system is promoted by the applicant.

Disposal field design

Based on an assessment by Midcoast Environmental Service (2007) on an adjacent property (previous Lot 104 DP 884312 and Lot 372 DP 1070288), the design parameters were:

Table 3-2 Design parameters

Design parameter	Assumption
System	Septic
Soil Permeability	<0.06 (m/d)
Design Daily Flow (4 bedroom dwelling)	870L/d
Crop Factor	0.75
Rainfall	1205mm/yr
Evaporation	1610 mm/yr
Design Loading Rate (DLR)	17mm/day
Trench width	400mm

Based on the design parameters in Table 3-2 and AS/NZS 1547 – 2012, the required length of a 400 mm wide trench for a 4 bedroom dwelling is 128m. The trench length can be reduced if the effluent is treated to a secondary level. Trench lengths have been calculated using the formulae provided in Section L4.2 of AS 1547 – 2000 as follows:

$$L = \frac{Q}{DLR \times W}$$

Where:

L	=	Length in m
Q	=	Design daily flow in L/day
DLR	=	Design Loading Rate in mm/d
W	=	Width in m

Future augmentation

As required by the Kempsey DCP 2013, provision is required for a reserve disposal area.

3.4.3 Potable water and servicing

Potable water

Each dwelling will be required to include a suitably sized rain water tank as the primary means of providing water. The minimum size of the water tank will be determined in consultation with Council during the development application process.

There will be a back-up water supply system via an unpressured water main to each tank. This would only be used should the tank run out of water or in the case of bushfire and emergencies. An unpressured water main already exists at the southern boundary of the site as part of the servicing works associated with the original Dulconghi Heights subdivision. The main is located at the end of the existing Neville Morton Drive. It is proposed to continue to bring this main through into the new subdivision and service all lots via the proposed internal road network.

Servicing

Telecommunications and electricity will also be supplied to the site via the extension of the services located at the end of the existing Neville Morton Drive. There is a servicing pit located to the immediate south of the proposed subdivision and these services will extend into the subdivision, servicing all lots, via the proposed internal road network.

3.4.4 Summary

The assessment of the site characteristics, soil type, waste generated and system capabilities have indicated that, in accordance with the relevant guidelines, the disposal of treated sullage by an on-site wastewater disposal system is a viable option for the site.

The assessment undertaken indicates that each of the indicative lots would have sufficient area to accommodate a suitable disposal field and reserve area that complies with the requirements of the Kempsey DCP 2013.

It is recommended that any future development be accompanied by a specific assessment based on expected loadings and the specific location of any treatment system.

3.5 Traffic assessment

The primary road network serving the proposed subdivision comprises:

- Neville Morton Drive – a two-way, unmarked bitumen sealed road.
- Crescent Head Road – a dual lane, sealed road with lane markings between Crescent Head and Kempsey.
- Macleay Valley Way – a dual lane, sealed road with lane marking linking Crescent Head to Kempsey and the Pacific Highway.
- Pacific Highway – a State Road and arterial route being the principal link between to Sydney and Brisbane.

GHD have reviewed traffic generation rates for residential dwellings in accordance with the Roads and Maritime Services (2002) publication *Guide to Traffic Generating Developments*. GHD have calculated that the Planning Proposal will generate the following traffic volumes:

- Proposed new dwellings = Maximum of 14
- Weekday peak hour vehicle trips (0.85 per dwelling) = 11.9

- Daily vehicle trips (9.0 per dwelling) = 126

Given such low traffic generation potential, the existing capacity of the surrounding road network is considered adequate to accommodate the Planning Proposal.

3.6 Visual assessment

The visual impacts associated with the proposal will be minimal with views of the site limited to the highest parts of Crescent Head only. Any visual impacts will be similar to the existing Dulconghi Heights subdivision, if not less, due to the applicants approach to dwelling siting on the proposed western lots within the existing E3 scenic protection zone. In addition, there is a large patch of intact native vegetation to the east of the site which will largely block the view to any future dwellings from Crescent Head (see Plate 2).

The proposal seeks to adjust the E3 zone to match the same contour as the E3 zone for the existing Dulconghi Estate. The difference with this planning proposal is that dwelling siting will be at the front of the western blocks meaning there will be no dwellings placed at the rear of these blocks which was the case within the existing subdivision. This approach has been presented by the applicant to reduce visual impacts and to better manage bushfire constraints.

To illustrate this, the applicant has taken photographs from an appropriate location within the village of Crescent Head. The subdivision could not be sighted from the water tower on Skyline Crescent so the applicant found a suitable location at the intersection of Comara Terrace and Dulconghi Street. The location and direction of the photo is shown in Plate 2. The resulting photo of the existing subdivision with the location of the proposed subdivision (blue ellipse) is shown in Plate 3



Plate 2 Location of visual assessment photo



Plate 3 View line towards site

The future development of the site for large lot rural residential purposes is not considered likely to result in a significant detrimental impact on the visual amenity of the Crescent Head area for the following reasons:

- Only a limited amount of vegetation is to be cleared to facilitate the use of the site for large lot residential purposes, consistent with the existing Dulconghi Estate.
- Indicative building envelopes have been sited on the lower elevations of the proposed lots thereby minimising exposure from Crescent Head.
- A large patch of intact native vegetation to the east of the site will largely block the view to any future dwellings from Crescent Head.
- The position of the site is located at the base of the predominant feature in the landscape Dulconghi Hill.
- Only limited vantage points exist to view the site.
- Mitigation measures such as use of complimentary colour schemes could minimise any impact from future development.

4. Planning Proposal

4.1 Part 1 - Statement of objectives of proposed LEP

To rezone Lot 3 DP 1164661, Neville Morton Drive, Crescent Head to R5 Large Lot Residential, with a minimum lot size of 1 hectare (ha). A plan of the proposed rezoning is provided in Figure 4, Appendix A.

4.2 Part 2 - Explanation of provisions to be included in proposed LEP

Explanation of the Provisions that are to be included in the proposed LEP

Table 4-1 Proposed rezoning

Current Zoning	Proposed Zoning	Proposed Area (Ha)
RU2 Rural Landscape	R5 Large Lot Residential	4.6
E3 Environmental Management	R5 Large Lot Residential	7.7
E3 Environmental Management	E2 Environmental Conservation	37.9

The proposed rezoning will be achieved by evaluating the justification for:

- Amending the Kempsey LEP 2013 Land Zoning Map for the site in accordance with the proposed zoning map, shown as Figure 4 in Appendix A; which indicates a rezoning of the site from RU2 Rural Landscape (4.54 ha) and E3 Environmental Management (7.28 ha) to R5 Large Lot Residential under Kempsey Local Environmental Plan (LEP) 2013.
- Amending the Kempsey LEP 2013 Land Zoning Map to adjust the current zoning to the west of the proposed subdivision from E3 Environmental Management to E2 Environmental Conservation.
- Amending the Kempsey LEP 2013 Lot Size Map for the site in accordance with the proposed lot size map, shown as Figure 4(a) in Appendix A, which proposes an approximate lot size of 1 ha for the site.
- Amending the Kempsey LEP 2013 Scenic Protection Land Map for the site in accordance with the proposed scenic protection map, shown as Figure 4(b) in Appendix A, which indicates the site as having scenic values.

4.3 Part 3 - Justification of proposal

4.3.1 Section A - Need for a Planning Proposal

Is the planning proposal a result of any strategic study or report?

A Planning Proposal is required as the site has been identified in Council's Rural Residential Land Release Strategy as a Stage 1 site for future rezoning.

Is the planning proposal the best means of achieving the objectives or intended outcomes or is there a better way?

The Planning Proposal is the most suitable means of achieving the objective of land rezoning.

A Strengths, Weaknesses, Opportunities, Threats (SWOT) analysis of the Planning Proposal has been undertaken to inform the rezoning process and provide an overview of the key issues, as tabulated below.

Table 4-2 SWOT analysis

Strengths	Weaknesses
• The site lies adjacent to an existing rural residential estate that has a central access road and associated services which extend to the boundary of the site. • The site is partially cleared of vegetation, including minimal understorey vegetation in the proposed development zone • Does not have any known heritage constraints • Is relatively secluded and therefore any subsequent development would not impact the scenic quality of the area • Is not flood prone, with the exception of a small portion in the east of the site • Does not contain SEPP 26 Littoral rainforest • Is not regionally significant farm land • Koala feed trees (Tallowwood) present on the site are limited to a few individual trees only distributed in the western portion of the site	• A SEPP 14 wetland is located to the east of the site • Vegetation on a portion of the site is identified as secondary (Class A) koala habitat • The site is identified as an Area Subject to a Koala Management Plan (Kempsey LEP 2013) • A bushfire hazard exists at the site and requires management • A portion of the site in the west is mapped as Scenic Protection land (Kempsey LEP 2013)
Opportunities	Threats
• Social benefits to future population by supplying rural residential land in a high demand location • Significant economic benefits as it is in close proximity to existing urban areas of Crescent Head and Kempsey town centre. The subject site would be an extension to an existing rural residential subdivision thereby lowering developmental costs • Environmental benefits as the lots will be large enough to sustain on site sewer, protection of visual amenity, koala feed trees and there are no significant environmental constraints that cannot be managed efficiently • The ability to rezone a site which has minimal environmental constraints, will not fragment significant agricultural land or reduce the heritage or scenic values of the region	• Rezoning land currently classified as E3 • Social and economic consequences if not enough land is available in appropriate and desirable locations

Is there a net community benefit?

Roads, services and other infrastructure already exist at the site's boundary. This means the development can proceed efficiently by extending the existing infrastructure. This will benefit the future population by delivering a more cost effective development helping to reduce property prices in this limited market. The Strategy (KSC, 2014) includes a market analysis for rural residential land demand. This was based on interviews with local agents. The report states the strongest demand in Kempsey Shire is at Crescent Head.

The analysis states 'there is latent demand in coastal areas' and 'local agents would particularly like to see an increase in rural residential land supply in Crescent Head, compared to any other suburb in Kempsey Shire'.

Of further importance is the fact the site has the ability to apply for rezoning and development approval quickly, meaning supply pressures could be reduced in a timely manner through the rezoning and development application approval process.

The existing population of Kempsey Shire will also benefit from the rezoning through the creation of jobs during the development stage. It is expected that industries required would include professional services, earthworks and construction trades and suppliers. Existing retail business would also presumably expect to benefit from residential expansion.

Finally, this Planning Proposal promotes the rezoning of a site with fewer constraints than others in the locality and identified in the Strategy.

4.3.2 Section B - Relationship to strategic planning framework

Is the Proposal consistent with the objectives and actions contained within the applicable Regional or Sub-Regional Strategy?

Mid North Coast Regional Strategy, 2009

Comment: The Planning Proposal is consistent with the Mid North Coast Regional Strategy (Department of Planning, 2009) in regard to actions for rural residential developments; these being.

1. Future rural residential land will only be zoned for release if it is in accordance with a local growth management strategy agreed to between council and the Department of Planning and consistent with the principles of the Settlement Planning Guidelines.
2. No new rural residential development will be permitted within the Coastal Area, other than development already zoned or in an approved current or future local growth management strategy (or rural residential land release strategy).
3. Planning for rural residential land must be integrated with the supply of infrastructure and transport.

Draft North Coast Regional Plan, 2016

The draft North Coast Regional Plan was prepared by Department of Planning and Environment in 2016 and was released for public exhibition between 2 March and 2 June 2016. The relevant goals, directions and actions of the plan are outlined below:

GOAL 2 – Focus growth opportunities to create a great place to live and work

- DIRECTION 2.3 Focus growth to the least sensitive and constrained areas to protect natural assets

- ACTION 2.3.2 identify residential, commercial and industrial uses in urban growth areas by developing local growth management strategies
- ACTION 2.3.3 minimise the impact of rural residential development

Comment: The Planning Proposal is consistent with Council's Rural Residential Land Release Strategy which identifies the subject site as being capable and suitable for rural residential purposes. In this respect the Planning Proposal is considered to be consistent with Direction 2.3 and Actions 2.3.2 and 2.3.3.

GOAL 3 – Housing choice, with homes that meet the needs of changing communities

- DIRECTION 3.1 Provide sufficient housing supply to meet the demands of the North Coast
 - ACTION 3.1.1 review land supply to identify proposed urban land for extra dwellings
 - ACTION 3.1.2 accelerate the supply of proposed urban land to meet demand in high growth areas
- DIRECTION 3.3 Deliver more opportunities for affordable housing
 - ACTION 3.3.1 Facilitate the supply of more affordable housing

Comment: The Planning Proposal is considered to be consistent with Direction 3.1 and Actions 3.1.1 and 3.1.2 and Direction 3.3 and Action 3.3.1 as it will provide for the demand for rural residential housing demonstrated in Council's Rural Residential Land Release Strategy.

Is the Planning Proposal consistent with applicable State Environmental Planning Policies?

State Environmental Planning Policy (SEPP)	Statement of Consistency
SEPP No. 14 - Coastal Wetlands	Clause 7 of the SEPP outlines the matters for consideration. The relevant matters are addressed below: <i>(1) In respect of land to which this policy applies, a person shall not:</i> <i>(a) clear that land,or</i> <i>(d) fill that land</i> No clearing or filling is proposed to be undertaken on lands inside the mapped SEPP 14 wetlands. This boundary is location within the proposed eastern lots of the subdivision and no activity associated with dwelling construction, APZ management and servicing is planned in these areas.
SEPP No 44 – Koala habitat protection	Clause 7 and 8 of the SEPP state that when considering a development application for land that has either potential or core koala habitat, Councils must consider guidelines for preparing plans of management for areas of identified habitat. Kempsey Shire's CKPoM (Biolink, 2011) has been developed and approved as a plan of management under the SEPP. This effectively means the SEPP's requirements have been satisfied and that the Planning Proposal would not contravene this SEPP providing the future subdivision complies with the requirements of the CKPoM.
SEPP No. 55 – Remediation of land	The site has only been used in the past for forestry and light grazing purposes. Infrastructure on the site comprises a metal cattle yard constructed in recent years. The site has not been the subject of notices issued by the EPA under the Contaminated Land Management Act 1997 (CLM Act). Additionally, GHD have checked the NSW Department of Primary Industries cattle dip site locator and confirmed that the site is not listed on this register. It is therefore considered that the Planning Proposal would not contravene this SEPP
SEPP Major Development 2005	The Planning Proposal would not contravene this SEPP
SEPP Infrastructure 2007	The Planning Proposal would not contravene this SEPP
SEPP Rural Lands 2008	Complies. The Planning Proposal is consistent with the Rural Planning Principles detailed in Clause 7 of this SEPP
SEPP Exempt and Complying Development 2008	Complies. The exempt and complying tables in Kempsey LEP 2013 have been carefully developed to be consistent with this SEPP. The Planning Proposal does not propose to change these provisions.

Is the Planning Proposal consistent with applicable Ministerial Directions (Section 117 Directions)?

Section 117(2) Direction	Relevant to the Planning Proposal	Consistent with the Direction?	Justification
1. Employment and Resources			
1.2 Rural Zones	Yes	No	Pursuant to this direction, a planning proposal must not rezone land from a rural zone to a residential, business, industrial, village or tourist zone. However, the Planning Proposal may be inconsistent where justified by a strategy which: (i) gives consideration to the objectives of this direction, (ii) identifies the land which is the subject of the planning proposal (if the planning proposal relates to a particular site or sites), and (iii) is approved by the Director-General of the Department of Planning As the site has been identified in Council's Rural Residential Land Release Strategy 2014 and approved by DPE, it is therefore eligible for consideration for rezoning and subdivision for rural residential development.
1.5 Rural Lands	Yes	Yes	The Planning Proposal is consistent with the Rural Planning Principles listed in <i>State Environmental Planning Policy (Rural Lands)</i> 2008 and therefore with the terms of the direction.
2. Environment and Heritage			
2.1 Environment Protection Zones	Yes	No	A planning proposal must include provisions that facilitate the protection and conservation of environmentally sensitive areas. Land in the eastern portion of the site is currently zoned E2. It is not proposed to rezone any of these lands and the proposed subdivision has been designed to ensure no dwelling, associated impacts or APZ's would impact on this area. There is a portion of the site in the west currently zoned E3 Scenic Protection. These lands contain Blackbutt-Tallowood open forest in a degraded form. This portion of the site is subjected to constant grazing meaning the mid storey has been completely removed and the ground layer is a mixture of introduced pastures with scattered native herbs and grasses. This vegetation type is not listed as an EEC and is listed as only being 35% cleared in the NSW Vegetation Types Database. It should be noted that the E3 zoning has been applied due to the previous scenic protection zoning rather than because this portion of the site includes environmentally sensitive lands as described in the 117 Directions for planning proposals. The planning proposal seeks to have this zoning boundary adjusted to match the same contour (approximately the 30m contour) as that which exists for the existing Dulconghi Estate to the immediate south. Lands to the east of this contour would be zoned R5. The ecological investigation indicates

Section 117(2) Direction	Relevant to the Planning Proposal	Consistent with the Direction?	Justification
			development in this location would not result in significant impacts to biodiversity and would be consistent with the strategy. The planning proposal will not result in impacts to endangered ecological communities. The planning proposal would include minor impacts to Koala habitat as the site contains scattered individuals of Tallowwood, a listed primary feed tree under the CKPOM. However, these impacts will be mitigated through the protection of such resources via the use of onsite conservation measures such as Tree Preservation Orders or Section 88B instruments as suitable. In addition, building footprints and associated APZ's have been identified to minimise impacts to existing vegetation and clearing restrictions will apply to a portion of some lots as indicated in the Ecology Assessment. The planning proposal also seeks to rezone the remaining lands in the western portion of Lot 3 DP 1164661 (i.e. lands to the west of the 30 m contour totally approximately 37.9 ha) from E3 to E2. to offset impacts to native vegetation at the site. This approach was discussed with representatives of the DPE and OEH during a site visit on 3 February 2016 and it was agreed this would be a suitable offset activity for the proposals impacts. Matters relating to threatened species impacts would be assessed in more detail during preparation of the development application for the site in accordance with relevant legislation, however the Planning proposal and the subsequent rural residential development of the site is not expected to result in any significant impacts to biodiversity. Pursuant to Clause (6) of this direction, a planning proposal may be inconsistent with the terms of this direction only if the relevant planning authority can satisfy the Director-General of the Department of Planning (or an officer of the Department nominated by the Director-General) that the provisions of the planning proposal that are inconsistent are: <i>(a) justified by a strategy which:</i> <i>i. gives consideration to the objectives of this direction,</i> <i>ii. identifies the land which is the subject of the planning proposal (if the planning proposal relates to a particular site or sites), and</i> <i>iii. is approved by the Director-General of the Department of Planning, or</i> <i>(b) justified by a study prepared in support of the planning proposal which gives consideration to the objectives of this direction, or</i> <i>(c) in accordance with the relevant Regional Strategy or Sub-Regional Strategy prepared by the Department of Planning which gives consideration to the objective of this direction, or</i> <i>(d) is of minor significance.</i> As the site has been identified in the Strategy and justified by the Ecology Assessment (GHD, 2016) supporting this Planning Proposal, the inconsistency is considered to be justified.

Section 117(2) Direction		Relevant to the Planning Proposal	Consistent with the Direction?	Justification
3. Housing, Infrastructure and Urban Development				
3.1	Residential Zones	Yes	Yes	The Planning Proposal proposes to rezone the subject land from RU2 Rural Landscape and E3 Environmental Management to R5 Large Lot Residential. The Planning Proposal if supported and gazetted would allow for the development of residential dwellings within a rural setting consistent with the existing development along Neville Morton Drive. As such it will broaden the choice of building types and locations available in the housing market and make more efficient use of existing infrastructure and services in the area. Any future development of the land can be controlled via Council's existing DCP to ensure quality design. As Kempsey LEP 2013 contains provisions that ensure residential development is not permitted until land is adequately serviced (or arrangements satisfactory to the council, or other appropriate authority, have been made to service it). The Planning Proposal is therefore considered to be consistent with this direction.
3.4	Integrating Land Use and Transport	Yes	Yes	The objective of this direction is to ensure that urban structures, building forms, land use locations, development designs, subdivision and street layouts achieve the following planning objectives: <i>(a) improving access to housing, jobs and services by walking, cycling and public transport, and</i> <i>(b) increasing the choice of available transport and reducing dependence on cars, and</i> <i>(c) reducing travel demand including the number of trips generated by development and the distances travelled, especially by car, and</i> <i>(d) supporting the efficient and viable operation of public transport services, and</i> <i>(e) providing for the efficient movement of freight.</i> The Planning Proposal will facilitate large lot residential development. As the subject land is located adjacent to an existing rural residential estate in close proximity to Crescent Head, it is considered to be consistent with the aims, objectives and principles of: <i>(a) Improving Transport Choice – Guidelines for planning and development (DUAP 2001), and</i> <i>(b) The Right Place for Business and Services – Planning Policy (DUAP 2001).</i> The Planning Proposal is therefore considered to be consistent with this direction.

Section 117(2) Direction		Relevant to the Planning Proposal	Consistent with the Direction?	Justification
4. Hazard and Risk				
4.1	Acid Sulfate Soils	Yes	No	A relevant planning authority must not prepare a planning proposal that proposes an intensification of land uses on land identified as having a probability of containing acid sulfate soils (ASS) on the Acid Sulfate Soils Planning Maps unless the relevant planning authority has considered an acid sulfate soils study assessing the appropriateness of the change of land use given the presence of acid sulfate soils. The relevant planning authority must provide a copy of any such study to the Director- General prior to undertaking community consultation in satisfaction of section 57 of the Act. KLEP 2013 Acid Sulfate Soil mapping (Sheet ASS012B) indicated the site is underlain by Class 2 and Class 5 ASS. Land mapped as Class 2 ASS (higher risk) are located to the east of the proposed rezoning and will remain zoned E2 Environmental Conservation. No works below the natural ground surface or works which may enable the watertable to be lowered would be undertaken in this area (dwelling construction and other activities will be restricted from this portion of the site). Therefore, this approach does not comprise an intensification of land uses. Land mapped as Class 5 ASS (lower risk) is proposed to be zoned to R5 Large Lot Residential. The proposed development will not include any works likely to lower the water table, such as: - the temporary or permanent use of pumps to lower the natural groundwater level within and/or around the development site. - the construction or maintenance of large drains. A inconsistency with this direction is therefore noted, but as the proposal does not include works likely to lower the watertable, the inconsistency is considered to be of minor significance and as such the Planning Proposal is considered acceptable.
4.3	Flood Prone Land	Yes	No	Due to proximity to the unnamed wetland, lands to the east of the proposed rezoning below 4.21 mAHD are affected by the 1 in 100 year flood event. As indicated on Figure 4, the proposed easterly boundary residential lots in this locality will coincide with the 1 in 100 ARI flood level. Therefore, future building envelopes and associated APZ's for would be located to the west of the 1 in 100 year ARI flood level with no development below 4.71 mAHD. The Planning Proposal is therefore considered to be compliant with this direction.

Section 117(2) Direction		Relevant to the Planning Proposal	Consistent with the Direction?	Justification
4.4	Planning for Bushfire Protection	Yes	Yes	The Planning Proposal is substantially consistent with this direction as: • Adequate space is available to meet the APZ requirements in all directions; however some vegetation would need to be cleared. • The intent of PBP 2006 in relation to Public Roads, Property Access and Fire Trails can still be achieved given the relatively cleared nature of the site. • The site contains sufficient area and conditions to achieve the PBP 2006 acceptable solutions for water, electricity and gas.
5. Regional Planning				
5.1	Implementation of Regional Strategies	Yes	Yes	The Planning Proposal is considered to be consistent with the Mid North Coast Regional Strategy as it responds to Council's Rural Residential Land Release Strategy prepared in 2014 terms of the direction.
6. Local Plan Making				
6.1	Approval and Referral Requirements	Yes	Yes	The Planning Proposal does not propose any additional approval or referral requirements over and above those identified in KLEP 2013.
6.2 Land	Reserving for Public Purposes	NA	Yes	The Planning Proposal is consistent with this direction because it does not affect land reserved for public purposes.
6.3	Site Specific Provisions	Yes	Yes	Direction applies substantially to amending LEPs. The Planning Proposal proposes to rezone the site to an existing zone (R5 Large Lot Residential) in KLEP 2013. The zone allows for rural residential subdivision and development without imposing any development standards or requirements in addition to those already applicable to the zone. The Planning Proposal is therefore considered to be consistent with this clause as it does not require any site specific provisions.

4.3.3 Section C - Environmental, social and economic impacts

Is there any likelihood that critical habitat, threatened species, populations or ecological communities or their habitats will be adversely affected as a result of the Proposal?

The site contains a small patch of remnant trees indicative of Paperbark Swamp Forest associated with a minor drainage line. This vegetation is not considered to be commensurate with the Swamp sclerophyll forest on coastal floodplains of the NSW North Coast endangered ecological community (EEC) as the vegetation does not occur on a floodplain. The community exists as a small patch of remnant *Melaleuca quinquinervia* trees only with no shrub layer present and groundcovers being limited to introduced pastures. The area is also subjected to constant grazing. This vegetation community would be subjected to the removal of several remnant trees only to accommodate the proposed access road with the majority of the remnant Paperbark trees being retained within lots. Indirect impacts would be managed by the use of appropriate planning restrictions, location and management of APZ's and proposed onsite wastewater management systems.

A second vegetation type present in the western portion of the site and is referred to as Blackbutt Tallowwood grassy open forest, which is in a modified state with the mid storey largely removed. Although not an EEC, this community is mapped as Secondary (Class B) Koala Habitat within the CKPoM. As this vegetation contains scattered individuals of the primary food trees Tallowwood (*Eucalyptus microcorys*) and Grey Gum (*Eucalyptus propinqua*) this portion of the site should be classified Secondary (Class A) Koala Habitat (GHD, 2016). Any subdivision of the site would include nominated building envelopes within lots, the retention of almost all Primary Koala Feed Trees via a suitable planning mechanism (such as Tree Preservation Order) and gazetting biodiversity offsets for conservation if required (see Figure 6 and Appendix B for details).

An assessment of the impacts of the proposed development on the Koala (*Phascolarctos cinereus*) has been completed for the proposed rezoning in accordance with the Kempsey CKPoM (Biolink, 2011) and is included in the Ecology Assessment (Appendix B).

Therefore, it can be concluded that the proposed subdivision would have a negligible impact on Swamp sclerophyll forest on coastal floodplains and a limited impact on secondary koala habitat.

The Ecology Assessment (Appendix B) also concludes the proposal would be unlikely to have a significant impact on any other threatened biota. However, a detailed impact assessment would be completed as part of any future DA documentation for the site. It should be noted that the indicative subdivision plan presented in the Planning Proposal has been provided to show how a potential subdivision may apply to the land and the considerations associated with reducing impacts to biodiversity. This layout may be subject to change (either through the realignment of lot boundaries or repositioning/reduction in dwellings) depending on decisions made by approval authorities and/or the applicant. In this regard it is not plausible to complete a full ecological impact assessment at this stage of the planning process.

Are there any other likely environmental effects as a result of the Planning Proposal and how are they proposed to be managed?

Flooding

The Planning Proposal addresses flooding by ensuring that any nominated building footprints and the associated road network would be located above the flood planning level (4.71 mAHD) for the area and therefore flood free for the 5, 20 and 100 year ARI flood events. In a 100-year ARI event (4.21 mAHD), over 80% of the proposed subdivision would be flood free, while the remaining portion of the site would receive localised area flooding to an average depth of approximately 1.5 m. In accordance with the NSW Floodplain Development Manual (Department of Planning and Infrastructure and Natural Resources, 2005) this depth equates to a High Flood Hazard rating. No development would be undertaken in this area, therefore the flood storage capacity of the area would remain unchanged and there would be no increased risk of property damage or issues with emergency egress.

Wastewater management

Given that there is no reticulated sewer available in the area, all effluent would need to be disposed of via an on-site wastewater treatment system. A site specific assessment has been undertaken (GHD, 2015) to ensure that proposed dwellings can be provided with on-site effluent treatment systems. The results show that the proposed Biocycle system can adequately accept effluent without detrimental environmental or health impacts in accordance with the On-site Sewage Management for Single Households and AS 1547 – 2000 and Council requirements.

Bushfire

The draft subdivision plan includes proposed locations for dwellings on the site to assist in minimising biodiversity impacts and to address bushfire requirements. Asset protection zones (APZs) are also indicated on the draft subdivision plan. In accordance with NSW planning legislation, management of APZs requires a discontinuous canopy and minimal understorey (which is the existing situation due to active grazing of the site) to comply with the provisions of *Planning for Bush Fire Protection* (PBP) (RFS, 2006). A Bushfire Hazard Assessment was undertaken (refer Section 3.2), the results of which indicate:

- Adequate space is available to meet the APZ requirements in all directions; however, some vegetation would need to be cleared.
- The intent of PBP 2006 in relation to Public Roads, Property Access and Fire Trails can be achieved given the relatively cleared nature of the site.
- The site contains sufficient area and conditions to achieve the PBP 2006 acceptable solutions for water, electricity and gas.

How has the Planning Proposal adequately addressed any social and economic effects?

Prior to preparation of this planning proposal GHD (2013) prepared a rezoning submission. The justification included a detailed review of land supply and demand and the social and economic factors associated with the proposed rezoning of the site.

The report concluded that the proposed rezoning would have:

- Significant social benefits by supporting high demand areas that are close to the coast and urban services and that are accessible from an existing rural residential subdivision.
- Significant economic benefits as it is in close proximity to existing urban areas of Crescent Head and Kempsey town centre. The subject site would be an extension to an existing rural residential subdivision thereby lowering development costs.

4.3.4 Section D - State and Commonwealth matters

Is there adequate public infrastructure for the Planning Proposal?

The site would simply be an extension to the existing rural residential estate on Neville Morton Drive. This subdivision has existing services, including a sealed road, through to the southern boundary of the site. The proposed subdivision would require an extension of the sealed road and associated services only.

The subject site is located within 3 km of Crescent Head town centre and approximately 10 km of Kempsey. The site is located immediately adjacent to existing rural residential land and can therefore support existing services.

The subject site will provide additional rural residential dwellings in an area which is in high demand, being in close proximity to Crescent Head. Residents are likely to utilise and support Kempsey as a major town centre.

Therefore, there is adequate public infrastructure for the Planning Proposal.

What are the views of State and Commonwealth public authorities consulted in accordance with the gateway determination?

Consultation undertaken as part of this Planning Proposal has been limited to meetings with Council. It is assumed that consultation with Office of Environment and Heritage, Department of Primary Industries and Environment Protection Authority would be undertaken by Council as part of its consideration of the Planning Proposal.

4.4 Part 4 - Mapping

The proposed rezoning has been documented as follows:

- Amending the Kempsey LEP 2013 Land Zoning Map for the site in accordance with the proposed zoning map shown in Appendix A; which indicates a rezoning of the site from RU2 Rural Landscape (4.6 ha E3 Environmental Management (7.7 ha) to R5 Large Lot Residential under Kempsey Local Environmental Plan (LEP) 2013.
- Amending the Kempsey LEP 2013 Land Zoning Map to adjust the current zoning to the west of the proposed subdivision from E3 Environmental Management to E2 Environmental Conservation.

- Amending the Kempsey LEP 2013 Lot Size Map for the site in accordance with the proposed lot size map, shown in Appendix A, which proposes an approximate lot size of 1 ha for the site.
- Amending the Kempsey LEP 2013 Scenic Protection Land Map for the site in accordance with the proposed scenic protection map, shown in Appendix A, which indicates the site as having scenic values.

4.5 Part 5 – Community consultation

The Planning Proposal has not been subject to any community consultation at this stage. In accordance with Department of Planning and Environment's guidelines (2012) *Guide to Preparing Planning Proposals*, it is understood a Council resolution would be sought following evaluation of the strategic justification for the amendment to KLEP 2013.

Further consultation would be undertaken should Council resolve to forward the Planning Proposal to the gateway for determination.

4.6 Part 6 – Project timeline

The proposed timeline for completing the rezoning process is summarised in Table 4-3 below.

Table 4-3 Project timeline

LEP Amendment Steps	Estimated Project Timing
Submit Updated Planning Proposal to DP&E	August 2016
Receive Gateway determination	October 2016
Authority consultation - pre-exhibition*	Already undertaken with primary agency of OEH. Other consultation will be part of general public exhibition.
Preparation of materials for public exhibition & authority consultation	October/November 2016
Public exhibition of Planning Proposal & government authority consultation (Min 28 Days)	Nov/Dec 2016
Review and consideration of submissions	January 2017
Council report preparation	February 2017
Public submissions report and draft LEP amendment to Council for adoption	March 2017
Submission to the department to finalise the LEP or exercise Council delegation to make the plan	March 2017
Submit request for drafting of LEP to Parliamentary Counsel's Office^	April 2017
Forward to the department for notification	
* If required	
^ If delegated	

5. Conclusion

A Planning Proposal was required as the subject site has been identified in Council's Rural Residential Land Release Strategy as a Stage 1 site for future rezoning.

This Planning Proposal recommends that Kempsey Shire Council, as the relevant planning authority, prepare an amendment to KLEP 2013, to reflect the proposed rezoning. The suggested rezoning of the site is shown in Figure 4 in Appendix A and recommends that an area of 12.3 ha of the site be rezoned to R5 Large Lot Residential.

The site is immediately adjacent to an existing rural residential subdivision and has no known constraints that would limit its ability to provide rural residential subdivision for the locality. It will not produce fragmentation of significant agricultural land nor will it reduce the heritage or scenic values of the region.

The proposed subdivision could provide lots to the market quickly due to:

- Single ownership under a landholder aware of, and financially capable of, undertaking additional environmental assessments as required in the subsequent planning stages.
- The existing provision of services and infrastructure to the southern boundary enabling the development to be delivered in a cost effective manner.
- A large portion of the site is unconstrained.
- Biodiversity and other environmental constraints can be readily addressed (as outlined in Section 3).

It is therefore requested that Council amend KLEP 2013 for Lot 3 DP 1164661, Neville Morton Drive, Crescent Head to R5 Large Lot Residential with an approximate lot size of 1 ha.

6. Disclaimer

This report: has been prepared by GHD for Dulconghi Investments Pty Ltd and may only be used and relied on by Dulconghi Investments Pty Ltd for the purpose agreed between GHD and the Dulconghi Investments Pty Ltd as set out in section 1.1 of this report.

GHD otherwise disclaims responsibility to any person other than Dulconghi Investments Pty Ltd arising in connection with this report. GHD also excludes implied warranties and conditions, to the extent legally permissible.

The services undertaken by GHD in connection with preparing this report were limited to those specifically detailed in the report and are subject to the scope limitations set out in the report.

The opinions, conclusions and any recommendations in this report are based on conditions encountered and information reviewed at the date of preparation of the report. GHD has no responsibility or obligation to update this report to account for events or changes occurring subsequent to the date that the report was prepared.

The opinions, conclusions and any recommendations in this report are based on assumptions made by GHD described throughout this report. GHD disclaims liability arising from any of the assumptions being incorrect.

GHD has prepared this report on the basis of information provided by Dulconghi Investments Pty Ltd and others who provided information to GHD (including Government authorities)], which GHD has not independently verified or checked beyond the agreed scope of work. GHD does not accept liability in connection with such unverified information, including errors and omissions in the report which were caused by errors or omissions in that information.

7. References

AS/NZS 1547-2012 *On-site Domestic-Wastewater Management*

Biolink Ecological Consultants (2011) *Comprehensive Koala Plan of Management for Eastern Portion of Kempsey Shire LGA*. Prepared for Kempsey Shire Council.

Department of Planning (2009) *Mid North Coast Regional Strategy*. March 2009.

Department of Planning and Infrastructure (2012) *Guide to Preparing Planning Proposals*. October 2012.

Department of Planning and Infrastructure and Natural Resources (2005) *NSW Floodplain Development Manual*. April 2005.

GHD (2013) *Crescent Head Rezoning Submission*. Prepared for Dulconghi Investments.

Insite (2013) *Background Report for Kempsey Shire Rural Residential Land Release Strategy*. Prepared for Kempsey Shire Council.

Kempsey LALC (1996) *Survey of Proposed Development on Lots 1, 2 & 3 – DP 794159*

Kempsey LALC (2015) *Aboriginal Site Inspection of the Dulconghi Heights Rezoning, Crescent Head*

Kempsey Shire Council (2014) *Kempsey Shire Rural Residential Land Release Strategy*. April 2014.

Midcoast Environmental (2007) *On-site Sewage Management Assessment*. Prepared for Peterson, Ryder, Ball and Geoportofino.

NSW Government (1998) *Environment and Health Protection Guidelines – On-site Sewage Management for Single Households*

NSW NPWS (1996) *NPWS Site inspection of Lots 1, 2, 3 DP794159 Crescent Head*.

Rural Fire Service (2006) *Planning for Bush Fire Protection*.

Appendices

Appendix A - Figures



Paper Size A4
0 155 310 620 930 1,240
Metres

Map Projection: Transverse Mercator
Horizontal Datum: GDA 1994
Grid: GDA 1994 MGA Zone 56



LEGEND

-  Investigation area
-  Cadastre




Dulconghi Investments Pty Ltd
Dulconghi Heights Rezoning Application

Job Number 22-17672
Revision A
Date 10 Mar 2016

Regional Locality

Figure 1



Paper Size A4
0 60 120 240 360 480
Metres

Map Projection: Transverse Mercator
Horizontal Datum: GDA 1994
Grid: GDA 1994 MGA Zone 56



LEGEND

- Investigation area
- Cadastre
- Watercourse
- SEPP No.14 - Coastal Wetlands
- SEPP No.71 - Coastal Protection



Dulconghi Investments Pty Ltd
Dulconghi Heights Rezoning Application

Job Number 22-17672
Revision A
Date 10 Mar 2016

Existing Condition


Figure 2

G:\22\17672\GIS\Maps\Deliverables\2217672_002_ExistingCondition_A.mxd

Level 3, GHD Tower, 24 Honeysuckle Drive, Newcastle NSW 2300 T 61 2 4979 9999 F 61 2 4979 9988 E ntlmail@ghd.com W www.ghd.com.au

© 2016. Whilst every care has been taken to prepare this map, GHD, OEH, LPI and ESRI make no representations or warranties about its accuracy, reliability, completeness or suitability for any particular purpose and cannot accept liability and responsibility of any kind (whether in contract, tort or otherwise) for any expenses, losses, damages and/or costs (including indirect or consequential damage) which are or may be incurred by any party as a result of the map being inaccurate, incomplete or unsuitable in any way and for any reason.

Data source: LPI: DCDB / DTDB, 2012; ESRI: Aerial Imagery, 2014; OEH: SEPP's, 2008. Created by: fmacKay



Paper Size A4

0 60 120 240 360 480

Metres

Map Projection: Transverse Mercator
Horizontal Datum: GDA 1994
Grid: GDA 1994 MGA Zone 56



LEGEND

- Investigation area
- Cadastre

- E1, National Parks and Nature Reserves
- E2, Environmental Conservation
- E3, Environmental Management

- R5, Large Lot Residential
- RU1, Primary Production
- RU2, Rural Landscape
- W1, Natural Waterway



Dulconghi Investments Pty Ltd
Dulconghi Heights Rezoning Application

Job Number 22-17672
Revision A
Date 10 Mar 2016

Current Zoning


Figure 3

G:\22\17672\GIS\Maps\Deliverables\2217672_003_CurrentZoning_A.mxd

Level 3, GHD Tower, 24 Honeysuckle Drive, Newcastle NSW 2300 T 61 2 4979 9999 F 61 2 4979 9988 E ntlmail@ghd.com W www.ghd.com.au

<FNT size="7">©</FNT> 2016. Whilst every care has been taken to prepare this map, GHD, LPI, DoP&I and ESRI make no representations or warranties about its accuracy, reliability, completeness or suitability for any particular purpose and cannot accept liability and responsibility of any kind (whether in contract, tort or otherwise) for any expenses, losses, damages and/or costs (including indirect or consequential damage) which are or may be incurred by any party as a result of the map being inaccurate, incomplete or unsuitable in any way and for any reason.

Data source: LPI: DCDB / DTDB, 2012; ESRI: Aerial Imagery, 2014; DoP&I: LEP Zoning, 2014. Created by: fmacKay



Paper Size A4
0 62.5 125 250 375 500
Metres

Map Projection: Transverse Mercator
Horizontal Datum: GDA 1994
Grid: GDA 1994 MGA Zone 56



LEGEND

- Investigation area
- Cadastre
- Proposed subdivision
- Existing zone boundary

Proposed zoning

- R5, Large Lot Residential
- RU1, Primary Production

- RU2, Rural Landscape
- E2, Environmental Conservation




Dulconghi Investments Pty Ltd
Dulconghi Heights Rezoning Application

Job Number	22-17672
Revision	0
Date	25 Aug 2016

Proposed Zoning

Figure 4



Paper Size A4

0 75 150 300 450 600
Metres

Map Projection: Transverse Mercator
Horizontal Datum: GDA 1994
Grid: GDA 1994 MGA Zone 56



LEGEND

- | | | |
|--|----------------------|----------|
| | Investigation area | Lot Size |
| | Cadastre | 1ha |
| | Proposed subdivision | 40ha |



Dulconghi Investments Pty Ltd
Dulconghi Heights Rezoning Application

Job Number	22-17672
Revision	0
Date	25 Aug 2016

LEP Lot Size - Amendment


Figure 4a

G:\22\17672\GIS\Maps\Deliverables\2217672_010_Modified_LEP_LSZ_withLotlayout_0.mxd

Level 3, GHD Tower, 24 Honeysuckle Drive, Newcastle NSW 2300 T 61 2 4979 9999 F 61 2 4979 9988 E ntlmail@ghd.com W www.ghd.com.au

© Whilst every care has been taken to prepare this map, GHD, LPI and DoP&I make no representations or warranties about its accuracy, reliability, completeness or suitability for any particular purpose and cannot accept liability and responsibility of any kind (whether in contract, tort or otherwise) for any expenses, losses, damages and/or costs (including indirect or consequential damage) which are or may be incurred by any party as a result of the map being inaccurate, incomplete or unsuitable in any way and for any reason.

Data source: LPI: DCDB / DTDB, 2012; DoP&I: LEP LSZ, 2014. Created by: fmackay, gmoddiarmid



Paper Size A4
0 75 150 300 450 600
Metres
Map Projection: Transverse Mercator
Horizontal Datum: GDA 1994
Grid: GDA 1994 MGA Zone 56



LEGEND

- Investigation area
- Scenic Protection Land
- Cadastre



Dulconghi Investments Pty Ltd
Dulconghi Heights Rezoning Application

Job Number	22-17672
Revision	A
Date	10 Mar 2016

LEP Scenic Protection
Land - Amendment


Figure 4b


G:\22\17672\GIS\Maps\Deliverables\2217672_008_Modified_LEP_SCP_A.mxd

Level 3, GHD Tower, 24 Honeysuckle Drive, Newcastle NSW 2300 T 61 2 4979 9999 F 61 2 4979 9988 E ntlmail@ghd.com W www.ghd.com.au

© Whilst every care has been taken to prepare this map, GHD, LPI and KSC make no representations or warranties about its accuracy, reliability, completeness or suitability for any particular purpose and cannot accept liability and responsibility of any kind (whether in contract, tort or otherwise) for any expenses, losses, damages and/or costs (including indirect or consequential damage) which are or may be incurred by any party as a result of the map being inaccurate, incomplete or unsuitable in any way and for any reason.

Data source: LPI: DCDB / DTDB, 2012; KSC: LEP Scenic protection 2015. Created by: fmackay





Service Layer Credits: Source: Esri, DigitalGlobe, GeoEye, i-cubed, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AEX, Getmapping, Aerogrid, IGN, IGP, swisstopo, and the GIS User Community

Paper Size A4
0 12.525 50 75 100
Metres

Map Projection: Transverse Mercator
Horizontal Datum: GDA 1994
Grid: GDA 1994 MGA Zone 56



LEGEND

- Cadastre
- Watercourse
- 1 in 100 year ARI
- New Zoning Boundary
- Proposed Dwelling
- Proposed Dwelling Asset Protection Zones

- Primary Food Tree (PFT) - Grey Gum
- Primary Food Tree (PFT) - Tallowood



Dulconghi Investments Pty Ltd
Dulconghi Heights Rezoning Application

Job Number | 22-17672
Revision | C
Date | 10 Mar 2016

Approximate APZ

Figure 6

G:\22\17672\GIS\Maps\Deliverables\2217672_005_APZ_C.mxd

Level 3, GHD Tower, 24 Honeysuckle Drive, Newcastle NSW 2300 T 61 2 4979 9999 F 61 2 4979 9988 E ntlmail@ghd.com W www.ghd.com.au

© 2016. Whilst every care has been taken to prepare this map, GHD, LPI and ESRI make no representations or warranties about its accuracy, reliability, completeness or suitability for any particular purpose and cannot accept liability and responsibility of any kind (whether in contract, tort or otherwise) for any expenses, losses, damages and/or costs (including indirect or consequential damage) which are or may be incurred by any party as a result of the map being inaccurate, incomplete or unsuitable in any way and for any reason.

Data source: LPI: DCDB / DTDB, 2012; ESRI: Aerial Imagery, 2014. Created by: fmackay, tmorton

Appendix B - Ecology assessment



Dulconghi Investments Pty Ltd

Dulconghi Heights Rezoning Ecology Assessment

October 2016

Table of contents

1.	Introduction.....	1
1.1	Overview	1
1.2	Proposal description	1
1.3	Terms and definitions.....	4
1.4	Scope of assessment.....	4
1.5	Purpose of this report.....	5
2.	Legislative context.....	6
2.1	NSW legislation.....	6
2.2	NSW policies and guidelines	7
2.3	Commonwealth legislation	9
3.	Methods.....	12
3.1	Desktop assessment.....	12
3.2	Field survey	12
3.3	Survey limitations	13
3.4	Staff qualifications.....	13
4.	Existing environment.....	14
4.1	Site context	14
4.2	Vegetation and habitat	15
4.3	Conservation significance	20
5.	Preliminary impact assessment	29
5.1	Overview	29
5.2	Direct impacts	29
5.3	Indirect impacts.....	32
6.	Conclusion.....	34
7.	Disclaimer.....	36
8.	References	37

Table index

Table 3-1	Staff qualifications.....	13
Table 4-1	Vegetation zones within the proposed development footprint	15
Table 4-2	Declared noxious weeds recorded during the field survey	20
Table 4-3	Threatened ecological communities known within the locality	21
Table 4-4	Threatened flora that may occur within the site	23
Table 4-5	Threatened fauna that may occur within the site	24
Table 5-1	Extent of vegetation within the proposed development footprint	30

Plate index

Plate 1	Blackbutt Tallowwood in the western portion of the site.....	16
Plate 2	Degraded Paperbark swamp forest in the centre of the site	17
Plate 3	Cleared lands in the eastern portion of the site	18
Plate 4	SEPP 14 Vegetation boundary	23

Figure index

Figure 1	Site location	2
Figure 2	Potential subdivision layout	3
Figure 3	Current zoning plan.....	10
Figure 4	Proposed zoning plan	11
Figure 5	Ecology constraints map.....	19
Figure 6	Vegetation impacts	33

Appendices

Appendix A – Field survey data

Appendix B – Threatened and migratory biota

1. Introduction

1.1 Overview

GHD Pty Ltd (GHD) has been engaged by Dulconghi Investments Pty Ltd to complete an ecology assessment to support a rezoning application for the proposed Dulconghi Heights rural residential subdivision. The rezoning application would be submitted to Council for approval under the NSW *Environment Protection and Assessment Act 1979* (EPA Act). This Ecology Assessment is a specialist appendix for inclusion in the rezoning application. It describes the ecological values at the site, with particular emphasis on threatened ecological communities, populations and species listed under the NSW *Threatened Species Conservation Act 1995* (TSC Act) and *Fisheries Management Act 1994* (FM Act), and *Matters of National Environmental Significance* (MNES) listed under the Commonwealth *Environmental Protection and Biodiversity Conservation Act 1999* (EPBC Act).

1.2 Proposal description

The subject site (Lot 3 DP 1164661 Neville Morton Drive, Crescent Head NSW (see Figure 1) has been included in the Rural Residential Land Strategy (Kempsey Shire Council 2014) as a Stage 1 site for future rezoning. The proponent is seeking approval for the rezoning of land within the indicative development footprint (see Figure 2) to R5 Large Lot Residential under the Kempsey Local Environmental Plan (LEP) 2013.

The exact location, size and nature of the proposal would be determined at the Development Application (DA) stage. A preliminary concept plan for the proposed subdivision has been developed which comprises 14 lots, with an approximate lot size of one hectare (ha) (see Figure 2). Access to the subdivision would be via Neville Morton Drive. Additional road and infrastructure services would also be constructed in accordance with relevant standards to service the proposed allotments. The retention of native vegetation located outside of the development footprint is also proposed to be rezoned E2 Environmental Conservation..

A final design layout that achieves an appropriate balance between development and conservation areas and ultimately improves or maintains the existing biodiversity values at the site would be included in a future Development Application (DA).



Paper Size A4
0 250 500 750 1,000
Metres
Map Projection: Transverse Mercator
Horizontal Datum: GDA 1994
Grid: GDA 1994 MGA Zone 56



LEGEND
 Investigation area



Dulconghi Investments Pty Ltd
Dulconghi Heights Rezoning
Ecology Assessment

Job Number	22-17672
Revision	B
Date	10 Mar 2016

Regional Locality

Figure 1



1.3 Terms and definitions

The following terms are used in this report:

The proposal	The proposed rezoning and residential subdivision at Neville Morton Drive, Crescent Head, NSW.
Indicative development footprint	The area to be directly impacted by the proposal (see Figure 2). In this case it comprises the preliminary construction footprint of the proposed residential subdivision and ancillary infrastructure.
Subject site	Lot 3 DP1164661 Neville Morton Drive, Crescent Head, NSW, as shown on Figure 1.
Locality	The area within a 10 km radius of the subject site boundary.
Threatened biota	Threatened species, populations and communities that are listed under the TSC Act, FM Act and/or the EPBC Act.
Biobanking agreement	An agreement entered into between the landowner and the Minister under Part 7A of the TSC Act for establishing a biobank site.
BioBanking Assessment Methodology (BBAM)	The rules of BioBanking established under the TSC Act that determine credits created, credits required and the circumstances that improve or maintain biodiversity values.
BioBanking	The biodiversity banking and offsets scheme established under Part 7A of the TSC Act.
Biobanking statement	Specifies the number and class of credits to be retired for a particular development in accordance with the BBAM. A biobanking statement can only be issued in circumstances that improve or maintain biodiversity values.

1.4 Scope of assessment

The aim of this ecology assessment report is to:

- Describe the existing environment of the subject site, including flora species, vegetation communities, fauna habitats and flora and fauna species known or likely to occur.
- Present the ecological assessment of the subject site to support the rezoning application.
- Assess the value and conservation significance of native vegetation and habitats within the subject site and the likelihood of occurrence of threatened biota based on habitats present.
- Compile a list of threatened biota previously recorded, or predicted to occur in the locality and an assessment of their potential to occur in the subject site and/or be affected by the proposal.
- Provide a preliminary assessment of likely impacts of the proposed development.
- Provide an analysis of the ecological constraints to development in the context of relevant environmental legislation.

1.5 Purpose of this report

To prepare an Ecology Assessment Report to support a Planning Proposal for a portion of Lot 3 DP 1164661 Neville Morton Drive, Crescent Head NSW. The report describes the site's biodiversity values as well as possible impacts associated with any future development of the land.

2. Legislative context

2.1 NSW legislation

2.1.1 Environmental Planning and Assessment Act 1979 (EPA Act)

The EPA Act forms the legal and policy platform for development proposal assessment and approval in NSW and aims to, inter alia, 'encourage the proper management, development and conservation of natural and artificial resources'. All development in NSW is assessed in accordance with the provisions of the EPA Act and EPA Regulation 2000. The rezoning application would be submitted to Council for approval under Part 4 of the NSW Environment Protection and Assessment Act 1979 (EPA Act).

Section 5A of the EPA Act lists seven factors that must be taken into account in the determination of the significance of potential impacts of a proposed activity on threatened species, populations or ecological communities (or their habitats) listed under the TSC Act and the FM Act. The '7-part test' is used to assist in the determination of whether a proposal is 'likely' to impose 'a significant effect' on threatened biota and thus whether a species impact statement (SIS) is required.

The future development application for the proposal would require assessment of impacts on threatened biota under Section 5A or an application for a biobanking statement (see TSC Act below).

2.1.2 Threatened Species Conservation Act 1995 (TSC Act)

The TSC Act provides legal status for biota of conservation significance in NSW. The Act aims to, inter alia, 'conserve biological diversity and promote ecologically sustainable proposal'. It contains schedules that list endangered, critically endangered and vulnerable species, populations, ecological communities, and key threatening processes in NSW. Potential impacts on any of these biota must be subject to an impact significance assessment ("7-part test") through the provisions of Section 5A of the EPA Act or a biobanking statement under Part 7A of the TSC Act.

Part 7A of the TSC Act establishes the biodiversity banking and offsets scheme (BioBanking). Under Part 7A a proponent may obtain a 'biobanking statement' for a development which means that Section 5A of the EPA Act does not apply to that development. A biobanking statement is issued under section 127ZL of the TSC Act and specifies the number and class of biodiversity credits to be retired for a particular development in accordance with the BBAM in order to achieve an 'improve or maintain' outcome for biodiversity values. The statement may include other conditions to minimise the impact of the development on biodiversity values. If provided to a consent or determining authority under the EPA Act, the statement must be included as a condition of development consent or approval.

2.1.3 National Parks and Wildlife Act 1979

The National Parks and Wildlife Act 1974 (NPW Act) provides the basis for the legal protection of native animals and plants in NSW. A wildlife licence is required under the NPW Act to harm or pick protected fauna and flora. All field surveys were carried out under a Section 132C scientific licence (SL100146).

2.1.4 Fisheries Management Act 1994 (FM Act)

The FM Act contains schedules that list endangered, critically endangered and vulnerable aquatic species, populations, ecological communities, and key threatening processes of relevance to aquatic environments. As for biota listed under the TSC Act, potential impacts on any of these species must be addressed through 7 part tests in accordance with section 5A of the EPA Act. If a significant impact is likely, an SIS must be completed and a licence obtained pursuant to Part 7a of the FM Act. The proposal does not involve any dredging or reclamation that would require specific consideration under the Act.

2.1.5 Noxious Weeds Act 1993 (NW Act)

The NW Act provides for the declaration of noxious weeds by the Minister for Primary Industries. Noxious weeds may be considered noxious on a National, State, Regional or Local scale. All private landowners, occupiers, public authorities and Councils are required to control noxious weeds on their land under Part 3 Division 1 of the NW Act. As such, if present, noxious weeds on the site should be assessed and controlled.

There are at least two noxious weed species present at the subject site, both of which would require management during construction of the proposal and control once the residential subdivision has been established.

2.2 NSW policies and guidelines

2.2.1 State Environmental Planning Policy No. 14 - Coastal Wetlands (SEPP 14)

This policy aims to preserve and protect areas identified and mapped as coastal wetlands in the environmental and economic interests of the State. Land on the eastern portion of the subject site is mapped as a coastal wetland under this policy. The Planning proposal does not include any change to the mapped boundary of the SEPP 14 wetland or the changing of the E2 zone to the east of this boundary. The proposed subdivision has been designed to ensure no dwellings, associated infrastructure or Assets Protection Zones (APZ's). As such, there would be no impacts to the mapped SEPP 14 area associated with the proposed rezoning. This approach also removes the need for Environmental Impact Assessments (EIS) to accompany future Development Applications.

2.2.2 State Environmental Planning Policy No. 44 - Koala Habitat (SEPP 44)

This policy aims to encourage the proper conservation and management of natural vegetation identified as providing habitat for Koalas to ensure a permanent free-living population over their present range and reverse the current trend of Koala population decline.

Kempsey Shire Council has developed a Comprehensive Koala Plan of Management (CKPoM) for the Eastern Portion of the Kempsey Shire Local Government Area (LGA). This plan satisfies the requirements of SEPP 44 and replaces the requirement for preparation of an individual KPoM in relation to development in areas of *core Koala* habitat. Further information regarding the Kempsey CKPoM and implications for the proposal is provided at Section 2.2.4.

2.2.3 Kempsey Local Environmental Plan (LEP) 2013

The Kempsey LEP outlines planning provisions for land within the Kempsey Shire LGA in accordance with the relevant standard environmental planning instrument under section 33A of the EPA Act.

Under the LEP, zoning for the subject site falls into the following two categories (see Figure 3):

- RU2 – Rural Landscape.
- E3 – Environmental Management.

The subject site has been included in the draft Rural Residential Land Strategy (Kempsey Shire Council 2013) as a Stage 1 site for future rezoning. Following approval and finalisation of the Strategy from the Department of Planning and Environment (DPE), rezoning of the site can occur, subject to approval from Kempsey Shire Council (KSC). The proponent is seeking approval for the rezoning of land within the indicative development footprint to R5 Large Lot Residential (see Figure 4).

2.2.4 Comprehensive Koala Plan of Management for the Eastern portion of the Kempsey LGA

The majority of subject site is mapped as Secondary (Class B) Preferred Koala Habitat with a small portion in the north east corner mapped as Secondary (Class A) under the Kempsey CKPoM. Vegetation that falls within the Class A category includes a Primary Feed Tree (PFT) growing in association with one or more Secondary Feed Trees (SFT). The Class B category is defined as vegetation communities and/or associations wherein primary food tree species are absent and secondary or supplementary food tree species are identified.

Assessments of the site indicated the presence of Tallowwood (*Eucalyptus microcorys*) and Grey Gum (*Eucalyptus propinqua*), which are listed as a PFTs, were recorded in scattered distribution within the western portion of the site. Consequently, despite the majority of the site being mapped as Secondary (Class B) Preferred Koala Habitat, this portion of the site is categorised as Secondary (Class A) and covers an area of 7.5 hectares. The small area of the site currently mapped as Secondary (Class A) habitat (approximately 0.4 hectares) was also visited and should be classified as 'other vegetation' as none of the listed PFTs or SFTs under the CKPoM occur in this location. The remainder of the site, covering an area of approximately 8.3 hectares, is considered 'other vegetation' as this portion of the site is cleared or contains only scattered trees which are not PFT's or SFT's.

Details of the possible impacts from the subdivision and associated compensation measures are include in Section 5.3.

2.3 Commonwealth legislation

2.3.1 Environment Protection and Biodiversity Conservation Act 1999 (EPBC Act)

The purpose of the EPBC Act is to ensure that actions likely to cause a significant impact on Matters of National Environmental Significance (MNES) undergo an assessment and approval process. Under the EPBC Act, an action includes a proposal, undertaking or activity. An action that 'has, will have or is likely to have a significant impact on a matter of national environmental significance' is deemed to be a 'controlled action' and may not be undertaken without prior approval from the Australian Government Minister for the Environment (the 'Minister').

The EPBC act identifies MNES as:

- World heritage properties.
- National heritage places.
- Wetlands of international importance (Ramsar wetlands).
- Threatened species and ecological communities.
- Migratory species.
- Commonwealth marine areas.
- Nuclear actions (including uranium mining).
- A water resource, in relation to coal seam gas development and large coal mining development.

Potential impacts on any MNES must be subject to assessments of significance pursuant to the Department of the Environment (DotE) *Significant Impact Guidelines* (DotE 2013). If a significant impact is considered likely, a referral under the EPBC Act must be submitted to the Commonwealth Environment Minister.

A number of threatened flora and fauna species listed under the EPBC Act have been identified as occurring (or potentially occurring based on known habitat requirements) within the subject site (see Section 4.3). Once the proposed subdivision design has been finalised, an assessment will be undertaken to determine whether the proposal is likely to impact on any listed threatened species and whether a referral is required under the provisions of the Act.





Figure 3



Paper Size A4
0 62.5 125 250 375 500
Metres

Map Projection: Transverse Mercator
Horizontal Datum: GDA 1994
Grid: GDA 1994 MGA Zone 56



LEGEND

- Investigation area
- Cadastre
- Existing zone boundary

Proposed zoning

- R5, Large Lot Residential
- RU1, Primary Production

- RU2, Rural Landscape
- E2, Environmental Conservation



Dulconghi Investments Pty Ltd
Dulconghi Heights Rezoning Application

Job Number	22-17672
Revision	0
Date	11 Aug 2016

Proposed Zoning

Figure 4

3. Methods

3.1 Desktop assessment

A desktop assessment was undertaken to identify threatened flora and fauna species, populations and ecological communities listed under the TSC Act and FM Act, and MNES listed under the EPBC Act that may be affected by the proposal. Reports and database records pertaining to the subject site and locality (ie within a 10 km radius of the subject site) were reviewed and included:

- NSW Office of Environment and Heritage (OEH) Wildlife Atlas database for records of threatened species listed under the TSC act (OEH 2015a; data downloaded on 2 March 2015).
- Department of the Environment (DotE) Protected Matters Online Search Tool for MNES listed under the EPBC Act and predicted to occur in the locality (DotE 2015a; database queried on 3 March 2015).
- Department of Primary Industries (DPI) Threatened Species Records Viewer (DPI 2015; database queried on 3 March 2015).
- OEH (2015b) *NSW Vegetation Types Database* and DECC (2009) BioBanking operation manual to define vegetation types and condition classes within the subject site.
- Biolink Ecological Consultants (2011) Comprehensive Koala Plan of Management for Eastern Portion of Kempsey Shire LGA (Volume 1 - Working Provisions). Prepared for Kempsey Shire Council.
- Biolink Ecological Consultants (2009) Comprehensive Koala Plan of Management for Eastern Portion of Kempsey Shire LGA Volume 2 Resource Study. Prepared for Kempsey Shire Council. A review of the following ecological assessments previously undertaken on or within close proximity to the subject site was also undertaken:
- Kendall & Kendall (1996) *Assessment of Significance on Possibly Occurring Threatened Species, SEPP 44 Koala Habitat Assessment and SEPP 46 Native Vegetation Assessment of Proposed Subdivision of Part Lots 2 & 3 DP794159*.
- Kendall & Kendall (1999) *Flora and Fauna Assessment of the "Habitat Zone" – Dulconghi Heights Estate*.
- GHD (2013) *Crescent Head Rezoning Submission*.

The habitat resources present at the site (determined during the site inspection) were compared with the known habitat associations/requirements of the relevant threatened and migratory biota identified by the desktop review. This was used to determine the likelihood of each threatened ecological community, endangered population and threatened or migratory species occurring within the study area.

3.2 Field survey

Preliminary field surveys were undertaken on 11 September 2013 to assess vegetation types and flora species present. Further detailed surveys were completed on 22 October 2014 to accurately describe and map vegetation communities within the proposed development footprint. A total of four BioBanking survey transects/plots were undertaken at the site in accordance with the BBAM. Koala Spot Assessment Technique (SAT's) and Koala Feed Tree mapping was completed on 1 October 2015.

3.3 Survey limitations

Vegetation mapping at the site comprises preliminary mapping of vegetation types and condition only. This level of survey reflects the intent to undertake more extensive survey effort at the development application stage should the rezoning application be successful.

The desktop assessment provided an indication of the native flora and fauna and especially threatened biota that could potentially occur in the subject site or be affected by the proposal (including seasonal, transient or cryptic species). The habitat assessment conducted for the site allows for identification of habitat resources for such species. As such, the survey was not designed to detect all species, rather to provide an overall assessment of the ecological values on site in order to predict potential impacts of the proposal, with particular emphasis on endangered ecological communities, threatened species and their habitats.

Survey effort undertaken to date would be insufficient to inform a detailed Ecological Assessment or Biobanking statement to support a Development Application for the proposed subdivision. Rather, the survey effort is commensurate with a rezoning application. It is anticipated that further detailed surveys would be undertaken to meet the requirements of these assessment processes, and would include formal flora and fauna surveys as well as targeted searches for threatened species identified as having the potential to occur within the subject site.

3.4 Staff qualifications

This report was prepared by Amanda Ayres based on field surveys conducted by GHD ecologists and review of existing information. The assessment was peer reviewed by Daniel Williams. Staff qualifications are presented in Table 3-1.

Table 3-1 Staff qualifications

Name	Position/project role	Qualifications	Relevant experience
Daniel Williams	Principal Environmental Consultant/technical review Field assessments	B. App. Sc. BioBanking Assessor Accreditation ¹	15+ years
Amanda Ayres	Ecologist/reporting	BEnvSc (Env Mgt)	10+ years
Arien Quinn	Ecologist/field surveys	BSc, (B.A/BSc) BioBanking Assessor Accreditation ¹	8+ years
Leanne Gallagher	Ecologist/field surveys	BSc(EM)	10+ years
¹ Refer to OEH (2015c) list of accredited assessors.			

4. Existing environment

4.1 Site context

4.1.1 Location and land uses

The subject site is known as Lot 3 DP 1164661, Neville Morton Drive, Crescent Head (see Figure 1) and is located on the north side of Crescent Head Road, less than 3 km to the north west of the Crescent Head town centre.

The site lies directly adjacent to and is accessed from an existing rural residential estate known as Dulconghi Heights. This estate currently has a central access road (Neville Morton Drive) and associated services which extend through to the boundary of the site. The rezoning of the site for rural residential development would simply lead to an extension of the existing subdivision.

As shown in Figure 3, the site is currently zoned RU2 – Rural Landscape, E2 – Environmental Conservation and E3 – Environmental Management under the Kempsey LEP 2013.

Land uses surrounding the site include the existing Dulconghi Heights rural residential estate to the south, agricultural lands to the east used for cattle grazing and vegetated lands to the north and west.

4.1.2 Climate

The climate is generally warm-temperate in nature. During summer, warm moist north-east to south-east winds prevail, bringing rain in the form of thunderstorms or depressions from subtropical cyclones moving south. In winter, the northern movement of the anticyclones leads to a dominance of usually dry west to south winds, often leading to fine sunny days and cool nights. Rainfall is usually associated with cold fronts and the coolest temperatures.

Annual rainfall is most influenced by distance from the coast and topographic position, with a general decrease from east to west. Annual rainfall in the Kempsey area (nearest station) is approximately 1,213 mm pa (BOM 2014), falling predominantly in summer and autumn.

The annual mean daily average temperature ranges from 29°C to 12°C (nearest recording location is Kempsey (BOM 2014). The coastal strip is usually several degrees cooler though in summer and is typically closer to an average of 24°C.

4.1.3 Landscape context

The site occurs within the 'Manning – Macleay Barriers and Beach' Mitchell Landscape (DECC, 2008). Mitchell (2002) describes this landscape as comprising beaches, dunes, swamps and lagoons on Quaternary coastal sands, with inner and outer barrier dune sequences. Elevation ranges between 0 to 160 m, increasing from east to west.

Based on interpretation of the 1:100 000 Kempsey Soil Landscapes map (DLWC 1999), the subject site appears to fall over four distinct soil landscapes (Atkinson 1999), these being:

- Beranghi Soil Landscape: Associated with undulating rises and low hills with broad crests and drainage depressions. Elevation ranges from 20-30m, rising to 50m. Soils on crests are shallow to deep (40-300cm); moderately deep (100-300cm) on footslopes and deep (>300cm) on flats. The soil has limitations of seasonal waterlogging, water erosion hazard, shallow and acidic soils and low permeability. The majority of the site (including the proposed development footprint) occurs on this soil landscape.

- Crescent Head Soil Landscape: Associated with isolated coastal headlands and rolling hills with elevation and relief up to 250m, on conglomerates and lithic sandstones of the Kempsey Beds. Comprises shallow (60-100cm) stony Lithosols on crests and sideslopes and limited by sodic, erodible, strong acidity soils with high aluminium toxicity potential and low available water holding capacity. Found within the steeper, western portion of the subject site.
- Connection Creek Soil Landscape: Associated with level, swamp, linear open-depressions and supratidal flats of low elevation and relief (<1m) with a narrow central channel and minor tidal influence. Soils are deep (>300cm) and very poorly drained and limited by waterlogging, low bearing wet strength, sodicity, acidity, salinity and aluminium toxicity. Mapped on the eastern section of the subject site, associated with a drainage line.

4.1.4 Hydrology

The site is traversed by one small ephemeral drainage line in the north western portion associated with the existing farm dam. In addition, there are two areas of 'low depressions' with one containing Paperbark Swamp Forest.

4.2 Vegetation and habitat

4.2.1 Vegetation zones

As mapped in Figure 5, the proposed development footprint includes three distinct vegetation types, these being:

- Blackbutt Tallowwood grassy open forest.
- Paperbark Swamp Forest.
- Cleared lands.

A summary of these vegetation zones is provided in Table 4-1 and more detailed information as follows. A complete list of flora species recorded during the surveys is provided at Appendix A.

Table 4-1 Vegetation zones within the proposed development footprint

Vegetation type (OEH 2014b)	Vegetation type ID	Condition	Area within the proposed development footprint	Conservation significance
Blackbutt Tallowwood dry grassy open forest of the central parts of the north coast	NR119	Moderate/Good - medium	7.5 ha	Not an EEC
Paperbark swamp forest of the coastal lowlands of the north coast	NR217	Moderate/Good - medium	0.6 ha	Not an EEC
Cleared lands	N/A		4.2	
Total area			12.3 ha	

Blackbutt Tallowwood dry grassy open forest of the central parts of the north coast (NR119)

This vegetation type is located throughout the western portion of the proposed development footprint and a small patch in the south eastern portion (covering approximately 45% of the footprint area) and is in a modified state with the mid storey largely removed and ground covers dominated in locations by introduced pastures. This portion of the site is subject to constant grazing from cattle.

The vegetation is primarily characterised by a tree canopy dominated by Blackbutt (*Eucalyptus pilularis*) and occasional scattered Tallowwood (*Eucalyptus microcorys*), Brush Box (*Lophostemon confertus*) and Pink Bloodwood (*Corymbia intermedia*). The mid storey has been largely removed through the impacts of grazing and regular slashing however species present included occasional occurrences of Cheese Tree (*Glochidion ferdinandi*), Blueberry Ash (*Elaeocarpus reticulatus*), Forest Sheoak (*Allocasuarina torulosa*), Geebung (*Persoonia stradbokensis*) and Sweet Pittosporum (*Pittosporum undulatum*).

Groundcovers include a mix of introduced grasses/herbs as well as Blady Grass (*Imperata cylindrica*), Dusky Coral Pea (*Kennedia rubicunda*), Sword Sedge (*Lepidosperma laterale*), Spiny-headed Mat-rush (*Lomandra longifolia*), Many-flowered Mat-rush (*Lomandra multiflora*), Weeping Grass (*Microlaena stipoides*), Barbed Wire Grass (*Cymbopogon refractus*), Blue Flax-lily (*Dianella caerulea*) and Kangaroo Grass (*Themeda australis*).

Weed species present included introduced grasses Cobbler's Pegs (*Bidens pilosa*), Flaxleaf Fleabane (*Conyza bonariensis*), Lantana (*Lantana camara*) and Fireweed (*Senecio madagascariensis*).



Plate 1 Blackbutt Tallowwood in the western portion of the site

Paperbark swamp forest of the coastal lowlands of the north coast (NR217)

This forested wetland vegetation type is restricted to a small area of the proposed development footprint in the eastern portion of the site. This vegetation type is heavily degraded and is characteristically dominated by scattered Broad-leaved Paperbark (*Melaleuca quinquenervia*) with occasional regenerating Swamp Oak (*Casuarina glauca*) only.

The mid storey has been largely removed due to the impacts of previous clearing and active grazing and is represented by a small number of individuals only comprising Cheese Tree, Geebung and Bottlebrush (*Callistemon* spp.).

The groundcover stratum is generally dominated by introduced weeds/grasses and also Tall Sedge (*Carex appressa*) and occasional sedges such as Saw-sedge (*Gahnia* spp.). This small patch of vegetation is not considered to be indicative of Swamp Sclerophyll Forest on Coastal Floodplains, which is listed as an EEC under the TSC Act. The patch of vegetation is not associated with a coastal floodplain as described in Section 4.3.2.



Plate 2 Degraded Paperbark swamp forest in the centre of the site

Cleared Lands

This area dominates the eastern portion of the proposed development footprint and covers approximately 45% of the total area. This area has been subjected to intense stock grazing and is dominated by the introduced grasses such as Paspalum (*Paspalum dilatatum*) and Kikuyu (*Pennisetum clandestinum*) as well as Fireweed.



Plate 3 Cleared lands in the eastern portion of the site

The distribution of vegetation at the site is shown in Figure 5.



4.2.2 Noxious and environmental weeds

The *Noxious Weeds Act 1993* provides for the declaration of noxious weeds in local government areas. Landowners and occupiers must control noxious weeds according to the control category specified in the Act. Public authorities must control noxious weeds according to the control category to the extent necessary to prevent their spread to adjoining land.

The subject site contains two species declared as noxious weeds in the Kempsey LGA, as shown in Table 4-2. Lantana occurs as scattered individuals throughout the Blackbutt Tallowwood dry grassy open forest while Fireweed is prevalent throughout the cleared grazing areas.

Table 4-2 Declared noxious weeds recorded during the field survey

Scientific name	Common name	Control category	Legal requirements
<i>Lantana camara</i>	Lantana	4	The growth of the plant must be managed in a manner that continuously inhibits the ability of the plant to spread
<i>Senecio madagascariensis</i>	Fireweed	4	The plant must not be sold, propagated or knowingly distributed

4.2.3 Fauna habitats

Targeted fauna surveys were not undertaken at the site, however broad habitat features identified include:

- Myrtaceous plant species – provides a foraging resource for a variety of nectivorous birds and mammals, including the Grey-headed Flying-fox.
- Modified grassland provides a potential foraging/nesting resource for insectivorous and grainivorous bird species and a sheltering resource for reptiles.
- The presence of Forest Oak – provides a potential foraging resource for the Glossy Black-cockatoo.
- The Koala food trees Tallowwood (*Eucalyptus microcorys*) and Grey Gum (*Eucalyptus propinqua*), potential foraging resource for the Koala.
- SEPP 14 wetland area to the east of the proposed subdivision provides a potential foraging/breeding resource for aquatic bird species, native frogs and other fauna.
- Small ephemeral drainage lines.

4.3 Conservation significance

4.3.1 Overview

Based on the desktop assessment the following threatened biota and MNES are known or predicted to occur in the locality:

- Nine threatened ecological communities (TECs).
- 11 threatened flora species.

- 37 threatened fauna species, comprising three frogs, 19 birds, 15 mammals and one reptile.
- 11 migratory species.

This list does not include marine threatened and migratory species or shorebirds which were identified during the database searches because the locality does not contain any marine or estuarine habitats.

The occurrence and potential occurrence of these threatened biota within the subject site is discussed in the following sections.

4.3.2 Threatened biota (TSC Act and FM Act)

The database searches identified 10 threatened flora species, 37 threatened fauna species and nine TECs listed under the TSC Act as having been previously recorded or predicted to occur in the locality. Each of the threatened biota are included in the likelihood of occurrence table included as Appendix B.

A search of the Department of Primary Industries Threatened Species Records Viewer (DPI 2015) showed that no threatened fish or invertebrate species listed under the FM Act have been previously recorded or are predicted to occur within the locality.

The potential for these threatened biota to occur within the subject site is discussed in the following sections and Appendix B.

Threatened ecological communities

A total of nine TECs were identified within the locality as a result of database searches. Details of these communities are provided in Table 4-3.

Table 4-3 Threatened ecological communities known within the locality

Naming under the TSC Act	Naming under the EPBC Act	TSC Act Status	EPBC Act Status
Coastal Saltmarsh in the NSW North Coast, Sydney Basin and South East Corner Bioregions	Subtropical and Temperate Coastal Saltmarsh	E	V
Freshwater Wetlands on Coastal Floodplains of the NSW North Coast, Sydney Basin and South East Corner Bioregions		E	-
Littoral Rainforest in the NSW North Coast, Sydney Basin and South East Corner Bioregions	Littoral Rainforest and Coastal Vine Thickets of Eastern Australia	E	CE
Lowland Rainforest in the NSW North Coast and Sydney Basin Bioregions	Lowland Rainforest of Subtropical Australia	E	CE
Lowland Rainforest on Floodplain in the NSW North Coast Bioregion	Lowland Rainforest of Subtropical Australia	E	CE

Naming under the TSC Act	Naming under the EPBC Act	TSC Act Status	EPBC Act Status
Subtropical Coastal Floodplain Forest of the NSW North Coast Bioregion		E	-
Swamp Oak Floodplain Forest of the NSW North Coast, Sydney Basin and South East Corner Bioregions		E	-
Swamp Sclerophyll Forest on Coastal Floodplains of the NSW North Coast, Sydney Basin and South East Corner Bioregions		E	-
Themeda Grassland on Seacliffs and Coastal Headlands in the NSW North Coast, Sydney Basin and South East Corner Bioregions		E	-

No other TECs were identified on the site. The Paperbark Swamp Forest community (NR217) identified in the eastern portion of the site in association with the minor drainage line, is not considered to be indicative of the Swamp Sclerophyll Forest on Coastal Floodplains which is a listed as an EEC under the TSC Act. The community exists as a small patch of remnant *Melaleuca quinquinervia* trees only with no shrub layer present and groundcovers being limited to introduced pastures. The small patch is not associated with a floodplain and it appears that the remnant Paperbark trees have established on the site due to the establishment of a farm dam immediately downstream changing the local hydrology in this location or may be associated with a small discharge area from water draining from Dulconghi Mountain. GHD has analysed soil samples taken from within the small patch of Paperbark Swamp Forest with soil immediately to the west of the patch, taken from within the Blackbutt Tallowood Forest, as well as samples from the floodplain associated with the vegetation to the east of the site. This analysis showed the soil from within the Paperbark Swamp Forest was similar to that contained within the Blackbutt Tallowood Forest to the west of the patch of Paperbark Swamp Forest. It should also be noted that Blackbutt Tallowood Forest also exists immediately below the farm dam which further supports the position the small patch of remnant Paperbarks does not constitute an example of the EEC. The area is also subjected to constant grazing.

SEPP 14 Wetlands

Lands in and to the east of the site are currently zoned E2. This zoning reflects the existing mapped boundary of the SEPP 14 wetlands. The proposed rezoning retains the existing E2 zone boundary within the proposed eastern lots. . The photo included as Plate 4, below, is taken from the north east corner of the site. The proposed subdivision will see the lots proposed in the eastern portion of the site include a portion of this land however no dwellings, associated infrastructure and APZ's would be included within the SEPP 14 boundary. This means there will be no impacts within the SEPP 14 boundary and future Development Applications would not require and EIS.



Plate 4 SEPP 14 Vegetation boundary

Threatened flora species

No threatened flora species have been recorded within the proposed development footprint to date. Based on the preliminary assessment of habitats, soil types and vegetation occurring within the site, a total of two threatened flora species have been identified as possibly occurring within the Paperbark Swamp Forest community on the eastern portion of the site. These species are listed in Table 4-4. Surveys of the site did not identify these species and details of potential habitat for these species are included in Appendix B. Areas identified as possible habitat for these species will be retained as part of the proposal.

Table 4-4 Threatened flora that may occur within the site

Scientific name	Common name	TSC Act status	EPBC Act status
<i>Cryptostylis hunteriana</i>	Leafless Tongue-orchid	V	V
<i>Maundia triglochinoides</i>	-	V	-

Threatened fauna species

A total of 20 threatened fauna species have been assessed as having the potential to occur within the subject site based on the habitats present. These species are listed in Table 4-5 and comprise 10 threatened birds, seven threatened bats, two threatened mammals and one threatened frog species. The value of habitats within the subject site for these species is discussed in Section 4.2.3.

Table 4-5 Threatened fauna that may occur within the site

Scientific name	Common name	TSC Act status	EPBC Act status
<i>Calyptorhynchus lathami</i>	Glossy Black-cockatoo	V	-
<i>Daphoenositta chrysoptera</i>	Varied Sittella	V	-
<i>Ephippiorhynchus asiaticus</i>	Black-necked Stork	E	-
<i>Glossopsitta pusilla</i>	Little Lorikeet	V	-
<i>Grus rubicunda</i>	Brolga	V	-
<i>Irediparra gallinacea</i>	Comb-crested Jacana	V	-
<i>Ixobrychus flavicollis</i>	Black Bittern	V	-
<i>Lophoictinia isura</i>	Square-tailed Kite	V	-
<i>Ninox strenua</i>	Powerful Owl	V	-
<i>Tyto novaehollandiae</i>	Masked Owl	V	-
<i>Dasyurus maculatus</i>	Spotted-tailed Quoll	V	E
<i>Miniopterus australis</i>	Little Bentwing-bat	V	-
<i>Miniopterus schreibersii oceanensis</i>	Eastern Bentwing-bat	V	-
<i>Mormopterus norfolkensis</i>	Eastern Freetail-bat	V	-
<i>Phascolarctos cinereus</i>	Koala	V	V
<i>Pteropus poliocephalus</i>	Grey-headed Flying-fox	V	V
<i>Saccolaimus flaviventris</i>	Yellow-bellied Sheath-tail-bat	V	-
<i>Scoteanax rueppellii</i>	Greater Broad-nosed Bat	V	-
<i>Syconycteris australis</i>	Common Blossom-bat	V	-
<i>Litoria aurea</i>	Green and Golden Bell Frog	E	V


4.3.3 Koala

Kempsey Shire Council has developed a Comprehensive Koala Plan of Management (CKPoM) for the eastern portion of the Kempsey Local Government Area (LGA). This plan satisfies the requirements of SEPP 44 and replaces the requirement for preparation of an individual KPOM in relation to development in areas of core Koala habitat.

The majority of subject site is mapped as Secondary (Class B) Preferred Koala Habitat with a small portion in the north east corner mapped as Secondary (Class A) under the Kempsey CKPoM. Vegetation that falls within the Class A category includes a Primary Feed Tree (PFT) growing in association with one or more Secondary Feed Trees (SFT). The Class B category is defined as vegetation communities and/or associations wherein primary food tree species are absent and secondary or supplementary food tree species are identified.

Assessments of the site indicated that significant adjustments to this mapping were required to reflect the site's actual habitat value to the Koala. The presence of Tallowwood (*Eucalyptus microcorys*) and Grey Gum (*Eucalyptus propinqua*), which are listed as a PFT's, were recorded in a scattered distribution within the western portion of the site. Consequently, despite the majority of the site being mapped as Secondary (Class B) Preferred Koala Habitat under the CKPoM, this portion of the site should be categorised as Secondary (Class A) and covers an area of 7.5 hectares. The small area of the site currently mapped as Secondary (Class A) habitat (0.4 hectares) was also visited and should be classified as 'other vegetation' as none of the listed PFT's or SFT's under the CKPoM occur in this location. The remainder of the site, covering an area of approximately 4.8 hectares, is considered 'other vegetation' as this portion of the site is cleared lands (4.2 hectares) or contains only scattered trees (0.6 hectares) which are not PFT's or SFT's. The difference in the mapping is an inherent result of the CKPoM being a broad scale assessment of the landscape.

GHD's ecologists completed ten SAT assessments associated with PFTs. No Koala activity was detected at the site however there are confirmed sightings of the Koala in the locality and it is assumed the Koala may utilise the site on a transient basis only as part of a broader range. In addition, all Koala feed trees (both Primary and Secondary) were mapped on the site. As mentioned, two PFTs were present on site. The Koala habitat is mapped in Figure 5a.



Service Layer Credits: Source: Esri, DigitalGlobe, GeoEye, i-cubed, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AEX, Getmapping, Aerogrid, IGN, IGP, swisstopo, and the GIS User Community

Paper Size A4
0 10 20 40 60 80
Metres
Map Projection: Transverse Mercator
Horizontal Datum: GDA 1994
Grid: GDA 1994 MGA Zone 56



LEGEND

Other vegetation
Secondary (Class A)
Preferred Koala habitat

Primary Food Tree (PFT) - Grey Gum
Primary Food Tree (PFT) - Tallowood



Dulconghi Investments Pty Ltd
Dulconghi Heights Rezoning
Ecology Assessment

Job Number | 22-17672
Revision | B
Date | 10 Mar 2016

Koala Habitat Features

Figure 5(a)

G:\22\17672\GIS\Maps\Deliverables\Ecology Assessment\2217672_EA007_KoalaHabitat_B.mxd

Level 3, GHD Tower, 24 Honeysuckle Drive, Newcastle NSW 2300 T 61 2 4979 9999 F 61 2 4979 9988 E ntlmail@ghd.com W www.ghd.com.au

© 2016. Whilst every care has been taken to prepare this map, GHD, LPI and ESRI make no representations or warranties about its accuracy, reliability, completeness or suitability for any particular purpose and cannot accept liability and responsibility of any kind (whether in contract, tort or otherwise) for any expenses, losses, damages and/or costs (including indirect or consequential damage) which are or may be incurred by any party as a result of the map being inaccurate, incomplete or unsuitable in any way and for any reason.

Data source: LPI: DCDB / DTDB, 2012; ESRI: Aerial Imagery, 2014. Created by: fmackay, tmorton

4.3.4 EPBC Act MNES

The database searches identified three threatened ecological communities, nine threatened flora species, 14 threatened fauna species and 11 migratory species listed under the EPBC Act as potentially occurring within the locality (see Appendix B).

Threatened ecological communities

As indicated in Table 4-3, the following three EPBC Act listed ecological communities, were identified during the database searches as occurring within the locality:

- Littoral Rainforest and Coastal Vine Thickets of Eastern Australia.
- Lowlands Rainforest of Subtropical Australia.
- Subtropical and Temperate Coastal Saltmarsh.

Site surveys revealed that these communities do not occur within the subject site.

Threatened flora species

As discussed in Section 4.3.2, no threatened flora species have been recorded within the proposed development footprint to date. One EPBC listed threatened flora species, Leafless Tongue-orchid, was identified as possibly occurring within the Paperbark Swamp Forest community on the eastern portion of the site. Areas identified as possible habitat for this species will be retained as part of the proposal.

Threatened fauna species

As indicated in Table 4-5, a total of four EPBC Act listed threatened species were assessed as having the potential to occur within the site. Three of these species (Koala, Grey-headed Flying-fox and Green and Golden Bell Frog) were considered likely to occur, and the fourth species, Spotted-tailed Quoll, was considered as a possible occurrence.

The Koala, Grey-headed Flying-fox and Spotted-tailed Quoll were assessed as potentially utilising the site as a foraging resource as part of a much larger home range. Paperbark Swamp Forest associated with the SEPP 14 wetland on the eastern portion of the site was considered to provide potential habitat for the Green and Golden Bell Frog. This area would be retained as part of the proposal.

Migratory fauna

A total of seven migratory terrestrial bird species and four migratory wetland species were identified by the database searches as known or having the potential to occur within the locality, comprising:

- Migratory terrestrial species
 - Black-faced Monarch (*Monarcha melanopsis*)
 - Rainbow Bee-eater (*Merops ornatus*)
 - Rufous Fantail (*Rhipidura rufifrons*)
 - Satin Flycatcher (*Myiagra cyanoleuca*)
 - Spectacled Monarch (*Monarcha trivirgatus*)
 - White-bellied Sea-Eagle (*Haliaeetus leucogaster*)
 - White-throated Needletail (*Hirundapus caudacutus*)

- Migratory wetland species
 - Cattle Egret (*Ardea ibis*)
 - Great Egret (*Ardea alba*)
 - Latham's Snipe (*Gallinago hardwickii*)
 - Painted Snipe (*Rostratula benghalensis*)

5. Preliminary impact assessment

5.1 Overview

A preliminary assessment of impacts of the proposal is included below. This assessment is based on the proposal and indicative development footprint as described in Section 1.2 and is intended to provide an overview of the potential impacts associated with the proposal. It should be noted, however, that a more comprehensive impact assessment, based on the final development footprint and informed by more extensive survey effort and assessment, would be undertaken at the Development Application stage should this rezoning application be successful.

The exact location, size, lot layout and nature of the development would be determined using reference to the BBAM before the DA stage.

This approach will assist in determining a subdivision design that may not be considered to have a 'significant impact' on threatened biota. The intended amendments to the current zoning would not result in direct impacts within the entire indicative development footprint shown on Figure 2. Impacts are likely to be reduced through retention of vegetation and habitat resources within large lots and potentially also a reduction or reconfiguration of lots. This preliminary impact assessment should therefore be considered as an indication of the maximum impacts that could be associated with the proposal.

5.2 Direct impacts

The direct impacts of the proposal would be limited to areas within the indicative development footprint as shown on Figure 6. The indicative development footprint is contained within Lot 3 DP 1164661 although would not affect the entirety of the subject site. Areas outside of the indicative development footprint would be retained. Impacts within potential conservation areas would therefore be positive in terms of biodiversity outcomes.

5.2.1 Removal of vegetation and habitat

The proposal would result in the removal or modification of approximately 6.98 ha of Blackbutt Tallowood dry grassy open forest within the indicative development footprint. This includes 2.3 ha that would be cleared for residential dwellings and their associated infrastructure (eg services, roads etc) and 4.68 ha that would be under scrubbed/thinned to accommodate bushfire protection areas. In addition, several remnant Paperbark trees would be removed to accommodate the main access road, dwellings and APZ's (approximately 0.36 ha).

As indicated on Figure 6, there is likely to be scope to retain native trees and some understorey vegetation within the residential lots and to retain native trees within the asset protection zones. In this regard, Preferred Koala Food Trees will be retained across the site where possible, as well as all large hollow-bearing trees within areas nominated as APZ's. Vegetation being impacted as part of the proposed subdivision has already been impacted by the effects of clearing and grazing of cattle meaning clearing of trees to accommodate the APZ's will be limited. This has enabled the project team to be able to retain most of the important habitat trees throughout the site.

No SEPP 14 wetland vegetation will be directly impacted by the proposal.

The extent of vegetation and habitats within the indicative development footprint is summarised in Table 5-1.

Table 5-1 Extent of vegetation within the proposed development footprint

Vegetation community	TSC Act Status	Area impacted by total clearing (hectares)	Area impacted by partial clearing (hectares)	Area to be retained (hectares)
Blackbutt Tallowwood dry grassy open forest of the central parts of the north coast Moderate/good - medium	-	2.3	4.68	0.52 (plus 37.9 within proposed new E2 zone)
Paperbark swamp forest of the coastal lowlands of the north coast Low		-0.06	0.3	0.24
Total Native Vegetation		2.36	4.98	38.66

Note:

1. Partial clearing calculations include Asset Protection Zones
2. Primary Koala feed trees (PFTs) will be retained in Asset Protection Zones and in areas proposed for dwelling construction through the use of Tree Preservation Order or Section 88b instruments.

The Planning Proposal also includes the rezoning of approx. 37.9 ha of Lot 3 DP 1164661 to offset impacts to native vegetation at the site. This approach was discussed with representatives of the DPE and OEH during the site visit on 3 February 2016 and it was agreed this would be a suitable offset activity for the proposals impacts. OEH indicated they were also supportive of the avoidance and mitigation measures proposed within the planning proposal however these actions alone were not considered adequate leading to the rezoning of the additional 37.9 ha as E2 Environmental Conservation.

5.2.2 Impacts on aquatic habitats

A drainage line bisects the proposed development footprint. This drainage line would be retained as part of the proposal. Impacts to water quality through increased runoff from hardstand areas and potential for contamination from surrounding residences may occur as a result of the proposal. However, the adoption of appropriate mitigation measures including appropriate sediment and erosion control measures would reduce the potential for impact.

5.2.3 Koala habitat impacts

Vegetation at the site is identified as Secondary (Class A) Preferred Koala habitat under the Kempsey CKPoM (see Section 2.2.4) and comprises scattered occurrences of the 'primary food trees', Tallowwood and Grey Gum (Biolink 2011) are present. It is considered likely that the Koala utilises the site as part of a much larger home range in a transient nature and consequently impacts to this species, in terms of habitat fragmentation would need to be addressed as part of the DA. Impacts to the Koala would be limited to the clearing of 2.3 hectares of Secondary (Class A) Koala habitat and the partial clearing (for APZ's) of 4.68 hectares. This vegetation is in a degraded state with the canopy already 'thinned' in the majority of the western portion of the site due to previous tree clearing and the mid storey largely removed due to the impacts of constant grazing. Approximately four (4) PFTs will be impacted by the proposal through the construction of the access roads or dwellings. Those PFTs occurring within Asset Protection Zones will be protected by a Tree Preservation Order. PFTs proposed to be retained are shown on Figure 5a.

Fragmentation/isolation of habitat would also need to be considered for other species identified as potentially occurring within the subject site (see Table 4-4 and Table 4-5).

Construction activities may result in the injury or mortality of terrestrial fauna that may be sheltering amongst vegetation within the site. Pre-clearing fauna surveys would be recommended as part of the Construction Environmental Management Plan (CEMP) to reduce the risk of injury or mortality to native fauna, especially tree dwelling fauna. The CEMP would also include protocols for the felling of habitat trees and measures for the safe management of native fauna if detected during construction.

Other direct impacts that would need to be considered during the DA phase of the proposal include habitat fragmentation and isolation and fauna injury/mortality.

Offsetting impacts to Koala habitat

The CKPoM Working Provisions (April 2011) outlines the planning provisions associated with the Koala within the portion of the shire covered by the CKPoM. Section 4 sets out the requirements when a Development Application or Planning Proposal seeks to impact on native vegetation, in particular, vegetation mapped as Preferred Koala Habitat (PKH).

This proposal will impact on approximately 6.98 ha of Secondary (Class A) Preferred Koala Habitat with the breakdown of these impacts discussed above. In this case consideration of Section 4.6 of the CKPoM is required. As such, mapping of Koala feed trees and SAT assessments were completed. Under Section 4.7 the proposed rezoning is considered to be 'higher density'. In this case, if the proposal seeks to retain almost all PFTs over 250 mm at dbhob (diameter at breast height over bark), the provisions outlined in Section 4.10 apply. In addition, a habitat compensation package will be prepared in accordance of the provisions outlined in Section 4.12.

The details of this package will be included in the detailed ecological assessment to be completed as part of the future DA documentation. In general, it will include:

- Securing at least twice the area of the habitat being cleared under a conservation mechanism. This will require some consultation with council as the majority of the impact to Koala habitat is limited to 'thinning' of canopy trees for Asset Protection Zones (approximately 4.68 hectares). The area of total clearing is approximately 2.3 hectares. The lands required for the Koala offset would be located within the 37.9 ha of land proposed to be rezoned E2.
- The offset will be secured using the E2 zoning and another conservation mechanism if required by KSC.
- The offset will be located adjacent to the site in vegetation mapped as the same type though in better condition (the preferred area for conservation is not subject to grazing from cattle). Vegetation proposed for conservation is Secondary (Class A) Preferred Koala Habitat.
- The offset site would be subjected to a Vegetation Management Plan or similar (depends on the type of mechanism used to secure the offset) and managed for conservation purposes.


5.3 Indirect impacts

A number of indirect impacts are identified that could potentially affect surrounding native vegetation, native fauna populations and waterways (including SEPP 14 wetland) outside of the proposed development footprint. These impacts relate to:

- Erosion, sedimentation and contamination.
- Weed invasion and edge effects.
- Introduction of pests and pathogens.
- Increased light, noise and vibration.

These impacts would be addressed in greater detail throughout the DA process. It should be remembered that the subdivision plan presented in the planning proposal has been provided to show how a potential subdivision may apply to the land and the considerations associated with reducing impacts to biodiversity. This layout may be subject to change (either through the realignment of lot boundaries or repositioning/ reduction in dwellings) depending on decisions made by approval authorities and/or the applicant. In this regard it is not possible to complete a full ecological impact assessment. Furthermore, such a detailed assessment is not required until the Development Application (DA) process commences.

The results of this assessment show the site is suitable for the proposed subdivision and indicates that the subdivision will not have a 'significant impact' on any threatened biota. Issues associated with the Koala have been considered and addressed in accordance with the CKPoM and it is anticipated that the majority of these issues would be satisfactorily addressed through the adoption of appropriate mitigation measures, which would be incorporated into the CEMP, and outlined during the complete ecological impact assessment which will accompany any future DA.



Service Layer Credits: Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AEX, Getmapping, Aerogrid, IGN, IGP, swisstopo, and the GIS User Community

Paper Size A4

0 10 20 40 60 80

Metres

Map Projection: Transverse Mercator
Horizontal Datum: GDA 1994
Grid: GDA 1994 MGA Zone 56

LEGEND

- Proposed subdivision
- Canopy Trees Retained
- Clearing
- Primary Food Tree (PFT) - Grey Gum
- Primary Food Tree (PFT) - Tallowwood

Dulconghi Investments Pty Ltd
Dulconghi Heights Rezoning
Ecology Assessment

Job Number | 22-17672
Revision | C
Date | 11 Feb 2016

Ecology Impacts

Figure 6

6. Conclusion

A review of existing literature and site surveys indicate the main constraint to future development is the management of biodiversity, including Koala habitat. Constraints to be considered and how they would be managed during future approvals include:

- Impacts to approximately 6.98 ha of modified Blackbutt Tallowwood grassy open forest vegetation, comprising the removal of 2.3 ha of vegetation for residential dwellings and associated infrastructure and partial clearing of 4.68 ha to accommodate bushfire protection areas. This vegetation type is in a degraded state with the canopy already 'thinned' in the majority of the western portion of the site due to previous tree clearing and the mid storey largely removed due to the impacts of constant grazing. This vegetation type is not listed as an EEC in NSW and such an impact would likely not be considered a 'significant' impact.
- Removal of several remnant Paperbark trees to accommodate construction of the main access road, dwelling and APZ (approximately 0.36 hectares).
- Impacts to habitat for potential threatened fauna as listed in Table 4-2. These impacts are considered minor due to the following:
 - The existing condition of the vegetation being impacted
 - The limited total clearing of 2.36 ha required
 - Limited tree removal in Asset Protection Zones (large areas of the western portion of the site already have a discontinuous canopy and cleared understorey)
 - The retention of all PFTs for the Koala
 - The retention of the majority of hollow-bearing trees within Asset Protections Zones and via the sighting of dwelling locations
 - The protection of habitat trees via Tree Preservation Orders (or other agreed planning mechanism)
 - Preparation of a Construction Environmental Management Plan (CEMP), including appropriate avoidance and mitigation measures, associated with native biota.
- Presence of Secondary (Class A) Preferred Koala habitat (Blackbutt Tallowwood grassy open forest). This vegetation type at the site includes scattered individuals of the 'primary food trees (PCTs)', Tallowwood and Grey Gum (Biolink 2011). The proposed subdivision would remove approx. four PCTs with most PCTs being retained and protected via a planning instrument (such as Tree Preservation Order). Impacts have been minimised by retaining PCTs in APZ's, determining building footprints within lots to avoid PCTs and gazetting biodiversity offsets for conservation if required. Impacts to Koala habitat have been assessed in accordance with the Comprehensive Koala Plan of Management, as detailed in Section 5.2.3, and the EPBC Act.
- SEPP 44. As mentioned above, the development would also be subject to detailed ecological impact assessment, including assessments of significance (7-part test) through the provisions of Section 5A of the EPA Act or a biobanking statement under Part 7A of the TSC Act.
- The mapped SEPP 14 boundary in the east of the site will be the extent of the proposed rezoning to R5. There will be no dwellings, associated infrastructure and APZ's constructed within the mapped SEPP 14 area within the proposed eastern lots and, therefore, this area will not be subjected to any impacts associated with the proposal.

The Rural Residential Land Strategy (Kempsey Shire Council 2014) determined that biodiversity was a constraint to the development of rural residential subdivisions in the Crescent Head locality. In regards to lands that are the subject of this report, GHD have completed an analysis of biodiversity constraints and impacts associated with the proposed subdivision and conclude that the land subject to the planning proposal is suitable for rezoning to R5. Any impacts to threatened biota would be further addressed in greater detail at the DA stage. It should be noted that the subdivision plan presented in the planning proposal has been provided to show how a potential subdivision may apply to the land and the considerations associated with reducing impacts to biodiversity. This layout may be subject to change (either through the realignment of lot boundaries or repositioning/ reduction in dwellings) depending on decisions made by approval authorities and/or the applicant. In this regard it is not possible to complete a full ecological impact assessment.

7. Disclaimer

This report: has been prepared by GHD for Dulconghi Investments Pty Ltd and may only be used and relied on by Dulconghi Investments Pty Ltd for the purpose agreed between GHD and the Dulconghi Investments Pty Ltd as set out in section 1.4 of this report.

GHD otherwise disclaims responsibility to any person other than Dulconghi Investments Pty Ltd arising in connection with this report. GHD also excludes implied warranties and conditions, to the extent legally permissible.

The services undertaken by GHD in connection with preparing this report were limited to those specifically detailed in the report and are subject to the scope limitations set out in the report.

The opinions, conclusions and any recommendations in this report are based on conditions encountered and information reviewed at the date of preparation of the report. GHD has no responsibility or obligation to update this report to account for events or changes occurring subsequent to the date that the report was prepared.

The opinions, conclusions and any recommendations in this report are based on assumptions made by GHD described throughout this report. GHD disclaims liability arising from any of the assumptions being incorrect.

GHD has prepared this report on the basis of information provided by Dulconghi Investments Pty Ltd and others who provided information to GHD (including Government authorities)], which GHD has not independently verified or checked beyond the agreed scope of work. GHD does not accept liability in connection with such unverified information, including errors and omissions in the report which were caused by errors or omissions in that information.

8. References

- ATRP (2010). *Streblus pendulinus*. [Online]. Available from: http://keys.trin.org.au:8080/key-server/data/0e0f0504-0103-430d-8004-060d07080d04/media/Html/taxon/Streblus_pendulinus.htm. Australian Tropical Rainforest Plants.
- Biolink Ecological Consultants (2009) *Comprehensive Koala Plan of Management for Eastern Portion of Kempsey Shire LGA Volume 2 Resource Study*. Prepared for Kempsey Shire Council.
- Biolink Ecological Consultants (2011) *Comprehensive Koala Plan of Management for Eastern Portion of Kempsey Shire LGA (Working Provisions)*. Prepared for Kempsey Shire Council.
- BOM (2014) Climate Data Online.
http://www.bom.gov.au/climate/averages/tables/cw_067084.shtml
- Campbell, S. (2011). Ecological specialisation and conservation of Australia's large-footed myotis: a review of trawling bat behaviour. In 'The Biology and Conservation of Australasian Bats' (eds B. Law, P. Eby, D. Lunney and L. Lumsden). Royal Zoological Society of NSW, pp. 72-85
- Churchill, S. (2008). *Australian Bats*. Second Edition. Allen & Unwin, Australia.
- DECC (2009). *BioBanking Assessment Methodology and Credit Calculator Operational Manual*. Department of Environment and Climate Change, Hurstville NSW.
- Department of Environment and Climate Change (DECC) (2008) *NSW (Mitchell) Landscapes Version 3*.
- Department of Primary Industries (DPI) (2015). Online Records Viewer.
<http://www.dpi.nsw.gov.au/fisheries/species-protection/records>
- DotE (2013) *Matters of National Environmental Significance Significant impact guidelines 1.1 Environment Protection and Biodiversity Conservation Act 1999*. Department of the Environment, Canberra ACT.
- DotE (2013a). EPBC Online Protected Matters Database.
<http://www.environment.gov.au/epbc/protected-matters-search-tool>
- Eby, P. and Law, B. (2008). Ranking the feeding habitats of Grey-headed flying foxes for conservation management: a report for The Department of Environment and Climate Change (NSW) & The Department of Environment, Water, Heritage and the Arts. Available from <http://www.environment.nsw.gov.au/resources/threatenedspecies/GHFFmainreport.pdf>
- GHD (2013) *Crescent Head Rezoning Submission*. Report prepared for Dulconghi Investments Pty Ltd.
- Higgins, P.J. (Ed) (1999), *Handbook of Australian, New Zealand and Antarctic Birds*, vol. 4, Oxford University Press, Melbourne.
- Hoye, G.A. and Hall, L.S. (2008). Little Bent-winged Bat *Miniopterus australis*. In S. Van Dyke and R. Strahan (eds), 'The Mammals of Australia' 3rd edition. Reed New Holland, Chatswood.
- Hoye, G.A. and Richards, G.C. (2008). Greater Broad-nosed Bat *Scoteanax rueppellii*. In S. Van Dyke and R. Strahan (eds), 'The Mammals of Australia' 3rd edition. Reed New Holland, Chatswood.
- Hoye, G.A. and Schulz, M. (2008). Large-eared Pied Bat *Chalinolobus dwyeri*. In S. Van Dyke and R. Strahan (eds), 'The Mammals of Australia' 3rd edition. Reed New Holland, Chatswood.

Jessup, L.W. (2003). *Flora of South-eastern Queensland: Volume 1: Changes to names or status of taxa*. [Online]. Queensland Herbarium. Toowong, Queensland: Queensland Herbarium, Environmental Protection Agency. Available from: <http://www.derm.qld.gov.au/register/p00721aa.pdf>.

Kempsey Shire Council (2014) Rural Residential Land Release Strategy. Insite Planning Services Pty Ltd, Cessnock NSW.

Kendall & Kendall (1996) Assessment of Significance on Possibly Occurring Threatened Species, SEPP No. 44 Koala Habitat Assessment and SEPP No. 46 Native Vegetation Assessment of Proposed Subdivision of part lots 2 & 3 DP 794159. Kendall & Kendall, West Kempsey NSW.

Kendall & Kendall (1999) Flora and Fauna Assessment of the "Habitat Zone" – Dulconghi Heights Estate. Kendall & Kendall, West Kempsey NSW.

Lock, M.L. and Wilson, B.A. (1999). The distribution of the New Holland mouse (*Pseudomys novaehollandiae*) with respect to vegetation near Anglesea, Victoria. *Wildlife Research* 26 (4) 565-577

Mahony, M., Knowles, R. and Pattinson, L. (1997). Stuttering Barred Frog. In H. Ehmann (ed) 'Threatened Frogs of New South Wales: Habitats, Status and Conservation' pp.65-71. Frog and Tadpole Study Group of NSW.

Office of Environment and Heritage (OEH) (2015a) NSW BioNet. The Website for the Atlas of NSW Wildlife. <http://www.bionet.nsw.gov.au/>

Office of Environment and Heritage (OEH) (2015b) *Vegetation Types Database*. <http://www.environment.nsw.gov.au/biobanking/VegTypeDatabase.htm>

Office of Environment and Heritage (OEH) (2015c). List of Accredited Assessors. <http://www.environment.nsw.gov.au/biobanking/Assessorlist.htm>

Office of Environment and Heritage (OEH) (2015d) *Threatened Species Profile Database*. <http://www.environment.nsw.gov.au/biobanking/VegType Database.htm>

The Royal Botanic Gardens and Domain Trust (2011). PlantNET. [Online]. The Plant Information Network System of The Royal Botanic Gardens and Domain Trust, Sydney, Australia (version 2). Available from: <http://plantnet.rbgsyd.nsw.gov.au>.

White, A.W. (2008a). *The Distribution and Conservation Status of Barred Frogs in the Sydney Basin. Part 1. Giant Barred Frog Mixophyes iteratus*. *Herpetofauna* 38(1) 24-34.

White, A.W. (2008b). *The Distribution and Conservation Status of Barred Frogs in the Sydney Basin. Part 2. Stuttering Frog Mixophyes balbus*. *Herpetofauna* 38(2) 84-95.

Wilson, B.A. and Bradtke, E. (1999). The diet of the New Holland mouse, *Pseudomys novaehollandiae* (Waterhouse) in Victoria. *Wildlife Research* 26(4) 439-451

Appendices

Appendix A – Field survey data

Vegetation plot/transect data

Veg zone	Veg type ID	Plot ID	Native plant species richness	Native over-storey cover	Native mid-storey cover	Native ground cover (grasses)	Native ground cover (shrubs)	Native ground cover (other)	Exotic plant cover	Number of trees with hollows	Over-storey regeneration	Total length of fallen logs	Eastings	Northings	Zone
1	NR 119	1	36	56.5	7	36	0	18	2.3	0	1	3	495381	6551983	56
1	NR 119	2	35	24.4	5.4	12	0	12	40	0	1	6	495208	6552006	56
1	NR 119	3	23	49	8.5	20	0	32	9.3	1	1	27	495392	6552062	56
1	NR 119	4	30	62	2	28	0	6	3.7	1	1	11	495507	6552048	56

Flora species recorded within the subject site

Family	Exotic	Scientific name	Common name	TSC status	EPBC status
ADIANTACEAE		<i>Cheilanthes sieberi</i>	Rock Fern		
APIACEAE		<i>Daucus glochidiatus</i>	Native Carrot		
APIACEAE		<i>Hydrocotyle hirta</i>	Hairy Pennywort		
APOCYNACEAE	Yes	<i>Gomphocarpus fruticosus</i>	Narrow-leaved Cotton Bush		
ASTERACEAE	Yes	<i>Ageratina adenophora</i>	Crofton Weed		
ASTERACEAE	Yes	<i>Bidens pilosa</i>	Cobbler's Pegs		
ASTERACEAE	Yes	<i>Cirsium vulgare</i>	Spear Thistle		
ASTERACEAE	Yes	<i>Conyza</i> spp.	Fleabane		
ASTERACEAE	Yes	<i>Gamochaeta americana</i>	Cudweed		
ASTERACEAE	Yes	<i>Hypochaeris radicata</i>	Catsear		
ASTERACEAE	Yes	<i>Senecio madagascariensis</i>	Fireweed		
ASTERACEAE	Yes	<i>Sonchus oleraceus</i>	Common Sowthistle		
BLECHNACEAE		<i>Blechnum</i> spp.			
CAMPANULACEAE		<i>Wahlenbergia gracilis</i>	Sprawling Bluebell		
CASUARINACEAE		<i>Allocasuarina torulosa</i>	Forest Oak		
CLUSIACEAE		<i>Hypericum japonicum</i>	-		
COMMELINACEAE		<i>Commelina cyanea</i>	Native Wandering Jew		
CONVOLVULACEAE		<i>Convolvulus erubescens</i>	Pink Bindweed		
CONVOLVULACEAE		<i>Dichondra repens</i>	Kidney Weed		
CYPERACEAE		<i>Carex appressa</i>	Tall Sedge		
CYPERACEAE		<i>Schoenus apogon</i>	Fluke Bogrush		
DENNSTAEDTIACEAE		<i>Pteridium esculentum</i>	Bracken		

Family	Exotic	Scientific name	Common name	TSC status	EPBC status
DILLENIACEAE		<i>Hibbertia obtusifolia</i>	Hoary Guinea Flower		
DILLENIACEAE		<i>Hibbertia</i> spp.			
ERICACEAE		<i>Lissanthe strigosa</i>	Peach Heath		
EUPHORBIACEAE		<i>Homalanthus populifolius</i>	Bleeding Heart		
FABACEAE (FABOIDEAE)		<i>Desmodium varians</i>	Slender Tick-trefoil		
FABACEAE (FABOIDEAE)		<i>Glycine clandestina</i>	Twining Glycine		
FABACEAE (FABOIDEAE)		<i>Kennedia rubicunda</i>	Dusky Coral Pea		
FABACEAE (MIMOSOIDEAE)	Yes	<i>Acacia saligna</i>	Golden Wreath Wattle		
GERANIACEAE		<i>Geranium solanderi</i>	Native Geranium		
GOODENIACEAE		<i>Goodenia</i> spp.			
HALORAGACEAE		<i>Gonocarpus teucroides</i>	Germander Raspwort		
LOBELIACEAE		<i>Pratia purpurascens</i>	White Root		
LOMANDRACEAE		<i>Lomandra longifolia</i>	Spiny-headed Mat-rush		
LOMANDRACEAE		<i>Lomandra multiflora</i>	Many-flowered Mat-rush		
LUZURIAGACEAE		<i>Eustrephus latifolius</i>	Wombat Berry		
MALVACEAE	Yes	<i>Sida rhombifolia</i>	Paddy's Lucerne		
MYRSINACEAE	Yes	<i>Anagallis arvensis</i>	Scarlet Pimpernel		
MYRTACEAE		<i>Acmena smithii</i>	Lilly Pilly		
MYRTACEAE		<i>Corymbia intermedia</i>	Pink Bloodwood		
MYRTACEAE		<i>Eucalyptus microcorys</i>	Tallowwood		
MYRTACEAE		<i>Eucalyptus pilularis</i>	Blackbutt		

Family	Exotic	Scientific name	Common name	TSC status	EPBC status
MYRTACEAE		<i>Lophostemon confertus</i>	Brush Box		
MYRTACEAE		<i>Melaleuca quinquenervia</i>	Broad-leaved Paperbark		
ORCHIDACEAE		<i>Dipodium variegatum</i>	-		
OXALIDACEAE		<i>Oxalis perennans</i>			
PASSIFLORACEAE	Yes	<i>Passiflora</i> spp.			
PHORMIACEAE		<i>Dianella caerulea</i>	Blue Flax-lily		
PHYLLANTHACEAE		<i>Breynia oblongifolia</i>	Coffee Bush		
PHYLLANTHACEAE		<i>Poranthera microphylla</i>	Small Poranthera		
PITTOSPORACEAE		<i>Billardiera scandens</i>	Hairy Apple Berry		
PLANTAGINACEAE	Yes	<i>Plantago lanceolata</i>	Lamb's Tongues		
PLANTAGINACEAE		<i>Veronica plebeia</i>	Trailing Speedwell		
POACEAE	Yes	<i>Andropogon virginicus</i>	Whisky Grass		
POACEAE	Yes	<i>Axonopus fissifolius</i>	Narrow-leaved Carpet Grass		
POACEAE		<i>Cymbopogon refractus</i>	Barbed Wire Grass		
POACEAE		<i>Echinopogon ovatus</i>	Forest Hedgehog Grass		
POACEAE		<i>Entolasia stricta</i>	Wiry Panic		
POACEAE		<i>Imperata cylindrica</i>	Blady Grass		
POACEAE		<i>Microlaena stipoides</i>	Weeping Grass		
POACEAE		<i>Opismenus aemulus</i>	Basket Grass		
POACEAE		<i>Opismenus imbecillis</i>	Basket Grass		
POACEAE	Yes	<i>Setaria</i> spp.	Pigeon Grass		
POACEAE	Yes	<i>Sporobolus africanus</i> .	Parramatta Grass		

Family	Exotic	Scientific name	Common name	TSC status	EPBC status
POACEAE	Yes	<i>Stenotaphrum secundatum</i>	Buffalo Grass		
POACEAE		<i>Themeda australis</i>	Kangaroo Grass		
POLYGONACEAE	Yes	<i>Rumex crispus</i>	Curled Dock		
PROTEACEAE		<i>Persoonia stradbokensis</i>	Geebung		
RHAMNACEAE		<i>Pomaderris</i> spp.			
ROSACEAE		<i>Rubus parvifolius</i>	Native Raspberry		
SMILACACEAE		<i>Smilax australis</i>	Lawyer Vine		
VERBENACEAE	Yes	<i>Lantana camara</i> *	Lantana		
VERBENACEAE	Yes	<i>Verbena bonariensis</i>	Purpletop		
VIOLACEAE		<i>Viola hederacea</i>	Ivy-leaved Violet		

Appendix B – Threatened and migratory biota

Threatened biota habitat table

Databases searched

Office of Environment and Heritage (OEH) (2015d) Threatened species profiles- threatened ecological communities known or predicted to occur within the Northern Rivers CMA subregion.

Department of the Environment (DotE) (2015) EPBC PMST Online Search 3 March 2015 - 10 km buffer.

Department of Primary Industries (DPI) (2015) Records viewer search for threatened and protected aquatic species - Northern Rivers CMA.

Office of Environment and Heritage (OEH) (2015a) NSW Wildlife Atlas Search - threatened species results within a 10 km buffer

Likelihood of occurrence

Matters considered in determining the likelihood of occurrence include:

- Known natural distributions including prior records (database searches) and site survey results.
- Geological/ soil preferences.
- Specific habitat requirements (e.g. aquatic environs, seasonal nectar resources, tree hollows etc).
- Climatic considerations (e.g. wet summers; snow fall).
- Home range size and habitat dependence.
- Topographical preferences (e.g. coastal headlands, ridgetops, midslopes, gilgai, wetlands).
- The likelihood of occurrence scale is defined as follows:

Likelihood of occurrence scale

Scale	Description
Known	Species known to occur within the site (e.g. breeding and foraging habitat; foraging habitat; movement corridors). Detected on or immediately adjacent to the site.
Likely	Presence of high value suitable habitat (e.g. breeding and foraging habitat; important movement corridors). Not detected.
Possible	Presence of medium value suitable habitat (e.g. disturbed breeding conditions; constrained foraging habitat; movement corridors). Not detected.
Unlikely	Presence of low value suitable habitat (e.g. disturbed conditions; isolated small habitat area; fragmented movement corridors). Not detected.
Nil	No suitable habitat or corridors linking suitable habitat present. Not detected.

Note: Marine species which are restricted to marine environments only (such as whales, dolphins, sharks and seabirds) are excluded from the Likelihood of Occurrence Table as there is no marine habitat in the subject site.

Threatened flora known or predicted from the locality, habitat association and likelihood of occurring at the subject site

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
<i>Allocasuarina defungens</i>	Dwarf Heath Casuarina	E	E	Grows mainly in tall heath on sand, but can also occur on clay soils and sandstone. The species also extends onto exposed nearby-coastal hills or headlands adjacent to sandplains. Confined to the north coast region of NSW, between Raymond Terrace and Port Macquarie. There are 32 sites recorded from six general localities over a geographic range of about 40 km.	Predicted to occur within 10km (DotE 2015)	Unlikely. No suitable habitat present at site.
<i>Arthraxon hispidus</i>	Hairy-joint Grass	V	V	Moisture and shade-loving grass, found in or on the edges of rainforest and in wet eucalypt forest, often near creeks or swamps.	Predicted to occur within 10km (DotE 2015)	Unlikely. No suitable habitat present at the site. Not previously recorded within the locality.
<i>Chamaesyce psammogeton</i>	Sand Spurge	E	-	Sand Spurge is found sparsely along the coast from south of Jervis Bay to Queensland. Populations have been recorded in Wamberal Lagoon Nature Reserve, Myall Lakes National Park, Moonee Beach Nature Reserve and Bundjalung National Park. Grows on fore-dunes, pebbly strandlines and exposed headlands, often with Spinifex (<i>Spinifex sericeus</i>) and Prickly Couch (<i>Zoysia macrantha</i>)	1 record within 10km (OEH 2015a)	Unlikely. No suitable habitat present at the site.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
<i>Cryptostylis hunteriana</i>	Leafless Tongue-orchid	V	V	Occurs in coastal areas from East Gippsland to southern Queensland. Habitat preferences not well defined. Grows mostly in coastal heathlands, margins of coastal swamps and sedgeland, coastal forest, dry woodland, and lowland forest. Prefers open areas in the understorey and is often found in association with <i>Cryptostylis subulata</i> and <i>Cryptostylis erecta</i> . Soils include moist sands, moist to dry clay loam and occasionally in accumulated eucalypt leaves. Flowers November-February.	Predicted to occur within 10km (DotE 2015)	Possible. Potential habitat present within the eastern portion of the site. Not previously recorded within the locality.
<i>Cynanchum elegans</i>	White-flowered Wax Plant	E	E	Restricted to eastern NSW where it is distributed from Brunswick Heads on the north coast to Gerroa in the Illawarra region. The species has been recorded as far west as Merriwa in the upper Hunter River valley. Usually occurs on the edge of dry rainforest vegetation. Flowering occurs between August and May, with a peak in November	Predicted to occur within 10km (DotE 2015)	Unlikely. No suitable habitat present at the site.
<i>Euphrasia arguta</i>	-	CE	CE	Recently rediscovered near Nundle on the north-western slopes and tablelands, once known from scattered locations between Sydney, Bathurst and Walcha. Known populations occur in eucalypt forest with a mixed grass/shrub understorey, while previous records are described as occurring	Predicted to occur within 10km (DotE 2015)	Unlikely. No habitat present at the site due to the disturbed understorey. Not previously recorded within the locality.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
				in open forest, grassy country and river meadows. Annual and dies back over winter. Dense stands observed in cleared firebreak areas, suggesting it may respond well to disturbance.		
<i>Maundia triglochinoides</i>	-	V	-	Restricted to coastal NSW and extending into southern Queensland. The current southern limit is Wyong; former sites around Sydney are now extinct. Grows in swamps, lagoons, dams, channels, creeks or shallow freshwater 30 - 60 cm deep on heavy clay, low nutrients.	1 record within 10km (OEH 2015a)	Possible. Some potential habitat provided by the SEPP 14 wetland to the east of the site.
<i>Melaleuca biconvexa</i>	Biconvex Paperbark	V	V	Scattered, disjunct populations in coastal areas from Jervis Bay to Port Macquarie, with most populations in the Gosford-Wyong areas. Grows in damp places, often near streams or low-lying areas on alluvial soils of low slopes or sheltered aspects.	Predicted to occur within 10km (DotE 2015)	Unlikely. The site is outside of the known distribution range. Not previously recorded within the locality.
<i>Phaius australis</i>	Lesser Swamp-orchid	E	E	Occurs in Queensland and north-east NSW as far south as Coffs Harbour. Occurs in swampy grassland or swampy forest including rainforest, eucalypt or paperbark forest, mostly in coastal areas.	Predicted to occur within 10km (DotE 2015)	Unlikely. Some suitable vegetation association present in the eastern portion of the site (Paperbark Swamp Forest), however, the site is outside of the known geographic range. Not previously recorded within the locality.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
<i>Streblus pendulinus</i>	Siah's Backbone	-	E	Siah's Backbone occurs from Cape York Peninsula to Milton, south-east New South Wales (NSW), as well as Norfolk Island (ATRP 2010; Jessup 2003; The Royal Botanic Gardens and Domain Trust 2011). Siah's Backbone is found in warmer rainforests, chiefly along watercourses. The species grows in well developed rainforest, gallery forest and drier, more seasonal rainforest (ATRP 2010).	Predicted to occur within 10km (DotE 2015)	Unlikely. No suitable habitat present at the site.
<i>Thesium australe</i>	Austral Toadflax	V	V	Austral Toad-flax is found in very small populations scattered across eastern NSW, along the coast, and from the Northern to Southern Tablelands. Although originally described from material collected in the SW Sydney area, populations have not been seen in a long time. It may persist in some areas in the broader region. Occurs in grassland on coastal headlands or grassland and grassy woodland away from the coast.	2 records within 10km (OEH 2015a) and predicted to occur within 10km (DotE 2015)	Unlikely. No suitable habitat present at the site.

All information in this table is taken from NSW OEH and Commonwealth DotE Threatened Species profiles (OEH, 2013a; DotE 2013a) unless otherwise stated. The codes used in this table are: CE – Critically Endangered; E – Endangered; V – Vulnerable; EP – Endangered Population; CEEC – Critically Endangered Ecological Community; EEC – Endangered Ecological Community.

Threatened fauna known or predicted from the locality, habitat association and likelihood of occurring at the subject site

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
Birds						
<i>Anthochaera phrygia</i>	Regent Honeyeater	CE	E	In NSW confined to two known breeding areas: the Capertee Valley and Bundarra-Barraba region. Non-breeding flocks occasionally seen in coastal areas foraging in flowering Spotted Gum and Swamp Mahogany forests, presumably in response to drought. Inhabits dry open forest and woodlands, particularly Box-Ironbark woodland and riparian forests of River Sheoak, with an abundance of mature trees, high canopy cover and abundance of mistletoes.	Predicted to occur within 10km (DotE 2015)	Unlikely. Preferred vegetation associations not present at the site. Not previously recorded within the locality.
<i>Botaurus poiciloptilus</i>	Australasian Bittern	E	E	Widespread but uncommon over most of NSW except the northwest. Favours permanent freshwater wetlands with tall dense reedbeds particularly <i>Typha</i> spp. and <i>Eleocharis</i> spp., with adjacent shallow, open water for foraging. Roosts during the day amongst dense reeds or rushes and feeds mainly at night on frogs, fish, yabbies, spiders, insects and snails. Scattered distribution across NSW. Inhabits lowland grassy woodland and open forest and, in coastal areas, Casuarina and Melaleuca woodlands, saltmarsh and mangroves.	Predicted to occur within 10km (DotE 2015)	Unlikely. Some potential habitat provided by the SEPP 14 wetland/Paperbark Swamp Forest community to the east of the site, however, not previously recorded within the locality.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
				Requires a low, sparse groundcover, some fallen timber and leaf litter, and a general lack of a shrubby understory.		
<i>Calyptorhynchus lathamii</i>	Glossy Black-cockatoo	V	-	Widespread but uncommon from coast to southern tablelands and central western plains. Feeds almost exclusively on the seeds of <i>Allocasuarina</i> species. Prefers woodland and open forests, rarely away from <i>Allocasuarina</i> . Roost in leafy canopy trees, preferably eucalypts, usually <1km from feeding site. Nests in large (approx. 20cm) hollows in trees, stumps or limbs, usually in Eucalypts (Higgins 1999).	12 records within 10km (OEH 2015a)	Likely. Some potential foraging habitat present due to the presence of Forest Oak (<i>Allocasuarina torulosa</i>).
<i>Carterornis leucotis</i>	White-eared Monarch	V	-	In NSW, White-eared Monarchs are generally found from the Queensland border south to Iluka at the mouth of the Clarence River, and inland as far as the Richmond Range. There are occasional records south of the Clarence River, near Woolgoolga and around Port Macquarie. Occurs in rainforest, especially drier types, such as littoral rainforest, as well as wet and dry sclerophyll forests, swamp forest and regrowth forest.	1 record within 10km (OEH 2015a)	Unlikely. Some suitable vegetation association present within the eastern portion of the site (Paperbark Swamp Forest), however, outside of the general distribution range.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
<i>Daphoenositta chrysoptera</i>	Varied Sittella	V	-	Sedentary, occurs across NSW from the coast to the far west. Inhabits eucalypt forests and woodlands, especially rough-barked species and mature smooth-barked gums with dead branches, mallee and Acacia woodland. Sensitive to habitat isolation and loss of structural complexity, and adversely affected by dominance of Noisy Miners. Cleared agricultural land is potentially a barrier to movement. Builds a cup-shaped nest of plant fibres and cobwebs in an upright tree fork high in the living tree canopy, and often re-uses the same fork or tree in successive years.	3 records within 10km (OEH 2015a)	Possible. Some potential habitat present, however, the high level of disturbance and loss of structural complexity as a result of the agricultural practices reduces the likelihood.
<i>Dasyornis brachypterus</i>	Eastern Bristlebird	E	E	Occurs in southern Queensland/northern NSW, the Illawarra Region and near the NSW/Victorian border. Illawarra population comprises an estimated 1600 birds, mainly from Barren Grounds Nature Reserve, Budderoo National Park and the Jervis Bay area. Habitat characterised by dense, low vegetation including heath and open woodland with a heathy understorey. The fire history of habitat is important, and the Illawarra and southern populations reach maximum densities in habitat that have not been burnt for over 15 years.	Predicted to occur within 10km (DotE 2015)	Unlikely. No suitable understorey vegetation present at the site.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
<i>Ephippiorhynchus asiaticus</i>	Black-necked Stork	E	-	In NSW, becomes increasingly uncommon south of the Northern Rivers region, and rarely occurs south of Sydney. Breeding recorded as far south as Buladelah, though most breeding in NSW occurs in the north-east. Primarily inhabits permanent freshwater wetlands and surrounding vegetation including swamps, floodplains, watercourses and billabongs, freshwater meadows, wet heathland, farm dams and shallow floodwaters. Will also forage in inter-tidal shorelines, mangrove margins and estuaries. Feeds in shallow, still water. Breeds during summer, nesting in or near a freshwater swamp.	25 records within 10km (OEH 2015a)	Likely. Suitable foraging habitat identified on the very eastern portion of the site.
<i>Glossopsitta pusilla</i>	Little Lorikeet	V	-	Occurs from coast to western slopes of the Great Dividing Range. Inhabits dry, open eucalypt forests and woodlands. Occurrence is positively associated with patch size, and with components of habitat complexity including canopy cover, shrub cover, ground cover, logs, fallen branches and litter. Feed primarily on profusely-flowering eucalypts and a variety of other species including melaleucas and mistletoes. On the western slopes and tablelands <i>Eucalyptus albens</i> and <i>E. melliodora</i> are particularly important food sources for pollen and nectar respectively.	2 records within 10km (OEH 2015a)	Possible. Suitable vegetation association identified, however, the lack of structural and habitat complexity reduces the likelihood.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
				Mostly nests in small (opening approx. 3cm) hollows in living, smooth-barked eucalypts, especially <i>Eucalyptus viminalis</i> , <i>E. blakelyi</i> and <i>E. dealbata</i> . Most breeding records are from the western slopes.		
<i>Grus rubicunda</i>	Brolga	V	-	The Brolga was formerly found across Australia, except for the south-east corner, Tasmania and the south-western third of the country. It is still abundant in the northern tropics, but very sparse across the southern part of its range. Though Brolgas often feed in dry grassland or ploughed paddocks or even desert claypans, they are dependent on wetlands too, especially shallow swamps, where they will forage with their head entirely submerged.	1 record within 10km (OEH 2015a)	Possible. Some potential foraging habitat to the east of the site.
<i>Haematopus fuliginosus</i>	Sooty Oystercatcher	V	-	Sooty Oystercatchers are found around the entire Australian coast, including offshore islands, being most common in Bass Strait. Small numbers of the species are evenly distributed along the NSW coast. Favours rocky headlands, rocky shelves, exposed reefs with rock pools, beaches and muddy estuaries.	2 records within 10km (OEH 2015a)	Unlikely. No suitable habitat present at the site.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
<i>Haematopus longirostris</i>	Pied Oystercatcher	E	-	In NSW the species is thinly scattered along the entire coast, with fewer than 200 breeding pairs estimated to occur in the State. It favours intertidal flats of inlets and bays, open beaches and sandbanks.	2 records within 10km (OEH 2015a)	Unlikely. No suitable habitat present at the site.
<i>Irediparra gallinacea</i>	Comb-crested Jacana	V	-	The Comb-crested Jacana occurs on freshwater wetlands in northern and eastern Australia, mainly in coastal and subcoastal regions, from the north-eastern Kimberley Division of Western Australia to Cape York Peninsula then south along the east coast to the Hunter region of NSW, with stragglers recorded in south-eastern NSW.	1 record within 10km (OEH 2015a)	Possible. SEPP 14 wetland to the east of the site potentially provides some habitat.
<i>Ixobrychus flavicollis</i>	Black Bittern	V	-	Occurs from southern NSW to Cape York and the Kimberley, and southwest WA. Inhabits terrestrial and estuarine wetlands, generally in areas of permanent water and dense vegetation. May occur in flooded grassland, forest, woodland, rainforest and mangroves as long as there is permanent water. Roosts by day in trees or within reeds on the ground. Nests in branches overhanging water and breeds from December to March.	1 record within 10km (OEH 2015a)	Possible. Paperbark Swamp Forest to the east of the site potentially provides suitable habitat.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
<i>Lathamus discolor</i>	Swift Parrot	E	E	Migratory, travelling to the mainland from March to October. Breeds in Tasmania from September to January. On the mainland, it mostly occurs in the southeast foraging on winter flowering eucalypts and lerps, with records of the species between Adelaide and Brisbane. Principal over-winter habitat is box-ironbark communities on the inland slopes and plains. <i>Eucalyptus robusta</i> , <i>Corymbia maculata</i> and <i>C. gummifera</i> dominated coastal forests are also important habitat.	1 record within 10km (OEH 2015a) and predicted to occur within 10km (DotE 2015)	Unlikely. Preferred mainland coastal foraging habitat not present at the site.
<i>Lophoictinia isura</i>	Square-tailed Kite	V	-	Occurs across NSW, resident in North, northeast and along west-flowing rivers. Summer breeding migrant to southeast of state. Inhabits a variety of habitats including woodlands and open forests, with preference for timbered watercourses. Favours productive forests on the coastal plain, box-ironbark-gum woodlands on the inland slopes, and Coolibah/River Red Gum on the inland plains. In Sydney area nests in mature living trees within 100m of ephemeral/permanent watercourse. Large home range > 100 km ² .	1 record within 10km (OEH 2015a)	Possible. May utilise the site as part of a larger foraging range, however, suitable nesting habitat not present at the site.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
<i>Ninox strenua</i>	Powerful Owl	V	-	Occurs from the coast to the western slopes. Solitary and sedentary species. Inhabits a range of habitats from woodland and open sclerophyll forest to tall open wet forest and rainforest. Prefers large tracts of vegetation. Nests in large tree hollows (> 0.5 m deep), in large eucalypts (dbh 80-240 cm) that are at least 150 years old. Pairs have high fidelity to a small number of hollow-bearing nest trees and defend a large home range of 400 - 1,450 ha. Forages within open and closed woodlands as well as open areas.	1 record within 10km (OEH 2015a)	Possible. May occasionally utilise the site as part of a wider foraging range although prefers large tracts of vegetation. No suitable nesting habitat present at the site.
<i>Pandion cristatus</i>	Eastern Osprey	V	-	Eastern Ospreys occur in littoral and coastal habitats and terrestrial wetlands of tropical and temperate Australia and offshore islands. They are mostly found in coastal areas but occasionally travel inland along major rivers, particularly in northern Australia. They require extensive areas of open fresh, brackish or saline water for foraging.	5 records within 10km (OEH 2015a)	Possible. SEPP 14 wetland area to the east of the site may provide limited foraging habitat although the lack of open areas reduces the likelihood. Presence would be in a transient nature only.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
<i>Rostratula australis</i>	Australian Painted Snipe	E	E	Normally found in permanent or ephemeral shallow inland wetlands, either freshwater or brackish. Nests on the ground amongst tall reed-like vegetation near water. Feeds on mudflats and the water's edge taking insects, worm and seeds. Prefers fringes of swamps, dams and nearby marshy areas with cover of grasses, lignum, low scrub or open timber.	Predicted to occur within 10km (DotE 2015)	Unlikely. Some limited habitat identified within the SEPP 14 wetland area however to the east of the site, not previously recorded from the locality.
<i>Tyto novaehollandiae</i>	Masked Owl	V	-	Occurs across NSW except NW corner. Most common on the coast. Inhabits dry eucalypt woodlands from sea level to 1100 m. Roosts and breeds in large (>40cm) hollows and sometime caves in moist eucalypt forested gullies. Hunts along the edges of forests and roadsides. Home range between 500 ha and 1000 ha. Prey mostly terrestrial mammals but arboreal species may also be taken.	4 records within 10km (OEH 2015a)	Possible. May occasionally utilise the site as part of a wider foraging range. No suitable nesting habitat present at the site.
Mammals						
<i>Chalinolobus dwyeri</i>	Large-eared Pied Bat	V	V	Occurs from the coast to the western slopes of the divide. Largest numbers of records from sandstone escarpment country in the Sydney Basin and Hunter Valley (Hoye and Schulz 2008). Roosts in caves and mines and most commonly recorded from dry sclerophyll forests and woodlands. An insectivorous species that	Predicted to occur within 10km (DotE 2015)	Unlikely. No suitable roosting habitat present at the site. Outside of general distribution range and not previously recorded within the locality.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
				flies over the canopy or along creek beds (Churchill 2008). In southern Sydney appears to be largely restricted to the interface between sandstone escarpments and fertile valleys.		
<i>Dasyurus maculatus</i>	Spotted-tailed Quoll	V	E	Inhabits a range of environments including rainforest, open forest, woodland, coastal heath and inland riparian forest, from the sub-alpine zone to the coastline. Den sites are in hollow-bearing trees, fallen logs, small caves, rock crevices, boulder fields and rocky-cliff faces. Females occupy home ranges of up to 750 ha and males up to 3,500 ha, usually traversed along densely vegetated creek lines.	4 records within 10km (OEH 2015a) and predicted to occur within 10km (DotE 2015)	Possible. May utilise the site as part of a larger foraging habitat, however the high level of disturbance, limited understorey and lack of available den sites reduces the likelihood.
<i>Falsistrellus tasmaniensis</i>	Eastern False Pipistrelle	V	-	Occurs on southeast coast and ranges. Prefers tall (>20m) and wet forest with dense understorey. Absent from small remnants, preferring continuous forest but can move through cleared landscapes and may forage in open areas. Roosts in hollow trunks of Eucalypts, underneath bark or in buildings. Forages in gaps and spaces within forest, with large foraging range (12km foraging movements recorded) (Churchill 2008, Law et al 2008).	2 records within 10km (OEH 2015a)	Unlikely. Preferred habitat not present at the site. Few records known from northern coastal areas.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
<i>Miniopterus australis</i>	Little Bentwing-bat	V	-	Occurs from Cape York to Sydney. Inhabits rainforests, wet and dry sclerophyll forests, paperbark swamps and vine thickets. Only one maternity cave known in NSW, shared with Eastern Bentwing-bats at Willi Willi, near Kempsey. Outside breeding season roosts in caves, tunnels and mines and has been recorded in a tree hollow on one occasion. Forages for insects beneath the canopy of well-timbered habitats (Churchill 2008, Hoyer and Hall 2008).	9 records within 10km (OEH 2015a)	Likely. May utilise the site as part of a larger foraging range, however, previous disturbance and lack of suitable roosting habitat reduces the likelihood.
<i>Miniopterus schreibersii oceanensis</i>	Eastern Bentwing-bat	V	-	Generally occurs east of the Great Dividing Range along the NSW coast (Churchill 2008). Inhabits various habitats from open grasslands to woodlands, wet and dry sclerophyll forests and rainforest. Essentially a cave bat but may also roost in road culverts, stormwater tunnels and other man-made structures. Only 4 known maternity caves in NSW, near Wee Jasper, Bungonia, Kempsey and Texas. Females may travel hundreds of kilometres to the nearest maternal colony (Churchill 2008).	4 records within 10km (OEH 2015a)	Likely. May utilise the site as part of a larger foraging range, however, previous disturbance and lack of suitable roosting habitat reduces the likelihood.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
<i>Mormopterus norfolkensis</i>	Eastern Freetail-bat	V	-	Occurs in dry sclerophyll forest and woodland east of the Great Dividing Range. Forages in natural and artificial openings in vegetation, typically within a few kilometres of its roost. Roosts primarily in tree hollows but also recorded from man-made structures or under bark (Churchill 2008).	2 records within 10km (OEH 2015a)	Possible. May utilise the site as part of a larger foraging range, however, previous disturbance and limited suitable roosting habitat reduces the likelihood.
<i>Myotis macropus</i>	Southern myotis	V	-	Mainly coastal but may occur inland along large river systems. Usually associated with permanent waterways at low elevations in flat/undulating country, usually in vegetated areas. Forages over streams and watercourses feeding on fish and insects from the water surface. Roosts in a variety of habitats including caves, mine shafts, hollow-bearing trees, stormwater channels, buildings, under bridges and in dense foliage, typically in close proximity to water (Campbell 2011). Breeds November or December (Churchill 2008)	1 record within 10km (OEH 2015a)	Unlikely. Lack of preferred foraging and roosting habitat at the site.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
<i>Petaurus australis</i>	Yellow-bellied Glider	V	-	Occurs along the east coast to the western slopes of the Great Dividing Range. Inhabits a variety of forest types but prefers tall mature eucalypt forest with high rainfall and rich soils. Relies on large hollow-bearing trees for shelter and nesting, with family groups of 2-6 typically denning together. In southern NSW its preferred habitat at low altitudes is moist gullies and creek flats in mature coastal forests. Mostly feeds on sap, nectar and honeydew.	1 record within 10km (OEH 2015a)	Unlikely. Preferred habitat not present at the site.
<i>Phascolarctos cinereus</i>	Koala	V	V	Occurs from coast to inland slopes and plains. Restricted to areas of preferred feed trees in eucalypt woodlands and forests. Home range varies depending on habitat quality, from < 2 to several hundred hectares.	61 records within 10km (OEH 2015a) and predicted to occur within 10km (DotE 2015)	Likely. Preferred feed trees identified at the site. Further surveys recommended.
<i>Pseudomys novaehollandiae</i>	New Holland Mouse		V	Occurs in disjunct, coastal populations from Tasmania to Queensland. In NSW inhabits a variety of coastal habitats including heathland, woodland, dry sclerophyll forest with a dense shrub layer and vegetated sand dunes (Wilson and Bradtke 1999). Populations may recolonise/ increase in size in regenerating native vegetation after wildfire, clearing and sandmining. Presence strongly correlated with understorey vegetation density, and high floristic	Predicted to occur within 10km (DotE 2015)	Unlikely. Lack of suitable understorey vegetation at the site. Not previously recorded within the locality.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
				diversity in regenerating heath (Lock and Wilson 1999).		
<i>Pteropus poliocephalus</i>	Grey-headed Flying-fox	V	V	Roosts in camps within 20 km of a regular food source, typically in gullies, close to water and in vegetation with a dense canopy. Forages in subtropical and temperate rainforests, tall sclerophyll forests and woodlands, heaths, swamps and street trees, particularly in eucalypts, melaleucas and banksias. Highly mobile with movements largely determined by food availability (Eby and Law 2008). Will also forage in urban gardens and cultivated fruit crops.	8 records within 10km (OEH 2015a) and predicted to occur within 10km (DotE 2015)	Likely. Suitable foraging habitat identified as part of a wider foraging range. No suitable roosting habitat identified at the site.
<i>Saccolaimus flaviventris</i>	Yellow-bellied Sheathtail-bat	V	-	The Yellow-bellied Sheathtail-bat is a wide-ranging species found across northern and eastern Australia. In the most southerly part of its range - most of Victoria, south-western NSW and adjacent South Australia - it is a rare visitor in late summer and autumn. Forages in most habitats across its very wide range, with and without trees.	1 record within 10km (OEH 2015a)	Possible. May utilise the site as part of a wider ranging foraging resource.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
<i>Scoteanax rueppellii</i>	Greater Broad-nosed Bat	V	-	Occurs on the east coast and Great Dividing Range. Inhabits a variety of habitats from woodland to wet and dry sclerophyll forests and rainforest, also remnant paddock trees and timber-lined creeks, typically below 500m asl. Forages in relatively uncluttered areas, using natural or man-made openings in denser habitats. Usually roosts in tree hollows or fissures but also under exfoliating bark or in the roofs of old buildings. Females congregate in maternal roosts in suitable hollow trees (Hoye and Richards 2008, Churchill 2008).	6 records within 10km (OEH 2015a)	Likely. Potential suitable habitat identified at the site.
<i>Syconycteris australis</i>	Common Blossom-bat	V	-	Coastal areas of eastern Australia from Hawks Nest in NSW to Cape York peninsula in Queensland. In areas, the distribution extends inland to coastal foothills. Common Blossom-bats often roost in littoral rainforest and feed on nectar and pollen from flowers in adjacent heathland and paperbark swamps. They have also been recorded in a range of other vegetation communities, such as subtropical rainforest, wet sclerophyll forest and other coastal forests.	1 record within 10km (OEH 2015a)	Possible. Some potential foraging habitat provided by the Paperbark Swamp Forest however no rainforest/roosting habitat identified at the site.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
<i>Vespadelus troughtoni</i>	Eastern Cave Bat	V	-	The Eastern Cave Bat is found in a broad band on both sides of the Great Dividing Range from Cape York to Kempsey, with records from the New England Tablelands and the upper north coast of NSW. The western limit appears to be the Warrumbungle Range, and there is a single record from southern NSW, east of the ACT. A cave-roosting species that is usually found in dry open forest and woodland, near cliffs or rocky overhangs; has been recorded roosting in disused mine workings, occasionally in colonies of up to 500 individuals.	1 record within 10km (OEH 2015a)	Unlikely. Suitable roosting habitat not present at the site.
Frogs						
<i>Litoria aurea</i>	Green and Golden Bell Frog	E	V	Formerly occurred from Brunswick Heads to Victoria, but >80% populations now extinct. Inhabits marshes, natural and artificial freshwater to brackish wetlands, dams and in stream wetlands. Prefers sites containing cumbungi (<i>Typha</i> spp.) or spike rushes (<i>Eleocharis</i> spp.), which are unshaded and have a grassy area and/or rubble as shelter/refuge habitat nearby. <i>Gambusia holbrooki</i> is a key threat as they feed on green and Golden Bell Frog eggs and tadpoles.	5 records within 10km (OEH 2015a) and predicted to occur within 10km (DotE 2015)	Possible. Potential habitat provided by the Paperbark Swamp Forest. More likely to the east of the site associated with the SEPP 14 wetland.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
<i>Mixophyes balbus</i>	Stuttering Frog	E	V	Occurs along the east coast of Australia. Has undergone a massive range reduction particularly in the south of its range: within the Sydney Basin, White (2008a) located only 3 populations south of Sydney (Macquarie Pass and Mt Werong) and Daly et al. (2002, in White 2008a) found only 2 extant populations between Macquarie Pass and Victoria. Inhabits rainforest and wet, tall, open forest. Shelter in deep leaf litter and thick understorey vegetation on the forest floor. Feeds on insects and smaller frogs, breeding in streams during summer after heavy rain. The species does not occur in areas where the riparian vegetation has been disturbed or where there have been significant upstream human impacts (Mahony et al 1997).	Predicted to occur within 10km (DotE 2015)	Unlikely. No suitable habitat present at the site.
<i>Mixophyes iteratus</i>	Giant Barred Frog	E	E	Occurs on the coast and ranges from south-eastern QLD to the Hawkesbury River in NSW, particularly in Coffs Harbour - Dorrigo area. Forage and live amongst deep, damp leaf litter in rainforest, moist eucalypt forest and nearby dry eucalypt forest. Breed in shallow, flowing rocky streams. Within Sydney Basin, confined to small populations in tall, wet forest in the Watagan Mountains north of the Hawkesbury and the lower Blue Mountains	Predicted to occur within 10km (DotE 2015)	Possible. No suitable habitat present at the site.

Scientific name	Common name	TSC Act status	EPBC Act status	Habitat association	Nature of record	Likelihood of occurrence in subject site
				(White 2008b).		
Reptiles						
<i>Coeranoscincus reticulatus</i>	Three-toed Snake-tooth Skink	V	V	The Three-toed Snake-tooth Skink occurs on the coast and ranges from the Macleay valley in NSW to south-eastern Queensland. It is very uncommon south of Grafton. Inhabits rainforest and occasionally moist eucalypt forest, on loamy or sandy soils.	Predicted to occur within 10km (DotE 2015)	Unlikely. Suitable habitat not present at the site due to disturbed understorey.

Notes:

The codes used in this table are: CE – Critically Endangered; E – Endangered; V – Vulnerable; EP – Endangered Population; CEEC – Critically Endangered Ecological Community; EEC – Endangered Ecological Community.

GHD

PO Box 2875 Port Macquarie NSW 2444
T: (02) 6586 8700 F: (02) 6586 8701 E: pqqmail@ghd.com.au

© GHD 2015

This document is and shall remain the property of GHD. The document may only be used for the purpose for which it was commissioned and in accordance with the Terms of Engagement for the commission. Unauthorised use of this document in any form whatsoever is prohibited.

G:\22\17672\WP\3507.docx

Document Status

Rev No.	Author	Reviewer		Approved for Issue		
		Name	Signature	Name	Signature	Date
0	A. Ayres	D. Williams	<i>D. Williams</i>	S. Lawer	<i>S. Lawer</i>	05/05/2015
1.	D Williams	D. Williams	<i>D. Williams</i>	S. Lawer	<i>S. Lawer</i>	06/10/2015
2.	D Williams	D. Williams	<i>D. Williams</i>	S. Lawer	<i>S. Lawer</i>	01/04/2016
3.	J Sharp	D. Williams	<i>D. Williams</i>	S. Lawer	<i>S. Lawer</i>	30/08/2016
4.	J Sharp	D. Williams	<i>D. Williams</i>	S. Lawer	<i>S. Lawer</i>	05/10/2016

www.ghd.com



Appendix C - Previous reports

Survey of Proposed Development


on

Lots 1, 2 & 3 - DP794159

**Parish of Beranghi,
Dulconghi, Crescent Head Road**

prepared by:

Neville Cohen & Dave Fernando



P.O. Box 540
Kempsey, N.S.W. 2440
Phone: (065) 62 8688
Fax: (065) 63 1293

KEMPSEY LOCAL ABORIGINAL LAND COUNCIL

17th September, 1996

Mr Robert Dennis
Belgrave Street,
KEMPSEY NSW 2440


INVOICE

Re: Archaeological Survey on Lots 1,2 & 3 D.P. 794159
Parish of Beranghi, Cresnet Head.

Survey Work	-	2 x 17hrs x \$75 per hr	=	\$2,550
Report	-			250
Community	-			
Consultation	-			650
Reserch	-			
Travel	-			
Other Costs	-			<u>100</u>
Total				<u>\$3,550</u>

Yours Faithfully

Neville Cohen
Culture & Heritage Officer
KEMPSEY LALC



P.O. Box 540
Kempsey, N.S.W. 2440
Phone: (065) 62 8688
Fax: (065) 63 1293

KEMPSEY LOCAL ABORIGINAL LAND COUNCIL

16/9/96

Robert Dennis
7/14 Belgrave Street
KEMPSEY, NSW 2440

Re: INSPECTION OF LOTS 1,2,&3 DP 794159, PARISH OF
BERANGHI, DULCONGHI HEIGHTS, CRESCENT HEAD.

Dear Robert,

KEMPSEY L.A.L.C. representatives, Neville Cohen and
David Fernando had conducted a thorough site inspection
of the above property.

On the 12th, 13th, & 15th of September 1996. both
walked the property, in total we spent 17 hours on foot
searching for Aboriginal relics, which was to no avail.

According to Community Consultation with Aboriginal
elders of the Macleay Valley, there was no evidence of
past Aboriginal significance or occupation. However each
of the elders we spoke to did mention that their
Ancestors were most likely to have occupied the area
before their time.

One of the elders Mr George Gray said that he and fellow
Aborigines had worked on the property cutting timber for
railway sleepers and fence posts and during that time he
also stated that the land was used intensively for
farming. And due to present day grazing by cattle, it
was difficult to determine whether there was Aboriginal
occupation of the past.

Therefore, on behalf of the KEMPSEY L.A.L.C. we
recommend that the proposed development on lots 1,2,&3
DP 794159 PARISH OF BERANGHI, DULCONGHI. CRESCENT HEAD
be allowed to go ahead.

On the proviso that a representative of the KEMPSEY
LOCAL ABORIGINAL LAND COUNCIL be present when subsurface
excavation begins to identify all Aboriginal relics
that may appear.

As a result of evidence appearing from below the
surface, an Anthropological survey of the property may
be required.

Yours faithfully

Neville Cohen
Senior Site Officer

FACSIMILE MESSAGE

To: Neelke Cohen Fax No.: 065 624 223From: Dennie HoustonDate: _____ Time: 3:30 No. of pages following: 6Subject: Site card info.NORTHERN
ZONEGIO House
24 Moonee Street
Coffs Harbour 2450
Tel: (066) 515 946
Fax: (066) 516 187

Comments:

The NPWS would appreciate an update of the site card reflecting any new information. i.e. Absence or presence of site & coordinates.

I very sorry about the delay.

Kind regards

Dennie

NSW
NATIONAL
PARKS AND
WILDLIFE
SERVICE



27 August, 1996

Robert Dennis
7/14 Belgrave Street
KEMPSEY NSW 2440

**NSW
NATIONAL
PARKS AND
WILDLIFE
SERVICE**

Our reference: 96/701/drh/1480
Your reference:

Dear Sir

NPWS SITE INSPECTION OF LOTS 1, 2, 3 DP 794159 CRESCENT HEAD

The National Parks and Wildlife Service (NPWS) makes reference to a site inspection undertaken at the above property conducted at your request. The intent of the inspection was to verify the absence or presence of NPWS Aboriginal site No. 30-3-37 which is listed on the NPWS Aboriginal Sites Register as located in the vicinity of lots 1, 2, & 3 Crescent Head.

On the 14 August 1996 Denise Houston (archaeologist, Northern Zone), accompanied by Ray Kelly (Snr Aboriginal sites officer, Port Macquarie District Office) and Jeff Ball (part owner of the property) walked from the gate of the property to the base of Beranghi Hill following a drain line allowing the best possible visibility. Owing to poor visibility (pasture cover), time constraints and the size of the property, only a small area of land was inspected for Aboriginal relics.

Past landuse, including intensive farming and present grazing by cattle, has resulted in substantial ground disturbance rendering the identification of evidence of past Aboriginal occupation difficult. In addition, Ray Kelly has stated he has no knowledge of any Aboriginal sites occurring directly on lots 1, 2 & 3 in Crescent Head. No Aboriginal relics were detected during the site inspection.

On the basis of the site inspection, NPWS recommends that monitoring of the initial subsurface excavation undertaken for development works be conducted by a representative of the Kempsey Local Aboriginal Land Council experienced in the identification of Aboriginal relics. This will allow the identification of any bone, shell or stone, not natural to the context.

Further investigations, including an anthropological study of the property, may be required to eliminate the possibility of potential impact upon Aboriginal sites which may occur on the property.


Northern Zone
GIO House
24 Moonee Street
Coffs Harbour NSW
Australia
PO Box 914
Coffs Harbour 2450
Fax: (066) 516 187
Tel: (066) 515 946

Head Office
43 Bridge Street
Hurstville NSW
Australia
PO Box 1967
Hurstville 2220
Fax: (02) 585 6555
Tel: (02) 585 6444

The developer should be aware that all Aboriginal sites and relics, recorded and as yet unrecorded, are protected under the *National Parks and Wildlife Act 1974*. It is an offence to knowingly damage, deface or destroy Aboriginal sites without the prior permission of the Director-General of the NPWS.

Further enquires with regard to this matter should be addressed to Denise Houston at this office on (066) 598240

Yours faithfully

A handwritten signature in dark ink, appearing to read 'S. Nally'.

SIMON NALLY
Manager Environmental Planning

for DIRECTOR-GENERAL

cc. Kempsey Shire Council

THE ABORIGINALS OF THE LOWER MACLEAY VALLEY

30-3-60

The stories contained in the following chapters were related to Mr Len Bull, of Crescent Head, New South Wales, by a full blood Aboriginal of the Macleay area named Mr Bob Smith. Bob Smith and Len Bull worked together for many years on the Macleay Shire Council, and, in the words of Len Bull "he told me the years when he boiled the billy". Len in turn passed the stories on to me.

THE BACKGROUND OF BOB SMITH

Bob Smith, as stated above, was a full blood aboriginal who was born and raised in the Macleay Valley. His parents were tribal aboriginals. He passed away approximately twelve years ago and was estimated to be then in his mid seventies. I have reason to believe from what he told Len Bull that a great deal of the history and law of the Macleay aboriginals was passed on to him by his parents. He also had a wide vocabulary in the native tongue, and the local native tongue, and some of the words and their meanings - which were told to Len Bull - are attached. I have no other source to verify the authenticity of these stories. However, whilst there may be omissions and exaggerations, I believe the basic stories to be true, for reasons that I will elaborate as I relate each story.

THE STORY OF THE BIG FIGHT

The time at which this incident occurred is unknown. According to Bob Smith, at one time the coastal tribe living around Crescent Head was almost wiped out. The tribe was apparently food-gathering in an area south of ~~Crescent Head~~ just north of Macleay Head and. The beach in this area is abundant in pippies and behind the beach is a long fresh water lagoon abundant in wild fowl and perch.

Whether by accident or prior planning, the local tribe was caught between a war party from the tribe living in the Nambeeca area which had moved south, and a war party which had moved north from the Hastings area. Strategically this would have been an ideal place for such an ambush. The defending tribe would have been caught between hostile aborigines to the north and south, but could not move inland from the beach front because of the long fresh water lagoon behind the sand hills.

In the ensuing unequal fight the local tribe was almost completely annihilated. Some verification for this story comes from the fact that Len Bull collected in this area (locally known as Cook's Crossing) a kerosene tin full of smashed jaw and skull bones.

THE STORY OF THE MASS DEATHS AT CRESCENT HEAD

This incident would have occurred almost certainly about the 1830's. It appears that a tribe from the far upper Macleay, or even the edge of the Tablelands, contracted measles or chicken pox from the first white settlers. Having no natural resistance, the disease ran rampant through the tribe. In an endeavour to leave the area of the disease, and to escape the fever associated with it, they walked down to the coast at Crescent Head and swam in the sea to cool their bodies. Here they died in large numbers, and were buried on what is now Crescent Head. The excavations on the reserve in the past years for toilet and shower facilities have revealed the bones of numerous aboriginals.

This last statement:- who has found the bones, and who has put the toilets/showers facilities - Maybe a statement from the specific

hungry Head and Crescent Head in littered with middens. I remember
examined a midden at Macquarie Crossing after a heavy storm had
the top of a sand hill. A number of hand axes, cleavers, and small
rough points were found. Also found were the brass handles of an old
iron pot, a 1903 three-piece set for 1921 pens, all together as though
they had been dropped at once. They were either dropped by a white
fishing there since 1921, or dropped by an aboriginal using the site
late as 1921. My enquiries among the residents living in the area indicate
that as late as the 1930's family groups of Aborigines (mostly from the
largely distributed) still roamed the area fishing, pig gathering,
working, and living in makeshift camps at Crescent Head, Port Macquarie,
Head and in the bush along the beach.

DANCING RING - RICHARDSON'S HILL

The Dancing Ring at Richardson's Hill has been previously discussed.

CRESCENT HILL RESERVE

During September 1975, sewer lines were laid throughout the Crescent
reserve at Crescent Head to the various antiquities blocks. At the time,
I examined trenches all over the reserve. At a depth of about eight
inches are the remains of old fires and shell fish which had been cooked
in the fires. A number of scrapers, cleavers and hand axes were found
in the earth dug from the trenches. In many areas of the reserve the
kitchen sites are visible.

RACECOURSE HEADLAND

On Racecourse Headland, on the southern side in a grove of brown
pine, are the remains of a campsite. The area features a large mound
of ash about five feet in diameter and about eight feet thick. Littered
around the area are the shells of shellfish collected from the rocks.
Near the fire site is an excellent grinding stone about eighteen inches
by ten inches, heavily concaved on both sides. Throughout this grove of
pine can be found used hand axes.
source material for the axes to be Kempsey mudstone, and are all constructed
by cracking the face of small round water-worn rocks.

On Racecourse Headland there is also a dancing ring that has been
dissected by a road. 20-3-41
21-3-40

BIG HILL HEADLAND

I know of no sites on Big Hill Headland, which is the next headland
south of Racecourse. However, as a boy my father remembers
traps constructed of rock were visible on the northern side of the headland.
These no longer exist.

POINT PLOMER

A large workshop exists on the southern headland of Point Plomer
facing towards Port Macquarie. This site has been well documented by
Frederick McCarthy and others. 30-3-60

ABORIGINAL SITES IN THE MARIA RIVER AREA

A very large oyster midden exists at a point approximately eight
miles down the Maria River road on a small side road on a property known
known as "Never-tire". A dig has been carried out here by the University
of New England, which indicates the site is very old.

28/08 '96 15:40
-31/07 '96 11:35

066 516187
066 420619

NPWS NTHN ZONE
NAT PARKS NTHN. --- ZONE-COFFS HBR

007
007

THE BARANGH RIVER AT DOWNHILL

Don Ball has told me there is another existing ring situated at the property known as "Barangh" on the western side of the Maria River. He also states there are pippy mounds nearby which is interesting considering the present day coastline is over six miles away. Either the pippies were carried there from the present beach line, or collected from ancient shore lines much closer to the site. Nearby on Kaporina Hill is a possible initiation ground.

LOWER BELASKE RIVER

At an undetermined site (will check) there is a complex of mounds in a swamp. Each of these mounds has a depression in the top. These could possibly be burial sites?

Mr Johnson also told me of a site at Fulton Cove, near Williamsport. Which was being dredged in April, 1975 Mr Johnson collected large quantities of stone material which he gave to Don Byall and Isabel McBryde. He thinks that some material may be still in the spoil heap at the site.


28/08 '96 15:41
31/07 '96 11:36

066 516187
066 420619

NPWS NTHN ZONE
NAT PARKS NTHN.

ZONE-COFFS HDR

009
009



ACTUAL SIZE.
15cm.

This stone artefact was collected by Len Bull in the Crescent Head area. It was recovered from a section exposed by the digging of a well. Mr Bull noticed that the soil around the end of the artefact that had presumably been buried was darkly discoloured. This Mr Johnson believed to represent the decay of the haft. Mr Johnson also described the artefact as being bifacially flaked.

28/08 '96 15:37
31/07 '98 11:33

066 516187
066 420619

NPWS NTHN ZONE
NAT PARKS NTHN. →→ ZONE-COFFS HBR

003
003

Associated with

rock engravings
stone arrangements
campsite

rock paintings
axe grooves
other relics

carved trees
quarry

Photo record by

Where deposited

Scale chart by

Where deposited

History M.R.E.S.

Seen by Ron Barrie as a boy (check with Mrs. Blackwell). Also said to have been seen in the early years of 20th.C. by Don (Ron)? Clarke.

Aboriginal meaning and name

Published reference

Remarks

28/08 '96 15:36
31/07 '96 11:32

0066 516187
0066 420618

NPWS NTHN ZONE
NAT PARKS NTHN. --- ZONE-COFFS HBR

0002
0002

30-3-37

Locality

CEREMONIAL GROUND
STONE ARRANGEMENT

CRESSENT HEAD

Military map/other reference Hastings 1:250,000.SM/56-14 Kempsey 1:63,560.014596
6018.1399

Pastoral or other property, park

A.M.G. 494-550

Description of site Stone arrangement and
Bora on nearby flat behind Goulbourne Howe's house about 3 miles west
of Crescent Head.

see report with
30-3-60

Length of site

Width

State of preservation


Nearest water supply

Vegetation

☎066 516187
☎066 420819

NPWS NTHN ZONE
NAT PARKS NTHN. +--+ ZONE-COFFS HBE

008
008



Michael Carrington Westaway
Department of Prehistoric and Historical Archaeology
The University of Sydney
Sydney, 2006.

Mr Campbell Petterson
C / Kempsey Shire Council
West Kempsey, 2440.
Facsimile 065 62 8902.

Dear Mr Petterson,

I conducted a brief field survey in early June of this year at the base of Beranghi Mountain in order to determine whether or not material evidence for prehistoric Aboriginal activity was present. The primary reason for this field work was for a Master of Arts proposal relating to hunter and gatherer subsistence and adaptation to the coast of the Macleay. Beranghi represents only one of a number of sites that I have visited for my initial data collection. Presented below are the results of the survey.

Aboriginal hunter and gatherers were active throughout the Macleay and would have utilised a range of environments in the area. A nomadic form of subsistence is generally difficult to identify in the archaeological record. Unless a site was used on a number of occasions traces can be very difficult to identify. Examples of sites of significance include such things as the Point Plomer fish trap, and the number of middens located in the dunes of Killick Beach. Ceremonial sites and sites of production (stone tool quarries) also represent an important element of Aboriginal material culture.

My survey involved the area where recent European activity was undertaken (such as cattle grazing and the activity of motor vehicles. Such disturbances to the surface of the soil often expose stone tools). Time did not permit a survey of the Mountain itself so I concentrated on those areas at the base. This involved walking along the main access road that follows the base of the hill. The geology of Beranghi is sedimentary which is unsuitable for the production of stone tools (as a general rule igneous and metamorphic rocks are utilised for stone tools such as blades and scrapers). No tools were located so further survey was conducted along the eastern side of the northern electric fence, and any area in the paddock where cattle

had disturbed the surface. Again no material that could be accredited to hunter and gather activity was identified.

There is little doubt that hunter and gatherers used the area, as well as the rest of Crescent Head. The general nature of a seasonal hunter and gatherer subsistence is that it encompasses a broad area. Indeed the coastal Macleay represented an area rich in resources. Ethnographic analogy and the material record (from sites such as the middens on Killick Beach) has demonstrated this.

Traditional Aboriginals possessed no laws of land ownership as we know it but they do have areas of significance that represent important aspects of their cultural beliefs. It is imperative that such sites are allowed to be located and protected for the benefit of Aboriginal identity and cultural preservation. The results of this limited survey (although by no means conclusive, as is any question in archaeology) have demonstrated that no material evidence that can be attributed to hunter and gatherer subsistence was identified on the base of Beranghi Mountain.

I would like to thank you Mr Petterson for granting me permission to conduct field work on your property as it has assisted me in formulating ideas for a possible research topic for 1995. If you require any further information please do not hesitate to contact me at the above address.

Yours sincerely,

Michael Carrington Westaway BA (ANU),
Grad.Dip.Ed (UNE).

19/9/94.



NSW
NATIONAL
PARKS AND
WILDLIFE
SERVICE

4 July, 1996

Kempsey Shire Council
P.O. Box 78
KEMPSEY NSW 2440

KSC RECEIVED	
- 5 JUL 1996	
FILE.....	S15-96-21
OFFICER.....	ASC
FOLIO.....	112558

Our reference: DRH:MC u\44 ASR 2109 1480
Your reference: **Attention: Tony Castle**

Dear Sir

**RE: NPWS ABORIGINAL SITES REGISTER SEARCH OF LOTS 1,2 & 3 IN
794159, PARISH OF BERANGHI, DULCONGHI HEIGHTS**

The National Parks and Wildlife Service (NPWS) makes reference to your enquiry dated 14/6/96 in relation to Aboriginal sites recorded at the above location.

As requested, a search was conducted of the NPWS Aboriginal sites register for the location of Aboriginal sites in the subject area. The register has located one site in the area and several sites occurring in the vicinity of the area indicated. Please find the details of the site location attached.

The following qualifications apply to the Aboriginal Sites Register:

- The database records only 'known' Aboriginal sites. Unknown sites may occur in areas which have not been subject to a systematic survey.
- Locational details are recorded as Australian Map Grid references. However, past experience indicates that the accuracy of these references depend on the skill of the recorder. Sites listed on the database have been recorded by people with a range of skill levels therefore, when a search of the register identifies sites in or near the area it is recommended that the site be accurately reallocated in the ground.

Should a proposal for a change of landuse be made which has the potential to impact on Aboriginal sites in this area, it would be in the interests of the proponent to make an assessment of the potential effects of the development on Aboriginal sites and to consult with the Kempsey Local Aboriginal Land Council as to their Aboriginal heritage interests on the area. Depending on the outcome of this assessment there may be a need to undertake a site specific archaeological investigation by an appropriately qualified person.

As you are aware, all Aboriginal sites and relics, recorded and as yet unrecorded, are protected under the National Parks and Wildlife Act 1974, and it is an offence to knowingly damage, deface or destroy Aboriginal sites without the prior permission of the Director-General of the NPWS.

Northern Zone
GIO House
24 Moonee Street
Coffs Harbour NSW
Australia
PO Box 914
Coffs Harbour 2450
Fax: (066) 516 187
Tel: (066) 515 946

Head Office
43 Bridge Street
Hurstville NSW
Australia
PO Box 1967
Hurstville 2220
Fax: (02) 585 6555
Tel: (02) 585 6444

Please address any further enquires with regard this matter to Denise Houston,
archaeologist, Northern Zone at this office on (066) 598240

Yours faithfully

M. Cameron

Matt Cameron
MANAGER, ENVIRONMENTAL PLANNING

for DIRECTOR-GENERAL

KEMPSEY LOCAL ABORIGINAL LAND COUNCIL
COMMUNITY CONSULTATION SURVEY

**SUBJECT: PROPOSAL TO SUBDIVIDE LOTS 1, 2 & 3 D.P.794159
PARISH OF BERANGHI, CRESCENT HEAD.
SEE ATTACHED MAP.**

Please answer by ticking either yes or no.

Do you have any knowledge of any Aboriginal cultural heritage matters associated with the subject land? (Location as shown on the attached plan.)

☒ No.

☐ Yes - Details No heritage matters associated
to his knowledge, he did state that
he use to work on the property

Do you have any knowledge of Aboriginal sites on the subject land?

☒ No.

☐ Yes - Details
.....
.....

Name: George Gray

Date: 10/9/96

Signature: George Gray

KEMPSEY LOCAL ABORIGINAL LAND COUNCIL
COMMUNITY CONSULTATION SURVEY

**SUBJECT: PROPOSAL TO SUBDIVIDE LOTS 1, 2 & 3 D.P.794159
PARISH OF BERANGHI, CRESCENT HEAD.
SEE ATTACHED MAP.**

Please answer by ticking either yes or no.

Do you have any knowledge of any Aboriginal cultural heritage matters associated with the subject land? (Location as shown on the attached plan.)

☒

No.

☐

Yes - Details

Same particulars as
Vince Smith

Do you have any knowledge of Aboriginal sites on the subject land?

☒

No.

☐

Yes - Details

Name: THOMAS MUMBLER

Date: 16/9/06

Signature: [Signature]

KEMPSEY LOCAL ABORIGINAL LAND COUNCIL
COMMUNITY CONSULTATION SURVEY

**SUBJECT: PROPOSAL TO SUBDIVIDE LOTS 1, 2 & 3 D.P.794159
PARISH OF BERANGHI, CRESCENT HEAD.
SEE ATTACHED MAP.**

Please answer by ticking either yes or no.

Do you have any knowledge of any Aboriginal cultural heritage matters associated with the subject land? (Location as shown on the attached plan.)

☒ No.

☐ Yes - Details *had no recollection of*
..... *any occupation at all.*
.....

Do you have any knowledge of Aboriginal sites on the subject land?

☒ No.

☐ Yes - Details
.....
.....

Name: *Kevin Smith*

Date: *16-9-96*

Signature: *16-9-96 KE Smith*

KEMPSEY LOCAL ABORIGINAL LAND COUNCIL
COMMUNITY CONSULTATION SURVEY

**SUBJECT: PROPOSAL TO SUBDIVIDE LOTS 1, 2 & 3 D.P.794159
PARISH OF BERANGHI, CRESCENT HEAD.
SEE ATTACHED MAP.**

Please answer by ticking either yes or no.

Do you have any knowledge of any Aboriginal cultural heritage matters associated with the subject land? (Location as shown on the attached plan.)

☒

No.

☐

Yes - Details

*No recollection of any
aboriginal significance of area*

Do you have any knowledge of Aboriginal sites on the subject land?

☒

No.

☐

Yes - Details

Name:

RON VALE

Date:

15/9/96

Signature:

Ron Vale

KEMPSEY LOCAL ABORIGINAL LAND COUNCIL
COMMUNITY CONSULTATION SURVEY

**SUBJECT: PROPOSAL TO SUBDIVIDE LOTS 1, 2 & 3 D.P.794159
PARISH OF BERANGHI, CRESCENT HEAD.
SEE ATTACHED MAP.**

Please answer by ticking either yes or no.

Do you have any knowledge of any Aboriginal cultural heritage matters associated with the subject land? (Location as shown on the attached plan.)

☒

No.

☐

Yes - Details

Vince spoke only of other areas surrounding the said property. eg. Maguiver Crossing, lefts Rd in regards to occupation.

Do you have any knowledge of Aboriginal sites on the subject land?

☒

No.

☐

Yes - Details

Name:


Vince Smith

Date:

15/9/06

Signature:

V. Smith



Campbell Petterson

Dulconghi Investments Pty Ltd

140 Neville Morton Drive

Crescent Head NSW 2440

Dear Campbell

Aboriginal Site inspection of the Dulconghi Heights Rezoning, Crescent Head.

Thank you for the opportunity to undertake the Aboriginal Sites Survey of the land of parts of Lot 3 DP 1164661 Dulconghi Heights, Crescent Head, NSW. A site inspection was undertaken by Graham Quinlan and Fred Kelly from Kempsey Local Aboriginal Land Council and Tim Hill from Everick Heritage Consultants on Friday 27 March 2015.

As a result of the site inspection one Aboriginal site was identified which consisted of two stone flakes- being a chert flake and a greywacke flake piece. The GPS coordinate for this site is (GDA 94) e0495466 n6551973 and photos are attached below of both artefacts. Based on the previous study by Kempsey LALC in 1996 and the knowledge of the area the Aboriginal site is likely to be of Low to Moderate significance however additional investigation would be required before making a definite statement on the sites significance. The site has not yet been recorded on the Aboriginal Heritage Information Management System (AHIM5).

The Due Diligence Code of Practice sets out the responsibilities of landowners to manage Aboriginal sites (Objects) in New South Wales. The Due Diligence Code identifies a number of landscape features where Aboriginal Objects are known to occur in New South Wales. These include ridge tops and ridge lines and any area within 200m of waters (including wetlands). At Crescent Head similar areas are known camping places for Aboriginal people and Aboriginal sites commonly occur on the edges of wetlands. It was also observed that across the ridgeline ground disturbance appears to be restricted to forestry and/ or agriculture. Whilst some recent disturbance from what appears to be the demolition of a house was noted, there was no evidence of large scale topsoil removal.

Based on the potential to harm Aboriginal Objects across the ridgecrest it is recommended that you undertake an Aboriginal Cultural Heritage Assessment prior to any additional ground disturbing works taking place on the ridge crest. However, based on the results of the site inspection Kempsey LALC see no significant objections to the proposal to rezone the land.

Please contact myself or Uncle Fred Kelly on 0429 568 577 should you wish to discuss this project further.

Sincerely



Fred Kelly

Deputy Chairperson, Kempsey Local Aboriginal Land Council

17/4/2015
8

Site Inspection Photos – Dulconghi, Crescent Head



Kempsey LALC (1996) *Survey of Proposed Development on Lots 1, 2 & 3 – DP 794159*

NSW NPWS (1996) *NPWS Site inspection of Lots 1, 2, 3 DP794159 Crescent Head.*

Kempsey LALC (2015) *Aboriginal Site Inspection of the Dulconghi Heights Rezoning, Crescent Head*

GHD

Coffs Harbour NSW 2450

T: (02) 6650 5600 F: (02) 6650 5601 E: cfsmail@ghd.com

© GHD 2015

This document is and shall remain the property of GHD. The document may only be used for the purpose for which it was commissioned and in accordance with the Terms of Engagement for the commission. Unauthorised use of this document in any form whatsoever is prohibited.

N:\AU\PortMacquarie\Projects\22\17672\WP\3468.docx

Document Status

Rev No.	Author	Reviewer		Approved for Issue		
		Name	Signature	Name	Signature	Date
0	A. Fletcher	D Williams	<i>D Williams</i>	S Lawer	<i>S Lawer</i>	04/05/2015
1	A Fletcher	D Williams	<i>D Williams</i>	S Lawer	<i>S Lawer</i>	3/09/2015
2	A Fletcher	D Williams	<i>D Williams</i>	S Lawer	<i>S Lawer</i>	06/10/2015
3	D Williams	D Williams	<i>D Williams</i>	S Lawer	<i>S Lawer</i>	01/04/2016
4	D Williams	D Williams	<i>D Williams</i>	S Lawer	<i>S Lawer</i>	30/08/2016
5	D Williams	D Williams	<i>D Williams</i>	S Lawer	<i>S Lawer</i>	21/09/2016
6	D Williams	D Williams	<i>D Williams</i>	S Lawer	<i>S Lawer</i>	05/10/2016

www.ghd.com

