**DEVELOPMENT WORKS UNDERTAKEN FOR:** 

# CAPPELLO DEVELOPMENT No.10

SUBDIVISION OF LOT 28, DP479 GOULBURN, NSW

# ISSUED FOR DEVELOPMENT APPLICATION

**NOVEMBER 2017** 




PO Box 310, Hall ACT 2618
02 6230 2823 • 0418 585 774
info@fraish.com.au • www.fraish.com.au



DRAWING INDEX						
DRAWING NUMBER	DRAWING TITLE					
C001	COVER SHEET					
C002	LAYOUT & INDEX					
C005	CIVIL NOTES & LEGEND					
LAYOUT						
C006	GENERAL ARRANGEMENT PLAN					
TYPICAL DETAILS						
C105	TYPICAL CROSS SECTIONS ROAD 1					
C106	TYPICAL CROSS SECTIONS ROAD 2					
C107	TYPICAL CROSS SECTIONS ROAD 3					
C108	TYPICAL CROSS SECTIONS ROAD 4					
C109	TYPICAL CROSS SECTIONS ROAD 5					
C110	TYPICAL CROSS SECTIONS ROAD 6					
C111	TYPICAL CROSS SECTIONS ROADS 7 & 8					
C112	TYPICAL CROSS SECTIONS ROAD 9					
TRAFFIC MANAGEMENT						
C201	TEMPORARY TRAFFIC CONTROL DEVICES					
<b>EROSION &amp; SEDIMENT CONTROL</b>						
C211	EROSION & SEDIMENT CONTROL PLAN					
C212	EROSION & SEDIMENT CONTROL DETAILS					
C213	EROSION & SEDIMENT CONTROL NOTES					
PAVEMENT						
C220	PAVEMENT PLAN					
C230	PAVEMENT MARKINGS & SIGNS					
STORMWATER						
C300	STORMWATER CATCHMENT PLAN					
C305	STORMWATER PLAN					
C310	RAIN GARDEN DETAILS					
WATER						
C320	WATER SUPPLY CONCEPT PLAN					
SEWER						
C330	SEWER CONCEPT PLAN					



REVISION DATE AMENDMENT / REVISION DESCRIPTION 14/11/17 ISSUED FOR DEVELOPMENT APPLICATION



AS SHOWN DA C002

# GENERAL

- ALL WORKS SHALL BE CARRIED OUT IN GENERAL DRAINAGE INSTALLATION NOTES ACCORDANCE WITH SNOWY MONARO REGIONAL COUNCIL AUSPEC #1 DESIGN & AUSPEC #2 CONSTRUCTION SPECIFICATION. AND STANDARD DRAWINGS
- ALL DRAWINGS SHOULD BE READ IN CONJUNCTION WITH THE RELEVANT SERVICES DRAWINGS & ALL OTHER DRAWINGS FROM OTHER CONSULTANTS.
- THE CONTRACTOR SHOULD REPORT ANY DISCREPANCIES ON THE DRAWINGS TO THE ENGINEER RESPONSIBLE FOR THE DESIGN.
- THE CONTRACTOR SHALL LOCATE AND LEVEL ALL EXISTING SERVICES PRIOR TO COMMENCING CONSTRUCTION AND PROTECT AND MAKE ARRANGEMENTS WITH THE RELEVANT AUTHORITY TO RELOCATE AND/OR ADJUST IF NECESSARY. INFORMATION GIVEN ON THE DRAWINGS IN RESPECT TO SERVICES IS FOR GUIDANCE ONLY AND IS NOT GUARANTEED COMPLETE NOR
- CONTRACTOR IS NOT TO ENTER UPON NOR DO ANY WORK WITHIN ADJACENT LANDS WITHOUT THE PERMISSION OF THE OWNER.
- SURPLUS EXCAVATED MATERIAL SHALL BE PLACED WHERE DIRECTED OR REMOVED FROM SITE.
- ALL NEW WORKS SHALL MAKE A SMOOTH JUNCTION WITH EXISTING.
- ALL DRAINAGE LINES THOUGH ADJACENT LOTS SHALL BE CONTAINED WITHIN EASEMENTS SUBSOIL DRAINAGE NOTATION CONFORMING TO COUNCIL'S STANDARDS.
- PRIOR TO COMMENCEMENT OF WORK, THE CONTRACTOR SHALL PROVIDE A TRAFFIC MANAGEMENT PLAN PREPARED BY AN ACCREDITED PERSON IN ACCORDANCE WITH RMS REQUIREMENTS, FOR ANY WORK ON OR ADJACENT TO PUBLIC ROADS, PLAN TO BE SUBMITTED TO COUNCIL & RMS AS APPLICABLE.
- ALL EXISTING SERVICES TO BE LOCATED AND LEVELLED BY THE CONTRACTOR PRIOR TO THE COMMENCEMENT OF WORK. ALL SERVICES AFFECTED BY THE NEW WORK TO BE ADJUSTED TO SUIT IN THE FIELD. TO THE SATISFACTION OF THE RELEVANT SERVICE AUTHORITY
- ALL CONSTRUCTION WORK IS TO BE CARRIED OUT INTER-ALLOTMENT DRAINAGE SO THAT AT ANY TIME ADJOINING PROPERTY OWNERS ARE NOT DEPRIVED OF AN ALL - WEATHER ACCESS OR SUBJECTED TO ADDITIONAL STORMWATER RUN-OFF DURING THE PERIOD OF CONSTRUCTION
- ALL DISTURBED SURFACES TO BE REINSTATED TO AS NEARLY AS POSSIBLE TO THE 2. PRE-CONSTRUCTED CONDITION.

# **SURVEY**

- FRAISH IS NOT RESPONSIBLE FOR THE ACCURACY 4. OF ANY SURVEY INFORMATION PROVIDED ON THIS DRAWING
- ALL LEVELS ARE TO A.H.D.
- ALL CHAINAGES AND LEVELS ARE IN METRES, AND DIMENSIONS IN MILLIMETRES.
- THE SURVEY INFORMATION ON THIS DRAWING TABLE DRAINS STABILISATION HAS BEEN PROVIDED BY P.J.SHAW & ASSOCIATES 1 PTY LTD CONSULTING SURVEYORS
- CONTRACTORS SHALL ARRANGE FOR THE WORKS TO BE SET OUT BY A REGISTERED SURVEYOR.

EVISION DATE AMENDMENT / REVISION DESCRIPTION

ISSUED FOR DEVELOPMENT APPLICATION

14/11/17

# DRAINAGE RETICULATION NOTES

- ENDS OF PIPES AND STUB CONNECTIONS TO BE SEALED WITH AN APPROVED SEALED DISC
- MILD STEEL 'STAR' PICKET 1200mm LONG WITH 300mm PAINTED GREEN, EXTENDED ABOVE GROUND 2. LEVEL TO BE PLACED AT EACH INTER-ALLOTMENT DRAINAGE CONNECTION POINT
- PROVIDE 90 DIAMETER STUB CONNECTION WHERE SHOWN
- GEOTEXTILE FABRIC TO BE PLACED UNDER RIP RAP SCOUR PROTECTION
- ALL BASES OF PITS TO BE BENCHED TO HALF PIPE DEPTH AND PROVIDE GALVANISED ANGLE SURROUNDINGS TO GRATE
- PROVIDE 1m WIDE JUTE MESH ANCHORED ALONG BASE OF SWALES AND SPRAY GRASS SWALE USING A SEED MIX CONSISTING OF:
- JAPANESE MILLET (75%)
- HULLED COUCH (6.25%) RED CLOVER (INOCULATED) (6.25%)
- WHITE CLOVER (INOCULATED) (6.25%)
- "ELKA" PERENNIAL RYE (6.25%)
- ALL PIPES SHALL BE RUBBER RING JOINTED (RRJ)
- ALL PIPE TRENCHES TO BE INSPECTED & APPROVED BY SITE SUPERINTENDENT & COUNCIL ENGINEER PRIOR TO PLACING OF PIPES & BACKFILLING. THIS 6. CONSTITUTES A HELD POINT

- SUBSOIL DRAINS TO KERBS SHALL BE 1000 TYPE 1 CLASS 400 SOCKED PIPE.
- 100Ø CLASS 'SH' SHALL BE USED WHERE SUBSOIL PIPES CROSS ROAD PAVEMENTS LAID AT MIN GRADE 1%, UNLESS SHOWN AS SLOTTED PIPES ON THE DRAWING
- GRADE SUBSOIL DRAINS AT MINIMUM AT 1% FROM OUTLET POINT UNLESS NOTED OTHERWISE ON THE DRAWINGS
- COMPACT 7mm CRUSHED TOCK FILTER MATERIAL TO ID=9% IN 250 TO 300mm DEEP LAYERS. THE PIPE SHALL BE 300mm DEEP

- INTER-ALLOTMENT DRAINAGE PIPES SHALL BE uPVC STORMWATER PIPE. INTER-ALLOTMENT DRAINAGE PIPES ARE TO BE LOCATED CENTRALLY IN IAD EASEMENT UNLESS OTHERWISE DIMENSIONED, MINIMUM COVER 600mm WITH A MINIMUM GRADE OF 1
- ALL INTER-ALLOTMENT DRAINAGE PITS TO BE MIN 600 x 600 IN SITU OR COUNCIL APPROVED PRE-CAST PITS.
- PITS TO BE FITTED WITH LOCKING CHAIN OR J BOLTS TO PREVENT GRATE REMOVAL.
- AREA AROUND PIT TO BE TURFED. MINIMUM 900mm RADIUS TURE TO BE MAINTAINED UNTIL ESTABLISHED
- ON CAST-INSITU INTER-ALLOTMENT PITS A 150mm STUB IS TO BE PROVIDED FOR ROOF WATER CONNECTION

- ALL TABLE DRAINS, SWALES, MITRES, BATTERS AND VERGESARE TO BE TOPSOILED AND SOWN WITH THE SEED MIX AS SHOWN IN THE EROSION AND SEDIMENT CONTROL PLAN AS SOON AS POSSIBLE AFTER COMPLETION
- TABLE DRAINS AND SWALES EXCEEDING 5% GRADE ARE TO BE STABILISED WITH JUTE MATTING AND BITUMEN IMMEDIATELY AFTER SOWING.
- WHERE DRAINS ARE ON GRADES IN EXCESS OF 10% THEY SHALL BE ARMOURED WITH ROCK, GENERALLY SIZED TO D/50 100mm UNDERLAID WITH BIDIM A14.
- SIMILAR TREATMENT IS TO BE PROVIDED TO ALL DRAINS, SWALES AND BATTERS IN PROPERTY ACCESS DRIVEWAYS
- RIPRAP SCOUR PROTECTION IS TO BE INSTALLED AT THE OUTLETS. TO ALL THE CULVERTS & TABLE DRAINS. CONSISTING OF D/50=150mm AND PLACED OVER BIDIM A14
- AREAS FOR PROTECTION ARE AS FOLLOWS:
- Ø300 & Ø375 PIPES = 1m WIDE X 2m LONG

# PAVEMENT NOTES

- ALL SUBGRADES TO BE PROOF ROLLED & APPROVED ROAD CROSSINGS BY SITE SUPERINTENDENT & COUNCIL ENGINEER PRIOR TO PLACING OF PAVEMENT LAYERS. THIS CONSTITUTES A HOLD POINT.
- SUB-BASE & BASECOURSE CAN BE CONSTRUCTED, OF APPROVED NGB & NGS IN LIEU OF DGS AND DSB. IN ACCORDANCE WITH AUSPEC #2 C242 FLEXIBLE PAVEMENTS
- WHERE REQUIRED BY SUPERVISING ENGINEER DESIGN CBR TO BE CONFIRMED ON SITE BY A MINIMUM OF FOUR DAY SOAKED CBR TESTS DURING THE BOXING OUT FOR THE PAVEMENT NO PAVEMENT MATERIALS ARE TO BE PLACED UNTIL THE DESIGN. CBR IS CONFIRMED AND THE SUBGRADE INSPECTED BY AN ENGINEER TO CONFIRM THE CONSISTENCY OF MATERIALS
- PRIOR TO THE PLACEMENT OF THE PRIMERSEAL AND AFTER THE REQUIRED DENSITY IS ACHIEVED, THE PAVEMENT IS TO BE ALLOWED TO DRY BACK TO APPROXIMATELY 60% TO 70% OPTIMUM MOISTURE CONTENT
- ALL PAVEMENTS TO BE PROOF ROLLED & APPROVED BY SITE SUPERINTENDENT & COUNCIL ENGINEER PRIOR TO PLACING OF PRIME, SEAL OR ASPHAULT. THIS CONSTITUTES A HOLD POINT
- COMPACTION TESTS ARE TO BE UNDERTAKEN FOR ALL PAVEMENT LAYERS INCLUDING SUBGRADE AT A RATES AS STATED IN AUSPEC #2 TO BE DETERMINED BY THE SUPERVISING ENGINEER AND THE RESULTS TO BE SUPPLIED TO THE ENGINEER PRIOR TO PLACEMENT OF THE NEXT PAVEMENT LAYER.

# RCP CONVENTIONAL INSTALLATIONS &

- SUPPLY & INSTALLATION OF DRAINAGE WORKS TO BE IN ACCORDANCE WITH THESE DRAWINGS, THE COUNCIL SPECIFICATION AUSPEC #2 AND THE CURRENT APPLICABLE AUSTRALIAN STANDARDS
- ALL PIPE TRENCHES TO BE INSPECTED & APPROVED BY SITE SUPERINTENDENT & COUNCIL ENGINEER PRIOR TO PLACING OF PIPES & BACKFILLING, THIS CONSTITUTES A HOLD POINT
- REDDING OF THE PIPELINES IS TO BE TYPE 'HS2' IN ACCORDANCE WITH THE STANDARDS AND AS FOLLOWS:
- BEDDING DEPTH UNDER THE PIPE TO BE 100mm BEDDING MATERIAL TO BE EXTENDED FROM THE TOP OF THE BEDDING ZONE UP TO 0.3 TIMES PIPE OUTSIDE DIAMETER. THIS REPRESENTS THE 'HAUNCH ZONE.'
- THE BEDDING & HAUNCH ZONE MATERIAL IS TO BE COMPACTED TO A MINIMUM RELATIVE COMPACTION OF 98% WITHIN ROAD RESERVES AND TRAFFICABLE AREAS AND 95% ELSEWHERE FOR COHESIVE MATERIAL OR A MINIMUM DENSITY INDEX OF 70% IN ACCORDANCE WITH THE STANDARDS FOR COHESIVENESS MATERIAL.
- COMPACTION TESTING SHALL BE CARRIED OUT BY AN APPROVED ORGANISATION WITH A NATA CERTIFIED LABORATORY FOR ALL DRAINAGE LINES LAID WHOLLY OR IN PART UNDER THE KERB & **GUTTER OR PAVEMENT.**
- BACKFILL SHALL BE PLACED & COMPACTED IN ACCORDANCE WITH THE SPECIFICATION. TESTING OF BACKFILL IS TO OCCUR AT THE SAME INTERVALS FOR THE BEDDING AND HAUNCH ZONES
- A MINIMUM OF 300mm CLEARANCE IS TO BE PROVIDED BETWEEN THE OUTSIDE OF THE PIPE BARREL AND THE TRENCH WALL.
- A Ø90 SUBSOIL DRAIN IS TO CONNECT INTO THE BASE OF EACH PIT WITHIN THE ROAD RESERVE & EXTEND 3.0m UPSTREAM OF THE PIT.
- ALL SERVICE CONNECTIONS SHALL BE Ø100 uPVC STORMWATER CLASSIFICATION TO AS1254 AT 1.0% MIN. GRADE UNLESS NOTED OTHERWISE.
- INSTALL TEMPORARY SEDIMENT BARRIERS TO INLET PITS, TO COUNCILS SPECIFICATIONS UNTIL SURROUNDING AREAS ARE PAVED OR GRASSED.CONTRACTOR IS TO VERIFY THE LEVEL AND ALIGNMENT OF ALL EXISTING SERVICES PRIOR TO COMMENCEMENT OF EXCAVATION FOR DRAINAGE
- STORMWATER PIT LOCATIONS & LEVELS MAY BE VARIED TO SUIT SITE CONDITIONS, AFTER CONSULTATION WITH THE ENGINEER.
- 10. ALL COURTYARD & LANDSCAPE PITS TO BE 450 SQ. UNLESS NOTED OTHERWISE. ALL DRIVEWAY & OSD PITS TO BE 600 SQ
- HAND EXCAVATE STORMWATER PIPES IN VICINITY OF TREE ROOTS
- FOOTPATH CROSSING LEVELS SHOWN ARE TO BE ADJUSTED TO FINAL COUNCIL ISSUED LEVELS.

# SEWER MAINS

- ALL SEWERS SHALL BE uPVC CLASS SH (<3m DEPTH) OR uPVC CLASS SEH (>3m DEPTH)
- ALL HOUSE CONNECTIONS SHALL BE 150mm uPVC ALL SEWERS AND HOUSE CONNECTIONS ARE TO BE LAID IN ACCORDANCE WITH STANDARD DRAWINGS
- AND SEWER SPECIFICATION. ALL MANHOLES SHALL BE AS PER STANDARD DRAWINGS. STEP IRONS SHALL BE INSTALLED IN ALL MANHOLES DEEPER THAN 1.2m.
- CONNECTION TO EXISTING LIVE SEWERAGE RETICULATION SHALL BE CARRIED OUT BY COUNCIL OR BY THE CONTRACTOR WITH COUNCILS WRITTEN APPROVAL AT THE CONTRACTOR'S EXPENSE
- END OF LINE MANHOLES SHALL BE AS PER STANDARD

# **STORMWATER**

- ROAD DRAINAGE PIPES SHALL BE RRJ REINFORCED CONCRETE CLASS 2. UNLESS OTHERWISE SHOWN.
- ROAD DRAINAGE PITS SHALL BE CONSTRUCTED AS PER PLANS, TYPE R SUMP
- INVERT LEVELS REFER TO THE CENTRE OF THE DRAINAGE STRUCTURE.
- ALL PIPES LAID UNDER TRAFFICABLE PAVEMENTS ARE TO BE BACK FILLED.
- ALL PIPES WITH LESS THAN 600mm COVER ARE TO BE CONCRETE ENCASED.
- ALL STRUCTURES TO HAVE A 1.22m SHORT LENGTH OF PIPE ON ALL INCOMING AND OUTGOING PIPES.
- 7. MINIMUM CONCRETE STRENGTH TO BE 32MPa-20

# **LEGEND**

PROPOSED SEWER MAIN PROPOSED WATER MAIN PROPOSED WATER SERVICE



PROPOSED WATER HYDRANT

PROPOSED END CAP

THRUST BLOCK EXISTING OVERHEAD ELECTRICITY LINE

O EP EXISTING ELECTRICAL POWER POLE

PROPOSED STORMWATER LINE

PROPOSED STORMWATER PIT

900x910 GRATED PIT

**6**) STORMWATER MANHOLE

600x600 IAD PIT

**EXISTING TREE** 

EXISTING TREE TO BE REMOVED

PROPOSED HEADWALL

SUBSOIL HIGH END RISER O HER

SUBSOIL INTERMEDIATE FLUSHING POINT O IFP SUBSOIL DRAINAGE

KERB & GUTTER TYPE KERB

EXISTING OVERHEAD POWER LINE

**BOULDER RIP RAP** \*\*\*\*

 $\boxtimes$ INTER-ALLOTMENT DRAINAGE PIT

PROPOSED SEWER MANHOLE

EXISTING HOUSING STRUCTURE TO BE RETAINED

EXISTING HOUSING STRUCTURE TO BE REMOVED

 $\frac{1}{2}$ DENOTES SEWER STRUCTURE

(<del>1</del>) DENOTES STORM WATER STRUCTURE

Δ SURVEY MARK EARTH BERM \_\_\_\_B\_\_\_

COMMON TRENCH

FRAISH Consulting Civil & Structural Engineers

CAPPELLO DEVELOPMENTS NO.10


ROJECT TITLE SUBDIVISION OF LOT 28, DP479


**CIVIL NOTES** & LEGEND


SHEET 1 **AS SHOWN** DA C005 Α

AJB

PO Box 310, Hall ACT 2618







F

REVISION DATE AMENDMENT / REVISION DESCRIPTION

A 15/11/17 ISSUED FOR DEVELOPMENT APPLICATION

LKK

DRAWN

LKK

DESIGNER

AJB

DO NOT SCALE OFF DRAWINGS VERIFY ALL DIMENSIONS ON SITE BEFORE COMMENCING WORK.

The concepts and information contained in this document are copyright of Fraish Consulting Pty Ltd. Use or copyright of most without market permission constitutes an infringement of copyright.



0m 1m 2m 3m SCALE: A1 1:40, A3 1:80 FRAISH Consulting
Civil & Structural Engineers

1/8 Victoria Street, Hall ACT
PO Box 310, Hall ACT 2618
02 6230 2823 • 0418 585 774
Info@fraish.com.au • www.fraish.com.au


CAPPELLO DEVELOPMENTS NO.10 SUBDIVISION OF LOT 28, DP479
MARY'S MOUNT ROAD, GOULBURN, NSW


TYPICAL SECTIONS
ROAD 2

SHEET 1

SHEET 1

AS SHOWN DA C106 REV
A C106





REVISION DATE AMENDMENT/REVISION DESCRIPTION

A 15/11/17 ISSUED FOR DEVELOPMENT APPLICATION


LKK DRAWN LKK


DESIGNER AJB

DO NOT SCALE DEF DRAWINGS VERIFY ALL DIMENSIONS ON SITE EFFORE COMMENCANG VORIFY.

The compright of Frieids Consultating in white of comprising in white document are copyright.

The compright of Frieids Consultating in white of comprising in white of white in part in white of in part i





REVISION DATE AMENDMENT / REVISION DESCRIPTION

A 15/11/17 ISSUED FOR DEVELOPMENT APPLICATION

LKK

DRAWN
LKK

DRAWN
LKK

DESIGNER

AJB

DO NT SCALE OF DRAWNGS VERIFY ALL DIMENSIONS ON STREET OF COUNEMAN SO VERIFY ALL DIMENSIONS ON TYPICAL SECTIONS

ROAD 5

SCALE: A1 1:40, A3 1:80

TYPICAL SECTIONS

ROAD 5

SCALE: A1 1:40, A3 1:80

SCALE: A1 1:40, A3 1:80

DESIGNER

FRAISH Consulting

Civil & Structural Engineers

NO.10

CAPPELLO

DEVELOPMENTS

NO.10

PROJECT ITILE

SUBDIVISION OF LOT 28, DP479

MARY'S MOUNT ROAD, GOULBURN, NSW

TYPICAL SECTIONS

ROAD 5

SHEET 1

SCALE

AS SHOWN
DA

C109

REV


C109

C109

C109

C109

C109



REVISION DATE AMENDMENT / REVISION DESCRIPTION DRAWN TITLE N/
A 15/11/17 ISSUED FOR DEVELOPMENT APPLICATION

LKK

DRAWN LK

DESIGNER A

DO NOT SCALE OFF DRAWINGS
SITE BEFORE COMMENCING W

The concepts and information control copyright of Fraish Constitutes an infringement of copy



0m 1m 2m 3m SCALE: A1 1:40, A3 1:80 FRAISH Consulting
Civil & Structural Engineers

1/8 Victoria Street, Hall ACT
PO Box 310, Hall ACT 2618
0,0 0,203,203,20 1 0,418 858 774
info@fraish.com.au · www.fraish.com.au

CAPPELLO DEVELOPMENTS NO.10 SUBDIVISION OF LOT 28, DP479
MARY'S MOUNT ROAD, GOULBURN, NSW

TYPICAL SECTIONS
ROAD 6


SHEET 1


DA

AS SHOWN

A A

C110





REVISION DATE AMENDMENT / REVISION DESCRIPTION

A 15/11/17 ISSUED FOR DEVELOPMENT APPLICATION

LKK

DRAWN

DESIGNER

AB

DON'S SCALE: A1 1:40, A3 1:80

DRAWN

DESIGNER

DON'S SCALE: A1 1:40, A3 1:80

DRAWN

DESIGNER

DON'S SCALE: A1 1:40, A3 1:80

DRAWN

DESIGNER

DRAWN

DESIGNER

DRAWN SWEDTHAL DIMENSIONS ON SITE BEFORE: COMMENT APPLICATION

TYPICAL SECTIONS

ROAD 9

SCALE: A1 1:40, A3 1:80

DRAWN

TYPICAL SECTIONS

ROAD 9

SHEET 1

SUBDIVISION OF LOT 28, DP479

MARY'S MOUNT ROAD, GOULBURN, NSW

TYPICAL SECTIONS

ROAD 9

SHEET 1

SCALE: A1 1:40, A3 1:80

DRAWNING No.

CLIENT

CAPPELLO

DEVELOPMENTS

NO.10

DEVELOPMENTS

NO.10

DEVELOPMENTS

NO.10

DRAWNING No.

CLIENT

CAPPELLO

DEVELOPMENTS

NO.10

DEVELOPMENTS

NO.10

DRAWNING No.

CLIENT

TYPICAL SECTIONS

ROAD 9

SHEET 1

SCALE: A1 1:40, A3 1:80

DRAWNING No.

CLI12

AS SHOWN

DA

C112

AS SHOWN

DA

C112

DRAWNING No.

CLIENT

TYPICAL SECTIONS

ROAD 9

SCALE: A1 1:40, A3 1:80

DRAWNING No.

CLIENT

TYPICAL SECTIONS

ROAD 9

SCALE: A1 1:40, A3 1:80


DRAWNING No.


CLI12


AS SHOWN


DA


C112











Seed and fertiliser sown at specified rate directly into topsoil or broadcast on surface and harrow into soil

Surface mulching can improve germination and establishment while protecting the soil surface

1 to 6 No < 5days Low 1 to 6 No < 5days Low 27 tonnes per hectare Moderate 0.05 0.05 0.05 No data 1 to 3 No < 5days Low 1.5 tonnes mulch + 300 litres binder per hectan 0.00 0.03 0.07 0.03 0.06 0.10 0.10 0.20 0.40 0.20 0.40 0.50 0.40 0.50 4 for any given technique, cost can vary greatly depending on geographic location, size or requirements. In addition, costs on any over time. Because of these factors, giving an possible, Newer-4 in a product is relatively prespective to pursuence of material close to will still be relatively inexpensive to pursuence and install close to Coconut fibre mesh Curied wood fibre

Jute matting (~350 gsm) 0.01 0.05 0.10 0.10 0.15 0.20 0.00 0.03 0.07 0.03 0.06 0.10 6 to 12 Yes < 5days Medium Moderate 6 to 12 Yes < 5days Medium Moderate Jute matting (~600 gsm) 0.00 0.03 0.07 0.03 0.06 0.10 Coconut fibre matting (~450 gsm) 6 to 12 Yes < 5days Medium Moderate Coconut fibre matting (~900 gsm) 0.00 0.03 0.07 0.03 0.06 0.10 Plastic fibres with netting > 12 Yes < 5days High 0.00 0.05 0.10 0.03 0.05 0.10 0.01 0.05 0.10 0.10 No data

> 12 Yes 5 - 15 days High High

0.05 0.05 0.10 0.10 No data


<0.01 <0.01 <0.01 <0.01 <0.01 <0.01

<0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.01 <0.

A-13

Table A3 Soil Stabilisation Control Matrix (adapted from various sources, including Meyer and Ports (1976), Israelson et al. (1980), Goldman et al. (1986), URS Greiner Woodward Clyde (1999) and the North American Green website)

Self-supportin



Wgter depth -Cut-off trench 800 mm min. depth backfilled with impermeable clay and compacted Construct a cut-off trench 500 mm deep and 1,200 mm wide along the centreline of the embankment extending to a point on the guily wall level with the riser crest. Maintain the trench free of water and recompact the materials with o

Spread the fill in 100 mm to 150 mm layers an following the SWMP.

Drive 1.5 metre long star pickets into ground at 2.5 metre intervals (max) at the french. Ensure any star pickets are fitted with safety cans.

SEDIMENT FENCE SD 6-8

DGB 20 roadbase Geofabric may be a woven or needle-p product with a minimum CBR burst strength (AS3706.4-90) of 2500 STABILISED SITE ACCESS

SEEDBED PREPARATION

Rip to a depth of 300 mm where a compacted layer occurs

THIS DRAWING TO BE READ IN CONJUNCTION WITH THE SOIL AND WATER MANAGEMENT PLAN REPORT

EVISION DATE AMENDMENT/REVISION DESCRIPTION 14/11/17 ISSUED FOR DEVELOPMENT APPLICATION



NOT TO SCALE

FRAISH Consulting Civil & Structural Engineers 1/8 Victoria Street, Hall ACT PO Box 310, Hall ACT 2618

SD 7.1

CAPPELLO DEVELOPMENTS NO.10

SUBDIVISION OF LOT 28, DP479 MARY'S MOUNT ROAD, GOULBURN, NSW SEDIMENT & **EROSION CONTROL NOTES** 

SHEET 1

AS SHOWN Α DA C212

- ALL WORK MUST COMPLY WITH ENVIRONMENT PROTECTION GUIDELINES FOR CONSTRUCTION AND LAND DEVELOPMENT IN NSW.
- 2. ALL EROSION & SEDIMENTATION CONTROLS TO BE CONSTRUCTED IN ACCORDANCE WITH THE REQUIREMENTS OF THE BEST PARACTICE GUIDELINES CONTAINED WITHIN SOILS AND CONSTRUCTION VOL. 1 (LANDCOM 2004).
- 3. THE KEY PRINCIPLES OF THIS PLAN ARE TO :-
- INTEGRATE EROSION AND SEDIMENT CONTROL ISSUES INTO SITE AND CONSTRUCTION PLANNING MINIMISE THE EXTENT AND DURATION OF SOIL DISTURBANCE
- CONTROL WATER MOVEMENT AROUND AND THROUGH THE SITE
- MINIMISE SOIL EROSION
- PROMPTLY STABILISE DISTURBED AREAS
- MAXIMISE SEDIMENT RETENTION ON SITE
- MAINTAIN ALL ESC MEASURES IN PROPER WORKING ORDER AT ALL TIMES
- 4. ALL NEW CONSTRUCTION WORK MUST BE CONTAINED WITHIN THE SITE EXCEPT FOR APPROVED SERVICE CONNECTIONS AND ROADWORKS.
- 5. LIMIT ACCESS TO SITE DURING AND IMMEDIATELY AFTER WET WEATHER
  6. NO STORAGE OF CONSTRUCTION MATERIALS, PARKING OF VEHICLES NOR EQUIPMENT PERMITTED OUTSIDE OF BLOCK WITHOUT COUNCIL APPROVAL
- 7. NO SITE SHEDS, STORAGE SHEDS, SITE AMENITIES TO BE ERECTED OUTSIDE OF BLOCK WITHOUT COUNCIL APPROVAL
- 8. ALL SERVICE TRENCHES TO BE BACK FILLED WITHIN 24HOURS OF INSPECTION
- 9. EXCESS SOIL IS TO BE DISPOSE AT A SUPERINTENDENT APPROVED LOCATION
- 10. THE CONTRACTOR TO CONTACT THE SUPERINTENDENT TO ARRANGE A SITE INSPECTION AND ENDORSEMENT OF SEDIMENT AND EROSION CONTROL MEASURES PRIOR TO WORKS COMMENCING.
- 11. THE CONTRACTOR TO CONTACT THE SUPERINTENDENT TO DISCUSS ANY PROPOSED MAJOR CHANGES TO SEDIMENT AND EROSION CONTROLS ON SITE PRIOR TO IMPLEMENTING THE CHANGES.
- 12. THE CONTRACTOR TO ENSURE CONTRACTORS ACCESS AND EXIT THE SITE USING ONLY APPROVED STABILISED ACCESS/EXIT POINTS AS DETAILED ON ENDORSED SEDIMENT AND EROSION CONTROL PLANS.
- 13. WHERE UNDERGROUND STORMWATER DRAINAGE IS INSTALLED TO ADJACENT ROADWORKS, PROVIDE INLET FILTER IN ACCORDANCE WITH DETAIL ON EROSION & SEDIMENT CONTROL DETAILS DRAWING

- STABILISED SITE ENTRANCE

  1. STABILISED SITE ENTRANCE TO BE CONSTRUCTED AT THE LOCATION(S) INDICATED ON THE PLANS.

  1. STABILISED SITE ENTRANCE TO BE CONSTRUCTED AT THE LOCATION(S) INDICATED ON THE PLANS. STABILISED SITE ENTRANCE TO BE CONSTRUCTED IN ACCORDANCE WITH DETAIL ON EROSION & SEDIMENT CONTROL DETAILS DRAWING
- AT THE LOCATION OF THE STABILISED SITE ENTRANCE FIRST STRIP THE TOPSOIL, LEVEL THE AREA AND COMPACT THE SUBGRADE
- COVER THE AREA WITH NEEDLE-PUNCHED GEOTEXTILE.
- CONSTRUCT A 200MM THICK PAD OVER THE GEOTEXTILE USING COARSE AGGREGATE MIN SIZE 30MM
- ENSURE THAT THE STABILISED SITE ENTRANCE IS AT LEAST 15M LONG OR TO THE BUILDING ALIGNMENT AND AT LEAST 3M WIDE
- WHERE A SEDIMENT FENCE JOINS ONTO THE STABILISED ACCESS, CONSTRUCT A HUMP IN THE STABILISED ACCESS TO DIVERT WATER TO THE SEDIMENT FENCE.
- REGULARILY MAINTAIN THE STABILISED SITE ENTRANCE BY REPLACING AGGREGATE IF INNUNDATED WITH SILT.

- UNDERTAKE PROGRESSIVE STABILISATION OF DISTURBED GROUND SURFACES AS THEY ARE COMPLETED RATHER THAN AT THE END OF THE WORKS PROGRAM (REFER TO TABLE 1)
- ENSURE THAT DISTURBED LANDS FOR EACH STAGE ARE STABILISED APPROPRIATELY BEFORE COMMENCING WORK ON THE FOLLOWING STAGE
- FINAL STABILISATION IS TO ACHIEVE THE C-FACTORS OUTLINED IN TABLE 1
- BATTERS SHOULD BE STABILISED TO BRING C-FACTORS DOWN TO 0.1 WITHIN 10 WORKING DAYS OF FINAL FORMATION
- STABILISATION OF BATTERS CAN BE ACHIEVED BY PLACING TOPSOIL OVER THEM WITH LOCALLY SOURCED NATIVE MULCH PLACED OVER THE SOIL, OR ALTERNATIVELY, THEY CAN BE HYDROMULCHED (OR EQUIVALENT)
- APPROPRIATE SEEDBED PREPARATION SHOULD BE CARRIED OUT WHEN STABILISING LANDS DIVERSION DRAINS AND TABLE DRAINS ARE TO BE STABILISED AS INDICATED IN TABLES 1 & 3
- STOCKPILES ARE TO BE STABILISED AS PER THE REQUIREMENTS OF TABLE 1
- SEDIMENT DAM AND CULVERT OUTLETS ARE TO BE STABILISED IN ACCORDANCE WITH TABLE 1 AND ENERGY DISSIPATERS ARE TO BE PROVIDED
- STABILISATION MEASURES AND PRODUCTS SHOULD BE IN ACCORDANCE WITH TABLES A1 AND A3
  AS SURFACES ARE STABILISED AND PERMANENT DRAINAGE MEASURES ARE INSTALLED, TEMPORARY WATER
- MANAGEMENT STRUCTURES CAN BE REMOVED (EG. DIVERSION DRAINS)

- SEDIMENT BASIN SIZE AND DETAILS ARE SHOWN ON RELEVANT DRAWINGS
- THE SEDIMENT BASIN IS TO BE BUILT TO INCORPORATE A PRIMARY OUTLET (WEIR OVERFLOW) SIZED TO HAVE A CAPACITY TO PASS THE 100 YEAR PEAK FLOW. THIS MUST BE MINIMUM 3m IN BASE WIDTH BY 0.3m IN DEPTH
- ENERGY DISSIPATERS ARE TO BE CONSTRUCTED ON THE OUTLETS OF THE WEIR OVERFLOWS. CONSTRUCT OUT OF ROCK RIP-RAP
- SECURITY FENCING AND WATER SAFETY CONTROL MEASURES MUST BE IMPLEMENTED AROUND ALL
- ANY RELEASE OF WATER FROM THE SEDIMENT BASIN UP TO THE DESIGN RAINFALL DEPTH (18mm IN 5 DAYS) WILL REQUIRE FLOCCULATION TO ACHIEVE ADEQUATE SETTLING OF DISPERSIBLE FINE MATERIAL (REFER TO FLOCCULATION NOTES FOR MORE DETAILS) HOWEVER IF THE WATER IS GOING TO BE USED WITHIN THE CONSTRUCTION SITE FOR DUST-SUPPRESSION PURPOSES AND WILL DRAIN BACK INTO THE SEDIMENT CAPTURE SYSTEM IT WILL NOT REQUIRE FLOCCULATION
- IF WATER IS PUMPED INTO A TANKER TRUCK TO USE FOR DUST SUPPRESSION AT A LATER STAGE. IT CANNOT
- BE DISCHARGED FROM THE TANKER INTO A CREEK/DAM WITHOUT FIRST BEING FLOCCULATED SEDIMENT BASIN MUST BE EFFECTIVELY FLOCCULATED, SETTLED AND DISCHARGED WITHIN 5 DAYS OR LESS FOLLOWING A RAINFALL EVENT
- SEDIMENT BASIN SHOULD INCORPORATE A "FULL OF SEDIMENT" MARKER TO SHOW WHEN THE SEDIMENT STORAGE CAPACITY HAS BEEN REACHED AND SEDIMENT REMOVAL IS REQUIRED (REFER TO TABLE 4)

# FLOCCULATION OF SEDIMENT BASIN

- FLOCCULATION IS TO BE ACHIEVED BY USING GYPSUM AT A RATE OF APPROXIMATELY 40kg/100m³ OF STORMWATER TO ACHIEVE 50mg/l OR LESS OF SUSPENDED SEDIMENT. OTHER FLOCCULANTS ARE PERMISSIBI E
- IT IS ESSENTIAL THAT THE FLOCCULATING AGENT IS SPREAD EVENLY OVER THE ENTIRE POND SURFACE FOR PROPER TREATMENT OF WATER
- FLOCCULATION MUST OCCUR WHENEVER THE AREA OF A STAGE IS LESS THAN 70% STABILISED
- ONCE FLOCCULATED THE TREATED WATER WILL BE RELEASED TO THE WETLAND

- ENSURE SLOPE LENGTHS ARE MAINTAINED AT 80m ACROSS ALL DISTURBED LANDS DURING ANY RAINFALL
- 2. DIVERSION BUNDS/DRAINS, LOW FLOW EARTH BANKS OR SANDBAGS/EQUIVALENT SHOULD BE INSTALLED PRIOR TO ANY RAINFALL EVENT TO ACHIEVE THIS

THIS DRAWING TO BE READ IN

CONJUNCTION WITH THE SOIL AND

WATER MANAGEMENT PLAN REPORT

- TOPSOIL STOCKPILES TO BE CONSTRUCTED AT THE LOCATION(S) INDICATED ON THE PLANS.
- TOPSOIL STOCKPILES TO BE CONSTRUCTED IN ACCORDANCE WITH DETAIL ON EROSION & SEDIMENT CONTROL
- PLACE STOCKPILES MORE THAN 2M (PREFERABLY 5M) FROM EXISTING VEGETATION. CONCENTRATED WATERFLOWS, ROADS AND HAZARD AREAS
- STOCKPILES ARE NOT TO BE POSITIONED WITHIN A RIPARIAN ZONE (IE. WITHIN 40m OF THE DRAINAGE RESERVE/CREEK)
- CONSTRUCT ON THE CONTOUR AS LOW, FLAT, ELONGATED MOUNDS.
- BATTERS SHOULD BE NO STEEPER THAN 1:2.
  WHERE THERE IS SUFFICIENT AREA, TOPSOIL STOCKPILES SHALL BE LESS THAN 2M IN HEIGHT.
- WHERE TOPSOIL STOCKPILES ARE TO BE IN PLACE FOR MORE THAN 10 DAYS. STABILISE THEIR SURFACE AREA USING AN APPROVED METHOD. THIS SHOULD REDUCE THE C-FACTOR TO LESS THAN 0.10.
- CONSTRUCT EARTHBANKS ON THE UPSLOPE SIDE OF TOPSOIL STOCKPILES TO DIVERT WATER AROUND CONSTRUCT SEDIMENT FENCES AROUND THE DOWNSLOPE SIDE OF TOPSOIL STOCKPILES. PREFERRABLY 1 TO
- 2M FROM THE EDGE OF THE STOCKPILE. REGULARILY INSPECT AND MAINTAIN TOPSOIL STOCKPILE EROSION AFTER RAINFALL EVENTS.

- EARTHWORKS, DISPOSAL OF SPOIL & IMPORTING FILL

  1. PRIOR TO ANY WORKS COMMENCING INVOLVING EXPORT OF SPOIL GREATER THAN 100M³, THE FOLLOWING INFORMATION MUST BE PROVIDED TO THE SUPERINTENDENT:
- WHERE THE SPOIL WILL ORIGINATE FROM
- WHO IS DISPOSING OF THE SPOIL
- WHERE THE SPOIL WILL BE TAKEN
- THE AMOUNT OF SPOIL TO BE TAKEN AWAY
- MOVEMENT DATES AND CONTACT DETAILS DESCRIPTION OF THE TYPE OF SPOIL TAKEN AWAY
- DETAILS OF HOW RECORDS WILL BE KEPT TIME FRAME TO COMPLETE THE WORKS
- SPOIL MAY BE TAKEN TO AN APPROVED LANDFILL SITE WITHOUT APPROVAL
- THE SPOIL IS TO BE TAKEN TO AN AREA OTHER THAN APPROVED LANDFILL SITE, ENSURE THE ACCEPTOR OF THE SPOIL IS AWARE OF ANY COUNCIL REQUIREMENTS SUCH AS A DA
- THE CONTRACTOR IS NOT TO ACCEPT IMPORTED MATERIAL WITHOUT RECEIVING DOCUMENTED EVIDENCE THAT THE MATERIAL COMPLIES WITH SPECIFICATION REQUIREMENTS.
- WASTE ENCLOSURE(S) ARE TO BE USED FOR ALL RUBBISH ON SITE AND RUBBISH REMOVED FROM ENCLOSURE(S) WHEN REQUIRED OR FULL.

# DUST MANAGEMENT

WHERE BUILDING WORK GENERATES DUST, ALL REASONABLE AND PRACTICABLE MEASURES SHOULD BE TAKEN TO MINIMISE THAT DUST

# THIS CAN OFTEN BE ACHIEVED BY :

- RETAIN EXISTING VEGETATION WHERE POSSIBLE
- STRIPPING ARES PROGRESSIVELY AND ONLY WHERE IT IS NECESSARY FOR WORKS TO OCCUR;
- EMPLOYING STABILISING METHODS SUCH AS MATTING, GRASSING OR MUILCH:
- DAMPENING THE GROUND WITH A LIGHT WATER SPRAY (CONTACT THE ENVIRONMENT PROTECTION AUTHORITY FOR REQUIREMENTS DURING EXTREME DROUGHT CONDITIONS);
- ROUGHENING SURFACE OF EXPOSED SOIL:
- COVERING STOCKPILES AND LOCATING THEM WHERE THEY ARE PROTECTED FROM THE WIND;
- RESTRICTING VEHICLE MOVEMENTS:
- COVERING THE LOAD WHEN TRANSPORTING MATERIAL;
- CONSTRUCTING WIND BREAKS SUCH AS WIND FENCES IN ACCORDANCE WITH THE BLUE BOOK; A WATER CART OR SUFFICIENT WATER SPRAYS SHALL BE MADE AVAILABLE AT ALL TIMES. IN ADVERSE
- CONDITIONS WHEN DUST CANNOT BE ADEQUATELY CONTROLLED WHEN WORKS ARE BEING UNDERTAKEN. WORKS WILL CEASE IN THESE AREAS UNTIL CONDITIONS IMPROVE;
- WATER SHALL BE APPLIED TO SUPPRESS DUST FROM OPEN EARTHWORKS AS WELL AS UNPROTECTED
- 12. AREAS OF COMPLETED EARTHWORKS SHALL BE PROGRESSIVELY REHABILITATED WITH DRY LAND GRASS AND FENCED OFF AS SOON AS PRACTICABLE TO PREVENT FURTHER EROSION:
- THE CONTRACTOR SHALL CONTACT COUNCIL TO OBTAIN WATER FOR CONSTRUCTION WORKS

- SEDIMENT FENCING

  1. SEDIMENT FENCING TO BE CONSTRUCTED AT THE LOCATION(S) INDICATED ON THE PLANS.
- SEDIMENT FENCING TO BE CONSTRUCTED IN ACCORDANCE WITH DETAIL ON EROSION & SEDIMENT CONTROL DETAILS DRAWING.
- CONSTRUCT SEDIMENT FENCES AS CLOSE AS POSSIBLE TO BEING PARALLEL TO THE CONTOURS OF THE SITE BUT WITH SMALL RETURNS AS SHOWN IN THE DRAWING TO LIMIT THE CATCHMENT AREA OF ANY ONE SECTION THE CATCHMENT BETWEEN RETURNS SHOULD BE SMALL ENOUGH TO LIMIT WATER FLOW IF CONCENTRATED AT ONE POINT TO 50 LITRES PER SECOND IN THE DESIGN STORM EVENT, USUALLY THE 10-YEAR EVENT.
- CUT A 150MM DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM OF THE FABRIC TO BE
- DRIVE 1.5M LONG STAR PICKETS INTO GROUND AT 2.5M INTERVALS (MAX) AT THE DOWNSLOPE EDGE OF THE TRENCH. ENSURE ANY STAR PICKETS ARE FITTED WITH SAFETY CAPS.
  FIX SELF SUPPORTING GEOTEXTILE TO THE UPSLOPE SIDE OF THE POSTS ENSURING IT GOES TO THE BASE OF
- THE TRENCH. FIX GEOTEXTILE WITH WIRE TIES OR AS RECOMMENDED BY THE MANUFACTURER. ONLY USE GEOTEXTILE SPECIFICALLY PRODUCED FOR SEDIMENT FENCING. THE USE OF SHADE CLOTH FOR THIS PURPOSE IS NOT ACCEPTABLE. JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150MM OVERLAP.
- BACKELL THE TRENCH OVER THE BASE OF THE FABRIC AND COMPACT IT THOUROUGHLY OVER THE
- REGULARILY MAINTAIN THE SILT FENCING BY REMOVING SILT AFTER RAINFALL EVENTS.

# MAINTENANCE & INSPECTION

- SWEEP AND REMOVE DIRT AND ANY OTHER BUILDING MATERIAL FROM GUTTERS, FOOTPATHS OR ROADWAYS ADJACENT TO THE SITE BY CLOSE OF BUSINESS AND OR PRIOR TO RAIN AND WHEN REQUIRED ALL NECESSARY STEPS SHOULD BE TAKEN THAT ARE PRACTICAL AND REASONABLE TO MINIMISE DUST
- POLLUTION WEEKLY

  1. INSPECT STABILISED CONSTRUCTION ENTRY AND TURN OVER STABILISED CONSTRUCTION ENTRY MATERIAL
- MONTHLY AND RENEW WHEN REQUIRED

# CHECK AND REINSTATE SILT CONTROL FENCES.

LIMIT CONSTRUCTION VEHICLE ACCESS TO SITE DURING AND IMMEDIATELY FOLLOWING WET WEATHER

- . WASTE ENCLOSURE(S) ARE TO BE USED FOR ALL RUBBISH ON SITE AND RUBBISH REMOVED FROM ENCLOSURE(S) WHEN REQUIRED OR FULL

- THIS THE ALL BUILDING WORK THAT GENERATES NOISE IS CONDUCTED WITHIN THE TIME PERIODS DETAILED IN THE CONTRACT ΙΝ ΑΠΠΙΤΙΩΝ
- SCHEDULE NOISY ACTIVITIES FOR THE LEAST SENSITIVE TIMES OF THE DAY SUCH AS MID-MORNING AND MID-AFTERNOON.
- SELECT MACHINERY THAT PRODUCE LESS NOISE; AND
- ENSURE MACHINERY IS WELL MAINTAINED

- BURNING OF WASTE MATERIALS ON THE SITE, SUCH AS PLASTICS, CHEMICALS OR WOOD THAT MAY BE PAINTED, CHEMICALLY TREATED OR CONTAMINATED WITH CHEMICALS IS ILLEGAL.
- A FIRE MAY BE PERMITTED FOR HEATING PURPOSES PROVIDED IT IS IN A BRAZIER OR CONSTRUCTED FIREPLACE. ONLY SEASONED, UNTREATED TIMBER CAN BE BURNED FOR HEATING PURPOSES.

TABLE 1 - MAXIMUM ACCEPTABLE C-FACTORS AT NOMINATED TIMES							
LANDS	MAX. C-FACTOR	REMARKS					
WATERWAYS AND OTHER AREAS SUBJECTED TO CONCENTRATED FLOWS (EG. TABLE DRAINS), POST CONSTRUCTION AND DURING OPERATION	0.05	APPLIES AFTER TEN WORKING DAYS FROM THE COMPLETION OF FORMATION AND BEFORE THEY ARE ALLOWED TO CARRY ANY CONCENTRATED FLOWS. FLOWS WILL BE LIMITED TO THOSE SHOWN IN TABLE 5.2 OF LANDCOM (2004). FOOT AND VEHICULAR TRAFFIC WILL BE PROHIBITED IN THESE AREAS					
STOCKPILES AND BATTERS, POST CONSTRUCTION AND DURING OPERATION	0.10	APPLIES AFTER TEN WORKING DAYS FROM COMPLETION OF FORMATION. MAXIMUM C-FACTOR OF 0.10 EQUALS 60% GROUND COVER					
ALL LANDS, INCLUDING WATERWAYS AND STOCKPILES DURING CONSTRUCTION AND OPERATION	0.15	APPLIES AFTER 20 WORKING DAYS OF INACTIVITY, EVEN THOUGH WORKS MIGHT CONTINUE LATER. MAXIMUM C-FACTOR of 0.15 EQUALS 50% GROUND COVER					
ALL LANDS POST CONSTRUCTION	0.05	APPLIES AFTER 60 WORKING DAYS OF COMPLETION OF WORKS. MAXIMUM C-FACTOR OF 0.05 EQUALS 70% GROUND COVER					

	TABLE 2 - LIMITATIONS TO ACCESS DURING CONSTRUCTION				
LAND USE	LIMITATION	REMARKS			
CONSTRUCTION AREAS	LIMITED TO 5 (PREFERABLY 2) METERS FROM THE EDGE OF ANY ESSENTIAL CONSTRUCTION ACTIVITY AS SHOWN ON THE ENGINEERING PLANS	ALL SITE WORKERS SHOULD CLEARLY RECOGNISE THESE AREAS THAT, WHERE APPROPRIATE, ARE IDENTIFIED WITH BARRIER FENCING (UPSLOPE) AND SEDIMENT (DOWNSLOPE) OR SIMILAR MATERIALS			
ACCESS AREAS	LIMITED TO MAXIMUM WIDTH OF 5 METERS	THE SITE MANAGER WILL DETERMINE AND MARK THE LOCATION OF THESE ZONES ON SITE. THEY CAN VARY IN POSITION SO AS TO BEST CONSERVE EXISTING VEGETATION AND PROTECT DOWNSTREAM AREAS WHILE BEING CONSIDERATE OF THE NEEDS OF EFFICIENT WORKS ACTIVITIES. ALL SITE WORKERS WILL CLEARLY RECOGNISE THESE BOUNDARIES			
REMAINING LANDS, INCLUDING RE-VEGETATION AREAS	ENTRY PROHIBITED EXCEPT FOR ESSENTIAL MANAGEMENT WORKS	THINNING OF GROWTH MIGHT BE NECESSARY, FOR EXAMPLE, FOR FIRE REDUCTION OR WEED REMOVAL			

AMENDMENT / REVISION DESCRIPTION 14/11/17 ISSUED FOR DEVELOPMENT APPLICATION

FSIGNER AJB

FRAISH Consulting Civil & Structural Engineers 1/8 Victoria Street, Hall ACT

PO Box 310, Hall ACT 2618

CAPPELLO

CLIENT

DEVELOPMENTS NO.10


ROJECT TITLE


SUBDIVISION OF LOT 28, DP479


SEDIMENT & EROSION **CONTROL NOTES** 


SHEET 1


Α **AS SHOWN** DA C213











NOTE: SUBSOIL PIPES TO BE EVENLY SPACED AT 1/3 WIDTH UP TO A MAXIMUM DISTANCE OF 1 METER. RAIN GARDENS WITH WIDTH GREATER THAN 3m WILL REQUIRED ADDITIONAL PIPES.

RAIN GARDEN PLAN

- RAIN GARDEN NOTES:

  1. FILTER SURFACE AREA DIMENSIONS DEPENDENT ON THE AREA TO BE TREATED


  2. RAIN GARDEN SHAPE MAY BE ALTERED

  3. INTERNAL AREA NEEDS TO BE MAINTAINED

  4. INLET PIPE FROM FUTURE DWELLING TO CONNECT INTO NEAREST POINT OF THE RAIN GARDEN

  5. RAIN GARDEN OUTLET CAN BE POSITIONED TO SUIT THE POINT OF DISCHARGE

  6. RAIN GARDEN TO BE PLANTED AT A DENSITY OF 8-12 PLANTS PER SQUARE METER CONSISTING OF CAREX SP WITHIN THE RAIN GARDEN AND JUNCUS SP AROUND THE PERIMETER



ents No											
REVISION	DATE	AMENDMENT / REVISION DESCRIPTION	DRAWN	TITLE	NAME	SCALE	DESIGNER	CLIENT	PROJECT TITLE SUBDIVISION C	F LOT 28, DP479	
A A	16/11/17	7 ISSUED FOR DEVELOPMENT APPLICATION	LKK	DRAWN	LKK		FRAISH Consulting Civil & Structural Engineers  1/8 Victoria Street, Hall ACT PO Box 310, Hall ACT 2618 02 6/330 2823 · O418 585 774 Info@fraish.com.au · www.fraish.com.au	CAPPELLO DEVELOPMENTS NO.10	MARY'S MOUNT ROAD, GOULBURN, NSW		
Z:\PROJECTS\Cappello D				DESIGNER  DO NOT SCALE OFF DRA' SITE BEFORE COMMENC					RAIN GARDEN DETAILS		
				copyright of Fraish Consulti	ion contained in this document are ing Pty Ltd. Use or copying of this rt without written permission of copyright.				SCALE PHASE DA	DRAWING No.	A REV

