

15/2011/DA-RA

Conditions of Consent

GENERAL CONDITIONS

The following conditions have been applied to ensure that the use of the land and/or building is carried out in such a manner that is consistent with the aims and objectives of the planning instrument affecting the land.

For the purpose of these conditions, the term 'applicant' means any person who has the authority to act on or benefit of the development consent.

1. Approved Development

The development shall take place in accordance with the approved development plans containing Council's approved development stamp and all associated documentation submitted with the application, except as modified in red by Council and/or any conditions of this consent.

2. Building Code of Australia

All building work must be carried out in accordance with the provisions of the *Building Code of Australia*. In this clause, a reference to the *Building Code of Australia* is a reference to that Code as in force on the date the application for the relevant construction certificate is made.

3. Contract of Insurance (residential building work)

In the case of residential building work for which the *Home Building Act 1989* requires there to be a contract of insurance in force in accordance with Part 6 of that Act, that such a contract of insurance is in force before any building work authorised to be carried out by the consent commences.

This clause does not apply:

- a. To the extent to which an exemption is in force under Clause 187 or 188 of the Environmental Planning and Assessment Regulation 2000, subject to the terms of any condition or requirement referred to in Clause 187(6) or 188(4) of that regulation, or
- b. To the erection of a temporary building.

4. Notification of Home Building Act 1989 Requirements

Residential building work within the meaning of the *Home Building Act 1989* must not be carried out unless the principal certifying authority for the development to which the work relates (not being Council) has given Council written notice of the following information:

- a. In the case of work for which a principal contractor is required to be appointed:
 - i. The name and licence number of the principal contractor, and
 - ii. The name of the insurer by which the work is insured under Part 6 of that Act.
- b. In the case of work to be done by an owner-builder:
 - i. The name of the owner-builder, and
 - ii. If the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.

If arrangements for doing the residential building work are changed while the work is in progress so that the information notified becomes out of date, further work must not be carried out unless the principal certifying authority for the development to which the work relates (not being Council) has given Council written notification of the updated information.

5. Landscaping

A revised landscape plan shall be provided to Council and its approval obtained prior to the issue of a Construction Certificate for works approved under this consent. The provision and maintenance of landscaping shall be in accordance with the approved landscape plan containing Council's approved development stamp including the engagement of a suitably qualified landscape consultant/contractor for landscaping works. The landscape design shall incorporate a significant portion of native, low water demand plants.

6. External Finishes

The external finishes shall be in accordance with the approved plans and the schedule of finishes submitted with this application. Any proposed alterations to these finishes are considered to be a modification to the development consent and require separate approval by Council.

7. Switchboards/Utilities

Switchboards, garbage storage areas and storage for other utilities shall not be attached to the front elevations of the building or side elevations that can be seen from a public place.

8. Deliveries

Vehicles servicing the site shall comply with the following requirements:

- a. Service delivery vehicles shall be a maximum size of small rigid vehicles.
- b. All vehicular entries and exits shall be made in a forward direction.
- c. All vehicles awaiting loading, unloading or servicing shall be parked on site and not on adjacent or nearby public roads.
- d. All deliveries to the premises shall be made to the loading bay/s provided.

A traffic sign shall be placed adjacent to the driveway at the entrance of the property advising drivers of the above information. Should the sign be damaged or removed, it shall be replaced within 48 hours.

9. Lighting

Illumination of the site is to be arranged to provide an appropriate level of lighting and in accordance with the requirements of *Australian Standard 4282 (as amended)* so as not to impact upon the amenity of the occupants of adjoining and nearby residential premises or traffic.

10. Graffiti Removal

In accordance with the environmental maintenance objectives of 'Crime Prevention Through Environmental Design', the owner/lessee of the building shall be responsible for the removal of any graffiti which appears on the buildings, fences, signs and other surfaces of the property within 48 hours of its application.

11. Unreasonable Noise, Dust and Vibration

The development, including operation of vehicles, shall be conducted so as to avoid the generation of unreasonable noise, dust or vibration and cause no interference to adjoining or nearby occupants. Special precautions must be taken to avoid nuisance in neighbouring

residential areas, particularly from machinery, vehicles, warning sirens, public address systems and the like.

12. Engineering Design Works

The design of all engineering works shall be carried out in accordance with the requirements set out in the *Campbelltown (Sustainable City) DCP 2009 - Volumes 1 and 2*.

13. Common Area

The recreation room and adjacent common outdoor area shall be made available for the use of residents and their visitors at all times.

The applicant shall install at least one permanent barbeque within the outdoor area for use by residents. The barbeque shall be kept clean and maintained by the managing body of the building.

14. Car Parking Spaces

Revised car parking plans shall be provided to Council and its approval obtained prior to the issue of a Construction Certificate for works approved under this consent. The revised plans shall show 118 car parking spaces designed and line marked within the basement car parking areas and made available to all users of the site in accordance with Australian Standards 2890.1, 2 & 6 and as per the conditions of this consent.

Blind aisles on the first floor parking area with a length greater than six parking spaces shall be provided with a vehicle turn around facility along the respective aisle. In this regard, proposed parking spaces P1.30 & P1.40 shall be converted to turnaround bays and shall be appropriately line marked and signed as such. To prevent unauthorised parking within these bays, in addition to the required line marking and signing, permanent high-visibility bollards shall be installed along the centre line of the bay at a point no less than 1.0m and no more than 1.5m from the rear of the respective turnaround bay.

The first floor parking area shall be provided with a minimum of 24 standard + 2 accessible visitor/customer parking spaces that are unrestricted and made freely available at all times the parking area is open to the public (i.e. the installation of removable bollards within those spaces and/or the restriction of parking in those spaces by way of restrictive signage is prohibited). These spaces shall be clearly nominated on the revised plan. Unrestricted *standard* parking spaces shall be P1.1 – P1.5, P1.7 – P1.11, P1.13 – P1.17, P1.20 – P1.24, P1.32, P1.33, P1.42 & P1.43 inclusive, shown on plan DA 01-03 F by architectus. Unrestricted *accessible* parking spaces shall be P1.25 & P1.26 shown on plan DA 01-03 F by architectus.

A maximum of 10 *standard* parking spaces within the first floor parking area can be made access restricted (i.e. installation of removable bollards, restrictive signage or the like is allowed) for the sole use of commercial tenants of the building. Restricted *standard* parking spaces shall only be located within proposed spaces 1.29, 1.31, 1.36 – 1.39, 1.41, 1.45 – 1.47 inclusive, shown on plan DA 01-03 F by architectus. These spaces are not to be sublet, leased, cross hired or otherwise rented in any capacity to any entity or person that is not a tenant of the complex.

A maximum of 6 *accessible* parking spaces within the first floor parking area can be made access restricted (i.e. installation of removable bollards, restrictive signage or the like is allowed) for the sole use of residential tenants of the building. Restricted *accessible* parking spaces shall only be located within proposed spaces P1.18, P1.19, P1.27, P1.28, P1.34 & P1.35 shown on plan DA 01-03 F by architectus. These spaces are not to be sublet, leased, cross hired or otherwise rented in any capacity to any entity or person that is not a tenant of the complex.

Where access to any *accessible* parking space is to be restricted (in accordance with this consent) by way of the installation of a physical device (e.g. bollard), the device is to be automated and is to be of a system that allows activation by the driver from within the authorised vehicle. The installation of any device or barrier within an *accessible* parking

space that requires manual handling of the device is prohibited. Where an automated barrier/device becomes non-functional, the device shall be repaired within 48 hours of the device being identified as defective, or otherwise the device is to be removed until the necessary repairs can be made.

No restrictive barrier or device installed within any of the approved 'access restricted' parking spaces shall cause an obstruction or nuisance to any other vehicles within the site.

15. Basement Car Parking Security

The basement car parking area shall be fitted with secure roller shutter device and associated security keys to restrict access to the car park for residents, their visitors and visitors to the commercial tenancies.

The ceiling of basement car parking levels is to be finished in white paint to increase the effectiveness of lighting.

16. Rubbish/Recycling Bin Storage

The rubbish and recycling bins shall not be stored within vehicle parking, vehicle manoeuvring areas or landscaped areas.

The bin(s) shall only be stored in accordance with the approved plans.

17. Garbage Storage

The garbage storage rooms identified on the plans shall:

- a. Be fully enclosed and shall be provided with concrete floor, with concrete or cement rendered walls coved to the floor;
- b. The floor shall be graded to an approved sewer connection incorporating a sump and galvanised grate cover or basket;
- c. A hose cock shall be provided within the rooms;
- d. Garbage rooms shall be vented to the external air by natural or mechanical means.

18. Air Conditioning Units

Air conditioning units shall not be affixed to external walls of the building or placed on balconies in such a manner they are visible from a public place.

19. Shoring and Adequacy of Adjoining Property

If the development referred to in this development consent involves an excavation that extends below the level of the base of the footings of a building on adjoining land, the person having the benefit of the development consent must at the person's own expense:

- a. Protect and support the adjoining premises from possible damage from the excavation, and
- b. Where necessary, underpin the adjoining premises to prevent any such damage.

This condition does not apply if the person having the benefit of the development consent owns the adjoining land or the owner of the adjoining land has given consent in writing to that condition not applying.

20. Construction Certificate

Prior to the commencement of any works that require a construction certificate:

- a. The applicant shall obtain a construction certificate for the particular works;
- b. The applicant shall appoint a principal certifying authority; and
- c. The private certifying authority shall notify Council of their appointment no less than two (2) days prior to the commencement of any works

PRIOR TO THE ISSUE OF A CONSTRUCTION CERTIFICATE

The following conditions of consent must be complied with prior to the issue of a construction certificate by either Campbelltown City Council or an accredited certifier. All necessary information to comply with the following conditions of consent must be submitted with the application for a construction certificate.

21. Utility Servicing Provisions

Prior to Council or an accredited certifier issuing a construction certificate, the applicant shall obtain a letter from both the relevant electricity authority and the relevant telecommunications authority stating that satisfactory arrangements have been made to service the proposed development.

Note: The applicant should also contact the relevant water servicing authority to determine whether the development will affect the authorities water or sewer infrastructure.

22. Geotechnical Report

Prior to Council or an accredited certifier issuing a construction certificate, a geotechnical report prepared by suitably qualified engineer relying on soil test results from a NATA registered lab shall be submitted which indicates that the land will not be subject to subsidence, slip, slope failure or erosion where excavation and/or filling exceeds 900mm in depth or identified as filled land.

23. Soil and Water Management Plan

Prior to Council or an accredited certifier issuing a construction certificate, a detailed soil and water management plan shall be submitted for approval.

24. Traffic Committee

Prior to Council or an accredited certifier issuing a construction certificate, the applicant shall submit plans and obtain approval from Council's Local Traffic Committee for any proposals for the construction of prescribed traffic control devices and traffic control facilities and all associated line marking and/or sign posting.

25. Traffic Control Plans

Prior to Council or an accredited certifier issuing a construction certificate, the applicant shall prepare and obtain approval from an accredited person, a Traffic Control Plan (TCP) in accordance with the State Roads Authority manual "*Traffic Control at Work Sites*" and *Australian Standard AS 1742.3 (as amended)*. A copy of the approved TCP shall be kept on site for the duration of the works in accordance with *Work Cover Authority* requirements. A copy shall be submitted to Council for its records.

26. Stormwater Management Plan (Development)

Prior to Council or an accredited certifier issuing a construction certificate, a plan indicating all engineering details and calculations relevant to site regrading and the collection and disposal of stormwater from the site, building/s and adjacent catchment, shall be submitted for approval. Floor levels of all buildings shall be a minimum of 150mm above the adjacent finished site levels and stormwater shall be conveyed from the site to the nearest system under Council's control. All proposals shall comply with the *Campbelltown (Sustainable City) DCP 2009 - Volumes 1 and 2*.

27. Dilapidation Report

Prior to Council or an accredited certifier issuing a construction certificate, the applicant shall submit a dilapidation report for all buildings on lands that adjoin the subject works.

28. Section 94A Developer Contribution - Community Facilities and Services

Prior to Council or an accredited certifier issuing a Construction Certificate, the applicant shall provide a receipt for the payment to Council of a community facilities and services contribution in accordance with the provisions of the *Campbelltown City Council Section 94A Development Contributions Plan*.

For the purposes of calculating the required S94A contribution, where the value of the total development cost exceeds \$100,000, the applicant is required to include with the application for the respective certificate, a report setting out a cost estimate of the proposed development in accordance with the following:

- where the value of the proposed development is greater than \$100,000 but less than \$500,000, provide a Cost Summary Report by a person who, in the opinion of the Council, is suitably qualified to provide a Cost Summary Report (Cost Summary Report Template 1). All Cost Summaries will be subject to indexation on a quarterly basis relative to the *Consumer Price Index - All Groups* (Sydney) where the contribution amount will be based on the indexed value of the development applicable at the time of payment; or
- where the value of the proposed development is \$500,000 or more, provide a detailed development cost report completed by a quantity surveyor who is a registered member of the Australian Institute of Quantity Surveyors (Quantity Surveyors Estimate Report Template 2). Payment of contribution fees will not be accepted unless the amount being paid is based on a Quantity Surveyors Estimate Report (QS Report) that has been issued within 90 days of the date of payment. Where the QS Report is older than 90 days, the applicant shall provide an updated QS Report that has been indexed in accordance with clause 25J(4) of the Environmental Planning and Assessment Regulation 2000 to ensure quarterly variations in the *Consumer Price Index All Group Index Number for Sydney* have been incorporated in the updated QS Report.

Copies of the Cost Summary Report - Template 1 and the Quantity Surveyors Estimate Report - Template 2 are located under "Developer Contributions" on Council's web site (www.campbelltown.nsw.gov.au) or can be collected from Council's Planning and Environment Division during normal business hours.

On calculation of the applicable contributions, all amounts payable will be confirmed by Council in writing.

Payment of Section 94A Developer Contributions will only be accepted by way of Cash, Credit Card or Bank Cheque issued by an Australian bank. Payment by any other means will not be accepted unless otherwise approved in writing by Council.

Note: This condition is only applicable where the total development value exceeds \$100,000.

29. Design for Access and Mobility

Prior to Council or an accredited certifier issuing a Construction Certificate, the applicant shall demonstrate by way of detailed design, compliance with the relevant access requirements of the BCA and AS 1428 – Design for Access and Mobility.

PRIOR TO THE COMMENCEMENT OF ANY WORKS

The following conditions of consent have been imposed to ensure that the administration and amenities relating to the proposed development comply with all relevant requirements. These conditions are to be complied with prior to the commencement of any works on site.

30. Erosion and Sediment Control

Prior to the commencement of any works on the land, adequate/approved erosion and sediment control measures shall be fully installed/implemented.

31. Erection of Construction Sign

Prior to the commencement of any works on the land, a sign/s must be erected in a prominent position on the site:

- a. Showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working hours;
- b. Stating that unauthorised entry to the work site is prohibited; and
- c. Pollution warning sign promoting the protection of waterways (issued by Council with the development consent);
- d. Stating the approved construction hours in which all works can occur.
- e. Showing the name, address and telephone number of the principal certifying authority for the work.

Any such sign/s is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.

32. Toilet on Construction Site

Prior to the commencement of any works on the land, toilet facilities are to be provided, at or in the vicinity of the work site on which work involved in the erection or demolition of a building is being carried out, at the rate of one toilet for every 20 persons or part thereof. Each toilet provided must be a standard flushing toilet and be connected to:

- a. A public sewer, or
- b. If connection to a public sewer is not practicable, to an accredited sewage management facility approved by Council, or
- c. If connection to a public sewer or an accredited sewage management facility is not practicable, to some other management facility approved by Council.

33. Trade Waste

Prior to the commencement of any works on the land, a trade waste facility shall be provided on-site to store all waste pending disposal. The facility shall be screened, regularly cleaned and accessible to collection vehicles.

34. Vehicular Access during Construction

Prior to the commencement of any works on the land, a single vehicle/plant access to the site shall be provided, to minimise ground disturbance and prevent the transportation of soil onto any public road system. Single sized aggregate, 40mm or larger placed 150mm deep, extending from the kerb and gutter to the property boundary, shall be provided as a minimum requirement.

35. Public Property

Prior to the commencement of any works on site, the applicant shall advise Council of any damage to property which is controlled by Council which adjoins the site, including kerbs, gutters, footpaths, and the like. Failure to identify existing damage may result in all damage detected after completion of the development being repaired at the applicant's expense.

36. Footpath and Vehicular Crossing Levels

Prior to the commencement of any work, footpath and vehicular crossing levels are to be obtained from Council by lodging an application on the prescribed form.

37. Hoarding / Fence

Prior to the commencement of any works, a hoarding or fence must be erected between the work site and a public place if the work involved in the development is likely to cause pedestrian or vehicular traffic in a public place to be obstructed or rendered inconvenient, or if the building involves the enclosure of a public place in accordance with *Work Cover* requirements.

The work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place.

A separate land use application under Section 68 of the Local Government Act 1993 shall be submitted to and approved by Council prior to the erection of any hoarding on public land.

DEVELOPMENT REQUIREMENTS DURING CONSTRUCTION

The following conditions of consent have been imposed to ensure that the administration and amenities relating to the proposed development comply with all relevant requirements. These conditions are to be complied with during the construction of the development on site.

38. Construction Work Hours

All work on site shall only occur between the following hours:

Monday to Friday	7.00am to 6.00pm
Saturday	8.00am to 1.00pm
Sunday and public holidays	No Work.

39. Construction Noise

In the event of a noise related issue arising during construction, the person in charge of the premises shall when instructed by Council, cause to be carried out an acoustic investigation by a suitably qualified acoustic consultant and submit the results of the investigation to Council. If required by Council, the person in charge of the premises shall implement any or all of the recommendations of the consultant and any additional requirements of Council to its satisfaction.

40. Erosion and Sediment Control

Erosion and sediment control measures shall be provided and maintained throughout the construction period, in accordance with the requirements of the manual – *Soils and Construction (2004) (Bluebook)*, the approved plans, Council specifications and to the satisfaction of the principal certifying authority. The erosion and sedimentation control devices shall remain in place until the site has been stabilised and revegetated.

Note: On the spot penalties up to \$1,500 will be issued for any non-compliance with this requirement without any further notification or warning.

41. Work Zones

All loading, unloading and other activities undertaken during construction shall be accommodated on the development site.

Where it is not practical to load, unload or undertake specific activities on the site during construction, the provision of a 'Work Zone' external to the site may be approved by Council following an application being submitted to Council's Traffic Unit outlining the proposal for the work zone. The application is required to be made prior to the commencement of any works and is to include a suitable 'Traffic / Pedestrian Management and Control Plan' for the area of the work zone that will be affected. All costs of approved traffic / pedestrian control measures, including relevant fees, shall be borne by the applicant.

42. Excavation and Backfilling

All excavations and backfilling associated with the approved works must be executed safely and in accordance with appropriate professional standards. All excavations must be properly guarded and protected to prevent them from being dangerous to life or property.

If an excavation associated with the approved works extends below the level of the base of the footings of a building on an adjoining allotment of land, the person causing the excavation to be made:

- a. Must preserve and protect the building from damage; and
- b. If necessary, must underpin and support the building in an approved manner, and
- c. Must, at least seven (7) days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished.

The owner of the adjoining allotment of land is not liable for any part of the cost of work carried out, whether carried out on the allotment of land being excavated or on the adjoining allotment of land.

43. Fill Compaction Requirements

Any filling carried out in accordance with this consent shall maintain a minimum requirement of 98% standard compaction.

Any lot filling operations carried out in accordance with this consent shall be tested to establish the field dry density every 300mm rise in vertical height. Test sites shall be located randomly across the fill site with 1 test per 500m² (minimum 1 test per 300mm layer) certified by a qualified geotechnical engineer.

44. Dust Nuisance

Measures shall be implemented to minimise wind erosion and dust nuisance in accordance with the requirements of the manual – *'Soils and Construction (2004) (Bluebook)*. Construction areas shall be treated/ regularly watered to the satisfaction of the principal certifying authority.

45. Termite Control

The building shall be protected from subterranean termites in accordance with *Australian Standard 3660.1*. Certification of the treatment shall be submitted to the principal certifying authority prior to the issue of an occupation certificate.

46. Excess Material

All excess material is to be removed from the site. The spreading of excess material or stockpiling on site will not be permitted without prior written approval from Council.

47. Public Safety

Any works undertaken in a public place are to be maintained in a safe condition at all times in accordance with *AS 1742.3*. Council may at any time and without prior notification make safe any such works Council considers to be unsafe, and recover all reasonable costs incurred from the applicant.

48. Footpath

The footpath adjoining the subject land shall be regraded, topsoiled and turfed in accordance with levels to be obtained from Council. The footpath formation may need to be extended beyond the site boundaries, to provide an acceptable transition to existing footpath levels.

49. Industrial / Commercial Driveway and Layback Crossing

The applicant shall provide reinforced concrete driveways and layback crossings to Council's *Commercial / Industrial Vehicle Crossing Specification*.

A separate application for this work, which will be subject to a crossing inspection fee, fixing of levels and inspections by Council, must be lodged with Council. Conduits must be provided to service authority requirements.

50. Associated Works

The applicant shall undertake any works external to the development, that are made necessary by the development, including additional road and drainage works or any civil works directed by Council, to make a smooth junction with existing work.

51. Completion of Construction Works

Unless otherwise specified in this consent, all construction works associated with the approved development shall be completed within twelve (12) months of the date of the notice of the intention to commence construction works under Section 81A of the Act.

In the event that construction works are not continually ongoing, the applicant shall appropriately screen the construction site from public view with architectural devices and landscaping to Council's written satisfaction.

PRIOR TO THE ISSUE OF AN OCCUPATION CERTIFICATE

The following conditions of consent must be complied with prior to the issue of an occupation certificate by either Campbelltown City Council or an accredited principal certifying authority. All necessary information to comply with the following conditions of consent must be submitted with the application for an occupation certificate.

Note: For the purpose of this development consent, any reference to "occupation certificate" shall also be taken to mean "interim occupation certificate".

52. Section 73 Certificate

Prior to the principal certifying authority issuing an occupation certificate, the submission of a Section 73 certificate issued by *Sydney Water*.

53. Structural Engineering Certificate

Prior to the principal certifying authority issuing an occupation certificate, the submission of a certificate from a practising structural engineer certifying that the building has been erected in compliance with the approved structural drawings and relevant *SAA Codes* and is structurally adequate.

54. Completion of External Works Onsite

Prior to the principal certifying authority issuing an occupation certificate, all external works, repairs and renovations detailed in the schedule of treatment/finishes, landscaping, driveways, fencing and retaining walls to be completed to the satisfaction of the principal certifying authority.

55. Final Inspection – Works as Executed Plans

Prior to the principal certifying authority issuing an occupation certificate, the applicant shall submit to Council two complete sets of fully marked up and certified work as executed plans in accordance with Council's *Specification for Construction of Subdivisional Road and Drainage Works (as amended)* and with the design requirements detailed in the *Campbelltown (Sustainable City) DCP Volume 2 (as amended)*.

The applicant shall **also** submit a copy of the Works as Executed information to Council in an electronic format in accordance with the following requirements:

Survey Information

- Finished ground and building floor levels together with building outlines.
- Spot levels every five (5) metres within the site area.
- Where there is a change in finished ground levels that are greater than 0.3.m between adjacent points within the above mentioned 5m grid, intermediate levels will be required.
- A minimum of fifteen (15) site levels.
- If the floor level is uniform throughout, a single level is sufficient.
- Details of all stormwater infrastructure including pipe sizes and types as well as surface and invert levels of all existing and/or new pits/pipes associated with the development.
- All existing and/or new footpaths, kerb and guttering and road pavements to the centre line/s of the adjoining street/s.
- The surface levels of all other infrastructure.

Format

- MGA 94 (Map Grid of Australia 1994) Zone 56 - Coordinate System
- All level information to Australian Height Datum (AHD)

AutoCAD Option

- The "etransmit" (or similar) option in AutoCAD with the transmittal set-up to include as a minimum:

Package Type	-	zip
File Format	-	AutoCAD 2004 Drawing Format or later
Transmittal Options	-	Include fonts Include textures from materials Include files from data links Include photometric web files Bind external references The drawing is not to be password protected.

MapInfo Option

- Council will also accept either MapInfo Native format (i.e. .tab file) or MapInfo mid/mif.

All surveyed points will **also** be required to be submitted in a point format (x,y,z) in either an Excel table or a comma separated text file format.

56. Public Utilities

Prior to the principal certifying authority issuing an occupation certificate, any adjustments to public utilities, required as a result of the development, shall be completed to the satisfaction of the relevant authority and at the applicant's expense.

57. Termite Protection

Prior to the principal certifying authority issuing an occupation certificate, certification from a licensed pest controller shall be submitted certifying that the termite treatment has been installed in accordance with *AS3660.1*.

58. BASIX

Prior to the principal certifying authority issuing an occupation certificate, completion of all requirements listed in the relevant BASIX certificate for the subject development shall be completed/installed.

59. Council Fees and Charges

Prior to the principal certifying authority issuing an occupation certificate, the applicant shall obtain written confirmation from Council that all applicable Council fees and charges associated with the development have been paid in full. Written confirmation will be provided to the applicant following Council's final inspection and satisfactory clearance of the public area adjacent the site.

ADVISORY NOTES

The following information is provided for your assistance to ensure compliance with the Environmental Planning and Assessment Act 1979, Environmental Planning and Assessment Regulation 2000, other relevant Council Policy/s and other relevant requirements. This information does not form part of the conditions of development consent pursuant to Section 80A of the Act.

Advice 1. Environmental Planning and Assessment Act 1979 Requirements

The Environmental Planning and Assessment Act 1979 requires you to:

- a. Obtain a construction certificate prior to the commencement of any works. Enquiries regarding the issue of a construction certificate can be made to Council's Customer Service Centre on 4645 4000.
- b. Nominate a principal certifying authority and notify Council of that appointment prior to the commencement of any works.
- c. Give Council at least two days notice prior to the commencement of any works.
- d. Have mandatory inspections of nominated stages of the construction inspected.
- e. Obtain an occupation certificate before occupying any building or commencing the use of the land.

Advice 2. Provision of Equitable Access

Nothing in this consent is to be taken to imply that the development meets the requirements of the *Disability Discrimination Act 1992* (DDA1992) or *Disability (Access to Premises – Buildings) Standards 2010* (Premises Standards).

Where a Construction Certificate is required for the approved works, due regard is to be given to the requirements of the *Building Code of Australia* (BCA) & the Premises Standards. In this regard it is the sole responsibility of the certifier, building developer and building manager to ensure compliance with the Premises Standards.

Where no building works are proposed and a Construction Certificate is not required, it is the sole responsibility of the applicant and building owner to ensure compliance with the DDA1992.

Advice 3. Smoke Alarms

From 1 May 2006 all NSW residents must have at least one working smoke alarm installed on each level of their home. This includes owner occupier, rental properties, relocatable homes and any other residential building where people sleep.

The installation of smoke alarms is required to be carried out in accordance with AS 3786. The licensed electrical contractor is required to submit to the Principal Certifying Authority a certificate certifying compliance with AS 3000 and AS 3786.

Advice 4. Covenants

The land upon which the subject building is to be constructed may be affected by restrictive covenants. Council issues this approval without enquiry as to whether any restrictive covenant affecting the land would be breached by the construction of the building, the subject of this permit. Persons to whom this permit is issued must rely on their own enquiries as to whether or not the building breaches any such covenant.

Advice 5. Tenancy Fit Out

A separate development application is required to be submitted for the fit out and use of individual commercial tenancies.

Advice 6. Adjustment to Public Utilities

Adjustment to any public utilities necessitated by the development is required to be completed prior to the occupation of the premises and in accordance with the requirements of the relevant Authority. Any costs associated with these adjustments are to be borne by the applicant.

Advice 7. Salinity

Please note that Campbelltown is an area of known salinity potential. As such any salinity issues should be addressed as part of the construction certificate application. Further information regarding salinity management is available within *Campbelltown (Sustainable City) DCP 2009 - Volumes 1 and 2*.

Advice 8. Asbestos Warning

Should asbestos or asbestos products be encountered during construction or demolition works you are advised to seek advice and information prior to disturbing the material. It is recommended that a contractor holding an asbestos-handling permit (issued by Work Cover NSW), be engaged to manage the proper disposal and handling of the material. Further information regarding the safe handling and removal of asbestos can be found at:

www.environment.nsw.gov.au
www.nsw.gov.au/fibro
www.adfa.org.au
www.workcover.nsw.gov.au

Alternatively, call Work Cover Asbestos and Demolition Team on 8260 5885.

Advice 9. Rain Water Tank

It is recommended that water collected within any rainwater tank as part of the development be limited to non-potable uses. NSW Health recommends that the use of rainwater tanks for drinking purposes not occur where a reticulated potable water supply is available.

Advice 10. Smoke Free Environment Act

Nothing in this consent is to be taken to imply that the development meets the requirements of the *Smoke Free Environment Act 2000* (SFEA2000) or the *Smoke Free Environment Regulations 2007* (SFER2007). In the event that the occupier wishes to facilitate smoking within any enclosed public place of the premises (in accordance with clause 6 of the SFER2007), the occupier must first contact NSW Department of Health to ensure that the design and construction of the area proposed to facilitate smoking fully complies with the requirements of the SFEA2000 and the SFER2007.

Advice 11. Dial 1100 Before you Dig

Underground cable and pipes may exist in the area. In your own interest and for safety, telephone 1100 before excavation or erection of structures. Information on the location of underground pipes and cables can also be obtained by fax on 1300 652 077 or through the following website - www.dialbeforeyoudig.com.au

END OF CONDITIONS

