REV	AMENDMENTS	DATE
B	- Lift in southern block has been relocated. - Studies removed from Penthouse units. - Unit 47 changed to reflect change to floor below. - Unit 46 changed to reflect change to lift position - Windows to bedrooms of Unit 48 no longer highlights. low sill windows have privacy screen in front of them. - Unit 49 reduced in area as a result of reduction of floor below. This weas done to achieve 60% area of floor below.	06.12.11

PENTHOUSE LEVEL
SCALE 1:100 @ A0

BASIX REQUIREMENTS

- All units must have 3 star (>4.5 but <=6L/min) rated shower heads
- All units must have 4 star rated toilet flushing system
- All units must have 4 star rated kitchen & bath'rm taps
- All units must have 5 star rated gas instantaneous hot water system
- Each bathroom in all units must have an individual fan into central duct + VSD
- Each bathroom in all units must have a manual switch on/off;
- Each kitchen in all units must have an individual fan into central duct + VSD
- Each kitchen in all units must have a manual switch on/off;
- Each laundry in all units must have an individual fan into central duct + VSD
- Each laundry in all units must have a manual switch on/off;
- All units must have 1-phase airconditioning 3.5 Star (new rating) to living areas for cooling & heating
- All dwellings to have artificial lighting to each kitchen, bathroom, laundry & hallways
- All dwellings to have artificial lighting to each kitchen, bathroom, laundry & hallways
- Dwellings 11, 16, 22, 23, 27, 33, 38, 44 & 48 must have natural lighting to 1 bathroom
- All units must have a gas cooktop & electric oven
- All units must have a well ventilated fridge space
- All units must have an indoor sheltered clothes drying line
- All units must have an indoor sheltered clothes drying line
- Where there is an in-slab heating or cooling system, the applicant must install insulation with an R-value not less than 1 around the vertical edges of the perimeter of the slab (or) on a suspended floor install insulation with an R-value not less than 1 underneath & around the vertical edges of the perimeter of the slab
- Common toilets must have 3 star rated toilet flushing system
- Common taps must have 4 star rating
- Lift car No.1 & 2 must have fluorescent lighting and be connected to lift call button
- Ground Floor Lobby must have no mechanical ventilation, fluorescent lighting with a manual on/ manual off switch
- Hallways & Lobbles of the remaining floors must have no mechanical ventilation, fluorescent lighting with a manual on/ manual off switch
- Lift No.1 & 2 must have gearless traction with VVV F motor servicing 7 levels (including basement)
- All dwellings must have a central water tank. This tank must connect to toilets
- The development must have a central water tank-rainwater or stormwater of about 13600 litres
- The central water tank must be configured to collect 327m2 of roof area of buildings in the development
- Car park area must be ventilated by exhaust & supply air and have a carbon monoxide VSD fan. The primary type of artificial lighting is fluorescent, with time clock & motion detectors.

MACKENZIE ARCHITECTS
Chartered Architects & Strategic Planners
Carem Pty. Ltd. ACN 084 320 543

4/3 The Postern
Castlecrag - NSW - 2068
Phone: (02) 9967 9966
Fax: (02) 9967 9977
Email: info@mackenziearchitects.com.au
Chartered Architect No 6033

Job:
RESIDENTIAL FLAT BUILDING: - 1147, 1149 PACIFIC HWY & 2 BOBBIN HEAD ROAD PYMBLE

Drawing title:
PENTHOUSE LEVEL

North point:

Scale: **1:100 @ A0**
Date: **22.07.2011**
Drawn: **JA**
Checked: **DM**
Drawing no.
SK09B

Copyright

Mackenzie Architects is the owner of the copyright subsisting in these drawings, plans, designs and specifications. They must not be used, reproduced or copied in whole or in part without prior written consent of Mackenzie Architects

Copyright © 2011, Mackenzie Architects