
365 BEAMISH STREET CAMPSIE, NSW



LOCATION PLAN

Scale: NTS

DRAWING SCHEDULE

DRAWING NO.	DRAWING TITLE	REVISION
000	COVER SHEET	В
001	COLOUR LANDSCAPE PLAN	В
101	LANDSCAPE PLAN	В
501	LANDSCAPE DETAILS	В
502	LANDSCAPE DETAILS	А

PLANTING SCHEDULE

<u> </u>	365 BEAMISH STREET PLA	ANT CONEDUCE			
CODE	BOTANIC NAME	COMMON NAME	MATURE SIZE	PROPOSED POT SIZE	QUANTITY
			(h x w) (m)		
	TREES & TREE FERNS				
Ca	Cyathea australis	Rough Tree Fern	5 x 2	300mm	6
Cv	Callistemon viminalis	Weeping Bottlebrush	8 x 5	75L	3
Da	Dicksonia antarctica	Scaly Tree Fern	9 x 4	300mm	8
Ee	Elaeocarpus eumundii	Blueberry Ash	6 x 3	75L	3
Eh	Eucalyptus haemastoma	Scribbly Gum	15 x 10	75L	6
Fr	Fraxinus 'Raywood'	Claret Ash	15 x 10	75L	1
Hf	Hymenosporum flavum	Native Frangipani	10 x 5	45L	3
Mg	Magnolia grandiflora 'Little Gem'	Dwarf Magnolia	8 x 5	45L	3
	SHRUBS AND ACCENTS				
Aa	Asplenium australasicum	Birds Nest Fern	1.5 x 1.5	200mm	10
Am	Alocasia macrorrhiza	Elephants Ears	2 x 1.5	200mm	13
CI	Callistemon 'Little John'	Bottlebrush	1.5 x 1.5	150mm	115
Cr	Correa reflexa	Native Fuchsia	1.5 x 1.5	200mm	17
Cyr	Cycas revoluta	Cycad	1.5 x 1	150mm	33
Dc	Dianella caerula	Flax Lily	0.5 x 0.5	150mm	237
Dlr	Dianella revoluta 'Little Rev'	Dwarf Flax Lily	0.3 x 0.3	150mm	88
Dr	Dianella revoluta	Mauve Flax Lily	0.4 x 0.4	150mm	190
Lm	Lomandra multiflora	Mat Rush	1 x 1	150mm	50
Мр	Murraya paniculata	Mock Orange	3 x 2	150mm	88
	GROUNDCOVERS & CLIMBERS				
Do	Doodia aspera	Prickly Rasp Fern	0.5 x 0.5	150mm	369
Fp	Ficus pumila	Creeping Fig	0.25 x spreading	150mm	76
Hv	Hardenbergia violacea	False Sarsaparilla	0.5 x spreading	150mm	254
Pр	Pratia purpurascens	White Root	0.15 x spreading	150mm	115
Vh	Viola hederacea	Native Violet	0.25 x spreading	150mm	196

Issue	Revision Description	Drawn	Check	Date
Α	DEVELOPMENT APPLICATION	LP	AL	06.02.2012
В	DEVELOPMENT APPLICATION	LP	AL	17.07.2012
-	-	-	-	,,
-	-	-	-	,,
-	-	-	-	,,
-	-	-	-	,,
-	-	-	-	,,
-	-	-	-	,,
-	-	-	-	,,
-	-	-	-	,,
-	-	-	-	,,
-	-	-	-	,,
-	-	-	-	,,
-	-	-	-	,,
-	-	-	-	,,
	- -	-		

LEGEND

Notes:

Notes:

Copyright remains the property of Arcadia Landscape Architecture Pty Ltd.

Use only figured dimensions. Any other required dimensions are to be referred to and supplied by the larchitect.

Key P



365 BEAMISH PTY LTD

Landscape Architect:

LANDSCAPE ARCHITECTURE

lower deck jones bay wharf suite 123 / 26-32 pirrama rd
pyrmont 2009 nsw p 61 2 9571 6259 f 61 2 9571 7930

Project:

365 BEAMISH STREET, CAMPSIE

DEVELOPMENT APPLICATION

COVER SHEET


 Scale:

 Job Number:
 Drawing Number:
 000
 Issue:


 11-047
 Sheet 1 of 5
 B



sue	Revision Description	Drawn	Check	Date
A	DEVELOPMENT APPLICATION	LP	AL	06.02.2012
В	DEVELOPMENT APPLICATION	LP	AL	17.07.2012
-			•	,,
2	-	-	-	,,
12	-	-	-	,,
7	งหรั้วทางการพบการพระพรพาจาก และพรพาพาศาสตร์		-	,,
				,,
-	-			,,
-			*	,,
-				,,
-	.=	*	-	,,
-	-	-	-	,,
		-		,,
-		-	-	,,
-	•		•	,,



EXISTING TREES TO BE REMOVED



PROPOSED TREE PLANTING



PROPOSED SHRUB & ACCENT PLANTING



PROPOSED GROUNDCOVER PLANTING



PROPOSED FERN PLANTING



PROPOSED TURF



PROPOSED PAVING



PROPOSED PAVER INLAYS



PROPOSED STREETSCAPE PAVING DIVEWAY PAVING (Refer Architects Specifications)



PROPOSED TIMBER EDGING



PROPOSED PLANTER



PROPOSED CLIMBERS



365 BEAMISH PTY LTD

lower deck jones bay wharf suite 123 / 26-32 pirrama rd pyrmont 2009 nsw p 61 2 9571 6259 f 61 2 9571 7930


365 BEAMISH STREET, CAMPSIE

DEVELOPMENT APPLICATION


COLOUR LANDSCAPE PLAN


Scale: 1:200 @ A1





365 BEAMISH STREET PLA	ANT SCHEDOLE			
BOTANIC NAME	COMMON NAME	MATURE SIZE	PROPOSED POT SIZE	QUANTITY
		(h x w) (m)		
TREES & TREE FERNS				
Cyathea australis	Rough Tree Fern	5 x 2	300mm	6
Callistemon viminalis	Weeping Bottlebrush	8 x 5	75L	3
Dicksonia antarctica	Scaly Tree Fern	9 x 4	300mm	8
Elaeocarpus eumundii	Blueberry Ash	6 x 3	75L	3
Eucalyptus haemastoma	Scribbly Gum	15 x 10	75L	6
Fraxinus 'Raywood'	Claret Ash	15 x 10	75L	1
Hymenosporum flavum	Native Frangipani	10 x 5	4 5L	3
Magnolia grandiflora 'Little Gem'	Dwarf Magnolia	8 x 5	45L	3
SHRUBS AND ACCENTS				
Asplenium australasicum	Birds Nest Fern	1.5 x 1.5	200mm	10
Alocasia macrorrhiza	Elephants Ears	2 x 1.5	200mm	13
Callistemon 'Little John'	Bottlebrush	1.5 x 1.5	150mm	115
Correa reflexa	Native Fuchsia	1.5 x 1.5	200mm	17
Cycas revoluta	Cycad	1.5 x 1	150mm	33
Dianella caerula	Flax Lily	0.5 x 0.5	150mm	237
Dianella revoluta 'Little Rev'	Dwarf Flax Lily	0.3 x 0.3	150mm	88
Dianella revoluta	Mauve Flax Lily	0.4 x 0.4	150mm	190
Lomandra multiflora	Mat Rush	1 x 1	150mm	50
Murraya paniculata	Mock Orange	3 x 2	150mm	88
GROUNDCOVERS & CLIMBERS				
Doodia aspera	Prickly Rasp Fern	0.5 x 0.5	150mm	369
Ficus pumila	Creeping Fig	0.25 x spreading	150mm	76
Hardenbergia violacea	False Sarsaparilla	0.5 x spreading	150mm	254
Pratia purpurascens	White Root	0.15 x spreading	150mm	115
Viola hederacea	Native Violet	0.25 x spreading	150mm	196
	TREES & TREE FERNS Cyathea australis Callistemon viminalis Dicksonia antarctica Elaeocarpus eumundii Eucalyptus haemastoma Fraxinus 'Raywood' Hymenosporum flavum Magnolia grandiflora 'Little Gem' SHRUBS AND ACCENTS Asplenium australasicum Alocasia macrorrhiza Callistemon 'Little John' Correa reflexa Cycas revoluta Dianella caerula Dianella revoluta 'Little Rev' Dianella revoluta Lomandra multiflora Murraya paniculata GROUNDCOVERS & CLIMBERS Doodia aspera Ficus pumila Hardenbergia violacea Pratia purpurascens	TREES & TREE FERNS Cyathea australis Callistemon viminalis Dicksonia antarctica Elaeocarpus eumundii Eucalyptus haemastoma Fraxinus 'Raywood' Hymenosporum flavum Magnolia grandiflora 'Little Gem' SHRUBS AND ACCENTS Asplenium australasicum Alocasia macrorrhiza Callistemon 'Little John' Correa reflexa Cycas revoluta Dianella caerula Dianella revoluta 'Little Rev' Dianella revoluta 'Little Rev' Dianella revoluta Unithe Mat Rush Murraya paniculata FROUNDCOVERS & CLIMBERS Doodia aspera Ficus pumila Flas Las Care Fern Prickly Rasp Fern Ficus pumila Flas Care Palse Sarsaparilla Pratia purpurascens Rough Tree Fern Roll And Pash White Root	Cyathea australis	Cyathea australis





SHRUB OR GROUNDCOVER PLANTING ON SLAB
SCALE 1:10

Issue	Revision Description	Drawn	Check	Date
Α	DEVELOPMENT APPLICATION	LP	AL	06.02.2012
В	DEVELOPMENT APPLICATION	LP	AL	17.07.2012
-	-	-	-	,,
-	-	-	-	,,
-	-	-	-	,,
-	-	-	-	,,
-	-	-	-	,,
-	-	-	-	,,
-	-	-		,,
-	-	-	-	,,
		-		
		······		
		····· <u>·</u>		
·····				
	-	·····-	-	
	-	-		
-	-	I -	-	

LEGEND

Copyright remains the property of Arcadia Landscape Architecture Pty Ltd. Use only figured dimensions. Any other required dimensions are to be referred to and supplied by the landscape architect. All discrepancies to be referred to the project manager and Arcadia Landscape Architecture Pty Ltd prior to construction. Ensure compliance with the Building Code of Australia and all relevant Australian Standards and Authority Requirements.

365 BEAMISH PTY LTD

Landscape Architect:

lower deck jones bay wharf suite 123 / 26-32 pirrama rd pyrmont 2009 nsw p 61 2 9571 6259 f 61 2 9571 7930


365 BEAMISH STREET, CAMPSIE


DEVELOPMENT APPLICATION

Drawing Name: LANDSCAPE DETAILS

Scale: AS SHOWN

501 Issue: 11-047





502 SCALE 1:10

LANDSCAPE SPECIFICATION NOTES

BEFORE LANDSCAPE WORK IS COMMENCED THE LANDSCAPE CONTRACTOR IS TO ESTABLISH THE POSITION OF ALL SERVICE LINES AND ENSURE TREE PLANTING IS CARRIED OUT AT LEAST 3 METRES AWAY FROM THESE SERVICES. SERVICE LIDS, VENTS AND HYDRANTS SHALL BE LEFT EXPOSED AND NOT COVERED BY ANY LANDSCAPE FINISHES (TURFING, PAVING, GARDEN BEDS ETC.) FINISH ADJOINING

ABORIST MANAGEMENT OF TREE PROTECTION A QUALIFIED AND APPROVED ABORIST IS TO BE CONTRACTED TO UNDERTAKE OR MANAGE THE INSTALLATION OF PROTECTIVE FENCING, AND TO UNDERTAKE SUCH MEASURES AS HE DEEMS APPROPRIATE TO PRESERVE THE SUBJECT TREES TO BE RETAINED. THE ARBORIST IS TO BE RETAINED FOR THE ENTIRE CONTRACT PERIOD TO UNDERTAKE ONGOING MANAGEMENT AND REVIEW OF THE TREES.

DRAINAGE CELL AND FILTER FARRIC

FOR ON-SLAB AREAS INSTALL AN APPROVED 'DRAINAGE CELL' PRODUCT TO COMPREHENSIVELY COVER THE BOTTOM OF ALL PLANTERS. OVER DRAINAGE CELL TO ON-SLAB AREAS, A POLYFELT GEOTEXTILE LINING (AS SUPPLIED BY 'POLYFELT TS' OR APPROVED EQUIVALENT) IS TO BE INSTALLED TO COVER THE BOTTOM OF ALL PLANTERS. TURNED UP 300MM AND TAPED TO THE PLANTER SIDES TO ENSURE SOIL MIX DOES NOT ESCAPE INTO DRAINAGE OUTLETS/HOLES. INSTALL MIN. 50MM COARSE RIVER SAND OVER ALL GEOTEXTILE LINING PRIOR TO INSTALLATION OF SOIL MIX.

SHALL BE HOMOGENOUS BLEND OF SOIL AND ADDITIVES IN THE FOLLOWING PROPORTIONS:

IMPORTED TOPSOIL 50%

COMPOST 30% D/W SAND 20%

SOIL TESTING OF EXISTING SITE SOIL IS TO BE UNDERTAKEN TO ASSESS SUITABILITY OF USE AS PLANTING TOPSOIL AND COMPLIANCE WITH AUSTRALIAN STANDARDS.

PLACE MULCH TO THE REQUIRED DEPTH, (REFER TO DRAWINGS) CLEAR OF PLANT STEMS, AND RAKE TO AN EVEN SURFACE FINISHING 25MM BELOW ADJOINING LEVELS. ENSURE MULCH IS WATERED IN AND TAMPED DOWN DURING INSTALLATION.

PINE BARK: FROM MATURE TREES, GRADED IN SIZE FROM 15MM TO 30MM, FREE FROM WOOD SLIVERS. DARK BROWN IN COLOUR AND TEXTURE.

SHALL BE WELL ROTTED VEGETATIVE MATERIAL OR ANIMAL MANUER OR OTHER APPROVED MATERIAL FREE FROM HARMEUL CHEMICALS, GRASS AND WEED GROWTH AND WITH NEUTRAL PH. PROVIDE A CERTIFICATE OF PROOF OF PH UPON REQUEST.

ALL PLANTS SUPPLIED ARE TO CONFORM WITH THOSE SPECIES LISTED IN THE PLANT SCHEDULE ON THE DRAWINGS, GENERALLY PLANTS SHALL BE VIGOROUS, WELL ESTABLISHED, HARDENED OFF, OF GOOD FORM CONSISTENT WITH SPECIES OR VARIETY, NOT SOFT OR FORCED, FREE FROM DISEASE OR INSECT PESTS WITH LARGE HEALTHY ROOT SYSTEMS AND NO EVIDENCE OF HAVING BEEN RESTRICTED OR DAMAGED. TREES SHALL HAVE A LEADING SHOOT. IMMEDIATELY REJECT DRIED OUT, DAMAGED OR UNHEALTHY PLANT MATERIAL BEFORE PLANTING. ALL STOCK IS TO BE CONTAINER GROWN FOR A MINIMUM OF SIX (6 MONTHS PRIOR TO DELIVERY TO SITE

FERTILISER MASS PLANTING AREAS:

FERTILISER SHALL BE 'NUTRICOTE' OR APPROVED EQUIVALENT IN GRANULE FORM INTENDED FOR SLOW RELEASE OF PLANT NUTRIENTS OVER A PERIOD OF APPROXIMATELY NINE MONTHS. THOROUGHLY MIX FERTILISER WITH PLANTING MIXTURE AT THE RECOMMENDED

SHALL BE SHIRLEYS NO. 17 OR APPROVED EQUAL THOROUGHLY MIXED INTO THE TOPSOIL PRIOR TO PLACING TURF. TREES IN GRASS AND SUPER ADVANCED TREES: PELLETS SHALL BE IN THE FORM INTENDED TO UNIFORMLY RELEASE PLANT FOOD ELEMENTS FOR A PERIOD OF APPROXIMATELY NINE MONTHS EQUAL TO SHIRLEYS KOKEI PELLETS, ANALYSIS 6.3:1.8:2.9. KOKEI PELLETS SHALL BE PLACED AT THE TIME OF PLANTING TO THE

BASE OF THE PLANT, 50MM MINIMUM FROM THE ROOT BALL AT A RATE OF TWO PELLETS PER 300MM OF TOP GROWTH TO A MAXIMUM

OF 8 PELLETS PER TREE. STAKING AND TYING

STAKES SHALL BE STRAIGHT HARDWOOD, FREE FROM KNOTS AND TWISTS, POINTED AT ONE END AND SIZED ACCORDING TO SIZE

OF PLANTS TO BE STAKED.

A. 5-15 LITRE SIZE PLANT 1X(1200X25X25MM) B. 35-75 LITRE SIZE PLANT 2X(1500X38X38MM)

SUPERINTENDENT PRIOR TO INSTALLATION

C. 100-GREATER THAN 200LITRE 3X(1800X50X50MM) TIES SHALL BE 50MM WIDE HESSIAN WEBBING OR APPROVED EQUIVALENT NAILED OR STAPLED TO STAKE, DRIVE STAKES A MINIMUM ONE THIRD OF THEIR LENGTH, AVOIDING DAMAGE TO THE ROOT SYSTEM, ON THE WINDWARD SIDE OF THE PLANT.

SUPPLY AN AUTOMATIC WATERING SYSTEM USING 'TORO IRRIGATION SYSTEM' OR SIMILAR APPROVED, WITH MICRO-JET SPRINKLER HEADS AND LOW DENSITY, RUBBER MODIFIED POLYPROPYLENE RETICULATION, TO INCLUDE FILTERS, BENDS JUNCTIONS, ENDS AND OTHER ANCILLARY EQUIPMENT. THE LANDSCAPER SHALL NOMINATE HIS SOURCE OF SUPPLY FOR THE WATERING SYSTEM AND OBTAIN APPROVAL FROM THE SUPERINTENDENT BEFORE PLACING ORDERS FOR EQUIPMENT OR SUPPLY.

A SCHEMATIC PLAN OF THE PROPOSED IRRIGATION SYSTEM IS TO BE PREPARED BY THE CONTRACTOR, SHOWING SOLENOIDS, PIPE DIAMETERS, AND ALL NOZZLE AND TRICKLE ATTACHMENT TYPES (INCLUDING SPRAY/HEAD ANGLE), FOR REVIEW BY THE

THE CONTRACTOR IS TO LIASE WITH THE HYDRAULIC ENGINEER AND COUNCIL AS NECESSARY, TO ENSURE THE THE IRRIGATION SYSTEM

CONFORMS WITH ALL THE COUNCIL AND WATER BOARD CODES AND REQUIREMENTS. PROVIDE AN AUTOMATIC CONTROLLER THAT PROVIDES FOR TWO WEEK SCHEDULING AND HOURLY MULTI-CYCLE OPERATION. THE CONTROLLER SHALL MANUAL OVERRIDE. PROGRAMMING SHALL BE UNDERTAKEN BY THE CONTRACTOR WHO SHALL ADVISE ON THE

PROVISION OF SECURE HOUSING FOR THE AUTOMATIC IRRIGATION CONTROLLER TO BE LOCATED IN ASSOCIATION WITH THE LANDSCAPE CONTRACTOR AND LOCATION CONFIRMED BY THE SUPERINTENDENT. WIRING TO CONNECT REMOTE SOLENOID LOCATIONS IS TO BE PROVIDED. THE CONTROLLER SHALL BE LOCATED IN A DRY PLACE, PROTECTED FROM THE WEATHER, AND ALL CABLE CONNECTIONS SHALL BE MADE WITH WATERPROOF CONNECTORS.

WATER SUPPLY POINTS TO BE SUPPLIED BY BUILDER.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ENSURE AND GUARANTEE SATISFACTORY OPERATION OF THE IRRIGATION

AFTER THE SYSTEM HAS BEEN INSTALLED TO THE SATISFACTION OF THE SUPERINTENDENT, THE INSTALLATION SHALL BE TESTED UNDER KNOWN WORKING CONDITIONS. ACCEPTANCE OF THE INSTALLED PLANT AND EQUIPMENT SHALL BE SUBJECT TO THESE BEING

TREATED PINE TIMBER EDGING TIMBER EDGE: 100 X 25MM CCA TREATED RADIATA PINE TIMBER STAKES: 50 X 50 X 500MM CCA TREATED RADIATA PINE-SHARPENED AT ONE END, INSTALL IN LOCATIONS SHOWN ON THE DRAWINGS FLUSH TO FINISHED SURFACE LEVELS.

TURF ALL LANDSCAPE AREAS AS SHOWN ON THE LANDSCAPE DRAWINGS. TURF IS TO HAVE AN EVEN THICKNESS OF NOT LESS THAN 25MM, OBTAIN TURF FROM AN APPROVED GROWER, FURNISH A WARRANTY FROM THE GROWER THAT THE TURF IS FREE FROM WEEDS AND OTHER FOREIGN MATTER. DELIVER TURF TO THE SITE WITHIN 24 HOURS OF BEING CUT, AND LAY IT WITHIN 24 HOURS OF BEING

TO PREPARE GRADED AREAS TO RECEIVE TURF, EXCAVATE THE AREA AND CULTIVATE SO AS TO ALLOW FOR IMPORTING OF 100MM OF TURF UNDERLAY SOIL. REMOVE ALL STONES OVER 50MM Ø AND REMOVE ALL WEEDS AND FOREIGN MATTER. SPREAD SOIL MIX A.B.S TO A DEPTH OF 100MM AND GRADE TO APPROPRIATE LEVELS TO ACHIEVE GENERAL EVEN GRADES TO DRAINAGE OUTLETS INSTALLED BY

LAY THE TURF ALONG THE LAND CONTOURS WITH STAGGERED, CLOSE BUTTED JOINTS, SO THAT THE FINISHED TURF SURFACE IS FLUSH WITH ADJACENT FINISHED SURFACES OF PAVING AND THE LIKE. AS SOON AS PRACTICABLE AFTER LAYING, ROLL THE TURF WITH A ROLLER WEIGHING NOT MORE THAN 90KG PER METRE OF WIDTH FOR SANDY OR LIGHT SOILS.

WATER AS NECESSARY TO KEEP THE SOIL MOIST TO A DEPTH OF 100MM. PROTECT NEWLY TURFED AREAS AGAINST TRAFFIC UNTIL GRASS IS ESTABLISHED, FERTILISE TWO WEEKS AFTER LAYING FERTILISE A.B.S

'TOP DRESS' THE TURF WHEN IT IS ESTABLISHED TO A DEPTH OF 10MM WITH COARSE WASHED RIVER SAND. RUB THE DRESSING WELL INTO THE JOINTS AND CORRECT ANY UNEVENNESS IN THE TURF SURFACES.

LANDSCAPE MAINTENANCE PROGRAM

MAINTENANCE SHALL MEAN THE CARE AND MAINTENANCE OF THE LANDSCAPE WORKS BY ACCEPTED HORTICULTURAL PRACTICE AS RECTIFYING ANY DEFECTS THAT BECOME APPARENT IN THE LANDSCAPE WORKS UNDER NORMAL USE. THIS SHALL INCLUDE, BUT SHALL NOT BE LIMITED TO, WATERING, MOWING, FERTILISING, RESEEDING, RETURFING, WEEDING, PEST AND DISEASE CONTROL, STAKING AND TYING, REPLANTING, CULTIVATION, PRUNING, AERATING, RENOVATING, TOP DRESSING, MAINTAINING THE SITE IN A NEAT AND

THE LANDSCAPE CONTRACTOR SHALL MAINTAIN THE LANDSCAPE WORKS FOR THE TERM OF THE MAINTENANCE (OR PLANT ESTABLISHMENT) PERIOD TO THE SATISFACTION OF THE COUNCIL. THE LANDSCAPE CONTRACTOR SHALL ATTEND TO THE SITE ON A WEEKLY BASIS. THE MAINTENANCE PERIOD SHALL COMMENCE AT PRACTICAL COMPLETION AND CONTINUE FOR A PERIOD OF TWENTY

WATERING GRASS, TREES AND GARDEN AREAS SHALL BE WATERED REGULARLY SO AS TO ENSURE CONTINUOUS HEALTHY GROWTH.

RUBBISH REMOVAL

DURING THE TERM OF THE MAINTENANCE PERIOD THE LANDSCAPE CONTRACTOR SHALL REMOVE RUBBISH THAT MAY OCCUR AND REOCCUR THROUGHOUT THE MAINTENANCE PERIOD. THIS WORK SHALL BE CARRIED OUT REGULARLY SO THAT AT WEEKLY INTERVALS THE AREA MAY BE OBSERVED IN A COMPLETELY CLEAN AND TIDY CONDITION.

REPLACEMENTS

THE LANDSCAPE CONTRACTOR SHALL REPLACE ALL PLANTS THAT ARE MISSING, UNHEALTHY OR DEAD AT THE LANDSCAPE CONTRACTOR'S COST. REPLACEMENTS SHALL BE OF THE SAME SIZE, QUALITY AND SPECIES AS THE PLANT THAT HAS FAILED UNLESS OTHERWISE DIRECTED BY THE LANDSCAPE ARCHITECT, REPLACEMENTS SHALL BE MADE ON A CONTINUING BASIS NOT EXCEEDING TWO (2) WEEKS AFTER THE PLANT HAS DIED OR IS SEEN TO BE MISSING.

STAKES AND TIES

THE LANDSCAPE CONTRACTOR SHALL REPLACE OR ADJUST PLANT STAKES, AND TREE GUARDS AS NECESSARY OR AS DIRECTED BY THE LANDSCAPE ARCHITECT. REMOVE STAKES AND TIES AT THE END OF THE MAINTENANCE PERIOD IF SO DIRECTED.

TREES AND SHRUBS SHALL BE PRUNED AS DIRECTED BY THE LANDSCAPE ARCHITECT. PRUNING WILL BE DIRECTED AT THE MAINTENANCE OF THE DENSE FOLIAGE OR MISCELLANEOUS PRUNING AND BENEFICIAL TO THE CONDITION OF THE PLANTS. ANY

DAMAGED GROWTH SHALL BE PRUNED. ALL PRUNED MATERIAL SHALL BE REMOVED FROM THE SITE.

ALL MULCHED SURFACES SHALL BE MAINTAINED IN A CLEAN AND TIDY CONDITION AND BE REINSTATED IF NECESSARY TO ENSURE THAT A DEPTH OF 75MM IS MAINTAINED. ENSURE MULCH IS KEPT CLEAR OF PLANT STEMS AT ALL TIMES.

PEST AND DISEASE CONTROL


THE LANDSCAPE CONTRACTOR SHALL SPRAY AGAINST INSECT AND FUNGUS INFESTATION WITH ALL SPRAYING TO BE CARRIED OUT IN ACCORDANCE WITH THE MANUFACTURER'S DIRECTIONS. REPORT ALL INSTANCES OF PESTS AND DISEASES (IMMEDIATELY THAT THEY ARE DETECTED) TO THE LANDSCAPE ARCHITECT.

GRASS AND TURF AREAS

THE LANDSCAPE CONTRACTOR SHALL MAINTAIN ALL GRASS AND TURF AREAS BY WATERING, WEEDING, DRESEEDING, ROLLING, MOWING, TRIMMING OR OTHER OPERATIONS AS NECESSARY. SEED AND TURF SPECIES SHALL BE THE SAME AS THE ORIGINAL SPECIFIED MIXTURE. GRASS AND TURF AREAS SHALL BE SPRAYED WITH APPROVED SELECTIVE HERBICIDE AGAINST BROAD LEAFED WEEDS AS REQUIRED BY THE LANDSCAPE ARCHITECT AND IN ACCORDANCE WITH THE MANUFACTURER'S DIRECTIONS, GRASS AND TURF AREAS SHALL BE FERTILISED ONCE A YEAR IN AUTUMN WITH "DYNAMIC LIFTER" FOR LAWNS AT A RATE OF 20KG PER 100M2. FERTILISER SHALL BE WATERED IN IMMEDIATELY AFTER APPLICATION. IRREGULARITIES IN THE GRASS AND TURF SHALL BE WATERED IN IMMEDIATELY AFTER APPLICATION. GRASS AND TURF AREAS SHALL BE KEPT MOWN TO MAINTAIN A HEALTHY AND VIGOROUS SWARD. MOWING HEIGHT: 30-50MM.

ERADICATE WEEDS BY ENVIRONMENTALLY ACCEPTABLE METHODS USING A NON-RESIDUAL GLYPHOSATE HERBICIDE (EG. 'ROUNDUP') IN ANY OF ITS REGISTERED FORMULAE, AT THE RECOMMENDED MAXIMUM RATE. REGULARLY REMOVE BY HAND, WEED GROWTH THAT MAY OCCUR OR RECUR THROUGHOUT GRASSED, PLANTED AND MULCHED AREAS. REMOVE WEED GROWTH FROM AN AREA 750MM DIAMETER AROUND THE BASE OF TREES IN GRASSED AREAS. CONTINUE ERADICATION THROUGHOUT THE COURSE OF THE WORKS AND DURING THE MAINTENANCE PERIOD.

SOIL SUBSIDENCE ANY SOIL SUBSIDENCE OR EROSION WHICH MAY OCCUR AFTER THE SOIL FILLING AND PREPARATION OPERATIONS SHALL BE MADE GOOD BY THE LANDSCAPE CONTRACTOR AT NO COST TO THE CLIENT.



Use only figured dimensions. Any other required dimensions are to be referred to and supplied by the landscape All discrepancies to be referred to the project manager and Arcadia Landscape Architecture Pty Ltd prior to

Ensure compliance with the Building Code of Australia and all relevant Australian Standards and Authority

365 BEAMISH PTY LTD

lower deck jones bay wharf suite 123 / 26-32 pirrama rd pyrmont 2009 nsw p 61 2 9571 6259 f 61 2 9571 7930

365 BEAMISH STREET, CAMPSIE

DEVELOPMENT APPLICATION

LANDSCAPE DETAILS

Scale: AS SHOWN

502 11-047