

1. Approved architectural plans and documentation

The development must be carried out in accordance with the following plans and documentation listed below and endorsed with Council's stamp, except where amended by other conditions of this consent:

Plan no.	Drawn by	Dated
DA-A102	Architectus	16/02/13
DA-A109	Architectus	16/02/13
DA-A110	Architectus	16/02/13
DA-A111	Architectus	16/02/13
DA-A112 – Level 2	Architectus	16/02/13
DA-A113 – Level 3	Architectus	16/02/13
DA-A114 – Level 4	Architectus	16/02/13
DA-A115 – Level 5	Architectus	16/02/13
DA-A116 – Roof	Architectus	16/02/13
DA-A200 Building A – East & West Elevations	Architectus	16/02/13
DA-A201 Building A & B – North & South Elevations	Architectus	16/02/13
DA-A202 Building B – East & West Elevations	Architectus	16/02/13
DA-A210 – Sections A & B	Architectus	16/02/13
DA-A211 – Sections C to H	Architectus	16/02/13
DA-A920 – Environmental Site Management Plan	Architectus	16/02/13
SK-31 – External Works Details – Fences and Screens	Architectus	30/11/2011
SK-37 – Way Finding Diagram	Architectus	16/02/13
005 – Colour Landscape Plan	Arcadia	14/02/13
006 – Path Hierarchy	Arcadia	14/02/13
100 – Master Landscape Plan	Arcadia	14/02/13
101 – Grading & Soil Plan	Arcadia	14/02/13
401 – Landscape Plan	Arcadia	14/02/13
402 – Landscape Plan	Arcadia	14/02/13
403 – Landscape Plan	Arcadia	14/02/13
404 – Landscape Plan	Arcadia	14/02/13
501 – Landscape Details	Arcadia	14/02/13
502 – Landscape Details	Arcadia	14/02/13
503 – Landscape Details	Arcadia	14/02/13
601 – Landscape Sections	Arcadia	14/02/13
602 – Landscape Sections	Arcadia	14/02/13
C005 – Bulk Earthworks Plan	Bonacci	20.12.12
C006 – Bulk Earthworks Sections Sheet 1	Bonacci	20.12.12
C007 – Bulk Earthworks Section Sheet 2	Bonacci	20.12.12

Co15 – Stormwater Plan	Bonacci	13.02.13
Co35 – Stormwater Details Sheet 1	Bonacci	20.12.12
Co36 – Stormwater Details Sheet 2	Bonacci	20.12.12
Co40 – Pavement Plan	Bonacci	13.02.13
Co45 – Pavement Details	Bonacci	20.12.12

Document(s)	Dated
Colours and finishes schedule Precinct 3 Edgelea Lindfield	undated
Bush fire risk assessment and certification, prepared by Daniel Copland - Project No. 11GOSBUS-0152	20 February 2013
Acoustic Assessment – Precinct 4 Report No. 12180-P3 Version C, prepared by Wilkinson Murray	December 2012
Typical storage area fit out	Undated

Reason: To ensure that the development is in accordance with the determination

2. Inconsistency between documents

In the event of any inconsistency between conditions of this consent and the drawings/documents referred to above, the conditions of this consent prevail.

Reason: To ensure that the development is in accordance with the determination.

Conditions to be satisfied prior to demolition, excavation or construction:

3. Road opening permit

The opening of any footway, roadway, road shoulder or any part of the road reserve shall not be carried out without a road opening permit being obtained from Council (upon payment of the required fee) beforehand.

Reason: Statutory requirement (Roads Act 1993 Section 138) and to maintain the integrity of Council's infrastructure.

4. Notice of commencement

At least 48 hours prior to the commencement of any development (including demolition, excavation, shoring or underpinning works), a notice of commencement of building or subdivision work form and appointment of the principal certifying authority form shall be submitted to Council.

Reason: Statutory requirement.

5. Notification of builder's details

Prior to the commencement of any development or excavation works, the Principal Certifying Authority shall be notified in writing of the name and contractor licence number of the owner/builder intending to carry out the approved works.

Reason: Statutory requirement.

6. Dilapidation survey and report (public infrastructure)

Prior to the commencement of any development or excavation works on site, the Principal Certifying Authority shall be satisfied that a dilapidation report on the visible and structural condition of all structures of the following public infrastructure, has been completed and submitted to Council:

Public infrastructure

- Grosvenor Road, Austral Avenue, Eton Road (Austral Avenue to site entrance).
- Road 1 from Eton Road to Precinct 3 site access point.

The report must be completed by a consulting structural/civil engineer. Particular attention must be paid to accurately recording (both written and photographic) existing damaged areas on the aforementioned infrastructure so that Council is fully informed when assessing any damage to public infrastructure caused as a result of the development.

The developer may be held liable to any recent damage to public infrastructure in the vicinity of the site, where such damage is not accurately recorded by the requirements of this condition prior to the commencement of works.

Note: A written acknowledgment from Council must be obtained (attesting to this condition being appropriately satisfied) and submitted to the Principal Certifying Authority prior to the commencement of any excavation works.

Reason: To record the structural condition of public infrastructure before works commence.

7. Dilapidation survey and report (private property)

Prior to the commencement of any demolition or excavation works on site, the Principal Certifying Authority shall be satisfied that a dilapidation report on the visible and structural condition of the gymnasium building has been completed and submitted to Council.

The dilapidation report must include a photographic survey of adjoining properties detailing their physical condition, both internally and externally, including such items as walls ceilings, roof and structural members. The report must be completed by a

consulting structural/geotechnical engineer as determined necessary by that professional based on the excavations for the proposal and the recommendations of the submitted geotechnical report.

In the event that access for undertaking the dilapidation survey is denied by a property owner, the applicant must demonstrate in writing to the satisfaction of the Principal Certifying Authority that all reasonable steps have been taken to obtain access and advise the affected property owner of the reason for the survey and that these steps have failed.

Note: A copy of the dilapidation report is to be provided to Council prior to any excavation works been undertaken. The dilapidation report is for record keeping purposes only and may be used by an applicant or affected property owner to assist in any civil action required to resolve any dispute over damage to adjoining properties arising from works.

Reason: To record the structural condition of likely affected properties before works commence.

8. Construction and traffic management plan

The applicant must submit to Council a Construction Traffic Management Plan (CTMP), which is to be approved prior to the commencement of any works on site.

The plan is to consist of a report with Traffic Control Plans attached.

The report is to contain commitments which must be followed by the demolition and excavation contractor, builder, owner and subcontractors. The CTMP applies to all persons associated with demolition, excavation and construction of the development.

The report is to contain construction vehicle routes for approach and departure to and from all directions.

The report is to contain a site plan showing entry and exit points. Swept paths are to be shown on the site plan showing access and egress for an 11 metre long heavy rigid vehicle.

The Traffic Control Plans are to be prepared by a qualified person (red card holder). One must be provided for each of the following stages of the works:

- Excavation
- Concrete pour

Traffic controllers must be in place at the site entry and exit points to control heavy vehicle movements in order to maintain the safety of pedestrians and other road users.

When a satisfactory CTMP is received, a letter of approval will be issued with conditions attached. Traffic management at the site must comply with the approved CTMP as well

as any conditions in the letter issued by Council. Council's Rangers will be patrolling the site regularly and fines may be issued for any non-compliance with this condition.

Reason: To ensure that appropriate measures have been considered during all phases of the construction process in a manner that maintains the environmental amenity and ensures the ongoing safety and protection of people.

9. Erosion and drainage management

Earthworks and/or demolition of any existing buildings shall not commence until an erosion and sediment control plan is submitted to and approved by the Principal Certifying Authority. The plan shall comply with the guidelines set out in the NSW Department of Housing manual "Managing Urban Stormwater: Soils and Construction" certificate. Erosion and sediment control works shall be implemented in accordance with the erosion and sediment control plan.

Reason: To preserve and enhance the natural environment.

10. Tree protection fencing/ground protection

To preserve the following tree/s, no work shall commence until the area beneath their canopy is fenced off or ground protection installed as per following Tree Management Plans to prevent any activities, storage or the disposal of materials within the fenced area. The fencing/ground protection shall be maintained intact until the completion of all demolition/building work on site.

Plan no.	Drawn by	Date
TMP01 Sheets 1 – 4	Naturally Trees	11/12/12

The tree protection fencing shall be constructed of galvanised pipe at 2.4 metres spacing's and connected by securely attached chain mesh fencing to a minimum height of 1.8 metres in height prior to work commencing. Ground protection shall be in accordance with AS4970-2009 Protection of trees on development sites.

Reason : To protect existing trees during construction phase

11. Tree fencing inspection

Upon installation of the required tree protection measures, an inspection of the site by the Principal Certifying Authority is required to verify that tree protection measures comply with all relevant conditions.

Reason: To protect existing trees during the construction phase.

12. Fauna protection

Prior to works commencing and/or tree removal works a qualified ecologist shall investigate all trees for fauna occupation. In accordance with appropriate licensing

requirements the ecologist shall supervise the relocation of any fauna found within the trees approved for removal.

The qualified ecologist must hold an Animal Ethics Permit from the Office of Environment & Heritage and a wildlife licence under section 132C of the National Parks and Wildlife Act 1974 issued by the Office of Environment and Heritage.

Evidence of engagement of the qualified ecologist and the required licensing must be provided to the Private Certifying Authority with a copy to Council prior to the trees being removed.

Reason: To ensure protection of native fauna species.

13. Project ecologist

A Project Ecologist shall be commissioned prior to the release of the relevant Construction Certificate to ensure all bushland/environmental protection measures are carried out in accordance with the conditions of consent.

The Project Ecologist shall have a minimum qualification of TAFE Certificate III in Bush Regeneration or Conservation and Land Management – Natural Area Restoration. He/she shall have at least 4 years experience in the management of native bushland in the Sydney region. Details of the [ecologist](#) including name, business name and contact details shall be provided to the Principal Certifying Authority with a copy to Council.

Reason: To ensure the protection of existing biodiversity values of the site

14. Nest boxes

Prior to works commencing and/or tree removal works being undertaken nine nest boxes comprising of 3 small mammal, 3 microbat & 3 medium mammal, shall be installed within the retained (bushland) area to the west of the proposed development. The nest boxes shall be constructed of durable wood material (marine ply) and installed at a minimum height of 6 metres from the ground and positioned under the direction of a qualified ecologist.

The qualified ecologist must hold an Animal Ethics Permit from the Office of Environment & Heritage and a wildlife licence under section 132C of the *National Parks and Wildlife Act 1974* issued by the Office of Environment and Heritage.

Reason: To ensure protection of native fauna species.

15. Construction waste management plan

Prior to the commencement of any works, the Principal Certifying Authority shall be satisfied that a waste management plan, prepared by a suitably qualified person, has been prepared in accordance with Council's DCP 40 – Construction and Demolition Waste Management.

The plan shall address all issues identified in DCP 40, including but not limited to: the estimated volume of waste and method for disposal for the construction and operation phases of the development.

Note: The plan shall be provided to the Certifying Authority.

Reason: To ensure appropriate management of construction waste.

16. Noise and vibration management plan

Prior to the commencement of any works, a noise and vibration management plan is to be prepared by a suitably qualified expert addressing the likely noise and vibration from demolition, excavation and construction of the proposed development and provided to the Principal Certifying Authority. The management plan is to identify amelioration measures to achieve the best practice objectives of AS 2436-2010 and NSW Department of Environment and Climate Change Interim Construction Noise Guidelines. The report shall be prepared in consultation with any geotechnical report that itemises equipment to be used for excavation works.

The management plan shall address, but not be limited to, the following matters:

- identification of the specific activities that will be carried out and associated noise sources
- identification of all potentially affected sensitive receivers, including residences, churches, commercial premises, schools and properties containing noise sensitive equipment
- the construction noise objective specified in the conditions of this consent
- the construction vibration criteria specified in the conditions of this consent
- determination of appropriate noise and vibration objectives for each identified sensitive receiver
- noise and vibration monitoring, reporting and response procedures
- assessment of potential noise and vibration from the proposed demolition, excavation and construction activities, including noise from construction vehicles and any traffic diversions
- description of specific mitigation treatments, management methods and procedures that will be implemented to control noise and vibration during construction
- construction timetabling to minimise noise impacts including time and duration restrictions, respite periods and frequency
- procedures for notifying residents of construction activities that are likely to affect their amenity through noise and vibration
- contingency plans to be implemented in the event of non-compliances and/or noise complaints

Reason: To protect the amenity afforded to surrounding residents during the construction process.

Conditions to be satisfied prior to the issue of the construction certificate:

17. Amendments to approved landscape plans

Prior to the issue of a relevant Construction Certificate, the Principal Certifying Authority shall be satisfied that the approved landscape plans, listed below and endorsed with Council's stamp, have been amended in accordance with the requirements of this condition as well as other conditions of this consent:

Plan no.	Drawn by	Date
As per Cover Sheet, dwg no 000 Issue C	Arcadia	14/02/13

The following changes are required to the landscape plan:

1. Existing trees to be retained shall be clearly numbered on the landscape plan with contours or spot level at the base of the tree. Where an arborist report is undertaken, tree numbers shall be consistent with the arborist report.
2. To provide clear access to the local walking trails, the path diagram should include way-finding signage at the top of the stair access on the southern side of the basement entry.
3. Access is to be provided to the lawn areas within the common open space along the western boundary.
4. The specified automatic irrigation system to the podium area shall be substituted with a system that utilises soil moisture sensors and associated regulators, to ensure correct watering of the proposed indigenous/low water use plant species within all areas of the proposed podium (Landscape specification notes, dwg 501/C, Arcadia, 14/02/13).
5. The dimensions and planting for the overland flow swale are to be consistent with the civil drawings by Bonacci.

Prior to the issue of the Construction Certificate, the Principal Certifying Authority shall be satisfied that the landscape plan has been amended are required by this condition.

Note: An amended plan, prepared by a landscape architect or qualified landscape designer shall be submitted to the Certifying Authority.

Reason: To ensure adequate landscaping of the site.

18. Amendments to Environmental Site Management Plan

Prior to the issue of the Construction Certificate, the Principal Certifying Authority shall be satisfied that the approved plans, listed below and endorsed with Council's stamp, have been amended in accordance with the requirements of this condition as well as

other conditions of this consent:

Plan no.	Drawn by	Date
DA-Ag20 Issue B	Architectus	16/02/13

The following changes are required to the Environmental Site Management Plan:

1. The protective fencing along the base of the retained embankment is incorrect. The fencing is to be shown at the toe of the base as per the Bulk Earthworks Plan, Bonacci, dwg SK02/P3, 20/08/12. The fence is to extend along the entire length of the retained embankment to the north-east corner of the site.
2. The protective fencing for Trees 496, 497 and 499 is to include the existing rock outcrops as indicated on the Landscape Plan (Dwg 402B, Arcadia, 30/11/12).

Prior to the issue of the relevant Construction Certificate, the Principal Certifying Authority shall be satisfied that the environmental site management plan has been submitted as required by this condition.

Note: A site management plan shall be submitted to the Certifying Authority.

Reason: To ensure that the development is in accordance with the determination.

19. Rainwater retention and re-use

Prior to the issue of the relevant Construction Certificate, the Principal Certifying Authority shall be satisfied that a minimum rainwater retention tank volume of 195 cubic metres will be provided (this includes 25 cubic metres for fire fighting) and rainwater re-use for washing machine cold water will be included.

Reason: To achieve the objectives of the concept plan approval and the Northrop Stormwater Management Plan.

20. Long service levy

In accordance with Section 109F(i) of the Environmental Planning and Assessment Act a Construction Certificate shall not be issued until any long service levy payable under Section 34 of the Building and Construction Industry Long Service Payments Act 1986 (or where such levy is payable by instalments, the first instalment of the levy) has been paid. Council is authorised to accept payment. Where payment has been made elsewhere, proof of payment is to be provided to Council.

Reason: Statutory requirement.

21. Builder's indemnity insurance

The applicant, builder, developer or person who does the work on this development, must arrange builder's indemnity insurance and submit the certificate of insurance in

accordance with the requirements of Part 6 of the Home Building Act 1989 to the Certifying Authority for endorsement of the plans accompanying the Construction Certificate.

It is the responsibility of the applicant, builder or developer to arrange the builder's indemnity insurance for residential building work over the value of \$20,000. The builder's indemnity insurance does not apply to commercial or industrial building work or to residential work valued at less than \$20,000, nor to work undertaken by persons holding an owner/builder's permit issued by the Department of Fair Trading (unless the owner/builder's property is sold within 7 years of the commencement of the work).

Reason: Statutory requirement.

22. External service pipes and the like prohibited

Proposed water pipes, waste pipes, stack work, duct work, mechanical ventilation plant and the like must be located within the building. Details confirming compliance with this condition must be shown on construction certificate plans and detailed with relevant Construction Certificate specifications. Required external vents or vent pipes on the roof or above the eaves must be shown on construction certificate plans and detailed with the Construction Certificate specifications. External vents or roof vent pipes must not be visible from any place unless detailed upon development consent plans. Where there is any proposal to fit external service pipes or the like this must be detailed in an amended development (S96) application and submitted to Council for determination.

Vent pipes required by Sydney Water must not be placed on the front elevation of the building or front roof elevation. The applicant, owner and builder must protect the appearance of the building from the public place and the appearance of the streetscape by elimination of all external services excluding vent pipes required by Sydney Water and those detailed upon development consent plans.

Reason: To protect the streetscape and the integrity of the approved development.

23. Access for people with disabilities (residential)

Prior to the issue of the relevant Construction Certificate, the Certifying Authority shall be satisfied that access for people with disabilities to and from and between the public domain, residential units and all common open space areas is provided. Consideration must be given to the means of dignified and equitable access.

Compliant access provisions for people with disabilities shall be clearly shown on the plans submitted with the Construction Certificate. All details shall be provided to the Principal Certifying Authority prior to the issue of the Construction Certificate. All details shall be prepared in consideration of the Disability Discrimination Act, and the relevant provisions of AS1428.1, AS1428.2, AS1428.4 and AS 1735.12.

Reason: To ensure the provision of equitable and dignified access for all people in

accordance with disability discrimination legislation and relevant Australian Standards.

24. Adaptable units

Prior to the issue of the relevant Construction Certificate, the Certifying Authority shall be satisfied that the nominated adaptable units within the development application, AGo4, AGo8, A1o4, A1o8, B1o7, A2o4, A2o8, B2o7, A3o4, A3o8, B3o7, A4o4, A4o8, B4o7, B5o7 are designed as adaptable housing in accordance with the provisions of Australian Standard AS4299-1995: Adaptable Housing.

Note: Evidence from an appropriately qualified professional demonstrating compliance with this control is to be submitted to and approved by the Certifying Authority prior to the issue of the Construction Certificate.

Reason: Disabled access & amenity.

25. Excavation for services

Prior to the issue of the relevant Construction Certificate, the Principal Certifying Authority shall be satisfied that no proposed underground services (i.e.: water, sewerage, drainage, gas or other service) unless previously approved by conditions of consent, are located beneath the canopy of any tree protected under Council's Tree Preservation Order, located on the subject allotment and adjoining allotments.

Note: A plan detailing the routes of these services and trees protected under the Tree Preservation Order shall be submitted to the Principal Certifying Authority.

Reason: To ensure the protection of trees.

26. Driveway grades – basement car parks

Prior to the issue of the relevant Construction Certificate, longitudinal driveway sections are to be prepared by a qualified civil/traffic engineer and be submitted for to and approved by the Certifying Authority. These profiles are to be at 1:100 scale along both edges of the proposed driveway, starting from the centreline of the frontage street carriageway to the proposed basement floor level. The traffic engineer shall provide specific written certification on the plans that:

- vehicular access can be obtained using grades of 20% (1 in 5) maximum and
- all changes in grade (transitions) comply with Australian Standard 2890.1 – "Off-street car parking" (refer clause 2.5.3) to prevent the scraping of the underside of vehicles.

If a new driveway crossing is proposed, the longitudinal sections must incorporate the driveway crossing levels as issued by Council upon prior application.

Reason: To provide suitable vehicular access without disruption to pedestrian and vehicular traffic.

27. Basement car parking details

Prior to issue of the relevant Construction Certificate, certified parking layout plan(s) to scale showing all aspects of the vehicle access and accommodation arrangements must be submitted to and approved by the Certifying Authority. A qualified civil/traffic engineer must review the proposed vehicle access and accommodation layout and provide written certification on the plans that:

- all parking space dimensions, driveway and aisle widths, driveway grades, transitions, circulation ramps, blind aisle situations and other trafficked areas comply with Australian Standard 2890.1 – 2004 “Off-street car parking”
- a clear height clearance of **2.6 metres** (required under DCP40 for waste collection trucks) is provided over the designated garbage collection truck manoeuvring areas within the basement
- no doors or gates are provided in the access driveways to the basement carpark which would prevent unrestricted access for internal garbage collection at any time from the basement garbage storage and collection area
- the vehicle access and accommodation arrangements are to be constructed and marked in accordance with the certified plans

Reason: To ensure that parking spaces are in accordance with the approved development.

28. Vehicular access and garaging

Driveways and vehicular access ramps must be designed not to scrape the underside of cars. In all respects, the proposed vehicle access and accommodation arrangements must be designed and constructed to comply with Australian Standard 2890.1 – 2004 “Off-Street car parking”. Details are to be provided to and approved by the Certifying Authority prior to the issue of the relevant Construction Certificate.

Reason: To ensure that parking spaces are in accordance with the approved development.

29. Car parking allocation

Car parking within the development shall be allocated in the following way:

Resident car spaces	218
Visitor spaces	32
Total spaces	250

Each adaptable dwelling must be provided with car parking complying with the dimensional and location requirements of AS2890.1 – parking spaces for people with disabilities.

At least one visitor space shall also comply with the dimensional and location requirements of AS2890.1 – parking spaces for people with disabilities. The spaces shall be painted nominating them as 'Visitor's Parking'.

Consideration must be given to the means of access from disabled car parking spaces to other areas within the building and to footpath and roads and shall be clearly shown on the plans submitted with the relevant Construction Certificate.

Reason: To ensure equity of access and appropriate facilities are available for people with disabilities in accordance with federal legislation.

30. Number of bicycle spaces

The basement car park shall be adapted to provide 39 bicycle spaces in accordance with the Edgelea Urban Design Guidelines. The bicycle parking spaces shall be designed in accordance with AS2890.3. Details shall be submitted to the satisfaction of the Certifying Authority prior to the issue of the relevant Construction Certificate.

Reason: To provide alternative modes of transport to and from the site.

31. Utility provider requirements

Prior to issue of the relevant Construction Certificate, the applicant must make contact with all relevant utility providers whose services will be impacted upon by the development. A written copy of the requirements of each provider, as determined necessary by the Certifying Authority, must be obtained. All utility services or appropriate conduits for the same must be provided by the developer in accordance with the specifications of the utility providers.

Reason: To ensure compliance with the requirements of relevant utility providers.

32. Underground services

All electrical services (existing and proposed) shall be undergrounded from the proposed building on the site to the appropriate power pole(s) or other connection point. Undergrounding of services must not disturb the root system of existing trees and shall be undertaken in accordance with the requirements of the relevant service provided. Documentary evidence that the relevant service provider has been consulted and that their requirements have been met are to be provided to the Certifying Authority prior to the issue of the relevant Construction Certificate. All electrical and telephone services to the subject property must be placed underground and any redundant poles are to be removed at the expense of the applicant.

Reason: To provide infrastructure that facilitates the future improvement of the streetscape by relocation of overhead lines below ground.

Conditions to be satisfied prior to the issue of the construction certificate or prior to demolition, excavation or construction (whichever comes first):

33. Infrastructure restorations fee

To ensure that damage to Council Property as a result of construction activity is rectified in a timely matter:

- a) All work or activity taken in furtherance of the development the subject of this approval must be undertaken in a manner to avoid damage to Council Property and must not jeopardise the safety of any person using or occupying the adjacent public areas.
- b) The applicant, builder, developer or any person acting in reliance on this approval shall be responsible for making good any damage to Council Property, and for the removal from Council Property of any waste bin, building materials, sediment, silt, or any other material or article.
- c) The Infrastructure Restoration Fee must be paid to the Council by the applicant prior to both the issue of the Construction Certificate and the commencement of any earthworks or construction.
- d) In consideration of payment of the Infrastructure Restorations Fee, Council will undertake such inspections of Council Property as Council considers necessary and also undertake, on behalf of the applicant, such restoration work to Council Property, if any, that Council considers necessary as a consequence of the development. The provision of such restoration work by the Council does not absolve any person of the responsibilities contained in (a) to (b) above. Restoration work to be undertaken by the Council referred to in this condition is limited to work that can be undertaken by Council at a cost of not more than the Infrastructure Restorations Fee payable pursuant to this condition.
- e) In this condition:
"Council Property" includes any road, footway, footpath paving, kerbing, guttering, crossings, street furniture, seats, letter bins, trees, shrubs, lawns, mounds, bushland, and similar structures or features on any road or public road within the meaning of the Local Government Act 1993 (NSW) or any public place; and
"Infrastructure Restoration Fee" means the Infrastructure Restorations Fee calculated in accordance with the Schedule of Fees & Charges adopted by Council as at the date of payment and the cost of any inspections required by the Council of Council Property associated with this condition.

Reason: To maintain public infrastructure.

34. Bush fire risk certification

Bush fire protection measures shall be carried out in accordance with the following bush fire risk assessment, report and certificate, listed below and endorsed with Council's stamp, except where amended by other conditions of this consent:

Document title	Prepared by	Dated
Bushfire Protection Assessment 11GOSBUS-0152	Ecological Australia	20 February 2013

Prior to the issue of the relevant construction certificate, the principal certifying authority must be satisfied that the relevant construction certificate is in accordance with the recommendations of the report and certificate as listed above.

Reason: To ensure that the development is in accordance with the determination.

Conditions to be satisfied during the demolition, excavation and construction phases:

35. Prescribed conditions

The applicant shall comply with any relevant prescribed conditions of development consent under clause 98 of the Environmental Planning and Assessment Regulation. For the purposes of section 80A (11) of the Environmental Planning and Assessment Act, the following conditions are prescribed in relation to a development consent for development that involves any building work:

- The work must be carried out in accordance with the requirements of the Building Code of Australia
- In the case of residential building work for which the Home Building Act 1989 requires there to be a contract of insurance in force in accordance with Part 6 of that Act, that such a contract of insurance is in force before any works commence.

Reason: Statutory requirement.

36. Hours of work

Demolition, excavation, construction work and deliveries of building material and equipment must not take place outside the hours of 7.00am to 5.00pm Monday to Friday and 8.00am to 12 noon Saturday. No work and no deliveries are to take place on Sundays and public holidays.

Excavation or removal of any materials using machinery of any kind, including compressors and jack hammers, must be limited to between 7.30am and 5.00pm Monday to Friday, with a respite break of 45 minutes between 12 noon 1.00pm.

Where it is necessary for works to occur outside of these hours (ie) placement of concrete for large floor areas on large residential/commercial developments or where building processes require the use of oversized trucks and/or cranes that are restricted by the RMS from travelling during daylight hours to deliver, erect or remove machinery, tower cranes, pre-cast panels, beams, tanks or service equipment to or from the site, approval for such activities will be subject to the issue of an "outside of hours works

permit" from Council as well as notification of the surrounding properties likely to be affected by the proposed works.

Note: Failure to obtain a permit to work outside of the approved hours will result in on the spot fines being issued.

Reason: To ensure reasonable standards of amenity for occupants of neighbouring properties.

37. Temporary irrigation

Temporary irrigation within the Tree Protection Fencing is to be provided. Irrigation volumes are to be determined by the Project Arborist.

Reason: To protect trees to be retained on site.

38. Demolition of existing site structures

To preserve the health and condition of existing trees to be retained, all demolition of existing building and landscape structures including tree removal, are to be undertaken within the access restricted to the existing roads and parking areas and in accordance with Section 2, Appendix 6 and Appendix 7, Arboricultural Impact Appraisal and Method Statement, Naturally Trees, 11/12/12. Where vehicular access is required across existing soft landscape area, temporary ground protection capable of supporting the vehicles is to be constructed in accordance with Section 4.5.3, AS4970-2009 Protection of trees on development sites.

Reason: To protect trees to be retained on site.

39. Approved plans to be on site

A copy of all approved and certified plans, specifications and documents incorporating conditions of consent and certification (including the Construction Certificate if required for the work) shall be kept on site at all times during the demolition, excavation and construction phases and must be readily available to any officer of Council or the Principal Certifying Authority.

Reason: To ensure that the development is in accordance with the determination.

40. Construction noise

During excavation, demolition and construction phases, noise generated from the site shall be controlled in accordance with the recommendations of the approved noise and vibration management plan.

Reason: To ensure reasonable standards of amenity to neighbouring properties.

41. Site notice

A site notice shall be erected on the site prior to any work commencing and shall be displayed throughout the works period.

The site notice must:

- be prominently displayed at the boundaries of the site for the purposes of informing the public that unauthorised entry to the site is not permitted
- display project details including, but not limited to the details of the builder, Principal Certifying Authority and structural engineer
- be durable and weatherproof
- display the approved hours of work, the name of the site/project manager, the responsible managing company (if any), its address and 24 hour contact phone number for any inquiries, including construction/noise complaint are to be displayed on the site notice
- be mounted at eye level on the perimeter hoardings/fencing and is to state that unauthorised entry to the site is not permitted

Reason: To ensure public safety and public information.

42. Dust control

During excavation, demolition and construction, adequate measures shall be taken to prevent dust from affecting the amenity of the neighbourhood. The following measures must be adopted:

- physical barriers shall be erected at right angles to the prevailing wind direction or shall be placed around or over dust sources to prevent wind or activity from generating dust
- earthworks and scheduling activities shall be managed to coincide with the next stage of development to minimise the amount of time the site is left cut or exposed
- all materials shall be stored or stockpiled at the best locations
- the ground surface should be dampened slightly to prevent dust from becoming airborne but should not be wet to the extent that run-off occurs
- all vehicles carrying spoil or rubble to or from the site shall at all times be covered to prevent the escape of dust
- all equipment wheels shall be washed before exiting the site using manual or automated sprayers and drive-through washing bays
- gates shall be closed between vehicle movements and shall be fitted with shade cloth
- cleaning of footpaths and roadways shall be carried out daily

Reason: To protect the environment and amenity of surrounding properties.

43. Post-construction dilapidation report

The applicant shall engage a suitably qualified person to prepare a post construction dilapidation report at the completion of the construction works. This report is to

ascertain whether the construction works created any structural damage to adjoining buildings, infrastructure and roads. The report is to be submitted to the Principal Certifying Authority. In ascertaining whether adverse structural damage has occurred to adjoining buildings, infrastructure and roads, the Principal Certifying Authority must:

- compare the post-construction dilapidation report with the pre-construction dilapidation report
- have written confirmation from the relevant authority that there is no adverse structural damage to their infrastructure and roads.

A copy of this report is to be forwarded to Council at the completion of the construction works.

Reason: Management of records.

44. RailCorp requirements

- All excavation and construction works are to be undertaken in accordance with the details, methodology, advice, undertakings and recommendations detailed in the following documents:
 - *Report on Geotechnical Investigation (for Precinct 3) prepared by Douglas Partners dated 17 August 2012 (Project 72980)*
 - *Structural Design Report for Development Application prepared by Bonacci Group Pty Ltd dated 29 November 2012 (Ref 2001275-3-SDA Rev 5)*
 - *Civil Design Report for Development Application prepared by Bonacci Group Pty Ltd dated 20 August 2012 (Ref 2001275-3-C-DA Rev 3)*
 - *Numerical Modelling Analysis prepared by Douglas Partners dated 31 October 2012 (Project 72980)*

Subject to the following modifications:

- The applicant shall undertake a pre-excavation dilapidation survey of RailCorp's tunnel infrastructure to the satisfaction of RailCorp prior to the issue of a construction certificate, on completion of excavation and a post-construction dilapidation survey to the satisfaction of RailCorp prior to the issue of an Occupation Certificate.
- Vibration caused by excavation and piling machinery to be controlled to a safe level as recommended by the consultants.
- All surface runoff and seepage towards the excavation site to be collected and immediately discharged outside to prevent water infiltration towards the tunnels. Prior to the issuing of a Construction Certificate, the applicant is to submit Final Construction/Shoring plans consistent with the above requirements to RailCorp for endorsement. The Principal Certifying Authority

shall not issue the Construction Certificate until written confirmation has been received from RailCorp confirming that this condition has been satisfied.

- All piling and excavation works with 25m of the rail corridor are to be supervised by a geotechnical engineer experience with such excavation projects.
- No rock anchors/bolts are to be installed into RailCorp's property or easements.
- No modifications may be made to that approved design without the consent of RailCorp.
- Prior to the issuing of an Occupancy Certificate the applicant shall provide as-built drawings and survey locating the development with respect to any rail boundary, RailCorp easement and rail infrastructure. This work is to be undertaken by a registered surveyor, to the satisfaction of RailCorp's representative. The as-built survey is to confirm that there has been no encroachment into any RailCorp land or easement area.
- A revised acoustic assessment is to be submitted to Council and RailCorp prior to the issue of a construction certificate addressing the following item:
 - No reference to measurements is included in the updated Acoustic Assessment. RailCorp requires clarification around the source level data used in the assessment (reference to previous reports, database, etc). The Principal Certifying Authority shall not issue the Construction Certificate until written confirmation has been received from Council and RailCorp confirming that the subject report is adequate in meeting the relevant requirements.
- Prior to the issue of a Construction Certificate the applicant is to engage an Electrolysis Expert to prepare a report on the Electrolysis Risk to the development from stray currents. The applicant must incorporate in the development all the measures recommended in the report to control that risk. A copy of the report is to be provided to the Principal Certifying Authority with the application for a Construction Certificate.
- Prior to the issue of a Construction Certificate a Risk Assessment/Management Plan and detailed Safe Work Method Statements (SWMS) for the proposed works are to be submitted to RailCorp for review and comment on the impacts on rail corridor. The Principal Certifying Authority shall not issue the Construction Certificate until written confirmation has been received from RailCorp confirming that this condition has been satisfied.
- Prior to the issue of a Construction Certificate the applicant must hold current public liability insurance cover for a sum to be determined by RailCorp. This insurance shall not contain any exclusion in relation to works on or near the rail corridor. The applicant is to contact RailCorp's Rail Corridor Management Group to obtain the level of insurance required for this particular proposal. Prior to

issuing the Construction Certificate the Principal Certifying Authority must witness written proof of this insurance in conjunction with RailCorp's written advice to the Applicant on the level of insurance required.

- Where a condition of consent requires RailCorp's endorsement the Principal Certifying Authority shall not issue a Construction Certificate or Occupancy Certificate, as the case may be, until written confirmation has been received from RailCorp that the particular condition has been complied with.

Reason: Statutory requirement.

45. Further geotechnical input

The geotechnical and hydro-geological works implementation, inspection, testing and monitoring program for the excavation and construction works must be in accordance with the report by Douglas Partners. Over the course of the works, a qualified geotechnical/hydro-geological engineer must complete the following:

- further geotechnical investigations and testing recommended in the above report(s) and as determined necessary
- further monitoring and inspection at the hold points recommended in the above report(s) and as determined necessary
- written report(s) including certification(s) of the geotechnical inspection, testing and monitoring programs

Reason: To ensure the safety and protection of property.

46. Compliance with submitted geotechnical report

A contractor with specialist excavation experience must undertake the excavations for the development and a suitably qualified and consulting geotechnical engineer must oversee excavation.

Geotechnical aspects of the development work, namely:

- appropriate excavation method and vibration control
- support and retention of excavated faces
- hydro-geological considerations

must be undertaken in accordance with the recommendations of the geotechnical report prepared by Douglas Partners. Approval must be obtained from all affected property owners, including Ku-ring-gai Council, where rock anchors (both temporary and permanent) are proposed below adjoining property(ies).

Reason: To ensure the safety and protection of property.

47. Use of road or footpath

During excavation, demolition and construction phases, no building materials, plant or the like are to be stored on the road or footpath without written approval being obtained from Council beforehand. The pathway shall be kept in a clean, tidy and safe condition during building operations. Council reserves the right, without notice, to rectify any such breach and to charge the cost against the applicant/owner/builder, as the case may be.

Reason: To ensure safety and amenity of the area.

48. Guarding excavations

All excavation, demolition and construction works shall be properly guarded and protected with hoardings or fencing to prevent them from being dangerous to life and property.

Reason: To ensure public safety.

49. Toilet facilities

During excavation, demolition and construction phases, toilet facilities are to be provided, on the work site, at the rate of one toilet for every 20 persons or part of 20 persons employed at the site.

Reason: Statutory requirement.

50. Recycling of building materials

During demolition and construction, the Principal Certifying Authority shall be satisfied that building materials suitable for recycling have been forwarded to an appropriate registered business dealing in recycling of materials. Materials to be recycled must be kept in good order.

Reason: To facilitate recycling of materials.

51. Road reserve safety

All public footways and roadways fronting and adjacent to the site must be maintained in a safe condition at all times during the course of the development works. Construction materials must not be stored in the road reserve. A safe pedestrian circulation route and a pavement/route free of trip hazards must be maintained at all times on or adjacent to any public access ways fronting the construction site. Where public infrastructure is damaged, repair works must be carried out when and as directed by Council officers. Where pedestrian circulation is diverted on to the roadway or verge areas, clear directional signage and protective barricades must be installed in accordance with AS1742-3 (1996) "Traffic Control Devices for Work on Roads". If pedestrian circulation is not satisfactorily maintained across the site frontage, and action is not taken promptly to rectify the defects, Council may undertake proceedings to stop work.

Reason: To ensure safe public footways and roadways during construction.

52. Road repairs necessitated by excavation and construction works

It is highly likely that damage will be caused to the roadway at or near the subject site as a result of the construction (or demolition or excavation) works. The applicant, owner and builder (and demolition or excavation contractor as appropriate) will be held responsible for repair of such damage, regardless of the Infrastructure Restorations Fee paid (this fee is to cover wear and tear on Council's wider road network due to heavy vehicle traffic, not actual major damage).

Section 102(1) of the Roads Act states "A person who causes damage to a public road is liable to pay to the appropriate roads authority the cost incurred by that authority in making good the damage."

Council will notify when road repairs are needed, and if they are not carried out within 48 hours, then Council will proceed with the repairs, and will invoice the applicant, owner and relevant contractor for the balance.

Reason: To protect public infrastructure.

53. Services

Where required, the adjustment or inclusion of any new utility service facilities must be carried out by the applicant and in accordance with the requirements of the relevant utility authority. These works shall be at no cost to Council. It is the applicants' full responsibility to make contact with the relevant utility authorities to ascertain the impacts of the proposal upon utility services (including water, phone, gas, NBN and the like). Council accepts no responsibility for any matter arising from its approval to this application involving any influence upon utility services provided by another authority.

Reason: Provision of utility services.

54. Sydney Water Section 73 Compliance Certificate

The applicant must obtain a **Section 73 Compliance Certificate** under the *Sydney Water Act 1994*. An application must be made through an authorised Water Servicing CoOrdinator. The applicant is to refer to "Your Business" section of Sydney Water's web site at www.sydneywater.com.au then the "e-develop" icon or telephone 13 20 92. Following application a "Notice of Requirements" will detail water and sewer extensions to be built and charges to be paid. Please make early contact with the CoOrdinator, since building of water/sewer extensions can be time consuming and may impact on other services and building, driveway or landscape design.

Reason: Statutory requirement.

55. Arborist's report

The trees to be retained shall be inspected, monitored and treated by a Project Arborist who must be a qualified (AQF) Level 5 arborist in accordance with AS4970-2009 Protection

of trees on development sites. Regular inspections and documentation from the Project Arborist to the Principal Certifying Authority are required including at the following times or phases of work. All monitoring shall be recorded and provided to the Principal Certifying Authority prior to completion of the works.

Schedule

Tree/location

As shown on Tree Management Plans, TMP01 Sheets 1-4, prepared by Naturally Trees and dated 20/08/12

Time of inspection

As per Program of arboricultural input, Appendix 7, Arboricultural Impact Appraisal and Method Statement, Naturally Trees, 11/12/12.

Reason: To ensure protection of existing trees.

56. Canopy/root pruning

Canopy and/or root pruning of tree(s) as necessary to accommodate the approved building works shall be undertaken by an experienced AQF level 3 Arborist under the supervision of the Project Arborist and in accordance with the reduction pruning clause of AS4373-2007. All other branches are to be tied back and protected during construction, under the supervision of a qualified arborist.

Reason: To protect the environment.

57. Treatment of tree roots

If tree roots are required to be severed for the purposes of constructing the approved works, they shall be cut cleanly by hand, by an experienced Arborist/Horticulturist with a minimum qualification of Horticulture Certificate or Tree Surgery Certificate. All pruning works shall be undertaken as specified in Australian Standard 4373-2007 – Pruning of Amenity Trees.

Reason: To protect existing trees.

58. No storage of materials beneath trees

No activities, storage or disposal of materials shall take place beneath the canopy of any tree protected under Council's Tree Preservation Order at any time.

Reason: To protect existing trees.

59. Removal of refuse

All builders' refuse, spoil and/or material unsuitable for use in landscape areas shall be removed from the site on completion of the building works.

Reason: To protect the environment.

60. Survey and inspection of waste collection clearance and path of travel

At the stage when formwork for the ground floor slab is in place and prior to concrete being poured, a registered surveyor is to:

- ascertain the reduced level of the underside of the slab at the driveway entry,
- certify that the level is not lower than the level shown on the approved DA plans; and
- certify that the minimum headroom of 2.6 metres will be available for the full path of travel of the small waste collection vehicle from the street to the collection area.
- This certification is to be provided to Council's Development Engineer prior to any concrete being poured for the ground floor slab.
- No work is to proceed until Council has undertaken an inspection to determine clearance and path of travel.

At the stage when formwork for the ground floor slab is in place and prior to concrete being poured, Council's Development Engineer and Manager Waste Services are to carry out an inspection of the site to confirm the clearance available for the full path of travel of the small waste collection vehicle from the street to the collection area. This inspection may not be carried out by a private certifier because waste management is not a matter listed in Clause 161 of the Environmental Planning and Assessment Regulation 2000.

Reason: To ensure access will be available for Council's contractors to collect waste from the collection point.

61. On site retention of waste dockets

All demolition, excavation and construction waste dockets are to be retained on site, or at suitable location, in order to confirm which facility received materials generated from the site for recycling or disposal.

- Each docket is to be an official receipt from a facility authorised to accept the material type, for disposal or processing.
- This information is to be made available at the request of an Authorised Officer of Council.

Reason: To protect the environment.

Conditions to be satisfied prior to the issue of an Occupation Certificate:

Reason: To provide for legal and physical vehicular access and stormwater disposal.

62. Easement for waste collection

Prior to issue of the final Occupation Certificate, an easement for waste collection is to

be created under Section 88B of the Conveyancing Act 1919. This is to permit legal access for Council, Council's contractors and their vehicles over the subject property for the purpose of collecting waste from the property. The terms of the easement are to be generally in accordance with Council's draft terms for an easement for waste collection and shall be to the satisfaction of Council's Development Engineer.

Reason: To permit legal access for Council, Council's contractors and their vehicles over the subject site for waste collection.

63. Maintenance of water quality measures

Prior to issue of the final Occupation Certificate, the applicant must create a positive covenant and restriction on the use of land under Section 88E of the Conveyancing Act 1919, burdening the owner with the requirement to maintain the water quality measures (Stormfilter cartridges) on the lot.

For existing titles, the positive covenant and the restriction on the use of land is to be created through an application to the Land Titles Office in the form of a request using forms 13PC and 13RPA. The relative location of the cartridges, in relation to the building footprint, must be shown on a scale sketch, attached as an annexure to the request forms.

Registered title documents, showing the covenants and restrictions, must be submitted and approved by the Principal Certifying Authority prior to issue of an Occupation Certificate.

Reason: To protect the environment.

64. Compliance with BASIX Certificate

Prior to the issue of the relevant Occupation Certificate, the Principal Certifying Authority shall be satisfied that all commitments listed in BASIX Certificate No. 434823M_03 have been complied with.

Reason: Statutory requirement.

65. Clotheslines and clothes dryers

Prior to the issue of the relevant Occupation Certificate, the Principal Certifying Authority shall be satisfied that the units either have access to an external clothes line located in common open space or have a mechanical clothes dryer installed.

Reason: To provide access to clothes drying facilities.

66. Mechanical ventilation

Following completion, installation and testing of all the mechanical ventilation systems, the Principal Certifying Authority shall be satisfied of the following prior to the issue of the relevant Occupation Certificate:

1. The installation and performance of the mechanical systems complies with:
 - The Building Code of Australia
 - Australian Standard AS1668
 - Australian Standard AS3666 where applicable
2. The mechanical ventilation system in isolation and in association with other mechanical ventilation equipment, when in operation will not be audible within a habitable room in any other residential premises adjoining the development site before 7am and after 10pm Monday to Friday and before 8am and after 10pm Saturday, Sunday and public holidays. The operation of the unit(s) outside these restricted hours shall emit a noise level of not greater than 5dbA above the background when measured at the nearest adjoining residential boundary.

Note: Written confirmation from an acoustic engineer that the development achieves the above requirements is to be submitted to the Principal Certifying Authority prior to the issue of the Occupation Certificate.

Reason: To protect the amenity of surrounding properties.

67. Completion of landscape works

Prior to the release of the final Occupation Certificate, the Principal Certifying Authority is to be satisfied that all landscape works, including the removal of all noxious and/or environmental weed species, have been undertaken in accordance with the approved plan(s) and conditions of consent.

Reason: To ensure that the landscape works are consistent with the development consent.

68. Completion of tree works

Prior to the release of the final Occupation Certificate, the Principal Certifying Authority is to be satisfied that all tree works, including pruning in accordance with AS4373-2007 or remediation works in accordance with AS4370-2009, have been undertaken in accordance with the approved plan(s) and conditions of consent.

Reason: To ensure that the tree works are consistent with the development consent.

69. Accessibility

Prior to the issue of the relevant Occupation Certificate, the Principal Certifying Authority shall be satisfied that:

- the lift design and associated functions are compliant with AS 1735.12 & AS 1428.2
- the level and direction of travel, both in lifts and lift lobbies, is audible and

- visible
- the controls for lifts are accessible to all persons and control buttons and lettering are raised
- international symbols have been used with specifications relating to signs, symbols and size of lettering complying with AS 1428.2
- the height of lettering on signage is in accordance with AS 1428.1 – 1993
- the signs and other information indicating access and services incorporate tactile communication methods in addition to the visual methods

Reason: Disabled access & services.

70. Retention and re-use positive covenant

Prior to issue of the final Occupation Certificate, the applicant must create a positive covenant and restriction on the use of land under Section 88E of the Conveyancing Act 1919, burdening the property with the requirement to maintain the site stormwater retention and re-use facilities on the property.

The terms of the instruments are to be generally in accordance with the Council's "draft terms of Section 88B instruments for protection of retention and re-use facilities" and to the satisfaction of Council (refer to appendices of Ku-ring-gai Water Management Development Control Plan No. 47). For existing titles, the positive covenant and the restriction on the use of land is to be created through an application to the Land Titles Office in the form of a request using forms 13PC and 13RPA. The relative location of the reuse and retention facility, in relation to the building footprint, must be shown on a scale sketch, attached as an annexure to the request forms.

Registered title documents showing the covenants and restrictions must be submitted to and approved by the Principal Certifying Authority prior to issue of an Occupation Certificate.

Reason: To protect the environment.

71. Provision of copy of OSD designs if Council is not the PCA

Prior to issue of the final Occupation Certificate, the following must be provided to Council's Development Engineer:

- a copy of the approved Construction Certificate stormwater detention/retention design for the site
- a copy of any works-as-executed drawings required by this consent
- the Engineer's certification of the as-built system.

Reason: For Council to maintain its database of as-constructed on-site stormwater detention systems.

72. Certification of drainage works

Prior to issue of the final Occupation Certificate, the Principal Certifying Authority is to

be satisfied that:

- the stormwater drainage works have been satisfactorily completed in accordance with the approved Construction Certificate drainage plans
- the minimum retention and on-site detention storage volume requirements of BASIX and Ku-ring-gai Water Management Development Control Plan No. 47 respectively, have been achieved
- retained water is connected and available for use
- basement and subsoil areas are able to drain via a pump/sump system installed in accordance with AS3500.3 and Appendix 7.1.1 of Ku-ring-gai Water Management Development Control Plan No. 47
- all grates potentially accessible by children are secured
- components of the new drainage system have been installed by a licensed plumbing contractor in accordance with the Plumbing and Drainage Code AS3500.3 2003 and the Building Code of Australia
- all enclosed floor areas, including habitable and garage floor levels, are safeguarded from outside stormwater runoff ingress by suitable differences in finished levels, gradings and provision of stormwater collection devices

The rainwater certification sheet contained in Appendix 13 of the Ku-ring-gai Water Management Development Control Plan No. 47, must be completed and attached to the certification. Where an on-site detention system has been constructed, the on-site detention certification sheet contained in Appendix 4 of DCP 47 must also be completed and attached to the certification.

Note: Evidence from a qualified and experienced consulting civil/hydraulic engineer documenting compliance with the above is to be provided to Council prior to the issue of an Occupation Certificate.

Reason: To protect the environment.

73. Certification of as-constructed driveway/carpark – RFB

Prior to issue of the final Occupation Certificate, the Principal Certifying Authority is to be satisfied that:

- the as-constructed car park complies with the approved Construction Certificate plans
- the completed vehicle access and accommodation arrangements comply with Australian Standard 2890.1 – 2004 "Off-Street car parking" in terms of minimum parking space dimensions
- finished driveway gradients and transitions will not result in the scraping of the underside of cars
- no doors, gates, grilles or other structures have been provided in the access driveways to the basement carpark, which would prevent unrestricted access for

internal garbage collection from the basement garbage storage and collection area

- the vehicular headroom requirements of:
 - Australian Standard 2890.1 – “Off-street car parking”,
 - **2.6 metres** height clearance for waste collection trucks (refer DCP 40) are met from the public street into and within the applicable areas of the basement carpark.

Note: Evidence from a suitably qualified and experienced traffic/civil engineer indicating compliance with the above is to be provided to and approved by the Principal Certifying Authority prior to the issue of an Occupation Certificate.

Reason: To ensure that vehicular access and accommodation areas are compliant with the consent.

74. WAE plans for stormwater management and disposal

Prior to issue of the final Occupation Certificate, a registered surveyor must provide a works as executed survey of the completed stormwater drainage and management systems. The survey must be submitted to and approved by the Principal Certifying Authority prior to issue of the Occupation Certificate. The survey must indicate:

- as built (reduced) surface and invert levels for all drainage pits
- gradients of drainage lines, materials and dimensions
- as built (reduced) level(s) at the approved point of discharge to the public drainage system
- as built location and internal dimensions of all detention and retention structures on the property (in plan view) and horizontal distances to nearest adjacent boundaries and structures on site
- the achieved storage volumes of the installed retention and detention storages and derivative calculations
- as built locations of all access pits and grates in the detention and retention system(s), including dimensions
- the size of the orifice or control fitted to any on-site detention system
- dimensions of the discharge control pit and access grates
- the maximum depth of storage possible over the outlet control
- top water levels of storage areas and indicative RL's through the overland flow path in the event of blockage of the on-site detention system

The works as executed plan(s) must show the as built details above in comparison to those shown on the drainage plans approved with the Construction Certificate prior to commencement of works. All relevant levels and details indicated must be marked in red on a copy of the Principal Certifying Authority stamped construction certificate stormwater plans.

Reason: To protect the environment.

75. Basement pump-out maintenance

Prior to issue of the final Occupation Certificate, the Principal Certifying Authority shall be satisfied that a maintenance regime has been prepared for the basement stormwater pump-out system.

Note: A maintenance regime specifying that the system is to be regularly inspected and checked by qualified practitioners is to be prepared by a suitable qualified professional and provided to the Principal Certifying Authority.

Reason: To protect the environment.

76. OSD positive covenant/restriction

Prior to issue of the final Occupation Certificate, the applicant must create a positive covenant and restriction on the use of land under Section 88E of the Conveyancing Act 1919, burdening the owner with the requirement to maintain the on-site stormwater detention facilities on the lot.

The terms of the instruments are to be generally in accordance with the Council's "draft terms of Section 88B instrument for protection of on-site detention facilities" and to the satisfaction of Council (refer to appendices of Ku-ring-gai Council Water Management DCP 47). For existing titles, the positive covenant and the restriction on the use of land is to be created through an application to the Land Titles Office in the form of a request using forms 13PC and 13RPA. The relative location of the on-site detention facility, in relation to the building footprint, must be shown on a scale sketch, attached as an annexure to the request forms.

Registered title documents, showing the covenants and restrictions, must be submitted and approved by the Principal Certifying Authority prior to issue of an Occupation Certificate.

Reason: To protect the environment.

77. Sydney Water Section 73 Compliance Certificate

Prior to issue of the final Occupation Certificate the Section 73 Sydney water Compliance Certificate must be obtained and submitted to the Principal Certifying Authority

Reason: Statutory requirement.

78. Infrastructure repair

Prior to issue of the final Occupation Certificate, the Principal Certifying Authority must be satisfied that any damaged public infrastructure caused as a result of construction works (including damage caused by, but not limited to, delivery vehicles, waste collection, contractors, sub contractors, concrete vehicles) is fully repaired to the satisfaction of Council Development Engineer and at no cost to Council.

Reason: To protect public infrastructure.

79. Fire safety certificate

Prior to the issue of the relevant Occupation Certificate(s), the Principal Certifying Authority shall be satisfied that a Fire Safety Certificate for all the essential fire or other safety measures forming part of this consent has been completed and provided to Council.

Note: A copy of the Fire Safety Certificate must be submitted to Council.

Reason: To ensure suitable fire safety measures are in place.

Conditions to be satisfied at all times:

80. Car parking

At all times, the visitor car parking spaces are to be clearly identified and are to be for the exclusive use of visitors to the site. On site permanent car parking spaces are not to be used by those other than an occupant or tenant of the subject building. Any occupant, tenant, lessee or registered proprietor of the development site or part thereof shall not enter into an agreement to lease, license or transfer ownership of any car parking spaces to those other than an occupant, tenant or lessee of the building.

The use of visitor's spaces and tenant spaces is to be protected and enforced through the following:

- restrictive covenant placed on title pursuant to Section 88B of the Conveyancing Act, 1919
- restriction on use under Section 68 of the Strata Schemes (Freehold Development) Act, 1973 to all lots comprising in part or whole car parking spaces

Reason: To ensure adequate provision of visitor parking spaces.

81. Concept Approval

All works associated with the development and its ongoing use shall have regard to, and be undertaken in accordance with the Conditions and supporting documentation of Concept Approval MPo6_0130.

Reason: To ensure compliance with the Concept Approval.

82. Waste services

The waste rooms at the bottom of the waste chute shall be serviced on a regular and at needs basis so as to ensure its continued function as designed.

Reason: To ensure the ongoing amenity of residents.