

# ORAN PARK REDEVELOPMENT

## TOWN CENTRE - STAGE 1 CIVIL

FOR DEVELOPMENT APPLICATION  
FOR GREENFIELDS DEVELOPMENT COMPANY



LOCALITY PLAN  
N.T.S.

LGA CAMDEN COUNCIL



**BROWN**  
*Smart Consulting*

### Sheet List Table

No.	Drawing Title
GENERAL	
000	COVERSHEET
001	SHEET LAYOUT PLAN
002	STANDARD NOTES & LEGEND
ROADWORKS	
101	ENGINEERING PLAN DRAWING 01 OF 03
102	ENGINEERING PLAN DRAWING 02 OF 03
103	ENGINEERING PLAN DRAWING 03 OF 03
104	MAIN STREET LONGITUDINAL & TYPICAL CROSS SECTIONS
105	KERB & SLAB DETAILS
SEDIMENT & EROSION CONTROL	
701	BULK EARTHWORKS & SOIL & WATER MANAGEMENT PLAN
702	SOIL & WATER MANAGEMENT NOTES & DETAILS

### ORAN PARK REDEVELOPMENT

#### TOWN CENTRE - STAGE 1 CIVIL



Project No.:  
L06002.57A


Stage:  
1

Milestone:  
DA

Drawing No.:  
000

Revision:  
01





Revisions	
No.	Description
00	PS RS RS 14/03/2012 ORIGINAL ISSUE
01	PS RS RS 15/10/2012 CLIENT AMENDMENTS
02	PS RS RS 14/03/2012

Revision Details

0 10 20 30 40 50 60 70 80 90 100

SCALE 1:1000 (A1) SCALE 1:2000 (A3)

Disclaimer and Copyright:  
ALL DIMENSIONS TO BE CHECKED ON SITE BY  
SUPERINTENDENT PRIOR TO CONSTRUCTION.  
USE WRITTEN DIMENSIONS ONLY, DO NOT  
SCALE.

© Brown Consulting Pty Ltd

Approval:  
BY: TOBY TAMES  
BE (Hons) GradDipMgt CPESC CPEng  
SIGN:

DATE:

Client:  
GREENFIELDS DEVELOPMENT COMPANY

Project:  
ORAN PARK REDEVELOPMENT  
TOWN CENTRE - STAGE 1 CIVIL

**BROWN**  
Smart Consulting  
©2012  
www.brownconsulting.com.au

Drawing Title:  
SHEET LAYOUT PLAN

Project No.	Stage	Milestone	Dwg No.	Revision
L06002.57A	1	DA	001	01

GENERAL NOTES

GENERAL

- G1 ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH CAMDEN COUNCIL'S ENGINEERING DESIGN, ENGINEERING CONSTRUCTION SPECIFICATION AND TO THE REQUIREMENTS OF THE PRINCIPAL CERTIFYING AUTHORITY/ ROADS AUTHORITY.
- G2 INSPECTIONS BY PRINCIPAL CERTIFYING AUTHORITY/ ROADS AUTHORITY SHALL BE REQUESTED AT THE FOLLOWING STAGES AND THE WORKS APPROVED PRIOR TO THE CONTINUANCE OF ANY WORK:  
(a) FOLLOWING THE INSTALLATION OF EROSION AND SEDIMENT CONTROL STRUCTURES/MEASURES  
(b) PRIOR TO BACKFILLING PIPELINES, SUBSOIL DRAINS AND DAMS.  
(c) PRIOR TO CASTING OF PITS AND OTHER CONCRETE STRUCTURES, INCLUDING KERB AND GUTTER BUT FOLLOWING THE PLACEMENT OF FOOTINGS, FORMWORK AND REINFORCEMENT.  
(d) PRIOR TO PLACEMENT OF SUBBASE AND ALL SUB SEQUENT PAVEMENT LAYERS, A PROOF ROLLER TEST OF EACH PAVEMENT LAYER IS REQUIRED.  
(e) FORMWORKS PRIOR TO POURING CONCRETE IN PARKING AREAS FOR FOOTPATH CROSSING AND OTHER ASSOCIATED WORK.  
(f) PRIOR TO BACKFILLING PUBLIC UTILITY CROSSINGS IN ROAD RESERVES.  
(g) FINAL INSPECTIONS AFTER ALL WORKS ARE COMPLETED AND "WORK AS EXECUTED" PLANS HAVE BEEN SUBMITTED TO COUNCIL.
- G3 NO TREES TO BE REMOVED UNLESS APPROVAL IS GRANTED BY COUNCILS LANDSCAPE COMPLIANCE OFFICER.
- G4 MAKE SMOOTH JUNCTIONS WITH EXISTING WORKS
- G5 NO WORK TO BE CARRIED OUT ON ADJOINING PROPERTIES WITHOUT THE WRITTEN PERMISSION FROM THE OWNER.
- G6 VEHICULAR ACCESS AND ALL UTILITIES/SERVICES ARE TO BE MAINTAINED AT ALL TIMES TO ADJOINING PROPERTIES AFFECTED BY CONSTRUCTION.
- G7 ALL RUBBISH, BUILDINGS, SHEDS, AND FENCES ARE TO BE REMOVED TO THE SATISFACTION OF THE PRINCIPAL CERTIFYING AUTHORITY/ ROADS AUTHORITY.

EARTHWORKS

- E1 EARTHWORKS ARE TO BE CARRIED OUT TO THE SATISFACTION OF THE PRINCIPAL CERTIFYING AUTHORITY/ ROADS AUTHORITY. UNSUITABLE MATERIALS ARE TO BE REMOVED FROM ROADS AND LOTS PRIOR TO FILLING. THE CONTRACTOR IS TO ARRANGE AND MAKE AVAILABLE COMPACTION TESTING RESULTS FOR ALL AREAS THAT CONTAIN FILL IN EXCESS OF 200mm.
- E2 COMPACTION OF EARTHWORKS SHALL CONTINUE UNTIL A DRY DENSITY RATIO OF 95% FOR SITE FILLING AND 100% FOR ROAD PAVEMENT SUBGRADES HAS BEEN ACHIEVED IN ACCORDANCE WITH TEST METHOD AS1289.5.3.1 OR AS1289.5.11.
- E3 THE CONTROL TESTING OF EARTHWORKS SHALL BE IN ACCORDANCE WITH THE GUIDELINES IN AS3798 "GUIDELINES ON EARTHWORKS FOR COMMERCIAL AND RESIDENTIAL DEVELOPMENTS". WHERE IT IS PROPOSED TO USE TEST METHOD AS1289.5.8.2 TO DETERMINE THE FIELD DENSITY, A SAND REPLACEMENT METHOD SHALL BE USED TO CONFIRM THE RESULTS.
- E4 THE SUBDIVISIONAL GEOTECH ACCREDITED CERTIFIER, SHALL HAVE A LEVEL1 RESPONSIBILITY FOR ALL FILLING AS DEFINED IN APPENDIX B AS3798 "GUIDELINES ON EARTHWORKS FOR COMMERCIAL AND RESIDENTIAL DEVELOPMENTS" AND AT THE END OF THE WORKS SHALL CONFIRM THE EARTHWORKS COMPLY WITH THE REQUIREMENTS OF THE SPECIFICATION AND DRAWINGS BY WRITTEN NOTIFICATION.
- E5 IN AREAS TO BE FILLED WHERE THE SLOPE OF THE NATURAL SURFACE EXCEEDS 1:1V:1H, BENCHES ARE TO BE CUT TO PREVENT SLIPPING OF THE PLACED FILL MATERIAL AS REQUIRED BY THE COUNCIL.
- E6 ALL BATTERS ARE TO BE SCARIFIED TO A DEPTH OF 50mm TO ASSIST THE ADHESION OF TOP SOIL TO BATTER FACE.
- E7 PROVIDE MINIMUM 150mm AND MAXIMUM 300mm TOPSOIL WITHIN FOOTPATHS, FILLED AREAS AND ALL OTHER AREAS DISTURBED DURING CONSTRUCTION. TOPSOILED AREAS TO BE STABILISED WITH APPROVED VEGETATION A MAXIMUM OF 2 DAYS AFTER TOPSOILING AND ARE TO BE WATERED TO ENSURE GERMINATION.
- E8 THE CONTRACTOR SHALL CONTROL SEDIMENTATION, EROSION AND POLLUTION DURING CONSTRUCTION IN ACCORDANCE WITH THE REQUIREMENTS OF THE CURRENT EDITION OF "MANAGING URBAN STORMWATER: SOILS AND CONSTRUCTION" PROVIDED BY LANDCOM.
- E9 A 1-METRE WIDE, CONTINUOUS STRIP OF COUGH GRASS SHALL BE PLACED BEHIND THE BACK OF ALL KERBS AND OTHER CONCRETE STRUCTURES IMMEDIATELY AFTER THE COMPLETION OF THE FOOTPATH GRADING OR OTHER ELEMENTS AS APPLICABLE, SHALL BE MAINTAINED AND REPLACED AS A REQUIREMENT DURING THE CONSTRUCTION MAINTENANCE PERIOD.

ROADWORKS

- R1 SUBGRADES AND SUBBASES ARE TO BE COMPACTED IN ACCORDANCE WITH COUNCILS CONSTRUCTION SPECIFICATION.
- R2 SUBSOIL DRAINS TO BE PROVIDED ON BOTH SIDES OF ROADS (EXCEPT WHERE THERE IS STORMWATER DRAINAGE AND ON SUSPENDED ROADWAYS)
- R3 LIPLESS PERAMBULATOR CROSSINGS ARE TO BE PROVIDED IN ALL KERB RETURNS WHERE REQUIRED BY COUNCIL.
- R4 SERVICE CONDUITS TO BE PLACED AS DIRECTED BY ALL PUBLIC UTILITY AUTHORITIES INCLUDING ENDEAVOUR ENERGY, TELSTRA AND SYDNEY WATER.
- R5 ALL PERMANENT ROADS MUST BE SEALED WITH A SINGLE COAT OF FLUSH SEAL AND 50mm OF AC TO BE APPLIED IN TWO 25mm THICK LAYERS. THE FINAL AC IS TO BE BONDED WITH COUNCIL AND PLACED FOLLOWING APPROVAL FROM COUNCIL EXCEPT ON SUSPENDED ROADWAYS
- R6 SIGNPOSTING AND LINE MARKING SHALL CONFORM TO AS 1742.2 "TRAFFIC CONTROL DEVICES FOR GENERAL USE", RAISED RETRO-REFLECTIVE PAVEMENT MARKERS TO CONFORM TO AS1906 "RETRO-REFLECTIVE DEVICES AND MATERIALS FOR ROAD TRAFFIC CONTROL PURPOSES". ALL APRONS AND KERB FACE ON CENTRAL ISLANDS OF ROUNDABOUTS AND ALL OTHER ISLANDS TO BE DELINEATED BY REFLECTIVE WHITE MARKING.
- R7 ALL LOT NUMBERS AND STREET NAMES TO BE STENCILED ON KERB FACE.
- R8 STREET SIGNS TO COUNCIL STANDARD MUST BE INSTALLED BY THE OWNER/APPLICANT/SUPERINTENDANT, STREET NAMES MUST BE STENCILED ON KERB AT INTERSECTIONS.

DRAINAGE

- S1 ALL PIPES TO BE SPIGOT AND SOCKET, RUBBER RING JOINTED UNLESS OTHERWISE NOTED.
- S2 ALL LONGITUDINAL PIPELINES IN ROADS MUST BE LOCATED UNDER KERB AND GUTTER AND BACKFILLED WITH APPROVED GRANULAR MATERIAL UNLESS OTHERWISE APPROVED BY THE COUNCIL ENGINEER.
- S3 DRAINAGE LINES MUST BE BACKFILLED WITH APPROVED GRANULAR MATERIAL IN TRAFFICABLE AREAS. THREE (3) METRES OF SUBSOIL DRAINAGE WRAPPED IN GEOTEXTILE STOCKING MUST BE PROVIDED ON THE UPSTREAM SIDE OF ALL DOWNSTREAM PITS.
- S4 ALL GULLY PITS TO COUNCILS STANDARD AND LINTELS CENTRALLY PLACED AT SAG PITS.
- S5 ALL PITS MUST BE BENCHED AND STREAMLINED. PROVIDE F72 REINFORCEMENT AND GALVANISED STEP IRONS IN ALL PITS OVER 1.2 METRES DEEP AS MEASURED FROM THE TOP OF GRATE TO THE INVERT OF THE PIT.
- S6 CONCRETE IS TO HAVE A MINIMUM COMPRESSIVE STRENGTH OF 32MPa AT 28-DAYS UNLESS OTHERWISE APPROVED BY THE COUNCIL ENGINEER.
- S7 CATCH DRAINS MUST BE CONSTRUCTED AS REQUIRED BY PRINCIPAL CERTIFYING AUTHORITY/ ROADS AUTHORITY.
- S8 ADEQUATE PROVISION IS TO BE MADE TO PREVENT SCOURING AND SEDIMENTATION FOR ALL DRAINAGE WORKS IN ACCORDANCE WITH COUNCILS REQUIREMENTS.
- S9 PIT LINTELS ARE TO BE STENCILED WITH APPLICABLE DESTINATION STENCIL AVAILABLE FROM COUNCIL.
- S10 PRECAST CONCRETE HEADWALL TO BE USED FOR PIPE OUTLETS UP TO 900 Ø
- S11 CONCRETE HEADWALLS FOR PIPE GREATER THAN 900 Ø ARE TO BE CAST IN SITU IN ACCORDANCE WITH SD.21

LEGEND

DESCRIPTION	PROPOSED	EXISTING	FUTURE
STORMWATER PIPELINE			
STORMWATER DRAINAGE PITS			
DRAINAGE LINE No.3 DRAINAGE PIT No. 10			
CONCRETE HEADWALL			
SUBSOIL DRAIN			
STANDARD 150mm KERB AND GUTTER		EXIST. K&G	FUT. K&G
STANDARD ROLL KERB AND GUTTER		EXIST. RK	FUT. RK
STANDARD KERB ONLY		EXIST. KO	FUT. KO
STANDARD EDGE STRIP		EXIST. ES	FUT. ES
STANDARD MOUNTABLE KERB		EXIST. MK	FUT. MK
STANDARD DISH CROSSING		EXIST. DC	FUT. DC
VEHICULAR CROSSING			
PEDESTRIAN RAMP			
EDGE OF BITUMEN			
ROAD PAVEMENT			
BENCHMARK		BM: 115 RL: 105.332	
BATTERS			
CONCRETE PATHWAY			
CONTOURS			
SITE REGRADING AREA			
SERVICE LINES SEWER, GAS, WATER, ELECTRICITY			
COMMUNICATION LINES TELSTRA, FIBRE OPTIC			
OVER HEAD LINES AND POLES			
SERVICE PITS TELECOM PIT, ACCESS CHAMBER, HYDRANT, STOP VALVE, AIR VALVE			
LIMIT OF CONSTRUCTION			
LIMIT OF STAGE			
FENCE POST AND RAIL FENCE SECURITY FENCE			
LOT NUMBERS	D-LOTNO	E-LOTNO	F-LOTNO
TREES TO RETAIN TREES TO REMOVE			
RETAINING WALL			
ROCK WALL			

FILE: L:\06002 - ORAN PARK LANDSCAPE\06002 STA - TOWN CENTRE\DRAWINGS\DWG\06002 STA - TOWN CENTRE - STAGE 1 CIVIL.DWG PRINTED: 10/12/2012 USER: PETER SPADARO

Revisions	Issue	Drawn	Design	Check	Appd.	Date	Revision Details
00	PS	RS	RS			14/03/2012	ORIGINAL ISSUE
01	PS	RS	RS			5/10/2012	CLIENT AMENDMENTS
First Issue	PS	RS	RS			14/03/2012	

Disclaimer and Copyright:  
ALL DIMENSIONS TO BE CHECKED ON SITE BY SUPERINTENDENT PRIOR TO CONSTRUCTION. USE WRITTEN DIMENSIONS ONLY, DO NOT SCALE.

© Brown Consulting Pty Ltd

Approval:  
BY: TOBY TAMES  
BE (Hons) Grad Dip Maj CPESC-CPEng  
MIEAust  
SIGN:

DATE: 5/10/12

Client:  
GREENFIELDS DEVELOPMENT COMPANY


Project:  
ORAN PARK REDEVELOPMENT  
TOWN CENTRE - STAGE 1 CIVIL

**BROWN**  
Smart Consulting  
©2012 www.brownconsulting.com.au

Drawing Title:  
STANDARD NOTES & LEGEND

Project No.: L06002.57A Stage: 1 Milestone: DA Dwg No.: 002 Revision: 01





PLAN  
SCALE 1:200

NOTE:  
FOR MAIN STREET LONGITUDINAL AND  
TYPICAL CROSS SECTIONS REFER SHEET  
No.104

Revisions					
00	PS	RS	RS	14/03/2012	ORIGINAL ISSUE
01	PS	RS	RS	5/10/2012	CLIENT AMENDMENTS
First Issue	Drawn	Design	Check	Appd.	Date
14/03/2012					

Revision Details



Disclaimer and Copyright:  
ALL DIMENSIONS TO BE CHECKED ON SITE BY  
SUPERINTENDENT PRIOR TO CONSTRUCTION.  
USE WRITTEN DIMENSIONS ONLY, DO NOT  
SCALE.

© Brown Consulting Pty Ltd

Approval:  
BY: TOBY TAMES  
BE (Hons) Grad Dip Mgt OPSC OPENG  
ME Aust  
SIGN: *[Signature]*  
DATE: 3/10/12

Client:  
GREENFIELDS DEVELOPMENT COMPANY

Project:  
ORAN PARK REDEVELOPMENT  
TOWN CENTRE - STAGE 1 CIVIL

**BROWN**  
Smart Consulting  
©2012  
www.brownconsulting.com.au

Drawing Title:  
ENGINEERING PLAN DRAWING 01 OF  
03

Project No.:  
L06002.57A

Stage:  
1

Milestone:  
DA

Dwg No.:  
101

Revision:  
01
























**NOTES:**  
1. MASTIC EXPANSION JOINTS TO BE PLACED AT NO MORE THAN 6m SPACING & NO LESS THAN 3m SPACING  
2. ALL CORNERS TO HAVE 25mm RADIUS UNL.O.

FILE: H:\06\0002 - ORAN PARK LANDSCAPE ARCHITECTS DETAILS - TOWN CENTRE DRIVEWAYS\DWG\002 - STAGE 1 CIVIL - PETER SPADARO  
PRINTED: 10/10/12 USER: PETER SPADARO

Revisions	Issue	Drawn	Design	Check	Appd.	Date	Revision Details
00	PS	RS	RS			14/03/2012	ORIGINAL ISSUE
01	PS	RS	RS			5/10/2012	CLIENT AMENDMENTS
02	PS	RS	RS			14/03/2012	



Disclaimer and Copyright:  
ALL DIMENSIONS TO BE CHECKED ON SITE BY SUPERINTENDENT PRIOR TO CONSTRUCTION. USE WRITTEN DIMENSIONS ONLY, DO NOT SCALE.  
© Brown Consulting Pty Ltd

Approval:  
BY: TOBY TAMES  
BE (Hons) GradDipMgt CPESC CPENG  
MIE Aust  
SIGN: [Signature]  
DATE: 5/10/12

Client:  
**GREENFIELDS DEVELOPMENT COMPANY**  
Project:  
**ORAN PARK REDEVELOPMENT TOWN CENTRE - STAGE 1 CIVIL**

**BROWN**  
Smart Consulting  
© 2012  
www.brownconsulting.com.au

Drawing Title:  
**KERB & SLAB DETAILS**  
Project No.: L06002.57A  
Stage: 1  
Milestone: DA  
Dwg No.: 105  
Revision: 01








## SEDIMENT & EROSION CONTROL NOTES

- THE CONTRACTOR SHALL IMPLEMENT ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO THE COMMENCEMENT OF ANY WORKS BEING CARRIED OUT. ALL SOIL AND EROSION MEASURES SHALL BE MAINTAINED AND KEPT IN PLACE FOR THE FULL DURATION OF THE WORKS AND SHALL ONLY BE REMOVED AT FINAL STABILISATION OF THE WORKS. WHERE IT IS NECESSARY TO UNDERTAKE STRIPPING IN ORDER TO CONSTRUCT A SEDIMENT CONTROL DEVICE ONLY SUFFICIENT GROUND SHALL BE STRIPPED TO ALLOW CONSTRUCTION.
- ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CONSTRUCTED AND MAINTAINED AS INDICATED ON THESE DRAWINGS. LOCATION AND EXTENT OF SOIL AND WATER MANAGEMENT DEVICES IS DIAGRAMMATIC ONLY AND THE ACTUAL REQUIREMENTS SHALL BE CONFIRMED ON SITE PRIOR TO COMMENCEMENT.
- CONFORMITY WITH THIS PLAN SHALL IN NO WAY REDUCE THE RESPONSIBILITY OF THE CONTRACTOR TO PROTECT AGAINST WATER DAMAGE DURING THE COURSE OF THE CONTRACT. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO ENSURE THAT ANY NECESSARY CONTROL IS IN PLACE EVEN THOUGH SUCH CONTROL MAY NOT BE SHOWN ON THE PLAN.
- THE CONTRACTOR SHALL INFORM ALL SUBCONTRACTORS AND ALL EMPLOYEES OF THEIR RESPONSIBILITIES IN MINIMISING THE POTENTIAL FOR SOIL EROSION AND POLLUTION TO DOWNSIDE AREAS.
- APART FROM SEDIMENT BASINS, THE CONTRACTOR SHALL REGULARLY MAINTAIN SEDIMENT AND EROSION CONTROL STRUCTURES AND DESILT SUCH STRUCTURES PRIOR TO THE REDUCTION IN CAPACITY OF 30% DUE TO ACCUMULATED SEDIMENT. THE SEDIMENT SHALL BE DISPOSED OF ON SITE IN A MANNER APPROVED BY THE ENGINEER.
- THE CONTRACTOR SHALL TEMPORARILY REHABILITATE WITHIN TEN (10) DAYS ANY DISTURBED AREAS PROVIDING A MINIMUM 60% COVER. FINAL REHABILITATION IS TO BE PROVIDED WITHIN A FURTHER 60 DAYS WITH A MINIMUM 70% COVER.
- THE CONTRACTOR SHALL PROVIDE WATERING OF THE VEGETATED BATTERS FOR MAINTENANCE PERIOD. PLANT, MACHINERY AND VEHICLES SHALL NOT BE DRIVEN OVER GRASSED AREAS UNLESS ON AN APPROVED HAULAGE ROUTE.
- ALL DRAINAGE WORKS SHALL BE CONSTRUCTED AND STABILISED AS QUICKLY AS POSSIBLE TO MINIMISE RISK OF EROSION.
- SITE ACCESS SHALL BE RESTRICTED TO THE NOMINATED POINTS. THE CONTRACTOR SHALL PROVIDE STABILISED SITE ACCESS.
- DUST AND SITE DISTURBANCE MUST BE KEPT TO A MINIMUM DURING WINDY WEATHER. LARGE, UNPROTECTED AREAS MUST BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO REDUCE WIND EROSION. ERECT BARRIER FENCING TO MINIMISE LAND DISTURBANCE BY PREVENTING VEHICULAR AND PEDESTRIAN ACCESS TO AREAS BEING REHABILITATED AND LANDS THAT DO NOT NEED TO BE DISTURBED BY THIS PROJECT.
- STOCKPILE TOPSOILS, SUBSOILS AND OTHER MATERIALS SEPARATELY.
- TOPSOIL SHALL BE STORED IN LOW MOUNDS NO MORE THAN 2 METRES HIGH AND RE-USED WITHIN TWO MONTHS TO MAINTAIN ACTIVE POPULATIONS OF BENEFICIAL SOIL MICROBES AND SEED.
- PLACE ALL STOCKPILES AT LEAST FIVE METRES FROM AREAS OF LIKELY CONCENTRATED OR HIGH VELOCITY FLOWS, ESPECIALLY EARTH BANKS AND ROADS. IF NECESSARY, EARTH BANKS OR DRAINS WILL BE CONSTRUCTED TO DIVERT LOCALISED RUN-ON.
- TURN TOPSOIL STOCKPILES OVER TO AERATE THEM AT MONTHLY INTERVALS. ENSURE VEGETATION IS NOT INCORPORATED INTO THE SOIL.
- AVOID REVERSING THE SOIL PROFILE MATERIALS DURING FILL OPERATIONS - REPLACE DISTURBED SOILS IN THEIR ORIGINAL ORDER.
- ON COMPLETION OF MAJOR EARTHWORKS AND BEFORE ADDING TOPSOIL, LEAVE DISTURBED LANDS WITH A LOOSE SURFACE. ALTERNATELY, DISTURBED AREAS PREVIOUSLY COMPACTED BY CONSTRUCTION WORKS WILL BE RIPPED TO MORE THAN 200-MM ALONG THE CONTOUR BEFORE APPLYING TOPSOIL.
- PROVIDING MATERIALS ARE AVAILABLE, SPREAD TOPSOIL TO A MINIMUM DEPTH OF 75mm IN REVEGETATION AREAS ON SLOPES OF 40:1 (H:V) OR LESS AND TO A DEPTH OF 40 TO 60mm IN REVEGETATION AREAS STEEPER THAN 4:1.
- LEAVE TOPSOIL IN A SCARIFIED OR ROUGH CONDITION ONCE REPLACED TO HELP MOISTURE INFILTRATION AND REDUCE SOIL EROSION.
- ENSURE SOIL IS THOROUGHLY SOAKED TO A DEPTH OF 75mm (RAIN OR IRRIGATION) IMMEDIATELY BEFORE PLANTING.
- HANDLE TOPSOIL ONLY WHEN IT IS MOIST (NOT WET OR DRY) TO AVOID DECLINE OF SOIL STRUCTURE.
- THE CONTRACTOR SHALL MAINTAIN A LOG BOOK DETAILING:
  - RECORDS OF ALL RAINFALL
  - CONDITION OF SOIL AND WATER MANAGEMENT STRUCTURES
  - ANY APPLICATION OF FLOCCULATING AGENTS TO SEDIMENT BASIN
  - VOLUMES OF ALL WATER DISCHARGED FROM SEDIMENT BASINS
  - ANY ADDITIONAL REMEDIAL WORKS REQUIRED.
- THE LOG BOOK SHALL BE MAINTAINED ON A WEEKLY BASIS AND BE MADE AVAILABLE TO ANY AUTHORISED PERSON UPON REQUEST. THE ORIGINAL LOG BOOK SHALL BE ISSUED TO THE PROJECT MANAGER AT THE COMPLETION OF WORKS.
- ALL ROAD EMBANKMENTS TO BE STABILISED AS PER LANDSCAPE ARCHITECTS DETAILS.
- A SELF AUDITING PROGRAM SHOULD BE ESTABLISHED BASED ON A CHECK SHEET DEVELOPED FOR THE SITE. A SITE INSPECTION USING THE CHECK SHEET SHOULD BE MADE BY THE SITE MANAGER AT LEAST WEEKLY, IMMEDIATELY BEFORE SITE CLOSURE AND IMMEDIATELY FOLLOWING RAINFALL EVENTS THAT CAUSE RUNOFF.
- UNDERTAKE THE SELF AUDIT BY:
  - WALKING AROUND THE SITE SYSTEMATICALLY (E.G. CLOCKWISE)
  - RECORDING THE CONDITION OF EVERY BMP EMPLOYED
  - RECORDING MAINTENANCE REQUIREMENTS OF ANY/ FOR EACH BMP
  - RECORDING THE SITE WHERE SEDIMENT IS DISPOSED
  - FORWARDING A SIGNED DUPLICATE OF THE COMPLETED CHECK SHEET TO THE PROJECT MANAGER/DEVELOPER/SITE OPERATOR FOR THEIR INFORMATION

- IN PARTICULAR, INSPECT:
  - LOCATIONS WHERE VEHICLES ENTER AND LEAVE THE SITE
  - ALL INSTALLED EROSION AND SEDIMENT CONTROL MEASURES, ENSURING THEY ARE OPERATING CORRECTLY
  - AREAS THAT MIGHT SHOW WHETHER SEDIMENT OR OTHER POLLUTANTS ARE LEAVING THE SITE OR HAVE POTENTIAL TO DO SO
  - ALL DISCHARGE POINTS, TO ASSESS WHETHER THE EROSION AND SEDIMENT CONTROL MEASURES ARE EFFECTIVE IN PREVENTING IMPACTS TO THE RECEIVING WATERS
- A SITE INSPECTION USING THE CHECK SHEET WILL BE MADE BY THE SITE MANAGER AT LEAST WEEKLY, IMMEDIATELY BEFORE SITE CLOSURE, AND IMMEDIATELY FOLLOWING RAINFALL EVENTS GREATER THAN 5mm IN 24 HOURS.




Level Spreader (or Sill)

- Construction Notes**
- Construct at the gradient specified on the ESCP or SWMP, normally between 1 and 5 percent.
  - Avoid removing trees and shrubs if possible - work around them.
  - Ensure the structures are free of projections or other irregularities that could impede water flow.
  - Build the drains with circular, parabolic or trapezoidal cross sections, not V-shaped, at the dimensions shown on the SWMP.
  - Ensure the banks are properly compacted to prevent failure.
  - Complete permanent or temporary stabilisation within 10 days of construction following Table 5.2 in Landoom (2004).
  - Where discharging to erodible lands, ensure they outlet through a properly constructed level spreader.
  - Construct the level spreader at the gradient specified on the ESCP or SWMP, normally less than 1 percent or level.
  - Where possible, ensure they discharge waters onto either stabilised or undisturbed disposal sites within the same subcatchment area from which the water originated. Approval might be required to discharge into other subcatchments.

## EARTH BANK (HIGH FLOWS)

SD 5-6




Geotextile Inlet Filter

- Construction Notes**
- Fabricate a sediment barrier made from geotextile or straw bales.
  - Follow Standard Drawing 6-8 for installation procedures for geofabric. Reduce the picket spacing to 1 metre centres.
  - In waterways, artificial sag points can be created with sandbags or earth banks as shown in the drawing.
  - Do not cover the inlet with geotextile unless the design is adequate to allow for all waters to bypass it.

## GEOTEXTILE INLET FILTER

SD 6-12




Sediment Fence

- Construction Notes**
- Place stockpiles more than 2 (preferably 5) metres from existing vegetation, concentrated water flow, roads and hazard areas.
  - Construct on the contour as low, flat, elongated mounds.
  - Where there is sufficient area, topsoil stockpiles shall be less than 2 metres in height.
  - Where they are to be in place for more than 10 days, stabilise following the approved ESCP or SWMP to reduce the C-factor to less than 0.10.
  - Construct earth banks (Standard Drawing 5-5) on the upslope side to divert water around stockpiles and sediment fences (Standard Drawing 6-8) 1 to 2 metres downslope.

## STOCKPILES

SD 4-1




Kerbside Turf Strip

- Construction Notes**
- Install a 400 mm minimum wide roll of turf on the footpath next to the kerb and at the same level as the top of the kerb.
  - Lay 14 metre long turf strips normal to the kerb every 10 metres.
  - Rehabilitate disturbed soil behind the turf strip following the ESCP/SWMP.

## KERBSIDE TURF STRIP

SD 6-13



Sediment Fence

- Construction Notes**
- Construct sediment fences as close as possible to being parallel to the contours of the site, but with small returns as shown in the drawing to limit the catchment area of any one section. The catchment area should be small enough to limit water flow if concentrated at one point to 50 litres per second in the design storm event, usually the 10-year event.
  - Cut a 150-mm deep trench along the upslope line of the fence for the bottom of the fabric to be entrenched.
  - Drive 15 metre long star pickets into ground at 25 metre intervals (max) at the downslope edge of the trench. Ensure any star pickets are fitted with safety caps.
  - Fix self-supporting geotextile to the upslope side of the posts ensuring it goes to the base of the trench. Fix the geotextile with wire ties or as recommended by the manufacturer. Only use geotextile specifically produced for sediment fencing. The use of shade cloth for this purpose is not satisfactory.
  - Join sections of fabric at a support post with a 150-mm overlap.
  - Backfill the trench over the base of the fabric and compact it thoroughly over the geotextile.

## SEDIMENT FENCE


SD 6-8

## STABILISED ACCESS POINT

### TYPE II SAP

THE TYPE II SAP DESIGN IS MORE DEFINED IN THAT IT REQUIRES AN AREA OF BALLAST WITHIN THE SITE COMBINED WITH A SHAKER PAD; ADJACENT TO THE SHAKER PAD AND IN THE PUBLIC WAY IS A TEMPORARY (CONCRETE) VEHICULAR CROSSING. (SEE DIAGRAM)

### STABILISED ACCESS POINT - TYPE 2



IN BOTH TYPE I AND TYPE II SAP'S, THE TEMPORARY VEHICULAR CROSSING MUST:

- CONNECT TO AN EXISTING GUTTER LAYBACK (WHERE THE KERB AND GUTTER EXIST). IF A GUTTER LAYBACK DOES NOT EXIST THEN THE CONNECTION MUST BE MADE TO THE GUTTER BY REMOVING THE ADJACENT KERB SECTION ONLY.
- CONNECT TO A DISH CROSSING (WHERE KERB AND GUTTER DOES NOT EXIST). IF A DISH CROSSING DOES NOT EXIST, THEN IT MUST BE CONSTRUCTED IN ACCORDANCE WITH DETAILS CONTAINED IN COUNCIL'S ISSUED FOOTPATH CROSSING LEVELS.

IT SHOULD BE NOTED THAT THESE TYPES OF SAPS ARE CONSIDERED TO BE APPLICABLE FOR THE MAJORITY OF ACTIVITIES HOWEVER SOME SITES MAY REQUIRE SPECIAL CONSIDERATION.

## SHAKER PAD (CATTLE GRID)


A CORRECTLY DESIGNED AND INSTALLED SHAKER PAD WILL ASSIST IN PREVENTING SEDIMENT TRANSFER FROM A SITE. ANY STABILISED ACCESS POINT (SAP) CAN BE DESIGNED WITH A SHAKER PAD (COMPULSORY IN TYPE II SAP'S)

SHAKER PADS CAN BE DESIGNED AND CONSTRUCTED TO ENABLE RE-USE ON FUTURE PROJECTS.

THE SHAKER PAD:

- MUST BE DESIGNED AND CERTIFIED BY A PRACTISING STRUCTURAL ENGINEER. THE CERTIFIED DESIGN SHOULD BE SUBMITTED WITH THE RELEVANT APPLICATION.
- CAN BE CONSTRUCTED FROM ANY SUITABLE MATERIAL.
- MUST BE LOCATED ON A SUITABLY PREPARED AND COMPACTED SUB-GRADE/BASE MATERIAL.
- MUST BE SITUATED SUCH THAT THE RUNGS OF THE SHAKER PAD ARE LEVEL WITH THE ADJOINING NATURAL SURFACE.
- MUST BE A MINIMUM OF 3.5m IN LENGTH.
- MUST BE A MINIMUM OF 3.5m IN WIDTH.
- MUST HAVE CLEAR SPACING BETWEEN RUNGS OF 200 - 250mm.
- RUNGS MUST HAVE A MAXIMUM WIDTH (BEARING AREA) OF 75mm.
- MUST HAVE A MINIMUM CLEAR DEPTH OF 300mm IF FROM THE TOP OF THE RUNG TO THE FINISHED SUB-GRADE/BASE LEVEL.

THE SHAKER PAD MUST BE PROVIDED WITH SUITABLE BARRIERS AT THE SIDES TO ENSURE THAT ALL TYPES OF VEHICLES LEAVING THE SITE TRAVERSE THE DEVICE.



Revision	By	Check	Date	Description
01	PS	RS	14/03/2012	ORIGINAL ISSUE
02	PS	RS	14/03/2012	CLIENT AMENDMENTS
03	PS	RS	14/03/2012	

Revision Details

Disclaimer and Copyright:  
ALL DIMENSIONS TO BE CHECKED ON SITE BY  
SUPERINTENDENT PRIOR TO CONSTRUCTION.  
USE WRITTEN DIMENSIONS ONLY, DO NOT  
SCALE.

© Brown Consulting Pty Ltd



Approval:  
BY: TOBY TAMES  
BE (Hons) GradDipMgt CPESC CPEng  
MIE Aust  
SIGN: [Signature]  
DATE: 5/10/12

Client:  
GREENFIELDS DEVELOPMENT COMPANY  
Project:  
ORAN PARK REDEVELOPMENT  
TOWN CENTRE - STAGE 1 CIVIL

**BROWN**  
Smart Consulting  
© 2012  
www.brownconsulting.com.au

Drawing Title:  
SOIL & WATER MANAGEMENT  
NOTES & DETAILS

Project No.: L06002.57A  
Stage: 1  
Milestone: DA  
Dwg No.: 702  
Revision: 01