

---

**CONDITIONS OF DEVELOPMENT CONSENT**

---

---

**DA No:** DA-459/2014  
**Property:** 5-7 Northumberland Road, AUBURN NSW 2144  
**Description:** Demolition of the soccer club and associated structures and construction of a 12 storey mixed use development incorporating 116 residential apartments and 2 commercial tenancies over 3 levels of basement parking.

---

**1. DC1 Amended architectural, landscape and stormwater plans:**

Amended landscape plans, site plans and stormwater plans (three (3) copies) are required to be submitted to the Council for final approval incorporating the following design changes.

- i) Landscaping that correlates with the modified and updated architectural plans.

Reason:- to ensure the landscaping plans correlate with the altered design layout of the development.

**ii) Storm water from the property known as 4 Station Road or SP 50061**

The storm water generated from SP50061 known as 4 Station Road Auburn shall be drained through the subject development site during and after construction. In this regard, all required details shall be shown on the amended storm water plan.

Reason:- to ensure prevent localised flooding and ensure the system in operation.

**iii) Storm water plan**

Detailed stormwater design shall be submitted to Auburn City Council for approval. The stormwater plan shall comply with Auburn City Council's DCP requirements. In this regard:-

- On site stormwater detention storage system shall be provided in conjunction with the stormwater disposal. The details shall be prepared by qualified practising Civil/Hydraulic Engineer in accordance with Council's Stormwater DCP and Australian Rainfall & Runoff 1987.
- Detailed on-site detention calculation sheets and Council's submission checklist are to be submitted.
- Detail section of the OSD tank shall be submitted. The section shall incorporate high early discharge control pit, dry platform, orifice, step irons and grated access covers. OSD shall comply with Council's standard sections.
- Detailed longitudinal section of the proposed outlet pipe from the OSD tank to Council's pipe drainage system shall be submitted. The plan shall show the proposed pipe size, invert levels, pipe grades and hydraulic grade lines.
- Basement pump out system shall comply with Council's stormwater DCP.

Basement below ground and above ground storage volumes shall comply with Section D3.6 of the Stormwater DCP.

- Rainwater tanks shall be provided.

Reason:- to prevent localised flooding.

iv) **Loading area design related to Development Application 197/2015**

A designated loading and unloading facility shall be provided for the development considered (Under development application 197/2015) within Lot 1 in DP104001 and lot 2 in DP104001 within lot 201 in DP 233376 and lot 1 in DP227083. In this regard:-

- A designated loading area for a medium rigid vehicle (MRV) shall be provided for lot 1 in DP104001 and lot 2 in DP104001. Loading area shall be marked on the plan.

Note: The above loading bay is in addition to the loading bay provisions related to the subject development.

- Delivery trucks shall enter and leave the site in a forward direction. In this regard detailed swept path analysis shall be provided. Headroom for the trucks shall comply with Australian standard AS2890.2.
- Delivery truck loading area shall have a minimum 4.5m head room. In this regard detailed cross sections shall be submitted.
- Detail swept path analysis showing access to the proposed loading area shall be shown on the plan.

Reason:- to ensure designated off street loading area is provided and loading area design complies with Australian standard AS2890.2.

**DC2 Realignment of easement**

A letter from the owners of SP 50061 shall be obtained for the proposed realignment of benefitted easement traversing through the subject development property. The written consent shall be submitted to Council stating the operation of the system during construction and future easement location with terms and conditions.

**DC3 Creation of Right of way / Easement for loading and unloading**

The applicant shall create a right of way/ easement in favour of lot 1 in DP104001 and lot 2 in DP104001, over the lot 201 in DP 233376 and lot 1 in DP227083 with respect to the waste collection and loading and unloading facility related to DA197/2015.

Such right of way/ easement and appropriate 88B instrument shall be submitted to Council for approval and then registered with the Land and Property Information Office.

A copy of the registered documents of the right of way/easement shall be submitted to and approved by Council.

Auburn City Council shall be nominated as the Authority to vary or modify the

easement.

Reason:- to ensure an appropriate easement is created to facilitate the waste collection and deliveries to the site.

#### **DC4 Creation of Right of way over the lot F of DP 100170**

The applicant shall create a right of way over Lot F in DP 100170 in favour of lot 1 of DP104001, lot 2 of DP104001, lot 201 of DP 233376 and lot 1 of DP227083 to facilitate the vehicle manoeuvring and to facilitate the subject development.

Such right of way and appropriate 88B instrument shall be submitted to Council for approval and then registered with the Land and Property Information Office. A copy of the registered documents of the right of way/easement shall be submitted to and approved by Council.

Auburn City Council shall be nominated as the Authority to vary or modify the easement.

Reason:- to ensure appropriate easement shall be created to facilitate the waste collection and deliveries to the site.

#### **DC5 Creation of Drainage Easement**

The applicant shall create a stormwater drainage easement to drain water in favour of lot 1 in DP104001 and lot 2 in DP104001, over the lot 201 in DP 233376 and lot 1 in DP227083 with respect to the disposal of stormwater runoff from the upstream lots to Council's pipe drainage system in Northumberland Road.

Such easements and appropriate 88B instrument shall be submitted to Council for approval and then registered with the Land and Property Information Office. A copy of the registered documents of the drainage easement shall be submitted to and approved by Council.

Auburn City Council shall be nominated as the Authority to vary or modify the easement.

Note: Drainage easement shall comply with stormwater plan details.

Reason:- to ensure appropriate easement shall be created to drain the stormwater from the development.

## **2. Approved Plans - Deferred Commencement**

The development is to be carried out generally in accordance with the following plans as numbered below, **except as modified by the deferred commencement condition of approval:**

<b><i>Plan Number</i></b>	<b><i>Prepared By</i></b>	<b><i>Revision No.</i></b>	<b><i>Dated</i></b>
Site Analysis Drawing DA01	Zhinar Architects	B	18/5/2015
Site Plan Drawing DA02	Zhinar Architects	B	18/5/2015
Basement 3 Plan Drawing DA03	Zhinar Architects	B	18/5/2015

Basement 2 Plan Drawing DA04	Zhinar Architects	B	18/5/2015
Basement 1 Plan Drawing DA05	Zhinar Architects	B	18/5/2015
Ground Floor Plan Drawing DA06	Zhinar Architects	B	18/5/2015
Level 1 Plan Drawing DA07	Zhinar Architects	B	18/5/2015
Level 2 Plan Drawing DA08	Zhinar Architects	B	18/5/2015
Level 3-7 Plan Drawing DA09	Zhinar Architects	B	18/5/2015
Level 8 Plan Drawing DA10	Zhinar Architects	B	18/5/2015
Level 9-11 Plan Drawing DA11	Zhinar Architects	B	18/5/2015
Roof Plan Drawing DA12	Zhinar Architects	B	18/5/2015
Section Plan Drawing DA13	Zhinar Architects	B	18/5/2015
West Elevation Drawing Number DA14	Zhinar Architects	B	18/5/2015
North Elevation Drawing Number DA15	Zhinar Architects	B	18/5/2015
South Elevation Drawing Number DA16	Zhinar Architects	B	18/5/2015
East Elevation Drawing Number DA17	Zhinar Architects	B	18/5/2015
West Elevation Materials and Finishes Drawing Number DA24	Zhinar Architects	B	18/5/2015
South Elevation Materials and Finishes Drawing Number DA25	Zhinar Architects	B	18/5/2015
Site 2 Basement 1 Drawing Number 05	Zhinar Architects	B	18/5/2015
Site 2 Ground Floor Plan Stormwater Plan	Zhinar Architects	B	18/5/2015
Flooding and Stormwater Aspects			June 2015
Auburn Soccer Club Redevelopment Flooding and Stormwater Aspects	NPC Management Consultants and Project Managers		June 2015
Soil and Water Management Plan	Junek and Junek Pty Ltd		29 April 2014
Assessor Certificate Certificate Number BDAV14510402	David Gradwell		4 June 2015
BASIX Certificate Certificate Number 597286M-02			4 June 2015
Access Compliance Assessment Report Report Number A410211	Certified Building Specialists		16 December 2014

Waste Management Plan	Zhinar Architects Pty Ltd		16/12/2014
Qualitative Wind Assessment Report Number 610.14748-R1	SLR Global Environmental Solutions		16 December 2014
DA Acoustic Assessment. Report Reference 20141400.1/1512A/R0/JL	Acoustic Logic		15/12/2014

**The plans will not be “stamped” by Council until the modifications required by the deferred commencement condition have been incorporated into revised plans.**

(Note:- modifications to the approved plans will require the lodgement and consideration by Council of a modification pursuant to Section 96 of the Environmental Planning and Assessment Act).

Reason:- to confirm and clarify the terms of Council’s approval.

### 3. **Auburn DCP 2007 - LGA Wide**

Development Contributions are payable in accordance with Auburn Council Council’s Section 94 Development Contribution Plan 2007, which has been prepared under Section 94 of the Environmental Planning and Assessment Act 1979, as amended.

The amounts payable will be adjusted in accordance with the section titled Review of Contribution rates and are generally indexed on a quarterly basis by the Consumer Price Index CPI (all Groups Sydney) unless otherwise stated in the plan.

Contributions will be adjusted at the payment date in accordance with the plan and payment is to be made prior to the issue of any occupation Certificate.

A sum of \$649,136.60 is to be paid to Council for the purpose of LGA Wide plans being the provision of open space and recreation facilities, community facilities, accessibility and traffic works, town centre upgrades, car parking and Council's administration of the development contributions framework.

The above sum is broken down to the following items:

Item	Amount
Community Facilities	\$159,241.68
Public Domain	\$352,193.06
Accessibility and Traffic	\$97,076.50
Administration	\$37,227.23
Employment Generating Development	\$3,398.03
<b>TOTAL</b>	<b>\$649,136.60</b>

Council’s Development Contribution Plan 2007 is available for inspection at Council’s Customer Services Centre, Civic Place, 1 Susan Street, Auburn or on line at [www.auburn.nsw.gov.au](http://www.auburn.nsw.gov.au).

Reason:- to provide open space and recreation facilities, community facilities, accessibility and traffic works, town centre upgrades, car parking and Council's administration of the development contributions framework.

4. **Time period of consent**

This consent shall lapse five (5) years from the date of determination unless the approved building, engineering or construction work has been physically commenced in accordance with this consent.

Development consent for the use of land does not lapse if the approved use of any land, building or work is actually commenced prior to the date on which the consent would otherwise lapse.

Reason:- to satisfy the requirements of Section 95 of the Environmental Planning and Assessment Act.

5. **Submission of Construction Certificate**

Construction works are not to commence until such time that a construction certificate for the proposed works has been issued by Council or an Accredited Certifier.

**NOTES:**

Where an Accredited Certifier issues a construction certificate, a copy of the following documents must be forwarded to Council within 7 days of issue, together with payment of the Council's adopted registration fee: determination; application to which it relates; construction certificate issued; plans and specifications; any fire safety schedule; and any other documents lodged with the certificate.

Any modification involving building works to the approved development made under Section 96 of the Environmental Planning and Assessment Act 1979 requires the submission of an amended construction certificate.

Reason:- to comply with the requirements of Section 81A of the Environmental Planning and Assessment Act and clause 142 of the Environmental Planning and Assessment Regulation 2000.

6. **Consolidation of lots**

The individual lots are to be consolidated into a single parcel. Written evidence of registration of consolidation by the Land and Property Information Office is to be submitted to Council prior to the granting of the occupation certificate.

Reason:- to ensure the whole of the land essential to the proper operation of the development is preserved.

7. **No alteration without prior Council approval**

The completed building is not to be altered externally in character or colour without the prior consent of Council.

Reason:- to ensure the external appearance of the development is not obtrusive or offensive and does not degrade the visual quality of the surrounding area.

---

8. **Appointment of Principal Certifying Authority/Notice of Commencement of Work**

Site works are not to commence until:-

- a) a construction certificate for the building work has been issued by the consent authority, and
- b) the person having the benefit of the development consent has:-
  - i) appointed a principal certifying authority for the building work, and
  - ii) notified the principal certifying authority that the person will carry out the building work as an owner-builder, if that is the case, and
- b1) the principal certifying authority has, no later than 2 days before the building work commences:-
  - i) notified the consent authority and the council (if the council is not the consent authority) of his or her appointment, and
  - ii) notified the person having the benefit of the development consent of any critical stage inspections and other inspections that are to be carried out in respect of the building work, and
- b2) the person having the benefit of the development consent, if not carrying out the work as an owner-builder, has:-
  - i) appointed a principal contractor for the building work who must be the holder of a contractor licence if any residential building work is involved, and
  - ii) notified the principal certifying authority of any such appointment, and
  - iii) unless that person is the principal contractor, notified the principal contractor of any critical stage inspections and other inspections that are to be carried out in respect of the building work, and
- c) the person having the benefit of the development consent has given at least 2 days' notice to the council of the person's intention to commence the erection of the building.

Reason:- to comply with the requirements of Section 81A of the Environmental Planning and Assessment Act.

9. **Principal Certifying Authority**

- 1) The person having the benefit of a development consent or complying development certificate for development involving building work or subdivision work may appoint the consent authority, the council or an accredited certifier as the principal certifying authority for the development.
- 1A) Despite subsection (1), such an appointment may not be made by any contractor or other person who will carry out the building work or subdivision work unless the contractor or other person is the owner of the land on which the work is to be carried out.
- 2) Despite subsection (1), an accredited certifier must not be appointed as the principal certifying authority for development involving subdivision work unless the subdivision to which the work relates is of a kind identified by an

environmental planning instrument as one in respect of which an accredited certifier may be a certifying authority.

- 3) A principal certifying authority for building work or subdivision work to be carried out on a site is required to be satisfied:-
  - a) that a construction certificate or complying development certificate has been issued for such of the building work or subdivision work as requires development consent and over which the principal certifying authority has control, before the work commences on the site, and
  - b) that the principal contractor for the work is the holder of the appropriate licence and is covered by the appropriate insurance, in each case if required by the [Home Building Act 1989](#), before any residential building work over which the principal certifying authority has control commences on the site, unless the work is to be carried out by an owner-builder, and
  - c) that the owner-builder is the holder of any owner-builder permit required under the [Home Building Act 1989](#), before an owner-builder commences on the site any residential building work over which the principal certifying authority has control, and
  - d) that building work or subdivision work on the site has been inspected by the principal certifying authority or another certifying authority on such occasions (if any) as are prescribed by the regulations and on such other occasions as may be required by the principal certifying authority, before the principal certifying authority issues an occupation certificate or subdivision certificate for the building or work, and
  - e) that any preconditions required by a development consent or complying development certificate to be met for the work before the issue of an occupation certificate or subdivision certificate have been met, before the principal certifying authority issues the occupation certificate or subdivision certificate.
- 4) A principal certifying authority must also comply with such other requirements of a like or different nature as may be imposed on principal certifying authorities by the regulations.

**Note.** Section 81A prohibits the commencement of building work or subdivision work unless the consent authority has been notified of the appointment of a principal certifying authority for the work. Section 109D (2) prohibits the issue of an occupation certificate authorising the occupation and use of a new building except by the principal certifying authority appointed for the erection of the building. Section 109D (3) prohibits the issue of a subdivision certificate for a subdivision involving subdivision work except by the principal certifying authority appointed for the carrying out of the subdivision.

Reason:- to comply with the requirements of Section 109E of the Environmental Planning and Assessment Act.

#### 10. **Provision of Street Numbers**

A street number is to be displayed in a prominent position at the entrance to the premises. Numbers are to be of a colour contrasting with the wall to which they are affixed.

Reason:- to clearly identify the street number of the property.



---

11. **Compliance with the Building Code of Australia**

All building work must be carried out in accordance with the requirements of the Building Code of Australia.

Reason:- to ensure compliance with the requirements of the Building Code of Australia and to comply with Clause 98 of the Environmental Planning and Assessment Regulation 2000.

12. **Insurance requirements under the Home Building Act 1989**

A contract of insurance for residential building work must be in force before any building works commence, where the works are being undertaken by a builder and tradesperson and the works have a market value of greater than \$20,000 (*or as varied from time to time by the Home Building Act 1989*).

Where the contract price or the reasonable market cost of the labour and materials involved does not exceed \$20,000, there is no legal requirement for home warranty insurance to be obtained.

Contractors who carry out residential building work must still hold an appropriate licence with Fair Trading where the labour and materials involved are valued at over \$1,000.

Home owners should be wary of any builder or tradesperson who says they do not need insurance if the value of work exceeds \$20,000, or who suggests you obtain an owner-builder permit while they carry out the work for you.

NOTE: Evidence of the contract of insurance or owner builder permit, if required, must be submitted with the application for construction certificate. The construction certificate will not be released by Council unless this evidence is provided.

Reason:- to comply with Clause 98 of the Environmental Planning and Assessment Regulation 2000.

13. **Disabled Access & Facilities**

Access and facilities for people with disabilities must be provided in accordance with the relevant requirements of the Building Code of Australia (for all new building work) and in addition, with the relevant requirements of the 'Disability (Access to Premises - Building) Standards 2010' (including for existing buildings, whether or not any works are proposed). Details of the proposed access, facilities and car parking for people with disabilities are to be included in the plans/specifications for the **construction certificate**.

Reason:- to ensure compliance with the requirements of the Building Code of Australia.

14. **Commonwealth Disability Discrimination Act**

The Commonwealth Disability Discrimination Act 1992 commenced the 'Disability (Access for Premises - Buildings) Standards 2010' on 1 May 2011 and now applies to all new buildings and affected parts of existing buildings. Submission and/or approval of this application does not imply or confer compliance with either the Act or the new Access Standard. Applicants should satisfy themselves and make their own

inquiries to the Human Rights and Equal Opportunity Commission.

Reason:- to provide advice on the requirements of the Commonwealth Disability Discrimination Act 1992.

15. **Replacement of Principal Certifying Authorities**

Unless the relevant authority so approves in writing, a person may not be appointed to replace another person as the principal certifying authority for development.

A principal certifying authority appointed to replace another principal certifying authority must ensure that notice of the appointment and of the approval of that appointment is given to the consent authority (and, if the consent authority is not the council, to the council) within 2 days of the appointment.

Reason:- to comply with the requirements of Section 109EA of the Environmental Planning and Assessment Act and clause 162 of the Environmental Planning and Assessment Regulation.

16. **Notice to Allow Inspections**

To allow a principal certifying authority or another certifying authority time to carry out critical stage inspections or any other inspections required by the principal certifying authority, the principal contractor for a building site, or the owner-builder, must notify the principal certifying authority at least 48 hours before building work is commenced at the site if a critical stage inspection is required before the commencement of the work.

Reason:- to comply with the requirements of Clause 163 of the Environmental Planning and Assessment Regulation.

17. **Erection of Signs**

A rigid and durable sign must be erected in a prominent position on any site on which building work, subdivision work or demolition work is being carried out:-

- a) showing the name, address and telephone number of the principal certifying authority for the work, and
- b) showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working hours, and
- c) stating that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.

Note: Principal certifying authorities and principal contractors must also ensure that signs required by this clause are erected and maintained (see clause 227A which currently imposes a maximum penalty of \$1,100.

Reason:- to comply with the requirements of Clause 98A and 136B of the Environmental Planning and Assessment Regulations.

---

**18. BASIX Requirements**

Under Clause 97A(3) of the Environmental Planning & Assessment Regulation 2000, it is a condition of this development consent that all the commitments listed in each relevant BASIX Certificate for the development are fulfilled. In this condition:-

- a) Relevant BASIX Certification means:-
  - i) A BASIX Certificate that was applicable to the development when this development consent was granted (or, if the development consent is modified under Section 96 of the Act, a BASIX Certificate that is applicable to the development when this development consent is modified) or;
  - ii) If a replacement BASIX Certificate accompanies any subsequent application for a construction certificate, the replacement BASIX Certificate; and
- b) BASIX Certificate has the meaning given to that term in the Environmental Planning & Assessment Regulation 2000.

Reason:- to comply with the Environmental Planning and Assessment Regulations.

**19. No Advertising Approved**

No advertising structures or signs shall be erected, affixed, painted or displayed without prior Council consent.

Reason:- to prevent the proliferation of signs which will result in a degradation of the visual quality of the area.

**20. Construction/Demolition Hours**

Site works, building works and demolition works, including the delivery of materials or equipment to and from the property are to be carried out between the hours of 7.00 am and 6.00 p.m. only from Mondays to Fridays and between 8.00 am and 4.00 p.m. only on Saturdays. No construction works or deliveries for the construction are to take place on Sundays or public holidays.

Prior to commencement of any demolition or construction work the applicant is to erect signs on the site, which are clearly visible from the footpaths adjoining the site boundaries, which state the permitted construction/demolition hours. These signs must also state "Any instances of site works, building works, demolition works or deliveries outside the permitted hours can be reported to Auburn Council on 9735-1222 during office hours or 0417-287-113 outside office hours".

Reason:- to reduce nuisance to the surrounding properties during the construction period.

**21. Information required prior to the issue of Construction Certificate**

The following documentation (where applicable) is to be submitted to Council or the accredited certifier, **prior to the granting of the construction certificate**:

- a) Detailed building plans and specifications containing sufficient information to

verify that the completed building will comply with the Building Code of Australia.

- b) A list of any existing fire safety measures provided in relation to the land or any existing building on the land (*not applicable to dwellings or outbuildings*)
- c) A list of any proposed fire safety measures provided in relation to the land or any existing building on the land (*not applicable to dwellings or outbuildings*)
- d) A report prepared by a *professional engineer* detailing the proposed methods of excavation, shoring or pile construction, and what measures are to be implemented to prevent damage from occurring to adjoining or nearby premises as a result of the proposed excavation works. (NOTE: Any practices or procedures specified to avoid damage to adjoining or nearby premises are to be incorporated into the plans and specifications for the construction certificate).
- e) Method of protecting window/door openings as required by BCA Part 3.
- f) Method of ventilating the basement car park. (Note: If mechanical ventilation is required, mechanical ventilation plans shall be submitted that also confirm the minimum height clearances specified by AS 2890.1 (Car parking, will be achieved).
- g) A Building Code of Australia Report addressing Sections C, D, E, F, G, H and I of the Building Code of Australia.
- h) A statement prepared by a Disability Access Consultant conforming that the building is compliant with Part D3 of the Building Code of Australia (The National Construction Code Series) and the Disability (Access to Premises Building) Standards 2010, AS1428.1-2009, AS1428.2, AS1428.3, AS1735.12, AS2890.1, AS1680.0, AS3661.1, AS4299, AS4586 and AS1228.2.
- i) Details of an awning structure over the footpath complying with Part 4.3 of the Auburn Development Control Plan 2010 "Local Centres" being Subparts D1, D2, D5, D6 and D7.

Reason:- to ensure that adequate information is submitted to enable assessment or that the development can proceed with the concurrence of others.

## 22. **Infrastructure Fee**

The infrastructure inspection fee in accordance with Councils Fees and Charges Schedule shall be paid prior to the issue of the Construction Certificate.

Reason:- to contribute to the cost of inspection and identification of any damage to Council's infrastructure as a result of the development.

## 23. **Maintain plans on-site**

A copy of the construction certificate, the approved plans & specifications and development consent conditions must be kept on the site at all times and be available to the Council officers upon request.

Reason:- to ensure a record of the approved plans are readily available.

## 24. **PCA - Inspection of works - general & site management**

The building works are to be inspected by the principal certifying authority (or other suitably qualified person on behalf of the applicant if permitted by the PCA) to monitor compliance with Council's approval and the relevant standards of construction.

Documentary evidence of compliance with Council's approval and relevant standards of construction is to be maintained by the principal certifying authority.

Upon inspection of each stage of construction, the principal certifying authority (or other suitably qualified person on behalf of the applicant) is also required to ensure that adequate provisions are made for the following measures (as applicable), to ensure compliance with the terms of Council's approval:

- Sediment control measures
- Provision of perimeter fences or hoardings for public safety and restricted access to building sites.
- Maintenance of the public place free from unauthorised materials, waste containers or other obstructions.

#### ADVISORY NOTE

*If Council is appointed as the PCA, the following critical inspections (as applicable to the development), must be arranged:*

- a) *Prior to the commencement of Building Works, ensure erosion controls PCA and the Builders signs are displayed and a temporary toilet is located on site.*
- b) *The pier holes before they are filled with concrete.*
- c) *The foundation material prior to covering.*
- d) *The steelwork when in position and before concrete is poured (footings, lintels, beams, columns, floors, walls, retaining walls or the like).*
- e) *The dampcourse level, ant capping and floor timbers before the floor materials are laid.*
- f) *The framework including roof members when completed and prior to the fixing of any internal sheets.*
- g) *Prior to covering waterproofing in any wet area.*
- h) *Fire resisting construction before concealment.*
- i) *Upper floor beams and joists before the fixing of any flooring material.*
- j) *The rainwater drainage lines within the property boundaries when completed and before covering.*
- o) *Final inspection.*

A minimum of 48 hours notice must be provided to Council to enable the following inspections to be carried out during the course of construction.

Reason:- to ensure the development is adequately monitored during the construction phase.

#### 25. **Items not to be placed on roadway**

The following items must not be placed on the footpath, roadway or nature strip at any time:-

- a) Building materials, sand, waste materials or construction equipment;
- b) Bulk bins/waste skips/containers; or
- c) Other items that may cause a hazard to pedestrians.

Reason:- to ensure the public is not inconvenienced, placed in danger and to prevent harm to the environment occurring.

#### 26. **Sign to be erected concerning unauthorised entry to the site**

A sign must be erected in a prominent position stating that unauthorised entry to the site is not permitted. The sign must also name the builder or other person responsible for the site and a telephone number at which the builder or other person can be contacted outside working hours. Where Council is not the Principal Certifying Authority, the sign shall also display the name and contact details of the nominated Principal Certifying Authority. The sign is to be removed when the building works have been completed.

Reason:- to restrict public access to the site and to provide suitable contact details in a clear and conspicuous position.

27. **Toilet accommodation for people working at the site**

Suitable toilet accommodation is to be provided at the work site at all times. If temporary toilet accommodation is proposed, it must:-

- Have a hinged door capable of being fastened from both inside and outside,
- Be constructed of weatherproof material,
- Have a rigid and impervious floor; and
- Have a receptacle for, and supply of, deodorising fluid.

Reason:- to ensure suitable toilet accommodation is provided for workers.

28. **Survey Report**

A Registered Surveyors check survey certificate is to be forwarded to the Principal Certifying Authority (and a copy is to be forwarded to the Council, if the Council is not the principal certifying authority), detailing compliance with Council's approval at the **following stage/s of construction:**

*(Setbacks and levels at commencement - new dwellings)*

- a) Prior to construction of the first completed floor/floor slab (prior to pouring of concrete), showing the area of land, building and boundary setbacks and verifying that the building is being constructed at the approved levels.

*(Setbacks and levels at completion - new dwellings)*

- b) On completion of the erection of the building showing the area of the land, the position of the building and boundary setbacks and verifying that the building has been constructed at the approved levels.

*(Maximum height of building at completion)*

- c) On completion of the building verifying that the maximum height limit of the building does not exceed 38 metres as per the maximum requirement established by Clause 4.3 of the Auburn Local Environmental Plan 2010.

Reason:- to ensure each stage of the development complies with the approved plans.

29. **Excavated and Filled Areas**

All excavated and filled areas shall be battered to a slope not steeper than two (2) horizontal to one (1) vertical and the fill area shall continue a minimum of one metre past the edge of the house, or similarly be retained in accordance with a retaining wall detail approved by Council. In the event that the retaining wall exceeds 600 mm when measured vertically from the base of the cut, the wall shall be designed by a

practicing Structural Engineer, the details submitted to Council, and approved prior to work commencing.

Reason:- to adequately retain excavated and filled areas and prevent soil movement, which may be detrimental to the subject or adjoining premises.

30. **Fencing of Construction Sites - Rental details to be provided to the PCA**

Public access to the site and building works, materials and equipment on the site is to be restricted, when work is not in progress or the site is unoccupied.

A temporary hoarding or fence is to be provided to protect the public, located to the perimeter of the site (unless the site is separated from the adjoining land by an existing structurally adequate fence, having a minimum height of 1.5 metres). Hoardings or fences are to have a minimum height of 1.8 metres and be constructed of solid plywood sheeting (painted white) or of cyclone wire fencing with geotextile fabric attached to the inside of the fence, to provide dust control.

Hoardings or fences are to be structurally adequate and be constructed in a good and workmanlike manner and the use of poor quality materials or steel reinforcement mesh as fencing is not permissible.

The public safety provisions and temporary fences must be in place prior to the commencement of any demolition, excavation or building works and be maintained throughout construction.

**NOTE: Should ANY part of the fence or hoarding encroach beyond the boundaries of the site, it will be necessary to:-**

- **Make payment to Council for the rental of the road reserve area in accordance with Council's adopted charges (per metre per month - minimum 3 months) BEFORE the fence/hoarding is erected.**
- **Supply evidence that the road reserve rental fee has been paid to the PCA and to any authorised Council officer.**
- **Comply with Council's specifications for the erection of Class A or B Hoardings.**

Reason:- to provide protection to public places and to prevent unauthorised access to the site.

31. **Sedimentation Control**

Prior to the commencement of site works, the following measures are to be implemented on the site to assist with sedimentation control during the construction phase of the project:-

- a) A dish shaped diversion drain or similar structure will be constructed above the proposed building works to divert run-off to a stable discharge area such as dense ground cover. This diversion drain is to be lined with turf or otherwise stabilised.
- b) A sediment-trapping fence using a geotechnical fabric specifically designed for such purpose and installed to manufacturer's specifications is to be placed below the construction area.
- c) Vegetation and/or existing building structures will be cleared from the construction site only, other areas to remain undisturbed.

- d) Restricting vehicle access to one designated point and having these driveways adequately covered at all times with blue metal or the like.
- e) A vehicle wheel wash, cattle grid, wheel shaker or other appropriate device, shall be installed prior to commencement of any site works or activities, to prevent mud and dirt leaving the site and being deposited on the street.
- f) Building operations such as brick cutting, washing tools or brushes and mixing mortar are not permitted on public roadways or footways or in any other locations which could lead to the discharge of materials into the stormwater drainage system.
- g) Stockpiles of topsoil, sand, aggregate, soil or other material shall not be located on any drainage line or easement, natural watercourse, footpath or roadway and shall be protected with adequate sediment controls.
- h) The installation of gutters, downpipes, and the connection of downpipes to the stormwater disposal system prior to the fixing of the roof cladding.

Such measures are to be maintained at all times to the satisfaction of Council and the Principal Certifying Authority. **Failure to do so may result in the issue of penalty infringement notices.**

Reason:- to minimise soil erosion and control sediment leaving the site during construction and to prevent water pollution from occurring.

32. **Display of a warning sign for soil and water management**

Throughout the construction/remediation/demolition period, a warning sign for soil and water management must be displayed on the most prominent point of the building site, visible to both the street and site works.

Reason:- to ensure all building workers are aware of the need to maintain the sediment and erosion control devices.

33. **Engineering Design - Basement Excavation**

The following engineering details or design documentation (where appropriate) shall be submitted to the Principal Certifying Authority (Council or accredited certifier) **prior to the issuing of a construction certificate:-**

- a) Documentary evidence prepared by a suitably qualified *professional geotechnical engineer* shall be submitted to the certifying authority, that confirms the suitability and stability of the site for the proposed excavation and building as well as certifying the suitability and adequacy of the proposed design and construction of the building for the site.
- b) A report shall be prepared by a *professional engineer* and submitted to the certifying authority prior to the issuing of a construction certificate, detailing the proposed methods of excavation, shoring or pile construction, including details of vibration emissions and detailing any possible damage which may occur to adjoining or nearby premises that may be caused by the proposed building and excavation works.

Any practices or procedures specified in the engineer's report in relation to the avoidance or minimisation of structural damage to nearby premises, are to be fully complied with and incorporated into the plans and specifications for the **construction certificate**.



A copy of the engineer's report is to be submitted to the Council, if the Council is not the certifying authority.

- c) Driven type piles/shoring **must not be provided** unless a geotechnical engineer's report is submitted to the certifying authority, **prior to the issuing of a construction certificate**, which states that damage should not occur to any adjoining premises and public place as a result of the works.
- d) The installation of ground or rock anchors underneath any adjoining premises including (a public roadway or public place) must not be carried out without the specific written consent of the owners of the affected adjoining premises and (where applicable) details of compliance must be provided to the certifying authority **prior to the commencement of any excavation or building works**.

Reason:- to ensure the proposed method of excavation is suitable for the site and to prevent damage from occurring to adjoining premises.

#### 34. **Excavations extending below the base of footings of adjoining development**

Where excavations extend below the level of the base of the footings of a building on an adjoining allotment of land, the person causing the excavation must preserve and protect the building from damage and, if necessary, underpin and support the adjoining building in an approved manner. The person causing the excavation must give the owner of the adjoining property at least seven (7) days written notice of its intention to excavate below the level of the base of the footing. The person must also furnish the adjoining property owner with particulars of the proposed work.

Reason:- to ensure the support for neighbouring buildings.

#### 35. **Dilapidation Report - Prior to Excavation of Basement**

- (a) A dilapidation report prepared by a *professional engineer* or suitably qualified building professional shall be submitted to the Principal Certifying Authority **prior to the commencement of demolition, excavation or building works**.

The report shall detail the current condition and status of all buildings, including ancillary structures (*i.e. including dwellings, residential flat buildings, commercial/industrial building, garages, carports, verandahs, fences, retaining walls, swimming pools and driveways etc.*) located upon all of the premises adjoining the subject site.

The report is to be supported with photographic evidence of the status of the buildings and a copy of the report must also be forwarded to the Council and to the owners of each of the abovementioned premises, prior to the commencement of any works. The applicant shall bear the full cost of this report.

- (b) Notwithstanding (a) above, certification by a practicing professional engineer in lieu of a dilapidation report may be provided **prior to the commencement of demolition, excavation or building works** certifying that the demolition, excavation and or building works will not have an impact on **any** adjoining structure including ancillary structures (*i.e. including dwellings, residential flat buildings, commercial/industrial building, garages, carports, verandahs, fences, retaining walls, swimming pools and driveways etc.*).

The applicant shall bear the full cost of this certification and the Council or Principal Certifier reserves the right to request a full report as described in (a) above should the certification provided by the engineer be considered unacceptable or insufficient.

Reason:- to enable the monitoring of any potential damage that may be caused to adjoining premises as a result of excavating and building in close proximity to the adjoining premises.

36. **Footpath area to be illuminated**

Where any hoarding or awning is constructed over the public place, the footpath area shall be kept illuminated between sunset and sunrise.

Reason:- to ensure the safety of pedestrians when passing the site.

37. **Fencing of construction sites - Rental details to be provided to the PCA (A & B Type Hoardings)**

A separate application is to be made to Council for Approval under Section 68 of the Local Government Act 1993 to erect any hoarding or scaffolding in a public place and such application is to include:

- A payment to Council for the following fees in accordance with Council's adopted charges:
  - Hoarding/Structure Application Fee
  - Rental of Footpath Area (per metre per month - minimum 3 months rental)
  - Footpath Bond
- Submit the following documents to Council with your application:
  - Certificate of Currency for Public Liability Insurance
  - Certificate of Currency for Worker's Compensation Insurance
  - Letter indemnifying Council against claims and expenses made in relation to the existence of the structure and/or traffic provisions
  - Traffic/Pedestrian Control Plan
  - In respect to any required Type B Hoarding, structural certification prepared and sign by an appropriately qualified practising Structural Engineer
- Comply with Council's specifications for the erection of Class A Hoardings.
- Supply evidence to the PCA and to any authorised Council officer that the road reserve rental fee has been paid.

Note: Public access to the site and building works, materials and equipment on the site is to be restricted, when work is not in progress or the site is unoccupied.

A temporary hoarding or fence is to be provided to protect the public, located to the perimeter of the site (unless the site is separated from the adjoining land by an existing structurally adequate fence, having a minimum height of 1.5 metres). Hoardings or fences are to have a minimum height of 1.8 metres and be constructed of solid plywood sheeting (painted white) or of cyclone wire fencing with geotextile fabric attached to the inside of the fence, to provide dust control.

Note: A "B Class" overhead type hoarding is required to be provided to protect the public, located adjacent to the development, prior to the commencement of any works on the site which comprise:

- Any works or hoisting of materials over a public footway or adjoining premises, or

- Any building or demolition works on buildings which are over 7.5 metres in height and located within 3.6 metres of the street alignment.

Hoardings or fences are to be structurally adequate and be constructed in a good and workmanlike manner and the use of poor quality materials or steel reinforcement mesh as fencing is not permissible.

The public safety provisions and temporary fences must be in place prior to the commencement of any demolition, excavation or building works and be maintained throughout construction. Details of the proposed hoardings or fences located upon the site are to be submitted to the PCA and the public safety provision and temporary fences must be in place prior to the commencement of any site works, demolition, excavation or building works and maintained throughout construction.

Reason:- to provide protection to public places, prevent unauthorised access to the site and a safe working environment.

38. **Soil and Water Management Plan - Large sites**

A Soil and Water Management Plan (also known as an Erosion and Sediment Control Plan) shall be prepared according to the NSW EPA's *Managing Urban Stormwater: Construction Activities*. This Plan shall be implemented prior to commencement of any site works or activities. All controls in the Plan shall be maintained at all times. A copy of the Soil and Water Management Plan must be kept on-site at all times and made available to Council officers on request.

Reason:- to ensure sediment and erosion controls are maintained during the construction process to prevent water pollution from occurring.

39. **Noise from construction activities**

Noise from construction activities associated with the development shall comply with the NSW Interim Construction Noise Guidelines (DECCW) 2009.

Reason:- to ensure noise arising from construction activities is in accordance with relevant legislation and Environment Protection Authority requirements.

40. **Dial before you dig (advisory)**

Dial Before You Dig is a free national community service designed to prevent damage and disruption to the vast pipe and cable networks which provides Australia with the essential services we use everyday - electricity, gas, communications and water.

Before you dig call "Dial before you dig" on 1100 (listen to the prompts) or facsimile 1300 652 077 (with your street no./name, side of street and the distance to the nearest cross street) or register on line at [www.dialbeforeyoudig.com.au](http://www.dialbeforeyoudig.com.au) for underground utility services information for any excavation areas.

The Dial Before You Dig service is also designed to protect Australia's excavators. Whether you are a back yard renovator, an individual tradesman or a professional excavator the potential for injury, personal liability and even death exists every day. Obtaining accurate information about your work site significantly minimises these risks.

Reason:- to ensure that essential services such as electricity, gas, communications and water are not affected by excavation or construction.

**41. Demolition of buildings**

The building/s shall only be demolished in accordance with the requirements of AS 2601-2001 "The Demolition of Structures".

Amongst others, precautions to be taken shall include compliance with the requirements of the WorkCover Authority of New South Wales, including but not limited to:-

- a) Protection of site workers and the general public.
- b) Erection of hoardings where appropriate.
- c) Asbestos handling and disposal where applicable.
- d) Any disused service connections shall be capped off to Council's requirements.
- e) The disposal of refuse is to be to an approved waste disposal depot.

Reason:- to ensure protection of the public, environment and to uphold public health standards. This also complies with the requirements of clause 92 of the Environmental Planning and Assessment Regulation 2000.

**42. Demolition - common sewerage system**

If the land to which the application relates is served by a common sewerage system that is also used by others, then measures must be placed in effect and prior to the commencement of work to ensure the operation of the sewerage system is without disruption to other joint users.

Reason:- to ensure demolition activities do not disrupt the operation of the sewerage system for other users of the system.

**43. Demolisher Details**

The demolisher/owner/applicant shall:-

- a) Lodge with Council, and at least forty-eight (48) hours prior to the commencement of work (due to the potential impact on Council's infrastructure):-
  - i) Written notice, indicating the date when demolition of the building is to commence.
  - ii) The demolisher's full name and address.
  - iii) Details of Public Liability Insurance.
- b) Comply with Australian Standard 2601 - 2001 "*Demolition of Structures*"; and,
- c) Have a current public liability/risk insurance, and policy details of such shall be submitted to Council for its records.
- d) Ensure that all possible/practicable steps are taken to prevent nuisance to the inhabitants of the surrounding neighbourhood from wind-blown dust, debris, noise and the like arising from the demolition works.

This Consent shall not preclude the demolisher from giving notice to other statutory authorities, such as Sydney Water Corporation, WorkCover, etc.

Reason:- to ensure details of the demolisher are provided to Council and relevant safety requirements are met.

#### 44. **Demolition Works - noise and vibration**

The following shall be compiled with:-

- a) Vibration levels induced by the demolition activities shall not exceed 1mm/sec peak particle velocity (ppv) when measured at the footing of any occupied building.
- b) Vibration levels induced by the demolition activities shall not exceed 3mmsec peak particle velocity (ppv) when measured at the footing of any unoccupied building.
- c) The upper noise level from the demolition operations measured over a period of 10 minutes must not exceed the background noise level by more than 10dB(A).

Reason:- to ensure noise and vibration arising from the demolition works does not impact on the amenity of the surrounding area.

#### 45. **Asbestos**

- a) In the event that asbestos is on a site or building under demolition or construction, WorkCover NSW is to be contacted to ascertain the appropriate response, to ensure the safety and protection of existing and future workers and residents. An Asbestos Removal Contractor licensed by WorkCover NSW is to handle/remove/transport and dispose of any products containing asbestos in a manner approved of by the Department of Environment and Conservation (DEC). Copies of tipping dockets are to be retained and able for viewing by Council officers on request.
- b) Asbestos material can only be disposed of at a landfill site nominated by Waste Services NSW for that purpose. An appointment must be made with Waste Services NSW to dispose of asbestos materials at the nominated landfill.
- c) Anyone who removes, repairs or disturbs bonded or a friable asbestos material must hold a current removal licence from Workcover NSW. Before starting work, a work site-specific permit approving each asbestos project must be obtained from Workcover NSW. A permit will not be granted without a current Workcover licence. All removal, repair or disturbance of or to asbestos material must comply with:-
  - i) Work Health and Safety Act 2011;
  - ii) The Work Health and Safety Regulation 2011;
  - iii) Protection of the Environment Operations Act 1997
  - iv) Environmental Guidelines: Assessment, Classification and Management of Liquid and Non-Liquid Wastes, NSW EPA, May 1999
  - v) Waste Avoidance and Resource Recovery Act 2001.
  - vi) The Code of Practice for the Safe Removal of Asbestos [NOHSC: 2002 (1998)];
  - vii) The Guide to the Control of Asbestos Hazards in Buildings and Structures [NOHSC: 3002 (1998)] <http://www.nohsc.gov.au> ; and
  - viii) The Workcover NSW Guidelines for Licensed Asbestos Removal Contractors.

Note: The Code of Practice and Guide referred to above are known collectively as the Worksafe Code of Practice and Guidance Notes on Asbestos. They are specifically referenced in the Occupational Health and Safety Regulation 2001 under Clause 259.

Under the Work Health and Safety Regulation 2011, the Worksafe Code of Practice and Guidance Notes on Asbestos are the minimum standards for asbestos removal work.

Council does not control or regulate the Worksafe Code of Practice and Guidance Notes on Asbestos. You should make yourself aware of the requirements by visiting <http://www.workcover.nsw.gov.au> or one of Workcover NSW's offices for further advice.

- d) In order to ensure safe handling of asbestos materials, the re-use or sale of asbestos building materials is strictly prohibited.

Reason:- to ensure the safe handling, treatment and disposal of asbestos materials arising from the demolition/construction works.

46. **Services to be capped**

Prior to the commencement of demolition works, the applicant must ensure that utility services to the land upon which the building to be demolished stands, as well as the building itself, are terminated and capped in accordance with the requirements of supply authority, eg. Electricity-Supplier of Electricity to the subject premises, Gas-Supplier of Gas to the subject premises.

Reason:- to ensure all services are capped adequately.

47. **Site to be kept in a clean condition**

Upon completion of demolition works and if no new building works are commenced on site, the site shall be kept in a clean manner with landscaping and fencing to the satisfaction of Council.

Reason:- to control soil erosion, and not have any unsightly views.

48. **Neighbour 24 notification of commencement of demolition**

Prior to the commencement of work the applicant shall provide 24 hours notice in writing to the neighbours adjoining and opposite the site of the intended time and date of the start of the demolition work.

Reason:- to ensure details of the demolisher are provided to neighbours.

49. **Reinstatement of footpath and footpath crossing**

The footpath and footpath crossing/s adjacent to the property shall be reinstated by Council at the completion of works with all costs being borne by the developer. Alternatives to the pre-payment for this work will be considered if written request is made to Council.

Reason:- to ensure the footpath and the footpath crossings are repaired from any damage caused during the construction phase.

50. **Vehicle Driveway Crossings and Gutter Laybacks**

Arrangements shall be made with Council for the prepaid construction of vehicular crossings and gutter laybacks at all property entrances and exits, and for the removal of all disused driveway crossings and gutter laybacks. Alternatives to the prepayment for this work will be considered if written request is made to Council. The gutter crossing and/or the removal of any redundant crossings must be constructed to the satisfaction of Council (and to the Council's specifications including payment of any required bonds) or the prepayment made to Council for Council to carry out the work, prior to the issue of any occupation certificate.

Removal of obstructions, such as power poles, trees, drainage pits and the like shall be carried out at the applicant's expense.

Reason:- to ensure that works are carried out in accordance with Council's standard.

51. **Carrying capacity of driveways - Heavy duty**

Suitable heavy-duty driveway crossings are to be installed at all ingress/egress points to the property at the applicant's cost by Council. Alternatives to the prepayment for this work will be considered if written request is made to Council. The gutter crossing and/or the removal of any redundant crossings must be constructed to the satisfaction of Council (and to the Council's specifications including payment of any required bonds) or the prepayment made to Council for Council to carry out the work, prior to the issue of any occupation certificate.

Reason:- to ensure the driveways can support the expected weight of heavy vehicles likely to frequent the site.

52. **Street boundary levels**

Street boundary levels for vehicle access and drainage purposes are to be obtained at the applicant's cost from Council's Service Planning Department prior to commencement of any works. These levels are to be incorporated in all drainage submissions required under this determination.

Reason:- to ensure the correct levels are obtained and used for the development.

53. **Road opening permit**

Prior to commencement of any work on Council roads and footpaths, a road-opening permit shall be obtained from Council's Service Planning Department.

Reason:- to safeguard Council property against damage.

54. **Restoration works**

Prior to commencement of any excavation work on Council roads or footpaths, the applicant shall pay for all restoration costs. The area of restoration shall be determined on site between the applicant or its contractor and Council's Contracts & Maintenance Engineer.

Reason:- to ensure that Council's infrastructure is maintained in a safe and trafficable manner.

---

55. **Structural Engineering Certificate**

The applicant shall submit a structural engineer's certificate of adequacy verifying that the works as detailed on the approved plans for the storage tank have been completed under his/her supervision and that the design is adequate to support the anticipated design loads. **The certificate shall be submitted to Council with the works-as-executed plan.**

Reason:- to ensure the construction is structurally adequate.

56. **Water Reuse**

The stormwater generated from the roof area shall be reused for the irrigation of the landscape area within the subject development site.

Full details of the Water reuse facilities shall be submitted to Council or the Accredited Certifier with the Construction Certificate.

On completion, a certificate from a registered plumber shall be submitted for the pipe network. The certification shall indicate the water reuse system has been installed in accordance with the approved water reuse design plans.

Reason:- to ensure the water reuse facilities within the development are constructed and maintained in good working order.

57. **Submission of full stormwater disposal details**

Full stormwater drainage details showing the proposed method of stormwater collection and disposal are to be submitted to Council or the Accredited Certifier to ensure the approved stormwater plans are incorporated with the Construction Certificate.

The details shall be prepared by a suitably qualified person and must be in accordance "Auburn Development Control Plans 2010 - Stormwater Drainage" and "Australian Rainfall & Runoff 1987". In this regard,

- i. ***The proposed stormwater system shall be generally in accordance with the stormwater concept plans approved as part of the deferred commencement conditions.***
- i. ***All access grates to the detention facility shall be double (2/900x450) hinged grates.***
- ii. Maximum spacing between the grated access pits in the OSD shall not exceed 5.0m.
- iii. A 900x900 size opening with double (2/900x450) hinged grates access grate shall be provided behind the flap valve.
- iv. Stormwater runoff from access ways will have to undergo some form of industrial standard primary treatment/separation prior to disposal into existing stormwater systems. In this regard, stormwater treatment device capable of removing litter, oil, grease and sediment shall be provided prior to discharge to the stormwater system.



Note: "Auburn Development Control Plans 2010 - Stormwater Drainage" is available to purchase at Council or the document can be found at Auburn Council's web page [www.auburn.nsw.gov.au](http://www.auburn.nsw.gov.au)

Reason:- to ensure the stormwater is suitably discharged.

58. **Stormwater disposal - on-site detention**

On-site stormwater detention storage is to be provided in conjunction with the stormwater disposal. The storage is to comply with "Auburn Development Control Plans 2000 - Stormwater Drainage". Where multiple detention basins with differing top water levels are used, the basins must be routed to the outlet pit independent of each other.

A positive covenant under Section 88E of the Conveyancing Act is to be created on the title of the property detailing the on-site stormwater detention system incorporated in the development. The wording of the instrument is to be submitted and approved by Council prior to lodgement at the Land Titles Office. Evidence confirming the positive covenant has been registered shall be submitted to Council prior to occupation of the building or issue of the occupation certificate.

Note:

1. Positive covenant wording shall be obtained from Council prior to lodgement.
2. Work as executed plan shall be accompanied by relevant checklists.

Reason:- to prevent localised flooding by ensuring the detention system is maintained as designed.

59. **Maintenance schedule - OSD**

Prior to the issue of the occupation certificate, a maintenance schedule of the proposed on-site detention facility shall be submitted to Council for approval with the stormwater work-as executed plan. This maintenance schedule shall be registered as part of the positive covenant.

Reason:- to ensure the onsite detention facility is in good working order.

60. **Annual maintenance inspection of OSD**

Annual maintenance inspection summary of the onsite detention with associated certificates shall be sent to Council within the first month of every calendar year. In this regard:-

- All critical inspections shall be carried out by a qualified person.
- A maintenance log book shall be maintained as per the approved maintenance schedule on site and readily available for inspection by a Council officer.
- All associated cost shall be borne by the owner.

Reason:- to ensure the onsite detention facility is in good working order.

61. **Engineer Certificate for pump**

A certificate from a practising hydraulic engineer verifying that the stormwater pump

installation and the design with the executed levels shall be submitted to the Council with the work as executed plan prior to the release of Occupation Certificate.

Reason:- to ensure the system has been constructed Council's standards and specifications.

62. **Basement drainage system**

Basement drainage is to comply with "Auburn development control plans 2010 stormwater drainage". In this regard:

- a) Two pump units being installed, the capacity of each being calculated on the basis of a hundred year storm recurrence interval and a storm duration of 5 (five) minutes, one pump acting in reserve capacity.
- a) The two pumps being designed to work on an alternate basis to ensure that both pumps receive equal usage and neither pump remain continuously idle.
- b) A holding well being provided within the basement, of sufficient capacity to store the discharge based on a hundred year storm recurrence interval and storm duration of ninety minutes. In addition to this an above ground storage shall be provided up to a hundred year storm recurrence interval and storm duration of two hours. The holding well is to be designed so that a minimum volume of water is retained in the well for health reasons when the pumps are in the "off" position or if there is a break in electric supply.
- c) A storm of two hours' duration has been adopted as a basis for determining the size of the well, the assumption being that electric supply will be reinstated within this period.
- d) The pump out system is to be independent of any gravity drainage line except at the property boundary where a grated surface pit is to be constructed from which a connection will be permitted to the gravity drainage system. The invert levels of the pipes in the grated surface are to be such that the outlet from the pump out system is above the invert of the gravity system.
- e) Storage areas and areas used for purposes other than car parking access aisles are to be constructed a minimum of 100mm above the finished water level.
- f) The contributing catchment area to the pump out system is to be limited to the access ramp area only and subsoil drainage.

Reason:- to prevent localised flooding.

63. **Development at no cost to Roads and Maritime Services**

All works, regulatory signposting associated with the proposed development are to be at no cost to the Roads and Maritime Services.

Reason:- to ensure the developer pays for all regulatory signposting.

---

64. **Power pole and any streetlight relocation**

The power pole and streetlight shall be relocated to provide appropriate clearance to the driveway at no cost to Council. In this regard:-

- a) Letters from relevant service authority shall be submitted for the relocation of the existing power pole and streetlight to satisfy the above requirements.
- a) Documents showing compliance of above requirements shall be submitted to and approved by Principal Certifying Authority as part of Construction certificate and **a copy shall be forwarded to Council as part of construction certificate if Council is not the Principal Certifying Authority.**

Reason:- to ensure service authority's consent is obtained for the driveway alignment.

65. **Vehicle manoeuvring**

The swept path of the longest vehicle to service the site entering and leaving as well as manoeuvrability within the site shall be in accordance with Austroads. Appropriate plans shall be submitted with the Construction Certificate confirming full compliance with the AUSTROADS provisions.

Reason:- to ensure adequate manoeuvrability of vehicles within and external to the site.

66. **Footpath Construction - Northumberland Road**

The footpath adjoining the site (all two frontages) shall be constructed in concrete unit paving in accordance with the **Auburn Council Town Centres Infrastructure Manual**. All associated costs shall be borne by the applicant. Site boundary levels shall be raised where necessary to eliminate any existing low-level footpath profiles, with satisfactory end-transitions provided. In this regard:-

- a) Prior to the issue of any Construction Certificate, detail footpath design shall be submitted and approved by Council's Works and Services section.
- a) Street boundary levels obtained from Council shall be incorporated in the design.
- b) All services shall be adjusted to relevant Authority requirements to the design levels.
- c) All associated cost shall be borne by the applicant.

Reason:- to provide a safe footpath for increased pedestrian use and one that will complement the Auburn Council requirements.

67. **Works-as-Executed Plan - Drainage Plans**

Prior to occupation of the building or issue of the occupation certificate, two (2) copies of the Works-as-Executed (W.A.E.) Plan prepared by a registered surveyor and certified by the design engineer shall be submitted to Council. The W.A.E. plan shall show (where applicable):

- i) Whether all works have been completed generally with the approved drainage plans.
- ii) Any departure from the approved plan and conditions.
- iii) Any additional work that has been undertaken.
- iv) Location, levels and sizes of pipes and pits.
- v) Finished floor and finished surface levels. The location of finished levels should in general correspond with those shown on Council's approved drainage plan.
- vi) Basement pump out volumes.

**NOTE:** The WAE surface level shall be taken after all landscaping has been completed.

In this regard:

- The above information is to be superimposed on a full sized copy of Council approved drainage plan and is to be submitted to Council.
- Checklists A3, A4 & A5 in the appendix of the "Auburn development control plans 2000 stormwater drainage" shall be completed and shall be certified by the practicing hydraulic engineer and the registered surveyor.

**Reason:-** to account for minor variations and to ensure Council has the final details.

68. **Creation of drainage easement**

Prior to the issue of any Occupation certificate, a drainage easement over the diverted drainage line shall be created in favour of SP 50061 over the subject development to Council's satisfaction. In this regard:-

All necessary documents shall be submitted to Council for approval.

Auburn Council shall be nominated as the authority to vary or modify the drainage easement.

All associated cost shall be borne by the applicant.

**Reason:-** to ensure the existing easement benefit is maintained.

69. **Stormwater disposal**

All stormwater runoff generated from the proposed development shall be directed to the On Site Detention system prior to being discharged to Council's underground drainage system in Northumberland Road.

**Reason:-** to prevent localised flooding.

70. **On street drainage design**

Prior to the issue of any Construction Certificate a detail design for the proposed connection to existing Council's stormwater pipe shall be submitted and approved by the Manager of Development Assessment of Auburn City Council. In this regard:-

Longitudinal section, of the proposed stormwater outlet within the Council controlled land, showing the depth and location of all the services within the area of the proposed works shall be submitted.

Reason:- to ensure Council's assets are designed to Council's requirements.

71. **On street drainage construction**

Prior to the commencement of any drainage works the street drainage works shall be completed to Council's satisfaction at no cost to Council. In this regard:-

Inspections will be required for the works related to the proposed connection to Council's storm water drainage system at following stages:

- After the excavation of pipeline trenches.
- After the laying of all pipes prior to backfilling.
- After the completion of all pits and connection points.

A minimum of 48 hours' notice shall be given to Council to inspect works. Inspections may be arranged by telephoning Council's Works and Services Section during office hours.

Work is not to proceed until the works are inspected and approved by Council.

Reason:- to ensure Council's assets are constructed to Council's requirements.

72. **Stormwater from the property SP 50061**

The stormwater generated from SP50061 known as 4 Station Road Auburn, shall be drained through the subject development site during and after construction. In this regard, all required details shall be shown on the stormwater plan and approved as part of deferred commencement Condition. The PCA shall ensure the operation of the system during and after construction.

Reason:- to ensure prevent localised flooding and ensure the system in operation.

73. **Works within Council controlled lands**

(1) For drainage works:

Within Council controlled lands.

Connecting to Council's stormwater drainage system.

Inspections will be required:-

- After the excavation of pipeline trenches.
- After the laying of all pipes prior to backfilling.
- After the completion of all pits and connection points.

(2) A minimum of 48 hours' notice shall be given to Council to inspect works. Inspections may be arranged by telephoning Council's Works and Services Section during office hours.

(3) Work is not to proceed until the works are inspected and approved by Council.

Reason:- to ensure works on public/Council controlled lands are carried out as per Council's requirements.

74. **Footpath /Nature strip maintenance during and after construction**

The footpath and nature strip within the street frontages shall be maintained during the period of construction to Council's satisfaction.

Reason:- to ensure pedestrian safety during the construction period.

75. **Traffic Management**

A traffic management plan shall be submitted to and approved by Council for all demolition, excavation and construction activities associated with the development prior to commencement of work.

Reason:- to minimise the impact on street traffic.

76. **Ramp gradients**

Circulation ramp grades shall comply with section 2.5.3 of the Australian Standard AS2890.1:2004. In this regard detail longitudinal section of the ramps to a scale of 1:20, shall be submitted to and approved by the Principal Certifying Authority prior to the issue of any Construction Certificate.

Copy of the approved plan shall be submitted to Council.

Reason:- to ensure the access ramps comply with Australian Standard AS28890.1:2004.

77. **Service relocation / Adjustment**

The applicant shall locate any utility services affected by the proposal and shall be responsible for any damage to, or relocation of services required by the proposal including adjustment to the levels of pit lids etc. All works shall be carried out to the satisfaction of the relevant Authority or Council.

All the costs shall be borne by the applicant.

Reason:- to protect utility services.

78. **Limit of the delivery trucks**

Vehicles making deliveries to the premises shall be limited Medium rigid vehicle (MRV) that is defined in Australian standard AS2890.2.

Reason:- to ensure delivery trucks use approved loading area.

79. **Light Overspill**

Any lighting on the site shall be designed so as not to cause nuisance to other residences in the area or to motorists on nearby roads, and to ensure no adverse impact on the amenity of the surrounding area by light overspill. All lighting shall comply with *AS4282-1997 Control of the obtrusive effects of outdoor lighting*.

Reason:- to ensure light overspill arising from the development does not interfere with the amenity of the locality and complies with relevant Australian Standards.

**80. Arrangements for Water and Sewer Services**

A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained.

**Application must be made through an authorised Water Servicing Coordinator. Please refer to “Your Business” section of Sydney Water’s web site at [www.sydneywater.com.au](http://www.sydneywater.com.au) then the “e-developer” icon or telephone 132 092.**

Following application a “Notice of Requirements” will detail water and sewer extensions to be built or charges to be paid. Please make early contact **with the Coordinator**, since building of water/sewer extensions can be time consuming and may impact on other services and building, driveway or landscaping design.

The Section 73 Certificate must be submitted to the Principal Certifying Authority (Council or accredited certifier) **prior to release of the final plan of subdivision or occupation of the development.**

Reason:- to ensure that adequate water and sewer services can be provided to the site.

**81. Stamping of development application plans by Sydney Water**

The approved development application plans must be submitted to a Sydney Water Quick Check agent or Customer Centre to determine whether the development will affect Sydney Water’s sewer and water mains, stormwater drains and/or easements and if further requirements need to be met. Plans will be appropriately stamped.

Please refer to the web site [www.sydneywater.com.au](http://www.sydneywater.com.au) for:

- Quick Check agents details - see Building Developing and Plumbing then Quick Check; and
- Guidelines for Building Over/Adjacent to Sydney Water Assets - see Building Developing and Plumbing then Building and Renovating or telephone 13 20 92.

**Note:**

The consent authority or accredited certifier must either:

- ensure that a Quick Check agent/Sydney Water has appropriately stamped the plans before the issue of any Construction Certificate; or
- if there is a combined Development/Construction Certificate application, ensure that a Quick Check agent/Sydney Water has appropriately stamped the plans prior to works commencing on site.

Reason:- to ensure the development does not damage or interfere with Sydney Water assets.

**82. Television Aerial/Satellite Dish**

A single common television aerial, and/or satellite dish (having a maximum diameter of 700mm and not located on the front or street elevation of the building) is to be installed to serve the development.

Reason:- to ensure the provision of these services does not impact on the finished

appearance of the development.

83. **Aboveground Power Lines**

Where practicable, all existing overhead power lines adjacent to the development site shall be relocated underground to Energy Australia standards and specifications. If not practicable to relocate the power lines underground, arrangements shall be made with Energy Australia to place the conduit to carry those power lines underground so that they can be utilized at a later date by Energy Australia. In this regard all associated costs shall be borne by the applicant.

Reason:- to improve the aesthetic quality of the area.

84. **Mail Box Structure**

An Australia Post approved lockable mail box structure shall be centrally located to the primary street entry of the site.

Reason:- to ensure compliance with Council's Development Control Plan requirements.

85. **Subdivision development application requirements**

The following requirements will apply to any future development application for subdivision at the site:-

- a) The Strata subdivision or other subdivision of the development being the subject of a further Development Application to Council; and,
- b) This development application for subdivision must be accompanied by the following documentation that indicates:-
  - i) The requirement for the employment of a person to manage the collection of waste material by Council, including, but not limited to bin placement at the road edge and retrieval of bins soon after collection of contents, cleansing of bins, storage of bins in the compound and the like.
  - ii) Responsibilities with regard to the ongoing maintenance of the building and landscaped areas at the property in accordance with the plans and details approved under this Development Consent.
  - iii) Responsibilities with regard to the operation maintenance of artificial features at the property (eg water features, intercom systems, vehicle access doors etc.) in accordance with the plans and details approved under this Development Consent.
  - iv) Responsibilities for ensuring owners and/or tenants have adequate and hygienic waste storage, disposal and collection arrangements and for ensuring the waste storage area is appropriately maintained and kept in a clean and safe state at all times.
  - v) Responsibilities to ensure that receptacles for the removal of waste, recycling on the designated day of collection.
  - vi) The Owners Corporation obligations under clauses 177, 182, 183, 184, 185 and 186 of the Environmental Planning and Assessment Regulation 2000.
  - vii) The Owners Corporation/Executive Committee obligations to ensure all wastewater and stormwater treatment devices (including drainage systems, sumps and traps) are regularly maintained in order to remain



effective. All solid and liquid wastes collected from the devices shall be disposed of in a manner that does not pollute waters and in accordance with the Protection of the Environment Operations Act 1997.

Reason:- to ensure appropriate documentation is submitted with any application for subdivision of the development.

86. **Discovery of additional information during remediation, demolition or construction**

Any new information which comes to light during remediation, demolition or construction works which has the potential to alter previous conclusions about site contamination shall be notified to the Council and the PCA immediately.

Reason:- to ensure Council is informed of any new information relevant to site conditions and site contamination associated with the development.

87. **Off-site soil disposal**

Any soil disposed of offsite shall be classified in accordance with the procedures in the NSW EPA Environmental Guidelines: Assessment, Classification & Management of Liquid & Non-Liquid Wastes (1999).

Reason:- to ensure soil disposed off-site is classified in accordance with relevant EPA requirements.

88. **Number of Car Parking Spaces**

A total of 171 off-street car parking spaces are to be provided to the development as follows:-

- Residential - Minimum 144 spaces.
- Commercial - 15 spaces.
- Visitor - 12 spaces.

The spaces are to have minimum dimensions of 5.5 m x 2.4 m and be suitably sealed, marked, drained and freely accessible at all times. Visitor car parking spaces shall be a minimum width of 2.6 m.

Carparking spaces are not to be enclosed by any device, such as a wire or mesh cage, walls or other similar fixtures unless there is a minimum clear internal width of 3 metres. Carparking spaces shall not be enclosed without the prior consent of council.

Reason:- to ensure there is sufficient car parking for the development and to comply with Auburn Parking & Loading DCP.

89. **Signs for Visitor Parking**

Suitable signs shall be erected at the front of the property indicating the availability of visitor parking within the property. All visitor parking spaces shall be clearly sign marked.

Reason:- to ensure the visitor parking spaces are clearly identified.

---

90. **Adequate Signs and Pavement Markings Required to Assist Traffic Flow on Site.**

Adequate signs and pavement markings are to be provided to direct the flow of traffic within the site. Details are to be provided prior to the issue of the construction certificate.

*Reason:-* to assist with traffic flow within the development.

91. **Vehicles Driven in Forward Direction**

All vehicles must be driven in a forward direction at all times when entering or leaving the premises.

*Reason:-* to preserve and enhance the safe operation of the car parking area.

92. **Garbage collection times**

Garbage collection shall only occur between the hours of 7 am to 6 pm Monday to Saturday. There shall be no garbage collection at any other times.

*Reason:-* to ensure garbage collection occurs at times with least impact to residents.

93. **Protective bar to vehicular entry**

A protective bar shall be installed at the vehicular entry to the development to prevent damage from vehicles that are too high or those that fail to wait for the opening of any roller shutter etc. Details and installation of the proposed protective bar shall be noted on the Construction Certificate drawings and installed prior to the issue of Occupation Certificate.

*Reason:-* to prevent damage from oversized vehicles when entering the premises.

94. **Roller doors and shutters - silent operation**

The roller doors or other shutters to the car park shall operate silently and be appropriately maintained.

*Reason:-* to ensure quiet operation and ongoing maintenance to car park doors.

95. **Intercom/remote access to basement**

An intercom and remote access system shall be provided at all vehicular access points to the basement car park and connected to all residential units. Details of the proposed intercom and remote access system to the basement car park are to be submitted with the Construction Certificate plans/specifications and the locations detailed on the construction drawings.

*Reason:-* to ensure that visitor car parking spaces are easily and conveniently accessible for visitors to the premises.

96. **Driveway surface treatment**

Driveway surface treatments must finish at the property boundary.

Reason:- to ensure compliance with Council's Development Control Plan requirements.

97. **Car Parking Spaces - Restrictive Covenant**

The following shall be complied with:-

- a) The on site car parking spaces, exclusive of service and visitor spaces, are not to be used by those other than the occupant or tenant of the subject building. Any occupant, tenant, lessee or registered proprietor of the development site or part thereof shall not enter into an agreement to lease, license or transfer ownership of any car parking spaces to those other than an occupant, tenant or lessee in the building.
- b) Prior to Occupation Certificate under the Environmental Planning and Assessment Act 1979 a documentary Restrictive Covenant, is to be registered on the Title of the development site pursuant to Section 88E of the Conveyancing Act 1919, to the effect of (a) above. The Covenant is to be created appurtenant to Council, at no cost to and to the satisfaction of Council.
- c) Any future strata subdivision of the site is to include a Restriction on User pursuant to Section 39 of the Strata Titles (Freehold Development) Act 1973, as amended, burdening all utility car parking allotments in the Strata Plan and/or an appropriate Restrictive Covenant pursuant to Section 88B of the Conveyancing Act 1919 burdening all car parking lots in the strata scheme.

Reason:- to ensure the car parking spaces are used in accordance with the details of the development approval.

98. **Car park and service vehicle area layout**

- a) The layout of the car park shall comply with Australian Standard AS2890.1:2004 Parking Facilities Part 1: Off Street Parking. All parking spaces are to be line marked.
- b) The layout of the service vehicle area shall comply with Australian Standard AS2890.2:2004 Off Street Parking Part 2 - Commercial Vehicle Facilities.

Reason:- to ensure that the car parking and service vehicles areas are designed and constructed to meet relevant Australian Standards.

99. **Headroom clearance - within the Basement**

The headroom clearance within the basement shall comply with AS 2890.1 and 2890.6 requirements. Minimum 2.2m headroom clearance shall be provided within the basement and all the car parking spaces except accessible car parking spaces.

Minimum 2.5m headroom shall be provided within the accessible car parking spaces.

In this regard detail longitudinal section of ramps, to a scale of 1:20, shall be submitted to and approved by the Principal Certifying Authority prior to the issue of any Construction Certificate.

Reason:- to ensure headroom clearance complies with Australian Standards AS 2890.1 AS2890.6 and Council's DCP.

**100. Materials and Finishes**

Materials and finishes to the development shall be in accordance with the details of the approved plans and the following requirements:-

- a) Quality and durable materials are to be used throughout the development.
- b) The applied external paint finishes to the building shall have a minimum aggregate thickness of 200 microns.

Reason:- to ensure a high quality appearance to all materials within the development.

**101. SEPP 65 - Design Verification**

The following requirements arising from State Environmental Planning Policy No. 65 - Design Quality of Residential Flat Buildings must be complied with:-

- a) A certifying authority must not issue a Construction Certificate in respect of the development unless the certifying authority has received a design verification from a qualified designer, being a statement in which the qualified designer verifies that the plans and specification achieve or improve the design quality of the development for which development consent was granted, having regard to the design quality principles set out in Part 2 of State Environmental Planning Policy No. 65 - Design Quality of Residential Flat Development.
- b) A certifying authority must not issue an Occupation Certificate to authorise a person to commence occupation or use of the development unless the certifying authority has received a design verification from a qualified designer, being a statement in which the qualified designer verifies that the development as shown in the plans and specifications in respect of which the Construction Certificate was issued, having regard to the design quality principles set out in Part 2 of State Environmental Planning Policy No. 65 - Design Quality of Residential Flat Development.

Reason:- to ensure that the requirements of SEPP No. 65 and the EP&A Regulations are complied with in the carrying out of the development.

**102. Architect - Notify Council if Changed**

The architect of the project, as approved, should not be changed without prior notice to Council.

Reason:- to ensure Council is aware and kept informed of the current project architect.

**103. Common Wall Construction**

Prior to the issue of a Construction Certificate, construction drawings shall be submitted to the Principal Certifying Authority for approval to indicate that common party walls between the dwellings being constructed from solid masonry materials and not being lightweight construction.

Reason:- to ensure adequate acoustic separation between dwellings within the development.

**104. Plumbing - separation and containment**

Prior to the issue of a Construction Certificate, construction drawings shall be submitted to the Principal Certifying Authority for approval to indicate that plumbing to each dwelling will be separated and adequately contained to prevent noise transmission and vibration.

Reason:- to ensure adequate separation and containment of plumbing between dwellings.

**105. Lockable Pedestrian Entries**

All shared pedestrian entries to the buildings must be lockable.

Reason:- to ensure adequate security provision to shared pedestrian entries to the development in accordance with Council's Development Control Plan requirements.

**106. Underside of balconies**

The underside of the balconies within the development must be designed to prevent exposed pipes and utilities being visible.

Reason:- to ensure an attractive appearance to the development in accordance with Council's Development Control Plan requirements.

**107. Switchboards/Service Panels**

Switchboards and/or service panels for utilities are not to be attached to the front facades/elevations of the building.

Reason:- to ensure that switchboards and service panels are appropriately located and do adversely impact on the appearance/presentation of the front building facade.

**108. Air conditioning units - location and acoustics**

- a) Air conditioning units are not to be visible from the street or public place and are not to obscure windows/window frames or architectural features of the building.
- b) The operation of air conditioning units shall be so:
  - (i) as not to cause "offensive noise" as defined under the Protection of the Environment Operations Act 1997;
  - (ii) as to be inaudible at the nearest affected residence between the hours of 10.00pm and 7.00am on weekdays and 10.00pm and 8.00am on weekends and public holidays;
  - (iii) as not to discharge a condensate or moisture onto the ground surface of the premises or into a stormwater drainage system in contravention of the requirements of the Protection of the Environment Operations Act 1997.
- c) Should Council receive noise complaints from neighbouring residents in relation to the air conditioning units, Council may issue a Noise Notice. Such notice may require you to engage the services of a competent and appropriately qualified Acoustic Consultant to undertake a noise level assessment of the air conditioning unit. If the unit is assessed as exceeding

the permitted noise criteria, you may be directed to provide noise attenuation measures such as an acoustic enclosure and/or relocation of the unit.

Reason:- to ensure that air conditioning units associated with the development are appropriately located and do not detract from the appearance of the buildings and to ensure the operation of air conditioning units does not adversely impact on the acoustic amenity of the locality.

109. **Compliance with Submitted Acoustic Report**

All noise control measures specified in the acoustic assessment report prepared by Acoustic Logic Reference number 20141400.1/1512A/R0/JL and dated 15/12/2014 shall be installed prior to the issuing of the occupation certificate. All noise reduction measures specified in the acoustic report shall be complied with at all times during the operation of the premises.

Reason:- to ensure and maintain appropriate residential amenity and noise reduction.

110. **Acoustic Certification**

Within three months of the premises being occupied, an acoustic report prepared by a suitably qualified person is to be submitted to the consent authority demonstrating that the noise emitted from the premises complies with the criteria contain in the acoustic assessment report prepared by Acoustic Logic Reference number 20141400.1/1512A/R0/JL dated 15/12/2014. The acoustic report is to include recommendations for additional noise control measures that are to be implemented to ensure compliance with the criteria should the criteria not be achieved.

Reason:- to ensure appropriate residential amenity and noise control.

111. **Future use of commercial tenancies and mechanical ventilation systems**

The commercial tenancies are to be designed so that a mechanical ventilation exhaust system is capable of being installed within each tenancy in accordance with the relevant Australian Standards to allow for any future use as a food premise.

Details shall be shown in the Construction Certificate for approval by Council or the Accredited Certifier.

Reason:- to ensure mechanical ventilation can be provided to the tenancies.

112. **Ventilation of the basement car park**

The basement car park shall be naturally or mechanically ventilated. The ventilation system shall comply with the requirements of the Building Code of Australia and relevant standards including AS1668.1 - 1998 - The Use of Ventilation and Air conditioning in Buildings Part 1: Fire and Smoke Control in Multi Compartment Buildings and/or AS 1668.2-2002; The Use of ventilation and Air conditioning in Buildings Part 2: Ventilation Design for Indoor Air Contaminant Control.

The system shall be certified by a suitably qualified and experienced engineer at the completion of installation prior to the issue of an Occupation Certificate. A copy of the certificate shall be provided to the Principal Certifying Authority (PCA). A copy shall also be provided to Council if Council is not the Principal Certifying Authority.

Any mechanical ventilation provided to the basement car park shall not create an offensive odour emission nor shall it create offensive noise. The system shall comply with the requirements of the Protection of Environment Operations Act and all subsequent relevant Regulations.

Reason:- to promote a satisfactory ventilation system within the basement car park.

113. **Use of building not to commence until conditions of consent satisfied**

The use of the premises is not to commence until all terms of this consent have been satisfied.

Reason:- to ensure compliance with the terms of the development consent.

114. **Separate consent required prior to occupation of premises**

Separate Development Consent must be obtained prior to occupation of the commercial tenancies (Both tenancies) situated on the ground floor of the building.

Reason:- to control and regulate the use of the premises.

115. **Side/Rear Boundary Fencing**

Fences located on the side or rear boundaries of the premises, behind the main building setback (not within the front yard), shall not exceed a maximum height of 1.8 metres.

Reason:- to maintain reasonable levels of amenity to the adjoining premises.

116. **Fencing/gates and adjoining land**

There must be no encroachment of any part of the structure/s onto the adjoining premises or onto Council's road reserve, footway or public place.

Reason:- to ensure that encroachments do not occur.

117. **Surveillance tapes:**

The surveillance tapes captured by the CCTV cameras shall be kept for a period of 14 days for viewing by the police upon request with the recording device located in a secure area to maintain the integrity of the recorded footage.

- Digital and monitored technology should be used to record images from the cameras.
- Installed surveillance equipment should be maintained in working order and regularly tested.

Reason:- to improve public safety late at night and to maintain the integrity of the recorded footage.

118. **CCTV Camera System**

The Management/Licensee shall install CCTV surveillance cameras in and around the premises, placed in strategic places such as the external entrance and exit

doors. The surveillance tapes shall be kept for a period of 14 days for viewing by the police upon request.

Reason:- to ensure that the use provides adequate visual surveillance and adequate records for the NSW Police to peruse is required.

119. **Warning signage**

Warning signs shall be placed strategic points within the premises especially near entry points to warn intruders of the security measures of the building. Examples of such signage may include:-

- Warning - The premises are under constant surveillance.
- Warning - Don't leave valuables inside your vehicle.

In addition, directional signage should be posted at decision making points such entry / exit points to provide guidance to drivers whilst driving their vehicle.

Details shall be shown in the Construction Certificate plans for approval by Council or the Accredited Certifier.

Reason:- to improve and promote adequate safety for the building and club premises

120. **Cleaning of facade**

The owner/manager of the building shall ensure that all windows on the facade, and the facade itself, of the premises are cleaned regularly and, in any event, not less than twice in an annual period.

Reason:- to ensure regular maintenance and cleaning to the exterior of the premises.

121. **Telecommunications Facilities - Residential**

The following requirements apply to telecommunication facilities in the building:-

- a) Appropriate access and space within the plant area of the building shall be provided for a minimum of three telecommunication carriers or other providers of broad-band access by ground or satellite delivery.
- b) Appropriate ducting and cabling shall be provided for a minimum of three telecommunication carriers or other providers for telecommunication access and broad-band cabling to each apartment of the building.
- c) The details of (a) and (b) above shall be submitted for the approval of the certifying authority, prior to issue of a construction certificate for the building under the Environmental Planning and Assessment Act 1979.
- d) A separate Development Application must be submitted at the appropriate time for any external receiving device proposed to be installed. For each form of transmitter, there shall be only one common receiving device installed on the subject development.

Reason:- to ensure adequate provision for telecommunication facilities within the development.

122. **Lighting to publicly accessible areas**

The following lighting requirements shall be complied with:



- a) The public areas shall be provided with lighting to ensure pedestrian safety. Such lighting shall be at a minimum level of 10 lux in the horizontal and vertical plane.
- b) Details of the lighting is to be submitted for the approval of the Principal Certifying Authority prior to issue of the Construction Certificate and location of the lighting endorsed on the construction drawings.

Reason:- to ensure publicly accessible areas of the development are provided with sufficient illumination.

123. **Suitable arrangements to be made for garbage and recycling services**

Suitable arrangements for garbage and recycling services are to be made with Council prior to occupation of the building.

Reason:- to ensure adequate garbage and recycling services are provided for the development.

124. **Garbage Storage and Collection**

All garbage shall be removed from the site directly via the basement/at grade garbage storage area. Garbage bins shall not be stored on or collected from the footpath or kerb.

Reason:- to ensure that all garbage storage and collection is managed efficiently and without significant impact on the street.

125. **Ongoing Waste Management**

Ongoing waste management within the development shall be carried out in accordance with the approved Waste Management Plan and the following requirements:-

- a) Appropriate waste management practices are to be adopted within the development at all times.
- b) The waste storage room shall be kept in a clean, tidy and hygienic condition at all times.
- c) The waste and recyclable storage area shall be fully enclosed, adequately ventilated and constructed with a concrete floor and concrete or cement rendered walls covering the floor. The floor shall be graded to an approved sewer connection incorporating a sump and galvanised grate cover or basket. A hot and cold hose cock shall be provided within the room. Details shall be provided with the Construction Certificate and endorsed on the construction drawings, and works completed prior to the issue of an Occupation Certificate.
- d) A person shall be employed/nominated to manage the collection of waste material by Council, including, but not limited to bin placement and retrieval of bins soon after collection of contents, cleansing of bins, storage of bins in the compound and the like.

Reason:- to ensure appropriate ongoing waste management practices within the development in accordance with Council's Development Control Plan requirements.

126. **Waste and recyclables storage area:**

The waste and recyclable storage area shall be fully enclosed, adequately ventilated

and constructed with a concrete floor and concrete or cement rendered walls covering the floor. The floor shall be graded to an approved sewer connection incorporating a sump and galvanised grate cover or basket. A hot and cold hose cock shall be provided within the room. Details shall be provided with the Construction Certificate and endorsed on the construction drawings, and works completed prior to the issue of an Occupation Certificate.

Reason:- to ensure the waste and recyclables storage area is appropriately constructed and able to be readily cleaned and maintained.

#### 127. **Final Fire Safety Certificate**

Prior to the occupation of the building, the owner of the building shall submit to the Principal Certifying Authority (Council or Accredited Certifier), a **final fire safety certificate** in relation to each essential fire safety measure specified in the **fire safety schedule**, attached to the development consent or construction certificate.

Such certificate shall state that each essential fire safety measure specified:-

- a) Has been assessed by a properly qualified person, and
- b) Was found, at the date of assessment, to be capable of performing to a standard not less than that required by the current fire safety schedule for the building for which the certificate is issued.

#### **NOTES:**

1. As soon as practicable after a final fire safety certificate is issued, the owner of the building to which it relates:-
  - i) Must cause a copy of the statement (and current fire safety schedule) to be given to the Commissioner of NSW Fire Brigades, and
  - ii) Must cause a further copy of the statement (and current copy of the current fire safety schedule) to be prominently displayed in the building.
2. A "fire safety measure" is defined as any measure (including any item of equipment, form of construction or fire safety strategy) that is , or is proposed to be, implemented in the building to ensure the safety of persons using the building in the event of fire.

Reason:- to ensure compliance with Regulations 149 & 171 of the Environmental Planning and Assessment Regulation 2000.

#### 128. **Annual Fire Safety Statement**

The owner of any building in which fire safety measures are installed, must cause the Council to be given an **annual fire safety statement**, within 12 months after the last such statement or final fire safety certificate was issued.

The certificate shall certify:-

- a) That each essential fire safety measure has been assessed by a properly qualified person and was found, at the date of assessment, to be capable of performing to a standard not less than that required by the current fire safety schedule.
- b) That a properly qualified person has inspected the building and has certified

that, as at the date of inspection, the condition of the building did not disclose any grounds for a prosecution under Division C.

**NOTES:**

1. As soon as practicable after an annual fire safety statement is issued, the owner of the building to which it relates:-
  - i) must cause a copy of the statement (and current fire safety schedule) to be given to the Commissioner of NSW Fire Brigades, and
  - ii) must cause a further copy of the statement (and current copy of the current fire safety schedule) to be prominently displayed in the building.
2. A “fire safety measure” is defined as any measure (including any item of equipment, form of construction or fire safety strategy) that is, or is proposed to be, implemented in the building to ensure the safety of persons using the building in the event of fire.

Reason:- to ensure compliance with Regulation 171 of the Environmental Planning and Assessment Regulation 2000.

**129. Fire Safety Notices**

The fire-isolated stairway, fire-isolated passageway or fire-isolated ramp must contain a notice advising of “Offences relating to fire exits”. The notice shall contain the wording prescribed by Clause 183 of the Environmental Planning and Assessment Regulation, 2000 and the Building Code of Australia.

Reason:- to comply with Clause 183 of the Environmental Planning and Assessment Regulation 2000 and the BCA.

**130. Submission of Works-as-Executed Fire Services Plan**

A *works-as-executed* fire services plan is to be submitted to the Council **prior to occupation** of the development, detailing the location of the essential fire safety measures installed within the building premises.

Reason:- to ensure a record of the location and type of fire safety services is documented.

**131. Occupation Certificate**

A person must not commence occupation or use of the whole or part of a new building unless an occupation certificate has been issued in relation to the building or part.

The application for an Occupation Certificate must be made to the Principal Certifying Authority (Council or an accredited certifier) using the approved form.

Reason:- to comply with the requirements of Section 109M/N of the Environmental Planning and Assessment Act.

**132. Smoke Detection/Alarm Systems - Class 2 Buildings**

The building is required to be provided with a smoke alarm system complying with

Clause 3 of Specification E2.2a of the B.C.A. or a smoke detection system complying with Clause 4 of Specification E2.2a of the B.C.A. or a combination of a smoke alarm system within the sole-occupancy units and a smoke detection system in areas not within the sole-occupancy units.

Details of compliance with the provisions of the Building Code of Australia must be included in the plans/specification for the **Construction Certificate**.

Reason:- to ensure that reasonable levels of fire safety are provided in the building.

133. **Sanitary Compartment doors - All Buildings**

The door to a fully enclosed sanitary compartment must open outwards OR slide OR be readily removable from the outside of the compartment, unless there is a clear space of at least 1.2m between the closet pan within the sanitary compartment and the nearest part of the doorway.

Reason:- to comply with BCA F2.5 and Part 3.8.3.3.