

CONDITIONS OF CONSENT

- 1) The proposal shall comply with the conditions of Development Consent. A Construction Certificate shall not be issued until the plans and specifications meet the required technical standards and the conditions of this Development Consent are satisfied.
- 2) Development shall take place in accordance with Development Application No. DA-303/2015, submitted by Gus Srou, accompanied by Drawing No. A1600 & A1601, Issue A, dated 17/09/14, Drawing No. A1201, A1202, A1203 & A121, Issue B, dated 9/1/15, Drawing No. A1701, Issue B, dated 25/6/15, Drawing No. A1200, A1206, A1207, A1208, A1210, A1500, A1501 A1700 & 1702, Issue C, dated 25/06/15, Drawing No. A1204, Issue D, dated 27/08/15, Drawing No. A1502 & A1503, Issue D, dated 07/09/15, Drawing No. A1209 & Issue E, 24/9/15 and Drawing No. A1205, Issue F, dated 02/09/15 all prepared by Ghazi Al Ali Architect and Drawing No. L01, Prepared by habitation landscape architecture, revision B, dated 02.09.14 affixed with Council's approval stamp, except where otherwise altered by the specific amendments listed hereunder and/or except where amended by the conditions contained in this approval.

The development plans shall be amended as follows:

- a) Clotheslines are to be added to the communal open space areas.
- b) The northern elevation plan Drawing No. A1500, Issue C, dated 25/06/15, shall be amended to exclude all development on the adjoining properties and only show the northern elevation of the subject property at No. 1-3 Palomar Parade Yagoona, as marked in red on the approved plan.

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF A CONSTRUCTION CERTIFICATE

Prior to the release of a Construction Certificate the following conditions MUST be satisfied and nominated fees/contributions/bonds paid:

- 3) Approval from Bankstown Airport Limited is required for the height of the proposed development, including height limits for construction equipment. The Construction Certificate shall not be issued until such approval from Bankstown Airport Limited is obtained. The development shall be compliant at all times with the provisions of any such approval.
- 4) The Certifying Authority must ensure that any certified plans forming part of the Construction Certificate are not inconsistent with this Development Consent and accompanying plans.
- 5) Landscaping shall be installed in accordance with the approved landscape plan. All works and methods nominated and materials and plants specified on the approved landscape plan are to be completed prior to the issue of an occupation certificate. The landscaping shall be maintained for the life of the development.

The Landscape Plan shall incorporate the following tree planting:

- 3 x trees known to attain a minimum height of 15 metres at maturity to be planted in the deep soil zone areas on property;
 - 2 x *Corymbia maculata* (Spotted Gum) to be planted on the nature strip forward of the property.
- 6) The landscape plan shall make provision for a new 1.8m fence to be erected along all side and rear boundaries of the subject allotment at full cost to the developer. The colour of the fence is to complement the development and the fence is to be constructed of lapped and capped timber paling, sheet metal or other suitable material unless the type of material is stipulated in any flood study prepared for the site. The selection of materials and colours of the fence is to be determined in consultation with the adjoining property owners. Fencing forward of the building line shall be no higher than 1m unless otherwise approved by Council.
- 7) A Soil Erosion and Sedimentation Control Plan shall be prepared in accordance with Council's relevant DCP. The plan shall be prepared by a suitably qualified professional and approved by the Principal Certifying Authority, prior to the issue of the Construction Certificate.
- 8) The approved plans must be submitted to a Sydney Water Quick Check agent or Customer Centre to determine whether the development will affect any Sydney Water asset's sewer and water mains, stormwater drains and/or easement, and if further requirements need to be met. Plans will be appropriately stamped.

Please refer to the web site www.sydneywater.com.au for:

- Quick Check agents details – see Building Developing and Plumbing then Quick Check; and
- Guidelines for Building Over/Adjacent to Sydney Water Assets – see Building Developing and Plumbing then Building and Renovating

Or telephone 13 20 92.

- 9) Approval in accordance with Council's Tree Preservation Order (TPO) is granted to remove existing trees within the boundaries of the site. Tree removal work shall be carried out by an experienced tree surgeon in accordance with NSW WorkCover Code of Practice for Amenity Tree Industry (1998) and Pruning of amenity trees – AS 4373 -2007.

Separate approval shall be obtained to prune or remove trees on adjoining properties. Failure to comply with Council's TPO may result in a fine of up to \$100,000.

- No fill, excavated material, building material or other items are to be placed around retained trees.
- No excavation is to take place around the root zone or canopy of retained trees.

- All preservation zones are to be mulched to a depth of no less than 70 – 100mm using a suitable organic mulch or sand around the trees to be retained, ie. around the root zone or canopy of trees.
- Fencing around retained trees is to be in place prior to commencement of site works and is to be kept in place during all construction, until final inspection is undertaken.
- Fences should be signposted to warn contractors of their purpose.
- Treatment and pruning of trees may only be undertaken by qualified arborists after approval of Council.
- Any tree removal carried out on Saturdays is permitted only between the hours of 7am and 1pm inclusive, Sunday removals **not** permitted.
- Construction to begin only when the above procedures are in place.

Failure to comply with the above conditions will result in an on the spot fine.

- 10) A Construction Certificate shall not be issued until written proof that all bonds, fees and/or contributions as required by this consent have been paid to the applicable authority.
- 11) Prior to issue of a Construction Certificate, a Long Service Levy payment of 0.35% of the value of the work is required to be paid to Council on behalf of the Long Service Corporation prior to issue of the Construction Certificate.
- 12) Pursuant to section 80A(1) of the Environmental Planning and Assessment Act 1979, and the Bankstown City Council Section 94A Development Contributions Plan 2009 (Section 94A Plan) a contribution of \$77,727.29 shall be paid to Council.

The amount to be paid is to be adjusted at the time of actual payment, in accordance with the provisions of the Section 94A plan. The contribution is to be paid before the issue of the construction certificate.

Note: The Section 94A Contributions Plans may be inspected at Council's Customer Service Centre, located at Upper Ground Floor, Civic Tower, 66-72 Rickard Road, Bankstown, between the hours of 8.30am-5.00pm Monday to Friday.

- 13) Finished surface levels of all internal works and at the street boundary, including driveways, landscaping and drainage structures, must be as shown on the approved plans. The levels at the street boundary must be consistent with the Street Boundary Alignment Levels issued by Council.
- 14) Stormwater drainage from the development shall be designed so as to comply with Council's Development Engineering Standards and the requirements of the BASIX Certificate. A final detailed stormwater drainage design shall be prepared by a qualified Professional Civil Engineer in accordance with the above requirements and shall generally be in accordance with the concept stormwater plan No. 20140214 SW00 to SW04, rev B, dated 29/6/2015 prepared by sgc CONSULTING ENGINEER S & G CONSULTANTS PTY LIMITED. The final plan shall be certified by the design engineer that it

complies with Council's Development Engineering Standards, the BASIX Certificate and the relevant Australian Standards.

- 15) The pump out drainage system for the access ramps and basement car parking areas shall be provided in accordance with Council's Development Engineering Standards. Engineering details and specifications shall be submitted to the Principal Certifying Authority (PCA) for approval prior to the issue of any Construction Certificate.
- 16) Engineering details and manufacturers specifications for the pumps, switching system and sump pit shall be submitted to the Principal Certifying Authority (PCA) for approval prior to issue of any Construction Certificate.
- 17) Where Council approved cut or fill exceeds 200mm and stable batter of 1 vertical to 3 horizontal maximum grade cannot be achieved, then a masonry or other proprietary material retaining wall, intended and suitable for that purpose, shall be constructed within the development site. Note, filling of the site needs specific approval from Council.

The retaining wall shall be located so that it will not impede or obstruct the natural flow of stormwater. Retaining walls exceeding 600mm in height shall be designed by a qualified professional Civil/Structural Engineer. Plans and details prepared and signed by the Engineer are to be submitted to the Principal Certifying Authority (PCA) prior to the issue of the Construction Certificate.

All works associated with the construction of the wall, including backfilling and drainage, is to be located wholly within the allotment boundaries.

- 18) An all weather pavement shall be designed to withstand the anticipated wheel loads for all areas subjected to vehicular movements. Internal pavements specification prepared and certified by all qualified professional Civil Engineer to comply with the relevant Australian Standards, shall be submitted to the Principal Certifying Authority (PCA) for approval prior to the issue of a construction certificate.
- 19) For internal driveways with a gradient exceeding 10% (1 in 10), longitudinal profiles of all vehicular driveways and ramps shall be submitted for approval by the Principal Certifying Authority (PCA) prior to the issue of the Construction Certificate. The maximum grade of the driveway/ramp shall not exceed **25%** and shall comply with AS 2890.1. The profile shall be drawn at a reduction ratio of 1 to 25 vertical and horizontal and shall be related to the datum used for the issue of the footway design levels and shall also show the road centre line levels, Council issued footway design levels and gutter levels. Council's Car Clearance Profile in Council's Development Engineering Standards, (Plan No. S 006) shall be used to design the profile.
- 20) Prior to the issue of any Construction Certificate for this development, the applicant must obtain approval from Council for a Site, Pedestrian and Traffic Management Plan. This Plan must address the measures that will be implemented for the protection of adjoining properties, pedestrian safety and traffic management and other requirements as specified below.

A PRIVATE CERTIFIER CANNOT APPROVE YOUR SITE, PEDESTRIAN & TRAFFIC MANAGEMENT PLAN

This plan shall include details of the following:

- a) Proposed ingress and egress points for vehicles to and from the construction site;
- b) Proposed protection of pedestrians, adjacent to the construction site;
- c) Proposed hoardings, scaffolding and/or fencing to secure the construction site;
- d) Proposed pedestrian management whilst vehicles are entering/exiting the construction site;
- e) Proposed measures to be implemented for the protection of all public roads and footway areas surrounding the construction site from building activities, crossings by heavy equipment, plant and materials delivery and static load from cranes, concrete pumps and the like;
- f) Proposed method of loading and unloading excavation machines, building material, construction materials and waste containers during the construction period;
- g) Proposed traffic control measures such as advanced warning signs, barricades, warning lights, after hours contact numbers etc are required to be displayed and shall be in accordance with Council's and the NSW Roads and Maritime Services requirements and AS1742.3.
- h) Proposed method of support of any excavation, adjacent to adjoining buildings or the public road. The proposed method of support is to be certified by a Civil Engineer with National Professional Engineering Registration (NPER) in the construction of civil works.
- i) Proposed measures to be implemented in order to ensure that no soil/excavated material is transported on wheels or tracks of vehicles or plant and deposited on the public road.
- j) Proposed measures for protection of the environment including procedures to control environmental impacts of work e.g. sediment control, proper removal, disposal or recycling of waste materials, protection of vegetation and control/prevention of pollution i.e. water, air noise, land pollution.
- k) Proposed construction vehicle routes, number of trucks, hours of operation, access arrangements and traffic control.

The approved Site, Pedestrian and Traffic Management Plan is to be implemented prior to the commencement of any works on the construction site. The applicant will be required to pay for inspections by Council Officers in accordance with Council's adopted fees and charges. In addition a RMS Approval / Road Occupancy Licence will be required for works on Regional or State Roads or within 100m of a traffic facility including roundabouts and traffic signals. Refer to Council's Development Engineering Standards for a list of Regional and State Roads.

- 21) The layout of the car parking areas associated with the development (including driveways, grades, turn paths, sight distances, aisle widths, aisle lengths and parking bay dimensions) shall be in accordance with AS 2890.1 2004.

- 22) Landscaping, fencing and the like must not restrict sight distance to pedestrians and cyclists travelling along the footpath of Palomar Parade – the development must comply with AS 2890.1:2004.
- 23) A Work Permit shall be applied for and obtained from Council for the following engineering works in front of the site, at the applicant's expense:
- a) A medium duty VFC of maximum width of 5.5 metres at the property boundary.
 - b) Drainage connection to Council's system.
 - c) 1.2 metre wide concrete footway paving along the sites entire frontage.
 - d) Concrete kerb and gutter along the sites entire frontage.
 - e) Removal of all driveway surfaces, reinstatement of laybacks to kerb and gutter and reshaping of the footway, all associated with redundant VFCs.
 - f) Repair of any damage to the public road including the footway occurring during development works.
 - g) Reinstatement of the footway reserve and adjustment or relocation of existing public utility services to match the footway design levels as proposed on the approved Work Permit. Adjustment or relocation to any public utility services shall be carried out to the requirements of the public utility authority.

Note: Council is required to prepare a site survey and design in order to determine the necessary information. The developer should make application and payment for the Work Permit at least twenty one (21) days prior to the information being required and prior to the issue of the Construction Certificate. The Work Permit must be approved prior to any works commencing within the Council Road Reserve or on Council's assets.

- 24) As any works within, or use of, the footway or public road for construction purposes requires separate Council approval under Section 138 of the Roads Act 1993 and/or Section 68 of the Local Government Act 1993, Council requires that prior to any Construction Certificate for this development being issued, a Works Permit and or a Roadway/Footpath Building Occupation Permit shall be obtained where one or more of the following will occur, within, on or over the public footway or public road:

A PRIVATE CERTIFIER CANNOT ISSUE THESE PERMITS

WORKS REQUIRING A 'WORKS PERMIT'

- a) Dig up, disturb, or clear the surface of a public footway or public road,
- b) Remove or interfere with a structure or tree (or any other vegetation) on a public footway or public road,
- c) Connect a road (whether public or private) to a classified road,
- d) Undertake footway, paving, vehicular crossing (driveway), landscaping or stormwater drainage works within a public footway or public road,
- e) Install utilities in, under or over a public road,
- f) Pump water into a public footway or public road from any land adjoining the public road,

- g) Erect a structure or carry out a work in, on or over a public road
- h) Require a work zone on the public road for the unloading and or loading of vehicles
- i) Pump concrete from within a public road,
- j) Stand a mobile crane within a public road
- k) Store waste and recycling containers, skips, bins and/or building materials on any part of the public road.
- l) The work is greater than \$50,000.
- m) Demolition is proposed.
- n) Subdivision is proposed.
- o) A Swimming pool is proposed.

Assessment of Works Permits (a to e) includes the preparation of footway design levels, vehicular crossing plans, dilapidation reports and issue of a Road Opening Permit.

All proposed works within the public road and footway shall be constructed under the supervision and to the satisfaction of Council. The applicant/developer shall arrange for necessary inspections by Council whilst the work is in progress.

For commercial or multi-unit residential developments within the designated CBD or an urban village area, footway design and construction and street tree supply, installation and tree hole detailing shall be as per the Council master plan for that area. Full width footways are to be supplied and installed at full cost to the developer to specification as supplied by Council. Layout plan of pavement to be submitted to Council for approval prior to the issue of the Works Permit.

All Council fees applicable, minimum restoration charges and inspection fees shall be paid prior to the assessment of the Work Permit in accordance with Council's adopted fees and charges. Note: Additional fees after approval will be charged where the Work Permit requires occupation of the Road or Footpath ie Hoardings, Work Zones etc.

In determining a Works Permit, Council can impose conditions and require inspections by Council Officers. Forms can be obtained from Council's Customer Service counter located on the ground floor of Council's administration building at 66 - 72 Rickard Road, Bankstown or Council's website www.bankstown.nsw.gov.au

Part of any approval will require the person or company carrying out the work to carry public liability insurance to a minimum value of ten million dollars. Proof of the policy is to be provided to Council prior to commencing any work approved by the Work Permit including the Road Opening Permit and must remain valid for the duration of the works.

The commencement of any works on public land, including the footway or public road, may incur an on the spot fine of not less than \$1100 per day that work continues without a Works Permit and/or a Roadway/Footpath Building Occupation Permit. All conditions attached to the permit shall be strictly

complied with prior to occupation of the development. Works non-conforming to Council's specification (includes quality of workmanship to Council's satisfaction) shall be rectified by the Council at the applicant's expense.

- 25) The route for transportation to and from the development site of bulk and excavation materials shall generally be by the shortest possible route to the nearest "regional road", with every effort to avoid school zones on public roads. The applicant shall nominate the route for approval by Council prior to commencement of any work on the site. An Agreement to Council's satisfaction, signed by the applicant/owner specifying the approved route and acknowledging responsibility to pay Council for damages to public property adjacent to the site shall be lodged with Council prior to release of any Construction Certificate. All damage must be rectified upon completion of work.

CONDITIONS TO BE SATISFIED PRIOR TO CONSTRUCTION

- 26) The building works in accordance with the development consent must not be commenced until:
- a) a construction certificate for the building work has been issued by the council or an accredited certifier, and
 - b) the person having benefit of the development consent has:
 - i. appointed a principal certifying authority for the building work, and
 - ii. notified the principal certifying authority that the person will carry out the building work as an owner- builder, if that is the case, and
 - c) the person having the benefit of the development consent, if not carrying out the work as an owner-builder, has:
 - iii. appointed a principal contractor for the building work who must be the holder of a contractor licence if any residential building work is involved, and
 - iv. notified the principal certifying authority of any such appointment, and
 - v. unless the person is the principal contractor, notified the principal contractor of any critical stage inspections and other inspections that are to be carried out in respect of the building work, and
 - d) the person having the benefit of the development consent has given at least 2 days' notice to the council of the person's intention to commence the erection of the building.
- 27) Suitable erosion and sediment control measures shall be erected in accordance with the plans accompanying the Construction Certificate prior to the commencement of construction works and shall be maintained at all times.
- 28) Prior to the commencement of works, a dilapidation report shall be prepared by the developer and a copy provided to the owners of properties directly adjoining the subject site. The report must clearly identify the condition of existing structures on these adjoining properties prior to the commencement of works.

All care shall be taken during the construction process to ensure adjoining structures are protected, and should any change in condition occur from that recorded in the dilapidation report. On the completion of the proposed work,

and prior to the issue of the final compliance certificate, a certificate prepared by an appropriately qualified engineer, to the effect that no damage has resulted to the adjoining premises, is to be provided to the Principal Certifying Authority. If damage is identified which is considered to require rectification, the damage shall be rectified or satisfactory agreement for rectification of the damage, is to be made with the affected person/s, as soon as possible and prior to occupation of the development - the rectification of such shall be at full cost to the developer.

Note: Where permission is not granted to access the property and evidence in writing that permission is not granted to enter the property can be provided, the report is not required for that property.

- 29) Existing trees within the vicinity of the construction works or paths of travel for construction vehicles accessing the development that are to be retained shall be protected with temporary fencing of a style non injurious to tree roots, placed 2m from the trunk base of the existing tree to prevent damage during construction, and retained in accordance with Council's Tree Preservation Order. There is to be no stockpiling of materials within the 2m fenced zone.
- 30) Council warning sign for Soil and Water Management must be displayed on the most prominent point of the site, visible to both the street and site works. The sign must be displayed throughout the construction period.
- 31) Prior to commencement, the applicant must provide a temporary on-site toilet if access to existing toilets on site is not adequate.
- 32) The following conditions are imposed in regards to tree removal:

Tree Removal: On-Site

Approval is granted for the removal of the following trees:

Tree Species	Location
1 x <i>Melaleuca bracteata</i> (Black Tea-tree)	Front yard of 1 Palomar Parade
1 x <i>Callistemon viminalis</i> (Weeping Bottlebrush)	Rear yard of 1 Palomar Parade

All tree removal works must comply with the Amenity Tree Industry – Code of Practice, 1998 (Workcover, NSW).

- Any tree/s growing within the building footprint of the approved structures;
- Any tree/s where the base of the trunk of the tree is located within 3 metres of the external wall of an approved dwelling on the same property;
- Any declared noxious plant. The applicant, builder and all contractors are to ensure that all noxious plants are properly identified, controlled and/or removed on this site without injury or death of any protected plants;
- Any tree species listed under clause 2.7 of Bankstown Development Control Plan 2005 Part E2 – Tree Preservation Order;
- Any of the following tree/s:

Tree Removal: Nature Strip

Approval is granted for the removal of the following trees:

Tree Species	Location
2 x <i>Callistemon viminalis</i> (Weeping Bottlebrush)	Nature strip forward of 1 and 3 Palomar Parade.

The tree removal works are subject to the following conditions:

- All tree removal works must be carried out by a qualified arborist - minimum qualification Australian Qualification Framework (AQF) Level 3 or equivalent;
- The tree removal contractor must hold a Public Liability Insurance Certificate of Currency with a minimum indemnity of \$20 million, together with a NSW Workers Compensation Insurance Certificate of Currency;
- The tree removal work must comply with the Amenity Tree Industry – Code of Practice, 1998 (Workcover, NSW);
- The tree stump is to be ground to 300mm below ground level. Investigation to locate underground services shall be the responsibility of the applicant.
- All tree material shall be removed from site, and the nature strip shall be backfilled, compacted and restored to the original level.
- The site must be maintained in a safe condition at all times;
- Appropriate hazard signage to be in place at all times during the tree works

- 33) A section 73 compliance certificate under the Sydney Water Act 1994 must be obtained from Sydney Water Corporation. Make early application for the certificate, as there may be water and sewer pipes to be built and this can take some time. This can also impact on other services and building, driveway or landscape design.

Application must be made through an authorised Water Servicing Coordinator. For help either visit www.sydneywater.com.au > Building and Developing > Developing your Land > Water Servicing Coordinator or telephone 13 20 92.

- 34) Prior to the commencement of any building work a fence shall be erected along the property boundaries of the development site, except where an existing 1.8m high boundary fence is in good condition and is capable of securing the site. Any new fencing shall be temporary (such as cyclone wire) and at least 1.8m high.

All fencing is to be maintained for the duration of the construction to ensure that the site is secured and privacy of the adjoining properties is not compromised.

Where the development site is located within 3.6m of a public place then a Class A or Class B hoarding shall be constructed appropriate to the works proposed. A Works Permit for such hoardings shall be submitted to Council for approval prior to the issue of any Construction Certificate.

- 35) A sign shall be displayed on the site indicating the name of the person responsible for the site and a telephone number of which that person can be contacted during and outside normal working hours or when the site is unattended.
- 36) In the case of residential building work for which the *Home Building Act 1989* requires there to be a contract of insurance in force in accordance with part 6 of that Act, such a contract of insurance must be in force before any building work authorised to be carried out by this consent commences.
- 37) Residential building work within the meaning of the *Home Building Act 1989* must not be carried out unless the Principal Certifying Authority (PCA) for the development to which the work relates (not being council) has given the Council written notice of the following information:
- a) in the case of work for which a principal contractor is required to be appointed:
 - (i) the name and licence number of the principal contractor, and
 - (ii) the name of the insurer by which the work is insured under Part 6 of that act,
 - b) in the case of work to be done by an owner-builder:
 - (i) the name of the owner-builder, and
 - (ii) if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.

Note: If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under the above requirements becomes out of date, further work must not be carried out unless the PCA for the development to which the work relates (not being the council) has given the council written notice of the updated information.

This clause does not apply in relation to Crown building work that is certified, in accordance with Section 116G of the Act, to comply with the technical provisions of the State's building laws.

- 38) For development that involves any building work, subdivision work or demolition work, a sign must be erected in a prominent position on any site on which building work, subdivision work or demolition is being carried out:
- a) showing the name, address and telephone number of the Principal Certifying Authority for the work, and
 - b) showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted during and outside working hours, and
 - c) stating that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.

Note: This clause does not apply in relation to building work, subdivision work or demolition work that is carried out inside an existing building that does not affect the external walls of the building, or in relation to Crown building work that is certified, in accordance with Section 116G of the Act, to comply with the technical provisions of the State's building laws.

39) Permission is granted for the demolition of existing structures on the property, subject to strict compliance with the following: -

- a) The developer is to notify adjoining residents seven (7) working days prior to demolition. Such notification is to be clearly written on A4 size paper giving the date demolition will commence and be placed in the letterbox of every premises (including every residential flat or unit, if any) either side, immediately at the rear of, and directly opposite the demolition site.
- b) Written notice is to be given to Bankstown City Council for inspection prior to demolition. Such written notice is to include the date when demolition will commence and details of the name, address, business hours and contact telephone number and licence number of the demolisher. The following building inspections shall be undertaken by Bankstown City Council:
 - (i) A *precommencement* inspection shall be carried out by Council when all the site works required as part of this consent are installed on the site and prior to demolition commencing.
 - (ii) A *final* inspection shall be carried out by Council when the demolition works have been completed to ensure that the site is left in a satisfactory manner, in accordance with the conditions of this consent.

NOTE: Payment of an inspection fee at Council's current rate will be required prior to each inspection. Council requires 24 hours notice to carry out inspections. Arrangements for inspections can be made by phoning **9707 9410, 9707 9412 or 9707 9635.**

- c) Prior to demolition, the applicant must erect a sign at the front of the property with the demolisher's name, license number, contact phone number and site address.
- d) Prior to demolition, the applicant must erect a 2.4m high temporary fence or hoarding between the work site and any public place. Access to the site shall be restricted to Authorised Persons Only and the site shall be secured against unauthorised entry when the building work is not in progress or the site is otherwise unoccupied. Where demolition is to occur within 3m of a public place a Work Permit application for the construction of a Class A or Class B hoarding shall be submitted to Council for approval.
- e) The demolition plans must be submitted to the appropriate Sydney Water Office to determine whether the development will affect Sydney Water's

sewer and water mains, stormwater drains and/or easements. If the development complies with Sydney Water's requirements, the demolition plans will be stamped indicating that no further requirements are necessary.

- f) Demolition is to be carried out in accordance with the appropriate provisions of Australian Standard AS2601-2001.
- g) The hours of demolition work shall be limited to between 7.00am and 6.00pm on weekdays, 7.00am and 1.00pm on Saturdays and no work shall be carried out on Sundays and public holidays, and weekends (Saturdays and Sundays) adjacent to public holidays.
- h) Where materials containing asbestos cement are to be removed, demolition is to be carried out by licensed contractors who have current Workcover Accreditation in asbestos removal.
- i) Hazardous or intractable wastes arising from the demolition process shall be removed and disposed of in accordance with the requirements of WorkCover NSW and the NSW EPA 'Environmental Guidelines: Assessment, Classification and Management of Liquid and Non-Liquid Wastes 2004'.
- j) Demolition procedures shall maximise the reuse and recycling of demolished materials in order to reduce the environmental impacts of waste disposal.
- k) During demolition, the public footway and public road shall be clear at all times and shall not be obstructed by any demolished material or vehicles. The public road and footway shall be swept (NOT hosed) clean of any material, including clay, soil and sand. (NOTE: If required, Council will clean the public road/footway at the applicant's expense). On the spot fines may be levied by Council against the demolisher and or owner for failure to comply with this condition.
- l) All vehicles leaving the site with demolition materials shall have their loads covered and vehicles shall not track soil and other material onto the public roads and footways and the footway shall be suitably protected against damage when plant and vehicles access the site. All loading of vehicles with demolished materials shall occur on site.
- m) The burning of any demolished material on site is not permitted and offenders will be prosecuted.
- n) Care shall be taken during demolition to ensure that existing services on the site (ie. sewer, electricity, gas, phone) are not damaged. Any damage caused to existing services shall be repaired by the relevant authority at the applicant's expense.
- o) Suitable erosion and sediment control measures shall be erected prior to the commencement of demolition works and shall be maintained at all times.

- p) Prior to the demolition of any building constructed before 1970, a Work Plan shall be prepared and submitted to Council in accordance with Australian Standard AS2601-2001 by a person with suitable expertise and experience. The Work Plan shall outline the identification of any hazardous materials, including surfaces coated with lead paint, method of demolition, the precautions to be employed to minimise any dust nuisance and the disposal methods for hazardous materials.

CONDITIONS TO BE SATISFIED DURING CONSTRUCTION

- 40) The hours of site works shall be limited to between 7.00am and 6.00pm on weekdays and 7.00am and 1.00pm on Saturdays. No work shall be carried out on Sundays and public holidays, and weekends (Saturdays and Sundays) adjacent to public holidays.
- 41) The building work must be carried out in accordance with the requirements of the Building Code of Australia, the provisions of the relevant Australian Standards and the approved plans.
- 42) The developer shall be responsible for all public utility adjustment/relocation works, necessitated by the development and as required by the various public utility authorities and/or their agents.
- 43) Prior to each floor slab being poured, an identification report prepared by a registered surveyor shall be submitted verifying that the proposed slab's finished floor level and siting to the property boundary conforms with the approved plans.
- 44) All Civil and Hydraulic engineering works on site must be carried out in accordance with Council's Development Engineering Standards. All Civil and Hydraulic engineering works associated with Council's assets and infrastructure must be carried out in accordance with Council's Work Permit requirements and to Council's satisfaction.
- 45) All excavations and backfilling must be executed safely and in accordance with the relevant Australian Standards.
- 46) If the soil conditions require it, retaining walls or other approved methods of preventing movement of the soil must be provided, and adequate provisions must be made for drainage. Separate approval may be required for retaining walls should they be required.
- 47) If an excavation extends below the level of the base of the footings of an adjoining building or a building on an adjoining allotment of land, the person causing the excavation to be made:
 - a) if necessary, must underpin and support the building in an approved manner, and
 - b) must, at least 7 days before excavating below the level of the base of the footings of a building give notice of intention to do so to the owner of that

building and furnish particulars of the excavation to the owner of the building being erected or demolished.

- c) must take all precautions to protect all of the structures from damage.

The owner of any affected buildings is not liable for any part of the cost of work carried out for the purposes of this clause, whether carried out on the allotment of land being excavated or on an adjoining allotment of land.

- 48) All boundary fencing behind the building line shall be replaced by a 1.8m high lapped and capped timber or sheet metal fence, or as stipulated in a flood study prepared for the site, or as determined in consultation with the adjoining property owners at the developer's expense. Fencing forward of the building line shall be no higher than 1m unless otherwise approved by Council.
- 49) The stormwater drainage system shall be constructed in accordance with Council's Development Engineering Standards and the engineering plans and details approved by the Principal Certifying Authority (PCA).
- 50) Prior to the commencement of work, the builder shall prepare a photographic record of the road reserve which clearly shows its condition prior to works occurring on site. For the entirety of demolition, subdivision or construction works, there shall be no stockpiling of building spoil, materials, or storage of equipment on the public road, including the footway and the road reserve shall be maintained in a safe condition at all times. No work shall be carried out on the public road, including the footway, unless a Work Permit authorised by Council has been obtained.
- 51) Any new information which comes to light during demolition and/or construction works which has the potential to alter previous conclusions about site contamination shall be notified to Council immediately.

Works are to cease until the new information is evaluated and an appropriate response determined by the applicant which is agreed to by Council. Council may also request that a NSW EPA accredited site auditor is involved to assist with the assessment of the new contamination information.

- 52) Any fill imported on to the site shall be classified/validated to ensure that it is suitable for the proposed land use. This validation must be undertaken by a suitably qualified and experienced environmental consultant. Fill imported on to the site shall also be compatible with the existing soil characteristic for site drainage purposes.
- 53) To avoid unnecessary damage to the *Eucalyptus scoparia* (Wallangarra White Gum) located on the adjoining property at 295 Cooper Road, tree roots along the perimeter of the building are to be exposed and severed by hand prior to the commencement of excavation. The work shall be carried out by a qualified arborist (minimum qualification AQF Level 3 or equivalent).

All work carried out on or around protected trees during demolition, clearing and construction shall comply with Australian Standard AS4373-2007 Pruning

of amenity trees and Australian Standard AS4970-2009 Protection of trees on development sites.

CONDITIONS TO BE SATISFIED PRIOR TO OCCUPATION

- 54) The use of a building in accordance with this Development Consent must not be commenced until Council or the PCA has issued an Occupation Certificate for the building and site works.
- 55) A final Occupation Certificate shall not be issued until all conditions relating to demolition, construction and site works of this development consent are satisfied and Council has issued a Work Permit Compliance Certificate.
- 56) Prior to the issue of any Occupation Certificate, design verification from a qualified designer shall be submitted to the Principal Certifying Authority. The design verification is a statement in which the qualified designer verifies that the development as shown in the plans and specifications in respect of which the Construction Certificate was issued, having regard to the design quality principles set out in Part 2 of SEPP No. 65.
- 57) Landscaping is to be installed in accordance with the approved landscape plan. All works and methods nominated and materials and plants specified on the approved landscape plan are to be completed prior to the issue of an occupation certificate. The landscaping shall be maintained for the life of the development.
- 58) The applicant is to plant the following replacement trees on the nature strip forward of the property. The trees shall have a container size not less than 200 litres, shall comply with NATSPEC Specifying Trees: a guide to assessment of tree quality (2003), and be planted and maintained in accordance with Councils street tree planting specifications Standard Drawing No. S-201:

Tree Species	Location
2 x <i>Corymbia maculata</i> (Spotted Gum)	Trees to be planted on the nature strip forward of the property.

Investigation to locate underground services shall be the responsibility of the applicant. Should such services be located and there is a reasonable belief that damage may occur to those services by the new plantings, the applicant is to:

- Carry out engineering works to protect those services from damage; or
- Relocate the plantings to a more suitable location following written approval from Bankstown City Council; or
- Substitute the approved tree species with an alternative species following written approval from Bankstown City Council.

The trees are to be planted to the satisfaction of Councils Tree Management Officer. The Applicant shall contact Councils Tree Management Officer to arrange for a site inspection of the completed tree planting prior to the issue of an occupation certificate.

- 59) A suitably qualified Professional Civil Engineer shall certify that the driveways, parking bays, and service areas have been constructed in accordance with the approved plans and specifications. Such Certification shall be submitted prior to the issue of the Occupation Certificate or occupation of the site.
- 60) Lighting must be provided to the entries of the dwellings, driveways and parking areas to promote a high level of safety and security at night and during periods of low light. Lighting provided should be hooded, shielded or directed away from neighbouring dwellings to minimise glare and associated nuisances to residents.
- 61) The premises must be readily identified from the street with the allocated house numbers. Numbering of the development without Council's written approval is not permitted. An official "house numbering" letter will be sent to the applicant indicating the proposed house numbers of the new development. Note: The house numbers of the development are subject to change depending of the type on subdivision that may occur at a later stage.
- 62) The Section 73 Certificate must be submitted to the Principal Certifying Authority before occupation of the development.
- 63) A registered surveyor shall prepare a Work As Executed Plan, and a suitably qualified Hydraulic Engineer shall provide certification of the constructed on-site stormwater detention system.

The Work As Executed information shall be shown in red on a copy of the approved stormwater plan and shall include all information specified in Council's Development Engineering Standards. The Work As Executed plan shall be submitted to the Hydraulic Engineer prior to certification of the on-site stormwater detention system.

The engineer's certification of the on-site stormwater detention system should be carried out similar to Council's standard form "On-Site Stormwater Detention System - Certificate of Compliance", contained in Council's Development Engineering Standards.

A copy of the Work As Executed Plan and Hydraulic Engineer's Certification shall be submitted to Council for information prior to issue of the final occupation certificate.

- 64) The developer shall register, on the title of the subject property, a Restriction on the Use of Land and Positive Covenant, in accordance with the standard terms for "Registration of OSD on title", as outlined in Council's Development Engineering Standards and in accordance with the appropriate provisions of the Conveyancing Act. The surveyor shall show the location of the "On-Site Stormwater Detention System" on an A4 size site plan attached to the Section 88E Instrument to be registered, on the title of the subject property, prior to the issue of the Final Occupation Certificate. The developer shall submit evidence of the final registration of the Restriction and Positive Covenant on the title of the property, to Council.

- 65) For 10 years from the date of the issue of the occupation certificate:
- a. at least 20% of the approved gross floor area must be used for the purposes of affordable housing, and
 - b. all accommodation that is used for affordable housing must be managed by a registered community housing provider.

A restriction must be registered, before the date of the issue of the occupation certificate, against the title of the property, in accordance with section 88E of the Conveyancing Act 1919, that will ensure that the requirements of this condition are met.

-END-