




Liquid amber



GRAVEL SERVICE AREA -

— WATER/GARDEN FEATURE

— WATER/GARDEN FEATURE









TRACHELOSPERMUM

JASMINOIDES



ELAEOCARPUS RETICULATUS



MAGNOLIA GRANDIFLORA

'LITTLE GEM'



LOMANDRA LONGIFOLIA





STRELITZIA JUNCEA




PHILODENDRON XANADU



SAPIUM SEBIFERUM







Issu	Issue					
No.	Date	Description				
Α	25/06/15	DA Issue				
В	13/10/15	Updated DA Issue				
_	40/00/40	A				

T35 Liquidambar styraciflua


Nominated Architects: Graham Thorburn reg No.5706

10/03/16 Amended as per council letter Any form of replication of this drawing in full or in part without the written permission of NBRS & PARTNERS Pty Ltd constitutes an infringement of the copyright ABN 16 002 247 565

Geoffrey Deane reg No.3766; Andrew Duffin reg No.5602; Garry Hoddinett reg No.5286


Disclaimer

These plans are for Client use and/or Council Approval only. Not intended for construction purpose unless specifically noted. The contractor intending to use these documents shall check and verify all works on site and report any discrepency to the Landscape Architect prior to commencement. Failure to do so shall not be the responsibility of the Client or Landscape Architect.



CORDYLINE FRUTICOSA 'RUBRA'






DORYANTHES EXCELSA



CUPANIOPSIS ANACARDIOIDES

TO BE REMOVED



CORDYLINE TERMINALIS





Project & Client Residential Development

Glory Property Group

7 & 9 Castlereagh Street 8,10 & 12 Copeland Street, Liverpool

LAGERSTROEMIA INDICA

'NATCHEZ'

Landscape Architect

NBRS+PARTNERS Level 3, 4 Glen Street, Milsons Point. NSW 2061 Australia T: 61 2 9922 2344 F: 61 2 9922 1308 E: architects@nbrsap.com.au W: www.nbrsap.com.au




WATERHOUSEA FLORIBUNDA

Mosca Pserras Architects Suite 501, 7 Secant Street


Liverpool NSW 2170

p 02 9601- 3244

WESTRINGIA FRUTICOSA




PHORMIUM 'BRONZE BABY'




SYZYGIUM 'CASCADE'

-2 STAKES AND HESSIAN TIES TO SUPPORT TREE 75mm MUI CH DISHED AROUND TOPSOIL MIX PLANTING HOLE MIN. 1.5 TIMES POT SIZE EXISTING SUB GRADE BREAK UP BASE OF HOLE

75-100 LITRE TREE PLANTING



150mm CONTAINER




TYPICAL TURF DETAIL

Issu	ıe		Disclaimer	
No. A	Date Description 25/06/15 DA Issue	•	Chkd AL	These plans are for Client use and/or Co Approval only. Not intended for construction pur unless specifically noted. The contractor intendi use these documents shall check and verify all v
NBRS 8		this drawing in full or in part without the wr Ltd constitutes an infringement of the copy	on site and report any discrepency to the Lands Architect prior to commencement. Failure to c shall not be the responsibility of the Clier	


Nominated Architects: Graham Thorburn reg No.5706

Geoffrey Deane reg No.3766; Andrew Duffin reg No.5602; Garry Hoddinett reg No.5286


Council urpose ding to works dscape do so ent or Landscape Architect.



50 Litre CONTAINER



5 - 25 Litre CONTAINER



PLANTER TYPICAL DETAIL

Drawing Title

Landscape Details

Project & Client Residential Development

> 7 & 9 Castlereagh Street 8,10 & 12 Copeland Street, Liverpool

Glory Property Group

Architect


Landscape Architect **NBRS**+PARTNERS Level 3, 4 Glen Street, Milsons Point. NSW 2061 Australia T: 61 2 9922 2344 F: 61 2 9922 1308 E: architects@nbrsap.com.au W: www.nbrsap.com.au

Mosca Pserras Architects

Liverpool NSW 2170

p 02 9601- 3244

Suite 501, 7 Secant Street





The landscape drawings are to be read in conjunction with the Architects / Builders plans to determine the full scope of works. Only work from drawings that have noted as approved for construction or with local Authority

The landscape and associated trade works are to be installed by qualified contractors holding the necessary building / construction certificates allowing him to undertake structural landscape works, horticultural and irrigation activities.

Inspect Site:

The landscape contractor shall thoroughly inspect the site prior to commencement of the works to determine any discrepancies or omissions between existing and proposals that may impact the works, as well as works by others ie, drainage, power, water supply, in-ground services & footings.

Tree Protection / Removal Measures:

All trees noted to be retained are to be protected by best Arboricultural practice or to the local authority requirements. Any works within the trees root zone is to be undertaken to the advice of an Arborist using hand tools. No works to the retained site trees such as pruning is to be undertaken without gaining local authority approval. No storage of materials (temporary stockpiling), building / construction activities (, mixing of materials, site shed, parking, or waste disposal) is to occur beneath existing trees. Tree removal shall only occur following local authority approval. Make sure tree stumps are ground/dug out to min 300 mm below surface and tree roots removed to allow installation of the new landscape / building works.

Site Preparation, Erosion control and Fencing:

Clear the site to the extent as directed / noted on the drawing to allow new planting. Garden and turf areas to be deep ripped to 150 mm. Apply clay breaker / gypsum to clay soils to the manufacturer recommendation. Subsoil drainage shall be installed where planting occurs in pockets of bedrock/ in low lying areas or in areas of poor subsoil drainage.

Erosion and sediment control measures such as sediment traps, straw bales and sandbags are to be in place to prevent contaminated stormwater runoff leaving the site or entering new installed drains. Ensure these measures meet the Builders responsibilities and local authority requirements.

The site is to be made safe with appropriate fencing to prevent unauthorised access for the period of the works.

Mulch:

All garden areas shall be finished with mulch to a minimum 75 mm depth from approved supplier. Mulch shall be placed following installation of the irrigation system and fertiliser. Place mulch carefully to ensure plant foliage is not covered and dish mulch around base of plant stems.

Soil Works:

Place new soil mix from approved supplier to 100 mm combining with site material. Where predominantly native planting is used then apply soil an approved native plant soil mix from an approved supplier.

All garden areas adjoining turf and gravel paths shall be edged as detailed for ease of maintenance.

Plant Material / Installation.

Plant material shall be supplied by an approved nursery. Plant material shall be true to species type and appropriate form and dimension relative to the container size. No substitution of plant species or sizes shall occur without approval of the NBRS + Partners. Plant material as delivered to site that is not found to be suitable shall be rejected at the discretion of the Landscape Architect, with replacement cost the responsibility of the Landscape Contractor.

Prepare the planting hole to allow for placement of the container plus backfill of imported soil. Make sure root-ball is not proud of adjoining ground. Following installation immediately hand water and stake plants. If plants are to be stored on site for a period of more than 24 hours then ensure they are made secure, not exposed to adverse sun/shade/wind conditions and are appropriately watered.

Following placement of plant material but prior to mulching apply slow release fertiliser across finished garden beds such as Osmocote™ and water in.

Hard Landscape Works

Paving works are to be installed to the manufacturer's recommendations, with driveways and other vehicle pavements to an Engineers specification. External walls, pavements and stairs are to be constructed to the relevant Australian Standards and Building Code of Australia requirements.

Irrigation

The landscape works are to incorporate a fully automatic irrigation system utilising drip systems for garden areas and pop sprays for lawn areas. The system is to be automatically controlled and fitted with a rain check device to prevent watering during periods of rain. If available connect the system to rainwater tanks. Ensure the system is installed and run to the Water Board and local authority requirements and relevant Australian Standards. The landscape contractor shall prepare a shop drawing of the irrigation system and components and gain approval from NBRS + Partners prior to installation.

Rubbish Removal:

Remove all rubbish form site including clearing works, plant containers, tags, cement spoil and excess materials. Do not place rubbish behind newly constructed walls, in planters or cavities. Do not burn material on site or dispose of chemical in gardens or drains.

Maintenance

The works will be subject to a defects liability period during which time the contractor will be responsible for the maintenance of all aspects of the landscape works including replacement of failed plant material. Following that period the maintenance of the landscape will become the responsibility of the owners.

Completion of the Works

The works shall not be deemed complete until all defects are rectified and inspected to the satisfaction of the Landscape Architect.