



- GENERAL DEMOLITION NOTES:**
- REFER PROJECT HOLD POINTS (BP-002-CS) FOR EXISTING TREE PROTECTION REQUIREMENTS.
 - EXISTING TURF TO EXTENT OF DEMOLITION & REGRADING WORKS
 - ALL MEMORIALS TO BE RELOCATED ARE TO BE STORED & PROTECTED UNTIL INSTALLATION
 - PERIMETER RETAINING WALLS & PEDESTRIAN PATH TO BE DEMOLISHED BY OTHERS. COORDINATION WITH BIGGE PARK DEMOLITION REQUIRED.
 - COLLEGE ST. ROAD WORKS TO BE COORDINATED WITH ROAD ENGINEERS
 - REMOVAL OF TURF AROUND EXISTING TREES FOR PROPOSED MULCH BEDS TO BE COMPLETED BY HAND TO ENSURE MINIMAL IMPACT TO TREE ROOTS
 - ALL EXISTING TREE NUMBERS & LOCATIONS TO BE CONFIRMED ON SITE BEFORE COMMENCEMENT OF CONSTRUCTION WORKS
- ITEMS TO BE REMOVED (UNLESS STATED OTHERWISE) :**
- RUBBISH BINS
 - SEATINGS & ASSOCIATED CONCRETE FOOTINGS/ PADS
 - LIGHTING POLES & ASSOCIATED FOOTINGS / ELECTRICAL CABLING
 - CONCRETE PATHS
- MEMORIAL SCHEDULE**
- REFER MEMORIAL SCHEDULE, LOCATED IN SCHEDULE OF LANDSCAPE WORKS APPENDIX, FOR ALL MEMORIAL INFORMATION & PROPOSED RETAIN &/OR RELOCATION REQUIREMENTS



REV	NO	DESCRIPTION	DWN	CHK	DATE
D	04	95% CONSTRUCTION DOCUMENTATION	CG	MK	06.03.15
C	03	50% CONSTRUCTION DOCUMENTATION	CG	MK	23.01.15
B	02	100% DESIGN DEVELOPMENT	CG	MK	28.11.14
A	01	75% DESIGN DEVELOPMENT	CG	MK	07.11.14