



- Demolition Notes:**
1. Refer to Landscape drawing for removal of trees.
  2. Do not remove topsoil within drip line of trees to be retained. Use hand methods to locate, expose, and clearly remove the roots within any area of specified excavation.
  3. All Vegetated Areas to be retained where possible are to be fenced off, unless noted otherwise.
  4. Contact '1100 Dial Before You Dig' prior to excavation to avoid damaging any existing underground services.
  5. No manoeuvring of vehicles or stockpiling of material should occur outside the construction site.
  6. All sediment control structures should be inspected and maintained by the site manager daily.
  7. All waste skips to be clear from drains, gutters and foot paths.
  8. Drainage is to be connected to stormwater system as soon as possible.
  9. Roads and footpaths outside of site to be kept clean and clear at all times.
  10. Construction site stabilisation to commence immediately on demolition of building.

- Legend:**
- To be demolished
  - Extent of existing ground surfaces to be removed
  - Existing trees to be retained (Refer to Landscape Drawings)
  - Existing trees to be removed (Refer to Landscape Drawings)
  - Existing site level from Survey Plan

**01** Demolition Plan/ Survey Plan  
1:150 @ A1

**NOTE:**  
Survey Drawing Prepared by:  
**G&R SURVEYING SERVICES P/L**  
JOB NO: 1395

B	6/10/15	DA Submission
ISSUE	DATE	REVISION
PROJECT	Multi Residential Development	
ADDRESS	325-327 & 331 Peats Ferry Rd, Asquith	PROJECT # 15002
CLIENT	Max Lucas	DATE # July 2015
DWG	Demolition Plan/ Survey plan	SCALE 1:150 @ A1
		DRAWN JH
		CHKD JH
		REVISION B
		DWG # DA 001