

## REPORT

# ARBORICULTURAL IMPACT ASSESSMENT

47-49 South Street &  
14-16 Burbang Crescent,  
Rydalmere, NSW

Prepared 16 March 2016  
Our Ref: 1769

# Contents

	Page
Preface	3
Introduction	3
Summary	3
1.0 Aims	6
2.0 Objectives	6
3.0 Methodology	6
4.0 Pruning Standards	7
5.0 Tree Assessments	8
• Assessment of a stand of trees	
• Observations	
• Discussions	
6.0 Conclusion	14
7.0 Recommendations	15
Disclaimer	15
<b>Tables</b>	
1.0 General description of trees and Schedule of works.	4
2.0 Tree Protection Zone fencing locations	5

## Appendices

- Appendix A IACA Significance of a Tree, Assessment Rating System (STARS) (IACA, 2010) ©
- Appendix B Matrix - Sustainable Retention Index Value (S.R.I.V.), Version 4, (IACA) 2010 ©
- Appendix C Extract from Australian Standard AS4970 2009 *Protection of trees on development sites*, Section 3 - Determining the tree protection zones of the selected trees, 3.1 Tree protection zone (TPZ) and 3.3.5 Structural root zone (SRZ)
- Appendix D Glossary of terminology
- Appendix E Survey of Subject Tree/s
- Appendix F Tree Protection Plan

## PREFACE

Redgum Horticultural has prepared this report for Architex (*the architect*) on behalf of Nan Zhuans, Strong Property Development Pty Ltd, PO Box 699, Mascot, NSW (*the applicant*).

Mr. Neville Shields (*the author*) attended 47-49 South Street & 14-16 Burbang Crescent, Rydalmere, NSW (*the site*), on 14 March 2016, all the trees and their growing environment were examined. The site is subject to a Development Application and this report and any works recommended herein, that require approval from the consenting authority, forms part of that development application.

## INTRODUCTION

The land is located in the Parramatta City Council (*the Council*) Local Government Area (LGA) and the trees are protected under Councils Tree Preservation Order. The Council is the consenting authority for development works on the site. This report involves 14 trees (*the trees*), as indicated on Site Plan A - Survey of Subject Trees (Appendix E) and considers the removal of ten (10) trees within the property and the retention of four (4) trees within the property and adjacent on the road reserve. The trees will be considered as 2 stands to encompass all trees within and immediately adjacent to the site, where appropriate, as marked on Appendix E, Site Plan A – Survey of Subject Trees. **Tree Protection Zone** fencing or works are marked on the Appendix F, Site Plan B - Trees to be Retained and Tree Protection Zones.

The site is comprised of four residential blocks where the existing structures are to be demolished and are to be replaced with a proposed residential unit development, requiring the removal of ten (10) existing trees within the site. As part of the Landscape Plan where appropriate, the tree cover on the site will be enhanced by planting with advanced specimens/s of appropriate tree species for the space available above and below ground being soil volumes available and to prevent future conflict between trees and built structures.

The proposed building design and its configuration and infrastructure were arrived at prior to the undertaking of an arboricultural assessment of the trees on the site to determine their significance by Redgum Horticultural. The plans provided do not show the location of sewer, water or electricity supply to the proposed development.

Setbacks for the new works and associated infrastructure should provide sufficient space to protect the existing growing environments both above and below ground for trees to be retained, and so that trees within the property and on adjoining properties will not be adversely affected.

The proposed design has considered the spatial requirements for the trees to be retained based on the information available or provided at the time of compiling this report, and those areas to be protected will be discussed further. The Summary lists the general condition of trees and a summary of works in Table 1.0. In section 5.0 each individual tree is described in greater detail including protective or remedial works. Tree maintenance works including pruning, removal or transplantation are detailed in section 4.0.

## SUMMARY

This report considers 14 trees, 13 trees within the site and 1 on the adjacent road reserve. The trees to be retained and protected are Trees 1, 2, 9 & 12 and Trees 3 to 8, 10, 11 & 13<sup>2</sup> are recommended to be removed. For Trees 1, 2, 9 & 12 these specimens are sufficiently setback from the development to not be affected.

*If associated infrastructure (pipe works) are to be installed within the Tree Protection Zone of these specimens, they are to be installed by hand with non-motorised machinery. If structural roots are found within the trench, they are to be left intact and dug around retaining this specimen's structural integrity. Works are to be undertaken in consultation with the project arborist.*

The impact will be that of minor encroachment for Tree 1, 2, 9 & 12 which are to be retained and protected as per AS 4970 (2009) Section 3, 3.3.3 *Major Encroachments* from development works within >10% of the area of the Tree Protection Zone.

**Table 1.0** General condition of trees and Schedule of works. Trees described in greater detail in section 5.0.

<b>Tree / Stand No.</b>	<b>Genus and species</b>	<b>Common name</b>	<b>Condition G = Good, F = Fair P = Poor, D = Dead</b>	<b>Description of work to be done</b>
1	<i>Sannantha bidwillii</i> (syn. <i>Baeckea virgate</i> )	Twiggy Heath Myrtle	F	Retain and protect within a Tree Protection Zone (TPZ) as per the Tree Protection Plan.
2	<i>Callistemon citrinus</i> 'Kings Park Special'	Kings Park Bottlebrush	F	Retain and protect within a Tree Protection Zone (TPZ) as per the Tree Protection Plan. – <i>Street Tree Specimen</i>
3	<i>Tibouchina lepidota</i> 'Alstonville'	Lasandra	F	Remove and replace with by new plantings as per Landscape Plan
4	<i>Juniperus glabra</i>	Smooth Cypress	G	Remove and replace with by new plantings as per Landscape Plan
5	<i>Thuja orientalis</i>	Bookleaf Conifer	F	Remove and replace with by new plantings as per Landscape Plan
6	<i>Bauhinia purpurea</i>	Butterfly Tree	F	Remove and replace with by new plantings as per Landscape Plan
7	<i>Camellia sasanqua</i>	Camellia	F	Remove and replace with by new plantings as per Landscape Plan
8	<i>Syzygium smithii</i>	Lilly Pilly	G	Remove and replace with by new plantings as per Landscape Plan
9	<i>Juniperus glabra</i>	Smooth Cypress	F	Retain and protect within a Tree Protection Zone (TPZ) as per the Tree Protection Plan.
10	<i>Grevillea robusta</i>	Silky Oak	F	Remove and replace with by new plantings as per Landscape Plan
11	<i>Archontophoenix cunninghamiana</i>	Bangalow Palm	G	Remove and replace with by new plantings as per Landscape Plan
12	<i>Pittosporum undulatum</i>	Native Daphne	F	Retain and protect within a Tree Protection Zone (TPZ) as per the Tree Protection Plan.
13	<i>Dypsis decaryi</i>	Triangle Palm	G	Remove and replace with by new plantings as per Landscape Plan



**Table 2.0** This table only applies to trees being retained. Tree Protection Zone fencing locations as measured from the centre of each tree and the recommended distances for the side closest to the building construction works e.g. excavation (see explanatory notes below). Tree Protection Zone fences and setbacks where applicable are indicated in Appendix F and are to be measured on site.

1. Redgum Tree / Stand No.	2. Structural Root Zone SRZ (DARB)  From centre of trunk (COT) Diameter Above Root Buttress AS4970 2009 Section 3, 3.3.5 (see Appendix C) where applicable (Minimum 1.5 metres)	3. Trunk Diameter at Breast Height DBH  1.4m above ground, AS4970 2009, or mm or m above ground where indicated. # = average. g = ground	4. Tree Protection Zone (TPZ) =  12 x DBH  From centre of trunk (COT) in metres AS4970 2009 Section 3 (see Appendix C) (Minimum 2.0 metres)	5. Distance of fence with TPZ setback  (reduced by 10% of area of TPZ) in metres as per AS4970 2009 Section 3, 3.3 (Minimum 2.0 metres)	6. Estimated distance of tree protection fence/works on the side closest to building construction <sup>2</sup> , in metres by Redgum Horticultural.
1	1.8	250	3.0	2.7	3.0 <sup>1,2</sup>
2	1.7	200 av @ g	2.4	2.2	2.4 <sup>1,2</sup>
9	1.8	250	3.0	2.7	3.0 <sup>1,2</sup>
12	1.8	250	3.0	2.7	3.0 <sup>1,2</sup>

<p><b>Descriptors for modified setbacks in Column 6.</b></p> <p><sup>1</sup> Special conditions apply to protect the roots of trees generally, see discussion points.  <sup>2</sup> Additional protective fencing information is detailed in discussion points.  <sup>3</sup> Acceptable due to the good relative tolerance of the species to development impacts.  <sup>4</sup> Range of setbacks for the trees at each end of a linear stand, see discussion points.  <sup>5</sup> Acceptable as fence located at a substantial distance beyond dripline, or may also include the location of a smaller tree in proximity to a larger tree to be retained and the smaller tree being protected well within the protective fencing for that larger tree.  <sup>6</sup> Acceptable due to additional special protection works, see Section 5.0 for this tree.  <sup>7</sup> Acceptable as pre-existing site conditions were conducive to having restricted the development of root growth in this direction.  <sup>8</sup> Street tree with protective fencing of minimal width to allow for pedestrian access along road reserve.</p>	<p><sup>9</sup> Acceptable as tree transplanted reducing the area of the root zone.  <sup>10</sup> Acceptable as not effected by development works.  <sup>11</sup> Young tree not expected to have established a substantially expansive root system and able to re-establish or modify growth to be sustainable due to age and good vigour.  <sup>12</sup> Set back prescribed by the consent authority.  <sup>13</sup> Acceptable as tree growing on a lean and encroachment on compression wood side where root growth is of reduced structural importance.  <sup>14</sup> Acceptable as root mapping has indicated extent of structural woody roots with a diameter of 20 mm or more.  <sup>15</sup> Acceptable as a specimen of palm taxa tolerant of encroachment.  <sup>16</sup> Acceptable as excavation on down slope or across slope side of tree.  <sup>17</sup> Acceptable as encroachment into growing area below ground minor, with one corner of building or excavation works extending to within the radius of the dripline.</p>	<p><sup>18</sup> Acceptable as encroachment by pier, including screw piles, with minimal disturbance.  <sup>19</sup> Acceptable as encroachment above grade without excavation or sub-base compaction.  <sup>20</sup> Acceptable as located within 0.5 m from edge of dripline.  <sup>21</sup> Acceptable as encroachment with gap graded fill that can accommodate gaseous exchange between roots/soil and the atmosphere and ongoing root growth.  <sup>22</sup> Minimum setback 2 m, AS4970 (2009) section 3, 3.2.  <sup>23</sup> Maximum setback 15 m, AS4970 (2009) section 3, 3.2.  <sup>24</sup> Tree is a palm, other monocot, cycad or tree fern TPZ is to be 1 m outside crown projection AS4970 (2009) section 3, 3.2.  <sup>25</sup> Minimum Structural Root Zone (SRZ) for trees less than 0.15 m diameter is 1.5 m, AS4970 (2009) section 3, 3.5.</p>
<p><b>Explanatory notes for Table 2.0.</b>  This table is based upon Australian Standard AS4970 2009 <i>Protection of trees on development sites</i>, Section 3 Determining the protection zone of the selected trees (see Appendix B), where the approved building works should be no closer, including excavation, than the dimensions stated above.</p>	<p><b>"3.3 Variations to the TPZ"</b>  <b>3.3.2 Minor Encroachment</b>  <i>If the proposed encroachment is less than 10% of the area of the TPZ and is outside the SRZ, detailed root investigations should not be required. The area lost to this encroachment should be compensated for elsewhere and contiguous with the TPZ.</i></p>	<p><b>3.3.3 Major Encroachment -</b> <i>If the proposed encroachment is greater than 10% of the area of the TPZ or inside the SRZ the project arborist must demonstrate that the tree(s) would remain viable. The area lost to this encroachment should be compensated for elsewhere and contiguous with the TPZ."</i></p>

## 1.0 AIMS

- 1.1 Detail the condition of the trees on the site, adjoining properties or adjacent road reserve where such trees may be affected by the proposed works, by assessment of individual trees or stands of trees, and indicate protection measures or remedial works for their retention and protection pre, during and post construction. Consider the location and condition of the trees in relation to the proposed building works and recommend retention and protection or removal and replacement where appropriate. The retained specimens are to remain in a safe and healthy condition, not less than at the time of initial inspection for this report, or in a reduced but sustainable condition due to the impact of the development but ameliorated through tree protection measures recommended to be applied.
- 1.2 Provide as an outcome of the assessment, the following: a description of the trees, observations made, discussion of the effects the location of the proposed building works may have on the trees, and make recommendations required for remedial or other works to the trees, if and where appropriate. *(See section 5 - Tree Assessment.)*
- 1.3 Determine from the assessment as detailed in 1.2 a description of the works or measures required to ameliorate the impact upon the trees to be retained, by the proposed building works or future impacts the trees may have upon the new building works if and where appropriate, or the benefits of removal and replacement if appropriate for the medium to long term safety and amenity of the site.

## 2.0 OBJECTIVES

- 2.1 Assess the condition of the subject trees.
- 2.2 Determine impact of development on the subject trees.
- 2.3 Provide recommendations for retention or removal of the subject trees.

## 3.0 METHODOLOGY

**Note: Individual methodologies applied as applicable.**

- 3.1 The method of assessment of tree/s applied is adapted from the principles of visual tree assessment undertaken from the ground, which considers:
  1. Tree health and subsequent stability, both long and short term
  2. Sustainable Retention Index Value (SRIV) Version 4 (IACA 2010)©
  3. Hazard potential to people and property
  4. Amenity values
  5. Habitat values
  6. Significance
- 3.2 This assessment is undertaken using standard tree assessment criteria for each tree based on the values above and is implemented as a result of at least one comprehensive and detailed site inspection to undertake a visual tree assessment from the ground of each individual tree, or stand of trees, or a representative population sample. Any dimensions recorded as averages, or by approximation are noted accordingly.

- 3.3 This report adopts Australian Standard AS4970 2009 *Protection of trees on development sites* as a point of reference and guide for the recommended minimum setbacks (Appendix C) from the centre of a tree's trunk to development works and the distances may be increased or decreased by the author in accordance with AS4970 – Section 3.3.4 as a result of other factors providing mitigating circumstances or constraints as indicated by but not restricted to the following:
1. Condition of individual trees,
  2. Tolerance of individual species to disturbance,
  3. Geology e.g. physical barriers in soil, rock floaters, bedrock to surface
  4. Topography e.g. slope, drainage,
  5. Soil e.g. depth, drainage, fertility, structure,
  6. Microclimate e.g. due to landform, exposure to dominant wind,
  7. Engineering e.g. techniques to ameliorate impact on trees such as structural soil, gap graded fill, lateral boring,
  8. Construction e.g. techniques to ameliorate impact on trees such as pier and beam, bridge footings, suspended slabs,
  9. Root mapping,
  10. Physical limitations - existing modifications to the environment and any impact to tree/s by development e.g. property boundaries, built structures, houses, swimming pools, road reserves, utility services easements, previous impact by excavation, or construction in other directions, soil level changes by cutting or filling, existing landscaping works within close proximity, modified drainage patterns,
  11. Extraneous factors e.g. potential future impacts from development on adjoining land when the tree is located on or near to a property boundary.
- 3.4 Trees in groups may be referred to as stands and a stand may exclusively contain specimens to be either retained or removed or a combination of both. A stand may be used to discuss all the trees on a given site to expedite their assessment, or refer to trees growing proximate to one another or within a defined space. Stands may be comprised by mass boundary or screen plantings, to form a group of the same or a mixture of taxa. Each stand is considered as a single unit with each component tree assessed and expressed in tabular form, or indicated by a given percentage as a population sample of each stand. Where it is appropriate for a stand of trees to be retained in full or part, the location and setback of Tree Protection Zone fences or works, are prescribed to provide for the preservation of the stand or selected component trees, in a condition not less than that at the time of initial inspection for its incorporation into the landscape works for the site, or in a reduced but sustainable condition due to the impact of the development but ameliorated through tree protection measures.
- 3.5 The meanings for terminology used herein are taken from the IACA Dictionary for Managing Trees in Urban Environments 2009. An extract from the IACA Dictionary forms a glossary of terms included as Appendix D.

## 4.0 PRUNING STANDARDS

- 4.1 Any pruning recommended in this report is to be to the Australian Standard® AS4373 *Pruning of amenity trees*, and conducted in accordance with the NSW Work Cover Authority Code of Practice, Tree Work, 2007.
- 4.2 All pruning or removal works are to be in accordance with the appropriate Tree Management Policy where applicable, or Tree Management Order (TMO), or Tree Preservation Order (TPO).
- 4.3 Tree maintenance work is specialised and in order to be undertaken safely to ensure the works carried out are not detrimental to the survival of a tree being retained, and to assist in the safe removal of any tree, should be undertaken by a qualified arboriculturist with appropriate competencies recognised within the Australian Qualification Framework, with a minimum of 5 years of continual experience within the industry of operational amenity arboriculture, and covered by appropriate and current types of insurance to undertake such works.

## 5.0 TREE ASSESSMENT – 5.1 - Assessment of a stand of Trees

Tree / Stand No.	Genus & Species Common Name	Age Y = Young M = Mature O = Overmature	Vigour GV = Good LV = Low Vigour	Condition G = Good F = Fair P = Poor D = Dead	1. SRV Age, Vigour, Condition / Index Rating <a href="http://www.laca.org.au">www.laca.org.au</a> / 2. Estimated Life Expectancy 1. Long 2. Medium 3. Short	Crown Form D = Dominant C = Co-dominant I = Intermediate S = Suppressed F = Forest E = Emergent	Ht. Approx. metres	Crown Spread approx. metres / Orientation R = Radial, or other	Crown Symmetry 1 = symmetrical 2 = asymmetrical / Orientation	Crown Cover % / Crown Density % / D = dormant	DBH in mm @ 1.4m, or other, as indicated / Trunk Orientation other than R = radial, e.g. N/S g = ground # = average	Trunk Lean 1 = Upright-Slight 2 = Moderate 3 = Severe 4 = Critical 5 = Acaulescent / Orientation / ST = Static P = Progressive Sc = Self-correcting	Roots Evident at Root Crown 1. = None 2. = Adventitious 3. = Basal Flare 4. = Buttresses 5. = First Order Roots (FOR), No. & distribution e.g. R = radial, or one each to N, S, E and W	Pests, Diseases & Damage No or Yes If Yes see comments	Branch Bark Included No or Yes or N/A	Form G = Good F = Poor Form	Significance scale 1=High 2=Medium 3=Low / Retention Value 1=High 2=Medium 3=Low 4=Remove
1	<i>Sannantha bidwillii</i> (syn. <i>Baeckea virgata</i> )	M	GV	F	MGVF - 9 1	D	7	3x2 EW	2/W	70 70	250 R	1/R ST	1	NO	NO	P	1 2
	Twiggy Heath Myrtle	Comment: Trunk erect, straight, gradually tapering & continuous, orientation E/W, asymmetrical bias to west, crown excurrent. Specimen lopped to east over neighbouring property.															
2	<i>Callistemon citrinus</i> 'Kings Park Special'	M	GV	F	MGVF - 9 2	D	5	6x2 EW	2/N	50 70	200# @ g R	5/R ST	1	NO	NO	P	2 3
	Kings Park Bottlebrush	Comment: Acaulescent or short trunk @ or near ground, crown deliquescent, orientation E/W, asymmetrical bias to north. - Street Tree Specimen lopped for line clearance															
3	<i>Tibouchina lepidota</i> 'Alstonville'	M	GV	F	MGVF - 9 2	D	5	4 R	1	70 70	270# @ g R	5/R ST	1	NO	NO	G	2 2
	Lasiandra	Comment: Acaulescent or short trunk @ or near ground, crown deliquescent, orientation radial, symmetrical.															
4	<i>Juniperus glabra</i>	M	GV	G	MGVG - 10 1	D	12	1 R	1	70 70	300 R	1/R ST	1	NO	NO	G	2 1
	Smooth Cypress	Comment: Trunk erect, straight, gradually tapering & continuous, crown excurrent.															
5	<i>Thuja orientalis</i>	M	LV	F	MLVF - 5 2	C	6	2 R	1	50 60	250# @ g R	5/R ST	1	NO	NO	P	2 3
	Bookleaf Conifer	Comment: Acaulescent or short trunk @ or near ground, crown deliquescent, orientation radial, symmetrical.															
6	<i>Bauhinia purpurea</i>	M	GV	F	MGVF - 9 1	D	8	7x5 EW	2/W	60 60	300 R	1/R ST	1	NO	NO	P	2 3
	Butterfly Tree	Comment: Trunk to 2 metres, crown deliquescent, orientation E/W, asymmetrical bias to west.															
7	<i>Camellia sasanqua</i>	M	GV	F	MGVF - 9 1	C	6	3 R	1	60 60	200 # @ g R	5/R ST	1	NO	NO	G	2 2
	Camellia	Comment: Acaulescent or short trunk @ or near ground, crown deliquescent, orientation radial, symmetrical.															
8	<i>Syzygium smithii</i>	M	GV	G	MGVG - 10 1	D	12	5 R	1	70 70	300 R	1/R ST	1	NO	NO	G	2 1
	Lilly Pilly	Comment: Trunk erect, straight, gradually tapering & continuous, crown excurrent.															
9	<i>Juniperus glabra</i>	M	GV	F	MGVF - 9 2	D	10	3 R	1	70 70	250 R	1/R ST	1	NO	NO	G	1 3
	Smooth Cypress	Comment: Trunk erect, straight, gradually tapering & continuous, crown excurrent. Major build up around trunk.															
10	<i>Grevillea robusta</i>	M	GV	F	MGVF - 9 2	D	15	9x7 EW	2/E	70 70	340 R	1/R ST	1	NO	NO	P	2 3
	Silky Oak	Comment: Trunk erect, straight, gradually tapering & continuous, orientation E/W, asymmetrical bias to east, crown excurrent. Self-sown specimen.															

Tree / Stand No.	Genus & Species Common Name	Age Y = Young M = Mature O = Overmature	Vigour GV = Good Vigour LV = Low Vigour	Condition G = Good F = Fair P = Poor D = Dead	1. SRV Age, Vigour, Condition / Index Rating <a href="http://www.laca.org.au">www.laca.org.au</a> / 2. Estimated Life Expectancy 1. Long 2. Medium 3. Short	Crown Form D = Dominant C = Co-dominant I = Intermediate S = Suppressed F = Forest E = Emergent	Ht. Approx. metres	Crown Spread approx. metres / Orientation R = Radial, or other	Crown Symmetry 1 = symmetrical 2 = asymmetrical / Orientation	Crown Cover % / Crown Density % / D = dormant	DBH in mm @ 1.4m, or other, as indicated / Trunk Orientation other than R = radial, e.g. N/S g = ground	Trunk Lean 1 = Upright-Slight 2 = Moderate 3 = Severe 4 = Critical 5 = Acaulescent / Orientation / ST = Static P = Progressive Sc = Self- correcting	Roots Evident at Root Crown 1. = None 2. = Adventitious 3. = Basal Flare 4. = Buttresses 5. = First Order Roots (FOR), No. & distribution e.g. R = radial, or one each to N, S, E and W	Pests, Diseases & Damage No or Yes If Yes see comments	Branch Bark Included No or Yes or N/A	Form G = Good Form P = Poor Form	Significance scale 1=High 2=Medium 3=Low / Retention Value 1=High 2=Medium 3=Low 4=Remove
11	<i>Archontophoenix cunninghamiana</i>	M	GV	G	MGVG - 10	D	7	3	1	70	300	1/R	1	NO	NO	G	1
	1				R			70		R	ST	2					
	Comment: Trunk erect, straight, gradually tapering & continuous, crown excurrent.																
12	<i>Pittosporum undulatum</i>	M	GV	F	MGVF - 9	C	6	4	1	70	250	1/R	1	NO	NO	G	2
	2				R			70		R	ST	2					
	Comment: Trunk to 1 metre, crown deliquescent, orientation radial, symmetrical. Build up around trunk																
13 /2	<i>Dypsis decaryi</i> x2	M	GV	G	MGVG - 10	D	7	4	1	70	200	1/R	1	NO	NO	G	2
	2				R			70		R	ST	2					
	Comment: Trunk erect, straight, gradually tapering & continuous, crown excurrent.																



## Observation/Discussion

- 5.2 The site has a stand of mature, planted endemic and non-locally indigenous or exotic evergreen and deciduous taxa within the current proposal. The proposed design requires the retention and protection of four (4) specimens within the site and adjacent on the road reserve as they are considered significant for their contribution as landscape elements to the property and the retention of these trees allows them as components of the current curtilage to be transferred to the new proposal, maintaining elements of a continuous landscape, providing a more harmonious integration and transition of the use of the land. The other specimens located within the site were within the proposed building envelope and are not able to be retained. They are recommended for removal and replacement with super advanced specimens in 75 or 100 litre bags size stock within more appropriate positions within the development. Replacement of these specimens needs to be mindful of their spatial requirements to allow them to grow to maturity and not be impeded by the built structure.

### Tree Significance

- 5.3 Significant Trees as established by the Rating System for Tree Significance – IACA Stars (2010), Appendix A.

#### Significance Scale

- 1 – High  
2 – Medium  
3 – Low

Significance Scale	1	2	3
Redgum Tree No.	1, 9, 11	2, 3, 4, 5, 6, 7, 8, 10, 12, 13 <sup>a</sup>	

### Tree Retention Value

- 5.4 See Appendix A for Retention Value Matrix.

#### Retention Value

- High – Priority for Retention  
Medium – Consider for Retention  
Low – Consider for Removal  
Remove – Priority for Removal

Retention Value	High Priority for Retention	Medium Consider for Retention	Low Consider for Removal	Remove Priority for Removal
Redgum Tree No.	4, 8	1, 3, 7, 11, 12, 13 <sup>a</sup>	2, 5, 6, 9, 10	

- 5.5 AS4970 (2009) section 3, 3.3.3 requires the Project Arborist to demonstrate that where a retained tree is subject to a major encroachment (>10% of area of TPZ) it can be protected to remain viable

- 5.6 Tree 1 Sannantha bidwillii (syn. Baeckea virgata) - Twiggy Heath Myrtle, this specimen was found in fair health & good vigour at time of assessment.

- Trees viability to development; this specimen is not impacted by the proposed development. The project arborist is to certify that installation of protection measures have been installed as per D/A conditions prior to commencement and works are to be monitored throughout the project at approx. 3 mthly intervals depending on the length of the development. This specimen should remain viable beyond completion of development provided recommended installation & protection measures are adhered too.*

- Development Impacts: AS4970 (2009) section 3 requires a Tree Protection Zone (TPZ) setback of 3.0 metres (m) from centre of trunk (COT), the setback for the proposed development adjacent to this specimen is estimated at 5.0m from COT, which is a minor encroachment. This specimen is sufficiently setback from the development to not be affected.*

- 5.7 Tree 2 Callistemon citrinus 'Kings Park Special' - Kings Park Bottlebrush, this specimen was found in fair health & good vigour at time of assessment.

- Trees viability to development; this specimen is not impacted by the proposed development. The project arborist is to certify that installation of protection measures have been installed as per D/A conditions prior to commencement and works are to be monitored throughout the project at approx. 3 mthly intervals depending on the length of the development. This specimen should remain viable beyond completion of development provided recommended installation & protection measures are adhered too.*

- Development Impacts: AS4970 (2009) section 3 requires a TPZ setback of 2.4m from COT, the setback for the proposed development adjacent to this specimen is estimated at 6.0 from COT, which is a minor encroachment. This specimen is sufficiently setback from the development to not be affected.*

5.8 Tree 9 Juniperus glabra - Smooth Cypress, this specimen was found in fair health & good vigour at time of assessment.

- Trees viability to development: this specimen is not impacted by the proposed development. The project arborist is to certify that installation of protection measures have been installed as per D/A conditions prior to commencement and works are to be monitored throughout the project at approx. 3 mthly intervals depending on the length of the development. This specimen should remain viable beyond completion of development provided recommended installation & protection measures are adhered to.

- Development Impacts: AS4970 (2009) section 3 requires a TPZ setback of 3.0m from COT, the setback for the proposed development adjacent to this specimen is estimated at 3.6m from COT, which is a minor encroachment. This specimen is sufficiently setback from the development to not be affected.

5.9 Tree 12 Pittosporum undulatum - Native Daphne, this specimen was found in fair health & good vigour at time of assessment.

- Trees viability to development: this specimen is not impacted by the proposed development. The project arborist is to certify that installation of protection measures have been installed as per D/A conditions prior to commencement and works are to be monitored throughout the project at approx. 3 mthly intervals depending on the length of the development. This specimen should remain viable beyond completion of development provided recommended installation & protection measures are adhered to.

- Development Impacts: AS4970 (2009) section 3 requires a TPZ setback of 3.0m from COT, the setback for the proposed development adjacent to this specimen is estimated at 3.0m from COT, which is a minor encroachment. These specimens are sufficiently setback from the development to not be affected.

*If associated infrastructure (pipe works) are to be installed within the Tree Protection Zone of these specimens, they are to be installed by hand with non-motorised machinery. If structural roots are found within the trench, they are to be left intact and dug around retaining this specimen's structural integrity. Works are to be undertaken in consultation with the project arborist.*

The impact will be that of minor encroachment for Tree 1, 2, 9 & 12 which are to be retained and protected as per AS 4970 (2009) Section 3, 3.3.3 Major Encroachments from development works within >10% of the area of the Tree Protection Zone.

#### **General – Tree Protection works – Prior to Demolition**

5.10 Tree Management Plan – Prior to demolition works, a site arborist shall be appointed to supervise all tree protection procedures detailed in this specification. The Site Arborist shall have a minimum level 5 AQF qualification in Arboriculture. Milestones are to be adhered to throughout the duration of this development and all relevant documentation is to be submitted to the local authority.

5.11 The Tree Protection Zone for each tree/s is to be incorporated into the construction works for the site and the protection fencing or works to be located as indicated on the Appendix F – Tree Protection Plan. The setbacks from building works on the side closest to each tree are to be carried out as indicated in Table 2.0, and Tree Protection Zones be constructed as described here and detailed in Appendix C. The trees will be sustained within the constraints of the modifications to the site by the proposed development works.

5.12 Trees 1, 2, 9 & 12 are to be retained and protected and incorporated into the landscape works for the site, and Tree Protection Zone fencing to be marked accordingly on the Landscape Plan, where appropriate and installed prior to any demolition or construction.

5.13 Ground protection - If temporary access for machinery is required within the TPZ ground protection measures will be required. The purpose of ground protection is to prevent root damage and soil compaction within the TPZ. Measures may include a permeable membrane such as geotextile fabric beneath a layer of mulch or crushed rock below rumble boards. These measures may be applied to root zones beyond the TPZ.

5.14 Where applicable, any excavation for the establishment of a batter slope or benching for reasons of safety and to comply with Work Cover Authority safety regulations should be restricted as far as is safely possible near to trees to be retained to prevent root damage. If the excavations cannot be undertaken near to vertical the stability of these trees and their long-term viability may be compromised and their retention in a safe and healthy condition jeopardized and they may need to be revised and possibly removed.



### Specific - Tree Protection Works - Prior to Demolition and Tree Removal

- 5.15 All other trees/shrubs; prior to demolition and tree removal works these tree/s are to be placed within a Tree Protection Zone with protective fencing and maintained and retained until the completion of all building works. Protective fencing is to be installed as shown in Appendix F - Tree Protection Plan.
- The Protective fencing where required may delineate the **Tree Protection Zone (TPZ)** and should be located as determined by the project arborist in accordance with AS4970 Protection of trees on development sites, Section 4, 4.3. "Fencing should be erected before any machinery or materials are brought onto the site and before the commencement of works including demolition. Once erected, protective fencing must not be removed or altered without approval by the project arborist. The TPZ must be secured to restrict access. AS4687 Temporary fencing and hoardings specifies applicable fencing requirements. Shade cloth or similar should be attached to reduce the transport of dust, other particulate matter and liquids into the protected area. Fence posts and supports should have a diameter greater than 20 mm and be located clear of roots. Existing perimeter fencing and other structures may be suitable as part of the protective fencing" or similar.
  - Tree Protection signage is to be attached to each **TPZ** and displayed from within the development site in accordance with AS4970 2009 *Protection of trees on development sites*
  - The area of the Tree Protection Zone to be mulched to a depth of 100 mm with organic material being 75% leaf litter and 25% wood, and this being composted material preferably from the same genus and species of tree as that to where the mulch is to be applied, i.e. species specific mulch. The depth of mulch and type as indicated, to be maintained for the duration of the project. Where deep excavation will expose the soil profile to drying out the root plate is to be protected by pegging jute matting across the ground surface 2 m back from the edge of the profile and 2 m down the face of the profile and is to be in one continuous sheet or layers up to 5 mm thick and overlapped 300 mm and pegged. Pegs are to be a minimum length of 200 mm and spaced at 500 mm increments in a grid pattern. Once installed mulch is to be placed on top of the jute matting previously described.
- 5.16 There is to be no storage of materials, rubbish, soil, equipment, structures or goods of any type to be kept or placed within 5 metres from the trunk or within the dripline of any tree for the duration of the development. This will ensure protection of the tree/s to be retained on or adjacent to site.
- 5.17 Milestone - Project/Site arborist is to inspect/assess all retained specimens prior to demolition to inspect tree protection measures have been carried out as per the approved D/A conditions for the site. Documentation is to be submitted to the consenting authority after each inspection.

### Demolition and Tree Removal/s

- 5.18 Trees 3 to 8, 10, 11 & 13<sup>2</sup> are to be removed as they are located within the site in a position where they cannot be retained due to the proposed building envelopes and its infrastructure such as excavation of the basement where encroachment will have an adverse impact on its roots and crown for viability and stability.
- Tree 3 to 8, 10, 11 & 13<sup>2</sup>: *Tibouchina lepidota* 'Alstonville' – Lasiandra, *Juniperus glabra* - Smooth Cypress, Tree 5: *Thuja orientalis* - Bookleaf Conifer, *Bauhinia purpurea* - Butterfly Tree, *Camellia sasanqua* – Camellia, *Syzygium smithii* - Lilly Pilly, *Grevillea robusta* - Silky Oak, *Archontophoenix cunninghamiana* - Bangalow Palm & *Dypsis decaryi* - Triangle Palm; located within the site and positioned within the proposed building envelope for the development. These specimens are recommended to be removed and replaced as they cannot be retained due to the proposed development.
- 5.19 Removal of a tree within 6 m of a tree to be retained should be undertaken only by cutting down such a tree without damaging the trees to be retained, and by grinding out its stump. Where possible the structural roots of 20 mm diameter or greater of the tree to be cut down should not be removed, to minimise soil disturbance and to reduce the impact on the roots of any tree to be retained nearby. Where structural roots are to be removed this should be undertaken manually by the use of non-motorized hand tools after the stump has been ground out when such roots are often easier to locate from the site of the stump from which they have been severed.
- 5.20 Ground protection in accordance with AS4970 section 4, 4.5.3 may require steel plates to protect the ground surface from compaction to protect roots between the stages of demolition and construction of the new pavement.

### **Specific - Tree Protection works – Post Demolition and Prior to Construction**

- 5.21 **Milestone** - Project/Site arborist is to inspect/assess all retained specimens prior to construction in relation to tree protection measures have been carried out as per the approved D/A conditions for the site. Documentation is to be submitted to the consenting authority after each inspection.
- 5.22 **Location of underground utilities within a Tree Protection Zone of a retained specimen.**  
Any utility services to be located underground within the TPZ are to be undertaken utilising excavation techniques that prevent or minimise damage to structural roots (roots greater than >20 mm diameter). To prevent soil compaction and root damage these works should be conducted with non-motorised hand tools, air knife or directional drilling.
- 5.23 **Re-grading of site near retained trees;** Grading &/or re-grading of sites/slopes within Tree Protection Zones or near retained specimens is to be undertaken **only** if at all, after consultation with the Project Arborist. This is to protect all structural roots systems from damage or compaction from machinery.
- 5.24 **Placement of relocatable buildings;** consideration should be given to tree sensitivity such as the buildings being placed on pier and beam or skids construction as they are to be positioned now on the eastern side of their driplines within the Tree Protection Zone (TPZ). The area of the Tree Protection Zone under the buildings is to be mulched to a depth of 200 mm (*if installed on skids*) with organic material to further reduce compaction. The mulch is to be composted material, i.e. species specific mulch. Alternatively, if installed on a pier & beam construction, piers are to be undertaken manually by using non-motorized hand tools to determine the location of first order and lower order structural roots with a diameter of 20 mm (*structural woody roots*) or greater, without damaging them.

### **Specific - Tree Protection works – During Construction**

- 5.25 **Milestone** - Project/Site arborist is to inspect/assess all retained specimens during construction in relation to tree protection measures have been carried out as per the approved D/A conditions for the site. Documentation is to be submitted to the consenting authority after each inspection.
- 5.26 Where any structural roots (roots with a diameter of greater than >20 mm) encountered by excavation are to be pruned and it is to be undertaken with clean sharp pruning tools, with a final cut to undamaged wood to prevent infestation by pathogens and assist continued root growth and undertaken in consultation with the Consulting Arboriculturist. Tree Protection Zone fences are to be maintained during these works. Ground protection in accordance with AS4970 section 4, 4.5.3 may require steel plates to protect the ground surface from compaction to protect roots between the stages of demolition and construction of the new pavement.
- 5.27 All Tree Protection Zones of retained trees are to be monitored for the duration of the construction phase of the development. The three main areas requiring monitoring are; **mulching** - mulch must be maintained to a depth of 50–100 mm using material that complies with AS 4454. Where the existing landscape within the TPZ is to remain unaltered (e.g. garden beds or turf) mulch may not be required, **Watering** - soil moisture levels should be regularly monitored by the project arborist. Temporary irrigation or watering may be required within the TPZ. An above-ground irrigation system could be installed and maintained by a competent individual and **weeding** - weeds should be removed by hand without disturbing soil or should be controlled with weedicide.
- 5.28 Trees to be removed are to be replaced with advanced specimens being mindful of the space limitations of the new use of the site. The advanced trees should be located in areas along the boundaries of the site. The planting in these locations will provide the maximum benefit to the surrounding properties by screening views to and from the site and the plantings included in the proposed landscape plan. The replacement trees will be located in positions where they may grow to maturity unhindered and will not conflict with built structures or utility services and in greater numbers than the trees removed should provide a net increase in the local amenity.

### **Specific - Tree Protection works – Post Construction**

- 5.29 At completion of construction work the Site/Project Arborist should carry out an assessment of all trees retained &/or affected by works. This assessment is to document and any required on-going remedial care needed to ensure viable retention of trees affected. Documentation is to be submitted to the consenting authority.

## 6.0 CONCLUSION

Ten (10) trees are nominated for removal and replacement with species in accordance with the associated Landscape documentation for the development. The four (4) trees to be preserved will be retained and protected through the implementation of adequate measures for their integration into the development by the application of appropriate technology as detailed in this report. Where appropriate, the Landscape Plan will include planting with new trees including street tree/s.

It is often a consequence of redevelopment, and subject to the nature of the proposed land use that some or all of the trees present on the site prior to that redevelopment may be required to be removed and replaced with new tree plantings in different locations. This may be dependent upon the type of development and its design constraints and the requirements of the local planning instruments and any Landscape Design Codes if existing. Where tree removal is required for this development, it is considered that those trees identified within this report are not sustainable within the context of the proposed development. Where tree retention has been considered, those trees are expected to survive the redevelopment process and remain stable and viable. The retention and protection of existing trees on site is a significant aspect of the development process, allowing those trees as components of the current curtilage to be transferred to the new development for incorporation into the landscaping works for the site. The retention of some or all of the existing trees contributes to: the preservation of local amenity, screening of views to and from the site, and a balance to the scale and bulk of buildings, while maintaining elements of a continuous landscape, providing a more harmonious integration and transition of the use of the land.

If all the recommendations and procedures detailed herein are adhered to, some or all of the trees the subject of this report will continue, or will be replaced with more appropriate plantings in suitable locations, or enhanced by additional new plantings, and will grow to develop as important landscape components providing elements of long term amenity for the property and its owners or occupants, and the local community.

The recommendations made in this report are subject to approval by the consent authority.

As a renewable and dynamic natural resource the urban tree and the growing environment essential for its survival must be understood and carefully managed to balance its needs with those of people. It is crucial that as required: this resource be planned for, planted, nurtured, protected, maintained and replaced, to ensure appropriateness and suitability of new plantings and trees retained, for safety and viability, so that it remains vital, and is sustainable in continuity.



## 7.0 RECOMMENDATIONS

- 7.1 Trees 1, 2, 9 & 12 are to be retained in situ within the site and are to be protected as detailed in 5.6 - 5.17 & 5.20 - 5.29. Tree protection fences, or works, to be located in accordance with *Site Plan B - Trees To Be Retained And Tree Protection Zones* (Appendix F).
- 7.2 Where Tree Protection Zone fences are to be moved or relocated this must be undertaken in consultation with the Consultant Arboriculturist for the project to ensure that tree protection is maintained. If the fences are relocated areas are to be mulched in accordance with 5.15 of this report to reduce compaction to the root system of the retained specimens.
- 7.3 To minimise damage to retained crowns, all Tree Protection Zones are to be adhered to. This must be undertaken in consultation with the Consultant Arboriculturist for the project to ensure that tree protection is maintained. Minor pruning may be required if damage occurs, work is to be undertaken in accordance with section 4 of this report.
- 7.4 **Milestones** - Project/Site arborist is to inspect/assess all retained specimens prior to Demolition and Tree Removal, Post Demolition, Prior to Construction during Construction and on completion in relation to trees protected and the protection measures have been carried out as per the approved D/A conditions for the site. Documentation is to be submitted to the consenting authority after each inspection.
- 7.5 Trees 3 to 8, 10, 11 & 13<sup>x2</sup> are to be removed which is to be undertaken in accordance with section 4.0, parts 4.1 - 4.3.
- 7.6 Tree removal near retained specimens is to be undertaken in accordance with 5.19 of this report.
- 7.7 Any work to be undertaken within Tree Protection Zones is to be undertaken in accordance 7.2 of this report.
- 7.8 There is to be no storage of materials, rubbish, soil, equipment, structures or goods of any type to be kept or placed within 5 metres from the trunk or within the dripline of any tree for the duration of the development. This will ensure protection of the tree/s to be retained on or adjacent to site.
- 7.9 Each of the replacement are to be a vigorous specimen with a straight trunk, gradually tapering and continuous, crown excurrent, symmetrical, with roots established but not pot bound in a volume container or approved similar and be maintained by an appropriately qualified and experienced landscape contractor for up to one (1) year after planting, or as appropriate.



**Neville Shields – MAIH5021**

**Principal Consultant (Director)**

**IACA-ACM0072003**

neville@redgumhrt.com.au

Diploma of Horticulture – Arboriculture; (ACF) 2001,

Work Place Assessment & Training Certificate; (ACF) 2001,

Associate Diploma of Horticulture – Park Management; 1987

Horticulture Certificate; 1984

Urban Pest Control Certificate; 1988

Member of: Institute of Australia Consulting Arboriculturists (IACA), 2003

International Society of Arboriculture (ISA), 2005

Australian Institute of Horticulture (AIH) 2008

& Arboriculture Australia (AA) 2015



### DISCLAIMER

The author and Redgum Horticultural take no responsibility for actions taken and their consequences, contrary to those expert and professional instructions given as recommendations pertaining to safety by way of exercising our responsibility to our client and the public as our duty of care commitment, to mitigate or prevent hazards from arising, from a failure moment in full or part, from a structurally deficient or unsound tree or a tree likely to be rendered true by its retention and subsequent modifications to its growing environment either above or below ground contrary to our advice.

### REFERENCES

1. Draper BD and Richards PA 2008, *Dictionary for Managing Trees in Urban Environments*, Institute of Australian Consulting Arboriculturists (IACA), CSIRO Publishing, Collingwood, Victoria, Australia.
2. IACA 2006, *Sustainable Retention Index Value*, Institute of Australian Consulting Arboriculturists, Australia, [www.iaca.org.au](http://www.iaca.org.au).
3. Standards Australia 2007, *Australian Standard 4373 Pruning of amenity trees*, Standards Australia, Sydney, Australia.
4. Standards Australia 2008, *Australian Standard 4970 Protection of trees on development sites*, Standards Australia, Sydney, Australia.
5. Work Cover NSW 2007, *Code of Practice Tree Work*, New South Wales Government, Australia.



# Appendix A

## IACA Significance of a Tree, Assessment Rating System (STARS) © (IACA 2010)©

In the development of this document IACA acknowledges the contribution and original concept of the Footprint Green Tree Significance & Retention Value Matrix, developed by Footprint Green Pty Ltd in June 2001.

The landscape significance of a tree is an essential criterion to establish the importance that a particular tree may have on a site. However, rating the significance of a tree becomes subjective and difficult to ascertain in a consistent and repetitive fashion due to assessor bias. It is therefore necessary to have a rating system utilising structured qualitative criteria to assist in determining the retention value for a tree. To assist this process all definitions for terms used in the *Tree Significance - Assessment Criteria* and *Tree Retention Value - Priority Matrix*, are taken from the IACA Dictionary for Managing Trees in Urban Environments 2009.

This rating system will assist in the planning processes for proposed works, above and below ground where trees are to be retained on or adjacent a development site. The system uses a scale of *High*, *Medium* and *Low* significance in the landscape. Once the landscape significance of an individual tree has been defined, the retention value can be determined.

### Tree Significance - Assessment Criteria



#### **1. High Significance in landscape**

- The tree is in good condition and good vigour;
- The tree has a form typical for the species;
- The tree is a remnant or is a planted locally indigenous specimen and/or is rare or uncommon in the local area or of botanical interest or of substantial age;
- The tree is listed as a Heritage Item, Threatened Species or part of an Endangered ecological community or listed on Councils significant Tree Register;
- The tree is visually prominent and visible from a considerable distance when viewed from most directions within the landscape due to its size and scale and makes a positive contribution to the local amenity;
- The tree supports social and cultural sentiments or spiritual associations, reflected by the broader population or community group or has commemorative values;
- The tree's growth is unrestricted by above and below ground influences, supporting its ability to reach dimensions typical for the taxa *in situ* - tree is appropriate to the site conditions.

#### **2. Medium Significance in landscape**

- The tree is in fair-good condition and good or low vigour;
- The tree has form typical or atypical of the species;
- The tree is a planted locally indigenous or a common species with its taxa commonly planted in the local area.
- The tree is visible from surrounding properties, although not visually prominent as partially obstructed by other vegetation or buildings when viewed from the street;
- The tree provides a fair contribution to the visual character and amenity of the local area;
- The tree's growth is moderately restricted by above or below ground influences, reducing its ability to reach dimensions typical for the taxa *in situ*.

#### **3. Low Significance in landscape**

- The tree is in fair-poor condition and good or low vigour;
- The tree has form atypical of the species;
- The tree is not visible or is partly visible from surrounding properties as obstructed by other vegetation or buildings;
- The tree provides a minor contribution or has a negative impact on the visual character and amenity of the local area;
- The tree is a young specimen which may or may not have reached dimension to be protected by local Tree Preservation orders or similar protection mechanisms and can easily be replaced with a suitable specimen;
- The tree's growth is severely restricted by above or below ground influences, unlikely to reach dimensions typical for the taxa *in situ* - tree is inappropriate to the site conditions;
- The tree is listed as exempt under the provisions of the local Council Tree Preservation Order or similar protection mechanisms;
- The tree has a wound or defect that has potential to become structurally unsound.

#### **Environmental Pest / Noxious Weed Species**

- The tree is an Environmental Pest Species due to its invasiveness or poisonous/ allergenic properties;
- The tree is a declared noxious weed by legislation.


#### **Hazardous/irreversible Decline**

- The tree is structurally unsound and/or unstable and is considered potentially dangerous;
- The tree is dead, or is in irreversible decline, or has the potential to fail or collapse in full or part in the immediate to short term.

**The tree is to have a minimum of three (3) criteria in a category to be classified in that group.**

Note: The assessment criteria are for individual trees only, however, can be applied to a monocultural stand in its entirety e.g. hedge.

Table 1.0 Tree Retention Value - Priority Matrix.

		Significance				
		1. High	2. Medium	3. Low		
		Significance in Landscape	Significance in Landscape	Significance in Landscape	Environmental Pest / Noxious Weed Species	Hazardous / Irreversible Decline
Estimated Life Expectancy	1. Long >40 years					
	2. Medium 15-40 Years					
	3. Short <1-15 Years					
	Dead					
<p><b>Legend for Matrix Assessment</b></p> 						
	<p><b>Priority for Retention (High)</b> - These trees are considered important for retention and should be retained and protected. Design modification or re-location of building/s should be considered to accommodate the setbacks as prescribed by the Australian Standard AS4970 <i>Protection of trees on development sites</i>. Tree sensitive construction measures must be implemented e.g. pier and beam etc if works are to proceed within the Tree Protection Zone.</p>					
	<p><b>Consider for Retention (Medium)</b> - These trees may be retained and protected. These are considered less critical; however their retention should remain priority with removal considered only if adversely affecting the proposed building/works and all other alternatives have been considered and exhausted.</p>					
	<p><b>Consider for Removal (Low)</b> - These trees are not considered important for retention, nor require special works or design modification to be implemented for their retention.</p>					
	<p><b>Priority for Removal</b> - These trees are considered hazardous, or in irreversible decline, or weeds and should be removed irrespective of development.</p>					

## REFERENCES

- Australia ICOMOS Inc. 1999, *The Burra Charter – The Australian ICOMOS Charter for Places of Cultural Significance*, International Council of Monuments and Sites, [www.icomos.org/australia](http://www.icomos.org/australia)
- Draper BD and Richards PA 2009, *Dictionary for Managing Trees in Urban Environments*, Institute of Australian Consulting Arboriculturists (IACA), CSIRO Publishing, Collingwood, Victoria, Australia.
- Footprint Green Pty Ltd 2001, *Footprint Green Tree Significance & Retention Value Matrix*, Avalon, NSW Australia, [www.footprintgreen.com.au](http://www.footprintgreen.com.au)



# Appendix B

## Matrix - Sustainable Retention Index Value (SRIV) ©

Version 4, 2010

Developed by IACA – Institute of Australian Consulting Arboriculturists [www.iaca.org.au](http://www.iaca.org.au)

The matrix is to be used with the value classes defined in the Glossary for Age / Vigour / Condition.  
An index value is given to each category where ten (10) is the highest value.

Age Class	Vigour Class and Condition Class					
	Good Vigour & Good Condition (GVG)	Good Vigour & Fair Condition (GVF)	Good Vigour & Poor Condition (GVP)	Low Vigour & Good Condition (LVG)	Low Vigour & Fair Condition (LVF)	Low Vigour & Poor Condition (LVP)
	Able to be retained if sufficient space available above and below ground for future growth. No remedial work or improvement to growing environment required. May be subject to high vigour. Retention potential - Medium - Long Term.	Able to be retained if sufficient space available above and below ground for future growth. Remedial work may be required or improvement to growing environment may assist. Retention potential - Medium Term. Potential for longer with remediation or favourable environmental conditions.	Able to be retained if sufficient space available above and below ground for future growth. Remedial work unlikely to assist condition, improvement to growing environment may assist. Retention potential - Short Term. Potential for longer with remediation or favourable environmental conditions.	May be able to be retained if sufficient space available above and below ground for future growth. No remedial work required, but improvement to growing environment may assist vigour. Retention potential - Short Term. Potential for longer with remediation or favourable environmental conditions.	May be able to be retained if sufficient space available above and below ground for future growth. Remedial work or improvement to growing environment may assist condition and vigour. Retention potential - Short Term. Potential for longer with remediation or favourable environmental conditions.	Unlikely to be able to be retained if sufficient space available above and below ground for future growth. Remedial work or improvement to growing environment unlikely to assist condition or vigour. Retention potential - Likely to be removed immediately or retained for Short Term. Potential for longer with remediation or favourable environmental conditions.
(Y)	<b>YGVG - 9</b>	<b>YGVF - 8</b>	<b>YGVP - 5</b>	<b>YLVG - 4</b>	<b>YLVF - 3</b>	<b>YLVP - 1</b>
Young	Index Value 9 Retention potential - Long Term. Likely to provide minimal contribution to local amenity if height <5 m. High potential for future growth and adaptability. Retain, move or replace.	Index Value 8 Retention potential - Short - Medium Term. Potential for longer with improved growing conditions. Likely to provide minimal contribution to local amenity if height <5 m. Medium-high potential for future growth and adaptability. Retain, move or replace.	Index Value 5 Retention potential - Short Term. Potential for longer with improved growing conditions. Likely to provide minimal contribution to local amenity if height <5 m. Low-medium potential for future growth and adaptability. Retain, move or replace.	Index Value 4 Retention potential - Short Term. Potential for longer with improved growing conditions. Likely to provide minimal contribution to local amenity if height <5 m. Medium potential for future growth and adaptability. Retain, move or replace.	Index Value 3 Retention potential - Short Term. Potential for longer with improved growing conditions. Likely to provide minimal contribution to local amenity if height <5m. Low-medium potential for future growth and adaptability. Retain, move or replace.	Index Value 1 Retention potential - Likely to be removed immediately or retained for Short Term. Likely to provide minimal contribution to local amenity if height <5 m. Low potential for future growth and adaptability.
(M)	<b>MGVG - 10</b>	<b>MGVF - 9</b>	<b>MGVP - 6</b>	<b>MLVG - 5</b>	<b>MLVF - 4</b>	<b>MLVP - 2</b>
Mature	Index Value 10 Retention potential - Medium - Long Term.	Index Value 9 Retention potential - Medium Term. Potential for longer with improved growing conditions.	Index Value 6 Retention potential - Short Term. Potential for longer with improved growing conditions.	Index Value 5 Retention potential - Short Term. Potential for longer with improved growing conditions.	Index Value 4 Retention potential - Short Term. Potential for longer with improved growing conditions.	Index Value 2 Retention potential - Likely to be removed immediately or retained for Short Term.
(O)	<b>OGVG - 6</b>	<b>OGVF - 5</b>	<b>OGVP - 4</b>	<b>OLVG - 3</b>	<b>OLVF - 2</b>	<b>OLVP - 0</b>
Over-mature	Index Value 6 Retention potential - Medium - Long Term.	Index Value 5 Retention potential - Medium Term.	Index Value 4 Retention potential - Short Term.	Index Value 3 Retention potential - Short Term. Potential for longer with improved growing conditions.	Index Value 2 Retention potential - Short Term.	Index Value 0 Retention potential - Likely to be removed immediately or retained for Short Term.



# Appendix C

## Extract from Australian Standard AS4970 2009 Protection of trees on development sites

### Section 3, Determining the tree protection zones of the selected trees

#### 3.1 Tree protection zone (TPZ)

*"The tree protection zone (TPZ) is the principal means of protecting trees on development sites. The TPZ is a combination of the root area and crown area requiring protection. It is an area isolated from construction disturbance, so that the tree remains viable.*

*The TPZ incorporates the structural root zone (SRZ) (refer to Clause 3.3.5)."*

#### 3.2 Determining the TPZ

The radius of the TPZ is calculated for each tree by multiplying its DBH x 12.

$$\text{TPZ} = \text{DBH} \times 12$$

where

DBH = trunk diameter measured at 1.4 m above ground

Radius is measured from the centre of the stem at ground level.

#### 3.3.5 Structural root zone (SRZ)

*"The SRZ is the area required for street stability. A larger area is required to maintain a viable tree. The SRZ only needs to be calculated when a major encroachment into a TPZ is proposed. Root investigation may provide more information on the extent of these roots."*

#### Determining the SRZ

The radius of the TPZ is calculated for each tree by multiplying its DBH x 12.

$$\text{SRZ radius} = (D \times 50)^{0.42} \times 0.64$$

where

D = trunk diameter, in metres, measured above the root buttress.


Note: The SRZ for trees with trunk diameters less than 0.15 m will be 1.5 m (see Figure 1).

The curve can be expressed by the following formula:  
 $R_{\text{SRZ}} = (D \times 50)^{0.42} \times 0.64$

#### NOTES:

- 1  $R_{\text{SRZ}}$  is the structural root zone radius.
- 2 D is the stem diameter measured immediately above root buttress.
- 3 The SRZ for trees less than 0.15 m diameter is 1.5 m.
- 4 The SRZ formula and graph do not apply to palms, other monocots, cycads and tree ferns.
- 5 This does not apply to trees with an asymmetrical root plate.

FIGURE 1 STRUCTURAL ROOT ZONE



# Appendix D

## Glossary

From

*Dictionary for Managing Trees in Urban Environments by Draper BD and Richards PA 2009,  
Institute of Australian Consulting Arboriculturists (IACA), CSIRO Publishing, Collingwood, Victoria, Australia.*

### Age of Trees

**Age** Most trees have a stable biomass for the major proportion of their life. The estimation of the age of a tree is based on the knowledge of the expected lifespan of the taxa in situ divided into three distinct stages of measurable biomass, when the exact age of the tree from its date of cultivation or planting is unknown and can be categorized as *Young*, *Mature* and *Over-mature* (British Standards 1991, p. 13, Harris *et al*, 2004, p. 262).

**Young Tree** aged less than <20% of life expectancy, *in situ*.

**Mature Tree** aged 20-80% of life expectancy, *in situ*.

**Over-mature Tree** aged greater than >80% of life expectancy, *in situ*, or *senescent* with or without reduced vigour, and declining gradually or rapidly but irreversibly to death.

### Condition of Trees

**Condition** A tree's *crown form* and growth habit, as modified by its *environment* (aspect, suppression by other trees, soils), the *stability* and *viability* of the *root plate*, trunk and structural branches (first (1<sup>st</sup>) and possibly second (2<sup>nd</sup>) order branches), including structural defects such as wounds, cavities or hollows, *crooked* trunk or weak trunk/branch junctions and the effects of predation by pests and diseases. These may not be directly connected with vigour and it is possible for a tree to be of *normal vigour* but in *poor condition*. Condition can be categorized as *Good Condition*, *Fair Condition*, *Poor Condition* and *Dead*.

**Good Condition** Tree is of good habit, with *crown form* not severely restricted for space and light, physically free from the adverse effects of *predation* by pests and diseases, obvious instability or structural weaknesses, fungal, bacterial or insect infestation and is expected to continue to live in much the same condition as at the time of inspection provided conditions around it for its basic survival do not alter greatly. This may be independent from, or contributed to by vigour.

**Fair Condition** Tree is of good habit or *misshapen*, a form not severely restricted for space and light, has some physical indication of *decline* due to the early effects of *predation* by pests and diseases, fungal, bacterial, or insect infestation, or has suffered physical injury to itself that may be contributing to instability or structural weaknesses, or is faltering due to the modification of the *environment* essential for its basic survival. Such a tree may recover with remedial works where appropriate, or without intervention may stabilise or improve over time, or in response to the implementation of beneficial changes to its local environment. This may be independent from, or contributed to by vigour.

**Poor Condition** Tree is of good habit or *misshapen*, a form that may be severely restricted for space and light, exhibits symptoms of advanced and *irreversible decline* such as fungal, or bacterial infestation, major die-back in the branch and *foliage crown*, *structural deterioration* from insect damage e.g. termite infestation, or storm damage or lightning strike, ring barking from borer activity in the trunk, root damage or instability of the tree, or damage from physical wounding impacts or abrasion, or from altered local environmental conditions and has been unable to adapt to such changes and may decline further to death regardless of remedial works or other modifications to the local *environment* that would normally be sufficient to provide for its basic survival if in *good* to *fair* condition. Deterioration physically, often characterised by a gradual and continuous reduction in vigour but may be independent of a change in vigour, but characterised by a proportionate increase in susceptibility to, and *predation* by pests and diseases against which the tree cannot be sustained. Such conditions may also be evident in trees of advanced senescence due to normal phenological processes, without modifications to the growing environment or physical damage having been inflicted upon the tree. This may be independent from, or contributed to by vigour.

**Senescent / Moribund** Advanced state of decline, dying or nearly dead.

**Dead Tree** is no longer capable of performing any of the following processes or is exhibiting any of the following symptoms:

#### *Processes*

Photosynthesis via its foliage crown (as indicated by the presence of moist, green or other coloured leaves);

Osmosis (the ability of the root system to take up water);

Turgidity (the ability of the plant to sustain moisture pressure in its cells);

Epilcomic shoots or *epicormic strands* in Eucalypts (the production of new shoots as a response to stress, generated from latent or adventitious buds or from a *lignotuber*);

#### *Symptoms*

Permanent leaf loss;

Permanent wilting (the loss of turgidity which is marked by desiccation of stems leaves and roots);

Abscission of the *epidermis* (bark desiccates and peels off to the beginning of the sapwood).

**Removed** No longer present, or tree not able to be located or having been cut down and retained on a site, or having been taken away from a site prior to site inspection.

## Branch

**Branch** An elongated woody structure arising initially from the trunk to support leaves, flowers, fruit and the development of other branches. A branch may itself fork and continue to divide many times as successive *orders of branches* with the length and taper decreasing incrementally to the *outer extremity* of the crown. These may develop initially as a gradually tapering continuation of the *trunk* with minimal division as in a *young tree* or a tree of *excurrent habit*, or in a *sapling*, or may arise where the trunk terminates at or some distance from the *root crown*, dividing into *first order branches* to form and support the *foliage crown*. In an *acaulescent tree*, branches arise at or near the *root crown*. Similarly branches may arise from a *sprout mass* from damaged *roots*, *branches* or *trunk*.

**Orders of branches** The marked divisions between successively smaller branches (James 2003, p. 168) commencing at the initial division where the trunk terminates on a *deliquescent tree* or from *lateral branches* on an *excurrent tree*. Successive branching is generally characterised by a gradual reduction in branch diameters at each division, and each gradation from the trunk can be categorised numerically, e.g. first order, second order, third order etc. (See Figure 21.)




Figure 21 Orders of branches

## Crown

**Canopy** 1. Of multiple trees, the convergence, or merging in full or part, of the crowns of two or more trees due to their proximity, or where competition for light and space available in a forest environment is limited as each tree develops forming a continuous layer of foliage. 2. Used as a plural for crown. 3. Sometimes synonymously used for crown (USA).

**Crown** Of an individual tree all the parts arising above the trunk where it terminates by its division forming branches, e.g. the branches, leaves, flowers and fruit; or the total amount of foliage supported by the branches. The crown of any tree can be divided vertically into three sections and can be categorised as *lower crown*, *mid crown* and *upper crown* (Figure 8). For a *leaning tree* these can be divided evenly into crown sections of one-third from the base to apex. The volume of a crown can be categorised as the *inner crown*, *outer crown* and *outer extremity of crown*.

**Lower crown** The *proximal* or lowest section of a crown when divided vertically into one-third ( $\frac{1}{3}$ ) increments. See also *Crown*, *Mid crown* and *Upper crown*.

**Mid crown** The middle section of a crown when divided vertically into one-third ( $\frac{1}{3}$ ) increments. See also *Crown*, *Lower crown* and *Upper crown*.

**Upper crown** The *distal* or highest section of a crown when divided vertically into one-third ( $\frac{1}{3}$ ) increments. See also *Crown*, *Mid crown* and *Lower crown*.

**Crown Projection (CP)** Area within the *dripline* or beneath the lateral extent of the *crown* (Geiger 2004, p. 2). See also *Crown spread* and *Dripline*.

**Dripline** A line formed around the edge of a tree by the lateral extent of the *crown*. Such a line may be evident on the ground with some trees when exposed soil is displaced by rain shed from the crown. See also *Crown Projection*.

## Crown Form of Trees

**Crown Form** The shape of the crown of a tree as influenced by the availability or restriction of space and light, or other contributing factors within its growing environment. Crown Form may be determined for tree shape and habit generally as *Dominant*, *Codominant*, *Intermediate*, *Emergent*, *Forest* and *Suppressed*. The habit and shape of a *crown* may also be considered qualitatively and can be categorized as *Good Form* or *Poor Form*.

**Good Form** Tree of *typical* crown shape and habit with proportions representative of the taxa considering constraints such as origin e.g. indigenous or exotic, but does not appear to have been adversely influenced in its development by environmental factors in situ such as *soil water* availability, prevailing wind, or cultural practices such as lopping and competition for space and light.

**Poor Form** Tree of *atypical* crown shape and habit with proportions not representative of the species considering constraints and appears to have been adversely influenced in its development by environmental factors in situ such as *soil water* availability, prevailing wind, cultural practices such as lopping and competition for space and light; causing it to be *misshapen* or disfigured by disease or vandalism.

**Crown Form Codominant** Crowns of trees restricted for space and light on one or more sides and receiving light primarily from above e.g. constrained by another tree/s or a building.




Figure 8 Sections of crown.




**Crown Form Dominant** Crowns of trees generally not restricted for space and light receiving light from above and all sides.

**Crown Form Emergent** Crowns of trees restricted for space on most sides receiving most light from above until the *upper crown* grows to protrude above the canopy in a stand or forest environment. Such trees may be *crown form dominant* or transitional from *crown form intermediate* to *crown form forest* asserting both *apical dominance* and *axillary dominance* once free of constraints for space and light.

**Crown Form Forest** Crowns of trees restricted for space and light except from above forming tall trees with narrow spreading crowns with foliage restricted generally to the top of the tree. The trunk is usually erect, straight and continuous, tapering gradually, crown often excurrent, with first order branches becoming structural, supporting the live crown concentrated towards the top of the tree, and below this point other first order branches arising radially with each *inferior* and usually temporary, divergent and ranging from horizontal to ascending, often with internodes exaggerated due to competition for space and light in the *lower crown*.

**Crown Form Intermediate** Crowns of trees restricted for space on most sides with light primarily from above and on some sides only.

**Crown Form Suppressed** Crowns of trees generally not restricted for space but restricted for light by being *overtopped* by other trees and occupying an understorey position in the canopy and growing slowly.



## **Deadwood**

**Deadwood** Dead branches within a tree's crown and considered quantitatively as separate to *crown cover* and can be categorised as *Small Deadwood* and *Large Deadwood* according to diameter, length and subsequent *risk potential*. The amount of dead branches on a tree can be categorized as *Low Volume Deadwood*, *Medium Volume Deadwood* and *High Volume Deadwood*. See also *Dieback*.

**Deadwooding** Removing of dead branches by *pruning*. Such pruning may assist in the prevention of the spread of *decay* from *dieback* or for reasons of safety near an identifiable target.

**Small Deadwood** A dead branch up to 10mm diameter and usually <2 metres long, generally considered of low *risk potential*.

**Large Deadwood** A dead branch >10mm diameter and usually >2 metres long, generally considered of high *risk potential*.

**High Volume Deadwood** High Volume Deadwood Where >10 dead branches occur that may require *removal*.

**Medium Volume Deadwood** Where 5-10 dead branches occur that may require *removal*.

**Low Volume Deadwood** Where <5 dead branches occur that may require *removal*.

## **Dieback**

**Dieback** The death of some areas of the *crown*. Symptoms are leaf drop, bare twigs, dead branches and tree death, respectively. This can be caused by root damage, root disease, bacterial or fungal canker, severe bark damage, intensive grazing by insects, *abrupt changes* in growth conditions, drought, water-logging or over-maturity. Dieback often implies reduced *resistance*, *stress* or *decline* which may be temporary. Dieback can be categorized as *Low Volume Dieback*, *Medium Volume Dieback* and *High Volume Dieback*.

**High Volume Dieback** Where >50% of the *crown cover* has died.

**Medium Volume Dieback** Where 10-50% of the *crown cover* has died.

**Low Volume Dieback** Where <10% of the *crown cover* has died. See also *Dieback*, *High Volume Dieback* and *Medium Volume Dieback*.

## **Epicormic shoots**

**Epicormic Shoots** Juvenile shoots produced at branches or trunk from *epicormic strands* in some Eucalypts (Burrows 2002, pp. 111-131) or sprouts produced from dormant or latent buds concealed beneath the bark in some trees. Production can be triggered by fire, pruning, wounding, or root damage but may also be as a result of *stress* or *decline*. Epicormic shoots can be categorized as *Low Volume Epicormic Shoots*, *Medium Volume Epicormic Shoots* and *High Volume Epicormic Shoots*.

**High Volume Epicormic Shoots** Where >50% of the *crown cover* is comprised of live *epicormic shoots*.

**Medium Volume Epicormic Shoots** Where 10-50% of the *crown cover* is comprised of live *epicormic shoots*.

**Low Volume Epicormic Shoots** Where <10% of the *crown cover* is comprised of live *epicormic shoots*.

## **General Terms**

**Cavity** A usually shallow void often localized initiated by a *wound* and subsequent *decay* within the trunk, branches or roots, or beneath bark, and may be enclosed or have one or more opening.

**Decay** Process of degradation of wood by microorganisms (Australian Standard 2007, p. 6) and fungus.

**Hazard** The threat of danger to people or property from a tree or tree part resulting from changes in the physical condition, growing environment, or existing physical attributes of the tree, e.g. included bark, soil erosion, or thorns or poisonous parts, respectively.

**Included bark** 1. The bark on the inner side of the *branch union*, or is within a concave *crotch* that is unable to be lost from the tree and accumulates or is trapped by *acutely divergent* branches forming a *compression fork*. 2. Growth of bark at the interface of two or more branches on the inner side of a branch union or in the crotch where each branch forms a branch collar and the collars roll past one another without forming a graft where no one collar is able to subsume the other. Risk of failure is worsened in some taxa where branching is *acutely divergent* or *acutely convergent* and ascending or erect.

**Hollow** A large void initiated by a *wound* forming a *cavity* in the trunk, branches or roots and usually increased over time by *decay* or other contributing factors, e.g. fire, or fauna such as birds or insects e.g. ants or termites. A hollow can be categorized as an *Ascending Hollow* or a *Descending Hollow*.

**Risk** The random or potentially foreseeable possibility of an episode causing harm or damage.

**Significant** Important, weighty or more than ordinary.

**Significant Tree** A tree considered important, weighty or more than ordinary. Example: due to prominence of location, or *in situ*, or contribution as a component of the overall landscape for *amenity* or aesthetic qualities, or *curtilage* to structures, or importance due to uniqueness of taxa for species, subspecies, variety, *crown form*, or as an historical or cultural planting, or for age, or substantial dimensions, or habit, or as *remnant vegetation*, or habitat potential, or a rare or threatened species, or uncommon in cultivation, or of aboriginal cultural importance, or is a commemorative planting.

**Substantial** A tree with large dimensions or proportions in relation to its place in the landscape.

**Sustainable Retention Index Value (SRIV)** A visual tree assessment method to determine a qualitative and numerical rating for the viability of urban trees for development sites and management purposes, based on general tree and landscape assessment criteria using classes of *age*, *condition* and *vigour*. SRIV is for the professional manager of urban trees to consider the tree *in situ* with an assumed knowledge of the *taxon* and its growing environment. It is based on the physical attributes of the tree and its response to its environment considering its position in a matrix for age class, vigour class, condition class and its sustainable retention with regard to the safety of people or damage to property. This also factors the ability to retain the tree with remedial work or beneficial modifications to its growing environment or removal and replacement. SRIV is supplementary to the decision made by a tree management professional as to whether a tree is retained or removed (IACA - Institute of Australian Consulting Arboriculturists 2005).

**Visual Tree Assessment (VTA)** A visual inspection of a tree from the ground based on the principle that, when a tree exhibits apparently superfluous material in its shape, this represents repair structures to rectify *defects* or to reinforce weak areas in accordance with the *Axiom of Uniform Stress* (Mattheck & Breloer 1994, pp. 12-13, 145). Such assessments should only be undertaken by suitably competent practitioners.

## **Leaning Trees**

**Leaning** A tree where the *trunk* grows or moves away from upright. A lean may occur anywhere along the *trunk* influenced by a number of contributing factors e.g. genetically predetermined characteristics, competition for space or light, prevailing winds, aspect, slope, or other factors. A *leaning* tree may maintain a *static lean* or display an increasingly *progressive lean* over time and may be hazardous and prone to *failure* and *collapse*. The degrees of leaning can be categorized as *Slightly Leaning*, *Moderately Leaning*, *Severely Leaning* and *Critically Leaning*.

**Slightly Leaning** A leaning tree where the trunk is growing at an angle within 0°-15° from upright.

**Moderately Leaning** A leaning tree where the trunk is growing at an angle within 15°-30° from upright.

**Severely Leaning** A leaning tree where the trunk is growing at an angle within 30°-45° from upright.

**Critically Leaning** A leaning tree where the trunk is growing at an angle greater than >45° from upright.

**Progressively Leaning** A tree where the degree of *leaning* appears to be increasing over time.

**Static Leaning** A leaning tree whose lean appears to have stabilized over time.

## **Periods of Time**

**Periods of Time** The life span of a tree in the urban environment may often be reduced by the influences of encroachment and the dynamics of the environment and can be categorized as *Immediate*, *Short Term*, *Medium Term* and *Long Term*.

**Immediate** An *episode* or occurrence, likely to happen within a twenty-four (24) hour period, e.g. tree failure or collapse in full or part posing an imminent danger.

**Short Term** A period of time less than <1 – 15 years.

**Medium Term** A period of time 15 – 40 years.

**Long Term** A period of time greater than >40 years.



## Roots

**First Order Roots (FOR)** Initial woody roots arising from the *root crown* at the base of the *trunk*, or as an *adventitious root mass* for structural support and *stability*. Woody roots may be buttressed and divided as a marked gradation, gradually tapering and continuous or tapering rapidly at a short distance from the root crown. Depending on soil type these roots may descend initially and not be evident at the root crown, or become buried by changes in soil levels. Trees may develop 4-11 (Perry 1982, pp. 197-221), or more first order roots which may radiate from the trunk with a relatively even distribution, or be prominent on a particular aspect, dependent upon physical characteristics e.g. leaning trunk, *asymmetrical crown*; and constraints within the growing *environment* from topography e.g. slope, soil depth, rocky outcrops, exposure to predominant wind, soil moisture, depth of *water table* etc.

**Orders of Roots** The marked divisions between woody roots, commencing at the initial division from the base of the trunk, at the *root crown* where successive branching is generally characterised by a gradual reduction in root diameters and each gradation from the trunk and can be categorized numerically, e.g. *first order roots*, *second order roots*, *third order roots* etc. Roots may not always be evident at the *root crown* and this may be dependent on species, age class and the growing environment. Palms at maturity may form an *adventitious root mass*.

**Root Plate** The entire root system of a tree generally occupying the top 300-600mm of soil including roots at or above ground and may extend laterally for distances exceeding twice the height of the tree (Perry 1982, pp. 197-221). Development and extent is dependent on water availability, soil type, *soil depth* and the physical characteristics of the surrounding landscape.

**Root Crown** Roots arising at the base of a trunk.

**Zone of Rapid Taper** The area in the *root plate* where the diameter of *structural roots* reduces substantially over a short distance from the *trunk*. Considered to be the minimum radial distance to provide structural support and *root plate* stability. See also *Structural Root Zone (SRZ)*.

**Structural Roots** Roots supporting the infrastructure of the *root plate* providing strength and *stability* to the tree. Such roots may taper rapidly at short distances from the *root crown* or become large and woody as with gymnosperms and dicotyledonous angiosperms and are usually 1<sup>st</sup> and 2<sup>nd</sup> order roots, or form an *adventitious root mass* in monocotyledonous angiosperms (palms). Such roots may be crossed and grafted and are usually contained within the area of *crown projection* or extend just beyond the *dripline*.




Figure 22 Orders of Roots.

## Symmetry

**Symmetry** Balance within a *crown*, or *root plate*, above or below the *axis* of the trunk of branch and foliage, and root distribution respectively and can be categorized as *Asymmetrical* and *Symmetrical*.

**Asymmetrical** Imbalance within a crown, where there is an uneven distribution of branches and the *foliage crown* or *root plate* around the vertical axis of the trunk. This may be due to *Crown Form Codominant* or *Crown Form Suppressed* as a result of natural restrictions e.g. from buildings, or from competition for space and light with other trees, or from exposure to wind, or artificially caused by pruning for clearance of roads, buildings or power lines. An example of an expression of this may be, crown asymmetrical, bias to west.

**Symmetrical** Balance within a crown, where there is an even distribution of branches and the *foliage crown* around the vertical axis of the trunk. This usually applies to trees of *Crown Form Dominant* or *Crown Form Forest*. An example of an expression of this may be crown symmetrical.




Figure 27 Symmetry within crown



## Trunk

**Trunk** A single stem extending from the *root crown* to support or elevate the *crown*, terminating where it divides into separate *stems* forming *first order branches*. A trunk may be evident at or near ground or be absent in *acaulescent* trees of *deliquescent* habit, or may be continuous in trees of *excurrent* habit. The trunk of any *caulescent* tree can be divided vertically into three (3) sections and can be categorized as *Lower Trunk*, *Mid Trunk* and *Upper Trunk*. For a *leaning* tree these may be divided evenly into sections of one third along the trunk.

**Acaulescent** A *trunkless* tree or tree growth forming a very short *trunk*. See also *Caulescent*. (See Fig. 21)

**Caulescent** Tree grows to form a *trunk*. See also *Acaulescent*. (See Fig. 21)

**Lower trunk** Lowest, or *proximal* section of a trunk when divided into one-third ( $\frac{1}{3}$ ) increments along its *axis*. See also *Trunk*, *Mid trunk* and *Upper trunk*.

**Mid trunk** A middle section of a trunk when divided into one-third ( $\frac{1}{3}$ ) increments along its *axis*. See also *Trunk*, *Lower trunk* and *Upper trunk*.

**Upper trunk** Highest, or *distal* section of a trunk when divided into one-third ( $\frac{1}{3}$ ) increments along its *axis*. See also *Trunk*, *Lower trunk* and *Mid trunk*.




Figure 28 Trunk sections.

**Diameter at Breast Height (DBH)** Measurement of trunk width calculated at a given distance above ground from the base of the tree often measured at 1.4 m. The trunk of a tree is usually not a circle when viewed in cross section, due to the presence of *reaction wood* or *adaptive wood*, therefore an average diameter is determined with a *diameter tape* or by recording the trunk along its narrowest and widest axes, adding the two dimensions together and dividing them by 2 to record an average and allowing the orientation of the longest axis of the trunk to also be recorded. Where a tree is growing on a lean the distance along the top of the trunk is measured to 1.4m and the diameter then recorded from that point perpendicular to the edge of the trunk. Where a *leaning* trunk is *crooked* a vertical distance of 1.4m is measured from the ground. Where a tree branches from a trunk that is less than 1.4m above ground, the trunk diameter is recorded perpendicular to the length of the *trunk* from the point immediately below the base of the flange of the *branch collar* extending the furthest down the trunk, and the distance of this point above ground recorded as *trunk length*. Where a tree is located on sloping ground the DBH should be measured at half way along the side of the tree to average out the angle of slope. Where a tree is *acaulescent* or *trunkless* branching at or near ground an average diameter is determined by recording the radial extent of the trunk at or near ground and noting where the measurement was recorded e.g. at ground.

## Vigour

**Vigour** Ability of a tree to sustain its life processes. This is independent of the *condition* of a tree but may impact upon it. Vigour can appear to alter rapidly with change of seasons (seasonality) e.g. *dormant*, deciduous or semi-deciduous trees. Vigour can be categorized as *Normal Vigour*, *High Vigour*, *Low Vigour* and *Dormant Tree Vigour*.

**Normal Vigour** Ability of a tree to maintain and sustain its life processes. This may be evident by the *typical* growth of leaves, *crown cover* and *crown density*, branches, roots and trunk and *resistance* to *predation*. This is independent of the *condition* of a tree but may impact upon it, and especially the ability of a tree to sustain itself against predation.

**High Vigour** *Accelerated growth* of a tree due to incidental or deliberate artificial changes to its growing *environment* that are seemingly beneficial, but may result in *premature aging* or failure if the favourable conditions cease, or promote *prolonged senescence* if the favourable conditions remain, e.g. water from a leaking pipe; water and nutrients from a leaking or disrupted sewer pipe; nutrients from animal waste, a tree growing next to a chicken coop, or a stock feed lot, or a regularly used stockyard; a tree subject to a stringent watering and fertilising program; or some trees may achieve an extended lifespan from continuous *pollarding* practices over the life of the tree.

**Low Vigour** Reduced ability of a tree to sustain its life processes. This may be evident by the *atypical* growth of leaves, reduced *crown cover* and reduced *crown density*, branches, roots and trunk, and a deterioration of their functions with reduced *resistance* to *predation*. This is independent of the *condition* of a tree but may impact upon it, and especially the ability of a tree to sustain itself against predation.



# Appendices E & F

## Appendix E – Survey of Subject Tree/s

## Appendix F – Tree Protection Plan

Trees the subject of this report are marked on the plans in the following appendices and are numbered as listed below.


Redgum Tree / Stand No.	Genus and species	Common name	Recommendation
1	<i>Sannantha bidwillii</i> (syn. <i>Baeckea virgata</i> )	Twiggy Heath Myrtle	Retain and protect
2	<i>Callistemon citrinus</i> 'Kings Park Special'	Kings Park Bottlebrush	Retain and protect – Street Tree
3	<i>Tibouchina lepidota</i> 'Alstonville'	Lasiandra	Remove and replace
4	<i>Juniperus glabra</i>	Smooth Cypress	Remove and replace
5	<i>Thuja orientalis</i>	Bookleaf Conifer	Remove and replace
6	<i>Bauhinia purpurea</i>	Butterfly Tree	Remove and replace
7	<i>Camellia sasanqua</i>	Camellia	Remove and replace
8	<i>Syzygium smithii</i>	Lilly Pilly	Remove and replace
9	<i>Juniperus glabra</i>	Smooth Cypress	Retain and protect
10	<i>Grevillea robusta</i>	Silky Oak	Remove and replace
11	<i>Archontophoenix cunninghamiana</i>	Bangalow Palm	Remove and replace
12	<i>Pittosporum undulatum</i>	Native Daphne	Retain and protect
13/2	<i>Dypsis decaryi</i>	Triangle Palm	Remove and replace

### Plan Details

1. Detail Survey of Lot 13 & 14 in DP 16517 & Lot 5 & 6 in DP 31350, Ref: 3071-15 DET, Sheet 1 & 2 of 2, Date 12.08.2015, Scale 1:100 by C & A Surveyors NSW Pty Ltd, P.O. Box 5203, Greystanes NSW 2145. T: 02 9638 4136 E: [info@candasurveyors.com.au](mailto:info@candasurveyors.com.au)
2. Site & Roof Plan, Job No. 2281, Drawing No. DA02, Issue A, Date 07.03.16 Scale 1:200 by Architex, Level 3 7K Parkes St, Parramatta, NSW, 2150. T 02 9633 5888 E: [email@architex.com.au](mailto:email@architex.com.au)

## Appendix E - Site Plan A – Survey of Subject Trees

Plan has been reproduced from electronic transmission and is no longer to original scale.



### Legend

● Trees numbered in **orange** are recommended for **retention**.


● Trees numbered in **blue** are recommended for **removal**.

Note: trees indicated, unnumbered are either shrubs, or trees of species, of dimensions, or condition class not protected by the Tree Preservation Order or missing at time of inspection.

## Appendix F - Site Plan B

### Survey of Trees to be Retained and Tree Protection Plan

Plan has been reproduced from electronic transmission and is no longer to original scale.  
All Tree Protection Zones are to be measured on site.



#### Legend

- Tree Protection Zone (TPZ), fencing with setbacks as indicated, or other protection measures or works as indicated.
- ..... Tree Protection Zone, area of special protection measures or works outside of fenced area.
- Tree numbers – trees to be retained only.  
Subject trees represented by the approximate location of the trunk.

Indicative location of Tree Protection fencing which is to be measured on site and positioned along the Tree Protection Zone, excavation zone or proposed building footprint and to remain installed for the duration of the development. Installation of boundary fences within rootzone to be of pier and beam construction. Red dotted Tree Protection around trees relates to relocation of fencing when construction is to be undertaken within these areas. All works to be carried out within the Tree Protection area after works commences is to be undertaken in consultation with site arboriculturist.

# **DICKENS SOLUTIONS**

## **WASTE MANAGEMENT PLAN**

### **FOR ARCHITEX (STRONG DEVELOPMENTS PTY LTD)**

### **PROPOSED RESIDENTIAL FLAT BUILDING @ 47-49 SOUTH ST & 14-16 BURBANG CR, RYDALMERE MARCH 2016**

#### **DISCLOSURE STATEMENT**

The information contained in this document has been produced by Dickens Solutions Pty Ltd and is solely for the use of (The Client) for the purpose for which it has been prepared. In preparing this document, Dickens Solutions Pty Ltd undertakes no duty to, nor accepts any responsibility to, any third party that may rely upon this document.

This document and the information contained in the document shall not be copied or reproduced without the consent of Dickens Solutions Pty Ltd, and, or the Client.

**Dickens Solutions Pty Ltd**  
(ABN 41 603 040 446)  
1214 Botany Road, Botany NSW 2019  
Telephone (Mb) 0400 388 996

Website: [www.dickenssolutions.com.au](http://www.dickenssolutions.com.au) E-mail: [garry@dickenssolutions.com.au](mailto:garry@dickenssolutions.com.au)



## **TABLE OF CONTENTS**

<b>PART</b>	<b>SUBJECT</b>	<b>PAGE</b>
<b>PART 1 – OVERVIEW &amp; PROPOSAL</b>		
1.1	Executive Summary	3
1.2	Introduction	4
1.3	Description of Property	4
1.4	Applicants Details	5
1.5	Proposal	5
<b>PART 2 – DEMOLITION</b>		
2.1	Demolition – Generally	7
2.2	Demolition – Recycling, Reuse, and Disposal Details	7
2.3	Demolition – On Site Storage of Materials	11
2.4	Demolition – Excavated Material	11
<b>PART 3 – CONSTRUCTION</b>		
3.1	Construction – Generally	12
3.2	Construction – Recycling, Reuse and Disposal Details	12
3.3	Construction – On Site Storage of Materials	16
3.4	Construction – Excavated Material	16
<b>PART 4 – ON GOING USE</b>		
4.1	Objectives	17
4.2	Assumptions	17
4.3	Waste Handling & Management	18
4.4	Waste & Recycling – Service Requirements	18
4.5	Waste & Recycling – Service Arrangements	18
4.6	Provision of Waste & Recycling Services	19
4.7	Green Waste	22
4.8	Bulk Waste	23
4.9	On Going Operation, Use & Management of Facilities	23
<b>PART 5 – SUMMARY</b>		
5.1	Summary	24

# **PART 1 – OVERVIEW AND PROPOSAL**

## **1.1 EXECUTIVE SUMMARY**

This Waste Management Plan (WMP) is an operational plan and describes in detail the manner in which all waste and other materials resulting from the demolition, construction and on-going use of the development are to be dealt with.

The aims and objectives of this WMP are to: -

- a) Satisfy all State and Local Government regulatory controls regarding waste management and minimisation practices;
- b) Promote the use of recyclable materials in the excavation, demolition, construction and on-going operation of the building;
- c) Maximise waste reduction, material separation, and resource recovery in all stages of the development;
- d) Ensure the design of waste and recycling storage facilities are of an adequate size, appropriate for the intended use of the building, hygienic with safe and manoeuvrable access; and,
- e) Ensure that the provision of waste and recycling services to the completed buildings are carried out in an efficient manner, which will not impact negatively on the health, safety and convenience of all stakeholders.

This WMP is prepared in accordance with: -

- Parramatta Local Environment Plan 2011;
- Parramatta DCP 2011 – Chapter 3.37 – Waste Management;
- The 'Better Practice Guide for Waste Management in Multi Unit Dwellings';
- Waste industry best practice standards for the storage and collection of waste within Multi Unit Dwellings and Mixed Use Developments; and,
- The objective of ensuring that all waste management facilities and collection services will provide an outcome that will be effective and efficient, as well as promote the principles of health, safety and convenience.

This Waste Management Plan has been prepared for a Development Application to be submitted to Parramatta City Council, for the construction of two (2) three (3) storey Residential Flat Buildings containing a total of 32 one, two and three bedroom units, at 47-49 South Street and 14-16 Burbang Crescent, Rydalmere.

One (1) basement level will be constructed under the buildings. The Basement will be common to, and link both buildings, and will have provisions for car parking, servicing and ancillary facilities.

This WMP is dated 24 March 2016.

## **1.2 INTRODUCTION**

This Waste Management Plan (WMP) has been specifically designed for the development described below: -

<b>DESCRIPTION</b>	<b>Two (2) x three (3) Storey Residential Flat Buildings</b>
<b>NUMBER OF UNITS</b>	<b>32 Sole Occupancy Residential Units consisting of: -</b> <ul style="list-style-type: none"><li>- 4 x 1 bedroom units;</li><li>- 24 x 2 bedroom units;</li><li>- 4 x 3 bedroom units; and,</li></ul> <b>One (1) basement level for the provision of car parking, service and ancillary facilities</b>
<b>LOCATION</b>	<b>47-49 South St &amp; 14-16 Burbang Cr, Rydalmere</b>
<b>LGA</b>	<b>Parramatta City Council</b>

## **1.3 DESCRIPTION OF PROPERTY**

<b>PROPERTY DESCRIPTION</b>	<b>The development is to be constructed over four (4) existing lots: -</b> <b>No 47 South Street – Lot 13, DP 16517;</b> <b>No 49 South Street – Lot 14, DP 16517;</b> <b>No 14 Burbang Crescent – Lot 5, DP 31350; and,</b> <b>No 16 Burbang Crescent – Lot 6, DP 31350.</b>
<b>STREET ADDRESS</b>	<b>47-49 South Street and 14-16 Burbang Crescent, Rydalmere</b>
<b>DIMENSIONS</b>	<b>- South St (South) Boundary – 29.6 metres;</b> <b>- Burbang Cr (North) Boundary – 31.1 metres;</b> <b>- Side (West) Boundary – 88.8 metres; and,</b> <b>- Side (East) Boundary – 86.4 metres.</b>
<b>AREA</b>	<b>2,784.9 square metres</b>
<b>ZONING</b>	<b>Zone R4 – High Density Residential</b>
<b>PLANNING INSTRUMENTS</b>	<b>Parramatta LEP 2011</b> <b>Parramatta Development Control Plan 2011</b>

The site occupies four (4) individual Torrens Title allotments and is located between two (2) street frontages at 47-49 South Street and 14-16 Burbang Crescent, Rydalmere. Park Road is the nearest cross street to the west and John Street to the east. The site is a short distance from two major arterial roads – Victoria Road, approximately 1km to the north, and Silverwater Road 2km's to the east.

Three existing dwellings are currently situated at No's 14 and 16 Burbang Crescent and 47 South Street. No 49 South Street is a vacant block currently for used for car parking, presumably in association with some of the industrial land uses located nearby.

The immediate surrounding development to the north of South Street, primarily consists of low density residential housing, with some pockets of medium density (villa, town houses) in its vicinity. South of South Street is a light industrial area consisting of a range of small to medium size industrial buildings.



## **1.4 APPLICANTS DETAILS**

<b>APPLICANT</b>	<b>Architex (Strong Developments Pty Ltd)</b>
<b>ADDRESS</b>	<b>Level 3, 7K Parkes Street, Parramatta. NSW. 2150.</b>
<b>TELEPHONE</b>	<b>02 9633 5888</b>
<b>E-MAIL</b>	<a href="mailto:email@architex.com.au"><b>email@architex.com.au</b></a>

## **1.5 PROPOSAL**

The proposal involves the construction of two (2) three (3) storey residential flat buildings containing a total of 32 sole occupancy units comprising of: -

- 4 x 1 bedroom units;
- 24 x 2 bedroom units; and,
- 4 x 3 bedroom units.

One basement level, linking both buildings will be constructed under them, providing facilities for: -

- Resident, visitor, and adaptable car parking spaces;
- Two (2) separate Waste storage facilities;
- Storage space for the units; and,
- Areas for lift wells, bicycle racks, and other facilities.

Egress from the basement will be onto South Street on the southern side of the development only. There will be no vehicular access from the development to Burbang Crescent.

Current structures on the site are: -

- No 47 South Street – a one and two storey brick and tile dwelling with two detached metal sheds, and a number of trees and miscellaneous vegetation;
- No 49 South Street – vacant land;
- No 14 Burbang Crescent – a two storey timber frame fibro dwelling with tiled roof, three detached fibro and metal outbuildings, an in-ground swimming pool, and a number of trees and miscellaneous vegetation; and,
- No 16 Burbang Crescent – a single storey timber frame weatherboard dwelling with tiled roof, two detached fibro and metal outbuildings, large landscaped garden area and concreted pathways with an awning over.

It is proposed to demolish all structures on all sites.

The project consists of: -

- a) The demolition of all existing buildings;
- b) The removal of all demolished materials in accordance with this WMP;
- c) The excavation of the site to construct one (1) basement level, linking both buildings, for car parking and other services;
- d) The construction of two (2) three (3) storey residential flat buildings;
- e) The provision of landscaping, driveways, concrete pathways and other elements associated with the development; and,
- f) The on-going use of the building.

Upon completion, at ground level and above, the development will comprise of two (2) separate and distinct three (3) storey structures.

For the purposes of this Waste Management Plan, each building will be dealt with separately, and will be referred to as: -

- Building A – South Street Building (17 units); and,
- Building B – Burbang Crescent Building (15 units).

Council has insisted that the provision of all waste and recycling services to the development, shall be take place in the following manner: -

- Building A – South Street Building – collections to take place from the South Street kerbside; and,
- Building B – Burbang Crescent Building – collections to take place from the Burbang Crescent kerbside.

## **PART 2 – DEMOLITION**

### **2.1 DEMOLITION**

#### **2.1.1 General Requirements**

It is recognised that Sydney has an ever increasing waste problem, and this practice is not sustainable. In alignment with current NSW waste management legislation, this WMP aims, where possible, to promote waste avoidance, reuse and the recycling of material, particularly during the course of demolition and construction works.

Section 2.2 on Pages 8, 9, 10 and 11 of this WMP describes the manner in which waste is to be managed during the course of the demolition of the existing structures.

The processes outlined in Section 2.2 are to be read in conjunction with and comply with the Development Consent issued in respect of the proposal. It will be the developer's overall responsibility to ensure compliance in this regard.

All material moved offsite shall be transported in accordance with the requirements of the Protection of the Environment Operations Act (1997).

Approved receptacles of an appropriate size will be located on site for the collection of food scraps, beverage containers, and other waste generated on site by workers.

#### **2.1.2 Management of Hazardous Materials**

Generation, storage, treatment and the disposal of hazardous waste (including asbestos) will be conducted in accordance with relevant waste legislation administered by the NSW EPA and any applicable WH&S legislation administered by Work Cover NSW.

### **2.2 DEMOLITION – RECYCLING, REUSE & DISPOSAL DETAILS**

The following details prescribe the manner in which all material involved in the demolition of the building will be dealt with, and includes: -

- a) An estimate of the types and volumes of waste and recyclables to be generated;
- b) A site plan showing sorting and storage areas for demolition waste and vehicle access to these areas (see Section 2.3 of this Plan);
- c) How excavation and demolition waste materials will be reused, and, or recycled and where residual wastes will be disposed (see below); and,
- d) The total percentage of demolition waste that will be reused or recycled.

It is noted that the quantities of materials detailed in this section (Section 2.2) are estimates only, based on current industry standards and quantity analysis, and may vary due to the prevailing nature of site constraints, weather conditions, and any other unforeseeable activities associated with the demolition works, which are beyond the control of the developer, including but not being limited to theft, accidents, and, or, other acts of misadventure.

Notwithstanding any of the above, the developer will provide Council with all details in relation to any major variations in this regard.



### 1. Excavated Materials & Overburden

Volume / Weight	2,700 cubic metres / 4,590 Tonnes
On Site Reuse	Yes. Keep and reuse topsoil for landscaping. Shore on site. Use some for support of retaining walls (Excavated Materials are only to be used if the material is not contaminated or has been remediated in accordance with any requirements specified by any Environmental Consultancy engaged to carry out any contamination assessment of excavated material).
Percentage Reused or Recycled	To be determined (see above comments)
Off Site Destination	To an approved Agency – excavated materials may need to be assessed to determine the quality of the material to ensure that all excavated material will be acceptable to the designated receival authority.

### 2. Green Waste

Volume / Weight	30 cubic metres / 4.5 Tonnes
On Site Reuse	To be separated. Chipped and stored on site for re-use in landscaping.
Percentage Reused or Recycled	90%
Off Site Destination	Bingo Industries, 3-5 Duck Street, Auburn (Tel 1300 424 646) or, Australian Native Landscapes, Lot 22, Martin Road, Badgerys Creek (Tel 02 4774 8484)

### 3. Bricks

Volume / Weight	18 cubic metres / 18 Tonnes
On Site Reuse	Clean and remove lime mortar from bricks. Re-use in new footings. Broken bricks for internal walls. Crush and reuse as drainage backfill. Crushed and used as aggregate.
Percentage Reused or Recycled	75% - 90%
Off Site Destination	Brandown, Lot 9 Elizabeth Drive, Kemps Creek (Tel 02 9826 1256) or, Jacks Gully Waste Management Centre, Richardson Road, Narellan (Tel 1300 651 116) or, Bingo Industries, 3-5 Duck Street, Auburn (Tel 1300 424 646)

#### **4. Concrete**

<b>Volume / Weight</b>	100 cubic metres / 240 Tonnes
<b>On Site Reuse</b>	Existing driveway to be retained during construction. Crushed and used as aggregate, drainage backfill.
<b>Percentage Reused or Recycled</b>	60% - 75%
<b>Off Site Destination</b>	Brandown, Lot 9 Elizabeth Drive, Kemps Creek (Tel 02 9826 1256) or, Auburn Waste & Recycling Centre, Old Hill Link, Homebush Bay (Tel 1300 651 116) or, Bingo Industries, 3-5 Duck Street, Auburn (Tel 1300 424 646)

#### **5. Timber**

<b>Volume / Weight</b>	45 cubic metres / 18 Tonnes
<b>On Site Reuse</b>	Re-use for formwork and studwork, landscaping, shoring.
<b>Percentage Reused or Recycled</b>	65% - 90%
<b>Off Site Destination</b>	Artistic Popular Furniture, 10 Raglan Road, Auburn (Tel 02 96443054) or, Hallinan's Recycling Centre, 37 Lee Holm Road, St.Marys (Tel 02 9833 0883)

#### **6. Plasterboard & Fibro**

<b>Volume / Weight</b>	30 cubic metres / 10.5 Tonnes
<b>On Site Reuse</b>	Break up and use in landscaping. Any material containing asbestos will be dealt with separately
<b>Percentage Reused or Recycled</b>	To be determined (dependent on asbestos content)
<b>Off Site Destination</b>	Ecocycle, 155 Newtown Road, Wetherill Park (Tel 02 0757 2999) or, Jacks Gully Waste Management Centre, Richardson Road, Narellan (Tel 1300 651 116)
<b>Off Site Destination (Asbestos)</b>	Jacks Gully Waste Management Centre, Richardson Road, Narellan (Tel 1300 651 116) or, Enviroguard, Cnr Mamre and Erskine Roads, Erskine Park (Tel 02 9834 3411).

### **7. Metals / Steel / Guttering & Downpipes**

<b>Volume / Weight</b>	25 cubic metres / 6.25 Tonnes
<b>On Site Reuse</b>	No
<b>Percentage Reused or Recycle</b>	60% - 90%
<b>Off Site Destination</b>	Boral Recycling, 3 Thackeray Street, Camelia (Tel 9529 4424) or, Bingo Industries, 3-5 Duck Street, Auburn (Tel 1300 424 646) or, Jacobson Metaland, 62-70 Silverwater Road, Silverwater (Tel 02 9748 2487)

### **8. Roof Tiles / Tiles**

<b>Volume / Weight</b>	15 cubic metres / 11.25 Tonnes
<b>On Site Reuse</b>	Broken up and used as fill, aggregate, driveways.
<b>Percentage Reused or Recycle</b>	80% - 90%
<b>Off Site Destination</b>	Obsolete Tiles, 3 South Street, Rydalmere. (Tel 02 9684 6333) or, Hallinan's Recycling Centre, 37 Lee Holm Road, St.Marys (Tel 02 9833 0883) or, Bingo Industries, 3-5 Duck Street, Auburn (Tel 1300 424 646)

### **9. Fixture & Fittings (Doors Fittings, Other Fixtures, etc)**

<b>Volume</b>	15 cubic metres / 4.8 Tonnes
<b>On Site Reuse</b>	Broken up and used as fill.
<b>Percentage Reused or Recycle</b>	80% - 90%
<b>Off Site Destination</b>	Recycle Works, 45 Parramatta Road, Annandale (Tel 02 9517 2711) or, Bingo Industries, 3-5 Duck Street, Auburn (Tel 1300 424 646)



#### **10. Glass, Electrical & Light Fittings, PC Items, Ceramics, etc**

Volume / Weight	15 cubic metres / 2 Tonnes
On Site Reuse	No
Percentage Reused or Recycle	To be determined (dependent upon nature of material)
Off Site Destination	To an approved agency, or agencies.

The developer will keep a written record of all documentation associated with the transportation, disposal and processing of all materials associated with the demolition of all structures on site.

Should any of the facilities nominated above, for any reason be unable to accommodate the receipt of these materials, the developer will be responsible for making alternative arrangements that will ensure all demolished materials removed from the site, are disposed of, or processed, appropriately.

#### **2.3 Demolition – On Site Storage of Materials**

During the demolition stage of the project, an area will be set aside on the site as a compound for the on-site storage of materials prior to their removal from the site. This compound will provide for: -

- Material sorting;
- Segregation of materials that may be hazardous and which will be required to be disposed of;
- Recovery equipment, such as concrete crushers, chippers, and skip bins;
- Material storage; and,
- Access for transport equipment.

Appropriate vehicular access will be provided on and off site, and to the compound, to enable the efficient removal of reusable, recyclable, and waste materials.

Prior to the commencement of demolition works, the developer will provide Council with a 'Site Plan for the On Site Storage of Materials at Demolition'. This plan will show in detail the location of each area within the compound, set aside for the segregated storage of all materials involved in the demolition of all buildings on the site.

#### **2.4 Demolition – Excavated Material**

All excavated material removed from the site, as a result of the demolition of all buildings, must be classified in accordance with the Department of Environment, Climate Change and Water NSW Waste Classification Guidelines prior to their removal, transportation and disposal to an approved waste management facility.

All relevant details must be reported to the PCA.

## **PART 3 – CONSTRUCTION**

### **3.1 CONSTRUCTION – GENERALLY**

Upon completion of all demolition works, construction of the building will commence with the excavation of the site for the basement levels of the building. All materials sourced from these activities will be disposed of in accordance with the information provided in Section 3.2 on pages 12, 13, 14, 15, and 16 of this WMP.

Additionally, all materials used in the construction of the building that are not required to be incorporated into it, shall be recycled, reused or disposed of in accordance with these provisions, and the requirements of the Protection of the Environment Operations Act (1997). It will be the developer's overall responsibility to ensure compliance in this regard.

Mobile Bins of an appropriate size will be located on site for the collection of food scraps, beverage containers, and other waste generated on site by workers.

### **3.2 CONSTRUCTION – RECYCLING, REUSE & DISPOSAL DETAILS**

The following details prescribe the manner in which all material surplus to the construction of the building will be dealt with.

The following details prescribe the manner in which all materials surplus to the construction of the building will be dealt with, and includes: -

- a) An estimate of the types and volumes of waste and recyclables to be generated;
- b) A site plan showing sorting and storage areas for construction waste and vehicle access to these areas (see Section 3.3 of this Plan);
- c) How excavated and other materials surplus to construction will be reused or recycled and where residual wastes will be disposed (see below); and,
- d) The total percentage of demolition waste that will be reused or recycled.

#### **1. Excavated Materials**

Volume / Weight	7,500 cubic metres / 12,750 Tonnes
On Site Reuse	Yes. Keep and reuse topsoil for landscaping. Shore on site. Use some for support of retaining walls (Excavated Materials are only to be used if the material is not contaminated or has been remediated in accordance with any requirements specified by any Environmental Consultancy engaged to carry out any contamination assessment of excavated material).
Percentage Reused or Recycled	To be determined (see above comments)
Off Site Destination	To an approved Agency – excavated materials may need to be assessed to determine the quality of the material to ensure that all excavated material will be acceptable to the designated receival authority.

## **2. Bricks**

<b>Volume / Weight</b>	<b>3 cubic metres / 3 Tonnes</b>
<b>On Site Reuse</b>	Clean and remove lime mortar from bricks. Re-use in new footings. Broken bricks for internal walls. Crush and reuse as drainage backfill. Crushed and used as aggregate.
<b>Percentage Reused or Recycle</b>	75% - 90%
<b>Off Site Destination</b>	Brandown, Lot 9 Elizabeth Drive, Kemps Creek (Tel 02 9826 1256) or, Bingo Industries, 3-5 Duck Street, Auburn (Tel 1300 424 646) or, Jacks Gully Waste Management Centre, Richardson Road, Narellan (Tel 1300 651 116)

## **3. Concrete**

<b>Volume / Weight</b>	<b>5 cubic metres / 12 Tonnes</b>
<b>On Site Reuse</b>	Existing driveway to be retained during construction. Crushed and used as aggregate, drainage backfill.
<b>Percentage Reused or Recycled</b>	60% - 75%
<b>Off Site Destination</b>	Brandown, Lot 9 Elizabeth Drive, Kemps Creek (Tel 02 9826 1256) or, Auburn Waste & Recycling Centre, Old Hill Link, Homebush Bay (Tel 1300 651 116) or, Bingo Industries, 3-5 Duck Street, Auburn (Tel 1300 424 646)

## **4. Timber**

<b>Volume / Weight</b>	<b>5 cubic metres / 7 Tonnes</b>
<b>On Site Reuse</b>	Re-use for formwork and studwork, and for landscaping
<b>Percentage Reused or Recycled</b>	65% - 90%
<b>Off Site Destination</b>	Artistic Popular Furniture, 10 Raglan Road, Auburn (Tel 02 96443054) or, Bingo Industries, 3-5 Duck Street, Auburn (Tel 1300 424 646)



### 5. Plasterboard & Fibro

Volume / Weight	12 cubic metres / 4 Tonnes
On Site Reuse	Break up and use in landscaping. Any material containing asbestos will be dealt with separately
Percentage Reused or Recycled	To be determined – depended on quantities of asbestos
Off Site Destination	Ecocycle, 155 Newtown Road, Wetherill Park (Tel 02 0757 2999) or, Jacks Gully Waste Management Centre, Richardson Road, Narellan (Tel 1300 651 116)
Off Site Destination (Asbestos)	Jacks Gully Waste Management Centre, Richardson Road, Narellan (Tel 1300 651 116) or, Enviroguard, Cnr Mamre and Erskine Roads, Erskine Park (Tel 02 9834 3411).

### 6. Metals / Steel / Guttering & Downpipes

Volume / Weight	7.5 cubic metres / 1.87 Tonnes
On Site Reuse	No
Percentage Reused or Recycled	60 – 90%
Off Site Destination	Sydney Wide Scrap Metal, 4/18 Alfred Street, Chipping Norton (Tel 9738 9771) or, Boral Recycling, 3 Thackeray Street, Camelia (Tel 9529 4424) or, Hallinan's Recycling Centre, 37 Lee Holm Road, St.Marys (Tel 02 9833 0883) or, Jacobson Metaland, 62-70 Silverwater Road, Silverwater (Tel 02 9748 2487)

### 7. Roof Tiles / Tiles

Volume / Weight	2 cubic metres / 1.5 Tonnes
On Site Reuse	Broken up and used as fill.
Percentage Reused or Recycled	80% - 90%
Off Site Destination	Obsolete Tiles, 3 South Street, Rydalmere. (Tel 02 9684 6333) or, Bingo Industries, 3-5 Duck Street, Auburn (Tel 1300 424 646)

**8. Plastics**

Volume / Weight	6 cubic metres / 1 Tonne
On Site Reuse	Nil
Percentage Reused or Recycled	80% - 95%
Off Site Destination	Recycle Works, 45 Parramatta Road, Annandale (Tel 02 9517 2711)

**9. Glass, Electrical & Light Fittings, PC items**

Volume / Weight	6 cubic metres / 1 Tonne
On Site Reuse	No
Percentage Reused or Recycled	70% - 90%
Off Site Destination	To an approved agency, or agencies.

**10. Fixture & Fittings (Doors Fittings, Other Fixtures, etc)**

Volume	5 cubic metres / 1.6 Tonnes
On Site Reuse	Broken up and used as fill.
Percentage Reused or Recycle	80% - 90%
Off Site Destination	Recycle Works, 45 Parramatta Road, Annandale (Tel 02 9517 2711) Bingo Industries, 3-5 Duck Street, Auburn (Tel 1300 424 646)

**11. Pallets**

Volume / Weight	6 cubic metres / 2 Tonne
On Site Reuse	No
Percentage Reused or Recycle	90% - 100%
Off Site Destination	Returned to supplier / to an approved agency, or agencies, for reuse and resale.

It is noted that the quantities of materials detailed in this section (Section 3.2) are estimates only, based on current industry standards and quantity analysis, and may vary due to the prevailing nature of construction constraints, weather conditions, and any other unforeseeable activities associated with the construction of the buildings, which are beyond the control of the developer, including but not being limited to theft, accidents, and other acts of misadventure.

Notwithstanding any of the above, the developer will provide Council with all details in relation to any major variations in this regard.

The developer will keep a record of all documentation associated with the transportation, disposal and processing of all materials surplus to the construction of the building.

Should any of the facilities nominated above, for any reason be unable to accommodate the receipt of these materials, the developer will be responsible for making alternative arrangements that will ensure all materials excess to construction that are removed from the site, are disposed of, or processed, appropriately.

Additionally, during the construction of the building, every effort will be made to reduce and minimise the amount of building materials excess to it.

### **3.3 Construction – On Site Storage of Materials**

During the construction of the buildings, an area will be set aside on the site as a compound for the on-site storage of materials prior to their removal from the site. This compound will provide for: -

- Material sorting;
- Segregation of materials that may be hazardous and which will be required to be disposed of;
- Recovery equipment, such as concrete crushers, chippers, and skip bins;
- Material storage; and,
- Access for transport equipment.

Appropriate vehicular access will be provided on and off site, and to the compound, to enable the efficient removal of reusable, recyclables, and waste materials.

Prior to the commencement of construction works, the developer will provide Council with a 'Site Plan for the On Site Storage of Materials at Construction'. This plan will show in detail the location of each area within the compound, set aside for the segregated storage of all materials involved in the demolition of all buildings on the site.

### **3.4 Construction – Excavated Material**

All excavated material removed from the site, as a result of any activities associated with the construction of the building, must be classified in accordance with the Department of Environment, Climate Change and Water NSW Waste Classification Guidelines prior to removal, transportation and disposal to an approved waste management facility.

All relevant details must be reported to the PCA.



## **PART 4 – ON GOING USE OF BUILDING**

### **4.1 OBJECTIVES**

1. To ensure that the storage, amenity and management of waste is sufficient to meet the needs of the development.
2. To ensure that all waste management activities are carried out effectively and efficiently, and in a manner that promotes the principles of health, safety and, convenience.
3. To promote waste minimisation practices.

### **4.2 ASSUMPTIONS**

1. Two (2) Waste Storage Areas (WSA's) – Garbage Room 1 (Building A – South Street Building) and Garbage Room 2 (Building B – Burbang Crescent Building) will be provided to store the appropriate number of mobile bins designated for the reception and storage of all waste and recyclables.
2. Garbage Room 1 (Building A – South Street Building) is located at the south western end of the Basement. This room will have two (2) separate storage areas, one each for waste and recycling bins. (See Attachment 1).
3. Garbage Room 2 (Building B – Burbang Crescent Building) is located at the north western end of the Basement. This room will have two (2) separate storage areas, one each for waste and recycling bins. (See Attachment 1).
4. The number and size of bins have been calculated from information provided by officers of Parramatta City Council, and from the Parramatta DCP 2011.
5. For Building A (South Street Building), all waste will be stored in 10 x 240 litre mobile bins.
6. For Building A (South Street Building), all recycling will be stored in 6 x 360 litre mobile bins.
7. For Building B (Burbang Crescent Building), all waste will be stored in 9 x 240 litre mobile bins.
8. For Building B (Burbang Crescent Building), all recycling will be stored in 5 x 360 litre mobile bins.
9. Waste services for both buildings will be provided weekly.
10. Recycling services for both buildings will be provided fortnightly.
11. All bins will be presented for servicing by representatives of the Owners Corporation.
12. All waste and recycling collections provided to Building A (South Street Building) will take place from the South Street kerbside frontage, and all bins will be returned to Garbage Room 1 after servicing by representatives of the Owners Corporation
13. All waste and recycling collections provided to Building B (Burbang Crescent Building) will take place from the Burbang Crescent kerbside frontage, and all bins will be returned to Garbage Room 2 after servicing by representatives of the Owners Corporation
14. Parramatta City Council's waste collection contractor will provide all waste and recycling services to the complex.

### **4.3 WASTE HANDLING & MANAGEMENT**

All waste and recyclables should be appropriately bagged or wrapped prior to being deposited into the designated waste or recycling bin.

### **4.4 WASTE & RECYCLING – SERVICE REQUIREMENTS**

All waste and recycling materials will be stored in approved receptacles of an appropriate size as specified in this WMP. The lids of the bins shall be closed at all times to reduce litter, stormwater pollution, odour and vermin.

The Council in general requires that colour coded receptacle lids that distinguish each service component are to be provided: -

- Waste Service – Red Lidded receptacle;
- Recycling Service – Yellow Lidded receptacle; and,

No formal green waste service will be provided to the building. All green waste will be disposed of privately by a contractor to be appointed by the Owners Corporation.

It will be the responsibility of the Owners Corporation to ensure that all green waste is removed from the complex in an appropriate manner.

### **4.5 WASTE & RECYCLING – SERVICE ARRANGEMENTS**

The following tables (Tables 1 and 2) specify the criteria for waste and recycling generation rates (as specified by Parramatta City Council) based on: -

- Waste – 140 litres of bin space per unit per week; and,
- Recycling – 120 litres of bin space per unit per week.

All waste and recycling generation rates were obtained from discussions with and advice from Council staff, and from information contained in Parramatta City Council's DCP 2011.

**TABLE 1 – RESIDENTIAL WASTE & RECYCLING GENERATION RATES**  
**BUILDING A – SOUTH STREET BUILDING**

SERVICE TYPE	UNITS	BIN SPACE PER UNIT	TOTAL SPACE REQUIRED	BINS SIZE	SERVICES PER WEEK	BINS REQUIRED	BINS PROVIDED
<b>Waste</b>	17	140	2,380	240	1	9.91	10
<b>Recycling</b>	17	120	2,040	360	0.5	5.66	6

**TABLE 2 – RESIDENTIAL WASTE & RECYCLING GENERATION RATES**  
**BUILDING B – BURBANG CRESCENT BUILDING**

SERVICE TYPE	UNITS	BIN SPACE PER UNIT	TOTAL SPACE REQUIRED	BINS SIZE	SERVICES PER WEEK	BINS REQUIRED	BINS PROVIDED
<b>Waste</b>	15	140	2,100	240	1	8.75	9
<b>Recycling</b>	15	120	1,800	360	0.5	5.00	5

The following tables (Table 3 and 4) specify the proposed bin servicing requirements for the building and is based on the above waste and recycling generation rates: -

**TABLE 3 – PROPOSED SERVICING ARRANGEMENTS**  
**BUILDING A – SOUTH STREET BUILDING**

<b>WASTE</b>	<b>RECYCLING</b>
10 x 240 litre bins / weekly	6 x 360 litre bins / Fortnightly

**TABLE 4 – PROPOSED SERVICING ARRANGEMENTS**  
**BUILDING B – BURBANG STREET BUILDING**

<b>WASTE</b>	<b>RECYCLING</b>
9 x 240 litre bins / weekly	5 x 360 litre bins / Fortnightly

## **4.6 PROVISION OF WASTE & RECYCLING SERVICES**

### **4.6.1 Waste and Recycling Collection Service Provider Details**

Parramatta City Council's waste collection contractor will provide all waste and recycling services to the building.

### **4.6.2 Details of Mobile Containers**

In relation to the size and design of the waste and recycling mobile bins, the following technical information is provided: -

<b>CONTAINER TYPE</b>	<b>HEIGHT (metres)</b>	<b>DEPTH (metres)</b>	<b>WIDTH (metres)</b>
240 litre mobile container	1.080	0.735	0.585
360 litre mobile container	1.100	0.850	0.680

### **4.6.3 Location, Design, and Construction of Waste Storage Areas**

#### **1. Building A (South Street Building)**

Garbage Room 1 is the Waste Storage Area (WSA) for Building A. It is fully enclosed and is located at the south western end of the Basement. It has two (2) separate areas, one for the storage of waste bins and one for recycling bins (see Attachment 1).

Within the confines of Garbage Room 1 is a storage area for 10 x 240 litre mobile waste bins (red lids). Separate space has been allocated for the storage of 6 x 360 litre mobile recycling bins (yellow lids).

The occupants of each unit in Building A will be responsible for depositing all of their waste and recycling material into the designated mobile bins in Garbage Room 1. All waste and recyclables should be appropriately bagged or wrapped prior to being deposited into the designated waste and recycling bins.

Residents of Building A will be provided with unrestricted 24-hour access to Garbage Room 1.

All mobile bins will be stored within the confines of each designated area of Garbage Room 1 all times.

All electrical equipment, including the provision of lighting, will be installed in accordance with the relevant Australian Standards.

Natural and mechanical ventilation will be required to be installed within each Garbage Room in accordance with the relative provisions of the Building Code of Australia.

According to the architectural drawings the size and design of the garbage room is a rectangular structure measuring 7.2 metres by 3.3 metres, with a total floor area of approximately 23.8 square metres.

In assessing the size and design of Garbage Room 1, it is considered that it is of a sufficient size and dimension to adequately store and manoeuvre (for collection and return) all of the required number of bins (both 240's and 360's) and ancillary facilities.

The entry to Garbage Room 1 is approximately 7 metres west (right on exiting) of the Building A lift.

## **2. Building B (Burbang Crescent Building)**

Garbage Room 2 is the Waste Storage Area (WSA) for Building B. It is fully enclosed and is located in the north western corner of the Basement. It has two (2) separate areas, one for the storage of waste bins and one for recycling bins (See Attachment 1).

Within the confines of Garbage Room 2 is a storage area for 9 x 240 litre mobile waste bins (red lids). Separate space has been allocated for the storage of 5 x 360 litre mobile recycling bins (yellow lids).

The occupants of each unit in Building B will be responsible for depositing all of their waste and recycling material into the designated mobile bins in Garbage Room 2. All waste and recyclables should be appropriately bagged or wrapped prior to being deposited into the designated waste and recycling bins.

Residents of Building B will be provided with unrestricted 24-hour access to Garbage Room 2.

All mobile bins will be stored within the confines of each designated area of Garbage Room 2 all times.

All electrical equipment, including the provision of lighting, will be installed in accordance with the relevant Australian Standards.

Natural and mechanical ventilation will be required to be installed within each Garbage Room in accordance with the relative provisions of the Building Code of Australia.

According to the architectural drawings the size and design of the garbage room is a rectangular structure measuring 8 metres by 3 metres, with a total floor area of approximately 24 square metres.

In assessing the size and design of Garbage Room 2, it is considered that it is of a sufficient size and dimension to adequately store and manoeuvre (for collection and return) all of the required number of bins (both 240's and 360's) and ancillary facilities.

The entry to Garbage Room 2 is approximately 10 metres west (left on exiting) of the Building B lift.



#### **4.6.4 Servicing Arrangements – Waste Collections**

##### **1. Building A – South Street Building**

All waste services will be provided by Parramatta City Council's waste collection contractor, using a collection vehicle, that will enable all collections to be carried out effectively and efficiently, and in a manner that will aim not to impact negatively on the principles of health, safety or convenience.

Representatives of the Owners Corporation will be responsible for presenting waste bins for servicing and returning them to Garbage Room 1 after collection.

As advised by Council, the waste bins will be serviced weekly, on the Thursday of that week.

Waste bins will be presented for collection to the South Street kerbside on the (Wednesday) afternoon prior to the collection day.

All waste bins will be placed into a kerbside collection area in a manner that will not adversely impact on the principles of health, safety or convenience. The bins will be returned to Garbage Room 1, as soon as practical after they have been serviced.

All 10x240 litre mobile waste bins will be presented for servicing on each collection day.

##### **2. Building B – Burbang Crescent Building**

All waste services will be provided by Parramatta City Council's waste collection contractor, using a collection vehicle, that will enable all collections to be carried out effectively and efficiently, and in a manner that will aim not to impact negatively on the principles of health, safety or convenience.

Representatives of the Owners Corporation will be responsible for presenting waste bins for servicing and returning them to Garbage Room 2 after collection.

As advised by Council, the waste bins will be serviced weekly, on the Thursday of that week.

Waste bins will be presented for collection to the Burbang Crescent kerbside on the (Wednesday) afternoon prior to the collection day.

All waste bins will be placed into a kerbside collection area in a manner that will not adversely impact on the principles of health, safety or convenience. The bins will be returned to Garbage Room 2, as soon as practical after they have been serviced.

All 9 x 240 litre mobile waste bins will be presented for servicing on each collection day.

#### **4.6.5 Servicing Arrangements – Recycling Collections**

##### **1. Building A – South Street Building**

All recycling services will be provided by Parramatta City Council's waste collection contractor, using a collection vehicle, that will enable all collections to be carried out effectively and efficiently, and in a manner that will aim not to impact negatively on the principles of health, safety or convenience.

Representatives of the Owners Corporation will be responsible for presenting recycling bins for servicing and returning them to Garbage Room 1 after collection.

As advised by Council, recycling bins will be serviced fortnightly, on the Thursday of that fortnight.

Recycling bins will be presented for collection to the South Street kerbside on the (Wednesday) afternoon prior to the collection day.

All recycling bins will be placed into a kerbside collection area in a manner that will not adversely impact on the principles of health, safety or convenience. The bins will be returned to Garbage Room 1, as soon as practical after they have been serviced.

All 6 x 360 litre mobile recycling bins will be presented for servicing on each collection day.

##### **2. Building B – Burbang Crescent Building**

All recycling services will be provided by Parramatta City Council's waste collection contractor, using a collection vehicle, that will enable all collections to be carried out effectively and efficiently, and in a manner that will aim not to impact negatively on the principles of health, safety or convenience.

Representatives of the Owners Corporation will be responsible for presenting recycling bins for servicing and returning them to Garbage Room 2 after collection.

As advised by Council, recycling bins will be serviced fortnightly, on the Thursday of that fortnight.

Recycling bins will be presented for collection to the Burbang Crescent kerbside on the (Wednesday) afternoon prior to the collection day.

All recycling bins will be placed into a kerbside collection area in a manner that will not adversely impact on the principles of health, safety or convenience. The bins will be returned to Garbage Room 2, as soon as practical after they have been serviced.

All 5 x 360 litre mobile recycling bins will be presented for servicing on each collection day.

#### **4.7 GREEN WASTE**

No formal green waste service will be provided to the development. It will be the responsibility of the Owners Corporation to ensure that all green waste generated from the on-going use of the development is disposed of appropriately.

#### **4.8 BULKY WASTE STORAGE**

Secure storage spaces are required to be provided for each residential unit in accordance with the provisions of Council's DCP 2011. Consistent with these requirements, storage areas have been provided within the basement.

The Owners Corporation will also be responsible for arranging Council 'Clean Ups' to ensure the efficient and regular removal bulky waste materials.

It will be the responsibility of the occupants of individual residential units, to dispose of these materials, appropriately.

#### **4.9 ON GOING OPERATION, USE & MAINTENANCE OF WASTE MANAGEMENT FACILITIES**

All waste management facilities will be maintained in a clean and hygienic condition that will promote the principles of health, safety and convenience.

In order to achieve these objectives, the following facilities and devices will be required: -

1. The walls and floors of both Waste Storage Areas (WSA's) are to be constructed of smooth faced masonry or concrete, and all walls will be painted with light coloured and washable paint.
2. The junction between all floors and walls will be coved and sealed up to 100mm above the floor level, in order to eliminate the build-up of dirt and grime.
3. A floor waste, connected to the Sydney Water drainage system in accordance with that Authority's requirements, will be provided to each WSA, and the floors will be graded to drain into it.
4. Appropriate washing facilities will be provided to each WSA, including appropriate plumbing and drainage fixtures and fittings, and the provision of running water.
5. The WSA's will be washed and cleaned on a regular basis.
6. All mobile bins will be washed and cleaned on a regular basis.
7. All electrical equipment, including the provision of lighting, will be installed in accordance with the relevant Australian Standards.
8. Natural and mechanical ventilation will be required to be installed within the WSA in accordance with the relative provisions of the Building Code of Australia.
9. Appropriate signage will be displayed in the basement clearly identifying waste and recycling bins and the waste storage areas.
10. Appropriate signage will be erected within each WSA providing instruction to residents on how to use waste and recycling facilities, including what is and what is not recyclable.
11. The Owners Corporation will be responsible for ensuring that all waste and recyclable matter and materials are placed and stored within the appropriate containers provided.

## **PART 5 – SUMMARY**

### **5.1 SUMMARY**

In summarising this proposal, the following information is provided:

1. This Waste Management Plan (WMP) has been developed and documented in accordance with the requirements of Parramatta Council, and in particular the Parramatta DCP 2011.
2. It aims to promote the use of recyclable materials in the excavation, demolition, construction and on-going operation of the building;
3. It aims to ensure the design of waste and recycling storage facilities are of an adequate size, appropriate for the intended use of the building, hygienic with safe and manoeuvrable access.
4. It aims to ensure that the provision of waste and recycling services to the completed buildings are carried out in an efficient manner, which will promote the principles of health, safety and convenience.

This is a unique development with a unique set of arrangements for its waste management activities.

The measures set out in this WMP aim to demonstrate that all such activities will be carried out efficiently and effectively, in a healthy, safe and convenient manner, to acceptable community standards, the buildings occupants, and to the requirements of Parramatta City Council.

---