

MIXED USE DEVELOPMENT 44 - 48 OXFORD STREET **EPPING**

DUNNET PROPERTIES PTY LTD

DRAWING No. TITLE NOTES AND DRAWING LEGEND SWDA 2.1 SITE PLAN UPPER GROUND LAYOUT BASEMENT 1, 2 & 3 LAYOUT **BASEMENT 4 LAYOUT & DETAILS DETAILS SHEET 1** DETAILS SHEET 2 SWDA 6.2 DRAINS MODEL OUTPUTS SOIL & WATER MANAGEMENT PLAN

DRAWING LIST

GENERAL NOTES

- SW1. SELECTION AND INSTALLATION OF PITS, PIPES, TANKS AND TRENCHES SHALL BE IN ACCORDANCE WITH THE CURRENT EDITION OF AS/NZS3500, THE HYDRAULIC SPECIFICATION AND THE LOCAL AND STATUTORY REQUIREMENTS U.N.O.
- SW2. UTILITY INFORMATION SHOWN ON THE PLANS IS NOT INTENDED TO DEPICT MORE THAN THE PRESENCE OF ANY SERVICES. ACTUAL LOCATIONS SHOULD BE VERIFIED BY HAND **EXCAVATION PRIOR TO CONSTRUCTION.**
- ALL EXISTING STORMWATER DRAINAGE LINES AND PITS THAT ARE TO REMAIN ARE TO BE INSPECTED AND CLEANED DURING THE CONSTRUCTION PERIOD. ANY PART OF THE STORMWATER DRAINAGE SYSTEM THAT WARRANTS REPAIRS SHALL BE REPORTED TO THE PROJECT MANAGER OR ARCHITECT.
- SW4. THE CONTRACTOR IS TO ORGANISE AND STAGE CONSTRUCTION WORK AND UNDERTAKE ANY DIVERSION WORKS, TO ENSURE THE EXISTING DRAINAGE SYSTEM IS ABLE TO CONVEY ALL STORMWATER FLOWS THAT MAY OCCUR DURING THE PERIOD OF CONSTRUCTION WORKS.
- SW5. THE CONTRACTOR SHALL ALLOW FOR THE CAPPING OFF, EXCAVATION AND REMOVAL OF ALL EXISTING SERVICES IN AREAS AFFECTED BY THE WORKS.
- SW6. ALL PIPEWORK IS TO BE TESTED IN ACCORDANCE WITH THE REQUIREMENTS OF AS3500.3-2003. ALL IN-GROUND PIPE WORK IS TO BE VIEWED BY THE SUPERINTENDENT (OR PERSON MANAGING THE CONTRACT ON THE CLIENTS BEHALF) UNDER TEST CONDITIONS PRIOR TO BACKFILLING.
- SW7. PIPE CLASSES AND TRENCH CONSTRUCTION SHALL BE ASSESSED IN ACCORDANCE WITH AS3725-1989 "LOADS ON BURIED CONCRETE PIPES" OR AS2566-1 "BURIED FLEXIBLE PIPE - PART 1 - STRUCTURAL DESIGN' AND SHALL TAKE ACCOUNT OF ANTICIPATED LOADINGS FROM TRAFFIC AND SOIL.
- SW8. BED ALL PIPES FIRMLY AND EVENLY WITH IMPORTED FILL ONLY. THICKNESS OF BEDDING LAYER SHALL BE 75mm IN SOIL AND 200mm IN ROCK.
- SW9. BACKFILL PIPES WITH IMPORTED FILL PROVIDE 200mm SIDE SUPPORT AND 150mm OVERLAY ABOVE PIPE CROWN. TRENCH FILL ABOVE THE EMBEDMENT LINE TO THE UNDERSIDE OF THE ROAD PAVEMENT OR THE FOOTPATH SHALL BE AS FOLLOWS:

UNDER ROADWAY: TRENCH FILL MATERIAL SHALL CONSIST OF IMPORTED FILL AS SPECIFIED HEREIN OF EITHER HIGH GRADE COMPACTION SAND OR APPROVED CRUSHED ROAD GRAVEL CONFORMING TO THE RMS SPECIFICATION 3051 OR SIMILAR.

OTHER THAN ROADWAY: TRENCH MATERIAL EXCAVATED SHALL CONSIST OF SELECT FILL AS SPECIFIED HEREIN AND SHALL NOT CONTAIN MORE THAN 20% OF STONES OF SIZE BETWEEN 25mm AND 75mm AND NONE LARGER THAN 75mm. PRIOR TO USE OF THE EXCAVATED MATERIAL IT SHALL BE INSPECTED AND APPROVED BY THE ENGINEER.

SW10. COMPACT BEDDING. EMBEDMENT AND TRENCH FILL MATERIALS SHALL BE AS FOLLOWS:-

FOR GRANULAR FILL MATERIAL (NON- COHESIVE SOIL) e.g. COARSE AGGREGATE FILL, THE DENSITY INDEX (ID) SHALL BE NOT LESS THAN 70%.

FOR GRANULAR MATERIAL (NON-COHESIVE SOILS) THE DENSITY INDEX (ID) SHALL BE NOT LESS THAN 70%. FOR NON- GRANULAR FILL MATERIAL (COHESIVE SOILS), THE DRY DENSITY RATIO (RD) SHALL BE NOT LESS THAN 95%.

- SW11. PIPES SHALL BE TRUE TO GRADES SHOWN AND ALIGNED SO THAT THE INVERT OF THE INLET PIPE INTERCEPTS WITH THE INVERT OF THE OUTLET PIPE AT THE DOWNSTREAM FACE OF THE PIT.
- SW12. STORMWATER DRAINAGE PIPES THAT EXCEED 1:5 GRADE, SHALL BE PROVIDED WITH REINFORCED CONCRETE ANCHOR BLOCKS. ANCHOR BLOCKS TO BE CONSTRUCTED TO SPECIFICATIONS SET OUT IN AS3500.3-2003.
- SW13. MINIMUM GRADE TO DRAINAGE PIPES TO BE 1% U.N.O, MIN. SIZE 100mm DIAMETER
- SW14. MINIMUM PIPE COVER TO BE 600mm UNDER TRAFFICABLE AREAS AND 300mm ELSEWHERE (U.N.O).
- SW15. PIPES UP TO AND INCLUDING 225mm SHALL BE UPVC (DWV) PIPE AND FITTINGS, MANUFACTURED TO AS1260 WITH SOLVENT WELDED JOINTS.

- SW16. PIPES LARGER THAN OR EQUAL TO 300mm TO BE REINFORCED CONCRETE RUBBER RING JOINTED TYPE (CLASS 2) MANUFACTURED TO AS4058 (U.N.O).
- SW17. EQUIVALENT STRENGTH FRC PIPES MAY BE USED WHERE APPROVED.
- SW18. PROVIDE CLEANING EYES LOCATED 500mm ABOVE FFL TO ALL DOWN PIPES NOT DIRECTLY CONNECTED TO PITS.
- SW19. STORMWATER DRAINAGE CONNECTIONS TO COUNCIL SYSTEM SHALL BE TO THE REQUIREMENTS AND SATISFACTION OF THE LOCAL COUNCIL.
- SW20. SUBSOIL PIPES SHALL BE LAID AT A MIN. GRADE OF 0.5% (U.N.O).
- SW21. ADDITIONAL SUBSOIL DRAINAGE SHALL BE LAID TO SUIT THE SITE CONDITIONS IF THE PRESENCE OF GROUNDWATER IS DETECTED.
- SW22. SUBSOIL DRAINAGE SHALL BE PROVIDED BEHIND RETAINING WALLS AND OTHER AREAS AS REQUIRED TO RELIEVE HYDROSTATIC PRESSURE AND DRAIN GROUND WATERS. CONNECT INTO THE DRAINAGE SYSTEM IN SUCH A WAY TO AVOID BACKFLOW OF STORMWATER INTO THE SUBSOIL DRAINAGE LINE.
- SW23. SUBSOIL DRAINAGE INCLUDING SUBSOIL PIPEWORK SERVING RETAINING WALLS. SHALL BE IN ACCORDANCE WITH AS2439 AND CONSIST OF A 100mm DIAMETER SMOOTH WALL SLOTTED PVC-U PLASTIC PIPE WITH 20mm BLUE GAUGE METAL SURROUND WRAPPED IN GEOTEXTILE. CLEAN OUTS SHALL BE EXTENDED TO THE SURFACE AND PROVIDED WITH A SCREWED COVER PLATE FLUSH WITH THE FINISHED SURFACE LEVEL.
- SW24. ALL DRAINAGE PITS SHALL BE PRECAST CONCRETE (U.N.O.).
- SW25. DRAINAGE PITS: PITS DEEPER THAN 1200mm TO BE FITTED WITH STEP IRONS AT 300mm CENTRES TO AS1657.-1992: FIXED PLATFORMS, WALKWAYS, STAIRWAYS AND LADDERS, -DESIGN, CONSTRUCTION AND INSTALLATION.
- SW26. BENCHING TO BE HALF OUTGOING PIPE DEPTH. TRENCHING TO BENCHING TO BE 20Mpa MASS CONCRETE.
- SW27. 100mm HOLE FOR SUBSOIL DRAINAGE OUTLET TO BE LOCATED 100mm ABOVE INVERT OF ALL INLET PIPES. SUBSOIL DRAINAGE TO EXTEND FOR A DISTANCE OF 3m UPSTREAM OF PIT (AT EACH INLET TRENCH) WITH THE UPSTREAM END SEALED.
- SW28. ALL CONNECTIONS TO EXISTING DRAINAGE PITS SHALL BE MADE IN TRADESMAN LIKE MANNER AND THE INTERNAL WALL OF THE PIT AT THE POINT OF ENTRY SHALL BE CEMENT RENDERED TO ENSURE A SMOOTH FINISH.
- SW29. PIT GRATE, FRAMES AND SOLID COVERS SHALL BE CLASS B IN NON TRAFFICABLE AREAS AND CLASS D IN TRAFFICABLE AREAS IN ACCORDANCE WITH AS3996.
- SW30. ALL GRATES SHALL BE PROVIDED WITH A LOCKING CLIP.
- SW31. TRASH SCREENS, SILT CONTROLS, OTHER POLLUTANT CONTROLS AND OVERLAND FLOW ROUTES SHALL BE REGULARLY MAINTAINED TO ENSURE THAT THE DRAINAGE SYSTEM REMAINS UNBLOCKED AND OPERATES AS ORIGINALLY INTENDED DURING THE CONSTRUCTION PROCESS.
- SW32. FOR CHARGED DRAINAGE SYSTEMS, THE UPVC PIPEWORK MUST BE SUITABLE FOR PRESSURE APPLICATIONS.
- SW33. FOR CHARGED DRAINAGE SYSTEMS, ALL UPVC PIPEWORK AND JOINTS, INCLUDING THE FULL HEIGHT OF THE DOWNPIPE, ARE TO HAVE SEALED AND SOLVENT WELDED JOINTS TO ENABLE WATER STORAGE IN PIPE NETWORK. ALL PIPES ARE TO BE FILLED WITH WATER AND PUT UNDER TEST CONDITIONS PRIOR TO HANDOVER.
- SW34. A CLEANING EYE IS TO BE FITTED AT THE LOWEST POINT OF THE CHARGED DRAINAGE SYSTEM AND EXTEND INTO A STORMWATER PIT, TO ALLOW FOR DRAINING AND CLEAR OUT
- SW35. LEAF GUARDS ARE TO BE FITTED OVER ALL EAVES GUTTERS BEING SERVED BY A CHARGED ROOF DRAINAGE SYSTEM.
- SW36. ALL EAVES GUTTERS SHALL HAVE A LO-FRONT LIP U.N.O. HIGH-FRONT EAVES GUTTERS SHALL BE REJECTED.
- SW37. UPON COMPLETION OF WORKS, THE CONTRACTOR SHALL FLUSH OUT ALL STORMWATER PIPES AND PITS TO ENSURE THE REMOVAL OF ALL LOOSE CONCRETE AND SEDIMENT.

SPECIFICATION NOTES

- S1. ALLOW TO COMPLETE ALL WORKS AS REQUIRED TO PROVIDE A COMPLETE AND FUNCTIONAL SYSTEM AS GENERALLY INDICATED ON THE DRAWINGS.
- S2. ALL WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH AS3500 TO THE COMPLETE SATISFACTION OF THE AUTHORITY HAVING JURISDICTION OVER THE WORKS. MAKE ALL APPLICATIONS AND PAY ALL FEES.
- S3. ALLOW TO CO-ORDINATE AND CONFIRM ALL DIMENSIONS, EXISTING LEVELS, EXISTING SERVICES AND STRUCTURE ON SITE PRIOR TO TENDER. ALL WORK IS TO BE CO-ORDINATED WITH PROJECT MANAGER OR ARCHITECT.
- S4. HYDRAULIC DRAWINGS ARE APPROXIMATE ONLY AND ARCHITECT'S DETAILS ARE TO BE REFERRED TO FOR ACCURATE SETOUTS.
- S5. THE HYDRAULIC CONTRACTOR SHALL BE DEEMED TO HAVE INSPECTED THE SITE PRIOR TO TENDER AND BE SATISFIED THAT THE WORKS, AS DOCUMENTED, ARE COMPLETE AND ALL EXISTING SERVICES AND LEVELS SHOWN FOR CONNECTION ARE SUITABLE.
- S6. ALLOW TO MAKE APPLICATION (DIAL BEFORE U DIG) TO ALL AUTHORITIES FOR THE LOCATION OF THEIR EXISTING SERVICES IN THE AREA. FAILURE TO DO SO WILL BE AT THE HYDRAULIC CONTRACTORS EXPENSE.
- S7. WHERE REQUIRED, STORMWATER EASEMENTS SHALL BE OBTAINED BY THE OWNER, ALL NEGOTIATION/COMPENSATION PAYMENTS AND THE
- S8. WHERE REQUIRED BY THE PRINCIPAL CERTIFIER OR THE PROJECT MANAGER, WORK AS EXECUTED DETAILS SHALL BE PREPARED BY A REGISTERED SURVEYOR/CHARTERED PROFESSIONAL ENGINEER VERIFYING THAT THE STORMWATER DRAINAGE SYSTEM HAS BEEN CONSTRUCTED IN ACCORDANCE WITH THE RELEVANT DRAWINGS. ANY DEVIATIONS FROM THE APPROVED PLANS SHALL BE NOTED AND BROUGHT TO THE ATTENTION OF THE DESIGN ENGINEER. ADEQUATE INSPECTIONS SHALL BE CARRIED OUT

EROSION AND SEDIMENT CONTROL

- E2. MEASURES PROVIDED WILL BE TO THE SATISFACTION OF THE PRINCIPAL'S REPRESENTATIVE IN ACCORDANCE WITH THE LOCAL AND STATUTORY REQUIREMENTS UNLESS NOTED OTHERWISE. ALL WORKS SHALL BE ERECTED AND CONSTRUCTED IN ACCORDANCE WITH THE LATEST EDITIONS OF THE 'BLUE BOOK'- MANAGING URBAN STORMWATER (MUS): SOILS AND CONSTRUCTION, LANDCOM (VOL 1) AND DECCW (VOL 2)
- E3. ALL SUB CONTRACTORS SHALL BE INFORMED OF THEIR RESPONSIBILITIES BY THE CONTRACTOR IN MINIMISING THE POTENTIAL FOR SOIL EROSION AND
- E4. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING AND PROVIDING ON GOING ADJUSTMENTS TO EROSION CONTROL MEASURES AS REQUIRED

STORMWATER RISING MAIN —— B——— BOUNDARY FENCE — e — e — EXISTING PIPE —— eG — X — eG — X — EXISTING PIPE MADE REDUNDANT SEDIMENT FENCE LINE

PIPEWORK

RAINWATER DRAINAGE

PROPERTY BOUNDARY

—— TB —— TB —— TURBIDITY BARRIER

GULLY PIT

CLEAR OUT

TRENCH GRATE

REFLUX VALVE

PIPE CONNECTION POINT

PIPE NOT PENETRATING

OVERLAND FLOW PATH

DOWNPIPE SPREADER

FOR CONTINUATION

FINISHED FLOOR LEVEL

HIGH LEVEL IN CEILING

RECTANGULAR HOLLOW SECTION

GRATED INLET PIT

REFER DRG No

ACCESS PANEL

BOX GUTTER

DOWNPIPE

EXISTING

HIGH POINT

OVERFLOW

INVERT LEVEL

KERB INLET PIT

RELATIVE LEVEL

RAINWATER HEAD

RAINWATER TANK

TO BE ADVISED

TOP KERB LEVEL

TREE ROOT ZONE

SLAB RELATIVE LEVEL

STRUCTURAL ROOT ZONE

UNLESS NOTED OTHERWISE

PIPE PENETRATING

DIRECTION OF FALL OR FLOW DOWN PIPE PB0 PLANTER BOX OUTLET RWO RAIN WATER OUTLET STORMWATER PIT (GRATE)

STORMWATER PIT (RWO IN BASE) SEALED PIT COVER

O CO

FFL

GIP

KIP

O/F

RHS

RWT

SRL

SRZ

TBA

TKL

TRZ

UNO

TG

ᄴ

LEGEND

INTEGRATION OF THE EASEMENTS INTO THE TITLE DOCUMENTS SHALL BE BY THE OWNER UNLESS AGREED OTHERWISE.

DURING THE COURSE OF THE CONSTRUCTION.

MISCELLANEOUS - SERVICE / SERVICE NUMBER - PIPE SIZE

E1. EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PROVIDED WHERE SHOWN ON THE DRAWINGS, IN ACCORDANCE WITH THE SPECIFICATION AND THE CONSTRUCTION ENVIRONMENTAL MANAGEMENT PLAN (IF APPLICABLE)

- POLLUTION TO DOWNSLOPE LANDS AND WATERWAYS.
- DURING CONSTRUCTION.

Р3	RE-ISSUED FOR DA	MB	GB	09.11.
	AMENDED ARCH. LAYOUT			
P2	ISSUED FOR DA	МВ	GB	31.05.3
P1	PRELIMINARY ISSUE	МВ	GB	13.05.1
Rev.	Issue / Amendment	Ву	App.	Date



t 612 9460 9000 f 612 9460 9090 e partridge@partridge.com.au w www.partridge.com.au

PARTRIDGE HYDRAULIC SERVICES ABN 11 608 027 578

Level 5, 1 Chandos Street, St Leonards NSW 2065 Australia

HYDRAULIC SERVICES

DUNNET PROPERTIES PTY LTD

NETTLETONTRIBE ARCHITECTS

117 WILLOUGHBY ROAD, CROWS NEST TEL: 9431 6431 WEB: nettletontribe.com.au


MIXED USE DEVELOPMENT 44 - 48 OXFORD STREET **EPPING**


STORMWATER DRAINAGE SERVICES NOTES AND DRAWING LEGEND


ELECTRONIC SIGNATURE:
THIS DRAWING HAS BEEN ASSIGNED AN ELECTRONIC SIGNATURE
CODE. THE PRESENCE OF THIS CODE SIGNIFIES THAT THIS IS THE
USE FIGURED DIMENSIONS Electronic Code Signature Date Designed M.B. Scale at A1 **MAY 2016** S.P/S.D Revision

2015H0038 SWDA 1.1

PRELIMINARY - NOT FOR CONSTRUCTION









1:200	MAY 2016	S.P/S.D
Scale at A1	Date	Drawn
		M.B.
Electronic Code	Signature Da	ate Designed
ELECTRONIC SIGNATUR THIS DRAWING HAS BEEN ASSIGNED CODE. THE PRESENCE OF THIS CODE CERTIFIED DRAWING ISSUED FOR CO	DO NOT SCALE DRAWING USE FIGURED DIMENSION	

PRELIMINARY - NOT FOR CONSTRUCTION







GALVANISED STEP RUNGS AT -


SPACING OF BETWEEN 250 - 300mm

TO BE INSTALLED IN ACCORDANCE


/-- 900 x 900 CLASS B HINGED

ACCESS COVER WITH LOCKING

AYMROO STEP IRONS (STEP283YW) OR APPROVED EQUIVALENT LIFTING HANDLE -**TOP VIEW**







D =228mm OD +100 **ORIFICE PLATE** В

- 228mmØ ORIFICE

CENTRE RL 98.77

ORIFICE SIZE

 $A = 0.041 m^2$

THEREFORE

 $Cd x \sqrt{2 x g x H}$

 $0.62 \times \sqrt{2 \times 9.81 \times 1.35}$

SIDE VIEW

375Ø OUTLET -

PIPE BEHIND

4x10Ø FIXING -

6mm STAINLESS -

STEEL PLATE

DYNABOLTS BOLTED + 2 PART EPOXY

STEP IRONS

A

STORMWATER PIT IN LANDSCAPE **ABOVE SUSPENDED CONCRETE SLAB**

PUMP OUT NOTES

900 x 900 CLASS B HINGED -

GALVANISED MILD STEEL

GRATE & FRAME WITH

THE PUMP OUT SYSTEM IS DESIGNED TO WORK IN THE FOLLOWING

- 1. THE PUMPS SHALL BE PROGRAMMED TO WORK ALTERNATELY ON A DUTY STANDBY ARRANGEMENT SO AS TO ALLOW BOTH PUMPS TO HAVE EQUAL OPERATION LOAD & PUMP LIFE.
- 2. A LOW LEVEL FLOAT SHALL BE PROVIDED TO ENSURE THAT THE MINIMUM REQUIRED WATER LEVEL IS MAINTAINED WITHIN THE SUMP AREA OF THE TANK. IN THIS REGARD THIS FLOAT WILL FUNCTION AS AN OFF SWITCH FOR THE PUMPS.
- 3. A SECOND FLOAT SHALL BE PROVIDED AT A HIGHER LEVEL, APPROXIMATELY 300mm ABOVE THE MINIMUM WATER LEVEL WHEREBY ONE OF THE PUMPS WILL OPERATE AND DRAIN THE TANK TO THE LEVEL OF THE LOW LEVEL FLOAT.
- 4. A THIRD FLOAT SHALL BE PROVIDED AT A HIGH LEVEL, WITHIN THE TANK. THIS FLOAT SHOULD START THE OTHER PUMP THAT IS NOT OPERATING AND ACTIVATE THE ALARM.
- 5. AN ALARM SYSTEM SHALL BE PROVIDED WITH A FLASHING STROBE LIGHT & A PUMP FAILURE WARNING SIGNAL WHICH ARE TO BE LOCATED AT THE DRIVEWAY ENTRANCE TO THE BASEMENT LEVEL. THE ALARM SYSTEM SHALL BE PROVIDED WITH A BATTERY BACK-UP IN CASE OF POWER FAILURE.
- 6. PUMP CONTROL SHALL BE IN A LOCKABLE & WEATHER PROOF

STORMWATER PUMP SET SPECIFICATION

INSTALL DUAL SUBMERSIBLE STORMWATER PUMP SET WITH A DUTY OF 2.0I/S AT 23 METERS HEAD OR EQUIVALENT COMPLETE WITH CONTROL PANEL WITH:

- MAIN ISOLATING SWITCH.
- AUTOMATIC ALTERNATION. MAN / OFF / AUTO SWITCH FOR EACH PUMP.
- CIRCUIT BREAKERS FOR CONTROL CIRCUIT.
- MANUAL RESET THERMAL OVERLOAD FOR EACH PUMP MOTOR. LIGHTS FOR POWER ON / PUMP RUN / PUMP FAIL / HIGH LEVEL.
- COMMON FAULT STROBE LIGHT.
- ALL MOUNTED IN A WEATHERPROOF SHEET METAL ENCLOSURE.

VOLT FREE CONTACTS FOR BMS CONNECTION.	
AUDIBLE ALARM WITH MUTE BUTTON.	

Р3	RE-ISSUED FOR DA	МВ	GB	09.11.17
	AMENDED ARCH. LAYOUT			
P2	ISSUED FOR DA	МВ	GB	31.05.16
P1	PRELIMINARY ISSUE	МВ	GB	13.05.16
Rev.	Issue / Amendment	Ву	App.	Date



PARTRIDGE HYDRAULIC SERVICES ABN 11 608 027 578 Level 5, 1 Chandos Street, St Leonards NSW 2065 Australia t 612 9460 9000 f 612 9460 9090 e partridge@partridge.com.au www.partridge.com.au

HYDRAULIC SERVICES

DUNNET PROPERTIES PTY LTD

NETTLETONTRIBE ARCHITECTS

117 WILLOUGHBY ROAD, CROWS NEST TEL: 9431 6431 WEB: nettletontribe.com.au

MIXED USE DEVELOPMENT 44 - 48 OXFORD STREET **EPPING**


STORMWATER DRAINAGE SERVICES **DETAILS SHEET 1**

ELECTRONIC SIGNATUR THIS DRAWING HAS BEEN ASSIGNED CODE. THE PRESENCE OF THIS CODE CERTIFIED DRAWING ISSUED FOR COP	AN ELECTRONIC SIGNATURE SIGNIFIES THAT THIS IS THE	DO NOT SCALE DRAWIF	
Electronic Code	Signature D	ate Designo	ed
		M.B.	
Scale at A1	Date	Drawn	
AS SHOWN	MAY 201	6 S.P/S.	.D

2015H0038 SWDA 6.1


PRELIMINARY - NOT FOR CONSTRUCTION

Revision




SECTION VIEW

TYPICAL BASEMENT PERIMETER DRAINAGE PIT DETAIL



TYPICAL BASEMENT PERIMETER DRAINAGE **DISHED DRAIN / SUB-SOIL DETAIL**




SECTION VIEW

GRASSED DRAINAGE SWALE WITH SUBSOIL / E


	STORMFIL	TER DESI	GN TABLE			
 STORMFILTER TREATMENT CAPACITY VARIES BY NUMBER OF FILTER CARTRIDGES INSTALLED AND BY REGION SPECIFIC INTERNAL FLOW CONTROLS. CONVEYANCE CAPACITY IS RATED AT 80L/S. THE STANDARD CONFIGURATION IS SHOWN. ACTUAL CONFIGURATION OF THE SPECIFIED STRUCTURE(S) PER CIVIL ENGINEER WILL BE SHOWN ON SUBMITTAL DRAWING(S). ALL PARTS PROVIDED AND INTERNAL ASSEMBLY BY STORMWATER360 AUSTRALIA UNLESS OTHERWISE NOTED. 						
CARTRIDGE HEIGHT	69	90	40	30	3	10
SYSTEM HYDRAULIC DROP (H - REQ'D. MIN.)	930		700		550	
TREATMENT BY MEDIA SURFACE AREA L/S/m2	1.4	0.7	1.4	0.7	1.4	0.7
CARTRIDGE FLOW RATE (Us)	1.42	0.71	0.95	0.47	0.63	0.32

GENERAL NOTES

- INLET AND OUTLET PIPING SHALL BE SPECIFIED BY SITE CIVIL ENGINEER (SEE PLANS) AND PROVIDED BY CONTRACTOR.
- STORMFILTER IS PROVIDED WITH OPENINGS AT INLET AND OUTLET LOCATIONS. IF THE PEAK FLOW RATE, AS DETERMINED BY THE SITE CIVIL ENGINEER, EXCEEDS THE PEAK HYDRAULIC CAPACITY OF
- THE PRODUCT, AN UPSTREAM BYPASS STRUCTURE IS REQUIRED. PLEASE CONTACT STORMWATER360 AUSTRALIA FOR
- THE FILTER CARTRIDGE(S) ARE SIPHON-ACTUATED AND SELF-CLEANING. THE ACTUAL NUMBER SHALL BE SPECIFIED BY THE SITE CIVIL ENGINEER ON SITE PLANS OR IN DATA TABLE BELOW. PRECAST STRUCTURE TO BE CONSTRUCTED BY STORMWATER360 AUSTRALIA IN ACCORDANCE WITH AS3600.
- SEE STORMFILTER DESIGN TABLE FOR REQUIRED HYDRAULIC DROP. FOR SHALLOW, LOW DROP OR SPECIAL DESIGN CONSTRAINTS, CONTACT STORMWATER360 AUSTRALIA FOR DESIGN OPTIONS.
- ALL WATER QUALITY PRODUCTS REQUIRE PERIODIC MAINTENANCE AS OUTLINED IN THE O&M GUIDELINES. PROVIDE MINIMUM CLEARANCE FOR MAINTENANCE ACCESS.
- STRUCTURE AND ACCESS COVERS DESIGNED TO MEET AUSTROADS T44 LOAD RATING WITH 0.0m TO 2.0m FILL MAXIMUM
- (CLASS D).
- THE STRUCTURE THICKNESSES SHOWN ARE FOR REPRESENTATIONAL PURPOSES AND VARY REGIONALLY. ANY BACKFILL DEPTH, SUB-BASE, AND OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS
- AND SHALL BE SPECIFIED BY SITE CIVIL ENGINEER.
- CARTRIDGE HEIGHT IS 690mm (SHOWN). CARTRIDGE HEIGHT AND ASSOCIATED DESIGN PARAMETERS PER
- STORMFILTER DESIGN TABLE.
- STORMFILTER BY STORMWATER360 AUSTRALIA: PHONE: 1300 354 722 OR www.stormwater360.com.au





DROP PIPE ENVIROPOD CONFIGURATION **SECTION**



PROVIDE CLEAN OUTS TO ENDS AND AT INTERMEDIATE LOCATIONS OF SUBSOIL PIPES WHERE NOTED C.O. ON PLAN

TYPICAL SUBSOIL DRAIN CLEANOUT





PLAN WITHOUT GRATE

TYPICAL GRATED INLET PIT

P4	RE-ISSUED FOR DA	МВ	GB	09.11.17
	AMENDED ARCH. LAYOUT			
РЗ	RE-ISSUED FOR DA	МВ	GB	08.06.16
P2	ISSUED FOR DA	МВ	GB	31.05.16
Ρ1	PRELIMINARY ISSUE	МВ	GB	13.05.16
Rev.	Issue / Amendment	Ву	App.	Date



PARTRIDGE HYDRAULIC SERVICES ABN 11 608 027 578 Level 5, 1 Chandos Street, St Leonards NSW 2065 Australia t 612 9460 9000 f 612 9460 9090 e partridge@partridge.com.au www.partridge.com.au

HYDRAULIC SERVICES

DUNNET PROPERTIES PTY LTD

NETTLETONTRIBE ARCHITECTS

117 WILLOUGHBY ROAD, CROWS NEST TEL: 9431 6431 WEB: nettletontribe.com.au

MIXED USE DEVELOPMENT 44 - 48 OXFORD STREET **EPPING**


STORMWATER DRAINAGE SERVICES **DETAILS SHEET 2**

ELECTRONIC SIGNATUR THIS DRAWING HAS BEEN ASSIGNED CODE. THE PRESENCE OF THIS CODE CERTIFIED DRAWING ISSUED FOR CO	AN ELECTRONIC SIGNATURE SIGNIFIES THAT THIS IS THE		ALE DRAWINGS ED DIMENSIONS
Electronic Code	Signature D	Signature Date	
			M.B.
Scale at A1	Date		Drawn
AS SHOWN	MAY 201	6	S.P/S.D

2015H0038 SWDA 6.2

PRELIMINARY - NOT FOR CONSTRUCTION


Revision




STORMFILTER CARTRIDGE DETAIL / F N.T.S

REFER TO DRAWING NO. SWDA 1.1 FOR CONSTRUCTION NOTES

GENERAL NOTES 15. ALL EXCAVATION WORKS ARE TO BE IN ACCORDANCE WITH THE GEOTECHNICAL REPORT, IF AVAILABLE, AND THE STRUCTURAL ENGINEER'S DRAWINGS.








- 19. ALL STOCKPILES TO BE CLEAR FROM DRAINS, **GUTTERS AND FOOTPATHS.**
- 20. TOP SOIL WILL BE RE SPREAD AND ALL DISTURBED AREAS WILL BE REHABILITATED WITHIN 20 WORKING DAYS OF THE COMPLETION OF WORKS.
- 21. ALL SEDIMENT TO BE STORED AND COLLECTED BY A LIQUID WASTE COMPANY FOR DISPOSAL AT A LICENSED TREATMENT FACILITY.
- 22. ROADS AND FOOTWAYS TO BE SWEPT AT THE END OF THE DAY.
- 23. ALL EROSION AND SEDIMENT CONTROLS WILL BE CHECKED AT LEAST WEEKLY AND AFTER RAINFALL EVENTS TO MAKE SURE THEY ARE MAINTAINED TO A FULLY FUNCTIONAL CONDITION.

Kerb-side inlet



SOIL AND WATER MANAGEMENT

ACCESS RAMP SUPPORT BY

STRUCTURAL

PROVIDE TAP &

FACILITIES TO

THE SITE TO

PREVENT THE

TRACKING OF

DEBRIS & SOIL

ONTO THE PUBLICWAY

HOARDING

ENGINEER

CLEAN THE WHEELS AND BODIES OF ALL

VEHICLES LEAVING

BOUNDARY FENCE /

PERMANENT SHORING

BY STRUCTURAL

TEMPORARY SITE OFFICE. FINAL

LOCATION TO BE

CONFIRMED BY SITE

SUPERINTENDENT.

TEMPORARY SITE

LOCATION TO BE

CONFIRMED BY SITE

SUPERINTENDENT

Earth bank

Construction Notes

STOCKPILES

Non-perforated tank —

LINED TANK

water flow, roads and hazard areas.

2. Construct on the contour as low, flat, elongated mounds.

or SWMP to reduce the C-factor to less than 0.10.

Observation opening

TOILET. FINAL

HOSE DOWN

ENGINEER

1. THIS IS A CONCEPTUAL SOIL AND WATER MANAGEMENT ONLY. IT PROVIDES SUFFICIENT DETAIL TO SHOW CLEARLY WORKS CAN PROCEED WITHOUT UNDUE POLLUTION TO RECEIVING WATERS. A DETAILED PLAN WILL BE PREPARED ONCE CONSENT IS GIVEN AND BEFORE WORKS START.

Stabilise stockpile surface

Sediment fence

1. Place stockpiles more than 2 (preferably 5) metres from existing vegetation, concentrated

4. Where they are to be in place for more than 10 days, stabilise following the approved ESCP

5. Construct earth banks (Standard Drawing 5-5) on the upslope side to divert water around

stockpiles and sediment fences (Standard Drawing 6-8) 1 to 2 metres downslope.

3. Where there is sufficient area, topsoil stockpiles shall be less than 2 metres in height.

TOPSOIL PRIOR TO BULK EARTHWORKS):

"CROSSING

CONSTRUCT STABILISED SITE ACCESS (SD6-14).

MESH AND GRAVEL INLET FILTER (SD6-11)

INSTAUL UPSTREAM OF ANY KERB INLET

PITS DOWNSTREAM FROM \$UBJECT SITE.

CONSTRUCT IN ACCORDANCE WITH SD6-11

- 3. PLACE SEDIMENT FENCES (SD6-8) ON THE DOWNSLOPE OF LANDS TO BE DISTURBED INCLUDING THOSE AREAS DISTURBED FOR CONSTRUCTION OF THE SEDIMENT BASINS.
- 4. STRIP AND STOCKPILE TOPSOIL (SD4-1) FROM THOSE LANDS TO BE EXPOSED TO CONSTRUCTION
- 5. STABILISE AND REVEGETATE LAND SURFACES DISTURBED DURING DEMOLITION ALONG EASTERN BOUNDARY.

SD 4-1

SD 6-5

DRAINAGE WORKS)

Sediment storage zone

- APPROX EXTENTS OF ACCESS

INALLESSIBLE AREA (C103.14

RAMP EMBANKMENT

TABILISED SITE ACCESS (SD6-14)

CONSTRUCT IN ACCORDANCE WITH

DETAIL SD6-14

6. ONCE THE EXCAVATION FOR THE BASEMENT HAS BEEN BROUGHT DOWN TO BULK EXCAVATION LEVEL THE LOWEST LIFT PIT IS TO BE USED AS A SUMP AND PUMP AREA. FALL ALL LEVELS AT A MINIMUM 1% GRADE TO THIS LOCATION.

FALL

7. CONSTRUCT SEDIMENT BASIN. THIS BASIN DOES NOT NEED TO BE CONSTRUCTED IN EARTH AS SHOWN IN SD 6-4 BUT THEY MUST BE CONSTRUCTED IN IMPERVIOUS MATERIALS. THE SETTLING VOLUME OF THE SEDIMENT BASIN HAS BEEN CALCULATED USING THE CONTAINMENT OF THE 5-DAY, 75TH PERCENTILE RAINFALL EVENT A VOLUMETRIC

RUNOFF COEFFICIENT OF 0.5 HAS BEEN ADOPTED, IN THIS INSTANCE A CONSERVATIVE VALUE.

C*102.29

LINED TANK (SD6-5) SAGE 1

CONNECT RISING MAIN TO INLET OF TANK. CONSTRUCT IN

ACCORDANCE WITH DETAIL SD6-5. EXCAVATION FOR TANK TO BE USED FOR FUTURE WATER QUALITY IMPROVEMENT DEVICE

EXCAVATION LEVEL = 87.15m AHD

EARTH BASIN WET (SD6-4) - STAGE 2 -

VOLUME CAPACITY = 70m³

WATER DEPTH = 1.9m

SEDIMENT BASIN (TYPE F SOILS)MINIMUM

Earth embankment

DIMENSIONS = 15m LONG x 2.5m WIDE

(LOCATED AT BASE OF LIFT WELL)

(TO BE CONFIRMED BY STRUCTURAL ENGINEER)

- 8. INSTALL EARTH BANKS TO DIRECT OVERLAND FLOWS TO THE SEDIMENT BASIN.
- 9. INSTALL FLOATING INLET PUMP IN BASIN.
- 10. THE PUMP SYSTEM IS TO BE ACTIVATED 24 HOURS AFTER CONCLUSION OF STORM EVENT OR WHEN SUSPENDED SOLIDS ARE LESS THAN 50 MILLIGRAMS PER LITRE.
- 11. THE PUMP SYSTEM IS TO DISCHARGE INTO LINED

CONCRETE PATHWAY 3

FLOATING INLET PUMP TO BE

ACTIVATED 24 HOURS AFTER

50 MILLIGRAMS PER LITRE

1.5m star pickets at max.

2.5m centres

500 mm to 600 m

SECTION DETAIL

2.5 m centres

1.5 m star pickets at max.

600 mm min

Direction of flow

20 m max. (unless stated otherwise on SWMP/ESCP)

2.5 m spacings

1. Construct sediment fences as close as possible to being parallel to the contours of the site,

but with small returns as shown in the drawing to limit the catchment area of any one

one point to 50 litres per second in the design storm event, usually the 10-year event.

edge of the trench. Ensure any star pickets are fitted with safety caps.

Join sections of fabric at a support post with a 150-mm overlap.

section. The catchment area should be small enough to limit water flow if concentrated at

Cut a 150-mm deep trench along the upslope line of the fence for the bottom of the fabric to

Drive 1.5 metre long star pickets into ground at 2.5 metre intervals (max) at the downslope

Fix self-supporting geotextile to the upslope side of the posts ensuring it goes to the base of

the trench. Fix the geotextile with wire ties or as recommended by the manufacturer. Only

use geotextile specifically produced for sediment fencing. The use of shade cloth for this

Flow

Star pickets at maximum PLAN

Undisturbed area

Min. 1.5 m

Construction Notes

purpose is not satisfactory.

SEDIMENT FENCE

CONCLUSION OF STORM EVENT WHEN

SUSPENDED SOLIDS ARE LESS THAN

- 12. UNDERTAKE ROAD AND DRAINAGE WORKS ACCORDINGLY TO THE ENGINEERING PLANS.
- 13. ALL STORMWATER PITS ARE TO BE SURROUNDED BY A MESH AND GRAVEL INLET FILTER (SD6-11).

Self supporting geotextile


On soil. 150 mm x 100 mm

backfill and on rock, set into

trench with compacted

surface concrete

14. PROVIDE A SEDIMENT FENCE ALONG WESTERN BOUNDARY ON COMPLETION OF BASEMENT WORKS ADJACENT EXISTING LEVELS.



Construction Notes

MESH & GRAVEL INLET FILTER (SD6-11) - STAGE 1

BREAK UP EXISTING HARDSTAND AREAS

SEDIMENT FENCE (SD6-8) - STAGE 1

CONSTRUCT IN ACCORDANCE WITH

- DASHED LINE DENOTES

EXTEND OF BASEMENT

EXCAVATION BELOW

& REVEGETATE LANDSCAPE ZONE TO PROVIDE FILTER AREA - STAGE 1

DETAIL SD6-8

STOCK PILE (SD4-1)

WITH DETAIL SD4-1

SUGGESTED LOCATION.

CONSTRUCT IN ACCORDANCE

INSTALL DEVICE AROUND EXISTING GRATED PIT

- DASHED LINE DENOTES **BOUNDARY LINE**

Timber spacer to suit

Install filters to kerb inlets only at sag points.
Fabricate a sleeve made from geotextile or wire mesh longer than the length of the inlet pit


and fill it with 25 mm to 50 mm gravel. Form an elliptical cross-section about 150 mm high x 400 mm wide.

Place the filter at the opening leaving at least a 100-mm space between it and the kerb

inlet. Maintain the opening with spacer blocks. Form a seal with the kerb to prevent sediment bypassing the filter.

Sandbags filled with gravel can substitute for the mesh or geotextile providing they are placed so that they firmly abut each other and sediment-laden waters cannot pass

MESH AND GRAVEL INLET FILTER SD 6-11



Construction Notes

- Strip the topsoil, level the site and compact the subgrade.
- Cover the area with needle-punched geotextile.
- Construct a 200 mm thick pad over the geotextile using road base or 30 mm aggregate. Ensure the structure is at least 15 metres long or to building alignment and at least 3 metres wide.

Where a sediment fence joins onto the stabilised access, construct a hump in the stabilised access

to divert water to the sediment fence.

SD 6-14

MB GB 09.11.1 P3 RE-ISSUED FOR DA AMENDED ARCH, LAYOUT P2 ISSUED FOR DA MB GB 31.05.16 MB GB 18.05.16 P1 PRELIMINARY ISSUE Rev. Issue / Amendment By App. Date



PARTRIDGE HYDRAULIC SERVICES ABN 11 608 027 578 Level 5, 1 Chandos Street, St Leonards NSW 2065 Australia t 612 9460 9000 f 612 9460 9090 e partridge@partridge.com.au www.partridge.com.au

HYDRAULIC SERVICES

DUNNET PROPERTIES PTY LTD

NETTLETONTRIBE ARCHITECTS 117 WILLOUGHBY ROAD, CROWS NEST

TEL: 9431 6431 WEB: nettletontribe.com.au

MIXED USE DEVELOPMENT 44 - 48 OXFORD STREET **EPPING**

STORMWATER DRAINAGE SERVICES **SOIL & WATER MANAGEMENT PLAN**

THIS DRAWING HAS BEEN ASSIGNED CODE. THE PRESENCE OF THIS CODE CERTIFIED DRAWING ISSUED FOR COT	AN ELECTRONIC SIGNATURE SIGNIFIES THAT THIS IS THE	DO NOT SCALE DRAWING USE FIGURED DIMENSION	-
Electronic Code	Signature D	ate Designed	
Scale at A1	Date	Drawn	
1:250	MAY 201	6 S.P/S.D	

2015H0038 SWDA 8.1

PRELIMINARY - NOT FOR CONSTRUCTION

Backfill the trench over the base of the fabric and compact it thoroughly over the geotextile. **SD 6-8** STABILISED SITE ACCESS

Removable baffle Collected runoff to be dosed where soils are 'Type D' before disposal **Construction Notes** Join the inlet to the stormwater, taking any suitable steps to remove bulky or coarse material before it can enter the tank. Connect the outlet to a safe disposal area following the SWMP. Install a removable baffle, central to the inflow/outflow and normal to the direction of flow, ensuring that it reaches 500 mm below the invert of the outlet pipe. Install a cover over the pit with an observation port and access cover.

500mm

1 500 mm min.

Length/width Plan View ratio 3:1 min. Original ground level - Sediment settling zone 600 mm min. Water depth 1500mm min. - Cut-off trench 600 mm Cross-section min. depth backfilled with impermeable clay and compacted **Construction Notes** embankment extending to a point on the gully wall level with the riser crest. Maintain the trench free of water and recompact the materials with equipment as specified in the SWMP to 95 per cent Standard Proctor Density.

- Remove all vegetation and topsoil from under the dam wall and from within the storage
- Construct a cut-off trench 500 mm deep and 1,200 mm wide along the centerline of the
- Select fill following the SWMP that is free of roots, wood, rock, large stone or foreign Prepare the site under the embankment by ripping to at least 100 mm to help bond
- compacted fill to the existing substrate. Spread the fill in 100 mm to 150 mm layers and compact it at optimum moisture content
- following the SWMP.
- Construct the emergency spillway. 8. Rehabilitate the structure following the SWMP.

EARTH BASIN - WET SD 6-4 (APPLIES TO 'TYPE D' AND 'TYPE F' SOILS ONLY)