





LEGEND

	SITE BOUNDARY
	EXISTING CONTOUR
	PROPOSED NEW CONTOUR

	EXISTING TREE
	TREE PROTECTION ZONE
	STRUCTURE PROTECTION ZONE
	EXISTING SPOT LEVEL
	PROPOSED SPOT LEVEL

	EXISTING TREE TO BE REMOVED
	EXISTING TREE TO BE TRANSPLANTED
	TRANSPLANTED TREE RELOCATED ON SITE

	TOP OF WALL LEVEL
	TOP OF SLAB LEVEL
	PLANTING ON CONCRETE SLAB
	PLANTING ON GRADE

	ARTIFICIAL TURF
	TURF ON NATURAL GROUND
	PAVING TYPE 1

	PAVING GRAVEL MAINTENANCE PATH
	PROPOSED SHRUBS
	PROPOSED GROUNDCOVERS

	RAISED PLANTER
	SEAT
	PROPOSED TREES

E	FOR DA APPROVAL	07.04.2017
D	FOR DA APPROVAL	03.04.2017
C	DEVELOPMENT APPLICATION	21.07.2016
B	AMENDED OVERLAND FLOW	08.07.2016
A	DEVELOPMENT APPLICATION	30.06.2016
PT	PRELIMINARY DRAFT	21.06.2016
ISSUE	DESCRIPTION	DATE

PROJECT: ESTIA HEALTH ST. IVES  
144-146 KILLEATON STREET

DRAWING TITLE: GROUND FLOOR MASTER PLAN

SCALE: 1:200 @B1

CHECKED: DMT

JOB NO: 16-058

DESIGNED: JMT

DRAWING NO: LA02

REVISION: E


0 2 4 8 12 16 20 m

Copyright of Taylor Brammer Landscape Architects Pty Ltd  
APN 61 008 724 988












1 MASS PLANTING BED (DRIPPER IRRIGATION DETAIL)  
TYPICAL SECTION 1:10




2 TREE PLANTING (75L)  
TYPICAL SECTION 1:20



3 RAISED PLANTER BOX  
TYPICAL SECTION 1:10




4 TURF  
SECTION 1:20



5 ARTIFICIAL TURF  
TYPICAL SECTION 1:20












PLANT SCHEDULE (ROOF TOP GARDEN)

ID	BOTANICAL NAME	COMMON NAME	HEIGHT (m)	SPREAD (m)	SIZE	QTY
<strong>TREES</strong>						
Ch-li	<i>Citrus latifolia</i>	Persian Lime	3m			2
Ci-me	<i>Citrus x meyeri</i> 'Lemon Meyer'	Lemon Meyer	3m			2
Hi-ru	<i>Hibiscus tiliaceus rubra</i>	Red Cottonwood	8m	5m		3
Pl-ru	<i>Plumeria rubra</i>	Frangipanis	3m		100L	1
Sy-pi	<i>Syzygium australe</i> 'Pinnacle'	Syzygium	6-10m		45L	3
Ba-in	<i>Banksia integrifolia</i>	coast banksia	6m	4m		6
Ce-av	<i>Cercis chinensis</i> 'Avondale'	Avondale Chinese Redbud	3m	2m	75L	6
Mi-fi	<i>Magnolia figo</i>	Michelia figo	3-4m	1-2m	45L	21
Ma-te	<i>Magnolia grandiflora</i> 'Teddy Bear'	Teddy Bear	4m	3m	150L	2
Vi-od	<i>Viburnum odoratissimum</i>	Sweet Viburnum	4m	3m	45L	7
Ci-au	<i>Citrus reticulata</i> 'Mandarin Emperor'	Mandarin Emperor	3-5m			1
<strong>SHRUBS</strong>						
Ca-gb	<i>Callistemon salignus</i> 'Great Balls of Fire'	Bottlebrush	1.5m	1.5m	300mm	8
Hi-au	<i>Hibiscus rosa-sinensis</i> 'Suffrider'	Tropical Hibiscus			200mm	17
Lu-ma	<i>Leucadendron</i> 'Maui Sunset'					3
Lu-pu	<i>Leucadendron galpinii</i> female Purple Haze	Purple Haze	1.2m	1.2m		3
Rh-ex	<i>Rhapis excelsa</i>	Lady Palm	1.5m	2m	400mm	2
La-zu	<i>Lagerstroemia indica</i> x L. 'fauriei' 'Zuni'	Zuni Crepe Myrtle	4m	3m	75L	3
Rh-op	<i>Raphiolepis indica</i> 'Oriental pearl'	Raphiolepis Oriental Pearl	1m	1m	200mm	40
La-de	<i>Lavandula dentata</i>	Indian Hawthorn				
		French lavender	60 cm			3
<strong>GROUNDCOVERS</strong>						
Li-ev	<i>Liriope muscari</i> 'Evergreen Giant'	Turf Lily	40cm	40cm	150mm	5
Vi-co	<i>Vitis coignetiae</i>	Crimson Glory Vine				2
Ro-pr	<i>Rosmarinus officinalis</i> 'Prostratus'	Rosemary	0-0.5	200mm	200mm	39
Tr-ja	<i>Trachelospermum jasminoides</i>	Star Jasmine			150mm	12

NOTE: \* Plant quantities on planting plan take precedence over quantities identified in this schedule.



LEGEND



ISSUE	DESCRIPTION	DATE
E	FOR DA APPROVAL	07.04.2017
D	FOR DA APPROVAL	03.04.2017
C	DEVELOPMENT APPLICATION	21.07.2016
B	AMENDED OVERLAND FLOW	08.07.2016
A	DEVELOPMENT APPLICATION	27.06.2016
P1	PRELIMINARY DRAFT	21.06.2016

PROJECT  
ESTIA HEALTH ST. IVES  
144-148 KILLEATON STREET

DRAWING TITLE:  
ON SLAB/ON GRADE SOIL PLAN



SCALE	CHECKED	DESIGNED	DRAWING NO.	REVISION
1:200 (B1)	DMT	JM	LA05	E
CREATED: 20.06.2016				
DRAWN: CG				





1 YARRABUNG ROAD STREETSCAPE  
ELEVATION @1:200




2 KILLEATON ROAD STREETSCAPE  
ELEVATION @1:200



3 COLLEGE CRESENT STREETSCAPE  
ELEVATION @1:200

NB: EXISTING TREES ARE SHOWN AT CURRENT HEIGHT WHILE PROPOSED PLANTINGS ARE SHOWING AT MATURE SIZE




















SUMMARY OF TREE RETENTION AND REMOVAL

Refer to "Tree Report, Preliminary Tree Assessment", prepared by:  
Stuart Pittendrigh FALA MAH M. Arb Aust.  
Registered Landscape Architect  
Horticulturist/Consultant Arborist  
Date: 19 July 2015

NOTE: "" = Refer to Tree Nominated Arborist for Removal  
"" = Remove to accommodate DA 2338/16

ID	BOTANICAL NAME	COMMON NAME	HEIGHT (m)	SPREAD (m)
<strong>TREES/ SHRUBS TO BE RETAINED</strong>				
1	Liquidambar orientalis	Oriental sweet gum	11	9
2	Liquidambar orientalis	Oriental sweet gum	11	9
6	Liquidambar styraciflua	Sweet gum	15	10
7	Pistacia chinensis	Chinese Pistachio	4.5	7
8	Liquidambar styraciflua	Sweet gum	16	13
9	Liquidambar styraciflua	Sweet gum	11	12
10	Agathis robusta	Queensland Kauri	23	7
23	Pistacia chinensis	Chinese Pistachio	5	7
26	Archontophoenix alexandrae	Alexander palm	6	4
27	Araucaria heterophylla	Norfolk Island pine	12	4
28	Angophora costata	Smooth bark apple	9	1.5
30	Arecastrum romanzoffianum	Queen palm	10	5
31	Araucaria heterophylla	Norfolk Island pine	11	4.5
32	Araucaria heterophylla	Norfolk Island pine	9	4
33	Eucalyptus paniculata	Grey iron bark	18	15
34	Melaleuca quinquenervia	Broad leaf paper-bark	8	4
36	Tristaniopsis laurina	Water gum	11	9
38	Melaleuca quinquenervia	Broad leaf paper-bark	15	9
39	Corymbia gummifera	Red blood wood	11	2.5
40	Eucalyptus saligna	Sydney Blue gum	8	3
41	Eucalyptus saligna	Sydney Blue gum	12	4
43	Tristaniopsis laurina	Water gum	6	7
44	Tristaniopsis laurina	Water gum	9	10
45	Tristaniopsis laurina	Water gum	7	8
48	Eucalyptus scoparia	Willow gum	17	15
49	Ulmus procera 'Louis van Houtte'	Golden elm	4	10
50	Ulmus procera 'Louis van Houtte'	Golden elm	4	6
67	Eucalyptus saligna	Sydney Blue gum	20	20
68	Eucalyptus saligna	Sydney Blue gum	33	22
69	Liquidambar orientalis	Oriental sweet gum	99	0
70	Angophora costata	Smooth bark apple	18	17
<strong>TREES / SHRUBS TO BE REMOVED</strong>				
3	Lophostemon confertus**	Brushbox	11	10
4	Magnolia grandiflora 'Exmouth'	'Exmouth'	4	4
5	Franklinia avicularis *	Fried - egg tree	5	4
11	Eucalyptus scoparia *	Willow gum	17	13
12	Cupressus species *	Cypress tree	16	5
13	Arbutus unedo *	Strawberry tree	8	7
14	Eucalyptus scoparia *	Willow gum	13	6
15	Liquidambar styraciflua*	Sweet gum	9	7
16	Eucalyptus scoparia *	Willow gum	15	7
17	Cedrus deodara *	Himalayan cedar	17	11
18	Cupressus species *	Cypress tree	12	4
19	Cupressus species *	Cypress tree	12	4
20	Cupressus species *	Cypress tree	12	3
21	Harpephyllum cafrum *	Kaffir-plum	11	9
22	Harpephyllum cafrum *	Kaffir-plum	11	7
24	Harpephyllum cafrum *	Kaffir-plum	11	8
35	Eucalyptus scoparia *	Willow gum	14	16
37	Jacaranda mimosifolia *	Jacaranda tree	8	3
42	Tecoma stans *	Yellow bells	10	6
46	Harpephyllum cafrum*	Kaffir-plum	9	11
47	Eucalyptus robusta *	Swamp mahogany	19	11
51	Cupressus sempervirens 'Swanes G'	Swane's golden cypret	8	1.5
52	Arecastrum romanzoffianum*	Queen palm	9	5
57	Celtis occidentalis *	Hackberry	9	10
58	Callistemon viminalis*	Callistemon viminalis	6	6
59	Tibouchina lepidota*	Lasiandra	6	8
60	Arecastrum romanzoffianum*	Queen palm	8	5
61	Celtis occidentalis*	Hackberry	17	15
62	Cupressus species*	Cypress tree	12	2
63	Cupressus species*	Cypress tree	15	3
64	Cupressus species*	Cypress tree	15	3
65	Cupressus species*	Cypress tree	15	3
66	Eucalyptus scoparia *	Willow gum	16	10
71	Acer negundo*	Box elder 3094	9	8
74	Arecastrum romanzoffianum*	Queen palm	8	3
75	Arecastrum romanzoffianum*	Queen palm	7	3
76	Arecastrum romanzoffianum*	Queen palm	9	4
77	Arecastrum romanzoffianum*	Queen palm	7	4
78	Syzygium australe *	Lillypilly spp.	12	5
<strong>TREES / SHRUBS TO BE TRANSPLANTED</strong>				
25	Arecastrum romanzoffianum	Queen palm	10	5
29	Arecastrum romanzoffianum	Queen palm	15	5
53	Camellia japonica	Camellia	4	3
54	Camellia reticulata	reticulata	4	3
55	Camellia reticulata	reticulata	4.5	3
56	Camellia japonica	Camellia	4.5	3
72	Howea forsteriana	Kentia palm	7	4.5
73	Howea forsteriana	Kentia palm	6	4.5

LEGEND




PROJECT  
ESTIA HEALTH ST. IVES  
144-148 KILLEATON STREET

DRAWING TITLE:  
TREE RETENTION AND REMOVAL

0 2 4 8 12 16 20 m

SCALE: 1:200 (B81)  
DATE: 20/06/2016  
DRAWN: CS  
CHECKED: DMT  
JOB NO: 160408  
DESIGNED: JH  
DRAWING NO:  
REVISION:  
LA01  
E





This drawing is copyright and is the property of TAYLOR THOMSON WHITTING (NSW) Pty Ltd and must not be used without authorisation.

## STORMWATER DRAINAGE NOTES

- Stormwater Design Criteria :
  - Average recurrence interval -
    - 1:100 years for roof drainage to first external pit
    - 1:20 years for paved and landscaped areas
  - Rainfall intensities
    - Time of concentration: 6 minutes
    - 1:100 years = 250 mm/hr
    - 1:20 years = 196 mm/hr
  - Runoff coefficients -
    - Roof areas:  $C_{ro} = 1.0$
    - Roads and paved areas:  $C_{ra} = 0.95$
    - Landscaped areas:  $C_{la} = 0.60$
- Pipes 300 dia and larger to be reinforced concrete Class "2" approved spigot and socket with rubber ring joints U.N.O.
- Pipes up to 300 dia shall be sewer grade uPVC with solvent welded joints.
- Equivalent strength VCP or FRP pipes may be used subject to approval.
- Precast pits may be used external to the building subject to approval by Engineer.
- Enlargers, connections and junctions to be manufactured fittings where pipes are less than 300 dia.
- Where subsoil drains pass under floor slabs and vehicular pavements, unslotted uPVC sewer grade pipe is to be used.
- Grates and covers shall conform with AS 3996-2006, and AS 1428.1 for access requirements.
- Pipes are to be installed in accordance with AS 3725. All bedding to be type H2 U.N.O.
- Care is to be taken with levels of stormwater lines. Grades shown are not to be reduced without approval.
- All stormwater pipes to be 150 dia at 1.0% min fall U.N.O.
- Subsoil drains to be slotted flexible uPVC U.N.O.
- Adopt invert levels for pipe installation (grades shown are only nominal).

## SITEWORKS LEGEND

- Stormwater diversion with pit
- Stormwater line with pit
- Proposed Easement
- Overland flow path


## NOTE

100 YEAR ARI STORM EVENT FLOW TO BE DIRECTED TO DETENTION TANK

## TREE PROTECTION NOTES

- Refer to Arborist Report prior to commencement of any works on site.
- Trees to be retained and managed throughout the development shall be fenced off from the proposed development or in some situations depending on site access may require trunk protection as detailed in Section 4 - Tree Protection Measures of AS4970 - 2009 The Protection of Trees on Development Sites or in some situation the existing boundary fence shall be retained throughout proposed development so as to provide tree protection barrier.
- Demolition works within the TPZ of trees to be preserved shall be carried out so as to avoid damage to the roots. In sensitive areas manual excavation may be necessary. Manual excavation shall be by hand under the direction of the project arborist.
- Where the project arborist identifies roots to be pruned within or at the outer edge of the TPZ, they should be pruned with a final cut to undamaged wood. Pruning cuts should be made with sharp tools such as secateurs, pruners, hand saws or chainsaws. Pruning wounds should not be treated with dressings or paints. It is totally unacceptable for roots within the TPZ to be 'pruned' with machinery such as backhoes or excavators.
- Where roots within the TPZ are exposed by excavation, temporary root protection should be installed to prevent them drying out. This may include jute mesh or hessian sheeting as multiple layers over exposed roots and excavated soil profile, extending to the full depth of the root zone. Root protection sheeting should be pegged in place and kept moist during the period that the root zone is exposed.
- All areas enclosed by protective fencing must have the entire ground surface mulched to a depth of 100 mm with composted Eucalyptus leaf and woodchip to help retain soil moisture and reduce erosion.
- Any site activity close to or beneath the drip line of Trees 10, 47 and 70 shall have elevated protection installed clear of the ground to avoid compaction and damage to roots. Protection may comprise timber planks or metal decking supported on scaffolding or the like.
- Hydraulic plans have provided by the applicant indicate that sub soil stormwater and sewer lines may need to be installed within the TPZ of trees nominated for preservation. Trenching for stormwater / sewer installation within the TPZ and SRZ shall be avoided. Adopt directional drilling / approved under boring techniques as per Section 4 of AS4970 CL4.4.5 to avoid adverse impacts on tree roots.
- The directional drilling bore should be at least 600 mm deep. The project arborist shall assess the likely impacts of boring and bore pits on retained trees. Bore pits within the TPZ shall be hand dug under the direction of an Arborist. No excavation shall occur within the Structural Root Zones of trees nominated for preservation.

# PRELIMINARY



P6	ISSUED FOR DA	PY	PK	30.06.16	P12	ISSUED FOR DA	QC	RG	06.04.17
P5	ISSUED FOR DA	PY	PK	30.06.16	P11	ISSUED FOR DA	PY	PK	22.07.16
P4	ISSUED FOR DA	PY	PK	29.06.16	P10	ISSUED FOR REVIEW	PY	PK	22.07.16
P3	ISSUED FOR DA	PY	PK	24.06.16	P9	ISSUED FOR COORDINATION	PY	PK	21.07.16
P2	ISSUED FOR COORDINATION	PY	PK	24.06.16	P8	ISSUED FOR COORDINATION	PY	PK	11.07.16
P1	ISSUED FOR COMMENT	PY	PK	10.06.16	P7	ISSUED FOR DA	PY	PK	01.07.16
Rev	Description	Eng	Draft	Date	Rev	Description	Eng	Draft	Date

Architect  
**Morrison Design Partnership**  
302/69 Christie Street,  
St Leonards, NSW 2065  
E: morrisondesign@mdpa.com.au  
P: 02 9966 5566


Structural Engineer  
**TTW Taylor Thomson Whitting**  
612 9439 7288 | 48 Chandos Street St Leonards NSW 2065

Project  
**ESTIA HEALTH DEVELOPMENT**  
144 Killeaton Street St Ives


Sheet Subject  
**STORMWATER PLAN**

Scale : A1  
1:250  
Job No  
**151553**  
Plot File Created: Apr 07, 2017 - 1:35pm  
Drawn  
**PK**  
Drawing No  
**SKC01**  
Authorised  
**P12**  
Revision






TRASH SCREEN DETAIL  
NTS




SECTION 1  
SCALE 1:20




DISCHARGE CONTROL PIT

PLAN  
SCALE 1: 20




SECTION THROUGH DETENTION TANK

SECTION 02  
SCALE 1:20 SKC01




SECTION THROUGH DETENTION TANK

SECTION 03  
SCALE 1:20 SKC01



SECTION 03  
SCALE 1:50 SKC01



ORIFICE PLATE DETAIL  
SCALE 1: 5

Filename: SKC02.dwg - User: gmac - Plot File Created: Apr 06, 2017 - 5:45pm

P6	ISSUE FOR DA	GC	RG	06.04.17					
P5	ISSUE FOR DA	PY	PK	22.07.16					
P4	ISSUE FOR COORDINATION	PY	PK	21.07.16					
P3	ISSUE FOR DA	PY	PK	29.06.16					
P2	ISSUE FOR DA	PY	PK	24.06.16					
P1	PRELIMINARY	PY	PK	10.06.16					
Rev	Description	Eng	Draft	Date	Rev	Description	Eng	Draft	Date

Architect	302/69 Christie Street, St Leonards, NSW 2065 E: morrisondesign@mdpa.com.au P: 02 9966 5566
<b>Morrison Design Partnership</b>	


Structural Engineer	612 9439 7288   48 Chandos Street St Leonards NSW 2065
<b>TTW</b>	
<b>Taylor Thomson Whitting</b>	

Project	ESTIA HEALTH DEVELOPMENT 144 Killeaton Street St Ives
Sheet Subject	DETAILS SHEET 1 OF 2

Scale : A1 AS SHOWN	Drawn RG	Authorised
Job No 151553	Drawing No SKC02	Revision P6
Plot File Created: Apr 06, 2017 - 5:45pm		


PRELIMINARY






### TREE PROTECTION NOTES

- Refer to Arborist Report prior to commencement of any works on site.
- Trees to be retained and managed throughout the development shall be fenced off from the proposed development or in some situations depending on site access may require trunk protection as detailed in Section 4 - Tree Protection Measures of AS4970 - 2009. The Protection of Trees on Development Sites or in some situation the existing boundary fence shall be retained throughout proposed development so as to provide tree protection barrier.
- Demolition works within the TPZ of trees to be preserved shall be carried out so as to avoid damage to the roots. In sensitive areas manual excavation may be necessary. Manual excavation shall be by hand under the direction of the project arborist.
- Where the project arborist identifies roots to be pruned within or at the outer edge of the TPZ, they should be pruned with a final cut to undamaged wood. Pruning cuts should be made with sharp tools such as secateurs, pruners, hand saws or chainsaws. Pruning wounds should not be treated with dressings or paints. It is totally unacceptable for roots within the TPZ to be 'pruned' with machinery such as backhoes or excavators.
- Where roots within the TPZ are exposed by excavation, temporary root protection should be installed to prevent them drying out. This may include jute mesh or hessian sheeting as multiple layers over exposed roots and excavated soil profile, extending to the full depth of the root zone. Root protection sheeting should be pegged in place and kept moist during the period that the root zone is exposed.
- All areas enclosed by protective fencing must have the entire ground surface mulched to a depth of 100 mm with composted Eucalyptus leaf and woodchip to help retain soil moisture and reduce erosion.
- Any site activity close to or beneath the drip line of Trees 10, 47 and 70 shall have elevated protection installed clear of the ground to avoid compaction and damage to roots. Protection may comprise timber planks or metal decking supported on scaffolding or the like.
- Hydraulic plans have provided by the applicant indicate that sub soil stormwater and sewer lines may need to be installed within the TPZ of trees nominated for preservation. Trenching for stormwater / sewer installation within the TPZ and SFZ shall be avoided. Adopt directional drilling / approved under boring techniques as per Section 4 of AS4970 QL4.4.5 to avoid adverse impacts on tree roots.
- The directional drilling bore should be at least 600 mm deep. The project arborist shall assess the likely impacts of boring and bore pits on retained trees. Bore pits within the TPZ shall be hand dug under the direction of an Arborist. No excavation shall occur within the Structural Root Zones of trees nominated for preservation.




### SILTATION FENCE DETAIL

SCALE 1: 20




### SEDIMENTATION TRAP

NTS




### SANDBAG KERB INLET SEDIMENT TRAP

NTS



### GEOTEXTILE PIT FILTER

NTS




### TYPICAL SECTION THROUGH CATCH DRAIN

SCALE 1: 20

### TEMPORARY CONSTRUCTION VEHICLE EXIT

NTS



### WATER QUALITY TESTING REQUIREMENTS

Prior to discharge of site stormwater, groundwater and seepage water into council's stormwater system, contractors must undertake water quality tests in conjunction with a suitably qualified environment consultant outlining the following:

- Compliance with the criteria of the Australian and New Zealand Guidelines for Fresh and Marine Water Quality (2000)
- If required subject to the environmental consultants advice, provide remedial measures to improve the quality of water that is to be discharged into Councils storm water drainage system. This should include comments from a suitably qualified environmental consultant confirming the suitability of these remedial measures to manage the water discharged from the site into Councils storm water drainage system. Outlining the proposed, ongoing monitoring, contingency plans and validation program that will be in place to continually monitor the quality of water discharged from this site. This should outline the frequency of water quality testing that will be undertaken by a suitably qualified environmental consultant.

### EROSION AND SEDIMENT CONTROL LEGEND

- Siltation fence
- Stormwater pit with Geotextile filter surround
- Sandbag sediment trap
- Catch drain

## PRELIMINARY

P6	ISSUE FOR DA	GC	RG	06.04.17			
P5	ISSUE FOR DA	PY	PK	22.07.16			
P4	ISSUE FOR COORDINATION	PY	PK	21.07.16			
P3	ISSUE FOR DA	PY	PK	29.06.16			
P2	ISSUE FOR DA	PY	PK	24.06.16			
P1	PRELIMINARY	PY	PK	10.06.16			
Rev	Description	Eng	Draft	Date	Rev	Description	Eng

Architect  
**Morrison Design Partnership**  
302/69 Christie Street,  
St Leonards, NSW 2065  
E: morrisondesign@mdp.com.au  
P: 02 9966 5566

302/69 Christie Street,  
St Leonards, NSW 2065  
E: morrisondesign@mdp.com.au  
P: 02 9966 5566

Structural Engineer  
**TTW** Taylor Thomson Whitting  
612 9439 7288 | 48 Chandos Street St Leonards NSW 2065


Project  
**ESTIA HEALTH DEVELOPMENT**  
144 Killeaton Street St Ives

Sheet Subject  
**ENVIRONMENTAL SITE MANAGEMENT PLAN**

Scale: A1  
1:250  
Drawn: RG  
Authorised:  
Job No: 151553  
Drawing No: SKC03  
Revision: P6  
Plot File Created: Apr 06, 2017 - 4:12pm



Scale : A1	Drawn	Authorised
1:250	PK	
Job No	Drawing No	Revision
151553	SKC04	P6
Plot File Created: Apr 06, 2017 - 4:13pm		



Sheet Subject
<b>BULK EARTHWORKS PLAN</b>