


BYRON SHIRE COUNCIL
BYRON BAY PUBLIC SCHOOL
PROPOSED SCHOOL UPGRADE
CONCEPT STORMWATER MANAGEMENT PLANS

Prepared for: Department Of Education

GENERAL NOTES

- 1. ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH BYRON BAY COUNCIL'S CIVIL CONSTRUCTION SPECIFICATION AND TO THE SATISFACTION OF THE DIRECTOR OF DEVELOPMENT.
- 2. ALL EROSION AND AND SEDIMENTATION CONTROL MEASURES ARE TO BE CARRIED OUT IN ACCORDANCE WITH COUNCILS CODE OF PRACTICE FOR EROSION AND SEDIMENTATION AND MUST BE IMPLEMENTED PRIOR TO THE COMMENCEMENT OF ANY BUILDING OF CIVIL WORKS.
- 3. ALL PUBLIC UTILITIES ARE TO BE CLEARLY IDENTIFIED IN THE FIELD PRIOR TO ANY CIVIL WORKS. COUNCIL DOES NOT ACCEPT ANY RESPONSIBILITY FOR DAMAGE OR RELOCATION COSTS TO PUBLIC UTILITIES DURING CONSTRUCTION OF THE DEVELOPMENT.
- 4. BYRON BAY COUNCIL ARE TO BE NOTIFIED 48 HOURS PRIOR TO THE COMMENCEMENT OF ANY WORKS.
- 5. IT IS THE CONTRACTORS RESPONSIBILITY TO ENSURE THAT ALL WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE WORKPLACE HEALTH & SAFETY ACT 2011.
- 6. THE DEVELOPER IS RESPONSIBLE FOR ONGOING MAINTENANCE OF EROSION AND SEDIMENT CONTROL MEASURES.
- 7. THESE PLANS ARE TO BE READ IN CONJUNCTION WITH THE CONDITIONS STATED IN BYRON BAY COUNCIL'S ENGINEERING PLAN APPROVAL CORRESPONDENCE AND THE CONDITIONS OF THE DEVELOPMENT CONSENT.

LOCATION OF WORKS




LOCALITY SKETCH
NOT TO SCALE

SHEET INDEX


SHEET No.	DESCRIPTION
1	COVER SHEET - GENERAL NOTES, SHEET INDEX AND LEGEND
2	CONCEPT STORMWATER MANAGEMENT PLAN
3	EROSION & SEDIMENT CONTROL PLAN
4	EROSION & SEDIMENT CONTROL DETAILS

LEGEND

- PROPOSED ROOF DRAINAGE LINE
- PROPOSED DRAINAGE LINE
- NATURAL SURFACE CONTOUR
- PIT 1/2
- PIT NUMBER
- GRATED SURFACE INLET PIT
- SEALED PIT
- DOWN PIPE SIZE & LOCATION



CONCEPT DESIGN ONLY
SUBJECT TO FINAL DESIGN
NOT TO BE USED FOR
CONSTRUCTION



1 & 2
DP 758207



SYDNEY
P. 02 9659 0005
CENTRAL COAST
P. 02 4325 6255
HUNTER
P. 02 4966 8388
ABN: 26 134 067 842
barkerryanstewart.com.au
mail@barkerryanstewart.com.au



BYRON BAY PUBLIC SCHOOL SCHOOL UPGRADE

CONCEPT STORMWATER DRAINAGE PLAN

Designed: NZ
Drawn: NZ
Checked: AD

Scales: Plan 1:200
Horiz.
Vert.
X-Sect.
Datum: A.H.D.

Plan No.
160169E1.02

File Ref.
CC160169E1.dwg
SHEET 2 OF 4 SHEETS

REV.
B

EROSION AND SEDIMENTATION CONTROL NOTES

1. PRIOR TO THE COMMENCEMENT OF SITE DISTURBANCE, THE CONTRACTOR SHALL ESTABLISH ALL NECESSARY EROSION AND SEDIMENTATION CONTROL MEASURES IN ACCORDANCE WITH THIS PLAN, COUNCIL'S "CIVIL WORKS SPECIFICATION, PART 2 -CONSTRUCTION", AND THE NSW DEPARTMENT OF HOUSING'S PUBLICATION "MANAGING URBAN STORMWATER - SOILS AND CONSTRUCTION".
2. THE LOCATION OF EROSION AND SEDIMENTATION CONTROL DEVICES SHOWN ON THIS PLAN ARE INDICATIVE ONLY AND SHOULD BE ADJUSTED TO SUIT SITE CONDITIONS.
3. WHERE WORKS ARE DELAYED OR IN ABEYANCE AND DISTURBED AREAS ARE LIKELY TO BE EXPOSED FOR A PERIOD OF TWO MONTHS OR MORE, TEMPORARY REHABILITATION WORKS SHALL BE UNDERTAKEN TO PROTECT THE SITE.
4. ALL DISTURBED AREAS SHALL BE TOP SOILED, SEEDED AND MULCHED WITHIN 20 DAYS OF THE COMPLETION OF THE WORKS.
5. THE CONTRACTOR SHALL CONDUCT WEEKLY INSPECTIONS OF THE SITE TO ENSURE THAT ALL DEVICES AND REHABILITATION AREAS HAVE BEEN ADEQUATELY MAINTAINED. THE CONTRACTOR SHALL ALSO KEEP A LOG BOOK DETAILING SUCH INSPECTIONS, AND RECORDING RAINFALL EVENTS AND OTHER RELEVANT EVENTS.
6. TOPSOIL SHALL BE STOCKPILED IN THE LOCATIONS SHOWN ON THIS PLAN OR AS DIRECTED BY COUNCIL'S ENGINEER. WHERE IT IS LIKELY THAT STOCKPILES WILL REMAIN IN PLACE FOR A PERIOD EXCEEDING 4 WEEKS, THEN THE STOCKPILE SHALL BE STABILISED BY SEEDING OR EQUIVALENT METHODS.
7. ALL REVEGETATION WORKS ARE TO BE MAINTAINED, INCLUDING WATERING AND MOWING WHERE NECESSARY UNTIL THE COMPLETION OF THE MAINTENANCE PERIOD.
8. THE MOVEMENT OF VEHICULAR TRAFFIC ON THE SITE SHALL BE CONFINED TO DESIGNATED AREAS DURING CONSTRUCTION WORKS. VEHICULAR ACCESS SHALL BE DENIED TO AREAS TO BE LEFT UNDISTURBED.
9. SITE ACCESS SHALL BE LIMITED TO THE LOCATIONS SHOWN ON THIS PLAN. SHAKE-DOWN AREAS SHALL BE CONSTRUCTED AS SHOWN.
10. DURING CONSTRUCTION WORKS, DUST CONTROL MEASURES SHALL BE IMPLEMENTED TO MINIMISE THE AMOUNT OF DUST GENERATED FROM THE SITE. THESE MEASURES TO BE IMPLEMENTED TO COUNCIL'S SATISFACTION.
11. MAINTENANCE AND CLEANING OF CONSTRUCTION PLANT SHALL BE CARRIED OUT IN AN AREA WHERE RUNOFF CAN BE CONTAINED AND APPROPRIATELY TREATED AND DISPOSED OF.
12. ALL EROSION AND SEDIMENTATION CONTROL DEVICES SHALL REMAIN IN PLACE UNTIL ALL DISTURBED AREAS HAVE ADEQUATELY REGENERATED. THIS STAGE SHALL BE DETERMINED BY THE CERTIFIER.

REY
THER

RY
RD


1 & 2
DP 758207

LEGEND

- SEDIMENT FENCE
- STABILISED SITE ACCESS AT ENTRANCE TO WORKS
- SURFACE INLET PIT SEDIMENT TRAP
- HAY BALE SEDIMENT TRAP
- MESH & GRAVEL 'SAUSAGE' FILTER

PROVIDE TRUCK
SHAKER GRID AT
SITE ACCESS POINT

CONSTRUCT SEDIMENT FENCE
AROUND SITE AS SHOWN
(REFER DETAIL).



EROSION & SEDIMENT CONTROL PLAN
SCALE 1:300



B	07/09/17	DA ISSUE
A	16/05/17	DRAFT ISSUE
No	DATE	AMENDMENT

**BARKER
RYAN
STEWART**

TOTAL PROJECT SOLUTIONS
PLANNING - PROJECT MANAGEMENT - ENGINEERING - CERTIFICATION

SYDNEY
P. 02 9659 0005
CENTRAL COAST
P. 02 4325 5255
HUNTER
P. 02 4966 8388
ABN: 26 134 067 842
barkerryanstewart.com.au
mail@barkerryanstewart.com.au

Client:

Education

BYRON BAY PUBLIC SCHOOL
SCHOOL UPGRADE

EROSION & SEDIMENT CONTROL PLAN

Designed: NZ
Drawn: NZ
Checked: AD

Scales: Plan 1:250
Horiz.
Vert.
X-Sect.

Datum: A.H.D.


Plan No.
160169E1.03

File Ref.
CC160169E1.dwg

SHEET 3 OF 4 SHEETS




REV.
B

A1



CONSTRUCTION NOTES








1. WHERE POSSIBLE LOCATE STOCKPILE AT LEAST 5 METRES FROM EXISTING VEGETATION, CONCENTRATED WATER FLOWS, ROADS, HAZARD AREAS AND MIN. 1.5m AWAY FROM EMBANKMENTS.
2. CONSTRUCT ON THE CONTOUR AS A LOW, FLAT ELONGATED MOUND.
3. WHERE THERE IS SUFFICIENT AREA TOPSOIL STOCKPILES SHALL BE LESS THAN 2 METRES IN HEIGHT.
4. REHABILITATE IN ACCORDANCE WITH THE SWMP/ESCP.
5. CONSTRUCT EARTH BANK (STANDARD DRAWING 5-5) ON THE UPSLOPE SIDE TO DIVERT RUN OFF AROUND THE STOCKPILE AND A SEDIMENT FENCE (STANDARD DRAWING 6-8) 1 TO 2 METRES DOWNSLOPE OF STOCKPILE.



CONSTRUCTION NOTES

1. FABRICATE A SLEEVE MADE FROM GEOTEXTILE OR WIRE MESH AND FILL IT WITH 25mm TO 50mm GRAVEL.
2. FORM AN ELLIPTICAL CROSS-SECTION ABOUT 150mm HIGH X 400mm WIDE.
3. FORM A SEAL WITH THE KERB TO PREVENT SEDIMENT BYPASSING FILTER.
4. SANDBAGS FILLED WITH GRAVEL CAN SUBSTITUTE FOR THE MESH OR GEOTEXTILE PROVIDING THEY ARE PLACED SO THAT THEY FIRMLY ABUT EACH OTHER AND SEDIMENT-LADEN WATERS CANNOT PASS BETWEEN.

MESH & GRAVEL FILTER "SAUSAGE" BARRIER



CONSTRUCTION NOTES

- | | |
|---|--|
| 1. STRIP TOPSOIL AND LEVEL SITE. | GEOTEXTILE FABRIC DESIGNED TO PREVENT INTERMIXING OF SUBGRADE AND BASE MATERIALS AND TO MAINTAIN GOOD PROPERTIES OF THE SUB-BASE LAYERS. |
| 2. COMPACT SUBGRADE. | |
| 3. COVER AREA WITH NEEDLE-PUNCHED GEOTEXTILE. | GEOFABRIC MAY BE A WOVEN OR NEEDLE PUNCHED PRODUCT WITH A MINIMUM CBR BURST STRENGTH (AS3706.4-90) OF 2500 N |
| 4. CONSTRUCT 200mm THICK PAD OVER GEOTEXTILE USING ROADBASE OR 30mm AGGREGATE. MINIMUM LENGTH 15 METRES OR TO BUILDING ALIGNMENT. MINIMUM WIDTH 3 METRES. | |
| 5. CONSTRUCT HUMP IMMEDIATELY WITHIN BOUNDARY TO DIVERT WATER TO A SEDIMENT FENCE OR OTHER SEDIMENT TRAP. | |

CONSTRUCTION NOTES

INSTALL FILTERS TO KERB INLET ONLY AT SAG POINTS.

1. FABRICATE A SLEEVE MADE FROM GEOTEXTILE OR WIRE MESH LONGER THAN THE LENGTH OF THE INLET PIT AND FILL IT WITH 25mm TO 50mm GRAVEL.
2. FORM AN ELLIPTICAL CROSS-SECTION ABOUT 150mm HIGH X 400mm WIDE.
3. PLACE THE FILTER AT THE OPENING LEAVING AT LEAST A 100mm SPACE BETWEEN IT AND THE KERB INLET MAINTAIN THE OPENING WITH SPACER BLOCKS.
4. FORM A SEAL WITH THE KERB TO PREVENT SEDIMENT BYPASSING FILTER.
5. SANDBAGS FILLED WITH GRAVEL CAN SUBSTITUTE FOR THE MESH OR GEOTEXTILE PROVIDING THEY ARE PLACED SO THAT THEY FIRMLY ABUT EACH OTHER AND SEDIMENT-LADEN WATERS CANNOT PASS BETWEEN.
- 6.

MESH & GRAVEL INLET "SAUSAGE" FILTER

TOPSOIL STOCKPILE

SURFACE INLET PIT SEDIMENT TRAP

STRAW BALE SEDIMENT FILTER

VEHICLE DUST SHAKE DOWN DETAIL

STRAW BALE & CRUSHED ROCK SEDIMENT FILTER

CATCH DRAIN DETAIL

CONSTRUCTION NOTES

1. CONSTRUCT SEDIMENT FENCE AS CLOSE AS POSSIBLE TO PARRALLEL TO THE CONTOURS OF THE SITE.
2. DRIVE 1.5m LONG STAR PICKETS INTO GROUND 2.5 METRES APART (MAX.)
3. DIG A 150mm DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM OF THE FABRIC TO BE ENTRENCHED.
4. FIX SELF-SUPPORTING GEOTEXTILE TO UPSLOPE SIDE OF POSTS WITH WIRE TIES OR AS RECOMMENDED BY GEOTEXTILE MANUFACTURER.
5. JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150mm OVERLAP.
6. BACKFILL THE TRENCH OVER THE BASE OF THE FABRIC AND COMPACT IT THOROUGHLY OVER THE GEOTEXTILE.

SECTION DETAIL

SEDIMENT FENCE

STABILISED SITE ACCESS

BYRON BAY PUBLIC SCHOOL
SCHOOL UPGRADE

EROSION & SEDIMENT CONTROL DETAILS

Designed:	AD
Drawn:	AD
Checked:	PM

Scales: Plan
Horiz.
Vert.
X-Sept.

Datum: A.H.D.

Plan No.
160117E1.04

File Ref. REV.
CC160169E1.dwg
SHEET 4 OF 4 SHEETS B

			 BARKER RYAN STEWART TOTAL PROJECT SOLUTIONS PLANNING - PROJECT MANAGEMENT - ENGINEERING - CERTIFICATION SYDNEY P: 02 9659 0005 CENTRAL COAST P: 02 4325 5255 HUNTER P: 02 4956 8388 ABN: 26 134 067 842 barkeryanstewart.com.au mail@barkeryanstewart.com.au
B	07/09/17	DA ISSUE	
A	16/05/17	DRAFT ISSUE	
No	DATE	AMENDMENT	

Client:

	Education
---	------------------

BYRON BAY PUBLIC SCHOOL SCHOOL UPGRADE

EROSION & SEDIMENT CONTROL DETAILS

Designed: AD	Scales: Plan	Plan No.	REV.
Drawn: AD	Horiz.	160117E1.04	
Checked: PM	Vert.	File Ref.	
	X-Sept.	CC160169E1.dwg	
Datum: A.H.D.		SHEET 4 OF 4 SHEETS	B