
CUNDALL

16 August 2017

Acoustic Report for DA Submission

1015587 - William Stimson Public School



JDH Architects

By Cundall Level 1, 48 Alfred Street Milsons Point, NSW 2061 Ph (02) 8424 7000 Fax (02) 8424 7099

> Please contact: Mark Evans



1015587-RPT-AS001 Acoustic Report for DA Submission

Author:	Mark Evans	M Zeans	-
Checked by:	Patrick Carpenter	-,	
Approved by:	Mark Evans	M Zeans	
Revision	Description		Date
-	First Issue for comment		12/07/2017
Α	Incorporating comments		16/08/2017

This report has been prepared in accordance with the terms and conditions of appointment. Cundall Johnston & Partners Pty Ltd trading as Cundall (ABN 16 104 924 370) cannot accept any responsibility for any use of or reliance on the contents of this report by any third party.

The success and realisation of the proposed initiatives will be dependent upon the commitment of the design team, the development of the initiatives through the life of the design and also the implementation into the operation of the building. Without this undertaking the proposed targets may not be achieved.

CUNDALL

William Stimson Public School

1015587-RPT-AS001 Acoustic Report for DA Submission

Contents

Exec	cutive Summary	1
1	Introduction	2
1.1	Proposed development	2
1.2	Design criteria	2
2	Site description	4
2.1	Existing site	4
2.2	Proposed site	5
3	Noise survey	7
3.1	Methodology	7
3.2	Conditions	7
3.3	Observations	8
3.4	Results	8
4	Internal acoustic criteria	11
4.1	Internal noise level targets	11
4.2	Applicable project-specific noise levels	11
4.3	Acoustic design recommendations	11
5	External plant noise emissions	13
5.1	Selection of noise sensitive receivers	14
5.2	Intrusiveness criteria	14
5.3	Amenity criteria	14
5.4	Applicable project-specific noise levels	15
5.5	Acoustic design recommendations	15
6	Consideration of activity noise	16
6.1	Current noise impacts	16
6.2	Potential noise impacts	16
6.3	Conclusion	16
7	Consideration of additional road traffic	17
7.1	Noise impact	17
72	Conclusion	17

Revision Date: 16/08/2017

CUNDALL

William Stimson Public School

1015587-RPT-AS001 Acoustic Report for DA Submission

8	Consideration of construction noise	18
8.1	Other measures	18
9	Conclusions	19



1015587-RPT-AS001 Acoustic Report for DA Submission

Executive Summary

This report presents acoustic input to the DA submission for the proposed development at William Stimson Public School.

The acoustic analysis has been undertaken based upon data from noise surveys at the site. Acoustic design targets have been determined, based on appropriate standards and guidelines to achieve acceptable noise levels for:

- Noise break-in to the development and internal noise levels;
- Noise break-out to the community.

Noise intrusion from the surroundings affecting the development, such as general road traffic, will be controlled by the selection of appropriate façade glazing, external construction, and ventilation strategy to meet the recommended internal noise levels.

It is understood that the development may include items of building services plant, and appropriate noise limits when assessed at the nearest residential properties have been set. It is considered that typical external noise sources could be adequately controlled using standard acoustic treatment techniques.



1015587-RPT-AS001 Acoustic Report for DA Submission

1 Introduction

Cundall has been commissioned by JDH Architects to carry out an assessment of noise levels affecting a proposed development at William Stimson Public School, Wetherill Park NSW, and consider noise break-out affecting neighbouring properties.

This report is based on the project brief provided to Cundall dated 5 May 2017.

1.1 Proposed development

Ground within the existing school site will be developed to provide the following facilities:

- New two storey building comprising 12 general learning areas, breakout spaces and wet areas;
- New single storey building comprising 4 IO/IS/P support learning areas, breakout spaces and wet areas;
- New single storey extension to existing single storey administration building and refurbishment of staff and administration areas.

It is understood that support classes provide individual programs within a regular school setting. If appropriate, the student is integrated in to other classes within the regular school. Below are some definitions of the types of support classes proposed within the development¹:

Type of class	Description
IO Support	A class consisting of a limited number of children with a moderate intellectual disability.
IS Support	A class consisting of a limited number of children with a severe intellectual disability.
P Support	A class consisting of a limited number of children with a significant physical disability and/or significant health impairment that requires regular support from allied health personnel.

Table 1 – Description of relevant support classes

1.2 Design criteria

In this report, acoustic design targets are established for:

- Noise impact of the surrounding community on the development, including internal noise levels;
- Noise impact of the development on the surrounding community.

The acoustic design targets and guidance have been derived from relevant Australian codes, standards, and guidance, including the following:

- NSW Educational Facilities Standards and Guidelines [EFSG], DG11 Acoustics;
- EPA 'NSW Industrial Noise Policy' [INP] (January 2000);
- State Environmental Planning Policy (Infrastructure) 2007 [ISEPP];
- Fairfield City Council 'Fairfield City Wide Development Control Plan 2013';

¹ Ref: NSW Parents' Council website information sheet (https://www.parentscouncil.nsw.edu.au/choosing-a-school-for-your-special-needs-child/)



1015587-RPT-AS001 Acoustic Report for DA Submission

- Australian Standard AS2107 'Acoustics Recommended design sound levels and reverberation times for building interiors' (2016);
- Association of Australia Acoustical Consultants [AAAC] 'Guideline for educational facilities acoustics' (September 2010).

A glossary of acoustic terminology used in this report is included in Appendix A.



1015587-RPT-AS001 Acoustic Report for DA Submission

2 Site description

2.1 Existing site

The immediate vicinity is residential in nature, with dwellings located to the east and south of the school boundary (Coleridge Road and Chaucer Street properties, respectively) and west (across Lily Street). Land to the north of the school site is open space and beyond are residential properties (across Shakespeare Street).

Lily Street is the main thoroughfare past the site and rises to the south as it passes the school grounds.

The figure below indicates the site and the immediate surrounds.




Figure 1 - Site location and surrounds



1015587-RPT-AS001 Acoustic Report for DA Submission

2.2 Proposed site

The figure below indicates the proposed location of the new two storey general teaching building to the south and single storey support learning development to the north.




Figure 2 – Outline development proposals (new-build & refurbishment highlighted)



1015587-RPT-AS001 Acoustic Report for DA Submission

The proposed upgrades will provide for an additional students and an anticipated net gain of four teaching staff. There will be no additional parking provided on site as part of the works.

The development will increase the number of students at the school by more than 50, and therefore the proposal is considered as 'traffic generating development' under Schedule 3 of ISEPP. Consideration of the potential acoustic impact of additional staff, students, and vehicle movements associated with the proposals will be considered further below.



1015587-RPT-AS001 Acoustic Report for DA Submission

3 Noise survey

The purpose of the noise survey was primarily to:

- Identify sources of noise that are likely to affect the development and their expected levels;
- Quantify existing ambient noise levels, to assist in setting appropriate noise criteria to assess the impact of the proposed development on the surroundings;
- Identify potential noise sensitive receivers in the vicinity.

3.1 Methodology

The environmental noise survey was based on a long-term unattended monitoring position, located adjacent to the southern boundary of the school grounds. This location was set back from Lily Road so as to be representative of noise levels on the most exposed façade of the proposed two-storey development, and characteristic of the background noise levels at the nearest adjacent residential properties on Chaucer Street.

The logger recorded at variety of noise parameters at 15 minute intervals, including the prevailing noise level (L_{Aeq}) and background noise level (L_{A90}). Measurements were made between June 23 – 29.

In addition to the long-term measurements, attended surveys were undertaken on June 23 & 29. A position adjacent to Lily Street was selected, considered representative of noise levels at residential façades opposite the site and (subject to distance correction) those of the proposed single-storey building and dwellings along Shakespeare Street.

3.2 Conditions

Reported weather conditions at the nearest monitoring location² were fine over the unattended logging periods. Conditions were therefore considered appropriate for representative noise data.




Figure 3 – June rainfall at the nearest monitoring location

² Ref: http://www.bom.gov.au/climate/data/stations/



1015587-RPT-AS001 Acoustic Report for DA Submission

It is considered that the survey generally meets recommendations given in relevant guidance documents.

3.3 Observations

From our site visits, the predominant noise source affecting the site was considered to be road traffic on Lily Street. Road traffic was observed to be consistently light to moderate during the survey periods.

3.4 Results

3.4.1 Attended measurements

Attended measurements indicated a typical average noise level of 66 dB L_{Aeq} at a location approximately 7 m from the centre of Lily Street. Since the nearest proposed façade of the two-storey development is approximately 50 m and that of the single-storey building approximately 40 m from the centre of the road, a correction due to the additional distance needs to be applied to determine likely daytime façade noise exposure levels.

Given the continuous nature of traffic flow observed during the attended survey periods, the road noise source could be considered as a line source when viewed from a distance of 40 to 50 m, and therefore the correction to measured levels can be determined as follows:

- Attenuation = $10 \times \log_{10}[7/50] = -9 \text{ dB (Two-storey building)};$
- Attenuation = $10 \times \log_{10}[7/40] = -7 \text{ dB (Single-storey building)}$.

Based on the attended survey data, the typical average noise level at the most exposed (nearest) façades would therefore be expected to be approximately 57 dB L_{Aeq} for the two-storey building (referring to Section 3.4.2, this correlates will with logger data) and 59 dB L_{Aeq} for the single-storey building.

3.4.2 Long-term measurements

The figure below illustrates the recorded L_{Aeq} and L_{A90} noise levels over the long-term monitoring period, based on the 15 minute survey data.

1015587-RPT-AS001 Acoustic Report for DA Submission




Figure 4 – Long-term noise level measurements

The peaks in noise level in excess of 65 dBA are considered to be due to children shouting on the adjacent sports field, and have been excluded from the analysis below.

The Table below presents the logarithmically averaged 15 minute L_{Aeq} values and typical L_{A90} values recorded across the whole survey period. It can be seen that there is only slight little variation in the noise levels across each daytime, evening, and night-time period³.

Date	Averaged L _{Aeq,15min} (dB)			Typical L _{A90,15min} (dB)		
Date	Daytime	Evening	Night	Daytime	Evening	Night
23 June (Fri)	53.4	52.0	47.4	46.6	44.6	37.5
24 June (Sat)	56.3	46.0	45.1	41.2	41.2	37.2
25 June (Sun)	56.6	50.2	48.9	40.5	41.9	39.8
26 June (Mon)	56.1	49.0	45.6	40.3	37.5	33.9
27 June (Tue)	56.9	48.8	48.8	43.8	42.5	40.2
28 Jun (Wed)	56.4	51.3	44.6	42.9	39.9	29.2
29 June (Thu)	55.8	49.1	44.2	41.9	41.4	32.9
30 June (Fri)	54.6	n/a	n/a	41.4	n/a	n/a

Table 2 – Averaged 15 minute noise levels

³ Refer to Table 6 for definition of time periods.



1015587-RPT-AS001 Acoustic Report for DA Submission

The table below summarises the average weekday and weekend hourly L_{Aeq} values, based on the values given above.

Data	Averaged L _{Aeq,15min} (dB)			Typical L _{A90,15min} (dB)		
Date	Daytime	Evening	Night	Daytime	Evening	Night
Weekday	56	50	46	43	41	35
Weekend	56	49	47	41	42	38

Table 3 – Averaged weekday and weekend noise levels



1015587-RPT-AS001 Acoustic Report for DA Submission

4 Internal acoustic criteria

4.1 Internal noise level targets

The internal noise level within each space is the combination of any building services and intrusive external noise levels.

Recommended design levels for steady-state internal noise levels within educational buildings are given in Australian Standard AS2107:2016 and referred to within the AAAC Guideline for Educational Facilities Acoustics. The table below gives requirements for typical spaces within the proposed development.

Room type	Design sound level range (dB L _{Aeq,T})		
Classroom	35 to 45		
Open-plan teaching	35 to 45		
Support class	30 *		
Staff room	40 to 45		

Room type	Design sound level range (dB L _{Aeq,T})	
Office – General	40 to 45	
Office – Admin	35 to 40	
Toilet	< 55	
Corridors & Lobbies	< 50	

Table 4 – Internal noise level requirements

* Note:

AS2107 does not provide specific acoustic criteria for Support classes. The value proposed in the table above is taken from the AAAC guide and refers to 'Teaching spaces for hearing impaired'.

4.2 Applicable project-specific noise levels

With reference to the above considerations, it is recommended that the building envelope (including glazed elements) and ventilation strategies (including any openings) be designed such that an internal noise level of \leq 40 dB $L_{Aeq,T}$ can be achieved in all noise-sensitive spaces within the two-storey teaching building and \leq 30 dB $L_{Aeq,T}$ for specific support classes within the single-storey building.

4.3 Acoustic design recommendations

Daytime noise levels monitored are objectively moderate at the proposed façades. To comply with the internal noise criteria given in Section 4.2, attention should be given to provide the necessary sound insulation performance of the façade and glazing and the selection of suitable ventilation systems.

Based on the worst-case façade noise levels, rooms will need to provide glazing attenuation as indicated in the table below to adequately control intrusiveness of road traffic noise.

Type of room	Worst-case façade noise level, dB L _{Aeq,T}	Internal noise level target, dB L _{Aeq,T}	Glazing attenuation, dB R _w +C _{tr}
Standard	57	40	≥ 17
Support	59	30	≥ 29

Table 5 – Glazing attenuation requirements

Both levels of performance can be achieved by standard single or double-glazed units such as 6 mm thick float glass or 6/12/6 double glazed units.



1015587-RPT-AS001 Acoustic Report for DA Submission

The acoustic performance of glazing systems should not be compromised by the framing system or seals. It is recommended that any selected systems be reviewed by a suitably qualified acoustic consultant.



1015587-RPT-AS001 Acoustic Report for DA Submission

5 External plant noise emissions

It is understood that the development proposals do not include mechanical ventilation or cooling systems to standard homebases, however there is the potential for localised items of plant (e.g. toilet extract fans, server room services). It is also understood that there is likely to be a requirement for cooling plant associated with the support rooms, located within the single-storey building to the north of the site.

Any environmental emissions from the proposed development must be designed to comply with the requirements of the NSW Environment Protection Authority's Industrial Noise Policy [INP] dated January 2000.

The objective of the INP is to protect residential areas and other sensitive receivers from noise generated by commercial, industrial, or trade premises. Noise limits are set based on land use in the area and existing background noise levels. Compliance is achieved if the adjusted L_{Aeq} noise level at any residence affected by noise from the facility is below these noise limits. The adjusted L_{Aeq} is determined by applying corrections for such noise characteristics as duration, intermittency, tonality, and impulsiveness.

The INP separates the day into three different time periods – day, evening and night. These time periods are detailed below.

Period	Day of week	Time period
Day	Monday-Saturday Sunday, Public Holiday	07:00 – 18:00 hours 08:00 – 18:00 hours
Evening	Monday-Sunday	18:00 – 22:00 hours
Night	Monday-Saturday Sunday, Public Holiday	22:00 – 07:00 hours 22:00 – 08:00 hours

Table 6 – INP Time periods

The INP provides guidance on acceptable noise levels from the introduction of new industrial noise sources to an area. The assessment procedure for industrial noise sources has two components:

- · Controlling intrusive noise impacts in the short term for residences; and
- Protecting noise level amenity for particular land uses such as residences and commercial offices etc.

Both of these components suggest noise criteria that should not be exceeded in order to minimise adverse noise impacts on the affected areas. Both criteria should be taken into account when assessing the noise impact of industrial source(s) associated with the proposed development, and where the intrusiveness and the amenity criterion differ, the lower of the noise criteria should be adopted as the project-specific noise criterion.

It should be noted that the assessment is based on industrial noise sources, which in this case would relate to mechanical services plant etc. Activity noise from children falls outside of this assessment and is considered further below.



1015587-RPT-AS001 Acoustic Report for DA Submission

5.1 Selection of noise sensitive receivers

The existing buildings most affected by potential noise from the development are considered to be the residential properties on Chaucer Street and Coleridge Road to the south and east, and across Shakespeare Street to the north.

5.2 Intrusiveness criteria

A 15-minute sampling period is typically used when measuring the level of intrusive noise. This is taken to be a reasonable estimate of the period over which annoyance may occur. The intrusiveness criterion is summarised as follows:

L_{Aeq,15min} ≤ L_{A90,15min} (i.e. background level) + 5 dB.

Because of the variable nature of background noise levels, the INP specifies single number background noise levels for use in setting the intrusiveness noise criterion. The Assessment Background Level [ABL] for each time period is the level exceeded by 90% of the LA90,15min measurements. The Rating Background Level [RBL] for a particular time period is the median of the ABL values for that time period for each day of the measurement period.

The applicable intrusiveness criteria for the development based on site measurement data from the noise logger are provided below.

Location	Location Time Period		Intrusiveness Criterion
		dBA	RBL + 5 dB
	Day	42	47
Nearest residential properties	Evening	41	46
	Night	37	42

Table 7 – Derivation of Intrusiveness Criteria

5.3 Amenity criteria

Criteria for the protection of amenity are given for various types of receiver and different times of day. The amenity criterion is set so that the L_{Aeq} noise level from the industrial noise source does not increase the total industrial noise levels at the receiver above the acceptable noise level [ANL] for that receiver.

The amenity criterion is set based on how close the existing average L_{Aeq} industrial noise levels are to the ANL, using the adjustment factors given in Table 2.2 of the INP.

In cases where the existing L_{Aeq} , average noise levels exceed the ANL by more than 2 dB, and the existing noise levels are unlikely to decrease in future, then the amenity criterion is set to be 10 dB lower than the existing noise levels at the receiver.

A summary of the amenity criteria using data from the noise logger is presented below.





1015587-RPT-AS001 Acoustic Report for DA Submission

Location	Classification	Time Period	Existing noise level dB L _{Aeq} ⁴	ANL ⁵ dB L _{Aeq}	Modification factor ⁶ dB	Amenity Criterion dB L _{Aeq}
Nearest		Day	56	55	ANL – 8	47
residential	Suburban	Evening	49	45	L _{Aeq} – 10	39
properties		Night	46	40	L _{Aeq} – 10	36

Table 6 – Derivation of Amenity Criteria

5.4 Applicable project-specific noise levels

The most stringent of the intrusiveness and the amenity criteria should be set as the limiting project-specific noise level to be met by the development. The Table below compares the intrusiveness and the amenity criteria, and identifies the limiting criterion for each time period.

Location	Classification	Time Period	Intrusiveness Criterion	Amenity Criterion	Project-specific Criterion dB L _{Aeq,15min}
Nearest residential properties	Suburban	Day	47	47	47
		Evening	46	39	39
		Night	42	36	36

Table 8 – Project-specific noise levels

5.5 Acoustic design recommendations

Noise from any mechanical plant should be controlled to meet the criteria given in Table 8 when assessed at the nearest affected noise-sensitive location(s).

Typical noise mitigation strategies include selection of low noise outdoor equipment, locating plant to take advantage of shielding from building elements, and the use of plant enclosures or screens if necessary.

5.5.1 Additional guidelines

Noise generated by waste collection or other service vehicles should be controlled by management of the collection/delivery times to ensure that disturbance to nearby residents during typical sleeping hours is avoided.

Other simple measures that should be adopted include the use of self-close gates with soft close hinges, and ensuring car park surfaces and access ways are smooth.

⁴ Ref: Lowest values recorded in Table 3 above.

⁵ Ref: Acceptable Noise Level for suburban residences, according to Table 2 of NSW INP, 2000.

⁶ Ref: According to Table 2.2 of NSW INP, 2000.



1015587-RPT-AS001 Acoustic Report for DA Submission

6 Consideration of activity noise

Student activity noise from schools is typically one of the most understandable, and tangible, causes of concern from the occupants of neighbouring premises.

There are no specific State criteria for children activity noise from schools and the local DCP does not reference educational facilities other than childcare centres.

6.1 Current noise impacts

The site is an existing and established school, covering a large site, and therefore adjacent noise-sensitive dwellings will already be acclimatised to the sounds of general school activity.

6.2 Potential noise impacts

The proposed upgrades will provide for 92 additional students (approximately 16% increase). The proposals do not include spaces with a high level of activity noise (such as music rooms). No new outdoor activity areas are being proposed in locations where this is not already the case.

6.3 Conclusion

In light of the above, it is not anticipated that there will be a significant change to the prevailing acoustic environment and additional assessment is not necessary.

It is also noted that activity noise will be limited to the daytime period and would be unusual at weekends or public holidays.



1015587-RPT-AS001 Acoustic Report for DA Submission

7 Consideration of additional road traffic

A Traffic and Transport Assessment has been carried out as part of the DA submission, identifying the likely changes to road traffic as a result of the proposed development.

The report notes that William Stimson Public School is well served by public transport (both bus and train links) and an abundance of unrestricted parking areas. It is noted that spare capacity exists within existing staff parking areas and any additional student drop-off / pick-up demand generated can easily be accommodated within the adjacent streets.

The proposed upgrades include a net increase of four teaching spaces, accommodating 92 additional students and an assumed four additional staff. A total of 28 additional vehicular trips are forecast. The Traffic and Transport Assessment concludes that 'minimal impact to the surrounding road network is predicted.'

7.1 Noise impact

Specific state guidance on the change to road traffic noise with increased traffic flow is not available, however the Design Manual for Roads and Bridges notes that:

an increase in traffic flow of 25% is associated with an increase in traffic noise of 1 dB.

Traffic count data are not available on the roads surrounding the school, however it is not anticipated that an additional 28 vehicle movements would result in an increase to traffic flows in excess of 25% and therefore the worst-case noise impact would be less than 1 dB.

7.2 Conclusion

It is not considered that there will be any significant change in road traffic noise generation on the basis of 28 additional vehicle movements, even assuming a worst-case assessment that all new vehicle movements affect one specific location.

On this basis, it is considered that any change to the noise impact from road traffic on adjacent sensitive receptors will be negligible, and the noise impact on the school itself will not be affected.



1015587-RPT-AS001 Acoustic Report for DA Submission

8 Consideration of construction noise

Assessment of demolition and construction noise is outside the scope of this DA report; however it should be noted that all work, including demolition, excavation, and building work should comply with the current Fairfield City Council Policy and Australian Standard AS2436-1981 Guide to Noise Control on Construction. Maintenance and Demolition Sites.

It is recommended that a construction noise and vibration management plan be developed at a later stage of the project, prior to the commencement of site works, once a contractor has been appointed and construction activities confirmed.

8.1 Other measures

Standard good-practice procedures should be adopted on site, including the following:

- Where possible, noise generating equipment should be strategically positioned to take advantage of natural screening from structures to reduce the transmission of noise to sensitive receptors;
- Fixed plant should be appropriately selected and sited and, where necessary, fitted with appropriate silencers or acoustic enclosures;
- Noisy plant operating simultaneously close together should be avoided to the greatest extent practicable, adjacent to noise affected sensitive receptors;
- All plant and equipment should be maintained in a proper and efficient manner to minimise
 noise emissions, including the replacement of engine covers, repair of defective silencing
 equipment, tightening of rattling components and the repair of leakages in air lines;
- All plant and equipment should be operated in the correct manner to minimise noise emissions;
- Noise generating equipment should be orientated away from nearby receivers where feasible to minimise noise impacts;
- Minimise plant and vehicles idling when not in use;
- PPE including hearing protection should be made available and worn where noise levels require.



1015587-RPT-AS001 Acoustic Report for DA Submission

9 Conclusions

This report presents acoustic input to the DA submission for the proposed development at William Stimson Public School.

Based on appropriate standards and guidance, intrusive noise impact on the development from the surroundings (primarily road traffic noise) has been assessed. It has been determined that standard glazing solutions should provide an acceptable environment within the development.

Noise limits on emissions from potential plant items have been set to see that any noise impact of the development on the surrounding community is acceptable.

Consideration has been given to the potential for change in activity noise due to an increased number of students, and an increased number of vehicle movements. Good practice guidance for controlling noise from construction sites has also been identified.



1015587-RPT-AS001 Acoustic Report for DA Submission

Appendices

Appendix A Acoustic Terms

ASSESSMENT BACKGROUND LEVEL (ABL)

A single-number figure used to characterise the background noise levels from a single day of a noise survey. ABL is derived from the measured noise levels for the day, evening or night time period of a single day of background measurements. The ABL is calculated to be the tenth percentile of the background L_{A90} noise levels – i.e. the measured background noise is above the ABL 90% of the time.

'A'-WEIGHTED SOUND LEVEL dBA

The unit generally used for measuring environmental, traffic or industrial noise is the A-weighted sound pressure level in decibels, denoted dBA. An A-weighting network can be built into a sound level measuring instrument such that sound levels in dBA can be read directly from a meter. The weighting is based on the frequency response of the human ear and has been found to correlate well with human subjective reactions to various sounds. An increase or decrease of approximately 10 dB corresponds to a subjective doubling or halving of the loudness of a noise. A change of 2 to 3 dB is subjectively barely perceptible.

DECIBEL

The ratio of sound pressures which we can hear is a ratio of one million to one. For convenience, therefore, a logarithmic measurement scale is used. The resulting parameter is called the 'sound level' (L) and the associated measurement unit is the decibel (dB). As the decibel is a logarithmic ratio, the laws of logarithmic addition and subtraction apply.

EQUIVALENT CONTINUOUS SOUND LEVEL (LAeq)

Another index for assessment for overall noise exposure is the equivalent continuous sound level, L_{eq}. This is a notional steady level, which would, over a given period of time, deliver the same sound energy as the actual time-varying sound over the same period. Hence fluctuating levels can be described in terms of a single figure level.

FREQUENCY

The rate of repetition of a sound wave. The subjective equivalent in music is pitch. The unit of frequency is the Hertz (Hz), which is identical to cycles per second. A thousand hertz is often denoted kilohertz (kHz), eg 2 kHz = 2000 Hz. Human hearing ranges from approximately 20 Hz to 20 kHz. The most commonly used frequency bands are octave bands, in which the mid frequency of each band is twice that of the band below it. For design purposes, the octave bands between 63 Hz to 8 kHz are generally used.

For more detailed analysis, each octave band may be split into three one-third octave bands or, in some cases, narrower frequency bands.

RATING BACKGROUND LEVEL (RBL)

A single-number figure used to characterise the background noise levels from a complete noise survey.

The RBL for a day, evening or night time period for the overall survey is calculated from the individual Assessment Background Levels (ABL) for each day of the measurement period, and is numerically equal to the median (middle value) of the ABL values for the days in the noise survey.



1015587-RPT-AS001 Acoustic Report for DA Submission

SOUND POWER AND SOUND PRESSURE

The sound power level (L_w) of a source is a measure of the total acoustic power radiated by a source.

The sound pressure level (L_p) varies as a function of distance from a source. However, the sound power level is an intrinsic characteristic of a source (analogous to its mass), which is not affected by the environment within which the source is located.

STATISTICAL NOISE LEVELS

For levels of noise that vary widely with time, for example road traffic noise, it is necessary to employ an index that allows for this variation. 'A'-weighted statistical noise levels are denoted L_{A10}, dB L_{A90} etc. The reference time period (T) is normally included, e.g. dB L_{A10 5min} or dB L_{A90,8hr}.

LA90 (T)

Refers to the sound pressure level measured in dBA, exceeded for 90% of the time interval (T) – i.e. measured noise levels were greater than this value for 90% of the time interval. This is also often referred to the background noise level.

L_{A10} (T)

Refers to the sound pressure level measured in dBA, exceeded for 10% of the time interval (T). This is often referred to as the average maximum noise level and is frequently used to describe traffic noise.

L_{A1} (T)

Refers to the sound pressure level measured in dBA, exceeded for 1% of the time interval (T). This is often used to represent the maximum noise level from a period of measurement.