

# PRELIMINARY SITE INVESTIGATION

FOR

# AMJ DEMOLITION AND EXCAVATION

*55 Martin Road, Badgerys Creek, New South Wales*

*Report No: 18/0089*

*Project No: 21649/8652C*

*January 2018*

## TABLE OF CONTENTS

EXECUTIVE SUMMARY .....	1
1. INTRODUCTION .....	2
2. REDEVELOPMENT AND PROPOSED LAND USE .....	3
3. SITE IDENTIFICATION .....	3
4. PREVIOUS ENVIRONMENTAL REPORTS .....	3
5. SITE FEATURES .....	3
6. GEOLOGY AND HYDROGEOLOGY .....	4
7. SITE HISTORY .....	5
7.1 Aerial Photographs .....	5
7.2 Section 149 (2) .....	7
7.3 Historical Title Search .....	7
7.4 NSW EPA Records .....	7
7.5 SafeWork NSW .....	7
7.6 Site History Summary .....	8
8 APPRAISAL OF POTENTIAL CONTAMINATION SOURCES .....	8
9 DATA QUALITY OBJECTIVES .....	9
10 FIELD INVESTIGATION .....	10
10.3 Soil Sampling .....	11
10.3.1 Soil Sample Handling and Equipment Decontamination .....	11
10.3.2 Analytical Program for Soil Samples .....	12
11 QUALITY ASSURANCE PROGRAM .....	12
11.3 Quality Control Sampling .....	12
11.4 Quality Control Criteria .....	13
11.5 Laboratory Quality Control .....	14
12 ASSESSMENT CRITERIA .....	14
12.3 Criteria for this Assessment .....	16
13 ANALYTICAL RESULTS AND INTERPRETATION .....	18
13.3 Human-Health Risks .....	18
13.4 Environmental Risks .....	18
13.5 Risk of Groundwater Impacts .....	19
13.6 Potential for Off-Site Migration of Contamination .....	19
13.7 Duty to Report Site Contamination .....	19
13.8 Assessment Outcomes .....	20

14	EVALUATION OF QUALITY ASSURANCE .....	20
14.3	Field Duplicate and Triplicate Sample Results .....	20
14.4	Laboratory Quality Control Program.....	20
14.5	Procedure-Based Quality Control .....	20
15	CONCLUSIONS AND RECOMMENDATIONS .....	21
16	LIMITATIONS .....	21

## Figures

DRAWING NO. 18/0089/1 – SITE LOCATION  
 DRAWING NO. 18/0089/2 – SITE FEATURES  
 DRAWING NO. 18/0089/3 – BOREHOLE LOCATIONS  
 DRAWING NO. 18/0089/4 – EXISTING SITE PLAN  
 DRAWING NO. 18/0089/5 – PROPOSED SITE PLAN

## Tables of Results

TABLE A: ANALYTICAL RESULTS FOR PRIMARY SOIL SAMPLES  
 TABLE B: RESULTS OF QUALITY CONTROL – INTRA AND INTER-LABORATORY DUPLICATE SAMPLES

## Appendices

APPENDIX A: AERIAL PHOTOGRAPHS AND SATELLITE IMAGERY  
 APPENDIX B: SECTION 149 (2) CERTIFICATE  
 APPENDIX C: HISTORICAL TITLES  
 APPENDIX D: SAFEWORK NSW NOTICE  
 APPENDIX E: SOIL PROFILE LOGS  
 APPENDIX F: CHAIN OF CUSTODY DOCUMENTATION  
 APPENDIX G: LABORATORY TEST RESULTS

## EXECUTIVE SUMMARY

The report describes the methodology and results of a preliminary site investigation (PSI) carried out by STS GeoEnvironmental Pty Ltd (STS) at 55 Martin Road, Badgerys Creek, New South Wales (the 'site'). The assessment was carried out at the request of Claron Consulting Pty Ltd on behalf of AMJ Demolition and Excavation Pty Ltd.

The aim of the PSI is to provide a preliminary assessment of the potential occurrence and extent of contamination at the site and assess any potential risk to human health and environment with respect to a proposed "Waste Resource Recovery Facility" at the site. Further, the results of the investigation will support an Environmental Impact Assessment (EIA) to be carried with respect to the proposed redevelopment the site.

The investigation was performed in accordance with Environment Protection Authority (EPA) and national guidelines for the assessment and management of site contamination.

The site is approximately 2.54ha in area and is currently rural residential land use. Our historical review indicates that that no agricultural activities have occurred since 1940. The only development at the site occurred in the mid 1980s which comprises the construction of a single storey brick residence on the eastern end of the site. Later, a metal shed was constructed west of the residence. No other facilities or installations appear to have been located on the property.

Soil samples were collected in nineteen boreholes at targeted locations across the site as part of the PSI. The soil samples were analysed to screen a range of both organic and inorganic contaminants. The results indicate no exceedances of the site assessment criteria nor the presence of asbestos.

Potential contaminants in the soil at the site are present at low levels and would not present an unacceptable risk to human-health or the environment for a commercial/industrial setting. We consider that no further investigation is required at the site.

Therefore, the site is considered to be suitable for the proposed "Waste Resource Recovery Facility" in its current condition.

## 1. INTRODUCTION

The report presents the results of a Preliminary Site Investigation (PSI) carried out by STS GeoEnvironmental Pty Ltd (STS) at 55 Martin Road, Badgerys Creek, New South Wales (the 'site'). The assessment was carried out at the request of Claron Consulting Pty Ltd on behalf of AMJ Group.

The objective of the PSI is to provide a preliminary assessment of the potential occurrence and extent of contamination at the site and assess any potential risk to human health and environment with respect to a proposed "Waste Resource Recovery Facility" at the site. Further, the investigation would support an Environmental Impact Assessment (EIA) for the proposed redevelopment.

The investigation was performed in accordance with Environment Protection Authority (EPA) and other national guidelines related to the assessment and management of site contamination.

The scope of the PSI included:

- examination of aerial photographs and satellite imagery to identify historical land uses at the site and its surrounds;
- review records held by EPA;
- site inspection;
- appraisal of the potential for surrounding land uses to cause site contamination;
- appraisal of local geology and hydrogeology;
- soil sampling from nineteen boreholes and laboratory analysis of selected soil samples for a broad range of potential contaminants;
- assessment of analytical data and quality assurance (QA);
- appraisal of the contaminant concentrations in the soil at the site, including an appraisal of potential harm to human-health and the environment, potential contaminant exposure pathways and off-site impacts;
- recommendations for any further investigation or remediation that may be required based on relevant guidelines on the assessment and management of site contamination; and
- preparation of a confidential report on the results of the investigation.

Our scope of work includes a geotechnical investigation of the site. Results are given in our Report Number 17/3905 dated January 2018 and should be read in conjunction with the current report.

## 2. REDEVELOPMENT AND PROPOSED LAND USE

We understand that the site is proposed to be developed as a “Waste Resource Recovery Facility”. Activities at the proposed facility comprise recycling of construction materials for reuse.

Bulk earthworks are anticipated at the site during the construction of the facility. Proposed features at the facility will include a site office/showroom, parking lots, a 1540m<sup>2</sup> colourbond shed, processing and stockpiling areas, hardstand truck turning bays, a weight bridge, site drainage structures and a sedimentation basin. The existing dam on the west of the site will be backfilled with its existing surrounds to be retained. Further, the remaining areas of the proposed compound will be covered with compacted road base or landscaped. The layout plan of the proposed facility is presented on Drawing No.18/0089/5.

Further, the remaining areas of the proposed compound will be covered with compacted road base or landscaped.

## 3. SITE IDENTIFICATION

The site, which is roughly rectangular and covers an area of approximately 2.54ha, is legally defined as Lot 4 in Deposited Plan (DP) 611519, Parish of Bringelly, County of Cumberland. The property has an approximate 90m frontage to Martin Road to the east. Vacant rural land and rural residential/agricultural land form the boundaries to the north and south respectively. Lawson Road borders the site to the west. The site location is shown on Drawing No. 18/0089/1.

The site is within the Liverpool Council local government area, and is currently zoned ‘RU1-Primary Production. Development at the site is managed under “Liverpool LEP 2008”.

## 4. PREVIOUS ENVIRONMENTAL REPORTS

No previous environmental assessment reports are known to have been prepared for the site.

## 5. SITE FEATURES

The site was inspected on 13 December 2017 to assess its current conditions and to identify potential existing contamination sources at the site and surrounds. A plan showing the current site configuration is shown on Drawing No. 18/0089/2.

The key site features as determined by the site inspection are:

- a fenced area of about 2900m<sup>2</sup> with 42m frontage to Martin Road encompasses a single storey brick residence, a gravel driveway, a metal shed. The soil was grassed covered and with some mature trees located to the south and west of the residence.

- the remaining area of the site is undeveloped and covered with thick grass. Overgrown vegetation was identified along a strip of land along Lawson road.
- a dam with a footprint of about 40m<sup>2</sup> is located on the north-western quadrant.
- levels at the site drops for about 6m westwards from Martin Road.
- identification of site filling not possible because of the thick grass cover.
- olfactory observations indicated no possible source of onsite contamination.

## 6. GEOLOGY AND HYDROGEOLOGY

Reference to the Geological Map of Penrith (Sheet 9029-9129) shows that the site is underlain by “Bringelly Shake”, which comprises shale, carbonaceous claystone, laminate, fine to medium grained lithic sandstone, rare coal and tuff.

The natural soils encountered on the site during this investigation consisted of brown/dark-brown/red-brown and grey silty clays with traces of sand. These soils are originated from in-situ weathering of the regional geological formations.

The subsurface conditions generally consist of topsoil overlying silty clays, sandy clays and weathered sandstone and shale. Topsoil materials were encountered across the site in all boreholes to depths of 0.3 to 0.5 metres. Natural silty clays and sandy clays were encountered below the topsoil to depths of 1.3 to 3.6 metres.

A review of the acid sulfate soil (ASS) risk map of Liverpool, sheet number 9030S2 (2ed. 1997), indicates that acid sulphate soil materials are unlikely to be present at the site.

During the advancement of the boreholes, which extended to a maximum depth of 4.3m below the land surface at BH15, no free-flowing groundwater was encountered.

A search of the groundwater database of the “NSW Office of Water” was carried out to substantiate information on the likely hydrogeological conditions at the site. The search confirmed the presence of one registered domestic/stock bore within a 500m radius of the site. The bore is located to the south of the site and was advanced to a depth of 252.5m below the existing land surface.

The aquifer depths in the bore are reported to be between 137.5 m to 1328 m, 155.5m to 155.7m and 207m to 210m. The aquifer lithology is reported to comprise of sandstone.

Based on the observations made during the on-site soil sampling activities, the results of the groundwater database search, the findings of the recent geotechnical investigation at the site (17-3905) and our review of the site geology, a summary of the site hydrogeology is shown in Table 6.1 below.

Table 6.1 – Site Hydrogeology

<b>Aquifer Type and Lithology:</b>	Sandstone <sup>1</sup>
<b>Perched groundwater:</b>	Not expected to be present <sup>1,2</sup>
<b>Depth to Regional Aquifer at Site:</b>	>50 m <sup>1,2</sup>
<b>Local Groundwater Flow Direction:</b>	West, towards key receiving environment <sup>2</sup>
<b>Regional Groundwater Flow Direction:</b>	West, towards key receiving environment <sup>2</sup>
<b>Receiving Environments:</b>	Badgerys Creek 500 m to the west into South Creek then Hawkesbury River, located approximately 12 km to the north of the site <sup>2</sup> .

<sup>1</sup> Actual conditions based on observations made during on-site drilling and sampling.

<sup>2</sup> Inferred conditions based on site/regional geology and geomorphology.

## 7. SITE HISTORY

STS GeoEnvironmental Pty Ltd (STS) researched the following sources of historical information:

- Aerial photographs of the site and surrounding areas held by the NSW Department of Lands;
- Section 149(2) Certificate provided by Liverpool City Council;
- SafeWork NSW
- Historical land titles; and
- NSW EPA records.

### 7.1 Aerial Photographs

Aerial photographs of the site and surrounds dated; 1947, 1961, 1970, 1986, 1994, 2007, 2014, 2016 and 2017 were obtained from Land and Property Information (LPI) NSW. A summary of the observations made from the photographs are presented in Table 7.1 below. Copies of the selected aerial photographs are provided in Appendix A.

**Table 7.1 – Aerial Photograph and Satellite Image Observations**

Year	Site Features	Surrounding Land Use
1947	The site comprises built structures and a dam on the north-eastern and north-western quadrant respectively. Ground disturbance is visible along Martin Road. The remaining area is vegetation covered.	Surrounding land is predominantly vacant and undeveloped, although structures inferred to be associated with agricultural activities visible to the west and downslope of the site.
1961	Vegetation around built structures cleared and the water level in the dam has decreased considerably.	The surrounding properties remain largely unchanged, although construction of new structures is apparent further north and northeast.
1970	No significant changes identified.	Establishment of new farms further north and redevelopment on properties west and southwest to the site.
1986	Seepage/spill, from a dam from the adjacent property due south, runs north-westerly along a swale towards the dam located on site.	Development on the property immediately north and south of the site. Single storey residences, swimming pool, shed and market garden/orchard visible (inferred). Increased in farming activities apparent on remaining surrounding land.
1994	Site structures removed, and a single storey residence constructed at about the same location. Localised greener patches of vegetation inferred to be eutrophication identified on site.	Extension of the market garden immediately south of the site. Increasing agricultural development apparent on surrounding lands.
2007	The site remains essentially unchanged.	Market gardening ceased on the property immediately south of the site. Considerable ground disturbance further north and an orchard identified two properties south of the site. Site filling identified on neighbouring lands.
2014	No significant changes identified.	More site filling in progress identified on properties in the locality. Junkyards established northeast and southwest of the site.
2016	No significant changes identified.	Built structures associated to farming removed on surrounding lands, except for one property north of the site. Decline of farming activities inferred on surrounding land.
2017	No significant changes identified.	Material stockpiles visible on a property north to the site. A junkyard established southeast of the site.

## 7.2 Section 149 (2)

A copy of the Planning Certificate for the site issued under section 149(2) obtained from Liverpool Council, is presented in Appendix B. A review of the document indicates that no notice had been issued for the site related to contamination risks under the provisions of the *Contaminated Land Management Act*. Further, the site had never been subjected to a Site Audit.

## 7.3 Historical Title Search

Copies of the historical land title transfers were obtained from the Land Titles Office, and are provided in Appendix C. Tables 7.2 below summarises the ownership of the site covered under this assessment. The activities of the owners/occupants are given where applicable and are based on the title documentation and/or an internet search.

Table 7.2 – Historical land title summary (Ownership) for lot 4 in DP611519

Period	Registered Owners	Occupation
6 May 1998 to date	Helen Nobbs & Jeffrey Nobbs	N/A
1 June 1981 to 6 May 1998	Kenneth John Nobbs & Jeffrey Nobbs	Famers
15 April 1943 to 1 June 1981	Mervyn Joseph Nobbs	Farmer
6 May 1930 to 15 April 1943	The Sydney City Mission	N/A

## 7.4 NSW EPA Records

STS GeoEnvironmental Pty Ltd conducted a search of the NSW EPA contaminated land records and the POEO public register on the 5 January 2018. The following was noted:

- no EPA notices have been issued to the site or any other site within a 500m radius under the CLM Act 1997.
- a search for the suburb of “Badgerys Creek” indicates that no site has been subjected to any type of EPA notices issued under CLM Act 1997.

A search of the POEO public register indicates that EPA issued a licence for waste “storage and composting” at a property located at 210 Martin Road, about 1.3km south east of the site.

## 7.5 SafeWork NSW

Our search of the SafeWork NSW records indicates that no storage of “Hazardous Chemicals” occurred at the site. The notification is given in Appendix D.

## 7.6 Site History Summary

Based on the historical information review, we believe that the site has been used mostly for residential purposes as there is no evidence of any other activities at least from 1947 onwards.

Built structures initially located on north-eastern quadrant of the property were removed and a single storey brick residence was constructed at about the same location. A shed was later erected to the south of the residence as witnessed by the 2007's aerial photograph. No other facilities or installations have been located on the property

Most of the surrounding land have been vacant until 1961. Development in the vicinity was gradual and involved establishment of farms and/or residences. Farming activities in the area declined past the year 2000. Recent satellite imagery, dated 2016 and 2017, indicates the cessation of agricultural activities on neighbouring lands. Surrounding properties located further from the site share the same site history. However, recent historical data indicates the installation of junkyards in the area.

## 8. APPRAISAL OF POTENTIAL CONTAMINATION SOURCES

Based on our site history review and site inspection, an appraisal of the potential contamination risks at the site has been performed, the results of which are summarised in Table 8.1.

Table 8.1 – Contamination risk analysis

Source	Location	Contamination Pathway Analysis	Potential for Impacts
Presence weathered construction materials including asbestos	Surface soil across the site	Inadvertent ingestion, direct contact, dust inhalation.	High for soil and low for groundwater.
Contaminated seepage/spill from dam on adjacent site	Soil along drainage line connecting the dam at the site to a dam located on the adjacent site due south.	Inadvertent ingestion, direct contact, dust inhalation.	High for soil and low for groundwater.
Historical use of pesticides on adjacent site	Surface soil across the site/dam sediments	Inadvertent ingestion, direct contact, dust inhalation.	Low to moderate for soil and low for groundwater

Currently potential receptors are mainly the occupant of the residence located at the site, visitors and maintenance workers. Construction workers and visitors will be the only receptors during the implementation of the project.

During the operation of the proposed facility, employees working in the yard and maintenance workers might be the main receptors to potential contaminants.

Pathways to contaminant exposures for all the potential receptors mentioned above would be mostly through inadvertent ingestion and inhalation.

On the other and, ecological receptors at the site are limited to the fauna and flora which live/grow within the site boundary.

## 9. DATA QUALITY OBJECTIVES

The *National Environment Protection (Assessment of Site Contamination) Measure 1999* (NEPM) (updated April 2013) and Australian Standard (AS) 4482.1-2005 recommend that data quality objectives (DQOs) be implemented during the investigation of potentially contaminated sites. The DQO process described in AS 4482.1-2005 outlines seven distinct steps which are designed to ensure an investigation is performed in a structured and efficient manner. The seven steps and the associated processes that were implemented to ensure data, hence decision making is of quality, are outlined below:

### Step 1 – State the Problem

The site is proposed to be redeveloped as a “Waste Resource Recovery Facility”. Prior to this assessment there was insufficient data to determine whether in its current condition the site is suitable for the intended end use.

### Step 2 – Identify the Decision

To determine if the concentrations of contaminants in the soil at the site are likely to present an unacceptable risk to human-health or the environment in the setting specific to the intended use.

### Step 3 – Identify Inputs to the Decision

To enable a decision regarding the contamination status of the site to be made, the following inputs were required:

- Soil sampling from nineteen boreholes, positioned randomly across the site;
- Analysis of the samples for a broad screen of potential chemical contaminants; and
- Implementation of a quality assurance/quality control (QA/QC) program.

#### Step 4 – Define the Study Boundaries

The assessment was undertaken within the boundaries of the site located at 55 Martin Road, Badgerys Creek, NSW. The boundaries of the site are defined in Section 3 and are shown on Drawing No. 18/0089/2.

#### Step 5 – Develop a Decision Rule

To determine if any soil impacts at the site are significant for the proposed use of the land as a “Waste Resource Recovery Facility”, data were compared to relevant EPA endorsed criteria.

#### Step 6 - Specify Limits on Decision Errors

A field QA program was implemented, and acceptable error limits were defined to ensure the precision, accuracy, completeness and comparability of data. Further details are given in Section 11.

#### Step 7 – Optimize the Design for Obtaining Data

The following was implemented to ensure data collected are sufficient and reliable to enable the project objectives to be met:

- obtain soil samples from targeted locations across the site, sufficient to reach the main objective of a limited soil contamination assessment.
- collect, store and transport of soil samples in an appropriate manner to ensure sample integrity (refer to Section 10); and
- collect of an appropriate number of samples from each location
- based on our site history review and site inspection, an appropriate suite of chemical analyses was requested to screen the soil samples for contaminants potentially present in the soil at the site.

## 10. FIELD INVESTIGATION

The field activities for the investigation were undertaken by STS GeoEnvironmental on 12 December 2017. The assessment was performed in accordance with:

- EPA guidelines comprising:
  - *Contaminated Sites: Sampling Design Guidelines (1995)*;
  - *Contaminated Sites: Guidelines for Consultants Reporting on Contaminated Sites (1997)*;
  - *Contaminated Sites: Guidelines for the NSW Site Auditor Scheme (2nd Edition) (2006)*; and
  - *Managing Asbestos in or on Soil (2014)*.

- Guidelines issued under Schedule B of the *National Environment Protection (Assessment of Site Contamination) Measure* (NEPM), Environment Protection and Heritage Council (EPHC)/National Environment Protection Council (NEPC), December 1999 (and updated NEPM April 2013);
- *Australian and New Zealand Guidelines for the Assessment and Management of Contaminated Sites* published by the Australian and New Zealand Environment and Conservation Council/National Health and Medical Research Council, January 1992 (ANZECC Guidelines);
- *Australian Standard 4482.1-2005: Guide to the Investigation and Sampling of Sites with Potentially Contaminated Soil – Part 1: Non-volatile and Semi-Volatile Compounds, Standards Australia* (2 November 2005);
- *Guidelines for the Assessment, Remediation and Management of Asbestos-Contaminated Sites in Western Australia*, Western Australian Department of Health (WA DOH) (2009); and
- *CRC Care Technical Report No. 10: Health Screening Levels for Petroleum Hydrocarbons in Soil and Groundwater* (Friebel, E. & Nadebaum, P., 2011).

## 10.1 Soil Sampling

A drill rig with solid rotary augers was used to advance the boreholes. Soil samples comprising both fill and natural soil were recovered directly from the auger at nominated depths, referenced to the existing ground level at the borehole locations. The borehole locations are shown on Drawing No. 18/0089/3.

The soil samples were placed in new clean glass jars and/or 500 ml plastic zip locked bags provided by Australian Laboratory Services (ALS). All soil samples were recovered by a qualified environmental technician. New disposable latex gloves were used to recover each sample to avoid cross contamination.

Soil sample identifications and the description of the soil profiles encountered at each borehole location are described on the bore log sheets presented in Appendix E.

### 10.1.1 Soil Sample Handling and Equipment Decontamination

As mentioned above, each sample was recovered using new disposable latex gloves to prevent cross contamination. Sampling equipment was decontaminated before each sample was recovered. Decontamination was carried out using water and DECON 90.

Further, soil samples were recovered in glass jars leaving no headspace. The soil samples were not mixed to minimise the potential loss of volatile compounds from the soil matrix. The samples recovered were then placed in an iced-cooled container and transferred to ALS laboratory for analysis under a “Chain of Custody” (COC). The COC detailed the requested

analyses and was used to record the samples' history. A copy of the COC is presented in Appendix F.

### 10.1.2 Analytical Program for Soil Samples

The selection of analytes was based on our review of the historical data, site inspection observations, along with EPA NSW and NEPM (2013) contaminated site assessment guidelines. Selected soil samples were analysed for both inorganic and organic contaminants.

The analytes included heavy metals (As, Cd, Cr, Cu, Hg, Ni, Pb, Zn), monocyclic aromatic hydrocarbons (MAHs), polycyclic aromatic hydrocarbons (PAHs), total petroleum hydrocarbons (TPHs), organochlorine pesticides (OCPs), organophosphorus pesticides (OPPs), polychlorinated biphenyls (PCBs), phenolic compounds, and asbestos. The analytical program is illustrated in greater details in the COC in Appendix F.

ALS Sydney and ALS Brisbane, which are both NATA accredited, were selected as the primary and secondary analytical laboratory respectively. ALS Sydney was responsible for the analyses of the primary and intra-lab duplicate samples. Inter-lab duplicate analysis was carried out by ALS Brisbane.

## 11. QUALITY ASSURANCE PROGRAM

In compliance with the NEPM (2013) and AS 4482.1-2005, data quality assurance (QA) was a key component of this investigation. The QA allows the assessment of the integrity of soil samples recovered during the site investigation and accuracy of the laboratory analyses. The reliability of the analytical results, hence the representativeness of analytical data to characterise the site condition is thus appraised.

The QA procedures, actions and checks implemented during the investigation included:

- the utilisation of appropriate sampling methods in accordance with EPA requirements and NEPM (2013);
- appropriate sample handling and transportation, and analysis of samples within recommended analytical holding times;
- the collection and analysis of quality control (QC) samples;
- implementation of internal laboratory QC analyses; and
- the use of National Association of Testing Authorities (NATA) registered laboratory and analytical methods.

### 11.1 Quality Control Sampling

Inaccuracies in sampling and analytical programs can result from many causes, including collection of unrepresentative and inhomogeneous samples, cross contamination between

samples, unanticipated interferences between elements during laboratory analyses, equipment malfunctions and operator error. Inappropriate sampling, preservation, handling, storage and analytical techniques can also reduce the precision and accuracy of results.

A field-based QC program was implemented, and the results were compared to accepted criteria to assess its effectiveness. NEPM (2013) has documented procedures for QC sampling and analysis to ensure that the required level of accuracy and precision is obtained. NEPM (2013) and EPA guidelines recommend the use of two analytical laboratories for the implementation of a field QC program in addition to the internal QC procedures that are required to be followed by the laboratories in compliance to their NATA accreditation.

According to the NEPM (2013) the collection of intra- and inter-laboratory duplicate samples is required, along with blank samples. Intra-laboratory and inter-laboratory samples are duplicates of primary samples that are collected in the field. Intra-laboratory samples are analysed by the primary laboratory and are used as a check on the precision of the sampling and analytical procedures. Inter-laboratory samples are analysed by a secondary laboratory and provide a check of the accuracy of the analytical data.

According to the NEPM a split of a minimum of 10% of the primary samples as field duplicate samples (5% inter-laboratory and 5% intra-laboratory) as well as blank samples is required. Where less than 20 samples are to be analysed, a minimum of two field duplicate samples (one inter-laboratory and one intra-laboratory sample) and a blank sample is generally considered sufficient. Blank samples are generally collected daily during the sampling period and analysed where necessary.

For this contamination assessment, the following field quality control samples were collected and analysed:

- three intra-laboratory duplicate soil sample; and
- two inter-laboratory duplicate soil sample.

STS places an emphasis on implementing robust field-based decontamination procedures and sample collection/storage strategies. These are outlined in Section 10. By implementing the documented procedures STS considers that the accuracy and precision of the soil data used in this assessment has not been compromised. In view of this, the analysis of rinsate and trip blank samples was not considered necessary.

## 11.2 Quality Control Criteria

The analytical results of each duplicate were compared with the results for the primary sample using Relative Percent Difference (RPD). The RPD is defined as the absolute difference between two values divided by their mean.

Reference to AS 4482.1-2005 (and referenced in the NEPM) indicates that RPDs below 50% are considered to demonstrate a good correlation between duplicate sample results for inorganic species.

However, the same standard indicates possible higher RPDs for organics. Based on our experience, RPDs of up to 70% are considered acceptable for organic analytes. RPDs are not calculated when the analytical results for either the primary sample or the duplicate is less than the laboratory limits of reporting (LOR). RPDs of 100% or greater demonstrate a poor correlation, unless results are less than five times the analytical laboratory limits of reporting (LOR).

### 11.3 Laboratory Quality Control

A laboratory QC program involves the preparation and analysis of their own duplicate samples, reagent blanks and control samples (where the analyte concentration is known) or matrix spikes. Duplicate samples are subjected to the same preparation and analytical procedures as primary samples. The laboratories are required to analyse matrix spikes or control samples at a minimum frequency of 5% of the total number of primary samples in each sample batch.

The results of method blanks, duplicates and control sample analyses are compared by the laboratory to established quality assurance criteria for data precision and accuracy. If the results do not meet the criteria, then the analyses should be repeated. The relevant criteria are:

- method blanks should not return any positives on analysis;
- duplicate samples should not vary by more than 35% from the mean result; and
- control samples should generally give a recovery of 75-125%.

The laboratory QC program implemented for this assessment involved the preparation and analysis of laboratory duplicates, method blanks, laboratory control spike and surrogate samples. The results of the laboratory quality control are documented in Appendix G and indicate that the analytical results of the primary samples can be relied upon for the contamination assessment of the site.

## 12. ASSESSMENT CRITERIA

The *National Environmental Protection (Assessment of Site Contamination) Measure* (NEPM, 1999, 2013) is the key national guideline on the assessment and management of site contamination. (NEPM, 1999, 2013) guidelines are endorsed by the NSW EPA and the equivalent regulatory authorities in other Australian states.

The key NEPM criteria comprise Health-Based Investigation Levels (HILs) and the Ecologically-Based Investigation Levels (EILs)/Environmental Screening Levels (ESLs). The HILs are threshold values that are indicative of potential adverse impacts to human health.

EILs/ESLs are values that indicate potential phytotoxicity to plants and potential harm to other environment compartments.

EILs requires pH and Cation Exchange Capacity (CEC) data and in some cases the clay content of the soil. In the absence of pH and CEC data, EILs from NEPM (1999) are considered as screening levels for the evaluation of potential adverse (phytotoxic) impacts to vegetation.

In addition, the NEPM (2013) outlines criteria for key volatile hydrocarbon compounds which are designed to be protective of human-health via a soil vapour inhalation exposure pathway, the “Health Screening Levels” (HSLs).

Four classes of HIL are described in the NEPM (2013) to appraise the risks posed by site contamination for different land use settings. These include:

**HIL Residential A:** for a ‘standard’ residential land use with garden and accessible soil, including children’s day care centres, preschools and primary schools;

**HIL Residential B:** for a residential land use with minimal opportunities for soil access, including properties with fully and permanently paved yard space such as high-rise apartment buildings and flats;

**HIL Recreational C:** for public open spaces, such as parks, playgrounds, playing fields (e.g. ovals), secondary schools and footpaths, but excluding undeveloped public open space; and

**HIL Commercial/Industrial D:** for a commercial/industrial land use such as shops, offices, factories and industrial sites.

The HSLs outlined in the NEPM also include thresholds for the different land use settings as defined above, however, a combined set of criteria is provided that is to be applied for both Residential A and B land use settings.

Regarding the EILs and ESLs, a three-tiered set of criteria are provided for land uses including a) areas of ecological significance, b) urban residential and public open space, and c) commercial industrial.

The NEPM (2013) also outlines ‘management limits’ for petroleum hydrocarbons in soil which are designed to be thresholds which minimise the potential for light non-aqueous phase liquids (LNAPL) formation, fire and explosive hazards and penetration/damage to below ground infrastructure by hydrocarbons. These criteria are considered key when evaluating immediate impacts to human-health and the environment and long-term potential impacts associated with the on-site containment of contamination.

It is noted that the NEPM HILs do not include criteria for petroleum hydrocarbons, however, CRC Care’s *Technical Report No. 10: Health Screening Levels for Petroleum Hydrocarbons in Soil and Groundwater* (Friebel and Nadebaum, 2011) does provide health-based screening levels for key petroleum hydrocarbons based on the direct contact with

soil which may be used as alternative screening criteria. The 1999 NEPM also provides threshold HIL values for petroleum hydrocarbon fractions that may be adopted provided that speciation testing is undertaken for specific aromatic and aliphatic components.

Where a proposed land use will include more than one land use category (e.g. mixed residential/commercial development) the criteria which are protective of the most sensitive of the combined land uses should be adopted.

## 12.1 Criteria for this Assessment

As outlined in Section 2, the site is proposed to be redeveloped for use as a “Waste Resource Recovery Facility”. Proposed installations of the facility include a site office/showroom, parking lots, a 1540m<sup>2</sup> colourbond shed, processing and stockpiling areas, concrete paved turning bays, a weight bridge, landscaped areas, site drainage structures and a sedimentation basin.

Reference to the proposed site plan indicates that the existing dam on the west of the site will be backfilled and a retention basin is proposed further east. Further, the existing vegetation surrounding the existing dam will remain. In addition, compacted road base is proposed for the remaining areas facility.

The preliminary plans of the redevelopment and activities to be carried out at the proposed facility indicate a Commercial/Industrial setting. Therefore, “Commercial/Industrial D” criteria are considered the most applicable and are adopted for this investigation. The Commercial/Industrial D criteria are designed to be protective of human-health for commercial/industrial land uses such as shops, offices, factories and industrial sites.

Further, a conservative approach has been adopted to evaluate potential adverse impacts of potential contaminants to all areas of vegetation to be kept to the proposed landscaped zones. To this end, the 2013 NEPM EILs/ESLs and management limits for “Urban Residential and Public Open Space” have been used. In the absence of site specific pH and CEC data for the soils, NEPM (1999) EILs have also been adopted where applicable.

In addition, the background ranges for contaminants in Australian soils outlined in the 1999 NEPM have been considered.

With regards to the HSLs, ESLs and management limits, criteria applicable for clay soils have been used, since materials encountered at the site was predominantly silty clays. The criteria adopted for this investigation are outlined in Table 12.1 below.

**Table 12.1 – Site soil assessment criteria (inorganics)**

Contaminant	NEPM 1999 Background Ranges <sup>(6)</sup>	NEPM 2013 HIL D <sup>(1)</sup> /HSL (Commercial/Industrial) <sup>(2)</sup>	NEPM 2013 EIL/ ESL (Urban Residential & Public Open Space) <sup>(3)</sup>
Arsenic	1-50	3 000	100 (e)
Cadmium	1	900	3 (f)
Chromium	5-1000	3 600 (b)	400 (f), (j)
Copper	2-100	240 000	100 (f)
Lead	2-200	1 500	1100 (e)
Manganese	850	60 000	500 (f)
Mercury	0.03 (c)	730 (c)	1 (c), (f)
Nickel	5-500	6 000	60 (f)
Zinc	10-300	400 000	200 (f)
Bonded asbestos		0.01% (w/w) (k)	
Friable Asbestos		0.001% (w/w) (k)	
Asbestos fibres		No detectable (k)	

**Table 12.1 – Site soil assessment criteria (organics)**

Contaminant	NEPM 1999 Background Ranges <sup>(6)</sup>	NEPM 2013 HIL D <sup>(1)</sup> /HSL (Commercial/ Industrial) <sup>(2)</sup>	NEPM 2013 EIL/ ESL (Urban Residential & Public Open Space) <sup>(3)</sup>	CRC CARE 2011 HIL-D Direct Soil Contact <sup>(4)</sup>	NEPM 2013 Management. Limits (Urban Residential & Public Open Space) <sup>(5)</sup>
TPH (C <sub>6</sub> -C <sub>10</sub> )				5 100	
TPH (C <sub>10</sub> -C <sub>16</sub> )				3800	
F1 TPH (C <sub>6</sub> -C <sub>10</sub> ) (g)		45 (d)	180 (i)		800 (l)
F2 TPH (C <sub>10</sub> -C <sub>16</sub> ) (h)		110 (d)	120 (i)		1000 (l)
F3 TPH (C <sub>16</sub> -C <sub>34</sub> )			1 300 (i)	27 000	3 500 (l)
F4 TPH (C <sub>34</sub> -C <sub>40</sub> )			5 600 (i)	38 000	10 000 (l)
Benzene	0.05-1 (a)	4 (d)	65 (i)	1 100	
Toluene	0.1-1 (a)	NL	105(i)	99 000	
Ethylbenzene		NL	125 (i)	85 000	
Xylenes		NL	45 (i)	130 000	
Naphthalene		NL	170 (e)	29 000	
Benzo(a)pyrene			0.7 (i)		
Carcinogenic PAHs		40			
Total PAHs	0.95-5 (a)	4000			
Aldrin + Dieldrin		45			
Chlordane		530			
DDT+DDD+ DDE		3 600	180 (e), (m)		
Heptachlor		50			
Phenols	0.03-0.5 (a)	240 000			
PCBs	0.02-0.1 (a)	7			

Notes: All criteria in mg/kg concentrations unless otherwise specified

- (1) NEPM (2013) – Schedule B1 – HILs for Soil Contaminants – Commercial/Industrial D - Table 1A (1).
- (2) NEPM (2013) – Schedule B1 – HSLs for Vapour Intrusion – HSL D Commercial/Industrial -Table 1A (3.)
- (3) NEPM (2013) – Schedule B1 – Soil EILs and ESLs – Urban Residential and Public Open Space – Tables 1B (5) and 1B (6).
- (4) CRC CARE (2011) – Technical Report No. 10 – Soil HSLs for Direct Contact – HSL D Commercial/Industrial – Table B4.
- (5) NEPM (2013) – Schedule B1 – Management Limits for TPH Fractions F1-F4 in Soil – Table 1B (7).
- (6) NEPM (1999) – Schedule B1 – Soil Investigation Levels – Background Ranges - Table 5-A.
- (a) ANZECC 1992 background ranges used where no NEPM criteria available.
- (b) Criterion for chromium VI.
- (c) Criterion for inorganic mercury.
- (d) NEPM 2013 HSL criterion for vapour intrusion, 0-1m depth in clay soils.
- (e) 2013 NEPM generic EIL.
- (f) NEPM 1999 EIL used where no NEPM 2013 criteria are available.
- (g) F1 TPH = TPH (C6-C10) minus BTEX fraction.
- (h) F2 TPH = TPH (C10-C16) minus naphthalene fraction.
- (i) NEPM 2013 ESL criterion for fine textured soils.
- (j) Criterion for chromium III.
- (k) 2009 WA DOH/NEPM 2013 thresholds for asbestos in soil, residential land use setting (NEPM 2013 - Schedule B1 - Table 7).
- (l) NEPM 2013 NEPM management limit criterion for coarse texture grade soils
- (m) Criterion for DDT
- NL Contaminant is not considered to pose a risk to human health through vapour inhalation regardless the concentration.

## 13. ANALYTICAL RESULTS AND INTERPRETATION

The analytical results for the soil samples are presented in the laboratory reports included in Appendix G. The results were compared with the adopted assessment criteria defined in section 12.3 above. A summary is presented in Table A of this report.

### 13.1 Human-Health Risks

The analytical results show that the concentrations of organic and inorganic chemical contaminants in all samples tested are low and well below the NEPM (2013) HIL-D and HSL-Commercial/industrial criteria. All results are also below the CRC Care HSL-D criteria. Further, no asbestos fibres were detected.

These results indicate that the concentrations of chemical contaminants measured in the soil samples are below criteria that are protective of human-health for a commercial/industrial land use setting.

### 13.2 Environmental Risks

The concentrations of organic and inorganic contaminants measured in soil samples are also below the NEPM (2013) EIL/ESL criteria for an “urban residential setting and public space” and the NEPM (2013) management limits. Therefore, the contaminant concentrations measured in the soil samples do not present an unacceptable risk to plant health and the environment in general.

### 13.3 Risk of Groundwater Impacts

In view of the very low concentrations of chemical contaminants detected in the soils at the site and an assumed deep groundwater table, the site is not likely to have contributed to unacceptable groundwater impacts.

### 13.4 Potential for Off-Site Migration of Contamination

Low levels of contaminants were detected in the soil samples analysed. The contaminants are present at levels comparable to the lower bounds of background concentration ranges. Therefore, even if offsite migration, for instance, via surface runoff or wind action have occurred, unfavourable impacts to off-site receptors are unlikely.

### 13.5 Duty to Report Site Contamination

Under the provisions of the *Contaminated Land Management Act 1997* (CLM Act), a site owner or occupant has a duty to notify the EPA of any significant contamination that has the potential to cause human-health or environmental harm. The requirements for reporting contamination are set out in the EPA's "*Guidelines on the Duty to Report Contamination Under the Contaminated Land Management Act 1997*", (2015). The guidelines describe the conditions which trigger notification regarding the contamination of soil, groundwater and soil vapour.

The notification thresholds for soils are the HILs and soil-based HSLs, which are outlined in Schedule B1 of the *National Environment Protection Measure (NEPM)*, 1999 & 2013. Where contaminants in the soils on a site exceed HIL criteria by more than 2.5 times in any one sample or where the average concentrations (i.e. 95% upper confidence limits of the arithmetic mean of the contaminant concentrations) of contaminants in soil exceed the applicable HILs, and where persons may have been, or foreseeably will be exposed to the contamination, EPA must be notified.

The Duty to Report Guidelines also applies to asbestos contamination in soil that are provided in NEPM. The guidelines recommend reporting the presence of friable asbestos of anthropogenic sources if present at a weight-based percentage exceeding 0.001%. In addition, EPA must also be notified for source sites responsible for the specified contamination to be realised on adjacent lands. The Duty to Report Guidelines does not define notification thresholds for all contaminants. EPA recommends reliance on advice provided by an environmental consultant for contaminants with no specified criteria.

The results of the soil sampling performed for this investigation show that the concentrations of chemical contaminants measured in the soils on the site are low. No exceedance of adopted NEPM (2013) HIL/HSL criteria occurred. Therefore, based on currently available data there is no need to notify NSW EPA.

### 13.6 Assessment Outcomes

Based on the results of this investigation, the site does not present an unacceptable risk to human-health or the environment.

## 14. EVALUATION OF QUALITY ASSURANCE

### 14.1 Field Duplicate and Triplicate Sample Results

The results of the field intra-laboratory and inter-laboratory duplicate sample analyses are compared to those of the corresponding primary sample in Table B. The results show that for all the analytes, only the Relative Percentage Difference (RPD) for nickel exceeds the allowable criteria. The nickel concentration in the primary sample is smaller than background level and only 5mg/kg higher than the same level in the corresponding duplicate sample. Therefore, we consider this discrepancy to be insignificant and the data are thus reliable to represent the current contamination condition at the site. The same observation and conclusion applies to the RPDs calculated based on analyte concentration detected in the triplicate samples.

### 14.2 Laboratory Quality Control Program

Our review of the laboratory's internal QC program has shown that the all laboratory blanks, internal duplicate samples, laboratory control samples, matrix spike recoveries, and surrogate recovery standards were generally within the analytical laboratories' recommended range for acceptable reproducibility. Therefore, STS GeoEnvironmental considers the laboratory data obtained in the sampling program to be of acceptable precision, accuracy and reliability and representative of the site conditions encountered.

### 14.3 Procedure-Based Quality Control

An appraisal of the key procedure-based quality control aspects of the investigation are summarized in Table 14.1 below.

TABLE 14.1 APPRAISAL OF PROCEDURE-BASED QUALITY CONTROL

Item	Compliance	Reference/Comments
Appropriate sampling methods adopted?	Yes	Refer to Section 10
Appropriate sample handling and transportation procedures implemented?	Yes	Refer to Section 10 and COC documentation in Appendix F
Samples analysed within recommended laboratory holding times?	Yes	Refer to COC documentation in Appendix F and laboratory reports in Appendix G
NATA-accredited laboratory testing methods used?	Yes	Refer to laboratory reports in Appendix G

## 15. CONCLUSIONS AND RECOMMENDATIONS

Based on the results of this investigation the following conclusions and recommendations are made:

Based on the results of this preliminary site investigation the following conclusions and recommendations are made:

- the assessment indicates that activities associated with former and current land use at the site and immediate surrounding to be low.
- All measured contaminant concentrations are low and below the NEPM human health and environmental criteria. Further, no asbestos fibres were detected.
- the site is not likely to contain sources of contaminants which would adversely impact groundwater or other offsite receptors.
- there is low potential for contaminants presently located at the site which would adversely affect the proposed development and the site is considered suitable for the proposed commercial/industrial use.
- if during development, potentially contaminated soil is encountered, a contaminated land consultant needs to be contacted.

## 16. LIMITATIONS

STS GeoEnvironmental Pty Ltd has performed its services for this project in accordance with its current professional standards. Laboratory analyses were undertaken as part of this investigation by ALS Environmental in Sydney and in Brisbane, who are NATA-accredited for the analyses performed.

When assessing the extent of contamination across a site from a soil sampling program there is the possibility that variations may occur between sample locations and the actual presence of contaminated material at the site may differ from that referred to herein, since no sampling program, no matter how comprehensive, can reveal all anomalies and hot spots that may be present.

The data collected has been used to form an opinion about land contamination regarding the proposed use of the site, that being as a commercial/industrial use. If the nature of the proposed land use changes, the conclusions given in this report may need to be revised. Also, regulatory evaluation criteria are constantly changing and therefore, concentrations of contaminants presently considered low may, in the future, fall under different regulatory standards that may alter the outcome of this investigation. Opinions and judgments expressed herein, which are based on our understanding and interpretation of current regulatory standards, should not be construed as legal opinions.


This document and the information herein have been prepared solely for the use of AMJ Demolition & Excavation Pty Ltd for the purposes nominated in this report. No person or organization other than of AMJ Demolition & Excavation Pty Ltd are entitled to rely on any part of the report without the prior written consent of STS GeoEnvironmental Pty Ltd. Any third party relying on this report shall have no legal recourse against STS GeoEnvironmental Pty Ltd or its parent organizations or subsidiaries and shall indemnify and defend them from all and against all claims arising out of, or in conjunction with such use or reliance.

Report Written By:



J A. Pierre, MEngSc, GradCert  
Environmental Engineer

Report Reviewed By:



Laurie Ihnativ, BE, MEngSc, MBA  
Principal Geotechnical Engineer

## FIGURES



Map reproduced with permission of UBD.  
Copyright Universal Publishers Pty. Ltd DG05/04

**STS GEOENVIRONMENTAL PTY LTD**

Scale: 1:14400 (at A4)

Date: January 2018


**CLIENT: AMJ DEMOLITION AND EXCAVATION**

Drawn by: JAP — Reviewed by:

**LIMITED SITE INVESTIGATION  
55, MARTIN ROAD, BADGERYS CREEK, NSW SITE LOCATION  
SITE LOCATION**

Project No.  
21649/8652C

Drawing No: 18/0089/1




- |          |                                   |          |                   |          |                 |          |                 |
|----------|-----------------------------------|----------|-------------------|----------|-----------------|----------|-----------------|
| <b>1</b> | <b>One Storey Brick Residence</b> | <b>2</b> | <b>Metal Shed</b> | <b>3</b> | <b>Farm Dam</b> | <b>4</b> | <b>Junkyard</b> |
|----------|-----------------------------------|----------|-------------------|----------|-----------------|----------|-----------------|

#### LEGEND

- Site Boundary**
- 1** **Site Features**
- Slope**





# LEGEND



Site Boundary



Borehole Locations


BH1

Borehole Number



Slope





STS GEOENVIRONMENTAL PTY LTD

Scale: 1:14400 (at A4)

Date: January 2018

CLIENT: AMJ DEMOLITION AND EXCAVATION

Drawn by: JAP — Reviewed by:

LIMITED SITE INVESTIGATION  
55, MARTIN ROAD, BADGERYS CREEK, NSW SITE LOCATION  
EXISTING SITE PLAN

Project No.  
21649/8652C

Drawing No: 18/0089/4



**STS GEOENVIRONMENTAL PTY LTD**

Scale: 1:14400 (at A4)

Date: January 2018


**CLIENT: AMJ DEMOLITION AND EXCAVATION**

Drawn by: JAP — Reviewed by:

**LIMITED SITE INVESTIGATION  
55, MARTIN ROAD, BADGERYS CREEK, NSW SITE LOCATION  
PROPOSED SITE PLAN**

Project No.  
21649/8652C

Drawing No: 18/0089/5



## TABLES OF RESULTS

Table A Analytical Results for Primary Soil Samples

Analytes	Sample Date	Borehole No.										NEPM 1999 Background Ranges	NEPM 2013 HIL D/ HSL D (Commercial/Industrial)	NEPM 2013 EIL/ ESL (Urban Residential & Public Open Space)	CRC CARE 2011 HSL-A Direct Soil Contact	NEPM 2013 Management Limits (Residential, Parkland & Public Open Space)		
		BH1	BH2	BH2	BH3	BH3	BH4	BH4	BH4	BH4	BH6						BH6	
		Sample No.	S1/1-1	S2-1	S2-2	S3/1-1	S3/2-1	S4/1-1	S4/2-1	S4/5-1	S4/6-1						S6/1-1	S6/2-1
		Sample Depth	0.2	0.2	0.5	0.2	0.8	0.2	0.7	2.1	3						0.2	0.6
Type of Soil	Natural	Natural	Natural	Natural	Natural	Natural	Natural	Natural	Natural	Natural	Natural	Natural						
Sample Date	18-Jan-17	18-Jan-17	18-Jan-17	18-Jan-17	18-Jan-17	18-Jan-17	18-Jan-17	18-Jan-17	18-Jan-17	18-Jan-17	18-Jan-17	18-Jan-17						
Metals																		
Arsenic		<5	--	12	5	<5	10	10	<5	7	7	10	1-50	3 000	100 (e)			
Cadmium		<1	--	<1	<1	<1	<1	<1	<1	<1	<1	<1	1	900	3 (f)			
Chromium		8	--	26	16	13	19	18	13	12	19	16	5-1000	3 600 (b)	400 (f),(g)			
Copper		11	--	15	28	33	14	16	36	31	25	44	2-100	240 000	100 (f)			
Lead		16	--	13	19	19	19	9	14	13	18	17	2-200	1 500	1100 (e)			
Manganese		--	--	--	--	--	--	--	--	--	--	--	850	60 000	500 (f)			
Mercury		<0.1	--	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	0.03 (c)	730 (c)	1 (c),(f)			
Nickel		5	--	3	9	14	8	4	22	21	17	18	5-500	6 000	60 (f)			
Zinc		18	--	7	22	40	32	7	65	47	38	50	10-300	400 000	200 (f)			
Monocyclic Aromatic Hydrocarbons (MAHs)																		
Benzene		--	--	--	--	--	--	--	--	--	--	--	0.05-1 (a)	4 (d)	50 (h)	100		
Toluene		--	--	--	--	--	--	--	--	--	--	--	0.1-1 (a)	NL (d)	85 (h)	14000		
Ethylbenzene		--	--	--	--	--	--	--	--	--	--	--		NL (d)	70 (h)	4500		
Xylenes		--	--	--	--	--	--	--	--	--	--	--		NL (d)	105 (h)	12000		
Napthalene		--	--	--	--	--	--	--	--	--	--	--		NL (d)	170 (e)	1400		
Total MAHs above detection limits		--	--	--	--	--	--	--	--	--	--	--						
Total Petroleum Hydrocarbons (TPHs)																		
Total C <sub>6</sub> -C <sub>10</sub>		--	--	--	--	--	--	--	--	--	--	--				4400		
Total C <sub>10</sub> -C <sub>16</sub>		--	--	--	--	--	--	--	--	--	--	--				3300		
F1 C <sub>6</sub> -C <sub>10</sub> <sup>1</sup> (l)		--	--	--	--	--	--	--	--	--	--	--		310 (d)	180 (h)	700 (j)		
F2 C <sub>10</sub> -C <sub>16</sub> <sup>1</sup> (m)		--	--	--	--	--	--	--	--	--	--	--		NL (d)	120 (h)	1000 (j)		
F3 >C <sub>16</sub> -C <sub>34</sub>		--	--	--	--	--	--	--	--	--	--	--			300 (h)	4500		
F4 >C <sub>34</sub> -C <sub>40</sub>		--	--	--	--	--	--	--	--	--	--	--			2800 (h)	6300		
Total C <sub>10</sub> -C <sub>36</sub>		--	--	--	--	--	--	--	--	--	--	--				10000 (j)		
Polycyclic Aromatic Hydrocarbons (PAHs)																		
Benzo(a)pyrene (as BaP TEQ)		--	--	--	--	--	--	--	--	--	--	--			0.7 (h)			
Carcinogenic PAHs <sup>2</sup>		--	--	--	--	--	--	--	--	--	--	--		40				
Total PAHs above detection limits		--	--	--	--	--	--	--	--	--	--	--	0.95-5 (a)	4 000				
Organochlorine Pesticides (OCPs)																		
Aldrin + Dieldrin		<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	--	<0.05	--	<0.05	--			45			
Chlordane		<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	--	<0.05	--	<0.05	--			530			
DDT+DDD+ DDE		<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	--	<0.05	--	<0.05	--			3 600	180 (e),(i)		
Heptachlor		<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	--	<0.05	--	<0.05	--			50			
Total OCPs above detection limits		ND	ND	ND	ND	ND	ND		ND	ND	ND	--						
Organophosphorus Pesticides (OPPs)																		
Total OPPs above detection limits		ND	ND	ND	ND	ND	ND		ND	ND	ND	--						
Phenolic Compounds																		
Total Phenols above detection lim		--	--	--	--	--	--	--	--	--	--	--	0.03-0.5 (a)	240 000				
Polychlorinated Biphenyls (PCBs)																		
Total PCBs above detection limits		--	--	--	--	--	--	--	--	--	--	--	0.02-0.1 (a)	7				
Asbestos																		
Free Fibres		ND	ND	--	ND	--	--	--	ND	ND	--	--		No detectable	(k)			
Friable Asbestos (% w/w)		<0.001	<0.001	--	<0.001	--	--	--	<0.001	<0.001	--	--		0.001%	(k)			
Bonded Asbestos (% w/w)		<0.01	<0.01	--	<0.01	--	--	--	<0.01	<0.01	--	--		0.01%	(k)			

Notes : Results expressed as mg/kg unless otherwise indicated

NA = Not applicable

ND = No individual species detected abovelaboratory detection limits.

<sup>1</sup> Calculated in accordance with Table 1A(3) of NEPM 2013<sup>2</sup> Combined carcinogenic PAHs with relative potency to benzo(a)pyrene

(a) ANZECC 1992 background ranges used where no NEPM criteria available.

(b) Criterion for chromium VI.

(c) Criterion for inorganic mercury.

(d) NEPM 2013 HSL criterion for vapour intrusion, 0-1m depth in sandy soils.

(e) 2013 NEPM generic EIL.

(f) NEPM 1999 EIL used where no NEPM 2013 criteria are available.

(g) Criterion for chromium III

(h) NEPM ESL criterion for coarse texture grade soils.

(i) Criterion for DDT

(j) Criterion for coarse texture grade soils

(k) 2013 NEPM/WA DOH criteria for asbestos fibres in soil.

(l) F1 TPH = TPH (C6-C10) minus BTEX fraction.

(m) F2 TPH = TPH (C10-C16) minus naphthalene fraction.

Table A Analytical Results for Primary Soil Samples

Analytes	Sample Date	Borehole No.												NEPM 1999 Background Ranges	NEPM 2013 HIL D/ HSL D (Commercial/Industrial)	NEPM 2013 EIL/ ESL (Urban Residential & Public Open Space)	CRC CARE 2011 HSL-A Direct Soil Contact	NEPM 2013 Management Limits (Residential, Parkland & Public Open Space)
		BH7	BH7	BH8	BH8	BH9	BH10	BH11	BH12	BH14	BH14	BH15	BH16					
Sample No.		S7/1-1	S7/2-1	S8-1	S8-2	S9-1	S10-1	S11-1	S12/1-1	S14/1-1	S14/1-2	S15-1	S16-1					
Sample Depth		0.2	0.7	0.2	0.5	0.2	0.2	0.2	0.2	0.2	0.4	0.2	0.2					
Type of Soil		Natural	Natural	Natural	Natural	Natural	Natural	Natural	Natural	Natural	Natural	Natural	Natural					
Sample Date		18-Jan-17	18-Jan-17	18-Jan-17	18-Jan-17	18-Jan-17	18-Jan-17	18-Jan-17	18-Jan-17	18-Jan-17	18-Jan-17	18-Jan-17	18-Jan-17					
<b>Metals</b>																		
Arsenic		8	<5	10	11	--	--	9	8	16	15	12	16	1-50	3 000	100 (e)		
Cadmium		<1	<1	<1	<1	--	--	<1	<1	<1	<1	<1	<1	1	900	3 (f)		
Chromium		16	11	14	18	--	--	13	23	24	19	18	26	5-1000	3 600 (b)	400 (f),(g)		
Copper		15	24	13	14	--	--	16	13	26	31	21	15	2-100	240 000	100 (f)		
Lead		14	14	17	15	--	--	24	21	41	20	68	28	2-200	1 500	1100 (e)		
Manganese		--	--	--	--	--	--	--	--	--	--	--	--	850	60 000	500 (f)		
Mercury		<0.1	<0.1	<0.1	<0.1	--	--	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	0.03 (c)	730 (c)	1 (c),(f)		
Nickel		17	11	7	8	--	--	6	7	12	52	14	8	5-500	6 000	60 (f)		
Zinc		38	29	22	18	--	--	39	37	110	124	55	40	10-300	400 000	200 (f)		
<b>Monocyclic Aromatic Hydrocarbons (MAHs)</b>																		
Benzene		--	--	--	--	--	--	--	--	--	--	--	<0.2	0.05-1 (a)	4 (d)	50 (h)	100	
Toluene		--	--	--	--	--	--	--	--	--	--	--	<0.5	0.1-1 (a)	NL (d)	85 (h)	14000	
Ethylbenzene		--	--	--	--	--	--	--	--	--	--	--	<0.5		NL (d)	70 (h)	4500	
Xylenes		--	--	--	--	--	--	--	--	--	--	--	<0.5		NL (d)	105 (h)	12000	
Napthalene		--	--	--	--	--	--	--	--	--	--	--	<1		NL (d)	170 (e)	1400	
Total MAHs above detectio		--	--	--	--	--	--	--	--	--	--	--	ND					
<b>Total Petroleum Hydrocarbons (TPHs)</b>																		
Total C <sub>10</sub> -C <sub>10</sub>		--	--	--	--	--	--	--	--	--	--	--	<10				4400	
Total C <sub>10</sub> -C <sub>16</sub>		--	--	--	--	--	--	--	--	--	--	--	<50				3300	
F1 C <sub>10</sub> -C <sub>10</sub> (l)		--	--	--	--	--	--	--	--	--	--	--	<10		310 (d)	180 (h)	700 (j)	
F2 C <sub>10</sub> -C <sub>16</sub> (m)		--	--	--	--	--	--	--	--	--	--	--	<50		NL (d)	120 (h)	1000 (j)	
F3 >C <sub>16</sub> -C <sub>34</sub>		--	--	--	--	--	--	--	--	--	--	--	<100			300 (h)	4500	2500 (j)
F4 >C <sub>34</sub> -C <sub>40</sub>		--	--	--	--	--	--	--	--	--	--	--	<100			2800 (h)	6300	10000 (j)
Total C <sub>10</sub> -C <sub>36</sub>		--	--	--	--	--	--	--	--	--	--	--	<50					
<b>Polycyclic Aromatic Hydrocarbons (PAHs)</b>																		
Benzo(a)pyrene (as BaP T		--	--	--	--	--	--	--	--	--	--	--	<0.5			0.7 (h)		
Carcinogenic PAHs <sup>2</sup>		--	--	--	--	--	--	--	--	--	--	--	<0.5		40			
Total PAHs above detectio		ND	--	--	--	--	--	--	--	--	--	--	ND	0.95-5 (a)	4 000			
<b>Organochlorine Pesticides (OCPs)</b>																		
Aldrin + Dieldrin		<0.05	<0.05	<0.05	--	<0.05	<0.05	--	--	--	--	--	<0.05			45		
Chlordane		<0.05	<0.05	<0.05	--	<0.05	<0.05	--	--	--	--	--	<0.05			530		
DDT+DDD+ DDE		<0.05	<0.05	<0.05	--	<0.05	<0.05	--	--	--	--	--	<0.05		3 600	180 (e),(l)		
Heptachlor		<0.05	<0.05	<0.05	--	<0.05	<0.05	--	--	--	--	--	<0.05		50			
Total OCPs above detectio		ND	ND	ND	--	ND	ND	--	--	--	--	--	ND					
<b>Organophosphorus Pesticides (OPPs)</b>																		
Total OPPs above detectio		ND	ND	ND	--	ND	ND	ND	--	ND	--	--	ND					
<b>Phenolic Compounds</b>																		
Total Phenols above detec		--	--	--	--	--	--	ND	--	ND	--	--	ND	0.03-0.5 (a)	240 000			
<b>Polychlorinated Biphenyls (PCBs)</b>																		
Total PCBs above detectio		--	--	--	--	--	--	<0.1	--	<0.1	--	--	<0.1	0.02-0.1 (a)	7			
<b>Asbestos</b>																		
Type																		
Free Fibres		ND	--	ND	--	--	--	ND	--	ND	--	ND	ND		No detectable	(k)		
Friable Asbestos (% w/w)		<0.001	--	<0.001	--	--	--	<0.001	--	<0.001	--	<0.001	<0.001		0.001%	(k)		
Bonded Asbestos (% w/w)		<0.01	--	<0.01	--	--	--	<0.01	--	<0.01	--	<0.01	<0.01		0.01%	(k)		

Notes : Results expressed as mg/kg unless otherwise indicated

NA = Not applicable

ND = No individual species detected above laboratory detection limits.

<sup>1</sup> Calculated in accordance with Table 1A(3) of NEPM 2013<sup>2</sup> Combined carcinogenic PAHs with relative potency to benzo(a)pyrene

(a) ANZECC 1992 background ranges used where no NEPM criteria available.

(b) Criterion for chromium VI.

(c) Criterion for inorganic mercury.

(d) NEPM 2013 HSL criterion for vapour intrusion, 0-1m depth in sandy soils.

(e) 2013 NEPM generic EIL.

(f) NEPM 1999 EIL used where no NEPM 2013 criteria are available.

(g) Criterion for chromium III

(h) NEPM ESL criterion for coarse texture grade soils.

(i) Criterion for DDT

(j) Criterion for coarse texture grade soils

(k) 2013 NEPM/WA DOH criteria for asbestos fibres in soil.

(l) F1 TPH = TPH (C6-C10) minus BTEX fraction.

(m) F2 TPH = TPH (C10-C16) minus naphthalene fraction.

Table A Analytical Results for Primary Soil Samples

Analytes	Borehole No.	BH18	NEPM 1999 Background Ranges	NEPM 2013 HIL D/ HSL D (Commercial/Industrial)	NEPM 2013 EIL/ ESL (Urban Residential & Public Open Space)	CRC CARE 2011 HSL-A Direct Soil Contact	CRC CARE 2011 HSL-B Direct Soil Contact	NEPM 2013 Management Limits (Residential, Parkland & Public Open Space)
	Sample No.	S18-1						
	Sample Depth	0.2						
	Type of Soil	Natural						
Sample Date	18-Jan-17							
<b>Metals</b>								
Arsenic	11		1-50	3 000	100 (e)			
Cadmium	<1		1	900	3 (f)			
Chromium	28		5-1000	3 600 (b)	400 (f),(g)			
Copper	15		2-100	240 000	100 (f)			
Lead	26		2-200	1 500	1100 (e)			
Manganese	--		850	60 000	500 (f)			
Mercury	<0.1		0.03 (c)	730 (c)	1 (c),(f)			
Nickel	7		5-500	6 000	60 (f)			
Zinc	38		10-300	400 000	200 (f)			
<b>Monocyclic Aromatic Hydrocarbons (MAHs)</b>								
Benzene	--		0.05-1 (a)	4 (d)	50 (h)	100		140
Toluene	--		0.1-1 (a)	NL (d)	85 (h)	14000		21000
Ethylbenzene	--			NL (d)	70 (h)	4500		5900
Xylenes	--			NL (d)	105 (h)	12000		17000
Napthalene	--			NL (d)	170 (e)	1400		2200
Total MAHs above detection limits	--							
<b>Total Petroleum Hydrocarbons (TPHs)</b>								
Total C <sub>6</sub> -C <sub>10</sub>	--					4400		5600
Total C <sub>10</sub> -C <sub>16</sub>	--					3300		4200
F1 C <sub>6</sub> -C <sub>10</sub> (l)	--			310 (d)	180 (h)			700 (j)
F2 C <sub>10</sub> -C <sub>16</sub> (m)	--			NL (d)	120 (h)			1000 (j)
F3 >C <sub>16</sub> -C <sub>34</sub>	--				300 (h)	4500		5800
F4 >C <sub>34</sub> -C <sub>40</sub>	--				2800 (h)	6300		8100
Total C <sub>10</sub> -C <sub>36</sub>	--							10000 (j)
<b>Polycyclic Aromatic Hydrocarbons (PAHs)</b>								
Benzo(a)pyrene (as BaP TEQ)	--				0.7 (h)			
Carcinogenic PAHs <sup>2</sup>	--			40				
Total PAHs above detection limits	ND		0.95-5 (a)	4 000				
<b>Organochlorine Pesticides (OCPs)</b>								
Aldrin + Dieldrin	<0.05			45				
Chlordane	<0.05			530				
DDT+DDD+ DDE	<0.05			3 600	180 (e),(i)			
Heptachlor	<0.05			50				
Total OCPs above detection limits	ND							
<b>Organophosphorus Pesticides (OPPs)</b>								
Total OPPs above detection limits	ND							
<b>Phenolic Compounds</b>								
Total Phenols above detection limits	--		0.03-0.5 (a)	240 000				
<b>Polychlorinated Biphenyls (PCBs)</b>								
Total PCBs above detection limits	--		0.02-0.1 (a)	7				
<b>Asbestos</b>								
Type								
Free Fibres	ND			No detectable	(k)			
Friable Asbestos (% w/w)	<0.001			0.001%	(k)			
Bonded Asbestos (% w/w)	<0.01			0.01%	(k)			

Notes : Results expressed as mg/kg unless otherwise indicated

NA = Not applicable

ND = No individual species detected above laboratory detection limits.

<sup>1</sup> Calculated in accordance with Table 1A(3) of NEPM 2013<sup>2</sup> Combined carcinogenic PAHs with relative potency to benzo(a)pyrene

(a) ANZECC 1992 background ranges used where no NEPM criteria available.

(b) Criterion for chromium VI.

(c) Criterion for inorganic mercury.

(d) NEPM 2013 HSL criterion for vapour intrusion, 0-1m depth in sandy soils.

(e) 2013 NEPM generic EIL.

(f) NEPM 1999 EIL used where no NEPM 2013 criteria are available.

(g) Criterion for chromium III

(h) NEPM ESL criterion for coarse texture grade soils.

(i) Criterion for DDT

(j) Criterion for coarse texture grade soils

(k) 2013 NEPM/WA DOH criteria for asbestos fibres in soil.

(l) F1 TPH = TPH (C6-C10) minus BTEX fraction.

(m) F2 TPH = TPH (C10-C16) minus naphthalene fraction.

(n) 2013 NEPM generic EIL for DDT.

Table B Results of Quality Control - Intra and Inter Laboratory Duplicate Samples

Analyte	Sample Numbers								
	S2-1	Dup1	RPD (%)	S8-1	Dup2	RPD (%)	S11-1	Dup3	RPD (%)
<b>Metals</b>									
Arsenic	--	--	--	10	10	0	9	13	36
Cadmium	--	--	--	<1	<1	<50	<1	<1	<50
Chromium	--	--	--	14	21	40	13	20	42
Copper	--	--	--	13	18	32	16	18	12
Lead	--	--	--	17	20	16	24	18	29
Manganese	--	--	--	--	--	--	--	--	--
Mercury	--	--	--	<0.1	<0.1	<50	<0.1	<0.1	<50
Nickel	--	--	--	2	10	133	6	9	40
Zinc	--	--	--	22	43	65	39	44	12
<b>Organochlorine Pesticides (OCPs)</b>									
alpha-BHC	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Hexachlorobenzene (HCB)	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
beta-BHC	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
gamma-BHC	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
delta-BHC	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Heptachlor	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Aldrin	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Heptachlor epoxide	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Total Chlordane (sum)	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
trans-Chlordane	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
alpha-Endosulfan	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
cis-Chlordane	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Dieldrin	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
4,4'-DDE	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Endrin	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Endosulfan (sum)	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
beta-Endosulfan	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
4,4'-DDD	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Endrin aldehyde	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Endosulfan sulfate	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
4,4'-DDT	<0.2	<0.2	<70	<0.2	<0.2	<70	--	--	--
Endrin ketone	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Methoxychlor	<0.2	<0.2	<70	<0.2	<0.2	<70	--	--	--
Sum of DDD + DDE + DDT	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Sum of Aldrin + Dieldrin	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
<b>Organophosphorus Pesticides (OP)</b>									
Dichlorvos	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Demeton-S-methyl	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Monocrotophos	<0.2	<0.2	<70	<0.2	<0.2	<70	--	--	--
Dimethoate	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Diazinon	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Chlorpyrifos-methyl	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Parathion-methyl	<0.2	<0.2	<70	<0.2	<0.2	<70	--	--	--
Malathion	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Fenthion	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Chlorpyrifos	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Parathion	<0.2	<0.2	<70	<0.2	<0.2	<70	--	--	--
Pirimphos-ethyl	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Chlorfenvinphos	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Bromophos-ethyl	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Fenamiphos	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Prothiofos	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Ethion	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Carbophenothion	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--
Azinphos Methyl	<0.05	<0.05	<70	<0.05	<0.05	<70	--	--	--

Note: Results expressed as mg/kg dry weight unless otherwise specified.

 RPDs that have been shaded exceed the acceptance criteria

Table B Results of Quality Control - Intra and Inter Laboratory Duplicate Samples

Analyte	Sample Numbers					
	S2-1	Trip1	RPD (%)	S8-1	Trip2	RPD (%)
<b>Metals</b>						
Arsenic	--	--	--	10	11	-10
Cadmium	--	--	--	<1	<1	<50
Chromium	--	--	--	14	17	19
Copper	--	--	--	13	16	21
Lead	--	--	--	17	22	26
Manganese	--	--	--	--	--	--
Mercury	--	--	--	<0.1	<0.1	<50
Nickel	--	--	--	2	10	133
Zinc	--	--	--	22	35	46
<b>Organochlorine Pesticides (OCPs)</b>						
alpha-BHC	<0.05	<0.05	<70	<0.05	<0.05	<70
Hexachlorobenzene (HCB)	<0.05	<0.05	<70	<0.05	<0.05	<70
beta-BHC	<0.05	<0.05	<70	<0.05	<0.05	<70
gamma-BHC	<0.05	<0.05	<70	<0.05	<0.05	<70
delta-BHC	<0.05	<0.05	<70	<0.05	<0.05	<70
Heptachlor	<0.05	<0.05	<70	<0.05	<0.05	<70
Aldrin	<0.05	<0.05	<70	<0.05	<0.05	<70
Heptachlor epoxide	<0.05	<0.05	<70	<0.05	<0.05	<70
Total Chlordane (sum)	<0.05	<0.05	<70	<0.05	<0.05	<70
trans-Chlordane	<0.05	<0.05	<70	<0.05	<0.05	<70
alpha-Endosulfan	<0.05	<0.05	<70	<0.05	<0.05	<70
cis-Chlordane	<0.05	<0.05	<70	<0.05	<0.05	<70
Dieldrin	<0.05	<0.05	<70	<0.05	<0.05	<70
4,4'-DDE	<0.05	<0.05	<70	<0.05	<0.05	<70
Endrin	<0.05	<0.05	<70	<0.05	<0.05	<70
Endosulfan (sum)	<0.05	<0.05	<70	<0.05	<0.05	<70
beta-Endosulfan	<0.05	<0.05	<70	<0.05	<0.05	<70
4,4'-DDD	<0.05	<0.05	<70	<0.05	<0.05	<70
Endrin aldehyde	<0.05	<0.05	<70	<0.05	<0.05	<70
Endosulfan sulfate	<0.05	<0.05	<70	<0.05	<0.05	<70
4,4'-DDT	<0.2	<0.2	<70	<0.2	<0.2	<70
Endrin ketone	<0.05	<0.05	<70	<0.05	<0.05	<70
Methoxychlor	<0.2	<0.2	<70	<0.2	<0.2	<70
Sum of DDD + DDE + DDT	<0.05	<0.05	<70	<0.05	<0.05	<70
Sum of Aldrin + Dieldrin	<0.05	<0.05	<70	<0.05	<0.05	<70
<b>Organophosphorus Pesticides (OP)</b>						
Dichlorvos	<0.05	<0.05	<70	<0.05	<0.05	<70
Demeton-S-methyl	<0.05	<0.05	<70	<0.05	<0.05	<70
Monocrotophos	<0.2	<0.2	<70	<0.2	<0.2	<70
Dimethoate	<0.05	<0.05	<70	<0.05	<0.05	<70
Diazinon	<0.05	<0.05	<70	<0.05	<0.05	<70
Chlorpyrifos-methyl	<0.05	<0.05	<70	<0.05	<0.05	<70
Parathion-methyl	<0.2	<0.2	<70	<0.2	<0.2	<70
Malathion	<0.05	<0.05	<70	<0.05	<0.05	<70
Fenthion	<0.05	<0.05	<70	<0.05	<0.05	<70
Chlorpyrifos	<0.05	<0.05	<70	<0.05	<0.05	<70
Parathion	<0.2	<0.2	<70	<0.2	<0.2	<70
Pirimphos-ethyl	<0.05	<0.05	<70	<0.05	<0.05	<70
Chlorfenvinphos	<0.05	<0.05	<70	<0.05	<0.05	<70
Bromophos-ethyl	<0.05	<0.05	<70	<0.05	<0.05	<70
Fenamiphos	<0.05	<0.05	<70	<0.05	<0.05	<70
Prothiofos	<0.05	<0.05	<70	<0.05	<0.05	<70
Ethion	<0.05	<0.05	<70	<0.05	<0.05	<70
Carbophenothion	<0.05	<0.05	<70	<0.05	<0.05	<70
Azinphos Methyl	<0.05	<0.05	<70	<0.05	<0.05	<70

Note: Results expressed as mg/kg dry weight unless otherwise specified.


 RPDs that have been shaded exceed the acceptance criteria

## APPENDIX A – AERIAL PHOTOGRAPHS AND SATELLITE IMAGERY

1947 Aerial Photograph Showing the Site and Surrounds



Legend

 Site Boundary

Approximate Scale 1:5,000

Image Copyright © Land and Property Information, NSW

**STS**  
GeoEnvironmental  
Pty Ltd  
Geotechnical and Environmental Solutions

1961 Aerial Photograph Showing the Site and Surrounds



Legend  
Site Boundary




Approximate Scale 1:5,000

Image Copyright © Land and Property Information, NSW

1970 Aerial Photograph Showing the Site and Surrounds



Legend

 Site Boundary



Approximate Scale 1:5,000

Image Copyright © Land and Property Information, NSW

1986 Aerial Photograph Showing the Site and Surrounds



1994 Aerial Photograph Showing the Site and Surrounds




# 2007 Aerial Photograph Showing the Site and Surrounds



2014 Aerial Photograph Showing the Site and Surrounds



Legend

 Site Boundary



Approximate Scale 1:5,000

Image Copyright © Land and Property Information, NSW

**STS**  
GeoEnvironmental  
Pty Ltd  
Geotechnical and Environmental Solutions

2016 Aerial Photograph Showing the Site and Surrounds



2017 Aerial Photograph Showing the Site and Surrounds



## APPENDIX B – SECTION 149 (2) CERTIFICATE

**PLANNING CERTIFICATE UNDER SECTION 149  
ENVIRONMENTAL PLANNING AND ASSESSMENT ACT 1979**

**Ref.:** 46135867:54156  
**Ppty:** 16795

**Cert. No.:** 1044

**Applicant:**  
SAI GLOBAL PROPERTY  
PO BOX 447  
SOUTH MELBOURNE VIC 3205

**Receipt No.:** 3703110  
**Receipt Amt.:** 53.00  
**Date:** 23-Aug-2017

The information in this certificate is provided pursuant to Section 149(2) of the Environmental Planning and Assessment Act (EP&A Act) 1979, as prescribed by Schedule 4 of the Environmental Planning and Assessment Regulation (EP&A Regulation) 2000. The information has been extracted from Council's records, as they existed at the date listed on the certificate. Please note that the accuracy of the information contained within the certificate may change after the date of this certificate due to changes in Legislation, planning controls or the environment of the land.

The information in this certificate is applicable to the land described below.

**Legal Description:** LOT 4 DP 611519  
**Street Address:** 55 MARTIN ROAD, BADGERYS CREEK NSW 2555

*Note: Items marked with an asterisk (\*) may be reliant upon information transmitted to Council by a third party public authority. The accuracy of this information cannot be verified by Council and may be out-of-date. If such information is vital for the proposed land use or development, applicants should instead verify the information with the appropriate authority.*

*Note: Commonly Used Abbreviations:*

**LEP:** Local Environmental Plan  
**DCP:** Development Control Plan  
**SEPP:** State Environmental Planning Policy  
**EPI:** Environmental Planning Instrument

## 1. Names of relevant planning instruments and DCPs

- (a) The name of each EPI that applies to the carrying out of development on the land is/are listed below:

LEPs:

**Liverpool LEP 2008**

SEPPs\*:

**SEPP No. 33 – Hazardous and Offensive Development**  
**SEPP No. 50 – Canal Estate Development**  
**SEPP No. 55 – Remediation of Land**  
**SEPP No. 62 – Sustainable Aquaculture**  
**SEPP No. 65 – Design Quality of Residential Flat Development**  
**SEPP (Building Sustainability Index: BASIX) 2004**  
**SEPP No. 70 – Affordable Housing (Revised Schemes)**  
**SEPP (Infrastructure) 2007**  
**SEPP (Mining, Petroleum Production and Extractive Industries) 2007**  
**SEPP (Miscellaneous Consent Provisions) 2007**  
**SEPP (State and Regional Development) 2011**  
**SEPP No 19 – Bushland in Urban Areas**  
**SEPP No 21 – Caravan Parks**  
**SEPP No 30 – Intensive Agriculture**  
**SEPP No 44 – Koala Habitat Protection**  
**SEPP (Exempt and Complying Development Codes) 2008**  
**SEPP No 64 – Advertising and Signage**  
**SEPP (Affordable Rental Housing) 2009**  
**SEPP (Sydney Region Growth Centres) 2006**

Deemed SEPPs\*:

**SREP No 20 – Hawkesbury – Nepean River (No. 2 – 1997)**

- (b) The name of each draft EPI, or Planning Proposal (which has been subject to community consultation).

Draft LEPs:

**N/A**

Draft SEPPs\*:

**Draft SEPP (Competition) 2010**

- (c) The name of each DCP that applies to the carrying out of development on the land.

**Liverpool DCP 2008**

## 2. Zoning and land use under relevant LEPs and /or SEPPs

This section contains information required under subclauses 2 and 2A of Schedule 4 of the EP&A Regulation 2000. Subclause 2 of the regulation requires Council to provide information with respect to zoning and land-use in areas zoned by, or proposed to be zoned by, a LEP. Subclause 2A of Schedule 4 of the regulation requires Council to provide information with respect to zoning and land-use in areas which are zoned by, or proposed to be zoned by, the SEPP (Sydney Region Growth Centres) 2006. The land use and zoning information under any EPI applying to the land is given below.

- (a) Name of zone, and the EPI from which the land zoning information is derived.

**RU1 Primary Production - Liverpool LEP 2008**

- (b) The purposes for which development may be carried out within the zone without the need for development consent

**Environmental protection works; Extensive agriculture; Home-based child care; Home occupations**

- (c) The purposes for which development may not be carried out within the zone except with development consent

**Agriculture; Airstrips; Animal boarding or training establishments; Bed and breakfast accommodation; Building identification signs; Business identification signs; Cemeteries; Community facilities; Crematoria; Dual occupancies; Dwelling houses; Environmental facilities; Extractive industries; Farm buildings; Farm stay accommodation; Flood mitigation works; Forestry; Hazardous storage establishments; Health consulting rooms; Helipads; Heliports; Home businesses; Home industries; Landscaping material supplies; Offensive storage establishments; Open cut mining; Plant nurseries; Recreation areas; Recreation facilities (outdoor); Roads; Roadside stalls; Rural industries; Rural supplies; Rural workers' dwellings; Secondary dwellings; Veterinary hospitals; Water recreation structures**

- (d) The purposes for which the instrument provides that development is prohibited within the zone

**Any development not specified in item (b) or (c)**

- (e) If a dwelling house is a permitted use, are there any principal development standards applying to the land that fix minimum land dimensions for the erection of a dwelling house?

**No**

(f) Does the land include or comprise critical habitat?

**No**

(g) Is the land is in a conservation area (however described):

**No**

(h) Is there an item of environmental heritage (however described) situated on the land

**No**

### 3. Complying development

The information below outlines whether complying development is permitted on the land as per the provisions of clauses 1.17A (1) (c) to (e), (2), (3) and (4), 1.18(1) (c3) and 1.19 SEPP of the (Exempt and Complying Development Codes) 2008.

The first column identifies the code(s). The second column describes the extent of the land in which exempt and complying development is permitted for the code(s) given to the immediate left. The third column indicates the reason as to why exempt and complying development is prohibited on some or all of the land, and will be blank if such development is permitted on all of the land.

Code	Extent of the land for which development is permitted:	The reason(s) as to why development is prohibited:
General Housing Code and Rural Housing Code	<b>None</b>	All of the land is identified as being within an <b>ANEF</b> contour of greater than or equal to 25, unless the development is only for the erection of ancillary development, the alteration of or an addition to ancillary development or the alteration of a dwelling house (Clause 1.19(1)(h))

Code	Extent of the land for which development is permitted:	The reason(s) as to why development is prohibited:
Commercial and Industrial (New Buildings and Additions) Code	All	
General Development Code, Fire Safety Code, Housing Alterations Code, Commercial and Industrial Alterations Code, Subdivisions Code, and Demolition Code	All	

Note: If council does not have sufficient information to ascertain the extent to which complying development may or may not be carried out on the land, a statement below will describe that a restriction applies to the land, but it may not apply to all of the land, and that council does not have sufficient information to ascertain the extent to which complying development may or may not be carried out on the land.

Nil

#### 4. Coastal protection\*

Has the Department of Finance, Services and Innovation notified Council of the land being affected by 38 or 39 of the Coastal Protection Act, 1979?

No

#### 4A. Certain information relating to beaches and coasts\*

(a) Has an order has been made under Part 4D of the Coastal Protection Act 1979 on the land (or on public land adjacent to that land)?

No

(b) Has Council been notified under section 55X of the Coastal Protection Act 1979 that temporary coastal protection works have been placed on the land (or on public land adjacent to that land), and if works have been so placed, is council is satisfied that the works have been removed and the land restored in accordance with that Act?

Not applicable

#### 4B. Annual charges under Local Government Act 1993 for coastal protection services that relate to existing coastal protection works\*

Has the owner (or any previous owner) of the land consented, in writing, that the land is subject to annual charges under section 496B of the Local Government Act 1993 for coastal protection services that relate to existing coastal protection works (within the meaning of section 553B of that Act)?

No

## 5. Mine subsidence\*

Is the land a proclaimed to mine subsidence district within the meaning of section 15 of the Mine Subsidence Compensation Act 1961?

No

## 6. Road widening and road realignment

Is the land is affected by any road widening or road realignment under:

(a) Division 2 of Part 3 of the Roads Act 1993?\*

No

(b) An EPI?

No

(c) A resolution of the council?

No

## 7. Council and other public authority policies on hazard risk restrictions

The following table lists hazard/risk policies that have been adopted by Council (or prepared by another public authority and subsequently adopted by Council). The right-most column indicates whether the land is subject to those policies.

Hazard/Risk		Adopted Policy	Does this hazard/risk policy apply to the land?
<b>Landslip hazard</b>	Nil		<b>No</b>
<b>Bushfire hazard</b>	Liverpool DCP 2008		<b>No</b>

Hazard/Risk	Adopted Policy	Does this hazard/risk policy apply to the land?
	Liverpool Growth Centre Precincts DCP*	No
	Edmondson Park South DCP 2012	No
	Planning for Bushfire Protection (Rural Fire Services, 2006)*	No
	Pleasure Point Bushfire Management Plan	No
<b>Tidal inundation</b>	Nil	No
<b>Subsidence</b>	Nil	No
<b>Acid Sulphate Soils</b>	Liverpool LEP 2008	No
	Liverpool DCP 2008	No
<b>Potentially Contaminated Land</b>	Liverpool DCP 2008	Yes, see section 10 of Part 1 of the Liverpool DCP 2008
	Liverpool Growth Centre Precincts DCP*	No
<b>Potentially Saline Soils</b>	Liverpool DCP 2008	Yes
	Liverpool Growth Centre Precincts DCP*	No

Note: Land for which a policy applies does not confirm that the land is affected by that hazard/risk. For example, all land for which the Liverpool DCP applies is subject to controls relating to contaminated land, as this policy contains triggers and procedures for identifying potential contamination. Applicants are encouraged to review the relevant policy, and other sections of this certificate, to determine what effect, if any, the policy may have on the land.

## 7A. Flood related development controls information

- (a) For the purpose of residential accommodation (excluding group homes or seniors housing), is the land, or part of the land, within the flood planning area and subject to flood planning controls?

No

For details of these controls, please refer to the flooding section of the relevant DCP(s) as specified in Section 1(c) of this certificate.

- (b) Is development on that land, or part of the land, for any other purpose subject to flood related development controls?

No

For details of these controls, please refer to the flooding section of the relevant DCP(s) as specified in Section 1(c) of this certificate.

*Note: Words and expressions in this clause have the same meanings as in the instrument set out in the Schedule to the Standard Instrument (Local Environmental Plans) Order 2006.*

## **8. Land reserved for acquisition**

Does a LEP, draft LEP, SEPP or draft SEPP identify the acquisition of the land, or part of the land, by a public authority, as referred to in section 27 of the Act?

No

## **9. Contribution Plans**

**Liverpool Contributions Plan 2009**

## **9A. Biodiversity certified land\***

Is the land, or part of the land, biodiversity certified land (within the meaning of Part 7AA of the Threatened Species Conservation Act 1995)?

Yes, part/all of the land is bio-diversity certified land

## **10. Biobanking agreements\***

Is the land subject to a bio-banking agreement under Part 7A of the Threatened Species Conservation Act 1995, as notified to Council by the Chief Executive of the Office of Environment and Heritage?

No

### **11. Bushfire prone land**

Is the land or part of the land, bushfire prone land as defined by the EP&A Act 1979?

No

### **12. Property vegetation plans\***

Is Council aware of the land being subject to a Property Vegetation Plan under the Native Vegetation Act 2003?

No, Liverpool is excluded from the operation of the Native Vegetation Act 2003

### **13. Orders under Trees (Disputes between Neighbours) Act 2006\***

Does an order, made under the Trees (Disputes Between Neighbours) Act 2006 in relation to carrying out of work in relation to a tree on the land, apply?

No, Council has not been notified of an order

### **14. Directions under Part 3A\***

Is there a direction (made by the Minister) that a provision of an EPI in relation to a development does not have effect?

No

### **15. Site compatibility certificates and conditions for seniors housing\***

(a) Is there is a current site compatibility certificate (seniors housing), in respect of proposed development on the land?

No, Council has not been notified of an order.

### **16. Site compatibility certificates for infrastructure\***

(a) Is there is a current site compatibility certificate (infrastructure), in respect of proposed development on the land?

No, Council has not been notified of an order

## **17. Site compatibility certificates and conditions for affordable rental housing\***

Is there is a current site compatibility certificate (Affordable housing), in respect of proposed development on the land?

No, Council has not been notified of an order.

## **18. Paper subdivision information\***

Does any development plan adopted by a relevant authority (or proposed plan subject to a consent ballot) apply to the land? If so the date of the subdivision order that applies to the land.

No

## **19. Site verification certificates\***

Does a current site verification certificate, apply to the land?

No, Council is not aware of a site verification certificate

## **20. Loose-fill asbestos insulation \***

Is a dwelling on the land listed on the register (maintained by the NSW Department of Fair Trading) as containing loose-fill asbestos insulation?

No

Note: despite any listing on the register, any buildings constructed before 1980 may contain loose-fill asbestos insulation or other asbestos products.

## **21. Contaminated land**

Is the land:

(a) Significantly contaminated land within the meaning of that Act?

No

(b) Subject to a management order within the meaning of that Act?

No

(c) Subject of an approved voluntary management proposal within the meaning of that Act?

No

(d) Subject to an ongoing maintenance order within the meaning of that Act?

No

(e) Subject of a site audit statement within the meaning of that Act? \*

No

Note: in this clause 'the Act' refers to the Contaminated Land Management Act 1997.



For further information, please contact  
CALL CENTRE – 1300 36 2170

Luke West  
Administration Services Coordinator  
Liverpool City Council

## APPENDIX C – HISTORICAL TITLES

# SEARCH REPORT

---

LPI

RECORDS BRANCH

SUBJECT LAND: Lot 4 in DP 611519

55 Martin Road, Badgerys Creek

## OWNERSHIP:

From 17/2/1930 to 15/4/1943 - The Sydney City Mission

From 15/4/1943 to 1/6/1981 - Mervyn Joseph Nobbs of Badgerys Creek, Farmer

From 1/6/1981 to 6/5/1998 - Kenneth John Nobbs & Jeffrey Nobbs

From 6/5/1998 to date - Helen Nobbs & Jeffrey Nobbs

LEASES - NIL

24<sup>th</sup> August 2107

SAI Global

per *R Williamson*

NEW SOUTH WALES

**CERTIFICATE OF TITLE**  
**PROPERTY ACT, 1900, as amended.**



10483103

Appln. No.8474

Prior Title Vol.1565 Fol. 58

Vol. **10483** Fol. **103**

Edition issued 20-1-1967

AS K526490



I certify that the person described in the First Schedule is the registered proprietor of the undermentioned land within described subject nevertheless to such exceptions encumbrances and interests as are shown in the Second Schedule.


Witness

*S. Vandine*

*Jawatson*  
Registrar General.



PLAN SHOWING LOCATION OF LAND



K526490

*JB*

Scale: 5 chains to one inch.

**ESTATE AND LAND REFERRED TO**

Estate in Fee Simple in the land shown in plan lodged with Transfer No.394029 (Filed as F.P.105559) in the City of Liverpool Parish of Bringelly and County of Cumberland, being part of Lot 37 in Deposited Plan 3050 shown in the plan hereon being part of Portion 31 granted to Thomas Matcham Pitt on 1-1-1810 and part of Portion 32 granted to Edward Powell on 1-1-1810.

**FIRST SCHEDULE (Continued overleaf)**

MERVYN JOSEPH NOBBS of Badgerys Creek, Farmer.

*Jawatson*  
Registrar General

**SECOND SCHEDULE (Continued overleaf)**

1. Reservations and conditions, if any, contained in the Crown Grants above referred to.

*Jawatson*  
Registrar General

NOTE: ENTRIES RULED THROUGH AND AUTHENTICATED BY THE SEAL OF THE REGISTRAR GENERAL ARE CANCELLED

PERSONS ARE CAUTIONED AGAINST ALTERING OR ADDING TO THIS CERTIFICATE OR ANY NOTIFICATION HEREON

WARNING THIS DOCUMENT MUST NOT BE REMOVED FROM THE LAND TITLES OFFICE

FIRST SCHEDULE (continued)

REGISTERED PROPRIETOR		INSTRUMENT		ENTERED	Signature of Registrar-General
NATURE	INSTRUMENT NUMBER	DATE			
<p>This deed is cancelled as to <u>the whole</u>                      New certificates of Title have issued on <u>23-3-1980</u>                      for lots in <u>classified</u> Plan No <u>61519</u> as follows:                      Lots <u>1 to 8</u> Vol. <u>10483</u> fol <u>201 to 204</u> respectively.</p> <p><i>[Signature]</i>                      REGISTRAR GENERAL</p> <p><i>[Stamp]</i>                      NOW CERTIFICATES OF TITLE ISSUED ON <u>23/3/80</u>                      NO DEEDS TO BE REGISTERED WITHOUT REFERENCE TO                      SURVEY CHARTER BRANCH.</p>					

SECOND SCHEDULE (continued)

NATURE	INSTRUMENT NUMBER	DATE	PARTICULARS	ENTERED	Signature of Registrar-General	CANCELLATION
	DR 611519		Interests created pursuant to Section 88B Conveyancing Act, 1979, by the registration of Deposited Plan 611519	1-9-1980.		

NOTE: ENTRIES RULED THROUGH AND AUTHENTICATED BY THE SEAL OF THE REGISTRAR-GENERAL ARE CANCELLED

D.F. 611519  
 22/9/80

NEW SOUTH WALES

# CERTIFICATE OF TITLE

REAL PROPERTY ACT, 1900

Appln. No.8474

Prior Title Vol.10483 Fol.103

Vol. 14239 Fol.204

EDITION ISSUED

24 9 1980



I certify that the person described in the First Schedule is the registered proprietor of the undermentioned estate in the land within described subject nevertheless to such exceptions encumbrances and interests as are shown in the Second Schedule.

**CANCELLED**


Registrar General.



## PLAN SHOWING LOCATION OF LAND

LENGTHS ARE IN METRES

ELIZABETH DRIVE



## ESTATE AND LAND REFERRED TO

Estate in Fee Simple in Lot 4 in Deposited Plan 611519 at Badgerys Creek in the City of Liverpool Parish of Bringelly and County of Cumberland being part of Portion 31 granted to Thomas Mactcham Pitt on 1-1-1810.

## FIRST SCHEDULE

~~MERVIN JOSEPH NOBBES~~ Badgerys Creek, Farmer.

## SECOND SCHEDULE

1. Reservations and conditions, if any, contained in the Crown Grant above referred to.  
2. DP611519<sup>9</sup> Easement to drain water affecting the land shown so burdened in Deposited Plan 611519.

NOTE: ENTRIES RULED THROUGH AND AUTHENTICATED BY THE SEAL OF THE REGISTRAR GENERAL ARE CANCELLED

MC

**FIRST SCHEDULE (continued)**

**REGISTERED PROPRIETOR**

Kenneth John Nobbs in  $\frac{1}{2}$  share and Jeffrey Nobbs in  $\frac{1}{2}$  share as tenants in common by Transfer 8486941. Registered 1-6-1981

CANCELLED

SEE AUTO FOLIO

[illegible]

## SECOND SCHEDULE (continued)

[illegible]

NOTE: ENTRIES RULED THROUGH AND AUTHENTICATED BY THE SEAL OF THE REGISTRAR GENERAL ARE CANCELLED

54869412 R  
60715577 W

LAND AND PROPERTY INFORMATION NEW SOUTH WALES - HISTORICAL SEARCH

SEARCH DATE

24/8/2017 7:36PM

FOLIO: 4/611519

First Title(s): SEE PRIOR TITLE(S)  
Prior Title(s): VOL 14239 FOL 204

Recorded	Number	Type of Instrument	C.T. Issue
28/3/1988		TITLE AUTOMATION PROJECT	LOT RECORDED FOLIO NOT CREATED
8/9/1988		CONVERTED TO COMPUTER FOLIO	FOLIO CREATED CT NOT ISSUED
10/11/1993		AMENDMENT: LOCAL GOVT AREA	
16/11/1993		AMENDMENT: LOCAL GOVT AREA	
3/2/1994	I994268	DISCHARGE OF MORTGAGE	EDITION 1
6/5/1998	3965120	TRANSFER	EDITION 2

\*\*\* END OF SEARCH \*\*\*

jennfib

PRINTED ON 24/8/2017

GlobalX Information Services Pty Ltd (ABN 99 073 436 414) an approved NSW Information Broker hereby certifies that the information contained in this document has been provided electronically by the Registrar General in accordance with section 96B(2) of the Real Property Act 1900.  
\* ANY ENTRIES PRECEDED BY AN ASTERISK DO NOT APPEAR ON THE CURRENT EDITION OF THE CERTIFICATE OF TITLE  
**WARNING: THE INFORMATION APPEARING UNDER NOTATIONS HAS NOT BEEN FORMALLY RECORDED IN THE REGISTER.**



## APPENDIX D – SAFEWORK NSW NOTICE



Our Ref: D17/200628  
Your Ref: David Yonge

1 September 2017

Attention: David Yonge  
STS Geoenvironmental Pty Ltd  
PO BOX 6989  
Wetherill Park NSW 2164

Dear Mr Yonge

**RE SITE: 55 Martin Rd Badgerys Creek NSW**

I refer to your site search request received by SafeWork NSW on 28 August 2017 requesting information on Storage of Hazardous Chemicals for the above site.

A search of the records held by SafeWork NSW has not located any records pertaining to the above mentioned premises.

For further information or if you have any questions, please call us on 13 10 50 or email [licensing@safework.nsw.gov.au](mailto:licensing@safework.nsw.gov.au)

Yours sincerely

A handwritten signature in blue ink, appearing to be a stylized 'D' or 'Y'.

Customer Service Officer  
Customer Experience - Operations  
SafeWork NSW

## APPENDIX E – SOIL PROFILE LOGS

Client: AMJ Demolition and Excavation P/L		Project / STS No.: 21649/8652C		BOREHOLE NO.: BH 1		
Project: 55 Martin Road, Badgerys Creek		Date: December 12, 2017				
Location: Refer to Drawing No. 18/0089/3		Logged: DL Checked By: MG		Sheet 1 of 1		
W A T E R L E	S A M P L E S	DEPTH (m)	DESCRIPTION OF DRILLED PRODUCT  (Soil type, colour, grain size, plasticity, minor components, observations)	S Y M B O L	CONSISTENCY (cohesive soils) or RELATIVE DENSITY (sands and gravels)	M O I S T U R E
	S1/1 @ 0.2 m		SILTY CLAY: brown with dark brown, low to medium plasticity, trace of gravel	CL		D-M
			TOPSOIL			
			BOREHOLE DISCONTINUED AT 0.3 M			
		1.0				
		2.0				
		3.0				
		4.0				
		5.0				
D - disturbed sample                      U - undisturbed tube sample                      B - bulk sample WT - level of water table or free water                      N - Standard Penetration Test (SPT) S - jar sample				Contractor: STS Equipment: Christie Hole Diameter (mm): 100/200/300		
NOTES:                      See explanation sheets for meaning of all descriptive terms and symbols				Angle from Vertical (°): Drill Bit: V/Spiral/Two Prong		

Client: AMJ Demolition and Excavation P/L			Project / STS No.: 21649/8652C		<b>BOREHOLE NO.: BH 2</b>	
Project: 55 Martin Road, Badgerys Creek			Date: December 12, 2017		Sheet 1 of 1	
Location: Refer to Drawing No. 18/0089/3			Logged: JK Checked By: MG			
W A T E R L E V E	S A M P L E S	DEPTH (m)	DESCRIPTION OF DRILLED PRODUCT  (Soil type, colour, grain size, plasticity, minor components, observations)	S Y M B O L	CONSISTENCY (cohesive soils) or <b>RELATIVE DENSITY</b> (sands and gravels)	M O I S T U R E
WT 18/12/17	S2-1/DUP/TRI @ 0.2 m		SILTY CLAY: dark brown, medium plasticity	CL	FIRM TO STIFF	D
	S2-2 @ 0.5 m		TOPSOIL			
	U50 0.5-0.8 m		SILTY CLAY: red brown with orange brown and light grey, medium to high plasticity	CL/CH	STIFF	D-M
	S2-3 @ 1.0 m	1.0				M
	B @ 0.5- 1.1 m					
	S2-4 @ 1.5 m		SILTY CLAY: light grey with yellow brown/orange brown, medium to high plasticity	CL/CH	VERY STIFF	M
	S2-5 @ 2.0 m	2.0				
	S2-6 @ 2.5 m					
	S2-7 @ 3.0 m	3.0				M-D
	S2-8 @ 4.0 m	4.0	WEATHERED SHALE: dark grey with light grey, clay seams, trace of fine grained sand		EXTREMELY LOW STRENGTH	D
	5.0					
			STANDPIPE PIEZOMETER INSTALLED			D-M
			BOREHOLE DISCONTINUED AT 6.0 M ON WEATHERED SHALE			
D - disturbed sample      U - undisturbed tube sample      B - bulk sample WT - level of water table or free water      N - Standard Penetration Test (SPT) S - jar sample				Contractor: STS Equipment: Edson RP70 Hole Diameter (mm): 100 Angle from Vertical (°): Drill Bit: Spiral		
NOTES: See explanation sheets for meaning of all descriptive terms and symbols						

Revision 7

Revision 7

Client: AMJ Demolition and Excavation P/L		Project / STS No.: 21649/8652C		BOREHOLE NO.: BH 5		
Project: 55 Martin Road, Badgerys Creek		Date: December 12, 2017				
Location: Refer to Drawing No. 18/0089/3		Logged: DL Checked By: MG		Sheet 1 of 1		
W A T E R L E	S A M P L E S	DEPTH (m)	DESCRIPTION OF DRILLED PRODUCT  (Soil type, colour, grain size, plasticity, minor components, observations)	S Y M B O L	CONSISTENCY (cohesive soils) or RELATIVE DENSITY (sands and gravels)	M O I S T U R E
	S5/1 @ 0.2 m		SILTY CLAY: brown with dark brown, low to medium plasticity, trace of gravel	CL		D
			TOPSOIL			
			BOREHOLE DISCONTINUED AT 0.3 M			
		1.0				
		2.0				
		3.0				
		4.0				
		5.0				
D - disturbed sample                      U - undisturbed tube sample                      B - bulk sample WT - level of water table or free water                      N - Standard Penetration Test (SPT) S - jar sample				Contractor: STS Equipment: Christie Hole Diameter (mm): 100/200/300		
NOTES:                      See explanation sheets for meaning of all descriptive terms and symbols				Angle from Vertical (°): Drill Bit: V/Spiral/Two Prong		

Revision 7

Client: AMJ Demolition and Excavation P/L		Project / STS No.: 21649/8652C		<b>BOREHOLE NO.: BH 7</b>		
Project: 55 Martin Road, Badgerys Creek		Date: December 12, 2017		Sheet 1 of 1		
Location: Refer to Drawing No. 18/0089/3		Logged: DL Checked By: MG				
W A T E R L E	S A M P L E S	DEPTH (m)	DESCRIPTION OF DRILLED PRODUCT  (Soil type, colour, grain size, plasticity, minor components, observations)	S Y M B O L	CONSISTENCY (cohesive soils) or RELATIVE DENSITY (sands and gravels)	M O I S T U R E
	S7/1 @ 0.2 m		SILTY CLAY: brown with light brown, low to medium plasticity, trace of gravel	CL	STIFF	D-M
	S7/2 @ 0.7 m		TOPSOIL SILTY CLAY: light brown with light grey, low to medium plasticity, trace of gravel	CL	VERY STIFF	D-M
	U50	1.0				
	S7/3 @ 1.6 m	2.0	SILTY CLAY: light grey with light brown, medium to high plasticity, trace of gravel	CL/CH	VERY STIFF	M
	S7/4 @ 2.8 m	3.0	SILTY CLAY: grey with light grey and some orange brown, low to medium plasticity, trace of shale	CL	VERY STIFF	M
			WEATHERED SHALE: grey with dark grey		EXTREMELY LOW STRENGTH	
			AUGER REFUSAL AT 3.6 M ON WEATHERED SHALE			
		4.0				
		5.0				
D - disturbed sample      U - undisturbed tube sample      B - bulk sample WT - level of water table or free water      N - Standard Penetration Test (SPT) S - jar sample				Contractor: STS Equipment: Christie Hole Diameter (mm): 100/200/300 Angle from Vertical (°): Drill Bit: V/Spiral/Two Prong		
NOTES: See explanation sheets for meaning of all descriptive terms and symbols						

Client: AMJ Demolition and Excavation P/L			Project / STS No.: 21649/8652C		<b>BOREHOLE NO.: BH 8</b>	
Project: 55 Martin Road, Badgerys Creek			Date: December 12, 2017			
Location: Refer to Drawing No. 18/0089/3			Logged: JK Checked By: MG		Sheet 1 of 1	
W A T E R L E V E	S A M P L E S	DEPTH (m)	DESCRIPTION OF DRILLED PRODUCT  (Soil type, colour, grain size, plasticity, minor components, observations)	S Y M B O L	CONSISTENCY (cohesive soils) or RELATIVE DENSITY (sands and gravels)	M O I S T U R E
	S1/DUP/TRI @ 0.2 m		SILTY CLAY: dark brown, low plasticity	CL	FIRM TO STIFF	D
	S8/2 @ 0.5 m		TOPSOIL	CL/CH	STIFF	M
	B @ 0.3-0.9m					
	S8/3 @ 1.0m	1.0	SILTY CLAY: light grey with yellow brown/orange brown, medium to high plasticity	CL/CH	STIFF	M
	S8/4 @ 1.5 m					
	S8/5 @ 2.0 m	2.0			VERY STIFF	
	S8/6 @ 2.5 m					
WT 18/12/17			WEATHERED SHALE: dark grey with occasional light grey, trace of fine grained sand		EXTREMELY LOW STRENGTH	D
	S8/7 @ 3.0 m	3.0				
	S8/8 @ 4.0 m	4.0				
		5.0				
			STANDPIPE PIEZOMETER INSTALLED			
			BOREHOLE DISCONTINUED AT 6.0 M			
D - disturbed sample      U - undisturbed tube sample      B - bulk sample WT - level of water table or free water      N - Standard Penetration Test (SPT) S - jar sample				Contractor: STS Equipment: Edson RP70 Hole Diameter (mm): 100 Angle from Vertical (°): Drill Bit: Spiral		
NOTES: See explanation sheets for meaning of all descriptive terms and symbols						

Client: AMJ Demolition and Excavation P/L			Project / STS No.: 21649/8652C		<b>BOREHOLE NO.: BH 9</b>	
Project: 55 Martin Road, Badgerys Creek			Date: December 12, 2017			
Location: Refer to Drawing No. 18/0089/3			Logged: JK Checked By: MG		Sheet 1 of 1	
W A T E R L E V E	S A M P L E S	DEPTH (m)	DESCRIPTION OF DRILLED PRODUCT  (Soil type, colour, grain size, plasticity, minor components, observations)	S Y M B O L	CONSISTENCY (cohesive soils) or <b>RELATIVE DENSITY</b> (sands and gravels)	M O I S T U R E
	S9/1 @ 0.2 m		SILTY CLAY: dark brown, low plasticity	CL	FIRM TO STIFF	D
			TOPSOIL			
			SILTY CLAY: orange brown with light grey, medium to high plasticity	CL/CH	STIFF	M-D
		1.0				
			SILTY CLAY: light grey with orange brown, medium to high plasticity	CL/CH	VERY STIFF	M
		2.0				
			WEATHERED SHALE: light grey with dark grey, fine grained, clay seams		EXTREMELY LOW STRENGTH	D
		3.0				
		4.0				
			AUGER REFUSAL AT 4.0 M ON WEATHERED SHALE			
		5.0				
D - disturbed sample      U - undisturbed tube sample      B - bulk sample WT - level of water table or free water      N - Standard Penetration Test (SPT) S - jar sample				Contractor: STS Equipment: Edson RP70 Hole Diameter (mm): 100/200/300		
NOTES: See explanation sheets for meaning of all descriptive terms and symbols				Angle from Vertical (°): Drill Bit: V/Spiral/Two Prong		

Client: AMJ Demolition and Excavation P/L		Project / STS No.: 21649/8652C		BOREHOLE NO.: BH 10		
Project: 55 Martin Road, Badgerys Creek		Date: December 12, 2017				
Location: Refer to Drawing No. 18/0089/3		Logged: DL Checked By: MG		Sheet 1 of 1		
W A T E R L E	S A M P L E S	DEPTH (m)	DESCRIPTION OF DRILLED PRODUCT  (Soil type, colour, grain size, plasticity, minor components, observations)	S Y M B O L	CONSISTENCY (cohesive soils) or RELATIVE DENSITY (sands and gravels)	M O I S T U R E
	S10/1 @ 0.2 m		SILTY CLAY: brown with dark brown, low to medium plasticity, trace of gravel	CL		D
			TOPSOIL			
			BOREHOLE DISCONTINUED AT 0.3 M			
		1.0				
		2.0				
		3.0				
		4.0				
		5.0				
D - disturbed sample                      U - undisturbed tube sample                      B - bulk sample WT - level of water table or free water                      N - Standard Penetration Test (SPT) S - jar sample				Contractor: STS Equipment: Christie Hole Diameter (mm): 100/200/300		
NOTES:                      See explanation sheets for meaning of all descriptive terms and symbols				Angle from Vertical (°): Drill Bit: V/Spiral/Two Prong		

Client: AMJ Demolition and Excavation P/L		Project / STS No.: 21649/8652C		<b>BOREHOLE NO.: BH 11</b>		
Project: 55 Martin Road, Badgerys Creek		Date: December 12, 2017				
Location: Refer to Drawing No. 18/0089/3		Logged: JK Checked By: MG		Sheet 1 of 1		
W A T E R L E	S A M P L E S	DEPTH (m)	DESCRIPTION OF DRILLED PRODUCT  (Soil type, colour, grain size, plasticity, minor components, observations)	S Y M B O L	CONSISTENCY (cohesive soils) or <b>RELATIVE DENSITY</b> (sands and gravels)	M O I S T U R E
	S1/DUP/TRI @ 0.2 m		SILTY CLAY: dark brown/orange brown, medium plasticity	CL	FIRM TO STIFF	D-M
			TOPSOIL			
			SILTY CLAY: orange brown with light grey, medium to high plasticity	CL/CH	STIFF	M
		1.0				
			SILTY CLAY: light grey with orange brown and yellow brown, medium plasticity, trace of fine grained sand	CL	VERY STIFF	M-D
		2.0				
			WEATHERED SHALE: light brown with orange brown and dark grey, fine grained, clay seams		EXTREMELY LOW STRENGTH	D
		4.0				
			AUGER REFUSAL AT 4.5 M ON WEATHERED SHALE			
		5.0				
D - disturbed sample                      U - undisturbed tube sample                      B - bulk sample WT - level of water table or free water                      N - Standard Penetration Test (SPT) S - jar sample				Contractor: STS Equipment: Edson RP70 Hole Diameter (mm): 100 Angle from Vertical (°): Drill Bit: Spiral		
NOTES: See explanation sheets for meaning of all descriptive terms and symbols						

Client: AMJ Demolition and Excavation P/L		Project / STS No.: 21649/8652C		BOREHOLE NO.: BH 12		
Project: 55 Martin Road, Badgerys Creek		Date: December 12, 2017				
Location: Refer to Drawing No. 18/0089/3		Logged: DL      Checked By: MG		Sheet 1 of 1		
W A T E R L E	S A M P L E S	DEPTH (m)	DESCRIPTION OF DRILLED PRODUCT  (Soil type, colour, grain size, plasticity, minor components, observations)	S Y M B O L	CONSISTENCY (cohesive soils) or RELATIVE DENSITY (sands and gravels)	M O I S T U R E
	S12/1 @ 0.2 m		SILTY CLAY: brown with dark brown, low to medium plasticity, trace of gravel	CL		D
			TOPSOIL			
			BOREHOLE DISCONTINUED AT 0.3 M			
		1.0				
		2.0				
		3.0				
		4.0				
		5.0				
D - disturbed sample      U - undisturbed tube sample      B - bulk sample WT - level of water table or free water      N - Standard Penetration Test (SPT) S - jar sample				Contractor: STS Equipment: Christie Hole Diameter (mm): 100/200/300		
NOTES:      See explanation sheets for meaning of all descriptive terms and symbols				Angle from Vertical (°): Drill Bit: V/Spiral/Two Prong		

Revision 7

Revision 7

Client: AMJ Demolition and Excavation P/L		Project / STS No.: 21649/8652C		<b>BOREHOLE NO.: BH 15</b>		
Project: 55 Martin Road, Badgerys Creek		Date: December 12, 2017				
Location: Refer to Drawing No. 18/0089/3		Logged: JK Checked By: MG		Sheet 1 of 1		
W A T E R L E	S A M P L E S	DEPTH (m)	DESCRIPTION OF DRILLED PRODUCT  (Soil type, colour, grain size, plasticity, minor components, observations)	S Y M B O L	CONSISTENCY (cohesive soils) or <b>RELATIVE DENSITY</b> (sands and gravels)	M O I S T U R E
	B4/S15-1 @ 0.2 m		SILTY CLAY: dark brown, low plasticity	CL	FIRM	D
	S15/2 @ 0.5 m		TOPSOIL SILTY CLAY: orange brown with light grey, medium to high plasticity	CL/CH	FIRM TO STIFF	D-M
	U50				STIFF	
	S15/3 @ 1.0 m	1.0			VERY STIFF	
	S15/4 @ 1.5 m		WEATHERED SANDSTONE: dark grey with light grey and orange brown, fine grained, clay seams			D
	S15/5 @ 2.0 m	2.0				
	S15/6 @ 2.5 m					
	S15/7 @ 3.0 m	3.0				D-M
	S15/8 @ 4.0 m	4.0				D
			AUGER REFUSAL AT 4.3 M ON WEATHERD SANDSTONE			
			STANDPIPE PIEZOMETER INSTALLED			
		5.0				
D - disturbed sample      U - undisturbed tube sample      B - bulk sample WT - level of water table or free water      N - Standard Penetration Test (SPT) S - jar sample				Contractor: STS Equipment: Edson RP70 Hole Diameter (mm): 100 Angle from Vertical (°): Drill Bit: Spiral		
NOTES: See explanation sheets for meaning of all descriptive terms and symbols						

Revision 7

Client: AMJ Demolition and Excavation P/L			Project / STS No.: 21649/8652C		<b>BOREHOLE NO.: BH 17</b>	
Project: 55 Martin Road, Badgerys Creek			Date: December 12, 2017			
Location: Refer to Drawing No. 18/0089/3			Logged: JK Checked By: MG		Sheet 1 of 1	
W A T E R L E	S A M P L E S	DEPTH (m)	DESCRIPTION OF DRILLED PRODUCT  (Soil type, colour, grain size, plasticity, minor components, observations)	S Y M B O L	CONSISTENCY (cohesive soils) or RELATIVE DENSITY (sands and gravels)	M O I S T U R E
	S17/1 @ 0.2 m B 0.4-1.0		SILTY CLAY: dark brown, low plasticity	CL	FIRM TO STIFF	D
			TOPSOIL			
			SILTY CLAY: orange brown with light grey, medium to high plasticity	CL/CH	STIFF	M
		1.0	SANDY CLAY: light grey with orange brown, fine grained sand, medium plasticity	CL	STIFF ----- VERY STIFF	M-D
		2.0				M
		3.0				
		4.0	WEATHERED SHALE: light grey with orange brown and yellow brown, trace of fined grained sand		EXTREMELY LOW STRENGTH	D
		5.0	AUGER REFUSAL AT 5.0 M ON WEATHERED SHALE			
D - disturbed sample                      U - undisturbed tube sample                      B - bulk sample WT - level of water table or free water                      N - Standard Penetration Test (SPT) S - jar sample				Contractor: STS Equipment: Edson RP70 Hole Diameter (mm): 100 Angle from Vertical (°): Drill Bit: Spiral		
NOTES: See explanation sheets for meaning of all descriptive terms and symbols						

Client: AMJ Demolition and Excavation P/L		Project / STS No.: 21649/8652C		BOREHOLE NO.: BH 18		
Project: 55 Martin Road, Badgerys Creek		Date: December 12, 2017				
Location: Refer to Drawing No. 18/0089/3		Logged: DL Checked By: MG		Sheet 1 of 1		
W A T E R L E	S A M P L E S	DEPTH (m)	DESCRIPTION OF DRILLED PRODUCT  (Soil type, colour, grain size, plasticity, minor components, observations)	S Y M B O L	CONSISTENCY (cohesive soils) or RELATIVE DENSITY (sands and gravels)	M O I S T U R E
	S18/1 @ 0.2 m		SILTY CLAY: brown with dark brown, low to medium plasticity, trace of gravel			
			TOPSOIL			
			BOREHOLE DISCONTINUED AT 0.3 M			
		1.0				
		2.0				
		3.0				
		4.0				
		5.0				
D - disturbed sample                      U - undisturbed tube sample                      B - bulk sample WT - level of water table or free water                      N - Standard Penetration Test (SPT) S - jar sample				Contractor: STS Equipment: Christie Hole Diameter (mm): 100/200/300		
NOTES:                      See explanation sheets for meaning of all descriptive terms and symbols				Angle from Vertical (°): Drill Bit: V/Spiral/Two Prong		

Client: AMJ Demolition and Excavation P/L		Project / STS No.: 21649/8652C		BOREHOLE NO.: BH 19		
Project: 55 Martin Road, Badgerys Creek		Date: December 12, 2017				
Location: Refer to Drawing No. 18/0089/3		Logged: DL Checked By: MG		Sheet 1 of 1		
W A T E R L E	S A M P L E S	DEPTH (m)	DESCRIPTION OF DRILLED PRODUCT  (Soil type, colour, grain size, plasticity, minor components, observations)	S Y M B O L	CONSISTENCY (cohesive soils) or RELATIVE DENSITY (sands and gravels)	M O I S T U R E
	S19/1 @ 0.2 m		SILTY CLAY: brown with dark brown, low to medium plasticity, trace of gravel	CL		D
			TOPSOIL			
			BOREHOLE DISCONTINUED AT 0.3M			
		1.0				
		2.0				
		3.0				
		4.0				
		5.0				
D - disturbed sample                      U - undisturbed tube sample                      B - bulk sample WT - level of water table or free water                      N - Standard Penetration Test (SPT) S - jar sample				Contractor: STS Equipment: Christie Hole Diameter (mm): 100/200/300		
NOTES:                      See explanation sheets for meaning of all descriptive terms and symbols				Angle from Vertical (°): Drill Bit: V/Spiral/Two Prong		

## APPENDIX F – CHAIN OF CUSTODY DOCUMENTATION



# CHAIN OF CUSTODY

ALS Laboratory:  
please tick →

DADELAIDE 21 Burma Road Pooraka SA 5095  
Ph: 08 8359 0890 E: adelaide@alsglobal.com  
BRISBANE 32 Shand Street Stafford QLD 4053  
Ph: 07 3243 7222 E: samples.brisbane@alsglobal.com  
GLADSTONE 46 Callemondah Drive Clinton QLD 4680  
Ph: 07 7471 5600 E: gladstone@alsglobal.com

MACKAY 78 Harbour Road Mackay QLD 4740  
Ph: 07 4944 0177 E: mackay@alsglobal.com  
MELBOURNE 2-4 Westall Road Springvale VIC 3171  
Ph: 03 8549 9600 E: samples.melbourne@alsglobal.com  
MUDGEE 27 Sydney Road Mudgee NSW 2850  
Ph: 02 6372 6735 E: mudgee.mel@alsglobal.com

NEWCASTLE 5 Rose Gum Road Warabrook NSW 2304  
Ph: 02 4968 9433 E: samples.newcastle@alsglobal.com  
NOWRA 4/13 Geary Place North Nowra NSW 2541  
Ph: 024423 2069 E: nowra@alsglobal.com  
PERTH 10 Hod Way Malaga WA 6099  
Ph: 08 9209 7655 E: samples.perth@alsglobal.com

SYDNEY 277-289 Woodpark Road Smithfield NSW 2164  
Ph: 02 8784 8555 E: samples.sydney@alsglobal.com  
TOWNSVILLE 14-15 Desma Court Bohle QLD 4818  
Ph: 07 4796 0600 E: townsville.environmental@alsglobal.com  
WOLLONGONG 99 Kenny Street Wollongong NSW 2500  
Ph: 02 4225 3125 E: portkembla@alsglobal.com

CLIENT: SMEC Testing Services

OFFICE: 14/1 Cowpasture Place Wetherill Park

PROJECT: 21649

ORDER NUMBER: E-2017-713

ORDER NUMBER: E-2017-713

SAMPLER:

COC emailed to ALS? ( YES / NO)

Email Reports to (will default to PM if no other addresses are listed):

Email Invoice to (will default to PM if no other addresses are listed):

## TURNAROUND REQUIREMENTS:

(Standard TAT may be longer for some tests e.g.,  
Ultra Trace Organics)

ALS QUOTE NO.:

☐ Standard TAT (List due date):

☐ Non Standard or urgent TAT (List due date):

COC SEQUENCE NUMBER (Circle)

COC: 3

OF:

## FOR LABORATORY USE ONLY (Circle)

Is the sample sealed? Yes No NA  
Is the sample properly labeled? Yes No NA  
Is the sample properly stored? Yes No NA  
Is the sample properly handled? Yes No NA  
Is the sample properly transported? Yes No NA  
Is the sample properly received? Yes No NA  
Is the sample properly stored? Yes No NA  
Is the sample properly handled? Yes No NA  
Is the sample properly transported? Yes No NA  
Is the sample properly received? Yes No NA

CONTACT PH:

SAMPLER MOBILE:

EDD FORMAT (or default):

RELINQUISHED BY:

DATE/TIME:

RECEIVED BY:

DATE/TIME:


RELINQUISHED BY:

DATE/TIME:

RECEIVED BY:

DATE/TIME:

COMMENTS/SPECIAL HANDLING/STORAGE OR DISPOSAL:

ALS USE		SAMPLE DETAILS		CONTAINER INFORMATION		ANALYSIS REQUIRED including SUITES (NB. Suite Codes must be listed to attract suite price) Where Metals are required, specify Total (unfiltered bottle required) or Dissolved (field filtered bottle required).								Additional Information	
LAB ID	SAMPLE ID	DATE / TIME	MATRIX	TYPE & PRESERVATIVE (refer to codes below)	TOTAL CONTAINERS	EA200F	S12	S2	EC + pH	SO4	CEC + ESP	Phosphorous Sorption Cap		Comments on likely contaminant levels, dilutions, or samples requiring specific QC analysis etc.	
1	21649/S7/2-1	14/12/2017	S	JAR + ICE	1		x	x							
2	21649/S7/3-1	14/12/2017	S	JAR + ICE	1										
3	21649/S7/4-1	14/12/2017	S	JAR + ICE	1										
4	21649/S8-1	14/12/2017	Environmental Division Sydney Work Order Reference <b>ES1731925</b>  Telephone : +61-2-8784 8555		1	x	x	x	x					Subson / Porvink Lab / Spill WO	
5	21649/S8-2	14/12/2017			1			x	x	x					Lab / Analysis: Asbestos
6	21649/S8-3	14/12/2017			1				x						Organised By / Date: Amenah
7	21649/S8-4	14/12/2017			1				x	x					Relinquished By / Date:
8	21649/S8-5	14/12/2017			1				x	x					Connote / Courier:
9	21649/S8-6	14/12/2017			1				x	x					WO No:
10	21649/S8-7	14/12/2017			1				x	x	x				Attach By PO / Internal Sheet:
11	21649/S8-8	14/12/2017			1				x						
12	21649/S9-1	14/12/2017	S	JAR + ICE, B	1		x		x						
TOTAL					12	1	3	3	9	4	4	0	0		

Water Container Codes: P = Unpreserved Plastic; N = Nitric Preserved Plastic; ORC = Nitric Preserved ORC; SH = Sodium Hydroxide/Cd Preserved; S = Sodium Hydroxide Preserved Plastic; AG = Amber Glass Unpreserved; AP = Airfreight Unpreserved Plastic  
V = VOA Vial HCl Preserved; VB = VOA Vial Sodium Bisulphate Preserved; VS = VOA Vial Sulfuric Preserved; AV = Airfreight Unpreserved Vial SG = Sulfuric Preserved Amber Glass; H = HCl preserved Plastic; HS = HCl preserved Speciation bottle; SP = Sulfuric Preserved Plastic; F = Formaldehyde Preserved Glass;  
Z = Zinc Acetate Preserved Bottle; E = EDTA Preserved Bottles; ST = Sterile Bottle; ASS = Plastic Bag for Acid Sulphate Soils; B = Unpreserved Bag.



# CHAIN OF CUSTODY

ALS Laboratory:  
please tick →

ADELAIDE 21 Burma Road Pooraka SA 5095  
Ph: 08 8359 0890 E: adelaide@alsglobal.com  
BRISBANE 32 Shand Street Stafford QLD 4053  
Ph: 07 3243 7222 E: samples.brisbane@alsglobal.com  
GLADSTONE 46 Callemondah Drive Clinton QLD 4680  
Ph: 07 7471 5600 E: gladstone@alsglobal.com

MACKAY 78 Harbour Road Mackay QLD 4740  
Ph: 07 4944 0177 E: mackay@alsglobal.com  
MELBOURNE 2-4 Westall Road Springvale VIC 3171  
Ph: 03 8549 9500 E: samples.melbourne@alsglobal.com  
MUDGEE 27 Sydney Road Mudgee NSW 2850  
Ph: 02 6372 6735 E: mudgee@mail@alsglobal.com

NEWCASTLE 5 Rose Gum Road Warabrook NSW 2304  
Ph: 02 4968 9433 E: samples.newcastle@alsglobal.com  
NOWRA 4/13 Geary Place North Nowra NSW 2541  
Ph: 024423 2063 E: nowra@alsglobal.com  
PERTH 10 Hod Way Malaga WA 6090  
Ph: 08 9209 7655 E: samples.perth@alsglobal.com

SYDNEY 277-289 Woodpark Road Smithfield NSW 2164  
Ph: 02 8784 8555 E: samples.sydney@alsglobal.com  
TOWNSVILLE 14-15 Deema Court Bohle QLD 4818  
Ph: 07 4796 0600 E: townsville.environment@alsglobal.com  
WOLLONGONG 99 Kenny Street Wollongong NSW 2500  
Ph: 02 4225 3125 E: portkembla@alsglobal.com

CLIENT: SMEC Testing Services	TURNAROUND REQUIREMENTS : (Standard TAT may be longer for some tests e.g. Ultra Trace Organics)	<input type="checkbox"/> Standard TAT (List due date): <input type="checkbox"/> Non Standard or urgent TAT (List due date):	*****	FOR LABORATORY USE ONLY (Circle) Custody Seal intact? Yes No N/A COC Sequence Number correct? Yes No N/A Sample temperature on receipt? S Other comments:	
OFFICE: 14/1 Cowpasture Place Wetherill Park	ALS QUOTE NO.:	COC SEQUENCE NUMBER (Circle) COC: 4 OF: 5			
PROJECT: 21649	ORDER NUMBER: E-2017-713				
PROJECT MANAGER:	CONTACT PH:				
SAMPLER:	SAMPLER MOBILE:	RELINQUISHED BY:	RECEIVED BY:	RELINQUISHED BY:	RECEIVED BY:
COC emailed to ALS? ( YES / NO)	EDD FORMAT (or default):	DATE/TIME: 14/12/2017 10:00	DATE/TIME: 14/12/17 4:02pm	DATE/TIME:	DATE/TIME:
Email Reports to (will default to PM if no other addresses are listed):	Email Invoice to (will default to PM if no other addresses are listed):				

## COMMENTS/SPECIAL HANDLING/STORAGE OR DISPOSAL:

ALS USE	SAMPLE DETAILS MATRIX SOLID /S/ WATER /G		CONTAINER INFORMATION			ANALYSIS REQUIRED including SUITES (NB. Suite Codes must be listed to attract suite price) Where Metals are required, specify Total (unfiltered bottle required) or Dissolved (field filtered bottle required).						Additional Information	
LAB ID	SAMPLE ID	DATE / TIME	MATRIX	TYPE & PRESERVATIVE (refer to codes below)	TOTAL CONTAINERS	EA200F	S12	S2	EC + pH	SO4	CEC + ESP	Phosphorous Sorption Cap	Comments on likely contaminant levels, dilutions, or samples requiring specific QC analysis etc.
13	21649/S10/1-1	14/12/2017	S	JAR + ICE, B	1		x						
14	21649/S11-1	14/12/2017	S	JAR + ICE, B	1	x		x	x				
15	21649/S12/1-1	14/12/2017	S	JAR + ICE, B	1			x	x				
16	21649/S13/1-1	14/12/2017	S	JAR + ICE	1				x		x	x	
17	21649/S13/1-2	14/12/2017	S	JAR + ICE	1								
18	21649/S14/1-1	14/12/2017	S	JAR + ICE, B	1	x		x					
19	21649/S14/1-2	14/12/2017	S	JAR + ICE	1			x	x		x	x	
20	21649/S15-1	14/12/2017	S	JAR + ICE, B	1	x		x	x				
21	21649/S15-2	14/12/2017	S	JAR + ICE	1				x	x	x		
22	21649/S15-3	14/12/2017	S	JAR + ICE	1				x	x	x		
23	21649/S15-4	14/12/2017	S	JAR + ICE	1				x				
24	21649/S15-5	14/12/2017	S	JAR + ICE	1				x	x	x		
TOTAL					12	3	1	5	9	3	5	2	0

Water Container Codes: P = Unpreserved Plastic; N = Nitric Preserved Plastic; ORC = Nitric Preserved ORC; SH = Sodium Hydroxide/Cd Preserved; S = Sodium Hydroxide Preserved Plastic; AG = Amber Glass Unpreserved; AP = Airfreight Unpreserved Plastic  
V = VOA Vial HCl Preserved; VB = VOA Vial Sodium Bisulphate Preserved; VS = VOA Vial Sulfuric Preserved; AV = Airfreight Unpreserved Vial SG = Sulfuric Preserved Amber Glass; H = HCl preserved Plastic; HS = HCl preserved Speciation bottle; SP = Sulfuric Preserved Plastic; F = Formaldehyde Preserved Glass;  
Z = Zinc Acetate Preserved Bottle; E = EDTA Preserved Bottles; ST = Sterile Bottle; ASS = Plastic Bag for Acid Sulphate Soils; B = Unpreserved Bag.



**DADELAIDE 21** Burma Road Pooraka SA 5095  
 Ph: 08 8359 0890 E: [adelaide@elsglobal.com](mailto:adelaide@elsglobal.com)  
**BRISBANE 32** Shand Street Stafford QLD 4053  
 Ph: 07 3243 7222 E: [samples.brisbane@elsglobal.com](mailto:samples.brisbane@elsglobal.com)  
**GLADSTONE 46** Callemondah Drive Clinton QLD 4680  
 Ph: 07 7471 5600 E: [gladstone@elsglobal.com](mailto:gladstone@elsglobal.com)

**Q**MACKAY 78 Harbour Road Mackay QLD 4740  
 Ph: 07 4944 0177 E: [mackay@aisglobal.com](mailto:mackay@aisglobal.com)  
**Q**MELBOURNE 2-4 Westall Road Springvale VIC 3171  
 Ph: 03 8549 9600 E: [samples.melbourne@aisglobal.com](mailto:samples.melbourne@aisglobal.com)  
**Q**MUDGEEO 27 Sydney Road Mudgee NSW 2850  
 Ph: 02 6372 6735 E: [mudgee\\_mail@aisglobal.com](mailto:mudgee_mail@aisglobal.com)

**NEWCASTLE** 5 Rose Gum Road Warabrook NSW 2304  
 Ph: 02 4968 9433 E: [samples.newcastle@alsglobal.com](mailto:samples.newcastle@alsglobal.com)  
**NOWRA** 4/13 Geary Place North Nowra NSW 2541  
 Ph: 024423 2063 E: [nowra@alsglobal.com](mailto:nowra@alsglobal.com)  
**PERTH** 10 Hod Way Malaga WA 6090  
 Ph: 08 9209 7855 E: [samples.perth@alsglobal.com](mailto:samples.perth@alsglobal.com)

**QSYDNEY** 277-289 Woodpark Road Smithfield NSW 2164  
Ph: 02 8784 8555 E: [samples.sydney@alsglobal.com](mailto:samples.sydney@alsglobal.com)

**QTOWNSVILLE** 14-15 Desma Court Bohle QLD 4818  
Ph: 07 4796 0800 E: [townsville.environmental@alsglobal.com](mailto:townsville.environmental@alsglobal.com)

**QWOLLONGONG** 99 Kenny Street Wollongong NSW 2500  
Ph: 02 4225 3125 E: [norkembla@alsglobal.com](mailto:norkembla@alsglobal.com)

DATE/TIME:

LAB ID	SAMPLE ID	DATE / TIME	MATRIX	TYPE & PRESERVATIVE (refer to codes below)	TOTAL CONTAINERS	EA200F	S12	S2	S19	EC + pH	SO4	CEC + ESP	Phosphorous Sorption Cap	Comments on likely contaminant levels, dilutions, or samples requiring specific QC analysis etc.
25	21649/S15-6	14/12/2017	S	JAR + ICE	1					x	x	x		
26	21649/S15-7	14/12/2017	S	JAR + ICE	1					x				
27	21649/S15-8	14/12/2017	S	JAR + ICE	1					x				
28	21649/S16/1-1	14/12/2017	S	JAR + ICE, B	1	x	x		x					
29	21649/S17-1	14/12/2017	S	JAR + ICE, B	1					x				
30	21649/S18/1-1	14/12/2017	S	JAR + ICE, B	1	x		x						
31	21649/S19/1-1	14/12/2017	S	JAR + ICE, B	1					x				
					1									
					1									
					1									
					1									
					1									
TOTAL					12	2	1	1	1	5	1	1	0	

**Water Container Codes:** P = Unpreserved Plastic; N = Nitric Preserved Plastic; ORC = Nitric Preserved ORC; SH = Sodium Hydroxide/Cd Preserved; S = Sodium Hydroxide Preserved Plastic; AG = Amber Glass Unpreserved; AP - Airfreight Unpreserved Plastic  
V = VOA Vial HCl Preserved; VB = VOA Vial Sodium Bisulphate Preserved; VS = VOA Vial Sulfuric Preserved; AV = Airfreight Unpreserved Vial SG = Sulfuric Preserved Amber Glass; H = HCl preserved Plastic; HS = HCl preserved Specimen storage bottle; SP = Sulfuric Preserved Plastic; F = Formaldehyde Preserved Glass;  
Z = Zinc Acetate Preserved Bottle; E = EDTA Preserved Bottles; ST = Sterile Bottle; ASS = Plastic Bag for Acid Sulphate Soils; B = Unpreserved Bag.



# CHAIN OF CUSTODY

ALS Laboratory:  
please tick →

ADELAIDE 21 Burma Road Pooraka SA 5095  
Ph: 08 8359 0590 E: adelaide@alsglobal.com

BRISBANE 32 Shand Street Stafford QLD 4053  
Ph: 07 3243 7222 E: samples.brisbane@alsglobal.com

GLADSTONE 48 Callamondah Drive Clinton QLD 4680  
Ph: 07 7471 5600 E: gladstone@alsglobal.com

MACKAY 78 Harbour Road Mackay QLD 4740  
Ph: 07 4944 0177 E: mackay@alsglobal.com

MELBOURNE 2-4 Westall Road Springvale VIC 3171  
Ph: 03 8549 9600 E: samples.melbourne@alsglobal.com

MUDGEE 27 Sydney Road Mudgee NSW 2850  
Ph: 02 6372 6735 E: mudgee@mail@alsglobal.com

NEWCASTLE 5 Rose Gum Road Warabrook NSW 2304  
Ph: 02 4968 9433 E: samples.newcastle@alsglobal.com

NOWRA 4/13 Geary Place North Nowra NSW 2541  
Ph: 024423 2063 E: nowra@alsglobal.com

PERTH 10 Hod Way Malaga WA 6060  
Ph: 08 9209 7655 E: samples.perth@alsglobal.com

SYDNEY 277-289 Woodpark Road Smithfield NSW 2164  
Ph: 02 8784 8555 E: samples.sydney@alsglobal.com

TOWNSVILLE 14-15 Desma Court Bohle QLD 4818  
Ph: 07 4796 0600 E: townsville.environmental@alsglobal.com

WOLLONGONG 99 Kenny Street Wollongong NSW 2500  
Ph: 02 4225 3125 E: portkenbla@alsglobal.com

CLIENT: SMEC Testing Services

OFFICE: 14/1 Cowpasture Place Wetherill Park

PROJECT: 21649

ORDER NUMBER: E-2017-713

ORDER NUMBER: E-2017-713

SAMPLER:

COC emailed to ALS? ( YES / NO)

Email Reports to (will default to PM if no other addresses are listed):

Email Invoice to (will default to PM if no other addresses are listed):

## TURNAROUND REQUIREMENTS :

(Standard TAT may be longer for some tests e.g.,  
Ultra Trace Organics)

ALS QUOTE NO.:

☐ Standard TAT (List due date):

☐ Non Standard or urgent TAT (List due date):

COC SEQUENCE NUMBER (Circle)

COC: 3

OF:

RECEIVED BY:

ANDREW

DATE/TIME:

14/12/17 16:00


RELINQUISHED BY:

DATE/TIME:

RECEIVED BY:

DATE/TIME:

## COMMENTS/SPECIAL HANDLING/STORAGE OR DISPOSAL:

ALS USE		SAMPLE DETAILS		CONTAINER INFORMATION		ANALYSIS REQUIRED including SUITES (NB. Suite Codes must be listed to attract suite price) Where Metals are required, specify Total (unfiltered bottle required) or Dissolved (field filtered bottle required).										Additional Information	
LAB ID	SAMPLE ID	DATE / TIME	MATRIX	TYPE & PRESERVATIVE (refer to codes below)	TOTAL CONTAINERS	EA200F	S12	S2	EC + pH	SO4	CEC + ESP	Phosphorous Sorption Cap				Comments on likely contaminant levels, dilutions, or samples requiring specific QC analysis etc.	
1	21649/S7/2-1	14/12/2017	S	JAR + ICE	1		x	x									
2	21649/S7/3-1	14/12/2017	S	JAR + ICE	1												
3	21649/S7/4-1	14/12/2017	S	JAR + ICE	1												
4	21649/S8-1	14/12/2017	<div>Environmental Division Sydney Work Order Reference <b>ES1731925</b>  Telephone : +61-2-6784 8555</div>		1	x	x	x	x								
5	21649/S8-2	14/12/2017			1			x	x	x							
6	21649/S8-3	14/12/2017			1				x								
7	21649/S8-4	14/12/2017			1				x	x							
8	21649/S8-5	14/12/2017			1				x								
9	21649/S8-6	14/12/2017			1				x								
10	21649/S8-7	14/12/2017			1				x	x	x						
11	21649/S8-8	14/12/2017			1				x								
12	21649/S9-1	14/12/2017	S	JAR + ICE, B	1		x		x								
TOTAL					12	1	3	3	9	4	4	0					

Water Container Codes: P = Unpreserved Plastic; N = Nitric Preserved Plastic; ORC = Nitric Preserved ORC; SH = Sodium Hydroxide/Cd Preserved; S = Sodium Hydroxide Preserved Plastic; AG = Amber Glass Unpreserved; AP = Airfreight Unpreserved Plastic; V = VOA Vial HCl Preserved; VB = VOA Vial Sodium Bisulphate Preserved; VS = VOA Vial Sulfuric Preserved; AV = Airfreight Unpreserved Vial SG = Sulfuric Preserved Amber Glass; H = HCl preserved Plastic; HS = HCl preserved Speciation bottle; SP = Sulfuric Preserved Plastic; F = Formaldehyde Preserved Glass; Z = Zinc Acetate Preserved Bottle; E = EDTA Preserved Bottles; ST = Sterile Bottle; ASS = Plastic Bag for Acid Sulphate Soils; B = Unpreserved Bag.



# CHAIN OF CUSTODY

ALS Laboratory:  
please tick →

ADELAIDE 21 Burma Road Pooraka SA 5095  
Ph: 08 8359 0980 E: adelaide@alsglobal.com

BRISBANE 32 Shand Street Stafford QLD 4063  
Ph: 07 3243 7222 E: samples.brisbane@alsglobal.com

GLADSTONE 46 Caillemondah Drive Clinton QLD 4680  
Ph: 07 7471 5600 E: gladstone@alsglobal.com

MACKAY 70 Harbour Road Mackay QLD 4740  
Ph: 07 4944 0177 E: mackay@alsglobal.com

MELBOURNE 2-4 Westall Road Springvale VIC 3171  
Ph: 03 8549 9600 E: samples.melbourne@alsglobal.com

MUDGEE 27 Sydney Road Mudgee NSW 2850  
Ph: 02 6372 6735 E: mudgee@mail@alsglobal.com

NEWCASTLE 5 Rose Gum Road Warabrook NSW 2304  
Ph: 02 4968 9433 E: samples.newcastle@alsglobal.com

NOWRA 4/13 Geary Place North Nowra NSW 2541  
Ph: 024423 2063 E: nowra@alsglobal.com

PERTH 10 Hod Way Malaga WA 6090  
Ph: 08 9209 7655 E: samples.perth@alsglobal.com

SYDNEY 277-289 Woodpark Road Smithfield NSW 2164  
Ph: 02 8784 8555 E: samples.sydney@alsglobal.com

TOWNSVILLE 14-15 Desma Court Bohle QLD 4816  
Ph: 07 4796 0600 E: townsville.environmental@alsglobal.com

WOLLONGONG 99 Kenny Street Wollongong NSW 2500  
Ph: 02 4226 3126 E: portkembla@alsglobal.com

CLIENT: SMEC Testing Services	TURNAROUND REQUIREMENTS : (Standard TAT may be longer for some tests e.g. Ultra Trace Organics)	<input type="checkbox"/> Standard TAT (List due date): <input type="checkbox"/> Non Standard or urgent TAT (List due date):	<b>FOR LABORATORY USE ONLY (Circle)</b> COC Sequence Number: 4 OF: 5
OFFICE: 14/1 Cowpasture Place Wetherill Park	ALS QUOTE NO.:		
PROJECT: 21649			
ORDER NUMBER: E-2017-713			
PROJECT MANAGER:	CONTACT PH:		
SAMPLER:	SAMPLER MOBILE:	RELINQUISHED BY: PK	RECEIVED BY: ANDREW
COC emailed to ALS? ( YES / NO)	EDD FORMAT (or default):	DATE/TIME: 14/12/2017 10:00	DATE/TIME: 14/12/17 4:02pm
Email Reports to (will default to PM if no other addresses are listed):			
Email Invoice to (will default to PM if no other addresses are listed):			

COMMENTS/SPECIAL HANDLING/STORAGE OR DISPOSAL:

LAB ID	SAMPLE ID	DATE / TIME	MATRIX	TYPE & PRESERVATIVE (refer to codes below)	TOTAL CONTAINERS	EA200F	S12	S2	EC + pH	SO4	CEC + ESP	Phosphorous Sorption Cap	Additional Information
13	21649/S10/1-1	14/12/2017	S	JAR + ICE, B	1		X						
14	21649/S11-1	14/12/2017	S	JAR + ICE, B	1	X		X	X				
15	21649/S12/1-1	14/12/2017	S	JAR + ICE, B	1			X	X				
16	21649/S13/1-1	14/12/2017	S	JAR + ICE	1				X		X	X	
SWR 17	21649/S13/1-2	14/12/2017	S	JAR + ICE	1								
18	21649/S14/1-1	14/12/2017	S	JAR + ICE, B	1	X		X					
19	21649/S14/1-2	14/12/2017	S	JAR + ICE	1			X	X		X	X	
20	21649/S15-1	14/12/2017	S	JAR + ICE, B	1	X		X	X				
21	21649/S15-2	14/12/2017	S	JAR + ICE	1				X	X	X		
22	21649/S15-3	14/12/2017	S	JAR + ICE	1				X	X	X		
23	21649/S15-4	14/12/2017	S	JAR + ICE	1				X				
24	21649/S15-5	14/12/2017	S	JAR + ICE	1				X	X	X		
TOTAL					12	3	1	5	9	3	5	2	0

Water Container Codes: P = Unpreserved Plastic; N = Nitric Preserved Plastic; ORC = Nitric Preserved ORC; SH = Sodium Hydroxide/Cd Preserved; S = Sodium Hydroxide Preserved Plastic; AG = Amber Glass Unpreserved; AP = Airfreight Unpreserved Plastic  
V = VOA Vial HCl Preserved; VB = VOA Vial Sodium Bisulphate Preserved; VS = VOA Vial Sulfuric Preserved; AV = Airfreight Unpreserved Vial SG = Sulfuric Preserved Amber Glass; H = HCl preserved Plastic; HS = HCl preserved Speciation bottle; SP = Sulfuric Preserved Plastic; F = Formaldehyde Preserved Glass;  
Z = Zinc Acetate Preserved Bottle; E = EDTA Preserved Bottles; ST = Sterile Bottle; ASS = Plastic Bag for Acid Sulphate Soils; B = Unpreserved Bag.



# CHAIN OF CUSTODY

ALS Laboratory:  
please tick →

ADELAIDE 21 Burma Road Pooraka SA 5095  
Ph: 08 8359 0890 E: adelaide@alsglobal.com  
BRISBANE 32 Shand Street Stafford QLD 4053  
Ph: 07 3243 7222 E: samples.brisbane@alsglobal.com  
GLADSTONE 46 Callemondah Drive Clinton QLD 4680  
Ph: 07 7471 5600 E: gladstone@alsglobal.com

MACKAY 76 Harbour Road Mackay QLD 4740  
Ph: 07 4944 0177 E: mackay@alsglobal.com  
MELBOURNE 2-4 Westall Road Springvale VIC 3171  
Ph: 03 8549 9600 E: samples.melbourne@alsglobal.com  
MUDGEE 27 Sydney Road Mudgee NSW 2850  
Ph: 02 6372 6735 E: mudgee.mall@alsglobal.com

NEWCASTLE 5 Rose Gum Road Warabrook NSW 2304  
Ph: 02 4968 9439 E: samples.newcastle@alsglobal.com  
NOWRA 4/13 Geary Place North Nowra NSW 2541  
Ph: 024423 2053 E: nowra@alsglobal.com  
PERTH 10 Hod Way Malaga WA 6090  
Ph: 08 9209 7655 E: samples.perth@alsglobal.com

SYDNEY 277-289 Woodpark Road Smithfield NSW 2164  
Ph: 02 8784 8555 E: samples.sydney@alsglobal.com  
TOWNSVILLE 14-15 Desma Court Bohle QLD 4818  
Ph: 07 4796 0600 E: townsville.environmental@alsglobal.com  
WOLLONGONG 99 Kenny Street Wollongong NSW 2500  
Ph: 02 4225 3125 E: portkembla@alsglobal.com

CLIENT: SMEC Testing Services	TURNAROUND REQUIREMENTS: <input type="checkbox"/> Standard TAT (List due date):	<b>FOR LABORATORY USE ONLY (OTG)</b> Custody Seal intact? YES NO Freeze/Freeze-Thaw? YES NO Random Sample Temperature at Receipt: °C Other Comments:
OFFICE: 14/1 Cowpasture Place Wetherill Park	(Standard TAT may be longer for some tests e.g. Ultra Trace Organics) <input type="checkbox"/> Non Standard or urgent TAT (List due date):	
PROJECT: 21649	ALS QUOTE NO.:	
ORDER NUMBER: E-2017-713	COC SEQUENCE NUMBER (Circle) COC: 5 OF: 5	
PROJECT MANAGER:	CONTACT PH:	
SAMPLER:	SAMPLER MOBILE:	RELINQUISHED BY:
COC emailed to ALS? (YES / NO)	EDD FORMAT (or default):	RECEIVED BY:
Email Reports to (will default to PM if no other addresses are listed):		DATE/TIME:
Email Invoice to (will default to PM if no other addresses are listed):		DATE/TIME:

## COMMENTS/SPECIAL HANDLING/STORAGE OR DISPOSAL:

ALS USE		SAMPLE DETAILS (LAND, SOIL, S, WATER, W)		CONTAINER INFORMATION		ANALYSIS REQUIRED including SUITES (NB. Suite Codes must be listed to attract suite price) Where Metals are required, specify Total (unfiltered bottle required) or Dissolved (field filtered bottle required).								Additional Information
LAB ID	SAMPLE ID	DATE / TIME	MATRIX	TYPE & PRESERVATIVE <i>(refer to codes below)</i>	TOTAL CONTAINERS	EA200F	S12	S2	S19	EC + pH	SO4	CEC + ESP	Phosphorous Sorption Cap	Comments on likely contaminant levels, dilutions, or samples requiring specific QC analysis etc.
25	21649/S15-6	14/12/2017	S	JAR + ICE	1					x	x	x		
26	21649/S15-7	14/12/2017	S	JAR + ICE	1					x				
27	21649/S15-8	14/12/2017	S	JAR + ICE	1					x				
28	21649/S16/1-1	14/12/2017	S	JAR + ICE, B	1	x	x		x					
29	21649/S17-1	14/12/2017	S	JAR + ICE, B	1					x				
30	21649/S18/1-1	14/12/2017	S	JAR + ICE, B	1	x		x						
31	21649/S19/1-1	14/12/2017	S	JAR + ICE, B	1					x				
	Received Extra Sample				1									
32	TRIP 1	35 Dup1			1									
33	TRIP 2	36 Dup2			1									
34	TRIP 3	37 Dup3			1									
					1									
TOTAL					12	2	1	1	1	5	1	1	0	

Water Container Codes: P = Unpreserved Plastic; N = Nitric Preserved Plastic; ORC = Nitric Preserved ORC; SH = Sodium Hydroxide/Cd Preserved; S = Sodium Hydroxide Preserved Plastic; AG = Amber Glass Unpreserved; AP = Airfreight Unpreserved Plastic  
V = VOA Vial HCl Preserved; VB = VOA Vial Sodium Bisulphate Preserved; VS = VOA Vial Sulfuric Preserved; AV = Airfreight Unpreserved Vial SG = Sulfuric Preserved Amber Glass; H = HCl Preserved Plastic; HS = HCl Preserved Speciation bottle; SP = Sulfuric Preserved Plastic; F = Formaldehyde Preserved Glass;  
Z = Zinc Acetate Preserved Bottle; E = EDTA Preserved Bottles; ST = Sterile Bottle; ASS = Plastic Bag for Acid Sulphate Soils; B = Unpreserved Bag.



# CHAIN OF CUSTODY

ALS Laboratory:  
please tick →

ADELAIDE 21 Burma Road Pooraka SA 5095  
Ph: 08 8359 0890 E: adelaide@alsglobal.com

BRISBANE 32 Shand Street Stafford QLD 4053  
Ph: 07 3243 7222 E: samples.brisbane@alsglobal.com

GLADSTONE 46 Cailmondah Drive Clinton QLD 4680  
Ph: 07 7471 5600 E: gladstone@alsglobal.com

MACKAY 78 Harbour Road Mackay QLD 4740  
Ph: 07 4944 0177 E: mackay@alsglobal.com

MELBOURNE 2-4 Westall Road Springvale VIC 3171  
Ph: 03 8549 9600 E: samples.melbourne@alsglobal.com

MUDGEE 27 Sydney Road Mudgee NSW 2850  
Ph: 02 6372 6735 E: mudgee.mal@alsglobal.com

NEWCASTLE 5 Rose Gum Road Warabrook NSW 2304  
Ph: 02 4958 9433 E: samples.newcastle@alsglobal.com

NOWRA 4/13 Geary Place North Nowra NSW 2541  
Ph: 024423 2063 E: nowra@alsglobal.com

PERTH 10 Hod Way Malaga WA 6060  
Ph: 08 9209 7655 E: samples.perth@alsglobal.com

SYDNEY 277-289 Woodpark Road Smithfield NSW 2164  
Ph: 02 8784 8555 E: samples.sydney@alsglobal.com

TOWNSVILLE 14-15 Deema Court Bohle QLD 4818  
Ph: 07 4796 0600 E: townsville.environmental@alsglobal.com

WOLLONGONG 89 Kenny Street Wollongong NSW 2500  
Ph: 02 4225 3125 E: portkembla@alsglobal.com

CLIENT: SMEC Testing Services

OFFICE: 14/1 Cowpasture Place Wetherill Park

PROJECT: 21649

ORDER NUMBER: E-2017-713

PROJECT MANAGER:

SAMPLER:

COC emailed to ALS? ( YES / NO)

Email Reports to (will default to PM if no other addresses are listed):

Email Invoice to (will default to PM if no other addresses are listed):

TURNAROUND REQUIREMENTS :

(Standard TAT may be longer for some tests e.g..  
Ultra Trace Organics)

ALS QUOTE NO.:

☐ Standard TAT (List due date):

☐ Non Standard or urgent TAT (List due date):

COC SEQUENCE NUMBER (Circle)

COC: 1

OP: 5

RELINQUISHED BY:

DATE/TIME:

14/12/17 16:00

RECEIVED BY:

DATE/TIME:

14/12/17 4:02 PM

FOR LABORATORY USE ONLY (Circle)

Custody sealed by: Yes No N/A

Freezer / frozen ice bricks present upon receipt: Yes No N/A

Random Sample Temperature on Receipt: °C

Other comments:


RELINQUISHED BY:

RECEIVED BY:

DATE/TIME:

DATE/TIME:

COMMENTS/SPECIAL HANDLING/STORAGE OR DISPOSAL:

ALS USE	SAMPLE DETAILS MATRIX: SOLID (S) WATER (W)			CONTAINER INFORMATION			ANALYSIS REQUIRED including SUITES (NB. Suite Codes must be listed to attract suite price) Where Metals are required, specify Total (unfiltered bottle required) or Dissolved (field filtered bottle required).										Additional Information	
	LAB ID	SAMPLE ID	DATE / TIME	MATRIX	TYPE & PRESERVATIVE (refer to codes below)	TOTAL CONTAINERS	EA200F	S12	S2	EC + pH	SO4	CEC + ESP	Phosphorous Sorption Cap					Comments on likely contaminant levels, dilutions, or samples requiring specific QC analysis etc.
	1	21649/S1/1-1	14/12/2017		Environmental Division Sydney Work Order Reference <b>ES1731937</b>  Telephone : + 61-2-8784 8555	1	x	x	x	x								
	2	21649/S2-1	14/12/2017			1	x	x										
	3	21649/S2-2	14/12/2017			1		x	x	x								
	4	21649/S2-3	14/12/2017			1				x	x	x						
	5	21649/S2-4	14/12/2017			1				x								
	6	21649/S2-5	14/12/2017			1				x	x							
	7	21649/S2-6	14/12/2017			1				x	x							
	8	21649/S2-7	14/12/2017			1				x								
	9	21649/S2-8	14/12/2017	S	JAR + ICE	1				x	x							
	10	21649/S3/1-1	14/12/2017	S	JAR + ICE, B	1	x	x	x									
	11	21649/S3/2-1	14/12/2017	S	JAR + ICE	1		x	x									
	12	21649/S3/3-1	14/12/2017	S	JAR + ICE	1												
TOTAL						12	3	5	4	8	4	4	0	0				

Water Container Codes: P = Unpreserved Plastic; N = Nitric Preserved Plastic; ORC = Nitric Preserved ORC; SH = Sodium Hydroxide/Cd Preserved; S = Sodium Hydroxide Preserved Plastic; AG = Amber Glass Unpreserved; AP = Airfreight Unpreserved Plastic  
V = VOA Vial HCl Preserved; VB = VOA Vial Sodium Bisulphate Preserved; VS = VOA Vial Sulfuric Preserved; AV = Airfreight Unpreserved Vial SG = Sulfuric Preserved Amber Glass; H = HCl preserved Plastic; HS = HCl preserved Speciation bottle; SP = Sulfuric Preserved Plastic; F = Formaldehyde Preserved Glass;  
Z = Zinc Acetate Preserved Bottle; E = EDTA Preserved Bottles; ST = Sterile Bottle; ASS = Plastic Bag for Acid Sulphate Soils; B = Unpreserved Bag.



# CHAIN OF CUSTODY

ALS Laboratory:  
please tick →

ADELAIDE 21 Burma Road Pooraka SA 5095  
Ph: 08 8359 0890 E: adelaide@alsglobal.com

BRISBANE 32 Stand Street Stafford QLD 4053  
Ph: 07 3243 7222 E: samples.brisbane@alsglobal.com

GLADSTONE 46 Calliomedah Drive Clinton QLD 4680  
Ph: 07 7471 5500 E: gladstone@alsglobal.com

MACKAY 78 Harbour Road Mackay QLD 4740  
Ph: 07 4844 0177 E: mackay@alsglobal.com

MELBOURNE 2-4 Westall Road Springvale VIC 3171  
Ph: 03 8549 9500 E: samples.melbourne@alsglobal.com

MUDGEE 27 Sydney Road Mudgee NSW 2950  
Ph: 02 6372 6735 E: mudgee@mail@alsglobal.com

NEWCASTLE 5 Rose Gum Road Warabrook NSW 2304  
Ph: 02 4968 9433 E: samples.newcastle@alsglobal.com

NOWRA 4/13 Geary Place North Nowra NSW 2541  
Ph: 024423 2063 E: nowra@alsglobal.com

PERTH 10 Hod Way Malaga WA 6090  
Ph: 08 9209 7655 E: samples.perth@alsglobal.com

SYDNEY 277-289 Woodpark Road Smithfield NSW 2164  
Ph: 02 8784 5555 E: samples.sydney@alsglobal.com

TOWNSVILLE 14-15 Desma Court Bohle QLD 4818  
Ph: 07 4795 0600 E: townsville@alsglobal.com

WOLLONGONG 99 Kenny Street Wollongong NSW 2500  
Ph: 02 4225 3125 E: portkembla@alsglobal.com

CLIENT: SMEC Testing Services	TURNAROUND REQUIREMENTS : (Standard TAT may be longer for some tests e.g., Ultra Trace Organics)	<input type="checkbox"/> Standard TAT (List due date): <input type="checkbox"/> Non Standard or urgent TAT (List due date):	FOR LABORATORY USE ONLY (Circle) Custody Seal Intact: Yes No N/A Freeze / freeze packs present upon receipt: Yes No N/A Random Sample Temperature on Receipt: C Other comments:	
OFFICE: 14/1 Cowpasture Place Wetherill Park	ALS QUOTE NO.:	COC SEQUENCE NUMBER (Circle) COC: 1 2 3 4 5 6 7 OF: 1 2 3 4 5 6 7		
PROJECT: 21649	ORDER NUMBER: E-2017-713			
PROJECT MANAGER:	CONTACT PH:			
SAMPLER:	SAMPLER MOBILE:	RELINQUISHED BY: <i>EX</i>	RECEIVED BY: <i>ANDREW</i>	RELINQUISHED BY:
COC emailed to ALS? ( YES / NO)	EDD FORMAT (or default):	DATE/TIME: <i>14/12/2017 16:00</i>	DATE/TIME: <i>14/12/17 10:02pm</i>	RECEIVED BY:
Email Reports to (will default to PM if no other addresses are listed):				DATE/TIME:
Email Invoice to (will default to PM if no other addresses are listed):				DATE/TIME:

## COMMENTS/SPECIAL HANDLING/STORAGE OR DISPOSAL:

ALS USE	SAMPLE DETAILS (MATRIX: SOLID (S) / WATER (W))			CONTAINER INFORMATION			ANALYSIS REQUIRED including SUITES (NB. Suite Codes must be listed to attract suite price) Where Metals are required, specify Total (unfiltered bottle required) or Dissolved (field filtered bottle required).								Additional Information
LAB ID	SAMPLE ID	DATE / TIME	MATRIX	TYPE & PRESERVATIVE (refer to codes below)	TOTAL CONTAINERS	EA200F	S12	S2	EC + pH	SO4	CEC + ESP	Phosphorous Sorption Cap			Comments on likely contaminant levels, dilutions, or samples requiring specific QC analysis etc.
13	21649/S4/1-1	14/12/2017	S	JAR + ICE, B	1		x	x	x						
14	21649/S4/2-1	14/12/2017	S	JAR + ICE	1			x							
15	21649/S4/3-1	14/12/2017	S	JAR + ICE	1										
16	21649/S4/4-1	14/12/2017	S	JAR + ICE	1										
17	21649/S4/5-1	14/12/2017	S	JAR + ICE, B	1	x	x	x							
18	21649/S4/6-1	14/12/2017	S	JAR + ICE, B	1	x		x							
19	21649/S5/1-1	14/12/2017	S	JAR + ICE	1										
20	21649/S6/1-1	14/12/2017	S	JAR + ICE, B	1	x	x	x	x						
21	21649/S6/2-1	14/12/2017	S	JAR + ICE	1			x							
22	21649/S6/3-1	14/12/2017	S	JAR + ICE	1										
23	21649/S6/4-1	14/12/2017	S	JAR + ICE	1										
24	21649/S7/1-1	14/12/2017	S	JAR + ICE, B	1	x	x	x	x						
TOTAL					12	4	4	7	3	0	0	0	0		

Water Container Codes: P = Unpreserved Plastic; N = Nitric Preserved Plastic; ORC = Nitric Preserved ORC; SH = Sodium Hydroxide/Cd Preserved; S = Sodium Hydroxide Preserved Plastic; AG = Amber Glass Unpreserved; AP = Airfreight Unpreserved Plastic  
V = VOA Vial HCl Preserved; VB = VOA Vial Sodium Bisulphate Preserved; VS = VOA Vial Sulfuric Preserved; AV = Airfreight Unpreserved Vial SG = Sulfuric Preserved Amber Glass; H = HCl preserved Plastic; HS = HCl preserved Speciation bottle; SP = Sulfuric Preserved Plastic; F = Formaldehyde Preserved Glass;  
Z = Zinc Acetate Preserved Bottle; E = EDTA Preserved Bottles; ST = Sterile Bottle; ASS = Plastic Bag for Acid Sulphate Soils; B = Unpreserved Bag.



# CHAIN OF CUSTODY

ALS Laboratory:  
please tick →

ADELAIDE 21 Burma Road Pooraka SA 5095  
Ph: 08 8359 0800 E: adelaide@alsglobal.com

BRISBANE 32 Shand Street Stafford QLD 4053  
Ph: 07 3243 7222 E: samples.brisbane@alsglobal.com

GLADSTONE 46 Callamondah Drive Clinton QLD 4680  
Ph: 07 7471 5600 E: gladstone@alsglobal.com

MACKAY 78 Harbour Road Mackay QLD 4740  
Ph: 07 4944 0177 E: mackay@alsglobal.com

MELBOURNE 2-4 Westall Road Springvale VIC 3171  
Ph: 03 8549 9600 E: samples.melbourne@alsglobal.com

MUDGEE 27 Sydney Road Mudgee NSW 2850  
Ph: 02 6372 6735 E: mudgee@mail@alsglobal.com

NEWCASTLE 5 Rose Gum Road Warabrook NSW 2304  
Ph: 02 4968 9433 E: samples.newcastle@alsglobal.com

NOOWRA 4/13 Geary Place North Nowra NSW 2541  
Ph: 024423 2063 E: nowra@alsglobal.com

PERTH 10 Hod Way Malaga WA 6090  
Ph: 08 9209 7655 E: samples.perth@alsglobal.com

SYDNEY 277-289 Woodpark Road Smithfield NSW 2164  
Ph: 02 8784 8555 E: samples.sydney@alsglobal.com

TOWNSVILLE 14-15 Desma Court Bohle QLD 4818  
Ph: 07 4796 0600 E: townsville.environmental@alsglobal.com

WOLLONGONG 89 Kenny Street Wollongong NSW 2500  
Ph: 02 4225 3125 E: portkembla@alsglobal.com

CLIENT: SMEC Testing Services

OFFICE: 14/1 Cowpasture Place Wetherill Park

PROJECT: 21649

ORDER NUMBER: E-2017-713

PROJECT MANAGER:

CONTACT PH:

SAMPLER:

SAMPLER MOBILE:

COC emailed to ALS? ( YES / NO)

EDD FORMAT (or default):

Email Reports to (will default to PM if no other addresses are listed):

Email Invoice to (will default to PM if no other addresses are listed):

## TURNAROUND REQUIREMENTS :

☐ Standard TAT (List due date):

(Standard TAT may be longer for some tests e.g.,  
Ultra Trace Organics)

☐ Non Standard or urgent TAT (List due date):

ALS QUOTE NO.:

COC SEQUENCE NUMBER (Circle)

COC: 1

OF: 5

FOR LABORATORY USE ONLY (ORPH)	
Sample ID	VS
Trace Metals	Yes
Random Sample Temperature	20°C
Other Comments	

RELINQUISHED BY:

RECEIVED BY:

RELINQUISHED BY:

RECEIVED BY:


DATE/TIME:

DATE/TIME:

DATE/TIME:

DATE/TIME:

COMMENTS/SPECIAL HANDLING/STORAGE OR DISPOSAL:

ALS USE		SAMPLE DETAILS MATRIX: SOLID (S) / WATER (W)		CONTAINER INFORMATION		ANALYSIS REQUIRED including SUITES (NB. Suite Codes must be listed to attract suite price) Where Metals are required, specify Total (unfiltered bottle required) or Dissolved (field filtered bottle required).										Additional Information	
LAB ID	SAMPLE ID	DATE / TIME	MATRIX	TYPE & PRESERVATIVE (refer to codes below)	TOTAL CONTAINERS	EA200F	S12	S2	EC + pH	S04	CEC + ESP	Phosphorous Sorption Cap		Comments on likely contaminant levels, dilutions, or samples requiring specific QC analysis etc.			
1	21649/S1/1-1	14/12/2017	Environmental Division Sydney Work Order Reference <b>ES1731937</b>  Telephone : + 61-2-8784 8555		1	x	x	x	x								
2	21649/S2-1	14/12/2017			1	x	x										
3	21649/S2-2	14/12/2017			1		x	x	x								
4	21649/S2-3	14/12/2017			1				x	x	x						
5	21649/S2-4	14/12/2017			1				x								
6	21649/S2-5	14/12/2017			1				x	x							
7	21649/S2-6	14/12/2017			1				x	x							
8	21649/S2-7	14/12/2017			1				x								
9	21649/S2-8	14/12/2017	S	JAR + ICE	1				x	x							
10	21649/S3/1-1	14/12/2017	S	JAR + ICE, B	1	x	x	x									
11	21649/S3/2-1	14/12/2017	S	JAR + ICE	1		x	x									
12	21649/S3/3-1	14/12/2017	S	JAR + ICE	1												
TOTAL					12	3	5	4	8	4	4	0	0				

Subtotal / Subtotal / Subtotal  
Lab / Analysis  
Organised By / Date: Nenual  
Delinquished By / Date: Asbestos  
Consolidate / Courier:  
WO No:  
Attach By PO / Internal Sheet:

Water Container Codes: P = Unpreserved Plastic; N = Nitric Preserved Plastic; ORC = Nitric Preserved ORC; SH = Sodium Hydroxide/Cd Preserved; S = Sodium Hydroxide Preserved Plastic; AG = Amber Glass Unpreserved; AP = Airfreight Unpreserved Plastic  
V = VOA Vial HCl Preserved; VB = VOA Vial Sodium Bisulphate Preserved; VS = VOA Vial Sulfuric Preserved; AV = Airfreight Unpreserved Vial SG = Sulfuric Preserved Amber Glass; H = HCl preserved Plastic; HS = HCl preserved Speciation bottle; SP = Sulfuric Preserved Plastic; F = Formaldehyde Preserved Glass;  
Z = Zinc Acetate Preserved Bottle; E = EDTA Preserved Bottles; ST = Sterile Bottle; ASS = Plastic Bag for Acid Sulphate Soils; B = Unpreserved Bag.



☐ADELAIDE 21 Burma Road Pooraka SA 5095  
 Ph: 08 8359 0890 E: [adelaide@alsglobal.com](mailto:adelaide@alsglobal.com)  
☐BRISBANE 32 Shand Street Stafford QLD 4053  
 Ph: 07 3243 7222 E: [samples.brisbane@alsglobal.com](mailto:samples.brisbane@alsglobal.com)  
☐GLADSTONE 46 Callendondah Drive Clinton QLD 4680  
 Ph: 07 7471 5600 E: [gladstone@alsglobal.com](mailto:gladstone@alsglobal.com)

**Q**MACKAY 78 Harbour Road Mackay QLD 4740  
 Ph: 07 4944 0177 E: [mackay@aisglobal.com](mailto:mackay@aisglobal.com)  
**Q**MELBOURNE 2-4 Westall Road Springvale VIC 3171  
 Ph: 03 8549 9600 E: [samples.melbourne@aisglobal.com](mailto:samples.melbourne@aisglobal.com)  
**Q**MUDGEE 27 Sydney Road Mudgee NSW 2850  
 Ph: 02 6372 6735 E: [mudgee.mail@aisglobal.com](mailto:mudgee.mail@aisglobal.com)

☐ **NEWCASTLE** 5 Rose Gum Road Warabrook NSW 2304  
 Ph: 02 4968 9433 E: [samples.newcastle@alsglobal.com](mailto:samples.newcastle@alsglobal.com)  
☐ **NOWRA** 4/13 Geary Place North Nowra NSW 2541  
 Ph: 024423 2063 E: [nowra@alsglobal.com](mailto:nowra@alsglobal.com)  
☐ **PERTH** 10 Hod Way Malaga WA 6090  
 Ph: 08 9209 7655 E: [samples.perth@alsglobal.com](mailto:samples.perth@alsglobal.com)

☐ **SYDNEY** 277-289 Woodpark Road Smithfield NSW 2164  
 Ph: 02 8784 8555 E: [samples.sydney@alsglobal.com](mailto:samples.sydney@alsglobal.com)  
☐ **TOWNSVILLE** 14-16 Desma Court Bohle QLD 4818  
 Ph: 07 4796 0600 E: [townsville.environmental@alsglobal.com](mailto:townsville.environmental@alsglobal.com)  
☐ **WOLLONGONG** 99 Kenny Street Wollongong NSW 2500  
 Ph: 02 4225 3125 E: [norkembla@alsglobal.com](mailto:norkembla@alsglobal.com)

**TURNAROUND REQUIREMENTS :**  
(Standard TAT may be longer for some tests e.g., Ultra Trace Organics)

☐ Standard TAT (List due date):

☐ Non Standard or urgent TAT (List due date):

PROJECT: 21649

ALS QUOTE NO.:

COC SEQUENCE NUMBER (Circle)

ORDER NUMBER:E-2017-713

COC:	1	2	3	4	5	6	7
------	---	---	---	---	---	---	---

**PROJECT MANAGER:**

CONTACT PH:

**SAMPLER:**

**SAMPLER MOBILE:**

COC emailed to ALS? ( YES / NO)

**EDD FORMAT (or default):**

**Email Reports to (will default to PM if no other addresses are listed):**

**Email Invoice to (will default to PM if no other addresses are listed):**

RELINQUISHED BY:

DATE/TIME:

RECEIVED BY:

DATE/TIME:

RELINQUISHED BY:

DATE/TIME:

RECEIVED BY:

DATE/TIME:

COMMENTS/SPECIAL HANDLING/STORAGE OR DISPOSAL:

ALS USE	SAMPLE DETAILS		CONTAINER INFORMATION			ANALYSIS REQUIRED including SUITES (NB. Suite Codes must be listed to attract suite price) Where Metals are required, specify Total (unfiltered bottle required) or Dissolved (field filtered bottle required).								Additional Information
	MATRIX SOLID (g) TARE (g)													
LAB ID	SAMPLE ID	DATE / TIME	MATRIX	TYPE & PRESERVATIVE (refer to codes below)	TOTAL CONTAINERS	EA200F	S12	S2	EC + pH	SO4	CEC + ESP	Phosphorous Sorption Cap		Comments on likely contaminant levels, dilutions, or samples requiring specific QC analysis etc.
13	21649/S4/1-1	14/12/2017	S	JAR + ICE, B	1		x	x	x					
14	21649/S4/2-1	14/12/2017	S	JAR + ICE	1			x						
15	21649/S4/3-1	14/12/2017	S	JAR + ICE	1									
16	21649/S4/4-1	14/12/2017	S	JAR + ICE	1									
17	21649/S4/5-1	14/12/2017	S	JAR + ICE, B	1	x	x	x						
18	21649/S4/6-1	14/12/2017	S	JAR + ICE, B	1	x		x						
19	21649/S5/1-1	14/12/2017	S	JAR + ICE	1									
20	21649/S6/1-1	14/12/2017	S	JAR + ICE, B	1	x	x	x	x					
21	21649/S6/2-1	14/12/2017	S	JAR + ICE	1			x						
22	21649/S6/3-1	14/12/2017	S	JAR + ICE	1									
23	21649/S6/4-1	14/12/2017	S	JAR + ICE	1									
24	21649/S7/1-1	14/12/2017	S	JAR + ICE, B	1	x	x	x	x					
TOTAL					12	4	4	7	3	0	0	0	0	

**Water Container Codes:** P = Unpreserved Plastic; N = Nitric Preserved Plastic; ORC = Nitric Preserved ORC; SH = Sodium Hydroxide/Cd Preserved; S = Sodium Hydroxide Preserved Plastic; AG = Amber Glass Unpreserved; AP = Airfreight Unpreserved Plastic; V = VOA Vial HCl Preserved; VB = VOA Vial Sodium Bisulphate Preserved; VS = VOA Vial Sulfuric Preserved; AV = Airfreight Unpreserved Vial SG = Sulfuric Preserved Amber Glass; H = HCl preserved Plastic; HS = HCl preserved Speciation bottle; SP = Sulfuric Preserved Plastic; F = Formaldehyde Preserved Glass; Z = Zinc Acetate Preserved Bottle; E = EDTA Preserved Bottles; ST = Sterile Bottle; ASS = Plastic Bag for Acid Sulphate Soils; B = Unpreserved Bag.