

Liverpool Tower - 9-23 Scott Street & 275-277 Bigge Street, Liverpool

Commercial Development

OPERATIONAL WASTE MANAGEMENT PLAN

24/09/2018 Report No. 18044 Revision B

Client

TSOP Pty Ltd c/o Mackycorp Pty Ltd

40 Lime Street, Sydney NSW 2000 T 0451 663 276 • E mikehercus@mackycorp.com.au

Architect

Fender Katsalidis (Aust) Pty Ltd.

Level 3, 414 Kent Street, Sydney NSW 2000 www.fkaustralia.com
T 02 8216 3500 • E fk@fkaustralia.com

ELEPHANTS FOOT RECYCLING SOLUTIONS • ABN 70 001 378 294

44-46 Gibson Ave Padstow NSW 2211 www.elephantsfoot.com.au

T +612 9780 3500 • **F** +612 9707 2588 **E** info@elephantsfoot.com.au



SCOPE

This waste management plan (WMP) only applies to the **operational** phase of the proposed development; therefore the requirements outlined in this WMP must be implemented during the operational phase of the site and may be subject to review upon further expansion for, and/or changes to the development.

The waste management of the **construction** and **demolition** phases of the development are not addressed in this report. It is EFRS's understanding that a construction and demolition WMP will be completed by a separate party appointed by the developer, and submitted separately to this report. Typically, the head contractor of the site will be responsible for removing all construction-related waste offsite in a manner that meets all authority requirements.

REVISION REFERENCE

Revision	Date	Prepared by	Reviewed by	Description	Signed
А	21/08/2018	J Parker	A Armstrong	Draft	Steellen
В	24/09/2018	J Parker	A Armstrong	Final	Steellen

The information contained in this document produced by Elephants Foot Recycling Solutions (EFRS) is solely for the use of the client identified on the cover sheet for the purpose for which it has been prepared for. EFRS undertakes no duty, nor accepts any responsibility for any third party who may rely upon this document. Reproduction, publication or distribution of this document without written permission from EFRS is strictly prohibited.



TABLE OF CONTENTS

GLOSSARY OF	TERMS	i
LIST OF TABLES	S	ii
INTRODUCTION	V	1
DEVELOPMENT	SUMMARY	1
SITE LOCATION	V	2
LIVERPOOL CIT	Y COUNCIL	3
	CTIVES	
COUNCIL REQU	JIREMENTS	3
STAKEHOLDER	ROLES AND RESPONSIBILITIES	4
EDUCATION		5
LIMITATIONS		5
COMMERCIAL/F	RETAIL WASTE MANAGEMENT	6
ESTIMATED WA	ASTE VOLUMES AND PROVISIONS	6
COMMERCIAL V	VASTE MANAGEMENT	6
RETAIL WASTE	MANAGEMENT	6
COMMON AREA	AS	7
WASTE OILS		7
OTHER WASTE	STREAMS	7
MOVEMENT AN	D TRANSPORTATION OF BINS	8
COLLECTION O	F WASTE	8
COLLECTION A	REA	8
INSTALLATION	EQUIPMENT AND DESIGN	9
EQUIPMENT SU	JMMARY	9
WASTE ROOM	AREAS	9
GARBAGE ROC	MS	10
CONSTRUCTIO	N REQUIREMENTS	10
SIGNAGE		10
VENTILATION		10
USEFUL CONTA	ACTS	11
APPENDICES		12
APPENDIX A	ARCHITECTURAL DRAWING EXCERPTS	12
APPENDIX A.1	SITE PLAN	12
APPENDIX A.2	WASTE STORAGE/COLLECTION AREA	13
APPENDIX B	PRIMARY WASTE MANAGEMENT PROVISIONS	14
APPENDIX B.1	TYPICAL BIN SPECIFICATIONS	14
APPENDIX B.2	SIGNAGE FOR WASTE & RECYCLING BINS	15
APPENDIX B.3	TYPICAL COLLECTION VEHICLE INFORMATION	16





19	TYPICAL MOTORISED BIN TUG	APPENDIX B.4
20	TYPICAL SEATED BIN MOVER	APPENDIX B.5
21	INSTALLATION EQUIPMENT	APPENDIX C
21	COOKING OIL CONTAINERS	APPENDIX C.1
RETAIL/COMMERCIAL	TYPICAL BACK OF HOUSE BINS FOR 22	APPENDIX C.2 OPERATIONS
23	TYPICAL PUBLIC PLACE WASTE BINS	APPENDIX C.3

GLOSSARY OF TERMS

TERM	DESCRIPTION
Baler	A device that compresses waste into a mould to form bales which may be self-supporting or retained in shape by strapping
Collection Area/Point	The identified position or area where garbage or recyclables are actually loaded onto the collection vehicle
Compactor	A machine for compressing waste into disposable or reusable containers
Composter	A container/machine used for composting specific food scraps
Crate	A plastic box used for the collection of recyclable materials
Garbage	All domestic waste (Except recyclables and green waste)
Green Waste	All vegetated organic material such as small branches, leaves and grass clippings, tree and shrub pruning, plants and flowers
Hopper	A fitting into which waste is placed and from which it passes into a chute or directly into a waste container. It consists of a fixed frame and hood unit (the frame) and a hinged or pivoted combined door and receiving unit
L	Litre(s)
Liquid Waste	Non-hazardous liquid waste generated by commercial premises that is supposed to be connected to sewer or collected for treatment and disposal by a liquid waste contractor (including grease trap waste)
LRV	Large rigid vehicle described by AS 2890.2-2002 Parking facilities – Offstreet commercial vehicle facilities as heavy rigid vehicle (HRV)
Mobile Garbage Bin(s) (MGB)	A waste container generally constructed of plastic with wheels with a capacity in litres of 120, 240, 360, 660, 1000 or 1100
MRV	Medium rigid vehicle
Putrescible Waste	Component of the waste stream liable to become putrid. Usually breaks down in a landfill to create landfill gases and leachate. Typically applies to food, animal and organic products.
Recycling	Glass bottles and jars – PET, HDPE and PVC plastics; aluminium aerosol and steel cans; milk and juice cartons; soft drink, milk and shampoo containers; paper, cardboard, junk mail, newspapers and magazines
Refuse	Material generated and discarded from residential and commercial buildings including general waste, recyclables, green waste and bulky items
SRV	Small rigid vehicle as in AS 2890.2-2002 Parking facilities – Off-street commercial vehicle facilities, generally incorporating a body width of 2.33

LIST OF TABLES

Table 1: Stakeholder Roles and Responsibilities	. 4
Table 2: Calculated Waste Generation – Commercial/Retail	
Table 3: Equipment Summary	. 9
Table 4: Waste Room Areas	



INTRODUCTION

EFRS has been tasked to prepare the following waste management plan for Macky Corp for the operational management of waste generated by the commercial development located at 9-23 Scott Street and 275-277 Bigge Street, Liverpool.

Waste management strategies and auditing are a requirement for new developments to provide support for the building design, and promote strong sustainability outcomes for the building. It is EFRS's belief that a successful waste management strategy contains three key objectives:

- *i.* **Promote responsible source separation** to reduce the amount of waste that goes to landfill, by implementing convenient and efficient waste management systems
- *ii.* **Ensure adequate waste provisions and robust procedures** that will cater for potential changes during the operational phase of the development
- iii. **Compliance** with all relevant council codes, policies, and guidelines.

To achieve these objectives, this WMP identifies the different waste streams likely to be generated during the operational phase of the development. Associated information includes: how the waste will be handled and disposed of, details of bin sizes/quantities and waste rooms, descriptions of the proposed waste management equipment used and information on waste collection points and frequencies.

It is essential that this waste management plan is integral to the overall management of the building and clearly communicated to all relevant stakeholders.

DEVELOPMENT SUMMARY

The proposed development falls under the LGA of Liverpool Council, and consists of:


- 1 building of 22 levels
 - Ground floor retail units with a total GFA of 460m²
 - 22 levels of commercial units with a total GFA of 25,257m²

All figures and calculations are based on area schedules as advised by our client and shown on architectural drawings.



SITE LOCATION

The site is located at 9-23 Scott Street and 275-277 Bigge Street, Liverpool, as shown below. The site has frontages to Scott Street, Railway and Bigge Street, with vehicle access via Railway Service Way.



Source: Fender Katsalidis - Site Plan



LIVERPOOL CITY COUNCIL

The garbage and recycling will be guided by the services and acceptance criteria of the Liverpool City Council. All waste facilities and equipment are to be designed and constructed to be in compliance with the Liverpool City Council's *Liverpool Development Control Plan 2008*, Australian Standards and statutory requirements.

COUNCIL OBJECTIVES

- To minimise waste generation and disposal to landfill with careful source separation, reuse and recycling.
- To avoid the generation of waste through design, material selection and building practices.
- To plan for the types, amount and disposal of waste to be generated during demolition, excavation and construction of the development.
- To ensure efficient storage and collection of waste and quality design of facilities

COUNCIL REQUIREMENTS

Access – Ensure waste systems are easy to use and collection vehicles are able to access buildings to safely remove waste and recycling;

Safety – Ensure safe practises for storage, handling and collection of waste and recycling;

Pollution Prevention – Prevent stormwater pollution that may occur as a result of poor waste storage and management practises;

Noise Minimisation – Provide acoustic insulation to the waste service facilities or units adjacent to or above chutes, waste storage facilities, chute discharge, waste compaction equipment and waste collection vehicle access points;

Ecologically Sustainable Development (ESD) – Promote the principles of ESD through resource recovery and recycling leading to a reduction in the consumption of finite natural resources;

Hygiene – Ensure health and amenity for residents, visitors and workers in the Liverpool City Council.



STAKEHOLDER ROLES AND RESPONSIBILITIES

The following table demonstrates the primary roles and responsibilities of the respective stakeholders:

Table 1: Stakeholder Roles and Responsibilities

Roles	Responsibilities
Strata/Management	 Ensuring that all waste service providers submit monthly reports on all equipment movements and waste quantities/weights; Organising internal waste audits/visual assessments on a regular basis; and Manage any non-compliances/complaints reported through waste audits.
Building Manager/Waste Caretaker	 Ensuring effective signage, communication and education is provided to occupants, tenants and cleaners; Providing staff/contractors with equipment manuals, training, health and safety procedures, risk assessments, and PPE to control hazards associated with all waste management activities; Ensuring site safety for tenants, children, visitors, staff and contractors; Abiding by all relevant OH&S legislation, regulations, and guidelines; Assessing any manual handling risks and prepare a manual handling control plan for waste and bin transfers; Preventing storm water pollution by taking necessary precautions (securing bin rooms, preventing overfilling of bins) Cleaning and transporting of bins as required; Organising, maintaining and cleaning the general and recycled waste holding area; Organising both garbage and recycled waste pick-ups as required; Organising replacement or maintenance requirements for bins; Organising bulky goods collection when required; and Investigating and ensuring prompt clean-up of illegally dumped waste materials.
Tenants	 Dispose of all garbage and recycling in the allocated MGBs provided; Ensure adequate separation of garbage and recycling; and Compliance with the provisions of Council and the WMP.
Council/Private Waste Contractor	 Provide a reliable and appropriate waste collection service; Provide feedback to building managers/tenants in regards to contamination of recyclables; and Work with building managers to customise waste systems where possible.
Gardening/Landscaping Contractor	Removal of all garden organic waste generated during gardening maintenance activities for recycling at an offsite location.
Building Contractors	Removing all construction related waste offsite in a manner that meets all authority requirements.



EDUCATION

Building management is responsible for creating and managing the waste management education process.

Educational material encouraging the correct separation of garbage and recycling items must be provided to each tenant to ensure the correct disposal of waste, including bulky goods (old furniture, large discarded items, etc.) It is recommended that information is provided in multiple languages to support correct practises and minimise the possibility of contamination in the collective waste bins.

LIMITATIONS

The purpose of this report is to document a Waste Management Plan (WMP) as part of a development application and is supplied by Elephants Foot Recycling Solutions (EFRS) with the following limitations:

- Drawings, estimates and information contained in this waste management plan have been prepared by analysing the information, plans and documents supplied by the client, and third parties including Council and government information. The assumptions based on the information contained in the WMP is outside the control of EFRS;
- the figures presented in the report are an estimate only the actual amount of waste generated will be dependent on the occupancy rate of the building/s and waste generation intensity as well as the building managements approach to educating tenants regarding waste management operations and responsibilities;
- the building manager will make adjustments as required based on actual waste volumes (if waste is greater than estimated) and increase the number of bins and collections accordingly;
- the report will not be used to determine or forecast operational costs or prepare any feasibility study or to document any safety or operational procedures;
- the report has been prepared with all due care however no assurance or representation is made that the WMP reflects the actual outcome and EFRS will not be liable to you for plans or outcomes that are not suitable for your purpose, whether as a result of incorrect or unsuitable information or otherwise;
- EFRS offer no warranty or representation of accuracy or reliability of the WMP unless specifically stated;
- any manual handling equipment recommended should be provided at the recommendation of the appropriate equipment provider who will assess the correct equipment for supply:
- Design of waste management equipment and systems must be approved by the supplier.



COMMERCIAL/RETAIL WASTE MANAGEMENT

The Better Practice Guide for Waste Management and Recycling has been referenced to calculate the total number of bins required for the retail and commercial areas. Calculations are based on generic figures; waste generation rates may differ according to the tenants' waste management practice.

ESTIMATED WASTE VOLUMES AND PROVISIONS

The following table shows the estimated volume (L) of garbage and recycling generated by the commercial/retail component of the development. A seven day operating week has been assumed.

Table 2: Calculated Waste Generation - Commercial/Retail

Tenancy	Туре	NLA (m²)	Garbage Generation Rate (L/100m²/day)	Generated Garbage (L/week)	Recycling Generation Rate (L/100m²/day)	Generated Recycling (L/week)		
Offices	Commercial	25257	10	17679.9	10	17679.9		
Pub	Restaurant	170	670	7973	135	1606.5		
Retail 1 (GF)	Café	52	210	764.4	135	491.4		
Retail 2 (GF)	Café	73	210	1073.1	135	689.85		
Retail 3 (GF)	Café	42	210	617.4	135	396.9		
Retail 4 (GF)	Café	26	210	382.2	135	245.7		
Retail 5 (GF)	Café	35	210	514.5	135	330.75		
Retail 6 (GF)	Café	62	210	911.4	135	585.9		
	TOTAL	25717		29915.9		22026.9		
		Bin Size (L)		1100	Bin Size (L)	1100		
Collections & Equipment		Collections per Week		5	Collections per Week	5		
		No. Bins Required		6	No. Bins Required	5		
Was	Waste Rooms		Equipment		None			
vvas	ne moonis	Storage Room		Approx. 34sqm				

COMMERCIAL WASTE MANAGEMENT

Typically, bins for paper or general waste are positioned next to each workers desk or work station. One or both of these bins are emptied by contract cleaners. The cleaners circulate around the workplace after normal office hours and also perform other cleaning tasks, generally vacuuming and cleaning toilets. Bins for general waste and recyclables are also located centrally in each office, generally in the kitchen area and printer room.

Cleaners empty the bins into bags which they transport around the office/s in a cart which is also used to store cleaning products, spare bags, PPE and consumables.

Bags of garbage and/or recycling are placed in a central location by the cleaners (often outside the goods lift/s) and transported to the collection bins by another cleaner.

RETAIL WASTE MANAGEMENT

Tenants will be responsible for their own storage of garbage and recycling back of house (BOH).

Food handling for food cooked or prepared, served and consumed on site will produce a typical waste composition of food scraps from plates, packaging waste and some plastics. Café or restaurant staff will be responsible for their own BOH waste management.



Cardboard is a major component of the waste generated by cafes/restaurants. All cardboard should be flattened (to save bin space), placed in and collected from bulk bins. Whilst cardboard is bulky, it is generally lightweight however it can be contaminated with food or liquid which makes it unsuitable for recycling.

On completion of each trading day or as required, nominated retail staff/cleaners will transport their garbage and recycling to the retail waste room on the ground level and place garbage and recycling into the appropriate collection bins.

To ensure the proper management and disposal of waste, tenants must be made aware of the following practices:

- all garbage should be bagged and garbage bins should be plastic lined;
- bagging of recyclables is not permitted;
- all interim waste storage is located BOH during operations;
- individual recycling programs are recommended for retailers to ensure commingled recycling is correctly separated;
- any food and beverage tenant will make arrangements for storing used and unused cooking oil in a bunded storage area;
- the operator will organise grease interceptor trap servicing;
- a suitable storage area needs to be provided and effectively bunded for chemicals, pesticides and cleaning products;
- dry basket arrestors need to be provided to the floor wastes in the food preparation and waste storage areas; and
- all flattened cardboard will be collected and removed to the waste room recycling MGB

Note: It is the responsibility of the building manager to monitor the number of bins required for the development. As waste volumes may change according to the development's management, customer base and retail tenancy attitudes to waste disposal and recycling, bin numbers and sizes may need to be altered to suit the building operation. Seasonal peak periods i.e. public and school holidays should also be considered.

COMMON AREAS

Any staff tea points will be supplied with a dedicated commingled MGB for the collection of all recyclable glass, aluminium, steel and plastic items. Staff will be responsible for sorting this material and allocating recyclables into the correct collection facility.

Washroom facilities should be supplied with collection bins for paper towels (if used). Sanitary bins for female restroom facilities must also be arranged with an appropriate contractor.

WASTE OILS

Consideration should be given to the use of cooking oil collection systems. A single service provider may be used to reduce the amount of commercial traffic into the loading bay or around the precinct area. This should be measured against bulk delivery of oils where the same vehicle is used to remove containers of waste cooking oils (see APPENDIX C.1 for Typical Cooking Oil Collection System)

OTHER WASTE STREAMS

Tenants are required make arrangements for the disposal and recycling of specialised waste (toner cartridges, batteries, etc.). Disposal of hard, electronic, liquid waste and any detox (paint/chemicals) can be organised with the assistance of the building management/cleaners.



MOVEMENT AND TRANSPORTATION OF BINS

The building manager/waste caretaker is responsible for the transportation of bins from their designated operational locations to their respective collection room/areas prior to scheduled collection times, and returning them once emptied to resume operational use.

Transfer of waste and all bin movements require minimal manual handling; the operator must assess manual handling risks and provide any relevant documentation to building management.

If required the developer should contact a bin-tug, trailer or tractor consultant to provide equipment recommendations. Examples of motorised bin moving equipment can be found in APPENDIX B.4 and APPENDIX B.5.

Bins may have to be fitted with hitches to enable the simultaneous transportation of multiple bins to the collection area. Council must be informed of any hitch attachments required to be installed on bins.

COLLECTION OF WASTE

All waste generated by this development will be collected by private contractor to an agreed schedule (this report assumes five times weekly collections for both garbage and recycling.

Prior to collection times, the facility manager will be responsible for ensuring that bins are neatly arranged within the waste room for ease of servicing.

The contractor's waste vehicle will access the site from the Railway Service Way and pull into the loading dock. Collection staff will service the bins directly from the waste room with the vehicle then leaving the site in a forward-facing direction.

COLLECTION AREA

It is Elephant Foot's understanding that the collection areas have been reviewed by a traffic consultant to confirm the swept paths for waste collections, access and egress, internal manoeuvring to assume parked position for loading and to exit, load requirements as well as collection vehicle. It must be ensured that that the collection vehicle (and other trucks if required) can enter and exit the building in a forward direction. The final number of truck movements will depend on management of waste contract; final configuration of waste and recycling arrangements therefore number of bin lifts and additional irregular truck movements for hard waste.



INSTALLATION EQUIPMENT AND DESIGN EQUIPMENT SUMMARY

Table 3: Equipment Summary

Component	Part	Qty	Notes
Equipment	Suitable Bin Moving Equipment	N/A	Optional (See APPENDIX B.4 for Typical Bin Mover)

WASTE ROOM AREAS

Any compaction units should be caged off to ensure the safety of any personnel accessing the waste room.

The areas allocated for waste storage are detailed in Table 4 below. The areas provided are estimates only. Final areas will depend upon room and bin layouts.

Table 4: Waste Room Areas

Level	Waste Room Type	Equipment	Allocated Area (m²)
G	Waste Holding Room	6 x 1100L MGBs (Garbage) 5 x 1100L MGBs (Recycling)	34

Note: Any requirement for increasing storage capacity may be met by increasing the frequency of collections for all waste.



GARBAGE ROOMS

CONSTRUCTION REQUIREMENTS

The garbage room will be required to contain the following facilities to minimise odours, deter vermin, protect surrounding areas, and make it a user-friendly and safe area:

- waste room floor to be sealed with a two pack epoxy;
- waste room walls and floor surface is flat and even;
- all corners coved and sealed 100mm up, this is to eliminate build-up of dirt;
- for retail/commercial: a cold water facility with hose cock must be provided for washing the bins:
- any waste water discharge from bin washing must be drained to sewer in accordance with the relevant water board. (Sydney Water);
- tap height of 1.6m;
- storm water access preventatives (grate);
- all walls painted with light colour and washable paint;
- equipment electric outlets to be installed 1700mm above floor levels;
- the room must be mechanically ventilated;
- light switch installed at height of 1.6m;
- waste rooms must be well lit (sensor lighting recommended);
- optional automatic odour and pest control system installed to eliminate all pest types and assist with odour reduction – this process generally takes place at building handover – building management make the decision to install;
- if 660L or 1100L bins are utilised, 2 x 820mm (minimum) door leafs must be used;
- all personnel doors are hinged, lockable and self-closing;
- waste collection area must hold all bins bin movements should be with ease of access;
- conform to the Building Code of Australia, Australian Standards and local laws; and
- childproofing and public/operator safety shall be assessed and ensured

SIGNAGE

The building manager/caretaker is responsible for waste room signage including safety signage (see APPENDIX B.2). Appropriate signage must be prominently displayed on walls and above all bins, clearly stating what type of waste or recyclables is to be placed in the bin underneath.

VENTILATION

Waste and recycling rooms must have their own exhaust ventilation system either;

- Mechanically exhausting at a rate of 5L/m² floor area, with a minimum rate of 100L/s minimum; or
- Naturally permanent, unobstructed, and opening direct to the external air, not less than one-twentieth (1/20) of the floor area

Mechanical exhaust systems shall comply with AS1668 and not cause any inconvenience, noise or odour problem.



USEFUL CONTACTS

Elephants Foot Recycling Solutions does not warrant or make representation for goods or services provided by suppliers.

LIVERPOOL CITY COUNCIL CUSTOMER SERVICE

Phone: 1300 36 21 70 Email: lcc@liverpool.nsw.gov.au

SULO MGB (MGB, Public Place Bins, Tugs and Bin Hitches)

Phone: 1300 364 388

CLOSED LOOP (Organic Dehydrator)

Phone: 02 9339 9801

ELECTRODRIVE (Bin Mover)

Phone: 1800 333 002 Email: sales@electrodrive.com.au

RUD (Public Place Bins, Recycling Bins)

Phone: 07 3712 8000 Email: Info@rud.com.au

CAPITAL CITY WASTE SERVICES (Private Waste Services Provider)

Phone: 02 9359 9999

REMONDIS (Private Waste Services Provider)

Phone: 13 73 73

SITA ENVIRONMENTAL (Private Waste Services Provider)

Phone: 13 13 35

NATIONAL ASSOCIATION OF CHARITABLE RECYCLING ORGANISATIONS INC.

(NACRO)

Phone: 03 9429 9884 Email: information@nacro.org.au

PURIFYING SOLUTIONS (Odour Control)

Phone: 1300 636 877 Email: sales@purifyingsolutions.com.au

MOVEXX (Bin Movers) Phone: 1300 763 444

AUSCOL (Recyling Oils & Animal Fats)

Phone: 1800 629 476

KOMPACT EQUIPMENT (Equipment & Servicing Provider)

Phone: 1300 566 722 Email: info@kompactequipment.com.au

ELEPHANTS FOOT RECYCLING SOLUTIONS (Chutes, Compactors & eDiverter Systems)

44 – 46 Gibson Avenue Padstow NSW 2211


Phone: 1300 434 374 Email: wmp@elephantsfoot.com.au



APPENDICES

APPENDIX A ARCHITECTURAL DRAWING EXCERPTS


APPENDIX A.1 SITE PLAN



Source: Fender Katsalidis - Site Plan

FOOT recycling solution

APPENDIX A.2 WASTE STORAGE/COLLECTION AREA



Source: Fender Katsalidis – Ground Floor Plan



APPENDIX B PRIMARY WASTE MANAGEMENT PROVISIONS APPENDIX B.1 TYPICAL BIN SPECIFICATIONS

Mobile garbage bins (MGBs)

MGBs with capacities up to 1700L should comply with the Australian Standard for Mobile Waste Containers (AS 4123). AS 4123 specifies standard sizes and sets out the colour designations for bodies and lids of mobile waste containers that relate to the type of materials they will be used for.

Indicative sizes only for common MGB sizes are provided below. Note that not all MGB sizes are shown; the dimensions are only a guide and differ slightly according to manufacturer, if bins have flat or dome lids and are used with different lifting devices. Refer to AS 4123 for further detail.

Mobile containers with a capacity from 80L to 360L with two wheels



Bin Type	80 Litre MGB	120 Litre MGB	140 Litre MGB	240 Litre MGB	360 Litre MGB
Height	870 mm	940 mm	1065 mm	1080 mm	1100 mm
Depth	530 mm	560 mm	540 mm	735 mm	885 mm
Width	450 mm	485 mm	500 mm	580 mm	600 mm

Mobile containers with a capacity from 500L to 1700L with four wheels



Dome or flat lld containers

Bin Type	660 Litre MGB	770 Litre MGB	1100 Litre MGB	1300 Litre MGB	1700 Litre MGB
Height	1250	1425	1470	1480	1470
Depth	850	1100	1245	1250	1250
Width	1370	1370	1370	1770	1770

SOURCE: Department of Environment and Climate Change NSW 2008, Better Practice Guide for Waste Management in Multi-Únit Dwellings



APPENDIX B.2 SIGNAGE FOR WASTE & RECYCLING BINS

WASTE SIGNS

Signs for garbage, recycling and organics bins should comply with the standard signs promoted by the Department of Environment and Heritage.

Example wall posters









Example bin lid stickers









SAFETY SIGNS

The design and use of safety signs for waste rooms and enclosures should comply with AS1319 Safety Signs for Occupational Environment. Safety signs should be used to regulate and control safety behaviour, warn of hazards and provide emergency information, including fire protection information. Below are some examples. Each development will need to decide which signs are relevant for its set of circumstances and service provided.

Examples of Australian Standards:









Australian Standards are available from the SAI Global Limited website (www.saiglobal.com).

SOURCE: Department of Environment and Climate Change NSW 2008, Better Practice Guide for Waste Management in Multi-Unit Dwellings




APPENDIX B.3 TYPICAL COLLECTION VEHICLE INFORMATION

Collection vehicles

Waste collection vehicles may be side loading, rear-end loading, front-end loading or crane trucks. The size of vehicle varies according to the collection service. Thus it is impossible to specify what constitutes the definitive garbage vehicle. Developers should consult the local council and/or relevant contractors regarding the type of vehicle used in that area.

The following characteristics represent the typical collection vehicle, however, these are only for guidance.

It may be possible to engage a collection service provider to use smaller collection vehicles to service developments with narrow roadways and laneways, or for on-site collections. However, as the availability of smaller vehicles to make services varies between councils and private contractors, wherever possible the development should be designed to accommodate vehicles of a similar size to that reported below.




Rear loading collection vehicle

Rear loading collection vehicle				
Length overall	10.24m			
Width overall	2.5m			
Operational height	3.5m			
Travel height	3.5m			
Weight (vehicle only)	12.4 tonnes			
Weight (payload)	9.5 tonnes			
Turning circle	18.0m			

This is commonly used for domestic garbage and recycling collections from MUDs. It can be used to collect waste stored in MGBs or bulk bins, particularly where bins are not presented on the kerbside.



Side-loading collection vehicle




Side-loading collection vehicle				
Length overall	9.64m			
Front overhang	1.51m			
Wheelbase	5.20m			
Rear overhang	2.93m			
Turning circle kerb to kerb	17.86m			
Turning circle wall to wall	20.56m			
Front of vehicle to collection arm	3.8m			
Maximum reach of side arm	3.0m			
Travel height	3.63m			
Clearance height for loading	3.9m			

This is the most commonly used vehicle for domestic garbage and recycling collections. It is only suitable for collecting MGBs up to 360 litres in size.



Front-lift loading collection vehicle



Front-lift loading collection vehicle			
Length overall	10.52m		
Front overhang	1.51m		
Wheelbase	5.84m		
Rear overhang	3.17m		
Turning circle kerb to kerb	22.10m		
Turning circle wall to wall	23.66m		
Travel height	3.82m		
Clearance height for loading	6.1m		

This is mainly used for collecting commercial and industrial waste, and is only suitable for bulk bins with front lift pockets (not MGBs).

SOURCE: Department of Environment and Climate Change NSW 2008, Better Practice Guide for Waste Management in Multi-Unit Dwellings



APPENDIX B.4 TYPICAL MOTORISED BIN TUG



Typical applications:

- Move trolleys, waste bin trailers and 660/1100L bins up and down a <u>ramp incline</u>.
- Quiet, smooth operation with zero emissions and simple to use, no driver's licence required
- Suitable for:
 - High rise building & apartment basements
 - Large factories & warehouse with sloped ground
 - Caravan parks & other large outdoor areas

Features:

- 1 tonne tow capacity of inclines up to 8 degrees
- 500kg tow capacity if inclines up to 14 degrees
- CE Compliant
- 4.5 km/h max speed
- 2 x 80amp batteries includes charger
- Powerful transaxle
- Hitch to suit 660L bins


Safety Features:

- Intuitive paddle lever control
- Stops and repels the unit if activated when reversing.
- Site assessment recommended to assess ramp incline steepness (See Useful Contacts)



APPENDIX B.5 TYPICAL SEATED BIN MOVER





		UNIT M.	BULL 2	BULL 4
Manufacturer	DEC			
Model	BULL			
Platform loading cap.	Nominal capacity	kg		
Pull capacity	Pull nominal capacity	kg	2000	4000
Power type	Electric - endotermic		electric	electric
Controltype	Standing / seated thiller / steer		seated / steer	seated / steer
Tyres	Pn=pneum. Se=superelastic		Pn	Pn
Wheels	N. front/rear - x drive	n.	1/2X	1/2X
Platform dimensions	L x B (lengh x width)	mm		
Platform hight	h6 = unload clearence	mm		
Overal dimensions	L = lenght B = width h1 = foot leve h3 = Seat height h4 = Steer height	mm mm mm mm	1500 900 1820 310 1250	1600 930 1960 340 1330
Turning radius	R1 = front min. external R2 = rear min. external R3 = front min. internal	mm mm mm	1400 1000 400	1500 1000 400
Aisle width	A = 180° turn	mm	2200	2300
Tow hook height	s = center from ground	mm	220-350-490	240-380-520




APPENDIX C INSTALLATION EQUIPMENT

APPENDIX C.1 COOKING OIL CONTAINERS



The RIGHT WAY for Cooking Oil Collection Systems







APPENDIX C.2 TYPICAL BACK OF HOUSE BINS FOR RETAIL/COMMERCIAL OPERATIONS










APPENDIX C.3 TYPICAL PUBLIC PLACE WASTE BINS



Source: Department of Environment and Conservation (NSW) Better Practice Guide for Public Place Recycling 2005