

DEVELOPMENT CONSENT OPERATIONAL CONDITIONS

1. **Approved Plans and Supporting Documentation**

The development must be carried out in compliance (except as amended by any other condition of consent) with the following:

a) Approved Plans

Architectural Plans - Endorsed with Council's stamp		
Drawing No.	Dated	Prepared By
DA101 - Site Analysis Plan (Issue A)	25/03/2019	PA Studio
DA201 - Subdivision Plan (Issue A)	25/03/2019	PA Studio
DA301 - Basement and Lower Floor Plan (Issue A)	25/03/2019	PA Studio
DA302 - Ground Floor Plan I(Issue A)	25/03/2019	PA Studio
DA303 - Levels 1 & 2 Floor Plans (Issue A)	25/03/2019	PA Studio
DA304 - Levels 3 & 4 Floor Plans (Issue A)	25/03/2019	PA Studio
DA305 - Levels 5 & 6 Floor Plans (Issue A)	25/03/2019	PA Studio
DA306 - Roof Plan (Issue A)	25/03/2019	PA Studio
DA401 -Sections (Issue A)	25/03/2019	PA Studio
DA501 - North Elevation (Issue A)	25/03/2019	PA Studio
DA502 - West Elevation (Issue A)	25/03/2019	PA Studio
DA503 -South Elevation (Issue A)	25/03/2019	PA Studio
DA504 - East Elevation (Issue A)	25/03/2019	PA Studio
DA601 - Materials Plan (Issue A)	25/03/2019	PA Studio
DA701 - Access Ramp Plan (Issue A)	25/03/2019	PA Studio
DA801 – Demolition Plan (Issue A)	25/03/2019	PA Studio

Engineering Plans		
Drawing No.	Dated	Prepared By
DA08712-10/19/Issue A	20 April 2018	ING Consulting Engineers PTY LTD
DA08712-11/19/Issue A	20 April 2018	ING Consulting Engineers PTY LTD
DA08712-12/19/Issue A	20 April 2018	ING Consulting Engineers PTY LTD
DA08712-13/19/Issue A	20 April 2018	ING Consulting Engineers PTY LTD
DA08712-14/19/Issue A	20 April 2018	ING Consulting Engineers PTY LTD
DA08712-15/19/Issue A	20 April 2018	ING Consulting Engineers PTY LTD
DA08712-16/19/Issue A	20 April 2018	ING Consulting Engineers PTY LTD
DA08712-17/19/Issue A	20 April 2018	ING Consulting Engineers PTY LTD
DA08712-18/19/Issue A	20 April 2018	ING Consulting Engineers PTY LTD

Reports / Documentation – All recommendations and requirements contained within:		
Report No. / Page No. / Section No.	Dated	Prepared By

Arboricultural Impact Appraisal and Method Statement	21/05/2018	Naturally Trees
Amended Bushfire Protection Assessment	17/05/2019	ABPP
Report of Geotechnical Assessment	07/05/2018	Douglas Partners
Building Code of Australia Report	18/05/2018	Incode Solutions
Acoustic Report	17/05/2018	Wood & Grieve Engineers
Access Report	14/05/2018	Code Performance
Traffic and Parking Assessment Report	28/03/2019	Varga Traffic Planning
Preliminary Site Investigation	7/05/2018	Benvirongroup

b) Any plans and/or documentation submitted to satisfy the Deferred Commencement Conditions of this consent as approved in writing by Council.

c) Any plans and/or documentation submitted to satisfy the Conditions of this consent.

d) The development is to be undertaken generally in accordance with the following:

Landscape Plans		
Drawing No.	Dated	Prepared By
DA1206 Landscape Plan	25/03/2019	PA Studio
L/00 Rev C	21/5/2018	A Total Concept Landscape Architects & Swimming Pool Designers
L/01 Rev	21/05/2018	A Total Concept Landscape Architects & Swimming Pool Designers
Waste Management Plan		
Drawing No./Title.	Dated	Prepared By
Waste Management Plan	Updated	Kaligem PTY LTD

In the event of any inconsistency between conditions of this consent and the drawings/documents referred to above, the conditions of this consent will prevail.

Reason: To ensure the work is carried out in accordance with the determination of Council and approved plans.

2. Compliance with Other Department, Authority or Service Requirements

The development must be carried out in compliance with all recommendations and requirements, excluding general advice, within the following:

Other Department, Authority or Service	EDMS Reference	Dated
RFS	D19/1347	15/03/2019
RMS	SYD17/00985/03	18/04/2019

(NOTE: For a copy of the above-referenced document/s, please see Application Tracking on Council's website www.northernbeaches.nsw.gov.au)

Reason: To ensure the work is carried out in accordance with the determination and the statutory requirements of other Department, Authority or Body's. (DACPLB02)

3. Prescribed Conditions

- (a) All building works must be carried out in accordance with the requirements of the Building Code of Australia (BCA).
- (b) BASIX affected development must comply with the schedule of BASIX commitments specified within the submitted BASIX Certificate (demonstrated compliance upon plans/specifications is required prior to the issue of the Construction Certificate);
- (c) A sign must be erected in a prominent position on any site on which building work, subdivision work or demolition work is being carried out:
 - (i) showing the name, address and telephone number of the Principal Certifying Authority for the work, and
 - (ii) showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working hours, and
 - (iii) stating that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.

- (d) Residential building work within the meaning of the Home Building Act 1989 must not be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council) has given the Council written notice of the following information:
 - (i) in the case of work for which a principal contractor is required to be appointed:
 - A. the name and licence number of the principal contractor, and
 - B. the name of the insurer by which the work is insured under Part 6 of that Act,
 - (ii) in the case of work to be done by an owner-builder:
 - A. the name of the owner-builder, and
 - B. if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.

If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under becomes out of date, further work must not be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council) has given the Council written notice of the updated information.

- (e) Development that involves an excavation that extends below the level of the base of the footings of a building on adjoining land, the person having the benefit of the development consent must, at the person's own expense:
 - (i) protect and support the adjoining premises from possible damage from the excavation, and
 - (ii) where necessary, underpin the adjoining premises to prevent any such damage.
 - (iii) must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished.
 - (iv) the owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this clause, whether carried out on the allotment of land being excavated or on the adjoining allotment of land.

In this clause, allotment of land includes a public road and any other public place.

Reason: Legislative Requirement (DACPLB09)

4. General Requirements

- (a) Unless authorised by Council:
Building construction and delivery of material hours are restricted to:
 - 7.00 am to 5.00 pm inclusive Monday to Friday,

- 8.00 am to 1.00 pm inclusive on Saturday,
- No work on Sundays and Public Holidays.

Demolition and excavation works are restricted to:

- 8.00 am to 5.00 pm Monday to Friday only.

(Excavation work includes the use of any excavation machinery and the use of jackhammers, rock breakers, excavators, loaders and the like, regardless of whether the activities disturb or alter the natural state of the existing ground stratum or are breaking up/removing materials from the site).

- (b) At all times after the submission the Notice of Commencement to Council, a copy of the Development Consent and Construction Certificate is to remain on site at all times until the issue of a final Occupation Certificate. The consent shall be available for the perusal of any Authorised Officer.
- (c) Where demolition works have been completed and new construction works have not commenced within 4 weeks of the completion of the demolition works that area affected by the demolition works shall be fully stabilised and the site must be maintained in a safe and clean state until such time as new construction works commence.
- (d) Onsite toilet facilities (being either connected to the sewer or an accredited sewer management facility) for workers are to be provided for construction sites at a rate of 1 per 20 persons.
- (e) Prior to the release of the Construction Certificate, payment of the Long Service Levy is required. This payment can be made at Council or to the Long Services Payments Corporation. Payment is not required where the value of the works is less than \$25,000. The Long Service Levy is calculated on 0.35% of the building and construction work. The levy rate and level in which it applies is subject to legislative change. The applicable fee at the time of payment of the Long Service Levy will apply.
- (f) The applicant shall bear the cost of all works associated with the development that occurs on the Council's property.
- (g) No building, demolition, excavation or material of any nature and no hoist, plant and machinery (crane, concrete pump or lift) shall be placed on Council's footpaths, roadways, parks or grass verges without Council Approval.
- (h) Demolition materials and builders' wastes are to be removed to approved waste/recycling centres.
- (i) No trees or native shrubs or understorey vegetation on public property (footpaths, roads, reserves, etc.) or on the land to be developed shall be removed or damaged during construction unless specifically approved in this consent including for the erection of any fences, hoardings or other temporary works.
- (j) Prior to the commencement of any development on site for:
 - i) Building/s that are to be erected
 - ii) Building/s that are situated in the immediate vicinity of a public place and is dangerous to persons or property on or in the public place
 - iii) Building/s that are to be demolished
 - iv) For any work/s that is to be carried out
 - v) For any work/s that is to be demolished

The person responsible for the development site is to erect or install on or around the development area such as temporary structures or appliances (wholly within the development site) as are necessary to protect persons or property and to prevent unauthorised access to the site in order for the land or premises to be maintained in a safe or healthy condition. Upon completion of the development, such temporary structures or appliances are to be removed within 7 days.

Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community. (DACPLB10)

FEES / CHARGES / CONTRIBUTIONS

5. Policy Controls

Northern Beaches Council Contributions Plan 2018

The proposal is subject to the application of Council's Section 7.12 Development Contributions Plan.

The following monetary contributions are applicable:

Northern Beaches Council Contributions Plan 2018		
Contribution based on a total development cost of \$ 45,144,636.00		
Contributions	Levy Rate	Payable
Total Section 7.12 Levy	0.95%	\$ 428,874.04
Section 7.12 Planning and Administration	0.05%	\$ 22,572.32
Total	1%	\$ 451,446.36

The amount will be adjusted at the time of payment according to the quarterly CPI (Sydney - All Groups Index). Please ensure that you provide details of this Consent when paying contributions so that they can be easily recalculated.

This fee must be paid prior to the issue of the Construction Certificate. Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To provide for contributions in accordance with Northern Beaches Council Contributions Plan 2018.

6. Security Bond

A bond (determined from cost of works) of \$10,000 and an inspection fee in accordance with Council's Fees and Charges paid as security to ensure the rectification of any damage that may occur to the Council infrastructure contained within the road reserve adjoining the site as a result of construction or the transportation of materials and equipment to and from the development site.

An inspection fee in accordance with Council adopted fees and charges (at the time of payment) is payable for each kerb inspection as determined by Council (minimum (1) one inspection).

All bonds and fees shall be deposited with Council prior to Construction Certificate or demolition work commencing, details demonstrating payment are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

To process the inspection fee and bond payment a Bond Lodgement Form must be completed with the payments (a copy of the form is attached to this consent and alternatively a copy is located on Council's website at www.northernbeaches.nsw.gov.au).

Reason: To ensure adequate protection of Council's infrastructure.

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE

7. On slab landscape planting and associated works (PLEP)

- Details shall be submitted to the Certifying Authority prior to the issue of the Construction Certificate indicating the proposed method of waterproofing to all internal walls and slab, and drainage of the concrete slab over which soil and planting is being provided.
- Landscape treatment details shall be submitted to the Certifying Authority prior to the issue of the Construction Certificate indicating the proposed soil volume, soil type, planting, automatic irrigation, services connections, and maintenance activity schedule.

c) The following soil depths are required in order to be counted as landscaping:

- 300mm for lawn
- 600mm for shrubs
- 1metre for trees

Reason: To ensure appropriate and secure waterproofing and drainage is installed to direct water flow into the drainage system, and away from habitable areas.

8. **Stormwater Disposal**

Stormwater shall be disposed of to an existing approved system or in accordance with Northern Beaches Council's [WARRINGAH WATER MANAGEMENT POLICY PL850,]

A certificate is to be provided to the Principal Certifying Authority with the Construction Certificate application by a qualified experienced practicing Civil Engineer, and has appropriate experience and competence in the related field that the existing approved system can accommodate the additional flows or provide drainage plans demonstrating compliance with Council's requirements.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority for approval prior to the issue of the Construction Certificate.

Reason: To ensure appropriate provision for disposal and stormwater management arising from development.

9. **Tanking of Basement Level**

The basement area is to be permanently tanked. Details of the tanking are to be prepared by a suitably qualified Engineer. Where temporary dewatering works are required on the development site during construction, the developer/applicant must apply for and obtain a bore license from the NSW Office of Water. The bore license must be obtained prior to commencement of dewatering works. All requirements of the NSW Office of Water are to be complied with and a copy of the approval must be submitted to the Principal Certifying Authority. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the Construction Certificate.

Reason: To prevent ingress of sub-surface flows into the basement area and to comply with State Government Requirements

10. **On-site Stormwater Detention**

An On-site Stormwater Detention system must be designed and constructed in accordance with Northern Beaches Council's current WARRINGAH WATER MANAGEMENT POLICY PL850.

Detailed drainage plans are to be prepared by a qualified experienced practicing Civil Engineer, with Corporate membership of the Institute of Engineers Australia (M.I.E.) or who is eligible to become a Corporate member and has appropriate experience and competence in the related field.

The drainage plans must address the required information as detailed in Councils "On Site Stormwater Detention technical specification" and additionally the following:

- i) The post development discharges are to be limited to pre developed state of nature flows up to the 100 year ARI storm event.
- ii) The stormwater outlet pipe from the OSD tank is to be directly connected to a stormwater inlet pit in Frenchs Forest road.
- iii) A DRAINS model is to be prepared to determine the On site detention storage volumes and discharges accordingly.

Detailed drainage plans ,a DRAINS model and engineering certification confirming the above requirements have been satisfied and complying with Council's requirements, are to be submitted to the Certifying Authority for approval prior to the issue of the Construction Certificate.

Reason: To ensure appropriate provision for the disposal of storm water and storm water management arising from the development.

11. **Structural Adequacy and Excavation Work**

Excavation work is to ensure the stability of the soil material of adjoining properties, the protection of

adjoining buildings, services, structures and / or public infrastructure from damage using underpinning, shoring, retaining walls and support where required. All retaining walls are to be structurally adequate for the intended purpose, designed and certified by a Structural Engineer, except where site conditions permit the following:

(a) maximum height of 900mm above or below ground level and at least 900mm from any property boundary, and

(b) Comply with AS3700, AS3600 and AS1170 and timber walls with AS1720 and AS1170.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the Construction Certificate.

Reason: To provide public and private safety.

12. **Vehicle Crossings Application**

A Driveway Levels and Formwork Inspections Application shall be made with Council subject to the payment of the fee in accordance with Council's Fees and Charges. The fee includes all Council inspections relating to the driveway construction and must be paid.

Approval of the application by Council is to be submitted to the Principal Certifying Authority prior to the issue of the Construction Certificate.

Reason: To facilitate suitable vehicular access to private property.

13. **Tree Protection Plan**

In order to protect and enhance onsite vegetation and trees the following applies to the development site:

(a) A Tree Protection Plan prepared by a AQF Level 5 Arborist (or equivalent) showing the following:

- Layout of the approved development
- Location of trees identified for retention
- Extent of canopy spread
- Location of tree protection fencing / barriers (fencing in accordance with AS2470 – 2009)
- General tree protection measures

(b) The Tree Protection Plan is to be submitted to the Principal Certifying Authority for approval prior to issue of a Construction Certificate.

(c) Tree protection measures identified on the plan are to be in place prior to commencement of works.

Reason: To ensure compliance with the requirement to retain and protect significant planting on the site. (DACLAC01)

14. **Amendments to the Landscape Plan**

a) Detailed Landscape Plans are to be prepared incorporating tree, shrub and ground cover plants to garden areas around the perimeter of the site.

b) Planting is to comprise local native species to be planted as a minimum at the following ratio:

- Groundcovers - 4 per m²
- Shrubs - 1 per m²
- Trees - 1 per 20m²

c) Details shall be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure the provision of suitable landscape amenity and character.

15. **Compliance with Standards**

The development is required to be carried out in accordance with all relevant Australian Standards.

(Note: At the time of determination the following (but not limited to) Australian Standards applied:

- (a) AS2601.2001 - Demolition of Structures**
- (b) AS4361.2 - Guide to lead paint management - Residential and commercial buildings**
- (c) AS4282:1997 Control of the Obtrusive Effects of Outdoor Lighting**
- (d) AS 4373 - 2007 'Pruning of amenity trees' (Note: if approval is granted) **
- (e) AS 4970 - 2009 'Protection of trees on development sites'***
- (f) AS/NZS 2890.1:2004 Parking facilities - Off-street car parking**
- (g) AS 2890.2 - 2002 Parking facilities - Off-street commercial vehicle facilities**
- (h) AS 2890.3 - 1993 Parking facilities - Bicycle parking facilities**
- (i) AS 2890.5 - 1993 Parking facilities - On-street parking**
- (j) AS/NZS 2890.6 - 2009 Parking facilities - Off-street parking for people with disabilities**
- (k) AS 1742 Set - 2010 Manual of uniform traffic control devices Set**
- (l) AS 1428.1 – 2009* Design for access and mobility - General requirements for access – New building work**
- (m) AS 1428.2 – 1992*, Design for access and mobility - Enhanced and additional requirements - Buildings and facilities**

*Note: The Australian Human Rights Commission provides useful information and a guide relating to building accessibility entitled "the good the bad and the ugly: Design and construction for access". This information is available on the Australian Human Rights Commission website [www.hreoc.gov.au/disability rights /buildings/good.htm](http://www.hreoc.gov.au/disability%20rights%20/buildings/good.htm).
<www.hreoc.gov.au/disability%20rights%20/buildings/good.htm>

**Note: the listed Australian Standards is not exhaustive and it is the responsibility of the applicant and the Certifying Authority to ensure compliance with this condition and that the relevant Australian Standards are adhered to.)

Details demonstrating compliance with the relevant Australian Standard are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure the development is constructed in accordance with appropriate standards.
(DACPLC02)

16. **Compliance with Standards**

The development is required to be carried out in accordance with all relevant Australian Standards.

Details demonstrating compliance with the relevant Australian Standard are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure the development is constructed in accordance with appropriate standards.
(DACPLC02)

17. **External Finishes to Roof**

The external finish to the roof shall have a medium to dark range in order to minimise solar reflections to neighbouring properties. Any roof with a metallic steel finish is not permitted.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure that excessive glare or reflectivity nuisance does not occur as a result of the development.

18. **Requirements for Seniors Housing or Housing for Persons with a Disability**

The development is for the purposes of Seniors Housing or Housing for Persons with a Disability and is required to comply with all the standards specified in Schedule 3 - "*Standards concerning accessibility and useability for hostels and self-contained dwellings*".

Details demonstrating compliance with the above requirement are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure public safety and equitable access for seniors or people with a disability.
(DACPLC16)

19. **Construction Traffic Management Plan**

As a result of the site constraints, limited vehicle access and parking, a Construction Traffic Management Plan (CTMP) and report shall be prepared by an RMS accredited person and submitted to and approved by the Certifying Authority prior to issue of any Construction Certificate.

Due to heavy traffic congestion throughout the town centre, truck movements will be restricted during the major commuter peak times being 8.00-9.30am and 4.30-6.00pm. Truck movements must be agreed with Council's Traffic and Development Engineer prior to submission of the CTMP.

The CTMP must address following:-

- The proposed phases of construction works on the site, and the expected duration of each construction phase;
- The proposed order in which works on the site will be undertaken, and the method statements on how various stages of construction will be undertaken;
- Make provision for all construction materials to be stored on site, at all times;
- The proposed areas within the site to be used for the storage of excavated materials, construction materials and waste containers during the construction period;
- The proposed method of access to and egress from the site for construction vehicles, including access routes and truck routes through the Council area and the location and type of temporary vehicular crossing for the purpose of minimising traffic congestion and noise in the area, with no access across public parks or reserves being allowed;
- The proposed method of loading and unloading excavation and construction machinery, excavation and building materials, formwork and the erection of any part of the structure within the site. Wherever possible mobile cranes should be located wholly within the site;
- Make provision for parking onsite. All Staff and Contractors are to use the basement parking once available.
- Temporary truck standing/ queuing locations in a public roadway/ domain in the vicinity of the site are not permitted unless approved by Council prior.
- Include a Traffic Control Plan prepared by a person with suitable RMS accreditation for any activities involving the management of vehicle and pedestrian traffic.
- The proposed manner in which adjoining property owners will be kept advised of the timeframes for completion of each phase of development/construction process. It must also specify that a minimum Fourteen (14) days notification must be provided to adjoining property owners prior to the implementation of any temporary traffic control measure.
- Include a site plan showing the location of any site sheds, location of requested Work Zones, anticipated use of cranes and concrete pumps, structures proposed on the footpath areas (hoardings, scaffolding or shoring) and any tree protection zones around Council street trees.
- Take into consideration the combined construction activities of other development in the surrounding area. To this end, the consultant preparing the CTMP must engage and consult with developers undertaking major development works within a 250m radius of the subject site to ensure that appropriate measures are in place to prevent the combined impact of construction activities, such as (but not limited to) concrete pours, crane lifts and dump truck routes. These communications must be documented and submitted to Council prior to work commencing on site.
- The proposed method/device to remove loose material from all vehicles and/or machinery before entering the road reserve, any run-off from the washing down of vehicles shall be directed to the sediment control system within the site;
- Specify that the roadway (including footpath) must be kept in a serviceable condition for the duration of construction. At the direction of Council, undertake remedial treatments such as patching at no cost to Council.
- The proposed method of support to any excavation adjacent to adjoining properties, or the road reserve. The proposed method of support is to be designed and certified by an appropriately qualified and practising Structural Engineer, or equivalent;
- Proposed protection for Council and adjoining properties;
- The location and operation of any on site crane; and
- The CTMP shall be prepared in accordance with relevant sections of Australian Standard 1742 – "Manual of Uniform Traffic Control Devices", RMS' Manual – "Traffic Control at Work Sites".

All fees and charges associated with the review of this plan is to be in accordance with Council's Schedule of Fees and Charges and are to be paid at the time that the Construction Traffic Management Plan is submitted.

Reason: To ensure public safety and minimise any impacts to the adjoining pedestrian and vehicular traffic systems. Confirming appropriate measures have been considered for site access, storage and the operation of the site during all phases of the construction process in a manner that respects adjoining owner's property rights and protects amenity in the locality, without unreasonable inconvenience to the community. The CTMP is intended to minimise impact of construction activities on the surrounding community, in terms of vehicle traffic (including traffic flow and parking) and pedestrian amenity adjacent to the site.

20. Porte-Cochere Design

The porte-cochere shall be designed to accommodate the turning path of a Council standard waste vehicle. The applicant is to prepare a plan demonstrating that Council's Waste Vehicle can enter and exit the porte-cochere in a forward direction. the plan shall be submitted to and approved by Council prior to the issue of any Construction Certificate.

Reason: To ensure trucks can service the site, entering and leaving in a forward direction.

21. Waste and Recycling Requirements

Details demonstrating compliance with Northern Beaches Council Waste Management Guidelines, including the required Northern Beaches Council Waste Management Plan, are to be submitted to and approved by the Certifying Authority prior to the issue of any Construction Certificate.

Note: If the proposal, when compliant with Northern Beaches Council Waste Management Guidelines, causes inconsistencies with other parts of the approval i.e. architectural or landscaped plans a modification(s) to the development may be required.

Reason: To ensure adequate and appropriate waste and recycling facilities are provided.
(DACWTC01)

CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT

22. Tree trunk, branch and root protection

(a) Existing trees which must be retained

- i) All trees not indicated for removal on the approved plans, unless exempt under relevant planning instruments or legislation
- ii) Trees located on adjoining land

(b) Tree protection

- i) No tree roots greater than 25mm diameter are to be cut from protected trees unless authorised by the Project Arborist on site.
- ii) All structures are to bridge tree roots greater than 25mm diameter unless directed otherwise by the Project Arborist on site.
- iii) All tree protection to be in accordance with the Arboricultural Impact Appraisal and Method Statement (Revision B) dated 21 May 2018 prepared by Naturally Trees and AS4970-2009 Protection of trees on development sites, with particular reference to Section 4 Tree Protection Measures.
- iv) All tree pruning within the subject site is to be in accordance with WDCP2011 Clause E1 Private Property Tree Management and AS 4373 Pruning of amenity trees
- v) All tree protection measures, including fencing, are to be in place prior to commencement of works.

Reason: To ensure compliance with the requirement to retain and protect significant planting on the site.

23. Project Arborist

- i) A Project Arborist with minimum qualification AQF Level 5 is to be appointed prior to commencement of works.
- ii) The Project Arborist is to oversee all tree protection measures, removals and works adjacent to protected trees as outlined in the Arboricultural Appraisal and Method Statement (Revision B) dated 21 May 2018 prepared by Naturally Trees and AS4970-2009 Protection of trees on development sites.
- iii) The Project Arborist is to ensure compliance as relevant with any other environmental requirements conditioned under this consent.

Reason: Environmental protection (DACLADPC1)

CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK**24. Road Reserve**

The public footways and roadways adjacent to the site shall be maintained in a safe condition at all times during the course of the work.

Reason: Public Safety.

25. Traffic Control During Road Works

Lighting, fencing, traffic control and advanced warning signs shall be provided for the protection of the works and for the safety and convenience of the public and others in accordance with RMS Traffic Control At Work Sites Manual (<http://www.rms.nsw.gov.au/business-industry/partners-suppliers/documents/technical-manuals/tcws-version-4/tcwsv4i2.pdf>) and to the satisfaction of the Principal Certifying Authority. Traffic movement in both directions on public roads, and vehicular access to private properties is to be maintained at all times during the works

Reason: Public Safety

26. Vehicle Crossings

The provision of one vehicle crossing 7 metres wide in accordance with Northern Beaches Council Drawing No A4-3330/ normal and specifications. An Authorised Vehicle Crossing Contractor shall construct the vehicle crossing and associated works within the road reserve in plain concrete. All redundant laybacks and crossings are to be restored to footpath/grass. Prior to the pouring of concrete, the vehicle crossing is to be inspected by Council and a satisfactory "Vehicle Crossing Inspection" card issued.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To facilitate suitable vehicular access to private property.

27. Maintenance of Road Reserve

The public footways and roadways adjacent to the site shall be maintained in a safe condition at all times during the course of the work.

Reason: Public Safety.

28. Temporary Sediment

Temporary sedimentation and erosion controls are to be constructed prior to commencement of any work to eliminate the discharge of sediment from the site.

Reason: To reduce erosion and prevent sediment runoff into public assets

29. Maintenance of Sediment

Sedimentation and erosion controls are to be effectively maintained at all times during the course of construction and shall not be removed until the site has been stabilised or landscaped to the Principal Certifying Authority's satisfaction.

Reason: To ensure sediment controls are effective

30. Site Entry Access way

An all-weather access way at the front of the property consisting of 50-75mm aggregate or similar material at a minimum thickness of 200mm and 15metres long laid over geotechnical fabric is to be constructed prior to commencement of works and maintenance over the works period.

Reason: To reduce sediment being taken offsite

31. Waste Management During Development

The reuse, recycling or disposal of waste during works must be done generally in accordance with the Waste Management Plan for this development.

Details demonstrating compliance must be submitted to the Principal Certifying Authority.

Reason: To ensure demolition and construction waste is recycled or reused and to limit landfill.

32. Requirement to Notify about New Contamination Evidence

Any new information revealed during demolition and excavation works that has the potential to alter previous conclusions about site contamination or hazardous materials shall be immediately notified to the Council and the Principal Certifying Authority. Management Plans will then be required for material disposal and remediation

Reason: To protect human health and the environment. (DACHPE01)

33. Excavation and Building Work Noise

Findings and recommendations for design of the Acoustic Report by Wood Grieve Engineers 17 May 2018 being implemented during excavation and construction.

Best practice noise minimisation processes being used in excavation related works

Reason: To ensure excavation and construction noise is minimised to adjoining business and residences.

34. Acid Sulfate Soil Management

Any new information which comes to light during excavation or construction works which has the potential to alter previous conclusions about the uncovering of Acid Sulfate Soil must be notified to the Certifier as soon as reasonably practicable. This will also require an Acid Sulfate Soil Management Plan, including disposal of affected soil to an approved facility, to be submitted to the certifier, before work continues.

Reason: To ensure potential Acid Sulfate Soil is appropriately managed

35. Installation and Maintenance of Sediment Control

Measures used for erosion and sediment control on building sites are to be adequately maintained at all times and must be installed in accordance with Council's Specifications for Erosion and Sediment Control. All measures shall remain in proper operation until all development activities have been completed and the site fully stabilised.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To protect the environment from the effects of sedimentation and erosion from development sites.

36. Waste/Recycling Requirements (Waste Plan Submitted)

During demolition and/or construction the proposal/works shall be generally consistent with the submitted Waste Management Plan

Reason: To ensure waste is minimised and adequate and appropriate waste and recycling facilities are provided. (DACWTE01)

CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

37. **Condition of retained vegetation**

Prior to the issue of an Occupation Certificate, a report prepared by an AQF Level 5 Arborist (or equivalent), shall be submitted to the Certifying Authority, assessing the health and impact of trees and vegetation required to be retained as a result of the proposed development, including the following information:

- a) Compliance to Arborist recommendations for tree protection and excavation works.
- b) Extent of damage sustained by vegetation as a result of the construction works.
- c) Any subsequent remedial works required to ensure the long term retention of the vegetation.

Reason: To ensure compliance with the requirement to retain and protect significant planting on development sites, and protect the existing amenity that trees and/or bushland vegetation provide.

38. **Mechanical Ventilation certification**

Prior to the issuing of any final occupation certificate, certification is to be provided from the installer of the mechanical ventilation system that the design, construction and installation of the mechanical ventilation system is compliant with the requirements of AS1668, 'The use of mechanical ventilation'.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To ensure that the mechanical ventilation system complies with the design requirements and National Construction Code.

39. **Authorisation of Legal Documentation Required for Onsite Detention**

The original completed request forms (NSW Land Registry standard forms 13PC and/or 13RPA) must be submitted to Council, with a copy of the Works-as-Executed plan (details overdrawn on a copy of the approved drainage plan), hydraulic engineers certification and Compliance Certificate issued by an Accredited Certifier in Civil Works. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To create encumbrances on the land.

40. **Reinstatement of Kerb**

All redundant laybacks and vehicular crossings shall be reinstated to conventional kerb and gutter, footpath or grassed verge as appropriate with all costs borne by the applicant. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To facilitate the preservation of on street parking spaces

41. **Restriction as to User for On-site Stormwater Detention**

A restriction as to user shall be created on the title over the on-site stormwater detention system, restricting any alteration to the levels and/or any construction on the land. The terms of such restriction are to be prepared to Council's standard requirements, (available from Northern Beaches Council), at the applicant's expense and endorsed by Council prior to lodgement with the Department of Lands. Northern Beaches Council shall be nominated as the party to release, vary or modify such restriction.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure modification to the on-site stormwater detention structure is not carried without

Council's approval. (DACENF04)

42. On-Site Stormwater Detention Compliance Certification

Upon completion of the on-site stormwater detention (OSD) system, certification from a consulting engineer and a "work as executed" (WAE) drawing certified by a registered surveyor and overdrawn in red on a copy of the approved OSD system plans are to be provided to Council. Additionally a Compliance Certificate is to be issued by an Accredited Certifier in Civil Works registered with the Institute of Engineers Australia, stating that the works are in accordance with the approved plans.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure stormwater disposal is constructed to Council's satisfaction. (DACENF10)

43. Positive Covenant and Restriction as to User for On-site Stormwater Detention

A positive covenant shall be created on the title of the land requiring the proprietor of the land to maintain the on-site stormwater detention structure in accordance with the standard requirements of Council. The terms of the positive covenant are to be prepared to Council's standard requirements at the applicant's expense and endorsed by Northern Beaches Council's delegate prior to lodgement with NSW Land Registry Services. Northern Beaches Council shall be nominated as the party to release, vary or modify such covenant.

A restriction as to user shall be created on the title over the on-site stormwater detention system, restricting any alteration to the levels and/or any construction on the land. The terms of such restriction are to be prepared to Council's standard requirements at the applicant's expense and endorsed by Council prior to lodgement with NSW Land Registry Services. Northern Beaches Council shall be nominated as the party to release, vary or modify such restriction.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure the on-site detention and/or pump system is maintained to an appropriate operational standard.

44. Creation of Positive Covenant and Restriction as a User

A restriction on the use of land and a positive covenant shall be created on the title of the land in respect of the installation and maintenance of on-site stormwater disposal structures. The detailed information for a restriction on the use of land and a positive covenant is shown in Northern Beaches Council's WARRINGAH WATER MANAGEMENT POLICY PL850, The terms of the positive covenant and a Restriction on the use of land are to be prepared to Council's standard requirements, at the applicant's expense and endorsed by Northern Beaches Council's delegate prior to lodgement with the Department of Lands. Northern Beaches Council shall be nominated as the party to release, vary or modify such covenant.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any final Occupation Certificate.

Reason: To ensure the on-site detention and/or pump system is maintained to an appropriate operational standard

45. Post-Construction Road Reserve Dilapidation Report

The applicant must bear the cost of all restoration works to Council's property damaged during the course of this development. All building work must have been carried out in accordance with the provisions of the Building Code of Australia

Note: Where by Council is not the Principal Certifying Authority, Refund of the trust fund deposit will also be dependent upon receipt of a final Occupation Certificate by the Principal Certifying Authority, Post Construction Dilapidation Report and infrastructure inspection by Council.

Reason: To ensure security against possible damage to Council property.

46. Restoration of Damaged Public Infrastructure

Restoration of all damaged public infrastructure caused as a result of the development to Council's satisfaction. Council's written approval that all restorations have been completed satisfactorily must be obtained and provided to the Private Certifying Authority with the Occupation Certificate application.

Reason: To ensure public infrastructure is returned to the state it was in prior to development

47. Kitchen Design, construction and fit out of food premises certification

Prior to the issuing of any interim / final occupation certificate, certification is to be provided from a person who is suitably qualified that the design, construction and fit out of food premises kitchen is compliant with the requirements of AS 4674 Design, construction and fit out of food premises.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To ensure that the kitchen complies with the design requirements. (DACHPFPOC3)

48. Mechanical Ventilation certification

Prior to the issuing of any interim / final occupation certificate, certification is to be provided from the installer of the mechanical ventilation system that the design, construction and installation of the mechanical ventilation system is compliant with the requirements of AS1668 The use of mechanical ventilation.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To ensure that the mechanical ventilation system complies with the design requirements. (DACHPFPOC4)

49. Noise Reduction Measures

Findings and recommendations for design of the Acoustic Report by Wood Grieve Engineers 17 May 2018 being implemented before construction commences..

The Acoustic report being reviewed to incorporate any implications of the amended approval issued by the Land and Environment Court 18.1.2019 and allowance being calculated for noise of overnight waste removal services, including reversing alarms, of neighbouring industrial premises. A copy being supplied to Council for its records.

Reason: To ensure design allows for reasonable site use of adjoining industrial premises does not interfere with the amenity of residents of this Development

50. Certification of Noise reduction measures prior to occupation

Prior to occupation a suitably qualified person shall certify that the recommendations of the Acoustic Report by Wood Grieve Engineers 17 May 2018 have been implemented including amendments required by conditions of this approval for allowance being calculated for noise of overnight waste removal services, including reversing alarms, of neighbouring industrial premises. A copy being supplied to Council for its records.

Reason: To ensure noise assessment and recommendations have been implemented and are adequate in reducing noise nuisance to residential occupiers.

51. Removal of All Temporary Structures/Material and Construction Rubbish

Once construction has been completed all silt and sediment fences, silt, rubbish, building debris, straw bales and temporary fences are to be removed from the site.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure bushland management. (DACPLF01)

52. Garbage and Recycling Facilities

All internal walls of the storage area shall be rendered to a smooth surface, coved at the floor/wall intersection, graded and appropriately drained to the sewer with a tap in close proximity to facilitate cleaning.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To prevent pollution of the environment and to protect the amenity of the area.(DACPLF03)

53. Garbage and Recycling Facilities

All internal walls of the storage area shall be rendered to a smooth surface, coved at the floor/wall intersection, graded and appropriately drained to the sewer with a tap in close proximity to facilitate cleaning.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To prevent pollution of the environment and to protect the amenity of the area.(DACPLF03)

54. Sydney Water

A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained from Sydney Water Corporation.

Application must be made through an authorised Water Servicing Co-ordinator. Please refer to the Building Developing and Plumbing section of the web site www.sydneywater.com.au <<http://www.sydneywater.com.au>> then refer to "Water Servicing Coordinator" under "Developing Your Land" or telephone 13 20 92 for assistance.

Following application a "Notice of Requirements" will advise of water and sewer infrastructure to be built and charges to be paid. Please make early contact with the Co-ordinator, since building of water/sewer infrastructure can be time consuming and may impact on other services and building, driveway or landscape design.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure compliance with the statutory requirements of Sydney Water. (DACPLF08)

55. Occupation of Seniors Housing or Housing for Persons with a Disability

A positive covenant pursuant to s88E of the Conveyancing Act 1919 is to be registered on the title of the land to which this development consent applies.

The covenant shall stipulate that Council is the sole authority to release or modify the covenant and that the development is only permitted to be occupied by persons detailed as follows:

- (a) seniors or people who have a disability;
- (b) people who live within the same household with seniors or people who have a disability;
- (c) staff employed to assist in the administration of and provision of services to housing provided under this Policy.

(Note: Under State Environmental Planning Policy (Housing for Seniors or People with a Disability 2004):

Seniors are people aged 55 or more years, people who are resident at a facility at which residential care (within the meaning of the Aged Care Act 1997 <http://www.comlaw.gov.au/> of the Commonwealth) is provided and/or people who have been assessed as being eligible to occupy housing for aged persons provided by a social housing provider.

AND

People with a disability are people of any age who have, either permanently or for an extended period, one or more impairments, limitations or activity restrictions that substantially affect their capacity to participate in everyday life.)

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue any Interim / Final Occupation Certificate.

Reason: Statutory requirements. (DACPLF11)

56. Certification of completion of requirements for Seniors Housing or Housing for Persons with a Disability

Details demonstrating that all stipulated requirements of this development consent for Seniors Housing or Housing for Persons with a Disability have been completed.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure statutory requirements have been completed, public safety, and equitable access for seniors of people with a disability. (DACPLF12)

57. Fire Safety Matters

At the completion of all works, a Fire Safety Certificate will need to be prepared which references all the Essential Fire Safety Measures applicable and the relative standards of Performance (as per Schedule of Fire Safety Measures). This certificate must be prominently displayed in the building and copies must be sent to Council and Fire and Rescue NSW.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Interim / Final Occupation Certificate.

Each year the Owners must send to the Council and Fire and Rescue NSW, an annual Fire Safety Statement which confirms that all the Essential Fire Safety Measures continue to perform to the original design standard.

Reason: Statutory requirement under Part 9 Division 4 & 5 of the Environmental Planning and Assessment Regulation 2000. (DACPLF07)

58. Parking Space Allocations

The 2 parking spaces in the porte-cochere shall be allocated for delivery/waste collection services. The applicant is to prepare a plan detailing the required signage to restrict the use of these spaces. the plan is to be submitted to and approved by Council prior to the issue of any Occupation Certificate.

Reason: To ensure safe servicing of the site can occur wholly within the site.

59. Waste and Recycling Facilities Certificate of Compliance

The proposal shall be constructed in accordance with Northern Beaches Council's Waste Management Guidelines

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure waste and recycling facilities are provided. (DACWTF01)

60. Waste/Recycling Compliance Documentation

Evidence of disposal for recycling from the construction/demolition works shall be submitted to the Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure waste is minimised and recycled. (DACWTF02)

61. Positive Covenant for Waste Services

A positive covenant shall be created on the title of the land requiring the proprietor of the land to provide access to the waste storage facilities prior to the issue of an Interim/Final Occupation

Certificate. The terms of the positive covenant are to be prepared to Council's standard requirements, (available from Warringah Council), at the applicant's expense and endorsed by Council prior to lodgement with the Department of Lands. Warringah Council shall be nominated as the party to release, vary or modify such covenant.

Reason: To ensure ongoing access for servicing of waste facilities (DACWTF03)

62. Authorisation of Legal Documentation Required for Waste Services

The original completed request form (Department of Lands standard form 13PC) must be submitted to Council for authorisation prior to the issue of the Interim/Final Occupation Certificate. A copy of the work-as-executed plan (details overdrawn on a copy of the approved plan) must be included with the above submission. Where required by Council or the Certifying Authority, a Compliance Certificate shall also be provided in the submission to Council.

If Council is to issue the Compliance Certificate for these works, the fee is to be in accordance with Council's Fees and Charges.

Reason: To create encumbrances on the land. (DACWTF04)

ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES

63. Environmental and priority weed control

Condition: All weeds are to be removed and controlled in accordance with the Biodiversity Conservation Act 2016.

Reason: Preservation of environmental amenity.

64. Landscape maintenance

- i) Trees shrubs and groundcovers required to be planted under this consent are to be mulched, watered and fertilized as required at the time of planting.
- ii) If any tree, shrub or groundcover required to be planted under this consent fails, they are to be replaced with similar species to maintain the landscape theme and be generally in accordance with the approved Landscape Plan.

Reason: To maintain local environmental amenity

65. Visitors Sign

A sign, legible from the street, shall be permanently displayed to indicate that visitor parking is available on the site and the visitor car parking spaces shall be clearly marked as such.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure that visitors are aware that parking is available on site and to identify those spaces to visitors. (DACPLG04)

66. Hours of Operation

The hours of operation for commercial/cafe premises are to be restricted to:

- Monday to Friday – 7 am - 7 pm
- Saturday – 8am - 5 pm
- Sunday and Public Holidays – Closed

Upon expiration of the permitted hours, all service (and entertainment) shall immediately cease, no patrons shall be permitted entry and all customers on the premises shall be required to leave within the following 30 minutes.

Reason: Information to ensure that amenity of the surrounding locality is maintained. (DACPLG08)

67. Commercial Waste Collection (DACPLG18)

Waste and recyclable material, generated by this premises, must not be collected between the hours of 10 pm and 6 am on any day.

Reason: To protect the acoustic amenity of surrounding properties.(DACPLG18)

68. Commercial Waste and Recycling Storage

Commercial waste and recycling material/storage bins must be stored in a separate area to the residential waste and recycling material/storage bins as shown on the approved plans.

Reason: To ensure that commercial waste and residential waste is not mixed and is properly managed. (DACPLG19)

69. Loading and Unloading

All loading and unloading of vehicles and the delivery of goods must be carried out wholly within the site.

Reason: To ensure that deliveries can occur safely within the site and does not adversely affect traffic or pedestrian safety and amenity. (DACPLG20)

70. Commercial Waste and Recycling Storage

Commercial waste and recycling material/storage bins must be stored in a separate area to the residential waste and recycling material/storage bins.

Reason: To ensure that commercial waste and residential waste is not mixed and is properly managed. (DACPLG25)

CONDITIONS THAT MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF ANY STRATA SUBDIVISION OR SUBDIVISION CERTIFICATE

71. Provision of Services for Subdivision

The applicant is to ensure all services including, water, electricity, telephone and gas are provided, located and certified by a registered surveyor on a copy of the final plan. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the Subdivision Certificate.

Reason: To ensure that utility services have been provided to the newly created lots

72. Services

All utilities/services and street lighting is to be installed by the applicant/developer. Certification is to be provided to Council stating the above requirement has been complied with. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the Subdivision Certificate.

Reason: Public safety and to ensure services have been provided for the newly created lots

73. Stormwater Drainage and Utility Services Plan

A plan of subdivision identifying the location of water, gas, telephone, electricity and stormwater drainage in relation to boundaries and/or relevant easements, prepared by a registered surveyor is to be submitted to Council. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the Subdivision Certificate.

Reason: To ensure that services have been provided with appropriate easements as required by the Conveyancing Act 1919

74. Survey Plan - Construction Identification

A declaration by a registered surveyor shall be provided to Council as evidence that all construction has been effected within the appropriate property, easement boundaries and rights of carriageway. This shall be in the form of a copy of the final subdivision or easement plan, with the distances from the boundaries to the edges of these structures endorsed in red thereon and signed by the surveyor. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the

issue of the Subdivision Certificate.

Reason: To ensure accurate location of buildings, access and services

75. Sydney Water Compliance Certification

A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained from Sydney Water Corporation. Application must be made through an authorised Water Servicing Co-ordinator. Please refer to the Building Developing and Plumbing section of the web site www.sydneywater.com.au <<http://www.sydneywater.com.au>> then refer to "Water Servicing Coordinator" under "Developing Your Land" or telephone 13 20 92 for assistance. Following application a "Notice of Requirements" will advise of water and sewer infrastructure to be built and charges to be paid. Please make early contact with the Co-ordinator, since building of water/sewer infrastructure can be time consuming and may impact on other services and building, driveway or landscape design. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the Subdivision Certificate.

Reason: To ensure compliance with the statutory requirements of Sydney Water

76. Easement for Drainage

An easement for drainage (under the provisions of Section 88B of the Conveyancing Act) is to be created on the final plan of subdivision the accompanying 88B instrument to ensure all drainage infrastructure is located within the appropriate easement(s). Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the Subdivision Certificate.

Reason: Council's Subdivision standards and statutory requirements of the Conveyancing Act 1919

77. Subdivision Certificate Application

Prior to the issue of the Subdivision Certificate, a completed Subdivision Certificate form, a final plan of subdivision prepared in accordance with the requirements of the Conveyancing Act 1919 are to be submitted to Council. Nine copies of the final plan of subdivision are to be submitted. All plans of survey are to show connections to at least two Survey Co-ordination Permanent Marks. The fee payable is to be in accordance with Council's fees and charges

Reason: Statutory requirement of the Conveyancing Act 1919

78. Restoration of Damaged Public Infrastructure

Restoration of all damaged public infrastructure caused as a result of the development to Council's satisfaction. Council's written approval that all restorations have been completed satisfactorily must be obtained and provided to the Private Certifying Authority with the Occupation Certificate application.

Reason: To ensure public infrastructure is returned to the state it was in prior to development.