RAYMOND TERRACE BOWLING CLUB

2 JACARANDA AVENUE, RAYMOND TERRACE, NSW, 2324 DA CIVIL ENGINEERING PACKAGE





LOCALITY PLAN

DRAWING LIST

DRAWING No. DRAWING TITLE


COVER SHEET LOCALITY PLAN AND DRAWING LIST CONCEPT EROSION AND SEDIMENT CONTROL PLAN DA-C02.12 CONCEPT EROSION AND SEDIMENT CONTROL DETAILS DA-C04.11 CONCEPT CIVIL WORKS PLAN - STAGE 1 AND 2 DA-C04.12 CONCEPT CIVIL WORKS PLAN - STAGE 3

NOT FOR CONSTRUCTION

A ISSUED FOR CLIENT REVIEW RS 31.10.23 1 ISSUED FOR DEVLOPMENT APPLICATION JR AB RS 27.11.23

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED

THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD





Ph (02) 4943 1777 Email newcastle@northrop.com.au

ABN 81 094 433 100

RAYMOND TERRACE BOWLING CLUB 2 JACARANDA AVENUE, RAYMOND

TERRACE, NSW, 2324


CIVIL ENGINEERING PACKAGE

COVER SHEET, LOCALITY PLAN AND DRAWING LIST

NL231087 DRAWING NUMBER

DA-C01.01 DRAWING SHEET SIZE = A1

REVISION DESCRIPTION



GENERAL NOTES

- THE CONTRACTOR SHALL PROVIDE BARRIER / PERSON PROOF FENCE TO THE SITE / THEIR COMPOUND TO ENSURE THE SITE IS MADE SAFE TO THE PUBLIC FOR THE DURATION OF CONSTRUCTION.
- THE SEDIMENT AND EROSION CONTROL MEASURES SHOWN ON THIS PLAN ARE GENERAL SITE MEASURES. ADDITIONAL MEASURES MAY BE REQUIRED AROUND INDIVIDUAL BUILDING ZONES DEPENDENT ON THE SEQUENCE OF CONSTRUCTION.

EROSION AND SEDIMENT CONTROL NOTES

- 1. ALL EROSION AND SEDIMENTATION CONTROL MEASURES MUST BE APPROPRIATE FOR THE SEDIMENT TYPE(S) OF THE SOILS ON-SITE, IN ACCORDANCE WITH THE 'BLUE BOOK' (MANAGING URBAN STORMWATER SOILS AND CONSTRUCTION. LANDCOM, 2004), OR OTHER CURRENT RECOGNISED INDUSTRY STANDARDS FOR EROSION AND SEDIMENT CONTROL FOR AUSTRALIAN CONDITIONS. THIS INCLUDES SEDIMENT TRAPS AND LINING OF CHANNELS.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING A DETAILED WRITTEN RECORD OF ALL EROSION AND SEDIMENT CONTROLS ON-SITE DURING THE CONSTRUCTION PERIOD. THIS RECORD SHALL BE UPDATED ON A DAILY BASIS AND SHALL CONTAIN DETAILS ON THE CONDITION OF CONTROLS AND ANY/ALL MAINTENANCE, CLEANING AND BREACHES. THIS RECORD SHALL BE KEPT ON-SITE AT ALL TIMES AND SHALL BE MADE AVAILABLE FOR INSPECTION BY THE PRINCIPAL CERTIFYING AUTHORITY AND THE SUPERINTENDENT DURING NORMAL WORKING HOURS.
- 3. INSTALL SEDIMENT PROTECTION FILTERS ON ALL NEW AND EXISTING STORMWATER INLET PITS IN ACCORDANCE WITH EITHER THE MESH AND GRAVEL INLET FILTER DETAIL SD6-11 OR THE GEOTEXTILE INLET FILTER DETAIL SD6-12 OF THE 'BLUE BOOK'.
- 4. ESTABLISH ALL REQUIRED SEDIMENT FENCES IN ACCORDANCE WITH DETAIL SD6-8 OF THE 'BLUE BOOK'.
- 5. INSTALL SEDIMENT FENCING, OR OTHER SEDIMENT CONTROL DEVICES, AROUND INDIVIDUAL BUILDING ZONES / AREAS AS REQUIRED AND AS DIRECTED BY THE SUPERINTENDENT OR APPROPRIATE COUNCIL OFFICER.
- 6. ALL TRENCHES INCLUDING ALL SERVICE TRENCHES AND SWALE EXCAVATION SHALL BE SIDE-CAST TO THE HIGH SIDE AND CLOSED AT THE END OF EACH DAYS WORK.
- 7. THE CONTRACTOR SHALL ENSURE THAT ALL VEGETATION (TREE, SHRUB AND GROUND COVER) WHICH IS TO BE RETAINED SHALL BE PROTECTED DURING THE DURATION OF CONSTRUCTION.
- 8. ALL VEGETATION TO BE REMOVED SHALL BE MULCHED ON-SITE AND SPREAD / STOCKPILED AS DIRECTED BY THE SUPERINTENDENT.
- 9. STRIP TOPSOIL IN AREAS DESIGNATED FOR STRIPPING AND STOCKPILE FOR RE-USE AS REQUIRED. ANY SURPLUS MATERIAL SHALL BE SPREAD ON-SITE AS DIRECTED BY THE SUPERINTENDENT OR REMOVED FROM SITE AND DISPOSED OF IN ACCORDANCE WITH EPA GUIDELINES.
- 10. CONSTRUCT AND MAINTAIN ALL MATERIAL STOCKPILES IN ACCORDANCE WITH DETAIL SD4-1 OF THE 'BLUE BOOK' (INCLUDING CUT-OFF SWALES TO THE HIGH SIDE AND SEDIMENT FENCES TO THE LOW SIDE).
- 11. ENSURE STOCKPILES DO NOT EXCEED 2.0m HIGH. PROVIDE WIND AND RAIN EROSION PROTECTION AS REQUIRED IN ACCORDANCE WITH THE 'BLUE BOOK'.
- 12. PROVIDE WATER TRUCKS OR SPRINKLER DEVICES DURING CONSTRUCTION AS REQUIRED TO SUPPRESS DUST.
- 13. ONCE CUT / FILL OPERATIONS HAVE BEEN FINALISED ALL DISTURBED AREAS THAT ARE NOT BEING WORKED ON SHALL BE RE-VEGETATED AS SOON AS IS PRACTICAL.

NOT FOR CONSTRUCTION

REVISION DESCRIPTION ISSUED VER'D APP'D DATE
A ISSUED FOR CLIENT REVIEW JR RS 31.10.23
1 ISSUED FOR DEVLOPMENT APPLICATION JR AB RS 27.11.23

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED NORTHRIBE 27.11.2023 S02 PM PIONE By: JAMES RYALL Found: Vine-right job_files 11/YEAR 2023 JobinNL231087 - Raymord Terrace Bowing Clubio - DrawingsICVIL-103-CADIDANNL231087_DA-CO2.11 ESC. dwg

INSTALL AND MAINTAIN SEDIMENT FENCE TO

DOWNSTREAM SIDE OF DISTURBED WORKS.

INDICATIVE LOCATION OF STOCKPILE.

WITH THE APPROPRIATE COUNCIL


EXACT LOCATION/S TO BE DETERMINED

REPRESENTATIVE TO AVOID DAMAGING

VEGETATION WHICH IS TO BE RETAINED.

DURING CONSTRUCTION IN CONSULTATION

EJE architecture



INSTALL AND MAINTAIN SEDIMENT FILTERS AND TRAPS



TEMPORARY CONTRACTORS VEHICULAR ACCESS POINT. PROVIDE A SHAKEDOWN CATTLE GRID OR STABILISED

SITE ACCESS TO SD6-14 OF THE 'BLUE BOOK'.

Newcastle
Level 1, 215 Pacific Hwy, Charlestown NSW 2290
(02) 4943 1777 Email newcastle@northrop.com.au
ABN 81 094 433 100

RAYMOND TERRACE BOWLING CLUB
2 JACARANDA AVENUE, RAYMOND

TERRACE, NSW, 2324 CONCEPT EROS

CIVIL ENGINEERING PACKAGE

CONCEPT EROSION AND SEDIMENT CONTROL PLAN

JOB NUMBER **NL231087**

DRAWING NUMBER
DA-C02.11

DRAWING SHEET SIZE = A1

THE COPYRIGHT OF THIS DRAWING REMAINS WITH
NORTHROP CONSULTING ENGINEERS PTY LTD


SCALE 1:400@ A1

Ph (02) 4943 1777 Email newcastle@northrop.com.au
ABN 81 094 433 100

SITE PARAMETERS				
CONSTRAINT	VALUE			
SEDIMENT TYPE	D/F (MILLERS FOREST SOIL LANDSCAPE)			
SOIL HYDROLOGY GROUP	С			
K = SOIL ERODIBILITY (K-FACTOR)	0.025			
R = RAINFALL EROSIVITY (R-FACTOR)	2500			
S = 2 YEAR, 6 HOUR STORM INTENSITY	10.7mm/hr			
LS = SLOPE LENGTH/GRADIENT	0.5 (45m SLOPE @ 3% GRADE)			
P = EROSION CONTROL PRACTICE (P-FACTOR)	1.3 (TYPICAL)			
C = GROUND COVER (C-FACTOR)	1.0 (TYPICAL FOR STRIPPED SITE)			
CALCULATED SOIL LOSS (RUSTLE METHOD)	41 t/ha/yr			

SEDIMENT BASIN SIZING CALCULATION


AVERAGE ANNUAL SOIL LOSS FROM TOTAL AREA OF LAND DISTURBANCE IS LESS THEN 150 CUBIC METRES PER YEAR. IN ACCORDANCE WITH THE BLUE BOOK, A SEDIMENT BASIN IS NOT REQUIRED



CONSTRUCTION NOTES

- 1. STRIP THE TOPSOIL, LEVEL THE SITE AND COMPACT THE SUBGRADE.
- COVER THE AREA WITH NEEDLE-PUNCHED GEOTEXTILE.
- 3. CONSTRUCT A 200mm THICK PAD OVER THE GEOTEXTILE USING ROAD BASE OR 30mm AGGREGATE.
- 4. ENSURE THE STRUCTURE IS AT LEAST 15 METRES LONG OR TO BUILDING ALIGNMENT AND AT LEAST 3 METRES
- 5. WHERE A SEDIMENT FENCE JOINS ONTO THE STABILISED ACCESS, CONSTRUCT A HUMP IN THE STABILISED ACCESS TO DIVERT WATER TO THE SEDIMENT FENCE.

STABILISED SITE ACCESS (SD 6-14)



CONSTRUCTION NOTES

1. BUILD WITH GRADIENTS BETWEEN 1 AND 5 PERCENT.

GRADIENT OF

OF FLOW

DRAIN 1% TO 5% —

- 2. AVOID REMOVING TREES AND SHRUBS IF POSSIBLE WORK AROUND THEM.
- 3. ENSURE THE STRUCTURES ARE FREE OF PROJECTIONS OR OTHER IRREGULARITIES THAT COULD IMPEDE WATER FLOW.

— CAN BE CONSTRUCTED WITH

— LINE CHANNEL WITH

GEOFABRIC OR JUTE-MATT

IF CLEAN WATER DIVERSION

— ALL BATTER GRADES

2(H):1(V) MAX.

OR WITHOUT CHANNEL.

2 METRES MIN.

- 4. BUILD THE DRAINS WITH CIRCULAR, PARABOLIC OR TRAPEZOIDAL CROSS SECTIONS, NOT V SHAPED.
- 5. ENSURE THE BANKS ARE PROPERLY COMPACTED TO PREVENT FAILURE.
- 6. COMPLETE PERMANENT OR TEMPORARY STABILISATION WITHIN 10 DAYS OF CONSTRUCTION.

NOTE: ONLY TO BE USED AS TEMPORARY BANK WHERE MAXIMUM UPSLOPE LENGTH IS 80 METRES.

DIVERSION DRAIN (SD 5-5)

CONSTRUCTION NOTES

- 1. INSTALL FILTERS TO KERB INLETS ONLY AT SAG POINTS.
- 2. FABRICATE A SLEEVE MADE FROM GEOTEXTILE OR WIRE MESH LONGER THAN THE LENGTH OF THE
- INLET PIT AND FILL IT WITH 25mm TO 50mm GRAVEL.

 3. FORM AN ELLIPTICAL CROSS-SECTION ABOUT 150mm HIGH x 400mm WIDE.
- 3. FORM AN ELLIPTICAL CROSS-SECTION ABOUT 150mm HIGH x 400mm WIDE.


 4. PLACE THE FILTER AT THE OPENING LEAVING AT LEAST A 100mm SPACE BETWEEN IT AND THE KERB
- INLET. MAINTAIN THE OPENING WITH SPACER BLOCKS.

WHERE SPECIFIED IN APPROVED SWMP/ESCP.

- 5. FORM A SEAL WITH THE KERB TO PREVENT SEDIMENT BYPASSING THE FILTER.
- 6. SANDBAGS FILLED WITH GRAVEL CAN SUBSTITUTE FOR THE MESH OR GEOTEXTILE PROVIDING THEY ARE PLACED SO THAT THEY FIRMLY ABUT EACH OTHER AND SEDIMENT-LADEN WATERS CANNOT PASS

.


SANDBAG SEDIMENT FILTER (SD 6-11)



CONSTRUCTION NOTES

- 1. CONSTRUCT SEDIMENT FENCES AS CLOSE AS POSSIBLE TO BEING PARALLEL TO THE CONTOURS OF THE SITE, BUT WITH SMALL RETURNS AS SHOWN IN THE DRAWING TO LIMIT THE CATCHMENT AREA OF ANY ONE SECTION. THE CATCHMENT AREA SHOULD BE SMALL ENOUGH TO LIMIT WATER FLOW IF CONCENTRATED AT ONE POINT TO 50 LITRES PER SECOND IN THE DESIGN STORM EVENT, USUALLY THE 10-YEAR EVENT.
- 2. CUT A 150mm DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM OF THE FABRIC TO BE ENTRENCHED.
- 3. DRIVE 1.5 METRE LONG STAR PICKETS INTO GROUND AT 2.5 METRE INTERVALS (MAX) AT THE DOWNSLOPE EDGE OF THE TRENCH. ENSURE ANY STAR PICKETS ARE FITTED WITH SAFETY CAPS.
- 4. FIX SELF-SUPPORTING GEOTEXTILE TO THE UPSLOPE SIDE OF THE POSTS ENSURING IT GOES TO THE BASE OF THE TRENCH. FIX THE GEOTEXTILE WITH WIRE TIES OR AS RECOMMENDED BY THE MANUFACTURER. ONLY USE GEOTEXTILE SPECIFICALLY PRODUCED FOR SEDIMENT FENCING. THE USE OF SHADE CLOTH FOR THIS PURPOSE IS NOT SATISFACTORY.
- 5. JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150mm OVERLAP.
- 6. BACKFILL THE TRENCH OVER THE BASE OF THE FABRIC AND COMPACT IT THOROUGHLY OVER THE GEOTEXTILE.

SEDIMENT FENCE (SD 6-8)



CONSTRUCTION NOTES

- 1. PLACE STOCKPILES MORE THAN 2m (PREFERABLY 5m) FROM EXISTING VEGETATION, CONCENTRATED WATER FLOW, ROADS AND HAZARD AREAS.
- 2. CONSTRUCT ON THE CONTOUR AS LOW, FLAT, ELONGATED MOUNDS.
- 3. WHERE THERE IS SUFFICIENT AREA, TOPSOIL STOCKPILES SHALL BE LESS THAN 2m IN HEIGHT.
- 4. WHERE THEY ARE TO BE IN PLACE FOR MORE THAN 10 DAYS, STABILISE FOLLOWING THE APPROVED ESCP OR SWMP TO REDUCE THE C-FACTOR TO LESS THAN 0.10.
- 5. CONSTRUCT EARTH BANKS (STANDARD DRAWING 5-5) ON THE UPSLOPE SIDE TO DIVERT WATER AROUND STOCKPILES AND SEDIMENT FENCES (STANDARD DRAWING 6-8) 1 TO 2m DOWNSLOPE.


STOCKPILES (SD 4-1)

NOT FOR CONSTRUCTION

REVISION DESCRIPTION |ISSUED| VER'D | APP'D | DATE OMMENCING WORK RAYMOND TERRACE BOWLING CLUB NL231087 CIVIL ENGINEERING PACKAGE A ISSUED FOR CLIENT REVIEW RS 31.10.23 NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE SABILITY, COMPLETENESS OR SCALE OF DRAWINGS JR | AB | RS | 27.11.23 1 ISSUED FOR DEVLOPMENT APPLICATION TRANSFERRED ELECTRONICALLY DRAWING NUMBER THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUF 2 JACARANDA AVENUE, RAYMOND AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE. Newcastle **CONCEPT EROSION AND SEDIMENT** TERRACE, NSW, 2324 **DA-C02.12** Level 1, 215 Pacific Hwy, Charlestown NSW 2290 CONTROL DETAILS Ph (02) 4943 1777 Email newcastle@northrop.com.au NOT TO SCALE THE COPYRIGHT OF THIS DRAWING REMAINS WITH DRAWING NOT TO BE USED FOR CONSTRUCTION ABN 81 094 433 100 NORTHROP CONSULTING ENGINEERS PTY LTD UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED DRAWING SHEET SIZE = A1

R.STEVENSON JOB MANAGER: R.STEVENSON VERIFIER:

AWN: J.RYALL DESIGNED: F



NEW BUILDING OUTLINE OVERHEAD. — — — REFER TO ARCHITECTURAL PLANS FOR MORE INFORMATION EXISTING BUILDING UNDERGOING RENOVATIONS. REFER TO ARCHITECTURAL PLANS FOR MORE INFORMATION PROPOSED VEHICULAR PAVEMENT. DETAILS TO BE PROVIDED AT CC STAGE PROPOSED DRIVEWAY REPLACEMENT CONSTRUCTED IN ACCORDANCE WITH S138 PROPOSED PEDESTRIAN PAVEMENT CONSTRUCTED AS PART OF STAGE 1. DETAILS TO BE PROVIDED AT CC STAGE PROPOSED STORMWATER PIPE CONSTRUCTED AS PART OF STAGE 1. DETAILS TO BE PROVIDED AT CC STAGE PROPOSED STORMWATER PIT AND TAG **⊠ ■** P1 CONSTRUCTED AS PART OF STAGE 1. DETAILS TO BE PROVIDED AT CC STAGE PROPOSED GRATED TRENCH DRAIN CONSTRUCTED AS PART OF STAGE 1. DETAILS TO BE DETAILED AT CC STAGE. PROPOSED 15kL UNDERGROUND RAINWATER TANK CONSTRUCTED AS PART OF STAGE 2. DETAILS TO BE PROVIDED AT CC STAGE PROPOSED OCEAN PROTECT JELLYFISH CONSTRUCTED AS PART OF STAGE 1. DETAILS TO BE PROVIDED AT CC STAGE PROPOSED FINISHED FLOOR LEVEL. FFL 4.75 REFER TO ARCHITECTURAL PLANS FOR DETAILS RL 3.15 PROPOSED SPOT LEVEL PROPOSED RETAINING WALL AND TYPE. DETAILS TO BE PROVIDED AT CC STAGE PROPOSED DIRECTION OF GRADE IN FINISHED SURFACE PROPOSED KERB CONSTRUCTED AS PART OF STAGE 1. DETAILS TO BE PROVIDED AT CC STAGE PROPOSED KERB RAMP CONSTRUCTED AS PART OF STAGE 1. DETAILS TO BE PROVIDED AT CC STAGE EXISTING STORMWATER PIT EXISTING STORMWATER PIPE TO REMAIN EXISTING GRATED TRENCH DRAIN TO REMAIN EXISTING STORMWATER PIPE TO BE EXISTING CONTOURS (0.5m INTERVALS)

LEGEND

SITE BOUNDARY LINE

NOT FOR CONSTRUCTION

REVISION	DESCRIPTION	ISSUED	VER'D	APP'D	DATE	CLIENT
Α	ISSUED FOR CLIENT REVIEW	JR		RS	31.10.23	
1	ISSUED FOR DEVLOPMENT APPLICATION	JR	AB	RS	27.11.23	Dallmond Toward
						Raymond errace
						DRAWING NOT TO BE USED FOR CONSTRUCTION
						UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED

EJE architecture THE COPYRIGHT OF THIS DRAWING REMAINS WITH





Level 1, 215 Pacific Hwy, Charlestown NSW 2290 Ph (02) 4943 1777 Email newcastle@northrop.com.au ABN 81 094 433 100

RAYMOND TERRACE BOWLING CLUB


2 JACARANDA AVENUE, RAYMOND TERRACE, NSW, 2324

CIVIL ENGINEERING PACKAGE

CONCEPT CIVIL WORKS PLAN - STAGE 1 AND 2

NL231087 DRAWING NUMBER DA-C04.11

DRAWING SHEET SIZE = A1



NOT FOR CONSTRUCTION

LEGEND

NEW BUILDING OUTLINE OVERHEAD. REFER TO ARCHITECTURAL PLANS

PROPOSED BUILDING. REFER TO ARCHITECTURAL PLANS FOR

PROPOSED VEHICULAR PAVEMENT. DETAILS TO BE PROVIDED AT CC STAGE

PROPOSED DRIVEWAY REPLACEMENT

PROPOSED PEDESTRIAN PAVEMENT CONSTRUCTED AS PART OF STAGE 3. DETAILS TO BE PROVIDED AT CC STAGE

PROPOSED STORMWATER PIPE CONSTRUCTED AS PART OF STAGE 3.

DETAILS TO BE PROVIDED AT CC STAGE

PROPOSED STORMWATER PIT AND TAG

CONSTRUCTED AS PART OF STAGE 3. DETAILS TO BE PROVIDED AT CC STAGE

PROPOSED GRATED TRENCH DRAIN CONSTRUCTED AS PART OF STAGE 3.

DETAILS TO BE DETAILED AT CC STAGE.

PROPOSED DETENTION TANK WITH 96m3 STORAGE VOLUME CONSTRUCTED AS PART OF STAGE 3. DETAILS TO BE

PROPOSED OCEAN PROTECT JELLYFISH CONSTRUCTED AS PART OF STAGE 1. REFER TO STAGE 1 AND 2 PLANS FOR

PROPOSED FINISHED FLOOR LEVEL. REFER TO ARCHITECTURAL PLANS FOR DETAILS

PROPOSED RETAINING WALL AND TYPE.

DETAILS TO BE PROVIDED AT CC STAGE

PROVIDED AT CC STAGE

MORE INFORMATION

PROPOSED SPOT LEVEL

PROPOSED DIRECTION OF

PROVIDED AT CC STAGE

EXISTING STORMWATER PIT

PROVIDED AT CC STAGE

TO REMAIN

PROPOSED 15kL UNDERGROUND RAINWATER TANK CONSTRUCTED AS PART OF STAGE 1. DETAILS TO BE

EXISTING STORMWATER PIPE TO

EXISTING GRATED TRENCH DRAIN

EXISTING CONTOURS (0.5m INTERVALS)

EXISTING STORMWATER PIPE TO REMAIN

GRADE IN FINISHED SURFACE

PROPOSED KERB CONSTRUCTED AS PART OF STAGE 3. DETAILS TO BE

CONSTRUCTED IN ACCORDANCE WITH S138

FOR MORE INFORMATION

MORE INFORMATION.

APPROVAL

■ P11

FFL 3.69

RW1


RL 3.15

FALL

— - - SITE BOUNDARY LINE

1 ISSUED FOR DEVLOPMENT APPLICATION JR AB RS 27.11.23 DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED

NORTHROP CONSULTING ENGINEERS PTY LTD





Level 1, 215 Pacific Hwy, Charlestown NSW 2290 Ph (02) 4943 1777 Email newcastle@northrop.com.au ABN 81 094 433 100

2 JACARANDA AVENUE, RAYMOND

TERRACE, NSW, 2324

CIVIL ENGINEERING PACKAGE

CONCEPT CIVIL WORKS PLAN - STAGE 3

NL231087 DRAWING NUMBER

DA-C04.12 DRAWING SHEET SIZE = A1