

TELEPHONE: (02) 4910 1719
EMAIL: jeffreylyons@ausgrid.com.au
REFERENCE: Notification No. 1900131750

ATTN: Emmilia Marshall
Maitland City Council
PO Box 220
Maitland NSW 2320

570 George Street
Sydney NSW 2000
ALL mail to GPO Box 4009
Sydney NSW 2001
T +61 2 131 525
F +61 2 9269 2830
www.ausgrid.com.au

**Re: DA/2024/763 - 559 ANAMBAH ROAD GOSFORTH -
Concept Development Application for Two (2) into Nine Hundred (900) Lot Staged Torrens Title
Subdivision, and Stage 1 Torrens Title Subdivision of Two Hundred and Forty One (241) Lots.**

I refer to Maitland City Council development application DA/2024/763.

This letter is Ausgrid's response under clause 45(2) of the State Environmental planning Policy (Transport and Infrastructure) 2021.

The assessment and evaluation of environmental impacts for a new development consent (or where a development consent is modified) is undertaken in accordance with requirements of Section 79C of the Environmental Planning and Assessment Act 1979. One of the obligations upon consent authorities, such as local councils, is to consider the suitability of the site for the development which can include a consideration of whether the proposal is compatible with the surrounding land uses and the existing environment.

In this regard, Ausgrid requires that due consideration be given to the compatibility of proposed development with existing Ausgrid infrastructure, particularly in relation to risks of electrocution, fire risks, Electric & Magnetic Fields (EMFs), noise, visual amenity and other matters that may impact on Ausgrid or the development.

With Regard to:

Concept Development Application for Two (2) into Nine Hundred (900) Lot Staged Torrens Title Subdivision, and Stage 1 Torrens Title Subdivision of Two Hundred and Forty One (241) Lots at 559 ANAMBAH ROAD GOSFORTH

Ausgrid does not object to the proposal. Please refer to the following information and conditions:-

Method of Electricity Connection

The method of connection will be in line with Ausgrid's Electrical Standard (ES)1 – 'Premise Connection Requirements'.

Supply of Electricity

It is recommended for the nominated electrical consultant/contractor to provide a preliminary enquiry to Ausgrid to obtain advice for the connection of the proposed development to the adjacent electricity network infrastructure. An assessment will be carried out based on the enquiry which may include whether or not:

- The existing network can support the expected electrical load of the development
- A substation may be required on-site, either a pad mount kiosk or chamber style and;
- site conditions or other issues that may impact on the method of supply.

Please direct the developer to Ausgrid's website, www.ausgrid.com.au about how to connect to Ausgrid's network.

Conduit Installation

The need for additional electricity conduits in the footway adjacent to the development will be assessed and documented in Ausgrid's Design Information, used to prepare the connection project design.

Vegetation

All proposed vegetation underneath overhead power lines and above underground cables must comply with the requirements of ISSC 3 Guideline For Managing Vegetation Near Power Lines.

Proximity to Existing Network Assets**Overhead Powerlines**

There are existing overhead electricity network assets in Anambah Rd.

Safework NSW Document – Work Near Overhead Powerlines: Code of Practice, outlines the minimum safety separation requirements between these mains/poles to structures within the development throughout the construction process. It is a statutory requirement that these distances be maintained throughout construction. Special consideration should be given to the positioning and operating of cranes and the location of any scaffolding.

The “as constructed” minimum clearances to the mains should also be considered. These distances are outlined in the Ausgrid Network Standard, NS220 Overhead Design Manual. This document can be sourced from Ausgrid’s website, www.ausgrid.com.au

Should the existing overhead mains require relocating due to the minimum safety clearances being compromised in either of the above scenarios, this relocation work is generally at the developers cost.

It is also the responsibility of the developer to ensure that the existing overhead mains have sufficient clearance from all types of vehicles that are expected be entering and leaving the site.

Underground Cables


There are existing underground electricity network assets in Anambah Rd.

Special care should also be taken to ensure that driveways and any other construction activities within the footpath area do not interfere with the existing cables in the footpath. Ausgrid cannot guarantee the depth of cables due to possible changes in ground levels from previous activities after the cables were installed. Hence it is recommended that the developer locate and record the depth of all known underground services prior to any excavation in the area.

Safework Australia – Excavation Code of Practice, and Ausgrid’s Network Standard NS156 outlines the minimum requirements for working around Ausgrid’s underground cables.

Please do not hesitate to contact Jeffrey Lyons on Ph: (02) 4910 1719 (please quote our ref: Trim 2017/26/453) should you require any further information.

Regards, Jeff



Jeffrey Lyons
Engineering Officer
Ausgrid
Ph: (02) 4910 1719