


#### **UNE Tamworth Central**





**Project:** UNE Tamworth Central

**Location:** Roderick Street and Peel Street,

Tamworth NSW 2340

**Prepared by:** ADP Consulting Pty Ltd

Level 6, 33 Erskine Street

Sydney NSW 2000

Project No: SYD2353

Revision: 01

**Date:** 28 July 2023

Rev	Date	Comment	Author	Technical Review	Signature	Authorisa- tion & QA	Signature
01	28.07.23	DA Submission	SY/MC/ME/AY/DB/DP/KS	Samuel Youssef	SY	James Cannam	JC

#### **Project Team**

Client / Principal University Of New England (UNE)

**Architect** Architectus

Services Consultant (MEP) ADP Consulting









#### **Contents**

1.2 Water Infrastructure	1.2 Water Infrastructure 1.3 Sewer Infrastructure 2. Introduction 2.1 Project Description. 2.2 References 3. Electrical Infrastructure 3.1 Existing Infrastructure 3.2 Calculated AS3000 Electrical Maximum Demand. 3.3 New Works Associated with Electrical Infrastructure. 4. Telecommunications Existing development and Infrastructure. 4.1 9 4.2 New Works Associated with Telecommunications Infrastructure. 5.1 Existing development and Infrastructure. 5.2 Water & Sewer Infrastructure 5.3 Existing development and Infrastructure. 5.4 Existing development and Infrastructure. 5.5 Water & Sewer Infrastructure. 5.6 New Works Associated with Sewer & Water Infrastructure.	3 4 6 7
1.3 Sewer Infrastructure	1.3 Sewer Infrastructure	3 4 6 7
2. Introduction	2. Introduction 2.1 Project Description	4 6
2.1 Project Description	2.1 Project Description	4 6 <b>7</b>
2.2 References	2.2 References	6 <b>7</b>
3. Electrical Infrastructure 3.1 Existing Infrastructure 3.2 Calculated AS3000 Electrical Maximum 3.3 New Works Associated with Electrical Maximum 4. Telecommunications  Existing development and Infrastructum 4.1 9 4.2 New Works Associated with Telecomm 5. Water & Sewer Infrastructure 5.1 Existing development and Infrastructum 5.2 New Works Associated with Sewer & New Works Ass	3. Electrical Infrastructure	7
3.1 Existing Infrastructure	3.1 Existing Infrastructure	
3.2 Calculated AS3000 Electrical Maximum 3.3 New Works Associated with Electrical Maximum 4. Telecommunications	3.2 Calculated AS3000 Electrical Maximum Demand	7
<ul> <li>New Works Associated with Electrical Materials</li> <li>Telecommunications</li></ul>	3.3 New Works Associated with Electrical Infrastructure	
4. Telecommunications	4. Telecommunications  Existing development and Infrastructure  4.1 9  4.2 New Works Associated with Telecommunications Infrastructure  5. Water & Sewer Infrastructure  5.1 Existing development and Infrastructure  5.2 New Works Associated with Sewer & Water Infrastructure	7
Existing development and Infrastructu 4.1 9 4.2 New Works Associated with Telecomm 5. Water & Sewer Infrastructure 5.1 Existing development and Infrastructu 5.2 New Works Associated with Sewer & N 5.3 Risks	Existing development and Infrastructure	7
4.1 9 4.2 New Works Associated with Telecomm 5. Water & Sewer Infrastructure 5.1 Existing development and Infrastructu 5.2 New Works Associated with Sewer & N 5.3 Risks	4.1 9  4.2 New Works Associated with Telecommunications Infrastructure	9
4.2 New Works Associated with Telecomm  5. Water & Sewer Infrastructure	4.2 New Works Associated with Telecommunications Infrastructure	9
5. Water & Sewer Infrastructure	5. Water & Sewer Infrastructure	
5.1 Existing development and Infrastructu 5.2 New Works Associated with Sewer & \ 5.3 Risks	5.1 Existing development and Infrastructure	9
5.2 New Works Associated with Sewer & \ 5.3 Risks	5.2 New Works Associated with Sewer & Water Infrastructure	. 10
5.3 Risks		10
	5.3 Risks	11
6. Gas Infrastructure		13
	6. Gas Infrastructure	. 14
6.1 Existing Infrastructure	6.1 Existing Infrastructure	14
6.2 New Works Associated with Gas Infras	6.2 New Works Associated with Gas Infrastructure	14
Annendices	Appendix A DBYD map	1 [
Appendices	Appendix B ASPL3 Assessment	



#### Executive Summary

This report provides a review of the existing services infrastructure surrounding and serving the site of the old Tamworth Velodrome, located on the corner of Peel St & Roderick St and bounded by the Peel River, Tamworth NSW.

The site is approx. 11,000m<sup>2</sup> area to be developed into a new University building and carpark as a first stage. Future stages include more university buildings on site. However, the extent of the later stages is not entirely defined.

This report is for the purpose of the first stage only.

In summary, the ADP desktop review has highlighted the following:

#### 1.1 Electrical Infrastructure

- > The site is currently supplied from an Essential Energy pad mount substation. Proposed works included upgrade of existing to meet developments requirements.
- > There are no NBN, Telstra and Optus communication services located to the site. Telstra pits are adjacent to the site. Works require instatement of a NBN connection.

#### 1.2 Water Infrastructure

- > The existing water main running adjacent to the site appear to be adequate to serve the proposed development subject to final pressure and flow enquiry.
- > ADP recommends connection into the 150mm water main along Peel St. The exact connection point is subject to the Section 307 application.
- > No gas mains are located around the site, therefore, no gas will be provided to the development.

#### 1.3 Sewer Infrastructure

- > The existing 300mm UPVC sewer main running within the site appears to be adequate to served the proposed development.
- > ADP recommends connection into this sewer main. The exact connection point is subject to the Section 307 application.



#### 2. Introduction

#### 2.1 Project Description

The project involves the design and construction of a new central teaching campus building located on the site of the old Tamworth Velodrome, located on the corner of Peel St & Roderick St and bounded by the Peel River.

The proposed building will comprise of the following:

- > Ground Level: Teaching spaces and amenities,
- > First Floor: Clinical Simulation Laboratories, student open space with kitchenette, cultural spaces with meeting room and amenities,
- > Second Floor: Teaching spaces, flexible spaces, student open spaces and amenities,
- > Third Floor: Studying desks, collaboration meeting rooms, focus rooms and amenities,
- > The External area of the building will contain car parking, services plant spaces and landscaping.

The objective of this document is to define the services strategies for the proposed development.

ADP have undertaken a desktop review of the information provided from the site Dial Before You Dig (DBYD) search.

The report provides an overview of the following information relating to each service:


- > Existing infrastructure surrounding and serving the site from the following in-ground services:
  - Water & Sewer (Tamworth Regional Council)
  - Power (Ausgrid)
  - Telecommunications (Telstra, NBN and Optus)
- > Estimated new infrastructure works associated with the development. The final scope for the supply authority works will be subject to the submission of a number of Applications for Connection or Technical Enquiries.







Figure 2 Proposed Development





This report reviews the existing infrastructure within the area, the capacity the infrastructure has to support this project (where known), and the outline scope of works associated with infrastructure for the site.

#### 2.2 References

This design return brief is based upon the following information:

- > Dial Before You Dig (DBYD) information package,
- > Architectural drawings by Architectus, Received on 30<sup>th</sup> May 2023,
- > Site visit, conducted on 4<sup>th</sup> May 2023.



#### Electrical Infrastructure

#### 3.1 Existing Infrastructure

The site is currently supplied from an Essential Energy pad mount substation 18-17158 located within the property boundary. This substation has a rating of 500kVA and is serving 18 other customers in the surrounding mixed residential/commercial area. The present load on this substation is estimated to be 409kVA.

#### 3.2 Calculated AS3000 Electrical Maximum Demand

The proposed load of UNE Tamworth is 365A per phase, which is equivalent to 253kVA. This proposed load cannot be supplied from the existing substation as it will overload this substation. It appears that there is no other available substation in the area to divert the electrical load. The proposed maximum demand of UNE Tamworth cannot be supplied from the existing network without considerable modification.

#### 3.3 New Works Associated with Electrical Infrastructure

<u>Works required would include the</u> upgrade of the existing pad mount substation at its current location to 1000kVA, subject to Essential Energy approval. This will enable UNE Tamworth to take a supply of 365A from the upgraded pad mount.

Street lighting assessment and Essential Energy Street lighting assets alternation works might be needed if local city council request further street lighting assessment on the public road in front of development frontage.






Figure 1 Essential Energy network around development site

Table 1. Electrical Authority Infrastructure Cost Estimate


Supply Options	Option A	Option B
Indicative costs	\$150,000*	\$250,000*

<sup>\*</sup> Does not include Ancillary Network Service (ANS) charges by Essential Energy, and material & installation cost for LV cables from substation to MSB and ASP/3 design fees.




#### 4. Telecommunications

#### 4.1 Existing development and Infrastructure



The site is currently not supplied by the NBN network. Application and further investigation required to liaise with NBN to obtain a telecommunications connection. There are 3 Telecommunications pits located adjacent to the premise that provide opportunity for connection.



The site currently has fully access to 4G and 3G coverage which is deemed adequate for the proposed site given the location.

#### 4.2 New Works Associated with Telecommunications Infrastructure

Works required for the development involve liaising with Telecommunications authorities to establish the works required to extend the existing telecommunications network to site. Application for connection to be submitted to NBN.



#### Water & Sewer Infrastructure

#### 5.1 Existing development and Infrastructure

#### 5.1.1 Sewer

The BYDA information provided by Tamworth Regional Council indicates:

- > An existing Ø300mm UPVC (Unplasticised Polyvinylchloride) Tamworth council sewer main runs in the west direction within the boundary of the site.
  - A 5.113m deep sewer manhole is located approximately 45m and 17m from the eastern and northern boundary respectively within the site.
  - A 1.99m deep sewer manhole is located on the western boundary of the site on Roderick St.
  - 30m south of the above manhole is another sewer manhole of depth 2.31m. The sewer main then runs in a western direction

#### 5.1.2 Potable Water

The BYDA information provided by Tamworth Regional Council indicates:

- > An existing Ø150mm DICL (Ductile Iron Cement Lined) water main runs along the northern side of Peel st.
  - It is proposed that the water connection for domestic water and fire services is made from here
- > An existing Ø150mm DICL (Ductile Iron Cement Lined) water main runs along the western side of Roderick St.

A google street view assessment indicates that there is an existing 100mm connection from the water main along Roderick St currently serving the site.

Figure 14 Water meter shown within the site boundary from Roderick St



This is consistent with the BYDA information received showing a capped off connection in this location.



The proposed connection point for the fire services for the development is on Peel St as it is road facing the main pedestrian entrance.

The size and flow of the main on Peel St is sufficient for the fire system demand required to the development according to the Pressure and Flow application received by Tamworth Regional Council. Amplification of the potable water main is not required.

Figure 14 Pressure and Flow Results – Ø150 Waterloo Road Main

Date: 6/4/2023 Time: 6.50am Water main size: 150mm							
Summary Results:	Flow & Residual	Flow & Residual Pressure Results:					
No.	Location (A)	Location (A)					
Static Pressure 800 (KPa)	Asset No: HYD0075284	Asset No: HYD000075284					
Maximum Flow During Test : 28.0 (Litres/Sec)	(Flow - Litres/second)	(Residual Pressure – Kpa)					
	0	800					
	5	780					
	10	710					
	15	600					
	20	525					
	25	340					
	28	140					

#### 5.2 New Works Associated with Sewer & Water Infrastructure


#### 5.2.1 Water & Sewer Infrastructure connections

The sewer connection is proposed to be via the existing 300mm UPVC Tamworth council sewer main. It is anticipated the main will be sufficient to serve the development. Should Tamworth council deem the main to be inadequate based on the loads in the existing infrastructure, an upgrade would potentially be required. It is not anticipated that this will be required.

The exact location of sewer connection is subjected to the Section 306 Notice of Requirements.



Figure 16 Proposed sewer connection (subject to Section 307 Application)








Figure 16 Proposed water connection (subject to Section 307 Application)

#### 5.3 Risks

The following risk items will need to be confirmed during the design development phase to determine the development sewer drainage and water final demand:

- > Fixture and Loading Units for the proposed building (respective sewer drainage and water services demand for the development).
- Excavating near an existing water main will likely affect the 'zone of influence' and trigger protection or relocation of the existing sewer mains. As there is no excavation for a basement level, it is not anticipated that any protection of Tamworth Regional Council's assets will be required
- > Exact location of sewer and water mains connections will be subject to Tamworth Regional Council's Section 307



#### Gas Infrastructure

#### 6.1 Existing Infrastructure

There is no existing gas infrastructure. No information was received from the BYDA or from Tamworth Regional Council.

#### 6.2 New Works Associated with Gas Infrastructure

If gas is required on site, an LPG tank will be provided where required. Otherwise, no gas provisions will be allowed for.




## Appendix A DBYD map





#### THIS PAGE IS INTENTIONALLY BLANK








## Appendix B ASPL3 Assessment





#### THIS PAGE IS INTENTIONALLY BLANK










#### THIS PAGE IS INTENTIONALLY BLANK



# Creating great environments with great people

Melbourne Level 13, 55 Collins Street Melbourne VIC 3000 τ. 03 9521 1195 Sydney Level 6, 33 Erskine Street Sydney NSW 2000 T. 02 8203 5447 Brisbane
Ground Floor, 102 Adelaide Street
Brisbane QLD 4000
T. 07 3088 4022

adpconsulting.com.au



Project Name:

Client:

UNE TAMWORTH CENTRAL

SERVICES SPATIAL REVIEW

SYD2353 S-SK-01

Drawing / Sketch No.

Rev.

02

Nominated Architect

Ray Brown, NSWARB 6359

Do not scale drawings. Verify all dimensions on site

The University of New England Tamworth Central Campus

Perth

Sydney

checked

F (61 2) 8252 8600

1:200@A1

220518.00

sydney@architectus.com.au

scale

project no


NE

ROOMS - Department

GA - GROUND LEVEL

drawing no. **DA1001** 

20/07/2023 5:35:04 PM



Client:

Drawing / Sketch No.

SYD2353 S-SK-01

Rev.

02


Do not scale drawings. Verify all dimensions on site


DA1002


project no LJ

220518.00

20/07/2023 5:35:09 PM







°architectus™ Architectus Australia Pty Ltd is the owner of the copyright subsisting in these drawings, plans, designs and specifications. They must not be used, reproduced or copied, in whole or in part, nor may the information, ideas and concepts therein contained (which are confidential to Architectus Australia Pty Ltd) be disclosed to any person without the prior written consent of that company. Nominated Architect Ray Brown, NSWARB 6359

Do not scale drawings. Verify all dimensions on site

Date	28.07.23 Drawn by VARIOUS			Building Services Engineers				
	20.07.20	Diami. Sy	77414000	_	ADF	CONSULTIN	G PTY LTD	
Scale	NTS	Checked by	SY	ADP	MELBOURNE Level 13 55 Collins St Melbourne VIC 3000	SYDNEY Level 6 33 Erskine St Sydney NSW 2000	BRISBANE Level 16 15 Adelaide St Brisbane QLD 4000	GOLD COAST Level 13 50 Cavill Ave Surfers Paradise QLD 4022
Sheet Size	Sheet Size - Approved by -			Consulting : Engine +61 39521 1195 +61 28203 5447 +61 73088 4022 +61 73088 40  www.adpconsulting.com.au contact@adpconsulting.com.a				
Project Na	Project Name:				Title:			
UNE TAM	UNE TAMWORTH CENTRAL				SPATIA	L REVII	EW	
Client:			Job No.	Drawing / Sk	etch No.		Rev.	
-	-				S-SK-01			02



# architectus™

		Architectus Sydne
		Level 1
Adelaide		25 Martin Plac
Brisbane		Sydney NSW 200
Melbourne		T (61 2) 8252 840
Perth		F (61 2) 8252 860
Sydney	sydi	ney@architectus.com.a
checked	scale	
	NE	1 : 200 @A′
drawa	project p	_

The University	of New England
Tamworth	Central Campus

GA - ROOF

drawing

drawing no. **DA1005** 

20/07/2023 5:35:24 PM



# Civil Engineering Concept Design Report

### **University of New England (UNE) - Tamworth Central Campus**

Prepared for Architectus/ 22 November 2023

221823

#### **Contents**

1.0	Intro	Introduction				
	1.1	Refere	ence Documents	3		
2.0	Exist	Existing Site				
	2.1 Existing Services					
		2.1.1	Electricity	5		
		2.1.2	Communications	5		
	2.2	Geoted	chnical Conditions	5		
	2.3	.3 Contamination				
3.0	Prop	osed Ard	chitectural & Landscape Concept	7		
4.0	Floor	ding		9		
5.0	Stormwater					
	5.1	5.1 Existing Stormwater				
	5.2	5.2 Proposed Stormwater				
	5.3	5.3 Stormwater Quantity				
	5.4	Stormy	water Quality	10		
		5.4.1	MUSIC Modelling	11		
	5.5	Operat	tions and Maintenance	11		
	5.6	Erosio	n and Sediment Control	11		
6.0	Grou	round and Water Conditions		13		
7.0	Surfa	face Impact Assessment				
8.0	Proje	Project Risks				
9.0 Preparation for Schematic Design Phase						
	9.1	Intende	ed Focus for Schematic Design Phase	16		
10.0	Cond	clusion		17		
Appen	dix A .			18		
Appen	dix B .			19		

Rev	Date	Prepared By	Approved By	Remarks
Concept	22/11/2023	NB	NB	For Authority Approval
DRAFT	25/08/2023	JL	NB	Concept Design

#### 1.0 Introduction

Taylor Thomson Whitting (TTW) has been engaged by Architectus to provide Civil Engineering consultancy services for the proposed works at UNE Tamworth Central Campus. The following chapters of this report were developed to form the Civil Engineering design component of Architectus' wider concept design report.

This report will address the civil engineering challenges of the site including stormwater quantity, overland flow, potential flooding, stormwater quality, pavements, soil & erosion and earthworks design. The relevant requirements of the Tamworth Regional Council's Development Control Plan (DCP) and engineering specifications will be addressed.

#### 1.1 Reference Documents

The following documents have been reviewed and referenced in preparing this report:

- Tamworth Regional Council Development Control Plan 2010;
- Tamworth Regional Council Local Environmental Plan 2010;
- Tamworth Regional Council Engineering Design Minimum Standards for Subdivisions and Developments Version 1, March 2019;
- Tamworth Regional Council: The Six Water Sensitive Design Essentials;
- Tamworth Regional Council: Water Sensitive Design Statements;
- Tamworth Regional Council: Raingardens;
- Tamworth City-Wide Flood Investigation Volume 1 and 2 by Lyall & Associates, May 2019
- Landcom NSW Managing Urban Stormwater Soils and Construction (The "Blue Book" Vol. 1 and Vol. 2);
- NSW MUSIC Modelling Guidelines;
- NSW Floodplain Development Manual 2005;
- Australian Rainfall and Runoff 2019;

#### And;

- Architectural documentation by Architectus;
- Landscape documentation by Tyrell Studio;
- Geotechnical Investigation report by JK Geotechnics (Ref: 36020PNrpt) dated 28 July 2023;
- Preliminary Site Investigation report by JK Geotechnics (Ref: E36020PDrpt) dated 31 July 2023;
- Survey by Baxter Geo Consulting Pty Ltd Dated 4 February 2016;

#### 2.0 Existing Site

The proposed site location sits within the Local Government Area (LGA) of the Tamworth Regional Council on a parcel of land legally known as Lot 73 Deposited Land (DP) 1107041. It is zoned E2 Commercial Centre under the Tamworth Regional Council LEP. The site is located at 545 Peel Street, Tamworth, NSW 2340 known as Bicentennial Park/Velodrome and is approximately 1.1 ha in area. It is surrounded by industrial/commercial buildings on Peel Street to the northeast and Roderick Street to the northwest, with Peel River adjacent to the site to the west as shown in Figure 1.



Figure 1 – Site Location (Source: Nearmaps)

As shown in the contours map in Figure 2 below, the site generally falls west towards Roderick Street from a reduced level (RL) of approximately 382m (AHD) at the eastern corner of the site boundary to an RL 379m at the western corner. The contours also show the surrounding land falling towards the site, with a low point at the Velodrome at RL377m.



Figure 2 - Site Location (Source: Department of Finance, Services and Innovation, 2017)

#### 2.1 Existing Services

Taylor Thomson Whitting conducted a Dial Before You Dig (DBYD) enquiry as part of the concept design stage to identify known in-ground public assets that may impact the development. For further detail, refer to the relevant consultants' reports and detailed survey including service reticulation.

#### 2.1.1 Electricity

DBYD information provided by Endeavour Energy shows a number of underground low-voltage, high-voltage. It is linked by a road crossing duct with series of 25mmØ and 150mmØ PVC and unknown cover to the opposite side of the Holloway Road.

#### 2.1.2 Communications

DBYD information received from Telstra indicate one 50mmØ PVC conduit between two 3-pits running across Murray Street, approximately 45.5m apart.

#### 2.2 Geotechnical Conditions

The geotechnical investigation report by JK Geotechnics (Ref. No. 36020PNrpt) have been prepared as part of this development. This civil concept design report references information from the geotechnical report relevant to the civil design.

The geotechnical consultant obtained fifteen boreholes (BH1 to BH15) at depths ranging from 6m to 15m to assess the general condition of the site. The subsurface conditions across the site were identified to have a fill depth ranging from 0.3m to 4.4m, which comprises of silty clay soil with layers of sandy fill. It is underlain by

stiff to very stiff clays of medium plasticity, which is in turn underlain by greywacke bedrock at depths of 3.15m to 9.5m.

The investigation encountered groundwater seepage at five borehole locations during the borehole drilling at 3.4m to 10.8m depth. Groundwater seepage was further identified at four borehole locations upon completion of the drilling at depths ranging from 4.9m to 9.4m. It is noted that no longer term monitoring of groundwater levels was carried out.

The geotechnical investigation recommended that a design California Bearing Ratio (CBR) of 1.5% be used for the site's external pavement design, provided that the subgrade was prepared according to their recommendations. According to the report, a weighted average design CBR of 3% could be used for a concrete pavement if a 0.4m thickness of material with a CBR of not less than 10% is placed above natural soils with a CBR of 1.5%. Once a suitable fill has been identified, a final design CBR value can be provided if needed.

For further detail, please refer to the original report by JK Geotechnics.

#### 2.3 Contamination

The findings of the Preliminary Site Investigation (PSI) documented by JK Geotechnics (Ref: E36020PDrpt) have been reviewed in preparing this report. For further information, refer to the original PSI report.

As stated in the report, all soil analysis results were below the adopted site assessment criteria (SAC). However, it is noted that the identified fill in BH9 and BH3 were confirmed to be a potential source of contamination, with traces of plastic, glass, slag and ash in some other borehole locations. Overall, the report initially concluded that contamination issues at the site were to be expected given the site's historical land use, and that the site could be made suitable through remediation processes if necessary.

The report recommends a Detailed Site Investigation (DSI) to address any additional assessment not covered by the PSI, as well as a Remediation Action Plan (RAP) if the DSI identifies the need for on-site remediation to confirm site suitability.

#### 3.0 Proposed Architectural & Landscape Concept

The proposed architectural concept includes construction of a new four-storey school building adjacent to Roderick Street, car park with access on Peel Street, bicycle parking spaces, community lawn, and associated landscaping.

The proposed site plan is shown below in Figure 3.






Figure 3 - Proposed Site Plan (Source: Architectus & Tyrrell Studio)

### 4.0 Flooding

For flood related scope, refer to TTW's separate "Flood Concept Report" for details.

#### 5.0 Stormwater

#### 5.1 Existing Stormwater

The survey investigation provided by Baxter Geo Consulting shows the inground stormwater pipe and pit network within the proposed site. It is noted that all stormwater pits within the site drain to Roderick Street. Council's initial comments below regarding stormwater were also noted on the survey:

- 1. Stormwater Servicing will be dependent on the proposal design;
- 2. Initially, stormwater is to be directed to Roderick Street;
- 3. The existing stormwater infrastructure in Roderick Street may need to be upgraded;
- 4. Detail developed stormwater discharge across the range 1 in 5-year to 1 in 100-year to predeveloped natural flows, or to the capacity of the receiving stormwater infrastructure, whichever is less;
- 5. Roderick Street and to a lesser extent of Peel Street receive significant overland flows during storm events which will need to be considered with regard to potential site access and any basement levels.

Figure 7 below shows the stormwater network in green colour as identified in the survey investigation.



Figure 4 – 100-year Overland Flow (Source: Council Correspondence-Appendix B)

#### 5.2 Proposed Stormwater

The proposed stormwater design is to be in accordance with the relevant Australian Standards, and Australian Rainfall and Runoff 2019 (ARR 2019), Tamworth Regional Council's DCP 2010, and Tamworth Regional Council's Engineering Design Minimum Standards for Subdivision & Developments 2019.

Civil engineering concept design drawings has been prepared and included in Appendix A which nominates indicative proposed stormwater pit and pipe network, subsoil drainage, as well proposed pavement profiles. The assumed impervious areas and catchment sizes are subject to adjustment following the development of the landscape design. The pervious and impervious areas that were allowed for are to be further developed during the schematic design phase.

#### 5.3 Stormwater Quantity

Council's Engineering Design Standards specifies that stormwater must be controlled to protect properties and infrastructures from flooding and limit the stormwater runoff by providing retention/detention basins. However, a Council correspondence confirmed that stormwater detention is not required for the site. Additionally, the general stormwater and flooding freeboard requirements for the site have been confirmed. Refer to Appendix B for Council's correspondence.

#### 5.4 Stormwater Quality

The proposed development will ensure the implementation of appropriate water quality treatment for stormwater runoff to reduce the discharge of pollutants from paved and other impermeable surfaces into waterways and council drainage systems.

The Tamworth Regional Council's Water Sensitive Design Statement Fact Sheet stipulates that the stormwater discharge must meet the following standards shown in Figure 8 below.

Site	Site Lots over 2,000 m <sup>2</sup> Lots less than					
Characteristics		in size	2,000 m <sup>2</sup> in size			
	Gross Pollutants	90%	90%			
tion Loads *	Total Suspended Solids	Neutral or Beneficial Effect on Water	80%			
Target Reduction Loads *	Total Phosphorus	Quality – meaning loads of pollutants from future development must be equivalent to or less than that from the existing land	65%			
	Total Nitrogen	use prior to development	45%			
* Based on increased pollution generated from development without treatment						

Figure 5 – Stormwater Quality Targets (Source: Tamworth Regional Council's Fact Sheet)

Some sites, however, that are part of a Council-approved Stormwater Strategy or Water Sensitive Design Statement, may be required to meet different stormwater quality targets. Council has been contacted to confirm whether the proposed site is included in this, and we are still waiting for their response to this date. Refer to Appendix B for Council's correspondence.

The Water Sensitive Urban Design (WSUD) for the stormwater runoff on site can be treated by a combination of rainwater reuse tank, pit-insert filter baskets and swales. Stormwater quality reduction targets and maintenance of treatment measures can also be met through a combination of the following treatment options;

- Constructed Wetlands (preferred over bioretention basins and ponds)
- Operation and Maintenance Plan
- Trash racks (preferred over GPTs)
- Ocean Protect StormFilter Cartridges (or equivalent)
- Ocean Protect Oceanguard Pit Inserts (or equivalent)
- Rainwater reuse tanks
- Swales, bioretention swales and buffer strips
- Bioretention basins
- Raingardens

#### 5.4.1 MUSIC Modelling

The proposed stormwater quality treatment train will be modelled using the Model for Urban Stormwater Improvement Conceptualisation (MUSIC) to ensure pollutant load target reductions are met during continued site operation.

MUSIC simulates the performance of a group of stormwater management measures, configured in series or in parallel to form a "treatment train" against historic rainfall event data sets. It is the industry standard water quality modelling software developed by the MUSIC development team of the Cooperative Research Centre for Catchment Hydrology (CRCCH). The MUSIC user manual suggests that the time-step should not exceed the time of concentration of the smallest sub-catchment however due consideration must also be made regarding the shortest detention time of nodes within the treatment train.

Since Tamworth Regional Council does not have an available MUSIC link, the 6-minute rainfall data from the closest rainfall station, Tamworth Airport Station no. 055054 will be adopted for the modelling.

#### 5.5 Operations and Maintenance

Regular maintenance of stormwater infrastructure, particularly stormwater quality treatment devices will be required to ensure they function as intended for the design life. Access roads will need to be assessed to ensure maintenance vehicles such as vacuum trucks are able to access the stormwater quality devices.

Any proposed water quality tank will need to be designed with an adequate number of access hatches in accordance with Australian Standards and the local Council requirements.

#### 5.6 Erosion and Sediment Control

An erosion and sediment control plan (ESCP) is to be implemented during the construction stage to mitigate soil erosion and control the discharge of stormwater laden with sediment, nutrients and other pollutants to adjoining properties, bushland, roadways or receiving water bodies. Stormwater controls on site are detailed in ESCPs which will be in accordance with regulatory authority guidelines including Landcom NSW's Managing Urban Stormwater, Soils and Construction ("Blue Book").

The disturbance of the site during construction must be controlled through erosion prevention and sediment control measures. A sediment basin will be required at the lowest point of the site to capture runoff from the construction site. A silt fence will prevent silt and waste being washed into neighbouring sites and streets. It can be integrated with safety fencing. A catch drain with hay bales will be utilised to carry and treat site runoff which will then be captured by a sedimentation basin that will be installed at the low point of site excavation. At the point of entry to site, cattle grids are required to ensure that vehicles and machinery leave the site with clean wheels. Pits will have silt protection installed to prevent silt from entering the stormwater system during construction.

Refer to Appendix A for details of the erosion and sediment control plan for the development site.

#### 6.0 Ground and Water Conditions

As per the Geotechnical investigation report by JK Geotechnics, the proposed building floor levels, carpark, landscaping and all external levels are above the inferred groundwater table and is not expected to cause significant quantities of groundwater seepage. The investigation encountered groundwater seepage during the borehole drilling at approximately at RL371m to RL372.5m. Groundwater seepage was further identified upon completion of the drilling at approximate levels of RL370.5m to RL372.5m. It is noted that no longer term monitoring of groundwater levels was carried out.

Refer to Figure 9 below for location and depths of groundwater observed on site. For further details, refer to JK Geotechnics' original report.




Figure 6 – Borehole Location and Groundwater Depths

### 7.0 Surface Impact Assessment

The proposed development will have little impact on the existing surface water conditions as the design intends to match the existing drainage scenario and reduce the flows. The proposed stormwater system and overland flow paths will reduce flows from the site which will only further protect the downstream ecology. Further, the introduction of water quality treatments will protect the receiving bodies from the pollutants introduced by increased impervious surfaces.

As such, the proposed drainage design will not adversely impact downstream ecosystems, nor impact existing hydrological systems.

### 8.0 Project Risks

The following risks in relation to the school development have been identified as outstanding in the concept stage and are subject to further investigation and advice:

 The water quality requirements discussed in this report have been determined from review of Council's DCP, consultation with Council, other supporting. This will be developed upon confirmation with Council, and as the architectural and landscape design progresses to ensure that the areas are accurate, and the required water quality measures be adjusted accordingly.

### 9.0 Preparation for Schematic Design Phase

#### 9.1 Intended Focus for Schematic Design Phase

The following list highlights the civil focus as the project goes into concept and schematic design phase:

- Design development of water quality and stormwater management including development of preliminary MUSIC modelling.
- Design development of bulk earthworks cut and fill, stormwater drainage network, external levels, and grading.
- Civil design and documentation for submission via the proposed planning pathway.

#### 10.0 Conclusion

This report provides a summary of the civil engineering and stormwater management requirements to inform the concept design phase for the new UNE- Tamworth Central Campus development. Stormwater is required to comply with Tamworth Regional Council requirements including provision of erosion and sediment control and stormwater quality treatment.

Prepared by TTW (NSW) PTY LTD

Authorised By TTW (NSW) PTY LTD

JEMA LOPEZ
Civil Engineer

**NEMESIO BIASON JR.** Associate Director

P:\2022\2218\221823\Reports\TTW\Civil\231122\231122 Civil Engineering Concept Design Report.docx

# Appendix A

# **Civil Engineering Drawings**

# UNIVERSITY OF NEW ENGLAND

# TAMWORTH CENTRAL CAMPUS NEW SOUTH WALES 2340





DRAWING SHEET LIST				
DRAWING NO.	DRAWING TITLE			
221823-TTW-00-DR-CV-00000	COVER SHEET			
221823-TTW-00-DR-CV-00001	GENERAL NOTES SHEET			
221823-TTW-00-DR-CV-00021	SEDIMENT AND EROSION CONTROL PLAN			
221823-TTW-00-DR-CV-00022	SEDIMENT AND EROSION CONTROL DETAILS			
221823-TTW-00-DR-CV-00031	BULK EARTHWORKS PLAN			
221823-TTW-00-DR-CV-00035	BULK EARTHWORKS SECTIONS SHEET 1			
221823-TTW-00-DR-CV-00036	BULK EARTHWORKS SECTIONS SHEET 2			
221823-TTW-00-DR-CV-00041	SITEWORKS AND STORMWATER PLAN SHEET 1			
221823-TTW-00-DR-CV-00101	DETAILS SHEET 1			
221823-TTW-00-DR-CV-00102	DETAILS SHEET 2			

LOCALITY PLAN
NTS

# PRELIMINARY NOT TO BE USED FOR CONSTRUCTION

Archite

| Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archite | Archi

architectus™



UNIVERSITY OF NEW ENGLAND
TAMWORTH

heet Subject	
COVER SHEET	

 Scale : A1
 Drawn
 Authorised

 NTS
 SS
 NB

 Job No
 Drawing No
 Revision

 221823-TTW-00-DR-CV-00000
 P1

Plot File Created: Aug 25, 2023 - 4:00pm

Taylor Thomson Whitting makes no guarantees that the boundary or

Taylor Thomson Whitting will accept no liabilities for boundary inaccuracies. The contractor/builder is advised to check/confirm all boundaries in relation to all proposed work prior to the commencement **CONCRETE NOTES** of construction. Boundary inaccuracies found are to be reported to the superintendent prior to construction starting.

#### **GENERAL NOTES**

easement information shown is correct.

1. Contractor must verify all dimensions and existing levels on site prior to commencement of works. Any discrepancies to be reported to the SUPERINTENDENT

2. Strip all topsoil from the construction area. All stripped topsoil shall be disposed of off-site unless directed otherwise.

3. Make smooth connection with all existing works. 4. Compact subgrade under buildings and pavements to minimum 98% standard maximum dry density in accordance with AS 1289 5.1.1. Compaction under buildings to extend 2m minimum beyond building

5. All work on public property, property which is to become public property, or any work which is to come under the control of the Statutory Authority; the Contractor is to ensure that the drawings used for construction have been approved by all relevant authorities prior to commencement site.

6. All work on public property, property which is to become public property, or any work which is to come under the control of the Statutory Authority is to be carried out in accordance with the requirements of the relevant Authority. The Contractor shall obtain these requirements from the Authority. Where the requirements of the Authority are different to the drawings and specifications, the requirements of the Authority shall be applicable.

7. For all temporary batters refer to geotechnical recommendations.

# REFERENCE DRAWINGS

1. These drawings have been based from, and to be read in conjunction with the following Consultants drawings. Any conflict to the drawings must be notified immediately to the Engineer.

Consultant I	Dwg Title	Dwg No	Rev	Date
	GA - GROUND LEVEL	DA1001	-	27.07.23
TYRRELLSTUDIO	GA PLAN	TW-L111	01	08.08.23
BAXTER GEO	SURVEY	0789-160229	В	04.02.16

# SURVEY AND SERVICES INFORMATION SURVEY

Origin of levels : CONTACT THE SURVEYOR Datum of levels : AHD Coordinate system: CONTACT THE SURVEYOR Survey prepared by: BAXTER GEO Setout Points : CONTACT THE SURVEYOR

Taylor Thomson Whitting does not guarantee that the survey information shown on these drawings is accurate and will accept no liability for any inaccuracies in the survey information provided to us from any cause

# **UNDERGROUND SERVICES - WARNING**

The locations of underground services shown on Taylor Thomson Whittings drawings have been plotted from diagrams provided by service authorities. This information has been prepared solely for the authorities own use and may not necessarily be updated or accurate.

The position of services as recorded by the authority at the time of installation may not reflect changes in the physical environment subsequent to installation. Taylor Thomson Whitting does not guarantee that the services

information shown on these drawings shows more than the presence or absence of services, and will accept no liability for inaccuracies in the services information shown from any cause whatsoever. The Contractor must confirm the exact location and extent of services prior to construction and notify any conflict with the drawings immediately to the Engineer/Superintendent.

The contractor is to get approval from the relevant state survey department, to remove/adjust any survey mark. This includes but is not limited to; State Survey Marks (SSM), Permanent Marks (PM), cadastral reference marks or any other survey mark which is to be

#### removed or adjusted in any way.

Taylor Thomson Whitting plans do not indicate the presence of any survey mark. The contractor is to undertake their own search.

# **CONCRETE FINISHING NOTES**

1. All exposed concrete pavements are to be broomed finished. 2. All edges of the concrete pavement including keyed and dowelled joints are to be finished with an edging tool.

3. Concrete pavements with grades greater than 10 % shall be heavily broomed finished.

4. Carborundum to be added to all stair treads and ramped crossings U.N.O.

**EXPOSURE CLASSIFICATION:** External: B2

as defined in AS 1379.	·		Ü
Location	AS 1379 fc MPa at 28 days	Specified Slump	Nominal Agg. Siz
Kerbs	S20	80	20
Retaining wall footing	S40	80	20

Place concrete of the following characteristic compressive strength f'c

Use Type 'GP' cement, unless otherwise specified. All concrete shall be subject to project assessment and testing to AS

Consolidate by mechanical vibration. Cure all concrete surfaces as directed in the Specification.

For all falls in slab, drip grooves, reglets, chamfers etc. refer to Architects drawings and specifications. . Unless shown on the drawings, the location of all construction joints

shall be submitted to Engineer for review. No holes or chases shall be made in the slab without the approval of

the Engineer.
Conduits and pipes are to be fixed to the underside of the top reinforcement layer. Slurry used to lubricate concrete pump lines is not to be used in any

structural members All slabs cast on ground require sand blinding with a Concrete

#### Underlay **FORMWORK**

The design, certification, construction and performance of the formwork, falsework and backpropping shall be the responsibility of the contractor. Proposed method of installation and removal of formwork is to be submitted to the superintendent for comment prior to work being carried out.

# **CIVIL SAFETY IN DESIGN**

Taylor Thomson Whitting (NSW) Pty Ltd operates under Safe Work Australia's Code of Conduct for the Safe Design of

These drawings shall be read in conjunction with the Taylor Thomson Whitting Transfer of Information Letter and Civil Risk and Solutions Register. Under the Code of Conduct it is the Client's responsibility to provide a copy of the Civil Risk and Solutions Register to the

Principal Contractor. It is the Principal Contractor's responsibility to review the hazards and risks identified during the design process to ensure a safe workplace is maintained for the construction. maintenance and eventual demolition of the civil infrastructure

# **DBYD SERVICES NOTE**

"Public Service Utility information shown on plan has been complied from information received from Dial Before You Dig inquiry, reference Number 34171774, which was obtained on 10/05/2023. Unless specifically shown otherwise, this location and depth of services shown on this plan have not been verified.

The location of services shown on this drawing have been plotted as accurately as possible from diagrams provided by service authorities and should be confirmed by site inspection."

# **KERBING NOTES**

are shown.

Includes all kerbs, gutters, dish drains, crossings and edges.

1. All kerbs, gutters, dish drains and crossings to be constructed on minimum 75mm granular basecourse compacted to minimum 98% modified maximum dry density in accordance with AS 1289 5.2.1. 2. Expansion joints (EJ) to be formed from 10mm compressible cork filler board for the full depth of the section and cut to profile. Expansion joints to be located at drainage pits, on tangent points of curves and elsewhere at 12m centres except for integral kerbs where the expansion joints are to match the joint locations in slabs. 3. Weakened plane joints to be min 3mm wide and located at 3m

centres except for integral kerbs where weakened plane joints are to match the joint locations in slabs.

4. Broomed finished to all ramped and vehicular crossings, all other kerbing or dish drains to be steel float finished.

5. In the replacement of kerbs -Existing road pavement is to be sawcut 900mm from lip of gutter. Upon completion of new kerbs, new basecourse and surface is to be laid 900mm wide to match existing materials and thicknesses.

Existing allotment drainage pipes are to be built into the new kerb with a 100mm dia hole. Existing kerbs are to be completely removed where new kerbs

# **JOINTING NOTES**

#### **Vehicular Pavement Jointing**

All vehicular pavements to be jointed as shown on drawings. 2. Dowelled expansion joints (DEJ) should generally be located at a maximum of 24.0m centres. Dowel bars to be plain round steel bars of Grade 250N, 450mm long and placed at 300mm spacing. Dowel diameter as specified below U.N.O

	Design base thickness, D (mm)	Dowel diameter (mm)
	150 < D ≤ 190	20
	200 < D ≤ 240	24
	250 < D ≤ 270	30
	280 < D ≤ 340	33
	D > 350	36 (500 long)
3.	Dowelled expansion joint type A	(DEJA) should generally be

located longitudinally and at a maximum of 24.0m centres. Refer

to DEJA detail provided on detail sheets. 4. Sawn joints should generally be located at a maximum of 6.0m centres or 1.5 x the spacing of perpendicular sawn joints

Provide 10mm wide full depth expansion joints (EJ) between buildings/structures and all concrete or unit pavers.

Vehicular pavement jointing as follows.

The timing of the saw cut is to be confirmed by the contractor on site. Site conditions will determine how many hours after the concrete pour before the saw cuts are commenced. Refer to the specification for weather conditions and temperatures required.

		— Face o	f ke	b				
જ	S E	S		જ	S	DEJ	જ	
	SJ_	6m MAX	- - -		24m MAX			     
	DEJA		24	MAX	6m MAX			 
	SJ_				 	 	; 	 
	    - SJ				24m MAX	<b>-</b>		   <del> </del>
	 		24m	MAX			Ì	 

# 


 Face of building or structure Pedestrian Footpath Jointing

maximum of 8.0m spacing U.N.O.

1. Expansion joints (EJ) are to be located where possible at tangent points of curves and elsewhere at max 6.0m centres. Weakened plane joints (WPJ) are to be located at a max 1.5 x width of the pavement.

Where possible joints should be located to match kerbing and / or adjacent pavement joints.

4. All pedestrian footpath jointings as follows U.N.O. 



# Wall Jointing

For concrete walls, weakened plane joints (WPJ) or control joints (CJ) to be located at a maximum of 8.0m centres. Expansion joints (EJ) to be located at a maximum of 30.0m centres U.N.O. For blockwork walls, dowelled control joints (CJ) to be located at

# REINFORCEMENT NOTES

size in millimetres of the reinforcement.

1. Fix reinforcement as shown on drawings. The type and grade is indicated by a symbol as shown below. On the drawings this is followed by a numeral which indicates the

N. Hot rolled ribbed bar grade D500N grade R250N R. Plain round bar SL. Square mesh grade 500L RL. Rectangular mesh grade 500L

2. Provide bar supports or spacers to give the following concrete cover to all reinforcement unless otherwise noted

on drawings. Footings - 50 top, 50 bottom, 50 sides. 30 generally. - 30 when cast in forms but later exposed to

Cover to reinforcement ends to be 50 mm u.n.o. Provide N12-450 support bars to top reinforcement as required, Lap 500 U.N.O.

weather or ground.

Maintain cover to all pipes, conduits, reglets, drip grooves

when cast directly in contact with ground.

. All cogs to be standard cogs unless noted otherwise. Fabric end and side laps are to be placed strictly in accordance with the manufacturers requirements to achieve a full tensile lap. Fabric shall be laid so that there is a maximum of 3 layers at any location.

8. Laps in reinforcement shall be made only where shown on the drawings unless otherwise approved. Lap lengths as per

# **RETAINING WALLS**

1. Drainage shall be provided as shown on the drainage drawings. 2. Backfilling shall be carried out after grout or concrete has reached a minimum strength of 0.85 f'c. Backfilling shall be approved granular material compacted in layers not exceeding

200mm to 95% Standard compaction unless noted otherwise. 3. Provide waterproofing to back of walls as specified or noted. 4. Where retaining walls rely on connecting structural elements for stability, do not backfill against the wall unless it is adequately propped or the elements have been constructed

and have sufficient strength to withstand the loads. 5. For all temporary batters obtain geotechnical engineers recommendations.

# STORMWATER DRAINAGE NOTES

1 Stormwater Design Criteria: (A) Average exceedance probability

1% AEP for roof drainage to first external pit 5% AEP for paved and landscaped areas (B) Rainfall intensities -Time of concentration: 5 minutes

(C) Rainfall losses -Impervious areas: IL = 1.5 mm , CL = 0 mm/hr Pervious areas: IL = 7.2mm, CL = 0.68mm/hr

3. Pipes up to 300 dia may be sewer grade uPVC with solvent welded joints, subject to approval by the engineer

to approval by 6. Enlargers, connections and junctions to be manufactured fittings where pipes are less than 300 dia.

8. Grates and covers shall conform with AS 3996-2006, and AS 1428.1 for access requirements. 9. Pipes are to be installed in accordance with AS 3725. All

bedding to be type H2 U.N.O. 10. Care is to be taken with invert levels of stormwater lines. Grades shown are not to be reduced without approval. 11. All stormwater pipes to be 150 dia at 1.0% min fall U.N.O. 12. Subsoil drains to be slotted flexible uPVC U.N.O.

#### 1% AEP = 211mm/hr 5% AEP = 160mm/hr

. Pipes 300 dia and larger to be reinforced concrete Class " " approved spigot and socket with rubber ring joints U.N.O.

4. Equivalent strength VCP or FRP pipes may be used subject to approval. . Precast pits may be used external to the building subject

7. Where subsoil drains pass under floor slabs and vehicular pavements, unslotted uPVC sewer grade pipe is to be used.

13. Adopt invert levels for pipe installation (grades shown are

only nominal).

# SAFETY IN DESIGN

Contractor to refer to Appendix B of the Civil Specification for the Civil Risk and Solutions Register.

# **EXISTING SERVICES**

Contractor to be aware existing services are located within the site. Location of all services to be verified by the Contractor prior to commencing works. Contractor to confirm with relevant authority regarding measures to be taken to ensure services are protected or procedures are in place to demolish and/or relocate.

**EXISTING STRUCTURES** Contractor to be aware existing structures may exist within the site. To prevent damage to existing structure(s) and/or personnel, site

# **EXISTING TREES**

structure(s).

Contractor to be aware existing trees exist within the site which need to be protected. To prevent damage to trees and/or personnel, site works to be carried out as far as practicably possible from existing trees. Advice needs to be sought from Arborist and/or Landscape Architect on measures required to protect trees.

works to be carried out as far as practicably possible from existing

#### **GROUNDWATER**

Contractor to be aware ground water levels are close to existing surface level. Temporary de-watering may be required during construction works.

#### **EXCAVATIONS**

Deep excavations due to stormwater drainage works is required. Contractor to ensure safe working procedures are in place for works. All excavations to be fenced off and batters adequately supported to approval of Geotechnical Engineer.

# **GROUND CONDITIONS**

Contractor to be aware of the site geotechnical conditions. Refer to geotechnical report by JK Geotechnics (Ref: 36020PNrpt) for details.

**HAZARDOUS MATERIALS** Existing asbestos products & contaminated material may be present on site. Contractor to ensure all hazardous materials are identified prior to commencing works. Safe working practices as per relevant authority to be adopted and appropriate PPE to be used when handling all hazardous materials. Refer to geotechnical/environmental

# **CONFINED SPACES**

Contractor to be aware of potential hazards due to working in confined spaces such as stormwater pits, trenches and/or tanks. Contractor to provide safe working methods and use appropriate PPE when entering confined spaces.

report by JK Geotechnics (Ref: E36020PDrpt) for details.

# MANUAL HANDLING

Contractor to be aware manual handling may be required during construction. Contractor to take appropriate measures to ensure manual handling procedures and assessments are in place prior to commencing works.

# WATER POLLUTION

Contractor to ensure appropriate measures are taken to prevent pollutants from construction works contaminating the surrounding environment. SITE ACCESS/EGRESS

Contractor to be aware site works occur in close proximity to

#### footpaths and roadways. Contractor to erect appropriate barriers and signage to protect site personnel and public.

**VEHICLE MOVEMENT** Contractor to supply and comply with traffic management plan and provide adequate site traffic control including a certified traffic marshall to supervise vehicle movements where necessary.

# EXTENT OF WORKS

× F22.20 FINISHED SURFACE LEVEL 22.50 MAJOR FINISHED SURFACE CONTOUR 0.5m INTERVAL 22.10 MINOR FINISHED SURFACE CONTOUR

KERB AND GUTTER KO KERB ONLY

FLUSH KERB

0.1m INTERVAL

VEHICULAR CROSSING

PEDESTRIAN KERB RAMP

TAPER KERB TO ZERO HEIGHT OVER 1.0m STORMWATER PIPE, FLOW DIRECTION STORMWATER PIPE, FLOW DIRECTION

ulL10.00 UPSTREAM PIPE INVERT LEVEL PIPE SIZE AND STRENGTH CLASS Ø600 '2' 1.25% PIPE GRADIENT Q=345L/s PEAK DESIGN FLOW

DOWNSTREAM PIPE INVERT LEVEL dIL9.65 JUNCTION PIT

SAG KERB INLET PIT

**GRATED INLET PIT** HAUNCHED GRATED INLET PIT

ON-GRADE KERB INLET PIT GROSS POLLUTANT TRAP

D01-2 DRAINAGE LINE AND PIT NUMBER **GRATED DRAIN** 

SUBSOIL DRAINAGE LINE, Ø100mm U.N.O. FLUSHING POINT ---- INTERMEDIATE RISER

DP DOWNPIPE --> --- GRASS CATCH DRAIN

-→ -→ OVERLAND FLOW PATH

BLOCKWORK RETAINING WALL

BATTER SLOPE

EXISTING SERVICES LEGEND -----eEA----- EXISTING OVERHEAD ELECTRICAL eEU EXISTING UNDERGROUND ELECTRICAL

eT——— eXISTING TELECOMMUNICATIONS —— EXISTING SEWER

eW EXISTING WATER

eSW EXISTING STORMWATER

———eG——— EXISTING GAS

# TOK TOP OF KERB eRL EXISTING SURFACE LEVEL

OL OBVERT LEVEL

**ABBREVIATIONS** 

IOK INVERT OF KERB F FINISHED SURFACE LEVEL RCL ROAD CENTRELINE F\* FUTURE SURFACE LEVEL BDY BOUNDARY FFL FINISHED FLOOR LEVEL

This drawing is copyright and is the property of TAYLOR THOMSON WHITTING (NSW) Pty Ltd and must not be used without authorisation

**RELEVANT NOTES ON DRAWING C01** 

THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL

TOW TOP OF WALL SSL STRUCTURAL SLAB LEVEL BOW BOTTOM OF WALL CHAINAGE TP TANGENT POINT CL COVER LEVEL IL INVERT LEVEL

**WORKS NEAR EXISTING SERVICES** ALL EXISTING UNDERGROUND SERVICES ARE TO BE LOCATED

ON SITE PRIOR TO COMMENCING WORKS

TREES IN THE VICINITY OF WORKS ARE NOT DAMAGED

DURING CONSTRUCTION ACTIVITIES

TWL TOP WATER LEVEL

**WORKS NEAR EXISTING TREES** RECAUTIONS ARE TO BE UNDERTAKEN TO ENSURE EXISTING

**HIGH PRESSURE GAS MAIN** PRECAUTIONS ARE TO BE UNDERTAKEN TO ENSURE HIGH PRESSURE GAS MAIN IN THE VICINITY OF WORKS IS NOT

DAMAGED DURING CONSTRUCTION ACTIVITIES.

LIAISE WITH THE ASSET OWNER AS REQUIRED

HIGH VOLTAGE ELECTRICAL CABLE PRECAUTIONS ARE TO BE UNDERTAKEN TO ENSURE HIGH VOLTAGE CABLE IN THE VICINITY OF WORKS IS NOT DAMAGED **DURING CONSTRUCTION ACTIVITIES.** 

LIAISE WITH ASSET OWNER AS REQUIRED

**EXISTING STORMWATER ASSETS** SIZE, INVERT LEVEL AND CONDITION OF ALL AFFECTED EXISTING STORMWATER ASSETS TO BE CONFIRMED PRIOR TO COMMENCING WORKS

> THIS DRAWING MUST BE PRINTED IN COLOUR

PRELIMINARY NOT TO BE USED FOR CONSTRUCTION

NOTES AND LEGEND SHEET

1:1

NB

Plot File Created: Aug 25, 2023 - 4:00pm

P1 ISSUE FOR INFORMATION NB SS 25.08.23 Eng Draft Date Rev Description Eng Draft Date Rev Description Eng Draft Date Rev Description


architectus™





UNIVERSITY OF NEW ENGLAND TAMWORTH


Scale : A1 SS Drawing No


221823-TTW-00-DR-CV-00001




















SCALE 1: 20

NOTE
ENDS OF SILTATION FENCE TO RETURNED
UP SLOPE TO PREVENT RUNOFF

SILTATION FENCE DETAIL

PRELIMINARY
NOT TO BE USED
FOR CONSTRUCTION

architectus™



UNIVERSITY OF NEW ENGLAND
TAMWORTH

Sheet Subject
SEDIMENT AND EROSION
CONTROL PLAN


 Scale : A1
 Drawn
 Authorised


 1:250
 SS
 NB


 Job No
 Drawing No
 Revision


 221823-TTW-00-DR-CV-00022
 P1

Plot File Created: Aug 25, 2023 - 4:13pm









THIS DRAWING MUST BE PRINTED IN COLOUR

# PRELIMINARY NOT TO BE USED FOR CONSTRUCTION


architectus™



UNIVERSITY OF NEW ENGLAND
TAMWORTH

Sheet Subject

DETAILS SHEET 1



+61 2 9439 7288 | L6 73 MILLER STREET NORTH SYDNEY NSW 2060

Eng Draft Date Rev Description

Rev Description

Eng Draft Date Rev Description

Eng Draft Date

# **Appendix B**

# **Council Correspondence**

#### Jema Lopez

From: Jema Lopez

Sent: Wednesday, 28 June 2023 4:32 PM

**To:** Pugh, Aidan; Brake, Steve

**Subject:** RE: Prince of Wales Park Flooding and Stormwater Requirements

Good afternoon Aidan, Steve,

I hope you both have been well.

I was wondering if there have been any updates to the below regarding the WSUD requirements for the site?

Thank you and regards,



#### Jema Lopez | Civil Engineer

+61 426 053 329 | +61 2 9067 5017 | jema.lopez@ttw.com.au

TTW Engineers | Sydney
Read our latest news here

From: Jema Lopez

Sent: Friday, May 12, 2023 12:40 PM

To: Pugh, Aidan <a.pugh@tamworth.nsw.gov.au>; Brake, Steve <s.brake@tamworth.nsw.gov.au>

Cc: Nemesio Biason Jr < Nemesio. Biason Jr @ttw.com.au>

Subject: RE: Prince of Wales Park Flooding and Stormwater Requirements

Hi Aidan,

Thank you for the confirmation and for providing the additional information below.

We will await advice in relation to the WSUD requirements for the site.



#### Jema Lopez | Civil Engineer

+61 426 053 329 | +61 2 9067 5017 | jema.lopez@ttw.com.au

**TTW Engineers** | Sydney

Read our latest news here

From: Pugh, Aidan <a.pugh@tamworth.nsw.gov.au>

Sent: Thursday, May 11, 2023 12:21 PM

To: Jema Lopez < jema.lopez@ttw.com.au >; Brake, Steve < s.brake@tamworth.nsw.gov.au >


Cc: Nemesio Biason Jr <nemesio.biasonJr@ttw.com.au>

Subject: RE: Prince of Wales Park Flooding and Stormwater Requirements

[External Email]: Do not click links or open attachments unless you recognize the sender and know the content is safe.


Hi Jema,

The Old Velodrome Site is protected by the Tamworth CBD levee along Peel River as shown below:



Council does not consider this location to be within the Flood Planning Area as defined in the LEP so the flood related development controls in the LEP do not apply.

This site has been identified in Council's draft Flood Risk Management Plan (currently on public exhibition) as being effected by overland flow. See the 1%AEP overland flow map below. During a development application you should consider the flows entering the site from Roderick Street especially considering that the current extent is limited by the velodrome embankment. I have also included a cross section through the LiDAR surface (green) and 1% flood surface (red) below.



Stormwater detention is not required at this site.

I will have to pass you on to our Development area to provide feedback on the WSUD requires. @Steve – are you able to comment on the status of the WSUD DCP amendment? Or pass Jema's last question on to someone who can?

Cheers,

#### **Aidan Pugh**

Stormwater Engineer

P 02 6767 5018 | E a.pugh@tamworth.nsw.gov.au

PO Box 555 Tamworth NSW 2340 www.tamworth.nsw.qov.au

From: Jema Lopez < <u>jema.lopez@ttw.com.au</u>>
Sent: Thursday, 11 May 2023 11:48 AM


**To:** Pugh, Aidan <a.pugh@tamworth.nsw.gov.au> **Cc:** Nemesio Biason Jr <a href="mailto:nemesio.biasonJr@ttw.com.au">nemesio.biasonJr@ttw.com.au</a>

**Subject:** Prince of Wales Park Flooding and Stormwater Requirements

#### Good day Aidan,

Thank you for your time on the phone. As per our discussion, could you please confirm the following items for a proposed school campus at the Prince of Wales Park on the corner of Peel Street and Roderick Street in Tamworth?

- The Prince of Wales Park is protected by a levee approximately 1.1-1.6m west along Peel River as shown below.



 The proposed development does not initially require any freeboard, however will need to comply with the flood planning level as specified in Tamworth Regional LEP 2010 which is 1:100 ARI flood level plus 0.5m freeboard.

The flood planning level adopted in the Tamworth Regional Local Environmental Plan 2010 is defined as the level of a 1:100 ARI (average recurrent interval) flood event plus 0.5 metres freeboard.

Additionally, I am seeking to confirm the stormwater requirements for a proposed development.

- On-Site Detention (OSD) is to be designed in accordance with Council's *Engineering Design Minimum Standards for Subdivisions & Developments (V1, March 2019)* Chapter 3.10.3.4 shown below, which is to match the existing undeveloped peak discharge up to and including the 100-year ARI storm event.

#### 3.10.3.4 DESIGN CRITERIA

All retention/detention structures are to be designed utilising:

- Hydrographs produced by an acceptable method of unit graph theory or mathematical modelling; and
- Flood routing through the structure.

Retention/detention structures shall be designed to maintain the existing undeveloped discharges for the range of storm durations and frequencies from 1 year ARI events up to and including 100 year ARI events.

The methods described in Section 3.6.3 of these Standards may be used to calculate peak flows.

Retention/detention structures with downstream established areas and no clear and safe overland flow paths shall be designed for the peak 100 year ARI storm with consideration of the sensitivity of the design given to 200 year ARI events.

The peak storm duration with retention/detention structures is to be confirmed by the *Developer's Representative*. The critical duration is likely to be longer than without retention/detention. A graph showing the range of peak flood levels in the structure and peak discharges from the structure are to be provided for all storm events examined. Consideration must be given to areas downstream to ensure that changes in timing of peak flows at the confluence of downstream reaches is not adversely impacted by construction of the structure.

A sensitivity analysis must be undertaken for a range of variables (catchment roughness, link lags etc.) to determine how sensitive the design is to minor changes in these variables.

Rainwater tanks either installed or intended to be installed as part of the development shall not be used in retention/detention basin design calculations. The volume of storage in pits and pipes in the minor system is also to be ignored.

- A Water Sensitive Design Statement (WSDS) is to be provided and the development must comply with Council's Fact Sheet: Water Sensitive Design Statements shown below. It was also noted on the fact sheet that some sites are part of Council-approved Stormwater Strategy or WSDS may be required to meet different stormwater quality targets that what is shown below. Could you please confirm what target reduction loads should be adopted for the site?

#### Requirements of a Water Sensitive Design Statement

A Water Sensitive Design Statement is supported by figures and diagrams which demonstrate how the development satisfies the objectives of the Development Control Plan and the Water Sensitive Design performance criteria as outlined in quality and quantity targets.

Stormwater Quality Targets - Subdivision

Site Characteristics		Lots over 2,000 m <sup>2</sup> in size	Lots less than 2,000 m <sup>2</sup> in size
	Gross Pollutants	90%	90%
Target Reduction Loads *	Total Suspended Solids	Neutral or Beneficial Effect on Water	80%
	loads of polluta from future development m be equivalent to	development must be equivalent to or less than that from	65%
	Total Nitrogen	use prior to development	45%

Stormwate	r Quantity	Targets
-----------	------------	---------

Stormwater Quantity	Flow rates (for environmental and infrastructure protection)
Target	Retention/detention structures shall be designed to maintain the existing undeveloped discharges for the range of storm durations and frequencies from 5 year ARI events up to and including 100-year ARI events.
	Retention/detention structures with downstream established areas and no clear and safe overland flow paths shall be designed for the peak 100-year ARI storm with consideration of the sensitivity of the design given to 200-year ARI events.
Intent	Reduce the likelihood of increased rates of bed and bank erosion and damage to benthic habitat in waterways.
	Ensure that the development does not result in increased stormwater flows that exceed the capacity of the external stormwater drainage infrastructure and/or exacerbate overland flow problems.

Thank you and please let me know if I have missed any flooding/stormwater-related requirements, or misinterpreted any of the above.

Best regards,



#### Jema Lopez | Civil Engineer

+61 426 053 329 | +61 2 9067 5017 | jema.lopez@ttw.com.au

TTW Engineers | Sydney

Read our latest news here