



Acoustic Assessment

Stringybark Solar Farm

Prepared for Stringybark Solar Farm Pty Ltd
Report Reference: 19SYA0044 R01_3



About TTM

For 30 years, we've been at the centre of the Australian development and infrastructure industry. Our unique combination of acoustics, data, traffic and waste services is fundamental to the success of any architectural or development project.

We have over 50 staff, with an unrivalled depth of experience. Our industry knowledge, technical expertise and commercial insight allow us to deliver an exceptional and reliable service.

T: (02) 9418 3033

F: (02) 9418 3112

E: ttmnsw@ttmgroup.com.au



Revision Record

No.	Author	Reviewed/Approved	Description	Date
A	K Dhayam	-	Draft A – Issued to client	25/07/2019
0	K Dhayam	J Fox	Final – Issued to client	26/07/2019
1	K Dhayam	J Fox	Revision 1	7/08/2019
2	K Dhayam	J Fox	Revision 2 – Minor Changes	12/08/2019
3	K Dhayam	J Fox	Revision 3 – Additional Receiver	14/08/2019

Contents

1	Introduction.....	4
2	Site Description.....	5
3	Proposal.....	6
3.1	Noise Sensitive Receivers (NSRs).....	6
4	Noise Environment	8
5	Noise Criteria	9
5.1	DECC Interim Construction Noise Guideline	9
5.1.1	ICNG Noise Management Levels	9
5.2	NSW Noise Policy for Industry 2017	10
5.2.1	Project Intrusiveness Noise Level	11
5.2.2	Amenity noise levels and Project Amenity Noise Levels.....	11
5.2.3	Project Noise Trigger Level.....	12
5.3	Noise-enhancing Weather Conditions.....	13
6	Construction Noise Assessment.....	14
6.1	Construction Phases.....	14
6.2	Plant and Equipment Noise Source Levels	16
6.3	Assessment Methodology	19
6.4	Predicted Noise Impact Radius.....	20
6.5	Impacted Receivers	20
6.5.1	Highly Noise Affected	20
6.5.2	Exceedance of ICNG Noise Management Level.....	21
6.6	Discussion and Recommendations.....	22
6.7	Good Practice – Mitigation and Management	23
7	Construction Traffic Noise Assessment	24
7.1	Predicted Traffic Noise Impact and Discussion.....	25
8	Operational Noise Assessment.....	26
8.1	Operations Phase	26
8.2	Operational Source Levels.....	27
8.3	Assessment Methodology	27
8.4	Predicted Impact from Inverter Stations.....	28

8.5	Predicted Impact from Trackers.....	28
8.6	Substation and Transformers	28
8.7	Predicted Operational Impact	29
9	Conclusion	30
Appendix A	Extract from AS1055.2	31
Appendix B	Glossary	33

Table Index

Table 1:	List of Noise Sensitive Receivers within one kilometre from the Proposal Footprint.....	6
Table 2:	Average background noise levels for a noise area category R1.....	8
Table 3:	Residential – ICNG noise management levels	10
Table 4:	Minimum assumed RBLs and project intrusiveness noise levels.	11
Table 5:	Amenity noise levels.....	12
Table 6:	NSW Noise Policy for Industry evaluated criteria	12
Table 7:	Standard and noise-enhancing meteorological conditions	13
Table 8:	Construction phases.....	14
Table 9:	Plant and machinery for each phase	16
Table 10:	Predicted noise impact radius for each task.....	20
Table 11:	Impacted receivers	21
Table 12:	Operation and maintenance tasks	26
Table 13:	Summary of operations phase and associated equipment	27

Figure Index

Figure 1:	Locality Plan	5
Figure 2:	Assessed Noise Sensitive Receivers.....	7
Figure 3:	Construction Traffic Route	24

1 Introduction

TTM Consulting has been engaged by Stringybark Solar Farm Pty Ltd to conduct a construction and operational noise impact assessment for the proposed Stringybark Solar Farm (the Proposal), located approximately 14 km east of Armidale in NSW. The assessment includes the following:

- Construction noise assessment:
 - Identification of construction stages and associated activities including, specialised machinery and equipment used during the works
 - Assessment in accordance with the *NSW Interim Construction Noise Guideline*¹ (ICNG), and
 - Advice on practical and appropriate in-principle noise mitigation and management, where required.
- Operational noise impact assessment:
 - Assessment of the substation, inverters, transformers and other noise generating equipment in accordance with the *NSW Noise for Industry Policy (2017)*², and
 - Advice on practical and appropriate in-principle noise mitigation and management, where required.

¹ NSW Department of Environment and Climate Change (DECC) (2009), Interim Construction Noise Guideline


² NSW Environment Protection Authority (2017), Noise Policy for Industry

2 Site Description

The Proposal is located approximately 14 km east of Armidale and 6 km south-west of Argyle in NSW, within the Armidale Regional Local Government Area. The area surrounding the Proposal is generally characterised by agricultural land and low residential density.

Access to the Proposal are via Waterfall Way and Gara Road. The Development Envelope where the panels will be located and the off-site Substation footprint, and the transportation routes are shown in Figure 1.

Figure 1: Locality Plan



3 Proposal

The Proposal will have a nameplate capacity of 29.9MW and will generate electricity through the conversion of solar radiation to electricity using Photovoltaic (PV) panels, laid out across the Proposal site in a series of modules, mounted on a single axis tracking system with piled supports. Other infrastructure on site would include electrical invertors, underground electrical cabling, internal access tracks, operational buildings, vehicular access and parking areas, security fencing along with landscape screening.

The Proposal will connect to the national electricity grid via an offsite substation located approximately 1.5 km to the north of the Proposal adjacent to an existing Essential Energy 66 kV distribution line.

The transportation route for the substation component is proposed to be along Waterfall Way.

3.1 Noise Sensitive Receivers (NSRs)

Three residential dwellings have been identified to be within 1000 metres of the Development Envelope and/or offsite Substation footprint. The closest residential dwelling to the Substation footprint is at approximately 896 metres away.


Residential properties within one kilometre of the Proposal Footprint have been identified as shown in Figure 2 and are summarised in Table 1. These are referred to as noise sensitive receivers (NSRs) and have been the subject of this noise impact assessment to determine whether and analyse how they may potentially be adversely impacted by noise from the construction and operation of the Proposal.

Noise impact at properties located further away will be further reduced due to increased distance attenuation. Should the derived noise limits in this report be met at the identified closest NSRs, with or without noise mitigation and management measures, compliance with the noise criteria is also expected further away, including more than one kilometre from the Development Envelope and/or offsite Substation footprint.

Table 1: List of Noise Sensitive Receivers within one kilometre from the Proposal Footprint

Receiver Reference	Distance from NSRs to Solar Farm, in metres	
	Development Envelope	Substation/Transformers
NSR1	368	3226
NSR2	716	2784
NSR3	2576	1073
NSR4	1537	896

Figure 2: Assessed Noise Sensitive Receivers



4 Noise Environment

The site is located in a rural area with an acoustic environment that is dominated in most parts by natural sounds, generally characterised by low background noise levels.

For the assessment, the identified noise sensitive receivers are expected to experience a similar acoustic environment with low background noise levels.

The background noise levels of the area have therefore been estimated by referring to Appendix A of Australian Standard AS 1055.2³. The standard provides estimated average background noise levels for different residential areas in Australia, which may be used as a guideline.

In accordance with Appendix A of AS 1055.2 (extract attached in Appendix A of this report), the noise area category R1 (category with lowest background noise levels) is relevant to the site and assessment. The corresponding average background noise levels for Category R1 are summarised in Table 2.

Table 2: Average background noise levels for a noise area category R1

Time period*	Average background noise level, L ₉₀ , in dB(A)
Day	40
Evening	35
Night	30
Note: * - Day-time period is from 0700 to 1800 (Monday to Saturday) and 0900 to 1800 (Sundays and Public Holidays) - Evening period is from 1800 to 2200 - Night-time period is from 2200 to 0700 (Monday to Saturday) and 2200 to 0900 (Sundays and Public Holidays)	

The above estimated background noise levels have been used to determine the applicable criteria for the assessment.

³ AS 1055.2:1997. Acoustics - Description and measurement of environmental noise - Application to specific situations

5 Noise Criteria

The main guidelines, standards and other policy documents relevant to the construction and operational noise impact assessment include:

- NSW Department of Environment and Climate Change (DECC) 2009, *Interim Construction Noise Guideline*.
- NSW Environment Protection Authority (2017), *NSW Noise Policy for Industry*.

5.1 DECC Interim Construction Noise Guideline

The DECC Interim Construction Noise Guideline (ICNG) provides guidelines for the assessment and management of noise from construction works. Construction activities and associated duration for the Proposal mean that it is considered a major construction project in accordance with the guideline. As such, the quantitative approach has been adopted for the construction noise assessment.

5.1.1 ICNG Noise Management Levels

The ICNG suggests the following standard hours for construction activities where noise is audible at residential premises:

- Monday to Friday, 7am to 6pm
- Saturday, 8am to 1pm, and
- No construction work is to take place on Sundays or public holidays.

Time restrictions on construction works are the primary management tool of the ICNG. The construction working hours of the Proposal are expected to be in line with the above standard hours.

The guideline also provides noise management levels for residential premises for both the recommended, and outside standard hours of construction. The noise management levels recommended for residential premises have been extracted from the ICNG and are summarised in Table 3.

Table 3: Residential – ICNG noise management levels

Time of day	Management level, $L_{Aeq,15\text{ min}}^*$	How to apply
Recommended standard hours: Monday to Friday 7am to 6pm Saturday 8am to 1pm No work on Sundays or public holidays	Noise affected $RBL^{\#} + 10\text{ dB} = 50\text{ dB(A)}$	The noise affected level represents the point above which there may be some community reaction to noise. - Where the predicted or measured $L_{Aeq,15\text{ min}}$ is greater than the noise affected level, the proponent should apply all feasible and reasonable work practices to meet the noise affected level. - The proponent should also inform all potentially impacted residents of the nature of works to be carried out, the expected noise levels and duration, as well as contact details.
	Highly noise affected 75 dB(A)	The highly noise affected level represents the point above which there may be strong community reaction to noise. - Where noise is above this level, the relevant authority (consent, determining or regulatory) may require respite periods by restricting the hours that the very noisy activities can occur, taking into account: - times identified by the community when they are less sensitive to noise (such as before and after school for works near schools, or mid-morning or mid-afternoon for works near residences) - if the community is prepared to accept a longer period of construction in exchange for restrictions on construction times.
Outside recommended standard hours	Noise affected $RBL + 5\text{ dB}$ = 40 dB(A) Evening period = 35 dB(A) Night-time period	- A strong justification would typically be required for works outside the recommended standard hours. - The proponent should apply all feasible and reasonable work practices to meet the noise affected level. - Where all feasible and reasonable practices have been applied and noise is more than 5 dB(A) above the noise affected level, the proponent should negotiate with the community. - For guidance on negotiating agreements see section 7.2.2 of the ICNG.
Note: * Noise levels apply at the property boundary that is most exposed to construction noise, and at a height of 1.5m above ground level. If the property boundary is more than 30m from the residence, the location for measuring or predicting noise levels is at the most noise-affected point within 30m of the residence. Noise levels may be higher at upper floors of the noise affected residence. [#] The Rating Background Level for each period is the median value of the Assessment Background Level values for the period over all the days measured. In this case the RBL has been assumed (Refer to Table 2)		

5.2 NSW Noise Policy for Industry 2017

The policy sets out the procedure to determine the project noise trigger levels relevant to assess noise from industrial developments. The project noise trigger level applies to existing NSRs.

The project noise trigger level provides a benchmark or objective for assessing a proposal or site. It is not intended for use as a mandatory requirement. The project noise trigger level is a level that, if exceeded, would indicate a potential noise impact on the community, and so ‘trigger’ a management response; for example, further investigation of mitigation measures.

The project noise trigger level is the lower (that is, the more stringent) value of the project intrusiveness noise level and project amenity noise level determined in Sections 2.3 and 2.4 of the policy.

5.2.1 Project Intrusiveness Noise Level

The Noise Policy for Industry states:

The intrusiveness of an industrial noise source may generally be considered acceptable if the level of noise from the source (represented by the L_{Aeq} descriptor), measured over a 15-minute period, does not exceed the background noise level by more than 5 dB when beyond a minimum threshold. This intrusiveness noise level seeks to limit the degree of change a new noise source introduces to an existing environment.

The intrusiveness noise level is determined as follows:

$$L_{Aeq, 15min} \leq \text{Rating Background Noise Level} + 5 \text{ dB}$$

5.2.1.1 Minimum Rating Background Noise Level and Intrusive Noise Levels

The rating background noise level (RBL) is the overall single-figure background level representing each assessment period (day/evening/night) over the whole monitoring period (as opposed to over each 24-hour period used for the assessment background level). The rating background noise level is the level used for assessment purposes.

However, for this assessment, noise monitoring was not conducted and instead RBLs have been assumed from AS1055, as shown in Table 2.

Regardless of the measured or assumed RBLs, minimum RBLs apply in this policy, which result in minimum intrusiveness noise levels as follows:

Table 4: Minimum assumed RBLs and project intrusiveness noise levels.

Time of day	Minimum assumed rating background noise level, in dB(A)	Minimum project intrusiveness noise levels, in $L_{Aeq, 15min}$ dB(A)
Day	35	40
Evening	30	35
Night	30	35

For the purpose of the assessment, the minimum project intrusive noise levels have been adopted.

5.2.2 Amenity noise levels and Project Amenity Noise Levels

To limit continuing increases in noise levels from application of the intrusiveness level alone, the ambient noise level within an area from all industrial noise sources combined should remain below the recommended amenity noise levels specified in Table 2.2 of the Noise Policy for Industry where feasible and reasonable. The recommended amenity noise levels will protect against noise impacts such as speech interference, community annoyance and some sleep disturbance. The noise amenity area is defined as residential rural and the relevant noise amenity levels are given in Table 5.

Table 5: Amenity noise levels

Receiver/ Noise amenity area	Assessment period	Recommended amenity noise level, L_{eq} dB(A)
Residential Rural	Day	50
	Evening	45
	Night	40
Note: - Day-time period is from 0700 to 1800 (Monday to Saturday) and 0800 to 1800 (Sundays and Public Holidays) - Evening period is from 1800 to 2200 - Night-time period is from 2200 to 0700 (Monday to Saturday) and 2200 to 0800h (Sundays and Public Holidays)		

The recommended amenity noise levels represent the objective for total industrial noise at a receiver location, whereas the project amenity noise level represents the objective for noise from a single industrial development at a receiver location.

To ensure that industrial noise levels (existing plus new) remain within the recommended amenity noise levels for an area, a project amenity noise level applies for each new source of industrial noise as follows:

Project amenity noise level for industrial developments = Recommended amenity noise level minus 5 dB(A)

5.2.3 Project Noise Trigger Level

The project noise trigger level (PNTL) has been determined in Table 6 and are the most stringent of the intrusiveness and amenity noise criteria.

Table 6: NSW Noise Policy for Industry evaluated criteria

Assessment period	Project Intrusiveness Noise Level $L_{eq,15min}$ dB(A) *	Project Amenity Noise Level L_{eq} dB(A)	Project Noise Trigger Level L_{eq} dB(A)
Day	40	45	40
Evening	35	40	35
Night	35	35	35
Note: - Day-time period is from 0700 to 1800 (Monday to Saturday) and 0800 to 1800 (Sundays and Public Holidays) - Evening period is from 1800 to 2200 - Night-time period is from 2200 to 0700 (Monday to Saturday) and 2200 to 0800h (Sundays and Public Holidays) * Based on minimum intrusive noise levels in Table 4.			

Table 6 shows that the PNTLs are set by the project intrusiveness noise level for all assessment periods.

By meeting the PNTLs at the identified NSRs, all other properties located further away from the Site are expected to comply with the noise requirements of this policy.

5.3 Noise-enhancing Weather Conditions

Certain meteorological/weather conditions may increase noise levels by focusing sound-wave propagation paths at a single point. Such refraction of sound waves will occur during temperature inversions (atmospheric conditions where temperatures increase with height above ground level), and where there is a wind gradient (that is, wind velocities increasing with height) with wind direction from the source to the receiver.

As meteorological data was not captured for the assessment, a range of meteorological conditions have been considered in the construction and operational noise impact assessment of the Proposal, to account for all conditions.

The standard meteorological conditions and noise-enhancing meteorological conditions as defined in the NSW Noise for Industry Policy, which have been considered in this assessment are summarised in Table 7.

Table 7: Standard and noise-enhancing meteorological conditions

Meteorological conditions	Meteorological parameters
Standard meteorological conditions	Day/evening/night: stability categories A–D with wind speed up to 0.5 m/s at 10 m AGL.
Noise-enhancing meteorological conditions	Daytime/evening: stability categories A–D with light winds (up to 3 m/s at 10 m AGL). Night-time: stability categories A–D with light winds (up to 3 m/s at 10 m AGL) and/or stability category F with winds up to 2 m/s at 10 m AGL.

6 Construction Noise Assessment

For the assessment, the noise impact has been assessed for each construction phase. Each construction phase is expected to occur sequentially. Although some construction phases will overlap, they are not expected to occur at the same location, thus eliminating the risk of cumulative impact.

6.1 Construction Phases

The construction phases of the Proposal and associated machinery and equipment required, including vehicles, are outlined in Table 8.

Table 8: Construction phases

Construction Phase	Area of Work/Task	Types of Equipment
Site Clearing Works	Earthworks construction machinery	D9 Dozer 20T Excavator 35T Excavator Scraper Pad Foot Roller Water Cart Moxy Front End Loader
	Tree Removal	Wood Chipper (tub grinder) D9 Dozer Tractor
Access Road Construction	Earthworks construction machinery	Grader Water Cart Drum Roller 13T Excavator 20T Excavator Bobcat Scraper
	Access Track Road Base	32T Truck and Dog Moxy Loader Crusher / Screener for quarry based activities, Scraper for placement of fill
Civil Construction of Benches	Construction Vehicles	D9 Dozer 20T Excavator 35T Excavator Scraper Pad Foot Roller Water Cart
	Foundation Compound	32T Truck and Dog Moxy
Construction / Installation Activities	Site Fencing	Bobcat

Construction Phase	Area of Work/Task	Types of Equipment
		Utes and Trailer Telehandler Tractor Small Excavator
	Site Offices	Flatbed Truck Crane (slew or Franna) Telehandler Hiab Truck
	Concrete Foundations	Concrete Truck Concrete Pump Sand Cart Water Cart
	Piling Works	Vermeer PD10 or Equivalent
	Pre-drilling works	Utes and Trailers Tractors Excavators
	Tracking System Installation	Telehandlers Tractors & trailers for deliveries
	PV Module Installation	Telehandlers Tractors & trailers for deliveries Forklifts
	Onsite Logistics	Telehandlers Bobcat Side loaders Tractors & trailers
	Cable and Trenching	Vermeer Trenchers Utes / Tractors (for MV cable) with Cables Reeler Sand Carts 20T Excavator Telehandler Backhoe Grader MR Truck Front End Loader
	Overhead Line (OHL) Construction	EWP Telehandler Drill Rig Concrete truck 20T Excavator HR Truck and Hiab Mobile Crane D7 Dozer (for clearing)
Deliveries	Piling Machines	Low Loader or side loader semis with pile rigs in 40' containers

Construction Phase	Area of Work/Task	Types of Equipment
	Main Equipment (Tracking, Piers, Modules, Inverters)	Typically, Semi-Trailer
	Gravel / Access Track Road Base	Typically, Semi-Trailer
	Sand	Typically, Semi-Trailer
	Mobile Crane	180T Mobile Crane
Waste Collection	-	Waste Collection Trucks

6.2 Plant and Equipment Noise Source Levels

For each construction process, the expected plant and machinery information to be used are summarised in Table 9. The table also includes an estimated percentage of use for each equipment during each phase, which reflects the transient and changing nature of the construction noise activities, dependent upon site-conditions, timelines, delays and other unexpected occurrences.

Table 9: Plant and machinery for each phase

Construction Phase	Task	Equipment	% Use	Sound Power Level, dB(A)	Reference*
Site Clearing Works	Earthworks construction machinery	D9 Dozer	75%	102	Ref. No. 1, Table 2 in DEFRA ⁴
		20T Excavator	50%	103	Ref. No. 3, Table 2 in DEFRA
		35T Excavator	50%	101	Ref. No. 15, Table 2 in DEFRA
		Scraper	75%	95	Ref. No. 8, Table 2 in DEFRA
		Pad Foot Roller	50%	105	Ref. No. 37, Table 2 in DEFRA
		Water Cart	100%	93	Ref. No. 45, Table 2 in DEFRA
		Moxy	75%	114	Ref. No. 31, Table 2 in DEFRA
		Front End Loader	75%	103	Ref. No. 28, Table 2 in DEFRA
	Tree Removal	Wood Chipper (tub grinder)	100%	113	Ref. No. 71, Table 4 in DEFRA
		D9 Dozer	75%	102	Ref. No. 1, Table 2 in DEFRA
Access Road Construction	Earthworks construction machinery	Tractor	50%	105	Ref. No. 34, Table 2 in DEFRA
		Grader	75%	106	Ref. No. 37, Table 2 in DEFRA
		Water Cart	100%	93	Ref. No. 45, Table 2 in DEFRA
		Drum Roller	75%	106	Ref. No. 37, Table 2 in DEFRA
		13T Excavator	50%	101	Ref. No. 5, Table 2 in DEFRA
		20T Excavator	50%	103	Ref. No. 3, Table 2 in DEFRA
		Bobcat	75%	103	Ref. No. 28, Table 2 in DEFRA
		Scraper	75%	95	Ref. No. 8, Table 2 in DEFRA
	Access Track Road Base	32T Truck and Dog	50%	105	Ref. No. 34, Table 2 in DEFRA
		Moxy	75%	114	Ref. No. 31, Table 2 in DEFRA
		Loader	75%	103	Ref. No. 28, Table 2 in DEFRA

⁴ Department for Environment Food and Rural Affairs (DEFRA) – Update of Noise Database for Prediction of Noise on Construction and Open Sites – (2005)

Construction Phase	Task	Equipment	% Use	Sound Power Level, dB(A)	Reference*
		Crusher / Screener for quarry based activities	50%	109	Ref. No. 15, Table 1 in DEFRA
		Scraper for placement of fill	75%	95	Ref. No. 8, Table 2 in DEFRA
Civil Construction of Benches	Construction Vehicles	D9 Dozer	75%	102	Ref. No. 1, Table 2 in DEFRA
		20T Excavator	50%	103	Ref. No. 3, Table 2 in DEFRA
		35T Excavator	50%	101	Ref. No. 15, Table 2 in DEFRA
		Scraper	75%	95	Ref. No. 8, Table 2 in DEFRA
		Pad Foot Roller	75%	106	Ref. No. 37, Table 2 in DEFRA
		Water Cart	100%	93	Ref. No. 45, Table 2 in DEFRA
	Foundation Compound	32T Truck and Dog	50%	105	Ref. No. 34, Table 2 in DEFRA
		Moxy	75%	114	Ref. No. 31, Table 2 in DEFRA
Construction / Installation Activities	Site Fencing	Bobcat	75%	103	Ref. No. 28, Table 2 in DEFRA
		Utes and Trailer	50%	105	Ref. No. 34, Table 2 in DEFRA
		Telehandler	50%	96	Ref. No. 35, Table 2 in DEFRA
		Tractor	75%	107	Ref. No. 34, Table 2 in DEFRA
		Concrete Truck	75%	107	Ref. No. 34, Table 2 in DEFRA
		Small Excavator	50%	101	Ref. No. 5, Table 2 in DEFRA
	Site Offices	Flatbed Truck	50%	105	Ref. No. 34, Table 2 in DEFRA
		Crane (slew or Franna)	75%	103	Ref. No. 48, Table 5 in DEFRA
		Telehandler	75%	97	Ref. No. 35, Table 2 in DEFRA
		Hiab Truck	50%	105	Ref. No. 34, Table 2 in DEFRA
	Concrete Foundations	Concrete Truck	50%	105	Ref. No. 34, Table 2 in DEFRA
		Concrete Pump	75%	94	Ref. No. 24, Table 4 in DEFRA
		Sand Cart	75%	107	Ref. No. 34, Table 2 in DEFRA
		Water Cart	100%	93	Ref. No. 45, Table 2 in DEFRA
	Piling Works	Vermeer PD10 or Equivalent	100%	96	Ref. No. 6, Table 3 in DEFRA
	Pre-drilling works	Utes and Trailers	50%	105	Ref. No. 34, Table 2 in DEFRA
		Tractors	75%	107	Ref. No. 34, Table 2 in DEFRA
		Excavators	50%	103	Ref. No. 3, Table 2 in DEFRA
	Tracking System Installation	Telehandlers	75%	97	Ref. No. 35, Table 2 in DEFRA
		Tractors & trailers for deliveries	75%	107	Ref. No. 34, Table 2 in DEFRA
	PV Module Installation	Telehandlers	75%	97	Ref. No. 35, Table 2 in DEFRA
		Tractors & trailers for deliveries	75%	107	Ref. No. 34, Table 2 in DEFRA
		Forklifts	75%	94	Ref. No. 57, Table 4 in DEFRA
	Onsite Logistics	Telehandlers	75%	97	Ref. No. 35, Table 2 in DEFRA
		Bobcat	75%	103	Ref. No. 28, Table 2 in DEFRA
		Side loaders	50%	101	Ref. No. 28, Table 2 in DEFRA
		Tractors & trailers	75%	107	Ref. No. 34, Table 2 in DEFRA

Construction Phase	Task	Equipment	% Use	Sound Power Level, dB(A)	Reference*
	Cable and Trenching	Vermeer Trenchers	75%	102	Ref. No. 64, Table 4 in DEFRA
		Utes / Tractors (for MV cable) with Cables Reeler	50%	105	Ref. No. 34, Table 2 in DEFRA
		Sand Carts	75%	107	Ref. No. 34, Table 2 in DEFRA
		20T Excavator	50%	103	Ref. No. 3, Table 2 in DEFRA
		Telehandler	75%	97	Ref. No. 35, Table 2 in DEFRA
		Backhoe	75%	95	Ref. No. 8, Table 2 in DEFRA
		Grader	75%	106	Ref. No. 37, Table 2 in DEFRA
		MR Truck	75%	114	Ref. No. 31, Table 2 in DEFRA
		Front End Loader	75%	103	Ref. No. 28, Table 2 in DEFRA
	OHL Construction	EWP	75%	105	Ref. No. 59, Table 4 in DEFRA
		Telehandler	75%	97	Ref. No. 35, Table 2 in DEFRA
		Drill Rig	75%	112	Ref. No. 35, Table 6 in DEFRA
		Concrete truck	50%	112	Ref. No. 31, Table 2 in DEFRA
		20T Excavator	75%	105	Ref. No. 3, Table 2 in DEFRA
		HR Tuck and Hiab	75%	93	Ref. No. 28, Table 3 in DEFRA
		Mobile Crane	50%	112	Ref. No. 31, Table 2 in DEFRA
		D7 Dozer (for clearing)	75%	102	Ref. No. 1, Table 2 in DEFRA
Deliveries	Piling Machines	Low Loader or Side loader semis with pile rigs in 40' containers	50%	101	Ref. No. 28, Table 2 in DEFRA
	Main Equipment (Tracking, Piers, Modules, Inverters)	Typically, Semi-Trailer	50%	105	Ref. No. 34, Table 2 in DEFRA
	Gravel / Access Track Road Base	Typically, Semi-Trailer	50%	105	Ref. No. 34, Table 2 in DEFRA
	Sand	Typically, Semi-Trailer	50%	105	Ref. No. 34, Table 2 in DEFRA
	Mobile Crane	180T Mobile Crane	50%	112	Ref. No. 31, Table 2 in DEFRA
Waste Collection	-	Waste Collection Trucks	50%	112	Ref. No. 31, Table 2 in DEFRA

6.3 Assessment Methodology

The noise impact radius of each construction phase has been predicted based on the following assumptions:

- Noise source modelled as follows:
 - One point source for each construction phase.
 - All plant and equipment for each construction phase are operating simultaneously at the same location.
 - Total sound power level for each construction phase is calculated based on sound power level information and percentage use of each plant and equipment given in Table 9.
- Distance attenuation, as follows:
 - a. Average impact scenario: Due to the transient and changing nature of construction works, the location of the noise source can be assumed to be in the middle of the site for each construction phase on average. This scenario provides an indication to the average impact on the receivers. Impact is typically maximum when the construction works are closest to the receivers on one side of the site, and minimal when works are on the other side of the site away from receivers.
 - b. Worst-case impact scenario: Maximum impact is experienced when construction works occur at the closest boundary of the construction works to each respective receiver. Maximum impact will however be for a short duration until the activities move to a different location. Assessing the maximum impact ensures the right mitigation methods are implemented.
- Atmospheric, meteorological and ground attenuation using the CONCAWE⁵ method (over 100 metres separation distance between source and receiver), as follows:
 - a. Category 6:
 - A conservative prediction of the propagation of noise from source to receiver, which includes the effects of temperature inversions and favourable winds onto the noise.
 - b. Category 4:
 - A neutral prediction based on neutral meteorological conditions.

For the construction noise assessment, noise levels have been predicted to the receivers based on the above methodology. The predicted noise levels have then been compared to the following noise targets:

1. ICNG noise management level of 50 dB(A) day-time, and
2. ICNG highly noise affected limit of 75 dB(A) as presented in Table 3.

⁵ CONCAWE is a noise prediction method developed for assessing environmental noise propagation, drawn from both acoustic theory and extensive field noise measurements. The CONCAWE predictions consider atmospheric, meteorological and ground attenuation. *The propagation of noise from petroleum and petrochemical complexes to neighbouring communities. Report no.4/81, 1981*

6.4 Predicted Noise Impact Radius

The predicted approximate noise impact radius for each construction process are provided in Table 10.

Table 10: Predicted noise impact radius for each task

Construction Process	Construction Task	Approx. noise Impact Radius (metres) to meet noise targets*			
		CONCAWE Category 6		CONCAWE Category 4	
		50 dB(A) noise target	75 dB(A) noise target	50 dB(A) noise target	75 dB(A) noise target
Site Clearing Works	Earthworks construction machinery	500	35	350	35
	Tree Removal	400	30	300	30
Access Road Construction	Earthworks construction machinery	400	25	250	25
	Access Track Road Base	500	40	350	40
Civil Construction of Benches	Construction Vehicles	350	20	250	20
	Foundation Compound	500	35	350	30
Construction / Installation Activities	Site Fencing	400	25	250	25
	Site Offices	350	20	250	20
	Concrete Foundations	300	20	200	20
	Piling Works	80	10	80	10
	Pre-drilling works	300	20	250	20
	Tracking System Installation	250	15	200	15
	PV Module Installation	250	15	200	15
	Onsite Logistics	300	20	250	20
	Cable and Trenching	550	40	400	40
	OHL Construction	550	40	400	40
Deliveries	Piling Machines	150	10	125	10
	Main Equipment (Tracking, Piers, Modules, Inverters)	400	25	300	25
	Gravel / Access Track Road Base	400	25	300	25
	Sand	400	25	300	25
	Mobile Crane	400	25	300	25
Waste Collection		400	25	300	25
Note: * Atmospheric, meteorological and ground attenuation corrections are 0 dB for predictions within 100 metres of the source.					

6.5 Impacted Receivers

6.5.1 Highly Noise Affected

The predicted construction impact for the noisiest construction task shows that the ICNG highly noise affected limit of 75 dB(A) will be exceeded at any receivers located less than 40 metres from the boundary of the Development Envelope and/or offsite Substation footprint.

The closest identified noise sensitive receiver, NSR1, is 368 metres from the closest boundary of the Development Envelope and/or offsite Substation footprint. Therefore, no receiver is predicted to be highly noise affected.

6.5.2 Exceedance of ICNG Noise Management Level

Based on the predicted approximate noise impact radius, receivers located within 550 metres of the noisiest construction tasks (Conservative prediction CONCAWE Category 6) will exceed the ICNG Noise Management Level of 50 dB(A).

The only receiver located within this radius is NSR1 for construction works within the Development Envelope only. No receivers are predicted to be impacted from works carried out within the offsite Substation footprint.

The approximate duration of impact for NSR1 where the impact levels exceed 50 dB(A) has been predicted based on the assumed duration of each construction task and the total area of the construction work (Development Footprint). The results are summarised in Table 11.

Table 11: Impacted receivers

Construction Phase	Area of Work/Task	Duration	Impacted Receivers	Approximate Duration of Impact in Working Days and Predicted Exceedance in dB(A) (Based on Worst-case prediction CONCAWE Category 6)
Site Clearing Works	Earthworks construction machinery	1 week	NSR1	Less than one day with minimal exceedances of 3dB
	Tree Removal	1 week (ad hoc)	NSR1	Less than one day with marginal exceedances of 1-2dB
Access Road Construction	Earthworks construction machinery	1 week	NSR1	Less than one day with marginal exceedances of 1-2dB
	Access Track Road Base	1 week	NSR1	Less than one day with minimal exceedances of 3dB
Civil Construction of Benches	Construction Vehicles	Ad hoc	None	-
	Foundation Compound	1 week	NSR1	Less than one day with minimal exceedances of 3dB
Construction / Installation Activities	Site Fencing	1 week	NSR1	Less than one day with marginal exceedances of 1-2dB
	Site Offices	Ad hoc	None	-
	Concrete Foundations	Ad hoc	None	-
	Piling Works	Ad hoc	None	-
	Pre-drilling works	Ad hoc	None	-
	Tracking System Installation	Ad hoc	None	-
	PV Module Installation	Ad hoc	None	-

Construction Phase	Area of Work/Task	Duration	Impacted Receivers	Approximate Duration of Impact in Working Days and Predicted Exceedance in dB(A) (Based on Worst-case prediction CONCAWE Category 6)
	Onsite Logistics	Ad hoc	None	-
	Cable and Trenching	2 weeks		For two to three days with maximum exceedance of 4dB
	OHL Construction	1 week	NSR1	For one to two days with maximum exceedance of 4dB
Deliveries	Piling Machines	Ad hoc	None	-
	Main Equipment (Tracking, Piers, Modules, Inverters)	Ad hoc	NSR1	Negligible Impact
	Gravel / Access Track Road Base	1 week	NSR1	Less than one day with marginal exceedances of 1-2dB
	Sand	2 weeks	NSR1	For one to two days with marginal exceedances of 1-2dB
	Mobile Crane	Ad hoc	NSR1	Negligible impact
Waste Collection	-	Ad hoc	NSR1	Negligible impact

6.6 Discussion and Recommendations

The construction noise prediction method represents a scenario where all the plant and equipment for each construction task have been assumed to be operating at the same time and location with the source noise levels adjusted for percentage usage.

This method allows to assess maximum impact but also represents impact for a short duration of time. Plant and equipment are expected to operate at one location for a short period of time and move on the next location, away from the boundary of the Proposal Footprint. For instance, sensitive areas located on the western boundary of the Site will be less impacted from works conducted on the eastern boundary of the Site, and vice versa.

Furthermore, plant and equipment are usually spread out across the site conducting specific tasks. The impact of one plant or equipment will be considerably less as compared to the cumulative impact of all plant and equipment, as presented in this assessment.

The approximate impact duration given in Table 11 represents maximum duration and is to be used as a guide only. Although the construction noise is expected to be noticeable for a short period of time at NSR1, and the degree of adverse impact is expected to be low, as is typical with construction projects in proximity to people, by incorporating noise control measures, the noise impact to residents and other NSRs surrounding the site can be significantly reduced.

At NSR1, the daily activities of the residents are not expected to be compromised. The construction works will occur in the day-time only and will only be noticeable when the works are carried out at the closest boundary of the Development Envelope. The maximum exceedance of the ICNG Noise Management Level is only 4dB for small durations during the Cable/Trenching and OHL Construction Stages of the project. Noise

control measures will be employed for works close to the boundary which will further reduce the noise impact at NSR1.

Construction noise impact will also be managed through a Construction Noise Management Plan (CNMP) to minimise the adverse impact to acceptable levels and manage community reaction.

6.7 Good Practice – Mitigation and Management

As with all construction projects, noise levels can be minimised with adherence to good practice, which means following some basic procedures.

Based on the results of the construction noise assessment showing that there are minimal exceedance of the ICNG noise management level at NSR1 and for a short period of time, suggestions and ideas to minimise construction noise have been provided below, mostly management suggestions, where to manage any adverse response from the community (NSR1).

The following management measures are recommended to be employed to minimise the construction noise impact onto NSR1. These can include:

- Informing and consulting residents and interested parties, as far as practicable, regarding impending or current events that may cause high levels of noise and how long they are expected to take. This may take the form of letter drops, or community notices.
- Provide a complaints telephone number prominently displayed where the works are taking place, and on any letter drops or community notices.
- Respite hours agreed with residents when noisy works will not take place, if necessary.
- Investigate complaints when received to establish the cause, and where possible implement a corrective action such as providing a respite period or other practical measure.
- Minimising the operating noise of machinery brought on to the Site.
- Where appropriate, obtaining acoustic test certificates for machinery brought on to the Site.
- If there is excessive noise from any process, that process will be stopped and if possible that noise attenuated to acceptable levels. Where there is no alternative the process will be rescheduled to non-sensitive hours.
- Ensuring that plant is not left idling when not in use.
- Ensuring that plant is well maintained and in good working order and not causing unnecessary noise, such as damaged mufflers on plant.
- All access hatches for plant to be kept closed.


7 Construction Traffic Noise Assessment

During the construction period, there will be two access points for the Proposal as shown in Figure 3.

On the main site via the Gara Road access, an average of up to eleven light vehicles (including three minibuses) and five heavy vehicles are forecast to be required daily. On the substation site, an average of five light vehicles and one heavy vehicle are forecast daily.

There is potential that peak hour truck movements could be as high as six vehicles in some situations such as due to weather delays, logistical delays, where the construction schedule pace is increased, or where a particular campaign or work front requires a higher frequency of truck movements for a shorter duration. Typical construction traffic will consist of deliveries, low loader trailers, truck and dog, semi-trailers, and waste collection trucks.

Figure 3: Construction Traffic Route



7.1 Predicted Traffic Noise Impact and Discussion

The closest receivers to the proposed access route are approximately 25 metres from the boundary of the construction traffic route, typically close to the Armidale town centre area.

Typical light vehicles, mini-buses and semi-trailers associated with deliveries have an approximate maximum pass-by noise level of **78 dB L_{Amax}** at 10 metres (Source: DEFRA database, Table 4, Ref. 91 Unit Trailer). This translates to a maximum noise level incident at the façade of that closest receiver of **70 dB L_{Amax}**.

As all traffic movements associated with the site will occur during daytime hours, sleep disturbance is not expected.

With an average of approximately 10-12 vehicle pass-by events per day (peak hour of 6 pass-by events) from delivery trucks occurring during a 12-hour construction period, it follows that the impact will be noticeable but relatively minor and momentary (vehicle pass-by event lasts only a matter of seconds) at the closest receivers to the access road.

Therefore, the risk of an adverse noise impact being caused to residents is considered low.

Other construction related traffic is not expected to result in an adverse noise impact to residents.

8 Operational Noise Assessment

This section of the report addresses the operational noise impact of the Proposal onto sensitive receivers. The assessment includes:

- Prediction of noise emissions from the operation and maintenance of the Proposal
- Comparison of predicted noise emissions to noise criteria derived from the NSW Noise Policy for Industry, and
- Provide noise mitigation measures, if any, to ensure compliance with the criteria.

8.1 Operations Phase

The solar modules at the Site are to operate during daylight hours, seven days per week, 365 days per year, for a period of approximately 28 years. The Proposal will operate independently, and no permanent employees will be stationed on-site during the operations phase. The Proposal will have approximately 3-6 full time workers who may visit the site on a daily basis. The main operational and maintenance tasks are summarised in Table 12.

Table 12: Operation and maintenance tasks

Task	Description
Noise from the operation of Inverter stations and substation (including transformers & trackers).	When the solar farm is fully operational, noise from the inverter stations and substations may impact upon nearby receivers. The inverter stations emit constant noise and are expected to be located within the module layout area. The substation is located offsite to the northwest of the module layout area. The stations are expected to operate 24/7.
Solar module washing	The solar modules are to be periodically washed to remove any excess dirt, dust or other matter (i.e. bird droppings), which may prevent sunlight from effectively reaching the solar cells and subsequently reducing the electricity production output. The solar panels are anticipated to be cleaned via means of water spray from a water truck driven through the informal roadways constructed on-site. No chemicals will be added to the water to ensure minimal impact to the surrounding environment through runoff.
Vegetation, weed, and pest management	Weed and vegetation control will be conducted throughout the project site for the duration of project operations. Weed control is likely to consist of any or, all of the following methods: biological (sheep grazing), mechanical or manual, or chemical methods. Site conditions are to be evaluated prior to the selection of the management method to ensure the method employed is the most appropriate to the environmental conditions of the Site.
Equipment maintenance and inspection	Responding to automated electronic alerts based on monitored data, including actual versus expected tolerances for system output and other key performance metrics.
Security detail	To ensure safety and security at the Site, a perimeter fence up to 2.5 m will be installed around the perimeter of the Proposal in accordance with the Proponent's requirements to ensure entry into the Site is controlled. Site access arrangements will be regulated for staff through identification requirements. Once operational, all access points will be gated. The Site security system may also include sensor lighting and closed-circuit television (CCTV) at several locations around the Site to act as a deterrent to possible nefarious activity. The lighting is designed not to react to birds and animals etc. entering the Site.

8.2 Operational Source Levels

For each operation phase, the expected equipment and associated sound levels are summarised in Table 13.

Table 13: Summary of operations phase and associated equipment

Operations Phase	Task	Equipment	% use per day	Sound Power Level, dB(A)	Reference*
Noise from Inverter Stations	Inverters	-	60	88	Data specification from Ingeteam 1640TL B630 Inverters
Noise from Tracker Motors – approximately 1,200 trackers spaced evenly across the site	The tracking motors would operate no more than 1 minute out of every 15-minute period	-	10	78	Data specification from NexTracker
Noise from Substation (Transformers)	Transformers	-	100	92	66 kV Power Transformer Empirical Sound Power Level
Solar module washing (Monthly or ad hoc)	Water spraying	Water Truck	75	107	AS 2436
		Water Pump	75	93	Ref. No. 45, Table 2 in DEFRA
Vegetation, weed, and pest management	Mechanical method	Truck	75	107	AS 2436
		Pump	75	93	Ref. No. 45, Table 2 in DEFRA
Equipment maintenance and inspection	Insignificant noise impact				
Security detail	Insignificant noise impact				
Communicating with customers, transmission system operators, and other entities involved in facility operations	Insignificant noise impact				
Note: * DEFRA – Department for Environment Food and Rural Affairs (DEFRA), 2005. Update of noise database for prediction of noise on construction and open sites. Noise levels are given as a sound pressure level at 10 metres from the source. The sound pressure levels have been converted to sound power levels in the table.					

8.3 Assessment Methodology

The impact radius of each noise generating source has been predicted based on the following assumptions:

- Noise source modelled as follows:
 - One point source for each noise generating source.
 - Total sound power level as given in Table 13.

- Atmospheric, meteorological and ground attenuation using the CONCAWE⁶ method (over 100 metres separation distance between source and receiver), as follows:
 - a. Category 6:
 - A conservative prediction of the propagation of noise from source to receiver, which includes the effects of temperature inversions and favourable winds onto the noise.
 - b. Category 4:
 - A neutral prediction based on neutral meteorological conditions.

8.4 Predicted Impact from Inverter Stations

Noise from the inverter stations are required to meet the Project Noise Trigger Levels of 35 dB(A) derived in Table 6.

Based on the sound levels given in Table 13, the radius of impact of one inverter station is 220 metres.

Receiver NSR1 is the closest receiver located at least 379 metres from any noise generating sources. Therefore, no receivers are predicted to be impacted from the inverters or transformers.

8.5 Predicted Impact from Trackers

Noise from the trackers are required to meet the Project Noise Trigger Levels of 35 dB(A) derived in Table 6.

Based on the sound levels given in Table 13 and the percentage use per day, the radius of impact of one inverter station is 50 metres.

Receiver NSR1 is the closest receiver located at least 379 metres from any noise generating sources. Therefore, no receivers are predicted to be impacted from the trackers.

8.6 Substation and Transformers

Noise from the substation and transformers are required to meet the Project Noise Trigger Levels of 35 dB(A) derived in Table 6.

Based on the sound levels given in Table 13, the radius of impact of the transformer is 260 metres.

Receiver NSR4 is the closest receiver located at least 896 metres from any noise generating sources. Therefore, no receivers are predicted to be impacted from the inverters or transformers.

⁶ CONCAWE is a noise prediction method developed for assessing environmental noise propagation, drawn from both acoustic theory and extensive field noise measurements. The CONCAWE predictions consider atmospheric, meteorological and ground attenuation. *The propagation of noise from petroleum and petrochemical complexes to neighbouring communities. Report no.4/81, 1981*

8.7 Predicted Operational Impact

Operational activities are expected to occur in the day-time period only. Noise from operational activities are required to meet the Project Noise Trigger Levels of 40 dB(A) Day-time as derived in Table 6.

Based on the sound levels given in Table 13, the radius of impact for the operational activities is approximately 150 metres.

No receivers have been identified with 150 metres of the Development Envelope and/or offsite Substation footprint. Therefore, no impact from operational activities is predicted.

9 Conclusion

TTM has carried out a construction and operational noise assessment for the proposed Stringybark Solar Farm.

TTM predicted construction impact levels from the phases of construction at the nearest sensitive receivers. The predictions showed that no receivers will be highly noise affected. The impact is considered to be of short duration and manageable. Impact to NSR1 will be maximum when the works are at the nearest boundary of the site for a short duration until the works move away with maximum predicted exceedance of 4dB only. Good practice construction noise management procedures have been provided to minimise noise impact to the community. No other identified receivers are predicted to be impacted by the construction works.

Construction traffic on public roads has been assessed and the risk of an adverse noise impact to residents living beside the public roads is considered low.

Noise from the inverter stations, substation, transformers and trackers has been assessed. None of the identified noise sensitive receivers are predicted to be impacted.

Noise generated from the operation of the solar farm has also been assessed and none of the identified noise sensitive receivers are predicted to be impacted. No additional noise mitigation measures are recommended.

Overall this noise assessment report has shown that noise associated with the construction and operation of the Proposal is manageable to acceptable levels.

Appendix A Extract from AS1055.2

APPENDIX A

ESTIMATED AVERAGE BACKGROUND A-WEIGHTED SOUND PRESSURE
LEVELS ($L_{A90,T}$) FOR DIFFERENT AREAS CONTAINING
RESIDENCES IN AUSTRALIA

(Informative)

This Appendix may only be used as a guideline. Whenever possible values of $L_{A90,T}$ shall be measured in accordance with Clause 4.2.1. Where the measured values are obtainable, this Appendix shall not be used.

Noise area category (Notes 1 and 2)	Description of neighbourhood	Average background A-weighted sound pressure level, $L_{A90,T}$					
		Monday to Saturday			Sundays and public holidays		
		0700–1800	1800–2200	2200–0700	0900–1800	1800–2200	2200–0900
R1	Areas with negligible transportation	40	35	30	40	35	30
R2	Areas with low density transportation	45	40	35	45	40	35
R3	Areas with medium density transportation or some commerce or industry	50	45	40	50	45	40
R4	Areas with dense transportation or some commerce or industry	55	50	45	55	50	45
R5 (See Note 3)	Areas with very dense transportation or in commercial districts or bordering industrial districts	60	55	50	60	55	50
R6 (See Note 3)	Areas with extremely dense transportation or within predominantly industrial districts	65	60	55	65	60	55

NOTES:

- 1 The division into noise area categories is necessary in order to accommodate existing sound levels encountered at residential sites in predominantly commercial or industrial districts, or in areas located close to main land transport routes, i.e. road and rail.
- 2 The noise area category most appropriate should be selected irrespective of metropolitan or rural zoning and will vary from location to location.
- 3 Some industrial and commercial sites are not predominant sources of high background sound levels.

Appendix B Glossary

In this acoustic report unless the context of the subject matter otherwise indicates or requires, a term has the following meaning:

TERM	DEFINITION
ABL	The Assessment Background Level is the single figure background level representing each assessment period (daytime, evening and night-time (for each day). It is determined by calculating the 10 th percentile (lowest 10 th percent) background level (L_{A90}) for each period.
Adverse Weather	Weather effects that increases noise (i.e. wind and temperature inversion) that occurs at a site for a significant period of time (i.e. wind occurring more than 30% of the time in any assessment period in any season and / or temperature inversion occurring more than 30% of the nights in winter).
Ambient Noise	The all-encompassing noise associated within a given environment. It is the composite of sounds from many sources both near and far.
Assessment Period	The period in a day over which assessments are made: day (0700 to 1800h), evening (1800 to 2200h) or night (2200 to 0700h) or actual operating period if only a part of a period(s).
A – Weighting Filter	A-weighting is the most commonly used of a family of curves defined in the International standard IEC 61672:2003 and various national standards relating to the measurement of sound pressure level. A-weighting is applied to instrument-measured sound levels in effort to account for the relative loudness perceived by the human ear, as the ear is less sensitive to low audio frequencies.
Background Noise	The underlying level of noise present in the ambient noise, excluding the noise source under investigation, when extraneous noise is excluded. Usually described using the L_{90} measurement parameter.
C – Weighting Filter	The C-weighting approximates the sensitivity of human hearing at industrial noise levels (above about 85 dB(A)). The C-weighted sound level (i.e., measured with the C-weighting) is more sensitive to sounds at low frequencies than the A-weighted sound level and is sometimes used to assess the low-frequency content of complex sound environments and entertainment noise.
Decibel	The ratio of sound pressures which we can hear is a ratio of 106 (one million:one). For convenience, therefore, a logarithmic measurement scale is used. The resulting parameter is called the ‘sound pressure level’ (L_p) and the associated measurement unit is the decibel (dB). As the decibel is a logarithmic ratio, the laws of logarithmic addition and subtraction apply.
dB(A)	The unit generally used for measuring environmental, traffic or industrial noise is the A-weighted sound pressure level in decibels, denoted dB(A). An A-weighting network can be built into a sound level measuring instrument such that sound levels in dB(A) can be read directly from a sound level meter. The weighting is based on the frequency response of the human ear and has been found to correlate well with human subjective reactions to various sounds. It is worth noting that an increase or decrease of approximately 10 dB corresponds to a subjective doubling or halving of the loudness of a noise, and a change of 2 to 3 dB is subjectively barely perceptible.

TERM	DEFINITION
Equivalent Continuous Sound Level (L_{eq})	Another index for assessment for overall noise exposure is the equivalent continuous sound level, L_{eq} . This is a notional steady level which would, over a given period of time, deliver the same sound energy as the actual time-varying sound over the same period, similar to the average. Hence fluctuating levels can be described in terms of a single figure level.
Extraneous Noise	Noise resulting from activities that are not typical of the area. Atypical activities may include construction, and traffic generated during holiday periods and during special events such as concert or sporting events.
Fast Time Weighting	125 ms integration time while the signal level is increasing and decreasing.
Frequency	The rate of repetition of a sound wave. The subjective equivalent in music is pitch. The unit of frequency is the Hertz (Hz), which is identical to cycles per second. A thousand hertz is often denoted kHz, e.g. 2 kHz = 2000 Hz. Human hearing ranges approximately from 20 Hz to 20 kHz. For design purposes, the octave bands between 63 Hz to 8 kHz are generally used. The most commonly used frequency bands are octave bands, in which the mid frequency of each band is twice that of the band below it. For more detailed analysis, each octave band may be split into three one-third octave bands or in some cases, narrow frequency bands.
Impulse Time Weighting	35 ms integration time while the signal level is increasing and 1.5s integration time while the signal level is decreasing.
L_{Aeq}	See equivalent continuous sound level definition above. This is the A-weighted energy average of the varying noise over the sample period and is equivalent to the level of a constant noise which contains the same energy as the varying noise environmental. This measure is also a common measure of environmental noise and road traffic noise.
$L_{Aeq,T}$	Equivalent continuous A-weighted sound pressure level over the measurement period T with impulse time weighting.
$L_{Ceq,T}$	The equivalent continuous C-weighted sound pressure level (integrated level) that, over the measurement period T, has the same mean square sound pressure (referenced to 20 μ Pa) as the fluctuating sound(s) under consideration.
$L_{C, Peak}$	The C-weighted Peak sound pressure level during a designated time interval or a noise event.
Low Frequency	Noise containing major components in the low-frequency range (20Hz to 250Hz) of the frequency spectrum.
Maximum Noise Levels L_{max}	The maximum noise level over a sample period is the maximum level, measured on fast response, during the sample period.
Minimum Noise Levels L_{min}	The minimum noise level over a sample period is the minimum level, measured on fast response, during the sample period.
Noise Sensitive Receiver (NSR)	A noise sensitive receiver is any person or building or outside space in which they reside or occupy that has the potential to be adversely impacted by noise from an outside source, or noise not generated by the noise sensitive receiver.

TERM	DEFINITION
Octave Bands	Octave bands are frequency ranges in which the upper limit of each band is twice the lower limit. Octave bands are identified by their geometric mean frequency, or centre frequency.
Project-Specific Noise Levels	They are target noise levels for a particular noise generating facility. They are based on the most stringent of the intrusive or amenity criteria derived from the NSW Industrial Noise Policy.
RBL	The Rating Background Level for each period is the median value of the ABL values for the period over all the days measured. There is a therefore an RBL value for each period – daytime, evening and night-time.
Shoulder Periods	Where early morning (5 am to 7 am) operations are proposed, it may be unduly stringent to expect such operations to be assessed against the night-time criteria (especially if existing background noise levels are steadily rising in these early morning hours). In these situations, appropriate noise level targets may be negotiated with the regulatory/consent authority on a case-by-case basis.
Slow Time Weighting	1 second integration time while the signal level is increasing and decreasing.
Sound Level Difference (D)	The sound insulation required between two spaces may be determined by the sound level difference needed between them. A single figure descriptor, the weighted sound level difference, D_w , is sometimes used (see BS EN ISO 717-1).
Sound Power	The sound power level (L_w) of a source is a measure of the total acoustic power radiated by a source. The sound pressure level varies as a function of distance from a source. However, the sound power level is an intrinsic characteristic of a source (analogous to its volume or mass), which is not affected by the environment within which the source is located.
Sound Reduction Index (R)	The sound reduction index (or transmission loss) of a building element is a measure of the loss of sound through the material, i.e. its attenuation properties. It is a property of the component, unlike the sound level difference which is affected by the common area between the rooms and the acoustic of the receiving room. The weighted sound reduction index, R_w , is a single figure description of sound reduction index which is defined in BS EN ISO 717-1: 1997. The R_w is calculated from measurements in an acoustic laboratory. Sound insulation ratings derived from site (which are invariably lower than the laboratory figures) are referred to as the R'_w ratings.
Statistical Noise Levels	For levels of noise that vary widely with time, for example road traffic noise, it is necessary to employ an index which allows for this variation. The L_{10} , the level exceeded for ten per cent of the time period under consideration, has been adopted in this country for the assessment of road traffic noise. The L_{90} , the level exceeded for ninety per cent of the time, has been adopted to represent the background noise level. The L_1 , the level exceeded for one per cent of the time, is representative of the maximum levels recorded during the sample period. A-weighted statistical noise levels are denoted L_{A10} , dBL_{A90} etc. The reference time period (T) is normally included, e.g. $dBL_{A10, 5min}$ or $dBL_{A90, 8hr}$.
L_{A1}	The L_{A1} level is the A-weighted noise level which is exceeded for 15 of the sample period. During the sample period, the noise level is below the L_{A1} level for 99% of the time.
L_{A10}	The L_{A10} level is the A-weighted noise level which is exceeded for 10% of the sample period. During the sample period, the noise level is below the L_{A10} level for 90% of the time. The L_{A10} is a common noise descriptor for environmental noise and road traffic noise.

TERM	DEFINITION
L _{A50}	The L _{A50} level is the A-weighted noise level which is exceeded for 50% of the sample period.
L _{A90}	The L _{A90} level is the noise level which is exceeded for 90% of the sample period. During the sample period, the noise level is below the L _{A90} level for 10% of the time. This measure is a commonly referred to as the background noise level.
Structureborne Noise	The L _{A90} level is the A-weighted noise level which is exceeded for 90% of the sample period. During the sample period, the noise level is below the L _{A90} level for 10% of the time. This measure is a commonly referred to as the background noise level.
Temperature Inversion	An atmospheric condition in which temperature increases with height above the ground.
Tonality	Noise containing a prominent frequency and characterised by a definite pitch.