

“Appendix 1” to Section 4.15 Assessment Report - DA/241/2020

DRAFT CONDITIONS OF CONSENT

Upon the signature of the applicable delegate the conditions in this Appendix will form the conditions of development consent.

Development Consent No.: DA/241/2020

**Property Address: Lot 1 in DP 1095407
2 Darcy Road, WESTMEAD NSW 2145**

General Matters

PA0001 # Approved plans and supporting documentation

1. The development is to be carried out in accordance with the following plans endorsed with Council's Stamp as well as the documentation listed below, except where amended by other conditions of this consent and/or any plan annotations:

Architectural Drawings (Project No.19122, prepared by Alleanza Architecture)

Drawing/Plan No.	Issue	Plan Title	Dated
CP-DA-000	B	Location Plan	15 July 2020
CP-DA-001	B	Site Plan	16 July 2020
CP-DA-003	B	Demolition Plan	15 July 2020
CP-DA-100	A	Proposed Basement Plan	31 March 2020
CP-DA-101	B	Proposed Ground Floor Plan – Part 1	16 July 2020
CP-DA-102	B	Proposed Ground Floor Plan – Part 2	16 July 2020
CP-DA-103	A	Proposed Level 1 Floor Plan	31 March 2020
CP-DA-200	A	Sections	31 March 2020
CP-DA-210	B	Elevations	17 July 2020
CP-DA-220	B	Finishes	17 July 2020
CP-DA-801	A	Staging Diagram	31 March 2020

Civil Drawings/Stormwater (Job No.192734, prepared by Northrop Consulting Engineers Pty Ltd)

Drawing/Plan No.	Revision	Plan Title	Dated
DAC101.01	1	Civil Documentation –	27 March 2020

Drawing/Plan No.	Revision	Plan Title	Dated
		Cover Sheet, Drawing Schedule and Locality Plan	
DAC101.11	1	Civil Documentation – Specification Notes	27 March 2020
DAC101.21	1	Civil Documentation – General Arrangement Plan	27 March 2020
DAC102.01	1	Civil Documentation – Concept Sediment and Erosion Control Plan	27 March 2020
DAC102.11	1	Civil Documentation – Sediment and Erosion Control Details	27 March 2020
DAC104.01	2	Civil Documentation - Siteworks and Stormwater Management Plan	1 April 2020
DAC104.21	1	Civil Documentation - Stormwater Longitudinal Sections – Sheet 01	27 March 2020
DAC104.22	1	Civil Documentation - Stormwater Longitudinal Sections – Sheet 02	27 March 2020
DAC104.23	1	Civil Documentation - Stormwater Longitudinal Sections – Sheet 03	27 March 2020
DAC104.31	2	Civil Documentation - Stormwater Management Devices	1 April 2020
DAC104.41	1	Civil Documentation - Stormwater Catchment Plan	27 March 2020
DAC107.01	1	Civil Documentation – Details – Sheet 01	27 March 2020
DAC107.02	1	Civil Documentation – Details – Sheet 02	27 March 2020

Landscape Drawings (Job No.20190722, prepared by Ground Ink Pty Ltd)

Drawing/Plan No.	Revision	Plan Title	Dated
LA-001	B	Landscape Cover Sheet	16 July 2020

LA-101	B	Landscape Masterplan	16 July 2020
LA-201	B	Existing Tree Plan	16 July 2020
LA-301	B	Carpark Landscape Plan	16 July 2020
LA-501	B	Indicative Planting Palette	16 July 2020

Specialist Reports

Document	Ref No.	Issue	Prepared By	Dated
Statement of Environmental Effects	218316	-	Ethos Urban Pty Ltd	9 April 2020
Traffic and Parking Impact Assessment, Version: V01	18173	-	The Transport Planning Partnership (TTPP)	7 April 2020
Heritage Impact Assessment Statement,	B.2020	-	Comber Consultants Pty Ltd	3 April 2020
Preliminary Geotechnical and Hydrogeological Assessment, Revision 1	P1907547JR03V01	Draft	Martens & Associates Pty Ltd	3 April 2020
Preliminary Site Investigation, Revision 1	P1907547JR04V01	Final	Martens & Associates Pty Ltd	3 April 2020
Civil Engineering Design Report	-	A	Northrop Consulting Engineers	3 April 2020
BCA Compliance Statement	-	-	Blackett Maguire & Goldsmith	6 April 2020
Operational Waste Management Plan, Revision B	-	Final	Elephants Foot Recycling Solution	3 April 2020
Arboricultural Impact Assessment and Tree Protection Plan	WEST/CATHEW/AIA/Revision 'B'	-	Tree IQ	6 April 2020
Noise & Vibration Impact Assessment, Revision B	Project Number: 190529	-	JHA Consulting Engineers	3 April 2020

Note: In the event of any inconsistency between the architectural plan(s) and the landscape plan(s) and/or stormwater disposal plan(s) (if applicable), the architectural plan(s) shall prevail to the extent of the inconsistency.

Reason: To ensure the work is carried out in accordance with the approved plans.

PA0002 Building work in compliance with BCA

2. All building work must be carried out in accordance with the current provisions of the Building Code of Australia (National Construction Code).

Reason: To comply with the Environmental Planning & Assessment Act 1979, as amended and the Environmental Planning & Assessment Regulation 2000.

PA0003 Construction Certificate

3. Prior to commencement of any construction works associated with the approved development (including excavation if applicable), it is mandatory to obtain a Construction Certificate. Plans, specifications and relevant documentation accompanying the Construction Certificate must include any requirements imposed by conditions of this Development Consent.

Reason: To ensure compliance with legislative requirements.

PA0004 No encroachment on Council and/or Adjoining proper

4. The development must be constructed within the confines of the property boundary. No portion of the proposed structure, including footings/slabs, gates and doors during opening and closing operations must encroach upon Council's footpath area or the boundaries of the adjacent properties.

Reason: To ensure no injury is caused to persons and the building is erected in accordance with the approval granted within the boundaries of the site.

PANSC Non-standard - General Matters - Water NSW GTA

5. Water NSW General Terms of Approval (GTA) - Reference Number: IDAS1124783, dated 30 June 2020 - for part of the proposed development requiring a Water Supply Work approval under the *Water Management Act 2000* (WM Act).

The GTA issued by WaterNSW do not constitute an approval under the *Water Management Act 2000*. The development consent holder must apply to WaterNSW for the relevant approval **after development consent** has been issued by Council **and before** the commencement of any work or activity.

- a) Groundwater shall not be pumped or extracted for any purpose other than temporary construction dewatering at the site identified in the development application.
- b) An authorisation under the relevant water legislation, such as a Water Access Licence (WAL), shall be obtained for the take of groundwater as part of the activity. For avoidance of doubt, these terms do not represent any authorisation for the take of groundwater,

nor do they constitute the grant, or the indication of an intention to grant, any required WAL.

- c) An authorisation under the relevant water legislation, such as an Approval, is also required for the works involved in extracting the groundwater. For avoidance of doubt, these terms do not represent any authorisation for the construction or installation of such works.
- d) The relevant works must not be carried out, installed or operated until a specialist hydrogeological assessment has been completed by the Department of Planning Industry and Environment, which concludes that adequate arrangements are in force to ensure that no more than minimal harm will be done to any water source, or its dependent ecosystems, as a consequence of the construction or use of the proposed water management work.
- e) The design and construction of the building must prevent any take of groundwater after the authorisation has lapsed by making any below-ground levels that may be impacted by any water table fully watertight for the anticipated life of the building. Waterproofing of below-ground levels must be sufficiently extensive to incorporate adequate provision for unforeseen high water table elevations to prevent potential future inundation.
- f) Sufficient permanent drainage shall be provided beneath and around the outside of the watertight structure to ensure that natural groundwater flow is not impeded and:
 - any groundwater mounding at the edge of the structure shall be at a level not greater than 10% above the level to which the water table might naturally rise in the location immediately prior to the construction of the structure; and
 - any elevated water table is more than 1 metre below the natural ground surface existent at the location immediately prior to the construction of the structure; and
 - where the habitable part of the structure (not being footings or foundations) is founded in bedrock or impermeable natural soil then the requirement to maintain groundwater flows beneath the structure is not applicable.
- g) Construction methods and material used in and for construction shall be designed to account for the likely range of salinity and pollutants which may be dissolved in groundwater, and shall not themselves cause pollution of the groundwater.
- h) The Applicant is bound by the above terms and any other terms and conditions of the subsequent authorisation(s) required for the extraction of groundwater and the associated works under the relevant water legislation.
- i) Measurement and monitoring arrangements to the satisfaction of WaterNSW are to be implemented. Weekly records of the volumes of all groundwater pumped and the quality of any water discharged are to be kept and a completion report provided after dewatering has ceased. Records of groundwater levels are to be kept and a

summary showing daily or weekly levels in all monitoring bores provided in the completion report.

- j) Following cessation of the dewatering operations and prior to the surrender of any associated authorisation, the applicant shall submit to WaterNSW the completion report which shall include: a. detail of the volume of water taken, the precise periods and location of water taken, the details of water level monitoring in all of the relevant bores; and b. The location and construction of groundwater extraction works that are decommissioned c. a water table map depicting the aquifer's settled groundwater condition and a comparison to the baseline conditions; and d. a detailed interpreted hydrogeological report identifying all actual resource and third party impacts, including an assessment of altered groundwater flows and an assessment of any subsidence or excessive settlement induced in nearby buildings and property and infrastructure.

Reason: To comply with Water NSW requirements.

LA0002 Demolition & tree removal

6. Trees equal to or greater than five (5) metres in height, which are protected under City of Parramatta Council Development Control Plan 2011 (Part 5.4 Preservation of Trees or Vegetation), must not be removed or damaged without Council consent, unless approved in the conditions of consent.

Reason: To preserve existing landscape features.

PANSC Non-standard - General Matters - SEPP55

7. All works are to be completed as per the recommendations in the 'Preliminary Site Investigation' report, Revision 1, Report No. P1907547JR04V01, dated 3 April 2020, prepared by Martens & Associates Pty Ltd.

To be implemented prior to construction:

- Where any soil material is to be removed from site, a formal waste classification assessment shall be required in accordance with the NSW EPA Waste Classification Guidelines (2014).

Reason: To comply with the statutory requirements of State Environmental Planning Policy No.55

EPA0062 Soil and Water Management – Stockpiles

8. Stockpiles of topsoil, sand, aggregate, soil or other material are not to be located on any drainage line or easement, natural watercourse, footpath or roadway and shall be protected with adequate sediment controls.

Reason: To ensure that building materials are not washed into stormwater drains.

EPA0064 Groundwater Extraction

9. A Water Access License shall be obtained for approval to extract groundwater from the appropriate authority (Water NSW if not a State Significant Development or NSW Department of Industry – Water if it is State Significant Development or development by (or for) a Government agency).

Reason: To comply with water access governance requirements.

EPA0065 Polluted water from excavation – water analysis

10. Site water discharged must not exceed suspended solid concentrations of 50 parts per million, and must be analysed for pH and any contaminants of concern identified during the preliminary or detailed site investigation, prior to discharge to the stormwater system. The analytical results must comply with relevant Environmental Protection Authority (EPA) and ANZ Guidelines for Fresh and Marine Water Quality.

Other options for the disposal of excavation pump-out water include disposal to sewer with prior approval from Sydney Water, or off-site disposal by a liquid waste transporter for treatment/disposal to an appropriate waste treatment/processing facility.

Reason: To prevent pollution of waterways.

ECA0001 Hazardous/intractable waste disposed legislation

11. Hazardous or intractable wastes arising from the demolition process shall be removed and disposed of in accordance with the requirements of Safework NSW and the EPA, and with the provisions of:
- a) Work Health and Safety Act 2011;
 - b) NSW Protection Of the Environment Operations Act 1997 (NSW); and
 - c) NSW Environment Protection Authority (EPA) Waste Classification Guidelines.

Reason: To ensure that the land is suitable for the proposed development and any contaminating material required to be removed from the property is removed in accordance with the prescribed manner.

ECA0006 Require to notify about new contamination evidence

12. Any new information which comes to light during remediation, demolition or construction works which has the potential to alter previous conclusions about site contamination shall be notified to the Council and the principal certifying authority immediately.

Reason: To ensure that the land is suitable for its proposed use and poses no risk to the environment and human health.

ECA0007 Discharge of Contaminated Groundwater

13. Groundwater shall be analysed for pH and any contaminants of concern identified during the preliminary or detailed site investigation, prior to discharge to the stormwater system. The analytical results must comply

with relevant NSW EPA water quality standards and Australian and New Zealand Guidelines for Fresh and Marine Water Quality.

Other options for the disposal of groundwater include disposal to sewer with prior approval from Sydney Water or off-site disposal by a liquid waste transporter for treatment/disposal to an appropriate waste treatment/processing facility.

Reason: To ensure that contaminated groundwater does not impact upon waterways.

ECA0009 Contaminated waste to licensed EPA landfill

14. Any contamination material to be removed from the site shall be disposed of to an EPA licensed landfill.

Reason: To comply with the statutory requirements of the Protection of the Environment Operations Act 1997.

EWA0002 Amenity of waste storage areas

15. All waste storage rooms/areas are to be fully screened from public view and are to be located clear of all landscaped areas, driveways, turning areas, truck standing areas and car parking spaces. No materials, waste matter or products are to be stored outside the building or any approved waste storage area at any time.

Reason: To maintain the amenity of the area.

PA0011 #Demolition of Buildings

16. Approval is granted for the demolition of the existing two-storey building currently on the north-east portion of the subject site, subject to compliance with the following:-

- (a) Demolition is to be carried out in accordance with the applicable provisions of Australian Standard AS2601-2001 - Demolition of Structures.

Note: Developers are reminded that WorkCover requires that all plant and equipment used in demolition work must comply with the relevant Australian Standards and manufacturer specifications.

- b) The developer is to notify owners and occupiers of premises on either side, opposite and at the rear of the development site 5 working days prior to demolition commencing. Such notification is to be a clearly written on A4 size paper giving the date demolition will commence and is to be placed in the letterbox of every premises (including every residential flat or unit, if any). The demolition must not commence prior to the date stated in the notification.
- c) 5 working days (i.e., Monday to Friday with the exclusion of Public Holidays) notice in writing is to be given to City of Parramatta for inspection of the site prior to the commencement of works. Such written notice is to include the date when demolition will commence and details of the name, address, business hours, contact telephone

number and licence number of the demolisher. Works are not to commence prior to Council's inspection and works must also not commence prior to the commencement date nominated in the written notice.

- d) On the first day of demolition, work is not to commence until City of Parramatta has inspected the site. Should the building to be demolished be found to be wholly or partly clad with asbestos cement, approval to commence demolition will not be given until Council is satisfied that all measures are in place so as to comply with WorkCover's document "Your Guide to Working with Asbestos", and demolition works must at all times comply with its requirements.
- e) On demolition sites where buildings to be demolished contain asbestos cement, a standard commercially manufactured sign containing the words "DANGER ASBESTOS REMOVAL IN PROGRESS" measuring not less than 400mm x 300mm is to be erected in a prominent visible position on the site to the satisfaction of Council's officers. The sign is to be erected prior to demolition work commencing and is to remain in place until such time as all asbestos cement has been removed from the site to an approved waste facility. This condition is imposed for the purpose of worker and public safety and to ensure compliance with Clause 259(2)(c) of the Occupational Health and Safety Regulation 2001.
- f) Demolition must not commence until all trees required to be retained are protected in accordance with the conditions detailed under "Prior to Works Commencing" in this Consent.
- g) All previously connected services are to be appropriately disconnected as part of the demolition works. The applicant is obliged to consult with the various service authorities regarding their requirements for the disconnection of services.
- h) Demolition works involving the removal and disposal of asbestos cement in excess of 10 square meters, must only be undertaken by contractors who hold a current WorkCover "Demolition Licence" and a current WorkCover "Class 2 (Restricted) Asbestos Licence".
- i) Demolition is to be completed within 5 days of commencement.
- j) Demolition works are restricted to Monday to Saturday between the hours of 7.00am to 7.00pm. No demolition works are to be undertaken on Sundays or Public Holidays.
- k) A 1.8m high protective fencing is to be installed to prevent public access to the site.
- l) Occupation of any part of the footpath or road at or above (carrying out work, storage of building materials and the like) during construction of the development shall require a Road Occupancy Permit from Council. The applicant is to be required to submit an application for a Road Occupancy Permit through Council's Traffic and Transport Services, prior to carrying out the construction/restoration works.

- m) Oversize vehicles using local roads require Council's approval. The applicant is to be required to submit an application for an Oversize Vehicle Access Permit through Council's Traffic and Transport Services, prior to driving through local roads within Parramatta LGA.
- n) All asbestos laden waste, including asbestos cement flat and corrugated sheets must be disposed of at a tipping facility licensed by the Environment Protection Authority (EPA).
- o) Before demolition works begin, adequate toilet facilities are to be provided.
- p) After completion, the applicant must notify City of Parramatta within 7 days to assess the site and ensure compliance with AS2601-2001 – Demolition of Structures.
- q) Within 14 days of completion of demolition, the applicant must submit to Council:
 - (i) An asbestos clearance certificate issued by a suitably qualified person if asbestos was removed from the site; and
 - (i) A signed statement verifying that demolition work and the recycling of materials was undertaken in accordance with the Waste Management Plan approved with this consent. In reviewing such documentation Council will require the provision of original.
 - (ii) Payment of fees in accordance with Council's current schedule of fees and charges for inspection by Parramatta Council of the demolition site prior to commencement of any demolition works and after the completion of the demolition works.

Reason: To protect the amenity of the area.

Prior to the issue of a Construction Certificate

(Note: Some conditions contained in other sections of this consent (including prior to occupation/use commencing) may need to be considered when preparing detailed drawings/specifications for the Construction Certificate.)

TB0001 #Car Parking Condition

17. The PCA shall ascertain that any new element in the multi storey carpark not illustrated on the approved plans such as columns, garage doors, fire safety measures and the like do not compromise appropriate manoeuvring and that compliance is maintained with AS 2890.1, AS 2890.2 and AS 2890.6. Details are to be illustrated on plans submitted with the construction certificate application.

Reason: To ensure appropriate vehicular manoeuvring is provided.

TB0003 #Parking Provision

18. Parking spaces are to be provided in accordance with the approved plans and with AS 2890.1, AS 2890.2 and AS 2890.6. A total of 260 parking spaces is to be provided and be allocated as follows:

a) 260 parking spaces for staff and visitors/parents including four (4) spaces as accessible parking.

Details are to be illustrated on plans submitted with the construction certificate application.

Reason: To comply with Council's parking requirements and Australian Standards.

TBNSC Non-standard - Prior to the issue of a CC

19. The applicant is required to encourage students to use the Maple Tree Road gate and provide a concrete path from the school to this gate to the satisfaction of Council's Traffic and Transport Manager. Details are to be illustrated on plans submitted with the construction certificate application.

Reason: To minimise interaction between pedestrians and vehicles in the Darcy Road area and the pick-up and set-down area.

DB0001 Stormwater Disposal

20. All roof water and surface water is to be connected to an operable drainage system. Details are to be shown on the plans and documentation accompanying the application for a Construction Certificate.

Reason: To ensure satisfactory stormwater disposal.

DB0002 Retaining walls

21. If no retaining walls are marked on the approved plans no approval is granted as part of this approval for the construction of any retaining wall that is greater than 600mm in height or within 900mm of any property boundary.

The provision of retaining walls along common boundary lines shall not impact on neighbouring properties. If impact upon neighbouring properties (including fences) is anticipated, then written approval from the affected neighbour shall be obtained and submitted to the certifying authority prior commencement of the works.

Structural details, certified by a practicing structural engineer, shall accompany the application for a Construction Certificate for assessment and approval by the certifying authority.

Reason: To minimise impact on adjoining properties.

DB0003 Sydney Water Quick check

22. A building plan approval must be obtained from Sydney Water Tap in™ to ensure that the approved development will not impact Sydney Water infrastructure.

A copy of the building plan approval receipt from Sydney Water Tap in™ must be submitted to the Principal Certifying Authority upon request prior to works commencing.

Please refer to the website

<http://www.sydneywater.com.au/tapin/index.htm>, Sydney Water Tap in™, or telephone 13 20 92.

Reason: To ensure the requirements of Sydney Water have been complied with.

DB0004 Dial Before you Dig Service

23. Prior to any excavation on or near the subject site the person/s having benefit of this consent are required to contact the NSW Dial Before You Dig Service (NDBYD) on 1100 to receive written confirmation from NDBYD that the proposed excavation will not conflict with any underground utility services. The person/s having the benefit of this consent are required to forward the written confirmation from NDBYD to their Principal Certifying Authority (PCA) prior to any excavation occurring.

Reason: To ensure Council's assets are not damaged.

DB0012 #On Site Detention

24. Full engineering construction details of the stormwater system, including OSD structures, pipe networks and calculations as per following points, shall be submitted for the approval of the PCA prior to release of the Construction Certificate for any work on the site.

- (a) The stormwater drainage detail design shall be prepared by a Registered Stormwater Design Engineer and shall be generally in accordance with the following Stormwater Plans approved by this consent and with Council's Stormwater Disposal Policy, Council's Design and Development Guidelines, The Upper Parramatta River Catchment Trust On Site Detention Hand book (Third or Fourth Edition), the relevant Australian Standards and the National Construction Code.

- Civil Engineering Design Report by Northrop Consulting Engineers REV A Dated 03 04 2020

- (b) A Site Storage Requirement of 470m³/ha and a Permissible Site Discharge of 80L/s/ha (when using 3rd edition of UPRCT's handbook)
- (c) Adequate grate(s) to be provided so the OSD tank storage area can be inspected from outside for silt and debris, and to ensure adequate cross ventilation within the tank.
- (d) Certificate from registered structural engineer certifying the structural adequacy of the OSD tank structure.

Reason: To minimise the quantity of storm water run-off from the site, surcharge from the existing drainage system and to manage downstream flooding.

DB0013 #Water treatment for stormwater

25. A stormwater quality treatment system must be installed to manage surface runoff water to Darcy Street, generally in accordance with the Civil Engineering Design Report REV A, prepared by Northrop Consulting Engineers, dated 3 April 2020, to satisfy section 3.3.6.1 of Parramatta City Council Development Control Plan 2011. Details of the proposed system and location must accompany the application for a Construction Certificate to the satisfaction of the Certifying Authority.

Reason: To ensure appropriate water quality treatment measures are in place.

DB0017A Construction of a heavy duty vehicular crossing

26. A heavy duty vehicular crossing shall be constructed in accordance with Council's Standard Drawing numbers DS9 and DS10. Details must accompany an application for a Construction Certificate to the satisfaction of the Certifying Authority.

A Vehicle Crossing application must be submitted to Council together with the appropriate fee as outlined in Council's adopted Fees and Charges prior to any work commencing.

Reason: To ensure appropriate vehicular access is provided.

DB0019 #Disabled parking

27. Four (4) accessible car-parking spaces must be provided as part of the development. These spaces and access to these spaces must comply with AS2890.6 - 'Parking facilities' - 'Off-street parking for people with disabilities and AS1428.1 - 'Design for access and mobility' - General requirements for access - New building work' 2001 and 2009 and AS1428.4 - 'Design for access and mobility' - 'Tactile ground surface indicators for orientation of people with vision impairment' - 'Means to assist the orientation of people with vision impairment - Tactile ground surface indicators' 1992 and 2009.

Details are to accompany an application for a Construction Certificate to the satisfaction of the Certifying Authority.

Reason: To ensure equity of access and appropriate facilities are available for people with disabilities in accordance with Federal legislation.

DB0021 Impact on Existing Utility Installations

28. Where work is likely to disturb or impact upon utility installations, (e.g. power pole, telecommunications infrastructure etc.) written confirmation from the affected utility provider that they raise no objections to the proposed works

must accompany an application for the relevant Construction Certificate to the satisfaction of the Certifying Authority.

Reason: To ensure no unauthorised work to public utility installations and to minimise costs to Council.

DB0022 Support for Council Rds, footpath, drainage reserv.

29. Council property adjoining the construction site must be fully supported at all times during all demolition, excavation and construction works. Details of any required shoring, propping and anchoring devices adjoining Council property, are to be prepared by a qualified structural or geotechnical engineer. These details must accompany an application for a Construction Certificate and be to the satisfaction of the Principal Certifying Authority (PCA). A copy of these details must be forwarded to Council prior to any work being commenced.

Backfilling of excavations adjoining Council property or any void remaining at the completion of the construction between the building and Council property must be fully compacted prior to the completion of works.

Reason: To protect Council's infrastructure.

PB0002 Long Service Levy payment for Constr. over \$25,000

30. The Construction Certificate is not to be issued unless the Certifying Authority is satisfied the required levy payable, under Section 34 of the Building and Construction Industry Long Service Payments Act 1986, has been paid.

Reason: To ensure that the levy is paid.

PB0006 Location of plant

31. All plant and equipment (including but not limited to air conditioning equipment) is to be located within areas within the multi-storey car park, where possible. Any plant and equipment located on the roof is to be screened in order to minimise visual impacts. Details demonstrating compliance are to be submitted with the Construction Certificate application.

Reason: Minimise impact on surrounding properties, improve visual appearance and amenity for locality.

PB0013 Reflectivity of external finishes

32. External materials must be pre colour coated on manufacture having a low glare and reflectivity finish. The reflectivity index of roof finishes and glazing is to be no greater than 20% so as not to result in glare that causes any nuisance or interference to any person or place. Details must accompany the construction certificate to the satisfaction of the Certifying Authority.

Reason: To have a minimal impact on the neighbouring property.

PB0015 Energy Provider requirements

33. Documentary evidence to the satisfaction of the Certifying Authority must be provided with the application for a Construction Certificate confirming satisfactory arrangements have been made with an energy provider for the provision of electricity supply to the development.

Reason: To ensure adequate electricity supply to the development.

PB0020 #Parra Develop Contrib. Plan – Outside City Centre

34. A monetary contribution comprising \$126,370.00 is payable to City of Parramatta Council in accordance with Section 7.12 of the Environmental Planning and Assessment Act 1979 and the *Parramatta Section 94A Development Contributions Plan (Amendment No. 5)*. Payment must be by EFTPOS, bank cheque or credit card only.

The contribution is to be paid to Council prior to the issue of a construction certificate.

The contribution levy is subject to indexation on a quarterly basis in accordance with movements in the Consumer Price Index (All Groups Index) for Sydney issued by the Australian Statistician. At the time of payment, the contribution levy may have been the subject of indexation.

Parramatta Section 94A Development Contributions Plan (Amendment No. 5) can be viewed on Council's website at:

<https://www.cityofparramatta.nsw.gov.au/business-development/planning/development-contributions>

Reason: To comply with legislative requirements and to provide for the increased demand for public amenities and services resulting from the development.

PB0023 Outdoor lighting

35. All outdoor lighting must comply with the relevant provisions of AS/NZS1158.3: 1999 Pedestrian Area (Category P) Lighting and AS4282: 1997 Control of the Obtrusive Effects of Outdoor Lighting.

Details demonstrating compliance with these requirements must accompany the Construction Certificate application and be to the satisfaction of the Certifying Authority.

Reason: To provide high quality external lighting for security without adverse effects on public amenity from excessive illumination levels.

PB0029 Environmental Enforcement Service Charge - All DAs

36. An Environmental Enforcement Service Charge must be paid to Council prior to the issue of a Construction Certificate. The fee will be in accordance with Council's adopted 'Fees and Charges' at the time of payment.

Note: Council's Customer Service Team can advise of the current fee and can be contacted on 9806 5524.

Reason: To comply with Council's adopted Fees and Charges Document and to ensure compliance with conditions of consent.

PB0030 Infrastructure & Restoration Adm. fee for all DAs

37. An Infrastructure and Restoration Administration Fee must be paid to Council prior to the issue of a Construction Certificate.

The fee will be in accordance with Council's adopted 'Fees and Charges' at the time of payment.

Note: Council's Customer Service Team can advise of the current fee and can be contacted on 9806 5524.

Reason: To comply with Council's adopted Fees and Charges Document and to ensure compliance with conditions of consent.

PB0033 Energy Provider requirements for Substations

38. Documentary evidence to the satisfaction of the Certifying Authority is to accompany the application for a Construction Certificate confirming satisfactory arrangements have been made with the energy provider for the provision of electricity supply to the development.

If a substation is required of the energy provider, it must be located internally within a building/s.

Substations are not permitted within the front setback of the site or within the street elevation of the building; unless such a location has been outlined and approved on the Council stamped Development Application plans. Substations are not permitted within Council's road reserve.

Reason: To ensure adequate electricity supply to the development and to ensure appropriate streetscape amenity.

PB0037 #Security Bonds (multi-unit and above)

39. In accordance with Section 80A(6)(a) of the Environmental Planning and Assessment Act 1979, security bonds payable to Council for the protection of the adjacent road pavement and public assets during construction works. The bond(s) are to be lodged with Council prior to the issue of any application/approval associated with the allotment, (being a Hoarding application, Construction Certificate) and prior to any demolition works being carried out where a Construction Certificate is not required.

The bond may be paid, by EFTPOS, bank cheque, or be an unconditional bank guarantee.

Should a bank guarantee be lodged it must:

- (a) Have no expiry date;
- (b) Be forwarded directly from the issuing bank with a cover letter that refers to Development Consent DA/241/2020;

- (c) Specifically reference the items and amounts being guaranteed. If a single bank guarantee is submitted for multiple items it must be itemised.

Should it become necessary for Council to uplift the bank guarantee, notice in writing will be forwarded to the applicant fourteen days prior to such action being taken. No bank guarantee will be accepted that has been issued directly by the applicant.

Bonds shall be provided as follows:

Bond Type	Amount
Hoarding:	\$2,652.00
Nature Strip and Roadway: <i>Applies to all developments with a cost greater than \$25K and swimming pools regardless of cost (fee is per street frontage). See current Schedule of Fees and Charges.</i>	\$25,750.00

A dilapidation report is required to be prepared and submitted electronically to the City of Parramatta Council (council@cityofparramatta.nsw.gov.au) prior to any work or demolition commencing and with the payment of the bond/s.

The dilapidation report is required to document/record any existing damage to kerbs, footpaths, roads, nature strips, street trees and furniture within street frontage/s bounding the site up to and including the centre of the road.

Reason: To safe guard the public assets of council and to ensure that these assets are repaired/maintained in a timely manner so as not to cause any disruption or possible accidents to the public.

Prior to Work Commencing

LC0002 #Tree protection as per arborist report

40. The trees identified for protection within the consent shall be protected prior to and during the demolition/construction process in accordance with the Arboricultural Impact Assessment and Tree Protection Plan prepared by Tree IQ (Report No – WEST/CATHEW/AIA/ Revision 'B') dated 6 April 2020:

Reason: To ensure the protection of the tree(s) to be retained on the site.

LC0004 Protective fencing

41. Retained trees or treed areas must be fenced with a 1.8 metre high chainwire link or welded mesh fence. The fence is to be fully supported at grade, to minimise the disturbance of existing ground conditions within the canopy drip line or the setback nominated on the approved landscaping

plan. The fencing is to be in place for the duration of the construction works. "Tree Protection Zone" signage must be attached to the protective fencing.
Reason: To protect the environmental amenity of the area.

DC0001 Construction and Traffic Management Plan

42. Prior to the commencement of any works on site, the applicant shall submit a Construction and Pedestrian Traffic Management Plan (CPTMP) to the satisfaction of Council's Traffic and Transport Manager and the Transport for NSW Sydney Coordination Office. The CPTMP shall be prepared by a suitably qualified and experienced traffic consultant. The following matters must be specifically addressed in the CPTMP:

- a) Dedicated construction site entrances and exits, controlled by a certified traffic controller, to safely manage pedestrians and construction related vehicles in the frontage roadways,
- b) Turning areas within the site for construction and spoil removal vehicles, allowing a forward entry and egress for all construction vehicles on the site,
- c) The location of proposed Work Zones in the egress frontage roadways,
- d) Location of any proposed crane standing areas,
- e) A dedicated unloading and loading point within the site for all construction vehicles, plant and deliveries,
- f) Material, plant and spoil bin storage areas within the site, where all materials are to be dropped off and collected,
- g) The provisions of an on-site parking area for employees, trade person and construction vehicles as far as possible,
- h) A detailed description and route map of the proposed route for vehicles involved in spoil removal, material delivery and machine floatage and a copy of this route is to be made available to all contractors,
- i) A detailed description of locations that will be used for layover for trucks waiting to access the construction site,
- j) Proposed construction hours,
- k) Estimated number and type of construction vehicle movements including morning and afternoon peak and off peak movements,
- l) Construction program that references peak construction activities and proposed construction 'Staging',
- m) Any potential impact to general traffic, cyclists, pedestrians and bus services within the vicinity of the site from construction vehicles during the construction of the proposed works,
- n) Cumulative construction impacts of the Parramatta Light Rail (Stage 1) project. Should any impacts be identified, the duration of the impacts,
- o) Measures proposed to mitigate any associated general traffic, public transport, pedestrian and cyclist impacts should be clearly identified,

- p) The plan may be required to include restrictions on the number of trucks that can access the site in peak hours and a requirement for the developer to provide video footage of the frontage of the site on a weekly basis so that Council can enforce this requirement,
- q) Evidence of Roads and Maritime Services concurrence where construction access is provided directly or within 20 m of an Arterial Road if applicable, and,
- r) A schedule of site inductions on regular occasions and as determined necessary to ensure all new employees are aware of the construction management obligations,

The CPTMP is to include the provision of a sign on the hoarding that provides a phone number and email address for members of the local community to make enquires or complaints regarding traffic control for the site. The construction company for the site is to provide a representative for meetings that may occur once a month and may include representatives of the local community and Council staff to discuss traffic control at the site.

Written concurrence from Council's Traffic and Transport Services in relation to installation of a proposed 'Work Zone' restriction in the egress frontage roadways of the development site. Application fees and kerbside charges for 6 months (minimum) are to be paid in advance in accordance with the Council's Fees and Charges. The 'Work Zone' restriction is to be installed by Council once the applicant notifies Council in writing of the commencement date (subject to approval through Parramatta Traffic Committee processes). Unused fees for kerbside charges are to be refunded once a written request to remove the restriction is received by Council.

All traffic control devices installed in the road reserve shall be in accordance with the NSW Transport for NSW / Roads and Maritime Services publication 'Traffic Control Worksite Manual' and be designed by a person licensed to do so (minimum RMS 'red card' qualification). The main stages of the development requiring specific construction management measures are to be identified and specific traffic control measures identified for each.

Approval shall be obtained from City of Parramatta Council for any temporary road closure or crane use from public property.

Reason: To comply with Transport for NSW (TfNSW) requirements and to ensure the appropriate measures have been considered during all phases of the construction process in a manner that maintains the environmental amenity and ensures the ongoing safety and protection of people.

DC0002 Road Opening Permits - DA's involving drainage wrk

43. The applicant must apply for a road-opening permit where a new pipeline is proposed to be constructed within or across Council owned land. Additional road opening permits and fees may be necessary where connections to public utilities are required (e.g. telephone, electricity, sewer, water or gas).

In addition, no drainage work can be carried out within the Council owned land without this permit being issued. A copy is required to be kept on site.

Reason: To protect Council's assets throughout the development process.

DC0003 Dilapidation survey & report for private properties

44. Prior to the commencement of any excavation works on site, the applicant must submit for approval by the Principal Certifying Authority (with an electronic copy forwarded to Council at council@cityofparramatta.nsw.gov.au) a dilapidation report on the visible and structural condition of all neighbouring structures within the 'zone of influence' of the excavation face to a depth of twice that of the excavation.

The report must include a photographic survey of the adjoining properties detailing their physical condition, both internally and externally, including such items as walls, ceilings, roof, structural members and other similar items. The report must be completed by a consulting structural/geotechnical engineer in accordance with the recommendation of the geotechnical report.

In the event access to adjoining allotments for the completion of a dilapidation survey is denied, the applicant must demonstrate in writing that all reasonable steps have been taken to advise the adjoining allotment owners of the benefit of this survey and details of failure to gain consent for access to the satisfaction of the Principle Certifying Authority.

Note: This documentation is for record keeping purposes only, and can be made available to an applicant or affected property owner should it be requested to resolve any dispute over damage to adjoining properties arising from works. It is in the applicant's and adjoining owner's interest for it to be as detailed as possible.

Reason: Management of records.

DC0006 Erosion and Sediment Control measures

45. Erosion and sediment control measures are to be installed in accordance with the publication 'Urban Stormwater: Soils and Construction "The Blue Book" 2004 (4th edition) prior to the commencement of any demolition, excavation or construction works upon the site. These measures are to be maintained throughout the entire works.

Reason: To ensure soil and water management controls are in place before site works commence.

DC0007 Site Maintenance

46. Prior to commencement of works and during construction works, the development site and any road verge immediately in front of the site must be maintained in a safe and tidy manner. In this regard the following must be undertaken:

- (a) all existing buildings are to be secured and maintained to prevent unauthorised access and vandalism
- (b) all site boundaries are to be secured and maintained to prevent unauthorised access to the site;
- (c) all general refuse and/or litter (inclusive of any uncollected mail/advertising material) is to be removed from the site on a fortnightly basis;
- (d) the site is to be maintained clear of weeds; and
- (e) all grassed areas are to be mowed on a monthly basis.

Reason: To ensure public safety and maintenance of the amenity of the surrounding environment.

DC0009 Special Permits

47. Unless otherwise specifically approved in writing by Council, all works, processes, storage of materials, loading and unloading associated with the development are to occur entirely within the property boundaries. The applicant, owner or builder must apply for specific permits if the following activities are required seeking approval pursuant to Section 138 of the Roads Act 1993:

- (a) On-street mobile plant:
E.g. Cranes, concrete pumps, cherry-pickers, etc. - restrictions apply to the hours of operation and the area where the operation will occur, etc. Separate permits are required for each occasion and each piece of equipment. It is the applicant's, owner's and builder's responsibilities to take whatever steps are necessary to ensure the use of any equipment does not violate adjoining property owner's rights.
- (b) Storage of building materials and building waste containers (skips) on Council's property.
- (c) Permits to utilise Council property for the storage of building materials and building waste containers (skips) are required for each location they are to be stored. Failure to obtain the relevant permits will result in the building materials or building waste containers (skips) being impounded. Storage of building materials and waste containers within Council's open space areas, reserves and parks is prohibited.
- (d) Kerbside restrictions - construction zones:
The applicant's attention is drawn to the possible existing kerbside restrictions adjacent to the development. Should the applicant require alteration of existing kerbside restrictions, or the provision of

a work zones, the appropriate application must be made to Council and the fee paid. Applicants should note that the alternatives of such restrictions may require referral to Council's Traffic Committee. An earlier application is suggested to avoid delays in construction programs..

The application is to be lodged with Council's Customer Service Centre.

Reason: Proper management of public land.

DC0010 Driveway Crossing Application

48. All works associated with the construction and/or extension of a driveway crossover/layback within Council owned land requires an application to be lodged and approved by Council.

All footpath crossings, laybacks and driveways are to be constructed according to Council's Specification for Construction or Reconstruction of Standard Footpath Crossings and in compliance with Standard Drawings DS1 (Kerbs & Laybacks); DS7 (Standard Passenger Car Clearance Profile); DS8 (Standard Vehicular Crossing); DS9 (Heavy Duty Vehicular Crossing) and DS10 (Vehicular Crossing Profiles).

The application for a driveway crossing requires the completion of the relevant application form and accompanied by plans, grades/levels and specifications. A fee in accordance with Councils adopted 'Fees and Charges' will need to be paid at the time of lodgement.

Note 1: This development consent is for works wholly within the property. Development consent does not imply approval of the footpath or driveway levels, materials or location within the road reserve, regardless of whether the information is shown on the development application plans.

Note 2: Council's Customer Service Team can advise of the current fee and can be contacted on 9806 5524

Reason: To provide suitable vehicular access without disruption to pedestrian and vehicular traffic.

BC0001 Toilet facilities on site

49. Prior to work commencing, adequate toilet facilities are to be provided on the work site.

Reason: To ensure adequate toilet facilities are provided.

ECC0001 Asbestos Hazard Management Strategy

50. The preparation of an appropriate hazard management strategy by an appropriately licensed asbestos consultant pertaining to the removal of contaminated soil, encapsulation or enclosure of any asbestos material is required. This strategy shall ensure that any such proposed demolition works involving asbestos are carried out in accordance with the requirements of the 'Code of Practice: How to Safely Remove Asbestos' published by Safework NSW. The strategy shall be submitted to the

Principal Certifying Authority, prior to the commencement of any works. The report shall confirm that the asbestos material has been removed or is appropriately encapsulated and that the site is rendered suitable for the development.

Reason: To ensure risks associated with the demolition have been identified and addressed prior to demolition work commencing.

ECC0002 Asbestos - signage

51. On demolition sites where buildings are known to contain friable or non-friable asbestos material, standard warning signs containing the words 'DANGER ASBESTOS REMOVAL IN PROGRESS' measuring not less than 400mm x 300mm are to be erected in a prominent position on site visible from the street kerb. The sign is to be erected prior to demolition work commencing and is to remain in place until such time as all asbestos material has been removed from the site. Advice on the availability of these signs can be obtained by contacting the Safework NSW hotline or their website www.safework.nsw.gov.au.

Reason: To comply with the requirements of Safework NSW.

ECC0003 Hazardous material survey

52. At least one (1) week prior to demolition, the applicant must submit to the satisfaction of the Principal Certifying Authority a hazardous materials survey of the site. Hazardous materials include (but are not limited to) asbestos materials, synthetic mineral fibre, roof dust, PCB materials and lead based paint. The report must be prepared by a suitably qualified and experienced environmental scientist and must include at least the following information:

- (a) The location of hazardous materials throughout the site;
- (b) A description of the hazardous material;
- (c) The form in which the hazardous material is found, eg AC sheeting, transformers, contaminated soil, roof dust;
- (d) An estimation (where possible) of the quantity of each particular hazardous material by volume, number, surface area or weight;
- (e) A brief description of the method for removal, handling, on-site storage and transportation of the hazardous materials, and where appropriate, reference to relevant legislation, standards and guidelines;
- (f) Identification of the disposal sites to which the hazardous materials will be taken.

Reason: To ensure risks associated with the demolition have been identified and addressed prior to demolition work commencing.

PC0001 #Appointment of PCA

53. Prior to commencement of work, the person having the benefit of the Development Consent and Construction Certificate approval must:

- (a) Appoint a Principal Certifying Authority (PCA) and notify Council in writing of the appointment (irrespective of whether Council or an accredited private certifier) within 7 days; and
- (b) Notify Council in writing a minimum of 48 hours prior to work commencing of the intended date of commencement.

The Principal Certifying Authority must determine and advise the person having the benefit of the Construction Certificate when inspections, certification and compliance certificates are required.

Reason: To comply with legislative requirements.

PC0002 Enclosure of the site

54. The site must be enclosed by a 1.8m high security fence erected wholly within the confines of the site to prevent unauthorised access. The fence must be installed to the satisfaction of the Principal Certifying Authority prior to the commencement of any work on site.

Reason: To ensure public safety.

PC0003 Site Sign

55. A sign must be erected in a prominent position on any site involving excavation, erection or demolition of a building in accordance with Clause 98 A (2) of the Environmental Planning and Assessment Regulations 2000 detailing:

- (a) Unauthorised entry of the work site is prohibited;
- (b) The name of the principal contractor (or person in charge of the work site), their telephone number enabling 24hour contact; and
- (c) The name, address and telephone number of the Principal Certifying Authority;
- (d) The development consent approved construction hours;
- (e) The sign must be maintained during excavation, demolition and building work, and removed when the work has been completed.
- (f) This condition does not apply where works are being carried out inside an existing building.

Reason: Statutory requirement.

PC0005 Public liability insurance

56. Public risk insurance in the amount of not less than \$20 million or such other amount as Council may require by notice) must be obtained and furnished to Council before any works authorised by this consent are conducted:

- (a) Above;
- (b) Below; or
- (c) On

Any public land owned or controlled by Council. The public risk insurance must be maintained for the period during which these works are being undertaken.

The public risk insurance must be satisfactory to Council and list Council as an insured and/or interested party.

A copy of the insurance policy obtained must be forwarded to Council before any of the works commence.

Note: Applications for hoarding permits, vehicular crossing etc. will require evidence of insurance upon lodgement of the application.

Reason: To ensure the community is protected from the cost of any claim for damages arising from works authorised by this consent conducted above, below or on any public land owned or controlled by Council.

PC0006 Noise Management Plan – Construction Sites

57. A noise management plan must be submitted to Council for approval prior to any work commencing and complied with during any construction works. The plan must be prepared by a suitably qualified person, who possesses qualifications to render them eligible for membership of the Australian Acoustic Society, Institution of Engineers Australia or the Australian Association of Acoustic Consultants.

The plan must include, but not be limited to the following:

- (a) Identify sensitive location near the site;
- (b) Identify potential impacts (i.e. exceedance of the goals at the identified locations);
- (c) Mitigation measures to control noise and dust from the site, the noise reduction likely and the feasibility and reasonableness of these measures;
- (d) Selection criteria for plant and equipment;
- (e) Community consultation;
- (f) Details of work schedules for all construction phases;
- (g) Selection of traffic routes to minimise residential noise intrusion;
- (h) Schedule of plant and equipment use and maintenance programs;
- (i) Noise monitoring techniques and method of reporting results;
- (j) The methodology to be employed for handling and investigating any complaints should they arise;
- (k) Site induction details for employees and contractors; and
- (l) A declaration of available technologies and the reason for the selection of the preferred technology from a noise generating perspective should be included.

Reason: To maintain appropriate amenity to nearby occupants.

PC0007 Footings and walls near boundaries

58. Prior to the commencement of work, a registered surveyor is to undertake a set out survey to identify the location of all footings, slabs, posts and walls adjacent to a boundary. This is to ensure the development when complete, will be constructed wholly within the confines of the subject allotment. This set out survey showing the location of the development relative to the

boundaries of the site, is to be forwarded to the Principal Certifying Authority prior to pouring of any footings or slabs and/or the construction of any walls/posts.

Reason: To ensure that the building is erected in accordance with the approval granted and within the boundaries of the site.

During Work

LD0004 Material storage and trees

59. No materials (including waste and soil), equipment, structures or goods of any type are to be stored, kept or placed within 5m of the trunk of a tree or within the drip line of any tree.

Reason: To ensure the protection of the tree(s) to be retained on the site.

LD0008 No attachments to trees

60. No service, structure, conduit or the like is permitted to be fixed or attached to any tree.

Reason: To ensure the protection of the tree(s).

LD0009 Planting Requirements

61. All trees planted as required by the approved landscape plan are to be a minimum 45 litre container size. All shrubs planted as part of the approved landscape plan are to have a minimum 200mm container size.

Reason: To ensure appropriate landscaping.

LD0011 Tree Removal

62. Trees numbered 1-18, 22-23, 28, 31-32, 47-51, 95, 97-99 & 183-185 are approved to be removed (refer to submitted Arboricultural Impact Assessment & Tree Protection Specification prepared by Tree IQ (Report No – WEST/CATHEW/AIA/ Revision 'B') dated 6 April 2020 for species and location.

Reason: To facilitate development.

LD0012 Trees with adequate root volume

63. All trees/shrubs planted within the site must be of an adequate root volume and maturity so as not to require staking or mechanical support. Planting must be carried out in accordance with the approved Landscape Plan and conditions of consent.

Reason: To ensure the trees/shrubs planted within the site are able to reach their required potential.

LD0013 Removal of trees by an arborist

64. All approved tree removal must be supervised by an Australian Qualification Framework (AQF) Level 3 Arborist in accordance with the provisions of the Safe Work Australia Guide to managing risks of tree trimming and removal work.

Reason: To ensure works are carried out in accordance the Safe Work Australia Guide to managing risks of tree trimming and removal work.

TD0001 Road Occupancy Permit

65. Occupation of any part of the footpath or road at or above (carrying out work, storage of building materials and the like) during construction of the development shall require a Road Occupancy Permit from Council. The applicant is to be required to submit an application for a Road Occupancy Permit through Council's Traffic and Transport Services, prior to carrying out the construction/restoration works.

Reason: To ensure proper management of Council assets.

TD0002 Oversize vehicles using local roads

66. Oversize vehicles using local roads require approval from the National Heavy Vehicle Regulator (NHVR). The applicant is to be required to submit an application for an Oversize Vehicle Access Permit through NHVR's portal (www.nhvr.gov.au/about-us/nhvr-portal), prior to driving through local roads within the City of Parramatta LGA.

Reason: To ensure maintenance of Council's assets.

DD0005 Erosion & sediment control measures

67. Works are not to result in sedimentation and or run-off from the approved works onto the adjoining properties and or public lands. The person having the benefit of this consent must ensure sediment is not tracked out from the development site.

Reason: To ensure no adverse impacts on neighbouring properties.

DD0006 Damage to public infrastructure

68. Any damage to Council assets that impacts on public safety during construction is to be rectified immediately to the satisfaction of Council with all costs to be borne by the person having the benefit of the Development Consent.

Reason: To protect public safety.

DD0009 Car parking & driveways

69. Car parking area and internal accessways must be constructed, marked and signposted in accordance with AS2890.1 –2004 'Off Street Car Parking Facilities' prior to an Occupation Certificate being issued.

Reason: To ensure appropriate car parking.

DD0011 Nomination of Engineering Works Supervisor

70. During construction of all public area civil and drainage works a qualified civil engineer must supervise the work to ensure it is completed in accordance with Council's "Guidelines for Public Domain Works". Certification is required to be provided with the Occupation Certificate.

Reason: To ensure Council's assets are appropriately constructed.

EWD0001 Asbestos-records disposal& licensed waste facility

71. Where demolition of asbestos containing materials is undertaken, the contractor must submit to the Principal Certifying Authority, copies of all receipts issued by the EPA licensed waste facility for friable or non-friable asbestos waste as evidence of proof of proper disposal within 7 days of the issue of the receipts.

Reason: To ensure appropriate disposal of asbestos materials.

EWD0002 Asbestos handled& disposed of by licensed facility

72. All friable and non-friable asbestos-containing waste material on-site shall be handled and disposed off-site at an EPA licensed waste facility by an EPA licensed contractor in accordance with the requirements of the Protection of the Environment Operations (Waste) Regulation 2014 and the Waste Classification Guidelines – Part 1 Classifying Waste (EPA 2014) and any other regulatory instrument as amended.

Reason: To ensure appropriate disposal of asbestos materials.

EWD0003 Waste data file maintained

73. A Waste Data file is to be maintained, recording building/demolition contractor's details and waste disposal receipts/dockets for any demolition or construction wastes from the site. These records must be retained and made available to Council on request.

Reason: To confirm waste minimisation objectives under Parramatta Development Control Plan 2011 are met.

EWD0004 Hazardous/intractable waste disposed of in accor.

74. Hazardous or intractable wastes arising from the demolition process shall be removed and disposed of in accordance with the requirements of Safework NSW and the EPA, and with the provisions of:

- (a) Work Health and Safety Act 2011;
- (a) NSW Protection of the Environment Operations Act 1997 (NSW); and
- (b) NSW Department of Environment and Climate Change Environmental Guidelines; NSW EPA Waste Classification Guidelines.

Reason: To ensure that the land is suitable for the proposed development and any contaminating material required to be removed from the property is removed in accordance with the prescribed manner.

EWD0005 General requirements for liquid and solid waste

75. Liquid and solid wastes generated onsite shall be collected, transported and disposed of in accordance with the Protection of the Environment Operations (Waste) Regulation 2014 and in accordance with DECC the

Environmental Guidelines Assessment, Classification and Management of Liquid and Non-Liquid Wastes (1999) and NSW EPA Waste Classification Guidelines.

Reason: To prevent pollution of the environment.

EWD0008 Contaminated waste to licensed EPA landfill

76. Any contamination material to be removed from the site shall be disposed of to an EPA licensed landfill.

Reason: To comply with the statutory requirements of the Protection of the Environment Operations Act 1997.

PD0001 Copy of development consent

77. A copy of this development consent together with the stamped plans, referenced documents and associated specifications is to be held on-site during the course of any works to be referred to by all contractors to ensure compliance with the approval and the associated conditions of consent.

Reason: To ensure compliance with this consent.

PD0003 Dust Control

78. Dust control measures shall be implemented during all periods of earth works, demolition, excavation and construction to minimise the dust nuisance on surrounding properties. In this regard, dust minimisation practices must be carried out in accordance with Section 126 of the Protection of the Environment Operations Act 1997.

Reason: To protect the amenity of the area.

PD0004 Materials on footpath

79. No building materials skip bins, concrete pumps, cranes, machinery, temporary traffic control, signs or vehicles associated with the construction, excavation or demolition shall be stored or placed on/in Council's footpath, nature strip, roadway, park or reserve without the prior approval being issued by Council under section 138 of the Roads Act 1993.

Reason: To ensure pedestrian access.

PD0006 Hours of work and noise

80. All work (excluding demolition which has separate days and hours outlined below) including building, and excavation work; and activities in the vicinity of the site generating noise associated with preparation for the commencement of work (e.g. loading and unloading of goods, transferring of tools, machinery etc.) in connection with the proposed development must only be carried out between the following hours:

- Monday to Friday inclusive: 7.00am and 5.00pm; and
- Saturday: 8.00am to 5.00pm.
- No work is to be carried out on Sunday or Public Holidays.

Demolition works are restricted to:

- Monday to Saturday: 7.00am to 7.00pm; and
- No demolition works are to be undertaken on Sundays or Public Holidays.

Note: Council may permit an extension to the approved hours of work in extenuating or unforeseen circumstances subject to an application and approval by City of Parramatta Council (CoPC) in accordance with the 'After Hours Works for Approved Development Applications Policy' (Policy).

A copy of this Policy and associated application form is available on the CoPC website. A fee will apply to any application made in accordance with this Policy.

The matters of consideration of any extension sought would include, but not be limited to the following aspects and should be detailed in any application made:

- Nature of work to be conducted;
- Reason for after-hours completion;
- Residual effect of work (noise, traffic, parking);
- Demographic of area (residential, industrial);
- Compliance history of subject premises;
- Current hours of operation;
- Mitigating or extenuating circumstance; and
- Impact of works not being completed.

Reason: To protect the amenity of the area.

PD0007 Complaints register

81. The applicant must record details of all complaints received during the construction period in an up to date complaints register. The register must record, but not necessarily be limited to:

- The date and time of the complaint;
- The means by which the complaint was made;
- Any personal details of the complainants that were provided, or if no details were provided, a note to that effect;
- Nature of the complaints;
- Any action(s) taken by the applicant in relation to the complaint, including any follow up contact with the complaint; and
- If no action was taken by the applicant in relation to the complaint, the reason(s) why no action was taken.

The complaints register must be made available to Council and/or the Principal Certifying Authority upon request.

Reason: To allow the Principal Certifying Authority/Council to respond to concerns raised by the public.

PD0009 Importation of clean fill

82. Any fill material, required by this consent, imported to the site is to be virgin excavated natural material (VENM) and is to be certified as such by a suitably qualified industry professional. The certification of each delivery is to be kept on site and produced for inspection if requested.

Reason: To ensure the site does not become contaminated and appropriate compaction levels can be achieved.

PD0010 Survey Report

83. A survey certificate is to be submitted to the Principal Certifying Authority at footing and/or formwork stage. The certificate must indicate the location of the building in relation to all boundaries, and must confirm the floor level is consistent with that approved under this consent prior to any further work proceeding on the building.

Reason: To ensure the development is being built as per the approved plans.

HD0002 Aboriginal and European Archaeology

84. If any European archaeological relics are discovered (or are believed to be discovered) during works, the works must cease and the NSW Office of Environment and Heritage must be notified, in accordance with the NSW Heritage Act.

If any Aboriginal archaeological relics are discovered (or are believed to be discovered) during works, the works must cease and the NSW Office of Environment and Heritage must be notified, in accordance with the NSW National Parks and Wildlife Service Act.

Reason: To ensure that the requirements of the Office of Environment and Heritage are met.

Prior to the issue of an Occupation Certificate

LE0002 Cert.Auth.Arrange Qualified LandscapeArch.(multi)

85. A qualified Landscape Architect/Designer must certify that the completed works are in accordance with the approved landscape plan. All landscape works must be completed prior to the issue of an Occupation Certificate.

Reason: To ensure restoration of environmental amenity.

TENSC Non-standard - Prior to issue of Occ

86. Prior to the issue of the relevant occupation certificate, the applicant must submit a Drop-Off/Pick-Up Management Plan to the satisfaction of Council's Traffic and Transport Manager, supported by details of how that Plan will be implemented during the operation of the school. The Plan must include the following requirements:

- Details and instructions pertaining to the use of the drop-off/pick-up facility along with other operational aspects of travel to and from the school;

- Ensure there is no queueing in Darcy Road, even if this means requiring parents to drive through the site and do a lap of the block in order to pick up a student (for example, if a large number of parents arrive early to pick students before classes finish).
- Preferred access routes to and from the car park access at Darcy Road;
- Internal circulation routes to be followed and queuing procedures;
- Unloading / loading procedures (e.g. drivers to stay in their vehicles);
- Monitoring scheme and a review of the measures based on the results of the monitoring scheme including making adjustments as required (e.g. staggered drop-off/pick-up times for students).

Reason: To ensure appropriate operation of the drop-off/pick-up facility.

DE0003 Work-as-Executed Plan

87. Works-As-Executed stormwater plans are to address the following:

- (a) The Work-As-Executed plans are prepared on the copies of the approved drainage plans issued with the Construction Certificate with the variations marked in red ink.
- (b) The Work-As-Executed plans have been prepared by a registered surveyor certifying the accuracy of dimensions, levels, storage volumes, etc.
- (c) The as built On-Site Detention (OSD) storage volumes are to be presented in a tabular form (depth verses volume table
- (d) OSD Works-As-Executed dimensions form (refer to UPRCT Handbook).
- (e) Certificate of Hydraulic Compliance from a qualified drainage / hydraulic engineer (refer to UPRCT Handbook).
- (f) Certificate of Structural compliance of the OSD tank walls and cover slab from a qualified structural engineer

The above is to be submitted to the Principal Certifying Authority prior to the issue of an occupation certificate and a copy is to accompany the Occupation Certificate when lodged with Council.

Reason: To ensure works comply with approved plans and adequate information is available for Council to update the Upper Parramatta River Catchment Trust.

DE0005 #OSD Positive Covenant/Restriction

88. Prior to the issue of an Occupation Certificate a Positive Covenant and Restriction on the Use of Land under Section 88E of the Conveyancing Act 1919 must be created, burdening the owner with the requirement to maintain the stormwater detention and water quality management system on the lot.

The terms of the 88E Instruments are to be generally in accordance with Council's "standard terms" available in Council's website, under Development Forms.

Where a Title exists, the Positive Covenant and Restriction on the Use of Land is to be created through via an application to the Land Titles Office using forms 13PC and 13RPA. Accompanying this form is the requirement for a plan to scale showing the relative location of the stormwater management system.

Registered title documents showing the covenants and restrictions must be submitted to and approved by the Principal Certifying Authority prior to Occupation or use of on-site.

Reason: To ensure maintenance of the stormwater management system.

DE0006 Section 73 Certificate

89. A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained prior to the issue of any Occupation Certificate. The application must be made through an authorised Water Servicing Coordinator. Please refer to “Your Business” section of Sydney Water’s web site at www.sydneywater.com.au then the “e-developer” icon or telephone 13 20 92.

Reason: To ensure the requirements of Sydney Water have been complied with.

DE0015 Driveway Crossover

90. Prior to the issue of any Occupation Certificate, an application is required to be obtained from Council for any new, reconstructed or extended sections of driveway crossings between the property boundary and road alignment.

All footpath crossings, laybacks and driveways are to be constructed according to Council’s Specification for Construction or Reconstruction of Standard Footpath Crossings and in compliance with Standard Drawings DS1 (Kerbs & Laybacks); DS7 (Standard Passenger Car Clearance Profile); DS8 (Standard Vehicular Crossing); DS9 (Heavy Duty Vehicular Crossing) and DS10 (Vehicular Crossing Profiles).

The application for a driveway crossing requires the completion of the relevant application form and be accompanied by detailed plans showing, grades/levels and specifications that demonstrate compliance with Council’s standards, without conflict with all internal finished surface levels. The detailed plan must be submitted to Council’s Civil Assets Team for approval prior to commencement of the driveway crossing works. A fee in accordance with Councils adopted ‘Fees and Charges’ will need to be paid at the time of lodgement.

Note 1: This development consent is for works wholly within the property. Development consent does not imply approval of the footpath or driveway levels, materials or location within the road

reserve, regardless of whether the information is shown on the development application plans.

Note 2: Council's Customer Service Team can advise of the current fee and can be contacted on 9806 5524.

Reason: Pedestrian and Vehicle safety.

DE0018 Reinstatement of laybacks etc

91. All redundant lay-backs and vehicular crossings must be reinstated to conventional kerb and gutter, foot-paving or grassed verge in accordance with Council's Standard Plan No. DS1. The reinstatement must be completed prior to the issue of an Occupation Certificate. All costs must be borne by the applicant.

Reason: To provide satisfactory drainage.

EAE0001 #All works/methods/procedures/control measures

92. Prior to the issue of an occupation certificate (Interim or Final), written certification from a suitably qualified person(s) shall be submitted to the Principal Certifying Authority and City of Parramatta Council, stating that all works/methods/procedures/control measures approved by Council in the following report have been completed:

(a) Noise and Vibration Impact Assessment, project number 190529, Revision B, dated 3 April 2020, prepared by JHA Consulting Engineers.

Reason: To demonstrate compliance with submitted reports.

PE0001 Occupation Certificate

93. Occupation or use of the building or part is not permitted until an Occupation Certificate has been issued in accordance with Section 109H of the Environmental Planning and Assessment Act 1979.

Reason: To comply with legislative requirements of the Environmental Planning and Assessment Act 1979.

PE0009 Provision of Endeavour Energy services

94. Submission of documentation confirming satisfactory arrangements have been made for the provision of electricity services from an approved electrical energy provider prior to the issue of an Occupation Certificate.

Reason: To ensure appropriate electricity services are provided.

PE0019 Floodlighting/light spillage diagram

95. A light spillage diagram is required to be prepared by a suitably qualified lighting engineer and submitted to the Principal Certifying Authority prior to the issue of the Occupation Certificate. This diagram is to demonstrate light spillage generated by the proposed floodlighting system complies with the requirements of Australian Standard AS4284 - Control of Obtrusive Effects of Outdoor Lighting. Light spillage mitigating measures shall be maintained, at all times.

Reason: To prevent light spillage onto adjoining properties.

PE0024 The Release of Bond(s)

96. A written application to Council's Civil Assets Team for the release of a bond must quote the following:

- (a) Council's Development Application number; and
- (b) Site address.

The bond is refundable only where Council is satisfied the public way has been adequately reinstated, and any necessary remediation/rectification works have been completed.

An Occupation Certificate is not to be issued until correspondence has been issued by Council detailing the bond has been released.

Note: Council's Civil Assets Team will take up to 21 days from receipt of the request to provide the written advice.

Reason: To safe guard the public assets of council and to ensure that these assets are repaired/maintained in a timely manner.

The Use of the Site

EAF0008 Noise to street

97. There are to be no external facing speakers on the façade of the multi-storey car park.

Reason: To prevent loss of amenity to the area.

EAF0007 Noise from mechanical equipment

98. The proposed use of the premises and the operation of all plant and equipment shall not give rise to an 'offensive noise' as defined in the Protection of the Environment Operations Act 1997.

Reason: To protect the amenity of the area.

PF0049 Graffiti Management

99. The owner/manager of the site/business is responsible for the removal of all graffiti from the building/structures/signage and/or fencing within 48 hours of its application.

Reason: To ensure the removal of graffiti.

EWF0003 Remove putrescible waste at sufficient frequency

100. All putrescible waste shall be removed from the site with sufficient frequency to avoid nuisance from pests and odours.

Reason: To ensure provision of adequate waste disposal arrangements.

EAF0004 No 'offensive noise'

101. Noise and vibration from the use and operation of any plant and equipment and/or building services associated with the premises shall not give rise to

"offensive noise" as defined by the Protection of the Environment Operations Act 1997.

Reason: To reduce noise levels.

PF0004 External Plant/Air-conditioning noise levels

102. Any external plant/air-conditioning system on or adjacent to the multi-storey car park in the north-eastern corner of the site must not exceed a noise level of 5dBA above the background noise level when measured at the boundaries of the property.

Reason: To minimise noise impact of mechanical equipment.

PF0006 Advertisement/ Signage consent

103. No advertisement/signage shall be erected on or in conjunction with the development without prior consent.

Reason: To comply with legislative controls.