



ARBORICULTURAL IMPACT ASSESSMENT REPORT



BOTANY AQUATIC CENTRE

FOR



PREPARED BY

STURT NOBLE ARBORICULTURE
CONSULTING ARBORISTS
Suite 307, 166 Glebe Point Rd, Glebe NSW

6th November 2024 DA issue Rev. E
PROJECT: 2307

CONTENTS

1.0	INTRODUCTION	6
2.0	METHODOLOGY	7
2.1	Site Inspection	7
2.2	Tree Locations	7
2.2.1	Visual Tree Assessment	7
2.2.2	Retention Value	7
2.2.3	Tree Protection Zones (TPZ) and Structural Root Zones (SRZ)	7
2.2.4	Encroachment and Development Impacts	8
3.0	OBSERVATIONS	9
3.1	The Site	9
3.2	Soils	9
3.3	Vegetation Community	9
3.4	Tree Health and Condition	10
3.6	Construction Impacts	11
4.0	DISCUSSION	12
4.2	Tree Retention	12
4.3	Tree Protection	13
4.3.1	Tree Protection Zones (TPZ)	13
5.0	CONCLUSIONS	14
6.0	TREE PROTECTION RECOMMENDATIONS	16
6.1	Design of the Development	16
6.2	Tree Removal	16
6.3	Canopy and root pruning	16
6.3.1	Canopy pruning	16
6.3.2	Root pruning	16
6.4	Tree Protection Measures	17
6.4.1	Tree Protection Zones	17
6.4.2	Tree Protection Fencing	18
6.4.3	Trunk, Branch & Ground Protection	18
6.4.4	Demolition Works within Tree Protection Zones	18
6.4.5	Underground Services	19
6.4.7	Tree Damage/ Decline	19
7.0	DISCLAIMER	20
8.0	REFERENCES	21
	APPENDIX 1: METHODOLOGY	22
	APPENDIX 2: PLANS	26
	APPENDIX 3: TREE ASSESSMENT SCHEDULE	27
	APPENDIX 4: TYPICAL TREE PROTECTION DETAILS	28

1.0 INTRODUCTION

Sturt Noble Arboricultural Consulting was engaged by Co.Op Studio to assess the trees on the site of a proposed redevelopment of Botany Aquatic Centre at the corner of Myrtle St and Jasmine St, Botany. We were also engaged to provide an Arboricultural Assessment Report, including management of any trees proposed to be retained, to assist Co.Op in preparing a Development Application to Bayside Council.

The Development Application seeks consent to redevelop existing outdoor and indoor swimming pools, open green space and buildings, and construct a new grandstand, health and fitness space, community space and new water play areas. This development will require removal of twenty-two (22) of the existing trees on site. All other trees will be retained and protected on site adjacent to the site on Council land and private industrial lots.

Arborist Guy Sturt inspected two hundred and twenty-seven (227) trees (Denoted trees 1-206) on 21st, 22nd and 28th of May 2020; and trees were assessed by the Visual Tree Assessment (VTA) method. (Mattheck & Breloer, 1994).

All of the trees were assessed by viewing from the ground. No aerial inspection or diagnostic testing was undertaken as part of this assessment.

Consulting Arborist Guy Sturt; in this report considers the likely impacts of works proposed and makes recommendations for tree removal, retention and protection.

The aims of this report are:

- To assess and review the condition of existing trees by undertaking a Visual Tree Assessment
- Assess each individual tree's suitability to be retained as a sustainable part of the proposed development in the long term, considering the likely impacts of works proposed.
- Provide recommendations for tree removal, retention and protection.
- Provide recommendations where appropriate to enable trees to be retained or have better long-term health outcomes and minimize potentials for hazard.
- To provide information on appropriate tree protection measures, appropriate setbacks, constraints and tree management procedures during site works.

None of the trees identified on the development site are listed as Threatened or Vulnerable species or form part of Bushland or an Endangered Ecological Community.

2.0 METHODOLOGY

2.1 Site Inspection

This report, its comments and recommendations have been prepared based on the information gathered during two detailed site inspections carried out on the on the 21st May and the 29th May 2020. This assessment is summarised in Appendix 1.

2.2 Tree Locations

The location of the subject trees are based on the site survey; *B04710-DETAIL*, Prepared by Project Surveyors on the 27/04/2020.

2.2.1 Visual Tree Assessment

The trees were assessed from the ground by the Visual Tree Assessment (VTA) method as described in Mattheck & Breloer (1994), using non-invasive tools such as binoculars and acoustic mallet. No digging or exposing of the root zones occurred in this inspection and no aerial inspection by climbing was performed. No aerial inspection or diagnostic testing was undertaken as part of this assessment.

The following data was collected for each tree:

- Botanical and common name.
- Tree dimensions (approximate only).
- Canopy density (approximate only).
- Overall health and vitality, including epicormic growth, deadwood and predation by pests and diseases.
- Structural condition including evident faults such as Bark Inclusions or poor branch attachments, decay, cavities and mechanical or biological damage.
- Stability of the tree including excessive trunk lean, stability of the soil, soil cracking, soil heaving, exposed roots and root damage.

2.2.2 Retention Value

Each tree has been given a Sustainable Retention Index Value (SRIV) according to the rating system set out in the Sustainable Retention Index Value Matrix (refer to Appendix 2). The SRIV for each tree is based on its health, vigour, structure and age class as established in the Visual Tree Assessment. The SRIV does not take into account the impact of the proposed development.

2.2.3 Tree Protection Zones (TPZ) and Structural Root Zones (SRZ)

The intention of the TPZ is to ensure protection of the root system and canopy from the potential damage from construction works and ensure the long-term health and stability of each tree to be retained.

The Structural Root Zone (SRZ) is located within the TPZ around the base of a tree and provides the bulk of mechanical support and anchorage for a tree.

The Tree Protection Zones (TPZ) and Structural Root Zones (SRZ) have been arrived at using methods as detailed in Australian Standard AS 4970– 2009. Specific site factors are also considered that may influence the location of the TPZ and/or structural tree roots.

2.2.4 Encroachment and Development Impacts

Encroachments and development impacts to tree TPZ's and SRZ's include;

- Excavation
- Filling
- Changes to existing soil levels
- Placing items and elements within the zones even if only temporarily
- Soil disturbance
- Any other physical damage to the trunk or root system or any other activity likely to cause damage to the tree.

Under AS 4970:2009 Protection of trees on development sites, a minor encroachment of up to 10% of the area of the TPZ is considered acceptable, provided that there is no encroachment to the SRZ. The area lost to this encroachment should be compensated for elsewhere in a contiguous area to the TPZ.

Major encroachments is greater than 10% of the area of the TPZ and the Project Arborist must determine and demonstrate that the tree would remain viable. More detailed investigations, such as exploratory excavations and root investigation to enable an informed evaluation of the potential impact of the proposed works may be required.

Encroachments into the SRZ are not likely to be supported unless the Project Arborist has undertaken exploratory investigation and can demonstrate that there will be minimal impact to the tree.

3.0 OBSERVATIONS

3.1 The Site

The site is a portion of land accessible from Myrtle St with close proximity to the train corridor at the rear. The site features a carpark to the east, the main pool outdoor area in the centre and a separate fenced off area to the west that contains the majority of the trees.

A preliminary assessment of the trees in the fenced off area was only included (species and general comments only) as this was outside the scope of the proposed development.

Tree specimens on site generally receive full sun exposure although some specimens in the western area are suppressed by their close proximity to each other.

Figure 1: Location Plan



3.2 Soils

The site is underlain by layers of marine quartz sands and sections of fill. Before settlement this area would have consisted of gently undulating coastal dunefields, however the site has been highly disturbed by human activity. It is likely that the sandy soils have been disturbed and areas could consist of fill covered by a layer of sand or clay.

3.3 Vegetation Community

The site is highly disturbed and modified. It would appear all the locally-indigenous vegetation has been cleared for the Aquatic centre. As noted by Doug Benson & Jocelyn Howell in "Taken for granted" the original vegetation of this area consisted of Low Swamp Woodland & Eastern Suburbs Banksia Scrub, with dominant locally-indigenous tree species including *Angophora costata* (Sydney Red Gum), *Eucalyptus piperita* (Sydney Peppermint) and *Banksia aemula* (Wallum Banksia) on higher areas and *Eucalyptus robusta* (Swamp Mahogany) and *Melaleuca quinquenervia* (Broadleaved Paperbark) occurring in low lying areas.

Booralee Park was proclaimed a Reserve on 17 September 1886. Botany Council cleared, grassed and planted trees in the park and in 1965 an Olympic pool was constructed at the site.

Although there are large stands of the endemic *Melaleuca quinquenervia* (Broadleaved Paperbark) existing and also specimens of *Angophora costata* (Sydney Red Gum), *Eucalyptus robusta* (Swamp Mahogany) and *Eucalyptus botryoides* (Bangalay); given the estimated age of these trees and the planting layout they would appear to have been planted and not remnant.

The existing plantings (227 trees/ palms) consist of a range of both exotic, non-local native and endemic species, located mostly around the periphery of the site. The trees have all been identified by number on the tree plan in Appendix 2. There are also a smaller number of exotic species (27).

3.4 Tree Health and Condition

A complete tree assessment schedule for the trees located within the current site was prepared and is included in Appendix 1. This includes the following: a tree number, botanical name, common name, height, canopy spread, canopy density, defects, pests & diseases and a SRIV rating (IACA 2010).

Botany Bay Development Control Plan 2013 Part 3L Landscaping and Tree management states that *“tree works requiring Council approval are actions affecting the health, form, habitat or canopy of a tree or vegetation community and includes modification to the tree crown (all types of pruning work, crown thinning and crown lifting – refer to AS4373-2007), root pruning and tree removal.”*

The removal, lopping, topping, ring barking, injuring or wilful destruction of the following trees and vegetation without Council approval is prohibited:

(i) Any tree works that are not considered to be exempt (refer to Part 3L. 4.3 – Exempt Tree Works);

A *Morus alba* (Mulberry) is the only tree which is exempt under their listing.

(ii) Any tree, palm or vegetation on private land (other than an exempt species listed in Table 3L.1) at least 3 metres in height or with a diameter at breast height (DBH) equal to or greater than 200mm or 600mm circumference for a multi trunked tree;

(iii) Any tree or plant identified as a heritage item, located on a heritage listed property; and

(iv) Any vegetation within an area identified as an Endangered Ecological Community under the Threatened Species Conservation Act 1995 or protected by any other State or Federal legislation (Environment Protection and Biodiversity Conservation Act 1999) irrespective of size.

Part 3L. 4.3: Exempt Tree Works

The following tree removal or pruning works do not require Council approval:

(i) Any tree works that do not require approval under Section 3L.4.2 – Tree Works Requiring Council Approval;

(ii) Tree works to exempt species identified in Table 3L.1;

(iii) Trees that meet criteria under SEPP (Exempt & Complying Development Codes) 2008 (Clause 3.6A and Clause 5A.3);

(iv) Removal of noxious weed species in the Botany Bay Local Government Area under the Noxious Weeds Act 1993 (as listed in Part 10 – Landscape Technical Guidelines for Development Sites);

(v) Pruning near domestic power or telecommunications lines to maintain line distance clearance where the work is a maximum distance clearance of 500mm of branches up to 50mm diameter at the nearest branch collar (Branch collar is the point of attachment to another branch/trunk). Work must be carried out by an experienced Arborist or Tree Surgeon AQF Level 5 in accordance with AS4373-2007;

(vi) Minor pruning work at a maximum distance clearance of 2 metres measured from the surface of the structural component (wall/ roof) of the building's edge and of branches up to 50mm in diameter at the nearest branch collar. (Branch collar is the point of attachment to another branch/trunk for branches overhanging the roof only);

(vii) Tree works authorised under the Electricity Supply Act 1995 or the Roads Act 1993;

(viii) Emergency work carried out by Council, State Emergency Services, Fire Services or a public authority;

(ix) Removal or pruning works undertaken by Council or a contractor acting on behalf of Council on Council owned or controlled land; and

(x) Where Council is satisfied the tree is dying or dead or poses a risk to human health or safety.

None of the native trees identified on the site are listed as Threatened or Vulnerable species or form part of Bushland or an Endangered Ecological Community.

3.6 Construction Impacts

Foreseeable impacts to note from the proposed construction type and anticipated methodology include:

- Demolition Activities
- Excavations for Foundations, paved areas and access paths.
- Excavations for crossovers and driveways.
- Excavations and trenching for underground services.
- Soil level changes including the placement to make up grades
- Laying impermeable paving to paths and slabs.
- Movement and storage of plant, equipment & vehicles;
- Erection of site sheds;
- Storage of building materials, waste and waste receptacles;

4.0 DISCUSSION

4.2 Tree Retention

The Retention Values for all trees on site was prepared and is included in the Tree Assessment in Appendix 3. These values have been determined on the basis of the estimated longevity of the trees and their landscape significance rating.

Of the surveyed trees; 127 trees were assessed. The impacts of the construction of the new aquatic centre are critical with regard to twenty-two (22) of the existing trees on site which will require removal. Four of these (Tree Nos. 46,47,47A and 51) need to be further assessed by Project Arborist and may be able to be retained if they are deemed to be not only safe but also if there is minimal impact to the tree and the tree can continue to thrive and provide amenity.

In addition; 13 palms to be removed will be transplanted for reuse on site.

It is assumed for this report that excavation for construction of the new aquatic centre will not extend greater than 500mm from the footprint; and this limit can be considered to be the extent of disturbance to the root zones with the exception of service lines.

Further detail of site works are required particularly details of excavation extent of services (water, telecoms and electrical), design details, levels of pavements and level changes, particularly within the TPZ of any trees proposed for retention. This should be provided prior to construction so any additional impacts can be assessed.

Table 1: Trees to be removed

Poor Health/Senescent	Exempt	Major Encroachment: Tree Trunk within New Footprint
15A, 65		36,37,41,48,49,50,52-59,180A,196A,196-199

Table 2: Trees to be retained

Clear of all Works	Major Encroachment: Tree Trunk within New Footprint	Transplanted
1-15,16-21,34,39,40,42-45,60-64,65A, 66-180,181,182,183,184A,185,185A, 185B,186,187,195,200-202	35,38,179A 184,188-194,203-206	22-33

Table 3: Trees to be investigated during construction for potential retention

Potential Retention: To be assessed by Arborist due to health and hazard potential
46, 47, 47A and 51

Proposed site design and construction of the development and associated infrastructure/facilities should consider the Tree Protection Zones as discussed in the following sections to minimise any adverse impact.

4.3 Tree Protection

4.3.1 Tree Protection Zones (TPZ)

The intention of the TPZ is to ensure protection of the root system from potential damage from construction works and ensure the long-term health and stability of each tree to be retained. Suitable protective devices, such as temporary fencing, trunk protection boards or ground protection (where appropriate) must be installed to ensure adequate protection of a tree from construction activity and avoid disturbance within the TPZ.

The indicative TPZ areas have been calculated as specified in Section 3.2 of *AS 4970:2009 Protection of trees on development sites*.

Additionally the report considers and addresses specific site factors that may influence the location of the TPZ and/or structural tree roots. Examples of factors to be considered are (but not limited to) the location of existing footings, paths, kerbs and roadways, other vegetation and soil types. The indicative TPZ may require adjustment accordingly.

AS 4970:2009 Protection of trees on development sites prohibits the following activities within specified Tree Protection Zones:

- a. *excavations and trenching (with exception of the approved foundations and underground services);*
- b. *ripping or cultivation of soil;*
- c. *mechanical removal of vegetation (using an excavator or similar);*
- d. *soil disturbance or movement of natural rock;*
- e. *soil level changes including the placement of fill material (excluding any suspended floor or slab);*
- f. *movement and storage of plant, equipment & vehicles;*
- g. *erection of site sheds;*
- h. *affixing of signage or hoardings to trees;*
- i. *storage of building materials, waste and waste receptacles;*
- j. *storage of bulk materials such as sand, gravel, soil, spoil or similar materials;*
- k. *disposal of waste materials and chemicals including paint, solvents, cement slurry, fuel, oil and other toxic liquids; and*
- l. *any other physical damage to the trunk or root system or any other activity likely to cause damage to the tree.*

5.0 CONCLUSIONS

127 trees have been considered on the site as part of this assessment and their locations are shown in **Appendix 2**.

The proposed development is a refurbishment of construction of the new aquatic centre.

Of the surveyed trees; 127 trees were assessed. The impacts of the construction of the new aquatic centre are critical with regard to twenty-two (22) of the existing trees on site which will require removal. Four of these (Tree Nos. 46,47,47A and 51) need to be further assessed by Project Arborist and may be able to be retained if they are deemed to be not only safe but also if there is minimal impact to the tree and the tree can continue to thrive and provide amenity.

In addition; 13 palms to be removed will be transplanted for reuse on site.

It is assumed for this report that excavation for construction of the new aquatic centre will not extend greater than 500mm from the footprint; and this limit can be considered to be the extent of disturbance to the root zones with the exception of service lines.

Further detail of site works are required particularly details of excavation extent of services (water, telecoms and electrical), design details, levels of pavements and level changes, particularly within the TPZ of any trees proposed for retention. This should be provided prior to construction so any additional impacts can be assessed.

Table 1: Trees to be removed

Poor Health/Senescent	Exempt	Major Encroachment: Tree Trunk within New Footprint
15A, 65		36,37,41,48,49,50,52-59,180A,196A,196-199

Table 2: Trees to be retained

Clear of all Works	Major Encroachment: Tree Trunk within New Footprint	Transplanted
1-15,16-21,34,39,40,42-45,60-64,65A, 66-180,181,182,183,184A,185,185A, 185B,186,187,195,200-202	35,38,179A 184,188-194,203-206	22-33

Table 3: Trees to be investigated during construction for potential retention

Potential Retention: To be assessed by Arborist due to health and hazard potential
46,47, 47A and 51

Proposed site design and construction of the development and associated infrastructure/facilities should consider the Tree Protection Zones as discussed in the following sections to minimise any adverse impact.

Detail design and documentation of services should be provided prior to construction so any addition impacts can be assessed.

Where recommended work processes and tree protection measures cannot be adhered to further advice should be sought from the Project Arborist.

6.0 TREE PROTECTION RECOMMENDATIONS

6.1 Design of the Development

Trees on the site are mostly mature specimens adapted to the existing conditions. In general any proposed new developments shall optimally provide for the long term health of those existing trees which are recommended for retention.

Excavation/ Construction on the site will require that close attention be paid to management of all trees being retained. Any disturbance to soil structure could destabilise the trees. Should any changes to soil within the TPZ/ SRZ be proposed further discussion and assessment must be undertaken.

6.2 Tree Removal

Application for removal of twenty-two (22) should be sought as part of the Development Application. Namely:-

Poor Health/Senescent	Exempt	Major Encroachment: Tree Trunk within New Footprint
15A, 65		36,37,41,48,49,50,52-59,180A,196A,196-199

6.3 Canopy and root pruning

6.3.1 Canopy pruning

Care shall be taken when operating backhoes, excavators and similar equipment near trees to avoid damage to tree canopies (foliage and branches). Under no circumstances shall branches be torn-off by construction equipment. Where there is potential conflict between tree canopy and construction activities, the advice of the Project Arborist must be sought.

All pruning works shall be directed by the Project Arborist and shall be carried out by an AQF Level 3 Arborist. All pruning works shall be in accordance with the Australian Standard (AS) 4373:2007 *Pruning of amenity trees*. This standard outlines appropriate pruning practices and procedures that reduce the risk of damage and injury to trees. Correct pruning practices respect the natural form and branching habit of a tree and work with the trees natural defence mechanisms against disease to avoid damage and injury to trees.

Pruning should always be limited to the minimum amount necessary to achieve the desired aim. Significant loss of foliage created by excessive pruning may weaken the tree, leading to premature decline or predisposition to branch failure or disease, creating potential hazards.

Council consent will be required prior to commencement of the work. Pruning must be performed in accordance with Australian Standard (AS) 4373:2007 *Pruning of amenity trees* (Standards Australia 2007).

6.3.2 Root pruning

Exploratory excavation may be required where the proposed excavation created by the development works exceeds 10% of the Tree Protection Zone of any Prescribed Tree; or service trenches are required within the TPZ; to determine the impact of the development on the tree. The purpose of the investigation is to verify the quantity, size, type, depth and orientation of tree roots along the perimeter of the proposed encroachment in order to make an informed judgement in relation to the potential impact on the tree.

Exploratory excavation shall only be carried out using non-destructive or non-injurious techniques, such as careful digging using handheld implements, using compressed air (Airscape®), water pressure, or suction (vacuum device) or a combination of these techniques, to carefully remove soil without damaging roots. The work shall be undertaken by an arborist with a minimum qualification of AQF Level 3. Once roots are exposed, a visual examination can be carried with the Project Arborist to evaluate the potential impact of the proposed root loss on the health and stability of the tree.

The results of the root investigation together with a Development Impact Assessment must be documented in the report and submitted to Council. The report shall contain information that demonstrates that the trees will remain viable in conjunction with the works.

Where root pruning is required, roots shall be severed with sterile, clean, sharp pruning implements resulting in a clean cut. Any excavated root zones shall be retained in a moist condition during the construction phase using Hessian material or mulch where practical. Trees that have roots removed shall have drip irrigation installed around the root zone to ensure they receive an adequate supply of water.

6.4 Tree Protection Measures

It is recommended a site-specific Tree Protection Plan (TPP) is prepared to guide the construction process to ensure all trees designated for retention remain as a sustainable part of the landscape in the long term.

The plan shall be prepared by a consulting arborist (AQF Level 5) and should at a minimum include a detailed plan of the locations of, and specifications for, tree protection measures.

The TPP shall include a monitoring schedule relating to critical points during the works (hold points) where the Project Arborist is required to visit the site and confirm that works are being undertaken as conditioned by Council/as required.

The following tree protection measures shall be implemented prior to the commencement of any site works, and shall remain in place for the duration of the development.

6.4.1 Tree Protection Zones

The Tree Protection Zones recommended for all trees within the site to be retained shall be equivalent to the Tree Protection Zone as illustrated in Figure 2. This is a radial distance measured from the centre of the trunk of the subject trees.

The following activities are prohibited within the specified Tree Protection Zones:-

- Excavations and trenching (with exception of the approved underground services);
- Ripping or cultivation of soil;
- Mechanical removal of vegetation;
- Soil level changes including the placement of fill;
- Movement and storage of plant, equipment & vehicles;
- Erection of site sheds;
- Affixing of signage or hoardings to trees;
- Storage of building materials, waste and waste receptacles;
- Disposal of waste materials and chemicals including paint, solvents, cement slurry, fuel, oil and other toxic liquids;
- Other physical damage to the trunk or root system; and
- Any other activity likely to cause damage to the tree.

Place a 50-75mm layer of coarse organic mulch over the entire surface of the TPZ. Where the TPZ is adjacent to construction activities first lay down geotextile fabric beneath the mulch to

facilitate easy removal of the mulch at completion and any accidental spillage of construction materials.

Install drip irrigation installed around the root zone if required by the Project Arborist.

6.4.2 Tree Protection Fencing

All trees within the site to be retained shall be protected prior to and during construction from all activities that may result in detrimental impact by erecting a suitable protective fence beneath the canopy to the full extent of the Tree Protection Zone (excluding the footprint of the proposed works and areas within adjoining properties).

As a minimum the fence should consist temporary chain wire panels 1.8 metres in height, supported by steel stakes as required and fastened together and supported to prevent sideways movement. The fence shall be erected prior to the commencement of any work on-site and shall be maintained in good condition for the duration of construction. Where tree protection zones merge together a single fence encompassing the area is deemed to be adequate.

Appropriate signage shall be installed on the fencing to prevent unauthorised movement of plant and equipment or entry to the Tree Protection Zone.

Refer to Appendix 4 for examples of protective fencing and signage.

6.4.3 Trunk, Branch & Ground Protection

Where provision of tree protection fencing is impractical due to its proximity to the proposed building envelope, trunk protection shall be erected around the tree to avoid accidental damage. As a minimum, the trunk protection shall consist of two metre (2m) lengths of hardwood timbers (100 x 50mm) spaced at 100-150mm centres secured together with 2mm galvanised wire. These shall be strapped around the trunk (not fixed in any way) to avoid mechanical injury or damage. Trunk protection should be installed prior to any site works and maintained in good condition for the duration of the construction period.

Pavements should be avoided within the Tree Protection Zone of trees to be retained where possible. Proposed paved areas within the Tree Protection Zone of trees to be retained should be placed above grade to minimise excavations within the root zone and avoid root severance and damage.

Placement of fill material within the Tree Protection Zone of trees to be retained should be avoided where possible. Where placement of fill cannot be avoided, the material should be a coarse, gap-graded material such as 20 – 50mm crushed basalt (Blue Metal) or equivalent to provide some aeration to the root zone. Note that Roadbase or crushed sandstone or other material containing a high percentage of fines is unacceptable for this purpose. The fill material should be consolidated with a non-vibrating roller to minimise compaction of the underlying soil. A permeable geotextile may be used beneath the sub-base to prevent migration of the stone into the sub-grade. No fill material should be placed in direct contact with the trunk.

Refer to Appendix 4 for examples of trunk, branch and ground protection.

6.4.4 Demolition Works within Tree Protection Zones

It is noted major demolition of existing buildings, swimming pools and concrete slabs is required on this site.

Any demolition in the Tree Protection Zone of trees to be retained shall be undertaken under the supervision of the Project Arborist. Pavement and sub-base shall be stripped-off using a

small rubber tracked excavator or alternative approved method to avoid damage to underlying roots and minimise soil disturbance. The machine shall work on the existing pavements to avoid compaction of the uncovered soil. The final layer of sub-base material shall be removed using hand tools were required to avoid compaction of the underlying soil profile and damage to woody roots.

Following removal of the pavement surface and sub-base, clean, friable topsoil shall be used to fill in the excavated area and bring flush with surrounding levels. Soil shall only be imported and spread when the underlying soil conditions are dry to avoid compaction of the soil profile.

6.4.5 *Underground Services*

All proposed underground services should be located as far away as practicable to avoid excavation within the Tree Protection Zone of trees to be retained.

For underground services, where the incursion to the Root Zone is less than 10% of the total TPZ (i.e. beyond the Minimum Setback Distance), a chain trenching device may be used. A backhoe or skid steer loader (bobcat) is unacceptable due to the potential for excessive compaction and root damage. Where large woody roots (greater than 50mm in diameter) are encountered during excavation or trenching, these shall be retained intact wherever possible (eg by sub-surface boring beneath roots or re-routing the service etc).

Excavations required for underground services within the Structural Root Zone of any tree to be retained should only be undertaken by sub-surface boring. The Invert Level of the pipe, plus the pipe diameter, must be lower than the estimated root zone depth as specified at a minimum depth of 600mm. This will depend on the soil conditions at the site. Where this is not practical and root pruning is the only alternative, proposed root pruning should be assessed by the Project Arborist to determine continued health and stability of the subject tree.

6.4.7 *Tree Damage/ Decline*

If trees show signs of stress or deterioration, remedial action shall be taken to improve the health and vigour of the subject tree(s) in accordance with best practice arboricultural principles. Advice must be sought from the Project Arborist.

In the event of any tree becoming damaged for any reason during the construction period the Project Arborist must be engaged to inspect and provide advice on any remedial action to minimise any adverse impact. Such remedial action shall be implemented as soon as practicable and certified by the arborist.

7.0 DISCLAIMER

The author and Sturt Noble Arboricultural Consulting take no responsibility for actions taken and their consequences, contrary to those expert and professional instructions given as recommendations.

This is not a hazard assessment report and it should be noted that trees are always inherently dangerous. This assessment was carried out from the ground, and covers what was reasonably able to be assessed and available to the assessor at the time of inspection. No aerial or subterranean inspections were carried out and structural weakness may exist within roots, trunk or branches.

Any protection or preservation methods recommended are not a guarantee of tree survival or safety but are designed to improve vigour and reduce risk. Timely inspections and reports are necessary to monitor the trees' condition. No responsibility is accepted for damage or injury caused by the trees and no responsibility is accepted if the recommendations in this report are not followed.

Limitations on the use of this report:

Trees are dynamic living structures, growing and adapting to conditions around them. Tree condition will change and vary over time depending on weather, environmental factors and mechanical or human interaction.

This report is to be utilised in its entirety only. Any written or verbal submission, report or presentation that includes statements taken from the findings, discussions, conclusions or recommendations made in this report, may only be used where the whole of the original report (or a copy) is referenced in, and directly attached to that submission, report or presentation.

Assumptions

Care has been taken to obtain information from reliable resources. All data have been verified insofar as possible; however, Sturt Noble Arboricultural Consulting can neither guarantee nor be responsible for the accuracy of information provided by others.

Unless stated otherwise:

Information contained in this report covers only the trees that were examined and reflects the condition of the trees at the time of inspection.

Assessment is limited to the conditions at the time of the inspection and only trees discussed in the report have been assessed.

Where access to the base of the tree is limited, such as difficult site access due to site conditions, only general comments can be made. Assessment of tree health and structure is limited to that visible from the site of proposed works and may not reflect the true condition of the tree. Assessment of tree health and structure is limited to that visible from the site of proposed works and may not reflect the true condition of the tree.

Plans used to assess likely impact are those appended/ referenced.

Ongoing monitoring of all trees is advised and where significant changes are observed, further advice should be requested.

Unusual developments or sudden changes in a tree's condition should be addressed immediately.

8.0 REFERENCES

Botany Bay Development Control Plan 2013 Part 3L Landscaping and Tree Management

Draper, D.B and Richards, P.A (2009) Dictionary for managing Trees in Urban Environments, (IACA) Institute of Australian Consulting Arboriculturists ©. Pub. CSIRO Publishing, Melbourne.

IACA, 2010, Sustainable Retention Index Value Matrix (SRIV) Version 4, A visual method of objectively rating the viability of urban trees for development sites and management, based on general tree and landscape assessment criteria, Institute of Australian Consulting Arboriculturists, Australia.

Googlemaps ©. Viewed 1st July 2023

<https://www.environment.nsw.gov.au/heritageapp/ViewHeritageItemDetails.aspx?ID=1210063> Booralee Park

Mattheck, Dr. Claus, Breloer Helge (1994) Sixth Edition (2001), *The Body Language of Trees – A handbook for failure analysis*. Research for Amenity Trees No 4. Pub. The Stationary Office London.

NSW Work Cover Code of Practice for the Amenity Tree Industry (1998) Pub. © WorkCover NSW

Standards Australia (2007) Australian Standard AS4373-2007 *Pruning of Amenity Trees*, Pub. Standards Australia, Sydney.

Standards Australia (2009) Australian Standard AS4970-2009 *Protection of Trees on Development Sites*, Pub. Standards Australia, Sydney.

APPENDIX 1: METHODOLOGY

A1.1 Site Inspection

This report, its comments and recommendations have been prepared based on the information gathered during a detailed site inspection carried out on the on the 20th April 2021. This assessment is summarised in **Appendix 1**.

A1.2 Tree Locations

The location of the subject trees are based on the site survey, 104-16G T02 [00] RO, 12/05/2021 prepared by Craig and Rhodes.

A1.3 Visual Tree Assessment

The trees were assessed from the ground by the Visual Tree Assessment (VTA) method as described in Mattheck & Breloer (1994), using non-invasive tools such as binoculars and acoustic mallet. No digging or exposing of the root zones occurred in this inspection and no aerial inspection by climbing was performed. No aerial inspection or diagnostic testing was undertaken as part of this assessment.

The following data was collected for each tree:

- Botanical and common name.
- Tree dimensions (approximate only).
- Canopy density (approximate only).
- Overall health and vitality, including epicormic growth, deadwood and predation by pests and diseases.
- Structural condition including evident faults such as Bark Inclusions or poor branch attachments, decay, cavities and mechanical or biological damage.
- Stability of the tree including excessive trunk lean, stability of the soil, soil cracking, soil heaving, exposed roots and root damage.

A1.4 Retention Value

Each tree has been given a Sustainable Retention Index Value (SRIV) according to the rating system set out in the Sustainable Retention Index Value Matrix (refer to the table in section A1.8). The SRIV for each tree is based on its health, vigour, structure and age class as established in the Visual Tree Assessment. The SRIV does not take into account the impact of the proposed development.

A1.5 Landscape Significance Assessment

Landscape Significance is an essential criterion to establish the importance that a particular tree may have on a site. Each tree has been given a Tree Significance in landscape rating based on the 'IACA Significance of a Tree, Assessment Rating System'. A tree is to have a minimum of three criteria in a category to be applicable for that rating.

Tree Significance in the landscape ratings:

High	Medium	Low
<ul style="list-style-type: none"> The tree is in good condition and good vigour; The tree has a form typical for the species; The tree is a remnant or is a planted locally indigenous specimen and/or is rare or uncommon in the local area or of botanical interest or of substantial age; The tree is listed as a Heritage Item, Threatened Species or part of an Endangered ecological community or listed on Councils significant Tree Register; The tree is visually prominent and visible from a considerable distance when viewed from most directions within the landscape due to its size and scale and makes a positive contribution to the local amenity; The tree supports social and cultural sentiments or spiritual associations, reflected by the broader population or community group or has commemorative values; The tree's growth is unrestricted by above and below ground influences, supporting its ability to reach dimensions typical for the taxa in situ - tree is appropriate to the site conditions. 	<ul style="list-style-type: none"> The tree is in fair-good condition and good or low vigour; The tree has form typical or atypical of the species; The tree is a planted locally indigenous or a common species with its taxa commonly planted in the local area The tree is visible from surrounding properties, although not visually prominent as partially obstructed by other vegetation or buildings when viewed from the street, The tree provides a fair contribution to the visual character and amenity of the local area, The tree's growth is moderately restricted by above or below ground influences, reducing its ability to reach dimensions typical for the taxa in situ. 	<ul style="list-style-type: none"> The tree is in fair-poor condition and good or low vigour; The tree has form atypical of the species; The tree is not visible or is partly visible from surrounding properties as obstructed by other vegetation or buildings, The tree provides a minor contribution or has a negative impact on the visual character and amenity of the local area, The tree is a young specimen which may or may not have reached dimension to be protected by local Tree Preservation orders or similar protection mechanisms and can easily be replaced with a suitable specimen, The tree's growth is severely restricted by above or below ground influences, unlikely to reach dimensions typical for the taxa in situ - tree is inappropriate to the site conditions, The tree is listed as exempt under the provisions of the local Council Tree Preservation Order or similar protection mechanisms, The tree has a wound or defect that has potential to become structurally unsound. Environmental Pest / Noxious Weed Species The tree is an Environmental Pest Species due to its invasiveness or poisonous/ allergenic properties, The tree is a declared noxious weed by legislation. Hazardous/Irreversible Decline The tree is structurally unsound and/or unstable and is considered potentially dangerous, - The tree is dead, or is in irreversible decline, or has the potential to fail or collapse in full or part in the immediate to short term.

A1.6 Tree Protection Zones (TPZ) and Structural Root Zones (SRZ)

The intention of the TPZ is to ensure protection of the root system and canopy from the potential damage from construction works and ensure the long-term health and stability of each tree to be retained.

The Structural Root Zone (SRZ) is located within the TPZ around the base of a tree and provides the bulk of mechanical support and anchorage for a tree.

The Tree Protection Zones (TPZ) and Structural Root Zones (SRZ) have been arrived at using methods as detailed in Australian Standard AS 4970– 2009. Specific site factors are also considered that may influence the location of the TPZ and/or structural tree roots.

A1.7 Encroachment and Development Impacts


Encroachments and development impacts to tree TPZ's and SRZ's include;

- Excavation
- Filling
- Changes to existing soil levels
- Placing items and elements within the zones even if only temporarily
- Soil disturbance
- Any other physical damage to the trunk or root system or any other activity likely to cause damage to the tree.


Under *AS 4970:2009 Protection of trees on development sites*, a major encroachment is greater than 10% of the area of the TPZ and the Project Arborist must determine and demonstrate that the tree would remain viable. More detailed investigations, such as exploratory excavations and root investigation to enable an informed evaluation of the potential impact of the proposed works may be required.

Encroachments into the SRZ are not likely to be supported unless the Project Arborist has undertaken exploratory investigation and can demonstrate that there will be minimal impact to the tree.

A1.8 SRIV Table

	Vigour Class and Condition Class					
						
Age Class	Good Vigour & Good Condition (GVG)	Good Vigour & Fair Condition (GVF)	Good Vigour & Poor Condition (GVP)	Low Vigour & Good Condition (LVG)	Low Vigour & Fair Condition (LVF)	Low Vigour & Poor Condition (LVP)
	Able to be retained if sufficient space available above and below ground for future growth. No remedial work or improvement to growing environment required. May be subject to high vigour. Retention potential - Medium - Long Term.	Able to be retained if sufficient space available above and below ground for future growth. Remedial work may be required or improvement to growing environment may assist. Retention potential - Medium Term. Potential for longer with remediation or favourable environmental conditions	Able to be retained if sufficient space available above and below ground for future growth. Remedial work unlikely to assist condition, improvement to growing environment may assist. Retention potential - Short Term. Potential for longer with remediation or favourable environmental conditions.	May be able to be retained if sufficient space available above and below ground for future growth. No remedial work required, but improvement to growing environment may assist vigour. Retention potential - Short Term. Potential for longer with remediation or favourable environmental conditions.	May be able to be retained if sufficient space available above and below ground for future growth. Remedial work or improvement to growing environment may assist condition and vigour. Retention potential - Short Term. Potential for longer with remediation or favourable environmental conditions.	Unlikely to be able to be retained if sufficient space available above and below ground for future growth. Remedial work or improvement to growing environment unlikely to assist condition or vigour. Retention potential - Likely to be removed immediately or retained for Short Term. Potential for longer with remediation or favourable environmental conditions
Young (Y)	YGVG - 9 Index Value 9 Retention potential - Long Term. Likely to provide minimal contribution to local amenity if height Retain, move or replace	YGVF - 8 Index Value 8 Retention potential - Short - Medium Term. Potential for longer with improved growing conditions. Likely to provide minimal contribution to local amenity if height Medium-high potential for future growth and adaptability. Retain, move or replace.	YGVP - 5 Index Value 5 Retention potential - Short Term. Potential for longer with improved growing conditions. Likely to provide minimal contribution to local amenity if height Low-medium potential for future growth and adaptability. Retain, move or replace	YLVG - 4 Index Value 4 Retention potential - Short Term. Potential for longer with improved growing conditions. Likely to provide minimal contribution to local amenity if height Medium potential for future growth and adaptability. Retain, move or replace	YLVF - 3 Index Value 3 Retention potential - Short Term. Potential for longer with improved growing conditions. Likely to provide minimal contribution to local amenity if height <5m. Low-medium potential for future growth and adaptability. Retain, move or replace	YLVP - 1 Index Value 1 Retention potential - Likely to be removed immediately or retained for Short Term. Likely to provide minimal contribution to local amenity if height
Mature (M)	MGVG - 10 Index Value 10 Retention potential - Medium - Long Term	MGVF - 9 Index Value 9 Retention potential - Medium Term. Potential for longer with improved growing conditions.	MGVP - 6 Index Value 6 Retention potential - Short Term. Potential for longer with improved growing conditions	MLVG - 5 Index Value 5 Retention potential - Short Term. Potential for longer with improved growing conditions	MLVF - 4 Index Value 4 Retention potential - Short Term. Potential for longer with improved growing conditions	MLVP - 2 Index Value 2 Retention potential - Likely to be removed immediately or retained for Short Term.
Over-mature (O)	OGVG - 6 Index Value 6 Retention potential - Medium - Long Term.	OGVF - 5 Index Value 5 Retention potential - Medium Term.	OGVP - 4 Index Value 4 Retention potential - Short Term.	OLVG - 3 Index Value 3 Retention potential - Short Term. Potential for longer with improved growing conditions.	OLVF - 2 Index Value 2 Retention potential - Short Term.	OLVP - 0 Index Value 0 Retention potential - Likely to be removed immediately or retained for Short Term

APPENDIX 2: PLANS



LEGEND

EXTENT OF WORKS

EXISTING TREE TRUNK
Refer to Tree Impact
Assessment Schedule

EXISTING TREE CANOPY
Refer to Tree Impact
Assessment Schedule

TREES TO BE RETAINED
Refer to Tree Impact
Assessment Schedule

TREES TO BE REMOVED
Refer to Tree Impact
Assessment Schedule

TREES TO BE INVESTIGATED
FOR POTENTIAL HAZARD AND
REMOVE IF REQUIRED
Refer to Tree Impact
Assessment Schedule

TREE PROTECTION ZONE

G	ISSUE FOR TENDER / REVIEW	05.11.2024
F	ISSUE FOR TENDER / REVIEW	22.10.2024
E	ISSUE FOR TENDER / REVIEW	29.02.2024
D	ISSUE FOR TENDER / REVIEW	15.08.2023
C	ISSUE FOR TENDER / REVIEW	18.07.2023
B	ISSUE FOR TENDER / REVIEW	12.04.2023
ISSUE	DESCRIPTION	DATE



Suite 307, 166 Glebe Point Rd
Glebe NSW 2037
T. 02 9211 3744
W. www.sturt-noble.com.au
landscape · architecture
environmental & urban design

PROJECT
BOTANY AQUATIC CENTRE
CNR MYRTLE ST & JASMINE ST, BOTANY


CLIENT
BAYSIDE COUNCIL

DRAWING
SHEET LAYOUT

DRAWING NUMBER
ARB-2007-001

SCALE
N/A

ISSUE			
G			
DRAWN	CHECKED	DIRECTOR	
ns	gs	gs	



0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150 160 170 180 190 200 210 220 230 240 250 260 270 280 290 300 310 320 330 340 350 360 370 380 390 400 410 420 430 440 450 460 470 480 490 500 510 520 530 540 550 560 570 580 590 600 610 620 630 640 650 660 670 680 690 700 710 720 730 740 750 760 770 780 790 800 810 820 830 840 850 860 870 880 890 900 910 920 930 940 950 960 970 980 990 1000 1010 1020 1030 1040 1050 1060 1070 1080 1090 1100 1110 1120 1130 1140 1150 1160 1170 1180 1190 1200 1210 1220 1230 1240 1250 1260 1270 1280 1290 1300 1310 1320 1330 1340 1350 1360 1370 1380 1390 1400 1410 1420 1430 1440 1450 1460 1470 1480 1490 1500 1510 1520 1530 1540 1550 1560 1570 1580 1590 1600 1610 1620 1630 1640 1650 1660 1670 1680 1690 1700 1710 1720 1730 1740 1750 1760 1770 1780 1790 1800 1810 1820 1830 1840 1850 1860 1870 1880 1890 1900 1910 1920 1930 1940 1950 1960 1970 1980 1990 2000 2010 2020 2030 2040 2050 2060 2070 2080 2090 2100 2110 2120 2130 2140 2150 2160 2170 2180 2190 2200 2210 2220 2230 2240 2250 2260 2270 2280 2290 2300 2310 2320 2330 2340 2350 2360 2370 2380 2390 2400 2410 2420 2430 2440 2450 2460 2470 2480 2490 2500 2510 2520 2530 2540 2550 2560 2570 2580 2590 2600 2610 2620 2630 2640 2650 2660 2670 2680 2690 2700 2710 2720 2730 2740 2750 2760 2770 2780 2790 2800 2810 2820 2830 2840 2850 2860 2870 2880 2890 2900 2910 2920 2930 2940 2950 2960 2970 2980 2990 3000 3010 3020 3030 3040 3050 3060 3070 3080 3090 3100 3110 3120 3130 3140 3150 3160 3170 3180 3190 3200 3210 3220 3230 3240 3250 3260 3270 3280 3290 3300 3310 3320 3330 3340 3350 3360 3370 3380 3390 3400 3410 3420 3430 3440 3450 3460 3470 3480 3490 3500 3510 3520 3530 3540 3550 3560 3570 3580 3590 3600 3610 3620 3630 3640 3650 3660 3670 3680 3690 3700 3710 3720 3730 3740 3750 3760 3770 3780 3790 3800 3810 3820 3830 3840 3850 3860 3870 3880 3890 3900 3910 3920 3930 3940 3950 3960 3970 3980 3990 4000 4010 4020 4030 4040 4050 4060 4070 4080 4090 4100 4110 4120 4130 4140 4150 4160 4170 4180 4190 4200 4210 4220 4230 4240 4250 4260 4270 4280 4290 4300 4310 4320 4330 4340 4350 4360 4370 4380 4390 4400 4410 4420 4430 4440 4450 4460 4470 4480 4490 4500 4510 4520 4530 4540 4550 4560 4570 4580 4590 4600 4610 4620 4630 4640 4650 4660 4670 4680 4690 4700 4710 4720 4730 4740 4750 4760 4770 4780 4790 4800 4810 4820 4830 4840 4850 4860 4870 4880 4890 4900 4910 4920 4930 4940 4950 4960 4970 4980 4990 5000 5010 5020 5030 5040 5050 5060 5070 5080 5090 5100 5110 5120 5130 5140 5150 5160 5170 5180 5190 5200 5210 5220 5230 5240 5250 5260 5270 5280 5290 5300 5310 5320 5330 5340 5350 5360 5370 5380 5390 5400 5410 5420 5430 5440 5450 5460 5470 5480 5490 5500 5510 5520 5530 5540 5550 5560 5570 5580 5590 5600 5610 5620 5630 5640 5650 5660 5670 5680 5690 5700 5710 5720 5730 5740 5750 5760 5770 5780 5790 5800 5810 5820 5830 5840 5850 5860 5870 5880 5890 5900 5910 5920 5930 5940 5950 5960 5970 5980 5990 6000 6010 6020 6030 6040 6050 6060 6070 6080 6090 6100 6110 6120 6130 6140 6150 6160 6170 6180 6190 6200 6210 6220 6230 6240 6250 6260 6270 6280 6290 6300 6310 6320 6330 6340 6350 6360 6370 6380 6390 6400 6410 6420 6430 6440 6450 6460 6470 6480 6490 6500 6510 6520 6530 6540 6550 6560 6570 6580 6590 6600 6610 6620 6630 6640 6650 6660 6670 6680 6690 6700 6710 6720 6730 6740 6750 6760 6770 6780 6790 6800 6810 6820 6830 6840 6850 6860 6870 6880 6890 6900 6910 6920 6930 6940 6950 6960 6970 6980 6990 7000 7010 7020 7030 7040 7050 7060 7070 7080 7090 7100 7110 7120 7130 7140 7150 7160 7170 7180 7190 7200 7210 7220 7230 7240 7250 7260 7270 7280 7290 7300 7310 7320 7330 7340 7350 7360 7370 7380 7390 7400 7410 7420 7430 7440 7450 7460 7470 7480 7490 7500 7510 7520 7530 7540 7550 7560 7570 7580 7590 7600 7610 7620 7630 7640 7650 7660 7670 7680 7690 7700 7710 7720 7730 7740 7750 7760 7770 7780 7790 7800 7810 7820 7830 7840 7850 7860 7870 7880 7890 7900 7910 7920 7930 7940 7950 7960 7970 7980 7990 8000 8010 8020 8030 8040 8050 8060 8070 8080 8090 8100 8110 8120 8130 8140 8150 8160 8170 8180 8190 8200 8210 8220 8230 8240 8250 8260 8270 8280 8290 8300 8310 8320 8330 8340 8350 8360 8370 8380 8390 8400 8410 8420 8430 8440 8450 8460 8470 8480 8490 8500 8510 8520 8530 8540 8550 8560 8570 8580 8590 8600 8610 8620 8630 8640 8650 8660 8670 8680 8690 8700 8710 8720 8730 8740 8750 8760 8770 8780 8790 8800 8810 8820 8830 8840 8850 8860 8870 8880 8890 8900 8910 8920 8930 8940 8950 8960 8970 8980 8990 9000 9010 9020 9030 9040 9050 9060 9070 9080 9090 9100 9110 9120 9130 9140 9150 9160 9170 9180 9190 9200 9210 9220 9230 9240 9250 9260 9270 9280 9290 9300 9310 9320 9330 9340 9350 9360 9370 9380 9390 9400 9410 9420 9430 9440 9450 9460 9470 9480 9490 9500 9510 9520 9530 9540 9550 9560 9570 9580 9590 9600 9610 9620 9630 9640 9650 9660 9670 9680 9690 9700 9710 9720 9730 9740 9750 9760 9770 9780 9790 9800 9810 9820 9830 9840 9850 9860 9870 9880 9890 9900 9910 9920 9930 9940 9950 9960 9970 9980 9990 10000 10010 10020 10030 10040 10050 10060 10070 10080 10090 10100 10110 10120 10130 10140 10150 10160 10170 10180 10190 10200 10210 10220 10230 10240 10250 10260 10270 10280 10290 10300 10310 10320 10330 10340 10350 10360 10370 10380 10390 10400 10410 10420 10430 10440 10450 10460 10470 10480 10490 10500 10510 10520 10530 10540 10550 10560 10570 10580 10590 10600 10610 10620 10630 10640 10650 10660 10670 10680 10690 10700 10710 10720 10730 10740 10750 10760 10770 10780 10790 10800 10810 10820 10830 10840 10850 10860 10870 10880 10890 10900 10910 10920 10930 10940 10950 10960 10970 10980 10990 11000 11010 11020 11030 11040 11050 11060 11070 11080 11090 11100 11110 11120 11130 11140 11150 11160 11170 11180 11190 11200 11210 11220 11230 11240 11250 11260 11270 11280 11290 11300 11310 11320 11330 11340 11350 11360 11370 11380 11390 11400 11410 11420 11430 11440 11450 11460 11470 11480 11490 11500 11510 11520 11530 11540 11550 11560 11570 11580 11590 11600 11610 11620 11630 11640 11650 11660 11670 11680 11690 11700 11710 11720 11730 11740 11750 11760 11770 11780 11790 11800 11810 11820 11830 11840 11850 11860 11870 11880 11890 11900 11910 11920 11930 11940 11950 11960 11970 11980 11990 12000 12010 12020 12030 12040 12050 12060 12070 12080 12090 12100 12110 12120 12130 12140 12150 12160 12170 12180 12190 12200 12210 12220 12230 12240 12250 12260 12270 12280 12290 12300 12310 12320 12330 12340 12350 12360 12370 12380 12390 12400 12410 12420 12430 12440 12450 12460 12470 12480 12490 12500 12510 12520 12530 12540 12550 12560 12570 12580 12590 12600 12610 12620 12630 12640 12650 12660 12670 12680 12690 12700 12710 12720 12730 12740 12750 12760 12770 12780 12790 12800 12810 12820 12830 12840 12850 12860 12870 12880 12890 12900 12910 12920 12930 12940 12950 12960 12970 12980 12990 13000 13010 13020 13030 13040 13050 13060 13070 13080 13090 13100 13110 13120 13130 13140 13150 13160 13170 13180 13190 13200 13210 13220 13230 13240 13250 13260 13270 13280 13290 13300 13310 13320 13330 13340 13350 13360 13370 13380 13390 13400 13410 13420 13430 13440 13450 13460 13470 13480 13490 13500 13510 13520 13530 13540 13550 13560 13570 13580 13590 13600 13610 13620 13630 13640 13650 13660 13670 13680 13690 13700 13710 13720 13730 13740 13750 13760 13770 13780 13790 13800 13810 13820 13830 13840 13850 13860 13870 13880 13890 13900 13910 13920 13930 13940 13950 13960 13970 13980 13990 14000 14010 14020 14030 14040 14050 14060 14070 14080 14090 14100 14110 14120 14130 14140 14150 14160 14170 14180 14190 14200 14210 14220 14230 14240 14250 14260 14270 14280 14290 14300 14310 14320 14330 14340 14350 14360 14370 14380 14390 14400 14410 14420 14430 14440 14450 14460 14470 14480 14490 14500 14510 14520 14530 14540 14550 14560 14570 14580 14590 14600 14610 14620 14630 14640 14650 14660 14670 14680 14690 14700 14710 14720 14730 14740 14750 14760 14770 14780 14790 14800 14810 14820 14830 14840 14850 14860 14870 14880 14890 14900 14910 14920 14930 14940 14950 14960 14970 14980 14990 15000 15010 15020 15030 15040 15050 15060 15070 15080 15090 15100 15110 15120 15130 15140 15150 15160 15170 15180 15190 15200 15210 15220 15230 15240 15250 15260 15270 15280 15290 15300 15310 15320 15330 15340 15350 15360 15370 15380 15390 15400 15410 15420 15430 15440 15450 15460 15470 15480 15490 15500 15510 15520 15530 15540 15550 15560 15570 15580 15590 15600 15610 15620 15630 15640 15650 15660 15670 15680 15690 15700 15710 15720 15730 15740 15750 15760 15770 15780 15790 15800 15810 15820 15830 15840 15850 15860 15870 15880 15890 15900 15910 15920 15930 15940 15950 15960 15970 15980 15990 16000 16010 16020 16030 16040 16050 16060 16070 16080 16090 16100 16110 16120 16130 16140 16150 16160 16170 16180 16190 16200 16210 16220 16230 16240 16250 16260 16270 16280 16290 16300 16310 16320 16330 16340 16350 16360 16370 16380 16390 16400 16410 16420 16430 16440 16450 16460 16470 16480 16490 16500 16510 16520 16530 16540 16550 16560 16570 16580 16590 16600 16610 16620 16630 16640 16650 16660 16670 16680 16690 16700 16710 16720 16730 16740 16750 16760 16770 16780 16790 16800 16810 16820 16830 16840 16850 16860 16870 16880 16890 16900 16910 16920 16930 16940 16950 16960 16970 16980 16990 17000 17010 17020 17030 17040 17050 17060 17070 17080 17090 17100 17110 17120 17130 17140 17150 17160 17170 17180 17190 17200 17210 17220 17230 17240 17250 17260 17270 17280 17290 17300 17310 17320 17330 17340 17350 17360 17370 17380 17390 17400 17410 17420 17430 17440 17450 17460 17470 17480 17490 17500 17510 17520 17530 17540 17550 17560 17570 17580 17590 17600 17610 17620 17630 17640 17650 17660 17670 17680 17690 17700 17710 17720 17730 17740 17750 17760 17770 17780 17790 17800 17810 17820 17830 17840 17850 17860 17870 17880 17890 17900 17910 17920 17930 17940 17950 17960 17970 17980 17990 18000 18010 18020 18030 18040 18050 18060 18070 18080 18090 18100 18110 18120 18130 18140 18150 18160 18170 18180 18190 18200 18210 18220 18230 18240 18250 18260 18270 18280 18290 18300 18310 18320 18330 18340 18350 18360 18370 18380 18390 18400 18410 18420 18430 18440 18450 18460 18470 18480 18490 18500 18510 18520 18530 18540 18550 18560 18570 18580 18590 18600 18610 18620 18630 18640 18650 18660 18670 18680 18690 18700 18710 18720 18730 18740 18750 18760 18770 18780 18790 18800 18810 18820 18830 18840 18850 18860 18870 18880 18890 18900 18910 18920 18930 18940 18950 18960 18970 18980 18990 19000 19010 19020 19030 19040 19050 19060 19070 19080 19090 19100 19110 19120 19130 19140 19150 19160 19170 19180 19190 19200 19210 19220 19230 19240 19250 19260 19270 19280 19290 19300 19310 19320 19330 19340 19350 19360 19370 19380 19390 19400 19410 19420 19430 19440 19450 19460 19470 19480 19490 19500 19510 19520 19530 19540 19550 19560 19570 19580 19590 19600 19610 19620 19630 19640 19650 19660 19670 19680 19690 19700 19710 19720 19730 19740 19750 19760 19770 19780 19790 19800 19810 19820 19830 19840 19850 19860 19870 19880 19890 19900 19910 19920 19930 19940 19950 19960 19970 19980 19990 20000 20010 20020 20030 20040 20050 20060 20070 20080 20090 20100 20110 20120 20130 20140 20150 2

REFER TO SHEET ARB-2007-102

LEGEND

--- EXTENT OF WORKS

- TX
EXISTING TREE TRUNK
Refer to Tree Impact Assessment Schedule
- EXISTING TREE CANOPY
Refer to Tree Impact Assessment Schedule
- TREES TO BE RETAINED
Refer to Tree Impact Assessment Schedule
- TREES TO BE REMOVED
Refer to Tree Impact Assessment Schedule
- TREES TO BE INVESTIGATED FOR POTENTIAL HAZARD AND REMOVE IF REQUIRED
Refer to Tree Impact Assessment Schedule
- TREE PROTECTION ZONE

H	ISSUE FOR TENDER / REVIEW	22.10.2024
G	ISSUE FOR TENDER / REVIEW	29.02.2024
F	ISSUE FOR TENDER / REVIEW	04.12.2023
E	ISSUE FOR TENDER / REVIEW	15.08.2023
D	ISSUE FOR TENDER / REVIEW	18.07.2023
C	ISSUE FOR TENDER / REVIEW	12.07.2023
ISSUE	DESCRIPTION	DATE



Suite 307, 166 Glebe Point Rd
Glebe NSW 2037
T. 02 9211 3744
W. www.sturnoble.com.au
landscape architecture
environmental & urban design

PROJECT
BOTANY AQUATIC CENTRE
CNR MYRTLE ST & JASMINE ST, BOTANY

CLIENT
BAYSIDE COUNCIL

DRAWING
TREE PLAN 01

DRAWING NUMBER
ARB-2007-101

SCALE
1:200 @ A1
1:400 @ A3

ISSUE
H
DRAWN
ns
CHECKED
gs
DIRECTOR
gs

ACN: 164 245 514
ABN: 99 164 245 514

THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL RELEVANT CONTRACTS, SPECIFICATIONS, REPORTS AND DRAWINGS. COPYRIGHT OF THIS DRAWING IS VESTED IN STURT NOBLE ASSOCIATES PTY LTD.

ALEXANDRIA
DUKES RUGBY
CLUB

SINGLE STORY
BRICK BUILDING-
METAL ROOF

N 6242988762
E 333825157

JASMIN

5 STORY
RISING



LEGEND

- EXTENT OF WORKS
- TX
⊕ EXISTING TREE TRUNK
Refer to Tree Impact Assessment Schedule
- ◯ EXISTING TREE CANOPY
Refer to Tree Impact Assessment Schedule
- ◯⊕ TREES TO BE RETAINED
Refer to Tree Impact Assessment Schedule
- ◯⊕ TREES TO BE REMOVED
Refer to Tree Impact Assessment Schedule
- ◯⊕ TREES TO BE INVESTIGATED FOR POTENTIAL HAZARD AND REMOVE IF REQUIRED
Refer to Tree Impact Assessment Schedule
- ◯ TREE PROTECTION ZONE
- ◯ PALMS TO BE TRANSPLANTED
Refer to Tree Impact Assessment Schedule.

REFER TO SHEET ARB-2007-103

H	ISSUE FOR TENDER / REVIEW	05.11.2024
G	ISSUE FOR TENDER / REVIEW	22.10.2024
F	ISSUE FOR TENDER / REVIEW	29.02.2024
E	ISSUE FOR TENDER / REVIEW	15.08.2023
D	ISSUE FOR TENDER / REVIEW	18.07.2023
C	ISSUE FOR TENDER / REVIEW	12.07.2023
ISSUE	DESCRIPTION	DATE



Suite 307, 166 Glebe Point Rd
Glebe NSW 2037
T: 02 9211 3744
W: www.sturt-noble.com.au
landscape · architecture
environmental & urban design

PROJECT
**BOTANY AQUATIC CENTRE
CNR MYRTLE ST & JASMINE ST, BOTANY**

CLIENT
BAYSIDE COUNCIL

DRAWING
TREE PLAN 02

DRAWING NUMBER
ARB-2007-102

SCALE
1:200 @ A1
1:400 @ A3

ISSUE
H

DRAWN	CHECKED	DIRECTOR
ns	gs	gs

0 4 8 20 m


ACN: 164 245 514 ABN: 99 164 245 514

THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL RELEVANT CONTRACTS, SPECIFICATIONS, REPORTS AND DRAWINGS. COPYRIGHT OF THIS DRAWING IS VESTED IN STURT NOBLE ASSOCIATES PTY LTD.

REFER TO SHEET ARB-2007-101

REFER TO SHEET ARB-2007-102

REFER TO SHEET ARB-2007-104



REFER TO SHEET ARB-2007-106

LEGEND

--- EXTENT OF WORKS

- EXISTING TREE TRUNK
Refer to Tree Impact Assessment Schedule
- EXISTING TREE CANOPY
Refer to Tree Impact Assessment Schedule
- TREES TO BE RETAINED
Refer to Tree Impact Assessment Schedule
- TREES TO BE REMOVED
Refer to Tree Impact Assessment Schedule
- TREES TO BE INVESTIGATED FOR POTENTIAL HAZARD AND REMOVE IF REQUIRED
Refer to Tree Impact Assessment Schedule
- TREE PROTECTION ZONE
- PALMS TO BE TRANSPLANTED
Refer to Tree Impact Assessment Schedule.

I	ISSUE FOR TENDER / REVIEW	04.11.2024
H	ISSUE FOR TENDER / REVIEW	22.10.2024
G	ISSUE FOR TENDER / REVIEW	29.02.2024
F	ISSUE FOR TENDER / REVIEW	04.12.2023
E	ISSUE FOR TENDER / REVIEW	15.08.2023
D	ISSUE FOR TENDER / REVIEW	18.07.2023
ISSUE	DESCRIPTION	DATE



Suite 307, 166 Glebe Point Rd
Glebe NSW 2037
T. 02 9211 3744
W. www.sturt-noble.com.au
landscape architecture
environmental & urban design


PROJECT
BOTANY AQUATIC CENTRE
CNR MYRTLE ST & JASMINE ST, BOTANY

CLIENT
BAYSIDE COUNCIL

DRAWING
TREE PLAN 03

DRAWING NUMBER
ARB-2007-103

SCALE
1:200 @ A1
1:400 @ A3



DRAWN	CHECKED	DIRECTOR
ns	gs	gs

0 4 8 20 m

ACN: 164 245 514 ABN: 99 164 245 514

THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL RELEVANT CONTRACTS, SPECIFICATIONS, REPORTS AND DRAWINGS. COPYRIGHT OF THIS DRAWING IS VESTED IN STURT NOBLE ASSOCIATES PTY LTD.

THE LAKES GOLF CLUB

REFER TO SHEET ARB-2007-103

RAILWAY CORRIDOR

RL7.75
EX RL7.75

EXISTING FENCE LINE

REFER TO SHEET ARB-2007-105

LEGEND

EXTENT OF WORKS

TX

⊕

EXISTING TREE TRUNK
Refer to Tree Impact
Assessment Schedule

◯

EXISTING TREE CANOPY
Refer to Tree Impact Assessment
Schedule

◯

⊕

TREES TO BE RETAINED
Refer to Tree Impact Assessment
Schedule

◯

⊕

TREES TO BE REMOVED
Refer to Tree Impact
Assessment Schedule

◯

⊕

TREES TO BE INVESTIGATED
FOR POTENTIAL HAZARD AND
REMOVE IF REQUIRED
Refer to Tree Impact
Assessment Schedule

◯

TREE PROTECTION ZONE

G	ISSUE FOR TENDER / REVIEW	22.10.2024
F	ISSUE FOR TENDER / REVIEW	29.02.2024
E	ISSUE FOR TENDER / REVIEW	15.08.2023
D	ISSUE FOR TENDER / REVIEW	16.07.2023
C	ISSUE FOR TENDER / REVIEW	12.07.2023
B	ISSUE FOR TENDER / REVIEW	12.04.2023
ISSUE	DESCRIPTION	DATE

Sturt Noble

Arboculture

Suite 307, 166 Glebe Point Rd
Glebe NSW 2037
T. 02 9211 3744
W. www.sturnoble.com.au
landscape · architecture
environmental & urban design

PROJECT

BOTANY AQUATIC CENTRE
CNR MYRTLE ST & JASMINE ST, BOTANY

CLIENT

BAYSIDE COUNCIL

DRAWING

TREE PLAN 04

DRAWING NUMBER

ARB-2007-104

ISSUE

G

SCALE

1:200 @ A1
1:400 @ A3

DRAWN

ns

CHECKED

gs

DIRECTOR

gs

0

4

8

20 m

0

4


8

20 m

ACN: 164 245 514

ABN: 99 164 245 514

THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL RELEVANT CONTRACTS, SPECIFICATIONS, REPORTS AND DRAWINGS. COPYRIGHT OF THIS DRAWING IS VESTED IN STURT NOBLE ASSOCIATES PTY LTD.



REFER TO SHEET ARB-2007-106

REFER TO SHEET ARB-2007-104

LEGEND

TX

EXISTING TREE TRUNK
Refer to Tree Impact
Assessment Schedule

EXISTING TREE CANOPY
Refer to Tree Impact Assessment
Schedule

TREES TO BE RETAINED
Refer to Tree Impact Assessment
Schedule

TREES TO BE REMOVED
Refer to Tree Impact
Assessment Schedule

TREES TO BE INVESTIGATED
FOR POTENTIAL HAZARD AND
REMOVE IF REQUIRED
Refer to Tree Impact
Assessment Schedule

TREE PROTECTION ZONE

G	ISSUE FOR TENDER / REVIEW	22.10.2024
F	ISSUE FOR TENDER / REVIEW	29.02.2024
E	ISSUE FOR TENDER / REVIEW	15.08.2023
D	ISSUE FOR TENDER / REVIEW	18.07.2023
C	ISSUE FOR TENDER / REVIEW	12.07.2023
B	ISSUE FOR TENDER / REVIEW	12.04.2023
ISSUE	DESCRIPTION	DATE

Sturt Noble

Arboculture

Suite 307, 166 Glebe Point Rd
Glebe NSW 2037
T. 02 9211 3744
W. www.sturnoble.com.au
landscape - architecture
environmental & urban design

PROJECT

BOTANY AQUATIC CENTRE
CNR MYRTLE ST & JASMINE ST, BOTANY

CLIENT

BAYSIDE COUNCIL

DRAWING

TREE PLAN 05

DRAWING NUMBER

ARB-2007-105

ISSUE

G

SCALE

1:200 @ A1
1:400 @ A3

DRAWN

ns

CHECKED

gs

DIRECTOR

gs

0 4 8 20 m

ACN: 164 245 514

ABN: 99 164 245 514

THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL RELEVANT CONTRACTS, SPECIFICATIONS, REPORTS AND DRAWINGS. COPYRIGHT OF THIS DRAWING IS VESTED IN STURT NOBLE ASSOCIATES PTY LTD.

REFER TO SHEET ARB-2007-103

REFER TO SHEET ARB-2007-101

REFER TO SHEET ARB-2007-105

LEGEND
- - - - - EXTENT OF WORKS

- TX
EXISTING TREE TRUNK
Refer to Tree Impact Assessment Schedule
- EXISTING TREE CANOPY
Refer to Tree Impact Assessment Schedule
- TREES TO BE RETAINED
Refer to Tree Impact Assessment Schedule
- TREES TO BE REMOVED
Refer to Tree Impact Assessment Schedule
- TREES TO BE INVESTIGATED FOR POTENTIAL HAZARD AND REMOVE IF REQUIRED
Refer to Tree Impact Assessment Schedule
- TREE PROTECTION ZONE

H	ISSUE FOR TENDER / REVIEW	22.10.2024
G	ISSUE FOR TENDER / REVIEW	29.02.2024
F	ISSUE FOR TENDER / REVIEW	04.12.2023
E	ISSUE FOR TENDER / REVIEW	15.08.2023
D	ISSUE FOR TENDER / REVIEW	18.07.2023
C	ISSUE FOR TENDER / REVIEW	12.07.2023
ISSUE	DESCRIPTION	DATE



Suite 307, 166 Glebe Point Rd
Glebe NSW 2037
T. 02 9211 3744
W. www.sturnoble.com.au
landscape - architecture
environmental & urban design


PROJECT
BOTANY AQUATIC CENTRE
CNR MYRTLE ST & JASMINE ST, BOTANY

CLIENT
BAYSIDE COUNCIL

DRAWING
TREE PLAN 06


DRAWING NUMBER
ARB-2007-106

SCALE
1:200 @ A1
1:400 @ A3



ACN: 164 245 514 ABN: 99 164 245 514

THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL RELEVANT CONTRACTS, SPECIFICATIONS, REPORTS AND DRAWINGS. COPYRIGHT OF THIS DRAWING IS VESTED IN STURT NOBLE ASSOCIATES PTY LTD.



APPENDIX 3: TREE ASSESSMENT SCHEDULE

Encroachment Analysis

		TPZ radius (m)	TPZ area (m2)	Encroachment (m2)	Percentage (%)	within development	Design Notes
1	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	10.80	366.25				No encroachment. Retain
2	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	7.20	162.78				No encroachment. Retain
3	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	9.48	282.19				No encroachment. Retain
4	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	9.60	289.38				No encroachment. Retain
5	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	12.00	452.16				No encroachment. Retain
6	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	12.48	489.06				No encroachment. Retain
7	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	12.00	452.16				No encroachment. Retain
8	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	8.40	221.56				No encroachment. Retain
9	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	11.52	416.71				No encroachment. Retain
10	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	6.36	127.01				No encroachment. Retain
11	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	11.28	399.53				No encroachment. Retain
12	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	8.76	240.96				No encroachment. Retain
13	<i>Eucalyptus microcorys</i> Tallowwood	6.72	141.80	0.00	0.0		No encroachment. Retain
14	<i>Eucalyptus microcorys</i> Tallowwood	6.48	131.85	0.00	0.0		No encroachment. Retain
15	<i>Eucalyptus microcorys</i> Tallowwood	6.72	141.80	0.00	0.0		No encroachment. Retain
15A	<i>Acacia sp.</i> Wattle						Poor condition. Remove
16	<i>Eucalyptus microcorys</i> Tallowwood	7.08	157.40	49.33	31.3		No encroachment. Retain
17	<i>Eucalyptus microcorys</i> Tallowwood						No encroachment. Retain
18	<i>Eucalyptus microcorys</i> Tallowwood	7.32	168.25	1.00	0.6		No encroachment. Retain
19	<i>Eucalyptus microcorys</i> Tallowwood	6.96	152.11	3.00	2.0		No encroachment. Retain
20	<i>Eucalyptus microcorys</i> Tallowwood	8.04	202.97	0.00	0.0		No encroachment. Retain
21	<i>Eucalyptus microcorys</i> Tallowwood	7.20	162.78	0.00	0.0		No encroachment. Retain
22	<i>Washingtonia robusta</i> Mexican Fan Palm					YES	Transplant on site
23	<i>Washingtonia robusta</i> Mexican Fan Palm					YES	Transplant on site
24	<i>Washingtonia robusta</i> Mexican Fan Palm					YES	Transplant on site
24A	<i>Washingtonia robusta</i> Mexican Fan Palm					YES	Transplant on site
25	<i>Washingtonia robusta</i> Mexican Fan Palm					YES	Transplant on site
26	<i>Washingtonia robusta</i> Mexican Fan Palm					YES	Transplant on site
27	<i>Washingtonia robusta</i> Mexican Fan Palm					YES	Transplant on site
28	<i>Washingtonia robusta</i> Mexican Fan Palm					YES	Transplant on site
29	<i>Washingtonia robusta</i> Mexican Fan Palm					YES	Transplant on site

Encroachment Analysis

		TPZ radius (m)	TPZ area (m2)	Encroachment (m2)	Percentage (%)	within development	Design Notes
30	<i>Washingtonia robusta</i> Mexican Fan Palm					YES	Transplant on site
31	<i>Washingtonia robusta</i> Mexican Fan Palm					YES	Transplant on site
32	<i>Washingtonia robusta</i> Mexican Fan Palm					YES	Transplant on site
33	<i>Washingtonia robusta</i> Mexican Fan Palm					YES	Transplant on site
34	<i>Eucalyptus microcorys</i> Tallowwood	7.20	162.78	8.67	5.3		No encroachment. Retain
35	<i>Angophora costata</i> Smooth-barked Apple	6.48	131.85	11.00	8.3		Minor encroachment. Retain
36	<i>Eucalyptus robusta</i> Swamp Mahogany	5.88	108.56	108.56	100.0	YES	Major encroachment incl. SRZ. Remove
37	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	6.84	146.91	146.91	100.0	YES	Major encroachment incl. SRZ. Remove
38	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	6.12	117.61	5.29	4.5		Minor encroachment. Retain
39	<i>Eucalyptus microcorys</i> Tallowwood	6.12	117.61	0.00	0.0		On adjacent property.No encroachment. Retain
40	<i>Eucalyptus microcorys</i> Tallowwood	6.72	141.80	0.00	0.0		On adjacent property.No encroachment. Retain
41	<i>Corymbia maculata</i> Spotted Gum	7.08	157.40	157.40	100.0	YES	Major encroachment incl. SRZ. Remove
42	<i>Eucalyptus microcorys</i> Tallowwood						On adjacent property.No encroachment. Retain
43	<i>Ficus hillii</i> Weeping Fig						On adjacent property.No encroachment. Retain
44	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark						On adjacent property.No encroachment. Retain
45	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark						On adjacent property.No encroachment. Retain
46	<i>Eucalyptus benthamii</i> Camden white gum *1	12.00	452.16	0.00	0.0		Wound wood with Chino seepage. Aerial investigation & possible removal
47	<i>Eucalyptus tereticornis</i> Forest Red Gum*1	8.88	247.60	57.46	23.2	YES	Major encroachment. Retain subject to root investigation and detail design levels.
47A	<i>Eucalyptus benthamii</i> Camden white gum *1	6.96	152.11	0.00	0.0		Poor condition. Retain. Aerial investigation & possible removal.
48	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	12.00	452.16	452.16	100.0	YES	Major encroachment incl. SRZ. Remove
49	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	8.76	240.96	240.96	100.0	YES	Major encroachment incl. SRZ. Remove
50	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	9.96	311.49	208.94	67.1	YES	Major encroachment incl. SRZ. Remove
51	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	12.48	489.06	78.67	16.1		Major encroachment. Investigation and possible removal.
52	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	9.36	275.09	275.09	100.0	YES	Major encroachment incl. SRZ. Remove
53	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	8.76	240.96	35.03	14.5		Major encroachment. Remove
54	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	6.24	122.26	122.26	100.0	YES	Major encroachment incl. SRZ. Remove
55	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	7.20	162.78	162.78	100.0	YES	Major encroachment incl. SRZ. Remove
56	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	11.64	425.44	425.44	100.0	YES	Major encroachment incl. SRZ. Remove
57	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	5.52	95.68	95.68	100.0	YES	Major encroachment incl. SRZ. Remove
58	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	9.96	311.49	311.49	100.0	YES	Major encroachment incl. SRZ. Remove
59	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	8.52	227.93	227.93	100.0	YES	Major encroachment incl. SRZ. Remove

Encroachment Analysis

		TPZ radius (m)	TPZ area (m2)	Encroachment (m2)	Percentage (%)	within development	Design Notes
60	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	6.00	113.04	0.00	0.0		No encroachment. Retain
61	<i>Eucalyptus sp</i> *1	10.08	319.04	0.00	0.0		No encroachment. Retain
62	<i>Eucalyptus sp</i> *1	6.60	136.78	0.57	0.4		Minor encroachment. Retain
63	<i>Melaleuca quinquenervia</i> Broad-leaved Paperbark	10.56	350.15	0.00	0.0		No encroachment. Retain
64	<i>Eucalyptus tereticornis</i> Forest Red Gum*1	14.40	651.11	0.00	0.0		No encroachment. Retain
65	<i>Acacia elata</i> Cedar Wattle	9.48	282.19	0.00	0.0		Remove. Refer to tree assessment schedule
65A	<i>Strelitzia nicolai</i> Giant White Bird of Paradise						No encroachment. Retain
66	<i>Eucalyptus robusta</i> Swamp Mahogany	3.12	30.57	0.00	0.0		No encroachment. Retain
67	<i>Eucalyptus leucoxylon rosea</i> Yellow Gum *1						No encroachment. Retain
68	<i>Eucalyptus ficifolia</i> Red Flowering Gum						No encroachment. Retain
69	<i>Eucalyptus sp</i> *1						No encroachment. Retain
70	<i>Eucalyptus citriodora</i> Lemon Scented Gum*1						No encroachment. Retain
70A	<i>Eucalyptus sp</i> *1						No encroachment. Retain
71	<i>Agonis flexuosa</i> Willow Myrtle						No encroachment. Retain
72	<i>Jacaranda mimosifolia</i> Jacaranda						No encroachment. Retain
73	<i>Jacaranda mimosifolia</i> Jacaranda						No encroachment. Retain
88	<i>Jacaranda mimosifolia</i> Blue Jacaranda						No encroachment. Retain
89	<i>Agonis flexuosa</i> Willow Myrtle						No encroachment. Retain
89A	<i>Eucalyptus botryiodes</i> Bangalay						No encroachment. Retain
91	<i>Araucaria heterophylla</i> Norfolk Island Pine						No encroachment. Retain
92	<i>Eucalyptus saligna</i> Sydney Blue Gum						No encroachment. Retain
94	<i>Corymbia maculata</i> Spotted Gum						No encroachment. Retain
95	<i>Corymbia maculata</i> Spotted Gum						No encroachment. Retain
96	<i>Corymbia maculata</i> Spotted Gum						No encroachment. Retain
97	<i>Corymbia maculata</i> Spotted Gum						No encroachment. Retain
98	<i>Corymbia maculata</i> Spotted Gum						No encroachment. Retain
99	<i>Archontophoenix cunninghamiana</i> Bangalow Palm						No encroachment. Retain
100	<i>Archontophoenix cunninghamiana</i> Bangalow Palm						No encroachment. Retain
101	<i>Strelitzia nicolai</i> Giant White Bird of Paradise						No encroachment. Retain
102	<i>Strelitzia nicolai</i> Giant White Bird of Paradise						No encroachment. Retain


Encroachment Analysis

		TPZ radius (m)	TPZ area (m2)	Encroachment (m2)	Percentage (%)	within development	Design Notes
178	<i>Eucalyptus botryiodes</i> Bangalay	6.72	141.80	0.00	0.0		No encroachment. Retain
179	<i>Eucalyptus saligna</i> X <i>Botryoides</i> Southern Blue Gum *1	14.76	684.07	0.00	0.0		No encroachment. Retain
179A	<i>Syzygium luehmannii</i> Small-leaved Lilly Pilly	2.28	16.32	0.00	0.0		No encroachment. Retain
179B	<i>Cupaniopsis anarcardioides</i> Tuckeroo	2.52	19.94	0.00	0.0		No encroachment. Retain
179C	<i>Corymbia eximia</i> Yellow Bloodwood	2.00	12.56	0.00	0.0		No encroachment. Retain
180	<i>Brachychiton populneus</i> Kurrajong	2.64	21.88	0.00	0.0		No encroachment. Retain
180A	<i>Strelitzia nicolai</i> Giant White Bird of Paradise					YES	Major encroachment incl. SRZ. Remove
181	<i>Cupaniopsis anarcardioides</i> Tuckeroo	4.56	65.29	166.67	255.3		No encroachment. Retain
182	<i>Syzygium paniculatum</i> Magenta Lilly Pilly	2.00	12.56	167.67	1335.0		No encroachment. Retain
183	<i>Acmena smithii</i> Lilly Pilly	2.00	12.56	168.67	1342.9		No encroachment. Retain
184A	<i>Morus alba</i> Mulberry						Retain. Refer to tree assessment schedule
184	<i>Brachychiton acerifolius</i> Illawarra Flame Tree	2.76	23.92	1.64	6.9		Minor encroachment. Retain
185	<i>Eucalyptus microcorys</i> Tallowwood	5.76	104.18	0.00	0.0		No encroachment. Retain
185A	<i>Eucalyptus botryiodes</i> Bangalay	13.08	537.21	3.80	0.7		Co-dominant. Bracket fungus. Retain
185B	<i>Corymbia eximia</i> Yellow Bloodwood	2.00	12.56	0.00	0.0		No encroachment. Retain
186	<i>Eucalyptus microcorys</i> Tallowwood	6.36	127.01	0.00	0.0		No encroachment. Retain
187	<i>Eucalyptus microcorys</i> Tallowwood	9.12	261.17	0.00	0.0		No encroachment. Retain
188	<i>Eucalyptus microcorys</i> Tallowwood	4.92	76.01	0.63	0.8		Minor encroachment. Retain
189	<i>Eucalyptus microcorys</i> Tallowwood	5.16	83.60			YES	Minor encroachment. Retain
190	<i>Eucalyptus microcorys</i> Tallowwood	8.88	247.60			YES	Minor encroachment. Retain
193	<i>Eucalyptus microcorys</i> Tallowwood	3.72	43.45	0.07	0.2		Minor encroachment. Retain
194	<i>Eucalyptus microcorys</i> Tallowwood	8.64	234.40	3.70	1.6		Minor encroachment. Retain
195	<i>Banksia integrifolia</i> Coast Banksia	3.12	30.57	0.00	0.0		No encroachment. Retain
196	<i>Banksia serrata</i> Old Man Banksia	4.80	72.35	0.00	0.0		Assume no excavation, cut/fill in car park area. No encroachment. Retain
196A	<i>Banksia integrifolia</i> Coast Banksia	2.00	12.56	0.00	0.0		Assume no excavation, cut/fill in car park area. No encroachment. Retain
197	<i>Banksia serrata</i> Old Man Banksia	5.40	91.56	0.00	0.0		Assume no excavation, cut/fill in car park area. No encroachment. Retain
198	<i>Angophora costata</i> Smooth-barked Apple	6.72	141.80	0.00	0.0		Assume no excavation, cut/fill in car park area. No encroachment. Retain
199	<i>Lophostemon confertus</i> Brush Box	6.96	152.11	0.00	0.0		No encroachment. Remove
200	<i>Lophostemon confertus</i> Brush Box	6.60	136.78	0.00	0.0		No encroachment. Retain
201	<i>Lophostemon confertus</i> Brush Box	6.24	122.26	0.00	0.0		No encroachment. Retain

Encroachment Analysis

		TPZ radius (m)	TPZ area (m2)	Encroachment (m2)	Percentage (%)	within development	Design Notes
202	<i>Lophostemon confertus</i> Brush Box	6.48	131.85	0.00	0.0		No encroachment. Retain
203	<i>Lophostemon confertus</i> Brush Box	5.40	91.56	23.53	25.7		Minor encroachment. Retain
204	<i>Lophostemon confertus</i> Brush Box	9.24	268.09	108.65	40.5		Minor encroachment. Retain
205	<i>Lophostemon confertus</i> Brush Box	7.68	185.20	76.17	41.1		Minor encroachment. Retain
206	<i>Lophostemon confertus</i> Brush Box	5.52	95.68	34.15	35.7		Minor encroachment. Retain


APPENDIX 4: TYPICAL TREE PROTECTION DETAILS



PROTECTIVE FENCING

Based on AS4970-2009

NOT TO SCALE




NOTE: Excavation required for the insertion of support posts for tree protection fencing should not involve the severance of any roots greater than 20mm in diameter, without the prior approval of the project arborist.

INDICATIVE SCAFFOLDING WITHIN A TPZ

Based on AS4970-2009

NOT TO SCALE



NOTE:

1. For trunk and branch protection use boards and padding that will prevent damage to bark. Boards are to be strapped to trees, not nailed or screwed.
2. Rumble boards should be of a suitable thickness to prevent soil compaction and root damage.

EXAMPLES OF TRUNK, BRANCH AND GROUND PROTECTION

Based on AS4970-2009

NOT TO SCALE



TREE PROTECTION ZONE SIGN

Based on AS4970-2009

NOT TO SCALE