

NORTH SYDNEY COUNCIL
WITHOUT PREJUDICE DRAFT CONDITIONS
54-58A WYCOMBE ROAD, NEUTRAL BAY
DEVELOPMENT APPLICATION NO. 306/19

A. Conditions that Identify Approved Plans

Development in Accordance with Plans/documentation

A1. The development must be carried out in accordance with the following drawings and documentation and endorsed with Council's approval stamp, except where amended by the following conditions of this consent.

Plan No.	Issue	Title	Dated	Received	Received
1813/DA01	G	Site Plan	3/08/2020	Boffa Robertson Group	7/08/2020
1813/DA03	D	Demolition Ground Floor Plan	21/02/2020	Boffa Robertson Group	04/03/2020
1813/DA04	D	Demolition First Floor Plan	21/02/2020	Boffa Robertson Group	04/03/2020
1813/DA05	C	Demolition Second Floor Plan	21/02/2020	Boffa Robertson Group	04/03/2020
1813/DA06	F	Proposed Basement Floor Plan	03/08/2020	Boffa Robertson Group	07/08/2020
1813/DA07	H	Proposed Lower Ground Floor Plan	03/08/2020	Boffa Robertson Group	07/08/2020
1813/DA08	K	Proposed Ground Floor Plan	03/08/2020	Boffa Robertson Group	07/08/2020
1813/DA09	K	Proposed First Floor Plan	03/08/2020	Boffa Robertson Group	07/08/2020
1813/DA10	J	Proposed Second Floor Plan	17/06/2020	Boffa Robertson Group	30/06/2020
1813/DA11	F	Proposed Roof Plan	17/06/2020	Boffa Robertson Group	30/06/2020
1813/DA12	G	Elevations – Sheet 1	18/06/2020	Boffa Robertson Group	30/06/2020
1813/DA13	F	Elevations – Sheet 2	18/06/2020	Boffa Robertson Group	30/06/2020
1813/DA14	G	Elevations – Sheet 3	18/06/2020	Boffa Robertson Group	30/06/2020
1813/DA14A	A	South Elevations	18/06/2020	Boffa Robertson Group	30/06/2020
1813/DA15	E	Sections – Height Plan	18/06/2020	Boffa Robertson Group	30/06/2020
1813/DA15A	E	Sections – Height Plan	18/06/2020	Boffa Robertson Group	30/06/2020
SKO1	P	Overall Site Plan	Aug 2020	Umbaco Landscape	07/08/2020
SKO9	P	Landscape Plan Ground Floor	Aug 2020	Umbaco Landscape	07/08/2020
SK10	P	Landscape Plan First and Second Floor	Aug 2020	Umbaco Landscape	07/08/2020
SKO4	N	Plant Material Ground Floor & Street Frontage	June 2020	Umbaco Landscape	30/06/2020
SKO5	N	Plant Material Ground Floor & Street Frontage	June 2020	Umbaco Landscape	30/06/2020
SKO6	N	Plant Material First and Second Floor	June 2020	Umbaco Landscape	30/06/2020
SK07	N	Sections Elevations	June 2020	Umbaco Landscape	30/06/2020

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information)

Plans on Site

- A2. A copy of all stamped approved plans, specifications and documents (including the plans, specifications and documents submitted and approved with the Construction Certificate) must be kept on site at all times so as to be readily available for perusal by any officer of Council or the Principal Certifying Authority.

All documents kept on site in accordance with this condition must be provided to any officer of the Council or the certifying authority upon their request.

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information and to ensure ongoing compliance)

No Demolition of Extra Fabric

- A3. Alterations to, and demolition of the existing buildings shall be limited to that documented on the approved plans.

(Reason: To ensure compliance with the approved development)

External Finishes & Materials

- A4. External finishes and materials must be in accordance with details provide on the plans referred to condition A1 unless otherwise modified by Council in writing.

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information)

B. Matters to be Completed before the lodgement of an Application for a Construction Certificate

Construction and Traffic Management Plan (Major DAs & sites with difficult access)

- B1. A Construction Management Program prepared by a suitably qualified and experienced traffic consultant must be submitted and approved in writing by North Sydney Traffic Committee PRIOR TO THE ISSUE OF ANY Construction Certificate. Any use of Council property will require appropriate approvals prior to any work commencing. At a minimum, the Construction Management Program must specifically address the following matters:

- a) A plan view (min 1:100 scale) of the entire site and frontage roadways indicating:
 - i. Dedicated temporary construction site driveway entrances and exits, controlled by a certified traffic controller, to safely manage pedestrians and construction related vehicles in the frontage roadways and footways;
 - ii. The proposed signage for pedestrian management to comply with the relevant Australian Standards, including pram ramps;
 - iii. Turning areas within the site for construction and spoil removal vehicles, allowing a forward egress for all construction vehicles on the site;
 - iv. The locations of any proposed Work Zones in the frontage roadways (to be approved by Council's Traffic Committee);
 - v. Locations of hoardings proposed;
 - vi. Location of any proposed crane standing areas;
 - vii. A dedicated unloading and loading point within the site for all construction vehicles, plant and deliveries;
 - viii. Material, plant and spoil bin storage areas within the site, where all materials are to be dropped off and collected; and
 - ix. The provision of an on-site parking area for employees, tradesperson and construction vehicles as far as possible.
- b) A detailed heavy vehicle access route map through the Council area to Arterial Roads. Provision is to be made to ensure through traffic is maintained at all times.
- c) The proposed phases of works on the site, and the expected duration of each phase.
- d) How access to neighbouring properties will be maintained at all times and the proposed manner in which adjoining property owners will be kept advised of the timeframes for completion of each phase of process.
- e) The road is not to be used as a waiting area for trucks delivering to or awaiting pick up of materials.
- f) The proposed method of support to any excavation adjacent to adjoining properties, or the road reserve. The proposed method of support is to be designed and certified by an appropriately qualified and practising structural engineer and must not involve any permanent or temporary encroachment onto Councils property.
- g) Proposed protection for Council and adjoining properties. Details are to include site fencing and the provision of "B" class hoardings over footpaths and laneways.

- h) A Waste Management Plan. The Waste Management Plan must include, but not be limited to, the estimated volume of waste and method of disposal for the construction and operation phases of the development, design of on-site waste storage and recycling area and administrative arrangements for waste and recycling management during the construction process.

All traffic control work and excavation, demolition and construction activities must be undertaken in accordance with the approved Construction Management Program and any conditions attached to the approved Program. A certificate of compliance with this condition must be obtained from Council's development engineers. The certificate and the approved Construction Management Program must be submitted as part of the documentation lodged with the application for approval of a construction certificate. A copy of the approved Construction Management Program and any conditions imposed on that Program, must be kept on the site at all times and made available to any officer of Council upon request.

Notes:

- 1) North Sydney Council's adopted fee for certification of compliance with this condition shall be payable on lodgement, or in any event, prior to the issue of the relevant approval.
- 2) Any use of Council property will require appropriate approvals and demonstration of liability insurances prior to such work commencing.
- 3) Failure to provide complete and detailed information may result in delays. It is recommended that your Construction Management Plan be lodged with Council as early as possible, as a minimum six (6) weeks notice is required to refer items to the Traffic Committee.
- 4) Dependent on the circumstances of the site, Council may request additional information to that detailed above.

(Reason: To ensure appropriate measures have been considered for site access, storage and the operation of the site during all phases of the demolition process in a manner that respects adjoining owner's property rights and residential amenity in the locality, without unreasonable inconvenience to the community)

C. *Prior to the Issue of a Construction Certificate (and ongoing, where indicated).*

Dilapidation Report Damage to Public Infrastructure

- C1. A dilapidation survey and report (including photographic record) must be prepared by a suitably qualified consultant which details the pre-developed condition of the existing public infrastructure in the vicinity of the development site. Particular attention must be paid to accurately recording any pre-developed damaged areas so that Council is fully informed when assessing any damage to public infrastructure caused as a result of the development. A copy of the dilapidation survey and report is to be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The developer may be held liable for all damage to public infrastructure in the vicinity of the site, where such damage is not accurately recorded and demonstrated as pre-existing under the requirements of this condition.

The developer shall bear the cost of carrying out works to restore all public infrastructure damaged as a result of the carrying out of the development, and no occupation of the development shall occur until damage caused as a result of the carrying out of the development is rectified.

A copy of the dilapidation survey and report must be lodged with North Sydney Council by the Certifying Authority with submission of the Construction Certificate documentation.

(Reason: To record the condition of public infrastructure prior to the commencement of construction)

Dilapidation Survey Private Property (Neighbouring Buildings)

- C2. A photographic survey and dilapidation report of adjoining properties No's. 60 Wycombe Road, 19 Harriette Street, 66 Aubin Street, 9 & 11 Thrupp Street detailing the physical condition of those properties, both internally and externally, including, but not limited to, such items as walls, ceilings, roof, structural members and other similar items, SHALL BE submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The survey and report are to be prepared by an appropriately qualified person agreed to by both the applicant and the owner of the adjoining property. A copy of the report is to be provided to Council, if Council is not the Certifying Authority, prior to the issue of any Construction Certificate.

All costs incurred in achieving compliance with this condition shall be borne by the person entitled to act on this Consent.

In the event that access for undertaking the photographic survey and dilapidation report is denied by an adjoining owner, the applicant MUST DEMONSTRATE, in writing, to the satisfaction of Council that all reasonable steps have been taken to obtain access and advise the affected property owner of the reason for the survey and that these steps have failed. Written concurrence must be obtained from Council in such circumstances.

Note: This documentation is for record keeping purposes only and may be used by an applicant or affected property owner to assist in any action required to resolve any dispute over damage to adjoining properties arising from the works. It is in the applicant's and adjoining owner's interest for it to be as full and detailed as possible.

(Reason: Proper management of records)

Geotechnical Report

C3. Prior to issue of any Construction Certificate a Geotechnical/Civil Engineering report must be prepared which addresses at a minimum (but is not limited to) the following:-

- a) the type and extent of substrata formations by the provision of a minimum of four (4) representative bore hole logs which are to provide a full description of all material from ground surface to 1.0m below the finished basement floor level and include the location and description of any anomalies encountered in the profile. The surface and depth of the bore hole logs must be related to Australian Height Datum;
- b) the appropriate means of excavation/shoring in light of point (a) above and proximity to adjacent property and structures. Potential vibration caused by method of excavation and potential settlements affecting nearby footings/foundations must be discussed and mechanisms to ameliorate any such impacts recommended;
- c) the proposed method to temporarily and permanently support the excavation for the basement adjacent to adjoining property, structures and road reserve if nearby (full support must be provided within the subject site);
- d) the existing groundwater levels in relation to the basement structure, where influenced;
- e) the drawdown effects on adjacent properties (including road reserve), if any, the basement excavation will have on groundwater together with the appropriate construction methods to be utilised in controlling groundwater. Where it is considered there is the potential for the development to create a "dam" for natural groundwater flows, a groundwater drainage system must be designed to transfer groundwater through or under the proposed development without a change in the range of the natural groundwater level fluctuations. Where an impediment to the natural flow path is constructed, artificial drains such as perimeter drains and through drainage may be utilised; and

- f) recommendations to allow the satisfactory implementation of the works. An implementation program is to be prepared along with a suitable monitoring program including control levels for vibration, shoring support, ground level and groundwater level movements during construction. The implementation program is to nominate suitable hold points at the various stages of the works for verification of the design intent before sign-off and before proceeding with subsequent stages.

The geotechnical report must be prepared by an appropriately qualified consulting geotechnical/ hydrogeological engineer with previous experience in such investigations and reporting.

It is the responsibility of the consulting geotechnical/ hydrological specialist to undertake the appropriate investigations, reporting and specialist recommendations to ensure a reasonable level of protection to adjacent property and structures both during and after construction. The report must contain site-specific geotechnical recommendations and shall specify the necessary hold/inspection points by relevant professionals as appropriate.

The design principles for the geotechnical report are as follows:

- a) no ground settlement or movement is to be induced which is sufficient enough to cause an adverse impact to adjoining property and/or infrastructure;
- b) no changes to the ground water level are to occur as a result of the development that are sufficient enough to cause an adverse impact to the surrounding property and infrastructure;
- c) no changes to the ground water level are to occur during the construction of the development that are sufficient enough to cause an adverse impact to the surrounding property and infrastructure;
- d) vibration is to be minimised or eliminated to ensure no adverse impact on the surrounding property and infrastructure occurs, as a result of the construction of the development;
- e) appropriate support and retention systems are to be recommended and suitable designs prepared to allow the proposed development to comply with these Design Principles; and
- f) an adverse impact can be assumed to be crack damage as identified within the relevant Australian Standard for determining such damage.

The report, satisfying the requirements of this condition, must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The professional recommendations, implementation program, monitoring

program, mitigation measures and the like contained in the report must be implemented in full during the relevant stages of excavation and construction.

(Reason: To ensure the structural integrity of the subject site and adjoining sites during the excavation process)

Sediment Control

C4. Where construction or excavation activity requires the disturbance of the soil surface or existing vegetation, erosion and sediment control techniques, as a minimum, are to be in accordance with the publication Managing Urban Stormwater: Soils & Construction (4th edition, Landcom, 2004) commonly referred to as the “Blue Book” or a suitable and effective alternative method. A Sediment Control Plan must be prepared and submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate and prior to any works commencing. The Sediment Control Plan must be consistent with the Blue Book and disclose:

- a) All details of drainage to protect and drain the site during the construction processes;
- b) All sediment control devices, barriers and the like;
- c) Sedimentation tanks, ponds or the like;
- d) Covering materials and methods; and
- e) A schedule and programme of the sequence of the sediment and erosion control works or devices to be installed and maintained.
- f) Methods for the temporary and controlled disposal of stormwater during construction.

All works must be undertaken in accordance with the approved Sediment Control plan.

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

Waste Management Plan

- C5. A Waste Management Plan is to be submitted for approval by the Certifying Authority prior to the issue of the relevant Construction Certificate. The plan must include, but not be limited to:
- a) The estimated volume of waste and method of disposal for the construction and operation phases of the development;
 - b) The design of the on-site waste storage and recycling area; and
 - c) Administrative arrangements for waste and recycling management during the construction process.

The approved Waste Management Plan must be complied with at all times in the carrying out of the development.

(Reason: To encourage the minimisation of waste and recycling of building waste)

Colours, Finishes and Materials (Heritage Items – 56 Wycombe Road, Neutral Bay)

- C6. A traditional palette of finishes, materials and colour schemes must be selected for the new building works appropriate to the architectural style of the original building and submitted to the Certifying Authority for approval prior to the issue of the relevant Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted fully satisfy the requirements of this condition prior to the release of the Construction Certificate.

(Reason: To ensure that exterior colours, finishes and materials are sympathetic to the significance of the heritage item.)

Colours, Finishes and Materials (Conservation Area – New Buildings)

- C7. The finishes, materials and exterior colours for the new buildings shall be complementary to the architectural style of the original buildings and sympathetic to the character of the Conservation Area. A schedule of finishes, materials and external colours shall be submitted to the Certifying Authority for approval prior to the issue of the relevant Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted fully satisfy the requirements of this condition prior to the release of the Construction Certificate.

(Reason: To ensure that the completed colours, finishes and materials are complementary to the Conservation Area.)

Sandstone Re-pointing

- C8. Any repointing works to the sandstone wall along the Wycombe Road boundary must be undertaken using traditional lime mortar by a qualified stonemason. Written details of the engagement of a qualified stonemason must be submitted to the Certifying Authority prior to the issue of any Construction Certificate.

The Certifying Authority must also ensure that the building plans and specifications submitted, referenced on and accompanying the relevant Construction Certificate, fully satisfy the requirements of this condition.

Note: The provisions of the Heritage Act may also apply to altering any sandstone elements on any site.

(Reason: To allow for preservation of cultural resources within the North Sydney Council area)

Heritage Architect to be commissioned

- C9. An appropriately qualified and experienced heritage architect must be commissioned to assist the design development, contract documentation and overseeing of construction works on 56 Wycombe Road for their duration by undertaking regular inspections of the works in progress and providing advice in relation to heritage matters including the retention or reuse of significant heritage fabric including but not limited to nib walls, fireplaces, mantle pieces, staircases, lead lights, flooring and joinery.

Written details of the engagement of the experienced heritage architect must be submitted to the Certifying Authority prior to the issue of the relevant Construction Certificate.

Note: if advice provided by the heritage architect is to the effect that works requiring development consent be carried out, such works would require an application under s4.55 of the Environmental Planning and Assessment Act 1979 or further development application. This condition, and any advice given by the heritage architect, should not be construed as authorising the carrying of development with/ otherwise than in accordance with the development consent.

(Reason: To ensure that all matters relating to significant fabric and spaces are resolved and recorded using best practice for heritage conservation)

Roofing Materials - Reflectivity

- C10. Roofing materials must be factory pre-finished with low glare and reflectivity properties to be compatible with the colours of neighbouring buildings. The selected roofing material must not cause a glare nuisance or excessive

reflectivity to adjoining or nearby properties. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure that excessive glare or reflectivity nuisance from roofing materials does not occur as a result of the development)

No External Service Ducts

C11. Service ducts must be provided within the building to keep external walls free of plumbing, drainage or any other utility installations. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the relevant Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure quality built form of the development)

Work Zone

C12. If a Work Zone is proposed, an application must be made to the North Sydney Local Traffic Committee to install the 'Work Zone'. A Work Zone permit is required to be issued by the Council prior to the issue of any Construction Certificate.

Work Zones are provided specifically for the set down and pick up of materials and not for the parking of private vehicles associated with the site. Works Zones will generally not be approved where there is sufficient space on-site for the setting down and picking up of goods being taken to or from a construction site. If the Works Zone is approved by the Committee, the Applicant must obtain a written copy of the related resolution from the North Sydney Local Traffic Committee and submit a copy of this to the Certifying Authority to enable issue of the Construction Certificate.

Where approval of the 'Work Zone' is given by the Committee, the requirements of the Committee, including installation of the necessary 'Work Zone' signage and payment of any fees, must occur prior to commencement of any works on the site. Further, at the expiration of the Work Zone approval, the developer is required to remove the Work Zone signs and reinstate any previous signs, all at the developer's cost. The requirements imposed by the Committee on the Work Zone permit (or permits) must be complied with at all times.

(Reason: Amenity and convenience during construction)

Maintain Property Boundary Alignment Levels

- C13. Except where otherwise approved by Council, the property boundary alignment levels must match the levels which existed prior to the commencement of works. Plans and specifications which document existing and proposed levels adjacent to the site boundaries and which comply with the requirements of this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure interface between property and public land remains uniform)

Bicycle Storage and Parking

- C14. A bicycle rail accommodating a minimum of 5 bicycles shall be provided. The bicycle rail shall be designed in accordance with the applicable Australian Standards. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of the relevant Construction Certificate. The Certifying Authority must ensure that the building plans and specifications, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To promote and provide facilities for alternative forms of transport)

Staff Shower & Change Facilities (Commercial and Mixed Use)

- C15. Shower and change facilities shall be provided and made accessible without charge to staff who work in the building. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the relevant Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To promote and provide facilities for alternative forms of transport)

Basement Car park to comply with relevant standards

- C16. The basement layout must comply with all requirements of Australian Standard AS2890.1. Certification from a suitably qualified and practicing Civil Engineer that the basement design will comply with the requirements of the Australian Standard must be provided to the Certifying Authority for approval prior to issue of the relevant Construction Certificate.

(Reason: To ensure the basement layout complies with relevant standards)

Required Infrastructure Works –Roads Act 1993

C17. Prior to issue of the relevant Construction Certificate engineering design plans and specifications must be prepared by a qualified civil design engineer. The plans and specifications must be to a detail suitable for construction issue purposes and must provide detail and specification for the following infrastructure works to be completed as part of the development. To obtain the permit, an application must be made to Council on a '*Application to satisfy development consent*' form with payment of the adopted assessment/inspection fees. The responsibility for accuracy of the design fully rests with the designing engineer. All responsibility on implementation and supervision of works specified on design plans fully rests on designing engineer or whoever is chosen to be applicant's engineering representative:

Road Works

- a) Construction of a fully new replacement concrete footpath is required across the entire site frontage in Wycombe Road. The new footpath levels shall generally match the existing footpath levels except where redundant vehicular crossings are replaced with footpath and grass verge. A longitudinal section is required along the footpath property boundary at a scale of 1:50 extending 5m past the property boundary line. The footpath shall be designed (at a single straight grade of 3% falling to the grass verge) so that it is uniform without showing signs of dipping or rising particularly at entrances.
- b) Construction of a fully new kerb and gutter is required across the entire site frontage in Wycombe Road. A longitudinal section is required along the gutter line (existing and proposed levels), at a scale of 1:50 extending 5m past the property boundary line.
- c) Construction of old parts of kerb & gutter in Aubin Street that are left out from recent reconstruction (undertaken by Council).
- d) Cross sections at a scale of 1:50 along the centre-line of each access point to the building must be provided and are to show the calculated clearance to the underside of any overhead structure. All the entry points are to comply with the Building Code of Australia (BCA), including disability requirements. The Council approved footpath levels must be accommodated at the building entry points.
- e) Construction of a fully new road shoulder (maximum grade 5% down towards new gutter) extending to 0.6 metres out from the gutter alignment adjacent to all new kerb & gutter and layback works on both street frontages.

Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of the relevant Construction Certificate.

Certifying Authorities must not issue a Construction Certificate without the formal written approval of Council (as Roads Authority) under the Roads Act 1993.

The required plans and specifications are to be designed in accordance with North Sydney Council's current documents Infrastructure Specification for Road Works, Drainage and Miscellaneous Works and Performance Guide for Engineering Design and Construction. The drawings must detail existing utility services and trees affected by the works, erosion control requirements and traffic management requirements during the course of works. A detailed survey must be undertaken as required. Traffic management is to be certified on the drawings as being in accordance with the documents SAA HB81.1 – 1996 – Field Guide for Traffic Control at Works on Roads – Part 1 and RMS Traffic Control at Work Sites (1998). **Construction of the works must proceed only in accordance with any conditions attached to the Council Roads Act 1993 approval.**

***Note:** A minimum of 21 days will be required for Council to assess Roads Act submissions. Early submission is recommended to avoid any delays in obtaining a Construction Certificate. A fee to cover cost of assessment (set out in Council's adopted fees and charges) is payable and Council will withhold any consent and approved plans until full payment of the correct fees. Plans and specifications must be marked to the attention of Council's Development Engineers. In addition, a copy of this condition must be provided, together with a covering letter stating the full address of the property and the accompanying DA number.*

(Reason: To ensure infrastructure works are designed and constructed to appropriate standards and requirements of the Roads Act, 1993)

Obtain Driveway Crossing and associated works permit

- C18. Prior to the issue of the Construction Certificate, North Sydney Council must issue the applicant with a driveway crossing and road infrastructure works **permit** to suit the approved off-street parking facilities. To obtain the permit, an application must be made to Council on a '*Vehicular Access Application*' form with payment of the adopted assessment/inspection fees. Council will require civil design construction drawings and certification from the applicant's Civil Engineer to verify design details and enable permit issue. The responsibility for accuracy of the design fully rests with the designing engineer. All responsibility on implementation and supervision of works specified on design plans fully rests on designing engineer or whoever is chosen to be applicant's engineering representative. The civil design drawings shall detail **the following infrastructure construction requirements of Council in relation to the consent:**

- a) The proposed vehicular access ways must comply with AS 2890.1 and Council's current Vehicular Access Application Guidelines and Specification (gutter bridges not permitted) to ensure that a B85 vehicle will not scrape/strike the surface of the carriageway, layback, vehicular crossing or parking floor.
- b) All redundant layback crossings on Wycombe Road must be reinstated as upright kerb gutter, grass verge and concrete footpath.
- c) The width of the new vehicular layback in Aubin Street must be 8.5m (including the wings).
- d) The vehicular laybacks must be set square to the kerb.
- e) The crossing (between the layback and the property boundary) must be perpendicular on a single straight grade of approximately 4.5%, falling to the back of the layback.
- f) The footpath property boundary levels must be set no more than 190 mm above the existing gutter invert levels at any point along the driveway crossing.
- g) Alignment levels at the boundary have an important impact on the proposed levels for new driveway. The works must not start until confirmation of boundary alignment levels from registered surveyor. Council has the authority to remove any unauthorized works at the cost of the property owner.
- h) The Certifying Authority must ensure that the internal property levels at boundary matches council's confirmed boundary levels.
- i) The gutter invert levels and road shoulder levels on Aubin Street must stay unchanged.
- j) The kerb gutter, and 600 mm road shoulder wide- strip, adjacent to all new layback and gutter works, on Aubin Street must be reconstructed, to ensure uniformity in the road reserve.
- k) Any twisting of driveway access to ensure vehicles do not scrape must occur wholly within the subject property.
- l) All inspection openings, utility services must be adjusted to match the proposed driveway levels and location.
- m) The design detail has to be provided with **vehicular access application** and must include sections along centre-line and extremities of the crossing at a scale of 1:25. Sections are to be taken from the centre of the roadway through to the parking area itself and shall include all changes of grade and levels, **both** existing and proposed.
- n) A longitudinal section along the footpath property boundary at a scale of 1:50 is required and shall include all changes of grade and levels, **both** existing and proposed.
- o) The sections must show the calculated clearance to the underside of any overhead structure.
- p) All details of internal ramps between parking levels.
- q) A swept path analysis is required demonstrating that an 85th percentile vehicle can manoeuvre in and out of the garage spaces in accordance with AS 2890.1 2004 "Off Street Parking".
- r) Pipelines within the footpath area must be hot dipped galvanized

rectangular steel hollow section with a minimum wall thickness of 4.0 millimetres and a section height of 100 millimetres.

- s) Any footpath panel on Aubin Street and Wycombe Road that is disturbed for the purpose of stormwater connection must be reconstructed as a whole panel.

All driveway and infrastructure works on the road reserve must proceed in accordance with the terms of the permit issued by Council. Inspections by Council will be required as specified on the permit. The Certifying Authority issuing the Construction Certificate must ensure that the permit issued by Council is obtained prior to its issue, is referenced on and accompanies the relevant Construction Certificate issued.

(Reason: To facilitate appropriate vehicular access to private sites, without disruption to pedestrian and vehicular traffic)

Stormwater Management and Disposal Design Plan – Construction Issue

C19. Prior to issue of the Construction Certificate, the applicant shall have a site drainage management plan prepared by a qualified drainage design engineer. The site drainage management plan must detail the following requirements of North Sydney Council:

- a) Compliance with BCA drainage requirements, Council's Engineering Performance guide and current Australian Standards and guidelines, such as AS/NZ3500.3.2 1998, National Plumbing and Drainage Code.
- b) The majority of Stormwater runoff and subsoil drainage generated by the approved dwellings must be conveyed in a controlled manner by gravity from OSD via a direct connection to Council's stormwater gully pit in Wycombe Road. When a direct connection to the pit option is implemented then the pipeline within the footpath area shall have a minimum cover of 300mm. Only minority of surface stormwater runoff from the property may be discharged to Council's kerb in Aubin Street.
- c) All redundant stormwater pipelines within the footpath area in both street frontages shall be removed and the footpath and kerb reinstated.
- d) Pipelines within the footpath area in Aubin Street shall be hot dipped galvanized steel rectangular hollow section with a minimum wall thickness of 4.0 millimetres and a section height of 100 millimetres.
- e) Any footpath panel on Aubin Street disturbed for the purpose of stormwater connection shall be reconstructed as whole panel.
- f) Provision is to be made for the collection and disposal in an approved manner of any overland flow entering the subject property, or concentrated as a result of the proposed works.
- g) All sub-soil seepage drainage shall be discharged via a suitable silt arrester pit. Details of all plans certified as being adequate for their intended purpose and compliant with the provisions of AS3500.3.2 by an appropriately qualified and practising civil engineer, shall be submitted with the application for a Construction Certificate.
- h) The design and installation of the Rainwater Tanks shall comply with

Basix and **Sydney Water** requirements. Overflow from tank shall be connected by gravity to the stormwater disposal system.

- i) Prevent any stormwater egress into adjacent properties by creating physical barriers and surface drainage interception.

Details demonstrating compliance are to be submitted with the Construction Certificate.

The Certifying Authority issuing the Construction Certificate must ensure that the approved drainage plan and specifications, satisfying the requirements of this condition, is referenced on and accompanies the Construction Certificate.

(Reason To ensure controlled stormwater management and disposal without nuisance)

On-Site Stormwater Detention

- C20. On site detention must be provided to ensure that the maximum discharge from the site does not exceed discharge which would occur during a 1 in 5 year storm for the time of concentration determined for the particular site, for the existing site conditions. All other stormwater run-off from the site for all storms up to the 1 in 100 year storm is to be retained on the site for gradual release to the kerb and gutter or drainage system. Provision is to be made for satisfactory overland flow should a storm in excess of the above parameters occur.

Determination of the required cumulative storage must be based on the mass curve technique as detailed in Technical Note 1, Chapter 14 of the Australian Rainfall and Runoff Volume 1, 1987 Edition.

Engineering calculations, design and certification complying with this condition must be provided by an appropriately qualified and practicing Civil Engineer and submitted to the Certifying Authority for approval prior to the issue of the relevant Construction Certificate.

(Reason: To ensure appropriate provision is made for the disposal and management of stormwater generated by the development, and to ensure that public infrastructure in Council's care and control is not overloaded)

Bond for Damage and Completion of Infrastructure Works – Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement

- C21. Prior to the issue of any Construction Certificate, security deposit or bank guarantee must be provided to Council to the sum of \$123,000.00 to be held by Council for the payment of cost for any/all of the following:

- a) making good any damage caused to any property of the Council as a consequence of the doing of anything to which this consent relates,

- b) completing any public work (such as road work, kerbing and guttering, footway construction, stormwater drainage and [environmental controls](#)) required in connection with this consent
- c) Remedying any defects in any such public work that arise within 1 year for stormwater and 6 months for major road works and 2 months for vehicular crossing & small associated footpath works, after the work is completed.

The security in accordance with the schedule contained later in these conditions and must be provided by way of a deposit with the Council; or a guarantee satisfactory to Council (such as a satisfactory bank guarantee).

The security will be refundable following the expiration of defect risk period for the particular type of work as specified above (under c)), from the issue of any final Occupation Certificate or completion of public work required to be completed (whichever is the latest) but only upon inspection and release by Council's Engineers.

Council shall have full authority to make use of the bond for such restoration works as deemed necessary by Council in circumstances including the following: -

- where the damage constitutes a hazard in which case Council may make use of the security immediately;
- the applicant has not repaired or commenced repairing damage within 48 hours of the issue by Council in writing of instructions to undertake such repairs or works;
- works in the public road associated with the development are to an unacceptable quality; and
- the Certifying Authority must ensure that security is provided to North Sydney Council prior to issue of any Construction Certificate.

(Reason: To ensure appropriate security for works on public land and an appropriate quality for new public infrastructure)

Tree Bond for Public Trees

- C22. Prior to the issue of any construction certificate, security in the sum of \$38,000 must be provided to Council for the protection of trees in public places, including the making good of any damage caused to such trees. The security is to be provided in accordance with the Schedule below.

The security required by this condition and in the schedule contained later in these conditions must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney

Council as the nominated beneficiary and must not be subject to an expiry date.

The security will be refundable following the expiration of 6 months from the issue of any final Occupation Certificate but only upon inspection and release by Council's Landscape Development Officer.

If any tree is removed or damaged Council may deduct from this security the reasonable cost of replacement with a tree of the same species and to a similar stage of growth it would have attained at the completion of the work.

In the case of any tree, which cannot be replaced with a similar specimen, the security for that tree will be forfeited to Council and used to provide replacement street plantings.

SCHEDULE

Tree	Location	Bond
<i>2 Callistemon citrinus</i>	Council Verge – Aubin Street	\$1,500
<i>3 Sapium sebiferum</i>	Council Verge – Wycombe Road	\$5,000
<i>4 Sapium sebiferum</i>	Council Verge – Wycombe Road	\$5,000
<i>5 Sapium sebiferum</i>	Council Verge – Wycombe Road	\$5,000
<i>6 Sapium sebiferum</i>	Council Verge – Wycombe Road	\$5,000
<i>7 Sapium sebiferum</i>	Council Verge – Wycombe Road	\$5,000
<i>8 Sapium sebiferum</i>	Council Verge – Wycombe Road	\$5,000
<i>Sapium sebiferum</i>	Council Verge, southern boundary of 58a Wycombe Road	\$5,000
<i>Pyrus sp.</i>	Council Verge outside 56 Wycombe Road	\$1,500

(Reason: Protection of existing environment public infrastructure, community assets and significant trees)

Tree Protection Measures to be shown on Construction Drawings

C23. The tree protection measures contained in the arborist report prepared by *Guy Paroissien, Landscape Matrix Pty Ltd* dated *16 September 2019* and received by Council on *11 October 2019* and the addendum report dated *4 August 2020* received by Council on *7 August 2020* shall be shown clearly on the Construction Certificate drawings. Plans and specifications showing the said tree protection measures must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure the construction plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure that appropriate tree protection measures are shown

on construction drawings)

Protection of Trees

C24. The following tree(s) are required to be protected and retained as part of the development consent in accordance with AS 4970-2009 – Protection of trees on development sites:

Tree	Location	Height
2 <i>Callistemon citrinus</i>	Council Verge – Aubin St	2.2
3 <i>Sapium sebiferum</i>	Council verge – Wycombe Rd	4
4 <i>Sapium sebiferum</i>	Council verge – Wycombe Rd	3.5
5 <i>Sapium sebiferum</i>	Council verge – Wycombe Rd	4
6 <i>Sapium sebiferum</i>	Council verge – Wycombe Rd	5
7 <i>Sapium sebiferum</i>	Council verge – Wycombe Rd	4
8 <i>Sapium sebiferum</i>	Council verge – Wycombe Rd	4
<i>Sapium sebiferum</i>	Council verge, southern boundary of 58a Wycombe Rd	3
<i>Pyrus</i> sp.	Council verge outside 56 Wycombe Rd	2.5
10 <i>Ulmus parviflora</i>	Within front setback-54 Wycombe Rd	11
15 <i>Jacaranda mimosifolia</i>	Within front setback-56 Wycombe Rd	9
16 <i>Platanus x hybrida</i>	Within front setback-56 Wycombe Rd	19
21 <i>Callistemon viminalis</i>	Within rear setback-56 Wycombe Rd	5
22 <i>Eucalyptus scoparia</i>	Within rear setback-56 Wycombe Rd	20
26 <i>Platanus x hybrida</i>	Within front setback-58 Wycombe Rd	16
30 <i>Celtis sinensis</i>	Within front setback-58 Wycombe Rd	9

Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

Any tree(s) shown as being retained on the approved plans (regardless of whether they are listed in the above schedule or not) must be protected and retained in accordance with this condition.

(Reason: Protection of existing environmental and community assets)

Approval for removal of Trees

C25. The following tree(s) are approved for removal in accordance with the development consent:

Trees that are acceptable to	Location	Reason
-------------------------------------	-----------------	---------------

remove		
1 <i>Callistemon viminalis</i>	Council Verge – Aubin St	Facilitate proposal
9 <i>Schinus areira</i>	Within front setback-54 Wycombe Rd	Facilitate proposal
11 <i>Acer palmatum</i>	Within rear setback-54 Wycombe Rd	Facilitate proposal
12 <i>Lagerstroemia indica</i>	Within rear setback-54 Wycombe Rd	Facilitate proposal
13 <i>Lagerstroemia indica</i>	Within rear setback-54 Wycombe Rd	Facilitate proposal
14 <i>Michellia figo</i>	Within rear setback-54 Wycombe Rd	Facilitate proposal
17 <i>Camellia sasanqua</i>	Within rear setback-56 Wycombe Rd	Facilitate proposal
18 <i>Unidentified small tree</i>	Within rear setback-56 Wycombe Rd	Facilitate proposal
19 <i>Callistemon citrinus</i>	Within rear setback-56 Wycombe Rd	Facilitate proposal
20 <i>Callistemon viminalis</i>	Within rear setback-56 Wycombe Rd	Facilitate proposal
23 <i>Magnolia grandiflora</i>	Within rear setback-56 Wycombe Rd	Facilitate proposal
24 <i>Ficus microcarpa 'Hilli'</i>	Within rear setback-56 Wycombe Rd	Facilitate proposal
25 <i>Syagrus romanzoffiana</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
27 <i>Platanus x hybrida</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
28 <i>Archontophoenix alexandrae</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
29 <i>Pittosporum undulatum</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
31 <i>Syagrus romanzoffiana</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
32 <i>Syagrus romanzoffiana</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
33 <i>Olea europaea subsp. cuspidata</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
34 <i>Celtis sinensis</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
35 <i>Syagrus romanzoffiana</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
36 <i>Archontophoenix alexandrae</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
37 <i>Celtis sinensis</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
38 <i>Strelitzia nicolai</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
39 <i>Syagrus romanzoffiana</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
40 <i>Archontophoenix alexandrae</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
41 <i>Eucalyptus sideroxylon</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
42 <i>Jacaranda mimosifolia</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
43 <i>Archontophoenix alexandrae</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
44 <i>Archontophoenix alexandrae</i>) x 3	Within front setback-58 Wycombe Rd	Facilitate proposal
45 <i>Syagrus romanzoffiana</i>	Within front setback-58 Wycombe Rd	Facilitate proposal

Removal of any other tree on the site is not approved, excluding species exempt under Council's Tree Preservation Order.

Any tree(s) shown as being retained on the approved plans (regardless of whether they are listed in the above schedule or not) must be protected and retained in accordance with this condition.

(Reason: Protection of existing environmental and community assets)

Pruning of Trees

C26. Any pruning works shall be undertaken under the guidance of an appropriately qualified arborist/tree surgeon in accordance with Australian Standard AS 4373-2007 - Pruning of Amenity Trees:

A report detailing the measures to be employed during construction shall be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

All measures required by the said report must be complied with at all times in the carrying out of the development.

(Reason: To ensure the protection and longevity of existing significant trees)

Amendments to the Landscape Plan

C27. The landscape plan must be amended, as follows to provide an appropriate landscaped setting:

- 2 x *Callistemon viminalis* (100l) shall be conditioned to be planted along the Aubin Street frontage of 54 Wycombe Road
- Plant species, number and pot sizes shall be shown on all drawings
- The areas of lawn depicted for the narrow garden between 58 and 58a Wycombe Road are not considered likely to be a viable solution in this location, and a more suitable shade tolerant planting option shall be used in this location
- The stormwater and drainage plan, and location of OSD shall be redesigned such that they do not impact the TPZ of any of trees nominated for protection and retention

An amended landscape plan complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the amended landscape plan and other plans and specifications submitted fully satisfy the requirements of this condition.

(Reason: To ensure residential amenity)

Cleanliness and Maintenance of Food Preparation Areas

C28. To ensure that adequate provision is made for the cleanliness and maintenance of all food preparation areas, all building work in connection with the occupation or use of the premises for the preparation and storage of food shall be designed and carried out in accordance with the requirements of: -

- a) the Food Act 2003;
- b) the Food Regulation;
- c) the relevant Australian Standards;
- d) Council's Food Premises Code;
- e) Sydney Water Corporation - Trade Waste Section;
- f) the Protection of the Environment Operations Act and associated Regulations; and
- g) the Building Code of Australia.

Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of the relevant Construction Certificate.

The Construction Certificate plans and documentation must incorporate details of the following: -

- a) construction, materials and finishes;
- b) installation of fixtures, fittings and equipment;
- c) washing facilities, other facilities and special requirements;
- d) mechanical ventilation and exhaust discharges; and
- e) temperature control

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure compliance with acceptable standards for the construction of food premises established under environmental health and safety legislation)

Garbage and Recycling Facilities

C29. Adequate provision must be made for the storage of waste and recyclable material generated by the premises. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the relevant Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the provision of appropriate waste facilities and to ensure efficient collection of waste by collection contractors)

Asbestos Material Survey

C30. A report must be prepared by a suitably qualified person in relation to the existing building fabric to be demolished and/or disturbed identifying the presence or otherwise of asbestos contamination and, if asbestos contamination is present, making recommendations as to the work required to safely address the contamination.

Any demolition works or other works identified in the report as having to be carried out must be carried out in accordance with the recommendations of the report and the following:

- a) the removal of asbestos must be undertaken by a WorkCover licensed contractor;

- b) all removal must be in strict accordance with the requirements of the WorkCover Authority in relation to the removal, handling and disposal of material containing asbestos and any Work Safe Australia requirements.
- c) during the removal of any asbestos a sign stating "DANGER ASBESTOS REMOVAL IN PROGRESS" must be erected in a visible position at the boundary of the site; and
- d) Waste disposal receipts must be provided to the Certifying Authority as proof of correct disposal of asbestos laden waste.

The report must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the report, and other plans, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the long term health of workers on site and occupants of the building is not put at risk unnecessarily)

Noise from Plant and Equipment

C31. The use of all plant and equipment installed on the premises must not:

- (a) Contribute an LAeq(15min) which will cause the total LAeq(15min) from all plant and equipment operating contemporaneously on the site or in the strata scheme or in the mixed strata schemes to exceed the RBL by more than 5dB when measured at the boundary of any affected receiver. The modifying factor adjustments in Section 4 of the EPA Industrial Noise Policy shall be applied.
- (b) Cause "offensive noise" as defined in the *Protection of the Environment Operations Act 1997*.

"affected receiver" includes residential premises (including any lot in the strata scheme or another strata scheme), premises for short-term accommodation, schools, hospitals, places of worship, commercial premises and parks and such other affected receiver as may be notified by the Council in writing.

"boundary" includes any window or elevated window of an affected receiver.

Terms in this condition have the same meaning as in the Noise Guide for Local Government and the Industrial Noise Policy published by the NSW Environment Protection Authority.

(Reason: To maintain an appropriate level of amenity for adjoining land uses)

Vibration from Plant and Equipment

- C32. The use of all plant and equipment to be installed on the premises must comply with the vibration limits specified in “Assessing Vibration: a technical guideline” issued by the NSW Environment Protection Authority, at the boundary of any affected receiver.

A certificate from an appropriately qualified acoustical consultant eligible for membership of the Association of Australian Acoustic Consultants must be submitted to the Certifying Authority, certifying that all plant and equipment on the site, together with the proposed plant and equipment, operating contemporaneously will comply with the requirements of this condition.

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

“affected receiver” includes residential premises (including any lot in the strata scheme or another strata scheme), premises for short-term accommodation, schools, hospitals, places of worship and commercial premises and such other affected receiver as may be notified by the Council in writing.

“boundary” includes any window or elevated window of an affected residence.

“contemporaneously” means *existing at or occurring in the same period of time* (Macquarie Dictionary 3rd rev. ed. 2004).

(Reason: To maintain an appropriate level of amenity for adjoining land uses)

Compliance with Acoustic Report

- C33. The recommendations contained in the acoustic report prepared by *Marshall Day Acoustics* dated *10 September 2019*, must be implemented during construction and use of the development.

A statement from an appropriately qualified acoustical consultant eligible for membership of the Association of Australian Acoustic Consultants, certifying that the acoustic mitigation measures outlined in Section 5 of the above stated report have been suitably incorporated into the development and that relevant noise criteria have been satisfied, must be submitted to the Certifying Authority for approval prior to the issue of the relevant Construction Certificate.

The Principal Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To maintain an appropriate level of amenity for adjoining land

uses)

Provision of Accessible Paths of Travel

C34. Access to and throughout the buildings must be designed and constructed to provide access and facilities in accordance with the Building Code of Australia and Disability (Access to Premises – Buildings) Standards 2010. Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of the relevant Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

Notes:

1. If, in complying with this condition, amendments to the development are required, the design changes must be submitted for the approval of Council prior to a Construction Certificate being issued. Approval of a modification application may be required.
2. It is not within Council's power to set aside National legislation which requires the upgrade of buildings to meet modern access standards. Such decisions remain the jurisdiction of the Building Professionals Board Access Advisory Committee who may grant an exemption in certain exceptional circumstances.
3. Information on making an application for an "unjustifiable hardship exemption" under the accessibility standards can be found in the website of the NSW Building Professional Boards at <http://www.bpb.nsw.gov.au/page/premises-standards>

(Reason: To ensure the provision of equitable and dignified access for all people in accordance with disability discrimination legislation and relevant Australian Standards)

Electricity and Other Services

C35. **Proximity to Existing Network Assets –**

Overhead Powerlines

There are existing overhead electricity network assets in Aubin St and Wycombe Rd.

Safework NSW Document– Work Near Overhead Powerlines:

Code of Practice, outlines the minimum safety separation requirements between these mains/poles to structures within the development throughout the construction process. It is a statutory requirement that these distances be maintained throughout construction. Special consideration should be given to

the positioning and operating of cranes and the location of any scaffolding.

The “as constructed” minimum clearances to the mains should also be considered. These distances are outlined in the Ausgrid Network Standard, NS 220 Overhead Design Manual. This document can be sourced from Ausgrid’s website, www.ausgrid.com.au

Should the existing overhead mains require relocating due to the minimum safety clearances being compromised in either of the above scenarios, this relocation work is generally at the developers cost.

It is also the responsibility of the developer to ensure that the existing overhead mains have sufficient clearance from all types of vehicles that are expected be entering and leaving the site.

Underground Cables

There are existing underground electricity network assets in Aubin St and Wycombe Rd. Special care should also be taken to ensure that driveways and any other construction activities within the footpath area do not interfere with the existing cables in the footpath. Ausgrid cannot guarantee the depth of cables due to possible changes in ground levels from previous activities after the cables were installed. Hence it is recommended that the developer locate and record the depth of all known underground services prior to any excavation in the area.

Should ground anchors be required in the vicinity of the underground cables, the anchors must not be installed within 300mm of any cable, and the anchors must not pass over the top of any cable.

Safework Australia – Excavation Code of Practice, and Ausgrid’s Network Standard NS156 outlines the minimum requirements for working around Ausgrid’s underground cables.

(Reason: Concurrence requirements of relevant authority)

Privacy

C36. The following privacy devices are to be provided:

- a) Fixed louvre privacy screens shall be attached to the windows or balconies on the west elevation that are within 12m of any windows in the east elevation of No. 66 Aubin Street or within 6m of the western boundary (except where the top of the window is below the level of the boundary fence), to prevent direct viewing to the west.

Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and

specifications submitted, referenced on and accompanying the relevant Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure an adequate level of privacy is provided to adjoining properties)

Screen Planting

- C37. The existing bamboo at the rear of No 58 Wycombe Road is to be retained to a height that would prevent overlooking from any windows or accessible areas at the top level of the building into Nos 9 & 11 Thrupp Street.

Plan and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To preserve the privacy of adjoining properties)

Security Deposit/ Guarantee Schedule

- C38. All fees and security deposits/ guarantees in accordance with the schedule below must be provided to Council prior to the issue of any Construction Certificate:

Security deposit/ guarantee	Amount (\$)
Tree Bond	\$38,000.00
Infrastructure Damage Bond	\$55,000.00
Engineering Construction Bond	\$68,000.00
TOTAL BONDS	\$161,000.00

The security required by the above schedule must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

(Reason: Compliance with the development consent)

Noise Management Plan – Construction Sites

- C39. A noise management plan prepared by an appropriately qualified acoustical consultant eligible for membership of the Association of Australian Acoustic Consultants must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The plan must include, but not be limited to, the following:

- (a) Identification of noise affected receivers near to the site.
- (b) A prediction as to the level of noise impact at noise affected receivers from the use and proposed number of high noise intrusive appliances intended to be operated onsite.
- (c) Details of work schedules for all construction phases;
- (d) A statement should also be submitted outlining whether or not predicted noise levels will comply with the noise criteria stated within the Environment Protection Authority's Interim Construction Noise Guideline ("ICNG").
- (e) Representative background noise levels should be submitted in accordance with the ICNG.
- (f) Confirmation of the level of community consultation that is to be undertaken by occupants at noise affected receivers likely to be most affected by site works and the operation of plant/machinery particularly during the demolition and excavation phases.
- (g) Confirmation of noise monitoring methodology that is to be undertaken during the noise intensive stages of work including details of monitoring to be undertaken at the boundary of any noise affected receiver.
- (h) What course of action will be undertaken following receipt of a complaint concerning offensive noise.
- (i) Details of any noise mitigation measures that have been outlined by an acoustic consultant or otherwise that will be deployed on site to reduce noise impacts on the occupants at noise affected receivers.
- (j) Details of selection criteria for any plant or equipment that is to be used on site, the level of sound mitigation measures to be undertaken in each case and the criteria adopted in their selection taking into account the likely noise impacts on occupants at noise affected receivers and other less intrusive technologies available; and
- (k) Details of site induction to be carried out for all employees and contractors undertaking work at the site.

"affected receiver" includes residential premises (including any lot in the strata scheme or another strata scheme), premises for short-term accommodation, schools, hospitals, places of worship, commercial premises and parks and such other affected receiver as may be notified by the Council in writing.

"boundary" includes any window or elevated window of an affected residence.

The Construction Noise Management Plan and must be submitted to the

Principle Certifying Authority and a copy provided to Council prior to the issue of the Construction Certificate.

(Reason: To ensure noise generating activities are appropriately managed and nearby sensitive receivers protected)

Remediation

C40. A detailed site investigation is to be undertaken in accordance with the Douglas Partners Report on Preliminary Site (Contamination) Investigation dated March 2019 and a Remedial Action Plan prepared to address any contamination on the site.

The site must be remediated in accordance with:

- (a) an approved Remedial Action Plan; and
- (b) North Sydney Development Control Plan 2013 – Section 14 – Contamination and Hazardous Building Materials; and
- (c) state Environmental Planning Policy No. 55 – Remediation of Land; and,
- (d) the guidelines in force under the Contaminated Land Management Act.

Within thirty (30) days after the completion of the remediation works, a notice of completion, including validation and/or monitoring report is to be provided to Council. This notice must be consistent with State Environmental Planning Policy No. 55 – Remediation of Land.

(Reason: To ensure the land is suitable for its intended purpose)

Telecommunication Infrastructure provision

C41. Prior to the issue of the Subdivision or Construction Certificate in connection with a development, the developer (whether or not a constitutional corporation) is to provide evidence satisfactory to the Certifying Authority that arrangements have been made for;

- (i) the installation of fibre-ready facilities to all individual lots and/or premises in a real estate development project so as to enable fibre to be readily connected to any premises that is being or may be constructed on those lots. Demonstrate that the carrier has confirmed in writing that they are satisfied that the fibre ready facilities are fit for purpose, and
- (ii) the provision of fixed-line telecommunications infrastructure in the fibre-ready facilities to all individual lots and/or premises in a real estate development project demonstrated through an agreement with a carrier.

All such facilities shall be underground if within or visible from a current or future public place.

(Note: Real estate development project has the meanings given in section 372Q of the Telecommunications Act 1997 Cth).

(Reason: To ensure that modern telecommunications infrastructure is provided in respect of all premises to be constructed in developments)

Upgrade of existing building – Fire Spread and Safe Egress

C42. Pursuant to Clause 94 of the EP&A Regulation 2000, aspects of the existing building must be brought into conformity with the Building Code of Australia (BCA).

Work must be carried out as part of the development so as to upgrade the buildings at 56 & 58A Wycombe Road, Neutral Bay in accordance with the BCA Upgrade Assessment Reports Revision 0 and Revision 1 both dated 4 August 2020 prepared by Blackett Macguire & Goldsmith.

Plans and specifications showing the upgrading works **which must be carried out under** this condition must be submitted to the Certifying Authority for approval prior to the issue of the relevant Construction Certificate.

Notes:

1. The Certifying Authority must be satisfied that the plans and specifications submitted prior to the issue of any Construction Certificate comply with the requirements of this condition.
2. The Certifying Authority issuing the Construction Certificate has no power to remove the requirements to upgrade the existing building as required by this condition.
3. Where this condition specifies compliance with the performance requirements of the BCA, the Certifying Authority, subject to their level of accreditation, may be satisfied as to such matters.

(Reason: Application of Regulations relating to Fire and Life Safety)

Salvage and Reuse of Original Fabric (54, 56 and 58 Wycombe Road)

C43. All original decorative fabric approved to be removed under this consent including but not limited to fireplaces, mantle pieces, staircases, lead lights and joinery is to be salvaged for reuse on the subject site or for resale.

Written concurrence confirming compliance with this condition is to be provided by the consultant heritage architect to the certifying authority prior to

the issue of the relevant construction certificates.

(Reason: To conserve significant heritage fabric)

D. Prior to the Commencement of any Works (and continuing where indicated)

Photographic Survey (Heritage Items)

- D1. Prior to any works commencing a photographic survey recording, in accordance with the NSW Heritage Office Guidelines "Photographic recording of Heritage Items using file or digital capture", is to be prepared to the satisfaction of Council's Historian and Conservation Planner. Two electronic copies on a USB device of the photographic survey must be provided to Council.

The Photographic Survey is to include:

- The interior and exterior of the Heritage Item at 56 Wycombe Road, Neutral Bay; and
- The exterior of the neutral items at 54 and 58 Wycombe Road, Neutral Bay.

(Reason: To provide a historical record of heritage significant fabric on site for archival purposes)

Protection of Trees

- D2. All trees that are specifically nominated to be retained by notation on plans or by condition as a requirement of this consent must be maintained and protected during demolition, excavation and construction on the site in accordance with AS4970-2009 (Protection of trees on development sites). A report containing recommendations, and methods of tree protection prepared by an appropriately qualified person must be provided to the Certifying Authority for approval by an appropriately qualified person prior to commencement of any works on the site. Any recommendations must be undertaken for the duration of works on the site.

(Reason: To ensure compliance with the requirement to retain significant planting on the site)

Tree Protection

- D3. The tree protection measures detailed in the approved Tree Protection and Management Plan, and as directed by the project arboriculturist shall be established before work commences.

(Reason: To ensure that the stability and ongoing viability of trees being retained are not compromised by tree protection measures)

Project Arborist Engaged

- D4.
- The project arboriculturist shall inspect tree protection measures and certify in writing to the Principal Certifying Authority the measures comply with the approved Tree Protection Plan and as directed by the project arboriculturist before work commences.
 - The project arboriculturist shall provide guidance and oversight of tree protection and management to ensure that the stability and ongoing viability of trees being retained is not compromised.
 - The project arboriculturist must contact the tree pruning contractor and Council's Tree Management Officer (giving at least 2 working days' notice) to arrange a joint site meeting, prior to commencing any pruning, to determine the exact location and extent of pruning that is permissible, with the tree pruning contractor to comply with any instructions issued by Council, acting reasonably.
 - Any pruning must be undertaken by a practicing arborist with a minimum Australian Qualification Framework Level 3 in arboriculture, in accordance with the principles of the Australian Standard AS 4373-2007 'Pruning of Amenity Trees,' and the NSW Work Cover Code of Practice for the Amenity Tree Industry (1998), as well as any instructions issued on site by Council, acting reasonably.
 - The practicing arborist must keep a log of dates and times of when they attended the site, the type of works that were performed, and must form part of the certification required prior to Occupation.

(Reason: To ensure that trees to be retained are professionally monitored throughout the development)

Protection of Public Trees

- D5. The following tree(s) are required to be protected and retained as part of the development consent in accordance with AS 4970-2009 – Protection of trees on development sites:

Tree	Location
2 <i>Callistemon citrinus</i>	Council verge – Aubin Street
3 <i>Sapium sebiferum</i>	Council verge – Wycombe Road
4 <i>Sapium sebiferum</i>	Council verge – Wycombe Road
5 <i>Sapium sebiferum</i>	Council verge – Wycombe Road

<i>6 Sapium sebiferum</i>	Council verge – Wycombe Road
<i>7 Sapium sebiferum</i>	Council verge – Wycombe Road
<i>8 Sapium sebiferum</i>	Council verge – Wycombe Road
<i>Sapium sebiferum</i>	Council verge, southern boundary of 58a Wycombe Road
<i>Pyrus sp.</i>	Council verge outside 56 Wycombe Road

All street trees contained in the table above shall be protected with 1.8m high steel mesh tree protection fencing.

Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: Protection of existing environmental and community assets)

Temporary Fences and Tree Protection

- D6. All protected trees on-site that are specifically nominated as per Condition C24 to be retained by notation on plans or by condition as a requirement of this consent must be tagged with luminous tape or the like for purposes of identification prior to demolition, excavation or construction works and must remain so for the duration of works on the site. No materials or builder's waste are to be stored in the vicinity of the nominated tree/trees at any time.

Appropriate fencing or barricades in accordance with AS4970-2009 (Protection of trees on development sites), not less than the distance shown in the schedule hereunder, must be installed to the satisfaction of the Certifying Authority prior to demolition or commencement of any works and must be maintained for the duration of the works: -

(Reason: To protect the trees to be retained on the site during construction works)

Public Liability Insurance – Works on Public Land

- D7. Any person or contractor undertaking works on public land must take out Public Risk Insurance with a minimum cover of \$20 million in relation to the occupation of public land and the undertaking of approved works within Council's road reserve or public land, as approved by this consent. The Policy is to note, and provide protection/full indemnification for North Sydney Council, as an interested party. A copy of the Policy must be submitted to

Council prior to commencement of any works. The Policy must be valid for the entire period that the works are being undertaken.

(Note: Applications for hoarding permits, vehicular crossings etc will require evidence of insurance upon lodgement of the application.)

(Reason: To ensure the community is protected from the cost of any claim for damages arising from works on public land)

Notification of New Addresses

- D8. Prior to the commencement of any building works, an application must be made and written confirmation received from North Sydney Council of the allocated street address (house number) and/ or unit numbers of the completed project.

To assist Council, a plan for unit numbering should be submitted for concurrence. These details will be recorded in Council records and must be displayed at the property in accordance with the provisions of the applicable Australian Standard relating to rural and urban addressing. A copy of the allocation confirmation must be submitted to the Certifying Authority with the application for a Construction Certificate.

(Reason: To ensure that Council records are accurate, and that house numbering complies with the requirements of Council's House Numbering Policy. Proper house numbering also assists emergency services in readily locating properties)

Sydney Water Approvals

- D9. Prior to the commencement of any works, the approved plans must be submitted to Sydney Water to determine whether the development application will affect Sydney Water's sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. The Certifying Authority must ensure that Sydney Water has appropriately stamped the plans before the commencement of building works.

Notes:

- **Sydney Water Building Plan Approvals** can be obtained from the Sydney Water Tap in™ online service. Building plans must be submitted to the Tap in™ to determine whether the development will affect any Sydney Water sewer or water main, stormwater drains and/or easement, and if further requirements need to be met. For further information visit <http://www.sydneywater.com.au/tapin/index.htm> or call 13 000 TAP IN (1300 082 746) for further information.

(Reason: To ensure compliance with Sydney Water requirements)

Commencement of Works Notice

- D10. Building work, demolition or excavation in accordance with this development consent must not be commenced until the developer has given at least 2 days notice to North Sydney Council of the person's intention to commence building work, demolition or excavation in accordance with this development consent.

(Reason: To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

E. During Demolition and Building Work

Cigarette Butt Receptacle

- E1. A cigarette butt receptacle is to be provided on the site for the duration of excavation/demolition/construction process, for convenient use of site workers.

(Reason: To ensure adequate provision is made for builders' waste)

Re-use of Sandstone

- E2. Sandstone blocks (if any) removed from the site are to be either stored for re-use on site or offered to Council in the first instance.

Note: The provisions of the Heritage Act may also apply to altering any sandstone elements on any site)

(Reason: To allow for preservation of cultural resources within the North Sydney Council area)

Structures Clear of Drainage Easements

- E3. It is the full responsibility of the Developer and their contractors to: -
- a) Ascertain the exact location of the Council drainage infrastructure traversing the site in the vicinity of the works;
 - b) Take full measures to protect the in-ground Council drainage system; and
 - c) Ensure dedicated overland flow paths are satisfactorily maintained through the site.

Drainage pipes can be damaged through applying excessive loading (such as

construction plant, material storage and the like). All proposed structures and construction activities are to be located clear of Council drainage pipes, drainage easements, watercourses and trunk overland flow paths on the site. Trunk or dedicated overland flow paths must not be impeded or diverted by fill or structures unless otherwise approved.

In the event of a Council drainage pipeline being uncovered during construction, all work is to cease and the Certifying Authority and Council (if it is not the Certifying Authority) must be contacted immediately for advice. Any damage caused to a Council drainage system must be immediately repaired in full as directed, and at no cost to Council.

(Reason: Protection of Public Drainage Assets)

Parking Restrictions

- E4. Existing public parking provisions in the vicinity of the site must be maintained at all times during works. The placement of any barriers, traffic cones, obstructions or other device in the road shoulder or kerbside lane is prohibited without the prior written consent of Council. Changes to existing public parking facilities/restrictions must be approved by the North Sydney Local Traffic Committee. The Developer will be held responsible for any breaches of this condition, and will incur any fines associated with enforcement by Council regulatory officers.

(Reason: To ensure that existing kerb-side parking provisions are not compromised during works)

Road Reserve Safety

- E5. All public footways and roadways fronting and adjacent to the site must be maintained in a safe condition at all times during the course of the development works, with no obstructions caused to the said footways and roadways. Construction materials and plant must not be stored in the road reserve without approval of Council. A safe pedestrian circulation route and a pavement/route free of trip hazards must be maintained at all times on or adjacent to any public access ways fronting the construction site.

Where public infrastructure is damaged, repair works must be carried out in when and as directed by Council officers (at full Developer cost). Where pedestrian circulation is diverted on to the roadway or verge areas, clear directional signage and protective barricades must be installed in accordance with AS1742-3 (1996) "Traffic Control Devices for Work on Roads". **If pedestrian circulation is not satisfactorily maintained across the site frontage, and action is not taken promptly to rectify the defects, Council may undertake proceedings to stop work.**

(Reason: Public Safety)

Service Adjustments

- E6. Where required, the adjustment or inclusion of any new utility service facilities must be carried out by the person acting on the consent and in accordance with the requirements of the relevant utility authority. These works shall be at no cost to Council. It is the Applicants full responsibility to make contact with the relevant utility authorities to ascertain the impacts of the proposal upon utility services at the appropriate stage of the development (including water, phone, gas and the like). Council accepts no responsibility whatsoever for any matter arising from its approval of this application involving any influence upon utility services provided by another authority.

(Reason: To ensure the service requirements are met)

Temporary Disposal of Stormwater Runoff

- E7. During construction, stormwater runoff must be disposed in a controlled manner that is compatible with the erosion and sediment controls on the site. Immediately upon completion of any impervious areas on the site (including roofs, driveways, paving) and where the final drainage system is incomplete, the necessary temporary drainage systems must be installed to reasonably manage and control runoff as far as the approved point of stormwater discharge. Such ongoing measures must be to the satisfaction of the Certifying Authority.

(Reason: Stormwater control during construction)

Geotechnical Stability during Works

- E8. A contractor with specialist excavation experience must undertake the excavations for the development and a suitably qualified and consulting geotechnical engineer must oversee the excavation procedure.

Geotechnical aspects of the development work, namely appropriate excavation method and vibration control, support and retention of excavated faces, and hydro geological considerations must be undertaken in accordance with the recommendations of the Geotechnical Engineer and all subsequent geotechnical inspections carried out during the excavation and construction phase.

Approval must be obtained from all affected property owners, including North Sydney Council where rock anchors (both temporary and permanent) are proposed below adjacent private or public property.

(Reason: Ensure appropriate professional are engaged at appropriate stages during construction)

Council Inspection of Public Infrastructure Works

E9. During the works on public infrastructure reverting to Council's care and control, Council's Development Engineer must undertake inspections of the works at the following hold points: -

- a) Vehicular access; and associated road civil works.
- b) Stormwater connection.

All works must proceed in accordance with Roads Act 1993 approvals or other permits relating to roads issued by Council. A minimum of 48 hours notice must be given to Council to book an inspection. Work must not proceed until the works or activity covered by the inspection is approved.

(Reason: To ensure quality of construction joints and connections in the drainage system)

Progress Survey

E10. In order to ensure compliance with approved plans, a Survey Certificate, prepared to Australian Height Datum, must be prepared by a Registered Surveyor showing the following: -

- a) at the completion of excavation, prior to the placement of any footings, showing the completed level of the excavation and its relationship to the boundaries;
- b) prior to placement of concrete at the ground floor level, showing the level of the form work and its relationship to boundaries including relevant footpath and roadway levels;
- c) prior to roofing, or completion of the highest point of the building showing the anticipated level of the completed work and its relationship to the boundary; and
- d) at completion, works showing the relationship of the building to the boundary and showing the maximum height of the overall works and the height of the principal roof elements.

Progress certifications in response to points (a) through to (e) must be provided to the Certifying Authority for approval at the time of carrying out relevant progress inspections. In the event that such survey information is not provided or reveals discrepancies between the approved plans and the proposed works, all works, save for works necessary to bring the development into compliance with the approved plans, must cease. Works may only continue upon notification by the Certifying Authority to the Applicant that survey information (included updated survey information following the carrying out of works to comply with the approved plans) complies with this condition.

(Reason: To ensure compliance with approved plans)

Developer's Cost of Work on Council Property

- E11. The developer must bear the cost of all works associated with the development that occurs on Council's property, including the restoration of damaged areas.

(Reason: To ensure the proper management of public land and funds)

Prohibition on Use of Pavements

- E12. Building materials must not be placed on Council's footpaths, roadways, parks or grass verges, (unless a permit is obtained from Council beforehand). A suitable sign to this effect must be erected adjacent to the street alignment.

(Reason: To ensure public safety and amenity on public land)

Removal of Extra Fabric

- E13. Should any portion of the existing building, trees, or curtilage of the site which is indicated on the approved plans to be retained be damaged for whatever reason, all the works in the area of the damaged portion are to cease and written notification of the damage is to be given to Council forthwith. No work is to resume until the written approval of Council to do so is obtained. Failure to comply with the provisions of this condition may result in the Council taking further action including legal proceedings if necessary.

(Reason: To ensure compliance with the terms of this development consent)

Dust Emission and Air Quality

- E14. The following must be complied with at all times:

- (a) Materials must not be burnt on the site.
- (b) Vehicles entering and leaving the site with soil or fill material must be covered.
- (c) Dust suppression measures must be carried out to minimise wind-borne emissions in accordance with the NSW Department of Housing's 1998 guidelines - Managing Urban Stormwater: Soils and Construction.
- (d) Odour suppression measures must also be carried out where appropriate so as to prevent nuisance occurring at adjoining properties.

(Reason: To ensure residential amenity is maintained in the immediate vicinity)

Compliance with Construction Noise Management Plan

- E15. All works conducted on site which form part of this development must be carried out in accordance with the submitted Construction Noise Management Plan submitted with the Construction Certificate and all conditions of consent.

(Reason: To ensure noise generating activities are appropriately managed and nearby sensitive receivers protected)

No Work on Public Open Space

- E16. No work can be undertaken within adjoining public lands (ie. Parks, Reserves, Roads etc) without the prior written consent of Council. In this regard the developer is to liaise with Council prior to the commencement of any design works or preparation of a Construction and Traffic Management Plan.

(Reason: Protection of existing public infrastructure and land and to ensure public safety and proper management of public land)

No Removal of Trees on Public Property

- E17. No trees on public property (footpaths, roads, reserves, etc.) unless specifically approved by this consent shall be removed or damaged during construction including for the erection of any fences, hoardings or other temporary works.

(Reason: Protection of existing environmental infrastructure and community assets)

Protection of Trees

- E18. All trees required to be retained, as part of this consent must be protected from any damage during construction works in accordance with AS4970-2009. All recommendations contained within the arborist report prepared by *Guy Paroissien, Landscape Matrix Pty Ltd* dated *16 September 2019* and the addendum report received by Council on *11 October 2019* and dated *4 August 2020* received by Council on *7 August 2020* must be implemented for the duration of the works.

In the event that any tree required to be retained is damaged during works on the site, notice of the damage must be given to Council forthwith.

Notes:

- a. If the nominated tree is damaged to a significant degree or removed from the site without prior written approval being obtained from Council, the issuing of fines or legal proceedings may be commenced for failure to comply with the conditions of this consent.

- b. An application to modify this consent pursuant to Section 4.55 of the Environmental Planning and Assessment Act 1979 will be required to address the non-compliance with any of the conditions of consent relating to the retention of nominated trees, and Council may require tree replenishment.

(Reason: Protection of existing environmental infrastructure and community assets)

Trees to be Removed

- E19. All trees on the site must be protected and retained save for those expressly identified below as being approved for removal: -

(Reference No.) Trees that are acceptable to remove	Location	Reason
1 <i>Callistemon viminalis</i>	Council Verge – Aubin St	Facilitate proposal
9 <i>Schinus areira</i>	Within front setback-54 Wycombe Rd	Facilitate proposal
11 <i>Acer palmatum</i>	Within rear setback-54 Wycombe Rd	Facilitate proposal
12 <i>Lagerstroemia indica</i>	Within rear setback-54 Wycombe Rd	Facilitate proposal
13 <i>Lagerstroemia indica</i>	Within rear setback-54 Wycombe Rd	Facilitate proposal
14 <i>Michellia figo</i>	Within rear setback-54 Wycombe Rd	Facilitate proposal
17 <i>Camellia sasanqua</i>	Within rear setback-56 Wycombe Rd	Facilitate proposal
18 <i>Unidentified small tree</i>	Within rear setback-56 Wycombe Rd	Facilitate proposal
19 <i>Callistemon citrinus</i>	Within rear setback-56 Wycombe Rd	Facilitate proposal
20 <i>Callistemon viminalis</i>	Within rear setback-56 Wycombe Rd	Facilitate proposal
23 <i>Magnolia grandiflora</i>	Within rear setback-56 Wycombe Rd	Facilitate proposal
24 <i>Ficus microcarpa 'Hillii'</i>	Within rear setback-56 Wycombe Rd	Facilitate proposal
25 <i>Syagrus romanzoffiana</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
27 <i>Platanus x hybrida</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
28 <i>Archontophoenix alexandrae</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
29 <i>Pittosporum undulatum</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
31 <i>Syagrus romanzoffiana</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
32 <i>Syagrus romanzoffiana</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
33 <i>Olea europaea subsp. cuspidata</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
34 <i>Celtis sinensis</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
35 <i>Syagrus romanzoffiana</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
36 <i>Archontophoenix alexandrae</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
37 <i>Celtis sinensis</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
38 <i>Strelitzia nicolai</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
39 <i>Syagrus romanzoffiana</i>	Within front setback-58 Wycombe Rd	Facilitate proposal

40 <i>Archontophoenix alexandrae</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
41 <i>Eucalyptus sideroxylon</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
42 <i>Jacaranda mimosifolia</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
43 <i>Archontophoenix alexandrae</i>	Within front setback-58 Wycombe Rd	Facilitate proposal
44 <i>Archontophoenix alexandrae</i>) x 3	Within front setback-58 Wycombe Rd	Facilitate proposal
45 <i>Syagrus romanzoffiana</i>	Within front setback-58 Wycombe Rd	Facilitate proposal

(Reason: To ensure compliance with the terms of this development consent)

Benchmarks

E20. All permanent survey markers must be retained, undamaged, and not relocated.

(Reason: Protection of existing environmental infrastructure and community assets)

Special Permits

E21. Unless otherwise specifically approved in writing by Council, all works, processes, storage of materials, loading and unloading associated with the development must occur entirely on the property.

The developer, owner or builder may apply for specific permits available from Council's Customer Service Centre for the undermentioned activities on Council's property. In the event that a permit is granted by Council for the carrying out of works, processes, storage of materials, loading and unloading associated with the development on Council's property, the development must be carried out in accordance with the requirements of the permit. A minimum of forty-eight (48) hours notice is required for any permit: -

1) On-street mobile plant

Eg. cranes, concrete pumps, cherry-pickers, etc. - restrictions apply to the hours of operation, the area of operation, etc. Separate permits are required for each occasion and each piece of equipment. It is the developer's, owner's and builder's responsibilities to take whatever steps are necessary to ensure that the use of any equipment does not violate adjoining property owner's rights.

(Reason: Proper management of public land)

2) Hoardings

Permits are required to erect Class A and Class B hoardings. If an 'A' Class hoarding is to alienate a section of Council's property, that section will require a permit for the occupation of Council's property.

(Reason: Proper management of public land)

3) Storage of building materials and building waste containers (skips) on Council's property

Permits to utilise Council property for the storage of building materials and building waste containers (skips) are required for each location. Failure to obtain the relevant permits will result in the building materials or building waste containers (skips) being impounded by Council with no additional notice being given. Storage of building materials and waste containers on open space reserves and parks is prohibited.

(Reason: Proper management of public land)

4) Kerbside restrictions, construction zones

Attention is drawn to the existing kerbside restrictions adjacent to the development. Should alteration of existing kerbside restrictions be required, or the provision of a construction zone, the appropriate application must be made and the fee paid to Council. Alternatives to such restrictions may require referral to Council's Traffic Committee and may take considerable time to be resolved. An earlier application is suggested to avoid delays in construction programs.

(Reason: Proper management of public land)

Noxious Plants

E22. All lantana, privet, rubber trees, asthma weed, and other declared noxious plants on the site, must be eradicated before the commencement of landscape works.

(Reason: To ensure that plants identified as weed species are not allowed to proliferate or interfere with a quality landscaping outcome)

Construction Hours

E23. Building construction and works must be restricted to within the hours of 7.00 am to 5.00 pm Monday to Friday and on Saturday to within the hours of 8.00 am to 1.00 pm inclusive, with no work on Sundays and Public Holidays.

Demolition and excavation works must be restricted to within the hours of 8.00 am to 5.00 pm Monday to Friday only. For the purposes of this condition:

- a) “Building construction” means any physical activity on the site involved in the erection of a structure, cladding, external finish, formwork, fixture, fitting of service installation and the unloading of plant, machinery, materials or the like.
- b) “Demolition works” means any physical activity to tear down or break up a structure (or part thereof) or surface, or the like, and includes the loading of demolition waste and the unloading of plant or machinery.
- c) “Excavation work” means the use of any excavation machinery and the use of jackhammers, rock breakers, excavators, loaders, or the like, regardless of whether the activities disturb or alter the natural state of the existing ground stratum or are breaking up/removing materials from the site and includes the unloading of plant or machinery associated with excavation work.

All builders, excavators must display, on-site, their twenty-four (24) hour contact telephone number, which is to be clearly visible and legible from any public place adjoining the site.

(Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community)

Out of Hours Work Permits

E24. Where it is necessary for works to occur outside those hours allowed by these conditions, an application may be made to Council's Customer Services Centre for a permit to carry out works outside of the approved hours. If a permit is issued the works approved must be carried out in accordance with any requirements specified in the permit. Permits will only be approved if **public safety is at risk**. Applications which seek a variation to construction hours solely to benefit the developer will require the lodgement and favourable determination of a modification application pursuant to the provisions of Section 96 of the Environmental Planning and Assessment Act 1979.

Notes:

- 1) Failure to obtain a permit for work outside of the approved hours will result in on the spot fines being issued, or Council pursuing any action required (including legal proceedings) to have the out of hours work cease, without prior warning.
- 2) Applications for out of hour's works should be lodged with Council no later than seven (7) calendar days prior to the date of the intended works.
- 3) Examples of activities for which permits may be granted include:
 - the erection of awnings,

- footpath, road and other infrastructure works which can not be carried out for public convenience reasons within normal hours,
 - the erection and removal of hoardings and site cranes, and
 - craneage of materials which cannot be done for public convenience reasons within normal working hours.
- 4) Examples of activities for which permits WILL NOT be granted include;
- extended concrete pours
 - works which are solely to convenience the developer or client, and
 - catch up works required to maintain or catch up with a construction schedule.
- 5) Further information on permits can be obtained from the Council website at www.northsydney.nsw.gov.au.

(Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community)

Installation and Maintenance of Sediment Control

- E25. Erosion and sediment controls must be installed and maintained at all times in accordance with the Sediment and erosion control plan submitted and approved with the Construction Certificate.

Erosion and sediment measures must be maintained in accordance with the publication Managing Urban Stormwater: Soils & Construction (4th edition, Landcom, 2004), commonly referred to as the “Blue Book” and can only be removed when development activities have been completed and the site fully stabilised.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

Sediment and Erosion Control Signage

- E26. A durable sign must be erected during building works in a prominent location on site, warning of penalties should appropriate erosion and sedimentation control devices not be maintained. A sign of the type referred to in this condition is available from Council.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

Remedial Action Plan (Contaminated Land)

- E27. The remediation work must be carried out in accordance with the Remedial Action Plan approved under this consent and all relevant guidelines issued

under the Contaminated Land Management Act.

(Reason: To ensure the proper management of contaminated land)

Site Amenities and Facilities

- E28. Where work involved in the erection and demolition of a building is being carried out, amenities which satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements, must be provided and maintained at all times. The type of work place determines the type of amenities required.

Further information and details can be obtained from the Internet at www.workcover.nsw.gov.au

(Reason: To ensure the health and safety of the community and workers on the site)

Health and Safety

- E29. All work undertaken must satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements to prepare a health and safety plan. Site fencing must be installed sufficient to exclude the public from the site. Safety signs must be erected that warn the public to keep out of the site, and provide a contact telephone number for enquiries.

Further information and details regarding occupational health and safety requirements for construction sites can be obtained from the internet at www.workcover.nsw.gov.au

(Reason: To ensure the health and safety of the community and workers on the site)

Community Information

- E30. Reasonable measures must be undertaken at all times to keep nearby residents informed about the proposed work, such as by way of signs, leaflets, public meetings and telephone contact numbers, to ensure that adjoining residents are aware of the likely duration of the construction works on the site

(Reason: To ensure that residents are kept informed of activities that may affect their amenity)

Archaeological Discovery During Works

- E31. Should any historical or Aboriginal relic be discovered on the site during demolition, excavation or site preparatory works, all excavation or disturbance

to the area is to stop immediately and the Heritage Council of NSW must be informed in accordance with the provisions of the Heritage Act 1977 and/or National Parks and Wildlife Act, 1974. Works must not recommence until such time as approval to recommence is given in writing by Council or a permit from the Director of the NPWS is issued.

(Reason: To prevent the unnecessary destruction or removal of unrecorded historical or Aboriginal relics)

Plant & Equipment Kept Within Site

- E32. All plant and equipment used in the undertaking of the development/ works, including concrete pumps, wagons, lifts, mobile cranes, hoardings etc, must be situated within the boundaries of the site (unless a permit is obtained from Council beforehand) and so placed that all concrete slurry, water, debris and the like must be discharged onto the building site, and is to be contained within the site boundaries.

Details of Council requirements for permits on public land for standing plant, hoardings, storage of materials and construction zones and the like are available on Council's website at www.northsydney.nsw.gov.au.

(Reason: To ensure public safety and amenity on public land)

Imported Fill Material

- E33. The only waste derived fill material that may be received at the development site is: -

- a) Virgin excavated natural material (within the meaning of the Protection of the Environment Operations Act 1997); and
- b) Any other waste-derived material the subject of a resource recovery exemption under cl. 51A of the Protection of the Environment Operations (Waste) Regulation 2005 that is permitted to be used as fill material.

Any waste-derived material the subject of a resource recovery exemption received at the development site, must be accompanied by documentation as the material's compliance with the exemption conditions and must be provided to the Certifying Authority on request.

(Reason: To ensure that imported fill is of an acceptable standard for environmental protection purposes)

Waste Disposal

- E34. All records demonstrating the lawful disposal of waste must be retained and kept readily accessible for inspection by regulatory authorities such as North

Sydney Council and the Environmental Protection Authority.

(Reason: To ensure the lawful disposal of construction and demolition waste)

Asbestos Removal

E35. All demolition works involving the removal and disposal of asbestos cement must only be undertaken by contractors who hold a current WorkCover Asbestos or "Demolition Licence" and a current WorkCover "Class 2 (Restricted) Asbestos Licence and removal must be carried out in accordance with National Occupational Health and Safety Commission.

(Reason: To ensure works are carried out in accordance with relevant WorkCover requirements)

F. Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation

National Construction Code

F1. All building work must be carried out in accordance with the provisions of the National Construction Code.

(Reason: Prescribed - Statutory)

Appointment of a Principal Certifying Authority (PCA)

F2. Building work, demolition or excavation in accordance with the development consent must not be commenced until the developer has appointed a Principal Certifying Authority for the building work in accordance with the provisions of the EP&A Act and its Regulations.

(Reason: Statutory; To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

Construction Certificate

F3. Building work, demolition or excavation in accordance with the development consent must not be commenced until a Construction Certificate for the relevant part of the building work has been issued in accordance with the provisions of the EP&A Act and its Regulations.

(Reason: Statutory; To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

Occupation Certificate

- F4. A person must not commence occupation or use of the whole or any part of a new building (*new building* includes an altered portion of, or an extension to, an existing building) unless an Occupation Certificate has been issued in relation to the building or part. Only the Principal Certifying Authority appointed for the building work can issue an Occupation Certificate.

(Reason: Statutory)

Critical Stage Inspections

- F5. Building work must be inspected by the Principal Certifying Authority on the critical stage occasions prescribed by the EP&A Act and its Regulations, and as directed by the appointed Principal Certifying Authority.

(Reason: Statutory)

Commencement of Works

- F6. Building work, demolition or excavation in accordance with this development consent must not be commenced until the developer has given at least 2 days notice to North Sydney Council of the person's intention to commence the erection of the building.

(Reason: Statutory; To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

Excavation/Demolition

- F7. 1) All excavations and backfilling associated with the erection or demolition of a building must be executed safely and in accordance with appropriate professional standards.
- 2) All excavations associated with the erection or demolition of a building must be properly guarded and protected to prevent them from being dangerous to life or property.
- 3) Demolition work must be undertaken in accordance with the provisions of AS2601- Demolition of Structures.

(Reason: To ensure that work is undertaken in a professional and responsible manner and protect adjoining property and persons from potential damage)

Protection of Public Places

- F8. 1) A hoarding and site fencing must be erected between the work site and adjoining public place.
- 2) If necessary, an awning is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place.
- 3) The work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place.
- 4) Any such hoarding, fence or awning is to be removed when the work has been completed.
- 5) No access across public reserves or parks is permitted.

Note: Prior to the erection of any temporary fence or hoarding over property owned or managed by Council, written approval must be obtained. Any application needs to be accompanied by plans indicating the type of hoarding and its layout. Fees are assessed and will form part of any approval given. These fees must be paid prior to the approval being given. Approval for hoardings will generally only be given in association with approved building works, maintenance or to ensure protection of the public. An application form for a Hoarding Permit can be downloaded from Council's website.

(Reason: To ensure public safety and the proper management of public land)

Site Sign

- F9. 1) A sign must be erected in a prominent position on the site
- a) stating that unauthorised entry to the work site is prohibited;
- b) showing the name of the principal contractor (or person in charge of the work site), and a telephone number at which that person may be contacted at any time for business purposes and outside working hours; and
- c) showing the name, address and telephone number of the Principal Certifying Authority for the work.
- 2) Any such sign must be maintained while building work or demolition work is being carried out, but must be removed when the work has been completed.

(Reason: Prescribed - Statutory)

G. *Prior to the Issue of an Occupation Certificate*

Infrastructure Repair and Completion of Works

G1. Prior to the issue of the relevant Occupation Certificate any and all works relating to the development:

- a. in the road reserve must be fully completed; and
- b. to repair and make good any damaged public infrastructure caused as a result of any works relating to the development (including damage caused by, but not limited to, delivery vehicles, waste collection, contractors, sub contractors, concrete vehicles) must be fully repaired;

to the satisfaction of Council Engineers at no cost to Council.

(Reason: Maintain quality of Public assets)

Line Marking

G2. A certificate prepared by an appropriately qualified and practising Civil Engineer certifying the construction, paving, line marking and signposting of the off-street car-parking spaces, together with access driveways, in accordance with the approved development plans, appropriate Australian Standards and industry best practice as appropriate must be submitted to, and approved by, the Certifying Authority prior to issue of the relevant Occupation Certificate.

(Reason: To ensure ongoing compliance with this development consent and Australian Standards relating to manoeuvring and access of vehicles)

Access to Premises

G3. Prior to the issue of the relevant Occupation Certificate, a certificate must be prepared an appropriately qualified and practising Access Consultant certifying that access and facilities for persons with a disability in accordance with the Building Code of Australia and AS Disability (Access to Premises – buildings) Standards 2010 (Premises Standards) has been provided. This certificate must be submitted to, and approved by, the Certifying Authority prior to issue of the relevant Occupation Certificate.

(Reason: Equitable access and facilities for people with a disability)

Noise Certification

G4. Prior to issue of the relevant Occupation Certificate a certificate from an appropriately qualified acoustical consultant eligible for membership of the Association of Australian Acoustic Consultants is to be submitted to, and

approved by, the Certifying Authority certifying that the noise and vibration from use of the development complies with the conditions of consent here-in.

(Reason: To ensure acoustic amenity)

Certification- Civil Works

- G5. a) An appropriately qualified and practising Civil Engineer must certify to the Certifying Authority that the stormwater drainage system is constructed in accordance with this consent and the provisions of the applicable Australian Standard. A copy of the certificate must be submitted to Council (if it is not the Certifying Authority) upon completion of the development works and prior to the issue of the relevant Occupation Certificate.
- b) An appropriately qualified and practicing Civil Engineer must certify to the Certifying Authority that the vehicular crossing and associated works and road works were constructed in accordance with this consent and any approval for works in the road reserve issued by the Council. A copy of the certificate must be submitted to Council (if it is not the Certifying Authority), upon completion of the development works and prior to the issue of the relevant Occupation Certificate.

(Reason: Compliance with the Consent)

Validation for Remediation

- G6. A validation and site monitoring report prepared in accordance with relevant guidelines issued under the *Contaminated Land Management Act* 1997 must be submitted to the Council within one month of completion of the remediation work, and prior to the issuing of any Occupation Certificate.

(Reason: To ensure environmental amenity is maintained)

Certification for Mechanical Exhaust Ventilation

- G7. Prior to issue of an Occupation Certificate and following the completion, installation, and testing of all the mechanical ventilation systems, a Mechanical Ventilation Certificate of Completion and Performance in accordance with Clause A2.2(a)(iii) of the Building Code of Australia, must be submitted to, and approved by, the Certifying Authority.

(Reason: To ensure compliance with acceptable standards for the construction and operation of mechanical plant)

Damage to Adjoining Properties

- G8. All precautions must be taken to prevent any damage likely to be sustained to adjoining properties. Adjoining owner property rights and the need for

owner's permission must be observed at all times, including the entering onto land for the purpose of undertaking works.

(Reason: To ensure adjoining owner's property rights are protected)

Utility Services

G9. All utility services shall be adjusted, to the correct levels and/or location/s required by this consent, prior to issue of the relevant Occupation Certificate. This shall be at no cost to Council.

(Reason: To ensure compliance with the terms of this consent)

Regulated Systems - Air Handling

G10. To ensure that adequate provision is made for ventilation of the building all mechanical and/or natural ventilation systems shall be designed, constructed installed and tested in accordance with the provisions of:

- 1) The Building Code of Australia;
- 2) The applicable Australian Standards;
- 3) The Public Health Act;
- 4) Public Health Regulation 2012;
- 5) Work Cover Authority;

The regulated system must be certified by an appropriately qualified engineer as compliant with the above provisions and registered with Council prior to commissioning the system and prior to issue of the Occupation Certificate.

(Reason: To ensure public health is maintained; Statutory)

Notification of New Address Developments

G11. Prior to any Occupation Certificate being issued, the person acting upon this consent must comply with the following: -

- (a) Notify Australia Post of the address(es) as issued by Council and the location in plan form of any secondary, internal addresses, in relation to built public roads. Check Australia Post Website (www.auspost.com.au) to find your nearest Australia Post Delivery Facility.

(Reason: To ensure that Council records are accurate, and that house numbering complies with the requirements of Council's House Numbering Policy. Proper house numbering also assists emergency services in readily locating properties)

Asbestos Clearance Certificate

G12. For building works where asbestos based products have been removed or altered, an asbestos clearance certificate signed by an appropriately qualified person (being an Occupational Hygienist or Environmental Consultant) must be submitted to and approved by the Certifying Authority (and a copy forwarded to Council if it is not the Certifying Authority) for the building work prior to the issue of any Occupation Certificate, the asbestos clearance certificate must certify the following: -

- a) the building/ land is free of asbestos; or
- b) the building/ land has asbestos that is presently deemed safe.

The certificate must also be accompanied by tipping receipts, which detail that all asbestos waste has been disposed of at an approved asbestos waste disposal depot. If asbestos is retained on site the certificate must identify the type, location, use, condition and amount of such material.

Note: Further details of licensed asbestos waste disposal facilities can be obtained from www.epa.nsw.gov.au

(Reason: To ensure that building works involving asbestos based products are safe for occupation and will pose no health risks to occupants)

Certification of Tree Condition

G13. Prior to the issue of an Occupation Certificate, a report prepared by an appropriately qualified person (being an arborist or the like) must be submitted to the Certifying Authority, describing the health of the trees specifically nominated below: -

(Reference No.) Tree	Location	Height
<i>Callistemon citrinus</i> (replacement) x 2	Council Verge – Aubin St	100l
2 <i>Callistemon citrinus</i>	Council Verge – Aubin St	2.2
3 <i>Sapium sebiferum</i>	Council verge – Wycombe Rd	4
4 <i>Sapium sebiferum</i>	Council verge – Wycombe Rd	3.5
5 <i>Sapium sebiferum</i>	Council verge – Wycombe Rd	4
6 <i>Sapium sebiferum</i>	Council verge – Wycombe Rd	5
7 <i>Sapium sebiferum</i>	Council verge – Wycombe Rd	4
8 <i>Sapium sebiferum</i>	Council verge – Wycombe Rd	4
<i>Sapium sebiferum</i>	Council verge, southern boundary of 58a Wycombe Rd	3
<i>Pyrus</i> sp.	Council verge outside 56 Wycombe Road	2.5
10 <i>Ulmus parviflora</i>	Within front setback-54 Wycombe Rd	11
15 <i>Jacaranda mimosifolia</i>	Within front setback-56 Wycombe Rd	9
16 <i>Platanus x hybrida</i>	Within front setback-56 Wycombe Rd	19
21 <i>Callistemon viminalis</i>	Within rear setback-56 Wycombe Rd	5
22 <i>Eucalyptus scoparia</i>	Within rear setback-56 Wycombe Rd	20
26 <i>Platanus x hybrida</i>	Within front setback-58 Wycombe Rd	16
30 <i>Celtis sinensis</i>	Within front setback-58 Wycombe Rd	9

The report must detail the condition and health of the nominated trees upon completion of the works and shall certify that the trees have not been significantly damaged during the works on the site and have reasonable prospects for survival.

(Reason: To ensure compliance with the terms of this consent)

Vehicle Egress Signs

- G14. Prior to the issue of an Occupation Certificate, appropriate sign(s) must be provided and maintained within the site at the point(s) of vehicular egress to ensure all vehicles stop before proceeding onto the public way.

(Reason: To ensure pedestrian safety)

Signal System

- G15. Prior to the issue of the relevant Occupation Certificate, a signal system must be installed at the street alignment and within the building to indicate traffic movement on the single lane ramp, and so designed that the signal indication at the point of ingress shall remain green except when an existing vehicle is detected upon the ramp or driveway.

(Reason: To properly manage vehicle entry to, and exit from, the subject site)

Sydney Water

- G16. A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained.

The final Section 73 Certificate must be submitted to the Certifying Authority prior to release of any linen plan for subdivision or prior to occupation of the development, whichever is the earlier.

Notes:

Application must be made through an authorised Water Servicing Co-ordinator, for details see the Sydney Water web site www.sydneywater.com.au/customer/urban/index, or telephone 13 20 92.

Following application, a 'Notice of Requirements' will be forwarded detailing water and sewer extensions to be built and charges to be paid. Please make early contact with the Coordinator since building of water/sewer extensions can be time consuming and may impact on other services and building, driveway or landscape design.

(Reason: To ensure compliance with the statutory requirements of Sydney Water)

Completion of Approved Landscaping

G17. The landscaping shown in the approved landscape plan numbered Landscape Plan prepared by Umbaco Landscape Architects dated February 2020 and received by Council on 4 March 2020, except as amended by condition C27 must be completed prior to the issue of the relevant Occupation Certificate.

(Reason: To ensure compliance with the approved development)

Landscape Maintenance Plan

G18. A Landscape Maintenance Plan is to be submitted to the satisfaction of Council's Landscape Development Officer that ensures the ongoing viability and vigour of plant species, the practicalities of undertaking landscape maintenance are met as well as the retention of the intended aesthetic values of the Landscape Plan, including but not limited to:

- a) Maintenance and usage of irrigation
- b) Mowing schedule
- c) Fertilising schedule
- d) Pruning and trimming schedule
- e) Re-mulching
- f) Replanting schedule
- g) Cleaning of exterior pavements, furniture and lighting
- h) Storage of materials
- i) Disposal of landscape waste
- j) Access of maintenance staff
- k) Use and noise control of power tools

(Reason: To ensure the ongoing maintenance of the approved landscaping.)

Damage to Adjoining Properties

G19. On completion of the development the subject of this consent and prior to the issue of the relevant Occupation Certificate, a report is to be prepared by an appropriately qualified consultant and is to be provided to the Certifying Authority (and a copy to Council if it is not the Certifying Authority) certifying:

- a) whether any damage to adjoining properties has occurred as a result of the development;
- b) the nature and extent of any damage caused to the adjoining property as a result of the development;

- c) the nature and extent of works required to rectify any damage caused to the adjoining property as a result of the proposed development;
- d) the nature and extent of works carried out to rectify any damage caused to the adjoining property as a result of the development; and
- e) the nature and extent of any agreements entered into for rectification of any damage caused to the adjoining property as a result of the development.

The report and certification must reference the dilapidation survey and reports required to be provided to the Certifying Authority in accordance with this consent.

Where works required to rectify any damage caused to adjoining property as a result of the development identified in the report and certification have not been carried out, a satisfactory agreement for rectification of the damage is to be made with the affected person/s as soon as possible prior to the issue of an Occupation Certificate.

All costs incurred in achieving compliance with this condition shall be borne by the developer.

(Reason: To ensure adjoining owner's property rights are protected in so far as possible)

Verification Statement (External Finishes and Materials)

G20. Prior to the issue of the relevant Occupation Certificate, a verification statement from a qualified designer or architect (preferably the original designer), must be submitted to Council and the Certifying Authority certifying that the external finishes and materials are in accordance with the approved schedule of finishes and materials identified in this consent.

"qualified designer" means a person registered as an architect in accordance with the Architects Act 2003 cf 50(1A) EP & A Regs 2000.

(Reason: To ensure the design quality and finishes for residential flat development)

Required Tree Planting

G21. On completion of works and prior to the issue of an Occupation Certificate trees in accordance with the schedule hereunder must be planted in Council's nature strip/footpath: -

Schedule

Tree Species	Location	Pot Size
2 x <i>Callistemon citrinus</i>	Council Verge – Aubin St	100l

The installation of such trees, their current health and their prospects for future survival must be certified upon completion by an appropriately qualified horticulturalist.

Upon completion of installation and prior to the issue of an Occupation Certificate an appropriately qualified horticulturalist must certify that any trees planted in accordance with this condition are healthy and have good prospects of future survival. The certification must be submitted with any application for an Occupation Certificate.

(Reason: To ensure that replacement plantings are provided to enhance community landscaped amenity and cultural assets)

Unpaved Verge

G22. The unpaved verge area must be constructed/reconstructed with an appropriate species of grass prior to completion of the works at no cost to Council

(Reason: To ensure that community assets are presented in accordance with reasonable community expectations)

Intercom

G23. An intercom system must be provided in a convenient location adjacent to the visitor parking entry to enable easier and safe access to visitor parking prior to issue of the relevant Occupation Certificate.

(Reason: To ensure convenient access is available for visitors to the building)

I. On-Going / Operational Conditions

Visiting Hours

I1. Except in exceptional circumstances visiting hours are restricted to 7am-10pm daily.

(Reason: to ensure that amenity of the surrounding locality is maintained)

Trade Waste

I2. Trade wastewater must be disposed of in accordance with the permit requirements of Sydney Water Corporation Ltd, Wastewater Source Control Branch.

(Reason: To ensure compliance with Sydney Water's requirements and protect the environment)

Noise and Vibration Impact

13. The on-going use of the premises approved under this consent must comply with all conditions pertaining to noise and vibration specified in this consent.

(Reason: To ensure compliance with the specified levels of noise and vibration and to maintain the amenity of surrounding land uses)

Visitors Parking Sign

14. A sign, legible from the street, must be permanently displayed to indicate that visitor parking is available on the site and the visitor car parking spaces must be clearly marked as such.

(Reason: To ensure that visitors are aware that parking is available on site and to identify those spaces to visitors)

Use of Car parking Spaces

15. Car parking spaces provided must only be used in conjunction with the approved uses contained within the development. Visitor parking facilities must not at any time be allocated, sold, licensed or leased for the exclusive use of any owner or occupier or third party and must be retained for use by visitors to the Residential Aged Care Facility.

(Reason: To ensure that visitor parking is not allocated to building occupants and remains available on an ongoing basis)

Loading within Site

16. All loading and unloading operations must be carried out wholly within the confines of the site, at all times and must not obstruct other properties or the public way.

(Reason: To ensure that deliveries can occur safely within the site and does not adversely affect traffic or pedestrian amenity)

No Illumination

17. No consent is given or implied for any form of illumination or floodlighting to the building or any sign. A separate development application must be lodged and approved prior to any external floodlighting or illumination of the building, approved sign or site landscaping.

(Reason: To ensure appropriate forms of signage that are consistent with Council's controls and those that are desired for the locality, and do not interfere with amenity of nearby properties)

Waste Collection

18. Waste collection is to be undertaken by a private contractor using vehicles that will allow the approved turning area on site to be used in compliance with the relevant Australian Standards. Waste and recyclable material, generated by this premises, must not be collected between the hours of 7pm and 7am on any day.

(Reason: To ensure the amenity of surrounding properties)

Delivery Hours

19. No deliveries, loading or unloading associated with the premises are to take place between the hours of 7pm and 7am on any day.

(Reason: To ensure the acoustic amenity of surrounding properties)

Food Shop Premises Registration

110. The food shop premises must be registered with Council and NSW Food Authority prior to commencement of operation of the approved activity. Shop Premises Registration must be maintained at all times.

Note:

- a) Council registration forms can be found at <http://www.northsydney.nsw.gov.au>
- b) Notification is required to the NSW Food Authority under Standard 3.2.2 Division 2 Section 4 Notification. (see www.foodnotify.nsw.gov.au)

(Reason: To ensure compliance with environmental health legislation)

Roof Top Open Space

111. The rooftop open space area is not to be used between 5pm and 9am each day.

(Reason: To ensure residential premises are not affected by noise or illumination)

Ongoing Street Tree Care

112. The 3 x *Callistemon* spp. located in the Aubin Street road reserve, and the 7 x *Sapium sebiferum* and 1 x *Pyrus* sp. located in the Wycombe Road reserve shall be watered for a period of six (6) months after the final Occupation Certificate is issued. The watering shall be approximately 20 litres per week (min) delivered gently by hose or watering can so that the surrounding soil can absorb the water. Seasol solution is recommended once a month over this period.

Plans and specifications showing the said tree protection measures must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure the construction plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure that appropriate tree protection measures are shown on construction drawings)

Maintenance of Approved Landscaping

- I13. The owner of the premises at 54-58A Wycombe Road shall maintain the landscaping approved by this consent generally in accordance with Landscape Plan prepared by Umbaco Landscape Architects dated February 2020 as modified by condition C27.

Any replacement plants required shall be advanced in growth and be selected to maintain the anticipated mature height, canopy density and nature of those plant species as originally approved.

(Reason: To ensure maintenance of the amenity, solar access and views of adjoining properties)

High Level Care

- I14. The proposed beds are to be 'high-level care' beds. High-level care means care is provided either by a Registered Nurse, or under the supervision of a Registered Nurse, on a 24 hour/7 day a week basis to people who need almost complete assistance with most activities of daily living. Evidence of meeting this requirement is to be provided to the Principle Certifying Authority prior to the release of the relevant Occupation Certificate.

(Reason: To ensure that the residents of the facility are provided with the necessary assistance to maintain access to reasonable facilities and services)

Private Bus Service

- I15. Private Bus Service A 12 seat bus is to be provided for the development and at a minimum is to ensure residents have access to a location within 400m of:

- (a) shops, bank service providers and other retail and commercial services that residents may reasonably require, and
- (b) community services and recreation facilities, and
- (c) the practice of a general medical practitioner,

and that the bus service is available both to and from the proposed development at least once between 8am and 12pm per day and at least once

between 12pm and 6pm each day from Monday to Friday (both days inclusive).

Evidence of meeting this requirement is to be provided to the Principle Certifying Authority prior to the release of the relevant Occupation Certificate.

(Reason: To ensure that the residents of the facility are provided with the necessary assistance to maintain access to reasonable facilities and services)

Residential Aged Care Kitchen Registration

I16. The Kitchen must be registered be registered with the NSW Food Authority prior to commencement of operation of the approved activity. Kitchen registration must be maintained at all times.

Note:

- a) Council registration forms can be found at <http://www.northsydney.nsw.gov.au>
- b) Notification is required to the NSW Food Authority under Standard 3.2.2 Division 2 Section 4 Notification. (see www.foodnotify.nsw.gov.au)

(Reason: To ensure compliance with environmental health legislation)