

16 November 2022

Contact lauren.preston Email lauren.preston@waternsw.com.au

Our ref IDAS1146040 Your ref A-54568 / CNR-46208

The General Manager Lane Cove Municipal Council PO Box 20 LANE COVE NSW 1595

Attention - gsamardzic@lanecove.nsw.gov.au

Dear Greg,

RE: Request for Further Information of Proposed Development PAN-259955 Property Address: 12 Berry Road LANE COVE NSW 2065

Reference is made to A-54568 / CNR-46208

Thank you for forwarding the response provided by Douglas Partners Pty Ltd - Comments on Groundwater Inflows, dated 02 November 2022. WaterNSW has reviewed this supporting information and documentation and provides the following comments to the applicant;

WaterNSW requires confirmation for all structures below the predicited groundwater table are either waterproofed (tanked basement) or alternatively, a drained basement design. If a tanked basement is to be constructed please provide a response to questions 1 - 5 as detailed below and request that the geotechnical report be updated accordingly.

1. Confirmation that the structures below the predicted highest groundwater table are waterproof (tanked basement) and dewatering management program is designed considering the Minimum requirements for building site groundwater investigations and reporting. Note: Department of Planning, Industry & Environment (DPIE) require the perimeter walls and floor of the basement being constructed using a 'tanked' (waterproof) construction method.

https://www.industry.nsw.gov.au/ data/assets/pdf file/0004/343291/minimumrequirem ents.pdf

- 2. Volume of water to be extracted annually
- 3. Duration of the water take for dewatering

- 4. Method of measuring the water take and recording
- 5. Provide documents updated with the above information

If a tanked basement design is not possible, DPIE will require additional modelled data to support a hydro-geological review and assessment of the alternative drained basement design. The Geotech report will need to be updated accordingly. For details of the additional data requirements for DPIE to assess drained basement scenarios , please refer to **Table 1 Modelling Inputs** in the attachment at he end of this letter.

Please be advised WaterNSW require the perimeter walls and floor of the basement to be constructed using a 'tanked' (waterproof) construction method and does not support a drained basement option for basements. However, if insistent on a drained basement alternative for the design of the basement, you will need to provide all the additional data and modelling inputs to enable DPE to undertake the necessary hydrogeological assessment.

Please arrange the provision of this information for WaterNSW to make assessment as soon as possible. Should you require additional time to provide a response or have any further enquiry please email <u>lauren.preston@waternsw.com.au</u>.

Yours sincerely,

Lauren Preston Water Regulation Officer Assessments and Approvals – WaterNSW



20th October 2022

Contact Lauren Preston Email lauren.preston@waternsw.com.au

Our ref IDAS1146040 Your ref A-54568 / CNR-46208

The General Manager Lane Cove Municipal Council PO Box 20 LANE COVE NSW 1595

Attention - gsamardzic@lanecove.nsw.gov.au

Dear Greg,

RE: Request for Further Information of Proposed Development PAN-259955 Property Address: 12 Berry Road LANE COVE NSW 2065

Reference is made to A-54568 / CNR-46208

WaterNSW has reviewed the information provided with the development application related to water supply works and send a request for further information. WaterNSW requests that the consent arrange for the applicant Altis Bulky Retail P/L to provide the following information to enable assessment of the application:

- Confirmation that the structures below the predicted highest groundwater table are waterproof (tanked basement) and dewatering management program is designed considering the Minimum requirements for building site groundwater investigations and reporting. Note: Department of Planning, Industry & Environment (DPIE) require the perimeter walls and floor of the basement being constructed using a 'tanked' (waterproof) construction method. <u>https://www.industry.nsw.gov.au/ data/assets/pdf file/0004/343291/minimumrequirements.pdf</u>
- 2. Volume of water to be extracted annually
- 3. Duration of the water take for dewatering
- 4. Method of measuring the water take and recording
- 5. Provide documents updated with the above information

6. It a tanked basement design is not possible, DPIE will require additional modelled data to support a hydro-geological review and assessment of the alternative drained basement design. The Geotech report will need to be updated accordingly. For details of the additional data requirements for DPIE to assess drained basement scenarios , please refer to **Table 1 Modelling Inputs in the attachment.**

Please arrange to provide this information within 28 days from the date of this document. Should there be any further enquiry in this matter, please email lauren.preston@waternsw.com.au

Yours sincerely,

Lauren Preston Water Regulation Officer Assessment and Approvals WaterNSW

Table 1 Modelling inputs

WaterNSW and DPIE do not support the drained basement option for basements. However if the proponent is insistent on a drained basement alternative for the design of the basement, they will need to provide all the following additional data and modelling inputs to enable DPIE to undertake the necessary hydrogeological assessment.

#	Assessment Item
1	The estimate volume of water take has been specified in the documentation supplied with the application (in megalitres).
2	Detailed explanation and supporting evidence have been provided to demonstrate the suitability of the volume estimation method (either description of numerical model used or analytical solution and source document).
3	The ground elevation across the site has been provided on an architectural plan or section or detailed in other supporting documents in a manner acceptable to WaterNSW and DPIE-Water.
4	A report outlining the geotechnical characterisation of the ground conditions, based on site- specific intrusive investigations that fully penetrate to a deep geological unit beneath the property that is identified in the geotechnical report as being consolidated or hard.
5	Frequently repeated water level measurements illustrating the natural range over at least three months (in metres below ground level)
6	The magnitude of required drawdown in water level to achieve dry conditions in the excavation has been identified (in metres).
7	The works proposed to be used for dewatering have been described in detail (number, spacing, depth, individual discharge rates, cumulative discharge rate) and illustrated on specific plan and section diagrams.
8	The base level of the aquifer has been identified or can it be determined from supplied bore logs (in metres below ground level).
9	Accurate excavation footprint dimensions (length, width, bulk excavation level) have been specified (in metres).
10	Field test results to determine the hydraulic conductivity of lithological units present beneath the site have been reported (in metres per day).
11	The anticipated duration of dewatering pumping has been specified (days or weeks or months).
12	The depth of piling embedment beneath the bulk excavation level has been specified (in metres).

In the case of a drained basement, we request that the geotechnical report be updated accordingly and uploaded to the planning portal. Further information can also be found at https://www.industry.nsw.gov.au/water/science/groundwater/aquifer-interference-activities