

## DRAFT CONDITIONS OF APPROVAL

<b>Application Number:</b>	DA2022/1510
<b>Land to be developed (Address):</b>	Part Lot 28 DP 7413, 9 Francis Street DEE WHY NSW 2099 Part Lot 28 DP 7413, 28 Fisher Road DEE WHY NSW 2099 Part Lot 28 DP 7413, 28 Fisher Road DEE WHY NSW 2099
<b>Proposed Development:</b>	Demolition works and Construction of a mixed use development to accommodate a café, church, conference centre, boarding house and two level of basement car park.

## DEVELOPMENT CONSENT OPERATIONAL CONDITIONS

### 1. Approved Plans and Supporting Documentation

The development must be carried out in compliance with the endorsed stamped plans and documentation listed below, except as amended by any other condition of consent:

#### a) Approved Plans

Architectural Plans - Endorsed with Council's stamp		
Drawing No.	Dated	Prepared By
Drawing 4089/4.2	March 2023	The George Group
Drawing 4089/4.4	March 2023	The George Group
Drawing 4089/4.9	March 2023	The George Group
Drawing 4089/4.10	March 2023	The George Group
Drawing 4089/4.14	March 2023	The George Group
Drawing 4089/4.15	March 2023	The George Group
Drawing 4089/4.16	March 2023	The George Group
Drawing 4089/4.17	March 2023	The George Group
Drawing 4089/5.1	March 2023	The George Group
Drawing 4089/5.5	March 2023	The George Group
Drawing 4089/5.3	March 2023	The George Group
Drawing 4089/5.4	March 2023	The George Group
Drawing 4089/5.5	March 2023	The George Group
Drawing 4089/5.6	March 2023	The George Group
Drawing 4089/5.7	March 2023	The George Group
Drawing 4089/5.8	March 2023	The George Group
Drawing 4089/5.9	March 2023	The George Group
Drawing 4089/5.10	March 2023	The George Group
Drawing 4089/5.11	March 2023	The George Group

Drawing 4089/5.12	March 2023	The George Group
Drawing 4089/5.13	March 2023	The George Group
Drawing 4089/5.14	March 2023	The George Group
Drawing 4089/5.15	March 2023	The George Group
Drawing 4089/5.16	March 2023	The George Group
Drawing 4089/5.17	March 2023	The George Group
Drawing 4089/5.18	March 2023	The George Group
Drawing 4089/5.19	March 2023	The George Group
Drawing 4089/5.20	March 2023	The George Group
Drawing 4089/5.21	March 2023	The George Group
Drawing 4089/06.1	March 2023	The George Group
Drawing 4089/06.2	March 2023	The George Group
Drawing 4089/06.3	March 2023	The George Group
Drawing 4089/06.4	March 2023	The George Group
Drawing 4089/06.5	March 2023	The George Group
Drawing 4089/06.6	March 2023	The George Group
Drawing 4089/06.7	March 2023	The George Group
Drawing 4089/06.8	March 2023	The George Group
Drawing 4089/06.9	March 2023	The George Group
Drawing 4089/06.10	March 2023	The George Group
Drawing 4089/07.1	March 2023	The George Group
Drawing 4089/07.2	March 2023	The George Group
Drawing 4089/07.3	March 2023	The George Group
Drawing 4089/07.4	March 2023	The George Group
Drawing 4089/07.5	March 2023	The George Group
Drawing 4089/07.6	March 2023	The George Group
Drawing 4089/07.7	March 2023	The George Group
Drawing 4089/07.8	March 2023	The George Group
Drawing 4089/07.9	March 2023	The George Group
Drawing 4089/07.10	March 2023	The George Group
Drawing 4089/07.11	March 2023	The George Group
Drawing 4089/08.1	March 2023	The George Group
Drawing 4089/08.2	March 2023	The George Group

Engineering Plans		
Drawing No.	Dated	Prepared By
STW-01 Issue A	20/03/2023	Mesh Group
STW-02 Issue A	20/03/2023	Mesh Group
STW-03 Issue A	26/08/2022	Mesh Group
STW-04 Issue A	20/03/2022	Mesh Group
STW-05 Issue A	20/03/2022	Mesh Group

STW-06 Issue A	20/03/2023	Mesh Group
----------------	------------	------------

<b>Reports / Documentation – All recommendations and requirements contained within:</b>		
<b>Report No. / Page No. / Section No.</b>	<b>Dated</b>	<b>Prepared By</b>
Plan of Management for Boarding House	16/03/2023	The George Group
Geotechnical Report SRE/524/DW/22/REV1	12/08/2022	Soilsrock Engineering
Section J Report Rev 1	2/08/2022	Soumya Prusty
Building Services Engineering Report	12/07/2022	The George Group
BCA Compliance Report	1/08/2022	The George Group
Acoustic Assessment Report 20SYA0029 R01_1	8/08/2022	TTM
Access Report	12/08/2022	Accessible Public Domain
BASIX Certificate No.1316906M	2/08/2022	Certified Energy 1

b) Any plans and / or documentation submitted to satisfy the Conditions of this consent.

c) The development is to be undertaken generally in accordance with the following:

<b>Landscape Plans</b>		
<b>Drawing No.</b>	<b>Dated</b>	<b>Prepared By</b>
22/2293 Issue F Sheets 1 to 6	14/03/2023	Paul Scrivener

<b>Waste Management Plan</b>		
<b>Drawing No/Title.</b>	<b>Dated</b>	<b>Prepared By</b>
Waste Management Plan	12/08/2022	Applicant

In the event of any inconsistency between conditions of this consent and the drawings/documents referred to above, the conditions of this consent will prevail.

Reason: To ensure the work is carried out in accordance with the determination of Council and approved plans.

## 2. **Compliance with Other Department, Authority or Service Requirements**

The development must be carried out in compliance with all recommendations and requirements, excluding general advice, within the following:

<b>Other Department, Authority or Service</b>	<b>EDMS Reference</b>	<b>Dated</b>
Ausgrid	Ausgrid Referral Response	26 October 2022

(NOTE: For a copy of the above referenced document/s, please see Application Tracking on Council's website [www.northernbeaches.nsw.gov.au](http://www.northernbeaches.nsw.gov.au))

Reason: To ensure the work is carried out in accordance with the determination and the statutory requirements of other departments, authorities or bodies.

### 3. Prescribed Conditions

- (a) All building works must be carried out in accordance with the requirements of the Building Code of Australia (BCA).
- (b) BASIX affected development must comply with the schedule of BASIX commitments specified within the submitted BASIX Certificate (demonstrated compliance upon plans/specifications is required prior to the issue of the Construction Certificate);
- (c) A sign must be erected in a prominent position on any site on which building work, subdivision work or demolition work is being carried out:
  - (i) showing the name, address and telephone number of the Principal Certifier for the work, and
  - (ii) showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working hours, and
  - (iii) stating that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.

- (d) Residential building work within the meaning of the Home Building Act 1989 must not be carried out unless the Principal Certifier for the development to which the work relates (not being the Council) has given the Council written notice of the following information:
  - (i) in the case of work for which a principal contractor is required to be appointed:
    - A. the name and licence number of the principal contractor, and
    - B. the name of the insurer by which the work is insured under Part 6 of that Act,
  - (ii) in the case of work to be done by an owner-builder:
    - A. the name of the owner-builder, and
    - B. if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.

If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under becomes out of date, further work must not be carried out unless the Principal Certifier for the development to which the work relates (not being the Council) has given the Council written notice of the updated information.

- (e) Development that involves an excavation that extends below the level of the base of the footings of a building on adjoining land, the person having the benefit of the development consent must, at the person's own expense:
  - (i) protect and support the adjoining premises from possible damage from the excavation, and
  - (ii) where necessary, underpin the adjoining premises to prevent any such damage.
  - (iii) must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished.
  - (iv) the owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this clause, whether carried out on the

allotment of land being excavated or on the adjoining allotment of land.

In this clause, allotment of land includes a public road and any other public place.

Reason: Legislative requirement.

#### 4. **General Requirements**

(a) Unless authorised by Council:

Building construction and delivery of material hours are restricted to:

- 7.00 am to 5.00 pm inclusive Monday to Friday,
- 8.00 am to 1.00 pm inclusive on Saturday,
- No work on Sundays and Public Holidays.

Demolition and excavation works are restricted to:

- 8.00 am to 5.00 pm Monday to Friday only.

(Excavation work includes the use of any excavation machinery and the use of jackhammers, rock breakers, excavators, loaders and the like, regardless of whether the activities disturb or alter the natural state of the existing ground stratum or are breaking up/removing materials from the site).

- (b) Should any asbestos be uncovered on site, its demolition and removal must be carried out in accordance with WorkCover requirements and the relevant Australian Standards.
- (c) At all times after the submission the Notice of Commencement to Council, a copy of the Development Consent and Construction Certificate is to remain onsite at all times until the issue of an Occupation Certificate. The consent shall be available for perusal of any Authorised Officer.
- (d) Where demolition works have been completed and new construction works have not commenced within 4 weeks of the completion of the demolition works that area affected by the demolition works shall be fully stabilised and the site must be maintained in a safe and clean state until such time as new construction works commence.
- (e) Onsite toilet facilities (being either connected to the sewer or an accredited sewer management facility) for workers are to be provided for construction sites at a rate of 1 per 20 persons.
- (f) Prior to the release of the Construction Certificate, payment of the Long Service Levy is required. This payment can be made at Council or to the Long Services Payments Corporation. Payment is not required where the value of the works is less than \$25,000. The Long Service Levy is calculated on 0.35% of the building and construction work. The levy rate and level in which it applies is subject to legislative change. The applicable fee at the time of payment of the Long Service Levy will apply.
- (g) The applicant shall bear the cost of all works associated with the development that occurs on Council's property.
- (h) No skip bins, building materials, demolition or excavation waste of any nature, and no hoist, plant or machinery (crane, concrete pump or lift) shall be placed on Council's footpaths, roadways, parks or grass verges without Council Approval.
- (i) Demolition materials and builders' wastes are to be removed to approved waste/recycling centres.

- (j) No trees or native shrubs or understorey vegetation on public property (footpaths, roads, reserves, etc.) or on the land to be developed shall be removed or damaged during construction unless specifically approved in this consent including for the erection of any fences, hoardings or other temporary works.
- (k) Prior to the commencement of any development onsite for:
  - i) Building/s that are to be erected
  - ii) Building/s that are situated in the immediate vicinity of a public place and is dangerous to persons or property on or in the public place
  - iii) Building/s that are to be demolished
  - iv) For any work/s that is to be carried out
  - v) For any work/s that is to be demolished

The person responsible for the development site is to erect or install on or around the development area such temporary structures or appliances (wholly within the development site) as are necessary to protect persons or property and to prevent unauthorised access to the site in order for the land or premises to be maintained in a safe or healthy condition. Upon completion of the development, such temporary structures or appliances are to be removed within 7 days.
- (l) A "Road Opening Permit" must be obtained from Council, and all appropriate charges paid, prior to commencement of any work on Council property. The owner/applicant shall be responsible for all public utilities and services in the area of the work, shall notify all relevant Authorities, and bear all costs associated with any repairs and/or adjustments as those Authorities may deem necessary.
- (m) The works must comply with the relevant Ausgrid Network Standards and SafeWork NSW Codes of Practice.
- (n) Requirements for new swimming pools/spas or existing swimming pools/spas affected by building works.
  - (1) Child resistant fencing is to be provided to any swimming pool or lockable cover to any spa containing water and is to be consistent with the following;
 

Relevant legislative requirements and relevant Australian Standards (including but not limited) to:

    - (i) Swimming Pools Act 1992
    - (ii) Swimming Pools Amendment Act 2009
    - (iii) Swimming Pools Regulation 2018
    - (iv) Australian Standard AS1926 Swimming Pool Safety
    - (v) Australian Standard AS1926.1 Part 1: Safety barriers for swimming pools
    - (vi) Australian Standard AS1926.2 Part 2: Location of safety barriers for swimming pools.
  - (2) A 'KEEP WATCH' pool safety and aquatic based emergency sign, issued by Royal Life Saving is to be displayed in a prominent position within the pool/spa area.
  - (3) Filter backwash waters shall be conveyed to the Sydney Water sewerage system in sewered areas or managed on-site in unsewered areas in a manner that does not cause pollution, erosion or run off, is separate from the irrigation area for any wastewater system and is separate from any onsite stormwater management system.
  - (4) Swimming pools and spas must be registered with the Division of Local



Government.

Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community.

## 5. **Approved Land Use**

Nothing in this consent shall authorise the use of site/onsite structures/units/tenancies as detailed on the approved plans for any land use of the site beyond the definition of a “Boarding House” and a “Place of Public Worship”, in accordance with the Dictionary of the Warringah Local Environmental Plan 2011, as follows:

- a) Place of public worship “means a building or place used for the purpose of religious worship by a congregation or religious group, whether or not the building or place is also used for counselling, social events, instruction or religious training.”
- b) Boarding House “*means a building or place—*
- (a) that provides residents with a principal place of residence for at least 3 months, and*
  - (b) that contains shared facilities, such as a communal living room, bathroom, kitchen or laundry, and*
  - (c) that contains rooms, some or all of which may have private kitchen and bathroom facilities, and*
  - (d) used to provide affordable housing, and*
  - (e) if not carried out by or on behalf of the Land and Housing Corporation—managed by a registered community housing provider,*
- but does not include backpackers’ accommodation, co-living housing, a group home, hotel or motel accommodation, seniors housing or a serviced apartment.”*

Any variation to the approved land use and/occupancy of any unit beyond the scope of the above definition will require the submission to Council of a new development application.

Reason: To ensure compliance with the terms of this consent.

## **FEES / CHARGES / CONTRIBUTIONS**

### 6. **Security Bond**

A bond (determined from cost of works) of \$10,000 and an inspection fee in accordance with Council's Fees and Charges paid as security are required to ensure the rectification of any damage that may occur to the Council infrastructure contained within the road reserve adjoining the site as a result of construction or the transportation of materials and equipment to and from the development site.

An inspection fee in accordance with Council adopted fees and charges (at the time of payment) is payable for each kerb inspection as determined by Council (minimum (1) one inspection).

All bonds and fees shall be deposited with Council prior to Construction Certificate or demolition work commencing, and details demonstrating payment are to be submitted to the Certifier prior to the issue of the Construction Certificate.

To process the inspection fee and bond payment a Bond Lodgement Form must be completed with the payments (a copy of the form is attached to this consent and alternatively a copy is located on Council's website at [www.northernbeaches.nsw.gov.au](http://www.northernbeaches.nsw.gov.au)).

Reason: To ensure adequate protection of Council's infrastructure.

## 7. **Dee Why Town Centre - Contribution Condition**

The applicant must pay a monetary contribution to Council of \$43,214.90. This contribution is calculated at the date of this consent, in accordance with Dee Why Town Centre Contributions Plan (as amended) and comprises:

- i a non-residential contribution of \$43,214.90 based on 228.5m<sup>2</sup> of additional non-residential gross floor area

The total amount payable will be adjusted at the time of payment in accordance with the Dee Why Town Centre Contributions Plan (as amended). Details demonstrating compliance, by way of written receipts issued by Council, are to be submitted to the Certifier prior to issue of any Construction Certificate.

The Applicant may negotiate with Council for the direct provision of other facilities and services, and/or the dedication of land in lieu of the monetary contribution above (or any portion of that monetary contribution) through a Planning Agreement between Council and the Applicant in accordance the Dee Why Town Centre Contributions Plan (as amended) and Council's Planning Agreement Policy. The Planning Agreement between the Applicant and Council must be finalised, formally signed, and in place prior to the payment of the monetary contribution.

A copy of the Contributions Plan is available for inspection at 725 Pittwater Road, Dee Why or



on Council's website at Northern Beaches Council - Development Contributions.

Reason: To provide for contributions in accordance with the Contribution Plan that enables the provision of local infrastructure and services commensurate with the increased demand resulting from development in the Dee Why Town Centre.

8. **Construction, Excavation and Associated Works Bond (Drainage works)**

The applicant is to lodge a bond of \$15000 as security against any damage or failure to complete the construction of stormwater drainage works in Fisher Road as part of this consent.

Details confirming payment of the bond are to be submitted to the Certifier prior to the issue of the Construction Certificate.

Reason: Protection of Council's infrastructure.

9. **Construction, Excavation and Associated Works Security Bond (Crossing / Kerb)**

The applicant is to lodge a Bond of \$25000 as security against any damage or failure to complete the construction of any vehicular crossings, kerb and gutter, any footpath works and removal of any redundant driveways required as part of this consent.

Details confirming payment of the bond are to be submitted to the Certifier prior to the issue of the Construction Certificate.

Reason: Protection of Council's infrastructure.

10. **Construction, Excavation and Associated Works (Security Bond)**

A bond of \$30000 as security against damage to Council's roads fronting the site caused by the transport and disposal of materials and equipment to and from the site.

Details confirming payment of the bond are to be submitted to the Certifier prior to the issue of the Construction Certificate.

Reason: Protection of Council's infrastructure.

## **CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE**

11. **Public Domain Plan**

A Public Domain Plan shall be concurrently submitted as part of the Civil Works under the Roads Act provisions of Section 138 to Council for development works within the road reserve, with sufficient detail design information including the following:

- i) alignment levels showing existing and proposed levels for altered kerbs and gutters,
- ii) existing and proposed pavement levels, with proposed gradients no more than a 2.5% fall from building openings to top of kerb, and to match existing levels along adjoining properties,
- iii) details of any utility alignment and level changes,
- iv) details of the proposed pavement finish from building to kerb which shall equal concrete unit paving 'Urbanstone Golden Gunmetal'; finish - honed; size - 400x400x40/50mm; pattern - stackbond parallel to kerb/building alignment; banding - to match existing at Redman Rd Plaza,
- v) proposed street tree planting (x2) on Fisher Rd, and in accordance with Northern Beaches Standard Drawing 1300 - Tree Pit Details, Plan and Section, including strata cell system; however, having a 1600mm (parallel to kerb) x 1200mm tree pit opening finished with mulch and

groundcover planting,

vi) the street tree species shall be as shown on the approved Landscape Plans, installed at a pre-ordered 200 litre container size,

vii) the groundcover planting shall be Liriope 'Evergreen Giant' planted at 9 per square metres and at 140mm container pots.

Any work carried out upon public land shall have all the necessary prior approvals and permits from Council in place prior to commencement to conduct such works.

Reason: Compliance with Council standards for works on public land.

## 12. **On Slab Landscape Works**

Details shall be submitted to the Certifier prior to the issue of the Construction Certificate indicating the proposed method of waterproofing and drainage to all planters over slab, over which soil and planting is being provided.

Landscape treatment details shall be submitted to the Certifier prior to the issue of the Construction Certificate indicating the proposed soil type, planting, automatic irrigation, and services connections.

The following soil depths are required to support landscaping: 300mm for groundcovers, perennials, grasses and lawn; 600mm for shrubs; and 1m for small trees.

Design certification shall be submitted to the Certifier by a qualified Structural Engineer, that the planters are designed structurally to support the 'wet' weight of landscaping (soil, materials and established planting).

Reason: To ensure appropriate soil depth for planting and ensure waterproofing and drainage is installed.

## 13. **Traffic Management and Control**

The Applicant is to submit an application for Traffic Management Plan to Council for approval prior to issue of the Construction Certificate. The Traffic Management Plan shall be prepared to TfNSW standards by an appropriately certified person.

Reason: To ensure appropriate measures have been considered for site access, storage and the operation of the site during all phases of the construction process.

## 14. **Erosion and Sediment Control Plan**

An Erosion and Sediment Control Plan (ESCP) shall be prepared by an appropriately qualified person and implemented onsite prior to commencement. The ESCP must meet the requirements outlined in the Landcom publication Managing Urban Stormwater: Soils and Construction - Volume 1, 4th Edition (2004). The ESCP must include the following as a minimum:

- i Site Boundaries and contours
- i Approximate location of trees and other vegetation, showing items for removal or retention (consistent with any other plans attached to the application)
- i Location of site access, proposed roads and other impervious areas (e.g. parking areas and site facilities)
- i Existing and proposed drainage patterns with stormwater discharge points
- i Locations and methods of all erosion and sediment controls that must include sediment fences, stabilised site access, materials and waste stockpiles locations, location of any

- stormwater pits on the site and how they are going to be protected.
- North point and scale.

Details demonstrating compliance are to be submitted to the Certifier for approval prior to the issue of the Construction Certificate.

Reason: Protection of the receiving environment.

15. **Detailed Design of Stormwater Treatment Measures - Major**

A certificate from a Civil Engineer, stating that the stormwater treatment measures have been designed in accordance with the Stormwater Plans prepared by The George Group Pty Ltd and Council's Water Management for Development Policy.

The certificate shall be submitted to the Certifier prior to the release of the Construction Certificate.

Reason: Protection of the receiving environment.

16. **Car Parking Standards**

The driveway/access ramp grades, access and car parking facilities must comply with the Australian/New Zealand Standard AS/NZS 2890.1:2004 - Parking facilities - Off-street car parking. The dimensions of car parking bays and aisle widths in the car park are to comply with Australian/New Zealand Standard for Off-Street Parking AS/NZS 2890.1-2004.

Details demonstrating compliance with this condition are to be submitted to the Certifier prior to the issue of a construction certificate.

Reason: To ensure compliance with Australian Standards relating to manoeuvring, access and parking of vehicles.

17. **Construction Traffic Management Plan**

As a result of the site constraints, limited vehicle access and parking, a Construction Traffic Management Plan (CTMP) and report shall be prepared by a TfNSW accredited person and submitted to and approved by the Northern Beaches Council Traffic Team prior to issue of any Construction Certificate.

Due to heavy traffic congestion throughout the Dee Why town centre, truck movements will be restricted during the major commuter peak times being 8.00-9.30am and 3.30-6.00pm. Truck movements must be agreed with Council's Traffic Engineer prior to submission of the CTMP.

The CTMP must address following:

- The proposed phases of construction works on the site, and the expected duration of each construction phase
- The proposed order in which works on the site will be undertaken, and the method statements on how various stages of construction will be undertaken
- Make provision for all construction materials to be stored on site, at all times
- The proposed areas within the site to be used for the storage of excavated materials, construction materials and waste containers during the construction period
- The proposed method of access to and egress from the site for construction vehicles, including access routes and truck routes through the Council area and the location and type of temporary vehicular crossing for the purpose of minimising traffic congestion and noise in the area, with no access across public parks or reserves being allowed
- The proposed method of loading and unloading excavation and construction machinery,

- excavation and building materials, formwork and the erection of any part of the structure within the site. Wherever possible mobile cranes should be located wholly within the site
- i Make provision for parking onsite. All Staff and Contractors are to use the basement parking once available
- i Temporary truck standing/ queuing locations in a public roadway/ domain in the vicinity of the site are not permitted unless approved by Council prior
- i Include a Traffic Control Plan prepared by a person with suitable RMS accreditation for any activities involving the management of vehicle and pedestrian safety
- i The proposed manner in which adjoining property owners will be kept advised of the timeframes for completion of each phase of development/construction process. It must also specify that a minimum Fourteen (14) days notification must be provided to adjoining property owners prior to the implementation of any temporary traffic control measure
- i Include a site plan showing the location of any site sheds, location of requested Work Zones, anticipated use of cranes and concrete pumps, structures proposed on the footpath areas (hoardings, scaffolding or shoring) and any tree protection zones around Council street trees
- i Take into consideration the combined construction activities of other development in the surrounding area. To this end, the consultant preparing the CTMP must engage and consult with developers undertaking major development works within a 250m radius of the subject site to ensure that appropriate measures are in place to prevent the combined impact of construction activities, such as (but not limited to) concrete pours, crane lifts and dump truck routes. These communications must be documented and submitted to Council prior to work commencing on site
- i The proposed method/device to remove loose material from all vehicles and/or machinery before entering the road reserve, any run-off from the washing down of vehicles shall be directed to the sediment control system within the site
- i Specify that the roadway (including footpath) must be kept in a serviceable condition for the duration of construction. At the direction of Council, undertake remedial treatments such as patching at no cost to Council
- i The proposed method of support to any excavation adjacent to adjoining properties, or the road reserve. The proposed method of support is to be designed and certified by an appropriately qualified and practising Structural Engineer, or equivalent
- i Proposed protection for Council and adjoining properties
- i The location and operation of any on site crane

The CTMP shall be prepared in accordance with relevant sections of Australian Standard 1742 – “Manual of Uniform Traffic Control Devices”, RMS’ Manual – “Traffic Control at Work Sites”.

All fees and charges associated with the review of this plan is to be in accordance with Council’s Schedule of Fees and Charges and are to be paid at the time that the Construction Traffic Management Plan is submitted.

Reason: To ensure public safety and minimise any impacts to the adjoining pedestrian and vehicular traffic systems.

#### 18. **Removal of Redundant Driveways**

All redundant driveways shall be removed and reinstated to Council standard kerb and gutter. Suitably prepared plans shall be submitted to for an approval under and approved by Council prior to the issue of the Construction Certificate. All costs associated with the works shall be borne by the applicant.

A plan checking fee (amount to be advised) and lodgement of a performance bond may be

required from the applicant prior to the release of the approval.

Reason: To maximise on street car parking by removing driveways that are no longer needed in accordance with Council policy.

19. **Geotechnical Report Recommendations have been Incorporated into Designs and Structural Plans**

The recommendations of the risk assessment required to manage the hazards as identified in the Geotechnical Report referenced in Condition 1 of this consent are to be incorporated into the construction plans.

Details demonstrating compliance are to be submitted to the Certifier prior to the issue of a Construction Certificate.

Reason: To ensure geotechnical risk is mitigated appropriately.

20. **Building Code of Australia Requirements**

The Building Code of Australia works as detailed and recommended in the Building Code of Australia Audit Report prepared by The George Group P/L, dated 1 August 2022 are to be considered as part of the assessment of the Construction Certificate.

Details demonstrating compliance are to be provided to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure adequate provision is made for Health, Amenity, access and Fire safety for building occupant health and safety.

21. **On-site Stormwater Detention Details**

The Applicant is to provide a certification of drainage plans detailing the provision of on-site stormwater detention in accordance with Northern Beaches Council's Water Management for Development Policy and generally in accordance with the concept drainage plans prepared by Mesh Group PTY LTD , drawing number STW03 Issue A, dated 28/8/22. Detailed drainage plans are to be prepared by a suitably qualified Civil Engineer, who has membership to the Institution of Engineers Australia, National Professional Engineers Register (NER) or Professionals Australia (RPENG) and registered in the General Area of Practice for civil engineering.

The drainage plans must address the following:

- i. As detailed in the stormwater concept plans the minimum On Site Detention storage volume is to be 39 cumecs.
- ii. Minimum information as detailed in section 7.1 of Councils Water Management for Development Policy is to be provided on the stormwater management plans.
- iii. The OSD tank needs to feature an overflow pipe to prevent overflows entering the building in the event of an orifice plate blockage. (IE surcharge out of the pit grates)  
Additionally the OSD tank level is to be above the invert of the Council stormwater line in Fisher Road and set at a height to prevent the a flooded outlet. Hydraulic Grade line analysis is required to demonstrate there is no flooded outlet.
- iv. In relation to the proposed new kerb inlet pit and the 300mm stormwater outlet in Fisher Road all utility services crossings and a hydraulic grade line are to be detailed on a suitable scaled longsection. The design invert levels of the new inlet pit are also to be detailed. ( Invert Level to be confirmed by an appropriate survey)

- v. Detailed drainage plans, including engineering compliance certification, are to be submitted to

the Certifier for approval prior to the issue of the Construction Certificate.

Reason: To ensure appropriate provision for the disposal of stormwater and stormwater management arising from the development.

22. **Submission Roads Act Application for Civil Works in the Public Road**

The Applicant is to submit an application for approval for infrastructure works on Council's roadway. Engineering plans for the new development works within the road reserve and this development consent are to be submitted to Council for approval under the provisions of Sections 138 and 139 of the Roads Act 1993.

The application is to include four (4) copies of Civil Engineering plans for the design of the full width paving works, stormwater outlet works and new kerb inlet pit in Fisher Road which are to be generally in accordance with the Council's specification for engineering works - AUS-SPEC #1. The plan shall be prepared by a qualified civil engineer. The design must include the following information: The fee associated with the assessment and approval of the application is to be in accordance with Council's Fee and Charges.

An approval is to be submitted to the Certifier prior to the issue of the Construction Certificate

Reason: To ensure engineering works are constructed in accordance with relevant standards and Council's specification.

23. **Tanking of Basement Level**

The basement area is to be permanently tanked. The Applicant is to submit structural details of the tanking, prepared by a suitably qualified Engineer. Where temporary dewatering works are required on the development site during construction, the developer/applicant must apply for and obtain a bore license from the NSW Office of Environment and Heritage. The bore license must be obtained prior to commencement of dewatering works. All requirements of the Water NSW are to be complied with and a copy of the approval must be submitted to the Certifier.

Details demonstrating compliance are to be submitted to the Certifier prior to the issue of the Construction Certificate.

Reason: To prevent ingress of sub-surface flows into the basement area and to comply with State Government Requirements.

24. **Structural Adequacy and Excavation Work**

Excavation work is to ensure the stability of the soil material of adjoining properties, the protection of adjoining buildings, services, structures and / or public infrastructure from damage using underpinning, shoring, retaining walls and support where required. All retaining walls are to be structurally adequate for the intended purpose, designed and certified by a Structural Engineer, except where site conditions permit the following:

- (a) maximum height of 900mm above or below ground level and at least 900mm from any property boundary, and
- (b) Comply with AS3700, AS3600 and AS1170 and timber walls with AS1720 and AS1170.

Details demonstrating compliance are to be submitted to the Certifier prior to the issue of the Construction Certificate.



Reason: To provide public and private safety.

**25. Shoring of Council's Road Reserve (Temporary road anchors)**

Should the proposal require shoring to support an adjoining property or Council land, the Applicant shall provide the adjoining properties with engineering drawings, detailing the proposed shoring works for their consideration and approval.

Written approval from Council under Section 138 of the Roads Act 1993 is required if temporary ground anchors are to be used within Council's road reserve. The Owner's approval is to be submitted to the Certifier prior to the issue of the Construction Certificate.

Reason: To ensure that owners consent is obtained for ancillary works, and to ensure the protection of adjoining properties and Council land.

**26. Vehicle Crossings Application**

The Applicant is to submit an application for driveway levels with Council in accordance with Section 138 of the Roads Act 1993. The fee associated with the assessment and approval of the application is to be in accordance with Council's Fee and Charges.

An approval is to be submitted to the Certifier prior to the issue of the Construction Certificate.

Reason: To facilitate suitable vehicular access to private property.

**27. Plans of Kitchen Design, construction and fit out**

Prior to any Construction Certificate (CC) being issued, detailed plans that demonstrate compliance with Standard 3.2.3 of the Australian and New Zealand Food Standards Code, the Food Act 2003 and Australian Standard AS 4674 'Design, construction and fit out of food premises', must be submitted to and approved by the Principle certifier. These plans are to be prepared by a suitably qualified person.

The plans must detail adequate provision for storage including separate storage of food, equipment, chemicals and personal belongings.

Reason: To ensure that the food premises complies with the design construction and fit-out requirements.

**28. Mechanical ventilation Plans**

Where Mechanical ventilation is required to be installed in the food premises ,prior to any Construction Certificate (CC) being issued, detailed plans must be submitted to and approved by the Principle certifier that demonstrate compliance with the following:

- i Australian Standard (AS) 1668.2 "The use of ventilation and air-conditioning in buildings - Mechanical ventilation in buildings"; and
- i Any external exhaust discharge must be above the roofline and discharged in a manner that is not likely to cause an amenity impact.
- i Provision of smoke and odour control equipment where necessary dependent on any cooking activity to prevent any nuisance to neighbouring residential premises and the roof deck common area

These plans are to be prepared by a suitably qualified person.

Reason: To ensure that the installed mechanical ventilation complies with the requirements of the Australian Standard 1668.2 and to prevent amenity impacts.



29. **Pre-commencement Dilapidation Report**

The applicant must prepare and submit a pre-commencement dilapidation report providing an accurate record of the existing condition of adjoining public property and public infrastructure (including roads, gutter, footpaths, etc). A copy of the report must be provided to Council, any other owners of public infrastructure and the owners of adjoining and affected private properties.

The pre-construction / demolition dilapidation report must be submitted to Council for written approval and the written approval is then to be submitted to the Certifier prior to the issue of the any Construction Certificate and the commencement of any works including demolition.

Reason: Protection of Council's infrastructure during construction.

30. **Compliance with Standards**

The development is required to be carried out in accordance with all relevant Australian Standards.

Details demonstrating compliance with the relevant Australian Standard are to be submitted to the Certifier prior to the issue of the Construction Certificate.

Reason: To ensure the development is constructed in accordance with appropriate standards.

31. **External Finishes to Roof**

The external finish to the roof shall have a medium to dark range in order to minimise solar reflections to neighbouring properties. Any roof with a metallic steel finish is not permitted.

Details demonstrating compliance are to be submitted to the Certifier prior to the issue of the Construction Certificate.

Reason: To ensure that excessive glare or reflectivity nuisance does not occur as a result of the development.

32. **Location of Air Conditioning Units**

The plans shall be updated to show the location of all air conditioning units, condensers and associated mechanical equipment. None of these elements are permitted to be placed or installed on the roof of the building, on the exterior of the building, or in any area nominated as landscaping.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure consistency with the approved plans and to minimise impacts on neighbours.

33. **Waste and Recycling Requirements**

Details demonstrating compliance with Northern Beaches Waste Management Guidelines, are to be submitted to and approved by the Certifier prior to the issue of any Construction Certificate.

If the proposal, when compliant with the Northern Beaches Waste Management Guidelines, causes inconsistencies with other parts of the approval i.e. architectural or landscaped plans, a modification(s) to the development may be required.

Reason: To ensure adequate and appropriate waste and recycling facilities are provided.

#### 34. **Services and Fire Hydrant Enclosure**

Prior to the issue of a Construction Certificate for works above ground slab level, the Certifying Authority is to be provided with plans demonstrating that all Services (Gas meter, water meter & fire hydrant and sprinkler booster valves and the like) are enclosed in a manner that complements the building and in accordance with the requirements of EP1.3 & EP1.4 of the BCA.

(Reason: To ensure essential services are appropriately screened)

### **CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT**

#### 35. **Work Zones and Permits**

Prior to commencement of the associated works, the applicant shall obtain a Work Zone Permit where it is proposed to reserve an area of road pavement for the parking of vehicles associated with a construction site.

A separate application is required with a Traffic Management Plan for standing of construction vehicles in a trafficable lane and a Roads and Maritime Services Work Zone Permit shall be obtained for State Roads.

Reason: To ensure Work zones are monitored and installed correctly.

#### 36. **Demolition Traffic Management Plan**

As a result of the site constraints, limited vehicle access and parking, a Demolition Traffic Management Plan (DTMP) shall be prepared by an suitably accredited person and submitted to and approved by the Northern Beaches Council Traffic Team prior to commencing any demolition work.

Due to heavy traffic congestion throughout the area, truck movements will be restricted during the major commuter peak times being 8.00-9.30am and 3.30-6.00pm.

The DTMP must:-

- i Make provision for all construction materials to be stored on site, at all times.
- i The DTMP is to be adhered to at all times during the project.
- i Specify construction truck routes and truck rates. Nominated truck routes are to be distributed over the surrounding road network where possible.
- i Provide for the movement of trucks to and from the site, and deliveries to the site. Temporary truck standing/ queuing locations in a public roadway/ domain in the vicinity of the site is not permitted unless prior approval is granted by Council's Traffic Engineers.
- i Include a Traffic Control Plan prepared by an TfNSW accredited traffic controller for any activities involving the management of vehicle and pedestrian traffic.
- i Specify that a minimum fourteen (14) days notification must be provided to adjoining property owners prior to the implementation of any temporary traffic control measures.
- i Include a site plan showing the location of any site sheds, location of requested Work Zones, anticipated use of cranes, structures proposed on the footpath areas (hoardings, scaffolding or temporary shoring) and extent of tree protection zones around Council street trees.
- i Take into consideration the combined construction activities of other development in the surrounding area. To this end, the consultant preparing the DTMP must engage and consult with developers undertaking major development works within a 250m radius of the subject site to ensure that appropriate measures are in place to prevent the combined impact of construction activities. These communications must be documented

- and submitted to Council prior to work commencing on site.
- i Specify spoil management process and facilities to be used on site.
- i Specify that the roadway (including footpath) must be kept in a serviceable condition for the duration of demolition. At the direction of Council, the applicant is to undertake remedial treatments such as patching at no cost to Council.

The DTMP shall be prepared in accordance with relevant sections of Australian Standard 1742–“Manual of Uniform Traffic Control Devices”, RMS’ Manual – “Traffic Control at Work Sites”.

All fees and charges associated with the review of this plan is to be in accordance with Council’s Schedule of Fees and Charges and are to be paid at the time that the Demolition Traffic Management Plan is submitted.

Reason: This condition is to ensure public safety and minimise any impacts to the adjoining pedestrian and vehicular traffic systems. The DTMP is intended to minimise impact of construction activities on the surrounding community, in terms of vehicle traffic (including traffic flow and parking) and pedestrian amenity adjacent to the site.

**37. Pre-Construction Dilapidation Report**

Dilapidation reports, including photographic surveys, of the following adjoining properties must be provided to the Principal Certifier prior to any works commencing on the site (including demolition or excavation). The reports must detail the physical condition of those properties listed below, both internally and externally, including walls, ceilings, roof, structural members and other similar items.

Properties:

- i 22-26 Fisher Road, Dee Why
- i 30 Fisher Road, Dee Why
- i 7 Francis Street, Dee Why
- i 11 Francis Street, Dee Why

The dilapidation report is to be prepared by a suitably qualified person. A copy of the report must be provided to Council, the Principal Certifier and the owners of the affected properties prior to any works commencing.

In the event that access for undertaking the dilapidation report is denied by an adjoining owner, the applicant must demonstrate, in writing that all reasonable steps have been taken to obtain access. The Principal Certifier must be satisfied that the requirements of this condition have been met prior to commencement of any works. If access is denied, then no dilapidation report is required.

Note: This documentation is for record keeping purposes and may be used by an applicant or affected property owner to assist in any action required to resolve any civil dispute over damage rising from the works.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the commencement of any works on site.

Reason: To maintain proper records in relation to the proposed development.

**38. Public Liability Insurance - Works on Public Land**

Any person or contractor undertaking works on public land must take out Public Risk Insurance

with a minimum cover of \$20 million in relation to the occupation of, and approved works within Council's road reserve or public land, as approved in this consent. The Policy is to note, and provide protection for Northern Beaches Council, as an interested party and a copy of the Policy must be submitted to Council prior to commencement of the works. The Policy must be valid for the entire period that the works are being undertaken on public land.

Reason: To ensure the community is protected from the cost of any claim for damages arising from works on public land.

## CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

### 39. Tree and Vegetation Protection

- a) Existing trees and vegetation shall be retained and protected, including:
  - i) all trees within the site not approved for removal, including trees and vegetation nominated for retention on the approved Plans,
  - ii) all trees and vegetation located on adjoining properties,
  - iii) all trees and vegetation within the road reserve.
- b) Tree protection shall be undertaken as follows:
  - i) tree protection shall be in accordance with AS4970-2009 Protection of trees on development sites, and any recommendations of an approved Arboricultural Impact Assessment,
  - ii) existing ground levels shall be maintained within the tree protection zone of trees to be retained, unless authorised by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture,
  - iii) removal of existing tree roots at or >25mm (Ø) diameter is not permitted without consultation with an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture,
  - iv) no excavated material, building material storage, site facilities, nor landscape materials are to be placed within the canopy dripline of trees and other vegetation required to be retained,
  - v) structures are to bridge tree roots at or >25mm (Ø) diameter unless directed by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture on site,
  - vi) excavation for stormwater lines and all other utility services is not permitted within the tree protection zone, without consultation with an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture including advice on root protection measures,
  - vii) should either or all of v) or vi) occur during site establishment and construction works, an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture shall provide recommendations for tree protection measures. Details including photographic evidence of works undertaken shall be submitted by the Arborist to the Principal Certifier,
  - viii) any temporary access to, or location of scaffolding within the tree protection zone of a protected tree or any other tree to be retained during the construction works is to be undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of AS4970-2009 Protection of trees on development sites,
  - ix) the activities listed in section 4.2 of AS4970-2009 Protection of trees on development sites, shall not occur within the tree protection zone of any tree on the lot or any tree on an adjoining site,
  - x) tree pruning from within the site to enable approved works shall not exceed 10% of any tree canopy, and shall be in accordance with AS4373-2007 Pruning of amenity trees,
  - xi) the tree protection measures specified in this clause must: i) be in place before work commences on the site, and ii) be maintained in good condition during the construction period, and iii) remain in place for the duration of the construction works.

The Principal Certifier must ensure that:

- c) The arboricultural works listed in a) and b) are undertaken and certified by an Arborist/Project Arborist as compliant to AS4970-2009 Protection of trees on development sites, and any recommendations of an approved Arboricultural Impact Assessment.

Reason: Tree and vegetation protection.

### 40. Road Reserve

The applicant shall ensure the public footways and roadways adjacent to the site are maintained

in a safe condition at all times during the course of the work.

Reason: Public safety.

41. **Dewatering Management**

The water to be discharged must be compliant with the General Terms of Approval/Controlled Activity permit issued by WaterNSW (if applicable), Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004) (Blue Book), Council's Compliance and Enforcement Policy and legislation including Protection of the Environment Operations Act 1997 and Contaminated Lands Act 1997.

All approvals, water discharges and monitoring results are to be documented and kept on site. Copies of all records shall be provided to the appropriate regulatory authority, including Council, upon request.

Reason: Protection of the receiving environment and groundwater resources and to ensure discharges remain within the capacity of the local stormwater system or waterway.

42. **Installation and Maintenance of Sediment and Erosion Controls**

Council proactively regulates construction sites for sediment management.

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004) and the Erosion and Sediment Control Plan prepared by The George Group Pty Ltd prior to commencement of any other works on site.

Erosion and sediment controls are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and vegetation cover has been re-established across 70 percent of the site, and the remaining areas have been stabilised with ongoing measures such as jute mesh or matting.

Reason: Protection of the receiving environment.

43. **Substitution of Stormwater Treatment Measures**

The substitution of an "equivalent" device for the stormwater treatment measure approved under the Development Consent must be submitted to the Principal Certifier for approval prior to installation.

Reason: To ensure stormwater is appropriately managed and in accordance with the Water Management for Development Policy.

44. **Implementation of Demolition Traffic Management Plan**

All works and demolition activities are to be undertaken in accordance with the approved Demolition Traffic Management Plan (DTMP). All controls in the DTMP must be maintained at all times and all traffic management control must be undertaken by personnel having appropriate TfNSW accreditation. Should the implementation or effectiveness of the DTMP be impacted by surrounding major development not encompassed in the approved DTMP, the DTMP measures and controls are to be revised accordingly and submitted to Council for approval. A copy of the approved DTMP is to be kept onsite at all times and made available to the accredited certifier or Council on request.

Reason: To ensure compliance and Council's ability to modify the approved Construction Traffic Management Plan where it is deemed unsuitable during the course of the project.

45. **Implementation of Construction Traffic Management Plan**

All works and construction activities are to be undertaken in accordance with the approved Construction Traffic Management Plan (CTMP). All controls in the CTMP must be maintained at all times and all traffic management control must be undertaken by personnel having appropriate TfNSW accreditation. Should the implementation or effectiveness of the CTMP be impacted by surrounding major development not encompassed in the approved CTMP, the CTMP measures and controls are to be revised accordingly and submitted to Council for approval. A copy of the approved CTMP is to be kept onsite at all times and made available to Council on request.

Reason: To ensure compliance of the developer/builder in adhering to the Construction Traffic Management procedures agreed and are held liable to the conditions of consent.

46. **Ongoing Management**

The applicant shall be responsible in ensuring that the road reserve remains in a serviceable state during the course of the demolition and building works.

Reason: To ensure public safety.

47. **Removing, Handling and Disposing of Asbestos**

Any asbestos material arising from the demolition process shall be removed and disposed of in accordance with the following requirements:

- Work Health and Safety Act;
- Work Health and Safety Regulation;
- Code of Practice for the Safe Removal of Asbestos [NOHSC:2002 (1998)];
- Guide to the Control of Asbestos Hazards in Buildings and Structures [NOHSC: 3002 (1998)];
- Clause 42 of the Protection of the Environment Operations (Waste) Regulation 2005; and
- The demolition must be undertaken in accordance with Australian Standard AS2601 – The Demolition of Structures.

Reason: For the protection of the environment and human health.

48. **Geotechnical Requirements**

All recommendations (if any) included in the Geotechnical Report referenced in Condition 1 of this consent are required to be complied with during works.

Reason: To ensure geotechnical risk is mitigated appropriately.

49. **Demolition Works - Asbestos**

Demolition works must be carried out in compliance with WorkCover Short Guide to Working with Asbestos Cement and Australian Standard AS 2601 2001 The Demolition of Structures.

The site must be provided with a sign containing the words DANGER ASBESTOS REMOVAL IN PROGRESS measuring not less than 400 mm x 300 mm and be erected in a prominent visible position on the site. The sign is to be erected prior to demolition work commencing and is to remain in place until such time as all asbestos cement has been removed from the site and disposed to a lawful waste disposal facility.

All asbestos laden waste, including flat, corrugated or profiled asbestos cement sheets must be disposed of at a lawful waste disposal facility. Upon completion of tipping operations the applicant must lodge to the Principal Certifier, all receipts issued by the receiving tip as evidence



of proper disposal.

Adjoining property owners are to be given at least seven (7) days' notice in writing of the intention to disturb and remove asbestos from the development site.

Reason: To ensure the long term health of workers on site and occupants of the building is not put at risk unnecessarily.

50. **Survey Certificate**

A survey certificate prepared by a Registered Surveyor at the following stages of construction:

(a) Commencement of perimeter walls columns and or other structural elements to ensure the wall or structure, to boundary setbacks are in accordance with the approved details.

(b) At ground level to ensure the finished floor levels are in accordance with the approved levels, prior to concrete slab being poured/flooring being laid.

(c) At completion of the roof frame confirming the finished roof/ridge height is in accordance with levels indicated on the approved plans.

Details demonstrating compliance are to be submitted to the Principal Certifier.

Reason: To determine the height of buildings under construction comply with levels shown on approved plans.

51. **Property Boundary Levels**

The Applicant is to maintain the property boundary levels. No approval is granted for any change to existing property alignment levels to accommodate the development.

Details demonstrating compliance are to be submitted to the Principal Certifier.

Reason: To maintain the existing profile of the nature strip/road reserve.

52. **Footpath Construction**

The applicant shall construct full width urban stone paving in Fisher Road in accordance with the following:

(a) All footpath works are to be constructed in accordance with Section 138 Road Act approval

(b) Council is to inspect the formwork prior to pouring of concrete base to ensure the works are in accordance with Section 138 Road Act approval for footpath.

(c) All footpath paving works are to be in accordance with Councils Dee Why Town Centre specifications and Auspec One.

Details demonstrating compliance are to be submitted to the Principal Certifier.

Reason: To ensure compliance of footpath works with Council's specification for engineering works.

53. **Traffic Control During Road Works**

Lighting, fencing, traffic control and advanced warning signs shall be provided for the protection

of the works and for the safety and convenience of the public and others in accordance with RMS Traffic Control At Work Sites Manual (<http://www.rms.nsw.gov.au/business-industry/partners-suppliers/documents/technical-manuals/tcws-version-4/tcwsv4i2.pdf>) and to the satisfaction of the Roads Authority. Traffic movement in both directions on public roads, and vehicular access to private properties is to be maintained at all times during the works

Reason: Public Safety.

54. **Vehicle Crossings**

The Applicant is to construct one vehicle crossing 5 metres wide in accordance with Northern Beaches Council Drawing No A4-3330/ Normal and the driveway levels application approval. An Authorised Vehicle Crossing Contractor shall construct the vehicle crossing and associated works within the road reserve in plain concrete. All redundant laybacks and crossings are to be restored to footpath/grass. Prior to the pouring of concrete, the vehicle crossing is to be inspected by Council and a satisfactory "Vehicle Crossing Inspection" card issued.

A copy of the vehicle crossing inspection form is to be submitted to the Certifier.

Reason: To facilitate suitable vehicular access to private property.

55. **Waste Management During Development**

The reuse, recycling or disposal of waste during works must be done generally in accordance with the Waste Management Plan for this development.

Details demonstrating compliance must be submitted to the Principal Certifier.

Reason: To ensure demolition and construction waste is recycled or reused and to limit landfill.

56. **Waste/Recycling Requirements (Waste Plan Submitted)**

During demolition and/or construction the proposal/works shall be generally consistent with the submitted Waste Management Plan titled dated 12/8/2022.

Reason: To ensure waste is minimised and adequate and appropriate waste and recycling facilities are provided.

57. **Waste/Recycling Requirements (Materials)**

During demolition and/or construction the following materials are to be separated for recycling: timber, bricks, tiles, plasterboard, metal, concrete, and evidence of disposal for recycling is to be retained on site.

Reason: To ensure waste is minimised and recovered for recycling where possible.

58. **Heavy Excavation Respite Periods**

During the works that relate to the basement excavation, there shall be a respite period between the hours of 10am and 12pm, Monday to Friday, that no heavy excavation or rock breaking shall be carried out.

The requirement shall be incorporated into any construction management plan prepared for the development.

Reason: To ensure that periods of respite are provided to the surrounding residents and business during business hours.

59. **Registration of food Business**

The food business must be registered with the Appropriate Regulatory Authority, prior to Occupation Certificate being issued.

Reason: Food premises are required to be registered with the Appropriate Regulatory Authority.

60. **Landscape Completion**

Landscape works are to be implemented in accordance with the approved Landscape Plan(s) (drawing 4 of 6, and 5 of 6 by Paul Scrivener dated 15 March 2023), and inclusive of the following conditions:

- a) landscape works are to be contained within the legal property boundaries,
- b) tree, shrub and groundcover planting shall be installed as indicated on the approved Landscape Plan(s),
- c) all tree planting shall meet the requirements of Natspec - Specifying Trees; planted into a prepared planting hole 1m x 1m x 600mm depth, backfilled with a sandy loam mix or approved similar, mulched to 75mm depth minimum and maintained, and watered until established; and located either within garden bed or within a prepared bed within lawn,
- d) all trees in the land area zone R3 shall be located at minimum 2.5 metres from buildings, and at least 1 metre from common boundaries,
- e) mass planting shall be installed in a garden bed prepared with a suitable free draining soil mix and minimum 75mm depth of mulch,
- f) all proposed tree planting shall be positioned in locations to minimise significant impacts on neighbours in terms of blocking winter sunlight to living rooms, private open space and where the proposed location of trees may otherwise be positioned to minimise any significant loss of views from neighbouring and nearby dwellings and from public spaces.

Prior to the issue of an Occupation Certificate, details (from a landscape architect, landscape designer or qualified horticulturalist) shall be submitted to the Principal Certifier, certifying that the landscape works have been completed in accordance with any conditions of consent.

Reason: Environmental amenity.

61. **Stormwater Disposal**

The stormwater drainage works on the site and in Fisher Road shall be certified as compliant with all relevant approved construction certificate plans and Councils water management for development policy by the design engineer. A compliance certificate is to be issued by a NER or RPENG qualified civil engineer. Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To ensure appropriate provision for the disposal of stormwater arising from the development.

62. **Post-Construction Road Reserve Dilapidation Report (Major Development)**

The applicant must bear the cost of all restoration works to Council's road, footpath and drainage assets damaged during the course of this development.

A Post Construction Dilapidation Report after the completion of all building works is to demonstrate that there is no damage to Council infrastructure prior to the refund of any security deposits.

Reason: To ensure security against possible damage to Council property.

63. **Certification for the Installation of Stormwater Treatment Measures**

A certificate from a Civil Engineer, who has membership to Engineers Australia and the National Engineers Register must be provided, stating that the stormwater treatment measures have been installed in accordance with the plans prepared by The George Group Pty Ltd. The certificate must confirm that stormwater treatment measures are completed, online, in good condition and are not impacted by sediment. Vegetated measures must exhibit an 80 percent survival rate of plantings.

The certificate shall be submitted to the Principal Certifier prior to the release of an Occupation Certificate.

Reason: Protection of the receiving environment.

**64. Positive Covenant, Restriction as to User and Registration of Encumbrances for Stormwater Treatment Measures**

A positive covenant shall be created on the title of the land requiring the proprietor of the land to maintain the stormwater treatment measures in accordance with the standard requirements of Council, the manufacturer and as required by the Stormwater Treatment Measures Operation and Maintenance Plan.

A restriction as to user shall be created on the title over the stormwater treatment measures, restricting any alteration to the measures.

The terms of the positive covenant and restriction as to user are to be prepared to Council's standard requirements (available from Council) at the applicant's expense and endorsed by the Northern Beaches Council's delegate prior to lodgement with the Department of Lands. Northern Beaches Council shall be nominated as the party to release, vary or modify such covenant.

A copy of the certificate of title demonstrating the creation of the positive covenant and restriction as to user is to be submitted to the Principal Certifier prior to the issue of the Occupation Certificate.

Reason: To identify encumbrances on land, ensure ongoing maintenance, and ensure modification to the stormwater treatment measures is not carried out without Council's approval.

**65. Stormwater Treatment Measures Operation and Maintenance Plan**

An Operation and Maintenance Plan is to be prepared to ensure the proposed stormwater treatment measures remain effective.

The Plan must be attached to the Positive Covenant (and the community or strata management statement if applicable) and contain the following:

**1. Detail on the stormwater treatment measures:**

- a) Work as executed drawings
- b) Intent of the stormwater treatment measures including modelled pollutant removal rates
- c) Site detail showing catchment for each device
- d) Vegetation species list associated with each type of vegetated stormwater treatment measure
- e) Impervious area restrictions to maintain the water balance for the site
- f) Funding arrangements for the maintenance of all stormwater treatment measures
- g) Identification of maintenance and management responsibilities
- h) Maintenance and emergency contact information

**2. Maintenance schedule and procedure - establishment period of one year following commissioning of the stormwater treatment measure:**

- a) Activity description, and duration and frequency of visits

Additionally for vegetated devices:

- b) Monitoring and assessment to achieve an 80 percent survival rate for plantings
- c) Management of weeds, pests and erosion, with weed and sediment cover limited to a maximum of 5 percent of the total area of the stormwater treatment measure

3. Maintenance schedule and procedure - ongoing

- a) Activity description, and duration and frequency of visits
- b) Routine maintenance requirements
- c) Work Health and Safety requirements
- d) Waste management and disposal
- e) Traffic control (if required)
- f) Renewal, decommissioning and replacement timelines and activities of all stormwater treatment measures (please note that a DA may be required if an alternative stormwater treatment measure is proposed)
- g) Requirements for inspection and maintenance records, noting that these records are required to be maintained and made available to Council upon request.

Details demonstrating compliance shall be submitted to the Principal Certifier prior to the release of the Occupation Certificate.

Reason: Protection of the receiving environment.

66. **Works as Executed Drawings - Stormwater Treatment Measures**

Works as Executed Drawings for the stormwater treatment measures must be prepared in accordance with Council's Guideline for Preparing Works as Executed Data for Council Stormwater Assets.

The drawings shall be submitted to the Principal Certifier prior to the release of the Occupation Certificate.

Reason: Protection of the receiving environment.

67. **Community Title Management Statement**

The Community Management Statement must specifically list the stormwater treatment measures that will be maintained under community title. The statement must also include the Stormwater Treatment Measure Operation and Maintenance Plan.

Details demonstrating compliance shall be submitted to the Principal Certifier prior to the release of the Occupation Certificate.

Reason: To ensure maintenance of all stormwater management assets and protection of the receiving environment.

68. **Maintenance of Stormwater Treatment Measures**

The Boarding House Operational Management Plan list the stormwater treatment measures that will be maintained by building management via a management statement. The statement must also include the Stormwater Treatment Measure Operation and Maintenance Plan. The management statement shall be prepared by a suitably qualified person.

Details demonstrating compliance shall be submitted to the Principal Certifier prior to the release of the Occupation Certificate.

Reason: To ensure maintenance of all stormwater management assets and protection of the receiving environment.

69. **Signage and Linemarking – Implementation**

The applicant is to install all signage and linemarking, as per any Roads Act approval. These works are to be completed prior to the issue of an Occupation Certificate.

Reason: To ensure compliance with the Road Act.

**70. Basement Garage Traffic Signal System**

To prevent conflicting vehicle flows on the internal basement garage ramps and avoid vehicles having to reverse up/ down the ramp, a traffic signal system must be installed at each ramp entry, designed to warn drivers about to enter the road of any conflicting vehicle approaching.

The signal system must;

- be clearly visible from ramp entrances,
- is to clearly indicate to an approaching driver, by way of red light or wording, that an opposing vehicle has entered the ramp,
- Incorporate linemarking to delineate traffic flow and nominate waiting bay locations to allow vehicles to overtake another.

Details of the system, including the system operation, components and placement within the development, must be specified by a practising Traffic Engineer. This engineer is to submit a compliance certificate to the Principal Certifier that the system has been installed and operating as designed, in accordance with the requirements of this condition, prior to the issue of an Occupation Certificate issued for the development.

Reason: To ensure no vehicle conflicts within the basement carpark.

**71. Signage and Linemarking - Internal**

A plan demonstrating appropriate wayfinding signage for cyclists is to be submitted to the Principal Certifier prior to the issue of any Occupation Certificate.

Reason: to maintain cyclist safety.

**72. Allocated Parking Spaces**

Parking allocated to this development must be clearly signposted and linemarked as being for the use of "church", "boarding house", "manager", "Cafe", "Loading" , Motor Bike". Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of any Occupation Certificate.

Reason: To ensure parking availability.

**73. Disabled Parking Spaces**

Where disabled parking spaces are provided they must be in accordance with AS2890.6:2009.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of any Occupation Certificate.

Reason: To ensure compliance with Australian Standards.

**74. Convex Mirror at Ramps**

A convex mirror together with Give-Way priority signage and line marking is to be installed and maintained at the upper basement carpark level to improve the visibility of oncoming vehicles from the upper level ramp to vehicles on the ramp leading from the lower basement carpark level. The Give Way priority is to be installed at the top point of the ramp. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any Occupation Certificate.



Reason: To minimise vehicular conflicts at ramps.

**75. Positive Covenant for Registered Community Housing Provider to operate boarding house**

A positive covenant pursuant to Section 88E of the Conveyancing Act 1919 shall be registered on the title of the land to which this consent applies, prior to the issue of a Occupation Certificate, requiring the proprietor of the land to require that:

- a) The boarding house is to be used for affordable housing in perpetuity (the meaning of 'affordable housing' being defined under the SEPP (Housing) 2021) and;
- b) require that the boarding house to be managed by a registered community housing provider in perpetuity.

The terms of the positive covenant are to be prepared to Council's requirements at the applicant's expense and endorsed by Council prior to lodgement with NSW Land Registry Services. Northern Beaches Council shall be nominated as the party to release, vary or modify such covenant.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the occupation of the building.

Reason: To ensure ongoing and continued use as affordable housing in accordance with state legislation.

**76. Post-Construction Dilapidation Report**

Post-Construction Dilapidation Reports, including photos of any damage evident at the time of inspection, must be submitted after the completion of works. The report must:

- Compare the post-construction report with the pre-construction report,
- Clearly identify any recent damage and whether or not it is likely to be the result of the development works,
- Should any damage have occurred, suggested remediation methods.

Copies of the reports must be given to the property owners referred to in the Pre-Construction Dilapidation Report Condition. Copies must also be lodged with Council.

Details demonstrating compliance with this condition are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To maintain proper records in relation to the proposed development.

**77. Geotechnical Certification Prior to Occupation Certificate**

A Geotechnical Engineer or Engineering Geologist is to provide written confirmation that they have inspected the site during construction or reviewed information relating to the construction and that they are satisfied that development referred to in the development consent has been constructed in accordance with the intent of the Geotechnical Report referenced in Condition 1 of this consent.

Written certification is to be provided to the Principal Certifier prior to the issue of the Occupation Certificate.

Reason: To ensure geotechnical risk is mitigated appropriately.

**78. Reinstatement of Kerb**

The Applicant shall reinstate all redundant laybacks and vehicular crossings to conventional kerb and gutter, footpath or grassed verge as appropriate with all costs borne by the applicant.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To facilitate the preservation of on street parking spaces.

79. **Positive Covenant and Restriction as to User for On-site Stormwater Disposal Structures**

The Applicant shall lodge the Legal Documents Authorisation Application with the original completed request forms (NSW Land Registry standard forms 13PC and/or 13RPA) to Council and a copy of the Works-as-Executed plan (details overdrawn on a copy of the approved drainage plan), hydraulic engineers' certification.

The Applicant shall create on the Title a restriction on the use of land and a positive covenant in respect to the ongoing maintenance and restriction of the on-site stormwater disposal structures within this development consent. The terms of the positive covenant and restriction are to be prepared to Council's standard requirements at the applicant's expense and endorsed by Northern Beaches Council's delegate prior to lodgement with the NSW Land Registry Services. Northern Beaches Council shall be nominated as the party to release, vary or modify such covenant. A copy of the certificate of title demonstrating the creation of the positive covenant and restriction for on-site storm water detention as to user is to be submitted.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To ensure the on-site stormwater disposal system is maintained to an appropriate operational standard.

80. **Maintenance contract for stormwater treatment measures**

A minimum of a five-year contract with a suitably qualified provider is required for the maintenance of the stormwater treatment measures.

A copy of the maintenance contract must be submitted to the Principal Certifying Authority prior to the issue of the Occupation Certificate.

Reason: To ensure maintenance of the stormwater treatment measures.

81. **Access for residential Waste collection**

The path from the kerb to the residential bin room is to have no 90 degree bends, have no steps and to be a smooth hard non-slip finish.

Any gates and doors must be unlocked on scheduled collection days and able to be latched in the open position during the collection process.

Reason: To ensure a safe and efficient waste collection service

82. **Boarding House Plan of Management**

Prior to the issuing of an Occupation Certificate, certification is to be provided from the operator that the requirements of the Boarding House Plan of Management have been implemented and are compliant and a copy sent to Council for its records.

The Plan of Management for the Boarding House shall be updated to include the following control measures:

- i The use of the outdoor communal area shall be restricted to between the hours of 7:00am and 10:00pm daily.
- i No amplified music is permitted at ANY time within the outdoor communal area.
- i Live music will not be permissible on the premises at ANY time.
- i A complaints and incident register being maintained on site.
- i That a 24 hour telephone contact number is to be available for members of the public to register a complaint or comment about the premises;
- i Signage is to be posted on the outside of the building with the contact details of the boarding house manager;
- i Measures for limiting noise from amplified noise within the indoor communal areas including the MP communal zone on the top level;
- i The plan of management shall be updated to reflect the number of boarding rooms approved under this application (being 51 rooms plus managers room) and number of persons to be accommodated within the boarding house (being a maximum of 102 occupants plus manager)

The boarding house plan of management is to be reviewed on an annual basis by the boarding house operator. Should there be any changes to the plan of management or changes to the above requirements, the applicant is to seek approval in writing from Council.

Reason: To ensure the premises are managed in an appropriate manner in perpetuity.

83. **Kitchen Design, construction and fit out of food premises certification**

Prior to the issuing of any occupation certificate, certification is to be provided to the Principal Certifier by a suitably qualified person demonstrating that the design, construction and fit out of food premises kitchen is compliant with the requirements of AS 4674 Design, construction and fit out of food premises.

Reason: To ensure that the kitchen complies with Australian Standard design requirements.

84. **Mechanical Ventilation certification**

Where Mechanical ventilation is required to be installed in the food premises it must comply with the following:

- i Australian Standard (AS) 1668.2 "The use of ventilation and air-conditioning in buildings - Mechanical ventilation in buildings"; and
- i Any external exhaust discharge must be above the roofline and discharged in a manner that is not likely to cause an amenity impact.
- i Demonstrate that there is adequate provision of smoke and odour control equipment to prevent any nuisance to neighboring residential premises and the roof deck common area.

Certification is to be provided to the Principal Certifier prepared by a suitably qualified person to demonstrate that the mechanical ventilation complies with the above requirements.

Reason: To ensure that the installed mechanical ventilation complies with the requirements of the Australian Standard 1668.2 and to prevent amenity impacts.

85. **Noise Related Criteria prior to any Occupation Certificate being issued**

Prior to an Occupation Certificate being issued, a full on site review and certification of compliance with the recommendations of the acoustic assessment by TTM Consulting Pty Ltd 20SYA0029 R01\_1 dated 8 August 2022 shall be carried out by a suitably qualified person including but not limited to:

A. Mechanical Plant Noise

Plant will need to be reviewed and if necessarily acoustically treated to prevent noise emissions

from adversely impacting NSRs. This may include selecting the quietest plant possible, or treating the plant and equipment with enclosures, acoustic louvres, barriers, duct lining and silencers, etc.

Mechanical plant where possible to be installed away from residential boundaries and bedroom windows in order to avoid direct line of sight to minimise noise impact during the night-time period.

A detailed mechanical plant noise assessment must be conducted by a suitably qualified acoustic consultant once plant selections are made. The noise assessment must include noise source levels of plant, location, adjustments for mechanical plant noise characteristics and application of practical and effective noise control to verify compliance with the relevant noise criteria derived in this report.

**B. Management of Auditorium being included in an up dated Plan of Management (copy to Council for its records)**

The use of the auditorium is not expected to cause any significant impact onto nearby NSRs. However, the following management practices are recommended to ensure the noise limits are adhered to, such as:

- Installation of loudspeakers facing away from the any opening of the area, such as windows and doors.
- Installation of individual speakers at least 3 metres apart.
- The door to the foyer may remain open.
- The premises shall not conduct live entertainment after 10pm. All amplified music or speech should be stopped before 10pm.
- Crowd management control measures are to be implemented to focus on the following:  
 Ensure a clear flow of people in and around the area.  
 Minimise crowd gatherings on the footpath, especially after 10pm.  
 Direct people to the exit areas, such as basement car parking, to ensure all crowds are dispersed smoothly after gatherings.

**C. Management of Rooftop Communal Areas being included in an up dated Plan of Management (copy to Council for its records)**

- Restrict access to the day and evening assessment periods only, which is from 7am to 10pm, or 8am to 10pm on Sundays and public holidays.
- Restrict access to the roof terrace between the hours of 10pm and 7am, 7 days a week.
- Provide clear instructions to the residents on maintaining responsible social practices at all times.

Reason: To ensure that adequate acoustic measures and the Plan of Management is implemented and a noise nuisance is not created to any residential receiver.

**86. Lighting**

Prior to the issuing of any Occupation Certificate, certification is to be provided that any outdoor lighting does not detrimentally impact upon the amenity of other premises and complies with where relevant, Australia Standard AS 1158.3:2005 Lighting for roads and public spaces – Pedestrian Area (Category P) lighting – Performance and design requirements and Australian Standard AS 4282:2019 Control of the obtrusive effects of outdoor lighting.

Reason: To protect the amenity of adjoining properties

**87. Removal of All Temporary Structures/Material and Construction Rubbish**

Once construction has been completed all silt and sediment fences, silt, rubbish, building debris, straw bales and temporary fences are to be removed from the site.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To ensure bushland management.

**88. Garbage and Recycling Facilities**

All internal walls of the waste rooms shall be rendered to a smooth surface, coved at the floor/wall intersection, graded and appropriately drained to the sewer with a tap in close proximity to facilitate cleaning.

Waste room floors shall be graded and drained to an approved Sydney Water drainage system.

Waste rooms shall be clear of any other services or utilities infrastructure such as gas, electricity air-conditioning, plumbing, piping ducting or equipment.

Reason: To prevent pollution of the environment, provide a safe workplace for contractors and residents and to protect the amenity of the area.

**89. House / Building Number**

The building number is to be affixed to the building to be readily visible from the public domain.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: Proper identification of buildings.

**90. Unit Numbering for Multi Unit Developments (Residential, Commercial and Industrial)**

The units within the development are to be numbered in accordance with NSW Address Policy and User Manual.

In this regard, the numbering is to be as per the Unit Numbering for Multi Unit Development Table available on Council's website Unit Numbering for Multi-Unit Developments Form

External directional signage is to be erected on site at driveway entry points and on buildings and is to reflect the numbering in the table provided. Unit numbering signage is also required on stairway access doors and lobby entry doors.

It is essential that all signage throughout the complex is clear to assist emergency service providers in locating a destination within the development with ease and speed, in the event of an emergency.

Details are to be submitted with any Occupation Certificate or Strata Subdivision Certificate certifying that the numbering has been implemented in accordance with this condition and the Unit Numbering for Multi Unit Development Table.

Reason: To ensure consistent numbering for emergency services access.

**91. Waste Management Confirmation**

Prior to the issue of an Occupation Certificate, evidence / documentation must be submitted to the Principal Certifier that all waste material from the development site arising from demolition and/or construction works has been appropriately recycled, reused or disposed of generally in accordance with the approved Waste Management Plan.

Reason: To ensure demolition and construction waste is recycled or reused and to limit landfill.

92. **Sydney Water**

A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained from Sydney Water Corporation.

Application must be made through an authorised Water Servicing Co-ordinator. Please refer to the Building Developing and Plumbing section of the web site [www.sydneywater.com.au](http://www.sydneywater.com.au) <<http://www.sydneywater.com.au>> then refer to “Water Servicing Coordinator” under “Developing Your Land” or telephone 13 20 92 for assistance.

Following application a “Notice of Requirements” will advise of water and sewer infrastructure to be built and charges to be paid. Please make early contact with the Co-ordinator, since building of water/sewer infrastructure can be time consuming and may impact on other services and building, driveway or landscape design.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To ensure compliance with the statutory requirements of Sydney Water.

93. **Fire Safety Matters**

At the completion of all works, a Fire Safety Certificate will need to be prepared which references all the Essential Fire Safety Measures applicable and the relative standards of Performance (as per Schedule of Fire Safety Measures). This certificate must be prominently displayed in the building and copies must be sent to Council and the NSW Fire Brigade.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Each year the Owners must send to the Council and the NSW Fire Brigade an annual Fire Safety Statement which confirms that all the Essential Fire Safety Measures continue to perform to the original design standard.

Reason: Statutory requirement of the Environmental Planning and Assessment Regulation 2021.

94. **No Parking restriction**

Given the location of the driveway south of a crest and near a bend, the inter-visibility between the exiting vehicles from the proposed driveway and approaching vehicles from the north is to be enhanced. This to be achieved by the installation of No Parking signage between the north of the proposed driveway and the northern driveway serving No. 11 Francis Street. An exemption to the No Parking restriction for waste collection vehicles during designated collection days and times is to apply. A plan demonstrating the proposed signage within Council’s Public Domain shall be prepared by a suitably qualified person and submitted to and approved by the Local Traffic Committee and installed at the applicant’s cost prior to the issue of any Occupation Certificate.

Note: The applicant is advised that the plan will require approval by the local Traffic Committee and hence, adequate time (at least 8 weeks) should be allowed for this process

Reason: To improve road safety



95. **Waste and Recycling Facilities Certificate of Compliance**

The proposal shall be constructed in accordance with the Northern Beaches Waste Management Guidelines.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To ensure waste and recycling facilities are provided.

96. **Waste/Recycling Compliance Documentation**

Evidence of disposal for recycling from the construction/demolition works shall be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To ensure waste is minimised and recycled.

97. **Positive Covenant for Council and Contractor Indemnity**

A positive covenant shall be created on the title of the land prior to the issue of an Occupation Certificate requiring the proprietor of the land to provide access to the waste storage facilities. The terms of the positive covenant are to be prepared to Council's requirements, (Appendix E of the Waste Management Guidelines), at the applicant's expense and endorsed by Council prior to lodgement with NSW Land Registry Services. Northern Beaches Council shall be nominated as the party to release, vary or modify such covenant.

Reason: To ensure ongoing access for servicing of waste facilities.

98. **Authorisation of Legal Documentation Required for Waste Services**

The original completed request form (NSW Land Registry Services form 13PC) must be submitted to Council for authorisation prior to the issue of an Occupation Certificate. A copy of the work-as-executed plan (details overdrawn on a copy of the approved plan) must be included with the above submission. Where required by Council or the Principal Certifier, a Compliance Certificate shall also be provided in the submission to Council.

If Council is to issue the Compliance Certificate for these works, the fee is to be in accordance with Council's Fees and Charges.

Reason: To create encumbrances on the land.

## **ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES**

99. **Landscape Maintenance**

If any landscape materials/components or planting under this consent fails, they are to be replaced with similar materials/components. Trees, shrubs and groundcovers required to be planted under this consent are to be mulched, watered and fertilised as required at the time of planting. If any tree, shrub or groundcover required to be planted under this consent fails, they are to be replaced with similar species to maintain the landscape theme and be generally in accordance with the approved Landscape Plan(s) and any conditions of consent.

A maintenance activity schedule for on-going maintenance of planters on slab shall be incorporated to monitor and replenish soil levels as a result of soil shrinkage over time.

The approved landscaped area shall in perpetuity remain as planting under the development consent.

Reason: To maintain local environmental amenity.

**100. Maintenance of Stormwater Treatment Measures - Major**

Stormwater treatment measures must be maintained at all times in accordance with the Stormwater Treatment Measure Operation and Maintenance Plan, manufacturer's specifications and as necessary to achieve the required stormwater quality targets for the development.

Vegetated stormwater treatment measures must maintain an 80 percent survival rate of plantings and limit weed cover to no more than 10 percent of the total area of the stormwater treatment measure.

Where replacement cartridges or other necessary components for the system become unavailable, an alternative system is required to be retrofitted into the development to achieve an equivalent pollutant reduction outcome. Evidence supporting the replacement must be retained on site and made available to Council as required.

Northern Beaches Council reserves the right to enter the property and carry out appropriate maintenance of the device at the cost of the property owner.

Reason: Protection of the receiving environment.

**101. Sight lines within carparks**

The required sight lines to pedestrians and other vehicles in and around the carpark and entrance(s) are not to be obstructed by landscaping or signage. The planting or signage on any land immediately adjacent to the driveway/property boundary intersection must not exceed a height of 1m

Reason: To maintain unobstructed sight distance for motorists.

**102. Collection of Commercial and Church waste**

Collection of commercial and Church waste should occur from within the property and it should not be presented on the footpath for collection. Council does not collect commercial waste and private arrangements must be made for its collection.

Reason: To ensure public safety and protect the amenity of the area

**103. Geotechnical Recommendations**

Any ongoing recommendations of the risk assessment required to manage the hazards identified in the Geotechnical Report referenced in Condition 1 of this consent are to be maintained and adhered to for the life of the development.

Reason: To ensure geotechnical risk is mitigated appropriately.

**104. Boarding House Plan of Management**

The boarding house shall operate in accordance with the document titled "Plan of Management for Boarding House" prepared by The George Group dated 16/03/2023 (as amended by the conditions of this consent). A copy of the plan of management shall be kept on the premises at all times and provided to each boarding house resident.

Reason: Protect the amenity of the area.

**105. Proposed Outdoor Dining Condition**

No outdoor dining is approved in this consent. Any proposed outdoor dining must be consistent with State Environmental Planning Policy (Exempt and Complying Development Codes) 2008.

Any outdoor dining that is consistent with the SEPP shall be the subject of a separate Outdoor Dining Application to Council's Property team.

Reason: To ensure that outdoor dining is assessed and approved under the appropriate regulatory framework and legislation.

**106. Dewatering Management**

Council proactively regulates construction sites for sediment management.

Discharge of groundwater or tailwater must achieve the following water quality targets in addition to any conditions/ documentation of this consent, any requirements of the General Terms of Approval/Controlled Activity permit issued by WaterNSW (if applicable), Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004) (Blue Book), Council's Compliance and Enforcement Policy and legislation including Protection of the Environment Operations Act 1997 and Contaminated Lands Act 1997.

Water Quality (<one hour of planned discharge)

Oil and grease, not visible

pH, 6.5-8.5

Total Suspended Solids (TSS), <50mg/L NTU from a meter/grab sample

NOTE: The correlation between NTU and TSS must be established by a NATA accredited laboratory prior to the commencement of dewatering activities.

All records of water discharges and monitoring results are to be documented and kept on site. Copies of all records shall be provided to the appropriate regulatory authority, including Council, upon request.

Tailwater must be discharged to the nearest stormwater pit in accordance with Council's Auspec1 Design Manual and must not spread over any road, footpath and the like. Discharge to the kerb and gutter will not be accepted. If an alternative solution is required, you must contact Council's Catchment Team at [catchment@northernbeaches.nsw.gov.au](mailto:catchment@northernbeaches.nsw.gov.au)

Reason: Protection of the receiving environment

**107. Reporting of stormwater treatment measures maintenance**

As a minimum, the owner of the stormwater treatment measures is required to submit an annual maintenance report to Council by 1 September each year.

This report must detail the inspection and maintenance activities carried out on-site over the previous 12 months, including any waste disposal dockets.

Reports must be submitted from commissioning of the stormwater treatment measures until five years after the issue of occupation certificates for a minimum of 70 percent of the development lot(s).

Council reviews the reports to ensure appropriate maintenance is occurring and is authorised under the Local Government Act 1993 to enter premises and serve penalty notices for failure to comply with maintenance requirements set out in the Positive Covenant.

Reports must be directed to Council's Environment (Catchments) Team at [catchment@northernbeaches.nsw.gov.au](mailto:catchment@northernbeaches.nsw.gov.au).

**108. Management of residential waste bin room**

The building manager is responsible for ensuring no waste is left in the residential bin room which is not contained within a bin. Bins must have lids closed for collection. If the bin room is not clear of waste which is not in bins and the lids of bins are not closed, then the building manager is responsible for the clearing of waste from the room prior and correct presentation of waste in the room for the subsequent scheduled collection.

Reason: To ensure a safe and efficient waste collection service.

**109. Auditorium Noise**

The following noise conditions are to be adhered to:

- A. Compliance with the Plan of Management and acoustic recommendations.
- B. The LA10 noise level emitted from the premises shall not exceed the background noise level in any Octave Band Centre (31.5 Hz – 8 kHz inclusive) by more than 5 dB between 7am and 10pm at the boundary of any affected residence.
- C. The premises shall not conduct live entertainment after 10pm.
- D. Amplified loudspeakers shall not be directed towards any footpath or face any external openings from building boundary walls.

Reason: To protect the acoustic amenity of neighbouring properties.

**110. Hours of Operation**

The hours of operation for the café and church/auditorium use are to be restricted to:

Cafe

- 6am to 6pm - Seven (7) days a week

Church/auditorium

- 7am to 10pm - Seven (7) days a week

Upon expiration of the permitted hours, all service (and entertainment) shall immediately cease, no patrons shall be permitted entry and all customers on the premises shall be required to leave within the following 30 minutes.

Reason: to ensure that amenity of the surrounding locality is maintained.

**111. Commercial Waste Collection**

Waste and recyclable material, generated by this premises, must not be collected between the hours of 10pm and 6am on any day.

Reason: To protect the acoustic amenity of surrounding properties.

**112. Commercial Waste and Recycling Storage**

Commercial waste and recycling material/storage bins must be stored in a separate area to the

residential waste and recycling material/storage bins as shown on the approved plans.

Reason: To ensure that commercial waste and residential waste is not mixed and is properly managed.

**113. Occupancy and Management of Boarding House**

The occupancy and management of the boarding house is be in accordance with the following:

1. The boarding house is to contain a maximum of 102 persons (and a manager), being no more than 2 persons per designated bedroom. In order to maintain this occupancy rate, a sign is to be erected immediately adjacent to the doorway accessing the boarding house detailing the maximum sleeping capacity of the occupancy.

2. The Plan of Management shall be updated to reflect the above occupancy numbers and shall be implemented throughout occupancy and a copy being maintained on site.

Should there be any changes to the above in relation to management and occupancy, the applicant to seek approval in writing from Council.

Reason: To ensure the amenity of occupants and neighbouring residential occupiers.

**114. Commercial Waste and Recycling Storage**

Commercial waste and recycling material/storage bins must be stored in a separate area to the residential waste and recycling material/storage bins.

Reason: To ensure that commercial waste and residential waste is not mixed and is properly managed.

**115. Noise from Air Conditioning Equipment**

Any mechanical equipment associated with the air conditioning units shall not produce noise that exceeds 5dBA above the background noise when measured from the nearest property boundary.

Reason: To ensure that the development does not impact on the acoustic privacy of surrounding residential properties

**116. Parking Enclosures**

No parking spaces, or access thereto, shall be constrained or enclosed by any form of structure such as fencing, cages, walls, storage space, or the like, without prior consent from Council.

Reason: To ensure accessibility is maintained.