

CONDITIONS OF APPROVAL

Application Number:	DA2019/1346
Land to be developed (Address):	Lot 1 DP 1220196, 4 - 10 Inman Road CROMER NSW 2099
Proposed Development:	Demolition works and alternations and additions to an existing industrial facility, including new warehouse, and self-storage, office premises and ancillary café.

DEVELOPMENT CONSENT OPERATIONAL CONDITIONS

1. Approved Plans and Supporting Documentation

The development must be carried out in compliance (except as amended by any other condition of consent) with the following:

a) Approved Plans

Architectural Plans - Endorsed with Council's stamp		
Drawing No.	Dated	Prepared By
DA101-C Rev.12 (Image 01 - External Finishes)		SBA Architects
DA201 Rev.12 (Site Plan)	12.11.2019	SBA Architects
DA202 Rev.12 (Ground Floor Plan)	06.11.2019	SBA Architects
DA203 Rev.12 (Basement Plan)	12.11.2019	SBA Architects
DA204 Rev.12 (Level 1 Floor Plan)	12.11.2019	SBA Architects
DA205 Rev.12 (Typical Offices 150sqm Plans and Elevations)	12.11.2019	SBA Architects
DA206 Rev.12 (Typical Offices 250sqm Plans and Elevations)	12.11.2019	SBA Architects
DA207 Rev.12 (Roof Plan)	12.11.2019	SBA Architects
DA208 Rev.12 (Demolition Plan)	12.11.2019	SBA Architects
DA301 Rev.12 (Elevations)	12.11.2019	SBA Architects
DA302 Rev.12 (Elevations 2)	12.11.2019	SBA Architects
DA305 Rev.12 (Sections)	12.11.2019	SBA Architects
DA306 Rev.12 (Sections 2)	12.11.2019	SBA Architects

Engineering Plans		
Drawing No.	Dated	Prepared By
C013674.01 - DA20 Issue B (Erosion & Sediment Control Plan)	28.02.20	Costin Roe Consulting Pty Ltd
C013674.01 - DA25 Issue A (Erosion & Sediment Control Plan)	26.11.19	Costin Roe Consulting

Sediment Control Details - Sheet 1)		Pty Ltd
C013674.01 - DA26 Issue A (Erosion & Sediment Control Details - Sheet 2)	26.11.19	Costin Roe Consulting Pty Ltd
C013674.01 - DA41 Issue C (Stormwater Drainage Plan - Ground Level)	28.02.20	Costin Roe Consulting Pty Ltd
C013674.01 - DA42 Issue B (Stormwater Drainage Plan - Basement)	26.11.19	Costin Roe Consulting Pty Ltd
C013674.01 - DA45 Issue B (Stormwater Details - Sheet 1)	26.11.19	Costin Roe Consulting Pty Ltd
C013674.01 - DA46 Issue B (Stormwater Details - Sheet 2)	26.11.19	Costin Roe Consulting Pty Ltd
C013674.01 - DA47 Issue B (Stormwater Details - Sheet 3)	26.11.19	Costin Roe Consulting Pty Ltd
C013674.01 - DA48 Issue A (Stormwater Details - Sheet 4)	26.11.19	Costin Roe Consulting Pty Ltd
C013674.01 - DA51 Issue C (Finished Levels Plan - Ground Level)	28.02.20	Costin Roe Consulting Pty Ltd
C013674.01 - DA52 Issue C (Finished Levels Plan - Basement)	28.02.20	Costin Roe Consulting Pty Ltd
C013674.01 - DA55 Issue B (Typical Sections - Sheet 1)	28.02.20	Costin Roe Consulting Pty Ltd
C013674.01 - DA56 Issue A (Typical Sections - Sheet 2)	28.02.20	Costin Roe Consulting Pty Ltd
C013674.01 - DA57 Issue A (Typical Sections - Sheet 3)	28.02.20	Costin Roe Consulting Pty Ltd
C013674.01 - DA65 Issue A (Retaining Wall Details)	26.11.19	Costin Roe Consulting Pty Ltd
C013674.01 - DA70 Issue A (Overland Flow Catchment Plan)	26.11.19	Costin Roe Consulting Pty Ltd
C013674.01 - DA71 Issue A (Pre-development Overland Flow Depth & Extent)	28.02.20	Costin Roe Consulting Pty Ltd
C013674.01 - DA72 Issue A (Post-development Overland Flow Depth & Extent)	28.02.20	Costin Roe Consulting Pty Ltd

Reports / Documentation – All recommendations and requirements contained within:		
Report No. / Page No. / Section No.	Dated	Prepared By
BCA Statement	13/11/2019	SBA Architects
Civil Engineering Report Rev.A	26/11/2019	Costin Roe Consulting Pty Ltd
Conservation Management Plan Issue 7	17/05/2019	Heritage 21 Pty Ltd
Statement of Heritage Impact Issue 4	11/11/2019	Heritage 21 Pty Ltd
Transport Impact Assessment Issue A	21/11/2019	GTA Consultants
Acoustic Assessment Report	20/11/2019	Acoustic Dynamics

Biodiversity Constraints Assessment	16/08/2017	Eco Logical Australia
Biodiversity Development Assessment Report (REF: 18EG02BDAR)	07/04/2020	Travers bushfire & ecology
Tree Assessment Report (REF: 18EG03T)	10 August 2018	Travers bushfire & ecology
Preliminary Geotechnical Assessment Rev.1 (Ref: 30766ZRpt)	18 August 2017	JK Geotechnics
Report on Desktop Groundwater Assessment (R.001.Rev1)	25 October 2019	Douglas Partners
Urban Design and Heritage Report Rev.2	1 November 2019	dfp planning consultants
Site Audit Report Rev.A	20 April 2018	AECOM Australia Pty Ltd
Overland Flow Report Rev.A	28 February 2020	Costin Roe Consulting Pty Ltd

b) Any plans and / or documentation submitted to satisfy the Conditions of this consent.

c) The development is to be undertaken generally in accordance with the following:

Landscape Plans		
Drawing No.	Dated	Prepared By
001 Issue B (Landscape Master Plan)	04.11.2019	Site Image
102 Issue B (Landscape Plan)	04.11.2019	Site Image
103 Issue B (Landscape Plan)	04.11.2019	Site Image
104 Issue B (Landscape Plan)	04.11.2019	Site Image
501 Issue C (Landscape Details)	06.11.2019	Site Image

Waste Management Plan		
Drawing No/Title.	Dated	Prepared By
Waste Management Plan Rev.2	30 October 2019	MRA Consulting Group

In the event of any inconsistency between conditions of this consent and the drawings/documents referred to above, the conditions of this consent will prevail.

Reason: To ensure the work is carried out in accordance with the determination of Council and approved plans.

2. **Compliance with Other Department, Authority or Service Requirements**

The development must be carried out in compliance with all recommendations and requirements, excluding general advice, within the following:

Other Department, Authority or Service	EDMS Reference	Dated
Ausgrid	Response Ausgrid Referral	17/01/2020
TfNSW	Response TfNSW (SYD20/00225/03)	28 April 2020
NSW EPA	DOC19/1061459-3	8 January 2020

Water NSW	Integrated Development Referral – General Terms of Approval Ref. IDAS1121681	26 February 2020
-----------	--	---------------------

(NOTE: For a copy of the above referenced document/s, please see Application Tracking on Council's website www.northernbeaches.nsw.gov.au)

Reason: To ensure the work is carried out in accordance with the determination and the statutory requirements of other departments, authorities or bodies.

3. **Approved Land Use**

Nothing in this consent shall authorise the use of site/onsite structures/units/tenancies as detailed on the approved plans for any land use of the site beyond the definition of a:

- **Warehouse or distribution centre** means a building or place used mainly or exclusively for storing or handling items (whether goods or materials) pending their sale, but from which no retail sales are made.
- **Storage premises** means a building or place used for the storage of goods, materials, plant or machinery for commercial purposes and where the storage is not ancillary to any industry, business premises or retail premises on the same parcel of land, and includes self-storage units, but does not include a heavy industrial storage establishment or a warehouse or distribution centre.
- **Office premises** means a building or place used for the purpose of administrative, clerical, technical, professional or similar activities that do not include dealing with members of the public at the building or place on a direct and regular basis, except where such dealing is a minor activity (by appointment) that is ancillary to the main purpose for which the building or place is used.
- **Restaurant or cafe** means a building or place the principal purpose of which is the preparation and serving, on a retail basis, of food and drink to people for consumption on the premises, whether or not liquor, take away meals and drinks or entertainment are also provided.

(development is defined by the Warringah Local Environment Plan 2011 (as amended) Dictionary)

Any variation to the approved land use and/occupancy of any unit beyond the scope of the above definition will require the submission to Council of a new development application.

Reason: To ensure compliance with the terms of this consent.

4. **Prescribed Conditions**

- (a) All building works must be carried out in accordance with the requirements of the Building Code of Australia (BCA).
- (b) BASIX affected development must comply with the schedule of BASIX commitments specified within the submitted BASIX Certificate (demonstrated compliance upon plans/specifications is required prior to the issue of the Construction Certificate);
- (c) A sign must be erected in a prominent position on any site on which building work, subdivision work or demolition work is being carried out:
 - (i) showing the name, address and telephone number of the Principal Certifying Authority for the work, and
 - (ii) showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working

hours, and

- (iii) stating that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.

- (d) Residential building work within the meaning of the Home Building Act 1989 must not be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council) has given the Council written notice of the following information:

- (i) in the case of work for which a principal contractor is required to be appointed:
 - A. the name and licence number of the principal contractor, and
 - B. the name of the insurer by which the work is insured under Part 6 of that Act,
- (ii) in the case of work to be done by an owner-builder:
 - A. the name of the owner-builder, and
 - B. if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.

If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under becomes out of date, further work must not be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council) has given the Council written notice of the updated information.

- (e) Development that involves an excavation that extends below the level of the base of the footings of a building on adjoining land, the person having the benefit of the development consent must, at the person's own expense:
 - (i) protect and support the adjoining premises from possible damage from the excavation, and
 - (ii) where necessary, underpin the adjoining premises to prevent any such damage.
 - (iii) must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished.
 - (iv) the owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this clause, whether carried out on the allotment of land being excavated or on the adjoining allotment of land.

In this clause, allotment of land includes a public road and any other public place.

Reason: Legislative requirement.

5. General Requirements

- (a) Unless authorised by Council:
Building construction and delivery of material hours are restricted to:
 - 7.00 am to 5.00 pm inclusive Monday to Friday,
 - 8.00 am to 1.00 pm inclusive on Saturday,
 - No work on Sundays and Public Holidays.

Demolition and excavation works are restricted to:

- 8.00 am to 5.00 pm Monday to Friday only.

(Excavation work includes the use of any excavation machinery and the use of jackhammers, rock breakers, excavators, loaders and the like, regardless of whether the activities disturb or alter the natural state of the existing ground stratum or are breaking up/removing materials from the site).

- (b) Should any asbestos be uncovered on site, its demolition and removal must be carried out in accordance with WorkCover requirements and the relevant Australian Standards.
- (c) At all times after the submission the Notice of Commencement to Council, a copy of the Development Consent and Construction Certificate is to remain onsite at all times until the issue of a final Occupation Certificate. The consent shall be available for perusal of any Authorised Officer.
- (d) Where demolition works have been completed and new construction works have not commenced within 4 weeks of the completion of the demolition works that area affected by the demolition works shall be fully stabilised and the site must be maintained in a safe and clean state until such time as new construction works commence.
- (e) Onsite toilet facilities (being either connected to the sewer or an accredited sewer management facility) for workers are to be provided for construction sites at a rate of 1 per 20 persons.
- (f) Prior to the release of the Construction Certificate, payment of the Long Service Levy is required. This payment can be made at Council or to the Long Services Payments Corporation. Payment is not required where the value of the works is less than \$25,000. The Long Service Levy is calculated on 0.35% of the building and construction work. The levy rate and level in which it applies is subject to legislative change. The applicable fee at the time of payment of the Long Service Levy will apply.
- (g) The applicant shall bear the cost of all works associated with the development that occurs on Council's property.
- (h) No skip bins, building materials, demolition or excavation waste of any nature, and no hoist, plant or machinery (crane, concrete pump or lift) shall be placed on Council's footpaths, roadways, parks or grass verges without Council Approval.
- (i) Demolition materials and builders' wastes are to be removed to approved waste/recycling centres.
- (j) No trees or native shrubs or understorey vegetation on public property (footpaths, roads, reserves, etc.) or on the land to be developed shall be removed or damaged during construction unless specifically approved in this consent including for the erection of any fences, hoardings or other temporary works.
- (k) Prior to the commencement of any development onsite for:
 - i) Building/s that are to be erected
 - ii) Building/s that are situated in the immediate vicinity of a public place and is dangerous to persons or property on or in the public place
 - iii) Building/s that are to be demolished
 - iv) For any work/s that is to be carried out
 - v) For any work/s that is to be demolished

The person responsible for the development site is to erect or install on or around the

development area such temporary structures or appliances (wholly within the development site) as are necessary to protect persons or property and to prevent unauthorised access to the site in order for the land or premises to be maintained in a safe or healthy condition. Upon completion of the development, such temporary structures or appliances are to be removed within 7 days.

- (l) A "Road Opening Permit" must be obtained from Council, and all appropriate charges paid, prior to commencement of any work on Council property. The owner/applicant shall be responsible for all public utilities and services in the area of the work, shall notify all relevant Authorities, and bear all costs associated with any repairs and/or adjustments as those Authorities may deem necessary.
- (m) The works must comply with the relevant Ausgrid Network Standards and SafeWork NSW Codes of Practice.
- (n) Requirements for new swimming pools/spas or existing swimming pools/spas affected by building works.
 - (1) Child resistant fencing is to be provided to any swimming pool or lockable cover to any spa containing water and is to be consistent with the following;

Relevant legislative requirements and relevant Australian Standards (including but not limited) to:

 - (i) Swimming Pools Act 1992
 - (ii) Swimming Pools Amendment Act 2009
 - (iii) Swimming Pools Regulation 2008
 - (iv) Australian Standard AS1926 Swimming Pool Safety
 - (v) Australian Standard AS1926.1 Part 1: Safety barriers for swimming pools
 - (vi) Australian Standard AS1926.2 Part 2: Location of safety barriers for swimming pools.
 - (2) A 'KEEP WATCH' pool safety and aquatic based emergency sign, issued by Royal Life Saving is to be displayed in a prominent position within the pool/spa area.
 - (3) Filter backwash waters shall be conveyed to the Sydney Water sewerage system in sewered areas or managed on-site in unsewered areas in a manner that does not cause pollution, erosion or run off, is separate from the irrigation area for any wastewater system and is separate from any onsite stormwater management system.
 - (4) Swimming pools and spas must be registered with the Division of Local Government.

Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community.

FEES / CHARGES / CONTRIBUTIONS

6. Policy Controls

Northern Beaches 7.12 Contributions Plan 2019

A monetary contribution of \$445,900.00 is payable to Northern Beaches Council for the provision of local infrastructure and services pursuant to section 7.12 of the Environmental Planning & Assessment Act 1979 and the Northern Beaches Section 7.12 Contributions Plan 2019. The monetary contribution is based on a development cost of \$44,590,000.00.

The monetary contribution is to be paid prior to the issue of the first Construction Certificate or Subdivision Certificate whichever occurs first, or prior to the issue of the Subdivision Certificate where no Construction Certificate is required. If the monetary contribution (total or in part) remains unpaid after the financial quarter that the development consent is issued, the amount unpaid (whether it be the full cash contribution or part thereof) will be adjusted on a quarterly basis in accordance with the applicable Consumer Price Index. If this situation applies, the cash contribution payable for this development will be the total unpaid monetary contribution as adjusted.

The proponent shall provide to the Certifying Authority written evidence (receipt/s) from Council that the total monetary contribution has been paid.

The Northern Beaches Section 7.12 Contributions Plan 2019 may be inspected at 725 Pittwater Rd, Dee Why and at Council's Customer Service Centres or alternatively, on Council's website at www.northernbeaches.nsw.gov.au

This fee must be paid prior to the issue of the Construction Certificate. Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To provide for contributions in accordance with the Contribution Plan to fund the provision of new or augmented local infrastructure and services.

7. Security Bond

A bond (determined from cost of works) of \$10,000 and an inspection fee in accordance with Council's Fees and Charges paid as security are required to ensure the rectification of any damage that may occur to the Council infrastructure contained within the road reserve adjoining the site as a result of construction or the transportation of materials and equipment to and from the development site.

An inspection fee in accordance with Council adopted fees and charges (at the time of payment) is payable for each kerb inspection as determined by Council (minimum (1) one inspection).

All bonds and fees shall be deposited with Council prior to Construction Certificate or demolition work commencing, and details demonstrating payment are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

To process the inspection fee and bond payment a Bond Lodgement Form must be completed with the payments (a copy of the form is attached to this consent and alternatively a copy is located on Council's website at www.northernbeaches.nsw.gov.au).

Reason: To ensure adequate protection of Council's infrastructure.

8. Construction, Excavation and Associated Works Bond (Drainage works)

The applicant is to lodge a bond of \$550,000 as security against any damage or failure to complete the construction of stormwater drainage works as part of this consent.

Details confirming payment of the bond are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: Protection of Council's Infrastructure.

9. **Construction, Excavation and Associated Works Security Bond (Crossing / Kerb)**

The applicant is to lodge a Bond of \$200,000 as security against any damage or failure to complete the construction of any vehicular crossings, kerb and gutter, any footpath works and removal of any redundant driveways required as part of this consent.

Details confirming payment of the bond are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: Protection of Council's Infrastructure.

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE

10. **Structures Located Adjacent to Council Pipeline or Council Easement**

All structures are to be located clear of any Council pipeline or easement. The Applicant is to ensure footings of any new development within this development consent adjacent to an easement or pipeline are to be designed in accordance with Northern Beaches Council's Warringah Water Management Policy PL850. Details and certification prepared by a suitably qualified Civil Engineer demonstrating compliance are to be submitted to the Certifying Authority for approval prior to the issue of the Construction Certificate.

Reason: Protection of Council's infrastructure.

11. **Traffic Management and Control**

The Applicant is to submit an application for Traffic Management Plan to Council for approval prior to issue of the Construction Certificate. The Traffic Management Plan shall be prepared to RMS standards by an appropriately certified person.

Reason: To ensure appropriate measures have been considered for site access, storage and the operation of the site during all phases of the construction process.

12. **Photographic Archival Record**

A simple photographic heritage record of the site is to be made of all buildings and structures, as a record of the site prior to works.

This record must be submitted and approved by the Principal Certifying Authority prior to commencement of any demolition or works on-site.

This photographic record should be made using digital technology and should include:

- Location of property, date of survey and author of survey;
- A site plan at a scale of 1:200 showing all structures and major landscape elements;
- Existing plans of any buildings (floor plans and elevations);
- Photographs of all elevations, interiors and key features (including gardens, fences, architectural details such as windows, joinery etc.) as well as a number of contextual shots depicting the sites surrounding environment.

Note: All images should be cross-referenced to a catalogue sheet.

Reason: To provide an historical photographic record of the site, including any buildings and landscape elements, prior to any works.

13. On-site Stormwater Detention Details

The Applicant is to provide a certification of drainage plans detailing the provision of on-site stormwater detention in accordance with Northern Beaches Council's Warringah Water Management Policy PL850, and generally in accordance with the concept drainage plans prepared by Costin Roe Consulting, drawing number C013674.01 - DA10, DA41, DA51, DA52, issue C, dated 28/2/20, drawing number drawing number C013674.01 - DA55, issue B, dated 28/2/20, drawing number C013674.01 - DA42, DA45, DA46, DA47, DA48, issue B, dated 26/11/19, drawing number C013674.01 - DA65, issue A, dated 26/11/19, and drawing number C013674.01 - DA70, DA71, DA72, issue A, dated 20/2/20. Detailed drainage plans are to be prepared by a suitably qualified Civil Engineer, who has membership to the Institution of Engineers Australia, National Professional Engineers Register (NPER) and registered in the General Area of Practice for civil engineering.

The drainage plans must address the following:

- i. The stormwater outlet connection to Council's drainage channel shall be amended to discharge

Detailed drainage plans, including engineering certification, are to be submitted to the Certifying Authority for approval prior to the issue of the Construction Certificate.

Reason: To ensure appropriate provision for the disposal of stormwater and stormwater management arising from the development.

14. Submission Roads Act Application for Civil Works in the Public Road

The Applicant is to submit an application for approval for Infrastructure works on Councils roadway. Engineering plans for the new development works within the road reserve and this development consent are to be submitted to Council for approval under the provisions of Sections 138 and 139 of the Roads Act 1993.

The application is to include four (4) copies of Civil Engineering plans for the design of vehicle crossing and footpath which are to be generally in accordance with the Council's specification for engineering works - AUS-SPEC #1. The plan shall be prepared by a qualified civil engineer. The design must include the following information:

1. The Applicant is to construct three vehicle crossings in Inman Road (i) 6.2 metres wide, (ii) 10 metres wide at the boundary and 12.8 metres wide at the kerb, and (iii) 7 metres wide and two vehicle crossings in South Creek Road (i) 8 metres wide at the boundary and 12.3 metres wide at the kerb and (ii) 7.7 metres wide at the boundary and 14.5 metres wide at the kerb in accordance with Northern Beaches Council Drawing No A4-3330/1 N. The vehicle crossing shall be design for the largest service vehicle and supported by turning path templates.
2. Provision of a 1.5 metre wide footpath and upgrade of any associated pram ramps for the entire development frontage.

The fee associated with the assessment and approval of the application is to be in accordance with Council's Fee and Charges.

An approval is to be submitted to the Certifying Authority prior to the issue of the Construction Certificate

Reason: To ensure engineering works are constructed in accordance with relevant standards and Council's specification.

15. Tanking of Basement Level

The basement area is to be permanently tanked. The Applicant is to submit structural details of the tanking, prepared by a suitably qualified Engineer. Where temporary dewatering works are required on the development site during construction, the developer/applicant must apply for and obtain a bore license from the NSW Office of Environment and Heritage. The bore license must be obtained prior to commencement of dewatering works. All requirements of the NSW Office of Water are to be complied with and a copy of the approval must be submitted to the Certifying Authority. Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To prevent ingress of sub-surface flows into the basement area and to comply with State Government Requirements.

16. Structural Adequacy and Excavation Work

Excavation work is to ensure the stability of the soil material of adjoining properties, the protection of adjoining buildings, services, structures and / or public infrastructure from damage using underpinning, shoring, retaining walls and support where required. All retaining walls are to be structurally adequate for the intended purpose, designed and certified by a Structural Engineer, except where site conditions permit the following:

- (a) maximum height of 900mm above or below ground level and at least 900mm from any property boundary, and
- (b) Comply with AS3700, AS3600 and AS1170 and timber walls with AS1720 and AS1170.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the Construction Certificate.

Reason: To provide public and private safety.

17. Shoring of Council's Road Reserve (Temporary road anchors)

Should the proposal require shoring to support an adjoining property or Council land, the Applicant shall provide the adjoining properties with engineering drawings, detailing the proposed shoring works for their consideration and approval.

Written approval from Council under Section 138 of the Roads Act 1993 is required if temporary ground anchors are to be used within Council's road reserve. The Owner's approval is to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure that owners consent is obtained for ancillary works, and to ensure the protection of adjoining properties and Council land.

18. Stormwater Drainage Application

The applicant is to provide a stormwater drainage application under Section 68 of the Local Government Act 1993 to Council for approval. The submission is to include four (4) copies of Civil Engineering plans for the design of the stormwater drainage channel which are to be generally in accordance with the civil design prepared by Costin Roe Consulting, drawing number C013674.01 - DA10, DA41, DA51, DA52, issue C, dated 28/2/20, drawing number drawing number C013674.01 - DA55, issue B, dated 28/2/20, drawing number C013674.01 - DA42, DA45, DA46, DA47, DA48, issue B, dated 26/11/19, drawing number C013674.01 - DA65, issue A, dated 26/11/19, and drawing number C013674.01 - DA70, DA71, DA72, issue A, dated 20/2/20 and Council's specification for engineering works - AUS-SPEC #1.

The form can be found on Council's website at www.northernbeaches.nsw.gov.au > Council Forms > Stormwater Drainage Application Form. The drainage plans must address the following:

- i. Certification that the stormwater channel has been designed in accordance with the Overland Flow Report prepared by Costin Roe Consulting, project number Co13674.01, revision A, dated 28/2/20.
- ii. An easement for drainage purposes shall be shown on the submitted plans over the drainage channel the greater of five metres wide or a minimum 1 metre from the outside wall of the top of the stormwater channel.
- iii. A clear access way shall be provided a minimum of 3.5 metres wide along the adjoining driveway to the east to access the top bank of the channel for the full length for operational and maintenance purposes. A Right of Access shall be shown on the submitted plans over the access way, and shall be created in favour of Council.

The fee associated with the assessment and approval of the application is to be in accordance with Council's Fees and Charges. Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure appropriate provision for disposal and maintenance stormwater management arising from the development.=

19. Temporary Protection Measures

Temporary protection measures are to be developed which identify potential risks and outline methodologies to negate any physical impact upon significant heritage fabric located in the vicinity of works. This includes any impacts upon the retained hexagonal tower and retained original office buildings. These measures are to be prepared by a suitably qualified contractor and submitted to the Certifying Authority for approval prior to the issue of a Construction Certificate. Measures are to be implemented prior to any works and monitored by the project architect.

Reason: To ensure that any original heritage fabric to be retained, is not damaged during construction.

20. Interpretation Strategy and Plan

An Interpretation Strategy is to be prepared by a suitable qualified heritage professional along with an Interpretation Plan outlining how this interpretation will be incorporated into the site development. This Interpretation Strategy and Plan are to be submitted to Council's Heritage Advisor for approval prior to the issue of a Construction Certificate.

Reason: To ensure that the history of the site and its use by Roche is interpreted and incorporated into the site development.

21. Kitchen Design, construction and fit out of food premises

The construction fit-out and finishes of the food premises must comply with Standard 3.2.3 of the Australian and New Zealand Food Standards Code, the Food Act 2003 and Australian Standard AS 4674 'Design, construction and fit out of food premises'. Prior to any Construction Certificate being issued certification is to be provided by a suitably qualified person to the principal certifying authority identifying that the fit-out complies with the above requirement.

Reason: To ensure that the kitchen complies with the design requirements.

22. Plans of Mechanical ventilation

Prior to any Construction Certificate (CC) being issued, detailed plans that demonstrate compliance with the Australian Standard (AS) 1668.2 "The use of ventilation and air-conditioning in buildings - Mechanical ventilation in buildings", must be approved by the Certifying Authority for any cooking equipment with an individual or combined power rating level that triggers the requirement for mechanical ventilation under AS1668.2 including any deep frying equipment.

Reason: To ensure that the design, construction and installation requirement for mechanical ventilation complies with the Australian Standard 1668.2.

23. Tree Protection Plan

In order to protect and enhance onsite vegetation and trees the following applies to the development site:

(a) A Tree Protection Plan prepared by a AQF Level 5 Arborist (or equivalent) showing the following:

- Layout of the approved development
- Location of trees identified for retention with species and tree number allocated
- Extent of canopy spread
- Location of tree protection fencing / barriers in accordance with AS2470 – 2009 Protection of trees on development sites
- General tree protection measures and inspection hold points

(b) The Tree Protection Plan is to be submitted to the Principal Certifying Authority for approval prior to issue of a Construction Certificate.

(c) Tree protection measures identified on the plan are to be in place prior to commencement of works.

Reason: To ensure compliance with the requirement to retain and protect significant planting on the site.

24. Amended Landscape Plans

Landscape Plans are to be amended to substitute the proposed *Cupaniopsis anacardioides* trees with an alternate native species not listed as an exempt species under WDCP E1 Preservation of Trees or Bushland Vegetation

Reason: Environmental amenity

25. Pre-Construction Stormwater Assets Dilapidation Report

The Applicant is to submit a pre-construction/demolition Dilapidation Survey of Council's Stormwater Assets is to be prepared by a suitably qualified person in accordance with Council's Guidelines for Preparing a Dilapidation Survey of Council Stormwater Asset, to record the existing condition of the asset prior to the commencement of works. Council's Guidelines are available at:

<https://files.northernbeaches.nsw.gov.au/sites/default/files/documents/general-information/engineering-specifications/preparingdilapidationsurveyforcouncilstormwaterassets.pdf>

The pre-construction/demolition dilapidation report must be submitted to Council for written

approval and the written approval is then to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: Protection of Council's infrastructure.

26. **Pre-commencement Dilapidation Report**

The applicant must prepare and submit a pre-commencement dilapidation report providing an accurate record of the existing condition of adjoining public property and public infrastructure (including roads, gutter, footpaths, etc). A copy of the report must be provided to Council, any other owners of public infrastructure and the owners of adjoining and affected private properties. The pre-construction / demolition dilapidation report must be submitted to Council for written approval and the written approval is then to be submitted to the Certifying Authority prior to the issue of the any Construction Certificate and the commencement of any works including demolition.

Reason: Protection of Council's Infrastructure during construction.

27. **Like for like credit retirement conditions - Ecosystem credit retirement conditions**

Prior to issue of the relevant Construction Certificate the class and number of ecosystem credits in Table 1 must be retired to offset the impacts of the development.

The requirement to retire credits outlined in Table 1 may be satisfied by payment to the Biodiversity Conservation Fund of an amount equivalent to the class and number of ecosystem credits, as calculated by the Biodiversity Offsets Payment Calculator.

Evidence of the retirement of credits or payment to the Biodiversity Conservation Fund in satisfaction of Table 1 requirements must be provided to the Manager Bushland and Biodiversity of Northern Beaches Council prior to release of construction certification.

Table 1 Ecosystem credits required to be retired – like for like

Impacted Plant Community Type	TEC	Number of ecosystem credits	Cont: HBT
1841-Smooth-barked Apple - Turpentine - Blackbutt tall open forest on enriched sandstone slopes and gullies of the Sydney region	N/A	Nine (9)	YES

Reason: To offset the residual biodiversity impacts of the development in accordance with the NSW Biodiversity Offset Scheme

28. **Detailed Design of Stormwater Treatment Measures**

A certificate from a Civil Engineer, stating that the stormwater treatment measures have been designed in accordance with the plans prepared by Costin Roe dated 26 November 2019 and Council's Water Management Policy.

The certificate shall be submitted to the Certifying Authority prior to the release of the Construction Certificate.

Reason: Protection of the receiving environment

29. **Like for like credit retirement conditions - Species credit retirement conditions**

Prior to issue of the relevant Construction Certificate the class and number of species credits in Table 2 must be retired to offset the impacts of development.

The requirement to retire credits outlined in Table 2 may be satisfied by payment to the Biodiversity Conservation Fund of an amount equivalent to the class and number of ecosystem credits, as calculated by the Biodiversity Offsets Payment Calculator.

Evidence of the retirement of credits or payment to the Biodiversity Conservation Fund in satisfaction of Table 2 requirements must be provided to the Manager Bushland and Biodiversity of Northern Beaches Council prior to release of construction certification.

Table 2 Species credits required to be retired – like for like

Impacted species credit species	Number of species credits	IBRA sub-region
Chalinolobus dwyeri/ Large-eared Pied Bat	Fourteen (14)	Any in NSW

Reason: To offset the residual biodiversity impacts of the development in accordance with the NSW Biodiversity Offset Scheme.

30. **Engagement of a Project Ecologist**

A Project Ecologist is to be employed for the duration of the approved works to ensure all biodiversity protection measures are carried out in accordance with these conditions of consent and the approved Biodiversity Development Assessment Report (BDAR) (Travers Bushfire & Ecology dated 7 April 2020).

The Project Ecologist must have one of the following memberships / accreditation:

- Practising member of the NSW Ecological Consultants Association (<https://www.ecansw.org.au/find-a-consultant/>) OR
- Biodiversity Assessment Method Accredited Assessor under the NSW Biodiversity Conservation Act 2016 (<https://customer.lmbc.nsw.gov.au/assessment/AccreditedAssessor>)

Evidence of engagement of the Project Ecologist is to be provided to the Principal Certifying Authority Prior to issue of Construction Certificate.

Reason: To protect native vegetation and wildlife in accordance with relevant Natural Environment LEP/DCP controls.

31. **Compliance with approved BDAR impact mitigation measures – Prior to Construction**

All pre-construction biodiversity-related measures specified in section 5.4 the approved BDAR and these conditions of consent are to be implemented at the appropriate stage of the development. Compliance with pre-construction measures are to be certified by the Project Ecologist prior to issue of the Construction Certificate.

Reason: To confirm compliance with wildlife and habitat protection/replacement measures in accordance with relevant Natural Environment LEP/DCP controls.

32. **Notification of determination to which the Biodiversity Offset Scheme applies**

The applicant or Project Ecologist, on behalf of the applicant, must download and complete the "Biodiversity Offsets Scheme – Notification of Determination" form.

The completed form and attachments, including a copy of the determination and any conditions of approval, must be emailed to the LMBC Service Centre <bam.support@environment.nsw.gov.au>. The LMBC Service Centre arranges for determination outcomes to be recorded in the Biodiversity Offset and Agreement Management System (BOAMS).

Council's Manager Bushland and Biodiversity and the Principal Certifying Authority must be copied into the notification email to confirm compliance.

Reason: To ensure the NSW Department of Planning, Industry and Environment are notified of determinations where the Biodiversity Offsets Scheme applies and Council are notified for compliance.

33. **Compliance with Standards**

The development is required to be carried out in accordance with all relevant Australian Standards.

Details demonstrating compliance with the relevant Australian Standard are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure the development is constructed in accordance with appropriate standards.

34. **External Finishes to Roof**

The external finish to the roof shall have a medium to dark range in order to minimise solar reflections to neighbouring properties. Any roof with a metallic steel finish is not permitted.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure that excessive glare or reflectivity nuisance does not occur as a result of the development.

35. **Construction Traffic Management Plan.**

As a result of the site constraints, limited vehicle access and parking, a Construction Traffic Management Plan (CTMP) and report shall be prepared by an RMS accredited person and submitted to and approved by the Northern Beaches Council Traffic Team prior to issue of any Construction Certificate.

The CTMP must address following:-

- The proposed phases of construction works on the site, and the expected duration of each construction phase;
- The proposed order in which works on the site will be undertaken, and the method statements on how various stages of construction will be undertaken;
- Make provision for all construction materials to be stored on site, at all times;
- The proposed areas within the site to be used for the storage of excavated materials,

construction materials and waste containers during the construction period;

- The proposed method of access to and egress from the site for construction vehicles, including access routes and truck routes through the Council area and the location and type of temporary vehicular crossing for the purpose of minimising traffic congestion and noise in the area, with no access across public parks or reserves being allowed;
- The proposed method of loading and unloading excavation and construction machinery, excavation and building materials, formwork and the erection of any part of the structure within the site. Wherever possible mobile cranes should be located wholly within the site;
- Make provision for parking onsite. All Staff and Contractors are to use the basement parking once available.
- Temporary truck standing/ queuing locations in a public roadway/ domain in the vicinity of the site are not permitted unless approved by Council prior.
- Include a Traffic Control Plan prepared by a person with suitable RMS accreditation for any activities involving the management of vehicle and pedestrian traffic.
- The proposed manner in which adjoining property owners will be kept advised of the timeframes for completion of each phase of development/construction process. It must also specify that a minimum Fourteen (14) days notification must be provided to adjoining property owners prior to the implementation of any temporary traffic control measure.
- Include a site plan showing the location of any site sheds, location of requested Work Zones, anticipated use of cranes and concrete pumps, structures proposed on the footpath areas (hoardings, scaffolding or shoring) and any tree protection zones around Council street trees.
- Take into consideration the combined construction activities of other development in the surrounding area. To this end, the consultant preparing the CTMP must engage and consult with developers undertaking major development works within a 250m radius of the subject site to ensure that appropriate measures are in place to prevent the combined impact of construction activities, such as (but not limited to) concrete pours, crane lifts and dump truck routes. These communications must be documented and submitted to Council prior to work commencing on site.
- The proposed method/device to remove loose material from all vehicles and/or machinery before entering the road reserve, any run-off from the washing down of vehicles shall be directed to the sediment control system within the site;
- Specify that the roadway (including footpath) must be kept in a serviceable condition for the duration of construction. At the direction of Council, undertake remedial treatments such as patching at no cost to Council.
- The proposed method of support to any excavation adjacent to adjoining properties, or the road reserve. The proposed method of support is to be designed and certified by an appropriately qualified and practising Structural Engineer, or equivalent;
- Proposed protection for Council and adjoining properties;
- The location and operation of any on site crane; and

The CTMP shall be prepared in accordance with relevant sections of Australian Standard 1742 – “Manual of Uniform Traffic Control Devices”, RMS’ Manual – “Traffic Control at Work Sites”.

All fees and charges associated with the review of this plan is to be in accordance with Council’s Schedule of Fees and Charges and are to be paid at the time that the Construction Traffic Management Plan is submitted.

Reason: To ensure public safety and minimise any impacts to the adjoining pedestrian and vehicular traffic systems. Confirming appropriate measures have been considered for site access, storage and the operation of the site during all phases of the construction process in a manner that respects adjoining owner’s property rights and protects amenity in the locality, without unreasonable inconvenience to the community. The CTMP is intended to minimise impact of construction activities on the surrounding community, in terms of vehicle traffic

(including traffic flow and parking) and pedestrian amenity adjacent to the site.
(DACTRCPC1)

36. **Submission of Engineering Plans**

The submission is to include four (4) copies of Civil Engineering plans for the design of:

- A Shared User Path along all frontages of the site

These are to be generally in accordance with the civil design approved with the Development Application and Council's specification for engineering works - AUS-SPEC #1 and or Council's Minor Works Policy. Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Section 138 and/or 139 applications are to be submitted to Council for Local Traffic Committee approval.

Reason: To ensure compliance with Council's specification for engineering works
(DACTRCPC2)

CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT

37. **Public Liability Insurance - Works on Public Land**

Any person or contractor undertaking works on public land must take out Public Risk Insurance with a minimum cover of \$20 million in relation to the occupation of, and approved works within Council's road reserve or public land, as approved in this consent. The Policy is to note, and provide protection for Northern Beaches Council, as an interested party and a copy of the Policy must be submitted to Council prior to commencement of the works. The Policy must be valid for the entire period that the works are being undertaken on public land.

Reason: To ensure the community is protected from the cost of any claim for damages arising from works on public land.

38. **Prior to commencement - Land Contamination**

Prior to the commencement of construction, the Applicant must engage an auditor accredited under the Contaminated Land Management Act 1997 (Site Auditor) throughout the duration of works to ensure that any work required in relation to soil and/or groundwater contamination is appropriately managed.

The Applicant must conduct site investigations to determine the full nature and extent of the contamination at the project area. The site investigations must be undertaken, and the subsequent report/s, must be prepared in accordance with relevant guidelines made or approved by the EPA under section 105 of the *Contaminated Land Management Act 1997*.

At the completion of the site investigations, the Applicant must provide a Remediation Action Plan to ensure the site will be suitable for the proposed use when the RAP is implemented. The Remediation Action Plan must be prepared in accordance with relevant guidelines made or approved by the EPA under section 105 of the *Contaminated Land Management Act 1997*.

Prior to commencing the remediation, the Applicant must submit Interim Audit Advice or a Section B Site Audit Statement from the Site Auditor that certifies that the site can be made suitable for the proposed use subject to the implementation of the Remediation

Action Plan.

The applicant must adhere to the management measures in the Remediation Action Plan which were approved by the Site Auditor.

Any variations to the approved Remediation Action Plan must be approved in writing by the Site Auditor.

If work is to be completed in stages, the Site Auditor must confirm satisfactory completion of each stage by the issuance of Interim Audit Advice/s.

Reason: To ensure all site contamination is managed to protect public and environmental health.

39. Tree trunk, branch and root protection

(a) Existing trees which must be retained

- i) All trees not indicated for removal on Landscape Plans Dwg Nos. 101B, 102B, 103B and 104B dated 04.11.2019 prepared by Site Image, unless exempt under relevant planning instruments or legislation
- ii) Trees located on adjoining land

(b) Tree protection

- i) No tree roots greater than 25mm diameter are to be cut from protected trees unless authorised by the Project Arborist on site.
- ii) All structures are to bridge tree roots greater than 25mm diameter unless directed otherwise by the Project Arborist on site.
- iii) All tree protection to be in accordance with the approved Tree Protection Plan and AS4970-2009 Protection of trees on development sites, with particular reference to Section 4 Tree Protection Measures.
- iv) All tree pruning within the subject site is to be in accordance with WDCP2011 Clause E1 Private Property Tree Management and AS 4373 Pruning of amenity trees
- v) All tree protection measures, including fencing, are to be in place prior to commencement of works.

Reason: To ensure compliance with the requirement to retain and protect significant planting on the site.

40. Project Arborist

- i) A Project Arborist with minimum qualification AQF Level 5 is to be appointed prior to commencement of works.
- ii) The Project Arborist is to oversee all tree protection measures, removals inspection hold points and works adjacent to protected trees as outlined in the approved Tree Protection Plan and AS4970-2009 Protection of trees on development sites.
- iii) The Project Arborist is to ensure compliance as relevant with any other environmental requirements conditioned under this consent.

Reason: to ensure protection of vegetation proposed for retention on the site.

41. Installation and Maintenance of Sediment and Erosion Controls

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004) and the Erosion and Sediment Control Plan

prior to commencement of any other works on site.

Erosion and sediment controls are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and vegetation cover has been re-established across 70 percent of the site, and the remaining areas have been stabilised with ongoing measures such as jute mesh or matting.

Reason: Protection of the receiving environment

42. **Compliance with approved BDAR impact mitigation measures – During Construction**

The approved BDAR includes f mitigation measures (section 5.4), which must to be implemented before, during and after construction to avoid and minimise the impacts of the proposal, including action, outcome, timing and responsibility.

All biodiversity-related measures are to be implemented during construction, as specified in the approved BDAR and these conditions of consent.

The Project Ecologist is required to provide details of compliance, including written and photographic evidence, and provide to the Principal Certifying Authority and Council prior to issue of Occupation Certificate.

Reason: To ensure measures required to avoid and minimise residual biodiversity impacts are undertaken in accordance with the approved BDAR

CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

43. **Road Reserve**

The applicant shall ensure the public footways and roadways adjacent to the site are maintained in a safe condition at all times during the course of the work.

Reason: Public Safety.

44. **Removing, Handling and Disposing of Asbestos**

Any asbestos material arising from the demolition process shall be removed and disposed of in accordance with the following requirements:

- Work Health and Safety Act;
- Work Health and Safety Regulation;
- Code of Practice for the Safe Removal of Asbestos [NOHSC:2002 (1998)];
- Guide to the Control of Asbestos Hazards in Buildings and Structures [NOHSC: 3002 (1998);
- Clause 42 of the Protection of the Environment Operations (Waste) Regulation 2005; and
- The demolition must be undertaken in accordance with Australian Standard AS2601 – The Demolition of Structures.

Reason: For the protection of the environment and human health.

45. **Survey Certificate**

A survey certificate prepared by a Registered Surveyor at the following stages of construction:

(a) Commencement of perimeter walls columns and or other structural elements to ensure the wall or structure, to boundary setbacks are in accordance with the approved details.

(b) At ground level to ensure the finished floor levels are in accordance with the approved levels, prior to concrete slab being poured/flooring being laid.

(c) At completion of the roof frame confirming the finished roof/ridge height is in accordance with levels indicated on the approved plans.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To determine the height of buildings under construction comply with levels shown on approved plans.

46. Installation and Maintenance of Sediment Control

Prior to any works commencing on site, including demolition, sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004). Techniques used for erosion and sediment control on site are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and the site is sufficiently stabilised with vegetation.

Reason: To protect the surrounding environment from the effects of sedimentation and erosion from the site.

47. Property Boundary Levels

The Applicant is to maintain the property boundary levels. No approval is granted for any change to existing property alignment levels to accommodate the development except where necessary to facilitate the provision of vehicular crossings approved within this consent.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To maintain the existing profile of the nature strip/road reserve.

48. Civil Works Supervision

The Applicant shall ensure all civil works approved in the Section 138 approval / Section 68 are supervised by an appropriately qualified and practising Civil Engineer.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority and/or Roads Authority.

Reason: To ensure compliance of civil works with Council's specification for engineering works.

49. Trees Condition

During the construction period the applicant is responsible for ensuring all protected trees are maintained in a healthy and vigorous condition. This is to be done by ensuring that all identified tree protection measures are adhered to. In this regard all protected plants on this site shall not exhibit:

- (a) A general decline in health and vigour.
- (b) Damaged, crushed or dying roots due to poor pruning techniques.
- (c) More than 10% loss or dieback of roots, branches and foliage.
- (d) Mechanical damage or bruising of bark and timber of roots, trunk and branches.
- (e) Yellowing of foliage or a thinning of the canopy untypical of its species.
- (f) An increase in the amount of deadwood not associated with normal growth.

- (g) An increase in kino or gum exudation.
- (h) Inappropriate increases in epicormic growth that may indicate that the plants are in a stressed condition.
- (i) Branch drop, torn branches and stripped bark not associated with natural climatic conditions.

Any mitigating measures and recommendations required by the Arborist are to be implemented.

The owner of the adjoining allotment of land is not liable for the cost of work carried out for the purpose of this clause.

Reason: Protection of Trees.

50. Protection of rock and sites of significance

- a) All rock outcrops outside of the area of approved works are to be preserved and protected at all times during demolition excavation and construction works.
- b) Should any Aboriginal sites be uncovered during the carrying out of works, those works are to cease and Council, the NSW Office of Environment and Heritage (OEH) and the Metropolitan Local Aboriginal Land Council are to be contacted.

Reason: Preservation of significant environmental features.

51. Substitution of Stormwater Treatment Measure

The substitution of an "equivalent" device for the stormwater treatment measure approved in the Development Application process must first be approved by the Principal Certifying Authority.

Details must be submitted to the Principal Certifying Authority for approval prior to installation.

Reason: To ensure stormwater is appropriately managed and in accordance with the Water Management Policy.

52. Dewatering Management

Dewatering of groundwater or tailwater must be carried out according to a dewatering management plan approved by Council, Council's dewatering permit, the General Terms of Approval/Controlled Activity permit issued by WaterNSW and the EPA, and legislation including Protection of the Environment Operations Act 1997 and Contaminated Lands Act 1997.

Council's Catchment Team must be notified of your intention to discharge and the expected time of discharge via the Team's email address - catchment@northernbeaches.nsw.gov.au

All records of approvals, water discharges and monitoring results are to be documented and kept on site. Copies of all records shall be provided to the appropriate regulatory authority, including Council, upon request.

Reason: Protection of the receiving environment

53. Aboriginal Heritage

Site A

Any proponent proposing to carry out future development works on the Property should initiate dialogue with the MLALC and Council about the prudence of developing appropriate management measures during the construction period for Site A (AHIMS Site #45-6-1760) that occurs on the footpath on Inman Road

Area C

Any proponent proposing to carry out future development works on the Property should consider undertaking an investigation to determine whether **Area C** has any Aboriginal heritage values given its potential connection with **Site B**.

Site B

Consultation with the **MLALC** should be initiated to seek approval from the **OEH** for an **AHIP** to allow the investigation of the suspected site of **Site B** (AHIMS Site #45-6-1851) to be carried out should future development of the Property be proposed in this area.

Reason: Aboriginal Heritage Protection. (DACAHE01)

54. **Installation and Maintenance of Sediment Control**

Measures used for erosion and sediment control on building sites are to be adequately maintained at all times and must be installed in accordance with Council's Specifications for Erosion and Sediment Control. All measures shall remain in proper operation until all development activities have been completed and the site fully stabilised.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To protect the environment from the effects of sedimentation and erosion from development sites.

55. **Implementation of Construction Traffic Management Plan.**

All works and construction activities are to be undertaken in accordance with the approved Construction Traffic Management Plan (CTMP). All controls in the CTMP must be maintained at all times and all traffic management control must be undertaken by personnel having appropriate RMS accreditation. Should the implementation or effectiveness of the CTMP be impacted by surrounding major development not encompassed in the approved CTMP, the CTMP measures and controls are to be revised accordingly and submitted to Council for approval. A copy of the approved CTMP is to be kept onsite at all times and made available to Council on request.

Reason: to ensure compliance of the developer/builder in adhering to the Construction Traffic Management procedures agreed and are held liable to the conditions of consent.
(DACTREDW1)

56. **Ongoing Management.**

The applicant shall be responsible in ensuring that the road reserve remains in a serviceable state during the course of the project. (DACTREDW2)

CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

57. **Landscape completion certification**

a) Prior to the issue of an Occupation Certificate, a landscape report prepared by a landscape architect or landscape designer shall be submitted to the Certifying Authority, certifying that the landscape works have been completed in accordance with the approved landscape plan and inclusive of any conditions of consent.

b) Prior to the issue of an Occupation Certificate, a landscape report prepared by a landscape architect or landscape designer shall be submitted to the Certifying Authority, certifying that the landscape works have been established and maintained in accordance with the approved

landscape plan.

Reason: To ensure that the landscape treatments are installed to provide landscape amenity.

58. **Condition of retained vegetation**

Prior to the issue of an Occupation Certificate, a report prepared by the Project Arborist shall be submitted to the Principal Certifying Authority, assessing the health and impact of trees and vegetation required to be retained as a result of the proposed development, including the following information:

- a) Compliance with all conditions for tree protection and excavation works.
- b) Extent of damage sustained by vegetation as a result of the construction works.
- c) Any subsequent remedial works required to ensure the long term retention of the vegetation.

Reason: To ensure compliance with the requirement to retain and protect significant planting on development sites.

59. **Stormwater Disposal**

The stormwater drainage works shall be certified as compliant with all relevant Australian Standards and Codes by a suitably qualified person. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure appropriate provision for the disposal of stormwater arising from the development.

60. **Post- Construction Stormwater Assets Dilapidation Report (Council stormwater assets)**

The Applicant shall submit a post-construction Dilapidation Survey of Council's Stormwater Assets is to be prepared by a suitably qualified person in accordance with Council's Guidelines for Preparing a Dilapidation Survey of Council Stormwater Asset in order to determine if the asset has been damaged by the works. Council's Guidelines are available at

<https://files.northernbeaches.nsw.gov.au/sites/default/files/documents/general-information/engineering-specifications/preparingdilapidationsurveyforcouncilstormwaterassets.pdf>

The post-construction / demolition dilapidation report must be submitted to Council for review Any damage to Council's stormwater infrastructure is to be rectified prior to the release of any Drainage security bonds.

Reason: Protection of Council's infrastructure.

61. **Certification of Structures Located Adjacent to Council Pipeline or Council Easement**

The Applicant shall submit a suitably qualified Civil Engineer's certification that the completed footing works have been constructed in accordance with this consent, Northern Beaches Council's Warringah Water Management Policy PL850 and the approved Construction Certificate plans. Civil Engineer demonstrating compliance is to be submitted to the Principal Certifying Authority prior to the issue of the Occupation Certificate.

Reason: Protection of Council's Infrastructure.

62. Positive Covenant and Restriction as to User for On-site Stormwater Disposal Structures

The Applicant shall lodge the Legal Documents Authorisation Application with the original completed request forms (NSW Land Registry standard forms 13PC and/or 13RPA) to Council and a copy of the Works-as-Executed plan (details overdrawn on a copy of the approved drainage plan), hydraulic engineers' certification.

The Applicant shall create on the Title a restriction on the use of land and a positive covenant in respect to the ongoing maintenance and restriction of the on-site stormwater disposal structures within this development consent. The terms of the positive covenant and restriction are to be prepared to Council's standard requirements at the applicant's expense and endorsed by Northern Beaches Council's delegate prior to lodgement with the NSW Land Registry Services. Northern Beaches Council shall be nominated as the party to release, vary or modify such covenant.

A copy of the certificate of title demonstrating the creation of the positive covenant and restriction for on-site storm water detention as to user is to be submitted.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of final Occupation Certificate.

Reason: To ensure the on-site stormwater disposal system is maintained to an appropriate operational standard.

63. Retaining wall

The retaining wall works shall be certified as compliant with all relevant Australian Standards and Codes by a Structural Engineer. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any final Occupation Certificate.

Reason: Public and Private Safety

64. Post-Construction Dilapidation Report (Major Development)

The applicant must bear the cost of all restoration works to Council's road, footpath and drainage assets damaged during the course of this development.

A Post Construction Dilapidation Report after the completion of all building works is to demonstrate that there is no damage to Council infrastructure prior to the refund of any security deposits.

Reason: To ensure security against possible damage to Council property.

65. Certification of Council Drainage Works and Works as Executed Data within Private Land

The Applicant shall submit a suitably qualified Civil Engineer's certification that the completed works have been constructed in accordance with this consent and the approved Section 68 approved plans. Works as Executed data certified by a registered surveyor prepared in accordance with Council's requirements is to be provided to Council. Full details of the information to be submitted to Council, as part of the Works as Executed Data, are outlined in Council's 'Guideline for preparing Works as Executed data for Council stormwater assets' which is available from Council's Environment Unit. The Works as Executed data is to be verified by the Principal Certifying Authority prior to submission of any documentation.

The Works as Executed Data is to include but not be limited to the following:

- Works As Executed (WAE) plan,
- a Spreadsheet Schedule of all stormwater asset attributes and

- a CCTV Report of the completed pipeline/channel

Reason: To ensure compliance of drainage works with Council's specification for engineering works.

66. **Easement for Drainage**

The Applicant shall create an easement for drainage (under the provisions of Section 88B of the Conveyancing Act) the greater of five metres wide or a minimum 1 metre from the outside wall of the top of the stormwater channel to ensure all drainage infrastructure is located within the appropriate easement(s).

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the Occupation Certificate.

Reason: To ensure access to Council stormwater infrastructure.

67. **Right of Access**

The Applicant shall create a right of access (under the provisions of Section 88B of the Conveyancing Act) a minimum 3.5 metres wide for Council to access stormwater infrastructure for operational and maintenance purposes.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the Occupation Certificate.

Reason: To ensure access to Council stormwater infrastructure.

68. **Positive covenant - Heritage conservation**

Positive Covenant (under the provisions of Section 88B of the Conveyancing Act 1919 (NSW)) shall be created on the title of the land to ensure the on-going conservation of the heritage item in accordance with works outlined within the 'Schedule of Conservation Works' prepared by Heritage 21 (Job No. 8851), dated July 2020.

Northern Beaches Council shall be nominated in the instrument as the only party authorised to release, vary or modify the instrument. Northern Beaches Council's delegate shall sign these documents prior to the submission to the NSW Land Registry Services.

Evidence of the registration of the Positive Covenant on the title of the land shall be submitted to the Principal Certifying Authority prior to the issue of the Occupation Certificate.

Reason: To ensure the required conservation actions are undertaken with works outlined within the 'Schedule of Conservation Works'.

69. **Registration of Food Business**

The food business must be registered with the Appropriate Regulatory Authority, prior to Occupation Certificate being issued.

Reason: Food premises are required to be registered with the Appropriate Regulatory Authority.

70. **Prior to Occupation Certificate - Cooling Tower Risk Management Plan**

Prior to the issuing of any interim / final occupation certificate, a risk management plan is to be completed before the cooling water system commences operation. The risk management plan must be conducted and reported to Council in accordance with Clause 13M and 13N of the Public Health Regulation 2012 NSW.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To ensure compliance with the Public Health Act 2010 NSW(DACHPFPOC7)

71. Prior to Occupation Certification - Land Contamination

The applicant must obtain a Section A1 Site Audit Statement - *or* a Section A2 Site Audit Statement accompanied by an Environmental Management Plan - from a Site Auditor and submit it to the principal certifying authority prior to commencement of occupation. The Site Audit Statement must certify the site is suitable for its use.

Reason: To protect public and environmental health.

72. Prior to occupation certificate - Cooling Tower Notification

Prior to the issue of the Occupation Certificate, notification of any cooling tower/s on the property must be submitted to Council by completing NSW Health approved form 6 Notification of installation or change in particulars.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: Compliance with the Public Health Act 2010 NSW

73. Required Planting

Trees shall be planted in accordance with the Landscape Plans Dwg Nos. 101B, 102B, 103B and 104B dated 04.11.2019 prepared by Site Image

Reason: To maintain environmental amenity.

74. Works as Executed Drawings - Stormwater Treatment Measures

Works as Executed Drawings for the stormwater treatment measures must be prepared in accordance with Council's Guideline for Preparing Works as Executed Data for Council Stormwater Assets.

The drawings shall be submitted to the Principal Certifying Authority prior to the release of the Occupation Certificate.

Reason: Protection of the receiving environment

75. Compliance with approved BDAR impact mitigation measures – Occupation Construction

The approved BDAR includes mitigation measures (section 5.4), which must to be implemented before, during and after construction to avoid and minimise the impacts of the proposal, including action, outcome, timing and responsibility.

All biodiversity-related measures are to be implemented immediately after construction, as specified in the approved BDAR and these conditions of consent.

The Project Ecologist is required to provide details of compliance, including written and photographic evidence, and provide to the Principal Certifying Authority and Council prior to issue of Occupation Certificate.

Reason: To ensure measures required to avoid and minimise residual biodiversity impacts are

undertaken in accordance with the approved BDAR

76. Certification for the Installation of Stormwater Treatment Measures

A certificate from a Civil Engineer, who has membership to Engineers Australia and the National Engineers Register must be provided, stating that the stormwater treatment measures have been installed in accordance with the plans prepared by Costin Roe dated 26 November 2019. The certificate must confirm that stormwater treatment devices are completed, online, in good condition and are not impacted by sediment.

The certificate shall be submitted to the Principal Certifying Authority prior to the release of the Occupation Certificate.

Reason: Protection of the receiving environment

77. Positive Covenant, Restriction as to User and Registration of Encumbrances for Stormwater Treatment Measures

A positive covenant shall be created on the title of the land requiring the proprietor of the land to maintain the stormwater treatment measures in accordance with the standard requirements of Council, the manufacturer and as required by the Stormwater Treatment Measures Operation and Maintenance Plan.

A restriction as to user shall be created on the title over the stormwater treatment measures, restricting any alteration to the measures.

The terms of the positive covenant and restriction as to user are to be prepared to Council's standard requirements (available from Council) at the applicant's expense and endorsed by the Northern Beaches Council's delegate prior to lodgement with the Department of Lands. Northern Beaches Council shall be nominated as the party to release, vary or modify such covenant.

A copy of the certificate of title demonstrating the creation of the positive covenant and restriction as to user is to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To identify encumbrances on land, ensure ongoing maintenance, and ensure modification to the stormwater treatment measures is not carried out without Council's approval.

78. Stormwater Treatment Measure Operation and Maintenance Plan

An Operation and Maintenance Plan is to be prepared to ensure the proposed stormwater treatment measures remain effective.

The Plan must be attached to the Positive Covenant (and the community or strata management statement if applicable) and contain the following:

1. Detail on the stormwater treatment measures:
 - a) Work as executed drawings
 - b) Intent of the stormwater treatment measures including modelled pollutant removal rates
 - c) Site detail showing catchment for each device
 - d) Vegetation species list associated with each type of vegetated stormwater treatment measure
 - e) Impervious area restrictions to maintain the water balance for the site
 - f) Funding arrangements for the maintenance of all stormwater treatment measures
 - g) Identification of maintenance and management responsibilities

h) Maintenance and emergency contact information

2. Maintenance schedule and procedure - establishment period of one year following commissioning of the stormwater treatment measure

a) Activity description, and duration and frequency of visits

Additionally for vegetated devices:

b) Monitoring and assessment to achieve an 80 percent survival rate for plantings

c) Management of weeds, pests and erosion, with weed and sediment cover limited to a maximum of 5 percent of the total area of the stormwater treatment measure

3. Maintenance schedule and procedure - ongoing

a) Activity description, and duration and frequency of visits

b) Routine maintenance requirements

c) Work Health and Safety requirements

d) Waste management and disposal

e) Traffic control (if required)

f) Renewal, decommissioning and replacement timelines and activities of all stormwater treatment measures (please note that a DA may be required if an alternative stormwater treatment measure is proposed)

g) Requirements for inspection and maintenance records, noting that these records are required to be maintained and made available to Council upon request.

Details demonstrating compliance shall be submitted to the Principal Certifying Authority prior to the release of the Occupation Certificate.

Reason: Protection of the receiving environment.

79. **Removal of All Temporary Structures/Material and Construction Rubbish**

Once construction has been completed all silt and sediment fences, silt, rubbish, building debris, straw bales and temporary fences are to be removed from the site.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure bushland management. (DACPLF01)

80. **Waste Management Confirmation**

Prior to the issue of a Final Occupation Certificate, evidence / documentation must be submitted to the Principal Certifying Authority that all waste material from the development site arising from demolition and/or construction works has been appropriately recycled, reused or disposed of generally in accordance with the approved Waste Management Plan.

Reason: To ensure demolition and construction waste is recycled or reused and to limit landfill.

81. **Sydney Water**

A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained from Sydney Water Corporation.

Application must be made through an authorised Water Servicing Co-ordinator. Please refer to the Building Developing and Plumbing section of the web site www.sydneywater.com.au <<http://www.sydneywater.com.au>> then refer to "Water Servicing Coordinator" under "Developing Your Land" or telephone 13 20 92 for assistance.

Following application a “Notice of Requirements” will advise of water and sewer infrastructure to be built and charges to be paid. Please make early contact with the Co-ordinator, since building of water/sewer infrastructure can be time consuming and may impact on other services and building, driveway or landscape design.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure compliance with the statutory requirements of Sydney Water.

82. Fire Safety Matters

At the completion of all works, a Fire Safety Certificate will need to be prepared which references all the Essential Fire Safety Measures applicable and the relative standards of Performance (as per Schedule of Fire Safety Measures). This certificate must be prominently displayed in the building and copies must be sent to Council and Fire and Rescue NSW.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of a part Occupation Certificate or Occupation Certificate.
Each year the Owners must send to the Council and Fire and Rescue NSW, an annual Fire Safety Statement which confirms that all the Essential Fire Safety Measures continue to perform to the original design standard.

Reason: Statutory requirement under Part 9 Division 4 & 5 of the Environmental Planning and Assessment Regulation 2000.

83. Loading Dock Management Plan.

A Loading Dock Management Plan shall be prepared by the applicant and submitted to and approved by the accredited certifier prior to the issue of any Occupation Certificate. The Plan will need to demonstrate how loading dock will be managed to ensure that there will be only one vehicle entering and exiting the loading dock access in any period and how safe servicing arrangements including waste collection will be undertaken without interrupting general traffic. Vehicle queuing on public road(s) is not permitted.

Reason: to ensure the loading dock is managed appropriately and that tenants are aware of the conditions of use.
(DACTRFPOC1)

84. Shared User Path Construction.

The Shared User Path, in accordance with approved plans and Council’s standard specifications, shall be constructed along the property frontage to Council’s satisfaction. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any Occupation Certificate.

Reason: To provide pedestrian access to and from the property.
(DACTRFPOC2)

ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES

85. Undesirable Trees

Leighton Green Cypress Cupressocyparis leylandii or any of its cultivars, must not be planted on the site for the life of the development. In the event of any inconsistency between this condition

and the development application documents, this condition will prevail to the extent of the inconsistency.

Reason: To reduce the potential for adverse amenity effects such as overshadowing, loss of views, and loss of plant diversity.

86. On going - Noise

The acoustic assessment prepared by Acoustic Dynamics dated 20 November 2019 for EC Funds Management is to be implemented into the development and all recommendations within section 5.1 and 5.2 of the report are to be implemented into the operation of the site at all times.

Reason: To protect the amenity of the area and nearby residential receivers. (DACHPGOG5)

87. Landscape maintenance

- i) Trees shrubs and groundcovers required to be planted under this consent are to be mulched, watered and fertilized as required at the time of planting.
- ii) If any tree, shrub or groundcover required to be planted under this consent fails, they are to be replaced with similar species to maintain the landscape theme and be generally in accordance with the approved Landscape Plan.

Reason: To maintain local environmental amenity.

88. Control of Weeds

Prior to the completion of works, all priority weeds (as listed under the Biosecurity Act 2015) are to be removed/controlled within the subject site using an appropriately registered control method. Information on weeds of the Northern Beaches can be found at the NSW WeedWise website (<http://weeds.dpi.nsw.gov.au/>). All environmental weeds are to be removed and controlled. Refer to Council website http://www.pittwater.nsw.gov.au/environment/noxious_weeds

Reason: Weed management.

89. Maintenance of Stormwater Treatment Measures

Stormwater treatment measures must be maintained at all times in accordance with the Stormwater Treatment Measure Operation and Maintenance Plan, manufacturer's specifications and as necessary to achieve the required stormwater quality targets for the development.

Vegetated stormwater treatment measures must maintain an 80 percent survival rate of plantings and limit weed cover to no more than 10 percent of the total area of the stormwater treatment measure.

Northern Beaches Council reserves the right to enter the property and carry out appropriate maintenance of the device at the cost of the property owner.

Reason: Protection of the receiving environment

90. Installation of Water Efficient Fittings

The following Water Efficiency Labelling and Standards (WELS) Scheme rated fittings must be installed:

- a) 4 star dual-flush toilets

- b) 3 star showerheads
- c) 4 star taps (for all taps other than bath outlets and garden taps)
- d) 3 star urinals
- e) 3.5 star washing machines
- f) 4 star dishwashers

A certificate from a licenced plumber demonstrating compliance shall be submitted to the Principal Certifying Authority prior to the release of the Occupation Certificate.

Reason: To conserve potable water

91. **Works to cease if item found**

If any Aboriginal Engravings or Relics are unearthed all work is to cease immediately and the Aboriginal Heritage Office (AHO) and Office of Environment and Heritage (OEH) are to be notified.

Reason: To protect Aboriginal Heritage.

92. **Dead or Injured Wildlife**

If construction activity associated with this development results in injury or death of a native mammal, bird, reptile or amphibian, a registered wildlife rescue and rehabilitation organisation must be contacted for advice.

Reason: To mitigate potential impacts to native wildlife resulting from construction activity.

93. **Hours of Operation**

The hours of operation are to be restricted to:

- Warehouse, office and café - 7am to 6pm
- Storage facility – 7am to 10pm

Upon expiration of the permitted hours, all service (and entertainment) shall immediately cease, no patrons shall be permitted entry and all customers on the premises shall be required to leave within the following 30 minutes.

Reason: Information to ensure that amenity of the surrounding locality is maintained.

94. **No Illumination**

No consent is given or implied for any form of illumination or floodlighting to any sign or building or other external areas other than that approved.

Reason: To ensure appropriate forms of illumination that are consistent with Council's controls, and do not interfere with amenity of nearby properties. (DACPLG13)

95. **Commercial Waste Collection (DACPLG18)**

Waste and recyclable material, generated by this premises, must not be collected between the hours of 10pm and 6am on any day.

Reason: To protect the acoustic amenity of surrounding properties.(DACPLG18)

