

NOTE:
AS PER KU-RING-GAI DEVELOPMENT CONTROL PLAN, SECTION 24C.3
CONDITION 8: FOR DEVELOPMENT TYPES 4 AND ABOVE, BASEMENTS ARE TO BE FULLY TANKED.

PIPES NOTE:
Ø65 PVC @ MIN 1.0%
Ø90 PVC @ MIN 1.0%
Ø100 PVC @ MIN 1.0%
Ø150 PVC @ MIN 1.0%
Ø225 PVC @ MIN 0.5%
Ø300 PVC @ MIN 0.4%
UNLESS NOTED OTHERWISE

NOTE:
ALL STORMWATER DRAINAGE PIPES ARE Ø100 uPVC U.N.O.

NOTE:
ALL LINEAR GRATED DRAINS TO BE MIN. 100mm DEEP.

NOTE:
ALLOW BENCHING WITHIN SPOON DRAIN TO ACHIEVE MIN 1.0% FALL TO FLOOR WASTES.

NOTE:
REFER ARCHITECTURAL DRAWINGS FOR FINAL SET-OUT LEVELS.

STANDARD PUMP OUT DESIGN NOTES

- THE PUMP OUT SYSTEM SHALL BE DESIGN TO BE OPERATED IN THE FOLLOWING MANNER:
- THE PUMP SHALL BE PROGRAMMED TO WORK ALTERNATELY TO ALLOW BOTH PUMPS TO HAVE AN EQUAL OPERATION LOAD AND PUMP LIFE.
 - A FLOAT SHALL BE PROVIDED TO ENSURE OF THE MINIMUM REQUIRED WATER LEVEL IS MAINTAINED WITHIN THE SUMP AREA OF THE BELOW GROUND TANK. IN THIS REGARD THIS FLOAT WILL FUNCTION AS AN OFF SWITCH FOR THE PUMPS AT THE MINIMUM WATER LEVEL. THE SAME FLOAT SHALL BE SET TO TURN ONE OF THE PUMPS ON UPON THE WATER LEVEL IN THE TANK RISING TO APPROXIMATELY 300mm ABOVE THE MINIMUM WATER LEVEL. THE PUMP SHALL OPERATE UNTIL THE TANK IS DRAINED TO THE MINIMUM WATER LEVEL.
 - A SECOND FLOAT SHALL BE PROVIDE AT A HIGH LEVEL, WHICH IS APPROXIMATELY THE ROOF LEVEL OF THE BELOW GROUND TANK. THIS FLOAT SHALL START THE OTHER PUMP THAT IS NOT OPERATING AND ACTIVATE THE ALARM.
 - AN ALARM SYSTEM SHALL BE PROVIDE WITH A FLASHING STROBE LIGHT AND A PUMP FAILURE WARNING SIGN WHICH ARE TO BE LOCATED AT THE DRIVEWAY ENTRANCE TO THE BASEMENT LEVEL THE ALARM SYSTEM SHALL BE PROVIDED WITH A BATTERY BACK-UP IN CASE OF POWER FAILURE.
 - A CONFINED SPACE DANGER SIGN SHALL BE PROVIDED AT ALL ACCESS POINT TO THE PUMP-OUT STORAGE TANK IN ACCORDANCE WITH THE UPPER PARRAMATTA RIVER CATCHMENT TRUST OSD HANDBOOK.



BASEMENT PUMP OUT FAILURE WARNING SIGN
SIGN SHALL BE PLACED IN A CLEAR AND VISIBLE LOCATION WHERE VEHICLES ENTER THE BASEMENT
COLOURS:
"WARNING" = RED
BORDER AND OTHER LETTERING = BLACK



CONFINED SPACE DANGER SIGN


A) A CONFINED SPACE DANGER SIGN SHALL BE POSITIONED IN A LOCATION AT ALL ACCESS POINTS, SUCH THAT IT IS CLEARLY VISIBLE TO PERSONS PROPOSING TO ENTER THE BELOW GROUND TANK/S CONFINED SPACE.

B) MINIMUM DIMENSIONS OF THE SIGN - 300mm x 450mm (LARGE ENTRIES, SUCH AS DOORS) -250mm x 180mm (SMALL ENTRIES SUCH AS GRATES & MANHOLES)

C) THE SIGN SHALL BE MANUFACTURED FROM COLOUR BONDED ALUMINUM OR POLYPROPYLENE

D) SIGN SHALL BE AFFIXED USING SCREWS AT EACH CORNER OF THE SIGN

COLOURS:
"DANGER" & BACKGROUND = WHITE
ELLIPTICAL AREA = RED
RECTANGLE CONTAINING ELLIPSE = BLACK
BORDER AND OTHER LETTERING = BLACK



POCKLEY AVENUE

ROSEVILLE AVENUE


NOT FOR CONSTRUCTION

Issue	Description	Date	Design	Checked
A	ISSUE FOR DEVELOPMENT APPLICATION	31/03/2025	EAB	SBF

Certification By: Dr. Michel Cheyaz
S.E., M.E., Ph.D., P.E., Aust. "PrEng"
Civil & Structural Engineer

Architect
PLACE STUDIO
Level 5, 140 William Street,
Woolloomooloo, NSW 2011.
J.ALEXANDER-HATZPLIS
NSW ARB # 10535
T 61 431 088 534
W www.PlaceStudio.com.au
E Studio@PlaceStudio.com.au












Council
Ku-Ring-Gai Council
Client
Primo Real Estate



TELFORD CIVIL
CONSULTING CIVIL & STORMWATER ENGINEERS
Level 14, 32 Smith Street,
Parramatta NSW 2150
PO BOX 3579 Parramatta 2124
Email: info@teffordcivil.com.au
Phone: 02 7809 4931
Company: Telford Consulting Pty Ltd



Project
**7-11 POCKLEY AVENUE, ROSEVILLE
PROPOSED RESIDENTIAL FLAT BUILDING
STORMWATER CONCEPT PLANS
DEVELOPMENT APPLICATION**

Drawing Title				
STORMWATER CONCEPT PLAN BASEMENT 2 SHEET 1 OF 2				
Scale	AD	Project No.	Eng. No.	Issue
1:100		25035	101	A



LEGEND

- PROPOSED STORMWATER
- VD: Ø100mm VERTICAL DROP
- Surface flow direction
- IO: INSPECTION OPENING
- RL 72.05: FINISHED SURFACE LEVEL
- Grated drain (HD): HEAVY DUTY
- FG: Ø150mm FLOOR GRATE
- FW: Ø100mm FLOOR WASTE



PIPES NOTE:

- Ø65 PVC @ MIN 1.0%
- Ø90 PVC @ MIN 1.0%
- Ø100 PVC @ MIN 1.0%
- Ø150 PVC @ MIN 1.0%
- Ø225 PVC @ MIN 0.5%
- Ø300 PVC @ MIN 0.4%

UNLESS NOTED OTHERWISE

NOTE:

ALL STORMWATER DRAINAGE PIPES ARE Ø100 uPVC U.N.O.

NOTE:

ALL LINEAR GRATED DRAINS TO BE MIN. 100mm DEEP.

NOTE:

ALLOW BENCHING WITHIN SPOON DRAIN TO ACHIEVE MIN 1.0% FALL TO FLOOR WASTES.

NOTE:

REFER ARCHITECTURAL DRAWINGS FOR FINAL SET-OUT LEVELS.

NOT FOR CONSTRUCTION

PIPES NOTE:

Ø65 PVC @ MIN 1.0%
Ø90 PVC @ MIN 1.0%
Ø100 PVC @ MIN 1.0%
Ø150 PVC @ MIN 1.0%
Ø225 PVC @ MIN 0.5%
Ø300 PVC @ MIN 0.4%
UNLESS NOTED OTHERWISE

NOTE:

ALL STORMWATER DRAINAGE PIPES ARE
Ø100 PVC AT MIN 1.0% SLOPE U.N.O.

NOTE:

1. CONTRACTOR IS TO PROVIDE OVERFLOW OUTLETS &
EMERGENCY OVERFLOW SPITTERS TO ALL TRAPPED AREAS.
2. DP/VD ARE Ø100 PIPES U.N.O.
3. ALL TRANSFERRING PIPES ARE SUSPENDED U.N.O.
4. BALCONIES PIPES ARE Ø50mm HDPE OR PVC CAST IN SLAB
AT MIN 1.0% SLOPE.

NOTE:

IT IS CONTRACTOR'S RESPONSIBILITY
TO ENSURE MINIMUM PONDING IS
ACHIEVED OVER THE FLOOR WASTES
BY GRADING CATCHMENTS' SURFACES
AT MINIMUM 1.0% FALL.

NOTE:

ALL REDUNDANT PIPELINES WITHIN
FOOTPATH AREA MUST BE REMOVED
AND FOOTPATH/KERB REINSTATED.

NOTE:

ALL GRATES WITHIN
FOOTWAY AREAS TO BE
HEEL GUARD & BIKE SAFE.

NOTE:

PITS DEEPER THAN
1.0m TO BE FITTED
WITH STEP IRONS.

NOTE:

ALL UPPER LEVELS DRAINAGE SYSTEM
TO BE CONNECTED TO WSUD, SUBJECT
TO DETAILED DESIGN STAGE.

NOTE:

REFER ARCHITECTURAL DRAWINGS
FOR FINAL SET-OUT LEVELS.

NOTE:

ALL LINEAR GRATED DRAINS
TO BE MIN. 100mm DEEP.

LEGEND

- PROPOSED STORMWATER DRAINAGE PIPE
PROPOSED STORMWATER DRAINING TO OSD
PROPOSED STORMWATER BYPASSING OSD
Ø100 HDPE OR PVC STORMWATER DRAINAGE PIPE CAST IN SLAB
Ø65 HDPE OR PVC STORMWATER DRAINAGE PIPE CAST IN SLAB
Ø50 HDPE OR PVC STORMWATER DRAINAGE PIPE CAST IN SLAB
PROPOSED STORMWATER PIPE TO RAINWATER TANK
Ø100 SUBSOIL DRAINAGE TO BE WRAPPED IN GEOTEXTILE BIDMA34
RISER PIPE
DOWNPIPE Ø100
VERTICAL DROP Ø100
VERTICAL DROP FROM SLAB
PLANTER GRATE Ø150
FLOOR GRATE Ø150
FLOOR GRATE 300x200 (ALLOW MINIMUM 1.0% FALL TO FG)
FLOOR GRATE 300x300 (ALLOW MINIMUM 1.0% FALL TO FW)
RAINWATER OUTLET Ø260 SPS (ALLOW MINIMUM 1.0% FALL TO RWO)
SUSPENDED PLANTER BOX RAINWATER OUTLET
AC CONDENSER TUNDISH TO MANUFACTURER'S DETAILS
INVERT LEVEL
DESIGN SURFACE LEVEL
EXISTING SURFACE LEVEL
EXISTING STORMWATER DRAINAGE
EXISTING WATER MAIN
EXISTING SEWER MAIN
EXISTING TELESTRA
EXISTING ELECTRICAL
EXISTING ELECTRICAL UNDERGROUND
EXISTING OVERHEAD ELECTRICAL
EXISTING GAS
EXISTING HOUSE DRAINAGE
EXISTING OPTIC FIBER


GENERAL NOTES

- ALL LINES ARE TO BE Ø100 uPVC 1.0% GRADE UNLESS NOTED OTHERWISE. CHARGED LINES TO BE SEWERGRADE & SEALED.
- EXISTING SERVICES LOCATIONS SHOWN INDICATIVE ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE & LEVEL ALL EXISTING SERVICES PRIOR TO THE COMMENCEMENT OF ANY EARTHWORKS.
- ALL PIPES TO HAVE MIN 150mm COVER IF LOCATED WITHIN PROPERTY.
- ALL PITS IN DRIVEWAYS TO BE 450x450 CONCRETE AND ALL PITS IN LANDSCAPED AREAS TO BE 450x450 PLASTIC.
- PITS LESS THAN 600mm DEEP MAY BE BRICK, PRECAST OR CONCRETE.
- ALL BALCONIES AND ROOFS TO BE DRAINED AND TO HAVE SAFETY OVERFLOWS IN ACCORDANCE WITH RELEVANT AUSTRALIAN STANDARDS.
- ALL EXTERNAL SLABS TO BE WATERPROOFED.
- ALL GRATES TO HAVE CHILD PROOF LOOKS.
- ALL DRAINAGE WORKS TO AVOID TREE ROOTS.
- ALL DPs TO HAVE LEAF GUARDS.
- ALL EXISTING LEVELS TO BE CONFIRMED BY BUILDER PRIOR TO CONSTRUCTION.
- ALL WORK WITHIN COUNCIL RESERVE TO BE INSPECTED BY COUNCIL PRIOR TO CONSTRUCTION.
- COUNCIL'S ISSUED FOOTWAY DESIGN LEVELS TO BE INCORPORATED INTO THE FINISHED LEVELS ONCE ISSUED BY COUNCIL.
- ALL WORK SHALL BE IN ACCORDANCE WITH B.C.A. AND A.S.3500.3.
- REFER TO LANDSCAPE ARCHITECT'S DRAWINGS FOR LANDSCAPING.
- CARE TO BE TAKEN AROUND EXISTING SEWER. STRUCTURAL ADVICE IS REQUIRED FOR SEWER PROTECTION AGAINST ADDITIONAL LOADING FROM NEW PITS, PIPES, RETAINING WALLS AND OSD BASIN WATER LEVELS.
- ALL PIPES IN BALCONIES TO BE Ø65 uPVC CAST IN CONCRETE SLAB. CONTRACTOR TO PROVIDE A BREAK / OPEN VOID IN RAIL / BALUSTRADE FOR STORMWATER EMERGENCY OVERFLOW. ALL ENCLOSED AREAS / PLANTER BOXES TO BE FITTED WITH FLOOR WASTES & DRAINED TO OSD DOWNPIPES TO BE CHECKED BY ARCHITECT & PLUMBER PRIOR TO CONSTRUCTION.
- THE OSD BASIN / TANK IS TO BE BUILT TO THE CORRECT LEVELS & SIZE AS PER THIS DESIGN. ANY VARIATIONS ARE TO BE DONE UNDER CONSULTATION FROM OUR OFFICE ONLY. ANY AMENDMENTS WITHOUT OUR APPROVAL WOULD RESULT IN ADDITIONAL FEES FOR REDESIGN AT OC STAGE OR IF A SOLUTION CANNOT BE FOUND, RECONSTRUCTION IS REQUIRED UNDER THE CONTRACTOR'S EXPENSES.

NOTE:

ALL NON-TRAFFICABLE AREAS DRAINAGE SYSTEM IN UPPER LEVELS IS SUBJECT TO DETAILED DESIGN STAGE & TO BE CONNECTED TO THE UNDERGROUND RAINWATER TANK.

ALL TRAFFICABLE AREAS DRAINAGE SYSTEM IN UPPER LEVELS IS SUBJECT TO DETAILED DESIGN STAGE & TO BE CONNECTED TO THE UNDERGROUND WSUD TANK.



LOWER GROUND FLOOR PLAN

SCALE 1:100

NOT FOR CONSTRUCTION

Issue	Description	Date	Design	Checked
A	ISSUE FOR DEVELOPMENT APPLICATION	31/03/2025	EAB	SBF

Certification by Dr. Michel Chey
S.E. M.E. (Pres. M.D. F.I.E. Aust. CEng.
Civil & Structural Engineer

Architect
PLACE STUDIO
Level 5, 140 William Street,
Woolloomooloo, NSW 2011.
J.ALEXANDER-HATZPLIS
NSW ARB # 10535
T 61 431 088 334
W www.PlaceStudio.com.au
E Studio@PlaceStudio.com.au

Council
Ku-Ring-Gai
Council
Client
Primo Real
Estate

Scale



TELFORD CIVIL
CONSULTING CIVIL & STORMWATER ENGINEERS
Level 14, 32 Smith Street,
Parramatta NSW 2150
PO BOX 3578 Parramatta 2124
Email: info@telfordcivil.com.au
Phone: 02 7809 4931
Company: Telford Consulting Pty Ltd

Project

7-11 POCKLEY AVENUE, ROSEVILLE
PROPOSED RESIDENTIAL FLAT BUILDING
STORMWATER CONCEPT PLANS
DEVELOPMENT APPLICATION

Drawing Title

STORMWATER CONCEPT PLAN
LOWER GROUND LEVEL

Scale 1:100
Project No. 25035
Dwg. No. 104
Issue A

PIPES NOTE:

Ø65 PVC @ MIN 1.0%
Ø90 PVC @ MIN 1.0%
Ø100 PVC @ MIN 1.0%
Ø150 PVC @ MIN 1.0%
Ø225 PVC @ MIN 0.5%
Ø300 PVC @ MIN 0.4%
UNLESS NOTED OTHERWISE

NOTE:

ALL STORMWATER DRAINAGE PIPES ARE
Ø100 PVC AT MIN 1.0% SLOPE U.N.O.

NOTE:

- CONTRACTOR IS TO PROVIDE OVERFLOW OUTLETS & EMERGENCY OVERFLOW SPITTERS TO ALL TRAPPED AREAS.
- DP/VD ARE Ø100 PIPES U.N.O.
- ALL TRANSFERRING PIPES ARE SUSPENDED U.N.O.
- BALCONIES PIPES ARE Ø50mm HDPE OR PVC CAST IN SLAB AT MIN 1.0% SLOPE.

NOTE:

IT IS CONTRACTOR'S RESPONSIBILITY
TO ENSURE MINIMUM PONDING IS
ACHIEVED OVER THE FLOOR WASTES
BY GRADING CATCHMENTS' SURFACES
AT MINIMUM 1.0% FALL.

NOTE:

ALL REDUNDANT PIPELINES WITHIN
FOOTPATH AREA MUST BE REMOVED
AND FOOTPATH/KERB REINSTATED.

NOTE:

ALL GRATES WITHIN
FOOTWAY AREAS TO BE
HEEL GUARD & BIKE SAFE.

NOTE:

PITS DEEPER THAN
1.0m TO BE FITTED
WITH STEP IRONS.

NOTE:

ALL UPPER LEVELS DRAINAGE SYSTEM
TO BE CONNECTED TO WSUD, SUBJECT
TO DETAILED DESIGN STAGE.

NOTE:

REFER ARCHITECTURAL DRAWINGS
FOR FINAL SET-OUT LEVELS.

NOTE:

ALL LINEAR GRATED DRAINS
TO BE MIN. 100mm DEEP.

LEGEND

- PROPOSED STORMWATER DRAINAGE PIPE
- PROPOSED STORMWATER DRAINING TO OSD
- PROPOSED STORMWATER BYPASSING OSD
- Ø100 HDPE OR PVC STORMWATER DRAINAGE PIPE CAST IN SLAB
- Ø65 HDPE OR PVC STORMWATER DRAINAGE PIPE CAST IN SLAB
- Ø50 HDPE OR PVC STORMWATER DRAINAGE PIPE CAST IN SLAB
- PROPOSED STORMWATER PIPE TO RAINWATER TANK
- Ø100 SUBSOIL DRAINAGE TO BE WRAPPED IN GEOTEXTILE BIDIMAS4
- RISER PIPE
- DOWNPIPE Ø100
- VERTICAL DROP Ø100
- VERTICAL DROP FROM SLAB
- PLANTER GRATE Ø150
- FLOOR GRATE Ø150
- FLOOR GRATE 200x200 (ALLOW MINIMUM 1.0% FALL TO FG)
- FLOOR GRATE 300x300 (ALLOW MINIMUM 1.0% FALL TO FW)
- RAINWATER OUTLET Ø280 SPS (ALLOW MINIMUM 1.0% FALL TO RWO)
- SUSPENDED PLANTER BOX RAINWATER OUTLET
- AC CONDENSER TUNDISH TO MANUFACTURER'S DETAILS
- INVERT LEVEL
- DESIGN SURFACE LEVEL
- EXISTING SURFACE LEVEL
- EXISTING STORMWATER DRAINAGE
- EXISTING WATER MAIN
- EXISTING SEWER MAIN
- EXISTING TELESTRA
- EXISTING ELECTRICAL
- EXISTING ELECTRICAL UNDERGROUND
- EXISTING OVERHEAD ELECTRICAL
- EXISTING GAS
- EXISTING HOUSE DRAINAGE
- EXISTING OPTIC FIBER

GENERAL NOTES

- ALL LINES ARE TO BE Ø100 uPVC 1.0% GRADE UNLESS NOTED OTHERWISE. CHARGED LINES TO BE SEWERGRADE & SEALED.
- EXISTING SERVICES LOCATIONS SHOWN INDICATIVE ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE & LEVEL ALL EXISTING SERVICES PRIOR TO THE COMMENCEMENT OF ANY EARTHWORKS.
- ALL PIPES TO HAVE MIN 150mm COVER IF LOCATED WITHIN PROPERTY.
- ALL PITS IN DRIVEWAYS TO BE 450x450 CONCRETE AND ALL PITS IN LANDSCAPED AREAS TO BE 450x450 PLASTIC.
- PITS LESS THAN 600mm DEEP MAY BE BRICK, PRECAST OR CONCRETE.
- ALL BALCONES AND ROOFS TO BE DRAINED AND TO HAVE SAFETY OVERFLOWS IN ACCORDANCE WITH RELEVANT AUSTRALIAN STANDARDS.
- ALL EXTERNAL SLABS TO BE WATERPROOFED.
- ALL GRATES TO HAVE CHILD PROOF LOCKS.
- ALL DRAINAGE WORKS TO AVOID TREE ROOTS.
- ALL DPs TO HAVE LEAF GUARDS.
- ALL EXISTING LEVELS TO BE CONFIRMED BY BUILDER PRIOR TO CONSTRUCTION.
- ALL WORK WITHIN COUNCIL RESERVE TO BE INSPECTED BY COUNCIL PRIOR TO CONSTRUCTION.
- COUNCIL'S ISSUED FOOTWAY DESIGN LEVELS TO BE INCORPORATED INTO THE FINISHED LEVELS ONCE ISSUED BY COUNCIL.
- ALL WORK SHALL BE IN ACCORDANCE WITH B.C.A. AND A.S.3500.3.
- REFER TO LANDSCAPE ARCHITECT'S DRAWINGS FOR LANDSCAPING.
- CARE TO BE TAKEN AROUND EXISTING SEWER. STRUCTURAL ADVICE IS REQUIRED FOR SEWER PROTECTION AGAINST ADDITIONAL LOADING FROM NEW PITS, PIPES, RETAINING WALLS AND OSD BASIN WATER LEVELS.
- ALL PIPES IN BALCONIES TO BE Ø65 uPVC CAST IN CONCRETE SLAB. CONTRACTOR TO PROVIDE A BREAK / OPEN VOID IN RAIL / BALUSTRADE FOR STORMWATER EMERGENCY OVERFLOW. ALL ENCLOSED AREAS/PLANTER BOXES TO BE FITTED WITH FLOOR WASTES & DRAINED TO OSD DOWNPIPES TO BE CHECKED BY ARCHITECT & PLUMBER PRIOR TO CONSTRUCTION.
- THE OSD BASIN / TANK IS TO BE BUILT TO THE CORRECT LEVELS & SIZE AS PER THIS DESIGN. ANY VARIATIONS ARE TO BE DONE UNDER CONSULTATION FROM OUR OFFICE ONLY. ANY AMENDMENTS WITHOUT OUR APPROVAL WOULD RESULT IN ADDITIONAL FEES FOR REDESIGN AT OUR STAGE OR IF A SOLUTION CANNOT BE FOUND, RECONSTRUCTION IS REQUIRED UNDER THE CONTRACTOR'S EXPENSES.

NOTE:

ALL NON-TRAFFICABLE AREAS DRAINAGE SYSTEM IN UPPER LEVELS IS SUBJECT TO DETAILED DESIGN STAGE & TO BE CONNECTED TO THE UNDERGROUND RAINWATER TANK.

ALL TRAFFICABLE AREAS DRAINAGE SYSTEM IN UPPER LEVELS IS SUBJECT TO DETAILED DESIGN STAGE & TO BE CONNECTED TO THE UNDERGROUND WSUD TANK.

UPPER GROUND FLOOR PLAN

SCALE 1:100

NOT FOR CONSTRUCTION


Issue	Description	Date	Design	Checked
A	ISSUE FOR DEVELOPMENT APPLICATION	31/03/2025	EAB	SBF

Certification By: Michel Cheyaz
E.L. M.E. (Pres.) P.D. F.I.E. Aust. CPEng.
Civil & Structural Engineer

Architect
PLACE STUDIO
Level 5, 140 William Street,
Woolloomooloo, NSW 2011.
J.ALEXANDER-HATZIDIS
NSW ARB # 10535
T 61 431 088 534
W www.PlaceStudio.com.au
E Studio@PlaceStudio.com.au

Council
Ku-Ring-Gai Council
Client
Primo Real Estate

Scale



TELFORD CIVIL
CONSULTING CIVIL & STORMWATER ENGINEERS

Level 14, 32 Smith Street,
Parramatta NSW 2150
PG BOX 3579 Parramatta 2124
Email: info@telfordcivil.com.au
Phone: 02 7809 4931
Company: Telford Consulting Pty Ltd

Project

7-11 POCKLEY AVENUE, ROSEVILLE
PROPOSED RESIDENTIAL FLAT BUILDING
STORMWATER CONCEPT PLANS
DEVELOPMENT APPLICATION

Drawing Title

STORMWATER CONCEPT PLAN
UPPER GROUND LEVEL

Scale 1:100
Project No. 25035
Dwg No. 105
Issue A



1. ALL LINES ARE TO BE 6100 UPVC 1.0% GRADE UNLESS NOTED OTHERWISE. CHARGED LINES TO BE 6100 UPVC 1.0% GRADE & SEPARATED BY 150mm.
2. EXISTING SERVICES LOCATIONS SHOWN INDICATIVE ONLY. IT IS THE CONTRACTORS RESPONSIBILITY TO LOCATE TO A LEVEL. ALL EXISTING SERVICES PRIOR TO THE CONSTRUCTION OF ANY NEW NETWORKS.
3. ALL PIPES TO HAVE MIN 150mm COVER IF LOCATED WITHIN PROPERTY.
4. ALL PITS IN DRIVEWAYS TO BE 450x450 AND ALL PITS IN LANDSCAPED AREAS TO BE 450x450 PLASTIC.
5. PITS LESS THAN 600mm DEEP MAY BE BRICK, PRECAST OR CONCRETE.
6. ALL BALCONIES AND ROOFS TO BE DRAINED AND DRAINAGE COVERED IN ACCORDANCE WITH RELEVANT AUSTRALIAN STANDARDS.
7. ALL EXTERNAL SLABS TO BE WATERPROOFED.
8. ALL GRATES TO HAVE CHILD PROOF LOCKS.
9. ALL DRAINAGE WORKS TO AVOID TREE ROOTS.
10. ALL GRATES TO HAVE CHILD PROOF LOCKS.
11. ALL DRAINING WORKS TO BE CONFIRMED BY BUILDER PRIOR TO CONSTRUCTION.
12. ALL WORK WITHIN COUNCIL RESERVE TO BE INSTALLED BY COUNCIL PRIOR TO CONSTRUCTION.
13. COUNCIL'S ISSUED FOOTPATH DESIGN LEVELS TO BE INCORPORATED INTO THE FINISHED LEVELS NOW ISSUED BY COUNCIL.
14. ALL COUNCIL USE TO BE IN ACCORDANCE WITH B.C.A. AND A 3500.3.
15. REFER TO LANDSCAPE ARCHITECT'S DRAWINGS FOR LANDSCAPING.
16. CARE TO BE TAKEN AROUND EXISTING SEWER STRUTS AND PIPES. IF REQUIRED FOR SEWER PROTECTION AGAINST ADDITIONAL LOADING FROM NEW PITS, PIPES, RETAINING WALLS AND OSD BASIN WATER LEVELS.
17. ALL NEW PIPES TO BE 6100 UPVC CAST IN CONCRETE SLAB CONTRACTOR TO PROVIDE A BREAK / OPEN VOID IN LAI / BALUSTRADE FOR STORMWATER EMERGENCY OVERTFLOW. ALL ENCLOSED AREAS/PARTIAL BOXES TO BE FITTED WITH 150mm DIA. DOWNPIPES TO OSD DOWNPIPES TO BE CHECKED BY ARCHITECT & PLUMBER PRIOR TO CONSTRUCTION.
18. THE OSD BASIN / TANK IS TO BE BUILT TO THE DESIGNER'S SPECIFIED SIZE AND DESIGN. ANY VARIATION FROM THIS IS TO BE UNDER CONSULTATION FROM OUR OFFICE ONLY. ANY AMENDMENTS WITHOUT OUR APPROVAL WOULD RESULT IN ADDITIONAL FEES FOR REDESIGN AT THE CLIENT'S SOLA. ALL CONSTRUCTION AND RECONSTRUCTION IS REQUIRED UNDER THE CONTRACTOR'S EXPENSES

Ø65 PVC @ MIN 1.0%
 Ø90 PVC @ MIN 1.0%
 Ø100 PVC @ MIN 1.0%
 Ø150 PVC @ MIN 1.0%
 Ø225 PVC @ MIN 0.5%
 Ø300 PVC @ MIN 0.4%
 UNLESS NOTED OTHERWISE

ALL STORMWATER DRAINAGE PIPES ARE
Ø100 PVC AT MIN 1.0% SLOPE U.N.O.

1. CONTRACTOR IS TO PROVIDE OVERFLOW OUTLETS & EMERGENCY OVERFLOW SPITTERS TO ALL TRAPPED AREAS.
2. DP/VD ARE Ø100 PIPES U.N.O.
3. ALL TRANSFERRING PIPES ARE SUSPENDED U.N.O.
4. BALCONIES PIPES ARE Ø50mm HDPE OR PVC CAST IN SLAB AT MIN 1.0% SLOPE.

IT IS CONTRACTOR'S RESPONSIBILITY TO ENSURE MINIMUM PONDING IS ACHIEVED OVER THE FLOOR WASTES BY GRADING CATCHMENTS' SURFACES AT MINIMUM 1.0% FALL.

ALL REDUNDANT PIPELINES WITHIN
FOOTPATH AREA MUST BE REMOVED
AND FOOTPATH/KERB REINSTATED.

ALL GRATES WITHIN
FOOTWAY AREAS TO BE
HEEL GUARD & BIKE SAFE.

PITS DEEPER THAN 1.0m TO BE FITTED WITH STEP IRONS.

ALL UPPER LEVELS DRAINAGE SYSTEM
TO BE CONNECTED TO WSUD, SUBJECT
TO DETAILED DESIGN STAGE.

REFER ARCHITECTURAL DRAWINGS
FOR FINAL SET-OUT LEVELS.

ALL LINEAR GRATED DRAINS
TO BE MIN. 100mm DEEP.

NOT FOR CONSTRUCTION


[illegible]

Certification By Dr. Michel Chassry
B.E., M.E. (Res), Ph.D., F.I.E. Aust., CPEng
Civil & Structural Engineer

Architect
PLACE STUDIO
Level 5, 140 William Street.
Woolloomooloo, NSW 2011.
J ALEXANDER-HATZIPLIS
NSW ARB # 10535
T 61 431 088 534
W www.PlaceStudio.com.au
E Studio@PlaceStudio.com.au

Council	Ku-Ring-Gai Council
Client	Primo Real Estate

Scale



TELFORD CIVIL
CONSULTING CIVIL & STORMWATER ENGINEERS

Level 14, 32 Smith Street,
Parramatta NSW 2150
PO BOX 3579 Parramatta 2124

Email: info@telfordcivil.com.au
Phone: 02 7809 4931
Company: Telford Consulting Pty Ltd

Order



7-11 POCKLEY AVENUE, ROSEVILLE
PROPOSED RESIDENTIAL FLAT BUILDING
STORMWATER CONCEPT PLANS
DEVELOPMENT APPLICATION

Drawing Title

STORMWATER CONCEPT PLAN

LEVEL 01


Scale 1:100	A0	Project No. 25035	Dwg. No. 106	Issue A
----------------	----	----------------------	-----------------	------------



UNDERGROUND OSD/WSUD & RAINWATER TANKS DETAILS

SECTION C


SCALE 1:20



UNDERGROUND OSD/WSUD & RAINWATER TANKS DETAILS

SECTION A


SCALE 1:20



UNDERGROUND OSD/WSUD & RAINWATER TANKS DETAILS


SECTION B

SCALE 1:20




UNDERGROUND OSD/WSUD/RWT
WALLS DIMENSIONS & WEIR HEIGHT

SCALE 1:50




UNDERGROUND OSD/WSUD/RWT
BOTTOM S.R.L.

SCALE 1:50



TRASH SCREEN DETAIL

N.T.S.



ORIFICE PLATE DETAIL

SCALE 1:10

Project	PROPOSED RESIDENTIAL FLAT BUILDING				
Address	7-11 POCKLEY AVENUE, ROSEVILLE				
Job No.	25035				
Designer	EAB				
Catchment Detail					
Catchment Area Code	BG1	Catchment Discharge Rate	0.0147	l/sec/m ²	
		Catchment Storage Rate	0.0287	m ³ /m ²	
Site Details					
Site Area			3098.0	m ²	
60% of Site Area			1859	m ²	
Area not Draining to the Detention System			438	m ²	
Total Impervious Area (roofs, driveway, paving etc)			1556	m ²	
Impervious area bypassing detention system			0	m ²	
Permitted Site Discharge	Flow 1		27.32	l/sec	
Adjustment for uncontrolled impervious flow			0.00	(<0.25)	
Adjusted flow	Flow 2		0.00	l/sec	
Final Permitted Site Discharge			27.32	l/sec	
Site Storage Requirement			53.35	m ³	
Landscaped surface OSD basin?			no		
Adjustment factor for Landscaped surface basin:			1.00		
Adjustment for Landscaped surface basin			53.35	m ³	
Surface Area			53.17	m ²	
Average depth of water			1.19	m	
Provided Volume of Storage= Surface Area X Average depth of water			63.06	m ³	
			Volume > than Required		
Max Head to Orifice Centre			1.26	m	
Orifice Diameter			108	mm	


NOT FOR CONSTRUCTION

A		ISSUE FOR DEVELOPMENT APPLICATION	31/03/2025	EAB	SBF
Issue	Description	Date	Design	Checked	

Certification by Dr. Michel Cheyaz
S.E. (M.E. (Pres. 11.11.11) E. Aust. Offeng.
Civil & Structural Engineer

Architect
PLACE STUDIO
Level 5, 140 William Street,
Woolloomooloo, NSW 2011.
J.ALEXANDER-HATZIDIS
NSW ARB # 10535
T 61 431 088 534
W www.PlaceStudio.com.au
E Studio@PlaceStudio.com.au

Council
Ku-Ring-Gai
Council
Client
Primo Real
Estate



TEL FORD CIVIL
CONSULTING CIVIL & STORMWATER ENGINEERS
Level 14, 32 Smith Street,
Parramatta NSW 2150
PO BOX 3579 Parramatta 2124
Email: info@telfordcivil.com.au
Phone: 02 7809 4931
Company: Telford Consulting Pty Ltd


Project
7-11 POCKLEY AVENUE, ROSEVILLE
PROPOSED RESIDENTIAL FLAT BUILDING
STORMWATER CONCEPT PLANS
DEVELOPMENT APPLICATION

ON-SITE DETENTION DETAILS AND CALCULATIONS			
Scale	As Shown	Project No.	25035
Dwg. No.	107	Issue	A

CATCHMENT LEGEND

	ROOF AREA TO RWT THEN TO SFC = 500.0m²
	IMPERVIOUS AREA TO SFC = 955.6m²
	PERVIOUS AREA TO SFC = 1104.1m²
	DRIVEWAY TO SFC = 62.2m²
	PERVIOUS AREA BYPASSING SFC = 438.2m²
	DRIVEWAY BYPASSING SFC = 37.90m²

TOTAL SITE AREA = 3098 m²
TOTAL AREA TO SFC = 2,621.9 m² (84.63% OF TOTAL SITE AREA)
TOTAL BYPASS AREA = 476.1m² (100% PERVIOUS)



25035 - 7-11 Pockley Avenue, Roseville (RESIDENTIAL FLAT BUILDING)

BoM Station: Pockley Avenue, Roseville - Daily Rainfall (66158) 1990 - 2016

Assumptions	Rainfall loss	1	mm			
	Roof area	500	m ²			
	Rainwater tank size	12.37	m ³			
	%Full at start	0	%			
	Total# of days	9611	days			
	Total wet days	3875	days			
	Total# of Green days	353	days			
	%Reduction in wet days	90.9	%			
	* Wet day = greater than 0mm of daily rain					
	* Total water usage is calculated in m ³ /day and subtracted on each day					
* Target a 30% reduction in runoff days						
* Assume that if rainwater tank does not overflow on a wet day, this is no longer a 'runoff' day. OF = Overflow Day						
* %Reduction in wet days = (wet days - OF days) / wet days						
References	[a] Blacktown Council WSD guidelines					
	[b] AW / Sydney Water					
	[c] Melbourne Household Water Use calculator					
	SoI time tank is empty			83	%	
	SoI time tank is full			4	%	
	Water Usage - Landscape Watering					
	Area to be watered		1595	m ²		
	Watering rate		0.4	m ³ /yr/m ²	[a]	
	Total water used		1.747	m ³ /day		
	Water Usage - Car Wash Bay					
Number units		0				
% of units using car wash		50	%			
Average washes		4	washes/yr/unit			
Usage Rate		100	L/wash	[b]		
Total water used		0.000	m ³ /day			
Total Water usage					4.722	m ³ /day
Water Usage - AAA Toilets						
No. of residents		119				
AAA Toilet flush rate		5	L/flush	[c]		
Flushes		5	flush/pers/day	[c]		
Total water used		2.975	m ³ /day			
Water Usage - 4A Washing Machines						
No. of units w. machines		0				
Water use		60	L/wash			
Washes per week		2				
Total water used		0.00	m ³ /day			

CATCHMENT PLAN

SCALE 1:100


GENERAL NOTES:

- INLET AND OUTLET PIPES TO BE IN ACCORDANCE WITH APPROVED PLANS.
- A HIGH FLOW BYPASS ARRANGEMENT OR DISSIPATION STRUCTURE MAY BE REQUIRED TO MINIMISE RE-SUSPENSION OF SOLIDS OR ANY SIGNIFICANT INERTIAL FORCES ON THE CARTRIDGES.
- ALL WATER QUALITY TREATMENT DEVICES REQUIRE PERIODIC MAINTENANCE. REFER TO OPERATION AND MAINTENANCE MANUAL FOR GUIDELINES AND ACCESS REQUIREMENTS.
- SITE SPECIFIC PRODUCTION DRAWINGS WILL BE PROVIDED ON PLACEMENT OF ORDER.
- THE INVERT LEVEL OF THE INLET PIPE MUST BE GREATER THAN THE RL OF THE FALSE FLOOR WITHIN THE CARTRIDGE CHAMBER.
- CONCRETE STRUCTURE AND ACCESS COVERS DESIGNED AND PROVIDED BY OTHERS. ACCESS COVERS TO BE A MINIMUM 900 x 900 ABOVE CARTRIDGES. OH&S REGARDING ACCESS COVERS AND TANK ACCESS TO BE ASSESSED BY OTHERS ON SITE.
- THE STRUCTURE THICKNESSES SHOWN ARE FOR REPRESENTATIONAL PURPOSES.
- DRAWINGS NOT TO SCALE.

	Sources	Residual Load	% Reduction
Flow (ML/yr)	2.046	1.72	15.93
Total Suspended Solids (kg/yr)	292.2	43.32	85.18
Total Phosphorus (kg/yr)	0.6612	0.1348	79.62
Total Nitrogen (kg/yr)	5.286	2.241	57.61
Gross Pollutants (kg/yr)	41.02	0.9994	97.56

MUSIC RESULTS

N.T.S.



STORMFILTER CARTRIDGE DETAIL

N.T.S.

Facility Component Requiring Maintenance	Maintenance Activity	When Maintenance Activity Is Required	Expected Facility Performance After Maintaining	INSPECTION/MINOR MAINTENANCE (TIMES/YEAR)	MAJOR MAINTENANCE (TIMES/YEAR)
StormFilter® Cartridges and Containment Structure	Trash and Debris Removal	Floatable objects or other trash is present in the filter. Remove to avoid hindrance of filtration and eliminate unsightly debris and trash.	Permanent removal from storm system.	2 (and after major storms)	1 (except in case of a spill)
	Cartridge Replacement and Sediment Removal	1. Media has been contaminated by high levels of pollutants, such as after a spill.	1. New media is able to effectively treat stormwater.	-	-
Drainage System Piping	Flushing With Water	Drainage system is obstructed by debris or sediment.	Outflow is not restricted.	-	-

FILTRATION UNIT MAINTENANCE SCHEDULE


NOT FOR CONSTRUCTION

Issue	Description	Date	Design	Checked
A	ISSUE FOR DEVELOPMENT APPLICATION	31/03/2025	EAB	SBF

Certification By Mr. Michel Cheyza
S.E. (M.E. Reg.) P.D. F.I.E. Aust. CPEng.
Civil & Structural Engineer

Architect
PLACE STUDIO
Level 5, 140 William Street,
Woolloomooloo, NSW 2011.
J.ALEXANDER-HATZIDIS
NSW ARB # 10535
T: 61 431 088 534
W: www.PlaceStudio.com.au
E: Studio@PlaceStudio.com.au

Council
Ku-Ring-Gai
Council
Client
Primo Real
Estate




TELFORD CIVIL
CONSULTING CIVIL & STORMWATER ENGINEERS
Level 14, 32 Smith Street,
Parramatta NSW 2150
PO BOX 3579 Parramatta 2124
Email: info@tefordcivil.com.au
Phone: 02 7809 4931
Company: Telford Consulting Pty Ltd







Project
7-11 POCKLEY AVENUE, ROSEVILLE
PROPOSED RESIDENTIAL FLAT BUILDING
STORMWATER CONCEPT PLANS
DEVELOPMENT APPLICATION

Drawing Title
CATCHMENT PLAN AND
MUSIC RESULTS

Scale	As Shown	Project No.	25035	Eng. No.	108	Issue	A
-------	----------	-------------	-------	----------	-----	-------	---



					Architect Certification by G. Mohr Charley S.E., M.S., (Reg.) P.D., F.T.E. Aust. CPDed. Civil & Structural Engineer		Architect PLACE STUDIO Level 5, 140 William Street, Woodlough, NSW 2011. J.ALEXANDER@HATZIPLIS NSW ARB # 10535 T 61 431 088 534 W www.PlaceStudio.com.au E Studio@PlaceStudio.com.au		Council Ku-Ring-Gai Council		Scale SCALE 1:100 @ A0		TELFORD CIVIL CONSULTING CIVIL & STORMWATER ENGINEERS Level 14, 32 Smith Street, Parramatta NSW 2150 PO BOX 3579 Parramatta 2124 Email: info@telfordcivil.com.au Phone: 02 7809 4931 Company: Telford Consulting Pty Ltd		Project 7-11 POCKLEY AVENUE, ROSEVILLE PROPOSED RESIDENTIAL FLAT BUILDING STORMWATER CONCEPT PLANS DEVELOPMENT APPLICATION		Drawing Title SEDIMENT AND EROSION CONTROL PLAN & DETAILS SHEET 1 OF 2		
A	ISSUE FOR DEVELOPMENT APPLICATION				31/03/2025	EAB	SBF												
Issue	Description				Date	Design	Checked												



SEDIMENT BASIN CALCULATION:

THE MINIMUM VOLUME OF THE UPPER SETTING ZONE IS DEFINED BY EQUATION:

$$V_g = 10 \cdot R_{(Y, 5-day)} \cdot C_v \cdot A$$

WHERE: V_g = VOLUME OF THE SETTING ZONE (m³)
 $R_{(Y, 5-day)}$ = Ym, 5-DAY RAINFALL DEPTH (mm)
 C_v = VOLUMETRIC RUNOFF COEFFICIENT
 A = EFFECTIVE CATCHMENT SURFACE AREA TO BE CONNECTED TO THE BASIN (ha)
 $R_{(Y, 5-day)}$ = $K_1 \cdot 1.72 \cdot 120 I_p + K_2$

WHERE: K_1 = CONSTANT = 17
 K_2 = CONSTANT = 11.2
 $I_p (120h)$ = AVERAGE RAINFALL INTENSITY FOR A 1 IN 1 YEAR ARI, 120 HR STORM (mm/hr) = 1.3

THEN: $R_{(Y, 5-day)} = 17 \times 1.3 + 11.2 = 33.3$

SEDIMENT BASIN:

$$R_{(Y, 5-day)} = 33.3$$
$$C_v = 0.5$$
$$A = 3,098 \text{ m}^2 = 0.3098 \text{ ha}$$

THEN: $V_g = 10 \times 33.3 \times 0.5 \times 0.3098 = 51.58 \text{ m}^3$

BASIN DEWATERING NOTES:

ALL SEDIMENT BASINS ON-SITE ARE TO BE CONTINUOUSLY MONITORED AND MAINTAINED BEFORE AND AFTER RAIN EVENTS. DEWATERING IS TO BE ACHIEVED BY:

- AFTER A RAIN EVENT, ALLOW UP TO 24 HOURS FOR ALL SURFACE FLOWS AND GROUND WATER TO CONTINUE SEEPING INTO THE BASIN;
- PLACE INDUSTRY STANDARD FLOCCULANT FOR A PERIOD OF 24-48 HOURS. MORE TIME MAY BE REQUIRED DEPENDING ON GROUND SEEPAGE FROM UPSTREAM CATCHMENT;
- WATER QUALITY TESTING BY AN ACCREDITED ENVIRONMENTAL ENGINEER AND LABORATORY FOR TOTAL SUSPENDED SOLIDS (TSS) IS TO OCCUR;
- ONCE CLEARANCE BY AN ENVIRONMENTAL ENGINEER HAS BEEN SOUGHT, PUMP WATER IN NEARBY DRAINAGE SYSTEM

GENERAL:

- WHERE POSSIBLE SEED ALL TOPSOIL AREAS TO STABILISE LOTS.
- CONSIDERATION SHOULD BE GIVEN TO LAYING A STRIP OF TURF AT THE BASE OF THE RETAINING WALLS ALONG HIAWATHA ROAD.
- STABILISATION OF KERBSIDE WOULD OCCUR VIA TURF STRIP AND FOOTPATH CONSTRUCTION AS SOON AS PRACTICAL.

SEDIMENT & EROSION CONTROL NOTES:

1. THE CONTRACTOR SHALL IMPLEMENT ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO THE COMMENCEMENT OF ANY WORKS BEING CARRIED OUT. ALL SOIL AND EROSION MEASURES SHALL BE MAINTAINED AND KEPT IN PLACE FOR THE FULL DURATION OF THE WORKS AND SHALL ONLY BE REMOVED AT FINAL STABILISATION OF THE WORKS, WHERE IT IS NECESSARY TO UNDERTAKE STRIPPING IN ORDER TO CONSTRUCT A SEDIMENT CONTROL DEVICE. ONLY SUFFICIENT GROUND SHALL BE STRIPPED TO ALLOW CONSTRUCTION.
2. ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CONSTRUCTED & MAINTAINED AS INDICATED ON THESE DRAWINGS. LOCATION AND EXTENT OF SOIL & WATER MANAGEMENT DEVICES IS DIAGRAMMATIC ONLY AND THE ACTUAL REQUIREMENTS SHALL BE CONFIRMED ON SITE PRIOR TO COMMENCEMENT.
3. CONFORMITY WITH THIS PLAN SHALL IN NO WAY REDUCE THE RESPONSIBILITY OF THE CONTRACTOR TO PROTECT AGAINST WATER DAMAGE DURING THE COURSE OF THE CONTRACT. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO ENSURE THAT ANY NECESSARY CONTROL IS IN PLACE EVEN THOUGH SUCH CONTROL MAY NOT BE SHOWN ON THE PLAN.
4. THE CONTRACTOR SHALL INFORM ALL SUBCONTRACTORS & ALL EMPLOYEES OF THEIR RESPONSIBILITIES IN MINIMISING THE POTENTIAL FOR SOIL EROSION & POLLUTION TO DOWNSLOPE AREAS.
5. IN ADDITION TO SEDIMENT BASINS, THE CONTRACTOR SHALL REGULARLY MAINTAIN SEDIMENT AND EROSION CONTROL STRUCTURES & DESLUD SUCH STRUCTURES PRIOR TO THE REDUCTION IN CAPACITY OF 30% DUE TO ACCUMULATED SEDIMENT. THE SEDIMENT SHALL BE DISPOSED OF ON SITE IN A MANNER APPROVED BY THE ENGINEER.
6. THE CONTRACTOR SHALL TEMPORARILY REHABILITATE WITHIN TEN (10) DAYS ANY DISTURBED AREAS PROVIDING A MINIMUM 80% COVER. FINAL REHABILITATION IS TO BE PROVIDED WITHIN A FURTHER 60 DAYS WITH A MINIMUM 70% COVER.
7. THE CONTRACTOR SHALL PROVIDE WATERING OF THE VEGETATED BATTERS FOR MAINTENANCE PERIOD. PLANT, MACHINERY AND VEHICLES SHALL NOT BE DRIVEN OVER GRASSED AREAS UNLESS ON AN APPROVED HALLAGE ROUTE.
8. ALL DRAINAGE WORKS SHALL BE CONSTRUCTED AND STABILISED AS QUICKLY AS POSSIBLE TO MINIMISE RISK OF EROSION.
9. SITE ACCESS SHALL BE RESTRICTED TO THE NOMINATED POINTS. THE CONTRACTOR SHALL PROVIDE STABILISED SITE ACCESS.
10. DUST AND SITE DISTURBANCE MUST BE KEPT TO A MINIMUM. DURING WINDY WEATHER, LARGE, UNPROTECTED AREAS MUST BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO REDUCE WIND EROSION. ERECT BARRIER FENCING TO MINIMISE LAND DISTURBANCE BY PREVENTING VEHICULAR AND PEDESTRIAN ACCESS TO AREAS BEING REHABILITATED AND LANDS THAT DO NOT NEED TO BE DISTURBED BY THIS PROJECT.
11. STOCKPILE TOPSOILS, SUBSOILS AND OTHER MATERIALS SEPARATELY.
12. TOPSOIL SHALL BE STORED IN LOW MOUNDS NO MORE THAN 2 METRES HIGH AND RE-USED WITHIN TWO MONTHS TO MAINTAIN ACTIVE POPULATIONS OF BENEFICIAL SOIL MICROBES & SEED.
13. PLACE ALL STOCKPILES AT LEAST FIVE METRES FROM AREAS OF LIKELY CONCENTRATED OR HIGH VELOCITY FLOWS, ESPECIALLY EARTH BANKS AND ROADS. IF NECESSARY, EARTH BANKS OR DRAINS WILL BE CONSTRUCTED TO DIVERT LOCALISED RUN-OFF.
14. TURN TOPSOIL STOCKPILES OVER TO AERATE THEM AT MONTHLY INTERVALS. ENSURE VEGETATION IS NOT INCORPORATED INTO THE SOIL.
15. AVOID REVERSING THE SOIL PROFILE MATERIALS DURING FILL OPERATIONS - REPLACE DISTURBED SOILS IN THEIR ORIGINAL ORDER.
16. ON COMPLETION OF MAJOR EARTHWORKS AND BEFORE ADDING TOPSOIL, LEAVE DISTURBED LANDS WITH A LOOSE SURFACE. ALTERNATELY, DISTURBED AREAS PREVIOUSLY COMPACTED BY CONSTRUCTION WORKS WILL BE RIPPED TO MORE THAN 200mm ALONG THE CONTOUR BEFORE APPLYING TOPSOIL.
17. PROVIDING MATERIALS ARE AVAILABLE, SPREAD TOPSOIL TO A MINIMUM DEPTH OF 75mm IN REVEGETATION AREAS ON SLOPES OF 4H:1V OR LESS AND TO A DEPTH OF 40 TO 60mm IN REVEGETATION AREAS STEEPER THAN 4:1.
18. LEAVE TOPSOIL IN A SCARIFIED OR ROUGH CONDITION ONCE REPLACED TO HELP MOISTURE INFILTRATION AND REDUCE SOIL EROSION.
19. ENSURE SOIL IS THOROUGHLY SOAKED TO A DEPTH OF 75mm (RAIN OR IRRIGATION) IMMEDIATELY BEFORE PLANTING.
20. HANDLE TOPSOIL ONLY WHEN IT IS MOIST (NOT WET OR DRY) TO AVOID DECLINE OF SOIL STRUCTURE.

21. THE CONTRACTOR SHALL MAINTAIN A LOG BOOK DETAILING:
 - RECORDS OF ALL RAINFALL
 - CONDITION OF SOIL AND WATER MANAGEMENT STRUCTURES
 - ANY APPLICATION OF FLOCCULATING AGENTS TO SEDIMENT BASIN
 - VOLUMES OF ALL WATER DISCHARGED FROM SEDIMENT BASINS
 - ANY ADDITIONAL REMEDIAL WORKS REQUIRED.
22. THE LOG BOOK SHALL BE MAINTAINED ON A WEEKLY BASIS AND BE MADE AVAILABLE TO ANY AUTHORISED PERSON UPON REQUEST. THE ORIGINAL LOG BOOK SHALL BE ISSUED TO THE PROJECT MANAGER AT THE COMPLETION OF WORKS.
23. ALL ROAD EMBANKMENTS TO BE STABILISED AS PER LANDSCAPE ARCHITECTS DETAILS.
24. A SELF AUDITING PROGRAM SHOULD BE ESTABLISHED BASED ON A CHECK SHEET DEVELOPED FOR THE SITE. A SITE INSPECTION USING THE CHECK SHEET SHOULD BE MADE BY THE SITE MANAGER AT LEAST WEEKLY, IMMEDIATELY BEFORE SITE CLOSURE AND IMMEDIATELY FOLLOWING RAINFALL EVENTS THAT CAUSE RUNOFF.
25. UNDERTAKE THE SELF AUDIT BY:
 - WALKING AROUND THE SITE SYSTEMATICALLY (E.G. CLOCKWISE)
 - RECORDING THE CONDITION OF EVERY BMP EMPLOYED
 - RECORDING MAINTENANCE REQUIREMENTS (IF ANY) FOR EACH BMP
 - RECORDING THE SITE WHERE SEDIMENT IS DISPOSED
 - FORWARDING A SIGNED DUPLICATE OF THE COMPLETED CHECK SHEET TO THE PROJECT MANAGER/DEVELOPERS/ SITE OPERATOR FOR THEIR INFORMATION
26. IN PARTICULAR, INSPECT:
 - LOCATIONS WHERE VEHICLES ENTER AND LEAVE THE SITE
 - ALL INSTALLED EROSION AND SEDIMENT CONTROL MEASURES, ENSURING THEY ARE OPERATING CORRECTLY
 - AREAS THAT MIGHT SHOW WHETHER SEDIMENT OR OTHER POLLUTANTS ARE LEAVING THE SITE OR HAVE POTENTIAL TO DO SO
 - ALL DISCHARGE POINTS, TO ASSESS WHETHER THE EROSION AND SEDIMENT CONTROL MEASURES ARE EFFECTIVE IN PREVENTING IMPACTS TO THE RECEIVING WATERS
27. A SITE INSPECTION USING THE CHECK SHEET WILL BE MADE BY THE SITE MANAGER AT LEAST WEEKLY, IMMEDIATELY BEFORE SITE CLOSURE, AND IMMEDIATELY FOLLOWING RAINFALL EVENTS GREATER THAN 5mm IN 24 HOURS.

A	ISSUE FOR DEVELOPMENT APPLICATION	31/03/2025	EAB	SBF	
Issue	Description	Date	Design	Checked	

Certification by Dr. Michel Cheyaz
i.e. (Prof.) P.D. 11-E. Aust. Offeng.
Civil & Structural Engineer

PLACE STUDIO
Level 5, 140 William Street,
Woolloomooloo, NSW 2011.
J.ALEXANDER-HATZIDIS
NSW ARB # 10035
T 61 431 088 534
W www.PlaceStudio.com.au
E Studio@PlaceStudio.com.au





Council
Ku-Ring-Gai Council
Client
Primo Real Estate

Scale
0 2 4 6 m
SCALE 1:100 @ A0

TELFORD CIVIL
CONSULTING CIVIL & STORMWATER ENGINEERS
Level 14, 32 Smith Street,
Parramatta NSW 2150
PO BOX 3579 Parramatta 2124
Email: info@tefordcivil.com.au
Phone: 02 7809 4931
Company: Telford Consulting Pty Ltd

Project	7-11 POCKLEY AVENUE, ROSEVILLE PROPOSED RESIDENTIAL FLAT BUILDING STORMWATER CONCEPT PLANS DEVELOPMENT APPLICATION	Drawing Title SEDIMENT AND EROSION CONTROL PLAN & DETAILS SHEET 2 OF 2
Scale	As Shown	Project No. 25035
Drawn	110	Issue A

NOT FOR CONSTRUCTION






V-SHAPE SWALE CHANNEL CAPACITY CALCULATIONS



RECTANGULAR SWALE CHANNEL CAPACITY CALCULATIONS

UPSTREAM CATCHMENT CALCULATIONS:
EXTERNAL CATCHMENT AREA = 1,476 m²
 $Q_{100} = CIA/3600 = (0.805 \times 268 \times 1,476) / 3600 = 0.088 \text{ m}^3/\text{s}$

UPSTREAM CATCHMENT CALCULATIONS:
EXTERNAL CATCHMENT AREA = 2,120 m²
 $Q_{100} = CIA/3600 = (0.805 \times 268 \times 2,120) / 3600 = 0.127 \text{ m}^3/\text{s}$



NOTE:
DETAIL TO BE CONFIRMED BY
WATERPROOFING CONSULTANT/ARCHITECT.



Stormwater Drainage System Maintenance Schedule			
Maintenance Action	Frequency	Responsibility	Procedure
General			
Inspect roof drainage system of building and remove any debris/sludge	Six Monthly	Strata/Maintenance Contractor	Remove any leaves or debris and sludge from gutters of building and flush downpipes of building to remove any blockages. Pits downstream of downpipes to be cleaned of flushed debris.
Inspect pits and trench drains on site and remove debris/litter/sludge	Monthly or following Rain Period	Strata/Maintenance Contractor	Remove grate. Remove any debris/litter/sludge from within pits.
Inspect site for litter and floatable debris and remove	Fortnightly	Strata/Maintenance Contractor	Remove litter from site and sweep all driveway and pathways in order to remove leaves or sediments that may enter into the drainage system.
Basement Pump out			
Inspect and clean flap valve,	Six Monthly	Strata/Maintenance Contractor	Remove grate and check flap valve and pipe for blockages and clean. Check hinges for rust and test operation by moving flap to full extent.
Check hinge operation.	Annually	Strata/Maintenance Contractor	Inspect hinge and check its operation.
Check attachment of flap valve to wall pit.	Annually	Strata/Maintenance Contractor	Remove grate and ensure valve fixings are secure.
Check flap valve seal.	Six Monthly	Strata/Maintenance Contractor	Remove grate and fill pit with water, ensure flap seals against side of pit with minimal leakage.
Inspect walls for cracking or spalling.	Annually	Strata/Maintenance Contractor	Remove grate to inspect internal walls, remove vegetation to inspect external wall, repair as required.
Inspect sump and clean.	Six Monthly	Strata/Maintenance Contractor	Remove grate and clean sediment/sludge from sump.
Inspect grate for damage or blockage.	Six Monthly	Strata/Maintenance Contractor	Check both sides of grate for corrosion (particularly welds and corners); also check for damage and blockages.
Inspect outlet pipe and remove blockages	Six Monthly	Strata/Maintenance Contractor	Remove grate and flush outlet pipe to ensure it drains freely. Check for debris on upstream side of return line.
Outlets			
Inspect & remove any blockage of orifices	Six monthly	Strata/Maintenance Contractor	Remove grate & screen to inspect orifice. See plan for location of outlets
Check attachment of orifice plates to wall of chamber and/or pit (gaps less than 5 mm)	Annually	Strata/Maintenance Contractor	Remove grate and screen. Ensure plates are mounted securely, tighten fixings if required. Seal gaps as required.
Check orifice diameters are correct and retain sharp edges	Five yearly	Strata/Maintenance Contractor	Compare diameter to design (see Work-as-Executed) and ensure edge is not pitted or damaged.
Inspect screens and clean	Six monthly	Strata/Maintenance Contractor	Remove grate(s) and screens if required to clean them.
Check attachment of screens to wall of chamber or pit	Annually	Strata/Maintenance Contractor	Remove grate(s) and screen(s). Ensure screen fixings are secure. Repair as required.
Check screen(s) for corrosion	Annually	Strata/Maintenance Contractor	Remove grate(s) and examine screen(s) for rust or corrosion, especially at corners or welds.
Inspect walls (internal and external, if appropriate) for cracks or spalling	Annually	Strata/Maintenance Contractor	Remove grate(s) to inspect internal walls. Repair as required. Clear vegetation from external walls if necessary and repair as required.
Inspect outlet sumps & remove any sediment/sludge	Six monthly	Strata/Maintenance Contractor	Remove grate(s) and screen(s). Remove sediment/sludge build-up and check orifices are clear.
Inspect grate(s) for damage or blockage	Six monthly	Strata/Maintenance Contractor	Check both sides of a grate for corrosion, (especially corners and welds) damage or blockage.
Inspect outlet pipe & remove any blockage	Six monthly	Strata/Maintenance Contractor	Remove grate(s) and screen(s). Ventilate underground storage if present. Check orifices and remove any blockages in outlet pipe. Flush outlet pipe to confirm it drains freely. Check for sludge/debris on upstream side of return line.
Check step irons for corrosion	Annually	Strata/Maintenance Contractor	Remove grate. Examine step irons and repair any corrosion or damage.
Check fixing of step irons is secure	Six monthly	Strata/Maintenance Contractor	Remove grate(s) and ensure fixings are secure prior to placing weight on step iron.
Storage			
Inspect storage & remove any sediment/sludge in pit	Six monthly	Strata/Maintenance Contractor	Remove grate(s) and screen(s). Remove sediment/sludge build-up.
Inspect internal walls of storage (and external, if appropriate) for cracks or spalling	Annually	Strata/Maintenance Contractor	Remove grate(s) to inspect internal walls. Repair as required. Clear vegetation from external walls if necessary and repair as required.
Inspect & remove any debris/litter/mulch etc blocking grates	Six monthly	Strata/Maintenance Contractor	Remove blockages from grate(s) and check if storage is blocked.
Inspect areas draining to the storage(s) & remove debris/mulch/litter etc likely to block screens/grates	Six monthly	Strata/Maintenance Contractor	Remove debris and floatable material likely to be carried to grates.
Compare storage volume to volume approved. (Rectify if loss > 5%)	Annually	Strata/Maintenance Contractor	Compare actual storage available with Work-as Executed plans. If volume loss is greater than 5%, arrange for reconstruction to replace the volume lost. Council to be notified of the proposal.
Inspect storages for subsidence near pits	Annually	Strata/Maintenance Contractor	Check along drainage lines and at pits for subsidence likely to indicate leakages.

NOT FOR CONSTRUCTION

Issue	Description	Date	Design	Checked
A	ISSUE FOR DEVELOPMENT APPLICATION	31/03/2025	EAB	SBF

Certification By: Dr. Michel Cheyaz
S.E., M.E. (Pres), P.D., F.I.E. (Aus.), CPEng,
Civil & Structural Engineer

Architect
PLACE STUDIO
Level 5, 140 William Street,
Woolloomooloo, NSW 2011.
J.ALEXANDER-HATZPLIS
NSW ARB # 10535
T 61 431 088 534
W www.PlaceStudio.com.au
E Studio@PlaceStudio.com.au

Council
Ku-Ring-Gai
Council
Client
Primo Real
Estate

Scale

TELFORD CIVIL
CONSULTING CIVIL & STORMWATER ENGINEERS

Level 14, 32 Smith Street,
Parramatta NSW 2150
PO BOX 3579 Parramatta 2124

Email:
Phone: 02 7809 4931
Company: Telford Consulting Pty Ltd

Project

7-11 POCKLEY AVENUE, ROSEVILLE
PROPOSED RESIDENTIAL FLAT BUILDING
STORMWATER CONCEPT PLANS
DEVELOPMENT APPLICATION

Drawing Title
MISCELLANEOUS
DETAILS SHEET

Scale
N.T.S.

AD
Project No.
25035

Eng. No.
111

Issue
A