
10 NELSON SHORT STREET POTTS HILL CIVIL WORKS PACKAGE

DRAWING LIS	T
<u>DWG No.</u>	DRAWING TITLE
DAC001	COVER SHEET AND LOCALITY PLAN
DAC002	GENERAL NOTES AND LEGENDS
DAC005	GENERAL ARRANGEMENT PLAN
DAC010	SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 1 OF 2
DAC011	SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 2 OF 2
DAC021	SITEWORKS AND STORMWATER DETAILS
DAC025	STORMWATER CATCHMENT PLAN
DAC026	OSD TANK SECTIONS
	SEDIMENT AND EROSION CONTROL PLAN
DAC031	SEDIMENT AND EROSION CONTROL DETAILS

		Bar Scales		Client	Scales		Drawn	JL	Projec
			THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN			NTS	Designed	JL	10
			ANY FORM OR USED FOR ANY				Checked	GJ	
			OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED		Height Datum	AHD	Approved		Title
C RE-ISSUED FOR DA	27-08-2		WITHOUT THE WRITTEN						
B RE-ISSUED FOR DA	28-10-20		PERMISSION OF AT&L						
A ISSUED FOR DA	24-08-1								
Issue Description	Date								
100mm on Original									



F:\17-457 Nelson Short Street\Drgs\Civil\Final\DA\DAC001.dwg

SURVEY NOTES

THE EXISTING SITE CONDITIONS SHOWN ON THE FOLLOWING DRAWINGS HAVE BEEN INVESTIGATED BY SDG, BEING REGISTERED SURVEYORS. THE INFORMATION IS SHOWN TO PROVIDE A BASIS FOR DESIGN. AT & L DOES NOT GUARANTEE THE ACCURACY OR COMPLETENESS OF THE SURVEY BASE OR ITS SUITABILITY AS A BASIS FOR CONSTRUCTION DRAWINGS.

SHOULD DISCREPANCIES BE ENCOUNTERED DURING CONSTRUCTION BETWEEN THE SURVEY DATA AND ACTUAL FIELD DATA. CONTACT AT & L.

THE FOLLOWING NOTES HAVE BEEN TAKEN DIRECTLY FROM THE ORIGINAL SURVEY DOCUMENTS.

- . THIS SURVEY IS NOT A 'LAND SURVEY' AS DEFINED BY SURVEYING AND SPATIAL INFORMATION ACT, 2000.
- 2. THE BOUNDARIES OF THE LAND HAVE NOT BEEN SURVEYED. THE RELATIONSHIP BETWEEN THE BOUNDARIES SHOWN AND FEATURES SURVEYED ARE APPROXIMATE AND SUITABLE FOR PLOTTING PURPOSES ONLY.
- ONLY THOSE SERVICES VISIBLE AT THE TIME OF SURVEY HAVE BEEN
- LOCATED AND ARE QUALITY LEVEL AS A DEFINED BY AS 5488-2013. . UNDERGROUND SERVICES HAVE BEEN PLOTTED FROM 'DIAL BEFORE YOU DIG' PLANS AND ARE QUALITY LEVEL D AS DEFINED BY AS 5488-2013. ALL RELEVANT AUTHORITIES MUST BE CONTRACTED TO DETERMINE THE FULL EXTENT OF SERVICES PRIOR TO ANY PLANNING OR WORKS NEAR THE SITE.
- ONLY TREES GREATER THAN 3.5 METRES IN HEIGHT ARE SHOWN ON THIS PLAN AND THEIR POSITIONS ARE DIAGRAMMATIC ONLY AND MAY REQUIRE ADDITIONAL SURVEY WHERE CRITICAL TO DESIGN.
- CONTOURS ARE INDICATIVE AT GROUND FORM ONLY. SPOT LEVELS ONLY SHOULD BE USED FOR CALACULATIONS OF QUANTITIES WITH CAUTION.
- CONTOUR INTERVAL 0.5m 8. ALL SETOUT LEVELS MUST BE REFERRED TO BENCH MARK.
- 9. THE ORIENTATION OF THIS PLAN IS APPROXIMATE TRUE NORTH. THIS IS BASED ON THE ASSUMPTION THAT THE VARIATION OF TRUE NORTH TO MGA IS 1°06'. THIS HAS NOT BEEN VERIFIED AS PART OF THIS SURVEY AND SHOULD YOU REQUIRE A MORE ACCURATE DETERMINATION OF TRUE NORTH A FURTHER SURVEY IS REQUIRED.
- 10. THE LAND IS AFFECTED BY: • RESTRICTION OF THE USE OF LAND (DP1149790)
- 11. THE LAND IS BENEFITED BY:
- EASEMENT FOR STORMWATER DRAINAGE 3 WIDE (DP1140109) NOT SHOWN
- EASEMENT FOR DRAINAGE 2 WIDE (DP1149790) NOT SHOWN • EASEMENT FOR DRAINAGE 4 WIDE (DP1149790) NOT SHOWN
- EASEMENT FOR TELECOMMUNICATION PURPOSES 0.6 WIDE & VARIABLE
- (DP1149790) NOT SHOWN EASEMENT FOR DRAINAGE 15 WIDE & VARIABLE (DP1149790) NOT SHOWN RIGHT OF CARRIAGEWAY 13.5 WIDE & VARIABLE (DP1149790) NOT
- SHOWN EASEMENT FOR SERVICES 13.5 WIDE & VARIABLE (DP1149790) NOT
- SHOWN 12. COVENANTS AND RESTRICTIONS NOTED ON THE TITLE HAVE NOT BEEN INVESTIGATED

LEGEND:-

- VC denotes VEHICLE CROSSING
- PC denotes PEDESTRIAN CROSSING
- TK denotes TOP OF KERB COM denotes COMMUNICATIONS PIT
- PP denotes POWER POLE
- LP denotes LIGHT POLE HYD denotes HYDRANT
- RHYD denotes RECYCLED HYDRANT
- SV denotes STOP VALVE
- RSV denotes RECYCLED STOP VALVE SWP denotes STORMWATER PIT
- SL denotes SURFACE LEVEL
- IL denotes INVERT LEVEL SMH denotes SEWER MANDHOLE
- SMS denotes SEWER MAINTENANCE SHAFT
- SIP denotes SEWER INSPECTION PIT
- TS denotes TRAFFIC SIGNAL
- TSB denotes TRAFFIC SIGNAL BOX TSP denotes TRAFFIC SIGNAL PIT

EXISTING UNDERGROUND SERVICES NOTES

THE LOCATIONS OF UNDERGROUND SERVICES SHOWN IN THIS SET OF DRAWINGS HAVE BEEN PLOTTED FROM SURVEY INFORMATION AND SERVICE AUTHORITY INFORMATION. THE SERVICE INFORMATION HAS BEEN PREPARED ONLY TO SHOW THE APPROXIMATE POSITIONS OF ANY KNOWN SERVICES AND MAY NOT BE AS CONSTRUCTED OR ACCURATE.

AT & L CAN NOT GUARANTEE THAT THE SERVICES

INFORMATION SHOWN ON THESE DRAWINGS ACCURATELY INDICATES THE PRESENCE OR ABSENCE OF SERVICES OR THEIR LOCATION AND WILL ACCEPT NO LIABILITY FOR INACCURACIES IN THE SERVICES INFORMATION SHOWN FROM ANY CAUSE WHATSOEVER.

CONTRACTORS SHALL TAKE DUE CARE WHEN EXCAVATING ONSITE INCLUDING HAND EXCAVATION WHERE NECESSARY.

CONTRACTORS ARE TO CONTACT THE RELEVANT SERVICE AUTHORITY PRIOR TO COMMENCEMENT OF EXCAVATION WORKS.

CONTRACTORS ARE TO UNDERTAKE A SERVICES SEARCH, PRIOR TO COMMENCEMENT OF WORKS ON SITE. SEARCH RESULTS ARE TO BE KEPT ON SITE AT ALL TIMES.

CONCRETE NOTES

- 1. ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH AS 3600 CURRENT EDITION WITH AMENDMENTS, EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENTS.
- 2. CONCRETE QUALITY ALL REQUIREMENTS OF THE CURRENT ACSE CONCRETE SPECIFICATION DOCUMENT 1 SHALL APPLY TO THE FORMWORK, REINFORCEMENT AND CONCRETE UNLESS NOTED OTHERWISE.

ELEMENT	AS 3600 F'c MPa AT 28 DAYS	SPECIFIED SLUMP	NOMINAL AGG. SIZE
VEHICULAR BASE KERBS, PATHS, AND PITS	32 25	60 80	20 20
CEMENT TYPE SHALL B PROJECT CONTROL TES			

WITH AS 1379. 3. NO ADMIXTURES SHALL BE USED IN CONCRETE UNLESS APPROVED IN WRITING BY AT & L.

- 4. CLEAR CONCRETE COVER TO ALL REINFORCEMENT FOR DURABILITY SHALL BE 40mm TOP AND 70mm FOR EXTERNAL EDGES UNLESS NOTED OTHERWISE.
- 5. ALL REINFORCEMENT SHALL BE FIRMLY SUPPORTED ON MILD STEEL PLASTIC TIPPED CHAIRS, PLASTIC CHAIRS OR CONCRETE CHAIRS AT NOT GREATER THAN 1m CENTRES BOTH WAYS. BARS SHALL BE TIED AT ALTERNATE INTERSECTIONS.
- 6. THE FINISHED CONCRETE SHALL BE A DENSE HOMOGENEOUS MASS, COMPLETELY FILLING THE FORMWORK, THOROUGHLY EMBEDDING THE REINFORCEMENT AND FREE OF STONE POCKETS. ALL CONCRETE INCLUDING SLABS ON GROUND AND FOOTINGS SHALL BE COMPACTED AND CURED IN ACCORDANCE WITH R.M.S SPECIFICATION R83.
- 7. REINFORCEMENT SYMBOLS: N DENOTES GRADE 450 N BARS TO AS 1302 GRADE N
- R DENOTES 230 R HOT ROLLED PLAIN BARS TO AS 1302 SL DENOTES HARD-DRAWN WIRE REINFORCING FABRIC TO AS 1304
- NUMBER OF BARS IN GROUP 17 N 20250
 - NOMINAL BAR SIZE IN mm
 - THE FIGURE FOLLOWING THE FABRIC SYMBOL SL IS THE REFERANCE NUMBER FOR FABRIC TO AS 1304.
- 8. FABRIC SHALL BE LAPPED IN ACCORDANCE WITH THE FOLLOWING DETAIL:

____LAP TWO WIRES

SITEWORKS NOTES

- 1. ORIGIN OF LEVELS:- REFER SURVEY NOTES.
- 2. CONTRACTOR MUST VERIFY ALL DIMENSIONS AND EXISTING LEVELS ON SITE PRIOR TO COMMENCEMENT OF WORK. ANY DISCREPANCIES TO BE REPORTED TO AT & L.
- 3. MAKE SMOOTH CONNECTION WITH EXISTING WORKS.
- 4. ALL TRENCH BACKFILL MATERIAL SHALL BE COMPACTED TO THE SAME DENSITY AS THE ADJACENT MATERIAL.
- 5. ALL SERVICE TRENCHES UNDER VEHICULAR PAVEMENTS SHALL BE BACKFILLED WITH SAND TO 300mm ABOVE PIPE. WHERE PIPE IS UNDER PAVEMENTS BACKFILL REMAINDER OF TRENCH TO UNDERSIDE OF PAVEMENT WITH SAND OR APPROVED GRANULAR MATERIAL COMAPACTED IN 150mm LAYERS TO MINIMUM 98% MODIFIED MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS 1289 5.2.1. (OR A DENSITY INDEX OF NOT LESS THAN 75)
- 6. PROVIDE 10mm WIDE EXPANSION JOINTS BETWEEN BUILDINGS AND ALL CONCRETE OR UNIT PAVEMENTS.
- 7. ASPHALTIC CONCRETE SHALL CONFORM TO R.M.S SPECIFICATION R116.
- 8. ALL BASECOURSE MATERIAL SHALL BE IGNEOUS ROCK QUARRIED MATERIAL TO COMPLY WITH R.M.S FORM 3051 (UNBOUND), R.M.S FORM 3052 (BOUND) COMPACTED TO MINIMUM 98% MODIFIED DENSITY IN ACCORDANCE WITH AS 1289 5.2.1 FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN 1 TEST PER 50m³ OF BASECOURSE MATERIAL PLACED.
- 9. ALL SUB-BASE COURSE MATERIAL SHALL BE IGNEOUS ROCK QUARRIED MATERIAL TO COMPLY WITH R.M.S FORM 3051, 3051.1 AND COMPACTED TO MINIMUM 95% MODIFIED DENSITY IN ACCORDANCE WITH A.S 1289 5.2.1 FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN 1 TEST PER 50m³OF SUB-BASE COURSE MATERIAL PLACED.
- 10. AS AN ALTERNATIVE TO THE USE OF IGNEOUS ROCK AS A SUB-BASE MATERIAL IN (9) A CERTIFIED RECYCLED CONCRETE MATERIAL COMPLYING WITH R.M.S FORM 3051 AND 3051.1 WILL BE CONSIDERED. SUBJECT TO MATERIAL SAMPLES AND APPROPRIATE CERTIFICATIONS BEING PROVIDED TO THE SATISFACTION OF AT & L.
- 11. SHOULD THE CONTRACTOR WISH TO USE A RECYCLED PRODUCT THE CONTRACTOR IS TO SEEK ACCEPTANCE OF THE PRODUCT FROM AT&L. THE PRICE DIFFERENCE BETWEEN AN IGNEOUS PRODUCT AND A RECYCLED PRODUCT SHALL BE CLEARLY INDICATED.
- 12. WHERE NOTED ON THE DRAWINGS THAT WORKS ARE TO BE CARRIED BY OTHERS, (eq. ADJUSTMENT OF SERVICES), THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CO-ORDINATION OF THESE WORKS.

			Bar Scales
C	RE-ISSUED FOR DA	27-08-21	
В	RE-ISSUED FOR DA	28-10-20	
А	ISSUED FOR DA	24-08-17	
Issue	Description	Date	

100mm on Original

CARPARKS

- (A) 1 TEST PER 200m OF FILL PLACED PER 300 LAYER OF FILL. (B) 3 TESTS PER VISIT (C) 1 TEST PER 1000m² OF EXPOSED SUBGRADE TESTING SHALL BE "LEVEL 1" TESTING IN ACCORDANCE WITH AS 3798
- 8. FILLING TO BE PLACED AND COMPACTED IN MAXIMUM 150mm LAYERS
- 9. NO FILLING SHALL TAKE PLACE TO EXPOSE SUBGRADE UNTIL THE AREA HAS BEEN PROOF ROLLED IN THE PRESENCE OF AT & L AND APPROVAL GIVEN IN WRITING THAT FILLING CAN PROCEED.
- 5. FOR NON COHESIVE MATERIAL, COMPACT TO 75% DENSITY INDEX. 6. BEFORE PLACING FILL PROOF ROLL EXPOSED SUBGRADE WITH AN 8 TONNE (MIN) DEADWEIGHT SMOOTH DRUM VIBRATORY ROLLER TO DETECT THEN REMOVE SOFT SPOTS (AREAS WITH MORE THAN 2mm MOVEMENT UNDER ROLLER). 7. FREQUENCY OF COMPACTION TESTING SHALL BE NOT LESS THAN :-

STORMWATER DRAINAGE NOTES

- . STORMWATER DESIGN CRITERIA (A) AVERAGE RECURRENCE INTERVAL 1:100 YEARS ROOFED AREAS TO SURCHARGE PIT 1:20 YEARS EXTERNAL PAVEMENTS (B) RAINFALL INTENSITIES: TIME OF CONCENTRATION: 5 MINUTES
- 1:100 YEARS= 242 mm/hr 1:20 YEARS= 187 mm/hr (C) RUNOFF COEFFICIENTS:
- ROOF AREAS =1.0 C100 EXTERNAL PAVEMENTS: C20 =1.0 . PIPES 300 DIA. AND LARGER TO BE REINFORCED CONCRETE CLASS '3' LONGITUDINAL AND CLASS '4' TRANSVERSE ROAD CROSSING
- APPROVED SPIGOT AND SOCKET WITH RUBBER RING JOINTS. U.N.O. B. PIPES UP TO 300 DIA SHALL BE SEWER GRADE UPVC WITH SOLVENT WELDED JOINTS.
- 4. EQUIVALENT STRENGTH VCP OR FRC PIPES MAY BE USED. SUBJECT TO THE APPROVAL OF BANKSTOWN CITY COUNCIL.
- 5. ALL STORMWATER DRAINAGE LINES UNDER PROPOSED BUILDING SLABS TO BE UPVC PRESSURE PIPE GRADE 6. ENSURE ALL VERTICALS AND DOWNPIPES ARE UPVC PRESSURE PIPE, GRADE 6 FOR A MIN OF 3.0m IN HEIGHT
- 6. PIPES TO BE INSTALLED TO TYPE HS1 SUPPORT IN ACCORDANCE WITH AS 3725 (1989) IN ALL CASES BACKFILL TRENCH WITH SAND TO 300mm ABOVE PIPE. WHERE PIPE IS UNDER PAVEMENTS BACKFILL REMAINDER OF TRENCH TO UNDERSIDE OF PAVEMENT WITH SAND OR APPROVED GRANULAR MATERIAL COMPACTED IN 150mm LAYERS TO MINIMUM 98% STANDARD MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS 1289 5.2.1. (OR A DENSITY INDEX OF NOT LESS THAN 75)
- ALL INTERNAL WORKS WITHIN PROPERTY BOUNDARIES ARE TO COMPLY WITH THE REQUIREMENTS OF AS 3500 3.1 (1998) AND AS/NZS 3500 3.2
- 8. PRECAST PITS MAY BE USED EXTERNAL TO THE BUILDING SUBJECT TO APPROVAL BY AT & L
- 9. ENLARGERS, CONNECTIONS AND JUNCTIONS TO BE PREFABRICATED FITTINGS WHERE PIPES ARE LESS THAN 300 DIA.
- 10. WHERE SUBSOIL DRAINS PASS UNDER FLOOR SLABS AND VEHICULAR PAVEMENTS, UNSLOTTED uPVC SEWER GRADE PIPE IS TO BE USED.
- 1. CARE IS TO BE TAKEN WITH LEVELS OF STORMWATER LINES. GRADES SHOWN ARE NOT TO BE REDUCED WITHOUT APPROVAL. 12. GRATES AND COVERS SHALL CONFORM TO AS 3996.
- 13. AT ALL TIMES DURING CONSTRUCTION OF STORMWATER PITS, ADEQUATE SAFETY PROCEDURES SHALL BE TAKEN TO ENSURE AGAINST THE POSSIBILITY OF PERSONNEL FALLING DOWN PITS
- 14. ALL EXISTING STORMWATER DRAINAGE LINES AND PITS THAT ARE TO REMAIN ARE TO BE INSPECTED AND CLEANED. DURING THIS PROCESS ANY PART OF THE STORMWATER DRAINAGE SYSTEM THAT WARRANTS REPAIR SHALL BE REPORTED TO THE SUPERINTENDENT/ENGINEER FOR FURTHER DIRECTIONS.

BULK EARTHWORKS NOTES

- 1. ORIGIN OF LEVELS: REFER SURVEY NOTES
- 2. STRIP ALL TOPSOIL/ORGANIC MATERIAL FROM CONSTRUCTION AREA AND REMOVE FROM SITE OR STOCK PILE AS DIRECTED BY SUPERINTENDENT. 3. EXCAVATED MATERIAL TO BE USED AS STRUCTURAL FILL PROVIDED THE PLACEMENT MOISTURE CONTENT OF THE MATERIAL IS +/- 2% OF THE **OPTIMUM MOISTURE CONTENT**
- 4. COMPACT FILL AREAS AND SUBGRADE TO NOT LESS THAN: STANDARD DRY DENSITY LOCATION
- (AS 1289 E 5.1.1.) UNDER ROADS AND

98% LANDSCAPED AREAS UNLESS NOTED OTHERWISE 98%

EROSION AND SEDIMENT CONTROL NOTES

GENERAL INSTRUCTIONS

- 1. THE SITE SUPERINTENDENT/ENGINEER WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE LOCATED AS DOCUMENTED.
- 2. ALL WORK SHALL BE GENERALLY CARRIED OUT IN ACCORDANCE WITH a. LOCAL AUTHORITY REQUIREMENTS **b. EPA REQUIREMENTS** c. NSW DEPARTMENT OF HOUSING MANUAL "MANAGING URBAN STORMWATER, SOILS AND CONSTRUCTION", 4th EDITION, MARCH
- 3. MAINTAIN THE EROSION CONTROL DEVICES TO THE SATISFACTION OF THE SUPERINTENDENT AND THE LOCAL AUTHORITY.
- 4. WHEN STORMWATER PITS ARE CONSTRUCTED. PREVENT SITE RUNOFF ENTERING UNLESS SEDIMENT FENCES ARE ERECTED AROUND PITS.
- 5. CONTRACTOR IS TO ENSURE ALL EROSION & SEDIMENT CONTROL DEVICES ARE MAINTAINED IN GOOD WORKING ORDER AND OPERATE EFFECTIVELY. REPAIRS AND OR MAINTENANCE SHALL BE UNDERTAKEN AS REQUIRED, PARTICULARLY FOLLOWING STORM EVENTS.

LAND DISTURBANCE

- 6. WHERE PRACTICAL. THE SOIL EROSION HAZARD ON THE SITE WILL BE KEPT AS LOW AS POSSIBLE. TO THIS END, WORKS SHOULD BE UNDERTAKEN IN THE FOLLOWING SEQUENCE:
- (A) INSTALL A WIND FENCE ALONG THE BOUNDARIES AS SHOWN ON PLAN. REFER DETAIL.
- (B) INSTALL A SEDIMENT FENCE ALONG THE BOUNDARIES AS SHOWN ON PLAN. REFER DETAIL.
- (C) CONSTRUCT STABILISED CONSTRUCTION ENTRANCE TO LOCATION AS DETERMINED BY SUPERINTENDENT/ENGINEER. REFER DETAIL
- (D) INSTALL SEDIMENT BASIN AS SHOWN ON PLAN
- (E) INSTALL SEDIMENT TRAPS AS SHOWN ON PLAN.
- (F) UNDERTAKE SITE DEVELOPMENT WORKS IN ACCORDANCE WITH THE ENGINEERING PLANS. WHERE POSSIBLE, PHASE DEVELOPMENT SO THAT LAND DISTURBANCE IS CONFINED TO AREAS OF WORKABLE SIZE.

EROSION CONTROL

- 7. DURING WINDY WEATHER, LARGE, UNPROTECTED AREAS WILL BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO KEEP DUST UNDER CONTROL.
- 8. FINAL SITE LANDSCAPING WILL BE UNDERTAKEN AS SOON AS POSSIBLE AND WITHIN 20 WORKING DAYS FROM COMPLETION OF CONSTRUCTION ACTIVITIES.

SEDIMENT CONTROL

- 9. STOCKPILES WILL NOT BE LOCATED WITHIN 2 METRES OF HAZARD AREAS, INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH VELOCITY FLOWS SUCH AS WATERWAYS. WHERE THEY ARE BETWEEN 2 AND 5 METRES FROM SUCH AREAS, SPECIAL SEDIMENT CONTROL MEASURES SHOULD BE TAKEN TO MINIMISE POSSIBLE POLLUTION TO DOWNSLOPE WATERS, E.G. THROUGH INSTALLATION OF SEDIMENT FENCING.
- 10. ANY SAND USED IN THE CONCRETE CURING PROCESS (SPREAD OVER THE SURFACE) WILL BE REMOVED AS SOON AS POSSIBLE AND WITHIN 10 WORKING DAYS FROM PLACEMENT.
- 11. WATER WILL BE PREVENTED FROM ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS IT IS RELATIVELY SEDIMENT FREE, I.E. THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR ANY LIKELY SEDIMENT HAS BEEN FILTERED THROUGH AN APPROVED STRUCTURE.
- 12. TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES WILL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE REHABILITATED.

OTHER MATTERS

- 13. ACCEPTABLE RECEPTORS WILL BE PROVIDED FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER.
- 14. ANY EXISTING TREES WHICH FORM PART OF THE FINAL LANDSCAPING PLAN WILL BE PROTECTED FROM CONSTRUCTION ACTIVITIES BY:
- (A) PROTECTING THEM WITH BARRIER FENCING OR SIMILAR MATERIALS INSTALLED OUTSIDE THE DRIP LINE
- (B) ENSURING THAT NOTHING IS NAILED TO THEM (C) PROHIBITING PAVING, GRADING, SEDIMENT WASH OR PLACING OF STOCKPILES WITHIN THE DRIP LINE EXCEPT UNDER THE
- FOLLOWING CONDITIONS. (I) ENCROACHMENT ONLY OCCURS ON ONE SIDE AND NO CLOSER
- TO THE TRUNK THAN EITHER 1.5 METRES OR HALF THE DISTANCE BETWEEN THE OUTER EDGE OF THE DRIP LINE AND THE TRUNK, WHICH EVER IS THE GREATER
- (II) A DRAINAGE SYSTEM THAT ALLOWS AIR AND WATER TO CIRCULATE THROUGH THE ROOT ZONE (E.G. A GRAVEL BED) IS PLACED UNDER ALL FILL LAYERS OF MORE THAN 300 MILLIMETRES DEPTH
- (III) CARE IS TAKEN NOT TO CUT ROOTS UNNECESSARILY NOR TO COMPACT THE SOIL AROUND THEM.

SITEWORKS LEGEND


EXISTING


	EXISTING BOUNDARY
5.00 PROPOSED	EXISTING CONTOUR
	PROPOSED BOUNDARY
<u> </u>	EXISTING BOUNDARY TO
5.00	PROPOSED CONTOUR
• F4.35	PROPOSED LEVEL
K&G	KERB AND GUTTER (REF
<u> </u>	KERB ONLY (REFER CCB
	MEDIUM DUTY VEHICLE C (REFER CBB STD DWG-0
SAWCUT	PAVEMENT SAWCUT
— << — ^{FP} o	SUBSOIL DRAINAGE AND
375ø	STORMWATER PIPE, SIZ
]	STORMWATER LINE WITH
	KERB INLET PIT (REFER
	KERB INLET PIT (SAG) (F
\boxtimes	JUNCTION PIT
	SURFACE INLET PIT
\rightarrow \rightarrow	OVERLAND FLOW PATH

KERBING NOTES

- 1. ALL CONCRETE TO HAVE A MINIMUM COMPRESSIVE STRENGTH OF 25 MPa U.N.O IN REINFORCED CONCRETE NOTES.
- 2. ALL KERBS, GUTTERS, DISH DRAINS AND CROSSINGS TO BE CONSTRUCTED ON MIN. 100mm GRANULAR BASECOURSE COMPACTED TO MINIMUM 95% MODIFIED DRY DENSITY (AS 1289 5.2.1).
- 3. EXPANSION JOINTS (E.J) TO BE FORMED FROM 10mm COMPRESSIBLE CORK FILLER BOARD FOR THE FULL DEPTH OF THE SECTION AND CUT TO PROFILE. EXPANSION JOINTS TO BE LOCATED AT DRAINAGE PITS, ON TANGENT POINTS OF CURVES AND ELSEWHERE AT MAX 12m CENTRES EXCEPT FOR INTEGRAL KERBS WHERE THE EXPANSION JOINTS ARE TO MATCH THE JOINT LOCATIONS IN THE SLABS.
- 4. WEAKENED PLANE JOINTS TO BE MIN 3mm WIDE AND LOCATED AT 3m CENTRES EXCEPT FOR INTEGRAL KERBS WHERE THE WEAKENED PLANE JOINTS ARE TO MATCH THE JOINT LOCATIONS IN THE SLABS.
- 5. BROOMED FINISH TO ALL RAMPED AND VEHICULAR CROSSINGS. ALL OTHER KERBING OR DISH DRAINS TO BE STEEL FLOAT FINISHED.
- 6. IN THE REPLACEMENT OF KERB AND GUTTER :-EXISTING ROAD PAVEMENT IS TO BE SAWCUT 900mm U.N.O FROM THE LIP OF GUTTER. UPON COMPLETION OF THE NEW KERB AND GUTTER NEW BASECOURSE AND SURFACE TO BE LAID 900mm WIDE U.N.O.
- 7. EXISTING ALLOTMENT DRAINAGE PIPES ARE TO BE BUILT INTO THE NEW KERB AND GUTTER WITH 100mm DIA HOLE.
- 8. EXISTING KERB AND GUTTER IS TO BE COMPLETELY REMOVED WHERE NEW KERB AND GUTTER IS SHOWN.

	Client	Scales	Drawn	JL	Projec
THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN		NTS	Designed	JL	10
ANY FORM OR USED FOR ANY	POTTS HILL	Grid MGA	Checked	GJ	
OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED	INVESTMENT PTY LTD	Height AHD Datum AHD	Approved		Title
WITHOUT THE WRITTEN PERMISSION OF AT&L					





NELSON SHORT STREET POTTS HILL

DIAL BEFORE YOU DIG 1100 PRIOR TO COMMENCEMENT OF WORK TO OBTAIN ALL CURRENT SERVICE AUTHORITY PLANS

CONTRACTOR SHALL CALL;



A1

Issue

С

REFER CCB STD DWG S-101A)

ГН САР CCB STD DWG S-101)

E AND FLOW DIRECTION

FLUSHING POINT

(A800

CROSSING

3 STD DWG S-001)


FER CCB STD DWG S-001)


BE REMOVED

		SHEET DAC010
	EXISTING	
	SYDNEY WATER RESERVOIR	
		SHEET DAC011
	Bar Scales	
C RE-ISSUED FOR DA B RE-ISSUED FOR DA	27-08-21 28-10-20	1 : 500 @ A1 1 : 1000 @ A3
A ISSUED FOR DA	24-08-17	
Issue Description	100mm on Original	




Project Scales Drawn Client JL 1 : 500 THIS DRAWING CANNOT BE Designed JL COPIED OR REPRODUCED IN Checked ANY FORM OR USED FOR ANY MGA GJ Grid POTTS HILL OTHER PURPOSE OTHER THAN Height Datum Approved INVESTMENT PTY LTD AHD THAT ORIGINALLY INTENDED Title WITHOUT THE WRITTEN PERMISSION OF AT&L






F:\17-457 Nelson Short Street\Drgs\Civil\Final\DA\DAC005.dwg

			FZ RHYD HYD ■ S S S S S S S S S S S S S	
			STORMWATER PIT	
			STORMWATER PIT Grate RL:56.59 Invert No Access	
			Z UNOS V	\sim
				X
			5071 ET 502 Q	C
				a
				\ \
				4
				(
			STREE	h
			EXISTING TELSTRA PITS	MS
			TO BE ADJUSTED TO SUIT	1
			TIE INTO EXISTING KERB & GUTTER. MAKE SMOOTH CONNECTION.	11 201
	EXISTING SYDNEY WATER		TREE TO BE REMOVED (TYP)	M
	RESERVOIR		TIE INTO EXISTING KERB & GUTTER.	
			MAKE SMOOTH CONNECTION.	
			SHOR	/
				ГК ! КI 9
				<u> </u>
			TIE INTO EXISTING KERB & GUTTER.	
			MAKE SMOOTH CONNECTION.	
			PROVIDE MEDIUM-DUTY VEHICULAR FOOTWAY CROSSING AS PER COUNCILSTD DWG S-008	
			Net son	
			Š Ž	
			DEPTH AND LOCATION OF EXISTING TELSTRA	
			AS PART OF CC WORKS	
				' M
				<u>}</u> ≥≤
			RELOCATE EXISTING STORMWATER PIT	-MS
			AS SHOWN.	the C
				J
				+
			Bar Scales	r >
			0 5 10 15 20 25m	
C	RE-ISSUED FOR DA	27-08-21	21 1 : 250 @ A1 1 : 500 @ A3	
B A	RE-ISSUED FOR DA ISSUED FOR DA	28-10-20 24-08-17	20	
sue	Description	Date	-	
	100mm on Original			




F:\17-457 Nelson Short Street\Drgs\Civil\Final\DA\DAC010.dwg



	Client	Scales	4 050	Drawn	JL	Projec
THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN			1 : 250	Designed	JL	10
ANY FORM OR USED FOR ANY	POTTS HILL	Grid	MGA	Checked	GJ	
OTHER PURPOSE OTHER THAN	INVESTMENT PTY LTD	Height Datum	AHD	Approved		
THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L						- Title

F:\17-457 Nelson Short Street\Drgs\Civil\Final\DA\DAC011.dwg



	Client		Scales		Drawn	JL	Project	Civil Engineers and Pr	oject Managers							
	ING CANNOT BE		A A	AS SHOWN	S SHOWN Designed JL 10 NELSON SHOWN		10 NELSON SHORT STREET		Level 7, 153 Walk North Sydney NS	W 2060						
	R USED FOR ANY	POTTS HILL	Grid MGA		Height AHD		Height AHD		Grid MGA		Checked	GJ	POTTS HILL	318	ABN 96 130 882 4 Tel: 02 9439 17 Fax: 02 9923 10	777
	OSE OTHER THAN NALLY INTENDED	INVESTMENT PTY LTD									Approved		Title		www.atl.net.au info@atl.net.au	000
WITHOUT	THE WRITTEN SION OF AT&L							Status FOR APF NOT TO BE USED FC		A1						
								Drawing No.	Project No. 17-457	Issue C						

F:\17-457 Ne Street\Drgs\CIVII\FInal\DA\DACU21.dwg

EXISTING SYDNEY WATER RESERVOIR




			Bar Scales						
]						
				0	10	20	30	40	50m
С	RE-ISSUED FOR DA	27-08-21			1 : 50() @ A1	1:1000 @	A3	
В	RE-ISSUED FOR DA	28-10-20							
А	ISSUED FOR DA	24-08-17							
Issue	Description	Date							


100mm on Original

BRUNKER


ROAD

	Client	Scales	4 . 500	Drawn	JL	Project
THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN			1 : 500	Designed	JL	10
ANY FORM OR USED FOR ANY	POTTS HILL	Grid	MGA	Checked	GJ	1
OTHER PURPOSE OTHER THAN	INVESTMENT PTY LTD	Height Datum	AHD	Approved		
THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L						Title






F:\17-457 Nelson Short Street\Drgs\Civil\Final\DA\DAC025.dwg



			Bar Scales					
				0	500	1000	1500	2000mm
					1:20@A1 1:40@A3			
				0	1	2 3	4	5m
В	RE-ISSUED FOR DA	28-10-20			1.50	۵ ۸ 1 1 . 1(
А	ISSUED FOR DA	24-08-17			1:00	@ A1 1:1(CAWJU	
Issue	Description	Date						


100mm on Original



ject	Civil Engineers and Project Managers					
0 NELSON SHORT STREET POTTS HILL	Level 7, 153 Walker Street North Sydney NSW 2060 ABN 96 130 882 405 Tel: 02 9439 1777 Fax: 02 9923 1055 www.atl.net.au info@atl.net.au					
° CATCHMENT PLAN	FOR AF	A1				
	Drawing No.	Project No. 17-457	Issue B			
EV17 4E7 Nolean Shart Streat/Dread(Swill Final) DAVDACO26 dwg						

F:\17-457 Nelson Short Street\Drgs\Civil\Final\DA\DAC026.dwg

EXISTING SYDNEY WATER RESERVOIR



C	RE-ISSUED FOR DA	27-08-21
В	RE-ISSUED FOR DA	28-10-20
А	ISSUED FOR DA	24-08-17
Issue	Description	Date
	100mm on Original	<u></u>

LEGEND


xx	SEDIMENT FENCE. REFER TO DWG DAC031.
>	CATCH DRAIN. REFER TO DWG DAC031.
В	BARRIER FENCE. REFER TO DWG DAC031.
	ROCK CHECK DAM. REFER TO DWG DAC031.
\frown	MESH AND GRAVEL INLET FILTER. REFER TO DWG DAC031.
\boxtimes	GEOTEXTILE INLET. REFER TO DWG DAC031.
	STABILISED SITE ACCESS AND TRUCK WASH DOWN AREA. REFER TO DWG DAC021.
\sim	PROPOSED SITE ACCESS GATE
$ \begin{tabular}{ c c c c } \hline & & & & \\ \hline & & & & & \\ \hline & & & & & \\ \hline & & & &$	LEVEL SPREADER. REFER TO DWG DAC031.

<u>NOTE:</u>

- 1. FOR EROSION AND SEDIMENTATION CONTROL DETAILS REFER DWG DAC031
- 2. ALL SEDIMENT AND EROSION CONTROL MEASURES TO BE IN ACCORDANCE WITH 'MANAGING URBAN STORMWATER, SOIL AND CONSTRUCTION VOLUME 1 (2004) BY LANDCOM.


Civil Engineers and Project Managers Level 7, 153 Walker Street North Sydney NSW 2060 **10 NELSON SHORT STREET** ABN 96 130 882 405 POTTS HILL Tel: 02 9439 1777 Fax: 02 9923 1055 www.atl.net.au info@atl.net.au FOR APPROVAL A1 SEDIMENT AND EROSION CONTROL PLAN Drawing No. Project No. Issue DAC030 17-457 С

F:\17-457 Nelson Short Street\Drgs\Civil\Final\DA\DAC030.dwg



100mm on Original

		Client	Scales		Drawn	JL	Proje
	THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L	POTTS HILL INVESTMENT PTY LTD	AS SHOWN		Designed	JL	10
			Grid	MGA	Checked	GJ	
			Height Datum	AHD	Approved		Title
					-		– ^{Title}




STAR PICKETS

GEOTEXTILE FILTER

RUNOFF WATER WITH SEDIMENT $\widehat{}$

FARRIC



THE EXIT SHALL BE MAINTAINED IN A CONDITION WHICH PREVENTS TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS OF WAY. THIS MAY REQUIRE REPAIR AND OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS OF WAY MUST BE REMOVED IMMEDIATELY.





SCALE 1:200





NI MI





HEAVY DUTY GAUGE WIRE MESH —

GRATE AS SPECIFIED

- EXISTING SURFACE LEVEL.


- KERB-SIDE INLET

— TIMBER SPACER TO

FILTERED WATER

SUIT

NTS



LEVEL SPREADER (OR SILL) NTS

WIRE OR STEEL MESH-DISTURBED AREA DETAIL OF OVERLAP \checkmark GROUND 🗸 \mathbf{V} UNDISTURBED AREA \checkmark SEDIMENT FENCE NTS