EDMUND RICE COLLEGE, WEST WOLLONGONG - TAS BUILDING & ACCESS WORKS DA

112 Mount Keira Rd WEST WOLLONGONG NSW


DEVELOPMENT APPLICATION DRAWING REGISTER

l	ID	Name	Re
	1000 S	ERIES - SITE	
	DA000 DA1100 DA1101 DA1102 DA1103	DRAWING REGISTER & LOCATION PLAN EXISTING SITE PLAN SITE ANALYSIS PLAN PROPOSED SITE PLAN INDICATIVE SITE MANAGEMENT PLAN DETAILED SITE PLAN SHEET 01 - DEMOLITION PLAN	02 07 02 02 02
l	DA1201	DETAILED SITE PLAN SHEET 02	03
	2000 S	ERIES - BLOCK L TAS HUB	
	DA2220 DA2221 DA2222 DA2300	BLOCK L - PROPOSED GROUND FLOOR PLAN BLOCK L - PROPOSED FIRST FLOOR PLAN BLOCK L - PROPOSED ROOF PLAN BLOCK L - ELEVATIONS AND SECTIONS SHEET 01	02 02 07 02
	DA2301 DA2900 DA2910 DA2920 DA2930 DA2931 DA2940 DA2941 DA2951	BLOCK L - ELEVATIONS AND SECTIONS SHEET 02 BLOCK L - DESIGN APPROACH DIAGRAMS BLOCK L - EGRESS PLANS BLOCK L - ACCESSIBILITY PLANS BLOCK L - EXTERNAL FINISHES NORTH ELEVATION BLOCK L - EXTERNAL FINISHES SOUTH ELEVATION BLOCK L - WINTER SHADOW DIAGRAMS BLOCK L - SUMMER SHADOW DIAGRAMS BLOCK L - PERSPECTIVES	

3000 SERIES - BLOCK A/B LIFT WORKS

	DEMILO DECON A/ B EII I WOMEO	
DA3220	LIFT - LOWER GROUND & GROUND FLOOR PLAN	02
DA3221	LIFT - FIRST FLOOR PLAN & ROOF PLAN	0
DA3300	LIFT - ELEVATIONS	O
DA3350	LIFT - SECTIONS	0′
DA3920	LIFT - ACCESSIBILITY PLANS	0
DA3930	LIFT - EXTERNAL FINISHES NORTH ELEVATION	O
DA3931	LIFT - EXTERNAL FINISHES SOUTH ELEVATION	0
DA3940	LIFT - SHADOW DIAGRAMS	0





AYLIE O'HANLON

SITE BOUNDARY

FIGURED DIMENSIONS TO BE USED ONLY. DO NOT SCALE

ANY DISCREPANCIES MUST BE REFERED TO THE ARCHITECT PRIOR TO THE COMMENCEMENT OF WORK ON SITE.

DIMENSIONS TO BE VERIFIED ON SITE BEFORE ANY SHOP DRAWINGS ARE COMMENCED OR OTHER WORK PUT IN HAND

MMEDIATELY REFER ANY SIGNIFICANT DISCREPANCIES TO THE ARCHITECT



EDMUND RICE COLLEGE, WEST WOLLONGONG - TAS BUILDING & ACCESS WORKS DA

112 Mount Keira Rd WEST WOLLONGONG NSW
CLIENT
EDMUND RICE COLLEGE

SCALE:

DRAWN BY:

CHECKED BY:


ALL DRAWINGS © QUINN O'HANLON ARCHITECTS PTY LTD

DRAWING REGISTER

LOCATION PLAN


DRAWING REGISTER & LOCATION PLAN


2301 DAOOO O




QUINN O'HANLON ARCHITECTS - MANAGING DIRECTOR NSW ARCHITECTS REGISTRATION NO: 9460 FIGURED DIMENSIONS TO BE USED ONLY. DO NOT SCALE ANY DISCREPANCIES MUST BE REFERED TO THE ARCHITECT PRIOR TO THE COMMENCEMENT OF WORK ON SITE. DIMENSIONS TO BE VERIFIED ON SITE BEFORE ANY SHOP DRAWINGS ARE COMMENCED OR OTHER WORK PUT IN HAND IMMEDIATELY REFER ANY SIGNIFICANT DISCREPANCIES TO THE ARCHITECT NOTE: IF AN (e) IS LOCATED AT THE FRONT OF AN ABBREVIATION IT INDICATES THE ELEMENT IS EXISTING, OTHERWISE IT SHOULD BE ASSUMED AS PROPOSED BUILDING WORKS PROPOSED LANDSCAPE WORKS **EXISTING BOUNDARY** ———— EXISTING SEWER B)W------ [B)W- EXISTING WATER)T----- (e) $T\cdot$ EXISTING TELECOMMUNICATIONS E - EXISTING POWER EXISTING STORMWATER ARCHITECTS QUINN O'HANLON ARCHITECTS PTY LTD NEWCASTLE PO Box 293 NEWCASTLE NSW 2293 (02) 4929 1165 **T** EDMUND RICE COLLEGE, WEST WOLLONGONG - TAS **BUILDING & ACCESS** ADDRESS
112 Mount Keira Rd WEST WOLLONGONG NSW CLIENT EDMUND RICE COLLEGE JB, CS, MF, EW, CYK ALL DRAWINGS © QUINN O'HANLON ARCHITECTS PTY LTD **EXISTING SITE PLAN**

AYLIE O'HANLON





AYLIE O'HANLON QUINN O'HANLON ARCHITECTS - MANAGING DIRECTOR NSW ARCHITECTS REGISTRATION NO: 9460 FIGURED DIMENSIONS TO BE USED ONLY. DO NOT SCALE ANY DISCREPANCIES MUST BE REFERED TO THE ARCHITECT PRIOR TO THE COMMENCEMENT OF WORK ON SITE. DIMENSIONS TO BE VERIFIED ON SITE BEFORE ANY SHOP DRAWINGS ARE COMMENCED OR OTHER WORK PUT IN HAND IMMEDIATELY REFER ANY SIGNIFICANT DISCREPANCIES TO THE ARCHITECT







EDMUND RICE COLLEGE, WEST WOLLONGONG - TAS **BUILDING & ACCESS**


ADDRESS
112 Mount Keira Rd WEST WOLLONGONG NSW CLIENT EDMUND RICE COLLEGE


JB, CS, MF, EW, CYK 6/08/2024 ALL DRAWINGS © QUINN O'HANLON ARCHITECTS PTY LTD

PROPOSED SITE PLAN






















(e)EASEMENTS


CC

ANY DISCREPANCIES MUST BE REFERED TO THE ARCHITECT PRIOR TO THE COMMENCEMENT OF WORK ON SITE. DIMENSIONS TO BE VERIFIED ON SITE BEFORE ANY SHOP DRAWINGS ARE COMMENCED OR OTHER WORK PUT IN HAND IMMEDIATELY REFER ANY SIGNIFICANT DISCREPANCIES TO THE ARCHITECT FLOOR PLAN LEGEND NOTE: IF AN (e) IS LOCATED AT THE FRONT OF AN ABBREVIATION IT INDICATES THE ELEMENT IS EXISTING, OTHERWISE IT SHOULD BE ASSUMED AS NEW (n) **HATCH LEGEND** PROPOSED BUILDING PROPOSED SITE WORKS PROPOSED VERTICAL CIRCULATION PROPOSED SOFT LANDSCAPING NO NEW WORKS EXISTING SEWER ----- [8]SW------ EXISTING STORMWATER - - - - (e) T· EXISTING TELECOMMUNICATIONS ARCHITECTS QUINN O'HANLON ARCHITECTS PTY LTD 1/153 Victoria Road, GLADESVILLE NSW 2111 (02) 9240 3655 **F** NEWCASTLE 20 Church Street, WICKHAM NSW 2293 PO Box 293 NEWCASTLE NSW 2293 (02) 4929 1165 **T** EDMUND RICE COLLEGE, **WEST WOLLONGONG - TAS BUILDING & ACCESS WORKS DA** ADDRESS
112 Mount Keira Rd WEST WOLLONGONG NSW EDMUND RICE COLLEGE 3/09/2024 DEVELOPMENT APPLICATION 30/11/2023 DEVELOPMENT APPLICATION JB, CS, MF, EW, CYK DRAWN BY: CHECKED BY: 3/09/2024 ALL DRAWINGS © QUINN O'HANLON ARCHITECTS PTY LTD GENERAL ARRANGEMENT LIFT - LOWER GROUND &

AYLIE O'HANLON

QUINN O'HANLON ARCHITECTS - MANAGING DIRECTOR NSW ARCHITECTS REGISTRATION NO: 9460

FIGURED DIMENSIONS TO BE USED ONLY. DO NOT SCALE





AYLIE O'HANLON GUINN O'HANLON ARCHITECTS - MANAGING DIRECTOR NSW ARCHITECTS REGISTRATION NO: 9460 FIGURED DIMENSIONS TO BE USED ONLY. DO NOT SCALE ANY DISCREPANCIES MUST BE REFERED TO THE ARCHITECT PRIOR TO THE COMMENCEMENT OF WORK ON SITE. DIMENSIONS TO BE VERIFIED ON SITE BEFORE ANY SHOP DRAWINGS ARE COMMENCED OR OTHER WORK PUT IN HAND IMMEDIATELY REFER ANY SIGNIFICANT DISCREPANCIES TO THE ARCHITECT



ACCESS PLAN LEGEND








EDMUND RICE COLLEGE, WEST WOLLONGONG - TAS BUILDING & ACCESS WORKS DA ADDRESS 112 Mount Keira Rd WEST WOLLONGONG NSW CLIENT


CLIENT EDMUND RICE COLLEGE


30/11/2023 DEVELOPMENT APPLICATION JB, CS, MF, EW, CYK CHECKED BY: 30/11/2023 ALL DRAWINGS © QUINN O'HANLON ARCHITECTS PTY LTD

DRAWING TITLE
ACCESSIBILITY PLAN


LIFT - ACCESSIBILITY PLANS







AYLIE O'HANLON QUINN O'HANLON ARCHITECTS - MANAGING DIRECTOR NSW ARCHITECTS REGISTRATION NO: 9460 FIGURED DIMENSIONS TO BE USED ONLY. DO NOT SCALE ANY DISCREPANCIES MUST BE REFERED TO THE ARCHITECT PRIOR TO THE COMMENCEMENT OF WORK ON SITE. DIMENSIONS TO BE VERIFIED ON SITE BEFORE ANY SHOP DRAWINGS ARE COMMENCED OR OTHER WORK PUT IN HAND IMMEDIATELY REFER ANY SIGNIFICANT DISCREPANCIES TO THE ARCHITECT







EDMUND RICE COLLEGE, WEST WOLLONGONG - TAS **BUILDING & ACCESS** WORKS DA


ADDRESS
112 Mount Keira Rd WEST WOLLONGONG NSW CLIENT EDMUND RICE COLLEGE

3/09/2024 DEVELOPMENT APPLICATION	02
30/11/2023 DEVELOPMENT APPLICATION	01
DATE REVISION SCALEBAR:	ISSUE
5	1
SCALE: 1:100 @ A1	
DRAWN BY: JB, CS, MF, EW, CYK	1
CHECKED BY: AOH	
DATE: 3/09/2024	
ALL DRAWINGS © QUINN O'HANLON ARCHITEC	 TS PTY LTD
DRAWING TITLE ELEVATIONS	

LIFI - ELEVATIONS








AYLIE O'HANLON

GUINN O'HANLON ARCHITECTS - MANAGING DIRECTOR
NSW ARCHITECTS REGISTRATION NO: 9460

FIGURED DIMENSIONS TO BE USED ONLY. DO NOT SCALE

ANY DISCREPANCIES MUST BE REFERED TO THE ARCHITECT PRIOR TO THE
COMMENCEMENT OF WORK ON SITE.





ELEVATION/SECTION LEGEND

NOTE: IF AN (a) IS LOCATED AT THE FRONT OF AN ABBREVIATION IT INDICATES THE ELEMENT IS EXISTING, OTHERWISE IT SHOULD BE ASSUMED AS NEW (n)

[e] EXISTING (n) NEW

BAL BALUSTRADE RD ROLLER DOOR BRK BRICK RL RELATIVE LEVEL CL CLADDING (LIGHTWEIGHT) RW RETAINING WALL CONC. CONCRETE TO AN ANY MATTER TABLE.

BALUSTRADE BIL RELATIVE LEVEL
CLADDING (LIGHTWEIGHT) RW RETAINING WALL
CONCRETE RWT RAIN WATER TANK
DOWN PIPE SC STEEL COLUMN
FINISHED CEILING LEVEL SPD SPREADER DOWNPIPE
FINISHED FLOOR LEVEL SPD SPREADER DOWNPIPE
HANDRALL TGI TACTILE GROUND INDICATO
METAL ROOF TOW TOP OF WALL
PLASTERBOARD TBC TO BE CONFIRMED
PAINT FINISH



EDMUND RICE COLLEGE, WEST WOLLONGONG - TAS BUILDING & ACCESS WORKS DA

ADDRESS
112 Mount Keira Rd WEST WOLLONGONG NSW
CLIENT
EDMUND RICE COLLEGE

30/11/2023 DEVELOPMENT APPLICATION

DATE REVISION

SCALEBAR:

0 5 10

SCALE: 1:100 @ A1

DRAWN BY: JB, CS, MF, EW, CYK

CHECKED BY: AOH

DATE: 30/11/2023


ALL DRAWINGS @ QUINN O'HANLON ARCHITECTS PTY LTD


DRAWING TITLE

SECTIONS

LIFT - SECTIONS

DRAWING NUMBER ISS DA3350 O





DESIGN APPROACH DIAGRAMS

BUILDING FORM

- GUIDED BY 9M LEP HEIGHT LIMIT AND FLOOD LEVEL DESIGN REQUIREMENTS.
- ROOF FORM SET TO DECREASE PERCEPTION OF MASS AND BULK.
- BUILDING BULK REDUCED TO THE WEST TO ALLOW OTHER BUILDINGS TO BE EVIDENT IN THE BACKGROUND ON APPROACH ALONG THE MAIN DRIVE.
- HEAVY MASONRY GROUND FLOOR, LIGHTWEIGHT FIRST FLOOR + SHADING SCREEN
 TIERED SPECTATOR SEATING CREATES A SMOOTH TRANSITION BETWEEN BUILDING AND
- MAINTAIN EXISTING OR REPLACE TREES WHERE POSSIBLE TO SOFTEN APPEARANCE OF FACADES.

ECOLOGICALLY SUSTAINABLE DEVELOPMENT

- NATURAL VENTILATION USING LOUVRE CLERESTORY WINDOWS.
- HIGH LEVEL LOUVRE WINDOWS TO ENABLE PASSIVE COOLING HEAT STACK.
- CLERESTORY PROVIDES NATURAL LIGHT INTO THE DEEP FLOOR PLATE.
- MAINTAIN EXISTING OR REPLACE TREES WHERE POSSIBLE TO PROVIDE SHADE FOR THE NEW BUILDING.
- SHADE SCREEN TO NORTHERN ELEVATION TO REDUCE SOLAR HEAT GAIN.
- BUILDING BULK REDUCED TO THE WEST TO REDUCE SOLAR HEAT GAIN.

SITE CONNECTIVITY


- BUILDING CONNECTS INTO EXISTING VEHICULAR AND PEDESTRIAN NETWORKS.
- ALLOWS FOR ACCESSIBLE PATHS CONNECTED TO THE REMAINDER OF THE CAMPUS.
 IMPROVE ACCESSIBILITY ACROSS THE SITE WITH THOUGHTFUL AND CONNECTED LANDSCAPES, WHILE MAINTAINING EXISTING SPORTS AND PLAY SPACE INFRASTRUCTURE.
- STAFF SUPERVISION THROUGH TO AND AROUND NEW BUILDING FACILITATED BY OPEN SPACES.
- TIERED SPECTATOR SEATING TO SPORTS FIELD CREATES AN INTERMEDIARY SPACE FOR BOTH LEARNING AND SPECTATING.
- BUILDING PLACEMENT CREATES CIRCULATION LOOP BETWEEN TAS, MULTI-PURPOSE
- HALL, ARTS CENTRE AND BACK TO THE MAJORITY OF THE CAMPUS.
 SITING DESIGNED TO MINIMISE AND SUPPORT CONTINUED OPERATION OF COLLEGE AND DELIVERY OF SUCCESSFUL CURRICULUM IN EXISTING SPACES WITHOUT THE NEED FOR

TEMPORARY WORKS.


- WAYFINDING + SITE PERCEPTION
 STREAMLINE TRAFFIC AND ACCESSIBILITY FOR DELIVERIES FOR TAS
- VIEW OF CHAPEL AND ADMIN FROM ENTRY CLEAR ONSITE WAYFINDING, LEGIBILITY & IDENTITY.
- NEW BUILDING REFERENCES EXISTING FINISHES AND MATERIAL PALETTES ON THE SITE AS THE TAS CURRICULUM IS ONE OF THE MOST POPULAR; PLACES THIS SPACE IN THE CAMPUS FOREGROUND, SPEAKING TO THE COLLEGE IDENTITY.



SITE DIAGRAM



SHORT SECTION DIAGRAM



AYLIE O'HANLON

QUINN O'HANLON ARCHITECTS - MANAGING DIRECTO

FIGURED DIMENSIONS TO BE USED ONLY. DO NOT SCALE

ANY DISCREPANCIES MUST BE REFERED TO THE ARCHITECT PRIOR TO THI COMMENCEMENT OF WORK ON SITE. DIMENSIONS TO BE VERIFIED ON SITE BEFORE ANY SHOP DRAWINGS ARE COMMENCED OR OTHER WORK PUT IN HAND



ARCHITECTS

GUINN O'HANLON ARCHITECTS PTY LTD

SYDNEY

1/153 Victoria Road, GLADESVILLE NSW 2111

(02) 9420 3155 T
(02) 9240 3655 F

NEWCASTLE

20 Church Street, WICKHAM NSW 2293
PO Box 293
NEWCASTLE NSW 2293
(02) 4929 1165 T

www.qoh.net.au W

EDMUND RICE COLLEGE, WEST WOLLONGONG - TAS BUILDING & ACCESS WORKS DA

112 Mount Keira Rd WEST WOLLONGONG NSW
CLIENT
EDMUND RICE COLLEGE

ALL DRAWINGS © QUINN O'HANLON ARCHITECTS PTY LTD

4/12/2023

BLOCK L - DESIGN APPROACH DIAGRAMS

DRAWING NUMBER ISSUED TO SERVICE OF THE PROPERTY OF THE PROPER







NORTHERN ELEVATION

AYLIE O'HANLON

GUINN O'HANLON ARCHITECTS - MANAGING DIRECTOR NSW ARCHITECTS REGISTRATION NO: 9460

FIGURED DIMENSIONS TO BE USED ONLY. DO NOT SCALE

ANY DISCREPANCIES MUST BE REFERED TO THE ARCHITECT PRIOR TO THE COMMENCEMENT OF WORK ON SITE. DIMENSIONS TO BE VERIFIED ON SITE BEFORE ANY SHOP DRAWINGS ARE COMMENCED OR OTHER WORK PUT IN HAND IMMEDIATELY REFER ANY SIGNIFICANT DISCREPANCIES TO THE ARCHITECT





SOUTH EAST CORNER VIEW





EAST ELEVATION - CARPARK



PROJECT EDMUND RICE COLLEGE, WEST WOLLONGONG - TAS BUILDING & ACCESS WORKS DA ADDRESS 112 Mount Keira Rd WEST WOLLONGONG NSW CLIENT EDMUND RICE COLLEGE

6/08/2024 30/11/2023	DEVELOPMENT APPLICATION DEVELOPMENT APPLICATION		02 01
DATE	REVISION		ISSUE
SCALEBAR	₹:		
SCALE:		@ A1	
DRAWN B	Y:	JB, CS, MF, EW, CYK	
CHECKED	BY:	НОА	
DATE:		6/08/2024	
	•		

ALL DRAWINGS © QUINN O'HANLON ARCHITECTS PTY LTD

DRAWING TITLE
PERSPECTIVES

BLOCK L - PERSPECTIVES



Job No:



ABN 44 003 755 986

W www.qoh.net.au

1096

E ohd@qoh.net.au

SYDNEY

1/153 Victoria Road GLADESVILLE NSW 2111

T 02 9420 3633

NEWCASTLE

20 Church Street WICKHAM NSW 2293

PO Box 293 WICKHAM NSW 2293

T 02 4929 1165

TRANSMITTAL OF DOCUMENTS

ERC West Wollongong - TAS Building Project:

112 Mount Keira Rd, West Wollongong NSW 2500 Address:

Edmund Rice College West Wollongong Client:

Date	of I	Issue
------	------	-------

Day	30	06							
Month	11	08							
Year	23	24							

Dwg No.	Drawing Title	Revision
DA 1800	Drawing Pegister & Site Plan	กาไกว

DA 1800 Dr	rawing Register & Site Plan	01	02							
DA 1801 La	andscape Plan 1	01	02							
DA 1802 La	andscape Plan 2	01	02							
DA 1803 La	andscape Plan 3	01	02							
DA 1804 La	andscape Plan 4	01	02							
DA 1805 Ty	ypical Details & Plant Schedule	01	02							

Distribution No. of Copies

QOH Quinn O'Hanlon Architects P/L	1	1							
Reason for Issue / Method of Issue / Method of Deliv	ery								
I - For Information A - For Approval P - Preliminary T - For Tender C - For Construction	А	А							
P - PDF H - Hardcopy D - DWG	Р	Р							
E - Email F - Fax C - Courier M - Mail H - By Hand	Ε	Е							
Issued by:	WF	WF							

EDMUND RICE COLLEGE, WEST WOLLONGONG - TAS BUILDING & ACCESS WORKS DA

112 Mount Keira Rd WEST WOLLONGONG NSW

DEVELOPMENT APPLICATION

OHD DRAWING REGISTER

D Name

DA1800 DRAWING REGISTER & LOCATION PLAN

DA1801 LANDSCAPE PLAN 1
DA1802 LANDSCAPE PLAN 2
DA1803 LANDSCAPE PLAN 3

DA1803 LANDSCAPE PLAN 3 DA1804 LANDSCAPE PLAN 4

DA1805 TYPICAL DETAILS & PLANT SCHEDULE



LOCATION PLAN

JANE O'HANLON O'HANLON DESIGN PTY LTD - DIREC

FIGURED DIMENSIONS TO BE USED ONLY. DO NOT SCALE

ANY DISCREPANCIES MUST BE REFERED TO THE ARCHITECT PRIOR TO THE
COMMENCEMENT OF WORK ON SITE.

DIMENSIONS TO BE VERIFIED ON SITE BEFORE ANY SHOP DRAWINGS ARE
COMMENCED OR OTHER WORK PUT IN HAND

MMEDIATELY REFER ANY SIGNIFICANT DISCREPANCIES TO THE ARCHITECT



NOTE: IF AN (e) IS LOCATED AT THE FRONT OF AN ABBREVIATION IT INDICATES
THE ELEMENT IS EXISTING, OTHERWISE IT SHOULD BE ASSUMED AS

PROPOSED BUILDING WORKS

PROPOSED SITE WORKS

SITE BOUNDARY
PROPOSED LANDSCAPE WORKS

OT FOR CONSTRUCTION



EDMUND RICE COLLEGE,
WEST WOLLONGONG - TAS
BUILDING & ACCESS
WORKS DA

112 Mount Keira Rd WEST WOLLONGONG NSW
CLIENT
EDMUND RICE COLLEGE

30/11/2023 DEVELOPMENT APPLICATION

DATE REVISION

SCALEBAR:

1:2000 @ A1

DRAWN BY:

CHECKED BY:

DATE:

30/11/2023


NORTH


A L L DRAWINGS © O'HANLON DESIGN PTY LTD


DRAWING REGISTER & LOCATION PLAN

1096 DA1800 01












5. Banksia serrata (Old Man Banksia) 6. Eucalyptus sideroxylon (Red Ironbark) 7. Cupaniopsis anacardioides (Tuckeroo)


— EQUAL) IN FIGURE OF EIGHT PATTERN. LOOSELY TIED _ **TREE** AS SELECTED STAKES
x3 (1800 x 50 x 50mm)
HARDWOOD STAKES INSTALLED
CLEAR OF ROOT BALL MULCH — FORM WATERING DISH TO BASE OF PLANT MULCH
— MIN 75mm OF HIGH QUALITY
— MULCH AS SPECIFIED TOPSOIL

300mm HIGH QUALITY

TOPSOIL TO SUIT SELECTED

PLANTS AND SITE CONDITIONS AS SPECIFIED DO NOT INSTALL PLANT ROOT — BALL BELOW SUBGRADE WITHOUT CULTIVATION EXISTING SUBGRADE TYP. TREE/300mm & ABOVE PLANTING DETAIL





2	TYP. PLANTING DETA
$\overline{}$	1:

	KEY	NAME	POT SIZE	SPACING	SIZE AT MATURITY (HxW)m	STAKING
	TREES					
01	Ba	Brachychiton acerifolius	75L	as shown	12 x 6	3
02	Ec	Eucalyptus cinerea	75L	as shown	11 x B	3
03	TL	Tristaniopsis laurina	75L	as shown	12 x 5	3
04	Af	Angophora floribunda	75L	as shown	15 x 8	3
05	Bs	Banksia serrata	75L	as shown	10 x 5	3
06	ES	Eucalyptus sideroxylon	75L	as shown	15 x 8	3
07	Ca	Cupaniopsis anacardioides	75L	as shown	8 x 6	3
	PLANT	ING		•		
08		Doryanthes excelsa	250mm	1/2m²	1.5 x 1.5	-
09	$\times \times$	Asplenium australascium	250mm	1/m ²	1.0 x 1.0	-
12	$\times \times$	Telopea speciosissima	45L	1/4m²	3.0 x 2.0	-
13	$\times \times$	Indigofera australis	250mm	1/2m²	1.5 x 1.5	-
10		Westringia fruticosa	250mm	1/m²	1.0 x 1.0	-
14	//	Correa Alba	250mm	1/m²	1.0 x 1.0	-
15		Lomandra longifolia	145mm	2/m²	0.8 x 0.8	-
11	$\langle \langle \langle \rangle \rangle$	Hardenbergia violacea	TUBE	1/m²	0.5 x 0.2	-
16	$\rightarrow \rightarrow$	Scaevola calendulacea	TUBE	1/m²	0.2 x 1.0	-
17		Hibbertia scandens	TUBE	1/m²	0.3 x 1.5	-
18	///	Carpobrotus glaucescens	TUBE	1/m²	0.2 x 1.5	-

1. ALL NEW GARDEN BEDS TO BE INSTALLED WITH SUITABLE NEW TOPSOIL AND MULCH.
2. IRRIGATION TO BE PROVIDED TO NEW GARDENS.
3. PLANTING GENERALLY TO BE LOW MAINTENANCE, NON-TOXIC AND NATIVE SPECIES SUITABLE FOR SCHOOL SITES.
4. NOTE "SIZE AT MATURITY" IS DEPENDANT ON MANY FACTORS.
5. REFER TO ARBORIST REPORT FOR MORE INFORMATION ON EXISTING TREES.

NOT FOR CONSTRUCTION

JANE O'HANLON O'HANLON DESIGN PTY LTD - DIRECTOR AILA REGISTRATION NO: 395

FIGURED DIMENSIONS TO BE USED ONLY. DO NOT SCALE

ANY DISCREPANCIES MUST BE REFERED TO THE ARCHITECT PRIOR TO THE COMMENCEMENT OF WORK ON SITE.

DIMENSIONS TO BE VERIFIED ON SITE BEFORE ANY SHOP DRAWINGS ARE COMMENCED OR OTHER WORK PUT IN HAND IMMEDIATELY REFER ANY SIGNIFICANT DISCREPANCIES TO THE ARCHITECT



EDMUND RICE COLLEGE, **WEST WOLLONGONG - TAS BUILDING & ACCESS** WORKS DA

112 Mount Keira Rd WEST WOLLONGONG NSW EDMUND RICE COLLEGE

30/11/2023	DEVELOPMENT APPLICATION		01	
DATE	REVISION			ISSUE
SCALE:		1:10 @ A1	<u> </u>	
SCALE:	Y:			
		1:10 @ A1 WF, MF WF		
DRAWN B	BY:	WF, MF		

DRAWING TITLE
LANDSCAPE PLANS TYPICAL DETAILS & PLANT SCHEDULE



SHRUBS, GRASSES, STRAPPY LEAF PLANTS, CLIMBERS AND GROUNDCOVERS
8. Doryanthes excelsa (Gymea Lilly)
9. Asplenium australasicum (Birds Nest Fern)
10. Westringia fruticosa (Coastal Rosemary)
11. Hardenbergia violacea (False Sarsaparilla)
15. Lomandr 12. Telopea speciosissima (Waratah) 13. Indigofera australis (Australian Indigo) 14. Correa Alba (White Correa) 15. Lomandra longifolia (Mat Rush)

- 16. Scaevola calendulacea (Dune Fan Flower) 17. Hibbertia scandens (Golden Guinea Flower) 18. Carpobrotus glaucescens (Pigface)



PROPOSED CRITICAL USE DEVELOPMENT LOT 419 DP1249737, 112 MOUNT KEIRA ROAD, WEST WOLLONGONG DEVELOPMENT APPLICATION CIVIL PLANS EDMUND RICE COLLEGE



Sheet List Table Sheet Number Sheet Title Title Page 01 02 Stormwater Plan 1 03 Stormwater Plan 2 Catchment Plan 1 04 05 Catchment Plan 2 06 Bulk Earthworks 07 OSD Details 08 Drainage Calculations 1 Drainage Calculations 2 SWM 11 SWM Details

LOCALITY SKETCH 1:5000 @ A1



GENERAL NOTES

- G1. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH WOLLONGONG DEVELOPMENT CODE AND TO THE REQUIREMENTS OF COUNCIL'S AUTHORISED OFFICER.
- G2. INSPECTIONS BY THE AUTHORISED OFFICER SHALL BE CARRIED OUT AT THE FOLLOWING STAGES:
- (a) PRIOR TO INSTALLATION OF EROSION AND SEDIMENT CONTROL STRUCTURES (b) PRIOR TO BACKFILLING PIPELINES, SUBSOIL DRAINS, TRENCH BEDDING AND DAMS
- (c) PRIOR TO CASTING OF PITS AND OTHER CONCRETE STRUCTURES, INCLUDING KERB AND GUTTER (d) PROOF ROLLER TEST OF SUBGRADE AND SUB-BASE
- (e) ROLLER TEST OF COMPLETED PAVEMENT PRIOR TO PLACEMENT OF WEARING COURSE (f) FORMWORKS PRIOR TO POURING CONCRETE IN PARKING AREA FOR FOOTPATH CROSSING AND OTHER ASSOCIATED WORK (q) PRIOR TO BACKFILLING PUBLIC UTILITY CROSSINGS IN ROAD RESERVES
- (h) PRIOR TO PLACEMENT OF ASPHALTIC CONCRETE (i) FINAL INSPECTION AFTER ALL WORKS ARE COMPLETED AND 'WORKS AS EXECUTED' PLANS HAVE BEEN SUBMITTED TO
- G3. NO TREES TO BE REMOVED UNLESS APPROVAL IS GRANTED BY COUNCIL
- G4. MAKE SMOOTH JUNCTIONS WITH EXISTING WORKS.
- G5. NO WORK TO BE CARRIED OUT ON COUNCIL PROPERTY OR ADJOINING PROPERTIES WITHOUT THE WRITTEN PERMISSION
- G6. VEHICULAR ACCESS AND ALL SERVICES TO BE MAINTAINED AT ALL TIMES TO ADJOINING PROPERTIES AFFECTED BY

- REGARDING TREATMENT OF SALINE AFFECTATION ARE TO BE IMPLEMENTED.
- G10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE VERIFICATION OF THE LOCATION OF ANY EXISTING SERVICES AFFECTING THE WORKS AREA, ANY DAMAGED SERVICES SHALL BE REPAIRED AT THE CONTRACTORS COST.

EARTHWORKS NOTES

- E1. EARTHWORKS TO BE CARRIED OUT TO THE SATISFACTION OF THE PCA AND GEOTECHNICAL ENGINEER, UNSOUND MATERIALS ARE
- E3. ALL BATTERS ARE TO BE SCARIFIED TO ASSIST WITH ADHESION OF TOP SOIL TO BATTER FACE
- 3798 2007. WHERE IT IS PROPOSED TO USE TEST METHOD AS1289 E8.1 OR AS1289 E8.2 TO DETERMINE THE FIELD DENSITY, A
- SAND REPLACEMENT METHOD SHALL BE USED TO CONFIRM THE RESULTS AS DIRECTED BY COUNCIL. THE GEOTECHNICAL TESTING AUTHORITY SHALL HAVE A LEVEL 1 RESPONSIBILITY FOR ALL FILLING AS DEFINED IN APPENDIX B AS 3798-2007, AND AT THE END OF THE WORKS SHALL CONFIRM THE EARTHWORKS COMPLY WITH THE REQUIREMENTS OF THE SPECIFICATION AND DRAWINGS.
- E6. THE CONTRACTOR SHALL CONTROL SEDIMENTATION, EROSION AND POLLUTION DURING CONSTRUCTION IN ACCORDANCE WITH MANAGING URBAN STORWATER: SOILS AND CONSTRUCTION VOLUME 1 (LANDCOM 2004) AND MANAGING URBAN STORMWATER: SOILS AND CONSTRUCTION VOLUME 2 (DEPARTMENT OF ENVIRONMENT AND CLIMATE CHANGE 2007).

ROADWORKS NOTES

- R3. 150 X 50 H.D. GALVANISED STEEL KERB OUTLETS TO BE PLACED IN LAYBACK KERB AND 90mm DIA. GALVANISED STEEL PIPE SECTION TO BE PLACED IN UPRIGHT KERB ON LOW SIDE OF LOTS. PROVIDE SUITABLE ADAPTOR TO ALLOW CONNECTION OF 90mm
- R4. PERAMBULATOR CROSSINGS TO BE PROVIDED IN ALL KERB RETURNS OR WHERE REQUIRED BY COUNCIL R5. SERVICE CONDUITS TO BE PLACED AS DIRECTED BY ENDEAVOUR ENERGY. TELECOMMUNICATIONS AND AS REQUIRED BY THE
- R7. SIGNPOSTING AND LINEMARKING TO CONFORM WITH AS1742.2 RAISED RETRO- REFLECTIVE PAVEMENT MARKERS TO CONFORM
- R8. STREET SIGNS TO COMPLY WITH COUNCIL'S SPECIFICATION FOR STREET NAME SIGNS AND MUST BE INSTALLED BY THE
- R9. ALL LEVELS ARE TO BE SET OUT FROM ESTABLISHED STATE SURVEY MARKS.

STORMWATER NOTES


- S1. ALL PIPES TO BE SPIGOT AND SOCKET, RUBBER RING JOINTED. ALL PIPES IN ROAD RESERVES (OTHER THAN ROOF WATER AND
- SUBSOIL) ARE TO BE STEEL REINFORCED CONCRETE PIPES. S2. ALL LONGITUDINAL PIPELINES IN ROADS MUST BE LOCATED UNDER KERB AND GUTTER AND BE BACKFILLED WITH 7mm
- AGGREGATE WHERE 10-15% OF FINES IS ALLOWABLE UNLESS OTHERWISE INDICATED ON PLANS AND APPROVED BY COUNCIL. S3. DRAINAGE LINES MUST BE BACKFILLED AS PER SHELLHARBOUR CITY COUNCILS DEVELOPMENT CODE C221 PIPE DRAINAGE. THREE
- (3) METRES OF AGLINE WRAPPED IN GEOTECH STOCKING MUST BE PROVIDED TO ALL DOWNSTREAM PITS. S4. ALL GULLY PITS TO COUNCIL'S STANDARD AND LINTELS CENTRALLY PLACED AT SAG PITS.
- S5. ALL PITS MUST BE BENCHED AND STREAMLINED. PROVIDE SL72 REINFORCEMENT AND STEP IRONS IN ALL PITS OVER 1.2M
- S6. CONCRETE TO HAVE MINIMUM COMPRESSIVE STRENGTH OF 25 MPA AT 28 DAYS UNLESS SPECIFIED OTHERWISE BY COUNCIL
- ENGINEER. S7. ALL INTER ALLOTMENT DRAINAGE MUST HAVE A MINIMUM COVER OF 300mm TO THE TOP OF PIPE UNLESS OTHERWISE
- APPROVED BY THE COUNCIL ENGINEER S8. CATCH DRAINS MUST BE CONSTRUCTED AS PER SWMP.
- S9. ALL COMMON DRAINAGE LINES MUST BE LAID CENTRALLY WITHIN 1.2m-3.0m EASEMENTS. CLEANING EYES MUST BE PROVIDED IMMEDIATELY DOWNSTREAM OF ALL SLOPE JUNCTIONS.
- S10. ONE HUNDRED (100) YEAR OVERLAND FLOW PATHS MUST BE FORMED AND SHOWN ON WORK AS EXECUTED DRAWINGS.
- S11. ADEQUATE PROVISION TO BE MADE FOR SCOURING AND SEDIMENTATION TO ALL DRAINAGE WORKS IN ACCORDANCE WITH SHELLHARBOUR CITY COUNCILS DEVELOPMENT CODE.
- S12. COMMON DRAINAGE LINES MUST BE INSTALLED AFTER SEWERAGE LINES HAVE BEEN INSTALLED WHERE SEWER IS PROPOSED ADJACENT TO INTER ALLOTMENT

GEOTECHNICAL NOTES

- GT1. THE CONTRACTOR SHALL IMPLEMENT EROSION AND SEDIMENT CONTROL MEASURES AS NECESSARY, AND TO THE SATISFACTION OF COUNCIL PRIOR TO THE COMMENCEMENT OF CONSTRUCTION AND DURING CONSTRUCTION SEE SWMP.
- GT2. TESTS SHALL BE UNDERTAKEN ON ANY PROPOSED FILL MATERIALS TO ENSURE THAT THEY DO NOT HAVE A HIGH
- DISPERSION POTENTIAL AS DEFINED BY EMERSON CRUMB/DISPERSION TESTS (AS1289 C8-1980) GT3. ALL FILLING AND PAVEMENT CONSTRUCTION MUST BE UNDERTAKEN TO THE REQUIREMENTS OF AS3798-2007 THE FOLLOWING COMPACTION LEVELS ARE RECOMMENDED:
 - LOT FILLING 98% STANDARD ROAD SUB-GRADE 100% STANDARD ROAD SUB-BASE 95% MODIFIED
 - ROAD BASE 98% MODIFIED
- GT4. ALL TESTING WORKS SHALL BE CONTROLLED AND CERTIFIED BY A N.A.T.A REGISTERED LABORATORY. A COLLATED COPY OF ALL TEST CERTIFICATES, ACCOMPANIED BY AN OVERALL SITE PLAN, CLEARLY INDICATING THE LOCATION OF EACH TEST AND FILL AREAS ETC, AND THE LABORATORY CERTIFICATE COVERING THE WHOLE OF THE AREA TESTED ARE TO BE FORWARDED TO COUNCIL UPON COMPLETION.
- GT5. FINAL PAVEMENT THICKNESS TO BE DETERMINED AFTER BOXING OUT BY JOINT INSPECTION BY N.A.T.A REGISTERED LABORATORY AND COUNCIL'S ENGINEER. PAVEMENT REPORT TO BE AVAILABLE TO COUNCIL A MINIMUM OF TWO CLEAR DAYS PRIOR TO INSPECTION.

	No.	DESCRIPTION
2	В	REVISED TO CLIENTS COMMENTS
2	С	REVISED DRAINAGE LINES
<u>></u>	D	REVISED TO UPDATED ARCH
	Ε	REVISED TO ARCH COMMENTS

REVISED TO ARCH COMMENTS





WOLLONGONG - HEAD OFFICE Shop 1, 18 Arrow Avenue Figtree NSW 252 PO Box 506 Figtree NSW 2525 T 61 2 4227 4233 F 61 2 4227 413 E info@siteplus.com.a managemei

E le	Height Datur	A.H.D.	Client Title
15 16	Drawn	I.B.	
5 3 3	Designed	I.B.	
nt	Checked	A.C.	Dwg Status
_	Approved	A.C.	Dwg Status

EDMUND RICE COLLEGE

APPROVAL


WOLLONGONG


PROPOSED CRITICAL USE DEVELOPMENT 112 MOUNT KEIRA RD WEST WOLLONGONG Sheet 01 of 11


23153.DA.C01


AS NOTED @ A?

TITLE PAGE









IMPERVIOUS AREA - EXISTING SCALE 1:250

0 2.5 5 METRES 1:250 @ A1 1:500 @ A3



OSD REQUIREMENT CALCUATIONS

CALCULATIONS CARRIED OUT AS PER WOLLONGONG CITY COUNCIL'S DCP CHAPTER E14 - STORMWATER MANAGEMENT CLAUSE 10.1.2.

 $= 3606 \text{ m}^2$ SUBJECT AREA EXISTING IMPERVIOUS AREA = 25 m² PROPOSED IMPERVIOUS AREA = 2441 m²

AS THE DEVELOPMENT INCREASES THE IMPERVIOUS AREA OF THE SITE BY MORE THAN 100m², OSD IS REQUIRED.



NON-POTABLE USAGE RATES: - TOTAL NUMBER OF TOILETS (INCL. ACCESSIBLE) - TOILET PAN/URINAL DEMAND FOR SCHOOLS HENCE, TOTAL DAILY USAGE FOR TOILETS

OSD REQUIREMENT CALCUATIONS

 REUSE FOR IRRIGATION (PET-RAIN) - HENCE, TOTAL YEARLY USAGE FOR IRRIGATION

- PROPOSED TOTAL RAINWATER STORAGE

- % REUSE DEMAND MET (MUSIC MODEL)

TOTAL AREA OF OVAL

CALCULATIONS FOR RAINWATER RE-USE AS PER MUSIC MODEL

- TOTAL ROOF AREA DRAINING TO RAINWATER STORAGE

= 120kL = 14.83%

= 1839m²

= 7

 $\frac{= 0.06kL/DAY}{= 0.42kL/DAY}$

<u>= 0.4kL/yr/m²</u>

= 2580kL/yr

 $= 6450 \,\mathrm{m}^2$

Ref & Dwg No PROPOSED CRITICAL USE DEVELOPMENT

23153.DA.C05 112 MOUNT KEIRA RD WEST WOLLONGONG Sheet 05 of 11

AS NOTED @ A1

DESCRIPTION ဖ္ B REVISED TO CLIENTS COMMENTS C REVISED DRAINAGE LINES $\stackrel{\mathcal{O}}{>}$ D REVISED TO UPDATED ARCH 뿐 E REVISED TO ARCH COMMENTS F REVISED TO ARCH COMMENTS

DRN APP DATE I.B. A.C. 21/11/23 I.B. A.C. 24/11/23 I.B. A.C. 29/11/23 I.B. A.C. 27/08/24 I.B. a.c. 29/08/24



WOLLONGONG - HEAD OFFICE Shop 1, 18 Arrow Avenue E info@siteplus.com.au

Height Datum A.H.D. Figtree NSW 2525 PO Box 506 Figtree NSW 2525 T 61 2 4227 4233 F 61 2 4227 4133 management

I.B.

I.B.

A.C.

A.C.

EDMUND RICE COLLEGE WOLLONGONG APPROVAL

IMPERVIOUS AREA - PROPOSED


SCALE 1:250

1:250 @ A1 1:500 @ A3


0 2.5 5

SCALE

CATCHMENT PLAN 2







CUT/FILL SUMMARY

- CUT/FILL SUMMARY ASSUMED 200mm TOP SOIL STRIPPING PRIOR TO EXCAVATION OF CUT OR PLACEMENT OF FILL.

- NO ALLOWANCE MADE FOR UNSUITABLE MATERIAL THAT MAY BE ENCOUNTERED ON SITE.

- FILL OR SUSPENDED SLAB DESIGN TO BE CONFIRMED DURING DESIGN DEVELOPMENT.

<u>SUMMARY</u>

CUT= 15 cu.m 2693 cu.m FILL=


TOTAL IMPORT OF MATERIAL 2678 cu.m TO SITE=

0 2.5 5 10 15 METRES 1:250 @ A1 1:500 @ A3 SCALE



SURFACE ELEVATION DATA													
NUMBER	MINIMUM ELEVATION	MAXIMUM ELEVATION	COLOR										
1	-0.84	0.00											
2	0.00	0.50											
3	0.50	1.00											
4	1.00	1.50											
5	1.50	2.18											

	No.	DESCRIPTION
)	В	REVISED TO CLIENTS COMMENTS
5	С	REVISED DRAINAGE LINES
) -	D	REVISED TO UPDATED ARCH
<u>.</u>	Ε	REVISED TO ARCH COMMENTS
	F	REVISED TO ARCH COMMENTS





	WOLLONGONG - HEAD OFFICE
	Shop 1, 18 Arrow Avenue
	Figtree NSW 2525
	PO Box 506
	Figtree NSW 2525
	T 61 2 4227 4233
	F 61 2 4227 4133
	E info@siteplus.com.au
oding	management

Client Title									
EDMIND RIC	EDMUND RICE COLLEGE								
LDIVIOIAD IXIOL OOLLLOL									
APPROVAL	Local Authority WOLLONGONG								
	EDMUND RIC								

PROPOSED CRITICAL USE DEVELOPMENT	
112 MOUNT KEIRA RD WEST WOLLONGONG	;

Ref & Dwg No 23153.DA.C06 Sheet 06 of 11 AS NOTED @ A1

BULK EARTHWORKS

29/08/24 F A1

Ø300mm SEWER ←

GRADE uPVC 🛕

INSTALL AN IDENTIFICATION SYSTEM ON EACH OSD IN THE FORM OF A CORROSION RESISTANT PLAQUE. THE PLAQUE SHALL BE ON OR CLOSE TO THE OSD SYSTEM AND IS TO INDICATE: A. THE STRUCTURE IS AN OSD FACILITY, PART OF THE STORMWATER NETWORK B. ITS IDENTIFICATION NUMBER, PROVIDED AS PART OF THE DEVELOPMENT APPROVAL PROCESS

IT IS NOT TO BE TAMPERED WITH, AND ANY SPECIALIST MAINTENANCE REQUIREMENTS; E.G. CONFINED SPACES WARNING

> -∅125m ORIFICE ~4M12 DYNA BOLTS FIXED TO PIT WALL

PROVIDE GALVANISED STEP —

IRONS AT 300mm CENTRES

BLOCK WALL TO PROVIDE WEIR.

Ø150mm SEWER GRADE uPVC−

STANDARDS

Ø300mm SEWER

GRADE upvc outle


IN ACCORDANCE WITH AUST.

ORIFICE PLATE DETAIL

SCALE 1:10 PLATE TO BE 3 mm STAINLESS STEEL MACHINE CUT

LIFTING HANDLE STEEL PLATE CLIP WELDED TO BASKET GALVANISED. TYPICAL BOTH SIDES -STEEL PLATE BRACKET GALVANISED FIXED TO FIT WALL WITH 2 LOXINS TO SEAT CLIPS INTO. RH3030 LYSAGHT

DEBRIS SCREEN DETAIL



OSD DISCHARGE CONTROL

43.30

DISCHARGE

PER ORIFICE

33.17

38.52

45.15

4000

PIT LIDS TO BE 900x900 CLASS C

-HIGH FLOW WEIR 900x200 OPENING

STRUCTURAL DETAILS BY OTHERS

TOTAL

 $=36.18 \,\mathrm{m}^3$

OSD VOLUME

-RH3030 MAXIMESH SCREEN FOR DEBRIS CONTROL

 $TWL_{100} = 43.269m$

 $TWL_{20} = 42.416m$

AT CC STAGE

OBV RL 43.98

1% SLOPE

LOCKABLE GRATES

RL 44.28


WEIR RL 43.28

INV RL 41.29

	On Site Stermy	vater Detention Mai	ptopapeo Schodulo
M-:			
Maintenance Action	Frequency	Performed By	Procedure
Inspect overflow weir and remove any	Six Monthly +	Maintenance	Remove grate and open cover to ventilate underground storage
blockage		Contractor	if present. Ensure weir clear of blockages.
Inspect screen and clean	Six Monthly +	Owner	Remove grate and clean screen removing debris from pit
Inspect outlet pipe and remove any blockage	Six Monthly +	Maintenance Contractor	Remove grate and screen. Ventilate underground storage if present. Check orifice and remove any blockages in outlet pipe. Flush outlet pipe to confirm it drains freely. Check for sludge/debris on upstream side of return line (if relevent).
Check fixing of step irons is secure	Six Monthly	Maintenance Contractor	Remove grate and ensure fixings secure prior to placing weight on step iron.
Check step irons for corrosion	Anually	Maintenance Contractor	Remove grate. Examine step irons and repair any corrosion or damage.
Check attachment of orifice plate to wall of	Annually	Maintenance	Remove grate and screen. Ensure plate mounted securely,
pit (gap less than 5 mm)		Contractor	tighten fixings if required. Seal gaps as required.
Check screen for corrosion	Annually	Maintenance Contractor	Remove grate and examine screen for rust or corrosion, especially at corners or welds.
Inspect internal walls of return pit (and external, if appropriate) for cracks or spalling	Annually	Maintenance Contractor	Remove grate to inspect internal walls. Repair as required. Clear vegetation from external walls if necessary and repair as required.
Compare storage volume to volume approved. (Rectify if loss >5%)	Annually	Maintenance Contractor	Compare actual storage available with Work-as-Executed Plans. If volume loss is greater than 5%, arrange for reconstruction to replace the volume lost. Council to be notified of the proposal.
Inspect storage areas for subsidence near pits	Annually	Maintenance Contractor	Check along drainage lines and pits for subsidence likely to indicate leakages.

DRN APP

DATE



DESCRIPTION ဖ္ B REVISED TO CLIENTS COMMENTS C REVISED DRAINAGE LINES $\frac{\omega}{2}$ D REVISED TO UPDATED ARCH 뿐 E REVISED TO ARCH COMMENTS REVISED TO ARCH COMMENTS

(maintenance schedule adopted from Wollongong City Council's On-Site Stormwater Detention Code)

+ and after every storm event

siteplus I.B. A.C. 21/11/23 I.B. A.C. 24/11/23 I.B. A.C. 29/11/23 I.B. A.C. 27/08/24 I.B. a.c. 29/08/24

WOLLONGONG - HEAD OFFICE Shop 1, 18 Arrow Avenue PO Box 506 Figtree NSW 2525 T 61 2 4227 4233 F 61 2 4227 4133 E info@siteplus.com.au management

Height Datum A.H.D. I.B. I.B. A.C. A.C.

EDMUND RICE COLLEGE

APPROVAL

AEP

(%)

20

5

STORAGE VOLUME @ RL

CENTRE OF ORIFICE LEVEL

ORIFICE DIAMETER

DISCHARGE

IN

105.13

146.32

205.84

WEIR LEVEL

WEIR LENGTH

PROPOSED CRITICAL USE DEVELOPMENT 112 MOUNT KEIRA RD WEST WOLLONGONG Sheet 07 of 11

36.180 m3

41.353 m

43.280 m

0.900 m

WEIR

0.00

0.00

0.00

125 mm

DISCHARGE DISCHARGE

TOTAL

33.17

38.52

45.15

23153.DA.C07 ÄS NOTED @ A1

WOLLONGONG

MAX WATER

LEVEL

42.416

42.765

43.269

OSD DETAILS 29/08/24 | F | A1

			Р	it Sc	hedul	e -	TAS [Drain	age			
Pit No.	Pit Type	Pit Width	Pit Length	Outlet Diameter	Outlet Invert RL	Inlet Diameter	Inlet Invert RL	Pit Depth	Pit Lid Level	Easting	Northing	Comment
		(mm)	(mm)	(mm)	(m)	(mm)	(m)	(m)	(m)	(m)	(m)	
A/11	HEADWALL					375	40.470	-0.048	40.422	303769.98	6189293.682	
A/10	JP 900x900	900	900	375	40.525	375	40.555	1.042	41.567	303759.32	6189294.276	
A/9	JP 900x900	900	900	375	40.766	300	41.196	1.833	42.599	303746.52	6189281.808	
						150	41.191					
						150	41.191					
A/8	Bend	0	0	300	41.240	300	41.240	1.185	42.425	303752.82	6189278.738	
D/2	JP 900x900	900	900	150	42.170	150	42.170	0.976	43.146	303720.42	6189292.886	
E/1	JP 450x450	450	450	150	41.987			0.750	42.737	303732.32	6189246.630	
A/7	JP 900x900	900	900	300	41.290	300	41.330	2.990	44.280	303750.39	6189273.464	
D/1	KIP 1.2m Lintel	600	900	150	42.276			0.781	43.057	303722.54	6189303.195	
A/6	Bend	0	0	300	41.350	300	41.350	2.930	44.280	303747.62	6189272.835	
A/5	JP 900x900	900	900	300	41.570	225	41.600	1.111	42.681	303733.09	6189244.871	
A/4	GSIP 900x900	900	900	225	42.065	225	42.095	1.391	43.456	303686.19	6189280.347	
A/3	GSIP 900x900	900	900	225	42.260	150	42.290	1.232	43.492	303695.63	6189293.320	
A/2	Bend	0	0	150	42.395	150	42.395	1.021	43.416	303701.75	6189301.838	
A/1	GSIP 600x600	600	600	150	42.505			0.750	43.255	303712.42	6189303.323	

	Pit Schedule – Lift Drainage 1														
Pi† No.	Pit Type	Pit Width	Pit Length	Outlet Diameter	Outlet Invert RL	Inlet Diameter	Inlet Invert RL	Pit Depth	Pit Lid Level	Easting	Northing	Comment			
		(mm)	(mm)	(mm)	(m)	(mm)	(m)	(m)	(m)	(m)	(m)				
B/3	EXISTING PIT					100	42.508	0.700	43.208	303661.24	6189391.469				
B/2	GSIP 450x450	450	450	100	42.644	100	42.669	1.274	43.918	303661.56	6189393.949				
B/1	Downpipe	100		100	43.837			1.488	45.325	303662.53	6189400.430				

	Pit Schedule – Lift Drainage 2													
Pi† No.	Pit Type	Width Length Diamet		Outlet Invert RL	Inlet Diameter	Inlet Invert RL	Pit Depth Pit Lid Level		Easting	Northing	Comment			
		(mm)	(mm)	(mm)	(m)	(mm)	(m)	(m)	(m)	(m)	(m)			
C/2	EXISTING PIT					150	43.308	0.750	44.058	303651.50	6189400.641			
C/1	Downpipe	100		150	43.387			0.750	44.137	303650.23	6189404.178			

HGL Report - TAS Drainage										ırn P	erioc	l: 10 y	ΓЅ	Location: Wollongong 1987 IFD										
Pipe Connecting Pits (Downstream Upstream)	Pipe Class	Pipe Diameter	Pipe Length	Pipe Design Flow	Mannings n	Pipe Velocity	Pipe Part Velocity	Pipe Velocity Head	HGL at Downstream Pit	Pipe Friction Slope	Pipe Friction Loss	HGL at Upstream Pit	Pit Loss Coefficient	Pipe Head Loss	Adopted Upstream Water Level	Pit Surcharge Level (Pit Inlet/Outlet Level)	Downstream Pipe Obvert	Upstream Pipe Obvert	Downstream Pipe Invert	Upstream Pipe Invert	Pipe Slope	Pipe Design Flow	Pipe HGL Capacity	Pipe Manning Capacity
		(mm)	(m)	(l/s)		(m/s)	(m/s)	(m)	(m)	(%)	(m)	(m)	Ku	(m)	(m)	(m)	(m)	(m)	(m)	(m)	(%)	(l/s)	(l/s)	(l/s)
A/2 A/1	PVC	150	10.777	16.7	0.009	0.95	1.381	0.046	42.883	0.01	0.064	42.946	5.001	0.229	43.175	43.255	42.545	42.655	42.395	42.505	1.021	16.7	22.4	22.2
A/11 A/10	Class 3 RCP	375	10.675	162.7	0.013	1.47	1.473	0.111	40.845	0.00	0.049	40.900	1.000	0.111	41.011	41.567	40.845	40.900	40.470	40.525	0.515	162.7	172.5	125.8
A/3 A/2	PVC	150	10.489	16.7	0.009	0.94	1.367	0.045	42.776	0.01	0.061	42.837	1.000	0.045	42.883	43.416	42.440	42.545	42.290	42.395	1.001	16.7	22.2	22.0
A/4 A/3	PVC	225	16.045	16.9	0.009	0.43	1.387	0.009	42.754	0.00	0.013	42.767	1.000	0.009	42.776	43.492	42.320	42.485	42.095	42.260	1.028	16.9	65.7	65.8
A/5 A/4	PVC	225	58.812	35.8	0.009	0.90	1.528	0.041	42.471	0.00	0.192	42.663	2.192	0.091	42.754	43.456	41.825	42.290	41.600	42.065	0.791	35.8	57.2	57.7
A/6 A/5	PVC	300	31.512	37.8	0.009	0.53	1.473	0.015	42.404	0.00	0.028	42.431	2.736	0.040	42.471	42.681	41.650	41.870	41.350	41.570	0.698	37.8	114.4	116.7
A/7 A/6	PVC	300	2.845	37.2	0.009	0.53	1.470	0.014	42.387	0.00	0.002	42.390	1.000	0.014	42.404	44.280	41.630	41.650	41.330	41.350	0.703	37.2	114.8	117.1
A/8 A/7	PVC	300	5.805	133.4	0.009	1.89	1.887	0.182	41.951	0.01	0.054	42.005	2.105	0.382	42.387	44.280	41.540	41.590	41.240	41.290	0.861	133.4	127.8	129.6
A/9 A/8	PVC	300	7.002	133.1	0.009	1.88	1.882	0.181	41.496	0.01	0.065	41.561	2.154	0.389	41.951	42.425	41.496	41.540	41.196	41.240	0.628	133.1	108.3	110.7
A/10 A/9	Class 3 RCP	375	17.864	163.7	0.013	1.48	1.939	0.112	41.011	0.00	0.083	41.094	2.595	0.291	41.385	42.599	40.930	41.141	40.555	40.766	1.181	163.7	265.4	190.5
D/2 D/1	PVC	150	10.525	7.5	0.009	0.42	1.120	0.009	42.230	0.00	0.014	42.337	9.803	0.089	42.426	43.057	42.320	42.426	42.170	42.276	1.012	7.5	22.3	22.1
A/9 D/2	PVC	150	28.356	7.4	0.009	0.42	1.769	0.009	41.385	0.00	0.037	42.213	1.798	0.016	42.229	43.146	41.341	42.320	41.191	42.170	3.453	7.4	42.5	40.9
A/9 E/1	PVC	150	37.938	15.4	0.009	0.87	1.783	0.039	41.385	0.01	0.191	42.060	5.395	0.209	42.269	42.737	41.341	42.137	41.191	41.987	2.097	15.4	32.8	31.9

	HGL Report – Lift Drainage 1 Return Period: 10yrs														atior	ı: Wol	longo	ong 1	987 I	FD										
Pipe Connecting Pits (Downstream Upstream)	Pipe Class	Pipe Diameter	Pipe Length	Pipe Design Flow	Mannings n	Pipe Velocity	Pipe Part Velocity	Pipe Velocity Head	HGL at Downstream Pit	Pipe Friction Slope	Pipe Friction Loss	HGL at Upstream Pit	Pit Loss Coefficient	Pipe Head Loss	Adopted Upstream Water Level	Pit Surcharge Level (Pit Inlet/Outlet Level)	Downstream Pipe Obvert	Upstream Pipe Obvert	Downstream Pipe Invert	Upstream Pipe Invert	Pipe Slope	Pipe Design Flow	Pipe HGL Capacity	Pipe Manning Capacity						
		(mm)	(m)	(l/s)		(m/s)	(m/s)	(m)	(m)	(%)	(m)	(m)	Ku	(m)	(m)	(m)	(m)	(m)	(m)	(m)	(%)	(l/s)	(l/s)	(l/s)						
B/2 B/1	PVC	100	6.552	8.3	0.009	1.05	2.809	0.014	42.819	0.00	0.022	43.862	3.749	0.053	43.915	45.325	42.769	43.937	42.669	43.837	17.821	8.3	68.3	63.0						
B/3 B/2	PVC	100	2.501	11.2	0.009	1.43	2.349	0.104	42.608	0.02	0.053	42.703	1.110	0.116	42.819	43.918	42.608	42.744	42.508	42.644	5.448	11.2	18.5	17.4						

		Ref	Return Period: 10yrs Location: Wollongong 1987 IFD																					
Pipe Connecting Pits (Downstream Upstream)	Pipe Class	Pipe Diameter	Pipe Length	Pipe Design Flow	Mannings n	Pipe Velocity	Pipe Part Velocity	Pipe Velocity Head	HGL at Downstream Pit	Pipe Friction Slope	Pipe Friction Loss	HGL at Upstream Pit	Pit Loss Coefficient	Pipe Head Loss	Adopted Upstream Water Level	Pit Surcharge Level (Pit Inlet/Outlet Level)	Downstream Pipe Obvert	Upstream Pipe Obvert	Downstream Pipe Invert	Upstream Pipe Invert	Pipe Slope	Pipe Design Flow	Pipe HGL Capacity	Pipe Manning Capacity
		(mm)	(m)	(l/s)		(m/s)	(m/s)	(m)	(m)	(%)	(m)	(m)	Ku	(m)	(m)	(m)	(m)	(m)	(m)	(m)	(%)	(l/s)	(l/s)	(l/s)
C/2 C/1	PVC	150	3.758	18.3	0.009	1.04	1.872	0.055	43.458	0.01	0.026	43.484	4.602	0.253	43.737	44.137	43.458	43.537	43.308	43.387	2.097	18.3	32.8	31.9

WOLLONGONG

DESCRIPTION B REVISED TO CLIENTS COMMENTS
OF CREVISED DRAINAGE LINES
D REVISED TO UPDATED ARCH 뿐 E REVISED TO ARCH COMMENTS F REVISED TO ARCH COMMENTS

DRN APP DATE
I.B. A.C. 21/11/23
I.B. A.C. 24/11/23
I.B. A.C. 29/11/23
I.B. A.C. 27/08/24
I.B. a.c. 29/08/24

siteplus

WOLLONGONG - HEAD OFFICE Shop 1, 18 Arrow Avenue Figtree NSW 2525 PO Box 506 Figtree NSW 2525 T 61 2 4227 4233 F 61 2 4227 4133 E info@siteplus.com.au

management

Height Datum A.H.D. I.B. I.B. A.C. A.C.

EDMUND RICE COLLEGE

APPROVAL

PROPOSED CRITICAL USE DEVELOPMENT 112 MOUNT KEIRA RD WEST WOLLONGONG
Sheet No Sheet 08 of 11

Ref & Dwg No 23153.DA.C08

AS NOTED @ A1 Date 29/08/24 F A1

H	ydrolo	gic D)esign	She	et -T			age ng 19			Perio	od: 10	Loca	tion:	
Pit	Catchment Flow Length	Catchment Slope	Catchment Roughness	Catchment Flow Time	Gutter Flow Time	Total Time	Pit C Factor	Total Catchment Area	Aera Contributing	Rainfall Intensity	Total Catchment Flow	Pit Type	Gutter Pit Inflow	Gutter Slope	Total Upstream
	(m)	(%)	'n	(min)	(min)	(min)		(ha)	(l/s)	(mm/hr)	(l/s)		(l/s)	(%)	(ha)
A/1				6.10		6	1.000	0.03	0.0	200.2	16.7	SITEPLUS			0.0
							0.000								
							0.000								
	20.59	5.0	0.300				1.000	0.03							
A/10									0.3	213.0		SITEPLUS			0.3
A/2									0.0	213.0		SITEPLUS			0.0
A/3				5.00		5	1.000	0.01	0.0	213.0	4.0	SITEPLUS	4.0		0.0
							1.000	0.01							
							0.000								
							0.000								
A/4				6.29		6	1.000	0.03	0.1	198.7	18.9	SITEPLUS			0.1
							0.000								
							0.000								
	20.00	4.3	0.300				1.000	0.03							
A/5									0.1	213.0		SITEPLUS			0.1
A/6									0.1	213.0		SITEPLUS			0.1
A/7				5.00		5	1.000	0.18	0.3	213.0	108.8	SITEPLUS	108.8		0.3
	50.00	1.0	0.012				1.000	0.18							
							0.000								
							0.000								
A/8									0.3	213.0		SITEPLUS			0.3
A/9				5.00		5	1.000	0.02	0.3	213.0	12.4	SITEPLUS	7.1		0.3
	12.00	3.0	0.012				1.000	0.01							
							0.000								
	5.00	3.0	0.300				1.000	0.01							
D/1				5.00		5	1.000	0.01	0.0	213.0	7.5	SITEPLUS	6.6		0.0
	15.76	3.0	0.012				1.000	0.01							
							0.000								
	5.00	3.0	0.300				1.000	0.00							
D/2									0.0	213.0		SITEPLUS			0.0
E/1				5.00		5	1.000	0.03	0.0	213.0	15.4	SITEPLUS	15.4		0.0
	67.45	3.0	0.012				1.000	0.03							
							0.000								
							0.000								

Ну	Hydrologic Design Sheet -Lift Drainage 1 Return Period: 10 Wollongong 1987 IFD														:
Piŧ	Catchment Flow Length	Catchment Slope	Catchment Roughness	Catchment Flow Time	Gutter Flow Time	Total Time	Pit C Factor	Total Catchment Area	Aera Contributing	Rainfall Intensity	Total Catchment Flow	Pit Type	Gutter Pit Inflow	Gutter Slope	Total Upstream Catchment
	(m)	(%)	'n	(min)	(min)	(min)		(ha)	(l/s)	(mm/hr)	(l/s)		(l/s)	(%)	(ha)
B/1				5.00		5	1.000	0.01	0.0	213.0	8.3	SITEPLUS	8.3		0.0
	25.52	3.5	0.012				1.000	0.01							
							0.000								
							0.000								
B/2				5.00		5	1.000	0.01	0.0	213.0	3.0	SITEPLUS			0.0
							0.000								
							0.000								
							1.000	0.01							

Hyd	Hydrologic Design Sheet -Lift Drainage 2 Return Period: 10 Location: Wollongong 1987 IFD														
+i4	Catchment Flow Length	Catchment Slope	Catchment Roughness	Catchment Flow Time	Gutter Flow Time	Total Time	Pit C Factor	Total Catchment Area	Aera Contributing	Rainfall Intensity	Total Catchment Flow	Pit Type	Gutter Pit Inflow	Gutter Slope	Total Upstream Catchment
	(m)	(%)	'n,	(min)	(min)	(min)		(ha)	(l/s)	(mm/hr)	(l/s)		(l/s)	(%)	(ha)
C/1				5.00		5	1.000	0.03	0.0	213.0	18.3	SITEPLUS	18.3		0.0
	23.67	5.0	0.012				1.000	0.03							
							0.000								
							0.000								

DESCRIPTION B REVISED TO CLIENTS COMMENTS
OF CREVISED DRAINAGE LINES
D REVISED TO UPDATED ARCH 뿐 E REVISED TO ARCH COMMENTS F REVISED TO ARCH COMMENTS

DRN APP DATE
I.B. A.C. 21/11/23
I.B. A.C. 24/11/23
I.B. A.C. 29/11/23
I.B. A.C. 27/08/24
I.B. a.c. 29/08/24

siteplus

WOLLONGONG - HEAD OFFICE Shop 1, 18 Arrow Avenue Figtree NSW 2525 PO Box 506 Figtree NSW 2525 T 61 2 4227 4233 F 61 2 4227 4133 E info@siteplus.com.au

management

Height Datum A.H.D. I.B. I.B. A.C. A.C.


EDMUND RICE COLLEGE

APPROVAL

PROPOSED CRITICAL USE DEVELOPMENT 112 MOUNT KEIRA RD WEST WOLLONGONG
Sheet No Sheet No Sheet 09 of 11

Ref & Dwg No 23153.DA.C09

AS NOTED @ A1 Date 29/08/24 F A1



DESCRIPTION

ဖ္ B REVISED TO CLIENTS COMMENTS

E REVISED TO ARCH COMMENTS

REVISED TO ARCH COMMENTS

REVISED DRAINAGE LINES

 $\frac{\omega}{5}$ D REVISED TO UPDATED ARCH

LEGEND PROPOSED

I.B. A.C. 21/11/23

I.B. A.C. 24/11/23 I.B. A.C. 29/11/23

I.B. A.C. 27/08/24

I.B. a.c. 29/08/24

DIVERSION BANK


STATEMENT OF SOIL MANAGEMENT


- 1 ALL TOPSOIL IS TO BE STOCKPILED IN AREAS DESIGNATED ON PLAN.
- 2 ALL FORMED EMBANKMENTS (CUT & FILL) ARE TO BE SEEDED WITHIN 7 DAYS. 3 ALL DISTURBED AREAS INCLUDING ANY CONTROLLED FILL ARE TO BE TOPSOILED & SEEDED PRIOR TO COMPLETION OF WORKS. ALL DISTURBED AREAS THAT WILL NOT BE STABILIZED WITHIN 2 MONTHS MUST BE TEMPORARILY REVEGETATED WITHIN 7 DAYS OF CLEARING. AREAS THAT FAIL TO ESTABLISH MUST BE RESOWN IMMEDIATELY.
- 4 ALL GULLY PITS ARE TO BE PROVIDED WITH SEDIMENT FILTER BARRIERS SUCH AS STRAW BAIL OR SANDBAGS. 5 PROVIDE TEMPORARY DIVERSION BANKS ON SITE AS DIRECTED.
- 6 AT THE TOP OF ALL FILL EMBANKMENTS, PROVIDE A BERM TO PREVENT WATER RUNNING DOWN EMBANKMENTS, BERM IS TO BE MAINTAINED AT ALL TIMES AS THE FILL EMBANKMENT PROGRESSES TO FINAL
- 7 ALL FORMED EMBANKMENTS (CUT & FILL) TO BE TOPSOILED & SEEDED/FERTILIZED ON FINAL TRIMMING. 8 FOR TEMPORARY REVEGETATION PURPOSES, THE REVEGETATION MIXTURE SHOULD BE TO COUNCIL
- 9 TRENCHES FOR INTERLOT DRAINAGE LINES ARE TO BE REINSTATED WITH TOPSOIL FOLLOWING PIPE INSTALLATION & BACKFILLING & IMMEDIATELY SEEDED/FERTILIZED
- 10 THE GROUND SHALL BE TYNED / SCARIFIED TO A MIN DEPTH 100mm PRIOR TO SEEDING 11 CONTRACTOR SHOULD LIASE REGULARLY WITH ENGINEER TO DETERMINE AREAS WHICH CAN BE PROGRESSIVELY
- REVEGETATED 12 TO ASSIST IN DUST CONTROL/WIND EROSION A TRACKIFIER SUCH AS CUROSOL SHOULD BE USED. OR EQUIVALENT ENDORSED PRODUCT BY EPA, RATES AS PER MANUFACTURES SPECIFICATION 13 DESIGNATED PLANT AND MACHINERY ACCESSWAYS TO BE DEFINED ONSITE BY THE INSTALLATION OF
- PARAWEBBING FENCING TO MINIMIZE UNNECESSARY SITE DISTURBANCE. 14 IT IS THE CONTRACTORS RESPOSIBILITY TO MAINTAIN SOIL EROSION CONTROL DEVICES AND CONTROL DUST


- 1 REMOVE ALL SOIL & SPOIL MATERIAL FROM THE ROADWAY & GUTTER SYSTEM FOR THAT SECTION OF TRENCHING & / OR OTHER WORKS CARRIED OUT ON ANY ONE DAY. THIS IS TO BE UNDERTAKEN
- ON THE COMPLETION OF EACH DAY'S WORK. 2 ABSTAIN FROM PLACING SPOIL / STOCKPILES ON OR IN THE IMMEDIATE VICINITY OF THE KERB &
- GUTTER SYSTEM. A MINIMUM SET BACK OF THREE (3) METRES WILL BE REQUIRED. 3 STOCKPILES REFERED TO IN ITEM 2 ARE NOT TO BE PLACED WITHIN FIFTEEN (15) METRES EITHER SIDE OF KERB INLET PITS. THIS IS TO BE REGARDED AS A DESIGNATED EXCLUSION ZONE.
- 4 WHERE ROCK IS ENCOUNTERED DURING THE TRENCHING OPERATIONS & THIS MATERIAL IS CONSIDERED TO BE UNSUITABLE AS BACKFILL, THEN ALL OVERSIZED ROCK WILL BE REQUIRED TO BE REMOVED FROM THE SITE & WILL NOT BE PERMITTED TO REMAIN ON THE SURFACE OF REGRADING & SURFACE PREPARATION PRIOR TO SEEDING DISTURBED AREAS.


MAINTENANCE PROCEDURES DURING CONSTRUCTION


1 ALL EROSION CONTROL MEASURES ARE TO BE MAINTAINED AT ALL TIMES SO THAT THOSE MEASURES ARE FULLY FUNCTIONAL / OPERATIONAL DURING THE CURRENCY OR WORKS. ALL SUCH CONTROLS MUST ALSO BE FULLY FUNCTIONAL / OPERATIONAL SHOULD WORK OPERATIONS CEASE TEMPORARILY, (e.g. WEEKENDS, ROSTERED DAYS OFF, etc.) 2 RESPREAD MATERIAL GAINED DURING MAINTENANCE OPERATION OR ALTERNATIVELY PLACE ON

































. Remove all vegetation and topsoil from under dam wall and from within storage area.

- 2. Construct cut—off trench 500mm deep and 1200mm wide along centreline of the embankment extending to a point on the gully wall level with riser crest.
- 3. Maintain the trench free of water and recompact the materials with equipment specified in the S SWMP to 95 per cent Standard Proctor Density. 4. Select fill according to the directions of the SWMP that is free of roots, wood, rock, large stones or
- foreign material. 5. Prepare the site under the embankment by ripping at least 100mm deep to help bond compacted
- fill to existing substrate. 6. Spread fill in 100mm to 150mm layers and compact at optimum moisture content in accordance
- with the SWMP. 7. Construct emergency spillway.
- 8. Rehabilitate structure in accordance with SWMP. 9. Place a "Full of Sediment" marker to show when less than design capacity occurs and sediment

Earth Construction Wet Sediment Basin — SD 6-4

NOT TO SCALE





PROPOSED CRITICAL USE DEVELOPMENT 112 MOUNT KEIRA RD WEST WOLLONGONG

23153.DA.C11 11 of 11

NOT TO SCALE

DESCRIPTION g B REVISED TO CLIENTS COMMENTS C REVISED DRAINAGE LINES $\stackrel{\mbox{\ensuremath{\bowtie}}}{=}$ D REVISED TO UPDATED ARCH 뿐 E REVISED TO ARCH COMMENTS REVISED TO ARCH COMMENTS

DRN APP DATE I.B. A.C. 21/11/23 I.B. A.C. 24/11/23 I.B. A.C. 29/11/23 I.B. A.C. 27/08/24 I.B. a.c. 29/08/24

siteplus

WOLLONGONG - HEAD OFFICE Shop 1, 18 Arrow Avenue Figtree NSW 2525 PO Box 506 Figtree NSW 2525 T 61 2 4227 4233 F 61 2 4227 4133 E info@siteplus.com.au

Height Datum A.H.D. I.B. I.B. A.C. A.C.

WOLLONGONG

SOIL AND WATER MANAGEMENT DETAILS

NTS

management

APPROVAL