SITE WORKS

- ALL WORKS TO BE IN ACCORDANCE WITH SPECIFICATIONS AND AUSTRALIAN STANDARDS. CONFLICTS SHALL BE REFERRED TO THE SUPERINTENDENT FOR DIRECTION.
- THE CONTRACTOR IS TO DESIGN, OBTAIN APPROVALS AND CARRY OUT REQUIRED TEMPORARY TRAFFIC CONTROL PROCEDURES DURING CONSTRUCTION IN ACCORDANCE WITH RMS & SHOALHAVEN CITY COUNCIL REGULATIONS AND REQUIREMENTS.
- THE CONTRACTOR IS TO OBTAIN ALL AUTHORITY APPROVALS AS REQUIRED.
- RESTORE ALL PAVED, COVERED, GRASSED AND LANDSCAPED AREAS TO THEIR ORIGINAL CONDITION ON COMPLETION OF WORKS. WHERE PLANTING OF NEW GRASS IS NECESSARY REFER TO LANDSCAPE ARCHITECT DOCUMENTATION.
- ON COMPLETION OF ANY TRENCHING WORKS, ALL DISTURBED AREAS SHALL BE RESTORED TO THEIR ORIGINAL CONDITION, INCLUDING KERBS, FOOTPATHS, CONCRETE AREAS, GRAVEL, GRASSED AREAS AND ROAD PAVEMENTS
- THE CONTRACTOR SHALL ARRANGE ALL SURVEY SETOUT TO BE CARRIED OUT BY A REGISTERED SURVEYOR.
- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND EXISTING LEVELS ON SITE PRIOR TO LODGMENT OF TENDER AND PRIOR TO CONSTRUCTION.
- THIS PLAN IS TO BE READ IN CONJUNCTION WITH THE ENGINEERING PLANS, AND ANY OTHER PLANS OR WRITTEN INSTRUCTIONS THAT MAY BE ISSUED RELATING TO
- ANY EXISTING TREES WHICH FORM PART OF THE FINAL LANDSCAPING PLAN SHALL BE PROTECTED FROM CONSTRUCTION ACTIVITIES BY:
 - PROTECTING THEM WITH BARRIER FENCING OR SIMILAR MATERIALS INSTALLED OUTSIDE THE DRIP LINE:
 - ENSURING THAT NOTHING IS NAILED TO THEM: PROHIBITING PAVING, GRADING, SEDIMENT WASH OR PLACING OF
 - STOCKPILES WITHIN THE DRIP LINE EXCEPT UNDER THE FOLLOWING CONDITIONS:
- (i) encroachment only occurs on one side and no closer to the trunk than either 1.5 metres or half
- the distance between the outer edge of the drip line and the trunk, which ever is
- (ii) a drainage system that allows air and water to circulate through the root zone (e.g. a gravel bed) is placed under all fill lavers of more than 300 millimetres depth (iii) care is taken not to cut roots unnecessarily nor to
- 10. DO NOT OBTAIN DIMENSIONS BY SCALING THE DRAWINGS.

compact the soil around them.

- 11. IN CASE OF DOUBT OR DISCREPANCY REFER TO SUPERINTENDENT FOR CLARIFICATION
- OR CONFIRMATION PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. 12. WHERE NEW WORKS ABUT EXISTING THE CONTRACTOR SHALL ENSURE THAT A
- SMOOTH EVEN PROFILE, FREE FROM ABRUPT CHANGES IS OBTAINED. 13. MAKE SMOOTH TRANSITION TO EXISTING FEATURES AND CONSTRUCTION.
- 14. THESE PLANS SHALL BE READ IN CONJUNCTION WITH ALL APPROVED DRAWINGS AND SPECIFICATIONS PREPARED BY OTHER PROJECT CONSULTANTS.
- TRENCHES THROUGH EXISTING ROAD AND CONCRETE PAVEMENTS SHALL BE SAWCUT TO FULL DEPTH OF CONCRETE AND A MIN 50mm IN BITUMINOUS PAVING.
- 16. ALL CONSTRUCTION WORK IS TO BE CARRIED OUT SO THAT AT ANY TIME ADJOINING PROPERTY OWNERS ARE NOT DEPRIVED OF AN ALL-WEATHER ACCESS OR SUBJECTED TO ADDITIONAL STORM WATER RUN-OFF DURING THE PERIOD OF CONSTRUCTION
- 17 ALL GREEN WASTE IS FITHER TO BE REMOVED FROM SITE OR MULCHED ON SITE AND SPREAD OVER DISTURBED AREAS. NO GREEN WASTE IS TO BE BURNT

EXISTING SERVICES

- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE AND CONFIRM THE LOCATION AND LEVEL OF ALL EXISTING SERVICES PRIOR TO THE COMMENCEMENT OF ANY WORK. ANY DISCREPANCIES SHALL BE REPORTED TO THE SUPERINTENDENT. CLEARANCES SHALL BE DISCUSSED WITH THE RELEVANT SERVICE AUTHORITIES
- CARE TO BE TAKEN WHEN EXCAVATING NEAR EXISTING SERVICES. NO MECHANICAL EXCAVATIONS ARE TO BE UNDERTAKEN OVER COMMUNICATION, GAS OR ELECTRICAL SERVICES. HAND EXCAVATION ONLY IN THESE AREAS.
- THE CONTRACTOR SHALL PROTECT AND MAINTAIN ALL EXISTING SERVICES THAT ARE TO BE RETAINED IN THE VICINITY OF THE PROPOSED WORKS. ANY AND ALL DAMAGE TO THESE SERVICES AS A RESULT OF THESE WORKS SHALL BE REPAIRED BY THE CONTRACTOR UNDER THE DIRECTION OF THE SUPERINTENDENT, AND AT NO EXTRA
- THE CONTRACTOR SHALL ALLOW FOR ADJUSTMENT (IF REQUIRED) OF EXISTING SERVICES IN AREAS AFFECTED BY WORKS.

OTHERWISE ON THE DRAWINGS OR BY THE SUPERINTENDENT.

- THE CONTRACTOR SHALL ALLOW FOR THE CAPPING OFF, EXCAVATION AND REMOVAL (IF REQUIRED) OF EXISTING SERVICES IN AREA AFFECTED BY WORKS UNLESS DIRECTED
- THE CONTRACTOR SHALL ENSURE THAT AT ALL TIMES SERVICES TO ALL BUILDINGS NOT AFFECTED BY THE WORKS ARE NOT DISRUPTED
- PRIOR TO COMMENCEMENT OF ANY WORKS THE CONTRACTOR SHALL GAIN APPROVAL FOR THE RELOCATION AND/OR CONSTRUCTION OF TEMPORARY SERVICES AND FOR ANY
- ASSOCIATED INTERRIPTION OF SUPPLY THE CONTRACTOR SHALL CONSTRUCT TEMPORARY SERVICES TO MAINTAIN EXISTING SUPPLY TO BUILDINGS REMAINING IN OPERATION DURING WORKS TO THE SATISFACTION AND APPROVAL OF THE SUPERINTENDENT. ONCE DIVERSION IS COMPLETE AND COMMISSIONED THE CONTRACTOR SHALL REMOVE ALL SUCH TEMPORARY SERVICES AND
- PRIOR TO COMMENCEMENT OF EXCAVATION. THE CONTRACTOR SHALL DETERMINE THE LOCATION OF ALL SERVICES AND WILL BE RESPONSIBLE FOR ADJUSTMENT AND REPAIR OF SERVICES.

MAKE GOOD TO THE SATISFACTION OF THE SUPERINTENDENT.

ADJUST ALL UTILITY SERVICE COVERS TO SUIT NEW GRADES & LEVELS TO SERVICE PROVIDERS SATISFACTION.

EARTHWORKS

- EARTHWORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH GEOTECHNICAL ENGINEERS RECOMMENDATIONS. REFER TO INFORMATION PROVIDED BY DEVELOPER.
- STRIP TOPSOIL, VEGETABLE MATTER AND RUBBLE TO EXPOSE NATURALLY OCCURRING MATERIAL AND STOCKPILE ON SITE AS DIRECTED BY THE SUPERINTENDENT.
- WHERE FILLING IS REQUIRED TO ACHIEVE DESIGN SUBGRADE, PROOF ROLL EXPOSED NATURAL SURFACE WITH A MINIMUM OF TEN PASSES OF A VIBRATING ROLLER (MINIMUM STATIC WEIGHT OF 10 TONNES) IN THE PRESENCE OF THE SUPERINTENDENT.
- ALL SOFT, WET OR UNSUITABLE MATERIAL IS TO BE REMOVED AS DIRECTED BY THE
- SUPERINTENDENT AND REPLACED WITH APPROVED MATERIAL SATISFYING THE THE CONTRACTOR SHALL PROGRAM THE EARTHWORKS OPERATION SO THAT THE
- THE SURFACE SHALL BE GRADED AND SEALED OFF TO REMOVE DEPRESSIONS, ROLLER MARKS AND SIMILAR WHICH WOULD ALLOW WATER TO POND AND PENETRATE THE UNDERLYING MATERIAL. ANY DAMAGE RESULTING FROM THE CONTRACTOR NOT OBSERVING THESE REQUIREMENTS SHALL BE RECTIFIED AT THE CONTRACTORS COST IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE AND MAINTAIN THE

DAMAGE TO NEW OR EXISTING SERVICES AS A RESULT OF THESE WORKS SHALL BE

WORKING AREAS ARE ADEQUATELY DRAINED DURING THE PERIOD OF CONSTRUCTION.

USE OF VIBRATING ROLLERS ARE TO BE LIMITED DUE TO THE CLOSENESS OF EXISTING STRUCTURES. SAFE DISTANCE = 1.5 x DRUM WEIGHT (DMW)

REPAIRED BY THE CONTRACTOR AT NO EXTRA COST.

INTEGRITY OF ALL SERVICES, CONDUITS AND PIPES DURING CONSTRUCTION, SPECIFICALLY DURING THE BACKFILLING AND COMPACTION PROCEDURE. ANY AND ALL

SUBGRADE NOTES

- 1. FOLLOWING SITE ESTABLISHMENT THE CONTRACTOR IS TO PROOF ROLL EXPOSED SUBGRADE IN THE PRESENCE OF THE GEOTECHNICAL ENGINEER TO CONFIRM SUITABILITY OF SUBGRADE.
- 2. THE SUBGRADE IS TO BE COMPACTED TO ACHIEVE 100% STANDARD MAXIMUM DRY DENSITY, (AS1289E1.1). AT A MOISTURE CONTENT WITHIN 2% OF STANDARD OPTIMUM, OR ALTERNATIVE INSTRUCTION IS TO BE OBTAINED FROM A GEOTECHNICAL ENGINEER.
- 3. REMOVE ANY SOFT, HEAVING, WET OR UNSTABLE AREAS IDENTIFIED DURING PROOF ROLLING AND REPLACE USING SELECT IMPORTED FILL COMPACTED IN LAYERS NOT EXCEEDING 200MM MEASURED LOOSE TO ACHIEVE 100% STANDARD COMPACTION AS SPECIFIED ABOVE. OBTAIN WRITTEN APPROVAL FROM CLIENT PRIOR TO PROCEEDING WITH THE ABOVE WORK.
- 4. ANY FILL REQUIRED TO RAISE LEVELS TO UNDERSIDE OF PROPOSED SLAB OR PAVEMENT FORMATION TO BE APPROVED GRANULAR MATERIAL COMPACTED IN LAYERS NOT EXCEEDING 200MM MEASURED LOOSE TO ACHIEVE A MINIMUM 98% STANDARD MAXIMUM DRY DENSITY AT
- 5. IMPORTED FILL IS TO CONSIST OF IMPORTED WELL-GRADED MATERIAL WITH A MAXIMUM PARTICLE SIZE OF 75MM, WITH 80% LESS THAN 20MM, AND A SOAKED C.B.R. GREATER THAN 15% AND PLASTICITY INDEX LESS THAN 12%.

A MOISTURE CONTENT WITHIN 2% OF STANDARD OPTIMUM.

- 6. BACKFILLING FOR SERVICE TRENCHES UNDER SLABS AND PAVEMENTS SHALL BE APPROVED WELL-GRADED GRANULAR MATERIAL. EITHER SELECT INSITU OR IMPORTED FILL COMPACTED AS
- 7. DO NOT PROCEED WITH ANY EARTHWORKS WHICH WILL BE SUBJECT TO A VARIATION CLAIM WITHOUT PRIOR APPROVAL FROM CLIENT. VARIATIONS FOR EARTHWORKS WILL NOT BE APPROVED UNLESS FORMAL INSTRUCTION, INCLUDING VARIATION VOLUMES, IS OBTAINED FROM

PAVEMENT NOTES

- 1. PAVEMENT DETAILS HAVE BEEN DESIGNED ASSUMING A SUBGRADE WITH A MINIMUM SOAKED C.B.R. OF 4%. CBR. PAVEMENT DESIGN TO BE CONFIRMED BY GEOTECHNICAL TESTING BY BUILDER DURING CONSTRUCTION.
- 2. BASE AND SUB-BASE COURSES SHALL BE COMPACTED TO 98% MODIFIED MAXIMUM DRY DENSITY AS A MOISTURE CONTENT WITHIN 2% OF STANDARD OPTIMUM, MINIMUM SOAKED C.B.R. 80% UNO.
- 3. SUBGRADE SHALL BE APPROVED NATURAL SUBGRADE OR IMPORTED FILL, PROOF ROLL AND COMPACTED TO 100% STANDARD MAXIMUM DRY DENSITY UNO.
- 4. FILL MATERIALS WHICH ARE PRONE TO ACCELERATED WEATHERING WILL NOT BE ACCEPTED EG. SOME MUDSTONES, CLAYSTONES, SILTSTONES, SHALES AND OTHER ROCKS. ENDORSEMENT OF THE SUITABILITY OF THE PROPOSED FILLING MATERIAL IS TO BE MADE BY A GEOTECHNICAL ENGINEER PRIOR TO APPROVAL.

CONCRETE

- 1. EACH CONCRETE POUR INCLUDING KERB & GUTTER SHALL BE INSPECTED PRIOR TO
- 2. THE CONTRACTOR SHALL GIVE 48 HOURS NOTICE OF POURS.
- 4. MINIMUM CONCRETE STRENGTH FOR PAVEMENTS SHALL BE F'C = 25 MPa AT 28 DAYS.
- 3. ALL WORK SHALL BE COMPLETED TO AS 3600.
- 4. REINFORCING SHALL BE TIED WITH MINIMUM COVER OF 40mm.
- 5. ALL CONCRETE SHALL BE FULLY COMPACTED BY MECHANICAL MEANS SUCH AS
- IMMERSION VIBRATOR. 6. SAMPLING AND TESTING TO AS 3600 SHALL BE UNDERTAKEN AND ALL COSTS MET BY
- THE CONTRACTOR
- 7. ALL CONCRETE SHALL BE CURED BY IMPERMEABLE MEMBRANE, CURING COMPOUND OR OTHER EQUAL METHOD.
- 8. FORMWORK SHALL BE TO AS3610.
- 9. ALL DISTURBED AREAS INCLUDING BATTERS AND FOOTPATH AREAS ARE TO BE TOPSOILED, FERTILISED AND TURFED.

SIGNAGE & LINEMARKING

- 1. LINE MARKING AND PAINT SHALL BE IN ACCORDANCE WITH THE FOLLOWING STANDARDS. AS 2700 AND AS 2709
- 2. PAINT SHALL BE TYPE 3, CLASS A AND THE COLOUR SHALL BE WHITE AND NOT SUBJECT TO DISCOLOURATION BY BITUMEN FROM THE ROAD SURFACE. EACH LINE SHALL BE 80mm WIDE. ALL PAINT SHALL BE APPLIED BY MECHANICAL SPRAYER.
- 3. LINE MARKING SHALL BE SPOTTED OUT AND APPROVED PRIOR TO SPRAYING.
- 4. PAINT SHALL BE APPLIED AT A WET THICKNESS OF BETWEEN 0.35mm TO 0.40mm. 5. PAINT 80mm LINEMARKING TO CARPARK PAVEMENT.
- 6. ALL SIGNAGE TO BE INSTALLED IN ACCORDANCE WITH AUSTRALIAN STANDARDS.

ACCESS & SAFETY

- 1. THE CONTRACTOR SHALL COMPLY WITH ALL STATUTORY AND INDUSTRIAL REQUIREMENTS FOR PROVISION OF A SAFE WORKING ENVIRONMENT INCLUDING TRAFFIC
- 2. THE CONTRACTOR SHALL ENSURE THAT AT ALL TIMES ACCESS TO ALL BUILDINGS ADJACENT THE WORKS IS NOT DISRUPTED.
- 3. WHERE NECESSARY THE CONTRACTOR SHALL PROVIDE SAFE PASSAGE OF VEHICLES AND/OR PEDESTRIANS THROUGH OR BY THE SITE.
- 4. TRAFFIC CONTROL MEASURES IN ACCORDANCE WITH AS1742.3 ARE TO BE IN PLACE AND MAINTAINED AT ALL TIMES. (TRAFFIC CONTROL PLANS TO BE SUBMITTED PRIOR TO COMMENCEMENT OF WORK.)

TRAFFIC MANAGEMENT

PARKING OF VEHICLES OR LOADING/UNLOADING OF VEHICLES ON ROADWAYS MAY CAUSE A TRAFFIC HAZARD. DURING CONSTRUCTION, MAINTENANCE OR DEMOLITION DESIGNATED PARKING FOR WORKERS AND LOADING AREAS SHOULD BE PROVIDED. TRAINED TRAFFIC MANAGEMENT PERSONNEL SHOULD BE RESPONSIBLE FOR THE SUPERVISION OF THESE AREAS. DELIVERY OF CONSTRUCTION MATERIALS SHOULD BE WELL PLANNED TO AVOID CONGESTION OF TRAFFIC AREAS AND TRAINED TRAFFIC MANAGEMENT PERSONNEL SHOULD BE USED TO SUPERVISE BUSY CONSTRUCTION AND DEMOLITION SITES PRESENT A RISK OF COLLISION WHERE DELIVERIES AND OTHER TRAFFIC ARE MOVING WITHIN THE SITE. A TRAFFIC CONTROL PLAN SUPERVISED BY TRAINED TRAFFIC MANAGEMENT PERSONNEL SHOULD BE ADOPTED FOR THE

SURVEY NOTE

THE LOCATION OF UNDERGROUND SERVICES SHOWN ON THESE PLANS IS INDICATIVE ONLY. IT IS YOUR RESPONSIBILITY TO LOCATE UNDERGROUND SERVICES BY CAREFUL HAND POT-HOLING PRIOR TO ANY EXCAVATION AND EXERCISE DUE CARE DURING THAT

STORMWATER NOTES

- CONTRACTOR IS TO VERIFY THE LEVEL OF ALL EXISTING SERVICES PRIOR TO COMMENCEMENT OF ANY EXCAVATION.
- CONTRACTOR SHALL CONFIRM ALL INVERTS AND GRADES PRIOR TO CONSTRUCTION.
- ALL PIPES LESS THAN OR EQUAL TO Ø225mm AND PIPES RUNNING UNDER FLOOR SLABS ARE TO BE SOLVENT WELD-JOINTED SEWER GRADE uPVC
- ALL PIPES ARE TO BE LAID AT (min) 1.0% GRADE (UNO), UNLESS OTHERWISE NOTED ON DRAWINGS.
- ALL CHARGED LINES FROM DOWNPIPES TO TANKS SHALL BE 1000 UPVC CLASS 6 SOLVENT WELDED.
- ALL LINES FROM TANK OVERFLOWS SHALL BE 1000 UPVC CLASS 6 SOLVENT WELDED UNLESS NOTED OTHERWISE.
- MATERIAL USED FOR BEDDING OF PIPES SHALL BE APPROVED NON-COHESIVE GRANULAR MATERIAL HAVING HIGH PERMEABILITY AND HIGH STABILITY WHEN SATURATED AND FREE OF ORGANIC AND CLAY MATERIAL.
- WHERE TRENCHES ARE IN ROCK, THE PIPE SHALL BE BEDDED ON A MIN. 50mm CONCRETE BED (OR 75mm THICK BED OF 12mm BLUE METAL) UNDER THE BARREL OF THE PIPE. THE PIPE COLLAR AT NO POINT SHALL
- BEDDING SHALL BE TYPE HS2 UNDER ROADS: H2 GENERAL AREAS. IN ACCORDANCE WITH CURRENT RELEVANT INDUSTRY STANDARDS AND
- PROVIDE 100mm MIN COVER TO PIPES NOT SUBJECT TO VEHICULAR LOADING TO AREAS WITHOUT PAVEMENT AND 500mm COVER IN AREAS SUBJECT TO CONSTRUCTION EQUIPMENT LOADING.
- 11. PROVIDE SEPARATION BETWEEN SERVICES IN ACCORDANCE WITH AS 3500
- A) USE HOT DIPPED GALVANISED COVERS AND GRATES COMPLYING WITH RELEVANT AUSTRALIAN STANDARDS.
- CLASS "C" IN VEHICULAR PAVEMENTS AND CLASS "B" ELSEWHERE. GRATED DRAINS SHALL BE MINIMUM 200wx150d INTERNAL DIMENSIONS WITH FALL (MIN.) TO THE INVERT OF THE GRATED DRAIN. GRATES TO DRAINS

UNLESS DETAILED OR SPECIFIED OTHERWISE COVERS AND GRATES TO BE

12. ALL PIPE BENDS, JUNCTIONS, ETC. ARE TO BE PROVIDED USING PURPOSE MADE FITTINGS OR STORMWATER PITS.

SHALL BE SCREW FIXED INTO POSITION.

- 13. THE CONTRACTOR SHALL SUPPLY AND INSTALL ALL FITTINGS AND SPECIALS INCLUDING VARIOUS PIPE ADAPTERS TO ENSURE PROPER CONNECTION BETWEEN DISSIMILAR PIPEWORK.
- 14. PIT DIMENSIONS SHALL BE IN ACCORDANCE WITH AS 3500.3 TABLE 8.2. ALL BASES OF PITS TO BE BENCHED TO HALF PIPE DEPTH AND PROVIDE GALVANISED ANGLE SURROUNDS TO GRATE. ALL CONNECTIONS TO EXISTING DRAINAGE PITS SHALL BE MADE IN A TRADESMAN-LIKE MANNER AND THE INTERNAL WALL OF THE PIT AT PIPE PENETRATIONS SHALL BE CEMENT RENDERED TO ENSURE A SMOOTH FINISH.
- INSPECTION OPENINGS SHALL BE INSTALLED WHERE REQUIRED IN ACCORDANCE WITH AS 3500.3.
- 16. THE CONTRACTOR SHALL ENSURE AND PROTECT THE INTEGRITY OF ALL STORMWATER PIPES DURING CONSTRUCTION. ANY AND ALL DAMAGE TO THESE PIPES AS A RESULT OF THESE WORKS SHALL BE REPAIRED BY THE CONTRACTOR UNDER THE DIRECTION OF THE SUPERINTENDENT, AND AT NO
- 17. INSTALL TEMPORARY SEDIMENT BARRIERS TO INLET PITS, UNTIL SURROUNDING AREAS ARE PAVED AND TURFED.
- 18. HAND EXCAVATE STORMWATER PIPES IN VICINITY OF TREE ROOTS.
- DOWNPIPES AND SPREADERS SHOWN ARE INDICATIVE ONLY. ALL ROOF GUTTERINGS AND DOWNPIPES TO AS/NZS 3500.3 SIZED AND LOCATED BY PLUMBER. MIN DOWNPIPE SIZE 100%.
- 20. ALL OTHER STORMWATER WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH AS 3500.3 AND EUROBODALLA SHIRE COUNCIL DEVELOPMENT DESIGN SPECIFICATIONS.

SOIL AND WATER MANAGEMENT NOTES

BUILDER SHALL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE UNDERTAKEN AS SPECIFIED IN ACCORDANCE WITH THE GUIDELINES SHOWN IN 'MANAGING URBAN STORMWATER - SOILS AND CONSTRUCTION 4TH EDITION 2004' (THE BLUE BOOK).

HEALTH AND SAFETY NOTES

THESE NOTES MUST BE READ AND UNDERSTOOD BY ALL INVOLVED IN THE PROJECT. THIS INCLUDES (but is not excluded to): OWNER, BUILDER, SUB-CONTRACTORS, CONSULTANTS, RENOVATORS, OPERATORS, MAINTENORS DEMOLISHERS

1. FALLS, SLIPS, TRIPS a) WORKING AT HEIGHTS DURING CONSTRUCTION

Wherever possible, components for this building should be prefabricated off—site or at ground level to minimise the risk of workers falling more than two metres. However, construction of this building will require workers to be working at heights where a fall in excess of two metres is possible and injury is likely to result from such a fall. The builder should provide a suitable barrier wherever a person is required to work in a situation where falling more than wo metres is a possibility.

DURING OPERATION OR MAINTENANCE For houses or other low—rise buildings where scaffolding is

leaning and maintenance of windows, walls, roof or other components of this building will require persons to be situated where a fall from a height in excess of two metres is possible. Where this type of activity is required, scaffolding, ladders or trestles should be used in accordance with relevant codes of practice, regulations or legislation.
For buildings where scaffold, ladders, trestles are not appropriate:
Cleaning and maintenance of windows, walls, roof or other
components of this building will require persons to be situated
where a fall from a height in excess of two metres is possible. Where
this type of activity is required, scaffolding, fall barriers or Personal
Protective Equipment (PPE) should be used in accordance with

relevant codes of practice, regulations or legislation ANCHORAGE POINTS ANCHORAGE POINTS

Anchorage points for portable scaffold or fall arrest devices are to be installed by the builder where required. Any persons engaged to work on the building after completion of construction work should be informed about the anchorage points.

b) SLIPPERY OR UNEVEN SURFACES

FLOOR FINISHES Specified If finishes have been specified by designer, these have been selected to minimise the risk of floors and paved areas becoming slippery when wet or when walked on with wet shoes/feet. Any changes to the specified finish should be made in consultation with the designer or, if this is not practical, surfaces with an equivalent or

better slip resistance should be chosen.

FLOOR FINISHES By Owner

If designer has not not been involved in the selection of surface finishes, the owner is responsible for the selection of surface finishes, in the pedestrian trafficable areas of this building. Surfaces should be selected in accordance with AS HB 197:1999 and AS/NZ 4586:2004

4586:2004. STEPS, LOOSE OBJECTS AND UNEVEN SURFACES Due to design restrictions for this building, steps and/or ramps are included in the building which may be a hazard to workers carrying objects or otherwise occupied. Steps should be clearly marked with both visual and tactile warning during construction, maintenance, demolition and at all times when the building operates as a

workplace. Building owners and occupiers should monitor the pedestrian access ways and in particular access to areas where maintenance is routinely carried out to ensure that surfaces have not moved or cracked so that they become uneven and present a trip hazard. Spills, loose material, stray objects or any other matter that may cause a slip or trip hazard should be cleaned or removed from access ways. ntractors should be required to maintain a tidy work site during construction, maintenance or demolition to reduce the risk of trip and falls in the workplace. Materials for construction or

maintenance should be stored in designated areas away from

2. FALLING OBJECTS

LOOSE MATERIALS OR SMALL OBJECTS Construction, maintenance or demolition work on or around this building is likely to involve persons working above ground level or above floor levels. Where this occurs one or more of the following measures should be taken to avoid objects falling from the area where the work is being carried out onto persons below.

1. Prevent or restrict access to areas below where the work is being carried out.

2. Provide toeboards to scaffolding or work platforms.

3. Provide protective structure below the work area.

4. Ensure that all persons below the work area have Personal Protective Equipment (PPE).

BUILDING COMPONENTS

During construction, renovation or demolition of this building, parts of the structure including fabricated steelwork, heavy panels and many other components will remain standing prior to or after supporting parts are in place. Contractors should ensure that temporary bracing or other required support is in place at all times when collapse which may injure persons in the area is a possibility. Mechanical lifting of materials and components during construction, maintenance or demolition presents a risk of falling objects. Contractors should ensure that appropriate lifting devices are used, that loads are properly secured and that access to areas below the load is prevented or restricted.

3. TRAFFIC MANAGEMENT

For building on a major road, narrow road or steeply sloping road: Parking of vehicles or loading/unloading of vehicles on this roadway may cause a traffic hazard. During construction, maintenance or demolition of this building designated parking for workers and loading areas should be provided. Trained traffic management personnel should be responsible for the supervision of these areas. For building where on—site loading/unloading is restricted: Construction of this building will require loading and unloading of materials on the roadway. Deliveries should be well planned to avoid congestion of loading areas and trained traffic management congestion of loading areas and trained traffic management personnel should be used to supervise loading/unloading areas. personnel should be used to superfice the personnel should be used to superfice the personnel should be used to superfice the personnel should be used to superfice present a risk of collision where deliveries and other traffic are moving within the site. A traffic management plan supervised by trained traffic management personnel should be adopted for the work site.

4. SERVICES GENERAL

Rupture of services during excavation or other activity creates a variety of risks including release of hazardous material. Existing services are located on or around this site. Where known, these are identified on the plans but the exact location and extent of services may vary from that indicated. Services should be located using an appropriate service (such as Dial Bedor and where appropriate excavation practice should be used and where necessary, specialist contractors should be used.

Locations with underground power:

Underground power lines MAY be located in or around this site. All underground power lines must be disconnected or carefully Locations with overhead power lines: Overhead power lines MAY be near or on this site. These pose a risk of electrocution if struck or approached by lifting devices or other plant and persons working above ground level. Where there is a danger of this occurring, power lines should be, where practical, disconnected or relocated. Where this is not practical adequate warning in the form of bright coloured tape or signage should be used or a protective barrier provided.

5. MANUAL TASKS

Components within this design with a mass in excess of 25kg should be lifted by two or more workers or by mechanical lifting device. Where this is not practical, suppliers or fabricators should be required to limit the component mass.

All material packaging, building and maintenance components should clearly show the total mass of packages and where practical all items should be stored on site in a way which minimises bending before lifting. Advice should be provided on safe lifting methods in all areas where lifting may occur. Construction, maintenance and demolition of this building will reguire the use of portable tools and equipment. These should be fully maintained in accordance with manufacturer?s specifications and not used where faulty or (in the case or electrical equipment) not carrying a current electrical safety tag. All safety guards or devices should be regularly checked and Personal Protective Equipment should be used in accordance with manufacturer?s specification.

6. HAZARDOUS SUBSTANCES

ASBESTOS For alterations to a building constructed prior to 1990: If this existing building was constructed prior to 1990:

If this existing building was constructed prior to:

1990 — it therefore may contain asbestos

1986 — it therefore is likely to contain asbestos
either in cladding material or in fire retardant insulation material. In
either case, the builder should check and, if necessary, take
appropriate action before demolishing, cutting, sanding, drilling or
otherwise disturbing the existing structure.

POWDERED MATERIALS Many materials used in the construction of this building can cause harm if inhaled in powdered form. Persons working on or in the building during construction, operational maintenance or demolition should ensure good ventilation and wear Personal Protective Equipment including protection against inhalation while using powdered material or when sanding, drilling, cutting or otherwise disturbing or creating powdered material.

The design of this building may include provision for the inclusion of treated timber within the structure. Dust or fumes from this material can be harmful. Persons working on or in the building during construction, operational maintenance or demolition should ensure good ventilation and wear Personal Protective Equipment including protection against inhalation of harmful material when sanding, drilling, cutting or using treated timber in any way that may cause harmful material to be released. Do not burn treated timber.

VOLATILE ORGANIC COMPOUNDS

Many types of glue, solvents, spray packs, paints, varnishes and some cleaning materials and disinfectants have dangerous emissions. Areas where these are used should be kept well ventilated while the material is being used and for a period after installation. Personal Protective Equipment may also be required. The manufacturer?s recommendations for use must be carefully

Fibreglass, rockwool, ceramic and other material used for thermal or sound insulation may contain synthetic mineral fibre which may be harmful if inhaled or if it comes in contact with the skin, eyes or other sensitive parts or the body. Personal Protective Equipment including protection against inhalation of harmful material should be used when installing, removing or working near bulk insulation material

This building may contain timber floors which have an applied finish. Areas where finishes are applied should be kept well ventilated during sanding and application and for a period after installation. Personal Protective Equipment may also be required. The manufacturer?s recommendations for use must be carefully considered at all times.

7. CONFINED SPACES

EXCAVATION Construction of this building and some maintenance on the building will require excavation and installation of items within excavations. Where practical, installation should be carried out using methods which do not require workers to enter the excavation. Where this is not practical, adequate support for the excavated area should be provided to prevent collapse. Warning signs and barriers to prevent accidental or unauthorised access to

all excavations should be provided. ENCLOSED SPACES
For buildings with enclosed spaces where maintenance or other access may be required:
Enclosed spaces within this building may present a risk to persons entering for construction, maintenance or any other purpose. The design documentation calls for warning signs and barriers to unauthorised access. These should be maintained throughout the

life of the building. Where workers are required to enter enclosed spaces, air testing equipment and Personal Protective Equipment should be provided

SMALL SPACES
For buildings with small spaces where maintenance or other access may be required: may be required:

Some small spaces within this building will require access by construction or maintenance workers. The design documentation calls for warning signs and barriers to unauthorised access. These should be maintained throughout the life of the building. Where workers are required to enter small spaces they should be scheduled so that access is for short periods. Manual lifting and other manual entirity chealth to restricted in mall spaces. other manual activity should be restricted in small spaces

8. PUBLIC ACCESS Public access to construction and demolition sites and to areas under maintenance causes risk to workers and public. Warning signs and secure barriers to unauthorised access should be provided. Where electrical installations, excavations, plant or loose materials are present they should be secured when not fully

9. OPERATIONAL USE OF BUILDING

RESIDENTIAL BUILDINGS This building has been designed as a residential building. If it, at a later date, it is used or intended to be used as a workplace, the provisions of the Work Health and Safety Act 2011 or subsequent replacement Act should be applied to the new use.

10. OTHER HIGH RISK ACTIVITY

All electrical work should be carried out in accordance with of Practice: Managing Electrical Risks at the Workplace, AS/NZ 3012 and all licensing requirements.

All work using Plant should be carried out in accordance with Code of Practice: Managing Risks of Plant at the Workplace.

All work should be carried out in accordance with Practice Managing Risks and Provention Managing Alexander Pro Practice: Managing Noise and Preventing Hearing Loss at Work. Due to the history of serious incidents it is recommended that particular care be exercised when undertaking work involving steel construction and concrete placement. All the above applies.

PROPOSED DEPOT BUILDING - CIVIL WORKS 6 FLINDERS ROAD, SOUTH NOWRA

CIVIL DRAWING LIST

19607/C01 NOTES

19607/C02 SITE PLAN

19607/C03 STORMWATER MANAGEMENT PLAN SHEET 1 19607/C04

19607/C05 EROSION & SEDIMENT CONTROL PLAN

STORMWATER MANAGEMENT PLAN SHEET 2

EROSION & SEDIMENT CONTROL NOTES & DETAILS



THIS DRAWING AND THE CONCEPTS CONTAINED THEREIN ARE THE PROPERTY Amendments Approved Date OF WESTLAKE PUNNETT & ASSOCIATES PTY. LTD. NO UNAUTHORISED COPYING ISSUED FOR DA APPROVAL S.Punnett | 22.06.20 IS PERMITTED. NO STRUCTURE IS TO BE CONSTRUCTED BASED ON THIS DRAWING, OR PART OF THIS DRAWING, WITHOUT THE WRITTEN PERMISSION OF WESTLAKE PUNNETT & ASSOCIATES PTY. LTD. ALL DIMENSIONS SHALL BE VERIFIED ON SITE. WHERE DIMENSIONS DIFFER FROM THOSE SHOWN ON ARCHITECTURAL DETAILS, DIRECTION SHALL BE OBTAINED FROM WESTLAKE PUNNETT & ASSOCIATES P/L. DO NOT SCALE - NO RESPONSIBILITY WILL BE TAKEN BY WESTLAKE PUNNETT & ASSOCIATES P/L FOR ANY DISCREPANCIES CAUSED BY SCALING THESE DRAWINGS.



CIVIL & STRUCTURAL ENGINEERS WWW.WESTLAKEPUNNETT.COM.AU

19607/C06


WOLLONGONG (02) 4211 0393 NOWRA (02) 4423 5533 ULLADULLA (02) 4455 4397 RESIDENTIAL - COMMERCIAL - INDUSTRIAL


NOTES


PROJECT: PROPOSED DEPOT BUILDING - CIVIL WORKS 6 FLINDERS ROAD, SOUTH NOWRA SHOALHAVEN WATER


Drawn: J.Taylor Checked: S.Punnett Date: 23/01/20 Drawing No. 19607/C01

Design: S.Punnett









GENERAL NOTES:

1. THE CONTRACTOR MUST ENTER INTO AN ENVIRONMENTAL PROTECTION AGREEMENT WITH THE SHOALHAVEN CITY

2. ENSURE THAT ALL ENVIRONMENTAL PROTECTION WORKS ARE IN PLACE BEFORE COMMENCING CONSTRUCTION ON THE

3. LIAISE AS NECESSARY WITH THE SHOALHAVEN CITY COUNCIL AND OBTAIN AGREEMENT TO THE ADEQUACY OF THE PROTECTION WORKS.

4. KEEP A COPY OF THE EPA SIGNED EROSION AND SEDIMENT CONTROL PLAN ONSITE AT ALL TIMES. DISPLAY IN A PROMINENT LOCATION.

5. LOCATE ALL PROTECTION WORKS WHOLLY WITHIN THE SITE UNLESS OTHERWISE PRE-APPROVED.

6. ASSIGN A DESIGNATED PARKING AREA. ALL WORKERS VEHICLES ARE TO BE PARKED IN LEGAL PARKING ZONES. WHERE POSSIBLE VEHICLES ARE TO BE PARKED WITHIN THE BLOCK.

7. MINIMISE THE DISTURBANCE OF THE EXISITNG SURFACE AND VEGETATION.

SOIL AND WATER MANAGEMENT NOTES

1. THE SOIL AND WATER MANAGEMENT PLAN IS TO BE READ IN CONJUNCTION WITH THE ENGINEERING PLANS AND COUNCIL'S WRITTEN GUIDELINES FOR THE DEVELOPMENT OF LAND.

2. CONTRACTORS SHALL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE UNDERTAKEN AS SPECIFIED ON THE PLAN AND IN ACCORDANCE WITH THE GUIDELINES SHOWN IN 'MANAGING URBAN STORMWATER - SOILS AND CONSTRUCTION 4TH EDITION 2004' (THE BLUE BOOK).

3. ALL CONTRACTORS ARE RESPONSIBLE FOR REDUCING THE SOIL EROSION AND POLLUTION OF DOWNSLOPE AREAS.

4. THE SOIL EROSION HAZARD ON THE SITE IS TO BE KEPT AS LOW AS POSSIBLE AND GENERALLY IN ACORDANCE WITH THE FOLLOWING SCHEDULE.

LAND USE	LIMITATION	COMMENTS
CONSTRUCTION AREAS	DISTURBANCE TO BE NO FURTHER THAN 5m (pref.2m) FROM THE EDGE OF ANY ESSENTIAL ENGINEERING ACTIVITY AS SHOWN ON THESE PLANS	ALL SITE WORKERS WILL CLEARLY RECOGNISE THESE ZONES - WHERE APPROPRIATE THE CONSTRUCTION AREAS ARE TO BE IDNTIFIED WITH BARRIER FENCING (UPSLOPE) & SEDIMENT FENCING (DOWNSLOPE) OR SIMILAR MATERIAL.
ACCESS AREAS	LIMITED TO A MAX. WIDTH OF 10m.	THE SITE MGR. SHALL DETERMINE AND MARK THE LOCATION OF THESE ZONES ONSITE. THEY CAN VARY IN POSITION TO BEST CONSERVE THE EXISTING VEGETATION AND PROTECT DOWNSTREAM AREAS WHILE BEING CONSIDERATE OF THE NEEDS OF EFFICIENT WORKS ACTIVITIES. ALL SITE WORKERS SHALL CLEARLY RECOGNISE THEIR BOUNDARIES - WHERE APPROPRIATE THE ACCESS AREAS ARE TO BE MARKED WITH BARRIER MESH, SEDIMENT FENCING OR SIMILAR MATERIALS
REMAINING LANDS	ENTRY PROHIBITED EXCEPT FOR ESSENTIAL THINNING OF PLANT GROWTH.	THINNING OF GROWTH MAY BE REQUIRED FOR FIRE HAZARD REDUCTION

NOTE: WORKS WITHIN WATERWAYS AND CREEKS SHALL BE RESTRICTED AS DIRECTED - ALL LANDS WITHIN CREEKS AND WATERWAYS SHALL HAVE C-FACTORS BELOW 0.05 FROM 1 JAN. TO 15 MAY USING MATERIALS THAT CAN CATER FOR CONCENTRATED FLOWS.

5. WORKS ARE TO BE UNDERTAKEN IN THE FOLLOWING SEQUENCE. EACH SUBSEQUENT STAGE IS NOT TO COMMENCE UNTIL THE PREVIOUS ONE IS COMPLETE:-

- a) INSTALL ALL BARRIER AND AND SEDIMENT FENCING WHERE SHOWN ON THE PLAN AND TO DETAIL (SD) 6-8,
- b) CONSTRUCT STABILISED SITE ACESS AS SHOWN ON THE PLAN AND TO DETAIL (SD) 6-14. c) CONSTRUCT LOW FLOW EARTH BANKS WHERE SHOWN ON THE PLAN AND TO DETAIL (SD) 5-5.
- d) CLEAR THE SITE AND STRIP AND STOCKPILE THE TOPSOIL IN THE LOCATIONS SHOWN ON THE PLANS OR AS DIRECTED BY
- THE SITE SUPERINTENDENT TO DETAIL (SD)4-1, e) UNTERTAKE ALL ESSENTIAL CONSTRUCTION WORKS,

DRAINAGE AREA MAXIMUM 0.4HA. SLOPE GRADIENT

MAXIMUM1:2 . SLOPE LENGTH MAXIMUM 40M.

STAKES DRIVEN 0.6M INTO -

THE GROUND.

DISTURBED AREA

- f) INSTALL MESH AND GRAVEL INLET PROTECTION (SD)6-11 FOR ADJACENT KERB INLETS NOT SHOWN,
- q) INSTALL GEOTEXTILE INLET FILTERS (SD)6-12 AROUND ALL DROP INLETS ONSITE, (NOT SHOWN), h) COMPLETE TRIMMING TO FINAL GRADES AND APPLY TURF TO DISTURBED AREAS WITHIN 5 DAYS OF COMPLETION OF
- CONSTRUCTION WORKS
- i) REMOVE TEMPORARY EROSION CONTROL MEASURES AFTER THE PERMANENT LANDSCAPING HAS BEEN COMPLETED.

UNDISTURBED AREA.

ANGLE FIRST STAKE TOWARDS PREVIOUSLY

ENSURE PICKETS ARE FITTED WITH SAFETY

LAID STRAW BALE.

CAPS.

6. CLEARLY VISIBLE BARRIER FENCING SHALL BE INSTALLED WHERE DIRECTED BY THE SITE SUPERINTENDENT TO CONTROL AND PROHIBIT UNNECESSARY SITE DISTURBANCE.

7. EARTH BATTERS SHALL BE CONSTRUCTED WITH AS LOW A GRADIENT AS PRACTICABLE BUT NO STEEPR THAN:

a) 2(h) - 1(v) WHERE SLOPE LENGTH IS LESS THAN 7m b) 2.5(h) - 1(v) WHERE SLOPE LENGTH IS BETWEEN 7m AND 10m c) 3(h) - 1(v) WHERE SLOPE LENGTH IS BETWEEN 10m AND 12m

d) 4(h) - 1(v) WHERE SLOPE LENGTH IS BETWEEN 12m AND 18m e) 5(h) - 1(v) WHERE SLOPE LENGTH IS BETWEEN 18m AND 27m

f) 6(h) - 1(v) WHERE SLOPE LENGTH IS GREATER THAN 27m SLOPE LENGTHS CAN BE SHORTENED BY USING LOW FLOW EARTH BANKS AS CATCH DRAINS ABOVE THE EARTH

8. PROTECTION FROM EROSIVE FORCES SHALL BE UNDERTAKEN ON ALL LANDS TO MEET THE REQUIREMENTS OF TABLE 9-7 'MAXIMUM ACCEPTABLE C-FACTORS AT NOMINATED TIMES DURING WORKS' FROM 'MANAGING URBAN STORMWATER - SOILS AND CONSTRUCTION 3RD EDITION'

9. TEMPORARY GROUND COVER IN SHEET FLOW AREAS IS TO BE IN ACCORDANCE WITH TABLE 9-7 'PLANT SPECIES FOR GROUND COVER' FROM ' MANAGING URBAN STORMWATER - SOILS AND CONSTRUCTION 3RD EDITION'. WHERE PRACTICAL FOOT AND VEHICULAR TRAFFIC SHALL BE KEPT AWAY FROM REHABILITATION AREAS.

10. WHERE POSSIBLE THE CONSTRUCTION PROGRAM IS TO BE SCHEDULED SO THAT THE TIME FROM STARTING LAND DISTURBANCE ACTIVITIES TO STABILISATION IS A DURATION OF LESS THAN 6 MONTHS THIS MEANS ACHIEVING A C-FACTOR OF LESS THAN 0.1 AND SETTING IN MOTION A PROGRAM THAT ENSURES THAT IT DROPS PERMANENTLY, (BY VEGETATION, PAVING, ARMOURING etc.) TO LESS THAN 0.05 WITHIN A FURTHER 60 DAYS. LOCAL WATER RESTRICTIONS PERMITTING. LANDS THAT HAVE BEEN NEWLY PLANTED WITH GRASS SPECIES SHALL BE WATERED REGULARLY UNTIL AN EFFECTIVE COVER HAS BEEN ESTABLISHED AND PLANTS ARE GROWING VIGOROUSLY. FOLLOW-UP SEED AND FERTILISER SHALL BE APPLIED AS NECESSARY IN AREAS OF MINOR SOIL FROSION AND/OR INADEQUATE VEGETATIVE PROTECTION. NOTWITHSTANDING THIS SCHEDULE OF WORKS SO THAT THE DURATION FROM THE CONCLUSION OF LAND SHAPING TO THE COMPLETION OF FINAL STABILISATION IS LESS THAN 20 WORKING DAYS.

11. THE VEGETATION SHALL BE AIMED AT RE-ESTABLISHING NATURAL SPECIES. THEREFORE, THE NATURAL SURFACE SOILS SHALL BE REPLACED AND NON PERSISTENT ANNUAL COVER CROPS SHALL BE USED.

12. SEDIMENT FENCES (SD)6-8 SHALL:

a) BE INSTALLED WHERE SHOWN ON THE PLAN AND AS DIRECTED AT THE DISCRETION OF THE SITE SUPERINTENDENT DURING THE COURSE OF CONSTRUCTION TO CONTAIN THE COARSER SEDIMENT FRACTIONS AS NEAR AS POSSIBLE TO

b) HAVE A CATCHMENT AREA NOT EXCEEDING 720sq.m. AND A STORAGE DEPTH OF AT LEAST 0.6m. c) PROVIDE AN UPSLOPE RETURN OF 1m AT INTERVALS ALONG THE FENCE WHERE THE CATCHEMNT AREA EXCEEDS 720sq.m. TO LIMIT THE DISCHARGE REACHING EACH SECTION TO 40litres/sec IN A MAX. 20yr Tc DISCHARGE.

13. STOCKPILES (SD) 4-1 SHALL BE LOCATED AS SHOWN ON THE PLANS AND AT DISCRETION OF THE SITE SUPERINTENDENT.

14, DURING WINDY WEATHER LARGE UNPROTECTED AREAS ARE TO BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO KEEP DUST UNDER CONTROL. IN THE EVENT WATER IS NOT AVAILABLE IN SUFFICIENT QUANTITIES SOIL BINDERS AND/OR DUST RETARDENTS SHALL BE USED OR THE SURFACE SHALL BE LEFT IN A CLODDY STATE THAT RESISTS REMOVAL BY WIND.

15. NOTWITHSTANDING NOTE 5d STOCKPILES SHALL NOT BE LOCATED WITHIN 5m OF HAZARD AREAS, INCLUDING LIKELY AREAS OF HIGH VELOCITY FLOWS SUCH AS WATERWAYS, PAVED AREAS OR DRIVEWAYS.

16. SEDIMENT REMOVED FROM ANY TRAPPING DEVICE SHALL BE DISPOSED IN LOCATIONS WHERE FURTHER EROSION AND CONSEQUENT POLLUTION TO DOWNSLOPE LANDS AND WATERWAYS SHALL NOT OCCUR

17. WATER SHALL BE PREVENTED FROM DIRECTLY ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS IT IS RELATIVELY SEDIMENT FREE (ie THE CATCHMENT HAS BEEN LANDSCAPED AND/OR ANY LIKELY SEDIMENT HAS BEEN TREATED IN AN APPROVED DEVICE) NEVERTHELESS STORMWATER INLETS SHALL BE PROTECTED (SD)6-11 & 6-12

18. TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES SHALL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE STABILISED

19. ACCEPTABLE BINS SHALL BE PROVIDED FOR ANY CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHTWEIGHT WASTE MATERIALS AND LITTER. CLEARANCE SERVICES SHALL BE PROVIDED AT LEAST ONCE A WEEK.

SITE INSPECTION AND MAINTENANCE

20. A SELF AUDITING PROGRAM SHALL BE ESTABLISHED BASED ON A CHECK SHEET. A SITE INSPECTION USING THE CHECK SHEET SHALL BE MADE BY THE SITE MANAGER:α) AT LEAST WEEKLY

b) IMMEADIATELY BEFORE SITE CLOSURE

c) IMMEADIATELY FOLLOWING RAINFALL EVENTS IN EXCESS OF 5mm IN ANY 24hr PERIOD. THE SELF AUDIT SHALL INCLUDE:a) RECORDING THE CONDITION OF EVERY 'BEST MANAGEMENT PRACTICE'

b) recording maintenance requirements (if any) for each 'best management practice'

c) RECORDING THE SITE WHERE SEDIMENT IS DISPOSED d) FORWARDING A SIGNED DUPLICATE OF THE COMPLETED CHECK SHEET TO THE PROJECT MANAGER/DEVELOPER FOR THEIR

21. IN ADDITION A SUITABLY QUALIFIED PERSON SHALL BE RESPONSIBLE FOR OVERSEEING THE INSTALLATION AND MAINTENANCE OF ALL SOIL AND WATER MANAGEMENT WORKS IN THE SITE. THE PERSON SHALL BE REQUIRED TO SPEND A

a) 2hrs onsite each fortnight up until completion of road and drainage works and/or the commisioning of SEDIMENT BASINS/WATER QUALITY CONTROL FACILITIES AND DURING THE DECOMMISIONING OF SAME AND/OR FINAL SITE STABILISATION. TO PROVIDE A SHORT MONTHLY WRITTEN REPORT.

b) ONE HOUR ONSITE EACH 2 MONTHS DURING THAT PHASE WHERE THE DEVELOPERS RESPONSIBILITIES ARE LIMITED TO MAINTENANCE OF THE SEDIMENT DEVICES AND/OR SEDIMENT BASINS (ie DURING THE STAGE WHEN BUILDING WORKS CAN BE UNDERTAKEN TO PROVIDE A SHORT WRITTEN REPORT EACH 4 mths. THE RESPONSIBLE PERSON SHALL ENSURE THAT:-

a) THIS PLAN IS BEING IMPLEMENTED CORRECTLY b) REPAIRS ARE BEING UNDERTAKEN AS REQUIRED

c) ESSENTIAL MODIFICATIONS TO THIS PLAN ARE MADE IF AND WHEN NECESSARY AND EACH REPORT SHALL CERTIFY THAT WORKS HAVE BEEN CARRIED OUT ACCORDING TO THE APPROVED PLANS.

24. WASTE BINS SHALL BE EMPTIED AS NECESSARY. DISPOSAL OF WASTE SHALL BE IN A MANNER APPROVED BY THE SITE

25. PROPER DRAINAGE OF THE SITE SHALL BE MAINTAINED. TO THIS END DRAINS (INCLUDING INLET AND OUTLET WORKS) SHALL BE CHECKED TO ENSURE THAT THEY ARE OPERATING AS INTENDED, ESPECIALLY THAT:a) NO LOW POINTS EXIST WHICH CAN OVERTOP IN LARGE STORM EVENTS.

b) AREAS OF EROSION ARE REPAIRED (eq LINED WITH SUITABLE MATERIAL) AND/OR VELOCITY OF FLOW IS REDUCED APPROPRIATELY THROUGH CONSTRUCTION OF SMALL CHECK DAMS OR INSTALLING ADDITIONAL DIVRESIONS UPSLOPE. c) BLOCKAGES ARE CLEARED (THESE MIGHT OCCUR BECAUSE OF SEDMINET POLLUTIONS, SAND/SOIL/SPOIL BEING DEPOSITED IN OR TOO CLOSE TO THEM, BREACHED BY VEHICLE WHEELS etc)

26. SAND/SOIL/SPOIL MATERIAL PLACED CLOSER THAN 2m FROM HAZARD AREAS SHALL BE REMOVED, SUCH HAZARD AREAS INCLUDE ANY AREAS OF HIGH VELOCITY WATER FLOWS (eg WATERWAYS AND GUTTERS) PAVED AREAS AND DRIVEWAYS.

27. RECENTLY STABILISED LANDS SHALL BE CHECKED TO ENSURE THAT THE EROSION HAZARD HAS BEEN EFFECTIVELY REDUCED. ANY REPAIRS SHALL BE INITIATED AS APPROPRIATE.

28. EXCESSIVE VEGETATION GROWTH SHALL BE CONTROLLED THROUGH MOWING OR SLASHING.

29. ALL SEDIMENT DETENTION SYSTEMS SHALL BE KEPT IN GOOD WORKING CONDITION. IN PARTICULAR ATTENTION SHALL BE x) RECENT WORKS TO ENSURE THAT THEY HAVE NOT RESULTED IN DIVERSION OF SEDIMENT LADEN WATER AWAY FROM

y) DEGRADEABLE PRODUCTS TO ENSURE THAT THEY ARE REPLACED AS REQUIRED z) SEDIMENT REMOVAL TO ENSURE THE DESIGN CAPACITY OR LESS REMAINS IN THE SETTLING ZONE.

30. ADDITIONAL EROSION AND/OR SEDIMENT CONTROL WORKS SHALL BE CONSTRUCTED AS MIGHT BECOME NECESSARY TO ENSURE THE DESIRED PROTECTION IS GIVEN TO DOWNSLOPE LANDS AND WATERWAYS (ie MAKE ONGOING CHANGES TO THIS PLAN WHERE IT PROVES INADEQUATE IN PRACTICE OR IS SUBJECTED TO CHANGES IN CONDITIONS AT THE WORKS SITE OR ELSEWHERE IN THE CATCHEMNT.

31. EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED IN A FUNCTIONING CONDITION UNTIL ALL EARTHWORKS ACTIVITIES ARE COMPLETED AND THE SITE STABLISED. VEGETATIVE STABILISATION SHOULD BE COMPLETED IMMEDIATELY AFTER COMPLETION OF FINAL LAND FORMING.

AIR & NOISE POLLUTION CONTROL


- 1. SUPPRESS DUST BY THE FOLLOWING METHODS WHERE APPLICABLE: a) STAGE WORKS TO LIMIT THE EXTENT OF EXPOSED AND UNPROTECTED AREAS.
- b) CONDUCT REGULAR SPRAYING OF WATER.
- c) COVER AND SECURE VEHICULAR LOADS ENTERING/EXITING THE SITE. d) USE AN ENVIRONMENTALLY FRIENDLY CHEMICAL SPRAY TO BIND SOIL TOGETHER THUS STABILISING UNUSED SOIL.
- e) RESTRICT SPEED OF VEHICLES ONSITE. f) COVER STOCKPILES TO PROTECT THEM FROM WIND.
- g) PROVIDE 1.8m HIGH DUST SCREENS; SHADE CLOTH, PVC BANNER OR POLYESTER MESH;


SECURELY FIXED TO PERIMETER FENCE

2. IMPLEMENT MEASURES TO LIMIT AIR POLLUTION BY VEHICLES AND PLANT WORKING ON OR PASSING THROUGH THE SITE. 3. MAINTAIN POLLUTION CONTROL MEASURES DURING CONSTRUCTION AND UNTIL FULL STABILISATION. ROUTINELY INSPECT EACH

WEEK AND AFTER SIGNIFICANT RAINFALL EVENTS. REPAIR AND REINSTATE WORKS AS NEEDED TO MAINTAIN PROTECTION. RECORD MAINTENANCE ACTIVITIES AND DETAILS AND PROVIDE TO EPA FOR INSPECTION WHEN REQUESTED.


4. ENSURE ALL CONSTRUCTION WORK THAT GENERATES NOISE TAKES PLACE ONLY WITHIN THE PRE-APPROVED OPERATING -MONDAY TO FRIDAY, BETWEEN 7A.M. & 6P.M. -SATURDAY, BETWEEN 8A.M & 3P.M.






STABILISED SITE ACESS (SD) 6-14

STRAW BALE SEDIMENT FILTER








PLACE HAY BALES LENGTHWISE IN A ROW WITH WITH ENDS TIGHTLY ABUTTING. USE

HAY TO FILL ANY GAPS BETWEEN BALES.

ENSURE THAT THE MAXIMUM HEIGHT OF

THE FILTER IS ONE BALE.

GEOTEXTILE FILTER FABRIC DROP INLET SEDIMENT TRAP



THE BOTTOM OF THE FABRIC TO BE


ENTRENCHED, BACKFILL THE TRENCH

OVER THE BASE OF THE FABRIC AND


COMPACT IT THOROUGHLY OVER THE

GEOTEXTILE.

MESH AND GRAVEL INLET FILTER TYPE A – LINTEL INLET NTS



MESH AND GRAVEL INLET FILTER TYPE B - SAG LINTEL INLET



CIVIL & STRUCTURAL ENGINEERS

CONSTRUCTION NOTES

SURFACE BEFORE LAYING MATTING. 2.TOPSOIL TO BE MINIMUM 75mm DEEP.

MATTING

SOIL BINDER.

THE SOIL GRADING THE SURFACE CAREFULLY.

5. LAY IN 'SHINGLE-FASION' WITH THE END OF THE

7. WATER TO BE DIVERTED AWAY FROM TREATED

SLOPES UNTIL VEGETATION IS ESTABLISHED UNLESS

CHANNEL IS SPRAYED WITH A SLOW-SETTING ANIONIC

WWW.WESTLAKEPUNNETT.COM.AU WOLLONGONG (02) 4211 0393 **NOWRA** (02) 4423 5533 ULLADULLA (02) 4455 4397 RESIDENTIAL - COMMERCIAL - INDUSTRIAL EROSION & SEDIMENT CONTROL NOTES & DETAILS

Checked: S.Punnett PROJECT: PROPOSED DEPOT BUILDING - CIVIL WORKS Date: 23/01/20 6 FLINDERS ROAD, SOUTH NOWRA Drawing No. 19607/C06 | SHOALHAVEN WATER

Design: S.Punnett

Drawn: J.Taylor

THIS DRAWING AND THE CONCEPTS CONTAINED THEREIN ARE THE PROPERTY Approved Date DF WESTLAKE PUNNETT & ASSOCIATES PTY. LTD. NO UNAUTHORISED COPYING ISSUED FOR DA APPROVAL S.Punnett | 22.06.20 S PERMITTED. NO STRUCTURE IS TO BE CONSTRUCTED BASED ON THIS DRAWING, OR PART OF THIS DRAWING, WITHOUT THE WRITTEN PERMISSION O WESTLAKE PUNNETT & ASSOCIATES PTY. LTD. ALL DIMENSIONS SHALL BE VERIFIED ON SITE. WHERE DIMENSIONS DIFFER FROM THOSE SHOWN ON ARCHITECTURAL DETAILS, DIRECTION SHALL BE OBTAINED FROM WESTLAKE PUNNETT & ASSOCIATES P/L. DO NOT SCALE - NO RESPONSIBILITY WILL BE TAKEN BY WESTLAKE PUNNETT & ASSOCIATES P/L FOR ANY DISCREPANCIES CAUSED BY SCALING THESE DRAWINGS.

