# Engineering

# Working Beyond Expectations

#### **ADW JOHNSON PTY LIMITED**

ABN 62 129 445 398

Sydney Level 35 One International Towers 100 Barangaroo Avenue Sydney NSW 2000 02 8046 7411 sydney@adwjohnson.com.au Central Coast 5 Pioneer Avenue Tuggerah NSW 2259 02 4305 4300

coast@adwjohnson.com.au

Hunter Region 7/335 Hillsborough Road Warners Bay NSW 2282 02 4978 5100

hunter@adwjohnson.com.au

# **Utility Services Report**

To accompany the Stage 1 and 2 Development Application for the Bonnyrigg Estate Masterplan

# **Property:**

Humphries Road, Bonnyrigg

## Applicant:

NSW Land and Housing Corporation

#### Date:

19th October 2020



Project Management • Town Planning • Engineering • Surveying Visualisation • Social Impact • Urban Planning

www.adwjohnson.com.au



### **Document Control Sheet**

| Issue No. | Amendment           | Date                         | Prepared By | Checked By |
|-----------|---------------------|------------------------------|-------------|------------|
| А         | Initial Draft Issue | 26 <sup>th</sup> August 2020 | JY          | ND         |
| В         | Client Comments     | 19th October 2020            | JY          | ND         |
|           |                     |                              |             |            |
|           |                     |                              |             |            |

#### **Limitations Statement**

This report has been prepared in accordance with and for the purposes outlined in the scope of services agreed between ADW Johnson Pty Ltd and the Client. It has been prepared based on the information supplied by the Client, as well as investigation undertaken by ADW Johnson and the sub-consultants engaged by the Client for the project.

Unless otherwise specified in this report, information and advice received from external parties during the course of this project was not independently verified. However, any such information was, in our opinion, deemed to be current and relevant prior to its use. Whilst all reasonable skill, diligence and care have been taken to provide accurate information and appropriate recommendations, it is not warranted or guaranteed and no responsibility or liability for any information, opinion or commentary contained herein or for any consequences of its use will be accepted by ADW Johnson or by any person involved in the preparation of this assessment and report.

This document is solely for the use of the authorised recipient. It is not to be used or copied (either in whole or in part) for any other purpose other than that for which it has been prepared. ADW Johnson accepts no responsibility to any third party who may use or rely on this document or the information contained herein.

The Client should be aware that this report does not guarantee the approval of any application by any Council, Government agency or any other regulatory authority.



# **Executive Summary**

ADW Johnson Pty Limited (ADW Johnson) has been commissioned by NSW Land and Housing Corporation to prepare a preliminary utility service designs to determine their ability to service Stage 1 and Stage 2 of the proposed overall development of Humphries Road, Bonnyrigg (the site).

A summary of each service authority's ability to service the overall development has been provided within the "Bonnyrigg Living Communities - Review of Services Infrastructure" prepared by Arcadis, Revision B and dated 31st August 2018 (hereafter referred to as: Review of Service Infrastructure Report). This report was completed as part of the Overall Masterplan Development (OMD) and did not involve contacting any of the service authorities, this is expected to be completed as part of the construction certificate documentation.

The purpose of this follow up report is to support a DA for Stage 1 and Stage 2 of the OMD and specifically provide additional details in regards to the provision of services within this stage of the development.

The Stage 1 and Stage 2 DA includes demolition of existing dwellings, services and roads as well as earthworks, service augmentation/installation, road construction and open space construction.

As was outlined within the Review of Service Infrastructure Report that accompanied the OMD, the provision of key services (i.e. potable water, sewer, electricity and telecommunications) does not pose a constraint to the proposed development. Please refer to the Review of Service Infrastructure Report for further information.

In order to provide further details in regards to the internal servicing of Stage 1 and Stage 2, a number of subconsultants were engaged to prepare concept designs of the infrastructure required to be installed. A summary of the works to be undertaken for each service within Stage 1 and Stage 2 appears in **Table A** below.

Table A: Summary of Servicing Infrastructure required for Stage 1 and Stage 2

| UTILITY SERVICE                      | LEAD-IN WORKS                                | INTERNAL WORKS  |  |  |  |  |  |
|--------------------------------------|--|---|--|--|--|--|--|
| Potable Water<br>Supply              | No significant<br>lead in works<br>required. | Retention of some existing water mains. Demolition of some existing water mains. Construction of DN100 and DN150 reticulation water mains to service the proposed development.  |  |  |  |  |  |
| Sewerage<br>Infrastructure           | No significant<br>lead in works<br>required. | Retention of some existing sewer mains. Demolition of some existing sewer mains. Construction of DN150 reticulation sewer mains to service the proposed development.  Retention of some existing pad mounted substations, high and low voltage cables, pillars and street lights. Demolition of some existing pad mounted substations, high and low voltage cables, pillars and street lights. Construction of 4 new pad mounted substations, electrical reticulation, pillars and street lights. |  |  |  |  |  |
| Electricity<br>Infrastructure        | No significant<br>lead in works<br>required. |   |  |  |  |  |  |
| Telecommunications<br>Infrastructure | No significant<br>lead in works<br>required. | Demolition of the majority of the existing Telstra pit and pipe. Construction of new NBN pit and pipe to service the proposed development.  |  |  |  |  |  |

**NOTE:** All service requirements subject to confirmation with relevant service authorities during the CC phase and therefore, the information contained within Table A may change accordingly.



The provision of key services to Stage 1 and Stage 2 of the OMD is not considered to present a constraint to the development.



# **Table of Contents**

| EXEC       | JTIVE SUMMARY                                   | . II |
|------------|---|------|
| 1.0        | INTRODUCTION                                    | . 1  |
| 2.0        | SITE DESCRIPTION                                | . 2  |
| 3.0        | PROPOSED DEVELOPMENT                            | . 3  |
| 4.0        | POTABLE WATER SUPPLY                            | . 4  |
| 4.1<br>4.2 | EXISTING INFRASTRUCTURE PROPOSED INFRASTRUCTURE |      |
| 5.0        | SEWERAGE INFRASTRUCTURE                         | . 5  |
| 5.1<br>5.2 | EXISTING INFRASTRUCTURE PROPOSED INFRASTRUCTURE |      |
| 6.0        | ELECTRICITY INFRASTRUCTURE                      | . 6  |
| 6.1<br>6.2 | EXISTING INFRASTRUCTURE PROPOSED INFRASTRUCTURE |      |
| 7.0        | TELECOMMUNICATIONS INFRASTRUCTURE               | . 7  |
| 7.1<br>7.2 | EXISTING INFRASTRUCTURE PROPOSED INFRASTRUCTURE |      |
| 8.0        | CONCLUSION                                      | . 8  |

#### **APPENDICES**

Appendix AProposed Stage 1 and Stage 2 Development PlanAppendix BWater and Sewer Concept Plans

**Appendix C** Electrical Concept Plans

**Appendix D** Telecommunications Concept Plans

**Appendix E** Combined Site Services Plans



#### 1.0 Introduction

This report supports a Development Application (DA) for Stage 1 and Stage 2 of the Bonnyrigg Estate redevelopment. It has been prepared for NSW Land and Housing Corporation.

This report should be read in conjunction with the "Bonnyrigg Living Communities – Review of Services Infrastructure" prepared by Arcadis, Revision B and dated 31st August 2018 (hereafter referred to as: Review of Service Infrastructure Report). This report was completed as part of the Overall Masterplan Development (OMD) and did not involve contacting any of the service authorities, this is expected to be completed as part of the construction certificate documentation.

The purpose of this follow up report is to support a DA for Stage 1 and Stage 2 of the OMD and specifically provide additional details in regards to the provision of services within these stages of the development.

As the purpose of this report is to accompany a DA only, it is high-level in nature. Further details will be prepared in conjunction with a future Construction Certificate (CC) application.



# 2.0 Site Description

The Bonnyrigg Estate site is located in Bonnyrigg and is generally bounded by Edensor Road to the north, Humphries Road to the east, Cabramatta Road West/ Elizabeth Drive to the south and Bonnyrigg Avenue to the west. Stage 1 and Stage 2 are located at the north eastern end of the site. The development is within the Fairfield City Council Local Government Area (LGA).

The current site contains a mix of privately owned residential dwellings and existing social housing. The current site also has existing roads which are proposed to be removed or modified. **Figure 1.0** below shows the existing site with the proposed site outline for Stage 1 and Stage 2.

Immediately to the west of the site are recently constructed social housing dwellings, a recently constructed park and an area of demolished housing which is DA approved for new social housing dwellings.



Figure 1.0 - Bonnyrigg Estate Site



# 3.0 Proposed Development

The proposed Stage 1 and Stage 2 Development Application seeks consent for the detailed works and redevelopment within the Bonnyrigg Estate.

The Stage 1 and Stage 2 Development Application seeks approval for:

- Site preparation works, including tree removal, demolition of roads, services and earthworks across the site;
- The provision and augmentation of utilities and services infrastructure across the site;
- The construction of internal roads and internal infrastructure;
- The consolidation of existing lots and subdivision of the site to reflect the revised road layout, open space.

An image of the DA layout and the proposed road reconfiguration is provided at **Figure 2.0** below.



Figure 2.0 - Stage 1 and Stage 2 DA Lot Layout



# 4.0 Potable Water Supply

#### 4.1 EXISTING INFRASTRUCTURE

A Dial Before You Dig (DB4YD) search was undertaken and it was found that there are trunk and reticulated water mains within Edensor Road, Humphries Road, Newleaf Parade and Bishop Crescent, as well as internal reticulation within the existing site. The internal potable water mains currently service the existing dwellings on site.

It is noted that the existing dwellings which are not privately owned will be demolished by the Land and Housing Corporation (LAHC) prior to the commencement of construction works. The privately owned dwellings will remain and will need to maintain a water service through construction. As such, there will be a staged approach to the removal of existing redundant water mains and the construction of the new water mains.

The sites current water supply is from a DN450 CICL trunk main in Edensor Road, a DN200 DICL in Humphries Road and Bishop Crescent which connects to the DN450 main and a DN150 DICL main which runs along Newleaf Parade.

A visual depiction of the abovementioned trunk and reticulation infrastructure is contained within 300241-ERPT-002 in Appendix B.

#### 4.2 PROPOSED INFRASTRUCTURE

Based upon the Review of Service Infrastructure Report it is expected that the proposed development can be serviced off the existing trunk water mains and that no lead in works will be required. It is however expected that the internal water main reticulation sizes may need to increase for the increased yield. This will be able to be confirmed with Sydney Water in conjunction with the preparation of CC documentation.

As mentioned in Section 4.1 of this report, there are existing private dwellings within the proposed development that are to remain and will require a water service to be maintained during construction. The existing social housing dwellings will be demolished prior to the construction works and therefore portions of the existing reticulation water mains will be able to be removed.

The water design proposes a number of internal DN100 and DN150 reticulation water mains to service the proposed development. The design will utilise a large portion of the existing water reticulation network where possible, however the existing network will still require a significant amount of demolition of existing water mains.

An indicative staged internal water reticulation layout and indicative sizing for the site is shown in 300241-ERPT-004 and 300241-ERPT-006 in Appendix B.



# 5.0 Sewerage Infrastructure

#### 5.1 EXISTING INFRASTRUCTURE

A DB4YD search was undertaken and it was found that there is an existing trunk sewer main which runs parallel to Humphries Road, crosses Humphries Road near Newleaf Parade and continues down to Green Valley Creek. There is also existing reticulation sewer throughout the existing site which drains to the existing trunk sewer main.

As previously mentioned, it is noted that the existing dwellings which are not privately owned will be demolished by the Land and Housing Corporation (LAHC) prior to the commencement of construction works. The privately owned dwellings will remain and will need to maintain a sewer service through construction. As such, there will be a staged approach to the removal of the existing redundant sewer mains and the construction of the new sewer mains.

The trunk sewer main is a DN225 VC main. The internal reticulation sewer is DN150 and are also VC mains.

A visual depiction of the abovementioned trunk and reticulation infrastructure is contained within 300241-ERPT-001 in Appendix B.

#### 5.2 PROPOSED INFRASTRUCTURE

Based upon the Review of Service Infrastructure Report it is expected that the proposed development can be serviced off the existing trunk sewer main and that no lead in works will be required. It is however expected that the internal sewer main reticulation sizes may need to increase for the increased yield. This will be able to be confirmed with Sydney Water in conjunction with the preparation of CC documentation.

As mentioned in Section 5.1 of this report, there are existing private dwellings within the proposed development that are to remain and will require a sewer service to be maintained during construction. The existing social housing dwellings will be demolished prior to the construction works and therefore portions of the existing reticulation sewer mains will be able to be removed.

The sewer design proposes a number of internal DN150 reticulation sewer mains to service the proposed development. The design will utilise a large portion of the existing sewer reticulation network where possible, however the existing network will still require a significant amount of demolition of existing sewer mains.

An indicative staged internal sewer reticulation layout and indicative sizing for the site is shown in 300241-ERPT-003 and 300241-ERPT-005 in Appendix B.



# 6.0 Electricity Infrastructure

#### 6.1 EXISTING INFRASTRUCTURE

A DB4YD search was undertaken and it was found that both high and low voltage, below ground, infrastructure exists within the existing road reserves adjacent to the site as well as within the existing site.

Based upon review of the DB4YD plans, the site is currently serviced from 3 pad mounted substations located alongside Humphries Road as well as a number of internal pad mounted substations. A number of the existing pad mounted substations are proposed to remain, however 2 pad mounted substations are proposed to be demolished.

Based upon review of the DB4YD plans, the site and surrounding roads also contains low voltage pillars to service existing dwellings as well as street lighting. A number of the existing pillars and street lights are proposed to remain, however a large number of pillars and street lights will need to be demolished due to their location in the vicinity of the new lots and potential driveway locations.

As previously mentioned, it is noted that the existing dwellings which are not privately owned will be demolished by the Land and Housing Corporation (LAHC) prior to the commencement of construction works. The privately owned dwellings will remain and will need to maintain an electrical service through construction. As such, there will be a staged approach to the removal of the existing redundant electrical mains and the construction of the new electrical reticulation.

A visual depiction of the abovementioned infrastructure is contained within **Appendix C**.

#### 6.2 PROPOSED INFRASTRUCTURE

Based upon the Review of Service Infrastructure Report it is expected that the proposed development can be serviced off the existing Bonnyrigg Zone Substation and no upgrades are required to the zone substation. Furthermore, no new 11kV feeders are anticipated and no major works to the existing network are anticipated external to the site.

As mentioned in Section 6.1 of this report, there are existing private dwellings within the proposed development that are to remain and will require an electrical service to be maintained during construction. The existing social housing dwellings will be demolished prior to the construction works and therefore portions of the existing electrical reticulation will be able to be removed.

The electrical design proposes a total of 4 new pad mounted substations, 3 are 500kVA and one is 1000kVA. The design will utilise a portion of the existing high and low voltage network as well as existing street lights where possible, however the existing network will still require a significant amount of demolition of existing electrical services and the construction of high and low voltage cables, electrical pillars and street lights.

An indicative staged electrical design for the site is shown in **Appendix C**.



# 7.0 Telecommunications Infrastructure

#### 7.1 EXISTING INFRASTRUCTURE

A DB4YD search was undertaken and it was found that telecommunications infrastructure exist within the existing road reserves adjacent to the site as well as within the existing site.

Based upon review of the DB4YD plans, the site is currently serviced via a Telstra and NBN pit and pipe network. A portion of the existing pit and pipe network is proposed to remain to the west of the proposed development. A large portion of the existing network will be required to be demolished or relocated due to the new road alignments. This will require an application to Telstra Network Integrity and NBN co Relocation Works.

As previously mentioned, it is noted that the existing dwellings which are not privately owned will be demolished by the Land and Housing Corporation (LAHC) prior to the commencement of construction works. The privately owned dwellings will remain and will need to maintain a telecommunications service through construction. As a result, it is likely that dwellings being retained will require a temporary solution until the NBN network is live because minimal telecommunications is being retained.

A visual depiction of the abovementioned infrastructure is contained within **Appendix D**.

#### 7.2 PROPOSED INFRASTRUCTURE

Based upon the Review of Service Infrastructure Report it is expected that the proposed development can be serviced from the existing NBN network, however it is noted that as the lot yield has increased since the original correspondence with NBN, it is recommended to re-engage with NBN to confirm there are no servicing issues. Furthermore, it is not expected that there will be any lead in works required for NBN servicing.

As mentioned in Section 7.1 of this report, there are existing private dwellings within the proposed development that are to remain. As the majority of the existing telecommunications network is getting removed or relocated there will be a need to provide a temporary solution until the NBN network is live.

The NBN design proposes to remove the majority of the existing Telstra pit and pipe network and as such a significant quantity of NBN pit and pipe network will be required to be constructed to service the proposed development.

An indicative staged telecommunications design for the site is shown in **Appendix D**.



#### 8.0 Conclusion

The Review of Service Infrastructure Report includes previous correspondence with the relevant authorities responsible for Water, Sewer, Electrical and Telecommunications in relation to the preliminary servicing advice for the OMD.

The purpose of this follow up report is to support a DA for Stage 1 and Stage 2 of the OMD and specifically provide additional details in regards to the provision of services within these stages of the development.

All authorities have advised that they can service the proposed overall development, albeit in some cases, with minor upgrades to the existing network required.

In order to provide further details in regards to the internal servicing of Stage 1 and Stage 2, a number of subconsultants where engaged to prepare concept designs of the infrastructure required to be installed. A summary of the works to be undertaken for each service within Stage 1 and Stage 2 appears in **Table 8.1** below.

Table 8.1: Summary of Existing Utility Services Infrastructure and Upgrades Required

| UTILITY SERVICE                      | LEAD-IN WORKS                                | INTERNAL WORKS   |  |  |  |  |  |  |
|--------------------------------------|--|--|--|--|--|--|--|--|
| Potable Water<br>Supply              | No significant<br>lead in works<br>required. | Retention of some existing water mains. Demolition of some existing water mains. Construction of DN100 and DN150 reticulation water mains to service the proposed development.   |  |  |  |  |  |  |
| Sewerage<br>Infrastructure           | No significant<br>lead in works<br>required. | Retention of some existing sewer mains. Demolition of some existing sewer mains. Construction of DN150 reticulation sewer mains to service the proposed development.   |  |  |  |  |  |  |
| Electricity<br>Infrastructure        | No significant<br>lead in works<br>required. | Retention of some existing pad mounted substations, high and low voltage cables, pillars and street lights.  Demolition of some existing pad mounted substations, high and low voltage cables, pillars and street lights. Construction of 4 new pad mounted substations, electrical reticulation, pillars and street lights. |  |  |  |  |  |  |
| Telecommunications<br>Infrastructure | No significant<br>lead in works<br>required. | Demolition of the majority of the existing Telstra pit and pipe. Construction of new NBN pit and pipe to service the proposed development.   |  |  |  |  |  |  |

**NOTE:** All service requirements subject to confirmation with relevant service authorities during the CC phase and therefore, the information contained within Table 8.1 may change accordingly.

Overall services plans are shown in **Appendix E**.


More detailed information is expected to be provided in conjunction with Construction Certificate documentation for each proposed stage of the development.



# Appendix A

PROPOSED STAGE 1 AND STAGE 2 DEVELOPMENT PLAN











# **Appendix B**


WATER AND SEWER CONCEPT PLANS




















# Appendix C


**ELECTRICAL CONCEPT PLANS** 















11kV SYSTEM DIAGRAM


|   |  |         |             |             |     |   |             |   | DESIGN BY  C.LEVER | 26/08/2020         | ITLE       | BONNYRIGG      |            |         |
|---|--|---------|-------------|-------------|-----|---|-------------|---|--------------------|--------------------|------------|----------------|------------|---------|
|   |  |         |             |             |     |   | Pov         | ver                                     | DRAWN M.ALMOND     | DATE               |            | HUMPHRIES ROA  | <b>'</b> D |         |
| Н |  |         |             |             |     |   |             | solutions                               |                    | 26/08/2020<br>DATE | SUBDIVISIO | ON INFRASTRUCT | URE REV    | /IEW H  |
| В | 26/08/2020         SUBSTATION 3 LOCATION REVIEWED         M.A           26/08/2020         CONCEPT - FINAL         M.A | C.L. C. | L. A. I. C. | 00 10.1/    |     |   |             | 1300 73 22 93                           | C.LEVER            | 26/08/2020         |            | HIGH VOLTAGE   |            |         |
| A | 12/08/2020         CONCEPT DRAFT         M.A           V DATE         REVISION DESCRIPTION         B'                  | C.L. C. |             | -20 - 10:13 | OAM |   | PO BOX 278, | (02) 4923 8199<br>jects@powersol.com.au |                    | JOB No. SI         | A1 NTS     | 363402         | 4 OF 4     | REV NO. |
| 1 | 1 2 3  | 5261(71 | 4 5         | 6           |     | 7 | 8           | 9                                       |                    | 10                 |            | 11             | 12         |         |































## Appendix D

TELECOMMUNICATIONS CONCEPT PLANS









## **Appendix E**

**COMBINED SITE SERVICES PLANS** 

