

DRAWING NOTES:

- Site establishment, tree protection and sediment erosion controls to be established in accordance with the construction management plan for the Site.
- 2. Demolish and remove redundant concrete hard stand on site (indicative areas shown on detailed site survey).
- 3. Demolish and remove redundant bitumised areas (indicative areas shown on detailed site survey).
- 4. No excavation works are shown on this plan. Refer bulk excavation drawing for excavation works.
- 5. No remediation works are shown on this plan. Refer to the remedial action plan for remediation works.
- Contractor to comply with all WHS and environmental legislation including the Work Health and Safety Act 2011 (NSW) and Work Health and Safety Regulation 2011 (NSW).
- 7. Contractor to comply with all conditions of development consent imposed by Liverpool City Council about demolition.
- 8. Contractor to comply with Code of Practice for Demolition issued by Safe Work NSW.
- Contractor to comply with Principal's construction management plan for the Site including the construction traffic management plan.
- 10. Contractor to comply with AS2601 demolition of structures.
- 11. Contractor to provide Principal's Representative with a dilapidation report of the public domain prior to the commencement of work.
- 12. Contractor to provide Principal's Representative with its SWMS's for the work prior to the commencement of work.
- 13. Contractor to undertake a risk assessment of the works prior to the commencement of works.



OFFICE: Unit 1, 139 Loftus Avenue, Loftus, NSW, 2232 MAIL: 5 Maddens Lane, Coldstream, VIC, 3770 WWW.MURDOCHPROJECTS.COM