



Memorial Ave Liverpool
Mixed Use Development

OPERATIONAL WASTE MANAGEMENT PLAN

22/02/2019
Report No. 18006
Revision E

Client

Il Capitano Investments Pty Ltd

79 Bathurst St Liverpool NSW 2710
T 02 9601 7166

Architect

Allen Jack + Cottier Architects

79 Myrtle St Chippendale Sydney NSW 2008
<http://architectsajc.com>
T 02 9311 8222 • E equiries@architectsajc.com

ELEPHANTS FOOT RECYCLING SOLUTIONS • ABN 70 001 378 294
44-46 Gibson Ave Padstow NSW 2211
www.elephantsfoot.com.au






T +612 9780 3500 • F +612 9707 2588
E info@elephantsfoot.com.au

SCOPE

This waste management plan (WMP) only applies to the **operational** phase of the proposed development; therefore the requirements outlined in this WMP must be implemented during the operational phase of the site and may be subject to review upon further expansion for, and/or changes to the development.

The waste management of the **construction** and **demolition** phases of the development are not addressed in this report. It is EFRS's understanding that a construction and demolition WMP will be completed by a separate party appointed by the developer, and submitted separately to this report. Typically, the head contractor of the site will be responsible for removing all construction-related waste offsite in a manner that meets all authority requirements.

REVISION REFERENCE

Revision	Date	Prepared by	Reviewed by	Description	Signed
A	19/07/2018	H Wilkes	A Armstrong	Draft	
B	7/11/2018	H Wilkes	A Armstrong	Amendment	
C	24/01/2019	H Wilkes	A Armstrong	Final	
D	25/01/2019	H Wilkes	A Armstrong	Amendment	
E	22/02/2019	H Wilkes	A Armstrong	Amendment	

The information contained in this document produced by Elephants Foot Recycling Solutions (EFRS) is solely for the use of the client identified on the cover sheet for the purpose for which it has been prepared for. EFRS undertakes no duty, nor accepts any responsibility for any third party who may rely upon this document. Reproduction, publication or distribution of this document without written permission from EFRS is strictly prohibited.

TABLE OF CONTENTS

LIST OF TABLES.....	ii
GLOSSARY OF TERMS.....	iii
INTRODUCTION	4
REPORT CONDITIONS.....	5
DEVELOPMENT SUMMARY	6
SITE LOCATION.....	6
LIVERPOOL CITY COUNCIL.....	7
COUNCIL OBJECTIVES.....	7
COUNCIL REQUIREMENTS.....	7
STAKEHOLDER ROLES AND RESPONSIBILITIES.....	8
EDUCATION.....	9
RESIDENTIAL WASTE MANAGEMENT.....	10
ESTIMATED WASTE VOLUMES AND PROVISIONS	10
HOUSEHOLD WASTE	10
COMMON AREAS	10
SOURCE SEPERATION.....	11
GENERAL WASTE (GARBAGE).....	11
RECYCLING	11
GREEN WASTE.....	11
BULKY GOODS	11
ELECTRONIC WASTE.....	12
CHEMICAL WASTE	12
ORGANIC WASTE AND COMPOSTING	12
CLOTHING WASTE	12
COMMERCIAL AND RETAIL WASTE MANAGEMENT	13
ESTIMATED WASTE VOLUMES AND PROVISIONS	13
RETAIL WASTE MANAGEMENT.....	13
COMMERCIAL WASTE MANAGEMENT	13
RESTURANT WASTE MANAGEMENT	14
WASHROOM	14
WASTE OILS	14
OTHER WASTE STREAMS.....	14
MOVEMENT AND TRANSPORTATION OF BINS	15
COLLECTION OF WASTE.....	15
RESIDENTIAL.....	15
RETAIL AND COMMERICAL	15
COLLECTION AREA.....	15
INSTALLATION EQUIPMENT AND DESIGN	16

EQUIPMENT SUMMARY.....	16
WASTE ROOM AREAS	16
GARBAGE ROOMS	17
CONSTRUCTION REQUIREMENTS	17
SIGNAGE.....	17
VENTILATION.....	17
USEFUL CONTACTS	18
APPENDICES.....	19
APPENDIX A ARCHITECTURAL DRAWING EXCERPTS	19
APPENDIX A.1 SITE PLAN	19
APPENDIX A.2 GROUND LEVEL – WASTE FACILITIES AND COLLECTION AREA.....	20
APPENDIX A.3 TYPICAL RESIDENTIAL LEVEL	21
APPENDIX B PRIMARY WASTE MANAGEMENT PROVISIONS	22
APPENDIX B.1 LIVERPOOL BIN SPECIFICATIONS.....	22
APPENDIX B.2 SIGNAGE FOR WASTE & RECYCLING BINS.....	23
APPENDIX B.3 TYPICAL COLLECTION VEHICLE INFORMATION	24
APPENDIX B.4 TYPICAL MOTORISED BIN TUG.....	27
APPENDIX B.5 TYPICAL SEATED BIN MOVER.....	28
APPENDIX C INSTALLATION EQUIPMENT AND WASTE ROOM LAYOUTS	29
APPENDIX C.1 TYPICAL SINGLE WASTE CHUTE SPECIFICATIONS	29
APPENDIX C.2 TYPICAL 2-BIN LINEAR TRACK SYSTEM FOR 660L MGBS.....	30
APPENDIX C.3 TYPICAL 3-BIN LINEAR TRACK SYSTEM FOR 660L MGBS.....	31
APPENDIX C.4 TYPICAL BIN LIFTER SUITABLE FOR 240L MGBS.....	32
APPENDIX D SECONDARY WASTE MANAGEMENT PROVISIONS.....	33
APPENDIX D.1 TYPICAL APARTMENT STYLE COMPOST BINS	33
APPENDIX D.2 ELECTRIC ORGANIC COMPOST BIN	34
APPENDIX D.3 TYPICAL COOKING OIL CONTAINERS.....	35
APPENDIX D.4 TYPICAL BACK OF HOUSE BINS FOR RETAIL/COMMERCIAL OPERATIONS	36

LIST OF TABLES

Table 1: Stakeholder Roles and Responsibilities.....	8
Table 2: Calculated Waste Generation – Residential	10
Table 3: Calculated Waste Generation – Commercial, Restaurant, and Retail Tenancies...	13
Table 4: Equipment Summary.....	16
Table 5: Waste Room Areas	16

GLOSSARY OF TERMS

TERM	DESCRIPTION
<i>Baler</i>	A device that compresses waste into a mould to form bales which may be self-supporting or retained in shape by strapping
<i>Chute</i>	A ventilated, vertical pipe passing from floor to floor of a building with openings as required to connect with hoppers and normally terminating at its lower end at the roof of the central waste room(s)
<i>Chute Discharge</i>	The point at which refuse exits from the refuse chute
<i>Chute Discharge Room</i>	A secure, enclosed area or room housing the discharge and associated equipment for the refuse chute
<i>Collection Area/Point</i>	The identified position or area where garbage or recyclables are actually loaded onto the collection vehicle
<i>Compactor</i>	A machine for compressing waste into disposable or reusable containers
<i>Composter</i>	A container/machine used for composting specific food scraps
<i>Crate</i>	A plastic box used for the collection of recyclable materials
<i>Garbage</i>	All domestic waste (Except recyclables and green waste)
<i>Green Waste</i>	All vegetated organic material such as small branches, leaves and grass clippings, tree and shrub pruning, plants and flowers
<i>Hopper</i>	A fitting into which waste is placed and from which it passes into a chute or directly into a waste container. It consists of a fixed frame and hood unit (the frame) and a hinged or pivoted combined door and receiving unit
<i>L</i>	Litre(s)
<i>Liquid Waste</i>	Non-hazardous liquid waste generated by commercial premises that is supposed to be connected to sewer or collected for treatment and disposal by a liquid waste contractor (including grease trap waste)
<i>LRV</i>	Large rigid vehicle described by AS 2890.2-2002 Parking facilities – Off-street commercial vehicle facilities as heavy rigid vehicle (HRV)
<i>Mobile Garbage Bin(s) (MGB)</i>	A waste container generally constructed of plastic with wheels with a capacity in litres of 120, 240, 360, 660, 1000 or 1100
<i>MRV</i>	Medium rigid vehicle
<i>Putrescible Waste</i>	Component of the waste stream liable to become putrid. Usually breaks down in a landfill to create landfill gases and leachate. Typically applies to food, animal and organic products.
<i>Recycling</i>	Glass bottles and jars – PET, HDPE and PVC plastics; aluminium aerosol and steel cans; milk and juice cartons; soft drink, milk and shampoo containers; paper, cardboard, junk mail, newspapers and magazines
<i>SRV</i>	Small rigid vehicle as in AS 2890.2-2002 Parking facilities – Off-street commercial vehicle facilities, generally incorporating a body width of 2.33

INTRODUCTION

Elephants Foot Recycling Solutions has been engaged to prepare the following waste management plan for Il Capitano Investments Pty Ltd for the operational management of waste generated by the mixed use development located at Memorial Ave Liverpool.

Waste management strategies and auditing are a requirement for new developments to provide support for the building design, and promote strong sustainability outcomes for the building. It is EFRS's belief that a successful waste management strategy contains three key objectives:

- i. **Promote responsible source separation** to reduce the amount of waste that goes to landfill, by implementing convenient and efficient waste management systems
- ii. **Ensure adequate waste provisions and robust procedures** that will cater for potential changes during the operational phase of the development
- iii. **Compliance** with all relevant council codes, policies, and guidelines.

To achieve these objectives, this WMP identifies the different waste streams likely to be generated during the operational phase of the development. Associated information includes: how the waste will be handled and disposed of, details of bin sizes/quantities and waste rooms, descriptions of the proposed waste management equipment used and information on waste collection points and frequencies.

It is essential that this waste management plan is integrated to the overall management of the building and clearly communicated to all relevant stakeholders.

REPORT CONDITIONS

The purpose of this report is to document a Waste Management Plan (WMP) as part of a development application and is supplied by EFRS with the following limitations:

- Drawings, estimates and information contained in this waste management plan have been prepared by analysing the information, plans and documents supplied by the client, and third parties including Council and government information. The assumptions based on the information contained in the WMP is outside the control of EFRS;
- The figures presented in the report are an estimate only – the actual amount of waste generated will be dependent on the occupancy rate of the building/s and waste generation intensity as well as the building managements approach to educating residents and tenants regarding waste management operations and responsibilities;
- The building manager will make adjustments as required based on actual waste volumes (if waste is greater than estimated) and increase the number of bins and collections accordingly;
- The report will not be used to determine or forecast operational costs or prepare any feasibility study or to document any safety or operational procedures;
- The report has been prepared with all due care however no assurance or representation is made that the WMP reflects the actual outcome and EFRS will not be liable to you for plans or outcomes that are not suitable for your purpose, whether as a result of incorrect or unsuitable information or otherwise;
- EFRS offer no warranty or representation of accuracy or reliability of the WMP unless specifically stated;
- Any manual handling equipment recommended should be provided at the recommendation of the appropriate equipment provider who will assess the correct equipment for supply;
- Design of waste management chute equipment and systems must be approved by the supplier.
- EFRS cannot be held accountable for late changes to the design after the WMP has been submitted to Council.
- EFRS will provide specifications and recommendations on bin access and travel paths within the WMP, however it is the architect's responsibility to ensure the architectural drawings meet these provisions.
- EFRS are not required to provide information on collection vehicle head heights, internal manoeuvring and loading requirements. These variables are considered to be within the applicable Traffic Consultants domain.
- Council are subject to changing waste and recycling policies and requirements at their own discretion.

This WMP has only been finalised once the Draft Watermark has been removed. If the Draft Watermark is present, the information in the WMP is not confirmed.

DEVELOPMENT SUMMARY

The proposed development falls under the LGA of Liverpool Council, and consists of:


- Two buildings, one building with 23 levels and one building with 17 Levels and 3 shared basement levels
 - 264 residential units in total consisting of;
 - 172 units in the West Tower
 - 92 units in the East Tower.
 - 1 restaurant tenancy with a total GFA of 1009 m²
 - Office tenancies with a total GFA of 111m²
 - 2 retail tenancies with a total GFA of 843m²

All figures and calculations are based on area schedules as advised by our client and shown on architectural drawings.

SITE LOCATION

The site located is Memorial Ave, 89-94 Castlereagh St & 77-79 Bathurst St Liverpool, as shown in Figure.1. The site has frontages to Memorial Ave and Castlereagh St and Bathurst St, with vehicle access via Castlereagh St.

Figure 1 - Site Location



LIVERPOOL CITY COUNCIL

The garbage and recycling will be guided by the services and acceptance criteria of the Liverpool City Council. All waste facilities and equipment are to be designed and constructed to be in compliance with the Liverpool City Council's *Liverpool Development Control Plan 2008*, Australian Standards and statutory requirements.

COUNCIL OBJECTIVES

- To minimise waste generation and disposal to landfill with careful source separation, reuse and recycling.
- To avoid the generation of waste through design, material selection and building practices.
- To plan for the types, amount and disposal of waste to be generated during demolition, excavation and construction of the development.
- To ensure efficient storage and collection of waste and quality design of facilities

COUNCIL REQUIREMENTS

Access – Ensure waste systems are easy to use and collection vehicles are able to access buildings to safely remove waste and recycling;

Safety – Ensure safe practises for storage, handling and collection of waste and recycling;

Pollution Prevention – Prevent stormwater pollution that may occur as a result of poor waste storage and management practises;

Noise Minimisation – Provide acoustic insulation to the waste service facilities or residential units adjacent to or above chutes, waste storage facilities, chute discharge, waste compaction equipment and waste collection vehicle access points;

Ecologically Sustainable Development (ESD) – Promote the principles of ESD through resource recovery and recycling leading to a reduction in the consumption of finite natural resources;

Hygiene – Ensure health and amenity for residents, visitors and workers in the Liverpool City Council.

STAKEHOLDER ROLES AND RESPONSIBILITIES

The following table demonstrates the primary roles and responsibilities of the respective stakeholders:

Table 1: Stakeholder Roles and Responsibilities

Roles	Responsibilities
Strata/Management	<ul style="list-style-type: none"> Ensuring that all waste service providers submit monthly reports on all equipment movements and waste quantities/weights; Organising internal waste audits/visual assessments on a regular basis; and Manage any non-compliances/complaints reported through waste audits.
Building Manager/Waste Caretaker	<ul style="list-style-type: none"> Ensuring effective signage, communication and education is provided to occupants, tenants and cleaners; Providing staff/contractors with equipment manuals, training, health and safety procedures, risk assessments, and PPE to control hazards associated with all waste management activities; Ensuring site safety for residents, children, visitors, staff and contractors; Abiding by all relevant OH&S legislation, regulations, and guidelines; Assessing any manual handling risks and prepare a manual handling control plan for waste and bin transfers; Preventing storm water pollution by taking necessary precautions (securing bin rooms, preventing overfilling of bins) General maintenance and cleaning of chute doors on each level; Cleaning and transporting of bins as required; Organising, maintaining and cleaning the general and recycled waste holding area; Organising both garbage and recycled waste pick-ups as required; Organising replacement or maintenance requirements for bins; Organising bulky goods collection when required; and Investigating and ensuring prompt clean-up of illegally dumped waste materials.
Residents/Tenants	<ul style="list-style-type: none"> Dispose of all garbage and recycling in the allocated waste chutes and/or MGBs provided; Ensure adequate separation of garbage and recycling; and Compliance with the provisions of Council and the WMP.
Council/Private Waste Contractor	<ul style="list-style-type: none"> Provide a reliable and appropriate waste collection service; Provide feedback to building managers/residents in regards to contamination of recyclables; and Work with building managers to customise waste systems where possible.
Gardening/Landscaping Contractor	<ul style="list-style-type: none"> Removal of all garden organic waste generated during gardening maintenance activities for recycling at an offsite location.
Building Contractors	<ul style="list-style-type: none"> Removing all construction related waste offsite in a manner that meets all authority requirements.

EDUCATION

Educational material encouraging correct separation of garbage and recycling items must be provided to each resident by building management to ensure correct use of the waste chute. This should include the correct disposal process for bulky goods (old furniture, large discarded items, etc.), and other appropriate materials (electronic, chemical waste, etc.). It is recommended that information is provided in multiple languages to support correct practises and minimise the possibility of chute blockages as well as contamination in the collective waste bins.

It is also recommended that the owners' corporation website contain information for residents to refer to regarding use of the chute. Information should include:

- Directions on using the chute doors;
- Recycling and garbage descriptions (council provides comprehensive information);
- How to dispose of bulky goods and any other items that are not garbage or recycling;
- Residents' obligations to health and safety and building management; and
- How to prevent damage or blockages to the chute (example below).

To prevent damage or blockage to rubbish chute DO NOT dispose of any newspapers, umbrellas, bedding, cigarettes, cartons, coat hangers, brooms, mops, large plastic wrappings from furniture, white goods, any sharp objects, hot liquid or ashes, oil, unwrapped vacuum dust, syringes, paint and solvents, car parts, bike parts, chemicals, corrosive and flammable items, soil, timber, bricks or other building materials, furniture, etc. down the chute.

WASRESIDENTIAL WASTE MANAGEMENT

The *Liverpool Development Control Plan 2008* has been referenced to calculate the total number of bins required for the residential units. Calculations are based on generic figures; waste generation rates may differ according to the residents' waste management practice.

ESTIMATED WASTE VOLUMES AND PROVISIONS

The following table shows the estimated volume (L) of garbage and recycling generated by the residential component of the development.

Table 2: Calculated Waste Generation – Residential

Building	# Units	Garbage Generation Rate (L/unit/week)	Generated Garbage (L/w eek)	Compacted Garbage (2:1) (L/w eek)	Recycling Generation Rate (L/unit/w eek)	Generated Recycling (L/w eek)
East Tower	92	120	11040	5520	120	11040
West Tower	172	120	20640	10320	120	20640
TOTAL	264		31680	15840		31680
Collections	Garbage Bin Size (L)			660	Collection Recycling Bin Size (L)	660
	Garbage Bins per Week			24.0	Recycling Bins per Week	48.00
	Garbage Collections per Week			2	Recycling Collections per Week	2
	Total Garbage Bins Required			12	Total Recycling Bins Required	24
Equipment	Number of Waste Bins Per Day	East Tower		1.19		
		West Tower		2.2		
	Chute Discharge Equipment		Single Chute			
	Other Equipment		1x 2-bin linear tracks for 660L MGB with Compactor 1x 3-bin linear tracks for 660L MGB with Compactor			

*Note: An additional 660L MGB should be provided for each chute discharge for use during collection periods. These bins are not included in the above figures.

HOUSEHOLD WASTE

Two garbage chutes will be installed with access provided on all residential levels of each Tower. The chutes are to be used for the disposal of garbage only. Garbage discharges into 660L MGBs placed on linear tracks and is compacted. The discharge is located in the waste discharge rooms for each tower.

240L recycling bins will be situated in the waste compartment on each residential level for collection of recyclable items. Each residential level of each tower must have at least one recycling bin. The building caretaker is responsible for monitoring the capacity of recycling bins and emptying the bins into 660L MGBs for collection as required. A bin lifter will be used to decant the 240L MGBs into the 660L MGBs.

Full garbage and recycling bins will be transferred to the collection area on Ground Level (see APPENDIX A.1) to await for servicing.

COMMON AREAS

The lobbies, amenities and circulation areas will be supplied with suitably branded waste and recycling bins where considered appropriate. These areas generate minimal waste, however garbage and recycling receptacles should be provided and located in convenient locations.

SOURCE SEPERATION

Waste avoidance, recovery and reuse of discarded materials and responsible management of hazardous waste are all crucial elements of sustainable development. Effective waste management practices in residential developments significantly improve environmental, social, and economic outcomes on both a local and regional scale, and should be integrated into the waste management processes.

GENERAL WASTE (GARBAGE)

Residents will be supplied with a collection area in each unit to deposit garbage and collect recyclable material suitable for one day's storage. This is typically located generally in the kitchen, under bench or similar alternate area. Residents should wrap or bag their garbage; bagged garbage should not exceed 3kg in weight or 35cm x 35cm x 35cm in dimension.

RECYCLING

Recycling must not be bagged. It is recommended that residents use a crate or dedicated bin for collecting recyclables within the allocated residential space provided to ensure correct separation.

Cardboard furniture boxes or large cardboard containers should not be included in the garbage chute – cardboard can be placed in the recycling bins on each residential level.

GREEN WASTE

Green waste is not typically generated from multi-unit dwellings other than from surrounding building landscaped areas and is removed by the designated maintenance contractor. In the event that green waste is produced i.e trimming of indoor or balcony plants then this may be disposed of via coordination with the building caretaker or cleaner. Very small quantities may be disposed of via the general waste stream.

BULKY GOODS

A room or caged area will be made available for the storage of discarded residential bulky items (e.g. whitegoods, furniture, etc.). This room should be located within close proximity of the garbage and recycling bin collection room and must have a minimum doorway width of 1.5m to allow for easy movement of large waste items in and out of the room.

These areas are crucial to prevent residents from illegally dumping bulky waste on the footpath outside Councils scheduled collection times. Regular illegal dumping can attract other dumped waste, generate litter, detract significantly from the quality and appearance of the development and reduce amenity of the street.

Residents will be required to liaise with building management regarding the transportation and disposal of bulky goods. Ideally, bulky waste should be collected on a regular schedule so that the storage area does not become overfull and so that residents know when to place items in there for collection. Councils may arrange for more frequent collections of bulky waste for MUDs, however collection frequencies vary among different local government areas.

Donations to charitable organisations should be encouraged. Clean, sound furniture and household goods etc. are highly sought after to provide for the disadvantaged. Donations can be arranged with the assistance of the building manager/waste caretaker.

ELECTRONIC WASTE

Electrical waste (e.g. fluorescent tubing, batteries, laptops etc.) can potentially contaminate soil and surrounding water bodies if not disposed correctly. These items must not be placed in standard garbage and recycling bins. Disposal or recycling of electronic waste will be organised with the assistance of the building caretaker. These items must not be placed in garbage or recycling bins due to safety and environmental factors. Residents and/or the building manager may choose to contact Council to find out about new/existing strategies for the disposal/collection of electronic waste.

CHEMICAL WASTE

Chemical wastes (e.g. cleaning chemicals, paints, oils solvents) pose detrimental effects to human health and the environment and should be disposed of to a suitable licensed disposal facility. No liquid wastes or wash down waters should be disposed of via the storm water drainage system. Household Chemical CleanOut events are held at various locations throughout NSW on specified dates throughout the year. Locations and dates are subject to change; hence it is recommended that the building caretaker confirm these details with their local Council.

ORGANIC WASTE AND COMPOSTING

Recycling organic waste, such as food scraps and garden materials, dramatically reduces the quantity of waste being diverted to land fill and thus reduces residents' ecological footprint. Compost material can also be returned to the soil as a rich fertilizer and improve plant growth and the overall health of surrounding vegetation. It is recommended that a space for composting and worm farming is made available for all residents in a communal facility or in small private courtyards. Composting facilities are to be sited on an unpaved area with soil depth of at least 300mm. Residents may also choose to purchase and install apartment style compost bin where practical and self-manage these systems (see *APPENDIX D.1* and *APPENDIX D.2*).

CLOTHING WASTE

Clothing is becoming an increasingly large waste stream for domestic dwellings. Unwanted clothing that is clean and undamaged can be donated to charities. Building management may choose to provide clothing donation bins for residents to donate their unwanted clothing. Building management can directly contact a charity to supply a donation bin or choose to provide their own nondenominational donation bin. Once a sufficient amount of clothing has been collected, the building management will be responsible for arranging the collection of donated items with the relevant charity.

COMMERCIAL AND RETAIL WASTE MANAGEMENT

The *Better Practice Guide for Waste Management and Recycling* has been referenced to calculate the total number of bins required for the retail and commercial areas. Calculations are based on generic figures; waste generation rates may differ according to the tenants' waste management practice.

ESTIMATED WASTE VOLUMES AND PROVISIONS

The following table shows the estimated volume (L) of garbage and recycling generated by the commercial and retail component of the development. A seven day operating week has been assumed.

Table 3: Calculated Waste Generation – Commercial, Restaurant, and Retail Tenancies

Type	NLA (m ²)	Garbage Generation Rate (L/100m ² /day)	Generated Garbage (L/week)	Recycling Generation Rate (L/100m ² /day)	Generated Recycling (L/week)
Commercial	111	10	77.7	10	77.7
Restaurant	1009	670	47322.1	135	9535.05
Retail	441	50	1543.5	50	1543.5
Reatil	402	50	1407	50	1407
TOTAL	1963		50350.3		12563.25
Collections & Equipment	Bin Size (L)		1100	Bin Size (L)	
	Garbage Bins Per Week		45.77	Recycling Bins Per Week	
	Collections per Week		3	Collections per Week	
	Total Garbage Bins Required		16	Total Recycling Bins Required	

It is the responsibility of the building manager to monitor the number of bins required for the development. As waste volumes may change according to the development's management, customer base and retail tenancy attitudes to waste disposal and recycling, bin numbers and sizes may need to be altered to suit the building operation. Seasonal peak periods i.e. public and school holidays should also be considered.

RETAIL WASTE MANAGEMENT

Retail tenants will be responsible for their own storage of garbage and recycling back of house (BOH) during daily operations. On completion of each trading day or as required, nominated retail staff or cleaners will transport their garbage and recycling to the Retail Waste Room and place garbage and recycling into the appropriate collection bins.

COMMERCIAL WASTE MANAGEMENT

Typically, bins for paper or general waste are positioned next to each workers desk or work station. Bins for general waste and recyclables are also located centrally in each office, generally in the kitchen area and printer room.

The cleaners circulate around the workplace after normal office hours and perform cleaning tasks. At this time the cleaners will empty the waste and recycling bins into bags which they transport around the offices in a cart which is also used to store cleaning products, spare bags, PPE and consumables.

The cleaners will be responsible for transporting of the waste and recycling to the Retail Waste Room and placing it into the appropriate bin.

RESTURANT WASTE MANAGEMENT

Restaurant tenants will be responsible for their own storage of garbage and recycling back of house (BOH) during daily operations. On completion of each trading day or as required, nominated retail staff or cleaners will transport their garbage and recycling to the Retail Waste Room and place garbage and recycling into the appropriate collection bins.

Food handling for food cooked or prepared, served and consumed on site will produce a typical waste composition of food scraps from plates, packaging waste and some plastics. Café and restaurant staff will be responsible for their own BOH waste management.

Cardboard is a major component of the waste generated by café and restaurant tenancies. All cardboard should be flattened (to save bin space), placed in and collected from bulk bins. Whilst cardboard is bulky, it is generally lightweight however it can be contaminated with food or liquid which makes it unsuitable for recycling.

To ensure the proper management and disposal of waste, tenants must be made aware of the following practices:

- All garbage should be bagged and garbage bins should be plastic lined;
- Bagging of recyclables is not permitted;
- All interim waste storage is located BOH during operations;
- Individual recycling programs are recommended for retailers to ensure commingled recycling is correctly separated;
- Any food and beverage tenant will make arrangements for storing used and unused cooking oil in a bunded storage area;
- The operator will organise grease interceptor trap servicing;
- A suitable storage area needs to be provided and effectively bunded for chemicals, pesticides and cleaning products;
- Dry basket arrestors need to be provided to the floor wastes in the food preparation and waste storage areas; and
- All flattened cardboard will be collected and removed to the waste room recycling MGB

WASHROOM

Washroom facilities should be supplied with collection bins for paper towels (if used). Sanitary bins for female restroom facilities must also be arranged with an appropriate contractor.

WASTE OILS

Consideration should be given to the use of cooking oil collection systems. A single service provider may be used to reduce the amount of commercial traffic into the loading bay or around the precinct area. This should be measured against bulk delivery of oils where the same vehicle is used to remove containers of waste cooking oils (see APPENDIX D.3 for Typical Cooking Oil Collection System)

OTHER WASTE STREAMS

Tenants are required make arrangements for the disposal and recycling of specialised waste (toner cartridges, batteries, etc.). Disposal of hard, electronic, liquid waste and any detox (paint/chemicals) can be organised with the assistance of the building management/cleaners.

MOVEMENT AND TRANSPORTATION OF BINS

The building manager is responsible for the transportation of bins from their designated operational locations to their respective collection area when full or prior to scheduled collection times, and returning them once emptied to resume operational use.

Transfer of waste and all bin movements require minimal manual handling; the operator must assess manual handling risks and provide any relevant documentation to building management.

If required the developer should contact a bin-tug, trailer or tractor consultant to provide equipment recommendations. Examples of motorised bin moving equipment can be found in APPENDIX B.4 and APPENDIX B.5.

COLLECTION OF WASTE

RESIDENTIAL

Council will be engaged to collect the residential garbage and recycling in accordance with council's collection schedule.

Prior to collection day, the building manager will be responsible for ensuring that the recycling bins on each residential level have been decanted into the recycling 660L MGBs located in the Bin Holding Room.

On collection days, the building manager will be responsible for moving the bins from the Waste Discharge Rooms on Basement Level 1 to the ground level collection area via the bin hoist. Service bins will remain under the chutes.

The waste collection vehicle will enter the site from Castlereagh Rd and Park in the designated loading bay. Servicing will occur directly from the Bin Holding Room directly adjacent to the loading bay via a collect and return arrangement.

After servicing has been completed. It will be the building manager's responsibility to ensure that the empty bins are returned to their designated operational location.

RETAIL AND COMMERCIAL

A private contractor will be engaged to collect the garbage and recycling bin for the retail and commercial component of the site to an agreed schedule.

The waste collection vehicle will enter the site from Castlereagh Rd and Park in the designated loading bay. Servicing will occur directly from the Retail and Commercial Waste Room directly adjacent to the loading bay via a collect and return arrangement.

COLLECTION AREA

It is Elephant Foot's understanding that the collection areas have been reviewed by a traffic consultant to confirm the swept paths for waste collections, access and egress, internal manoeuvring to assume parked position for loading and to exit, load requirements as well as collection vehicle. It must be ensured that the collection vehicle (and other trucks if required) can enter and exit the building in a forward direction. The final number of truck movements will depend on management of waste contract.

INSTALLATION EQUIPMENT AND DESIGN

EQUIPMENT SUMMARY

Table 4: Equipment Summary

Component	Part	Qty	Notes
Chutes	Please refer to supplier's information	2	(See APPENDIX C for Typical Chute Section)
Equipment A	Garbage – East Tower 2-bin 660L MGB Linear Track System with Compactor	1	(See APPENDIX C.2 for Typical Linear System)
	Garbage –West Tower 3-bin 660L MGB Linear Track System with Compactor	1	(See APPENDIX C.3 for Typical Linear System)
Equipment B	Bin Lifter suitable for 240L MGBs	1	(See APPENDIX C.4 for Typical Bin Lifter)
	Suitable Bin Moving Equipment	1	(See 0 for Typical Bin Mover)

WASTE ROOM AREAS

Access to waste discharge rooms should be provided to the building manager **only**. Under no circumstances should access be provided to any residents, or waste collection staff. The immediate space around the chute discharge needs to be free of service pipes and other overhead obstacles.

It is assumed that the café, restaurant, childcare, SOHO offices and commercial (office) tenancies will share the bins located in the Retail and Commercial Waste Room.

During operation, any requirement for increasing storage capacity can be done by increasing the frequency of collections for all waste.

The areas allocated for waste storage and collection areas are detailed in Table 5 below. The areas provided are estimates only. Final areas will depend upon room and bin layouts.

Table 5: Waste Room Areas

Level	Waste Room Type	Equipment	Recommended Area (m ²)	Layout Ref
G	Waste Discharge Room – East Tower	<i>Minimum</i> 1x 2-bin linear with compactor 1x 660L MGB (service bin)	10	APPENDIX A.1
G	Waste Discharge Room – West Tower	<i>Minimum</i> 1x 3-bin linear with compactor 1x 660L MGB (service bin)	10	APPENDIX A.1
G	Residential Bin Holding Room (Collection Area)	12x 660L MGBs (garbage) 24x 660L MGBs (recycling) Bin Lifter for 240L MGBs	75	APPENDIX A.1
G	Bulky Goods Waste Storage Room		61	APPENDIX A.1
G	Retail & Commercial Waste Room	16x 1100L MGBs (garbage) 4x 1100L MGBs (recycling)	60	APPENDIX A.1

GARBAGE ROOMS

CONSTRUCTION REQUIREMENTS

The garbage room will be required to contain the following facilities to minimise odours, deter vermin, protect surrounding areas, and make it a user-friendly and safe area:

- Waste room floor to be sealed with a two pack epoxy;
- Waste room walls and floor surface is flat and even;
- All corners coved and sealed 100mm up, this is to eliminate build-up of dirt;
- For residential: a hot and cold water facility with mixing facility and hose cock must be provided for washing the bins;
- For retail/commercial: a cold water facility with hose cock must be provided for washing the bins;
- Any waste water discharge from bin washing must be drained to sewer in accordance with the relevant water board. (Sydney water);
- Tap height of 1.6m;
- Storm water access preventatives (grate);
- All walls painted with light colour and washable paint;
- Equipment electric outlets to be installed 1700mm above floor levels;
- The room must be mechanically ventilated;
- Light switch installed at height of 1.6m;
- Waste rooms must be well lit (sensor lighting recommended);
- Optional automatic odour and pest control system installed to eliminate all pest types and assist with odour reduction – this process generally takes place at building handover – building management make the decision to install;
- If 660l or 1100l bins are utilised, 2 x 820mm (minimum) door leafs must be used;
- All personnel doors are hinged, lockable and self-closing;
- Waste collection area must hold all bins – bin movements should be with ease of access;
- Conform to the building code of Australia, Australian standards and local laws; and
- Childproofing and public/operator safety shall be assessed and ensured

SIGNAGE

The building manager/caretaker is responsible for waste room signage including safety signage (see *APPENDIX B.2*). Appropriate signage must be prominently displayed on doors, walls and above all bins, clearly stating what type of waste or recyclables is to be placed in the bin underneath.

All chute doors on all residential levels will be labelled with signs directing chute operations and use of chute door.

VENTILATION

Waste and recycling rooms must have their own exhaust ventilation system either;

- Mechanically - exhausting at a rate of 5L/m² floor area, with a minimum rate of 100L/s minimum; or
- Naturally - permanent, unobstructed, and opening direct to the external air, not less than one-twentieth (1/20) of the floor area

Mechanical exhaust systems shall comply with AS1668 and not cause any inconvenience, noise or odour problem.

USEFUL CONTACTS

Elephants Foot Recycling Solutions does not warrant or make representation for goods or services provided by suppliers.

Liverpool City Council Customer Service

Phone: 1300 36 21 70

Email: lcc@liverpool.nsw.gov.au

SULO MGB (MGB, Public Place Bins, Tugs and Bin Hitches)

Phone: 1300 364 388

CLOSED LOOP (Organic Dehydrator)=

Phone: 02 9339 9801

ELECTRODRIVE (Bin Mover)

Phone: 1800 333 002

Email: sales@electrodrive.com.au

RUD (Public Place Bins, Recycling Bins)

Phone: 07 3712 8000

Email: Info@rud.com.au

CAPITAL CITY WASTE SERVICES (Private Waste Services Provider)

Phone: 02 9359 9999

REMONDIS (Private Waste Services Provider)

Phone: 13 73 73

SITA ENVIRONMENTAL (Private Waste Services Provider)

Phone: 13 13 35

NATIONAL ASSOCIATION OF CHARITABLE RECYCLING ORGANISATIONS INC.
(NACRO)

Phone: 03 9429 9884

Email: information@nacro.org.au

PURIFYING SOLUTIONS (Odour Control)

Phone: 1300 636 877

Email: sales@purifyingsolutions.com.au

MOVEXX (Bin Movers)

Phone: 1300 763 444

AUSCOL (Recycling Oils & Animal Fats)

Phone: 1800 629 476

ELEPHANTS FOOT RECYCLING SOLUTIONS (Chutes, Compactors and eDiverter Systems)

44 – 46 Gibson Avenue

Padstow NSW 2211

Free call: 1800 025 073

Email: info@elephantsfoot.com.au

KOMPACT EQUIPMENT (Waste Handling Equipment Sales, Servicing and Maintenance)

1/81 Governor Macquarie Drive

Chipping Norton NSW 2170

Free call: 1800 566 722


Email:

info@kompactequipment.com.au

APPENDICES


APPENDIX A ARCHITECTURAL DRAWING EXCERPTS

APPENDIX A.1 SITE PLAN




Source: Allen Jack & Cottier Architects, Memorial Ave Liverpool, Site Plan, DA1001 Issue 1 –Jan2019

APPENDIX A.2 GROUND LEVEL – WASTE FACILITIES AND COLLECTION AREA



Source: Allen Jack & Cottier Architects, Memorial Ave Liverpool, Ground Floor Plan, DA2000 issue 1 –Feb2019

APPENDIX A.3 TYPICAL RESIDENTIAL LEVEL



Source: Allen Jack & Cottier Architects, Memorial Ave Liverpool, Level 3 Plan DA2103 Rev 1 –Feb2019

APPENDIX B PRIMARY WASTE MANAGEMENT PROVISIONS**APPENDIX B.1 LIVERPOOL BIN SPECIFICATIONS**

Bin Size	Dimensions
660 Litres	1070 x 910 x 635mm
240 Litres	1180 x 740 x 570mm

Source: Liverpool Development Control Plan 2008

APPENDIX B.2 SIGNAGE FOR WASTE & RECYCLING BINS


WASTE SIGNS

Signs for garbage, recycling and organics bins should comply with the standard signs promoted by the Department of Environment and Heritage.

Example wall posters




Example bin lid stickers



SAFETY SIGNS

The design and use of safety signs for waste rooms and enclosures should comply with AS1319 Safety Signs for Occupational Environment. Safety signs should be used to regulate and control safety behaviour, warn of hazards and provide emergency information, including fire protection information. Below are some examples. Each development will need to decide which signs are relevant for its set of circumstances and service provided.

Examples of Australian Standards:



Australian Standards are available from the SAI Global Limited website (www.saiglobal.com).

SOURCE: Department of Environment and Climate Change NSW 2008, Better Practice Guide for Waste Management in Multi-Unit Dwellings


APPENDIX B.3 TYPICAL COLLECTION VEHICLE INFORMATION

Collection vehicles

Waste collection vehicles may be side loading, rear-end loading, front-end loading or crane trucks. The size of vehicle varies according to the collection service. Thus it is impossible to specify what constitutes the definitive garbage vehicle. Developers should consult the local council and/or relevant contractors regarding the type of vehicle used in that area.

The following characteristics represent the typical collection vehicle, however, these are only for guidance.

It may be possible to engage a collection service provider to use smaller collection vehicles to service developments with narrow roadways and laneways, or for on-site collections. However, as the availability of smaller vehicles to make services varies between councils and private contractors, wherever possible the development should be designed to accommodate vehicles of a similar size to that reported below.




Rear loading collection vehicle

Rear loading collection vehicle	
Length overall	10.24m
Width overall	2.5m
Operational height	3.5m
Travel height	3.5m
Weight (vehicle only)	12.4 tonnes
Weight (payload)	9.5 tonnes
Turning circle	18.0m

This is commonly used for domestic garbage and recycling collections from MUDs. It can be used to collect waste stored in MGBs or bulk bins, particularly where bins are not presented on the kerbside.


Side-loading collection vehicle



Side-loading collection vehicle	
Length overall	9.64m
Front overhang	1.51m
Wheelbase	5.20m
Rear overhang	2.93m
Turning circle kerb to kerb	17.86m
Turning circle wall to wall	20.56m
Front of vehicle to collection arm	3.8m
Maximum reach of side arm	3.0m
Travel height	3.63m
Clearance height for loading	3.9m

This is the most commonly used vehicle for domestic garbage and recycling collections. It is only suitable for collecting MGBs up to 360 litres in size.

Front-lift loading collection vehicle



Front-lift loading collection vehicle	
Length overall	10.52m
Front overhang	1.51m
Wheelbase	5.84m
Rear overhang	3.17m
Turning circle kerb to kerb	22.10m
Turning circle wall to wall	23.66m
Travel height	3.82m
Clearance height for loading	6.1m

This is mainly used for collecting commercial and industrial waste, and is only suitable for bulk bins with front lift pockets (not MGBs).

SOURCE: Department of Environment and Climate Change NSW 2008, *Better Practice Guide for Waste Management in Multi-Unit Dwellings*

APPENDIX B.4 TYPICAL MOTORISED BIN TUG



Typical applications:

- Move trolleys, waste bin trailers and 660/1100L bins up and down a ramp incline.
- Quiet, smooth operation with zero emissions and simple to use, no driver's licence required
- Suitable for:
 - High rise building & apartment basements
 - Large factories & warehouse with sloped ground
 - Caravan parks & other large outdoor areas


Features:

- 1 tonne tow capacity of inclines up to 8 degrees
- 500kg tow capacity if inclines up to 14 degrees
- CE Compliant
- 4.5 km/h max speed
- 2 x 80amp batteries – includes charger
- Powerful transaxle
- Hitch to suit 660L bins

Safety Features:

- Intuitive paddle lever control
- Stops and repels the unit if activated when reversing.
- Site assessment recommended to assess ramp incline steepness (*See Useful Contacts*)


APPENDIX B.5 TYPICAL SEATED BIN MOVER



		UNIT M.	BULL 2	BULL 4
Manufacturer	DEC			
Model	BULL			
Platform loading cap.	Nominal capacity	kg	-----	-----
Pull capacity	Pull nominal capacity	kg	2000	4000
Power type	Electric - endothermic		electric	electric
Control type	Standing / seated thiller / steer		seated / steer	seated / steer
Tyres	Pn=pneum. Se=superelastic		Pn	Pn
Wheels	N. front/rear - x drive	n.	1/2X	1/2X
Platform dimensions	L x B (lengh x width)	mm	-----	-----
Platform hight	h6 = unload clearence	mm	-----	-----
Overall dimensions	L = lenght	mm	1500	1600
	B = width	mm	900	930
	h1 = foot leve	mm	1820	1960
	h3 = Seat height	mm	310	340
	h4 = Steer height	mm	1250	1330
Turning radius	R1 = front min. external	mm	1400	1500
	R2 = rear min. external	mm	1000	1000
	R3 = front min. internal	mm	400	400
Aisle width	A = 180° turn	mm	2200	2300
Tow hook height	s = center from ground	mm	220-350-490	240-380-520

APPENDIX C INSTALLATION EQUIPMENT AND WASTE ROOM LAYOUTS

APPENDIX C.1 TYPICAL SINGLE WASTE CHUTE SPECIFICATIONS





Waste chutes are supplied per the following specifications:

- either 510mm or 610mm (for 20+ levels) galvanised steel or recycled LLDPE polyethylene plastic;
- galvanised steel chute hoppers are wrapped with 50mm poly-wool R1.3 noise insulation foil to assist in noise reduction (or equivalent);
- penetrations on each building level at vertically perpendicular points with minimum penetration dimensions of either 600x600/700x700mm (square) or 650/750mm diameter (round) are required to accommodate the chute installation;
- a wash down system and vent should also be included as part of the chute system;
- council and supplier require that all chutes are installed without offsets to achieve best practise operationally for the building; and
- two hour fire-rated (AS1530.4-2005) stainless steel refuse chute doors at each service level. All doors are to be fitted with a self-closing mechanism to meet BSA fire standards.

NOTE: Chute doors are installed after walls rendered, painted or when required. Information stickers will be placed on each chute door at each residential level.

APPENDIX C.2 TYPICAL 2-BIN LINEAR TRACK SYSTEM FOR 660L MGBS





© Copyright 2013 Ark Design Studio Reproduction of the whole or part copyright. The information, ideas and concepts contained in this document are confidential and/or prohibited from disclosing such information, ideas and concepts to any person without the prior written consent of the copyright holder.		DATE: 21.10.13	TITLE: 2 BIN LINEAR TRACK & COMPACTOR w/- 660L BINS
CAUTION The stated scale of this plan may have been altered by copying or other means. Accordingly the scale should be verified prior to using the plan to derive measurements.		SCALE AS SHOWN	
DRAWN: CK A4 		DRAWING No: DM009-2BIN660LINCOM	REV -

OPERATIONAL WASTE MANAGEMENT PLAN

APPENDIX C.3 TYPICAL 3-BIN LINEAR TRACK SYSTEM FOR 660L MGBS

3- 660 L BIN LINEAR



 <p>ELEPHANTS FOOT recycling solutions</p> <p>45-45 Office Ave. Parkville 1500 2211 403-221-1500 info@elephantsfoot.com Fax 403-221-1501</p>		<p>Elephants Foot Standard</p>	
<p>Copyright 2014 Elephants Foot Recycling Solutions. All rights reserved. Reproduction of the whole or part of the document constitutes an infringement of copyright. The information, ideas and concepts contained in the document are confidential. The recipient of this document shall not disclose such information, ideas and concepts to any person without the prior written consent of the copyright holder.</p> <p>DO NOT SCALE FROM DRAWINGS</p>		<p>MINIMUM REQUIREMENT FOR 3X660L LINEAR</p>	
<p>Scale</p> <p>1:100</p>	<p>Sheet Size</p> <p>A3</p>	<p>Project Name</p> <p>3X660L LINEAR</p>	<p>Project Number</p> <p>EFN-BTD-P01</p>
		<p>Revision</p> <p>A</p>	

APPENDIX C.4 TYPICAL BIN LIFTER SUITABLE FOR 240L MGBS



MULTI BIN LIFTER



The multi bin lifter is designed to safely empty wheelie bins into large dumpsters and compactors.


The multi bin lifter has been designed to operate using 240,660 & 1100 litre wheelie bins.

With easy operating push button instructions, the bin lifter is complemented by a safety cage.

This unit can be built portable or static. It is well suited to be used to tip mobile bins into any skip.

A yearly maintenance can be purchased for the binlifter.

FEATURES	MULTI BINLIFTER
BIN COMPATIBILITY	240, 660 & 1100 litre bins
OPERATION METHOD	Automatic
HYDRAULIC	yes
DIMENSIONS	W1745mm x L3050mm
SAFETY	Safety cage & control box
EMERGENCY STOP	yes
TIPPING HEIGHT	1376mm variable
CLEARANCE	3700mm variable
SUITABILITY IN TIPPING INTO	bins, dumpsters and compactors
POWER	3 phase, 20 amp, 5 pin
CAN IT BE CUSTOMISED	yes
WEIGHING & DATA CAPTURE	no



APPENDIX D SECONDARY WASTE MANAGEMENT PROVISIONS

APPENDIX D.1 TYPICAL APARTMENT STYLE COMPOST BINS



Apartment Style Compost bin – available from hardware stores

Suitable for:

- Vegetables
- Coffee grounds and filters
- Tea and tea bags
- Crushed eggshells (but not eggs)
- Nutshells
- Houseplants
- Leaves
- Cardboard rolls, cereal
- Boxes, brown paper bags
- Clean paper
- Shredded newspaper
- Fireplace ashes
- Wood chips, sawdust,
- Toothpicks, burnt matches
- Cotton and wool rags
- Dryer and vacuum cleaner lint
- Hair and fur
- Hay and straw

APPENDIX D.2 ELECTRIC ORGANIC COMPOST BIN



Product Specifications

Decomposition Method	Fermentation by microorganisms
Decomposition Capacity	2 metric tonnes per year* (4 kg per day*)
Rating	220–240 V 50/60 Hz – 1.1 A
Decomposition Time	24 hrs
Operating Temperature	0C and 40C.**
Deodorisation Method	Nano-Filter system
Maximum Power	210 W
Power Usage	Average 1 kwh per day
Weight	21 kgs
External Dimensions	w 400 mm d 400 mm h 780 mm


* Food Waste Handling Capacity – based on an optimal operating environment.

** Ambient temperature range of area where unit may be installed.

SOURCE: Closed Loop Domestic Composter – See Useful Contacts

<http://www.closedloop.com.au/domestic-composter>


APPENDIX D.3 TYPICAL COOKING OIL CONTAINERS




A GrainCorp business

[Home](#)
[About](#)
[Services](#)
[Our Parent Company](#)
[Contact](#)

The RIGHT WAY for Cooking Oil Collection Systems




Drums 205L



Pour in Bulk Tank


[View Brochure](#)




Oil Kaddy System

[View Brochure](#)

- Collection Service
- Collection Systems
- Recycling & Environment
- Safety
- Fresh Oil (WA Only)



Eco Systems



Direct-Connect to Fryer

APPENDIX D.4 TYPICAL BACK OF HOUSE BINS FOR RETAIL/COMMERCIAL OPERATIONS

