30 May 2022

610.30735-L01-v1.0-20220530.docx

Goodman Property Services (Australia) Pty Ltd 1-11 Hayes Road Rosebery NSW 2108

Requirement to Update Air Quality Impact Assessment

Attention: Stephanie Partridge

Dear Stephanie

Oakdale West Estate
Precincts 3C and 5
Requirement to Update Air Quality Impact Assessment

1 Objective

A building Development Approval (DA) for warehouses at Precinct 3C and Precinct 5 within the Oakdale West Estate (OWE) is being submitted to Penrith City Council for assessment. Precincts 3C and 5 are largely consistent with the building footprint and traffic generation as approved under the current Oakdale West Masterplan approval (SSD 7348 – as amended), with minor changes.

The objective of this letter report is to assess whether a revision of the Air Quality Impact Assessment (AQIA) prepared by SLR Consulting (SLR) in 2017 for the OWE is required to address the construction and operation of Precincts 3C and 5.

2 Background

The AQIA prepared by SLR for the OWE, dated 23 March 2017 (610.15617-R01-v1.1), assessed the potential air quality impacts associated with the construction and operational phases of all five precincts within the OWE.

Air quality impacts associated with the proposed construction activities were assessed using a qualitative risk-based approach. It was concluded that air quality impacts during construction of the OWE Project could be adequately managed using best practice management and mitigation measures. The risk of any residual impacts after the implementation of mitigation measures was concluded to be low.

For the operational phase, atmospheric dispersion modelling was used to assess potential air quality impacts at the nearest sensitive receptors due to air emissions from vehicular traffic associated with each of the precincts within the OWE. The results of the modelling were presented as:

- the incremental impacts associated with traffic emissions from all five precincts; and
- cumulative impacts of emissions from the OWE and background concentrations.


It was concluded from the modelling results that air emissions from the proposed operational activities (vehicle movements) at the OWE would comply with all relevant ambient air quality criteria at all representative surrounding sensitive receptors. A summary of the pollutant concentrations predicted at the most impacted sensitive receptor due to emissions from the OWE is provided in **Table 1**. The road network included in the modelling presented in the AQIA is shown in **Figure 1**.

Table 1 Summary of AQIA Dispersion Modelling Results for OWE at Most Impacted Sensitive Receptor

Pollutant	Averaging Period	Criteria (μg/m³)	Incremental Impact of Emissions from OWE (µg/m³)	Cumulative Impact of Emissions from OWE and Regional Background Concentrations (µg/m³)	Contribution of OWE to total Predicted Cumulative Concentrations
TSP	Annual	90	13.8	44.2	31%
PM ₁₀	24-hour	50	22.9	38.9	59%
	Annual	25	4.6	19.8	23%
PM _{2.5}	24-hour	25	6.0	NA ^a	-
	Annual	8	1.2	NA ^a	-
NO ₂	1-hour	246	158.8 ^b	91.6 ^b	-
	Annual	62	6.1 ^b	12.7 ^b	-

^a No background PM_{2.5} data were available from the St Marys Air Quality Monitoring Station.

Figure 1 Oakdale West Estate – Roads Modelled in the AQIA




Source: SBA Architects, SSDA Estate Masterplan, 18 April 2018 (yellow marked line indicates modelled roads.

^b The incremental concentrations represent the predicted <u>NOx concentrations</u>, while the cumulative concentrations represent the NO₂ concentrations, calculated using the Ozone Limiting Method (OLM).

The maximum impacts due to air emissions from the OWE were predicted to occur at receptors R8 and R9, which are located to the west and south of the OWE respectively, as shown in **Figure 2**.

Figure 2 Locations of Identified Sensitive Receptors




3 Modifications to the OWE Masterplan

Since the completion of the AQIA in March 2017, minor modifications to the OWE Masterplan have been proposed and approved. The updated masterplan is shown in **Figure 3**. Precincts 3C and 5 are largely consistent with the building footprint and traffic generation as approved under current Oakdale West Masterplan approval (SSD 7348 – as amended), with minor changes.

A comparison of **Figure 1** and **Figure 3** shows that the revisions to the masterplan have slightly modified the road networks considered in the AQIA modelling study. The changes to the road network have occurred in the western half of the OWE and include a slightly longer Estate Road 3.

Figure 3 Oakdale West Estate – Updated Masterplan



Date: 30 May 2022

SLR Ref: 610.30735-L01-v1.0-20220530.docx

4 Precincts 3C and 5 - Construction

The AQIA concluded that air quality impacts during construction of the OWE could be adequately managed using best practice mitigation and management measures. The risk of any residual impacts after the implementation of mitigation measures was concluded to be *low*.

As a result of the proposed modifications to the OWE Masterplan (see **Section 3**), it is concluded that the magnitude of construction impacts is unlikely to change, and hence the residual risk of dust emissions during construction of Precincts 3C and 5 remains *low*. The recommended management and mitigation measures during construction of the OWE are reproduced in **Table 2**.

Table 2 Site-Specific Management Measures – OWE

1	Communications			
1.1	Develop and implement a stakeholder communications plan that includes community engagement before work commences on site.	Н		
1.2	Display the name and contact details of person(s) accountable for air quality and dust issues on the site boundary. This may be the environment manager/engineer or the site manager.			
1.3	Display the head or regional office contact information.			
1.4	Develop and implement a Dust Management Plan (DMP), which may include measures to control other emissions, approved by the Local Authority.	Н		
2	Site Management			
2.1	Record all dust and air quality complaints, identify cause(s), take appropriate measures to reduce emissions in a timely manner, and record the measures taken.			
2.2	Make the complaints log available to the Local Authority when requested.	Н		
2.3	Record any exceptional incidents that cause dust and/or air emissions, either on- or offsite, and the action taken to resolve the situation in the log book.	Н		
3	Monitoring			
3.1	Perform daily on-site and off-site inspections where receptors (including roads) are nearby, to monitor dust, record inspection results, and make the log available to the Local Authority when requested. This should include regular dust soiling checks of surfaces such as street furniture, cars and window sills within 100 m of the site boundary.			
3.2	Carry out regular site inspections to monitor compliance with the DMP, record inspection results, and make an inspection log available to the Local Authority when requested.			
3.3	Increase the frequency of site inspections by the person accountable for air quality and dust issues on site when activities with a high potential to produce dust are being carried out and during prolonged dry or windy conditions.			
3.4	Agree dust deposition, dust flux, or real-time PM10 continuous monitoring locations with the Local Authority. Where possible commence baseline monitoring at least three months before work commences on site or, if it a large site, before work on a phase commences. Further guidance is provided by IAQM on monitoring during demolition, earthworks and construction.			
4	Preparing and Maintaining the Site			
4.1	Plan site layout so that machinery and dust causing activities are located away from receptors, as far as is possible.	Н		
4.2	Erect solid screens or barriers around dusty activities or the site boundary that they are at least as high as any stockpiles on site.			
4.3	Fully enclose site or specific operations where there is a high potential for dust production and the site is active for an extensive period.			
4.4	Avoid site runoff of water or mud.	Н		
4.5	Keep site fencing, barriers and scaffolding clean using wet methods.	Н		
4.6	Remove materials that have a potential to produce dust from site as soon as possible, unless being re-used on site. If they are being re-used on-site cover as described below.	Н		

5.2 Ensure all vehicles switch of 5.3 Avoid the use of diesel or per practicable. 5.4 Impose and signpost a maximum work areas. 5.5 Produce a Construction Logical Science of Construction Log	comply with relevant vehicle emission standards, where applicable. If engines when stationary - no idling vehicles. Petrol powered generators and use mains electricity or battery powered equipment where Imum-speed-limit of 25 km/hr on surfaced and 15 km/hr on unsurfaced haul roads and Initiation is a sustainable delivery of goods and materials. In the supports and encourages sustainable travel (public transport, cycling, walking, and carraction, e.g. suitable local exhaust ventilation systems. In the site for effective dust/particulate matter suppression/ mitigation, using non-side and appropriate. In the veryors and covered skips. In conveyors, loading shovels, hoppers and other loading or handling equipment and use quipment wherever appropriate. In a varilable on site to clean any dry spillages, and clean up spillages as soon as reasonably	H H D H H H H		
5.2 Ensure all vehicles switch of 5.3 Avoid the use of diesel or per practicable. 5.4 Impose and signpost a maxi work areas. 5.5 Produce a Construction Logical Society of the sharing. 6.6 Operations 6.1 Only use cutting, grinding of as water sprays or local extraction of the sharing of the	ff engines when stationary - no idling vehicles. etrol powered generators and use mains electricity or battery powered equipment where imum-speed-limit of 25 km/hr on surfaced and 15 km/hr on unsurfaced haul roads and istics Plan to manage the sustainable delivery of goods and materials. at supports and encourages sustainable travel (public transport, cycling, walking, and car- ar sawing equipment fitted or in conjunction with suitable dust suppression techniques such fraction, e.g. suitable local exhaust ventilation systems. supply on the site for effective dust/particulate matter suppression/ mitigation, using non- sole and appropriate. noveyors and covered skips. conveyors, loading shovels, hoppers and other loading or handling equipment and use quipment wherever appropriate.	H H D H H H		
5.3 Avoid the use of diesel or per practicable. 5.4 Impose and signpost a maxi work areas. 5.5 Produce a Construction Loging of the sharing. 6.0 Operations 6.1 Only use cutting, grinding of the sharing. 6.2 Ensure an adequate water sharing water sprays or local extractions. 6.3 Use enclosed chutes and confine water sprays on such extractions. 6.5 Ensure equipment is readily practicable after the event of the water sharing. 7 Waste Management 7.1 Avoid bonfires and burning. 8 Demolition 8.1 Soft strip inside buildings be provide a screen against dues. 8.2 Ensure effective water supphoses attached to equipment suppression systems, manual.	etrol powered generators and use mains electricity or battery powered equipment where Imum-speed-limit of 25 km/hr on surfaced and 15 km/hr on unsurfaced haul roads and istics Plan to manage the sustainable delivery of goods and materials. In supports and encourages sustainable travel (public transport, cycling, walking, and car- are sawing equipment fitted or in conjunction with suitable dust suppression techniques such fraction, e.g. suitable local exhaust ventilation systems. Isoupply on the site for effective dust/particulate matter suppression/ mitigation, using non- sole and appropriate. In conveyors, loading shovels, hoppers and other loading or handling equipment and use equipment wherever appropriate. In available on site to clean any dry spillages, and clean up spillages as soon as reasonably	H D H H		
practicable. 5.4 Impose and signpost a maxi work areas. 5.5 Produce a Construction Loging 5.6 Implement a Travel Plan that sharing). 6 Operations 6.1 Only use cutting, grinding on as water sprays or local extremation of the summary of the sum	imum-speed-limit of 25 km/hr on surfaced and 15 km/hr on unsurfaced haul roads and istics Plan to manage the sustainable delivery of goods and materials. It supports and encourages sustainable travel (public transport, cycling, walking, and carray sawing equipment fitted or in conjunction with suitable dust suppression techniques such raction, e.g. suitable local exhaust ventilation systems. Supply on the site for effective dust/particulate matter suppression/ mitigation, using non-ole and appropriate. In conveyors, loading shovels, hoppers and other loading or handling equipment and use quipment wherever appropriate. In available on site to clean any dry spillages, and clean up spillages as soon as reasonably	D H D H H H H		
work areas. 5.5 Produce a Construction Logical Section 1. Implement a Travel Plan that sharing). 6 Operations 6.1 Only use cutting, grinding on as water sprays or local extractions. 6.2 Ensure an adequate water spotable water where possible water where possible water where possible water sprays on such extractions. 6.3 Use enclosed chutes and confine water sprays on such extractions. 6.4 Minimise drop heights from fine water sprays on such extractions. 6.5 Ensure equipment is readily practicable after the event of waster water supported a screen against dustable after the extraction. 7 Waste Management 7.1 Avoid bonfires and burning 8 Demolition 8.1 Soft strip inside buildings be provide a screen against dustable after the equipment suppression systems, manual suppression systems.	istics Plan to manage the sustainable delivery of goods and materials. at supports and encourages sustainable travel (public transport, cycling, walking, and cararsawing equipment fitted or in conjunction with suitable dust suppression techniques such raction, e.g. suitable local exhaust ventilation systems. supply on the site for effective dust/particulate matter suppression/ mitigation, using non-ole and appropriate. Inveyors and covered skips. In conveyors, loading shovels, hoppers and other loading or handling equipment and use quipment wherever appropriate. In available on site to clean any dry spillages, and clean up spillages as soon as reasonably	H D H		
5.6 Implement a Travel Plan that sharing). 6 Operations 6.1 Only use cutting, grinding or as water sprays or local extrement of the sharing	r sawing equipment fitted or in conjunction with suitable dust suppression techniques such raction, e.g. suitable local exhaust ventilation systems. supply on the site for effective dust/particulate matter suppression/ mitigation, using non-ole and appropriate. noveyors and covered skips. a conveyors, loading shovels, hoppers and other loading or handling equipment and use quipment wherever appropriate. a vavailable on site to clean any dry spillages, and clean up spillages as soon as reasonably	D H H		
sharing). Operations Only use cutting, grinding of as water sprays or local extractions Ensure an adequate water spotable water where possib Use enclosed chutes and co Minimise drop heights from fine water sprays on such extractions Ensure equipment is readily practicable after the event of water water sprays Waste Management Avoid bonfires and burning Demolition Soft strip inside buildings be provide a screen against dus Ensure effective water supp hoses attached to equipment suppression systems, manual	r sawing equipment fitted or in conjunction with suitable dust suppression techniques such raction, e.g. suitable local exhaust ventilation systems. supply on the site for effective dust/particulate matter suppression/ mitigation, using non-sle and appropriate. noveyors and covered skips. conveyors, loading shovels, hoppers and other loading or handling equipment and use quipment wherever appropriate.	Н		
6.1 Only use cutting, grinding of as water sprays or local extr. 6.2 Ensure an adequate water spotable water where possib. 6.3 Use enclosed chutes and co. 6.4 Minimise drop heights from fine water sprays on such ed. 6.5 Ensure equipment is readily practicable after the event of the water sprays. 7 Waste Management. 7.1 Avoid bonfires and burning. 8 Demolition. 8.1 Soft strip inside buildings be provide a screen against dus. 8.2 Ensure effective water supp hoses attached to equipment suppression systems, manual.	raction, e.g. suitable local exhaust ventilation systems. supply on the site for effective dust/particulate matter suppression/ mitigation, using non- sole and appropriate. inveyors and covered skips. It conveyors, loading shovels, hoppers and other loading or handling equipment and use equipment wherever appropriate. It available on site to clean any dry spillages, and clean up spillages as soon as reasonably	Н		
as water sprays or local extr 6.2 Ensure an adequate water's potable water where possib 6.3 Use enclosed chutes and co 6.4 Minimise drop heights from fine water sprays on such ecceptation 6.5 Ensure equipment is readily practicable after the event of the water sprays on such ecceptation 7 Waste Management 7.1 Avoid bonfires and burning 8 Demolition 8.1 Soft strip inside buildings be provide a screen against dus 8.2 Ensure effective water supp hoses attached to equipment suppression systems, manual	raction, e.g. suitable local exhaust ventilation systems. supply on the site for effective dust/particulate matter suppression/ mitigation, using non- sole and appropriate. inveyors and covered skips. It conveyors, loading shovels, hoppers and other loading or handling equipment and use equipment wherever appropriate. It available on site to clean any dry spillages, and clean up spillages as soon as reasonably	Н		
potable water where possible 6.3 Use enclosed chutes and co 6.4 Minimise drop heights from fine water sprays on such ed 6.5 Ensure equipment is readily practicable after the event of 7 Waste Management 7.1 Avoid bonfires and burning 8 Demolition 8.1 Soft strip inside buildings be provide a screen against dus 8.2 Ensure effective water supp hoses attached to equipment suppression systems, manual	ole and appropriate. Inveyors and covered skips. In conveyors, loading shovels, hoppers and other loading or handling equipment and use quipment wherever appropriate. In available on site to clean any dry spillages, and clean up spillages as soon as reasonably	Н		
6.4 Minimise drop heights from fine water sprays on such ed 6.5 Ensure equipment is readily practicable after the event of 7 Waste Management 7.1 Avoid bonfires and burning 8 Demolition 8.1 Soft strip inside buildings be provide a screen against dus 8.2 Ensure effective water supp hoses attached to equipment suppression systems, manual	conveyors, loading shovels, hoppers and other loading or handling equipment and use quipment wherever appropriate.			
fine water sprays on such ed 6.5 Ensure equipment is readily practicable after the event of 7 Waste Management 7.1 Avoid bonfires and burning 8 Demolition 8.1 Soft strip inside buildings be provide a screen against dus 8.2 Ensure effective water supp hoses attached to equipment suppression systems, manual	quipment wherever appropriate.	Н		
7 Waste Management 7.1 Avoid bonfires and burning 8 Demolition 8.1 Soft strip inside buildings be provide a screen against dus 8.2 Ensure effective water supp hoses attached to equipment suppression systems, manual		1		
 7.1 Avoid bonfires and burning 8 Demolition 8.1 Soft strip inside buildings be provide a screen against dus 8.2 Ensure effective water supp hoses attached to equipment suppression systems, manual 	Ensure equipment is readily available on site to clean any dry spillages, and clean up spillages as soon as reasonably practicable after the event using wet cleaning methods.			
8.1 Soft strip inside buildings be provide a screen against dus 8.2 Ensure effective water supp hoses attached to equipment suppression systems, manual	Waste Management			
 8.1 Soft strip inside buildings be provide a screen against dus 8.2 Ensure effective water supp hoses attached to equipment suppression systems, manual 	of waste materials.	Н		
8.2 Ensure effective water supp hoses attached to equipmen suppression systems, manual				
hoses attached to equipmer suppression systems, manual	efore demolition (retaining walls and windows in the rest of the building where possible, to st).	D		
	Ensure effective water suppression is used during demolition operations. Hand held sprays are more effective than hoses attached to equipment as the water can be directed to where it is needed. In addition high volume water suppression systems, manually controlled, can produce fine water droplets that effectively bring the dust particles to the ground.			
8.2 Avoid explosive blasting, usi	ing appropriate manual or mechanical alternatives.	Н		
8.3 Bag and remove any biologi	Bag and remove any biological debris or damp down such material before demolition.			
9 Construction				
9.1 Avoid scratching or rougher	ning of concrete surfaces, where possible.	D		
	egates are stored in bunded areas and are not allowed to dry out, unless this is required which case ensure that appropriate additional control measures are in place.	D		
10 Trackout				
10.1 Use water-assisted dust swe the site.	eeper(s) on the access and local roads to remove, as necessary, any material tracked out of	D		
10.2 Avoid dry sweeping of large	areas.	D		
10.3 Ensure vehicles entering and	d leaving sites are covered to prevent escape of materials during transport.	D		
10.4 Record all inspections of ha	ul routes and any subsequent action in a site log book.	D		
10.5 Implement a wheel washing where reasonably practicab	arroates and any subsequent detroit in a site log book.	D		

5 Combined Operations of Lots 3C and 5 - Operations

The peak hourly traffic volumes and daily traffic volumes were calculated based on application of factors contained within the *Technical Direction 04a: Traffic Generated Developments – Updated traffic surveys* (RMS Guide Update), being:

- 1.892 daily vehicle trips per 100 m² of industrial gross floor area (GFA) including ancillary office floor space.
- 0.163 peak hour vehicle trips per 100 m² of industrial GFA including ancillary office floor space.

Traffic numbers used in the AQIA were provided by the traffic consultant as a conservative estimate due to the Project uncertainties. The peak and daily vehicle numbers adopted for the AQIA were 1,426 vehicles per hour (vph) and 16,544 vehicles per day (vpd) respectively. A review of the proposed GFAs for each Precinct in the modified OWE masterplan has identified minor variations in the GFAs of all Precincts. A summary of the currently proposed Precinct GFAs and associated peak and daily vehicle numbers calculated using the factors above, compared to that assessed in the AQIA, is provided in **Table 3**.

Table 3 Vehicle Volumes Projected for each Precinct in OWE

	Current Proposed				
Precinct	GFA (m²)	Vehicles per Day (vpd)	Peak Vehicles per Hour (vph)		
1	125,198	2,369	204		
2	267,860	5,068	437		
3	54,460	1,030	89		
4	115,952	2,194	189		
5	35,640	674	58		
Amenities Lot	345	-	-		
Total	599,455	11,342	977ª		
Assumed in AQIA mod	elling study:	16,544 (+46%)	1,426 (+46%)		

^a AM Peak traffic estimates (Source: Transport Assessment, Ason 2022)

As the air dispersion modelling was based on the vehicular emissions for the total OWE, it can be seen from **Table 3** that the AQIA was based on significantly higher peak and daily traffic estimates than currently proposed under the modified masterplan. Therefore, the predicted dispersion modelling results shown in **Table 1**, which are well below the relevant impact assessment criteria, provide a conservative assessment of the expected worst case air quality impacts at the sensitive receptor locations.

6 Conclusions

Based on the above, it is concluded that an update of the AQIA is not required to address the proposed revision to the layout of Precincts 3C and 5, and that as originally concluded, air quality impacts should not be considered a constraint to this development application.

Yours sincerely

VARUN MARWAHA

Principal Air Quality Consultant

Checked/

Authorised by: KL