



**Transport for New South Wales
Piling Report**

160,162 & 172 Lord Sheffield Circuit, North Penrith

Document Control Record

Approved by:	Ash Afnani
Position:	Senior Associate – Structural
Signed:	
Date:	02/11/2022
Job No.	SY220-070

REVISION STATUS

Revision	Description of Revision	Date	Issued By:
A	Preliminary	07/10/2022	Monika Stawowczyk
B	For Information	02/11/2022	Monika Stawowczyk

Recipients are responsible for eliminating all superseded documents in their possession.

van der Meer Consulting (NSW)
 ABN 56 158 266 301

Level 3, 39 Chandos Street,
 ST LEONARDS, NSW 2065

Telephone: +61 2 9436 0433
 Facsimile: +61 2 9436 1370

This document and its contents are intended for the addressee only and contains opinions held by the Author based on material available at the time and expresses those opinions for the purposes of consideration by the Addressee and not for general publication without written consent.

Table of Contents

1. Introduction.....	4
2. References.....	4
3. Summary of Ground Conditions	5
4. Analysis.....	6
5. Assumptions.....	7
5.1. Surcharge Loads.....	7
5.2. Wall Properties.....	7
5.3. Strut Properties - Basement 1 Slab	7
5.4. Construction Sequence.....	7
6. Summary of Findings.....	8
7. Lateral Wall Deflection of the Ground behind the Wall.....	11
Appendix A: WALLAP Output.....	12
A.1. Section_2 (BH2)	12
A.2. Section_6 (BH6)	62
Appendix B: Van der Meer Structural drawings.....	114
Appendix C: Excavation methodology statement.....	115

1. Introduction

This report has been prepared to summarize the shoring wall design for the proposed development site location at 160,162 & 172 Lord Sheffield Circuit, North Penrith, in order to investigate any potential adverse effects on the adjacent Transport for New South Wales (TfNSW) infrastructure.

The western portion of the site accommodates the Thornton Community Garden. The site is immediately adjacent to the northern entrance of Penrith Station (west boundary). The Eastern boundary is adjacent a parcel of defence land (east boundary). The Southern boundary has a direct interface with the railway corridor.

This report will compare the results of the soil-structure interaction analyses performed by Van der Meer Consulting to the minimum design criteria as outlined in the “Technical Direction Geotechnology” GTD 2020/001 issued by Transport for New South Wales, date 2 July 2020., and make conclusions based on these results.

2. References

This report is provided based on the following documents, and should be viewed in conjunctions with the following:

- Geotechnical Investigation Report: EI Australia, Report No. E25358.G03_Rev 1, dated 23 September 2022;
- Technical Direction Geotechnology – Transport for New South Wales, GTD 2020/001, dated 2 July 2022;
- Architectural Drawings number A1000 to A1014, A1401-A1404, A1501-A1502.
- Structural Drawings number S02-01 to S02-51.

3. Summary of Ground Conditions

The following section summarises the results obtained from the mentioned geotechnical report for retaining wall design.

Table 1: Definition of geotechnical units, Reference Geotechnical Report No. E25358.G03, Table 1

Geotechnical Unit	Material Description
Unit 1: Topsoil/ Fill	Topsoil/ fill composed of silty clay with traces of rootlets.
Unit 2a: Silty/ Sandy Clay (Fluvial Soil)	Low to high plasticity, firm to very stiff silty/sandy clay.
Unit 2b: Clayey/ Silty Sand (Fluvial Soil)	Fine to medium grained, loose to medium dense clayey/silty sand.
Unit 2c: Sandy Gravel (Fluvial Soil)	Sandy Gravel, sub-angular to rounded fine to coarse gravel with medium to coarse grained sand, with rounded cobbles, trace silt and clay.
Unit 3: Very Low to Low Strength Sandstone/Shale	The very low to low strength sandstone/ shale generally consisted of closely to moderately spaced defects consisting of sub-vertical joints and decomposed zones.
Unit 4: Medium to High Strength Laminite/Sandstone/Shale	Medium to high strength laminate/ sandstone/ shale generally consisted of moderately spaced defects consisting of sub-vertical joints, sub-horizontal bedding partings and decomposed zones.

Table 2: Depth and thicknesses of geotechnical units, Reference Geotechnical Report No. E25358.G03, Table 2

Geotechnical Unit	Depth to top of unit	Unit Thickness (m)
Unit 1: Topsoil/ Fill	Surface Level	0.2 to 1.20
Unit 2a: Silty/ Sandy Clay (Fluvial Soil)	0.20 to 1.20	3.0 to 5.60
Unit 2b: Clayey/ Silty Sand (Fluvial Soil)	3.50 to 6.80	1.00 to 3.70
Unit 2c: Sandy Gravel (Fluvial Soil)	6.0 to 8.10	3.70 to 6.50
Unit 3: Very Low to Low Strength Sandstone/Shale	11.45 to 14.30	0.20 to 0.75
Unit 4: Medium to High Strength Laminite/Sandstone/Shale	11.10 to 14.50	Observed up to termination depth in all boreholes.

Table 3: Design Parameters for retaining wall design, Reference Geotechnical Report No. E25358.G03, Table 5

Material	Bulk Density (kN/m ³)	Effective Cohesion c' (kPa)	Effective Friction Angle ϕ' (degrees)	Coefficient of Earth Pressure at rest, K _o	Elastic Modulus (MPa)
Unit 1: Topsoil/ Fill	18	0	25	0.58	5
Unit 2a: Silty/ Sandy Clay (Fluvial Soil)	20	15	25	0.58	15
Unit 2b: Clayey/ Silty Sand (Fluvial Soil)	20	5	33	0.45	20
Unit 2c: Sandy Gravel (Fluvial Soil)	22	5	33	0.45	40
Unit 3: Very Low to Low Strength Sandstone/Shale	24	75	37	0.40	75
Unit 4: Medium to High Strength Laminite/Sandstone/Shale	24	200	45	-	500

4. Analysis

Commercially available software WALLAP is used for the soil-structure interaction analysis of the retaining wall. The horizontal displacements, internal pile bending moment and shear forces, and the anchor loads are obtained by modelling each of the construction stages.

Several WALLAP analyses have been performed on multiple sections along the wall in order to accurately capture the whole length of the retaining wall. The results of the analysis are presented in Appendix A.

The output from WALLAP is used to design the secant piles, shotcrete walls and the anchors. Concrete design software RCC is used to design the reinforcements in the piles. The shoring system is designed and detailed based on general engineering principles and our vast experience in similar successful projects.

5. Assumptions

A soil-structure interaction retaining wall analysis using the software program WALLAP, an industry standard analysis program, has been undertaken on different wall design sections along 160,162 & 172 Lord Sheffield Circuit, North Penrith.

5.1. Surcharge Loads

A nominal 10 kPa surcharge is applied to the first 5 meters from the shoring, followed by 30kPa allowed for the railway.

Groundwater Levels

Based on the recommendations of the mentioned geotechnical report, for the analysis, we have adopted a groundwater table at level 7.10 for BH2 and 7.60 for BH6 in both temporary and permanent conditions.

5.2. Wall Properties

The secant pile wall will be generally constructed using soft piles 900mm diameter at 1.4m centre to centre and hard piles 900mm diameter piles spaced at 1.4m centre to centre.

Young's Modulus = 20e6 kPa

Moment of Inertia = $\frac{\pi d^4}{64}$ divided by the pile spacing (m⁴/m run of wall)
= 0.023 m⁴/m

5.3. Strut Properties - Basement 1 Slab

Slab thickness = 350mm

Cross Sectional Area= 0.35m²

Young's Modulus = 20e6 kPa

5.4. Construction Sequence

Due to the changes in the natural ground level and the soil and rock layers along the boundary, several WALLAP runs are performed, and appropriate construction sequences are defined for each

of the cases. The construction sequence of Run ID: Section 2 (BH2) (along Grid A) is presented herein. The details of the other runs are presented in Appendix A.

- 1 Apply surcharge no.1 at elevation 0.00
- 2 Apply surcharge no.2 at elevation 0.00
- 3 Excavate to elevation -4.00 on RIGHT side
- 4 Install strut or anchor no.1 at elevation -3.00
- 5 Excavate to elevation -7.10 on RIGHT side
- 6 Apply water pressure profile no.1
- 7 Excavate to elevation -9.50 on RIGHT side

For detailed construction methodology please refer to the Appendix C.

6. Summary of Findings

The results of one of the analyses for each of the runs are presented in the following tables.

Table 4: WALLAP results for Section 2 (BH2)

Maximum wall bending moment (working), M_{working}	301.2kNm/m
Maximum wall shear force (working), S_{working}	113.9kN/m
Maximum predicted lateral wall deflection at the ground level	21mm
Strut	
Design strut load (working)	129.86kN/m run

Table 5: WALLAP results for Section 6 (BH6)

Maximum wall bending moment (working), M_{working}	311.2kNm/m
Maximum wall shear force (working), S_{working}	119.5kN/m
Maximum predicted lateral wall deflection at the ground level	19mm
Strut	
Design strut load (working)	139.43kN/m run




Figure 1: Pile type P1 structural capacity




Figure 2: Pile type P1 structural capacity

7. Lateral Wall Deflection of the Ground behind the Wall

TfNSW have indicated the total (serviceability) lateral deflection of the wall in any one direction acceptable for non-sensitive TfNSW assets is to be limited to 0.5% of the excavated height or 30mm, whichever is lesser. The maximum retained wall height is 9.5m, and therefore the maximum allowable horizontal wall deflections is:

$$0.005 \times 9500 = 47.5mm \rightarrow 30mm$$

Our WALLAP analysis predicts a maximum 21mm of horizontal wall deflection and this falls within the TfNSW guideline.

Appendix A: WALLAP Output

A.1. Section_2 (BH2)

VAN der MEER CONSULTING	Sheet No.
Program: WALLAP Version 6.07 Revision A55.B74.R58	Job No. 220070
Licensed from GEOSOLVE	Made by : MS
Data filename/Run ID: Section_2 (BH2)	
Penrith	Date: 7-10-2022
Section A	Checked :

Units: kN,m

INPUT DATA

SOIL PROFILE

Stratum no.	Elevation of top of stratum	Soil types	
		Left side	Right side
1	0.00	1 Fill	1 Fill
2	-1.20	2 Silty Clay	2 Silty Clay
3	-3.70	2 Silty Clay	2 Silty Clay
4	-6.80	3 Silty Sand	3 Silty Sand
5	-7.80	5 Sandy Gravel	5 Sandy Gravel
6	-14.50	6 Sandstone (medium)	6 Sandstone (medium)

SOIL PROPERTIES

-- Soil type --	Bulk density	Young's Modulus	At rest coeff.	Consol state.	Active limit	Passive limit	Cohesion
No. Description (Datum elev.)	kN/m3	Eh, kN/m2 (dEh/dy)	Ko (dKo/dy)	NC/OC (Nu)	Ka (Kac)	Kp (Kpc)	kN/m2 (dc/dy)
1 Fill	18.00	5000	0.580	OC (0.300)	0.403 (0.000)	3.222 (0.000)	
2 Silty Clay	20.00	15000	0.580	OC (0.300)	0.356 (1.380)	3.222 (4.760)	15.00d
3 Silty Sand	20.00	20000	0.450	OC (0.300)	0.254 (1.149)	5.160 (6.407)	5.000d
4 Not defined							
5 Sandy Gravel	22.00	40000	0.450	OC (0.300)	0.254 (1.149)	5.160 (6.407)	5.000d
6 Sandstone (-medium)	24.00	500000	0.000	OC (0.250)	0.151 (0.849)	11.75 (10.745)	200.0d

Additional soil parameters associated with Ka and Kp

--- parameters for Ka ---				--- parameters for Kp ---			
Soil		Wall	Back-	Soil		Wall	Back-
friction		adhesion	fill	friction		adhesion	fill
angle		coeff.	angle	angle		coeff.	angle
1 Fill	25.00	0.022	0.00	25.00	0.475	0.00	
2 Silty Clay	25.00	0.575	0.00	25.00	0.475	0.00	
3 Silty Sand	33.00	0.554	0.00	33.00	0.456	0.00	
4 Not defined							
5 Sandy Gravel	33.00	0.554	0.00	33.00	0.456	0.00	
6 Sandstone (medium)	45.00	0.364	0.00	45.00	0.364	0.00	

GROUND WATER CONDITIONS

STRUTS and ANCHORS

Prop no.	Elev.	Prop spacing m	Cross- section area sq.m	Youngs modulus kN/m2	Free length m	Inclin -ation (degs)	Pre- stress /prop kN	Strut or Anchor	Allow tension ?	L/R
1	-3.00	1.00	0.350000	2.000E+07	370.0	0.00	1.00	Strut	Yes	R

SURCHARGE LOADS

Surch -arge no.	Elev.	Distance from wall	Length parallel to wall	Width perpend. to wall	Surcharge ----- Near edge	Surcharge ----- Far edge	Equiv. soil type	Partial factor/ Category
1	0.00	0.00 (L)	30.00	5.00	10.00	=	N/A	N/A
2	0.00	5.00 (L)	30.00	15.00	20.00	=	N/A	N/A

Note: L = Left side, R = Right side

CONSTRUCTION STAGES

Construction stage no.	Stage description
1	Apply surcharge no.1 at elevation 0.00
2	Apply surcharge no.2 at elevation 0.00
3	Excavate to elevation -4.00 on RIGHT side
4	Install strut or anchor no.1 at elevation -3.00
5	Excavate to elevation -7.10 on RIGHT side
6	Apply water pressure profile no.1
7	Excavate to elevation -9.50 on RIGHT side

FACTORS OF SAFETY and ANALYSIS OPTIONS

Stability analysis:

Method of analysis - Strength Factor method

Factor on soil strength for calculating wall depth = 1.00

Parameters for undrained strata:

Minimum equivalent fluid density = 5.00 kN/m3

Maximum depth of water filled tension crack = 0.00 m

Bending moment and displacement calculation:

Method - Subgrade reaction model using Influence Coefficients

Open Tension Crack analysis? - No

Non-linear Modulus Parameter (L) = 0 m

Boundary conditions:

Length of wall (normal to plane of analysis) = 1000.00 m

Width of excavation on Left side of wall = 20.00 m

Width of excavation on Right side of wall = 20.00 m

Distance to rigid boundary on Left side = 20.00 m

Distance to rigid boundary on Right side = 20.00 m

OUTPUT OPTIONS

Stage no.	----- Stage description	----- Output options
		Displacement Active, Graph.
		Bending mom. Passive output
		Shear force pressures

1 Apply surcharge no.1 at elev. 0.00	Yes	Yes	Yes
2 Apply surcharge no.2 at elev. 0.00	Yes	Yes	Yes
3 Excav. to elev. -4.00 on RIGHT side	Yes	Yes	Yes
4 Install prop no.1 at elev. -3.00	Yes	Yes	Yes
5 Excav. to elev. -7.10 on RIGHT side	Yes	Yes	Yes
6 Apply water pressure profile no.1	Yes	Yes	Yes
7 Excav. to elev. -9.50 on RIGHT side	Yes	Yes	Yes
* Summary output	Yes	-	Yes

Program WALLAP - Copyright (C) 2020 by DL Borin, distributed by GEOSOLVE
 150 St. Alphonsus Road, London SW4 7BW, UK www.geosolve.co.uk

VAN der MEER CONSULTING

Program: WALLAP Version 6.07 Revision A55.B74.R58

Licensed from GEOSOLVE

Data filename/Run ID: Section_2 (BH2)

Penrith

Section A

| Sheet No.

| Job No. 220070


| Made by : MS

| Date: 7-10-2022

| Checked :

Units: kN,m

Stage No.1 Apply surcharge no.1 at elev. 0.00



VAN der MEER CONSULTING	Sheet No.
Program: WALLAP Version 6.07 Revision A55.B74.R58	Job No. 220070
Licensed from GEOSOLVE	Made by : MS
Data filename/Run ID: Section_2(BH2)	
Penrith	Date: 7-10-2022
Section A	Checked :

Units: kN,m

Stage No. 1 Apply surcharge no.1 at elevation 0.00

STABILITY ANALYSIS of Soldier Pile Wall according to Strength Factor method
Factor of safety on soil strength

			FoS for toe elev. = -16.00		Toe elev. for FoS = 1.000			
<u>Stage</u> <u>No.</u>	<u>Ground level</u> <u>Act.</u>	<u>Pass.</u>	<u>Prop</u> <u>Elev.</u>	<u>Factor</u> <u>of</u>	<u>Moment</u> <u>equilib.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u>	<u>Direction</u> <u>of</u>
				<u>Safety</u> <u>at elev.</u>			<u>-ation</u>	<u>failure</u>
1	0.00	0.00	Cant.	Conditions not suitable for FoS calc.				

BENDING MOMENT and DISPLACEMENT ANALYSIS of Soldier Pile Wall

Analysis options

Soldier Pile width = 0.90m; spacing = 1.40m

Passive mobilisation factor = 3.000

Length of wall perpendicular to section = 1000.00m

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Rigid boundaries: Left side 20.00 from wall
Right side 20.00 from wall

Node no.	Y coord	Nett pressure kN/m ²	Wall disp. m	Wall rotation rad.	Shear force kN/m	Bending moment kN.m/m	Prop forces kN/m
1	0.00	4.03	0.002	1.83E-04	0.0	0.0	
2	-0.60	2.06	0.001	1.82E-04	1.8	0.7	
3	-1.20	2.21	0.001	1.80E-04	3.1	2.2	
		-1.91	0.001	1.80E-04	3.1	2.2	
4	-1.65	-1.57	0.001	1.78E-04	2.3	3.4	
5	-2.10	-1.27	0.001	1.74E-04	1.7	4.3	
6	-2.55	-0.99	0.001	1.69E-04	1.2	4.9	
7	-3.00	-0.73	0.001	1.64E-04	0.8	5.3	
8	-3.70	-0.39	0.001	1.56E-04	0.4	5.7	
9	-4.00	-0.25	0.001	1.52E-04	0.3	5.8	
10	-4.80	0.06	0.001	1.42E-04	0.2	6.0	
11	-5.60	0.34	0.001	1.31E-04	0.4	6.1	
12	-6.20	0.52	0.001	1.23E-04	0.6	6.4	
13	-6.80	0.69	0.001	1.15E-04	1.0	6.9	
		-0.08	0.001	1.15E-04	1.0	6.9	
14	-7.10	0.05	0.000	1.10E-04	1.0	7.2	
15	-7.80	0.32	0.000	9.89E-05	1.1	7.9	
		-2.10	0.000	9.89E-05	1.1	7.9	
16	-8.23	-1.71	0.000	9.15E-05	0.3	8.2	
17	-8.65	-1.35	0.000	8.40E-05	-0.3	8.2	
18	-9.08	-1.03	0.000	7.66E-05	-0.8	7.9	
19	-9.50	-0.74	0.000	6.95E-05	-1.2	7.4	
20	-10.00	-0.45	0.000	6.18E-05	-1.5	6.7	

21	-10.60	-0.14	0.000	5.37E-05	-1.7	5.7
22	-11.20	0.12	0.000	4.69E-05	-1.7	4.7
23	-12.00	0.41	0.000	3.99E-05	-1.5	3.4
24	-12.80	0.65	0.000	3.50E-05	-1.1	2.3
25	-13.60	0.86	0.000	3.16E-05	-0.5	1.6
26	-14.05	0.97	0.000	3.00E-05	-0.0	1.5
27	-14.50	1.08	0.000	2.85E-05	0.4	1.6
		-2.82	0.000	2.85E-05	0.4	1.6
28	-15.25	-1.34	0.000	2.63E-05	-1.1	1.1
29	-16.00	4.36	-0.000	2.53E-05	0.0	-0.0

Run ID. Section_2 (BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.1 Apply surcharge no.1 at elevation 0.00

LEFT side								
Node no.	Y coord	Water press. kN/m2	Vertic -al kN/m2	Effective stresses		Earth pressure kN/m2	Total earth pressure kN/m2	Coeff. of subgrade reaction kN/m3
				Active limit kN/m2	Passive limit kN/m2			
1	0.00	0.00	10.00	4.03	32.22	4.03	4.03a	760
2	-0.60	0.00	20.79	8.38	66.98	9.44	9.44	760
3	-1.20	0.00	31.54	12.71	101.62	15.76	15.76	760
		0.00	31.54	0.00	173.04	13.71	13.71	2280
4	-1.65	0.00	40.46	0.00	201.77	19.07	19.07	2280
5	-2.10	0.00	49.34	0.00	230.37	24.42	24.42	2280
6	-2.55	0.00	58.17	0.01	258.81	29.75	29.75	2280
7	-3.00	0.00	66.96	3.14	287.13	35.05	35.05	2280
8	-3.70	0.00	80.57	7.98	330.99	43.26	43.26	2280
9	-4.00	0.00	86.38	10.05	349.73	46.76	46.76	2280
10	-4.80	0.00	101.87	15.57	399.62	56.09	56.09	2280
11	-5.60	0.00	117.34	21.07	449.47	65.40	65.40	2280
12	-6.20	0.00	128.95	25.21	486.87	72.36	72.36	2280
13	-6.80	0.00	140.57	29.34	524.32	79.32	79.32	2280
		0.00	140.57	29.90	757.45	61.57	61.57	3041
14	-7.10	0.00	146.39	31.38	787.47	64.30	64.30	3041
15	-7.80	7.00	152.98	33.05	821.47	67.49	74.49	3041
		7.00	152.98	33.05	821.47	66.29	73.29	6081
16	-8.23	11.25	157.84	34.28	846.57	68.73	79.98	6081
17	-8.65	15.50	162.71	35.52	871.72	71.15	86.65	6081
18	-9.08	19.75	167.60	36.76	896.91	73.56	93.31	6081
19	-9.50	24.00	172.49	38.00	922.15	75.95	99.95	6081
20	-10.00	29.00	178.25	39.46	951.91	78.75	107.75	6081
21	-10.60	35.00	185.19	41.22	987.70	82.09	117.09	6081
22	-11.20	41.00	192.14	42.98	1023.57	85.41	126.41	6081
23	-12.00	49.00	201.43	45.34	1071.52	89.80	138.80	6081
24	-12.80	57.00	210.75	47.70	1119.60	94.18	151.18	6081
25	-13.60	65.00	220.09	50.07	1167.79	98.55	163.55	6081
26	-14.05	69.50	225.35	51.40	1194.95	101.01	170.51	6081
27	-14.50	74.00	230.62	52.74	1222.14	103.46	177.46	6081
		74.00	230.62	0.00	4857.74	0.00	74.00a	72380
28	-15.25	81.50	240.91	0.00	4978.65	0.00	81.50a	72380
29	-16.00	89.00	251.22	0.00	5099.73	4.36	93.36	4065999

RIGHT side								
Node no.	Y coord	Water press. kN/m2	Vertic -al kN/m2	Effective stresses		Earth pressure kN/m2	Total earth pressure kN/m2	Coeff. of subgrade reaction kN/m3
				Active limit kN/m2	Passive limit kN/m2			
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	760
2	-0.60	0.00	10.80	4.35	34.79	7.38	7.38	760
3	-1.20	0.00	21.60	8.70	69.58	13.56	13.56	760
		0.00	21.60	0.00	141.00	15.61	15.61	2280
4	-1.65	0.00	30.60	0.00	169.99	20.65	20.65	2280
5	-2.10	0.00	39.60	0.00	198.99	25.69	25.69	2280

6	-2.55	0.00	48.60	0.00	227.99	30.73	30.73	2280
7	-3.00	0.00	57.60	0.00	256.99	35.78	35.78	2280
8	-3.70	0.00	71.60	4.79	302.10	43.64	43.64	2280
9	-4.00	0.00	77.60	6.93	321.43	47.02	47.02	2280
10	-4.80	0.00	93.60	12.62	372.98	56.03	56.03	2280
11	-5.60	0.00	109.60	18.32	424.53	65.06	65.06	2280
12	-6.20	0.00	121.60	22.59	463.20	71.84	71.84	2280
13	-6.80	0.00	133.60	26.86	501.86	78.64	78.64	2280
		0.00	133.60	28.14	721.47	61.65	61.65	3041

Run ID. Section_2(BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.1 Apply surcharge no.1 at elevation 0.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u>	<u>RIGHT side</u>				<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
			<u>Vertic</u> <u>-al</u>	<u>Effective stresses</u>		<u>Earth</u> <u>pressure</u>		
		<u>kN/m2</u>	<u>kN/m2</u>	<u>Active</u> <u>limit</u>	<u>Passive</u> <u>limit</u>	<u>kN/m2</u>	<u>kN/m2</u>	<u>kN/m3</u>
14	-7.10	0.00	139.60	29.66	752.43	64.25	64.25	3041
15	-7.80	7.00	146.60	31.43	788.56	67.18	74.18	3041
		7.00	146.60	31.43	788.56	68.39	75.39	6081
16	-8.23	11.25	151.70	32.73	814.88	70.44	81.69	6081
17	-8.65	15.50	156.80	34.02	841.19	72.50	88.00	6081
18	-9.08	19.75	161.90	35.31	867.51	74.59	94.34	6081
19	-9.50	24.00	167.00	36.61	893.83	76.70	100.70	6081
20	-10.00	29.00	173.00	38.13	924.79	79.20	108.20	6081
21	-10.60	35.00	180.20	39.95	961.95	82.23	117.23	6081
22	-11.20	41.00	187.40	41.78	999.10	85.29	126.29	6081
23	-12.00	49.00	197.00	44.21	1048.65	89.39	138.39	6081
24	-12.80	57.00	206.60	46.65	1098.19	93.53	150.53	6081
25	-13.60	65.00	216.20	49.08	1147.73	97.69	162.69	6081
26	-14.05	69.50	221.60	50.45	1175.59	100.04	169.54	6081
27	-14.50	74.00	227.00	51.82	1203.46	102.39	176.39	6081
		74.00	227.00	0.00	4815.23	2.82	76.82	72380
28	-15.25	81.50	237.50	0.00	4938.56	1.34	82.84	72380
29	-16.00	89.00	248.00	0.00	5061.88	0.00	89.00a	4065999


Note: 89.00 a Soil pressure at active limit
 123.45 p Soil pressure at passive limit

VAN der MEER CONSULTING
 Program: WALLAP Version 6.07 Revision A55.B74.R58
 Licensed from GEOSOLVE
 Data filename/Run ID: Section_2 (BH2)
 Penrith
 Section A


| Sheet No.
 | Job No. 220070
 | Made by : MS
 |
 | Date: 7-10-2022
 | Checked :

Units: kN,m

Stage No.1 Apply surcharge no.1 at elev. 0.00



Stage No.1 Apply surcharge no.1 at elev. 0.00




VAN der MEER CONSULTING
 Program: WALLAP Version 6.07 Revision A55.B74.R58
 Licensed from GEOSOLVE
 Data filename/Run ID: Section_2 (BH2)
 Penrith
 Section A

| Sheet No.
 | Job No. 220070
 | Made by : MS
 |
 | Date: 7-10-2022
 | Checked :

Units: kN,m

Stage No.2 Apply surcharge no.2 at elev. 0.00



VAN der MEER CONSULTING	Sheet No.
Program: WALLAP Version 6.07 Revision A55.B74.R58	Job No. 220070
Licensed from GEOSOLVE	Made by : MS
Data filename/Run ID: Section_2(BH2)	
Penrith	Date: 7-10-2022
Section A	Checked :

Units: kN,m

Stage No. 2 Apply surcharge no.2 at elevation 0.00

STABILITY ANALYSIS of Soldier Pile Wall according to Strength Factor method
Factor of safety on soil strength

				FoS for toe	Toe elev. for	
				elev. = -16.00	FoS = 1.000	
<u>Stage</u>	<u>Ground level</u>	<u>Prop</u>	<u>Factor</u>	<u>Moment</u>	<u>Toe</u>	<u>Wall</u>
<u>No.</u>	<u>Act.</u>	<u>Pass.</u>	<u>Elev.</u>	<u>of</u>	<u>elev.</u>	<u>Penetr</u>
				<u>Safety</u>	<u>at elev.</u>	<u>-ation</u>
				<u>Conditions not suitable for FoS calc.</u>		<u>of failure</u>

BENDING MOMENT and DISPLACEMENT ANALYSIS of Soldier Pile Wall

Analysis options

Soldier Pile width = 0.90m; spacing = 1.40m

Passive mobilisation factor = 3.000

Length of wall perpendicular to section = 1000.00m

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Rigid boundaries: Left side 20.00 from wall
Right side 20.00 from wall

<u>Node</u>	<u>Y</u>	<u>Nett</u>	<u>Wall</u>	<u>Wall</u>	<u>Shear</u>	<u>Bending</u>	<u>Prop</u>
<u>no.</u>	<u>coord</u>	<u>pressure</u>	<u>disp.</u>	<u>rotation</u>	<u>force</u>	<u>moment</u>	<u>forces</u>
		kN/m2	m	rad.	kN/m	kN.m/m	kN/m
1	0.00	4.03	0.002	1.36E-04	0.0	0.0	
2	-0.60	1.85	0.002	1.36E-04	1.8	0.7	
3	-1.20	2.01	0.002	1.34E-04	2.9	2.1	
		-2.58	0.002	1.34E-04	2.9	2.1	
4	-1.65	-2.24	0.002	1.31E-04	1.8	3.2	
5	-2.10	-1.89	0.001	1.28E-04	0.9	3.8	
6	-2.55	-1.53	0.001	1.24E-04	0.1	4.0	
7	-3.00	-1.16	0.001	1.20E-04	-0.5	3.9	
8	-3.70	-0.59	0.001	1.14E-04	-1.1	3.3	
9	-4.00	-0.35	0.001	1.12E-04	-1.2	3.0	
10	-4.80	0.27	0.001	1.08E-04	-1.3	1.9	
11	-5.60	0.86	0.001	1.06E-04	-0.8	1.0	
12	-6.20	1.27	0.001	1.04E-04	-0.2	0.7	
13	-6.80	1.66	0.001	1.03E-04	0.7	0.8	
		0.47	0.001	1.03E-04	0.7	0.8	
14	-7.10	0.70	0.001	1.03E-04	0.9	1.1	
15	-7.80	1.21	0.001	1.01E-04	1.6	1.9	
		-2.92	0.001	1.01E-04	1.6	1.9	
16	-8.23	-2.38	0.001	9.91E-05	0.4	2.3	
17	-8.65	-1.87	0.001	9.70E-05	-0.5	2.2	
18	-9.08	-1.39	0.001	9.51E-05	-1.2	1.9	
19	-9.50	-0.94	0.001	9.36E-05	-1.7	1.3	
20	-10.00	-0.44	0.001	9.28E-05	-2.0	0.3	

21	-10.60	0.12	0.001	9.32E-05	-2.1	-1.0
22	-11.20	0.66	0.001	9.53E-05	-1.9	-2.2
23	-12.00	1.35	0.000	1.00E-04	-1.1	-3.5
24	-12.80	2.03	0.000	1.06E-04	0.3	-3.9
25	-13.60	2.72	0.000	1.12E-04	2.2	-3.0
26	-14.05	3.12	0.000	1.15E-04	3.5	-1.8
27	-14.50	3.51	0.000	1.15E-04	5.0	0.1
		-9.23	0.000	1.15E-04	5.0	0.1
28	-15.25	-4.89	0.000	1.14E-04	-0.3	1.2
29	-16.00	5.70	0.000	1.13E-04	0.0	-0.0

Run ID. Section_2 (BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.2 Apply surcharge no.2 at elevation 0.00

LEFT side								
Node no.	Y coord	Water press. kN/m2	Effective stresses				Total earth pressure kN/m2	Coeff. of subgrade reaction kN/m3
			Vertic -al kN/m2	Active limit kN/m2	Passive limit kN/m2	Earth pressure kN/m2		
1	0.00	0.00	10.00	4.03	32.22	4.03	4.03a	459
2	-0.60	0.00	20.81	8.38	67.03	9.33	9.33	459
3	-1.20	0.00	31.65	12.75	101.96	15.69	15.69	459
		0.00	31.65	0.00	173.38	13.39	13.39	1378
4	-1.65	0.00	40.72	0.00	202.61	18.80	18.80	1378
5	-2.10	0.00	49.83	0.00	231.96	24.22	24.22	1378
6	-2.55	0.00	58.98	0.30	261.44	29.65	29.65	1378
7	-3.00	0.00	68.16	3.56	291.01	35.09	35.09	1378
8	-3.70	0.00	82.48	8.66	337.15	43.56	43.56	1378
9	-4.00	0.00	88.63	10.85	356.95	47.19	47.19	1378
10	-4.80	0.00	105.01	16.68	409.75	56.87	56.87	1378
11	-5.60	0.00	121.37	22.51	462.46	66.52	66.52	1378
12	-6.20	0.00	133.61	26.87	501.89	73.74	73.74	1378
13	-6.80	0.00	145.81	31.21	541.20	80.93	80.93	1378
		0.00	145.81	31.23	784.48	62.97	62.97	1837
14	-7.10	0.00	151.90	32.78	815.89	65.81	65.81	1837
15	-7.80	7.00	159.06	34.59	852.85	69.24	76.24	1837
		7.00	159.06	34.59	852.85	67.18	74.18	3674
16	-8.23	11.25	164.23	35.90	879.54	69.76	81.01	3674
17	-8.65	15.50	169.38	37.21	906.14	72.32	87.82	3674
18	-9.08	19.75	174.52	38.51	932.64	74.86	94.61	3674
19	-9.50	24.00	179.64	39.81	959.04	77.39	101.39	3674
20	-10.00	29.00	185.63	41.33	990.00	80.34	109.34	3674
21	-10.60	35.00	192.80	43.15	1026.99	83.85	118.85	3674
22	-11.20	41.00	199.94	44.96	1063.84	87.35	128.35	3674
23	-12.00	49.00	209.43	47.37	1112.77	91.99	140.99	3674
24	-12.80	57.00	218.87	49.76	1161.50	96.61	153.61	3674
25	-13.60	65.00	228.28	52.15	1210.06	101.24	166.24	3674
26	-14.05	69.50	233.56	53.49	1237.32	103.84	173.34	3674
27	-14.50	74.00	238.83	54.82	1264.53	106.44	180.44	3674
		74.00	238.83	0.00	4954.24	0.00	74.00a	43217
28	-15.25	81.50	249.11	0.00	5074.92	0.00	81.50a	43217
29	-16.00	89.00	259.37	0.00	5195.43	6.39	95.39	43217

RIGHT side								
Node no.	Y coord	Water press. kN/m2	Effective stresses				Total earth pressure kN/m2	Coeff. of subgrade reaction kN/m3
			Vertic -al kN/m2	Active limit kN/m2	Passive limit kN/m2	Earth pressure kN/m2		
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	459
2	-0.60	0.00	10.80	4.35	34.79	7.48	7.48	459
3	-1.20	0.00	21.60	8.70	69.58	13.68	13.68	459
		0.00	21.60	0.00	141.00	15.97	15.97	1378
4	-1.65	0.00	30.60	0.00	169.99	21.04	21.04	1378
5	-2.10	0.00	39.60	0.00	198.99	26.10	26.10	1378

6	-2.55	0.00	48.60	0.00	227.99	31.18	31.18	1378
7	-3.00	0.00	57.60	0.00	256.99	36.25	36.25	1378
8	-3.70	0.00	71.60	4.79	302.10	44.16	44.16	1378
9	-4.00	0.00	77.60	6.93	321.43	47.55	47.55	1378
10	-4.80	0.00	93.60	12.62	372.98	56.60	56.60	1378
11	-5.60	0.00	109.60	18.32	424.53	65.66	65.66	1378
12	-6.20	0.00	121.60	22.59	463.20	72.47	72.47	1378
13	-6.80	0.00	133.60	26.86	501.86	79.27	79.27	1378
		0.00	133.60	28.14	721.47	62.50	62.50	1837

Run ID. Section_2(BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.2 Apply surcharge no.2 at elevation 0.00

Node no.	Y coord	RIGHT side					Total earth pressure	Coeff. of subgrade reaction
		Water press.	Vertic -al	Effective stresses Active limit	Passive limit	Earth pressure		
		kN/m2	kN/m2	kN/m2	kN/m2	kN/m2	kN/m2	kN/m3
14	-7.10	0.00	139.60	29.66	752.43	65.10	65.10	1837
15	-7.80	7.00	146.60	31.43	788.56	68.03	75.03	1837
		7.00	146.60	31.43	788.56	70.10	77.10	3674
16	-8.23	11.25	151.70	32.73	814.88	72.14	83.39	3674
17	-8.65	15.50	156.80	34.02	841.19	74.19	89.69	3674
18	-9.08	19.75	161.90	35.31	867.51	76.26	96.01	3674
19	-9.50	24.00	167.00	36.61	893.83	78.33	102.33	3674
20	-10.00	29.00	173.00	38.13	924.79	80.78	109.78	3674
21	-10.60	35.00	180.20	39.95	961.95	83.73	118.73	3674
22	-11.20	41.00	187.40	41.78	999.10	86.69	127.69	3674
23	-12.00	49.00	197.00	44.21	1048.65	90.64	139.64	3674
24	-12.80	57.00	206.60	46.65	1098.19	94.58	151.58	3674
25	-13.60	65.00	216.20	49.08	1147.73	98.52	163.52	3674
26	-14.05	69.50	221.60	50.45	1175.59	100.73	170.23	3674
27	-14.50	74.00	227.00	51.82	1203.46	102.93	176.93	3674
		74.00	227.00	0.00	4815.23	9.23	83.23	43217
28	-15.25	81.50	237.50	0.00	4938.56	4.89	86.39	43217
29	-16.00	89.00	248.00	0.00	5061.88	0.69	89.69	43217


Note: 81.50 a Soil pressure at active limit
 123.45 p Soil pressure at passive limit

VAN der MEER CONSULTING
 Program: WALLAP Version 6.07 Revision A55.B74.R58
 Licensed from GEOSOLVE
 Data filename/Run ID: Section_2 (BH2)
 Penrith
 Section A


| Sheet No.
 | Job No. 220070
 | Made by : MS
 |
 | Date: 7-10-2022
 | Checked :

Units: kN,m

Stage No.2 Apply surcharge no.2 at elev. 0.00



Stage No.2 Apply surcharge no.2 at elev. 0.00



VAN der MEER CONSULTING

Program: WALLAP Version 6.07 Revision A55.B74.R58

Licensed from GEOSOLVE

Data filename/Run ID: Section_2 (BH2)

Penrith

Section A

| Sheet No.

| Job No. 220070


| Made by : MS

| Date: 7-10-2022

| Checked :

Units: kN,m

Stage No.3 Excav. to elev. -4.00 on RIGHT side



VAN der MEER CONSULTING	Sheet No.
Program: WALLAP Version 6.07 Revision A55.B74.R58	Job No. 220070
Licensed from GEOSOLVE	Made by : MS
Data filename/Run ID: Section_2(BH2)	
Penrith	Date: 7-10-2022
Section A	Checked :

Units: kN,m

Stage No. 3 Excavate to elevation -4.00 on RIGHT side

STABILITY ANALYSIS of Soldier Pile Wall according to Strength Factor method
Factor of safety on soil strength

Stage No.	Ground level Act.	Pass.	Prop Elev.	FoS for toe elev. = -16.00		Toe elev. for FoS = 1.000		Direction of failure
				Factor of Safety	Moment of equilib. at elev.	Toe elev.	Wall Penetration	
3	0.00	-4.00	Cant.	3.063	-15.12	-5.28	1.28	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Soldier Pile Wall

Analysis options

Soldier Pile width = 0.90m; spacing = 1.40m

Passive mobilisation factor = 3.000

Length of wall perpendicular to section = 1000.00m

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Rigid boundaries: Left side 20.00 from wall
Right side 20.00 from wall

Node no.	Y coord	Nett pressure kN/m ²	Wall disp. m	Wall rotation rad.	Shear force kN/m	Bending moment kN.m/m	Prop forces kN/m
1	0.00	4.03	0.019	1.95E-03	0.0	0.0	
2	-0.60	8.38	0.018	1.95E-03	3.7	1.1	
3	-1.20	12.75	0.017	1.95E-03	10.1	5.1	
		0.00	0.017	1.95E-03	10.1	5.1	
4	-1.65	0.00	0.016	1.94E-03	10.1	9.7	
5	-2.10	0.00	0.015	1.93E-03	10.1	14.2	
6	-2.55	1.44	0.014	1.91E-03	10.4	19.7	
7	-3.00	8.65	0.013	1.89E-03	12.7	24.7	
8	-3.70	19.82	0.012	1.84E-03	22.6	36.3	
9	-4.00	24.58	0.012	1.82E-03	29.3	44.1	
		-17.53	0.012	1.82E-03	29.3	44.1	
10	-4.80	-10.38	0.010	1.72E-03	18.1	61.9	
11	-5.60	-3.66	0.009	1.61E-03	12.5	73.1	
12	-6.20	1.02	0.008	1.51E-03	11.7	79.9	
13	-6.80	5.37	0.007	1.40E-03	13.6	87.1	
		-5.66	0.007	1.40E-03	13.6	87.1	
14	-7.10	-2.95	0.007	1.34E-03	12.3	91.0	
15	-7.80	2.87	0.006	1.19E-03	12.3	98.9	
		-32.77	0.006	1.19E-03	12.3	98.9	
16	-8.23	-26.41	0.005	1.10E-03	-0.3	101.2	
17	-8.65	-20.60	0.005	1.01E-03	-10.3	98.7	
18	-9.08	-15.31	0.004	9.26E-04	-17.9	92.4	
19	-9.50	-10.52	0.004	8.45E-04	-23.4	83.4	

20	-10.00	-5.46	0.004	7.61E-04	-27.4	70.4
21	-10.60	-0.09	0.003	6.81E-04	-29.0	53.0
22	-11.20	4.69	0.003	6.23E-04	-27.7	35.6
23	-12.00	10.43	0.002	5.79E-04	-21.6	14.9
24	-12.80	15.78	0.002	5.65E-04	-11.1	0.9
25	-13.60	21.00	0.001	5.67E-04	3.6	-3.0
26	-14.05	23.92	0.001	5.68E-04	13.7	0.7
27	-14.50	26.81	0.001	5.63E-04	25.1	9.3
		-55.51	0.001	5.63E-04	25.1	9.3
28	-15.25	-27.13	0.000	5.46E-04	-5.9	12.1

Run ID. Section_2 (BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.3 Excavate to elevation -4.00 on RIGHT side

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> kN/m2	<u>Wall</u> <u>disp.</u> m	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> kN/m	<u>Bending</u> <u>moment</u> kN.m/m	<u>Prop</u> <u>forces</u> kN/m
29	-16.00	42.87	0.000	5.36E-04	0.0	-0.0	

LEFT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u> kN/m2	<u>Effective stresses</u>				<u>Total</u> <u>earth</u> <u>pressure</u> kN/m2	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> kN/m3
			<u>Vertic</u> <u>-al</u> kN/m2	<u>Active</u> <u>limit</u> kN/m2	<u>Passive</u> <u>limit</u> kN/m2	<u>Earth</u> <u>pressure</u> kN/m2		
1	0.00	0.00	10.00	4.03	32.22	4.03	4.03a	732
2	-0.60	0.00	20.81	8.38	67.03	8.38	8.38a	732
3	-1.20	0.00	31.65	12.75	101.96	12.75	12.75a	732
		0.00	31.65	0.00	173.38	0.00	0.00a	2197
4	-1.65	0.00	40.72	0.00	202.61	0.00	0.00a	2197
5	-2.10	0.00	49.83	0.00	231.96	0.00	0.00a	2197
6	-2.55	0.00	58.98	0.30	261.44	1.44	1.44	2197
7	-3.00	0.00	68.16	3.56	291.01	8.65	8.65	2197
8	-3.70	0.00	82.48	8.66	337.15	19.82	19.82	2197
9	-4.00	0.00	88.63	10.85	356.95	24.58	24.58	2197
10	-4.80	0.00	105.01	16.68	409.75	37.18	37.18	2197
11	-5.60	0.00	121.37	22.51	462.46	49.58	49.58	2197
12	-6.20	0.00	133.61	26.87	501.89	58.72	58.72	2197
13	-6.80	0.00	145.81	31.21	541.20	67.70	67.70	2197
		0.00	145.81	31.23	784.48	45.33	45.33	2929
14	-7.10	0.00	151.90	32.78	815.89	49.28	49.28	2929
15	-7.80	7.00	159.06	34.59	852.85	55.12	62.12	2929
		7.00	159.06	34.59	852.85	38.93	45.93	5858
16	-8.23	11.25	164.23	35.90	879.54	44.13	55.38	5858
17	-8.65	15.50	169.38	37.21	906.14	49.09	64.59	5858
18	-9.08	19.75	174.52	38.51	932.64	53.81	73.56	5858
19	-9.50	24.00	179.64	39.81	959.04	58.30	82.30	5858
20	-10.00	29.00	185.63	41.33	990.00	63.33	92.33	5858
21	-10.60	35.00	192.80	43.15	1026.99	69.05	104.05	5858
22	-11.20	41.00	199.94	44.96	1063.84	74.50	115.50	5858
23	-12.00	49.00	209.43	47.37	1112.77	81.48	130.48	5858
24	-12.80	57.00	218.87	49.76	1161.50	88.30	145.30	5858
25	-13.60	65.00	228.28	52.15	1210.06	95.07	160.07	5858
26	-14.05	69.50	233.56	53.49	1237.32	98.87	168.37	5858
27	-14.50	74.00	238.83	54.82	1264.53	102.66	176.66	5858
		74.00	238.83	0.00	4954.24	0.00	74.00a	69695
28	-15.25	81.50	249.11	0.00	5074.92	0.00	81.50a	69695
29	-16.00	89.00	259.37	0.00	5195.43	42.87	131.87	9951284

RIGHT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u> kN/m2	<u>Effective stresses</u>				<u>Total</u> <u>earth</u> <u>pressure</u> kN/m2	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> kN/m3
			<u>Vertic</u> <u>-al</u> kN/m2	<u>Active</u> <u>limit</u> kN/m2	<u>Passive</u> <u>limit</u> kN/m2	<u>Earth</u> <u>pressure</u> kN/m2		
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0

2	-0.60	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	-1.20	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	-1.65	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	-2.10	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	-2.55	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	-3.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	-3.70	0.00	0.00	0.00	0.00	0.00	0.00	0.0
9	-4.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	0.00	0.00	71.40	42.11	42.11	2703

Run ID. Section_2(BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.3 Excavate to elevation -4.00 on RIGHT side

Node no.	Y coord	Water press. kN/m2	RIGHT side				Total earth pressure kN/m2	Coeff. of subgrade reaction kN/m3
			Vertic -al kN/m2	Effective stresses Active limit kN/m2	Passive limit kN/m2	Earth pressure kN/m2		
10	-4.80	0.00	16.00	0.00	122.96	47.56	47.56	2703
11	-5.60	0.00	32.02	0.00	174.56	53.25	53.25	2703
12	-6.20	0.00	44.04	0.00	213.31	57.70	57.70	2703
13	-6.80	0.00	56.09	0.00	252.12	62.34	62.34	2703
		0.00	56.09	8.48	321.47	50.99	50.99	3604
14	-7.10	0.00	62.12	10.01	352.60	52.23	52.23	3604
15	-7.80	7.00	69.22	11.81	389.22	52.25	59.25	3604
		7.00	69.22	11.81	389.22	71.70	78.70	7208
16	-8.23	11.25	74.39	13.12	415.94	70.54	81.79	7208
17	-8.65	15.50	79.59	14.44	442.75	69.69	85.19	7208
18	-9.08	19.75	84.80	15.76	469.64	69.12	88.87	7208
19	-9.50	24.00	90.03	17.08	496.62	68.82	92.82	7208
20	-10.00	29.00	96.20	18.65	528.48	68.79	97.79	7208
21	-10.60	35.00	103.65	20.54	566.89	69.14	104.14	7208
22	-11.20	41.00	111.13	22.44	605.50	69.81	110.81	7208
23	-12.00	49.00	121.16	24.98	657.29	71.06	120.06	7208
24	-12.80	57.00	131.27	27.54	709.43	72.52	129.52	7208
25	-13.60	65.00	141.44	30.12	761.91	74.07	139.07	7208
26	-14.05	69.50	147.18	31.58	791.57	74.95	144.45	7208
27	-14.50	74.00	152.95	33.04	821.33	75.85	149.85	7208
		74.00	152.95	0.00	3945.51	55.51	129.51	85953
28	-15.25	81.50	164.10	0.00	4076.50	27.13	108.63	85953
29	-16.00	89.00	175.30	0.00	4208.04	0.00	89.00a	9951284


Note: 89.00 a Soil pressure at active limit
 123.45 p Soil pressure at passive limit

VAN der MEER CONSULTING
 Program: WALLAP Version 6.07 Revision A55.B74.R58
 Licensed from GEOSOLVE
 Data filename/Run ID: Section_2 (BH2)
 Penrith
 Section A


| Sheet No.
 | Job No. 220070
 | Made by : MS
 |
 | Date: 7-10-2022
 | Checked :

Units: kN,m

Stage No.3 Excav. to elev. -4.00 on RIGHT side



Stage No.3 Excav. to elev. -4.00 on RIGHT side



VAN der MEER CONSULTING

Program: WALLAP Version 6.07 Revision A55.B74.R58

Licensed from GEOSOLVE

Data filename/Run ID: Section_2 (BH2)

Penrith

Section A

| Sheet No.

| Job No. 220070


| Made by : MS

| Date: 7-10-2022

| Checked :

Units: kN,m

Stage No.4 Install prop no.1 at elev. -3.00



VAN der MEER CONSULTING	Sheet No.
Program: WALLAP Version 6.07 Revision A55.B74.R58	Job No. 220070
Licensed from GEOSOLVE	Made by : MS
Data filename/Run ID: Section_2(BH2)	
Penrith	Date: 7-10-2022
Section A	Checked :

Units: kN,m

Stage No. 4 Install strut or anchor no.1 at elevation -3.00

STABILITY ANALYSIS of Soldier Pile Wall according to Strength Factor method
Factor of safety on soil strength

			FoS for toe elev. = -16.00		Toe elev. for FoS = 1.000		
<u>Stage</u>	<u>Ground level</u>	<u>Prop</u>	<u>Factor</u>	<u>Moment</u>	<u>Toe</u>	<u>Wall</u>	<u>Direction</u>
<u>No.</u>	<u>Act.</u>	<u>Pass.</u>	<u>Elev.</u>	<u>of</u>	<u>Toe</u>	<u>Penetr</u>	<u>of</u>
				<u>Safety</u>	<u>at elev.</u>	<u>-ation</u>	<u>failure</u>
4	0.00	-4.00	-3.00	Conditions not suitable for FoS calc.			

BENDING MOMENT and DISPLACEMENT ANALYSIS of Soldier Pile Wall

Analysis options

Soldier Pile width = 0.90m; spacing = 1.40m

Passive mobilisation factor = 3.000

Length of wall perpendicular to section = 1000.00m

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Rigid boundaries: Left side 20.00 from wall
Right side 20.00 from wall

Node no.	Y coord	Nett pressure kN/m ²	Wall disp. m	Wall rotation rad.	Shear force kN/m	Bending moment kN.m/m	Prop forces kN/m
1	0.00	4.10	0.019	1.94E-03	0.0	0.0	
2	-0.60	8.45	0.018	1.94E-03	3.8	1.1	
3	-1.20	12.81	0.017	1.94E-03	10.1	5.2	
		0.17	0.017	1.94E-03	10.1	5.2	
4	-1.65	0.16	0.016	1.93E-03	10.2	9.7	
5	-2.10	0.15	0.015	1.92E-03	10.3	14.4	
6	-2.55	1.59	0.014	1.90E-03	10.7	20.0	
7	-3.00	8.78	0.013	1.88E-03	13.0	25.1	-1.0
		8.78	0.013	1.88E-03	12.0	25.1	
8	-3.70	19.93	0.012	1.83E-03	22.1	36.3	
9	-4.00	24.68	0.012	1.80E-03	28.7	43.9	
		-17.27	0.012	1.80E-03	28.7	43.9	
10	-4.80	-10.17	0.010	1.71E-03	17.8	61.4	
11	-5.60	-3.51	0.009	1.60E-03	12.3	72.4	
12	-6.20	1.14	0.008	1.50E-03	11.6	79.1	
13	-6.80	5.46	0.007	1.39E-03	13.6	86.3	
		-5.54	0.007	1.39E-03	13.6	86.3	
14	-7.10	-2.85	0.007	1.33E-03	12.3	90.1	
15	-7.80	2.93	0.006	1.19E-03	12.3	98.0	
		-32.64	0.006	1.19E-03	12.3	98.0	
16	-8.23	-26.32	0.005	1.10E-03	-0.2	100.3	
17	-8.65	-20.53	0.005	1.01E-03	-10.1	97.9	
18	-9.08	-15.27	0.004	9.23E-04	-17.8	91.7	

19	-9.50	-10.50	0.004	8.42E-04	-23.2	82.8
20	-10.00	-5.46	0.004	7.59E-04	-27.2	69.9
21	-10.60	-0.10	0.003	6.80E-04	-28.9	52.5
22	-11.20	4.66	0.003	6.22E-04	-27.5	35.2
23	-12.00	10.40	0.002	5.79E-04	-21.5	14.6
24	-12.80	15.75	0.002	5.66E-04	-11.0	0.7
25	-13.60	20.98	0.001	5.68E-04	3.7	-3.1
26	-14.05	23.90	0.001	5.69E-04	13.8	0.7
27	-14.50	26.79	0.001	5.64E-04	25.2	9.3
		-55.59	0.001	5.64E-04	25.2	9.3

Run ID. Section_2(BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.4 Install strut or anchor no.1 at elevation -3.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> kN/m2	<u>Wall</u> <u>disp.</u> m	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> kN/m	<u>Bending</u> <u>moment</u> kN.m/m	<u>Prop</u> <u>forces</u> kN/m
28	-15.25	-27.18	0.000	5.47E-04	-5.9	12.1	
29	-16.00	42.86	0.000	5.37E-04	0.0	-0.0	
At elev. -3.00				Prop force =	1.0	kN/m run	

LEFT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u> kN/m2	<u>Vertic</u> <u>-al</u> kN/m2	<u>Effective</u> <u>Active</u> <u>limit</u> kN/m2	<u>Effective</u> <u>Passive</u> <u>limit</u> kN/m2	<u>Earth</u> <u>pressure</u> kN/m2	<u>Total</u> <u>earth</u> <u>pressure</u> kN/m2	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> kN/m3
1	0.00	0.00	10.00	4.03	32.22	4.10	4.10	832
2	-0.60	0.00	20.81	8.38	67.03	8.45	8.45	832
3	-1.20	0.00	31.65	12.75	101.96	12.81	12.81	832
		0.00	31.65	0.00	173.38	0.17	0.17	2495
4	-1.65	0.00	40.72	0.00	202.61	0.16	0.16	2495
5	-2.10	0.00	49.83	0.00	231.96	0.15	0.15	2495
6	-2.55	0.00	58.98	0.30	261.44	1.59	1.59	2495
7	-3.00	0.00	68.16	3.56	291.01	8.78	8.78	2495
8	-3.70	0.00	82.48	8.66	337.15	19.93	19.93	2495
9	-4.00	0.00	88.63	10.85	356.95	24.68	24.68	2495
10	-4.80	0.00	105.01	16.68	409.75	37.26	37.26	2495
11	-5.60	0.00	121.37	22.51	462.46	49.64	49.64	2495
12	-6.20	0.00	133.61	26.87	501.89	58.77	58.77	2495
13	-6.80	0.00	145.81	31.21	541.20	67.74	67.74	2495
		0.00	145.81	31.23	784.48	45.38	45.38	3327
14	-7.10	0.00	151.90	32.78	815.89	49.32	49.32	3327
15	-7.80	7.00	159.06	34.59	852.85	55.14	62.14	3327
		7.00	159.06	34.59	852.85	38.98	45.98	6654
16	-8.23	11.25	164.23	35.90	879.54	44.17	55.42	6654
17	-8.65	15.50	169.38	37.21	906.14	49.11	64.61	6654
18	-9.08	19.75	174.52	38.51	932.64	53.82	73.57	6654
19	-9.50	24.00	179.64	39.81	959.04	58.31	82.31	6654
20	-10.00	29.00	185.63	41.33	990.00	63.33	92.33	6587
21	-10.60	35.00	192.80	43.15	1026.99	69.04	104.04	6587
22	-11.20	41.00	199.94	44.96	1063.84	74.49	115.49	6587
23	-12.00	49.00	209.43	47.37	1112.77	81.47	130.47	6587
24	-12.80	57.00	218.87	49.76	1161.50	88.29	145.29	6587
25	-13.60	65.00	228.28	52.15	1210.06	95.06	160.06	6587
26	-14.05	69.50	233.56	53.49	1237.32	98.86	168.36	6587
27	-14.50	74.00	238.83	54.82	1264.53	102.65	176.65	6587
		74.00	238.83	0.00	4954.24	0.00	74.00a	78472
28	-15.25	81.50	249.11	0.00	5074.92	0.00	81.50a	78472
29	-16.00	89.00	259.37	0.00	5195.43	42.87	131.87	78472

RIGHT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Effective</u> <u>Active</u> <u>limit</u>	<u>Effective</u> <u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>	<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>

		kN/m2	kN/m2	kN/m2	kN/m2	kN/m2	kN/m2	kN/m3
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	-0.60	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	-1.20	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	-1.65	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	-2.10	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	-2.55	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	-3.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	-3.70	0.00	0.00	0.00	0.00	0.00	0.00	0.0

Run ID. Section_2(BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.4 Install strut or anchor no.1 at elevation -3.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u>	<u>RIGHT side</u>				<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
			<u>Vertic</u> <u>-al</u>	<u>Active</u> <u>limit</u>	<u>Passive</u> <u>limit</u>	<u>Earth</u> <u>pressure</u>		
		kN/m2	kN/m2	kN/m2	kN/m2	kN/m2	kN/m2	kN/m3
9	-4.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	0.00	0.00	71.40	41.95	41.95	3883
10	-4.80	0.00	16.00	0.00	122.96	47.44	47.44	3883
11	-5.60	0.00	32.02	0.00	174.56	53.15	53.15	3883
12	-6.20	0.00	44.04	0.00	213.31	57.63	57.63	3883
13	-6.80	0.00	56.09	0.00	252.12	62.28	62.28	3883
		0.00	56.09	8.48	321.47	50.92	50.92	5178
14	-7.10	0.00	62.12	10.01	352.60	52.17	52.17	5178
15	-7.80	7.00	69.22	11.81	389.22	52.21	59.21	5178
		7.00	69.22	11.81	389.22	71.61	78.61	10356
16	-8.23	11.25	74.39	13.12	415.94	70.48	81.73	10356
17	-8.65	15.50	79.59	14.44	442.75	69.65	85.15	10356
18	-9.08	19.75	84.80	15.76	469.64	69.09	88.84	10356
19	-9.50	24.00	90.03	17.08	496.62	68.81	92.81	10356
20	-10.00	29.00	96.20	18.65	528.48	68.79	97.79	6587
21	-10.60	35.00	103.65	20.54	566.89	69.14	104.14	6587
22	-11.20	41.00	111.13	22.44	605.50	69.82	110.82	6587
23	-12.00	49.00	121.16	24.98	657.29	71.07	120.07	6587
24	-12.80	57.00	131.27	27.54	709.43	72.54	129.54	6587
25	-13.60	65.00	141.44	30.12	761.91	74.08	139.08	6587
26	-14.05	69.50	147.18	31.58	791.57	74.96	144.46	6587
27	-14.50	74.00	152.95	33.04	821.33	75.86	149.86	6587
		74.00	152.95	0.00	3945.51	55.59	129.59	78472
28	-15.25	81.50	164.10	0.00	4076.50	27.18	108.68	78472
29	-16.00	89.00	175.30	0.00	4208.04	0.01	89.01	78472


Note: 81.50 a Soil pressure at active limit
 123.45 p Soil pressure at passive limit

VAN der MEER CONSULTING
 Program: WALLAP Version 6.07 Revision A55.B74.R58
 Licensed from GEOSOLVE
 Data filename/Run ID: Section_2 (BH2)
 Penrith
 Section A


| Sheet No.
 | Job No. 220070
 | Made by : MS
 |
 | Date: 7-10-2022
 | Checked :

Units: kN,m

Stage No.4 Install prop no.1 at elev. -3.00



Stage No.4 Install prop no.1 at elev. -3.00



VAN der MEER CONSULTING

Program: WALLAP Version 6.07 Revision A55.B74.R58

Licensed from GEOSOLVE

Data filename/Run ID: Section_2 (BH2)

Penrith

Section A

| Sheet No.

| Job No. 220070


| Made by : MS

| Date: 7-10-2022

| Checked :

Units: kN,m

Stage No.5 Excav. to elev. -7.10 on RIGHT side



VAN der MEER CONSULTING	Sheet No.
Program: WALLAP Version 6.07 Revision A55.B74.R58	Job No. 220070
Licensed from GEOSOLVE	Made by : MS
Data filename/Run ID: Section_2(BH2)	
Penrith	Date: 7-10-2022
Section A	Checked :

Units: kN,m

Stage No. 5 Excavate to elevation -7.10 on RIGHT side

STABILITY ANALYSIS of Soldier Pile Wall according to Strength Factor method
Factor of safety on soil strength

Stage No.	Ground level Act.	Pass.	Prop Elev.	FoS for toe elev. = -16.00		Toe elev. for FoS = 1.000		Direction of failure
				Factor of Safety	Moment of equilib. at elev.	Toe elev.	Wall Penetr-ation	
5	0.00	-7.10	-3.00	4.445	n/a	-8.28	1.18	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Soldier Pile Wall

Analysis options

Soldier Pile width = 0.90m; spacing = 1.40m

Passive mobilisation factor = 3.000

Length of wall perpendicular to section = 1000.00m

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Rigid boundaries: Left side 20.00 from wall
Right side 20.00 from wall

Node no.	Y coord	Nett pressure kN/m ²	Wall disp. m	Wall rotation rad.	Shear force kN/m	Bending moment kN.m/m	Prop forces kN/m
1	0.00	4.03	0.021	1.08E-03	0.0	0.0	
2	-0.60	8.38	0.020	1.08E-03	3.7	1.1	
3	-1.20	12.75	0.019	1.08E-03	10.1	5.1	
		0.00	0.019	1.08E-03	10.1	5.1	
4	-1.65	0.00	0.019	1.07E-03	10.1	9.7	
5	-2.10	0.00	0.018	1.06E-03	10.1	14.2	
6	-2.55	0.30	0.018	1.04E-03	10.1	19.7	
7	-3.00	3.56	0.017	1.02E-03	11.0	24.3	-76.5
		3.56	0.017	1.02E-03	-65.5	24.3	
8	-3.70	13.00	0.017	1.02E-03	-59.7	-19.6	
9	-4.00	17.39	0.016	1.03E-03	-55.1	-36.9	
10	-4.80	29.15	0.015	1.13E-03	-36.5	-74.8	
11	-5.60	40.98	0.015	1.28E-03	-8.5	-94.1	
12	-6.20	49.91	0.014	1.40E-03	18.8	-91.5	
13	-6.80	58.89	0.013	1.50E-03	51.4	-71.0	
		33.57	0.013	1.50E-03	51.4	-71.0	
14	-7.10	37.62	0.012	1.55E-03	62.1	-54.0	
		5.58	0.012	1.55E-03	62.1	-54.0	
15	-7.80	1.90	0.011	1.59E-03	64.7	-8.6	
		-33.58	0.011	1.59E-03	64.7	-8.6	
16	-8.23	-39.63	0.011	1.59E-03	49.2	16.5	
17	-8.65	-36.13	0.010	1.57E-03	33.1	33.7	
18	-9.08	-32.77	0.009	1.53E-03	18.4	44.4	

19	-9.50	-29.58	0.009	1.49E-03	5.2	49.1
20	-10.00	-21.44	0.008	1.43E-03	-7.6	48.8
21	-10.60	-11.92	0.007	1.38E-03	-17.6	40.4
22	-11.20	-2.90	0.006	1.33E-03	-22.0	27.7
23	-12.00	8.60	0.005	1.30E-03	-19.7	9.1
24	-12.80	19.78	0.004	1.29E-03	-8.4	-3.9
25	-13.60	30.86	0.003	1.30E-03	11.9	-4.4
26	-14.05	37.07	0.002	1.30E-03	27.1	4.1
27	-14.50	43.23	0.002	1.29E-03	45.2	20.1
		-109.13	0.002	1.29E-03	45.2	20.1

Run ID. Section_2 (BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.5 Excavate to elevation -7.10 on RIGHT side

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> kN/m2	<u>Wall</u> <u>disp.</u> m	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> kN/m	<u>Bending</u> <u>moment</u> kN.m/m	<u>Prop</u> <u>forces</u> kN/m
28	-15.25	-42.80	0.001	1.26E-03	-11.8	22.9	
29	-16.00	74.17	0.000	1.24E-03	0.0	-0.0	
At elev. -3.00				Prop force =	76.5	kN/m run	

LEFT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u> kN/m2	<u>Vertic</u> <u>-al</u> kN/m2	<u>Effective</u> <u>Active</u> limit kN/m2	<u>Effective</u> <u>Passive</u> limit kN/m2	<u>Earth</u> <u>pressure</u> kN/m2	<u>Total</u> <u>earth</u> <u>pressure</u> kN/m2	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> kN/m3
1	0.00	0.00	10.00	4.03	32.22	4.03	4.03a	504
2	-0.60	0.00	20.81	8.38	67.03	8.38	8.38a	504
3	-1.20	0.00	31.65	12.75	101.96	12.75	12.75a	504
		0.00	31.65	0.00	173.38	0.00	0.00a	1513
4	-1.65	0.00	40.72	0.00	202.61	0.00	0.00a	1513
5	-2.10	0.00	49.83	0.00	231.96	0.00	0.00a	1513
6	-2.55	0.00	58.98	0.30	261.44	0.30	0.30a	1513
7	-3.00	0.00	68.16	3.56	291.01	3.56	3.56a	1513
8	-3.70	0.00	82.48	8.66	337.15	13.00	13.00	1513
9	-4.00	0.00	88.63	10.85	356.95	17.39	17.39	1513
10	-4.80	0.00	105.01	16.68	409.75	29.15	29.15	1513
11	-5.60	0.00	121.37	22.51	462.46	40.98	40.98	1513
12	-6.20	0.00	133.61	26.87	501.89	49.91	49.91	1513
13	-6.80	0.00	145.81	31.21	541.20	58.89	58.89	1513
		0.00	145.81	31.23	784.48	33.57	33.57	2017
14	-7.10	0.00	151.90	32.78	815.89	37.62	37.62	2017
15	-7.80	7.00	159.06	34.59	852.85	43.89	50.89	2017
		7.00	159.06	34.59	852.85	34.59	41.59a	4035
16	-8.23	11.25	164.23	35.90	879.54	35.90	47.15a	4035
17	-8.65	15.50	169.38	37.21	906.14	37.21	52.71a	4035
18	-9.08	19.75	174.52	38.51	932.64	38.51	58.26a	4035
19	-9.50	24.00	179.64	39.81	959.04	39.81	63.81a	4035
20	-10.00	29.00	185.63	41.33	990.00	45.92	74.92	4035
21	-10.60	35.00	192.80	43.15	1026.99	53.30	88.30	4035
22	-11.20	41.00	199.94	44.96	1063.84	60.46	101.46	4035
23	-12.00	49.00	209.43	47.37	1112.77	69.77	118.77	4035
24	-12.80	57.00	218.87	49.76	1161.50	78.95	135.95	4035
25	-13.60	65.00	228.28	52.15	1210.06	88.09	153.09	4035
26	-14.05	69.50	233.56	53.49	1237.32	93.23	162.73	4035
27	-14.50	74.00	238.83	54.82	1264.53	98.36	172.36	4035
		74.00	238.83	0.00	4954.24	0.00	74.00a	47633
28	-15.25	81.50	249.11	0.00	5074.92	0.00	81.50a	47633
29	-16.00	89.00	259.37	0.00	5195.43	74.17	163.17	3635061

RIGHT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Effective</u> <u>Active</u> limit	<u>Effective</u> <u>Passive</u> limit	<u>Earth</u> <u>pressure</u>	<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>

		kN/m2	kN/m2	kN/m2	kN/m2	kN/m2	kN/m2	kN/m3
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	-0.60	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	-1.20	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	-1.65	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	-2.10	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	-2.55	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	-3.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	-3.70	0.00	0.00	0.00	0.00	0.00	0.00	0.0

Run ID. Section_2(BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.5 Excavate to elevation -7.10 on RIGHT side

Node no.	Y coord	Water press. kN/m2	Effective stresses				Total earth pressure kN/m2	Coeff. of subgrade reaction kN/m3
			Vertic -al kN/m2	Active limit kN/m2	Passive limit kN/m2	Earth pressure kN/m2		
9	-4.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
10	-4.80	0.00	0.00	0.00	0.00	0.00	0.00	0.0
11	-5.60	0.00	0.00	0.00	0.00	0.00	0.00	0.0
12	-6.20	0.00	0.00	0.00	0.00	0.00	0.00	0.0
13	-6.80	0.00	0.00	0.00	0.00	0.00	0.00	0.0
14	-7.10	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	0.00	0.00	32.03	32.03	32.03p	2945
15	-7.80	7.00	7.00	0.00	68.17	41.98	48.98	2945
		7.00	7.00	0.00	68.17	68.17	75.17p	5890
16	-8.23	11.25	12.11	0.00	94.53	75.54	86.79	5890
17	-8.65	15.50	17.23	0.00	120.93	73.34	88.84	5890
18	-9.08	19.75	22.36	0.00	147.40	71.29	91.04	5890
19	-9.50	24.00	27.50	1.23	173.95	69.39	93.39	5890
20	-10.00	29.00	33.58	2.77	205.30	67.36	96.36	5890
21	-10.60	35.00	40.91	4.63	243.13	65.23	100.23	5890
22	-11.20	41.00	48.29	6.50	281.21	63.36	104.36	5890
23	-12.00	49.00	58.21	9.02	332.44	61.17	110.17	5890
24	-12.80	57.00	68.25	11.56	384.23	59.17	116.17	5890
25	-13.60	65.00	78.40	14.14	436.63	57.23	122.23	5890
26	-14.05	69.50	84.17	15.60	466.38	56.17	125.67	5890
27	-14.50	74.00	89.97	17.07	496.33	55.13	129.13	5890
		74.00	89.97	0.00	3205.79	109.13	183.13	70081
28	-15.25	81.50	101.23	0.00	3338.05	42.80	124.30	70081
29	-16.00	89.00	112.60	0.00	3471.56	0.00	89.00a	3635061


Note: 89.00 a Soil pressure at active limit
 75.17 p Soil pressure at passive limit

VAN der MEER CONSULTING
 Program: WALLAP Version 6.07 Revision A55.B74.R58
 Licensed from GEOSOLVE
 Data filename/Run ID: Section_2 (BH2)
 Penrith
 Section A


| Sheet No.
 | Job No. 220070
 | Made by : MS
 |
 | Date: 7-10-2022
 | Checked :

Units: kN,m

Stage No.5 Excav. to elev. -7.10 on RIGHT side



Stage No.5 Excav. to elev. -7.10 on RIGHT side



VAN der MEER CONSULTING

Program: WALLAP Version 6.07 Revision A55.B74.R58

Licensed from GEOSOLVE

Data filename/Run ID: Section_2 (BH2)

Penrith

Section A

| Sheet No.

| Job No. 220070


| Made by : MS

| Date: 7-10-2022

| Checked :

Units: kN,m

Stage No.7 Excav. to elev. -9.50 on RIGHT side



VAN der MEER CONSULTING	Sheet No.
Program: WALLAP Version 6.07 Revision A55.B74.R58	Job No. 220070
Licensed from GEOSOLVE	Made by : MS
Data filename/Run ID: Section_2(BH2)	
Penrith	Date: 7-10-2022
Section A	Checked :

Units: kN,m

Stage No. 7 Excavate to elevation -9.50 on RIGHT side

STABILITY ANALYSIS of Soldier Pile Wall according to Strength Factor method
Factor of safety on soil strength

Stage No.	Ground level Act.	Pass.	Prop Elev.	FoS for toe elev. = -16.00		Toe elev. for FoS = 1.000		Direction of failure
				Factor of Safety	Moment of equilib. at elev.	Toe elev.	Wall Penetration	
7	0.00	-9.50	-3.00	3.180	n/a	-11.53	2.03	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Soldier Pile Wall

Analysis options

Soldier Pile width = 0.90m; spacing = 1.40m

Passive mobilisation factor = 3.000

Length of wall perpendicular to section = 1000.00m

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Rigid boundaries: Left side 20.00 from wall
Right side 20.00 from wall

Node no.	Y coord	Nett pressure kN/m ²	Wall disp. m	Wall rotation rad.	Shear force kN/m	Bending moment kN.m/m	Prop forces kN/m
1	0.00	10.79	0.018	-6.22E-04	0.0	0.0	
2	-0.60	12.11	0.019	-6.23E-04	6.9	2.3	
3	-1.20	13.45	0.019	-6.31E-04	14.5	8.9	
		2.09	0.019	-6.31E-04	14.5	8.9	
4	-1.65	0.00	0.019	-6.43E-04	15.0	15.6	
5	-2.10	0.00	0.020	-6.61E-04	15.0	22.4	
6	-2.55	0.30	0.020	-6.87E-04	15.1	30.1	
7	-3.00	3.56	0.020	-7.20E-04	15.9	37.0	-129.9
		3.56	0.020	-7.20E-04	-113.9	37.0	
8	-3.70	8.66	0.021	-7.16E-04	-109.6	-41.1	
9	-4.00	10.85	0.021	-6.79E-04	-106.7	-73.6	
10	-4.80	19.51	0.021	-4.81E-04	-94.6	-154.3	
11	-5.60	29.35	0.022	-1.53E-04	-75.0	-223.1	
12	-6.20	36.97	0.022	1.63E-04	-55.1	-262.5	
13	-6.80	44.85	0.021	5.22E-04	-30.6	-288.6	
		31.23	0.021	5.22E-04	-30.6	-288.6	
14	-7.10	32.78	0.021	7.13E-04	-21.0	-296.4	
15	-7.80	41.59	0.021	1.16E-03	5.1	-301.2	
16	-8.23	47.15	0.020	1.44E-03	23.9	-294.4	
17	-8.65	52.71	0.019	1.70E-03	45.1	-280.0	
18	-9.08	58.26	0.019	1.95E-03	68.7	-256.1	
19	-9.50	63.81	0.018	2.17E-03	94.7	-221.6	
		31.78	0.018	2.17E-03	94.7	-221.6	

20	-10.00	-18.47	0.017	2.39E-03	98.0	-172.0
21	-10.60	-40.42	0.015	2.57E-03	80.3	-115.0
22	-11.20	-30.88	0.013	2.70E-03	58.9	-74.5
23	-12.00	-17.67	0.011	2.79E-03	39.5	-38.0
24	-12.80	3.71	0.009	2.84E-03	33.9	-10.3
25	-13.60	29.08	0.007	2.83E-03	47.0	18.0
26	-14.05	43.14	0.005	2.80E-03	63.3	42.1
27	-14.50	56.92	0.004	2.74E-03	85.8	75.0
		-256.80	0.004	2.74E-03	85.8	75.0
28	-15.25	-102.28	0.002	2.63E-03	-48.9	66.7

Run ID. Section_2(BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.7 Excavate to elevation -9.50 on RIGHT side

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> kN/m2	<u>Wall</u> <u>disp.</u> m	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> kN/m	<u>Bending</u> <u>moment</u> kN.m/m	<u>Prop</u> <u>forces</u> kN/m
29	-16.00	232.55	0.000	2.57E-03	0.0	-0.0	
At elev. -3.00				Prop force =	129.9	kN/m run	

LEFT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u> kN/m2	<u>Vertic</u> <u>-al</u> kN/m2	<u>Active</u> <u>limit</u> kN/m2	<u>Passive</u> <u>limit</u> kN/m2	<u>Earth</u> <u>pressure</u> kN/m2	kN/m2	kN/m3
1	0.00	0.00	10.00	4.03	32.22	10.79	10.79	3082
2	-0.60	0.00	20.81	8.38	67.03	12.11	12.11	3082
3	-1.20	0.00	31.65	12.75	101.96	13.45	13.45	3082
		0.00	31.65	0.00	173.38	2.09	2.09	9245
4	-1.65	0.00	40.72	0.00	202.61	0.00	0.00a	1640
5	-2.10	0.00	49.83	0.00	231.96	0.00	0.00a	1640
6	-2.55	0.00	58.98	0.30	261.44	0.30	0.30a	1640
7	-3.00	0.00	68.16	3.56	291.01	3.56	3.56a	1640
8	-3.70	0.00	82.48	8.66	337.15	8.66	8.66a	1640
9	-4.00	0.00	88.63	10.85	356.95	10.85	10.85a	1640
10	-4.80	0.00	105.01	16.68	409.75	19.51	19.51	1640
11	-5.60	0.00	121.37	22.51	462.46	29.35	29.35	1640
12	-6.20	0.00	133.61	26.87	501.89	36.97	36.97	1640
13	-6.80	0.00	145.81	31.21	541.20	44.85	44.85	1640
		0.00	145.81	31.23	784.48	31.23	31.23a	2186
14	-7.10	0.00	151.90	32.78	815.89	32.78	32.78a	2186
15	-7.80	7.00	159.06	34.59	852.85	34.59	41.59a	2186
		7.00	159.06	34.59	852.85	34.59	41.59a	4372
16	-8.23	11.25	164.23	35.90	879.54	35.90	47.15a	4372
17	-8.65	15.50	169.38	37.21	906.14	37.21	52.71a	4372
18	-9.08	19.75	174.52	38.51	932.64	38.51	58.26a	4372
19	-9.50	24.00	179.64	39.81	959.04	39.81	63.81a	4372
20	-10.00	29.00	185.63	41.33	990.00	41.33	70.33a	4372
21	-10.60	35.00	192.80	43.15	1026.99	43.15	78.15a	4372
22	-11.20	41.00	199.94	44.96	1063.84	44.96	85.96a	4372
23	-12.00	49.00	209.43	47.37	1112.77	47.37	96.37a	4372
24	-12.80	57.00	218.87	49.76	1161.50	57.75	114.75	4372
25	-13.60	65.00	228.28	52.15	1210.06	72.24	137.24	4372
26	-14.05	69.50	233.56	53.49	1237.32	80.34	149.84	4372
27	-14.50	74.00	238.83	54.82	1264.53	88.35	162.35	4372
		74.00	238.83	0.00	4954.24	0.00	74.00a	51734
28	-15.25	81.50	249.11	0.00	5074.92	0.00	81.50a	51734
29	-16.00	89.00	259.37	0.00	5195.43	203.55	292.55	4384164

RIGHT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u> kN/m2	<u>Vertic</u> <u>-al</u> kN/m2	<u>Active</u> <u>limit</u> kN/m2	<u>Passive</u> <u>limit</u> kN/m2	<u>Earth</u> <u>pressure</u> kN/m2	kN/m2	kN/m3

1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	-0.60	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	-1.20	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	-1.65	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	-2.10	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	-2.55	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	-3.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	-3.70	0.00	0.00	0.00	0.00	0.00	0.00	0.0
9	-4.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0

Run ID. Section_2 (BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.7 Excavate to elevation -9.50 on RIGHT side

Node no.	Y coord	Water press. kN/m2	Effective stresses				Total earth pressure kN/m2	Coeff. of subgrade reaction kN/m3
			Vertic -al kN/m2	Active limit kN/m2	Passive limit kN/m2	Earth pressure kN/m2		
10	-4.80	0.00	0.00	0.00	0.00	0.00	0.00	0.0
11	-5.60	0.00	0.00	0.00	0.00	0.00	0.00	0.0
12	-6.20	0.00	0.00	0.00	0.00	0.00	0.00	0.0
13	-6.80	0.00	0.00	0.00	0.00	0.00	0.00	0.0
14	-7.10	0.00	0.00	0.00	0.00	0.00	0.00	0.0
15	-7.80	0.00	0.00	0.00	0.00	0.00	0.00	0.0
16	-8.23	0.00	0.00	0.00	0.00	0.00	0.00	0.0
17	-8.65	0.00	0.00	0.00	0.00	0.00	0.00	0.0
18	-9.08	0.00	0.00	0.00	0.00	0.00	0.00	0.0
19	-9.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	0.00	0.00	32.03	32.03	32.03p	7668
20	-10.00	0.00	11.00	0.00	88.80	88.80	88.80p	7668
21	-10.60	6.00	18.21	0.00	126.02	112.57	118.57	7668
22	-11.20	12.00	25.45	0.71	163.36	104.84	116.84	7668
23	-12.00	20.00	35.16	3.17	213.45	94.03	114.03	7668
24	-12.80	28.00	44.95	5.65	264.01	83.04	111.04	7668
25	-13.60	36.00	54.86	8.17	315.16	72.16	108.16	7668
26	-14.05	40.50	60.50	9.60	344.23	66.20	106.70	7668
27	-14.50	45.00	66.18	11.04	373.54	60.43	105.43	7668
		45.00	66.18	0.00	2926.33	285.80	330.80	91497
28	-15.25	52.50	77.25	0.00	3056.39	131.28	183.78	91497
29	-16.00	60.00	88.47	0.00	3188.11	0.00	60.00a	4384164


Note: 60.00 a Soil pressure at active limit
 88.80 p Soil pressure at passive limit

VAN der MEER CONSULTING
 Program: WALLAP Version 6.07 Revision A55.B74.R58
 Licensed from GEOSOLVE
 Data filename/Run ID: Section_2 (BH2)
 Penrith
 Section A


| Sheet No.
 | Job No. 220070
 | Made by : MS
 |
 | Date: 7-10-2022
 | Checked :

Units: kN,m

Stage No.7 Excav. to elev. -9.50 on RIGHT side



Stage No.7 Excav. to elev. -9.50 on RIGHT side



VAN der MEER CONSULTING	Sheet No.
Program: WALLAP Version 6.07 Revision A55.B74.R58	Job No. 220070
Licensed from GEOSOLVE	Made by : MS
Data filename/Run ID: Section_2(BH2)	
Penrith	Date: 7-10-2022
Section A	Checked :

Units: kN,m

Summary of results

STABILITY ANALYSIS of Soldier Pile Wall according to Strength Factor method
 Factor of safety on soil strength

			FoS for toe		Toe elev. for			
			elev. = -16.00		FoS = 1.000			
<u>Stage</u>	<u>Ground level</u>		<u>Prop</u>	<u>Factor</u>	<u>Moment</u>	<u>Toe</u>	<u>Wall</u>	<u>Direction</u>
<u>No.</u>	<u>Act.</u>	<u>Pass.</u>	<u>Elev.</u>	<u>of</u>	<u>equilib.</u>	<u>elev.</u>	<u>Penetr</u>	<u>of</u>
				<u>Safety</u>	<u>at elev.</u>		<u>-ation</u>	<u>failure</u>
1	0.00	0.00	Cant.	<u>Conditions not suitable for FoS calc.</u>				
2	0.00	0.00	Cant.	<u>Conditions not suitable for FoS calc.</u>				
3	0.00	-4.00	Cant.	3.063	-15.12	-5.28	1.28	L to R
4	0.00	-4.00	-3.00	<u>Conditions not suitable for FoS calc.</u>				
5	0.00	-7.10	-3.00	4.445	n/a	-8.28	1.18	L to R
6	0.00	-7.10	-3.00	4.797	n/a	-7.98	0.88	L to R
7	0.00	-9.50	-3.00	3.180	n/a	-11.53	2.03	L to R

VAN der MEER CONSULTING	Sheet No.
Program: WALLAP Version 6.07 Revision A55.B74.R58	Job No. 220070
Licensed from GEOSOLVE	Made by : MS
Data filename/Run ID: Section_2(BH2)	
Penrith	Date: 7-10-2022
Section A	Checked :

Units: kN,m

Summary of results

BENDING MOMENT and DISPLACEMENT ANALYSIS of Soldier Pile Wall

Analysis options

Soldier Pile width = 0.90m; spacing = 1.40m
 Passive mobilisation factor = 3.000
 Length of wall perpendicular to section = 1000.00m
 Subgrade reaction model - Boussinesq Influence coefficients
 Soil deformations are elastic until the active or passive limit is reached

Rigid boundaries: Left side 20.00 from wall
 Right side 20.00 from wall

Bending moment, shear force and displacement envelopes

Node no.	Y coord	Displacement		Bending moment		Shear force	
		maximum	minimum	maximum	minimum	maximum	minimum
		m	m	kN.m/m	kN.m/m	kN/m	kN/m
1	0.00	0.021	0.000	0.0	0.0	0.0	0.0
2	-0.60	0.020	0.000	2.3	0.0	6.9	0.0
3	-1.20	0.019	0.000	8.9	0.0	14.5	0.0
4	-1.65	0.019	0.000	15.6	0.0	15.0	0.0
5	-2.10	0.020	0.000	22.4	0.0	15.0	0.0
6	-2.55	0.020	0.000	30.1	0.0	15.1	0.0
7	-3.00	0.020	0.000	37.0	0.0	15.9	-113.9
8	-3.70	0.021	0.000	36.3	-41.1	22.6	-109.6
9	-4.00	0.021	0.000	44.1	-73.6	29.3	-106.7
10	-4.80	0.021	0.000	61.9	-154.3	18.1	-94.6
11	-5.60	0.022	0.000	73.1	-223.1	12.5	-75.0
12	-6.20	0.022	0.000	79.9	-262.5	18.8	-55.1
13	-6.80	0.021	0.000	87.1	-288.6	51.4	-30.6
14	-7.10	0.021	0.000	91.0	-296.4	62.1	-21.0
15	-7.80	0.021	0.000	98.9	-301.2	64.7	0.0
16	-8.23	0.020	0.000	101.2	-294.4	49.2	-0.3
17	-8.65	0.019	0.000	98.7	-280.0	45.1	-10.3
18	-9.08	0.019	0.000	92.4	-256.1	68.7	-17.9
19	-9.50	0.018	0.000	83.4	-221.6	94.7	-23.4
20	-10.00	0.017	0.000	70.4	-172.0	98.0	-27.4
21	-10.60	0.015	0.000	53.0	-115.0	80.3	-29.0
22	-11.20	0.013	0.000	35.6	-74.5	58.9	-27.7
23	-12.00	0.011	0.000	14.9	-38.0	39.5	-21.6
24	-12.80	0.009	0.000	2.3	-38.3	33.9	-11.1
25	-13.60	0.007	0.000	18.0	-30.8	47.0	-0.5
26	-14.05	0.005	0.000	42.1	-15.8	63.3	-0.0
27	-14.50	0.004	0.000	75.0	0.0	85.8	0.0
28	-15.25	0.002	0.000	66.7	0.0	0.0	-48.9
29	-16.00	0.000	-0.000	0.0	-0.0	0.0	0.0

Maximum and minimum bending moment and shear force at each stage

Stage	-----	Bending moment	-----	-----	Shear force	-----
no.		<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	<u>maximum</u>
						<u>minimum</u>
						<u>elev.</u>

	kN.m/m		kN.m/m		kN/m		kN/m	
1	8.2	-8.23	-0.0	-16.00	3.1	-1.20	-1.7	-11.20
2	4.0	-2.55	-3.9	-12.80	5.0	-14.50	-2.1	-10.60
3	101.2	-8.23	-3.0	-13.60	29.3	-4.00	-29.0	-10.60
4	100.3	-8.23	-3.1	-13.60	28.7	-4.00	-28.9	-10.60
5	49.1	-9.50	-94.1	-5.60	64.7	-7.80	-65.5	-3.00
6	27.3	-3.00	-101.9	-6.20	65.7	-14.50	-68.6	-3.00
7	75.0	-14.50	-301.2	-7.80	98.0	-10.00	-113.9	-3.00

Run ID. Section_2(BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

Summary of results (continued)

Maximum and minimum displacement at each stage

Stage ----- Displacement -----

no.	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	<u>Stage description</u>
	m		m		
1	0.002	0.00	-0.000	-16.00	Apply surcharge no.1 at elev. 0.00
2	0.002	0.00	0.000	0.00	Apply surcharge no.2 at elev. 0.00
3	0.019	0.00	0.000	0.00	Excav. to elev. -4.00 on RIGHT side
4	0.019	0.00	0.000	0.00	Install prop no.1 at elev. -3.00
5	0.021	0.00	0.000	0.00	Excav. to elev. -7.10 on RIGHT side
6	0.020	0.00	0.000	0.00	Apply water pressure profile no.1
7	0.022	-5.60	0.000	0.00	Excav. to elev. -9.50 on RIGHT side

Prop forces at each stage (horizontal components)


Stage --- Strut no. 1 ---

no.	at elev.-3.00	
	kN/m run	kN/prop
4	1.00	1.00
5	76.49	76.49
6	81.00	81.00
7	129.86	129.86

VAN der MEER CONSULTING
 Program: WALLAP Version 6.07 Revision A55.B74.R58
 Licensed from GEOSOLVE
 Data filename/Run ID: Section_2 (BH2)
 Penrith
 Section A

| Sheet No.
 | Job No. 220070
 | Made by : MS
 | Date: 7-10-2022
 | Checked :

Units: kN,m



A.2. Section_6 (BH6)

VAN der MEER CONSULTING
 Program: WALLAP Version 6.07 Revision A55.B74.R58
 Licensed from GEOSOLVE
 Data filename/Run ID: Section_2 (BH2)
 Penrith
 Section A

| Sheet No.
 | Job No. 220070
 | Made by : MS
 | Date: 7-10-2022
 | Checked :

Units: kN,m

INPUT DATA

SOIL PROFILE

Stratum no.	Elevation of top of stratum	Soil types	
		Left side	Right side
1	0.00	1 Fill	1 Fill
2	-1.20	2 Silty Clay	2 Silty Clay

3	-3.70	2	Silty Clay	2	Silty Clay
4	-6.80	3	Silty Sand	3	Silty Sand
5	-7.80	5	Sandy Gravel	5	Sandy Gravel
6	-14.50	6	Sandstone (medium)	6	Sandstone (medium)

SOIL PROPERTIES

-- Soil type --	Bulk density	Young's Modulus	At rest coeff.	Consol state.	Active limit	Passive limit	Cohesion
No. Description (Datum elev.)	kN/m3	Eh, kN/m2 (dEh/dy)	Ko (dKo/dy)	NC/OC (Nu)	Ka (Kac)	Kp (Kpc)	kN/m2 (dc/dy)
1 Fill	18.00	5000	0.580	OC (0.300)	0.403 (0.000)	3.222 (0.000)	
2 Silty Clay	20.00	15000	0.580	OC (0.300)	0.356 (1.380)	3.222 (4.760)	15.00d
3 Silty Sand	20.00	20000	0.450	OC (0.300)	0.254 (1.149)	5.160 (6.407)	5.000d
4 Not defined							
5 Sandy Gravel	22.00	40000	0.450	OC (0.300)	0.254 (1.149)	5.160 (6.407)	5.000d
6 Sandstone(-medium)	24.00	500000	0.000	OC (0.250)	0.151 (0.849)	11.75 (10.745)	200.0d

Additional soil parameters associated with Ka and Kp

--- parameters for Ka ---				--- parameters for Kp ---			
Soil	Wall	Back-	fill	Soil	Wall	Back-	fill
No. Description	friction angle	adhesion coeff.	angle	friction angle	adhesion coeff.	angle	angle
1 Fill	25.00	0.022	0.00	25.00	0.475	0.00	
2 Silty Clay	25.00	0.575	0.00	25.00	0.475	0.00	
3 Silty Sand	33.00	0.554	0.00	33.00	0.456	0.00	
4 Not defined							
5 Sandy Gravel	33.00	0.554	0.00	33.00	0.456	0.00	
6 Sandstone (medium)	45.00	0.364	0.00	45.00	0.364	0.00	

GROUND WATER CONDITIONS

Density of water = 10.00 kN/m3

	Left side	Right side
Initial water table elevation	-7.10	-7.10

Automatic water pressure balancing at toe of wall : No

Left side				Right side			
Water press.	Point no.	Elev. m	Piezo elev. m	Water press.	Point no.	Elev. m	Piezo elev. m
	1	-7.10	-7.10		1	-10.00	-10.00

WALL PROPERTIES

Type of structure = Soldier Pile Wall
 Soldier Pile width = 0.90 m
 Soldier Pile spacing = 1.40 m
 Passive mobilisation factor = 3.00
 Elevation of toe of wall = -16.00
 Maximum finite element length = 0.80 m
 Youngs modulus of wall E = 2.0000E+07 kN/m2
 Moment of inertia of wall I = 0.023000 m4/m run
 = 0.032200 m4 per pile

E.I = 460000 kN.m²/m run
Yield Moment of wall = Not defined

STRUTS and ANCHORS

Prop no.	Elev.	Prop spacing m	Cross- section area sq.m	Youngs modulus kN/m2	Free length m	Inclin -ation (degs)	Pre- stress /prop kN	Strut or Anchor	Allow tension ?	L/R
1	-3.00	1.00	0.350000	2.000E+07	370.0	0.00	1.00	Strut	Yes	R

SURCHARGE LOADS

Surch -arge no.	Elev.	Distance from wall	Length parallel to wall	Width perpend. to wall	Surcharge ----- Near edge	Surcharge ----- Far edge	Equiv. soil type	Partial factor/ Category
1	0.00	0.00 (L)	30.00	5.00	10.00	=	N/A	N/A
2	0.00	5.00 (L)	30.00	15.00	20.00	=	N/A	N/A

Note: L = Left side, R = Right side

CONSTRUCTION STAGES

Construction stage no.	Stage description
1	Apply surcharge no.1 at elevation 0.00
2	Apply surcharge no.2 at elevation 0.00
3	Excavate to elevation -4.00 on RIGHT side
4	Install strut or anchor no.1 at elevation -3.00
5	Excavate to elevation -7.10 on RIGHT side
6	Apply water pressure profile no.1
7	Excavate to elevation -9.50 on RIGHT side

FACTORS OF SAFETY and ANALYSIS OPTIONS

Stability analysis:

Method of analysis - Strength Factor method

Factor on soil strength for calculating wall depth = 1.00

Parameters for undrained strata:

Minimum equivalent fluid density = 5.00 kN/m3

Maximum depth of water filled tension crack = 0.00 m

Bending moment and displacement calculation:

Method - Subgrade reaction model using Influence Coefficients

Open Tension Crack analysis? - No

Non-linear Modulus Parameter (L) = 0 m

Boundary conditions:

Length of wall (normal to plane of analysis) = 1000.00 m

Width of excavation on Left side of wall = 20.00 m

Width of excavation on Right side of wall = 20.00 m

Distance to rigid boundary on Left side = 20.00 m

Distance to rigid boundary on Right side = 20.00 m

OUTPUT OPTIONS

Stage no.	----- Stage description	----- Output options
		Displacement Active, Graph.
		Bending mom. Passive output
		Shear force pressures

1 Apply surcharge no.1 at elev. 0.00	Yes	Yes	Yes
2 Apply surcharge no.2 at elev. 0.00	Yes	Yes	Yes
3 Excav. to elev. -4.00 on RIGHT side	Yes	Yes	Yes
4 Install prop no.1 at elev. -3.00	Yes	Yes	Yes
5 Excav. to elev. -7.10 on RIGHT side	Yes	Yes	Yes
6 Apply water pressure profile no.1	Yes	Yes	Yes
7 Excav. to elev. -9.50 on RIGHT side	Yes	Yes	Yes
* Summary output	Yes	-	Yes

Program WALLAP - Copyright (C) 2020 by DL Borin, distributed by GEOSOLVE
 150 St. Alphonsus Road, London SW4 7BW, UK www.geosolve.co.uk

VAN der MEER CONSULTING

Program: WALLAP Version 6.07 Revision A55.B74.R58

Licensed from GEOSOLVE

Data filename/Run ID: Section_2 (BH2)

Penrith

Section A

| Sheet No.

| Job No. 220070


| Made by : MS

| Date: 7-10-2022

| Checked :

Units: kN,m

Stage No.1 Apply surcharge no.1 at elev. 0.00



VAN der MEER CONSULTING	Sheet No.
Program: WALLAP Version 6.07 Revision A55.B74.R58	Job No. 220070
Licensed from GEOSOLVE	Made by : MS
Data filename/Run ID: Section_2(BH2)	
Penrith	Date: 7-10-2022
Section A	Checked :

Units: kN,m

Stage No. 1 Apply surcharge no.1 at elevation 0.00

STABILITY ANALYSIS of Soldier Pile Wall according to Strength Factor method
Factor of safety on soil strength

			FoS for toe elev. = -16.00		Toe elev. for FoS = 1.000		
<u>Stage</u> <u>No.</u>	<u>Ground level</u> <u>Act.</u> <u>Pass.</u>	<u>Prop</u> <u>Elev.</u>	<u>Factor</u> <u>of</u> <u>Safety</u>	<u>Moment</u> <u>equilib.</u> <u>at elev.</u>	<u>Toe</u> <u>elev.</u>	<u>Wall</u> <u>Penetr</u> <u>-ation</u>	<u>Direction</u> <u>of</u> <u>failure</u>
1	0.00 0.00	Cant.	Conditions not suitable for FoS calc.				

BENDING MOMENT and DISPLACEMENT ANALYSIS of Soldier Pile Wall

Analysis options

Soldier Pile width = 0.90m; spacing = 1.40m

Passive mobilisation factor = 3.000

Length of wall perpendicular to section = 1000.00m

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Rigid boundaries: Left side 20.00 from wall
Right side 20.00 from wall

Node no.	Y coord	Nett pressure kN/m ²	Wall disp. m	Wall rotation rad.	Shear force kN/m	Bending moment kN.m/m	Prop forces kN/m
1	0.00	4.03	0.002	1.83E-04	0.0	0.0	
2	-0.60	2.06	0.001	1.82E-04	1.8	0.7	
3	-1.20	2.21	0.001	1.80E-04	3.1	2.2	
		-1.91	0.001	1.80E-04	3.1	2.2	
4	-1.65	-1.57	0.001	1.78E-04	2.3	3.4	
5	-2.10	-1.27	0.001	1.74E-04	1.7	4.3	
6	-2.55	-0.99	0.001	1.69E-04	1.2	4.9	
7	-3.00	-0.73	0.001	1.64E-04	0.8	5.3	
8	-3.70	-0.39	0.001	1.56E-04	0.4	5.7	
9	-4.00	-0.25	0.001	1.52E-04	0.3	5.8	
10	-4.80	0.06	0.001	1.42E-04	0.2	6.0	
11	-5.60	0.34	0.001	1.31E-04	0.4	6.1	
12	-6.20	0.52	0.001	1.23E-04	0.6	6.4	
13	-6.80	0.69	0.001	1.15E-04	1.0	6.9	
		-0.08	0.001	1.15E-04	1.0	6.9	
14	-7.10	0.05	0.000	1.10E-04	1.0	7.2	
15	-7.80	0.32	0.000	9.89E-05	1.1	7.9	
		-2.10	0.000	9.89E-05	1.1	7.9	
16	-8.23	-1.71	0.000	9.15E-05	0.3	8.2	
17	-8.65	-1.35	0.000	8.40E-05	-0.3	8.2	
18	-9.08	-1.03	0.000	7.66E-05	-0.8	7.9	
19	-9.50	-0.74	0.000	6.95E-05	-1.2	7.4	
20	-10.00	-0.45	0.000	6.18E-05	-1.5	6.7	

21	-10.60	-0.14	0.000	5.37E-05	-1.7	5.7
22	-11.20	0.12	0.000	4.69E-05	-1.7	4.7
23	-12.00	0.41	0.000	3.99E-05	-1.5	3.4
24	-12.80	0.65	0.000	3.50E-05	-1.1	2.3
25	-13.60	0.86	0.000	3.16E-05	-0.5	1.6
26	-14.05	0.97	0.000	3.00E-05	-0.0	1.5
27	-14.50	1.08	0.000	2.85E-05	0.4	1.6
		-2.82	0.000	2.85E-05	0.4	1.6
28	-15.25	-1.34	0.000	2.63E-05	-1.1	1.1
29	-16.00	4.36	-0.000	2.53E-05	0.0	-0.0

Run ID. Section_2(BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.1 Apply surcharge no.1 at elevation 0.00

LEFT side								
Node no.	Y coord	Water press. kN/m2	Vertic -al kN/m2	Effective stresses		Earth pressure kN/m2	Total earth pressure kN/m2	Coeff. of subgrade reaction kN/m3
				Active limit kN/m2	Passive limit kN/m2			
1	0.00	0.00	10.00	4.03	32.22	4.03	4.03a	760
2	-0.60	0.00	20.79	8.38	66.98	9.44	9.44	760
3	-1.20	0.00	31.54	12.71	101.62	15.76	15.76	760
		0.00	31.54	0.00	173.04	13.71	13.71	2280
4	-1.65	0.00	40.46	0.00	201.77	19.07	19.07	2280
5	-2.10	0.00	49.34	0.00	230.37	24.42	24.42	2280
6	-2.55	0.00	58.17	0.01	258.81	29.75	29.75	2280
7	-3.00	0.00	66.96	3.14	287.13	35.05	35.05	2280
8	-3.70	0.00	80.57	7.98	330.99	43.26	43.26	2280
9	-4.00	0.00	86.38	10.05	349.73	46.76	46.76	2280
10	-4.80	0.00	101.87	15.57	399.62	56.09	56.09	2280
11	-5.60	0.00	117.34	21.07	449.47	65.40	65.40	2280
12	-6.20	0.00	128.95	25.21	486.87	72.36	72.36	2280
13	-6.80	0.00	140.57	29.34	524.32	79.32	79.32	2280
		0.00	140.57	29.90	757.45	61.57	61.57	3041
14	-7.10	0.00	146.39	31.38	787.47	64.30	64.30	3041
15	-7.80	7.00	152.98	33.05	821.47	67.49	74.49	3041
		7.00	152.98	33.05	821.47	66.29	73.29	6081
16	-8.23	11.25	157.84	34.28	846.57	68.73	79.98	6081
17	-8.65	15.50	162.71	35.52	871.72	71.15	86.65	6081
18	-9.08	19.75	167.60	36.76	896.91	73.56	93.31	6081
19	-9.50	24.00	172.49	38.00	922.15	75.95	99.95	6081
20	-10.00	29.00	178.25	39.46	951.91	78.75	107.75	6081
21	-10.60	35.00	185.19	41.22	987.70	82.09	117.09	6081
22	-11.20	41.00	192.14	42.98	1023.57	85.41	126.41	6081
23	-12.00	49.00	201.43	45.34	1071.52	89.80	138.80	6081
24	-12.80	57.00	210.75	47.70	1119.60	94.18	151.18	6081
25	-13.60	65.00	220.09	50.07	1167.79	98.55	163.55	6081
26	-14.05	69.50	225.35	51.40	1194.95	101.01	170.51	6081
27	-14.50	74.00	230.62	52.74	1222.14	103.46	177.46	6081
		74.00	230.62	0.00	4857.74	0.00	74.00a	72380
28	-15.25	81.50	240.91	0.00	4978.65	0.00	81.50a	72380
29	-16.00	89.00	251.22	0.00	5099.73	4.36	93.36	4065999

RIGHT side								
Node no.	Y coord	Water press. kN/m2	Vertic -al kN/m2	Effective stresses		Earth pressure kN/m2	Total earth pressure kN/m2	Coeff. of subgrade reaction kN/m3
				Active limit kN/m2	Passive limit kN/m2			
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	760
2	-0.60	0.00	10.80	4.35	34.79	7.38	7.38	760
3	-1.20	0.00	21.60	8.70	69.58	13.56	13.56	760
		0.00	21.60	0.00	141.00	15.61	15.61	2280
4	-1.65	0.00	30.60	0.00	169.99	20.65	20.65	2280
5	-2.10	0.00	39.60	0.00	198.99	25.69	25.69	2280

6	-2.55	0.00	48.60	0.00	227.99	30.73	30.73	2280
7	-3.00	0.00	57.60	0.00	256.99	35.78	35.78	2280
8	-3.70	0.00	71.60	4.79	302.10	43.64	43.64	2280
9	-4.00	0.00	77.60	6.93	321.43	47.02	47.02	2280
10	-4.80	0.00	93.60	12.62	372.98	56.03	56.03	2280
11	-5.60	0.00	109.60	18.32	424.53	65.06	65.06	2280
12	-6.20	0.00	121.60	22.59	463.20	71.84	71.84	2280
13	-6.80	0.00	133.60	26.86	501.86	78.64	78.64	2280
		0.00	133.60	28.14	721.47	61.65	61.65	3041

Run ID. Section_2(BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.1 Apply surcharge no.1 at elevation 0.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u> kN/m2	<u>RIGHT side</u> <u>Effective stresses</u>				<u>Total</u> <u>earth</u> <u>pressure</u> kN/m2	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> kN/m3
			<u>Vertic</u> <u>-al</u> kN/m2	<u>Active</u> <u>limit</u> kN/m2	<u>Passive</u> <u>limit</u> kN/m2	<u>Earth</u> <u>pressure</u> kN/m2		
14	-7.10	0.00	139.60	29.66	752.43	64.25	64.25	3041
15	-7.80	7.00	146.60	31.43	788.56	67.18	74.18	3041
		7.00	146.60	31.43	788.56	68.39	75.39	6081
16	-8.23	11.25	151.70	32.73	814.88	70.44	81.69	6081
17	-8.65	15.50	156.80	34.02	841.19	72.50	88.00	6081
18	-9.08	19.75	161.90	35.31	867.51	74.59	94.34	6081
19	-9.50	24.00	167.00	36.61	893.83	76.70	100.70	6081
20	-10.00	29.00	173.00	38.13	924.79	79.20	108.20	6081
21	-10.60	35.00	180.20	39.95	961.95	82.23	117.23	6081
22	-11.20	41.00	187.40	41.78	999.10	85.29	126.29	6081
23	-12.00	49.00	197.00	44.21	1048.65	89.39	138.39	6081
24	-12.80	57.00	206.60	46.65	1098.19	93.53	150.53	6081
25	-13.60	65.00	216.20	49.08	1147.73	97.69	162.69	6081
26	-14.05	69.50	221.60	50.45	1175.59	100.04	169.54	6081
27	-14.50	74.00	227.00	51.82	1203.46	102.39	176.39	6081
		74.00	227.00	0.00	4815.23	2.82	76.82	72380
28	-15.25	81.50	237.50	0.00	4938.56	1.34	82.84	72380
29	-16.00	89.00	248.00	0.00	5061.88	0.00	89.00a	4065999


Note: 89.00 a Soil pressure at active limit
 123.45 p Soil pressure at passive limit

VAN der MEER CONSULTING
 Program: WALLAP Version 6.07 Revision A55.B74.R58
 Licensed from GEOSOLVE
 Data filename/Run ID: Section_2 (BH2)
 Penrith
 Section A


| Sheet No.
 | Job No. 220070
 | Made by : MS
 |
 | Date: 7-10-2022
 | Checked :

Units: kN,m

Stage No.1 Apply surcharge no.1 at elev. 0.00




Stage No.1 Apply surcharge no.1 at elev. 0.00



VAN der MEER CONSULTING	Sheet No.
Program: WALLAP Version 6.07 Revision A55.B74.R58	Job No. 220070
Licensed from GEOSOLVE	Made by : MS
Data filename/Run ID: Section_2 (BH2)	
Penrith	Date: 7-10-2022
Section A	Checked :

Units: kN,m

Stage No.2 Apply surcharge no.2 at elev. 0.00



VAN der MEER CONSULTING	Sheet No.
Program: WALLAP Version 6.07 Revision A55.B74.R58	Job No. 220070
Licensed from GEOSOLVE	Made by : MS
Data filename/Run ID: Section_2(BH2)	
Penrith	Date: 7-10-2022
Section A	Checked :

Units: kN,m

Stage No. 2 Apply surcharge no.2 at elevation 0.00

STABILITY ANALYSIS of Soldier Pile Wall according to Strength Factor method
Factor of safety on soil strength

				FoS for toe elev. = -16.00	Toe elev. for FoS = 1.000	
<u>Stage</u>	<u>Ground level</u>	<u>Prop</u>	<u>Wall</u>	<u>Factor</u>	<u>Moment</u>	<u>Toe</u>
<u>No.</u>	<u>Act.</u>	<u>Pass.</u>	<u>Elev.</u>	<u>of</u>	<u>equilib.</u>	<u>elev.</u>
				<u>Safety</u>	<u>at elev.</u>	<u>Penetr</u>
						<u>-ation</u>
						<u>failure</u>
2	0.00	0.00	Cant.	<u>Conditions not suitable for FoS calc.</u>		

BENDING MOMENT and DISPLACEMENT ANALYSIS of Soldier Pile Wall

Analysis options

Soldier Pile width = 0.90m; spacing = 1.40m

Passive mobilisation factor = 3.000

Length of wall perpendicular to section = 1000.00m

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Rigid boundaries: Left side 20.00 from wall
Right side 20.00 from wall

<u>Node</u>	<u>Y</u>	<u>Nett</u>	<u>Wall</u>	<u>Wall</u>	<u>Shear</u>	<u>Bending</u>	<u>Prop</u>
<u>no.</u>	<u>coord</u>	<u>pressure</u>	<u>disp.</u>	<u>rotation</u>	<u>force</u>	<u>moment</u>	<u>forces</u>
		kN/m2	m	rad.	kN/m	kN.m/m	kN/m
1	0.00	4.03	0.002	1.36E-04	0.0	0.0	
2	-0.60	1.85	0.002	1.36E-04	1.8	0.7	
3	-1.20	2.01	0.002	1.34E-04	2.9	2.1	
		-2.58	0.002	1.34E-04	2.9	2.1	
4	-1.65	-2.24	0.002	1.31E-04	1.8	3.2	
5	-2.10	-1.89	0.001	1.28E-04	0.9	3.8	
6	-2.55	-1.53	0.001	1.24E-04	0.1	4.0	
7	-3.00	-1.16	0.001	1.20E-04	-0.5	3.9	
8	-3.70	-0.59	0.001	1.14E-04	-1.1	3.3	
9	-4.00	-0.35	0.001	1.12E-04	-1.2	3.0	
10	-4.80	0.27	0.001	1.08E-04	-1.3	1.9	
11	-5.60	0.86	0.001	1.06E-04	-0.8	1.0	
12	-6.20	1.27	0.001	1.04E-04	-0.2	0.7	
13	-6.80	1.66	0.001	1.03E-04	0.7	0.8	
		0.47	0.001	1.03E-04	0.7	0.8	
14	-7.10	0.70	0.001	1.03E-04	0.9	1.1	
15	-7.80	1.21	0.001	1.01E-04	1.6	1.9	
		-2.92	0.001	1.01E-04	1.6	1.9	
16	-8.23	-2.38	0.001	9.91E-05	0.4	2.3	
17	-8.65	-1.87	0.001	9.70E-05	-0.5	2.2	
18	-9.08	-1.39	0.001	9.51E-05	-1.2	1.9	
19	-9.50	-0.94	0.001	9.36E-05	-1.7	1.3	
20	-10.00	-0.44	0.001	9.28E-05	-2.0	0.3	

21	-10.60	0.12	0.001	9.32E-05	-2.1	-1.0
22	-11.20	0.66	0.001	9.53E-05	-1.9	-2.2
23	-12.00	1.35	0.000	1.00E-04	-1.1	-3.5
24	-12.80	2.03	0.000	1.06E-04	0.3	-3.9
25	-13.60	2.72	0.000	1.12E-04	2.2	-3.0
26	-14.05	3.12	0.000	1.15E-04	3.5	-1.8
27	-14.50	3.51	0.000	1.15E-04	5.0	0.1
		-9.23	0.000	1.15E-04	5.0	0.1
28	-15.25	-4.89	0.000	1.14E-04	-0.3	1.2
29	-16.00	5.70	0.000	1.13E-04	0.0	-0.0

Run ID. Section_2(BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.2 Apply surcharge no.2 at elevation 0.00

LEFT side								
Node no.	Y coord	Water press. kN/m2	Effective stresses				Total earth pressure kN/m2	Coeff. of subgrade reaction kN/m3
			Vertic -al kN/m2	Active limit kN/m2	Passive limit kN/m2	Earth pressure kN/m2		
1	0.00	0.00	10.00	4.03	32.22	4.03	4.03a	459
2	-0.60	0.00	20.81	8.38	67.03	9.33	9.33	459
3	-1.20	0.00	31.65	12.75	101.96	15.69	15.69	459
		0.00	31.65	0.00	173.38	13.39	13.39	1378
4	-1.65	0.00	40.72	0.00	202.61	18.80	18.80	1378
5	-2.10	0.00	49.83	0.00	231.96	24.22	24.22	1378
6	-2.55	0.00	58.98	0.30	261.44	29.65	29.65	1378
7	-3.00	0.00	68.16	3.56	291.01	35.09	35.09	1378
8	-3.70	0.00	82.48	8.66	337.15	43.56	43.56	1378
9	-4.00	0.00	88.63	10.85	356.95	47.19	47.19	1378
10	-4.80	0.00	105.01	16.68	409.75	56.87	56.87	1378
11	-5.60	0.00	121.37	22.51	462.46	66.52	66.52	1378
12	-6.20	0.00	133.61	26.87	501.89	73.74	73.74	1378
13	-6.80	0.00	145.81	31.21	541.20	80.93	80.93	1378
		0.00	145.81	31.23	784.48	62.97	62.97	1837
14	-7.10	0.00	151.90	32.78	815.89	65.81	65.81	1837
15	-7.80	7.00	159.06	34.59	852.85	69.24	76.24	1837
		7.00	159.06	34.59	852.85	67.18	74.18	3674
16	-8.23	11.25	164.23	35.90	879.54	69.76	81.01	3674
17	-8.65	15.50	169.38	37.21	906.14	72.32	87.82	3674
18	-9.08	19.75	174.52	38.51	932.64	74.86	94.61	3674
19	-9.50	24.00	179.64	39.81	959.04	77.39	101.39	3674
20	-10.00	29.00	185.63	41.33	990.00	80.34	109.34	3674
21	-10.60	35.00	192.80	43.15	1026.99	83.85	118.85	3674
22	-11.20	41.00	199.94	44.96	1063.84	87.35	128.35	3674
23	-12.00	49.00	209.43	47.37	1112.77	91.99	140.99	3674
24	-12.80	57.00	218.87	49.76	1161.50	96.61	153.61	3674
25	-13.60	65.00	228.28	52.15	1210.06	101.24	166.24	3674
26	-14.05	69.50	233.56	53.49	1237.32	103.84	173.34	3674
27	-14.50	74.00	238.83	54.82	1264.53	106.44	180.44	3674
		74.00	238.83	0.00	4954.24	0.00	74.00a	43217
28	-15.25	81.50	249.11	0.00	5074.92	0.00	81.50a	43217
29	-16.00	89.00	259.37	0.00	5195.43	6.39	95.39	43217

RIGHT side								
Node no.	Y coord	Water press. kN/m2	Effective stresses				Total earth pressure kN/m2	Coeff. of subgrade reaction kN/m3
			Vertic -al kN/m2	Active limit kN/m2	Passive limit kN/m2	Earth pressure kN/m2		
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	459
2	-0.60	0.00	10.80	4.35	34.79	7.48	7.48	459
3	-1.20	0.00	21.60	8.70	69.58	13.68	13.68	459
		0.00	21.60	0.00	141.00	15.97	15.97	1378
4	-1.65	0.00	30.60	0.00	169.99	21.04	21.04	1378
5	-2.10	0.00	39.60	0.00	198.99	26.10	26.10	1378

6	-2.55	0.00	48.60	0.00	227.99	31.18	31.18	1378
7	-3.00	0.00	57.60	0.00	256.99	36.25	36.25	1378
8	-3.70	0.00	71.60	4.79	302.10	44.16	44.16	1378
9	-4.00	0.00	77.60	6.93	321.43	47.55	47.55	1378
10	-4.80	0.00	93.60	12.62	372.98	56.60	56.60	1378
11	-5.60	0.00	109.60	18.32	424.53	65.66	65.66	1378
12	-6.20	0.00	121.60	22.59	463.20	72.47	72.47	1378
13	-6.80	0.00	133.60	26.86	501.86	79.27	79.27	1378
		0.00	133.60	28.14	721.47	62.50	62.50	1837

Run ID. Section_2(BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.2 Apply surcharge no.2 at elevation 0.00

Node no.	Y coord	RIGHT side					Total earth pressure	Coeff. of subgrade reaction
		Water press.	Vertic -al	Effective stresses Active limit	Passive limit	Earth pressure		
		kN/m2	kN/m2	kN/m2	kN/m2	kN/m2	kN/m2	kN/m3
14	-7.10	0.00	139.60	29.66	752.43	65.10	65.10	1837
15	-7.80	7.00	146.60	31.43	788.56	68.03	75.03	1837
		7.00	146.60	31.43	788.56	70.10	77.10	3674
16	-8.23	11.25	151.70	32.73	814.88	72.14	83.39	3674
17	-8.65	15.50	156.80	34.02	841.19	74.19	89.69	3674
18	-9.08	19.75	161.90	35.31	867.51	76.26	96.01	3674
19	-9.50	24.00	167.00	36.61	893.83	78.33	102.33	3674
20	-10.00	29.00	173.00	38.13	924.79	80.78	109.78	3674
21	-10.60	35.00	180.20	39.95	961.95	83.73	118.73	3674
22	-11.20	41.00	187.40	41.78	999.10	86.69	127.69	3674
23	-12.00	49.00	197.00	44.21	1048.65	90.64	139.64	3674
24	-12.80	57.00	206.60	46.65	1098.19	94.58	151.58	3674
25	-13.60	65.00	216.20	49.08	1147.73	98.52	163.52	3674
26	-14.05	69.50	221.60	50.45	1175.59	100.73	170.23	3674
27	-14.50	74.00	227.00	51.82	1203.46	102.93	176.93	3674
		74.00	227.00	0.00	4815.23	9.23	83.23	43217
28	-15.25	81.50	237.50	0.00	4938.56	4.89	86.39	43217
29	-16.00	89.00	248.00	0.00	5061.88	0.69	89.69	43217

Note: 81.50 a Soil pressure at active limit
 123.45 p Soil pressure at passive limit

VAN der MEER CONSULTING

Program: WALLAP Version 6.07 Revision A55.B74.R58

Licensed from GEOSOLVE

Data filename/Run ID: Section_2 (BH2)

Penrith

Section A

| Sheet No.

| Job No. 220070


| Made by : MS

| Date: 7-10-2022


| Checked :

Units: kN,m

Stage No.2 Apply surcharge no.2 at elev. 0.00



Stage No.2 Apply surcharge no.2 at elev. 0.00



VAN der MEER CONSULTING

Program: WALLAP Version 6.07 Revision A55.B74.R58

Licensed from GEOSOLVE

Data filename/Run ID: Section_2 (BH2)

Penrith

Section A

| Sheet No.

| Job No. 220070


| Made by : MS

| Date: 7-10-2022

| Checked :

Units: kN,m

Stage No.3 Excav. to elev. -4.00 on RIGHT side



VAN der MEER CONSULTING	Sheet No.
Program: WALLAP Version 6.07 Revision A55.B74.R58	Job No. 220070
Licensed from GEOSOLVE	Made by : MS
Data filename/Run ID: Section_2(BH2)	
Penrith	Date: 7-10-2022
Section A	Checked :

Units: kN,m

Stage No. 3 Excavate to elevation -4.00 on RIGHT side

STABILITY ANALYSIS of Soldier Pile Wall according to Strength Factor method
Factor of safety on soil strength

Stage No.	Ground level Act.	Pass.	Prop Elev.	FoS for toe elev. = -16.00		Toe elev. for FoS = 1.000		Direction of failure
				Factor of Safety	Moment of equilib. at elev.	Toe elev.	Wall Penetr-ation	
3	0.00	-4.00	Cant.	3.063	-15.12	-5.28	1.28	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Soldier Pile Wall

Analysis options

Soldier Pile width = 0.90m; spacing = 1.40m

Passive mobilisation factor = 3.000

Length of wall perpendicular to section = 1000.00m

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Rigid boundaries: Left side 20.00 from wall
Right side 20.00 from wall

Node no.	Y coord	Nett pressure kN/m2	Wall disp. m	Wall rotation rad.	Shear force kN/m	Bending moment kN.m/m	Prop forces kN/m
1	0.00	4.03	0.019	1.95E-03	0.0	0.0	
2	-0.60	8.38	0.018	1.95E-03	3.7	1.1	
3	-1.20	12.75	0.017	1.95E-03	10.1	5.1	
		0.00	0.017	1.95E-03	10.1	5.1	
4	-1.65	0.00	0.016	1.94E-03	10.1	9.7	
5	-2.10	0.00	0.015	1.93E-03	10.1	14.2	
6	-2.55	1.44	0.014	1.91E-03	10.4	19.7	
7	-3.00	8.65	0.013	1.89E-03	12.7	24.7	
8	-3.70	19.82	0.012	1.84E-03	22.6	36.3	
9	-4.00	24.58	0.012	1.82E-03	29.3	44.1	
		-17.53	0.012	1.82E-03	29.3	44.1	
10	-4.80	-10.38	0.010	1.72E-03	18.1	61.9	
11	-5.60	-3.66	0.009	1.61E-03	12.5	73.1	
12	-6.20	1.02	0.008	1.51E-03	11.7	79.9	
13	-6.80	5.37	0.007	1.40E-03	13.6	87.1	
		-5.66	0.007	1.40E-03	13.6	87.1	
14	-7.10	-2.95	0.007	1.34E-03	12.3	91.0	
15	-7.80	2.87	0.006	1.19E-03	12.3	98.9	
		-32.77	0.006	1.19E-03	12.3	98.9	
16	-8.23	-26.41	0.005	1.10E-03	-0.3	101.2	
17	-8.65	-20.60	0.005	1.01E-03	-10.3	98.7	
18	-9.08	-15.31	0.004	9.26E-04	-17.9	92.4	
19	-9.50	-10.52	0.004	8.45E-04	-23.4	83.4	

20	-10.00	-5.46	0.004	7.61E-04	-27.4	70.4
21	-10.60	-0.09	0.003	6.81E-04	-29.0	53.0
22	-11.20	4.69	0.003	6.23E-04	-27.7	35.6
23	-12.00	10.43	0.002	5.79E-04	-21.6	14.9
24	-12.80	15.78	0.002	5.65E-04	-11.1	0.9
25	-13.60	21.00	0.001	5.67E-04	3.6	-3.0
26	-14.05	23.92	0.001	5.68E-04	13.7	0.7
27	-14.50	26.81	0.001	5.63E-04	25.1	9.3
		-55.51	0.001	5.63E-04	25.1	9.3
28	-15.25	-27.13	0.000	5.46E-04	-5.9	12.1

Run ID. Section_2 (BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.3 Excavate to elevation -4.00 on RIGHT side

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> kN/m2	<u>Wall</u> <u>disp.</u> m	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> kN/m	<u>Bending</u> <u>moment</u> kN.m/m	<u>Prop</u> <u>forces</u> kN/m
29	-16.00	42.87	0.000	5.36E-04	0.0	-0.0	

LEFT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u> kN/m2	<u>Effective stresses</u>				<u>Total</u> <u>earth</u> <u>pressure</u> kN/m2	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> kN/m3
			<u>Vertic</u> <u>-al</u> kN/m2	<u>Active</u> <u>limit</u> kN/m2	<u>Passive</u> <u>limit</u> kN/m2	<u>Earth</u> <u>pressure</u> kN/m2		
1	0.00	0.00	10.00	4.03	32.22	4.03	4.03a	732
2	-0.60	0.00	20.81	8.38	67.03	8.38	8.38a	732
3	-1.20	0.00	31.65	12.75	101.96	12.75	12.75a	732
		0.00	31.65	0.00	173.38	0.00	0.00a	2197
4	-1.65	0.00	40.72	0.00	202.61	0.00	0.00a	2197
5	-2.10	0.00	49.83	0.00	231.96	0.00	0.00a	2197
6	-2.55	0.00	58.98	0.30	261.44	1.44	1.44	2197
7	-3.00	0.00	68.16	3.56	291.01	8.65	8.65	2197
8	-3.70	0.00	82.48	8.66	337.15	19.82	19.82	2197
9	-4.00	0.00	88.63	10.85	356.95	24.58	24.58	2197
10	-4.80	0.00	105.01	16.68	409.75	37.18	37.18	2197
11	-5.60	0.00	121.37	22.51	462.46	49.58	49.58	2197
12	-6.20	0.00	133.61	26.87	501.89	58.72	58.72	2197
13	-6.80	0.00	145.81	31.21	541.20	67.70	67.70	2197
		0.00	145.81	31.23	784.48	45.33	45.33	2929
14	-7.10	0.00	151.90	32.78	815.89	49.28	49.28	2929
15	-7.80	7.00	159.06	34.59	852.85	55.12	62.12	2929
		7.00	159.06	34.59	852.85	38.93	45.93	5858
16	-8.23	11.25	164.23	35.90	879.54	44.13	55.38	5858
17	-8.65	15.50	169.38	37.21	906.14	49.09	64.59	5858
18	-9.08	19.75	174.52	38.51	932.64	53.81	73.56	5858
19	-9.50	24.00	179.64	39.81	959.04	58.30	82.30	5858
20	-10.00	29.00	185.63	41.33	990.00	63.33	92.33	5858
21	-10.60	35.00	192.80	43.15	1026.99	69.05	104.05	5858
22	-11.20	41.00	199.94	44.96	1063.84	74.50	115.50	5858
23	-12.00	49.00	209.43	47.37	1112.77	81.48	130.48	5858
24	-12.80	57.00	218.87	49.76	1161.50	88.30	145.30	5858
25	-13.60	65.00	228.28	52.15	1210.06	95.07	160.07	5858
26	-14.05	69.50	233.56	53.49	1237.32	98.87	168.37	5858
27	-14.50	74.00	238.83	54.82	1264.53	102.66	176.66	5858
		74.00	238.83	0.00	4954.24	0.00	74.00a	69695
28	-15.25	81.50	249.11	0.00	5074.92	0.00	81.50a	69695
29	-16.00	89.00	259.37	0.00	5195.43	42.87	131.87	9951284

RIGHT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u> kN/m2	<u>Effective stresses</u>				<u>Total</u> <u>earth</u> <u>pressure</u> kN/m2	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> kN/m3
			<u>Vertic</u> <u>-al</u> kN/m2	<u>Active</u> <u>limit</u> kN/m2	<u>Passive</u> <u>limit</u> kN/m2	<u>Earth</u> <u>pressure</u> kN/m2		
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0

2	-0.60	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	-1.20	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	-1.65	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	-2.10	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	-2.55	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	-3.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	-3.70	0.00	0.00	0.00	0.00	0.00	0.00	0.0
9	-4.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	0.00	0.00	71.40	42.11	42.11	2703

Run ID. Section_2(BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.3 Excavate to elevation -4.00 on RIGHT side

Node no.	Y coord	Water press. kN/m2	RIGHT side Effective stresses				Total earth pressure kN/m2	Coeff. of subgrade reaction kN/m3
			Vertic -al kN/m2	Active limit kN/m2	Passive limit kN/m2	Earth pressure kN/m2		
10	-4.80	0.00	16.00	0.00	122.96	47.56	47.56	2703
11	-5.60	0.00	32.02	0.00	174.56	53.25	53.25	2703
12	-6.20	0.00	44.04	0.00	213.31	57.70	57.70	2703
13	-6.80	0.00	56.09	0.00	252.12	62.34	62.34	2703
		0.00	56.09	8.48	321.47	50.99	50.99	3604
14	-7.10	0.00	62.12	10.01	352.60	52.23	52.23	3604
15	-7.80	7.00	69.22	11.81	389.22	52.25	59.25	3604
		7.00	69.22	11.81	389.22	71.70	78.70	7208
16	-8.23	11.25	74.39	13.12	415.94	70.54	81.79	7208
17	-8.65	15.50	79.59	14.44	442.75	69.69	85.19	7208
18	-9.08	19.75	84.80	15.76	469.64	69.12	88.87	7208
19	-9.50	24.00	90.03	17.08	496.62	68.82	92.82	7208
20	-10.00	29.00	96.20	18.65	528.48	68.79	97.79	7208
21	-10.60	35.00	103.65	20.54	566.89	69.14	104.14	7208
22	-11.20	41.00	111.13	22.44	605.50	69.81	110.81	7208
23	-12.00	49.00	121.16	24.98	657.29	71.06	120.06	7208
24	-12.80	57.00	131.27	27.54	709.43	72.52	129.52	7208
25	-13.60	65.00	141.44	30.12	761.91	74.07	139.07	7208
26	-14.05	69.50	147.18	31.58	791.57	74.95	144.45	7208
27	-14.50	74.00	152.95	33.04	821.33	75.85	149.85	7208
		74.00	152.95	0.00	3945.51	55.51	129.51	85953
28	-15.25	81.50	164.10	0.00	4076.50	27.13	108.63	85953
29	-16.00	89.00	175.30	0.00	4208.04	0.00	89.00a	9951284


Note: 89.00 a Soil pressure at active limit
 123.45 p Soil pressure at passive limit

VAN der MEER CONSULTING
 Program: WALLAP Version 6.07 Revision A55.B74.R58
 Licensed from GEOSOLVE
 Data filename/Run ID: Section_2 (BH2)
 Penrith
 Section A


| Sheet No.
 | Job No. 220070
 | Made by : MS
 |
 | Date: 7-10-2022
 | Checked :

Units: kN,m

Stage No.3 Excav. to elev. -4.00 on RIGHT side



Stage No.3 Excav. to elev. -4.00 on RIGHT side



VAN der MEER CONSULTING

Program: WALLAP Version 6.07 Revision A55.B74.R58

Licensed from GEOSOLVE

Data filename/Run ID: Section_2 (BH2)

Penrith

Section A

| Sheet No.

| Job No. 220070


| Made by : MS

| Date: 7-10-2022

| Checked :

Units: kN,m

Stage No.4 Install prop no.1 at elev. -3.00



VAN der MEER CONSULTING	Sheet No.
Program: WALLAP Version 6.07 Revision A55.B74.R58	Job No. 220070
Licensed from GEOSOLVE	Made by : MS
Data filename/Run ID: Section_2(BH2)	
Penrith	Date: 7-10-2022
Section A	Checked :

Units: kN,m

Stage No. 4 Install strut or anchor no.1 at elevation -3.00

STABILITY ANALYSIS of Soldier Pile Wall according to Strength Factor method
Factor of safety on soil strength

			FoS for toe elev. = -16.00		Toe elev. for FoS = 1.000		
<u>Stage</u>	<u>Ground level</u>	<u>Prop</u>	<u>Factor</u>	<u>Moment</u>	<u>Toe</u>	<u>Wall</u>	<u>Direction</u>
<u>No.</u>	<u>Act.</u>	<u>Pass.</u>	<u>Elev.</u>	<u>of</u>	<u>elev.</u>	<u>Penetr</u>	<u>of</u>
				<u>Safety</u>	<u>at elev.</u>	<u>-ation</u>	<u>failure</u>
4	0.00	-4.00	-3.00	Conditions not suitable for FoS calc.			

BENDING MOMENT and DISPLACEMENT ANALYSIS of Soldier Pile Wall

Analysis options

Soldier Pile width = 0.90m; spacing = 1.40m

Passive mobilisation factor = 3.000

Length of wall perpendicular to section = 1000.00m

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Rigid boundaries: Left side 20.00 from wall
Right side 20.00 from wall

Node no.	Y coord	Nett pressure kN/m ²	Wall disp. m	Wall rotation rad.	Shear force kN/m	Bending moment kN.m/m	Prop forces kN/m
1	0.00	4.10	0.019	1.94E-03	0.0	0.0	
2	-0.60	8.45	0.018	1.94E-03	3.8	1.1	
3	-1.20	12.81	0.017	1.94E-03	10.1	5.2	
		0.17	0.017	1.94E-03	10.1	5.2	
4	-1.65	0.16	0.016	1.93E-03	10.2	9.7	
5	-2.10	0.15	0.015	1.92E-03	10.3	14.4	
6	-2.55	1.59	0.014	1.90E-03	10.7	20.0	
7	-3.00	8.78	0.013	1.88E-03	13.0	25.1	-1.0
		8.78	0.013	1.88E-03	12.0	25.1	
8	-3.70	19.93	0.012	1.83E-03	22.1	36.3	
9	-4.00	24.68	0.012	1.80E-03	28.7	43.9	
		-17.27	0.012	1.80E-03	28.7	43.9	
10	-4.80	-10.17	0.010	1.71E-03	17.8	61.4	
11	-5.60	-3.51	0.009	1.60E-03	12.3	72.4	
12	-6.20	1.14	0.008	1.50E-03	11.6	79.1	
13	-6.80	5.46	0.007	1.39E-03	13.6	86.3	
		-5.54	0.007	1.39E-03	13.6	86.3	
14	-7.10	-2.85	0.007	1.33E-03	12.3	90.1	
15	-7.80	2.93	0.006	1.19E-03	12.3	98.0	
		-32.64	0.006	1.19E-03	12.3	98.0	
16	-8.23	-26.32	0.005	1.10E-03	-0.2	100.3	
17	-8.65	-20.53	0.005	1.01E-03	-10.1	97.9	
18	-9.08	-15.27	0.004	9.23E-04	-17.8	91.7	

19	-9.50	-10.50	0.004	8.42E-04	-23.2	82.8
20	-10.00	-5.46	0.004	7.59E-04	-27.2	69.9
21	-10.60	-0.10	0.003	6.80E-04	-28.9	52.5
22	-11.20	4.66	0.003	6.22E-04	-27.5	35.2
23	-12.00	10.40	0.002	5.79E-04	-21.5	14.6
24	-12.80	15.75	0.002	5.66E-04	-11.0	0.7
25	-13.60	20.98	0.001	5.68E-04	3.7	-3.1
26	-14.05	23.90	0.001	5.69E-04	13.8	0.7
27	-14.50	26.79	0.001	5.64E-04	25.2	9.3
		-55.59	0.001	5.64E-04	25.2	9.3

Run ID. Section_2 (BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.4 Install strut or anchor no.1 at elevation -3.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> kN/m2	<u>Wall</u> <u>disp.</u> m	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> kN/m	<u>Bending</u> <u>moment</u> kN.m/m	<u>Prop</u> <u>forces</u> kN/m
28	-15.25	-27.18	0.000	5.47E-04	-5.9	12.1	
29	-16.00	42.86	0.000	5.37E-04	0.0	-0.0	
At elev. -3.00		Prop force = 1.0 kN/m run					

LEFT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u> kN/m2	<u>Vertic</u> <u>-al</u> kN/m2	<u>Effective</u> <u>Active</u> limit kN/m2	<u>Effective</u> <u>Passive</u> limit kN/m2	<u>Earth</u> <u>pressure</u> kN/m2	<u>Total</u> <u>earth</u> <u>pressure</u> kN/m2	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> kN/m3
1	0.00	0.00	10.00	4.03	32.22	4.10	4.10	832
2	-0.60	0.00	20.81	8.38	67.03	8.45	8.45	832
3	-1.20	0.00	31.65	12.75	101.96	12.81	12.81	832
		0.00	31.65	0.00	173.38	0.17	0.17	2495
4	-1.65	0.00	40.72	0.00	202.61	0.16	0.16	2495
5	-2.10	0.00	49.83	0.00	231.96	0.15	0.15	2495
6	-2.55	0.00	58.98	0.30	261.44	1.59	1.59	2495
7	-3.00	0.00	68.16	3.56	291.01	8.78	8.78	2495
8	-3.70	0.00	82.48	8.66	337.15	19.93	19.93	2495
9	-4.00	0.00	88.63	10.85	356.95	24.68	24.68	2495
10	-4.80	0.00	105.01	16.68	409.75	37.26	37.26	2495
11	-5.60	0.00	121.37	22.51	462.46	49.64	49.64	2495
12	-6.20	0.00	133.61	26.87	501.89	58.77	58.77	2495
13	-6.80	0.00	145.81	31.21	541.20	67.74	67.74	2495
		0.00	145.81	31.23	784.48	45.38	45.38	3327
14	-7.10	0.00	151.90	32.78	815.89	49.32	49.32	3327
15	-7.80	7.00	159.06	34.59	852.85	55.14	62.14	3327
		7.00	159.06	34.59	852.85	38.98	45.98	6654
16	-8.23	11.25	164.23	35.90	879.54	44.17	55.42	6654
17	-8.65	15.50	169.38	37.21	906.14	49.11	64.61	6654
18	-9.08	19.75	174.52	38.51	932.64	53.82	73.57	6654
19	-9.50	24.00	179.64	39.81	959.04	58.31	82.31	6654
20	-10.00	29.00	185.63	41.33	990.00	63.33	92.33	6587
21	-10.60	35.00	192.80	43.15	1026.99	69.04	104.04	6587
22	-11.20	41.00	199.94	44.96	1063.84	74.49	115.49	6587
23	-12.00	49.00	209.43	47.37	1112.77	81.47	130.47	6587
24	-12.80	57.00	218.87	49.76	1161.50	88.29	145.29	6587
25	-13.60	65.00	228.28	52.15	1210.06	95.06	160.06	6587
26	-14.05	69.50	233.56	53.49	1237.32	98.86	168.36	6587
27	-14.50	74.00	238.83	54.82	1264.53	102.65	176.65	6587
		74.00	238.83	0.00	4954.24	0.00	74.00a	78472
28	-15.25	81.50	249.11	0.00	5074.92	0.00	81.50a	78472
29	-16.00	89.00	259.37	0.00	5195.43	42.87	131.87	78472

RIGHT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Effective</u> <u>Active</u> limit	<u>Effective</u> <u>Passive</u> limit	<u>Earth</u> <u>pressure</u>	<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>

		kN/m2	kN/m2	kN/m2	kN/m2	kN/m2	kN/m2	kN/m3
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	-0.60	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	-1.20	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	-1.65	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	-2.10	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	-2.55	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	-3.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	-3.70	0.00	0.00	0.00	0.00	0.00	0.00	0.0

Run ID. Section_2(BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.4 Install strut or anchor no.1 at elevation -3.00

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u>	<u>RIGHT side</u>				<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
			<u>Vertic</u> <u>-al</u>	<u>Effective</u> <u>Active</u>	<u>Effective</u> <u>Passive</u>	<u>Earth</u> <u>pressure</u>		
		kN/m2	kN/m2	limit	limit	kN/m2	kN/m2	kN/m3
9	-4.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	0.00	0.00	71.40	41.95	41.95	3883
10	-4.80	0.00	16.00	0.00	122.96	47.44	47.44	3883
11	-5.60	0.00	32.02	0.00	174.56	53.15	53.15	3883
12	-6.20	0.00	44.04	0.00	213.31	57.63	57.63	3883
13	-6.80	0.00	56.09	0.00	252.12	62.28	62.28	3883
		0.00	56.09	8.48	321.47	50.92	50.92	5178
14	-7.10	0.00	62.12	10.01	352.60	52.17	52.17	5178
15	-7.80	7.00	69.22	11.81	389.22	52.21	59.21	5178
		7.00	69.22	11.81	389.22	71.61	78.61	10356
16	-8.23	11.25	74.39	13.12	415.94	70.48	81.73	10356
17	-8.65	15.50	79.59	14.44	442.75	69.65	85.15	10356
18	-9.08	19.75	84.80	15.76	469.64	69.09	88.84	10356
19	-9.50	24.00	90.03	17.08	496.62	68.81	92.81	10356
20	-10.00	29.00	96.20	18.65	528.48	68.79	97.79	6587
21	-10.60	35.00	103.65	20.54	566.89	69.14	104.14	6587
22	-11.20	41.00	111.13	22.44	605.50	69.82	110.82	6587
23	-12.00	49.00	121.16	24.98	657.29	71.07	120.07	6587
24	-12.80	57.00	131.27	27.54	709.43	72.54	129.54	6587
25	-13.60	65.00	141.44	30.12	761.91	74.08	139.08	6587
26	-14.05	69.50	147.18	31.58	791.57	74.96	144.46	6587
27	-14.50	74.00	152.95	33.04	821.33	75.86	149.86	6587
		74.00	152.95	0.00	3945.51	55.59	129.59	78472
28	-15.25	81.50	164.10	0.00	4076.50	27.18	108.68	78472
29	-16.00	89.00	175.30	0.00	4208.04	0.01	89.01	78472


Note: 81.50 a Soil pressure at active limit
 123.45 p Soil pressure at passive limit

VAN der MEER CONSULTING
 Program: WALLAP Version 6.07 Revision A55.B74.R58
 Licensed from GEOSOLVE
 Data filename/Run ID: Section_2 (BH2)
 Penrith
 Section A


| Sheet No.
 | Job No. 220070
 | Made by : MS
 |
 | Date: 7-10-2022
 | Checked :

Units: kN,m

Stage No.4 Install prop no.1 at elev. -3.00



Stage No.4 Install prop no.1 at elev. -3.00



VAN der MEER CONSULTING

Program: WALLAP Version 6.07 Revision A55.B74.R58

Licensed from GEOSOLVE

Data filename/Run ID: Section_2(BH2)

Penrith

Section A

| Sheet No.

| Job No. 220070


| Made by : MS

| Date: 7-10-2022

| Checked :

Units: kN,m

Stage No.5 Excav. to elev. -7.10 on RIGHT side



VAN der MEER CONSULTING	Sheet No.
Program: WALLAP Version 6.07 Revision A55.B74.R58	Job No. 220070
Licensed from GEOSOLVE	Made by : MS
Data filename/Run ID: Section_2(BH2)	
Penrith	Date: 7-10-2022
Section A	Checked :

Units: kN,m

Stage No. 5 Excavate to elevation -7.10 on RIGHT side

STABILITY ANALYSIS of Soldier Pile Wall according to Strength Factor method
Factor of safety on soil strength

Stage No.	Ground level Act.	Pass.	Prop Elev.	FoS for toe elev. = -16.00		Toe elev. for FoS = 1.000		Direction of failure
				Factor of Safety	Moment of equilib. at elev.	Toe elev.	Wall Penetr -ation	
5	0.00	-7.10	-3.00	4.445	n/a	-8.28	1.18	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Soldier Pile Wall

Analysis options

Soldier Pile width = 0.90m; spacing = 1.40m

Passive mobilisation factor = 3.000

Length of wall perpendicular to section = 1000.00m

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Rigid boundaries: Left side 20.00 from wall
Right side 20.00 from wall

Node no.	Y coord	Nett pressure kN/m ²	Wall disp. m	Wall rotation rad.	Shear force kN/m	Bending moment kN.m/m	Prop forces kN/m
1	0.00	4.03	0.021	1.08E-03	0.0	0.0	
2	-0.60	8.38	0.020	1.08E-03	3.7	1.1	
3	-1.20	12.75	0.019	1.08E-03	10.1	5.1	
		0.00	0.019	1.08E-03	10.1	5.1	
4	-1.65	0.00	0.019	1.07E-03	10.1	9.7	
5	-2.10	0.00	0.018	1.06E-03	10.1	14.2	
6	-2.55	0.30	0.018	1.04E-03	10.1	19.7	
7	-3.00	3.56	0.017	1.02E-03	11.0	24.3	-76.5
		3.56	0.017	1.02E-03	-65.5	24.3	
8	-3.70	13.00	0.017	1.02E-03	-59.7	-19.6	
9	-4.00	17.39	0.016	1.03E-03	-55.1	-36.9	
10	-4.80	29.15	0.015	1.13E-03	-36.5	-74.8	
11	-5.60	40.98	0.015	1.28E-03	-8.5	-94.1	
12	-6.20	49.91	0.014	1.40E-03	18.8	-91.5	
13	-6.80	58.89	0.013	1.50E-03	51.4	-71.0	
		33.57	0.013	1.50E-03	51.4	-71.0	
14	-7.10	37.62	0.012	1.55E-03	62.1	-54.0	
		5.58	0.012	1.55E-03	62.1	-54.0	
15	-7.80	1.90	0.011	1.59E-03	64.7	-8.6	
		-33.58	0.011	1.59E-03	64.7	-8.6	
16	-8.23	-39.63	0.011	1.59E-03	49.2	16.5	
17	-8.65	-36.13	0.010	1.57E-03	33.1	33.7	
18	-9.08	-32.77	0.009	1.53E-03	18.4	44.4	

19	-9.50	-29.58	0.009	1.49E-03	5.2	49.1
20	-10.00	-21.44	0.008	1.43E-03	-7.6	48.8
21	-10.60	-11.92	0.007	1.38E-03	-17.6	40.4
22	-11.20	-2.90	0.006	1.33E-03	-22.0	27.7
23	-12.00	8.60	0.005	1.30E-03	-19.7	9.1
24	-12.80	19.78	0.004	1.29E-03	-8.4	-3.9
25	-13.60	30.86	0.003	1.30E-03	11.9	-4.4
26	-14.05	37.07	0.002	1.30E-03	27.1	4.1
27	-14.50	43.23	0.002	1.29E-03	45.2	20.1
		-109.13	0.002	1.29E-03	45.2	20.1

Run ID. Section_2(BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.5 Excavate to elevation -7.10 on RIGHT side

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> kN/m2	<u>Wall</u> <u>disp.</u> m	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> kN/m	<u>Bending</u> <u>moment</u> kN.m/m	<u>Prop</u> <u>forces</u> kN/m
28	-15.25	-42.80	0.001	1.26E-03	-11.8	22.9	
29	-16.00	74.17	0.000	1.24E-03	0.0	-0.0	
At elev. -3.00				Prop force =	76.5	kN/m run	

LEFT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u> kN/m2	<u>Vertic</u> <u>-al</u> kN/m2	<u>Effective</u> <u>Active</u> limit kN/m2	<u>Effective</u> <u>Passive</u> limit kN/m2	<u>Earth</u> <u>pressure</u> kN/m2	<u>Total</u> <u>earth</u> <u>pressure</u> kN/m2	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u> kN/m3
1	0.00	0.00	10.00	4.03	32.22	4.03	4.03a	504
2	-0.60	0.00	20.81	8.38	67.03	8.38	8.38a	504
3	-1.20	0.00	31.65	12.75	101.96	12.75	12.75a	504
		0.00	31.65	0.00	173.38	0.00	0.00a	1513
4	-1.65	0.00	40.72	0.00	202.61	0.00	0.00a	1513
5	-2.10	0.00	49.83	0.00	231.96	0.00	0.00a	1513
6	-2.55	0.00	58.98	0.30	261.44	0.30	0.30a	1513
7	-3.00	0.00	68.16	3.56	291.01	3.56	3.56a	1513
8	-3.70	0.00	82.48	8.66	337.15	13.00	13.00	1513
9	-4.00	0.00	88.63	10.85	356.95	17.39	17.39	1513
10	-4.80	0.00	105.01	16.68	409.75	29.15	29.15	1513
11	-5.60	0.00	121.37	22.51	462.46	40.98	40.98	1513
12	-6.20	0.00	133.61	26.87	501.89	49.91	49.91	1513
13	-6.80	0.00	145.81	31.21	541.20	58.89	58.89	1513
		0.00	145.81	31.23	784.48	33.57	33.57	2017
14	-7.10	0.00	151.90	32.78	815.89	37.62	37.62	2017
15	-7.80	7.00	159.06	34.59	852.85	43.89	50.89	2017
		7.00	159.06	34.59	852.85	34.59	41.59a	4035
16	-8.23	11.25	164.23	35.90	879.54	35.90	47.15a	4035
17	-8.65	15.50	169.38	37.21	906.14	37.21	52.71a	4035
18	-9.08	19.75	174.52	38.51	932.64	38.51	58.26a	4035
19	-9.50	24.00	179.64	39.81	959.04	39.81	63.81a	4035
20	-10.00	29.00	185.63	41.33	990.00	45.92	74.92	4035
21	-10.60	35.00	192.80	43.15	1026.99	53.30	88.30	4035
22	-11.20	41.00	199.94	44.96	1063.84	60.46	101.46	4035
23	-12.00	49.00	209.43	47.37	1112.77	69.77	118.77	4035
24	-12.80	57.00	218.87	49.76	1161.50	78.95	135.95	4035
25	-13.60	65.00	228.28	52.15	1210.06	88.09	153.09	4035
26	-14.05	69.50	233.56	53.49	1237.32	93.23	162.73	4035
27	-14.50	74.00	238.83	54.82	1264.53	98.36	172.36	4035
		74.00	238.83	0.00	4954.24	0.00	74.00a	47633
28	-15.25	81.50	249.11	0.00	5074.92	0.00	81.50a	47633
29	-16.00	89.00	259.37	0.00	5195.43	74.17	163.17	3635061

RIGHT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Water</u> <u>press.</u>	<u>Vertic</u> <u>-al</u>	<u>Effective</u> <u>Active</u> limit	<u>Effective</u> <u>Passive</u> limit	<u>Earth</u> <u>pressure</u>	<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>

		kN/m2	kN/m2	kN/m2	kN/m2	kN/m2	kN/m2	kN/m3
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	-0.60	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	-1.20	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	-1.65	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	-2.10	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	-2.55	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	-3.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	-3.70	0.00	0.00	0.00	0.00	0.00	0.00	0.0

Run ID. Section_2(BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.5 Excavate to elevation -7.10 on RIGHT side

Node no.	Y coord	Water press. kN/m2	Effective stresses				Total earth pressure kN/m2	Coeff. of subgrade reaction kN/m3
			Vertic -al kN/m2	Active limit kN/m2	Passive limit kN/m2	Earth pressure kN/m2		
9	-4.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
10	-4.80	0.00	0.00	0.00	0.00	0.00	0.00	0.0
11	-5.60	0.00	0.00	0.00	0.00	0.00	0.00	0.0
12	-6.20	0.00	0.00	0.00	0.00	0.00	0.00	0.0
13	-6.80	0.00	0.00	0.00	0.00	0.00	0.00	0.0
14	-7.10	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	0.00	0.00	32.03	32.03	32.03p	2945
15	-7.80	7.00	7.00	0.00	68.17	41.98	48.98	2945
		7.00	7.00	0.00	68.17	68.17	75.17p	5890
16	-8.23	11.25	12.11	0.00	94.53	75.54	86.79	5890
17	-8.65	15.50	17.23	0.00	120.93	73.34	88.84	5890
18	-9.08	19.75	22.36	0.00	147.40	71.29	91.04	5890
19	-9.50	24.00	27.50	1.23	173.95	69.39	93.39	5890
20	-10.00	29.00	33.58	2.77	205.30	67.36	96.36	5890
21	-10.60	35.00	40.91	4.63	243.13	65.23	100.23	5890
22	-11.20	41.00	48.29	6.50	281.21	63.36	104.36	5890
23	-12.00	49.00	58.21	9.02	332.44	61.17	110.17	5890
24	-12.80	57.00	68.25	11.56	384.23	59.17	116.17	5890
25	-13.60	65.00	78.40	14.14	436.63	57.23	122.23	5890
26	-14.05	69.50	84.17	15.60	466.38	56.17	125.67	5890
27	-14.50	74.00	89.97	17.07	496.33	55.13	129.13	5890
		74.00	89.97	0.00	3205.79	109.13	183.13	70081
28	-15.25	81.50	101.23	0.00	3338.05	42.80	124.30	70081
29	-16.00	89.00	112.60	0.00	3471.56	0.00	89.00a	3635061


Note: 89.00 a Soil pressure at active limit
 75.17 p Soil pressure at passive limit

VAN der MEER CONSULTING
 Program: WALLAP Version 6.07 Revision A55.B74.R58
 Licensed from GEOSOLVE
 Data filename/Run ID: Section_2 (BH2)
 Penrith
 Section A


| Sheet No.
 | Job No. 220070
 | Made by : MS
 |
 | Date: 7-10-2022
 | Checked :

Units: kN,m

Stage No.5 Excav. to elev. -7.10 on RIGHT side



Stage No.5 Excav. to elev. -7.10 on RIGHT side



VAN der MEER CONSULTING

Program: WALLAP Version 6.07 Revision A55.B74.R58

Licensed from GEOSOLVE

Data filename/Run ID: Section_2 (BH2)

Penrith

Section A

| Sheet No.

| Job No. 220070


| Made by : MS

| Date: 7-10-2022

| Checked :

Units: kN,m

Stage No.7 Excav. to elev. -9.50 on RIGHT side



VAN der MEER CONSULTING	Sheet No.
Program: WALLAP Version 6.07 Revision A55.B74.R58	Job No. 220070
Licensed from GEOSOLVE	Made by : MS
Data filename/Run ID: Section_2(BH2)	
Penrith	Date: 7-10-2022
Section A	Checked :

Units: kN,m

Stage No. 7 Excavate to elevation -9.50 on RIGHT side

STABILITY ANALYSIS of Soldier Pile Wall according to Strength Factor method
Factor of safety on soil strength

Stage No.	Ground level Act.	Pass.	Prop Elev.	FoS for toe elev. = -16.00		Toe elev. for FoS = 1.000		Direction of failure
				Factor of Safety	Moment of equilib. at elev.	Toe elev.	Wall Penetration	
7	0.00	-9.50	-3.00	3.180	n/a	-11.53	2.03	L to R

BENDING MOMENT and DISPLACEMENT ANALYSIS of Soldier Pile Wall

Analysis options

Soldier Pile width = 0.90m; spacing = 1.40m

Passive mobilisation factor = 3.000

Length of wall perpendicular to section = 1000.00m

Subgrade reaction model - Boussinesq Influence coefficients

Soil deformations are elastic until the active or passive limit is reached

Rigid boundaries: Left side 20.00 from wall
Right side 20.00 from wall

Node no.	Y coord	Nett pressure kN/m ²	Wall disp. m	Wall rotation rad.	Shear force kN/m	Bending moment kN.m/m	Prop forces kN/m
1	0.00	10.79	0.018	-6.22E-04	0.0	0.0	
2	-0.60	12.11	0.019	-6.23E-04	6.9	2.3	
3	-1.20	13.45	0.019	-6.31E-04	14.5	8.9	
		2.09	0.019	-6.31E-04	14.5	8.9	
4	-1.65	0.00	0.019	-6.43E-04	15.0	15.6	
5	-2.10	0.00	0.020	-6.61E-04	15.0	22.4	
6	-2.55	0.30	0.020	-6.87E-04	15.1	30.1	
7	-3.00	3.56	0.020	-7.20E-04	15.9	37.0	-129.9
		3.56	0.020	-7.20E-04	-113.9	37.0	
8	-3.70	8.66	0.021	-7.16E-04	-109.6	-41.1	
9	-4.00	10.85	0.021	-6.79E-04	-106.7	-73.6	
10	-4.80	19.51	0.021	-4.81E-04	-94.6	-154.3	
11	-5.60	29.35	0.022	-1.53E-04	-75.0	-223.1	
12	-6.20	36.97	0.022	1.63E-04	-55.1	-262.5	
13	-6.80	44.85	0.021	5.22E-04	-30.6	-288.6	
		31.23	0.021	5.22E-04	-30.6	-288.6	
14	-7.10	32.78	0.021	7.13E-04	-21.0	-296.4	
15	-7.80	41.59	0.021	1.16E-03	5.1	-301.2	
16	-8.23	47.15	0.020	1.44E-03	23.9	-294.4	
17	-8.65	52.71	0.019	1.70E-03	45.1	-280.0	
18	-9.08	58.26	0.019	1.95E-03	68.7	-256.1	
19	-9.50	63.81	0.018	2.17E-03	94.7	-221.6	
		31.78	0.018	2.17E-03	94.7	-221.6	

20	-10.00	-18.47	0.017	2.39E-03	98.0	-172.0
21	-10.60	-40.42	0.015	2.57E-03	80.3	-115.0
22	-11.20	-30.88	0.013	2.70E-03	58.9	-74.5
23	-12.00	-17.67	0.011	2.79E-03	39.5	-38.0
24	-12.80	3.71	0.009	2.84E-03	33.9	-10.3
25	-13.60	29.08	0.007	2.83E-03	47.0	18.0
26	-14.05	43.14	0.005	2.80E-03	63.3	42.1
27	-14.50	56.92	0.004	2.74E-03	85.8	75.0
		-256.80	0.004	2.74E-03	85.8	75.0
28	-15.25	-102.28	0.002	2.63E-03	-48.9	66.7

Run ID. Section_2(BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.7 Excavate to elevation -9.50 on RIGHT side

<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Nett</u> <u>pressure</u> kN/m2	<u>Wall</u> <u>disp.</u> m	<u>Wall</u> <u>rotation</u> rad.	<u>Shear</u> <u>force</u> kN/m	<u>Bending</u> <u>moment</u> kN.m/m	<u>Prop</u> <u>forces</u> kN/m
29	-16.00	232.55	0.000	2.57E-03	0.0	-0.0	
At elev. -3.00				Prop force =	129.9	kN/m run	

LEFT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u> kN/m2	<u>Vertic</u> <u>-al</u> kN/m2	<u>Active</u> <u>limit</u> kN/m2	<u>Passive</u> <u>limit</u> kN/m2	<u>Earth</u> <u>pressure</u> kN/m2	kN/m2	kN/m3
1	0.00	0.00	10.00	4.03	32.22	10.79	10.79	3082
2	-0.60	0.00	20.81	8.38	67.03	12.11	12.11	3082
3	-1.20	0.00	31.65	12.75	101.96	13.45	13.45	3082
		0.00	31.65	0.00	173.38	2.09	2.09	9245
4	-1.65	0.00	40.72	0.00	202.61	0.00	0.00a	1640
5	-2.10	0.00	49.83	0.00	231.96	0.00	0.00a	1640
6	-2.55	0.00	58.98	0.30	261.44	0.30	0.30a	1640
7	-3.00	0.00	68.16	3.56	291.01	3.56	3.56a	1640
8	-3.70	0.00	82.48	8.66	337.15	8.66	8.66a	1640
9	-4.00	0.00	88.63	10.85	356.95	10.85	10.85a	1640
10	-4.80	0.00	105.01	16.68	409.75	19.51	19.51	1640
11	-5.60	0.00	121.37	22.51	462.46	29.35	29.35	1640
12	-6.20	0.00	133.61	26.87	501.89	36.97	36.97	1640
13	-6.80	0.00	145.81	31.21	541.20	44.85	44.85	1640
		0.00	145.81	31.23	784.48	31.23	31.23a	2186
14	-7.10	0.00	151.90	32.78	815.89	32.78	32.78a	2186
15	-7.80	7.00	159.06	34.59	852.85	34.59	41.59a	2186
		7.00	159.06	34.59	852.85	34.59	41.59a	4372
16	-8.23	11.25	164.23	35.90	879.54	35.90	47.15a	4372
17	-8.65	15.50	169.38	37.21	906.14	37.21	52.71a	4372
18	-9.08	19.75	174.52	38.51	932.64	38.51	58.26a	4372
19	-9.50	24.00	179.64	39.81	959.04	39.81	63.81a	4372
20	-10.00	29.00	185.63	41.33	990.00	41.33	70.33a	4372
21	-10.60	35.00	192.80	43.15	1026.99	43.15	78.15a	4372
22	-11.20	41.00	199.94	44.96	1063.84	44.96	85.96a	4372
23	-12.00	49.00	209.43	47.37	1112.77	47.37	96.37a	4372
24	-12.80	57.00	218.87	49.76	1161.50	57.75	114.75	4372
25	-13.60	65.00	228.28	52.15	1210.06	72.24	137.24	4372
26	-14.05	69.50	233.56	53.49	1237.32	80.34	149.84	4372
27	-14.50	74.00	238.83	54.82	1264.53	88.35	162.35	4372
		74.00	238.83	0.00	4954.24	0.00	74.00a	51734
28	-15.25	81.50	249.11	0.00	5074.92	0.00	81.50a	51734
29	-16.00	89.00	259.37	0.00	5195.43	203.55	292.55	4384164

RIGHT side								
<u>Node</u> <u>no.</u>	<u>Y</u> <u>coord</u>	<u>Effective stresses</u>					<u>Total</u> <u>earth</u> <u>pressure</u>	<u>Coeff. of</u> <u>subgrade</u> <u>reaction</u>
		<u>Water</u> <u>press.</u> kN/m2	<u>Vertic</u> <u>-al</u> kN/m2	<u>Active</u> <u>limit</u> kN/m2	<u>Passive</u> <u>limit</u> kN/m2	<u>Earth</u> <u>pressure</u> kN/m2	kN/m2	kN/m3

1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
2	-0.60	0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	-1.20	0.00	0.00	0.00	0.00	0.00	0.00	0.0
4	-1.65	0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	-2.10	0.00	0.00	0.00	0.00	0.00	0.00	0.0
6	-2.55	0.00	0.00	0.00	0.00	0.00	0.00	0.0
7	-3.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
8	-3.70	0.00	0.00	0.00	0.00	0.00	0.00	0.0
9	-4.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0

Run ID. Section_2 (BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

(continued)

Stage No.7 Excavate to elevation -9.50 on RIGHT side

Node no.	Y coord	Water press. kN/m2	Effective stresses				Total earth pressure kN/m2	Coeff. of subgrade reaction kN/m3
			Vertic -al kN/m2	Active limit kN/m2	Passive limit kN/m2	Earth pressure kN/m2		
10	-4.80	0.00	0.00	0.00	0.00	0.00	0.00	0.0
11	-5.60	0.00	0.00	0.00	0.00	0.00	0.00	0.0
12	-6.20	0.00	0.00	0.00	0.00	0.00	0.00	0.0
13	-6.80	0.00	0.00	0.00	0.00	0.00	0.00	0.0
14	-7.10	0.00	0.00	0.00	0.00	0.00	0.00	0.0
15	-7.80	0.00	0.00	0.00	0.00	0.00	0.00	0.0
16	-8.23	0.00	0.00	0.00	0.00	0.00	0.00	0.0
17	-8.65	0.00	0.00	0.00	0.00	0.00	0.00	0.0
18	-9.08	0.00	0.00	0.00	0.00	0.00	0.00	0.0
19	-9.50	0.00	0.00	0.00	0.00	0.00	0.00	0.0
		0.00	0.00	0.00	32.03	32.03	32.03p	7668
20	-10.00	0.00	11.00	0.00	88.80	88.80	88.80p	7668
21	-10.60	6.00	18.21	0.00	126.02	112.57	118.57	7668
22	-11.20	12.00	25.45	0.71	163.36	104.84	116.84	7668
23	-12.00	20.00	35.16	3.17	213.45	94.03	114.03	7668
24	-12.80	28.00	44.95	5.65	264.01	83.04	111.04	7668
25	-13.60	36.00	54.86	8.17	315.16	72.16	108.16	7668
26	-14.05	40.50	60.50	9.60	344.23	66.20	106.70	7668
27	-14.50	45.00	66.18	11.04	373.54	60.43	105.43	7668
		45.00	66.18	0.00	2926.33	285.80	330.80	91497
28	-15.25	52.50	77.25	0.00	3056.39	131.28	183.78	91497
29	-16.00	60.00	88.47	0.00	3188.11	0.00	60.00a	4384164


Note: 60.00 a Soil pressure at active limit
 88.80 p Soil pressure at passive limit

VAN der MEER CONSULTING
 Program: WALLAP Version 6.07 Revision A55.B74.R58
 Licensed from GEOSOLVE
 Data filename/Run ID: Section_2 (BH2)
 Penrith
 Section A


| Sheet No.
 | Job No. 220070
 | Made by : MS
 |
 | Date: 7-10-2022
 | Checked :

Units: kN,m

Stage No.7 Excav. to elev. -9.50 on RIGHT side



Stage No.7 Excav. to elev. -9.50 on RIGHT side



VAN der MEER CONSULTING	Sheet No.
Program: WALLAP Version 6.07 Revision A55.B74.R58	Job No. 220070
Licensed from GEOSOLVE	Made by : MS
Data filename/Run ID: Section_2(BH2)	
Penrith	Date: 7-10-2022
Section A	Checked :

Units: kN,m

Summary of results

STABILITY ANALYSIS of Soldier Pile Wall according to Strength Factor method
Factor of safety on soil strength

			FoS for toe		Toe elev. for			
			elev. = -16.00		FoS = 1.000			
<u>Stage</u>	<u>Ground level</u>		<u>Prop</u>	<u>Factor</u>	<u>Moment</u>	<u>Toe</u>	<u>Wall</u>	<u>Direction</u>
<u>No.</u>	<u>Act.</u>	<u>Pass.</u>	<u>Elev.</u>	<u>of</u>	<u>equilib.</u>	<u>elev.</u>	<u>Penetr</u>	<u>of</u>
				<u>Safety</u>	<u>at elev.</u>		<u>-ation</u>	<u>failure</u>
1	0.00	0.00	Cant.	<u>Conditions not suitable for FoS calc.</u>				
2	0.00	0.00	Cant.	<u>Conditions not suitable for FoS calc.</u>				
3	0.00	-4.00	Cant.	3.063	-15.12	-5.28	1.28	L to R
4	0.00	-4.00	-3.00	<u>Conditions not suitable for FoS calc.</u>				
5	0.00	-7.10	-3.00	4.445	n/a	-8.28	1.18	L to R
6	0.00	-7.10	-3.00	4.797	n/a	-7.98	0.88	L to R
7	0.00	-9.50	-3.00	3.180	n/a	-11.53	2.03	L to R

VAN der MEER CONSULTING	Sheet No.
Program: WALLAP Version 6.07 Revision A55.B74.R58	Job No. 220070
Licensed from GEOSOLVE	Made by : MS
Data filename/Run ID: Section_2(BH2)	
Penrith	Date: 7-10-2022
Section A	Checked :

Units: kN,m

Summary of results

BENDING MOMENT and DISPLACEMENT ANALYSIS of Soldier Pile Wall

Analysis options

Soldier Pile width = 0.90m; spacing = 1.40m
 Passive mobilisation factor = 3.000
 Length of wall perpendicular to section = 1000.00m
 Subgrade reaction model - Boussinesq Influence coefficients
 Soil deformations are elastic until the active or passive limit is reached

Rigid boundaries: Left side 20.00 from wall
 Right side 20.00 from wall

Bending moment, shear force and displacement envelopes

Node no.	Y coord	Displacement		Bending moment		Shear force	
		maximum	minimum	maximum	minimum	maximum	minimum
		m	m	kN.m/m	kN.m/m	kN/m	kN/m
1	0.00	0.021	0.000	0.0	0.0	0.0	0.0
2	-0.60	0.020	0.000	2.3	0.0	6.9	0.0
3	-1.20	0.019	0.000	8.9	0.0	14.5	0.0
4	-1.65	0.019	0.000	15.6	0.0	15.0	0.0
5	-2.10	0.020	0.000	22.4	0.0	15.0	0.0
6	-2.55	0.020	0.000	30.1	0.0	15.1	0.0
7	-3.00	0.020	0.000	37.0	0.0	15.9	-113.9
8	-3.70	0.021	0.000	36.3	-41.1	22.6	-109.6
9	-4.00	0.021	0.000	44.1	-73.6	29.3	-106.7
10	-4.80	0.021	0.000	61.9	-154.3	18.1	-94.6
11	-5.60	0.022	0.000	73.1	-223.1	12.5	-75.0
12	-6.20	0.022	0.000	79.9	-262.5	18.8	-55.1
13	-6.80	0.021	0.000	87.1	-288.6	51.4	-30.6
14	-7.10	0.021	0.000	91.0	-296.4	62.1	-21.0
15	-7.80	0.021	0.000	98.9	-301.2	64.7	0.0
16	-8.23	0.020	0.000	101.2	-294.4	49.2	-0.3
17	-8.65	0.019	0.000	98.7	-280.0	45.1	-10.3
18	-9.08	0.019	0.000	92.4	-256.1	68.7	-17.9
19	-9.50	0.018	0.000	83.4	-221.6	94.7	-23.4
20	-10.00	0.017	0.000	70.4	-172.0	98.0	-27.4
21	-10.60	0.015	0.000	53.0	-115.0	80.3	-29.0
22	-11.20	0.013	0.000	35.6	-74.5	58.9	-27.7
23	-12.00	0.011	0.000	14.9	-38.0	39.5	-21.6
24	-12.80	0.009	0.000	2.3	-38.3	33.9	-11.1
25	-13.60	0.007	0.000	18.0	-30.8	47.0	-0.5
26	-14.05	0.005	0.000	42.1	-15.8	63.3	-0.0
27	-14.50	0.004	0.000	75.0	0.0	85.8	0.0
28	-15.25	0.002	0.000	66.7	0.0	0.0	-48.9
29	-16.00	0.000	-0.000	0.0	-0.0	0.0	0.0

Maximum and minimum bending moment and shear force at each stage

Stage	-----	Bending moment	-----	-----	Shear force	-----
no.		<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	<u>maximum</u>
						<u>minimum</u>
						<u>elev.</u>

	kN.m/m		kN.m/m		kN/m		kN/m	
1	8.2	-8.23	-0.0	-16.00	3.1	-1.20	-1.7	-11.20
2	4.0	-2.55	-3.9	-12.80	5.0	-14.50	-2.1	-10.60
3	101.2	-8.23	-3.0	-13.60	29.3	-4.00	-29.0	-10.60
4	100.3	-8.23	-3.1	-13.60	28.7	-4.00	-28.9	-10.60
5	49.1	-9.50	-94.1	-5.60	64.7	-7.80	-65.5	-3.00
6	27.3	-3.00	-101.9	-6.20	65.7	-14.50	-68.6	-3.00
7	75.0	-14.50	-301.2	-7.80	98.0	-10.00	-113.9	-3.00

Run ID. Section_2(BH2)
 Penrith
 Section A

| Sheet No.
 | Date: 7-10-2022
 | Checked :

Summary of results (continued)

Maximum and minimum displacement at each stage

Stage ----- Displacement -----

no.	<u>maximum</u>	<u>elev.</u>	<u>minimum</u>	<u>elev.</u>	<u>Stage description</u>
	m		m		
1	0.002	0.00	-0.000	-16.00	Apply surcharge no.1 at elev. 0.00
2	0.002	0.00	0.000	0.00	Apply surcharge no.2 at elev. 0.00
3	0.019	0.00	0.000	0.00	Excav. to elev. -4.00 on RIGHT side
4	0.019	0.00	0.000	0.00	Install prop no.1 at elev. -3.00
5	0.021	0.00	0.000	0.00	Excav. to elev. -7.10 on RIGHT side
6	0.020	0.00	0.000	0.00	Apply water pressure profile no.1
7	0.022	-5.60	0.000	0.00	Excav. to elev. -9.50 on RIGHT side

Prop forces at each stage (horizontal components)

Stage --- Strut no. 1 ---

no.	at elev.-3.00	
	kN/m run	kN/prop
4	1.00	1.00
5	76.49	76.49
6	81.00	81.00
7	129.86	129.86

VAN der MEER CONSULTING

Program: WALLAP Version 6.07 Revision A55.B74.R58

Licensed from GEOSOLVE

Data filename/Run ID: Section_2 (BH2)

Penrith

Section A

| Sheet No.

| Job No. 220070


| Made by : MS

| Date: 7-10-2022


| Checked :

Units: kN,m

Bending moment, shear force, displacement envelopes



Appendix B: Van der Meer Structural drawings




RETENTION PLAN - SHEET 1 (BASEMENT 1 SLAB)





SCALE 1 : 200

NOTES:

* DENOTES TEMPORARY PILE



- NOTES:**
1. REFER DRG. No. S01-02 AND S01-03 FOR STRUCTURAL NOTES
 2. REFER DRG. No. S01-05 FOR TYPICAL DETAILS
 3. FOR ALL SET OUT DIMENSIONS, LEVELS, SET DOWNS, HOBS, KERBS AND FALLS, REFER TO ARCHITECTS DRAWINGS.
- PROPOSED CONSTRUCTION METHODOLOGY:**
1. CONSTRUCT THE SHORING PILES FROM GROUND LEVEL & POUR THE CAPPING BEAM.
 2. EXCAVATE TO THE BASMENT LEVEL 1.
 3. CONSTRUCT THE PERMANENT & TEMPORARY PILES.
 4. FORM UP AND POUR BASEMENT 1 SLAB.
- BASEMENT B1 DOWN CONSTRUCTION METHODOLOGY:**
1. EXACAVATE TO BASEMENT 3.
 2. INSTALL PILES & PILE CAPS SUPPORTING THE CORE WALLS.
 3. POUR BASMENT 3 (HYDRASTATIC SLAB).
 4. CONSTRUCT THE CORE WALL AND POUR BASEMENT 2 SLAB.
- BASEMENT B1 UP CONSTRUCTION METHODOLOGY:**
1. CONSTRUCT THE COLUMNS ABOVE BASEMENT 1 & POUR GROUND FLOOR SLAB.
 2. CONSTRUCT THE COLUMNS ON UPPER LEVELS & POUR UPPER SLABS.




TYPICAL INFILL SLAB DETAIL AT TEMPORARY PENETRATIONS



REVISIONS				
No.	REVISION DESCRIPTION	DATE	W.W.	DATE
C	PRELIMINARY ISSUE	03-11-2022	W.W.	03-11-2022
B	PRELIMINARY ISSUE	02-11-2022	W.W.	02-11-2022
A	PRELIMINARY ISSUE	07-10-2022	W.W.	07-10-2022

SCALE BAR	
0 10 20 30 40 50 100 mm	1:1
COPYRIGHT THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF VAN DER MEER (NSW) PTY LTD. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE AUTHORITY OF VAN DER MEER (NSW) PTY LTD.	
NOTE THIS IS AN UNCONTROLLED DOCUMENT ISSUED FOR INFORMATION PURPOSES ONLY. UNLESS SIGNED, FIGURED DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS. VERIFY DIMENSIONS PRIOR TO COMMENCING ANY ON-SITE OR OFF-SITE WORKS OR FABRICATION. IF IN DOUBT - ASK.	



van der meer

LEVEL 6, 39 CHANDOS STREET
SYDNEY NSW 2065
Telephone 61-2-9436 0433

www.vandermeer.com.au
van der Meer (NSW) Pty Ltd
ABN 56 158 266 301

CLIENT

URBAN PROPERTY
LEVEL 10/11-15 DEANE STREET
BURWOOD NSW 2134
PH: (02) 9744 3333

ARCHITECT

SJB ARCHITECTS
LEVEL 2, 490 CROWN STREET
SURRY HILLS NSW 2010
PH: (02) 9380 9911

PROJECT TITLE

160, 162 & 172 LORD SHEFFIELD
CIRCUIT, NORTH PENRITH

DRAWING TITLE

RETENTION PLAN - SHEET 1

DRAWING STATUS			
PRELIMINARY NOT TO BE USED FOR CONSTRUCTION			
PROJECT LEADER A.A.	DESIGNER M.S.	SIGNATURE	
DRAFTSPERSON W.W.	SCALE 1:20, 1:200	DATE	SHEET SIZE A1
JOB No. SY220-070	DRAWING No. S02-01	REVISION C	

1. REFER DRG. No. S01-02 AND S01-03 FOR STRUCTURAL NOTES
2. REFER DRG. No. S01-05 FOR TYPICAL DETAILS
3. FOR ALL SET OUT DIMENSIONS, LEVELS, SET DOWNS, HOBS, KERBS AND FALLS, REFER TO ARCHITECTS DRAWINGS.

BASEMENT B1 DOWN CONSTRUCTION METHODOLOGY:


1. EXCAVATE TO BASEMENT 3.
2. INSTALL PILES & PILE CAPS SUPPORTING THE CORE WALLS.
3. POUR BASEMENT 3 (HYDRASTATIC SLAB).
4. CONSTRUCT THE CORE WALL AND POUR BASEMENT 2 SLAB

RETENTION PLAN - SHEET 2 (BASEMENT 1 SLAB)

SCALE 1:200


NOTES:
* DENOTES TEMPORARY PILE

NOTES:
* DENOTES TEMPORARY PILE



SECTION 4
SCALE 1:200 S02-02


REVISIONS				
No.	REVISION DESCRIPTION	DRAWN	DATE	
C	PRELIMINARY ISSUE	W.W.	03-11-2022	
B	PRELIMINARY ISSUE	W.W.	02-11-2022	
A	PRELIMINARY ISSUE	W.W.	07-10-2022	



COPYRIGHT
THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF VANDER MEER (NSW) PTY LTD. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE AUTHORITY OF VANDER MEER (NSW) PTY LTD.

DISCLAIMER
THIS DRAWING AND ITS CONTENTS ARE ELECTRONICALLY GENERATED, ARE CONFIDENTIAL, AND MAY ONLY BE USED FOR THE PURPOSES FOR WHICH THEY WERE INTENDED. VANDER MEER (NSW) PTY LTD WILL NOT ACCEPT RESPONSIBILITY FOR ANY CONSEQUENCES ARISING FROM THE USE OF THE DRAWING FOR OTHER THAN ITS INTENDED PURPOSE.

WHERE THE DRAWING HAS BEEN ALTERED, AMENDED OR CHANGED EITHER MANUALLY OR ELECTRONICALLY BY ANY THIRD PARTY, NOTE
THIS IS AN UNCONTROLLED DOCUMENT SUITABLE FOR INFORMATION PURPOSES ONLY. UNLESS SIGNED, FIGURED DIMENSIONS TAKE PRECEDENCE OVER SCALED
DO NOT SCALE REQUIRED SCALE DRAWINGS. VERY DIMENSIONS REFER TO COMMENCING ANY ON-SITE OR OFF-SITE WORKS OR FURTHER CONSTRUCTION.
IF IN DOUBT - ASK



 **van der meer**

LEVEL 6, 39 CHANDOS STREET
SYDNEY NSW 2065
Telephone 61-2-9436 0433

www.vandermeer.com.au
van der Meer (NSW) Pty Ltd
ABN 56 158 266 301

CLIENT

URBAN PROPERTY
LEVEL 10/11-15 DEANE STREET
BURWOOD NSW 2134
PH: (02) 9744 3333

ARCHITECT

SJB ARCHITECTS
LEVEL 2, 490 CROWN STREET
SURRY HILLS NSW 2010
PH: (02) 9380 9911

PROJECT TITLE

160, 162 & 172 LORD SHEFFIELD
CIRCUIT, NORTH PENRITH

DRAWING TITLE

RETENTION PLAN - SHEET 2


DRAWING STATUS

PRELIMINARY
NOT TO BE USED FOR CONSTRUCTION


PROJECT LEADER A.A.	DESIGNER M.S.	SIGNATURE	
DRAFTSPERSON W.W.	SCALE 1:200, 1:600	DATE	SHEET SIZE A1
JOB No. SY220-070	DRAWING No. S02-02	REVISION C	

C:\Users\warren.williams\Documents\SY220-070_Lord_Sheffield_Circuit_RVT21_warren.williams\WMS2.dwg


3/11/2022 4:10:07 PM




ELEVATION - SW1
SCALE 1 : 200




ELEVATION - SW2
SCALE 1 : 200




ELEVATION - SW3
SCALE 1 : 200




ELEVATION - SW4
SCALE 1 : 200




ELEVATION - SW5
SCALE 1 : 200



ELEVATION - SW6
SCALE 1 : 200




ELEVATION - SW7
SCALE 1 : 200



ELEVATION - SW8
SCALE 1 : 200

- NOTES:**
1. REFER DRG. No. S01-02 AND S01-03 FOR STRUCTURAL NOTES
 2. REFER DRG. No. S01-05 FOR TYPICAL DETAILS
 3. FOR ALL SET OUT DIMENSIONS, LEVELS, SET DOWNS, HOBS, KERBS AND FALLS, REFER TO ARCHITECTS DRAWINGS.

REVISIONS				
No.	REVISION DESCRIPTION	W.W.	DATE	
B	PRELIMINARY ISSUE	W.W.	03-11-2022	
A	PRELIMINARY ISSUE	W.W.	07-10-2022	



COPYRIGHT
THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF VAN DER MEER (NSW) PTY LTD. IT MUST NOT BE RETAINED, COPIED OR USED WITHOUT THE AUTHORITY OF VAN DER MEER (NSW) PTY LTD.
NOTE
THIS IS AN UNCONTROLLED DOCUMENT ISSUED FOR INFORMATION PURPOSES ONLY. UNLESS SIGNED, FIGURED DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS.
DO NOT SCALE REDUCED SIZE DRAWINGS. VERIFY DIMENSIONS PRIOR TO COMMENCING ANY ON-SITE OR OFF-SITE WORKS OR FABRICATION.
IF IN DOUBT - ASK.



van der meer

LEVEL 6, 39 CHANDOS STREET
SYDNEY NSW 2065
Telephone 61-2-9436 0433

www.vandermeer.com.au
van der Meer (NSW) Pty Ltd
ABN 56 158 266 301

CLIENT URBAN PROPERTY LEVEL 10/11-15 DEANE STREET BURWOOD NSW 2134 PH: (02) 9744 3333		PROJECT TITLE 160, 162 & 172 LORD SHEFFIELD CIRCUIT, NORTH PENRITH		DRAWING STATUS PRELIMINARY NOT TO BE USED FOR CONSTRUCTION	
ARCHITECT SJB ARCHITECTS LEVEL 2, 490 CROWN STREET SURRY HILLS NSW 2010 PH: (02) 9380 9911		DRAWING TITLE RETENTION ELEVATIONS - SHEET 1		PROJECT LEADER A.A.	DESIGNER M.S.
		DRAFTSPERSON W.W.	SCALE 1:200	DATE	SHEET SIZE A1
		JOB No. SY220-070	DRAWING No. S02-11	REVISION B	



- NOTES:**
1. REFER DRG. No. S01-02 AND S01-03 FOR STRUCTURAL NOTES
 2. REFER DRG. No. S01-05 FOR TYPICAL DETAILS
 3. FOR ALL SET OUT DIMENSIONS, LEVELS, SET DOWNS, HOBS, KERBS AND FALLS, REFER TO ARCHITECTS DRAWINGS.

REVISIONS				SCALE BAR 01020304050 100 mm 1:1		van der meer LEVEL 6, 39 CHANDOS STREET SYDNEY NSW 2065 Telephone 61-2-9436 0433 www.vandermeer.com.au van der Meer (NSW) Pty Ltd ABN 56 158 266 301	CLIENT URBAN PROPERTY LEVEL 10/11-15 DEANE STREET BURWOOD NSW 2134 PH: (02) 9744 3333		PROJECT TITLE 160, 162 & 172 LORD SHEFFIELD CIRCUIT, NORTH PENRITH		DRAWING STATUS PRELIMINARY NOT TO BE USED FOR CONSTRUCTION											
COPYRIGHT THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF VAN DER MEER (NSW) PTY LTD. IT MUST NOT BE REPRODUCED, COPIED OR USED WITHOUT THE AUTHORITY OF VAN DER MEER (NSW) PTY LTD. THIS DRAWING AND ITS CONTENTS ARE ELECTRONICALLY GENERATED, ARE CONFIDENTIAL AND MAY ONLY BE USED FOR THE PURPOSE FOR WHICH THEY WERE INTENDED. VAN DER MEER (NSW) PTY LTD. WILL NOT ACCEPT RESPONSIBILITY FOR ANY CONSEQUENCES ARISING FROM THE USE OF THE DRAWING FOR OTHER THAN ITS INTENDED PURPOSE OR WHERE THE DRAWING HAS BEEN ALTERED, AMENDED OR CHANGED EITHER MANUALLY OR ELECTRONICALLY BY ANY THIRD PARTY. THIS IS AN UNCONTROLLED DOCUMENT ISSUED FOR INFORMATION PURPOSES ONLY (UNLESS SOLEMNLY STATED OTHERWISE). THIS PRECEDENCE OVER SCALE. DO NOT SCALE DIMENSIONS. VERIFY DIMENSIONS PRIOR TO COMMENCING ANY ON-SITE OR OFF-SITE WORKS OR FABRICATION. IF IN DOUBT - ASK.				ARCHITECT SJB ARCHITECTS LEVEL 2, 490 CROWN STREET SURRY HILLS NSW 2010 PH: (02) 9380 9911			DRAWING TITLE RETENTION DETAILS - SHEET 1		<table><tr><td>PROJECT LEADER A.A.</td><td>DESIGNER M.S.</td><td colspan="2">SIGNATURE</td></tr><tr><td>DRAFTSPERSON W.W.</td><td>SCALE 1:20</td><td>DATE</td><td>SHEET A1</td></tr><tr><td colspan="2">JOB No. SY220-070</td><td>DRAWING No. S02-51</td><td>REVISION A</td></tr></table>		PROJECT LEADER A.A.	DESIGNER M.S.	SIGNATURE		DRAFTSPERSON W.W.	SCALE 1:20	DATE	SHEET A1	JOB No. SY220-070		DRAWING No. S02-51	REVISION A
PROJECT LEADER A.A.	DESIGNER M.S.	SIGNATURE																				
DRAFTSPERSON W.W.	SCALE 1:20	DATE	SHEET A1																			
JOB No. SY220-070		DRAWING No. S02-51	REVISION A																			
<table><tr><th>No.</th><th>PRELIMINARY ISSUE</th><th>REVISION DESCRIPTION</th><th>W/W</th><th>DATE</th></tr><tr><td>A</td><td></td><td></td><td></td><td>07-10-2022</td></tr></table>				No.	PRELIMINARY ISSUE	REVISION DESCRIPTION	W/W	DATE	A				07-10-2022									
No.	PRELIMINARY ISSUE	REVISION DESCRIPTION	W/W	DATE																		
A				07-10-2022																		

Appendix C: Excavation methodology statement

Our Ref: SY220-070
Enquiries to: AA



18 October 2022

URBAN Property
Level 10, 11-15 Deane St
Burwood NSW 2134

Attention: Mr Chris Georgas

**RE: 160,162 & 172 LORD SHEFFIELD CIRCUIT, NORTH PENRITH
EXCAVATION METHODOLOGY**

This letter has been prepared to detail the excavation methodology for the proposed development located at 160,162 & 172 Lord Sheffield Circuit, North Penrith.

The western portion of the site accommodates the Thornton Community Garden. The site is immediately adjacent to the northern entrance of Penrith Station (west boundary). The Eastern boundary is adjacent a parcel of defence land (east boundary). The Southern boundary has a direct interface with the railway corridor.

Due to the proximity of Transport for New South Wales assets, the use of ground anchors has not been permitted. As a result, the concept design is focused on the top-down construction with the permanent slab restraining the shoring wall at basement 1 level.

Based on the received architectural drawings, the maximum excavation level of 10m is assumed in the preliminary design which accounts for three basements. Ground water level is approximately one meter above the level of the future basement 2 slab and therefore tanked basement with hydrostatic slab is required. To resist water pressure, secant pile wall will be constructed as per the geotechnical advice.

Construction methodology is allowing for the excavation of the soil up to 3.5m to allow construction of the basement 1 slab which will provide restraint to the shoring wall in lieu of ground anchors. The slab will be designed for both temporary and permanent stage. During construction, slab at basement 1 will be used as a working platform to allow not only excavation of the soil from underneath but also construction of the structure above B1 at the same time.



The above design assumptions result in two construction methodologies required:


- Top-down excavation
- Bottom-up construction

Both construction methodologies are detailed below.

1. Top-down excavation (basement 3 to basement 1)

Below is a plan showing our working platform at basement 1 level and section reflecting interaction of the proposed shoring wall in respect to the existing train corridor.





To further elaborate on the sequencing of top-down construction, please find below detailed shoring and excavation sequence advice for the 160,162 & 172 Lord Sheffield Circuit, North Penrith development.

Construction methodology for the basement 3 to basement 1 levels (top-down):

1. Site to be levelled to the top of shoring wall.
2. Shoring soft (unreinforced) piles to be installed in accordance with structural documentation and geotechnical advice.
3. Shoring hard (reinforced) piles to be installed in accordance with structural documentation and geotechnical advice.
4. Capping beam to be poured.
5. Ground to be excavated to 0.5m below the basement 1 level (maximum 3.5m)
6. Permanent and temporary piles supporting future basement 1 slab to be installed in accordance with structural documentation and geotechnical advice.
7. Slab at basement 1 to be formed and poured. Slab at basement 1 will require penetrations left to allow the construction of the future core walls.
8. Ground to be excavated to the BEL level after slab at B1 achieved sufficient design strength.
9. Pile foundations for the core walls to be installed in accordance with structural documentation and geotechnical advice.
10. Pile cap to be formed and poured.
11. Hydrostatic slab on ground to be poured.
12. Core walls from B3 to B2 to be poured.
13. Basement 2 slab to be formed and poured ensuring adequate connections to the permanent piles have been achieved in accordance with the structural documentation.
14. Core walls from B2 to B1 to be poured ensuring that adequate connections to the slab at basement 1 have been achieved in accordance with the structural documentation.

2. Bottom-up construction (basement 1 – up)

Construction sequencing has been prepared to allow construction of the levels above the basement 1 slab whilst excavating the soil from underneath the slab. Please find below detailed construction sequencing:

1. Columns and walls at basement 1 to be formed and poured. Core walls to be constructed at the later time after the excavation and piling has been completed.
2. Ground floor slab and upper levels to be formed and poured. Temporary penetrations will be required to allow future construction of the core walls.
3. Steps 1 and 2 to be followed until the core walls have been constructed to the level of the next slab to avoid creating temporary penetration in the slab above.

Yours faithfully
van der Meer Consulting



Ash Afnani

Senior Associate – Structural
PhD, CPEng, NER