

Oakdale West Estate Kemps Creek Lot 4C & Lot 4D Civil Report

CLIENT/ GOODMAN DATE/ JANUARY 2023 CODE/ 15-272

Commercial in Confidence

All intellectual property rights, including copyright, in designs developed and documents created by AT&L remain the property of this company. Any use made of such design or document without the prior written approval of AT&L will constitute an infringement of the rights of the company which reserves all legal rights and remedies in respect of any such infringement.

The information, including any intellectual property, contained in this proposal is confidential and proprietary to the Company. It may only be used by the person to whom it is provided for the stated purpose for which it is provided and must not be imparted to any third person without the prior written approval of the Company. The Company reserves all legal rights and remedies in relation to any infringement of its rights in respect of its confidential information.

This report has been prepared in accordance with the terms and conditions of appointment. AT&L cannot accept any responsibility for any use of or reliance on the contents of this report by any third party.

This report may be based upon information supplied by other consultants and contractors. To the extent that the report incorporates such material, AT&L takes no responsibility for any loss or damage caused by any error or omission arising from reliance on it.

Document Title	Oakdale West Estate – Lot 4C & Lot 4D Civil Report
Document File Name	REP107-02-15-272 - Lot 4C Lot 4D Civil Report.docx
Section	AT&L - Engineering Division
Document Author	Alastair Charteris

Document Registration

Issue	Description	Date	Author	Checked	Approved
01	Draft	21-11-22	Alastair Charteris		
02	Final	11-01-23	Alastair Charteris		



Contents

1	Execu	itive Sumr	tive Summary			
2	Introd	luction		2		
	2.1	Scope of R	eport	2		
3	Storm	water Mar	nagement	3		
	3.1	The Existin	ıg Site	3		
	3.2	Proposed S	Site Stormwater Drainage	3		
	3.3	Council Re	quirements, SSD Consent Conditions & Recommendations	3		
		3.3.1	Modelling Software	.4		
		3.3.2	Hydrology	. 4		
		3.3.3	Hydraulics	.5		
		3.3.4	Catchments	. 5		
		3.3.5	Overland Flows	.6		
	3.4	Conclusion	1	6		
4	Sedim	nentation a	and Erosion Control	7		
	4.1	Sedimenta	tion and Erosion Control (Construction)	7		
		4.1.1	Design of Sediment and Erosion Control Measures	.7		
	4.2	Site Inspec	tion and Maintenance	7		
		4.2.1	Sediment Basin Maintenance	. 8		
	4.3	Conclusion	1	8		



APPENDIX

Appendix A – Proposed Site Plans, Staging and Catchment Plans Appendix B – List of Civil Works & Erosion and Sediment Control Drawings Appendix C – Lot 4C and 4D Stormwater Drainage Catchment Plan

Abbreviations

OWE	Oakdale West Estate
WNSLR	Western North South Link Road
TfNSW	Transport for NSW
OEH	Office of Environment and Heritage
EP	Equivalent Persons
ET	Equivalent Tenancy
IWM	Integrated Water Management
GPS	Goodman Property Services (Aust) Pty Ltd
STP	Sewerage Treatment Plant
SWC	Sydney Water Corporation
WELS	Water Efficiency Labelling
EIS	Environmental Impact Statement
SSDA	State Significant Development Application
RMS	Roads and Maritime Service
EPLR	Erskine Park Link Road



1 Executive Summary

Goodman Property Services (Aust) Pty Ltd is developing the Oakdale West Estate for the purposes of providing a warehouse and distribution complex. The Oakdale West site is a precinct within the wider 'Oakdale' Estate development and forms part of a progressive development designed to make 'Oakdale' a regional distribution park of warehouses, distribution centres and freight logistics facilities.

The Oakdale West project is a staged development including bulk earthworks, civil works, and services infrastructure and stormwater disposal and management. All reports, drawings are approved under a separate application SSD 7348.

For the purpose of this report, it is assumed that the infrastructure stage works are approved and completed. This includes but not limited to; Bulk earthworks, Access Roads, Services, Stormwater Basins, Stormwater system and connection into each lot.

This development application encompasses the planned phase of civil works on the Oakdale West site, specifically on-lot works associated with Lot 4C & Lot 4D.

The on-lot works include:

- Proposed detailed earthworks to accommodate the building and external carpark levels
- Proposed stormwater (piped) system and connection / relocation of the existing drainage system provided in the infrastructure works.
- Proposed overland flow path to relevant basin, outlined in SSD 7348. Lot 4C & Lot 4D drains predominantly to Basin 4.
- Proposed hardstand and carpark pavement.
- Proposed Erosion and Sediment control

This report is prepared to satisfy condition C11 with SSD 7348:

Future DAs shall demonstrate the design of the warehouses, offices and hardstand areas are consistent with (or the latest revision of) the:

(a) Civil, Stormwater and Infrastructure Services Report, prepared by AT&L, dated October 2018; and

(b) Flood Impact Assessment: Oakdale West Estate, prepared by Cardno, dated 27 March 2017.

This report is to be read in conjunction with AT&L's latest civil report prepared for SSD 7348, which is entitled 'REP005-01-15-272-MOD 7 Civil Report'.

The site is located in the Penrith City Council Local Government area. Under SSD 7348, Precinct based bio-retention basins are provided as part of the infrastructure works. The basins are designed to both attenuate stormwater flows and treat the nutrients to Penrith City Council treatment rates. The Precinct based Site Detention is designed to mitigate post development flows to pre-developed flows for peak Average Reoccurrence Interval (ARI) events and has been sized to ensure that for all storm events up to and including the 1% AEP event.



2 Introduction

The aim of the report is to assess the potential impacts of the proposed development with respect to Stormwater and has been prepared in accordance with Penrith City Council current design guidelines and the relevant Australian Standards.

2.1 Scope of Report

This report generally discusses the design philosophy behind the following components of the Stormwater Management design for Oakdale West Estate (OWE):

- Stormwater Management
 - o Infrastructure Biodiversity and Bioretention Basin
 - Piped and Overland Flows
 - o Water Balance across the site
- Erosion and Sediment Control
- Pavement
- Site Services

The proposed Lot 4C is bound by Future Southern Link Road to the West, Tundra Close (Estate Road 08) To the north, an existing Transgrid easement and Lot 4D to the West, and South Erskine Park Zone Substation to the South.

The proposed Lot 4D is bound by an existing Transgrid easement and Road No.8 (Tundra Close) to the East, Lot 4E to the south, and Lot 4C/Cuprum Close to the West and North.




Figure 1 – Locality Plan



3 Stormwater Management

3.1 The Existing Site

For the purpose of this report, it is assumed that the infrastructure stage works are approved and completed. This includes but not limited to; Bulk earthworks, Access Roads, Services, Stormwater Basins, Stormwater system and connections into lots. The works are detailed in Stage 1 consent, SSD 7348.

Refer to Drawings C1086 and C1087 within Appendix A for a pre-development and postdevelopment stormwater catchment plans indicating the location of basins and catchments provided in the infrastructure stage.

3.2 Proposed Site Stormwater Drainage

Lot 4C and Lot 4D are a part of a larger catchment which ultimately discharges into Bio-Retention Basin No.4 as shown in Appendix A. For additional details on Basin 4, refer to 'REP005-01-15-272-MOD 7 Civil Report'.

- Lot 4C has a catchment of approximately 5.8Ha. The main proposed stormwater discharge point is located to the east of Lot 4C by connecting into the existing stormwater line. A GPT will be provided to capture the gross pollutants generated within Lot 4C before discharging into Basin 4. There is a catch drain provided to the north of Lot 4C which collects no hardstand run off and discharges into the Road 8 network.
- Lot 4D has a catchment of approximately 1.3Ha. The proposed stormwater discharge point is to the northeast of Lot 4D by connecting into the existing stormwater line. A GPT will be provided to capture the gross pollutants generated within Lot 4D before discharging into Basin 4.

Refer to the Civil Drawings for layout and details for the proposed stormwater network across the site contained in Appendix B.

Refer to drawing C7950 detailing Lot's 4C and 4D site stormwater drainage catchment plan contained in Appendix C.

3.3 Council Requirements, SSD Consent Conditions & Recommendations

This report is prepared to satisfy condition C11 with SSD 7348, which states:

Future DAs shall demonstrate the design of the warehouses, offices and hardstand areas are consistent with (or the latest revision of) the:

- (a) Civil, Stormwater and Infrastructure Services Report, prepared by AT&L, dated October 2018; and
- (b) Flood Impact Assessment: Oakdale West Estate, prepared by Cardno, dated 27 March 2017.

All estate level stormwater drainage for the OWE development is designed to comply with the following:



- Penrith City Council Design Guidelines for Engineering Works;
- Penrith City Council Water Sensitive Urban Design (WSUD) Policy December 2013; and
- C3 Water Management DCP.

A summary of the design requirements adopted is listed below:

- All stormwater drainage within the Lot 4C and Lot 4D will be the responsibility of Goodman;
- Finished Floor Levels (FFL) of proposed buildings within the precinct (separate approval) to have minimum 500mm freeboard to 1% AEP overland flows; and
- Gross pollutant traps (GPTs) will be installed within Lot 4C and Lot 4D on the final downstream stormwater pits prior to discharging. As these GPT's will be located on-lot, they will be owned and maintained by Goodman. The GPT will capture 90% of Gross Pollutants from Lot 4C and Lot 4D as per the PCC WSUD guidelines.

Rainwater tanks are desirable for re-use for irrigation, toilet and other non-potable water uses. Rainwater tank size is determined in accordance with the Penrith City Council C3 Water Management DCP to meet 80% of non-potable demand for irrigation and toilet flushing.

3.3.1 Modelling Software

12D modelling software has been used to calculate the Hydraulic Grade Line (HGL) of the estate level stormwater pipes. 12D is a computer program used for designing and analysing urban stormwater drainage systems and catchments.

3.3.2 Hydrology

- Pipe drainage shall be designed to accommodate the 5% AEP storm event;
- The combined piped and overland flow paths shall be designed to accommodate the 1% AEP storm event;
- Where trapped low points are unavoidable and potential for flooding private property is a concern, an overland flow path capable of carrying the total 1% AEP storm event shall be provided. Alternatively, the pipe and inlet system may be upgraded to accommodate the 1% AEP storm event;
- Rainfall intensities shall be as per the Intensity-Frequency-Duration table in accordance with the Australian Rainfall and Runoff (AR&R) volume 2;
- Times of concentration for each sub catchment shall be determined using the kinematic wave equation;
- Runoff coefficients shall be calculated in accordance with AR&R. The fraction impervious shall be determined from analysis of the sub catchments;
- Flow width in kerb and gutter shall not exceed 2.5m for the minor design storm event;
- Velocity depth ratios shall not exceed 0.4 for all storms up to and including the 1% AEP event;
- Inlet pits to be spaced so that flow width shall not exceed 80L/sec;
- Bypass from any pit on grade shall not exceed 15% of the total flow at the pit; and
- Blockage factors of 20% and 50% shall be adopted for pits on grade and at sags respectively, with these blockage factors in-built to each pit within the 12D model.



3.3.3 Hydraulics

- Pipe drainage shall be designed to accommodate the 5% AEP storm event;
- The combined piped and overland flow paths shall be designed to accommodate the 1% AEP storm event;
- Where trapped low points are unavoidable and potential for flooding private property is a concern, an overland flow path capable of carrying the total 1% AEP storm event shall be provided. Alternatively, the pipe and inlet system may be upgraded to accommodate the 1% AEP storm event;
- Rainfall intensities shall be as per the Intensity-Frequency-Duration table in accordance with the Australian Rainfall and Runoff (AR&R) volume 2;
- Times of concentration for each sub catchment shall be determined using the kinematic wave equation;
- Runoff coefficients shall be calculated in accordance with AR&R. The fraction impervious shall be determined from analysis of the sub catchments;
- Flow width in kerb and gutter shall not exceed 2.5m for the minor design storm event;
- Velocity depth ratios shall not exceed 0.4 for all storms up to and including the 1% AEP event;
- Inlet pits to be spaced so that flow width shall not exceed 80L/sec;
- Bypass from any pit on grade shall not exceed 15% of the total flow at the pit; and
- Blockage factors of 20% and 50% shall be adopted for pits on grade and at sags respectively, with these blockage factors in-built to each pit within the 12D model;
- The pipe friction coefficients to adopted shall be:

Materials	Mannings – n	Colebrook-White - k	Min. Pipe Class
RCP	0.012	0.6	3
FRC	0.01	0.15	3

Table 1 – Pipe Details

- All pipes classes shall be designed for the ultimate service loads and where applicable, construction loads will be designed for;
- Pipes discharging to the overland flow path shall adopt a minimum tailwater level equivalent to respective overland flow level;
- Pit Loss coefficients shall be calculated in accordance with Missouri Charts;
- A minimum 150mm freeboard shall be maintained between pit HGL and pit surface levels for the minor storm event;
- Overland flowpaths shall maintain a minimum of 500mm freeboard to all habitable floor levels; and
- Pits deeper than 1.2m shall contain step irons at 300 mm centres.

3.3.4 Catchments

A Stormwater Catchment Plan for Lot 4C and Lot 4D, and flow paths into the Bio-retention Basins No. 4 are shown in Appendix A.



3.3.5 Overland Flows

Overland flows within the hardstand area and carparks have been designed to be safely conveyed to inground drainage for all storms above the 5% AEP up to 1% AEP.

All flow widths and velocities are design in accordance with the Penrith City Council Design Guidelines for Engineering Works.

3.4 Conclusion

As highlighted in the above section, all stormwater drainage within Lot 4C & Lot 4D development has been designed in accordance with the Penrith City Council Engineering Guidelines. This includes design of the stormwater network (pits and pipes) and GPTs.

Finished Floor Levels (FFL) to have minimum 500mm freeboard to 1% AEP overland flows.



4 Sedimentation and Erosion Control

4.1 Sedimentation and Erosion Control (Construction)

A Soil and Water Management Plan (SWMP) will be prepared in accordance with the NSW Department of Housing Publication titled: Managing Urban Stormwater – Soils and Construction (2004) for Lot 4C and Lot 4D.

The key objective of the SWMP are:

- Acknowledging the activities on a construction site which may contribute to erosion, sedimentation and water quality impacts;
- The implementation of industry best management practices to minimise adverse water quality and sedimentation impacts brought about through construction activities on waterbodies surrounding the work; and
- Establishment of processes that effectively manage erosion, sedimentation and water quality practices during the life of the project.

4.1.1 Design of Sediment and Erosion Control Measures

Suitable erosion and sediment controls shall be provided by the Contractor and maintained throughout all stages of works, including at completion of the bulk earthworks.

All design, documentation, installation and maintenance of sediment and erosion controls will be in accordance with the requirements of:

- Protection of the Environment Operations Act;
- Penrith City Council's specifications; and
- Office of Environment and Heritage's 'Managing Urban Stormwater: Soils and Construction. Landcom, (4th Edition) (The "Blue Book") Volume 1 and Volume 2.

Temporary sediment basin in Lot 4C and Lot 4D will be provided within the infrastructure stage associated with the SSD 7348 Stage 1 consent works. The basins are to be maintained throughout the construction phase of the on-lot works, until such time that the site has been suitably stabilised and the sediment basin is no longer required to meet the requirements of the Blue Book.

4.2 Site Inspection and Maintenance

The inspection and maintenance requirements outlined in this section must be carried out while either earthworks or quarrying is being conducted, and all areas re-established.

The Contractor will be required to inspect the site after every rainfall event and at least weekly, and will:

- Inspect and assess the effectiveness of the SWMP and identify any inadequacies that may arise during normal work activities or from a revised construction methodology;
- Construct additional erosion and sediment control works as necessary to ensure the desired protection is given to downstream lands and waterways;



- Ensure that drains operate properly and to affect any repairs;
- Remove spilled sand or other materials from hazard areas, including lands closer than 5 metres from areas of likely concentrated or high velocity flows especially waterways and paved areas;
- Remove trapped sediment whenever less than design capacity remains within the structure;
- Ensure rehabilitated lands have affectively reduced the erosion hazard and to initiate upgrading or repair as appropriate;
- Maintain erosion and sediment control measures in a fully functioning condition until all construction activity is completed and the site has been rehabilitated;
- Remove temporary soil conservation structures as the last activity in the rehabilitation.
- Inspect the sediment basin during the following periods:
 - During construction to determine whether machinery, falling trees, or construction activity has damaged and components of the sediment basin. If damage has occurred, repair it;
 - After each runoff event, inspect the erosion damage at flow entry and exit points. If damage has occurred, make the necessary repairs;
 - At least weekly during the nominated wet season (if any), otherwise at least fortnightly; and
 - Prior to, and immediately after, periods of 'stop work' or site shutdown.
- Clean out accumulated sediment when it reaches the marker board/post, and restore the original volume. Place sediment in a disposal area or, if appropriate, mix with dry soil on the site;
- Do not dispose of sediment in a manner that will create an erosion or pollution hazard;
- Check all visible pipe connections for leaks, and repair as necessary;
- Check all embankments for excessive settlement, slumping of the slopes or piping between the conduit and the embankment, make all necessary repairs;
- Remove the trash and other debris from the basin and riser; and
- Submerged inflow pipes must be inspected and de-silted (as required) after each inflow event.

4.2.1 Sediment Basin Maintenance

Stormwater within the settling zone should be drained or pumped out within 5 days (design time), if the nominated water quality targets can be met, to the satisfaction of the superintendent. Flocculation should be employed where extended settling is likely to fail to meet the objectives within the 5-day time period.

Flocculation is when flocculating agents are applied to the sediment basins causing the colloidal particles to clump into larger units or 'floc' that can either settle in a reasonable time or be filtered.

Refer to Appendix E4 of the Blue Book for flocculation methodologies and manufacturer's instructions for application rates, regarding the proposed sediment basins.

4.3 Conclusion

The erosion control measures proposed for the site will comply with the requirements of Penrith City Council Engineering Guidelines and in accordance with the latest revision AT&L infrastructure report.





A SWMP will ensure that the best management practice is applied to the development site in controlling and minimising the negative impacts of soil erosion.



Appendix A

Pre-Development and Post-Development Site Catchment Plans








Appendix B

List of Civil Works & Erosion and Sediment Control Drawings

OAKDALE WEST 7900-SERIES LOT 4C & 4D CIVIL WORKS PACKAGE DEVELOPMENT APPLICATION

	DRAWING LIST
DRAWING No.	DRAWING TITLE
15-272-C7900	COVER SHEET DRAWING LIST LOCALITY PLAN
15-272-C7901	GENERAL NOTES
15-272-C7905	GENERAL ARRANGEMENT PLAN
15-272-C7910	TYPICAL SECTIONS SHEET 1
15-272-C7911	TYPICAL SECTIONS SHEET 2
15-272-C7912	TYPICAL SECTIONS SHEET 3
15-272-C7913	TYPICAL SECTIONS SHEET 4
15-272-C7914	TYPICAL SECTIONS SHEET 5
15-272-C7915	BULK EARTHWORKS PLAN
15-272-C7920	SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 1
15-272-C7921	SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 2
15-272-C7922	SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 3
15-272-C7923	SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 4
15-272-C7924	SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 5
15-272-C7925	SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 6
15-272-C7926	SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 7
15-272-C7930	PAVEMENT PLAN
15-272-C7935	RETAINING WALL GENERAL ARRANGEMENT PLAN
15-272-C7936	RETAINING WALL PROFILES
15-272-C7940	EROSION AND SEDIMENT CONTROL PLAN
15-272-C7941	EROSION AND SEDIMENT DETAILS

			Bar Scales
]
P5	FINAL FOR DA	18-01-23	
P4	REISSUED FOR DA	22-12-22	
P3	REISSUED FOR DRAFT	20-12-22	
P2	ISSUED FOR DA	18-11-22	
P1	ISSUED FOR DRAFT	11-11-22	
Issue	Description	Date	
	100mm on Original		7




LOCALITY PLAN

NTS

	Client		Scales		Drawn	KS	Project
THIS DRAWING CANNOT BE		+			Designed	AC	1
COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY			Grid	LOCAL	Checked	SC	
OTHER PURPOSE OTHER THAN		Goodman	Height Datum	AHD	Approved		OA Title
THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN							nue
PERMISSION OF AT&L							
						F•\15_	272 Oaki

:\15-272 Oakdale West\Drgs\Civil\Final\SSDA\7000_On-Lot Works Packages\7900 LOT 4C 4D\15-272-C7900.dwg



SITEWORKS NOTES

- 1. ORIGIN OF LEVELS:- REFER SURVEY NOTES.
- 2. CONTRACTOR MUST VERIFY ALL DIMENSIONS AND EXISTING LEVELS ON SITE PRIOR TO COMMENCEMENT OF WORK. ANY DISCREPANCIES TO BE REPORTED TO AT & L.
- 3. MAKE SMOOTH CONNECTION WITH EXISTING WORKS.
- 4. ALL TRENCH BACKFILL MATERIAL SHALL BE COMPACTED TO THE SAME DENSITY AS THE ADJACENT MATERIAL
- 5. ALL SERVICE TRENCHES UNDER VEHICULAR PAVEMENTS SHALL BE BACKFILLED WITH SAND TO 300mm ABOVE PIPE. WHERE PIPE IS UNDER PAVEMENTS BACKFILL REMAINDER OF TRENCH TO UNDERSIDE OF PAVEMENT WITH SAND OR APPROVED GRANULAR MATERIAL COMAPACTED IN 150mm LAYERS TO MINIMUM 98% MODIFIED MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS 1289 5.2.1. (OR A DENSITY INDEX OF NOT LESS THAN 75)
- 6. PROVIDE 10mm WIDE EXPANSION JOINTS BETWEEN BUILDINGS AND ALL CONCRETE OR UNIT PAVEMENTS.
- 7. ASPHALTIC CONCRETE SHALL CONFORM TO R.M.S SPECIFICATION R116.
- 8. ALL BASECOURSE MATERIAL SHALL BE IGNEOUS ROCK QUARRIED MATERIAL TO COMPLY WITH R.M.S FORM 3051 (UNBOUND), R.M.S FORM 3052 (BOUND) COMPACTED TO MINIMUM 98% MODIFIED DENSITY IN ACCORDANCE WITH AS 1289 5.2.1 FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN 1 TEST PER 50m OF BASECOURSE MATERIAL PLACED.
- 9. ALL SUB-BASE COURSE MATERIAL SHALL BE IGNEOUS ROCK QUARRIED MATERIAL TO COMPLY WITH R.M.S FORM 3051, 3051.1 AND COMPACTED TO MINIMUM 95% MODIFIED DENSITY IN ACCORDANCE WITH A.S 1289 5.2. FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN 1 TEST PER 50m OF SUB-BASE COURSE MATERIAL PLACED.
- 10. AS AN ALTERNATIVE TO THE USE OF IGNEOUS ROCK AS A SUB-BASE MATERIAL IN (9) A CERTIFIED RECYCLED CONCRETE MATERIAL COMPLYING WITH R M S FORM 3051 AND 3051 1 WILL BE CONSIDERED SUBJECT TO MATERIAL SAMPLES AND APPROPRIATE CERTIFICATIONS BEING PROVIDED TO THE SATISFACTION OF AT & L.
- 11. SHOULD THE CONTRACTOR WISH TO USE A RECYCLED PRODUCT THE CONTRACTOR IS TO SEEK ACCEPTANCE OF THE PRODUCT FROM AT&L. THE PRICE DIFFERENCE BETWEEN AN IGNEOUS PRODUCT AND A RECYCLED PRODUCT SHALL BE CLEARLY INDICATED.
- 12. WHERE NOTED ON THE DRAWINGS THAT WORKS ARE TO BE CARRIED BY OTHERS, (eg. ADJUSTMENT OF SERVICES), THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CO-ORDINATION OF THESE WORKS.

SURVEY NOTES

THE EXISTING SITE CONDITIONS SHOWN ON THE FOLLOWING DRAWINGS HAVE BEEN INVESTIGATED BY CARDNO HARD & FORESTER PTY LTD, BEING REGISTERED SURVEYORS. THE INFORMATION IS SHOWN TO PROVIDE A BASIS FOR DESIGN. AT & L DOES NOT GUARANTEE THE ACCURACY OR COMPLETENESS OF THE SURVEY BASE OR ITS SUITABILITY AS A BASIS FOR CONSTRUCTION DRAWINGS.

SHOULD DISCREPANCIES BE ENCOUNTERED DURING CONSTRUCTION BETWEEN THE SURVEY DATA AND ACTUAL FIELD DATA. CONTACT AT & L.

THE FOLLOWING NOTES HAVE BEEN TAKEN DIRECTLY FROM THE ORIGINAL SURVEY DOCUMENTS.

IMPORTANT NOTE:

THIS PLAN IS PREPARED FROM A COMBINATION OF FIELD SURVEY AND EXISTING RECORDS FOR THE PURPOSE OF DESIGNING NEW CONSTRUCTIONS ON THE LAND AND SHOULD NOT BE USED FOR ANY OTHER PURPOSE. THE TITLE BOUNDARIES SHOWN HEREON WERE NOT MARKED BY THE AUTHOR AT THE TIME OF SURVEY AND HAVE BEEN DETERMINED BY PLAN DIMENSIONS ONLY AND NOT BY FIELD MEASUREMENT.

A SERVICES SEARCH OF THE AREA SURVEYED ABOVE HAS NOT BEEN UNDERTAKEN. VISIBLE SERVICES SHOWN HEREON HAVE BEEN LOCATED WHERE POSSIBLE BY FIELD SURVEY. PRIOR TO ANY DEMOLITION, EXCAVATION OR CONSTRUCTION ON THE SITE, THE RELEVANT AUTHORITY SHOULD BE CONTACTED FOR POSSIBLE LOCATION OF FURTHER UNDERGROUND SERVICES AND DETAILED LOCATIONS OF ALL SERVICES. THIS NOTE IS AN INTEGRAL PART OF THIS PLAN.

EXISTING UNDERGROUND SERVICES NOTES

THE LOCATIONS OF UNDERGROUND SERVICES SHOWN IN THIS SET OF DRAWINGS HAVE BEEN PLOTTED FROM SURVEY INFORMATION AND SERVICE AUTHORITY INFORMATION. THE SERVICE INFORMATION HAS BEEN PREPARED ONLY TO SHOW THE APPROXIMATE POSITIONS OF ANY KNOWN SERVICES AND MAY NOT BE AS CONSTRUCTED OR ACCURATE.

AT & L CAN NOT GUARANTEE THAT THE SERVICES INFORMATION SHOWN ON THESE DRAWINGS ACCURATELY INDICATES THE PRESENCE OR ABSENCE OF SERVICES OR THEIR LOCATION AND WILL ACCEPT NO LIABILITY FOR INACCURACIES IN THE SERVICES INFORMATION SHOWN FROM ANY CAUSE WHATSOEVER.

CONTRACTORS SHALL TAKE DUE CARE WHEN EXCAVATING ONSITE INCLUDING HAND EXCAVATION WHERE NECESSARY.

CONTRACTORS ARE TO CONTACT THE RELEVANT SERVICE AUTHORITY PRIOR TO COMMENCEMENT OF EXCAVATION WORKS.

CONTRACTORS ARE TO UNDERTAKE A SERVICES SEARCH, PRIOR TO COMMENCEMENT OF WORKS ON SITE. SEARCH RESULTS ARE TO BE KEPT ON SITE AT ALL TIMES.

Bar Scales P5 FINAL FOR DA 18-01-23 REISSUED FOR DA 22-12-22 P4 REISSUED FOR DRAFT 20-12-22 P3 ISSUED FOR DA 18-11-22 P2 ISSUED FOR DRAFT 11-11-22 Date Description

100mm on Original

CONCRETE NOTES

- 1. ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH AS 3600 CURRENT EDITION WITH AMENDMENTS, EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENTS.
- 2. CONCRETE QUALITY ALL REQUIREMENTS OF THE CURRENT ACSE CONCRETE SPECIFICATION DOCUMENT 1 SHALL APPLY TO THE FORMWORK, REINFORCEMENT AND CONCRETE UNLESS NOTED OTHERWISE.

ELEMENT	AS 3600 F'c MPa	SPECIFIED	NOMINAL
	AT 28 DAYS	SLUMP	AGG. SIZE
VEHICULAR BASE KERBS, PATHS, AND PITS	32 25	60 80	20 20

- CEMENT TYPE SHALL BE (ACSE SPECIFICATION) TYPE SL - PROJECT CONTROL TESTING SHALL BE CARRIED OUT IN ACCORDANCE
- WITH AS 1379. 3. NO ADMIXTURES SHALL BE USED IN CONCRETE UNLESS APPROVED IN WRITING BY AT & L.
- 4. CLEAR CONCRETE COVER TO ALL REINFORCEMENT FOR DURABILITY SHALL BE 40mm TOP AND 70mm FOR EXTERNAL EDGES UNLESS NOTED OTHERWISE.
- 5. ALL REINFORCEMENT SHALL BE FIRMLY SUPPORTED ON MILD STEEL PLASTIC TIPPED CHAIRS, PLASTIC CHAIRS OR CONCRETE CHAIRS AT NOT GREATER THAN 1m CENTRES BOTH WAYS. BARS SHALL BE TIED AT ALTERNATE INTERSECTIONS.
- 6. THE FINISHED CONCRETE SHALL BE A DENSE HOMOGENEOUS MASS. COMPLETELY FILLING THE FORMWORK, THOROUGHLY EMBEDDING THE REINFORCEMENT AND FREE OF STONE POCKETS, ALL CONCRETE INCLUDING SLABS ON GROUND AND FOOTINGS SHALL BE COMPACTED AND CURED IN ACCORDANCE WITH R.M.S SPECIFICATION R83.
- 7. REINFORCEMENT SYMBOLS: N DENOTES GRADE 450 N BARS TO AS 1302 GRADE N
- R DENOTES 230 R HOT ROLLED PLAIN BARS TO AS 1302 SL DENOTES HARD-DRAWN WIRE REINFORCING FABRIC TO AS 1304
- NUMBER OF BARS IN GROUP

17 N 20250 NOMINAL BAR SIZE IN mm ____ L_SPACING IN mm

THE FIGURE FOLLOWING THE FABRIC SYMBOL SL IS THE REFERANCE NUMBER FOR FABRIC TO AS 1304.

8. FABRIC SHALL BE LAPPED IN ACCORDANCE WITH THE FOLLOWING DETAIL:



KERBING NOTES

- 1. ALL CONCRETE TO HAVE A MINIMUM COMPRESSIVE STRENGTH OF 25 MPa U.N.O IN REINFORCED CONCRETE NOTES.
- 2. ALL KERBS, GUTTERS, DISH DRAINS AND CROSSINGS TO BE CONSTRUCTED ON MIN. 100mm GRANULAR BASECOURSE COMPACTED TO MINIMUM 95% MODIFIED DRY DENSITY (AS 1289 5.2.1).
- 3. EXPANSION JOINTS (E.J) TO BE FORMED FROM 10mm COMPRESSIBLE CORK FILLER BOARD FOR THE FULL DEPTH OF THE SECTION AND CUT TO PROFILE. EXPANSION JOINTS TO BE LOCATED AT DRAINAGE PITS. ON TANGENT POINTS OF CURVES AND ELSEWHERE AT MAX 12m CENTRES EXCEPT FOR INTEGRAL KERBS WHERE THE EXPANSION JOINTS ARE TO MATCH THE JOINT LOCATIONS IN THE SLABS.
- 4. WEAKENED PLANE JOINTS TO BE MIN 3mm WIDE AND LOCATED AT 3m CENTRES EXCEPT FOR INTEGRAL KERBS WHERE THE WEAKENED PLANE JOINTS ARE TO MATCH THE JOINT LOCATIONS IN THE SLABS.
- 5. BROOMED FINISH TO ALL RAMPED AND VEHICULAR CROSSINGS. ALL OTHER KERBING OR DISH DRAINS TO BE STEEL FLOAT FINISHED.
- 6. IN THE REPLACEMENT OF KERB AND GUTTER :-EXISTING ROAD PAVEMENT IS TO BE SAWCUT 900mm U.N.O FROM THE LIP OF GUTTER. UPON COMPLETION OF THE NEW KERB AND GUTTER NEW BASECOURSE AND SURFACE TO BE LAID 900mm WIDE U.N.O.
- EXISTING ALLOTMENT DRAINAGE PIPES ARE TO BE BUILT INTO THE NEW KERB AND GUTTER WITH 100mm DIA HOLE.
- EXISTING KERB AND GUTTER IS TO BE COMPLETELY REMOVED WHERE NEW KERB AND GUTTER IS SHOWN.



CONTRACTOR SHALL CALL; DIAL BEFORE YOU DIG 1100 PRIOR TO COMMENCEMENT OF WORK TO OBTAIN ALL CURRENT SERVICE AUTHORITY PLANS



STORMWATER DRAINAGE NOTES

1. STORMWATER DESIGN CRITERIA (A) AVERAGE RECURRENCE INTERVAL 1:100 YEARS MAJOR STORM (OVERLAND FLOW)

- 1:20 YEARS MINOR STORM (PIPED NETWORK) (B) RAINFALL INTENSITIES:
- TIME OF CONCENTRATION:5 MINUTES
- 1:100 YEARS= 219 mm/hr 1:20 YEARS= 167 mm/hr (C) RUNOFF COEFFICIENTS:
- ROOF AREAS: C 100 =1.0 EXTERNAL PAVEMENTS: C 100 =1.0

2. PIPES 300 DIA. AND LARGER TO BE REINFORCED CONCRETE CLASS '3' APPROVED SPIGOT AND SOCKET WITH RUBBER RING JOINTS, U.N.O. ALL ROAD CROSSINGS TO BE CLASS "4" U.N.O.

3. PIPES UP TO 300 DIA SHALL BE SEWER GRADE uPVC WITH SOLVENT WELDED JOINTS.

4. EQUIVALENT STRENGTH VCP OR FRC PIPES MAY BE USED, SUBJECT TO THE APPROVAL.

- 5. ALL STORMWATER DRAINAGE LINES UNDER PROPOSED BUILDING SLABS TO BE uPVC PRESSURE PIPE GRADE 6. ENSURE ALL VERTICALS AND DOWNPIPES ARE uPVC PRESSURE PIPE, GRADE 6 FOR A MIN OF 3.0m IN HEIGHT
- 6. PIPES TO BE INSTALLED TO TYPE HS1 SUPPORT IN ACCORDANCE WITH AS 3725 (2007) IN ALL CASES BACKFILL TRENCH WITH SAND TO 300mm ABOVE PIPE. WHERE PIPE IS UNDER PAVEMENTS BACKFILL REMAINDER OF TRENCH TO UNDERSIDE OF PAVEMENT WITH SAND OR APPROVED GRANULAR MATERIAL COMPACTED IN 150mm LAYERS TO MINIMUM 98% STANDARD MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS 1289 5.2.1 (OR A DENSITY INDEX OF NOT LESS THAN 75)
- 7. ALL INTERNAL WORKS WITHIN PROPERTY BOUNDARIES ARE TO COMPLY WITH THE REQUIREMENTS OF AS 3500 3.1 (1998) AND AS/NZS 3500 3.2
- 8. PRECAST PITS MAY BE USED EXTERNAL TO THE BUILDING SUBJECT TO APPROVAL BY AT & L.
- 9. ENLARGERS, CONNECTIONS AND JUNCTIONS TO BE PREFABRICATED FITTINGS WHERE PIPES ARE LESS THAN 300 DIA.
-). WHERE SUBSOIL DRAINS PASS UNDER FLOOR SLABS AND VEHICULAR PAVEMENTS, UNSLOTTED uPVC SEWER GRADE PIPE IS TO BE USED. 1. CARE IS TO BE TAKEN WITH LEVELS OF STORMWATER LINES. GRADES
- SHOWN ARE NOT TO BE REDUCED WITHOUT APPROVAL. 12. GRATES AND COVERS SHALL CONFORM TO AS 3996.
- 13. AT ALL TIMES DURING CONSTRUCTION OF STORMWATER PITS, ADEQUATE SAFETY PROCEDURES SHALL BE TAKEN TO ENSURE AGAINST THE POSSIBILITY OF PERSONNEL FALLING DOWN PITS.
- 4. ALL EXISTING STORMWATER DRAINAGE LINES AND PITS THAT ARE TO REMAIN ARE TO BE INSPECTED AND CLEANED. DURING THIS PROCESS ANY PART OF THE STORMWATER DRAINAGE SYSTEM THAT WARRANTS REPAIR SHALL BE REPORTED TO THE SUPERINTENDENT/ENGINEER FOR FURTHER DIRECTIONS.

BULK EARTHWORKS NOTES

- 1. ORIGIN OF LEVELS: REFER SURVEY NOTES
- 2. REFER PELLS SULLIVAN MEYNINK REPORT PSM1541-126S REV 0 (DATED NOV 2015) FOR BULK EARTHWORKS SPECIFICATIONS.

FINISHED SURFACE LEVELS

1. ALL FINISHED SURFACE LEVELS ARE ±1000mm U.N.O.

EROSION AND SEDIMENT CONTROL NOTES

GENERAL INSTRUCTIONS

- 1. THE SITE SUPERINTENDENT/ENGINEER WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE LOCATED AS DOCUMENTED.
- 2. ALL WORK SHALL BE GENERALLY CARRIED OUT IN ACCORDANCE WITH a. LOCAL AUTHORITY REQUIREMENTS b. EPA REQUIREMENTS c. NSW DEPARTMENT OF HOUSING MANUAL "MANAGING URBAN
- STORMWATER, SOILS AND CONSTRUCTION", 4th EDITION, MARCH 3. MAINTAIN THE EROSION CONTROL DEVICES TO THE SATISFACTION
- OF THE SUPERINTENDENT AND THE LOCAL AUTHORITY. 4. WHEN STORMWATER PITS ARE CONSTRUCTED, PREVENT SITE RUNOFF
- ENTERING UNLESS SEDIMENT FENCES ARE ERECTED AROUND PITS. 5. CONTRACTOR IS TO ENSURE ALL EROSION & SEDIMENT CONTROL DEVICES ARE MAINTAINED IN GOOD WORKING ORDER AND OPERATE EFFECTIVELY, REPAIRS AND OR MAINTENANCE SHALL BE UNDERTAKEN

AS REQUIRED, PARTICULARLY FOLLOWING STORM EVENTS.

LAND DISTURBANCE

- 6. WHERE PRACTICAL, THE SOIL EROSION HAZARD ON THE SITE WILL BE KEPT AS LOW AS POSSIBLE. TO THIS END, WORKS SHOULD BE UNDERTAKEN IN THE FOLLOWING SEQUENCE:
- (A) INSTALL A WIND FENCE ALONG THE BOUNDARIES AS SHOWN ON PLAN. REFER DETAIL.
- (B) INSTALL A SEDIMENT FENCE ALONG THE BOUNDARIES AS SHOWN ON PLAN. REFER DETAIL.
- (C) CONSTRUCT STABILISED CONSTRUCTION ENTRANCE TO LOCATION AS DETERMINED BY SUPERINTENDENT/ENGINEER. REFER DETAIL.
- (D) INSTALL SEDIMENT BASIN AS SHOWN ON PLAN
- (E) INSTALL SEDIMENT TRAPS AS SHOWN ON PLAN.
- (F) UNDERTAKE SITE DEVELOPMENT WORKS IN ACCORDANCE WITH THE ENGINEERING PLANS. WHERE POSSIBLE, PHASE DEVELOPMENT SO THAT LAND DISTURBANCE IS CONFINED TO AREAS OF WORKABLE SIZE.

EROSION CONTROL

- 7. DURING WINDY WEATHER, LARGE, UNPROTECTED AREAS WILL BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO KEEP DUST UNDER CONTROL.
- 8. FINAL SITE LANDSCAPING WILL BE UNDERTAKEN AS SOON AS POSSIBLE AND WITHIN 20 WORKING DAYS FROM COMPLETION OF CONSTRUCTION ACTIVITIES.

SEDIMENT CONTROL

- 9. STOCKPILES WILL NOT BE LOCATED WITHIN 2 METRES OF HAZARD AREAS, INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH VELOCITY FLOWS SUCH AS WATERWAYS. WHERE THEY ARE BETWEEN 2 AND 5 METRES FROM SUCH AREAS, SPECIAL SEDIMENT CONTROL MEASURES SHOULD BE TAKEN TO MINIMISE POSSIBLE POLLUTION TO DOWNSLOPE WATERS, E.G. THROUGH INSTALLATION OF SEDIMENT FENCING
- 10. ANY SAND USED IN THE CONCRETE CURING PROCESS (SPREAD OVER THE SURFACE) WILL BE REMOVED AS SOON AS POSSIBLE AND WITHIN 10 WORKING DAYS FROM PLACEMENT.
- 11. WATER WILL BE PREVENTED FROM ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS IT IS RELATIVELY SEDIMENT FREE. I.E. THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR ANY LIKELY SEDIMENT HAS BEEN FILTERED THROUGH AN APPROVED STRUCTURE.
- 12. TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES WILL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE REHABILITATED.

OTHER MATTERS

- 13. ACCEPTABLE RECEPTORS WILL BE PROVIDED FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER.
- 14. ANY EXISTING TREES WHICH FORM PART OF THE FINAL LANDSCAPING PLAN WILL BE PROTECTED FROM CONSTRUCTION ACTIVITIES BY:
- (A) PROTECTING THEM WITH BARRIER FENCING OR SIMILAR MATERIALS INSTALLED OUTSIDE THE DRIP LINE
- (B) ENSURING THAT NOTHING IS NAILED TO THEM (C) PROHIBITING PAVING, GRADING, SEDIMENT WASH OR PLACING OF STOCKPILES WITHIN THE DRIP LINE EXCEPT UNDER THE FOLLOWING CONDITIONS.
- (I) ENCROACHMENT ONLY OCCURS ON ONE SIDE AND NO CLOSER TO THE TRUNK THAN EITHER 1.5 METRES OR HALF THE DISTANCE BETWEEN THE OUTER EDGE OF THE DRIP LINE AND THE TRUNK, WHICH EVER IS THE GREATER
- (II) A DRAINAGE SYSTEM THAT ALLOWS AIR AND WATER TO CIRCULATE THROUGH THE ROOT ZONE (E.G. A GRAVEL BED) IS PLACED UNDER ALL FILL LAYERS OF MORE THAN 300 MILLIMETRES DEPTH
- (III) CARE IS TAKEN NOT TO CUT ROOTS UNNECESSARILY NOR TO COMPACT THE SOIL AROUND THEM.

				1			
	Client	Scales	Drawn	KS	Project	Civil Engineers and Project Managers	
THIS DRAWING CANNOT BE	+		Designed	AC	PROPOSED INDUSTRIAL	Level 7, 153 Walk North Sydney NS	W 2060
COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY		Grid LOCAL	Checked	SC		ABN 96 130 882 4 Tel: 02 9439 1 Fax: 02 9923 1	777
OTHER PURPOSE OTHER THAN	Goodman	Height AHD Datum	Approved		OAKDALE WEST - LOT 4C & 4D	www.atl.net.au info@atl.net.au	
THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L					GENERAL NOTES	Status FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION	A1
						Project - Drawing No. 15-272-C7901	Issue P5

EROSION AND SEDIMENT CONTROL


NOTES


STAGING

SUITABLE EROSION AND SEDIMENT CONTROLS SHALL BE DESIGNED. PROVIDED AND MAINTAINED BY THE CONTRACTOR THROUGHOUT ALL STAGES OF WORKS, INCLUDING AT COMPLETION OF THE BULK EARTHWORKS WHERE SHOWN ON AT&L DRAWINGS OR WHERE DIRECTED BY THE SUPERINTENDENT OR PENRITH CITY COUNCIL'S ENGINEERS.

SEDIMENT AND EROSION CONTROLS ARE TO BE DESIGNED AND DOCUMENTED BY A SUITABLY QUALIFIED EXPERT ENGAGED BY THE CONTRACTOR AND APPROVED AS PART OF THE CONSTRUCTION ENVIRONMENTAL MANAGEMENT PLAN PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. SUCH CONTROLS SHALL BE IN ACCORDANCE WITH THE RELEVANT REQUIREMENTS IN THE LATEST VERSION OF THE MANAGING URBAN STORMWATER: SOILS AND CONSTRUCTION GUIDELINE (LANDCOM).

F:\15-272 Oakdale West\Drgs\Civil\Final\SSDA\7000_On-Lot Works Packages\7900 LOT 4C 4D\15-272-C7901.dwg







PROPOSED INDUSTRIAL DEVELOPMENT OAKDALE WEST - LOT 4C & 4D	Cartes Cartes Cartes Level 7, 153 Walker Street North Sydney NSW 2060 ABN 96 130 882 405 Tel: 02 9439 1777 Fax: 02 9923 1055 www.atl.net.au info@atl.net.au			
TYPICAL SECTIONS	Status FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION	A1		
SHEET 1	Project - Drawing No. 15-272-C7910	Issue P5		

Civil Engineers and Project Managers

F:\15-272 Oakdale West\Drgs\Civil\Final\SSDA\7000_On-Lot Works Packages\7900 LOT 4C 4D\15-272-C7910.dwg




	Client	Scales	4 400	Drawn	KS	Proje
THIS DRAWING CANNOT BE	+		1 : 100	Designed	AC	1
COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY		Grid	LOCAL	Checked	SC] ,
OTHER PURPOSE OTHER THAN	Goodman	Height Datum	AHD	Approved		Title
THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L						



	LOT 4C	
NT	46.6m	
		لے ا
	- EXISTING SURFACE LEVEL	
		-
		-






100mm on Original

		1 : 100			
THIS DRAWING CANNOT BE	+	1:100	Designed	AC	
COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY		Grid LOCAL	Checked	SC]
OTHER PURPOSE OTHER THAN	Goodman	Height AHD Datum AHD	Approved		Title
THAT ORIGINALLY INTENDED					nue
WITHOUT THE WRITTEN PERMISSION OF AT&L					

F:\15-272 Oakdale West\Drgs\Civil\Final\SSDA\7000_On-Lot Works Packages\7900 LOT 4C 4D\15-272-C7913.dwg




100mm on Original


	Client		Scales	4 . 400	Drawn	KS	Project
THIS DRAWING CANNOT BE		+		1 : 100	Designed	AC	Р
COPIED OR REPRODUCED IN			Grid	LOCAL	Checked	SC	
ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN		Goodman	Height Datum	AHD	Approved		OAK
THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L							Title
						F:\15-2	272 Oakdale


PROPOSED INDUSTRIAL DEVELOPMENT OAKDALE WEST - LOT 4C & 4D	ABN 96 130 882 4 Tel: 02 9439 17 Fax: 02 9923 10 www.atl.net.au info@atl.net.au	V 2060 05 77
TYPICAL SECTIONS	Status FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION	A1
SHEET 5	Project - Drawing No.	Issue
	5-272-C7914	P5

Civil Engineers and Project Managers

Dakdale West\Drgs\Civil\Final\SSDA\7000_On-Lot Works Packages\7900 LOT 4C 4D\15-272-C7914.dwg








NOTES 1. THE ABOVE VOLUMES ARE CALCULATED WITH THE ASSUMPTION THAT THE INFRASTRUCTURE WORKS ARE COMPLETED.

- 2. ASSUMED 300mm SET DOWN FROM PRELIMINARY FINISHED LEVELS.
- 3. THE VOLUMES DO NOT TAKE INTO ACCOUNT THE FOLLOWING :-
 - BULKING FACTORS OF REMOVED CUT REMOVAL OF EXISTING BUILDING SLABS AND PAVEMENTS
 - REMOVAL AND\OR REMEDIATION OF
 - ANY EXISTING UNCONTROLLED FILL
 - PROPOSED LANDSCAPING
 - STORMWATER AND UTILITY TRENCHING EROSION AND SEDIMENTATION CONTROL
 - SWALES AND BASINS NO ALLOWANCE FOR RETAINING WALL
 - BACKFILL MATERIAL


ect	Civil Engineers and Project Managers	
PROPOSED INDUSTRIAL DEVELOPMENT OAKDALE WEST - LOT 4C & 4D	ABN 96 130 882 4 Tel: 02 9439 17 Fax: 02 9923 10 www.atl.net.au info@atl.net.au	N 2060 105 777
BULK EARTHWORKS	Status FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION	A1
PLAN	Project - Drawing No. 1 5-272-C7915	Issue P5

F:\15-272 Oakdale West\Drgs\Civil\Final\SSDA\7000_On-Lot Works Packages\7900 LOT 4C 4D\15-272-C7915.dwg




	Client	Scales	Drawn	KS	Projec
THIS DRAWING CANNOT BE	+	1 : 250	Designed	AC	
		Grid LOCAL	Checked	SC	1
ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN	Goodman	Height AHD Datum	Approved		
THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L					Title


F:\15-272 Oakdale West\Drgs\Civil\Final\SSDA\7000_On-Lot Works Packages\7900 LOT 4C 4D\15-272-C7920.dwg




1924				
	Client	Scales	Drawn KS	Projec
THIS DRAWING CANNOT BE	+	1 : 250	Designed AC	
COPIED OR REPRODUCED IN		Grid LOCAL	Checked SC	
ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L	Goodman	Height AHD Datum	Approved	Title


F:\15-272 Oakdale West\Drgs\Civil\Final\SSDA\7000_On-Lot Works Packages\7900 LOT 4C 4D\15-272-C7921.dwg








F:\15-272 Oakdale West\Drgs\Civil\Final\SSDA\7000_On-Lot Works Packages\7900 LOT 4C 4D\15-272-C7923.dwg












ject	Civil Engineers and Project Managers	
PROPOSED INDUSTRIAL DEVELOPMENT OAKDALE WEST - LOT 4C & 4D	ABN 96 130 882 4 Tel: 02 9439 17 Fax: 02 9923 10 www.atl.net.au info@atl.net.au	V 2060 05 77
PAVEMENT	Status FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION	A1
PLAN	Project - Drawing No.	Issue
	5-272-C7930	P5

F:\15-272 Oakdale West\Drgs\Civil\Final\SSDA\7000_On-Lot Works Packages\7900 LOT 4C 4D\15-272-C7930.dwg




F:\15-272 Oakdale West\Drgs\Civil\Final\SSDA\7000_On-Lot Works Packages\7900 LOT 4C 4D\15-272-C7935.dwg

	TO	oposei Struc Tail							E
Datum RL45			<u> </u>		<u> - 32 -</u>		<u>- 35</u> -		- SUBSL DRAIN,
BOTTOM OF RETAINING WALL	72.93	72.96	72.94	72.91	72.88	72.85	72.87	72.90	72.93
TOP OF RETAINING WALL	73.038	73.113	73.171	73.218	73.265	73.312	73.347	73.394	73.441
HEIGHT OF RETAINING WALL	0.108	0.153	0.231	0.308	0.385	0.462	0.477	0.494	0.511
EXISTING SURFACE LEVEL	73.40	73.41	73.47	73.52	73.56	73.61	73.65	73.69	73.74
CHAINAGE	0.000	5.000	10.000	15.000	20.000	25.000	30.000	35.000	40.000

RETAINING WALL RW1 PROFILE

SCALE 1:500 HORI. 1:500 VERT.


		Bar Scales		Client	Scales	4 . 500	Drawn	KS	Proje
			THIS DRAWING CANNOT BE	+		1 : 500	Designed	AC	
			COPIED OR REPRODUCED IN		Grid	LOCAL	Checked	SC	
P5 FINAL FOR DA	18-01-23	0 10 20 30 40 50m	ANY FORM OR USED FOR ANY	Goodman	Height	AHD	Approved		
P4 REISSUED FOR DA	22-12-22		OTHER PURPOSE OTHER THAN	GUUUIIIAII	Datum				Title
P3 REISSUED FOR DRAFT	20-12-22	1 : 500 @ A1 1 : 1000 @ A3	THAT ORIGINALLY INTENDED						
P2 ISSUED FOR DA	18-11-22		WITHOUT THE WRITTEN						
P1 ISSUED FOR DRAFT	11-11-22		PERMISSION OF AT&L						
Issue Description	Date								
100mm on Original								F:\15-	272 0




PROPOSED RETA TO STRUCTURAL DETAIL						- EXIS	11T;
			.22		- 22-		:
Datum RL41	-						
BOTTOM OF RETAINING WALL	72.23	71.71	71 20	02.17	70.60	70.03	69.49
FOP OF RETAINING WALL	72.631	72.601	70 6 74	1 10.71	72.541	72.579	72.699
HEIGHT OF RETAINING WALL	0.404	0.887	1 370	0/6.1	1.942	2.551	3.209
EXISTING SURFACE LEVEL	72.23	71.71	71 20	07.11	70.69	70.03	69.49
CHAINAGE	0.000	5.000		000.01	15.000	20.000	25.000
	-						


RETAINING WALL RW2 PROFILE

SCALE 1:500 HORI. 1:500 VERT.






Dakdale West\Drgs\Civil\Final\SSDA\7000_On-Lot Works Packages\7900 LOT 4C 4D\15-272-C7936.dwg



<u>LEGEND</u>



6-8)

STRAW BALE FILTER (SD 6-7)

MESH AND GRAVEL INLET FILTER (SD 6-11) GEOTEXTILE INLET (SD


6-12) STABILISED SITE ACCESS AND TRUCK WASH DOWN


AREA (SD 6-14) PROPOSED SITE ACCESS

GATE

Civil Engineers and Project Managers Level 7, 153 Walker Street North Sydney NSW 2060 PROPOSED INDUSTRIAL ABN 96 130 882 405 DEVELOPMENT LÖ Tel: 02 9439 1777 OAKDALE WEST - LOT 4C & 4D Fax: 02 9923 1055 www.atl.net.au info@atl.net.au **EROSION AND SEDIMENT** Status FOR APPROVAL A1 NOT TO BE USED FOR CONSTRUCTION Project - Drawing No. Issue 5-272-C7940 P5

F:\15-272 Oakdale West\Drgs\Civil\Final\SSDA\7000_On-Lot Works Packages\7900 LOT 4C 4D\15-272-C7940.dwg





Goodman

OTHER PURPOSE OTHER THAN

THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L

Height Datum

AHD

P5	FINAL FOR DA	18-01-23
P4	REISSUED FOR DA	22-12-22
P3	REISSUED FOR DRAFT	20-12-22
P2	ISSUED FOR DA	18-11-22
P1	ISSUED FOR DRAFT	11-11-22
Issue	Description	Date
		100mm on Original

Approved

PROPOSED INDUSTRIAL DEVELOPMENT OAKDALE WEST - LOT 4C & 4D	Level 7, 153 Walker Street North Sydney NSW 2060 ABN 96 130 882 405 Tel: 02 9439 1777 Fax: 02 9923 1055 www.atl.net.au info@atl.net.au	
EROSION AND SEDIMENT DETAILS	Status FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION	A1
	Project - Drawing No. 1 5-272-C7941	Issue P5


Civil Engineers and Project Managers

F:\15-272 Oakdale West\Drgs\Civil\Final\SSDA\7000_On-Lot Works Packages\7900 LOT 4C 4D\15-272-C7941.dwg



Appendix C

Lot 4C and 4D Stormwater Drainage Catchment Plan



ject	Civil Engineers and Project Managers		
PROPOSED INDUSTRIAL DEVELOPMENT OAKDALE WEST - LOT 4C & 4D	North Sydney NSV ABN 96 130 882 4 Tel: 02 9439 17	Fax: 02 9923 1055 www.atl.net.au	
STORMWATER DRAINAGE	Status FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION	A1	
	Project - Drawing No.	Issue	
	15-272-C7950	P3	
ws\data\BYRNE-TMS\SEQ22075 - ATL_Oakdale West_1100\04 CADD\DWG\15-272-catchment plan.dwg			





ROOFWATER CATCHMENT BOUNDARY