



**Consulting.**<sup>TM</sup>  
an Elephants Foot Company

Caddens Corner, 68-80 O'Connell Street, Kingswood  
Mixed Use Development.

## OPERATIONAL WASTE MANAGEMENT PLAN

29/02/2024  
Report No. 4484  
Revision F

Client

---

**Caddens Estate Development Pty Ltd.**  
2/2-4 Giffnock Avenue, Macquarie Park, NSW 2113

Architect

---

**TURNER**



---

## REVISION REFERENCE

| Revision | Date       | Prepared by  | Description   |
|----------|------------|--------------|---------------|
| A        | 12-12-2022 | T. McPherson | Draft         |
| B        | 15-12-2022 | T. McPherson | Amendment     |
| C        | 15-02-2023 | T. McPherson | Updated Plans |
| D        | 10-03-2023 | T. McPherson | Final         |
| E        | 06-02-2024 | T. McPherson | Amendment     |
| F        | 29-02-2024 | T. McPherson | Amendment     |

The information contained in this document produced by Elephants Foot Consulting (EFC) is solely for the use of the client identified on the cover sheet for the purpose for which it has been prepared for. EFC undertakes no duty, nor accepts any responsibility for any third party who may rely upon this document. Reproduction, publication or distribution of this document without written permission from EFC is strictly prohibited.

## TABLE OF CONTENTS

|   |    |
|---|----|
| TABLE OF FIGURES.....   | iv |
| LIST OF TABLES.....   | iv |
| GLOSSARY OF ABBREVIATIONS AND TERMS .....                       | i  |
| 1.0 ACKNOWLEDGEMENT OF COUNTRY .....                            | 3  |
| 2.0 INTRODUCTION.....   | 3  |
| 2.1 SCOPE OF REPORT .....                                       | 3  |
| 2.2 REPORT CONDITIONS .....                                     | 4  |
| 3.0 LEGISLATION & GUIDANCE .....                                | 5  |
| 3.1 PENRITH CITY COUNCIL OBJECTIVES .....                       | 5  |
| 4.0 DEVELOPMENT OVERVIEW.....                                   | 6  |
| 4.1 SITE LOCATION .....   | 6  |
| 5.0 RESIDENTIAL WASTE MANAGEMENT .....                          | 7  |
| 5.1 WASTE GENERATION ESTIMATES.....                             | 7  |
| 5.2 BIN SUMMARY .....   | 10 |
| 5.3 WASTE DISPOSAL PROCEDURES.....                              | 10 |
| 5.3.1 COMMON AREAS.....   | 10 |
| 5.4 WASTE COLLECTION PROCEDURES.....                            | 11 |
| 5.5 BULKY WASTE PROCEDURES.....                                 | 12 |
| 6.0 RETAIL WASTE MANAGEMENT .....                               | 13 |
| 6.1 WASTE GENERATION ESTIMATES.....                             | 13 |
| 6.2 BIN SUMMARY .....   | 14 |
| 6.3 WASTE DISPOSAL PROCEDURES.....                              | 14 |
| 6.4 WASTE COLLECTION PROCEDURES.....                            | 14 |
| 6.5 OTHER WASTE MANAGEMENT CONSIDERATIONS .....                 | 14 |
| 6.5.1 KITCHEN, OFFICE TEA ROOMS AND FOOD PREPARATION AREAS..... | 14 |
| 6.5.2 BATHROOMS .....   | 15 |
| 6.5.3 PRINTING & PHOTOCOPYING ROOMS.....                        | 15 |
| 6.5.4 LIQUID WASTE .....  | 15 |
| 6.5.5 PROBLEM WASTE.....  | 15 |
| 7.0 STAKEHOLDER ROLES & RESPONSIBILITIES .....                  | 16 |
| 8.0 SOURCE SEPARATION.....                                      | 17 |
| 9.0 EDUCATION .....   | 18 |
| 9.1 SIGNAGE.....  | 18 |
| 9.2 POLLUTION PREVENTION.....                                   | 19 |
| 10.0 EQUIPMENT SUMMARY .....                                    | 20 |
| 11.0 WASTE ROOMS .....  | 20 |
| 12.0 BIN MOVING PATHS.....                                      | 25 |

|               |  |    |
|---------------|--|----|
| 12.0          | CONSTRUCTION REQUIREMENTS.....                             | 26 |
| 12.1          | ADDITIONAL CONSIDERATIONS .....                            | 26 |
| 13.0          | USEFUL CONTACTS.....                                       | 27 |
| APPENDIX A:   | ARCHITECTURAL PLANS.....                                   | 28 |
| APPENDIX: A.1 | BASEMENT 2 FLOOR PLAN – STAGE FOUR (BIN STORAGE ROOMS) ... | 29 |
| APPENDIX: A.2 | TYPICAL FLOOR PLAN – STAGE FOUR. ....                      | 30 |
| APPENDIX: A.3 | TYPICAL FLOOR PLAN – STAGE TWO.....                        | 31 |
| APPENDIX: A.4 | TYPICAL FLOOR PLAN – STAGE THREE .....                     | 32 |
| APPENDIX: A.5 | TYPICAL FLOOR PLAN – STAGE ONE .....                       | 33 |
| APPENDIX B:   | INSTALLATION EQUIPMENT .....                               | 34 |
| APPENDIX: B.1 | TYPICAL DUAL CHUTE SHAFT & PENETRATION SET-OUT.....        | 35 |
| APPENDIX: B.2 | TYPICAL LINEAR TRACK SYSTEM FOR 1100L MGBS .....           | 36 |
| APPENDIX C:   | PRIMARY WASTE MANAGEMENT PROVISIONS.....                   | 38 |
| APPENDIX: C.1 | TYPICAL BIN SPECIFICATIONS.....                            | 39 |
| APPENDIX: C.2 | SIGNAGE FOR WASTE AND RECYCLING BINS.....                  | 40 |
| APPENDIX: C.3 | REAR LOAD WASTE COLLECTION VEHICLE (LOW ENTRY) .....       | 42 |
| APPENDIX: C.4 | TYPICAL BIN MOVERS .....                                   | 43 |
| APPENDIX: C.5 | TYPICAL SEATED BIN MOVERS .....                            | 44 |
| APPENDIX D:   | SECONDARY WASTE MANAGEMENT PROVISIONS.....                 | 46 |
| APPENDIX: D.1 | TYPICAL WORM FARM SPECIFICATIONS .....                     | 47 |
| APPENDIX: D.2 | EXAMPLE APARTMENT STYLE COMPOST BIN.....                   | 48 |
| APPENDIX: D.3 | TYPICAL COOKING OIL CONTAINERS .....                       | 48 |
| APPENDIX: D.4 | TYPICAL SOURCE SEPARATION BINS .....                       | 50 |

## TABLE OF FIGURES

|                              |   |
|------------------------------|---|
| Figure 1. Site Location..... | 6 |
|------------------------------|---|

## LIST OF TABLES

|  |    |
|--|----|
| Table 1: Estimated Waste and Recycling Volumes – Stage One ..... | 8  |
| Table 2: Estimated Waste and Recycling Volumes – Stage Two ..... | 8  |
| Table 3: Bin Summary Table .....                                 | 10 |
| Table 4: Collection Points and Locations Summary .....           | 11 |
| Tables 5: Bulky Waste Room Requirements. ....                    | 12 |
| Table 6: Estimated Waste and Recycling Volumes. ....             | 13 |
| Table 7: Stakeholder Roles and Responsibilities .....            | 16 |
| Table 8: Operational Waste Streams.....                          | 17 |
| Table 9: Equipment Summary.....                                  | 20 |
| Table 10: Waste Room Areas- Stage One. ....                      | 21 |
| Table 11: Waste Room Areas - Stage Two. ....                     | 21 |
| Table 12: Waste Room Areas - Stage Three .....                   | 22 |
| Table 13: Waste Room Areas - Stage Four .....                    | 23 |
| Table 14: Waste Room Requirements.....                           | 24 |

## GLOSSARY OF ABBREVIATIONS AND TERMS

| TERM                               | DESCRIPTION  |
|------------------------------------|--|
| <i>Bin-carting Route</i>           | Travel route for transferring bins from the storage area to a nominated collection point   |
| <i>Chute</i>                       | A ventilated, vertical pipe passing from floor to floor of a building with openings as required to connect with hoppers and normally terminating at its lower end at the roof of the central waste room(s) |
| <i>Chute Discharge</i>             | The point at which refuse exits from the refuse chute  |
| <i>Chute Discharge Room</i>        | A secure, enclosed area or room housing the discharge and associated equipment for the refuse chute  |
| <i>Collection Area/Point</i>       | The identified position or area where general waste or recyclables are loaded onto the collection vehicle  |
| <i>Compactor</i>                   | A machine for compressing waste into disposable or reusable containers   |
| <i>Composter</i>                   | A container/machine used for composting specific food scraps   |
| <i>DA</i>                          | Development Application  |
| <i>DCP</i>                         | Development Control Plan   |
| <i>EPA</i>                         | Environmental Protection Authority   |
| <i>HRV</i>                         | Heavy Rigid Vehicle described by AS 2890.2-2002 Parking facilities – Off-street commercial vehicle facilities  |
| <i>L</i>                           | Litre(s)   |
| <i>LEP</i>                         | Local Environmental Plans guide planning decisions for local government areas  |
| <i>Liquid Waste</i>                | Non-hazardous liquid waste generated by commercial premises that must be connected to sewer or collected for treatment and disposal by a liquid waste contractor (including grease trap waste)             |
| <i>Mixed Use Development</i>       | A development comprised of two or more different uses  |
| <i>MUD</i>                         | Multi-Unit Dwellings comprise of a development with more than one dwelling. This ranges from dual occupancies and attached dwellings to high-rise residential developments                                 |
| <i>Mobile Garbage Bin(s) (MGB)</i> | A waste container generally constructed of plastic with wheels with a capacity in litres of 120, 240, 360, 660, 1000 or 1100   |
| <i>MRV</i>                         | Medium Rigid Vehicle described by AS 2890.2-2002 Parking facilities – Off-street commercial vehicle facilities   |
| <i>Onsite Collection</i>           | When the collection vehicle enters the property and services the development within the property boundary from a designated loading area   |
| <i>Owners Corporation</i>          | An organisation or group of persons that is identified by a particular name and acts, or may act, as an entity   |

|                                   |   |
|-----------------------------------|---|
| <i>Service Bins</i>               | Bin set side to be placed under a chute while the remainder of the bins are being collected   |
| <i>WHS</i>                        | Workplace Health and Safety   |
| <i>Wheel-in wheel-out service</i> | A type of waste collection service offered by local councils where the council waste collection personnel enter the premises to collect the bins and returns them to the property |

## 1.0 ACKNOWLEDGEMENT OF COUNTRY

We acknowledge Australia's First Nations People as the Traditional Custodians of this land. We pay respect to ancestors and Elders, past and present. We honour Aboriginal and Torres Strait Islander people and their connection to land, waters and seas, and their vital contribution to the vibrant nation that we share, Australia.

## 2.0 INTRODUCTION

Elephants Foot Consulting (EFC) has been engaged to prepare the following waste management plan for the operational management of waste generated by the mixed use development located at Caddens Corner, 68-80 O'Connell Street, Kingswood.

Waste management strategies and audits are required for new developments in order to support the design and sustainable performance of the building. It is EFC's belief that a successful waste management strategy contains three key objectives:

- i. **Promote responsible source separation** to reduce the amount of waste that goes to landfill by implementing convenient and efficient waste management systems.
- ii. **Ensure adequate waste provisions and robust procedures** that will cater for potential changes during the operational phase of the development.
- iii. **Comply** with all relevant council codes, policies, and guidelines.

To achieve these objectives, this operational waste management plan (OWMP) identifies the different waste streams likely to be generated during the operational phase of the development, as well as how the waste will be handled and disposed, details of bin sizes/quantities and waste rooms, descriptions of the proposed waste management equipment used, and information on waste collection points and frequencies.

It is essential that this OWMP is integrated into the overall management of the building and is clearly communicated to all relevant stakeholders.

### 2.1 SCOPE OF REPORT

This operational waste management plan (OWMP) only applies to the **operational** phase of the proposed development; therefore, the requirements outlined in this OWMP must be implemented during the operational phase of the site and may be subject to review upon further expansion of, and/or changes to the development.

The waste management of the **construction** and **demolition** phases of the development are not addressed in this report. A construction and demolition WMP will need to be provided separately. EFC can supply this if required.

## 2.2 REPORT CONDITIONS

The purpose of this report is to document an OWMP as part of a development application, which is supplied by EFC with the following limitations:

- Drawings, estimates and information contained in this OWMP have been prepared by analysing the information, plans and documents supplied by the client and third parties including Council and other government agencies. The assumptions based on the information contained in the OWMP is outside the control of EFC,
- The figures presented in the report are an estimate only – the actual amount of waste generated will be dependent on the occupancy rate of the building/s and waste generation intensity as well as the building management's approach to educating residents and tenants regarding waste management operations and responsibilities,
- The building manager will adjust waste management operations as required based on actual waste volumes (e.g., if waste is greater than estimated) and increase the number of bins and collections accordingly,
- The report will not be used to determine or forecast operational costs or prepare any feasibility study or to document any safety or operational procedures,
- The report has been prepared with all due care; however, no assurance is made that the OWMP reflects the actual outcome of the proposed waste facilities, services, and operations, and EFC will not be liable for plans or results that are not suitable for purpose due to incorrect or unsuitable information or otherwise,
- EFC offer no warranty or representation of accuracy or reliability of the OWMP unless specifically stated,
- Any manual handling equipment recommended in this OWMP should be provided at the recommendation of the appropriate equipment provider who will assess the correct equipment for supply,
- Design of waste management chute equipment and systems must be approved by the supplier,
- EFC cannot be held accountable for late changes to the design after the OWMP has been submitted to Council,
- EFC will provide specifications and recommendations on bin access and travel paths within the OWMP; however, it is the architect's responsibility to ensure the architectural drawings meet these provisions,
- EFC are not required to provide information on collection vehicle swept paths, head heights, internal manoeuvring or loading requirements. It is assumed this information will be provided by a traffic consultant,
- Council are subject to changing waste and recycling policies and requirements at their own discretion.

This OWMP is only finalised once the Draft Watermark has been removed. If the Draft Watermark is present, the information in the OWMP is not confirmed.



### 3.0 LEGISLATION & GUIDANCE

Waste management and resource recovery regulation in Australia is administered by the Australian Constitution, Commonwealth laws, and international agreements. State and territory governments maintain primary responsibility for controlling development and regulating waste. The following legislation has been enacted in New South Wales, and provides the lawful underpinnings of this OWMP.

- NSW Environmental Planning & Assessment Act 1979
- NSW Protection of the Environment Operations Act 1997
- NSW Waste Avoidance & Resource Recovery Act 2001

At the local level, councils or Local Government Areas (LGAs) require OWMPs to be included in new development applications. This OWMP is specifically required by:

- Penrith Development Control Plan 2014
- Penrith Local Environmental Plan 2010

The primary purpose of a development control plan (DCP) is to guide development according to the aims of the corresponding local environmental plan (LEP). The DCP must be read in conjunction with the provisions of the relevant LEP.

Information provided in this OWMP comes from a wide range of waste management guidance at the local, state, and federal levels. The primary sources of guidance include:

- Penrith Development Control Plan: Part C, Waste Management
- Penrith Council Industrial, Commercial and Mixed-Use Waste Management Guidelines
- Penrith City Council: Residential Flat Building Waste Management Guidelines
- NSW Better Practice Guidelines for Waste Management and Recycling in Commercial and Industrial Facilities 2012
- NSW Better practice guide for resource recovery in residential developments 2019
- NSW Waste Avoidance and Resource Recovery (WARR) Strategy 2014-2021
- NSW Waste Classification Guidelines 2014
- Australia's National Waste Policy 2018

#### 3.1 PENRITH CITY COUNCIL OBJECTIVES

To ensure new developments are able to access Council's waste service in an efficient and effective manner, the following must be taken into consideration in the assessment of development applications:

- Site planning of the development accommodates on-site waste collection and allows the waste collection vehicle to enter/exit, manoeuvre within the site and access the nominated collection point in a safe and efficient manner.
- Site planning of the development ensures amenity and safety of all users (including residents, caretakers, cleaners and waste collection staff) at all stages of the waste management process.
- Waste management system selection ensures that it is safe and convenient for resident use; and
- Adequate waste storage area(s) are provided within the development site to store all required waste bins.

## 4.0 DEVELOPMENT OVERVIEW

The proposed development falls under the LGA of Penrith City Council, and consists of four stages for the proposed development.

- Stage One** will consist of 99 residential units in total.
- Stage Two** will consist of 115 residential units in total.
- Stage Three** will consist of 112 residential units in total.
- Stage Four** will consist of 139 residential units in total, and retail GFA of 1415m<sup>2</sup>.


| Stage | Buildings Involved   |
|-------|----------------------|
| One   | B, C, H & J          |
| Two   | D, E, F & G          |
| Three | K, L, M & N          |
| Four  | P1, P2,, R, S, T & U |

In this current revision of the OWMP (revision E), building A has been deleted in stage one. All figures and calculations are based on area schedules as advised by our client and shown on architectural drawings.

### 4.1 SITE LOCATION

The site is located 68-80 O'Connell Street, Kingswood NSW 2747 as shown in Figure.1 (boundaries are indicative only). The site is legally known as Lot 1 & 2 (DP1268507). The site has frontages and vehicular access via O'Connell Street (and its internal roads).

Figure 1: Site Location



Source: TURNER, Drawing no. DA-001-002.

## 5.0 RESIDENTIAL WASTE MANAGEMENT

The following section outlines best practice waste management for the residential component of the development, including waste generation estimates, and waste disposal and collection procedures.

### 5.1 WASTE GENERATION ESTIMATES

The 'Penrith City Council *Residential Flat Building Waste Management*' has been referenced to calculate the total number of bins required for the residential units. Calculations are based on generic waste and recycling rates. Actual volumes of waste and recycling generated in operation may differ according to the residents' actual waste management practices.

During operation, it is the responsibility of the building manager to monitor the number of bins required for the residential component. Waste and recycling volumes may change according to residents' attitudes to waste disposal and recycling, building occupancy levels or development's management.

Any requirements for adjusting the capacity of the waste facilities can be achieved by changing the number of bins, the bin sizes or collection frequencies. Building management will be required to negotiate any changes to bins or collections with the collection service provider.

The following table shows the estimated volume (L) of general waste and recyclables generated by the residential component of the development. Advice from the 'Penrith City Councils Addendum – Technical Advice' for DA230281 has also been taken into consideration in the current revision of the OWMP.

Figure 2: Screenshot of Waste Generation Rates for Residents 'per bin'.

| Weekly Waste Generation Volumes (L) | 240L Bin Allocation | 660L Bin Allocation | 1100L Bin Allocation |
|-------------------------------------|---------------------|---------------------|----------------------|
| Residual                            | 2 dwellings per bin | 9 dwellings per bin | 18 dwellings per bin |
| Recycling                           | 2 dwellings per bin | 9 dwellings per bin | 18 dwellings per bin |

Table 1: Estimated Waste and Recycling Volumes – Stage One

| Type of Dwelling     | # Units | Waste Generation Rate (L/Unit/Week) |   | Generated Waste (L/Week) | Recycling Generation Rate (L/Unit/Week) |   | Generated Recyclables (L/Week) |
|----------------------|---------|-------------------------------------|---|--------------------------|---|---|--------------------------------|
| B                    | 19      | 61.11                               |   | 1161.1                   | 61.11                                   |   | 1161.1                         |
| C                    | 23      | 61.11                               |   | 1405.6                   | 61.11                                   |   | 1405.6                         |
| H                    | 35      | 61.11                               |   | 2138.9                   | 61.11                                   |   | 2138.9                         |
| J                    | 26      | 61.11                               |   | 1588.9                   | 61.11                                   |   | 1588.9                         |
| TOTAL                | 103     |                                     |   | 6294.4                   |   |   | 6294.4                         |
| Bins and Collections |         | Waste Bin Size (L)                  |   | 1100                     | Recycling Bin Size (L)                  |   | 1100                           |
|                      |         | Waste Collections/Week              |   | 2                        | Recycling Collections/Week              |   | 1                              |
|                      |         | Bins Per Day                        | B | 0.2                      | Bins Per Day                            | B | 0.2                            |
|                      |         |                                     | C | 0.2                      |   | C | 0.2                            |
|                      |         |                                     | H | 0.3                      |   | H | 0.3                            |
|                      |         |                                     | J | 0.2                      |   | J | 0.2                            |
|                      |         | Bins Per Collection                 | B | 2                        | Bins Per Collection                     | B | 2                              |
|                      |         |                                     | C | 2                        |   | C | 2                              |
|                      |         |                                     | H | 2                        |   | H | 2                              |
|                      |         |                                     | J | 2                        |   | J | 2                              |

Table 2: Estimated Waste and Recycling Volumes – Stage Two

| Type of Dwelling     | # Units | Waste Generation Rate (L/Unit/Week) |   | Generated Waste (L/Week) | Recycling Generation Rate (L/Unit/Week) |   | Generated Recyclables (L/Week) |
|----------------------|---------|-------------------------------------|---|--------------------------|---|---|--------------------------------|
| D                    | 26      | 61.11                               |   | 1588.9                   | 61.11                                   |   | 1588.9                         |
| E                    | 29      | 61.11                               |   | 1772.2                   | 61.11                                   |   | 1772.2                         |
| F                    | 25      | 61.11                               |   | 1527.8                   | 61.11                                   |   | 1527.8                         |
| G                    | 35      | 61.11                               |   | 2138.9                   | 61.11                                   |   | 2138.9                         |
| TOTAL                | 115     |                                     |   | 7027.8                   |   |   | 7027.8                         |
| Bins and Collections |         | Waste Bin Size (L)                  |   | 1100                     | Recycling Bin Size (L)                  |   | 1100                           |
|                      |         | Waste Collections/Week              |   | 2                        | Recycling Collections/Week              |   | 1                              |
|                      |         | Bins Per Day                        | B | 0.2                      | Bins Per Day                            | B | 0.2                            |
|                      |         |                                     | C | 0.2                      |   | C | 0.2                            |
|                      |         |                                     | H | 0.2                      |   | H | 0.2                            |
|                      |         |                                     | J | 0.3                      |   | J | 0.3                            |
|                      |         | Bins Per Collection                 | B | 2                        | Bins Per Collection                     | B | 2                              |
|                      |         |                                     | C | 2                        |   | C | 2                              |
|                      |         |                                     | H | 2                        |   | H | 2                              |
|                      |         |                                     | J | 2                        |   | J | 2                              |

Figure 3: Estimated Waste and Recycling Volumes - Stage Three

| Type of Dwelling     | # Units    | Waste Generation Rate (L/Unit/Week) | Generated Waste (L/Week) | Recycling Generation Rate (L/Unit/Week) | Generated Recyclables (L/Week) |
|----------------------|------------|-------------------------------------|--------------------------|---|--------------------------------|
| K                    | 26         | 61.11                               | 1588.9                   | 61.11                                   | 1588.9                         |
| L                    | 31         | 61.11                               | 1894.4                   | 61.11                                   | 1894.4                         |
| M                    | 28         | 61.11                               | 1711.1                   | 61.11                                   | 1711.1                         |
| N                    | 27         | 61.11                               | 1650.0                   | 61.11                                   | 1650.0                         |
| <b>TOTAL</b>         | <b>112</b> |                                     | <b>6844.4</b>            |   | <b>6844.4</b>                  |
| Bins and Collections |            | Waste Bin Size (L)                  | 1100                     | Recycling Bin Size (L)                  | 1100                           |
|                      |            | Waste Collections/Week              | 2                        | Recycling Collections/Week              | 1                              |
|                      |            | Bins Per Day                        | B                        | 0.2                                     | 0.2                            |
|                      |            |                                     | C                        | 0.2                                     | 0.2                            |
|                      |            |                                     | H                        | 0.2                                     | 0.2                            |
|                      |            |                                     | J                        | 0.2                                     | 0.2                            |
|                      |            | Bins Per Collection                 | B                        | 2                                       | 2                              |
|                      |            |                                     | C                        | 2                                       | 2                              |
|                      |            |                                     | H                        | 2                                       | 2                              |
|                      |            |                                     | J                        | 2                                       | 2                              |

Figure 4: Estimated Waste and Recycling Volumes - Stage Four

| Type of Dwelling     | # Units    | Waste Generation Rate (L/Unit/Week) | Generated Waste (L/Week) | Recycling Generation Rate (L/Unit/Week) | Generated Recyclables (L/Week) |
|----------------------|------------|-------------------------------------|--------------------------|---|--------------------------------|
| P1                   | 24         | 61.11                               | 1466.7                   | 61.11                                   | 1466.7                         |
| P2                   | 24         | 61.11                               | 1466.7                   | 61.11                                   | 1466.7                         |
| R                    | 20         | 61.11                               | 1222.2                   | 61.11                                   | 1222.2                         |
| S                    | 24         | 61.11                               | 1466.7                   | 61.11                                   | 1466.7                         |
| T                    | 23         | 61.11                               | 1405.6                   | 61.11                                   | 1405.6                         |
| U                    | 24         | 61.11                               | 1466.7                   | 61.11                                   | 1466.7                         |
| <b>TOTAL</b>         | <b>139</b> |                                     | <b>9961.1</b>            |   | <b>8494.4</b>                  |
| Bins and Collections |            | Waste Bin Size (L)                  | 1100                     | Recycling Bin Size (L)                  | 1100                           |
|                      |            | Waste Collections/Week              | 2                        | Recycling Collections/Week              | 1                              |
|                      |            | Bins Per Day                        | P1                       | 0.2                                     | 0.2                            |
|                      |            |                                     | P2                       | 0.2                                     | 0.2                            |
|                      |            |                                     | R                        | 0.2                                     | 0.2                            |
|                      |            |                                     | S                        | 0.2                                     | 0.2                            |
|                      |            |                                     | T                        | 0.2                                     | 0.2                            |
|                      |            |                                     | U                        | 0.2                                     | 0.2                            |
|                      |            | Bins Per Collection                 | P1                       | 2                                       | 2                              |
|                      |            |                                     | P2                       | 2                                       | 2                              |
|                      |            |                                     | R                        | 2                                       | 2                              |
|                      |            |                                     | S                        | 2                                       | 2                              |
|                      |            |                                     | T                        | 2                                       | 2                              |
|                      |            |                                     | U                        | 2                                       | 2                              |

\*Note: It is strongly recommended bins/equipment at the base of each chute allow for 2-days' worth of waste or recycling generation.

## 5.2 BIN SUMMARY

Based on the estimated waste generated by the residential component of this development, the recommended bin quantities and collection frequencies are as follows:

Table 3: Bin Summary Table

| Stage        | General Waste bins     | Collection Frequency | Recycling Bins         | Collection Frequency | Service Bins           |
|--------------|------------------------|----------------------|------------------------|----------------------|------------------------|
| <b>One</b>   | 8 x 1100L MGBs         | 2 x Weekly           | 8 x 1100L MGBs         | 1 x Weekly           | 8 x 1100L MGBs         |
| <b>Two</b>   | 8 x 1100L MGBs         | 2 x Weekly           | 8 x 1100L MGBs         | 1 x Weekly           | 8 x 1100L MGBs         |
| <b>Three</b> | 8 x 1100L MGBs         | 2 x Weekly           | 8 x 1100L MGBs         | 1 x Weekly           | 8 x 1100L MGBs         |
| <b>Four</b>  | 12 x 1100L MGBs        | 2 x Weekly           | 12 x 1100L MGBs        | 1 x Weekly           | 12 x 1100L MGBs        |
| <b>Total</b> | <b>37 x 1100L MGBs</b> |                      | <b>37 x 1100L MGBs</b> |                      | <b>36 x 1100L MGBs</b> |

## 5.3 WASTE DISPOSAL PROCEDURES

Dual chute systems, comprising One (1) waste and one (1) recycling chute will be installed with access provided on each residential level of each core.

Residents will wrap or bag their general waste before placing in the waste chute. Bagged waste should not exceed 3kg in weight, or 35cm x 35cm x 35cm. Recycling (comingle only) must not be bagged when disposed of into the recycling chute. Cardboard boxes or large containers should also not be disposed of in the chute and a separate cardboard collection bin must be made available and managed by the building caretaker.

The general waste will discharge from the waste chute into 1100L MGBs on linear tracks and the comingled recyclables will discharge into 1100L MGBs on linear tracks in the chute discharge room located on the basement levels.

Residents that are located in the same level as the chute discharge room will be provided direct access to the chute discharge room to decant into the designated 1100L bin. The chute offset area is recommended to be caged to prevent unauthorised access, and maintain safety regulation. The bins for the residents will be located outside the caged area.

There are residents located in the buildings that do not have access to the chute system. These residents will have a bin room in their level for 1100L bins for waste and recycling to dispose of, and will be rotated when required by the building caretaker.

Refer to Council guidance for the types of materials accepted in the general waste and recycling streams.

### 5.3.1 COMMON AREAS

Residential common areas such as lobbies, amenities and circulation areas will be supplied with suitably branded waste and recycling bins where considered appropriate. These areas generate minimal waste, however general waste and recycling receptacles should be placed in convenient locations.

## 5.4 WASTE COLLECTION PROCEDURES

Council will be engaged to collect the residential waste and recycling in accordance with Council's collection schedule. This report assumes general waste will be collected twice weekly and recycling once weekly.

On the nominated waste collection day, the building caretaker will be responsible for transporting the 1100L MGBs from each chute discharge room to the bin collection rooms for each stage, located on the lower basement or the ground level. A provision of 2 x 1100L service bins are placed under each dual chute to collect discharge while the other bins are being serviced for each dual chute system.

To service the bins, a Council collection vehicle will enter the site from the internal roads of O'Connell Street and in the designated loading bay for each stage. The building caretaker will provide the driver with access to the bin collection room for each stage. Once the bins are serviced, the collection vehicle will exit the site onto the internal roads of O'Connell Street a forward direction.

- **Collection Point 1 (Stage One)** will have bins serviced via Loading Dock B.
- **Collection Point 2 (Stage Two)** will have bins serviced via Loading Dock D.
- **Collection Point 3 (Stage Three)** will have bins serviced via Loading Dock M.
- **Collection Point 4 (Stage Four)** will have bins serviced via Loading Dock U.

It is the responsibility of the caretaker to ensure that the loading area is clear of any vehicles or obstructions prior to waste collection. When waste collection is complete, the building caretaker will return the bins to resume operational use.

All bin collection rooms is to be locked through Council's Abloy key System, where the lock system number is **50L092** as viewed in the Councils DCP.

*Table 4: Collection Points and Locations Summary*

| Stage        | Collection Point   | Buildings Serviced by the Collection Point | Location of Loading Dock |
|--------------|--------------------|--|--------------------------|
| <b>One</b>   | Collection Point 1 | Buildings B, C, H and J                    | Below Building B         |
| <b>Two</b>   | Collection Point 2 | Buildings D, E, F and G                    | Below Building D         |
| <b>Three</b> | Collection Point 3 | Buildings K, L, M and N                    | Below Building M         |
| <b>Four</b>  | Collection Point 4 | Buildings P1, P2, R, S, T and U            | Below Building U         |

*Building A* will have bins transported from the chute discharge rooms to the temporary hardstand area on ground floor for collection. The bins will be transported with an approved bin tug device to aid for both collections, and return of bins.

## 5.5 BULKY WASTE PROCEDURES

An area will be made available for the storage of discarded residential bulky items (e.g., whitegoods, furniture, etc.). This room should be located within close proximity of the garbage and recycling bin collection room and must have a minimum doorway width of 1.8m to allow for easy movement of large waste items in and out of the room.

Residents will need to liaise with building management regarding the transportation of bulky items and the availability of the bulky waste storage room on the basement levels. It is the caretaker's responsibility to arrange collection dates with Council and then coordinate with the residents.

On the day of bulky waste collection, a Council collection vehicle will enter the site from the internal roads in a forward direction, and park in the loading bay. The building caretaker will provide the driver with access to the bulky waste storage room, which are all located adjacent to the collection room. Once bulky items have been loaded, the collection vehicle will exit the site onto the internal roads in a forward direction. Refer to Council's website for acceptable items and other information regarding bulky waste collection.

The bulky waste rooms have been calculated in accordance with the 'Penrith City Council Residential Flat Building Waste Management', which the formula from the guidelines below:

$$\text{Bulky Goods Room Area (m}^2\text{)} = \left[ \text{Number of Units} \times 8 \right] \div 52$$

Tables 5: Bulky Waste Room Requirements.

### Stage One

| Type of Dwelling | # Units    | Bulky Waste Room (sqm) |
|------------------|------------|------------------------|
| B                | 19         | 3                      |
| C                | 23         | 4                      |
| H                | 35         | 6                      |
| J                | 26         | 4                      |
| <b>TOTAL</b>     | <b>103</b> | <b>17</b>              |

### Stage Two

| Type of Dwelling | # Units    | Bulky Waste Room (sqm) |
|------------------|------------|------------------------|
| D                | 26         | 4                      |
| E                | 29         | 5                      |
| F                | 25         | 4                      |
| G                | 35         | 6                      |
| <b>TOTAL</b>     | <b>115</b> | <b>19</b>              |

### Stage Three

| Type of Dwelling | # Units    | Bulky Waste Room (sqm) |
|------------------|------------|------------------------|
| K                | 26         | 4                      |
| L                | 31         | 5                      |
| M                | 28         | 5                      |
| N                | 27         | 5                      |
| <b>TOTAL</b>     | <b>112</b> | <b>19</b>              |

### Stage Four

| Type of Dwelling | # Units    | Bulky Waste Room (sqm) |
|------------------|------------|------------------------|
| P1               | 24         | 4                      |
| P2               | 24         | 4                      |
| R                | 20         | 4                      |
| S                | 24         | 4                      |
| T                | 23         | 4                      |
| U                | 24         | 4                      |
| <b>TOTAL</b>     | <b>139</b> | <b>24</b>              |



## 6.0 RETAIL WASTE MANAGEMENT

The following section outlines best practice waste management for the anticipated retail components of the development, including waste generation estimates and waste disposal and collection procedures.

### 6.1 WASTE GENERATION ESTIMATES

The 'Penrith Councils' *'Industrial, Commercial and Mixed-Use Waste Management Guidelines'* has been referenced to calculate the total number of bins required for the anticipated tenants. Calculations are based on generic figures, and waste generation rates may differ according to the tenants' actual waste management practice.

The following table shows the estimated volume (L) of general waste and recyclables that will be generated by the retail tenants.

The total GFA of the retail component has been divided into halves to take into account the waste generation of future possible tenancies. It is assumed that retail tenancies will share waste bins, the waste storage room, and the waste collection service.

The following estimates are based on a seven-day operating week for the anticipated tenancy types.

*Table 6: Estimated Waste and Recycling Volumes.*

| Tenancy Type         | GFA m <sup>2</sup> | Waste Generation Rate (L/100m <sup>2</sup> /Day) | Generated Waste (L/Week) | Recycling Generation Rate (L/100m <sup>2</sup> /Day) | Generated Recyclables (L/Week) |
|----------------------|--------------------|--|--------------------------|--|--------------------------------|
| Café                 | 708                | 300  | 14857.5                  | 100  | 4952.5                         |
| Retail: Non-Food     | 708                | 50   | 2476.3                   | 50   | 2476.3                         |
| <b>TOTALS</b>        | <b>1415</b>        |  | <b>17334</b>             |  | <b>7429</b>                    |
| Bins and Collections |                    | Bin Size (L)                                     | 1100                     | Bin Size (L)   | 1100                           |
|                      |                    | Bins/Week  | 15.8                     | Bins/Week  | 6.8                            |
|                      |                    | Collections/Week                                 | 3                        | Collections/Week                                     | 3                              |
|                      |                    | Total Bins                                       | <b>6</b>                 | Total Bins   | <b>3</b>                       |

## 6.2 BIN SUMMARY

The Penrith Councils' *'Industrial, Commercial and Mixed-Use Waste Management Guidelines'* have been used to calculate the estimated retail and commercial bin quantities. Rates have been split into 'halves to future-proof the design should the tenant undergo a 'change-of-use'. Based on the estimated waste generated by the retail tenancies, the recommended bin quantities and collection frequencies are as follows:

### ➤ Retail Bin Room

|                       |   |
|-----------------------|---|
| <b>General waste:</b> | 6 x 1100L MGBs collected <u>3 x Weekly.</u> |
| <b>Recycling:</b>     | 3 x 1100L MGBs collected <u>3 x Weekly.</u> |

Bin sizes, quantities, and/or collection frequencies may be modified by the building manager once the proposed development is operational. Building management will be required to negotiate any changes to bins or collections with the collection service provider. Seasonal peak periods such as public and school holidays should also be considered.

## 6.3 WASTE DISPOSAL PROCEDURES

On completion of each trading day or as required, nominated staff or contracted cleaners will transport all general waste and recyclables to the retail bin room and place into the appropriate collection bins (see APPENDIX A.1).

## 6.4 WASTE COLLECTION PROCEDURES

A private waste collection contractor will be engaged to service the retail waste and recycling bins per an agreed schedule. This report assumes waste and recycling is collected twice weekly.

On the day of service, a private waste collection vehicle will enter the site via the internal road from O'Connell Street, and park in the loading bay. The building caretaker will provide the driver with access to the commercial/retail bin rooms. Once the bins are serviced, the collection vehicle will exit the site onto the internal road at O'Connell Street in a forward direction.

Please note that the collection of commercial/retail bins should occur on separate days from the collection of residential bins to ensure proper segregation of waste streams.

## 6.5 OTHER WASTE MANAGEMENT CONSIDERATIONS

Based on the types of tenancies anticipated for this development, the following waste management practices are recommended.

### 6.5.1 KITCHEN, OFFICE TEA ROOMS AND FOOD PREPARATION AREAS

Any food preparation area, including kitchens and office tea rooms will be provided with dedicated source separation bins including a general waste bin and a recycling bin. Cleaners or nominated staff will be responsible for monitoring these bins and emptying them as required.

### **6.5.2 BATHROOMS**

Washroom facilities should be supplied with collection bins for paper towels (if used). Sanitary bins for female restroom facilities must also be arranged with an appropriate contractor.

### **6.5.3 PRINTING & PHOTOCOPYING ROOMS**

It is recommended that printing rooms and photocopying rooms are supplied with bins for the collection of paper, as well as separate receptacles for ink toner cartridges for recycling. The cleaners or nominated staff are responsible for monitoring these bins and ensuring the items are collected and recycled by an appropriate contractor.

### **6.5.4 LIQUID WASTE**

Liquid wastes such cleaning products, chemicals, paints, and cooking oil, etc., will be stored in a secure space that is bunded and drained to a grease trap in accordance with State government authorities and legislation.

### **6.5.5 PROBLEM WASTE**

The building manager is responsible for making arrangements for the disposal and recycling of problem waste streams with an appropriate contractor. Problem wastes cannot be placed in general waste as they can have adverse impacts to human health and the environment if disposed of in landfill. Retail and commercial tenants will need to liaise with the building manager when disposing of problem waste streams.

Problem waste streams include:

- Chemical Waste
- Liquid wastes
- Toner cartridges
- Lightbulbs
- eWaste
- Batteries

## 7.0 STAKEHOLDER ROLES & RESPONSIBILITIES

The following table demonstrates the primary roles and responsibilities of the respective stakeholders:

*Table 7: Stakeholder Roles and Responsibilities*

| Roles                                       | Responsibilities   |
|---|--|
| <b>Strata, Body Corporate or Management</b> | <ul style="list-style-type: none"> <li>• Ensure all waste service providers submit monthly reports on all equipment movements and waste quantities/weights;</li> <li>• Organise internal waste audits/visual assessments on a regular basis</li> <li>• Purchase any on-going waste management equipment or maintenance of equipment once building is operational; and</li> <li>• Manage any non-compliances/complaints reported through waste audits.</li> </ul>   |
| <b>Building Manager or Waste Caretaker</b>  | <ul style="list-style-type: none"> <li>• Maintain and clean chute doors on each level;</li> <li>• Coordinate general waste and recycling collections;</li> <li>• Clean and transport bins as required;</li> <li>• Organise replacement or maintenance requirements for bins;</li> <li>• Organise, maintain and clean the waste holding area;</li> <li>• Organise bulky goods collection when required</li> <li>• Investigate and ensure prompt clean-up of illegally dumped waste materials.</li> <li>• Prevent storm water pollution by taking necessary precautions (securing bin rooms, preventing overfilling of bins)</li> <li>• Abide by all relevant WH&amp;S legislation, regulations, and guidelines;</li> <li>• Provide staff/contractors with equipment manuals, training, health and safety procedures, risk assessments, and PPE to control hazards associated with all waste management;</li> <li>• Assess any manual handling risks and prepare a manual handling control plan for waste and bin transfers;</li> <li>• Ensure site safety for residents, children, visitors, staff and contractors; and</li> <li>• Ensure effective signage, communication and education is provided to occupants, tenants, maintenance staff, and cleaning contractors.</li> </ul> |
| <b>Residents</b>                            | <ul style="list-style-type: none"> <li>• Dispose of all general waste and recycling in the allocated waste chutes and/or MGBs provided;</li> <li>• Ensure adequate separation of general waste and recycling; and</li> <li>• Compliance with the provisions of Council and the OWMP.</li> </ul>  |
| <b>Retail/Commercial Tenants</b>            | <ul style="list-style-type: none"> <li>• Manage the back of house storage of generated waste and recycling during daily operation.</li> <li>• Correctly separate waste and recycling streams; bag general waste and ensure recyclables are not bagged.</li> <li>• Flatten cardboard within the recycling bin.</li> <li>• If required, make arrangements for storing used and unused cooking oil in a bunded storage area,</li> <li>• Organise grease interceptor trap servicing,</li> <li>• Ensure dry basket arrestors are provided to the floor wastes in the food preparation, and</li> <li>• Ensure the suitable storage for chemicals, pesticides and cleaning products waste back of house.</li> </ul>   |
| <b>Waste Collection Contractor</b>          | <ul style="list-style-type: none"> <li>• Provide a reliable and appropriate waste collection service;</li> <li>• Provide feedback to building managers/residents regarding contamination of recyclables; and</li> <li>• Work with building managers to customise waste systems where possible.</li> </ul>  |
| <b>Gardening/Landscaping Contractor</b>     | <ul style="list-style-type: none"> <li>• Remove all garden organic waste generated during gardening maintenance activities for recycling at an offsite location.</li> </ul>  |
| <b>Developer</b>                            | <ul style="list-style-type: none"> <li>• Purchase all equipment required to implement this OWMP prior to the occupation of the building to be provided to the strata/body corporate.</li> </ul>  |

## 8.0 SOURCE SEPARATION

Better practice waste management includes the avoidance, reuse, and recovery of unwanted items, which can be achieved through source separation. The table below outlines what is typically included in various waste streams and how they can be managed. Refer to your local council for a list of accepted materials. Planet Ark can be accessed online to find other facilities that recover unwanted items.

*Table 8: Operational Waste Streams*

| Waste Stream            | Description  | Typical Destination                  | Waste Stream Management  |
|-------------------------|--|--------------------------------------|--|
| <b>General Waste</b>    | The remaining portion of the waste stream that is not recovered for re-use, processing, or recycling. May include soft plastics, food scraps, polystyrene, etc.  | Landfill                             | Waste should be bagged before placing in chutes, or in designated waste bins.  |
| <b>Recycling</b>        | A mixture of items that are commonly recycled usually segregated through a MRF. Typically include food and beverage containers (e.g. aluminium, glass, steel, hard plastics, cartons). Also included cardboard and paper products. | Resource Recovery Centre             | Recycling must not be bagged, and instead should be placed loosely in the recycling chute or in designated recycling bins.<br><br>Bulky cardboard must not be placed in any chute. Cardboard should be flattened before placing in the designated cardboard bin. |
| <b>Green Waste</b>      | Green waste consists of unwanted organic materials that are easily biodegradable and/or compostable (e.g. lawn clippings, branches)  | Resource Recovery Centre             | Landscape Maintenance Contractors will remove the green waste from site during scheduled maintenance.<br><br>Green waste will be collected in council or private contractor bins and removed from site.  |
| <b>Food Waste</b>       | Food waste consists of unwanted or uneaten kitchen scraps that are easily compostable/biodegradable (e.g. vegetable peels, fruit rinds, coffee grounds).   | Composting facility or Landfill      | Food waste can be composted on-site, off-site, or else included in the general waste stream.   |
| <b>Electronic Waste</b> | Discarded e-waste, electronic components and materials such as computers, mobile phones, keyboards, etc.   | Resource Recovery Centre             | Building manager arranges collection for e-waste recycling as needed by residents. Commercial tenants arrange for recycling of their own e-waste.  |
| <b>Bulky Items</b>      | Items that are too large to place into general rubbish collection. This includes disused and/or broken furniture, mattresses, white goods, etc.  | Resource Recovery Centre or Landfill | Residents liaise with building manager to store in Bulky Goods Room. Building manager arranges with Council for removal. Commercial tenants are responsible for removal of their bulky items.  |
| <b>Sanitary Waste</b>   | Feminine hygiene waste generated from female bathrooms.  | Incineration or Landfill             | Sanitary bins are serviced by sanitary waste contractor.   |
| <b>Other</b>            | Other recyclable items that require special recovery may include ink cartridges, batteries, chemical waste, fluorescent tubes, etc.  | Resource Recovery Facility           | Building manager arranges collection by appropriate recycling services when required.  |

## 9.0 EDUCATION

Educational materials encouraging correct separation of general waste and recyclables must be provided to each resident and commercial/retail tenant. This should include the correct disposal process for bulky waste such as old furniture, large discarded items, and other materials including electronic and chemical wastes. It is recommended that the building caretaker provides information in multiple languages to support correct behaviours, and to minimise the possibility of chute blockages and contamination in communal waste bins.

Education and communication must be provided consistently on a regular basis to encourage behaviour change and account for transient building personnel such as new residents, tenants, or cleaning staff. It is also recommended that the owners' corporation website contain information for residents' referral regarding use of the chute. Information should include:

- Directions on using the chute doors;
- Descriptions of items accepted in the recycling and general waste streams (refer to Council guidance);
- How to dispose of bulky goods and any other items that are not general waste or recycling (refer to Council guidance);
- Residents' obligations to health and safety as well as building management; and
- How to prevent damage or blockages to the chute (example below).

***To prevent damage or blockage to rubbish chute DO NOT*** dispose of any umbrellas, bedding, cigarettes, cartons, coat hangers, brooms, mops, large plastic wrappings from furniture, white goods, any sharp objects, hot liquid or ashes, oil, unwrapped vacuum dust, syringes, paint and solvents, car parts, bike parts, chemicals, corrosive and flammable items, soil, timber, furniture, bricks or other building materials down the chute.

### 9.1 SIGNAGE

Signage and education are essential components to support best practice waste management including resource recovery, source separation, and diversion of waste from landfill.

Signage should include:

- Clear and correctly labelled waste and recycling bins,
- Instructions for separating and disposing of waste items. Different languages should be considered,
- Locations of, and directions to, the waste storage areas with directional signs, arrows, or lines,
- The identification of all hazards or potential dangers associated with the waste facilities, and
- Emergency contact information should there be issues with the waste systems or services in the building.

The building manager is responsible for waste room signage including safety signage. Appropriate signage must be prominently displayed on doors, walls and above all bins, clearly stating what type of waste or recyclables is to be placed in each bin.

All chute doors on all residential levels will be labelled with signs directing chute operations and use of chute door.

All signage should conform to the relevant Australian Standards.

## 9.2 POLLUTION PREVENTION

Building management shall be responsible for the following to minimise dispersion of site litter and prevent stormwater pollution to avoid impact to the environment and local amenity:

- Promoting adequate waste disposal into the bins;
- Securing all bin rooms (whilst affording access to staff/contractors);
- Prevent overfilling of bins, keep all bin lids closed and bungs leak-free;
- Taking action to prevent dumping or unauthorised use of waste areas;
- Require collection contractor/s to clean up any spillage when clearing bins.

## 10.0 EQUIPMENT SUMMARY

Table 9: Equipment Summary

|                 | Part  | Qty | Notes  |
|-----------------|---|-----|--|
| Chutes          | Please refer to supplier's information                                  | 36  | (See APPENDIX B.1 for Typical Dual Chute Layout) |
| Chute Equipment | <b>Waste</b><br>2-Bin 1100L Linear Track System (without Compactor)     | 18  | (See APPENDIX B.2 for Linear Track System)       |
|                 | <b>Recycling</b><br>2-Bin 1100L Linear Track System (without Compactor) | 18  |  |
| Other Equipment | Bin Tug   | 4   | (See APPENDIX C.4 for Typical Bin Movers)        |

## 11.0 WASTE ROOMS

The areas allocated for waste storage and collection areas are detailed in the table below, and are estimates only. Final areas will depend on room and bin layouts.

EFC recommends bins sizes, collection frequencies and/or equipment for best practice waste management at this site, however EFC also acknowledges there are a range of other suitable options that may alter waste room requirements (e.g., floor area, accessibility, head height, etc.)

*\*Note: Rooms with a \* will be caged to prevent unauthorised access to the chute offset when residents dispose of their waste in the bins outside. This applies to the residents situated on the same floor as the chute offset, providing an alternative method of resource separation and disposal.*



Table 10: Waste Room Areas- Stage One.

| Level | Waste Room Type                        | Equipment and MGBs   | Estimated Area Required (m <sup>2</sup> ) | Actual Area Provided (m <sup>2</sup> ) |
|-------|--|--|---|--|
| B1    | Chute Discharge Room B                 | Waste and Recycling:<br>2 x 2-bin 1100L linear track systems<br>Service bins: 2 x 1100L MGBs | 23  | 50                                     |
|       | Interim Bulky Waste Room B             |  | 3   | 5                                      |
|       | Chute Discharge Room C*                | Waste and Recycling:<br>2 x 2-bin 1100L linear track systems<br>Service bins: 2 x 1100L MGBs | 23  | 57                                     |
|       | Interim Bulky Waste Room C             |  | 4   | 15                                     |
|       | Chute Discharge Room H                 | Waste and Recycling:<br>2 x 2-bin 1100L linear track systems<br>Service bins: 2 x 1100L MGBs | 23  | 69                                     |
|       | Interim Bulky Waste Room H             |  | 6   | 10                                     |
|       | Chute Discharge Room J                 | Waste and Recycling:<br>2 x 2-bin 1100L linear track systems<br>Service bins: 2 x 1100L MGBs | 23  | 50                                     |
|       | Interim Bulky Waste Room J             |  | 3   | 9                                      |
|       | Central Residential Bin Holding Room   | General waste: 8 x 1100L MGB<br>Recycling: 8 x 1100L MGBs<br>1 x bin tug                     | 48  | 54                                     |
|       | Central Bulky Goods Waste Storage Room |  | 17  | 16                                     |

Table 11: Waste Room Areas - Stage Two.

| Level | Waste Room Type               | Equipment and MGBs   | Estimated Area Required (m <sup>2</sup> ) | Actual Area Provided (m <sup>2</sup> ) |
|-------|-------------------------------|--|---|--|
| B2    | Chute Discharge Room D        | Waste and Recycling:<br>2 x 2-bin 1100L linear track systems<br>Service bins: 2 x 1100L MGBs | 23  | 51                                     |
|       | B2 Lobby Residents Bin Room E | General waste: 1 x 1100L MGB<br>Recycling: 1 x 1100L MGB                                     | 6   | 6                                      |
|       | Interim Bulky Waste Room D    |  | 4   | 6                                      |
|       | Chute Discharge Room E        | Waste and Recycling:<br>2 x 2-bin 1100L linear track systems<br>Service bins: 2 x 1100L MGBs | 23  | 71                                     |
|       | Interim Bulky Waste Room E    |  | 5   | 10                                     |
|       | B2 Lobby Residents Bin Room E | General waste: 1 x 1100L MGB<br>Recycling: 1 x 1100L MGB                                     | 6   | 6                                      |
|       | Chute Discharge Room F        | Waste and Recycling:<br>2 x 2-bin 1100L linear track systems<br>Service bins: 2 x 1100L MGBs | 23  | 49                                     |
|       | Interim Bulky Waste Room F    |  | 4   | 10                                     |
|       | B2 Lobby Residents Bin Room F | General waste: 1 x 1100L MGB<br>Recycling: 1 x 1100L MGB                                     | 6   | 6                                      |
|       | Chute Discharge Room G        | Waste and Recycling:<br>2 x 2-bin 1100L linear track systems<br>Service bins: 2 x 1100L MGBs | 23  | 62                                     |
|       | Interim Bulky Waste Room G    |  | 6   | 10                                     |

|  |  |  |    |    |
|--|--|--|----|----|
|  | Central Residential Bin Holding Room   | General waste: 8 x 1100L MGB<br>Recycling: 8 x 1100L MGBs<br>1 x bin tug | 48 | 48 |
|  | Central Bulky Goods Waste Storage Room |  | 19 | 19 |

Table 12: Waste Room Areas - Stage Three

| Level | Waste Room Type                        | Equipment and MGBs   | Estimated Area Required (m <sup>2</sup> ) | Actual Area Provided (m <sup>2</sup> ) |
|-------|--|--|---|--|
| B1    | Chute Discharge Room K                 | Waste and Recycling:<br>2 x 2-bin 1100L linear track systems<br>Service bins: 2 x 1100L MGBs | 23  | 50                                     |
|       | Interim Bulky Waste Room K             |  | 4   | 26                                     |
|       | Chute Discharge Room L                 | Waste and Recycling:<br>2 x 2-bin 1100L linear track systems<br>Service bins: 2 x 1100L MGBs | 23  | 57                                     |
|       | Interim Bulky Waste Room L             |  | 5   | 6                                      |
|       | B1 Lobby Residents Bin Room M          | General waste: 1 x 1100L MGB<br>Recycling: 1 x 1100L MGB                                     | 6   | 6                                      |
|       | Chute Discharge Room M                 | Waste and Recycling:<br>2 x 2-bin 1100L linear track systems<br>Service bins: 2 x 1100L MGBs | 23  | TBD                                    |
|       | Interim Bulky Waste Room M             |  | 5   | TBD                                    |
|       | B1 Lobby Residents Bin Room N          | General waste: 1 x 1100L MGB<br>Recycling: 1 x 1100L MGB                                     | 6   | 6                                      |
|       | Chute Discharge Room N                 | Waste and Recycling:<br>2 x 2-bin 1100L linear track systems<br>Service bins: 2 x 1100L MGBs | 23  | 46                                     |
|       | Interim Bulky Waste Room N             |  | 5   | 5                                      |
|       | Residential Bin Holding Room           | Recycling: 8 x 1100L MGBs<br>Recycling: 8 x 1100L MGBs<br>1 x bin tug                        | 48  | 61                                     |
|       | Central Bulky Goods Waste Storage Room |  | 19  | 20                                     |

Table 13: Waste Room Areas - Stage Four

| Level | Waste Room Type                         | Equipment and MGBs   | Estimated Area Required (m <sup>2</sup> ) | Actual Area Provided (m <sup>2</sup> ) |
|-------|---|--|---|--|
| B2    | Chute Discharge Room P1                 | Waste and Recycling:<br>2 x 2-bin 1100L linear track systems<br>Service bins: 2 x 1100L MGBs | 23  | 46                                     |
|       | Chute Discharge Room P2                 | Waste and Recycling:<br>2 x 2-bin 1100L linear track systems<br>Service bins: 2 x 1100L MGBs | 23  | 45                                     |
|       | Interim Bulky Waste Room P              |  | 5   | 19                                     |
|       | Chute Discharge Room R                  | Waste and Recycling:<br>2 x 2-bin 1100L linear track systems<br>Service bins: 2 x 1100L MGBs | 23  | 57                                     |
|       | Interim Bulky Waste Room R + S          |  | 8   | 17                                     |
|       | Chute Discharge Room S                  | Waste and Recycling:<br>2 x 2-bin 1100L linear track systems<br>Service bins: 2 x 1100L MGBs | 23  | 55                                     |
|       | Chute Discharge Room T                  | Waste and Recycling:<br>2 x 2-bin 1100L linear track systems<br>Service bins: 2 x 1100L MGBs | 23  | 78                                     |
|       | Interim Bulky Waste Room T              |  | 4   | 7                                      |
|       | Chute Discharge Room U                  | Waste and Recycling:<br>2 x 2-bin 1100L linear track systems<br>Service bins: 2 x 1100L MGBs | 23  | 60                                     |
|       | Interim Bulky Waste Room U              |  | 4   | 14                                     |
|       | Retail Bin Room (Buildings R, S, T & U) | General waste: 6 x 1100L MGBs<br>Recycling: 3 x 1100L MGBs<br>1 X Bin tug                    | 28  | 46                                     |
|       | Residential Bin Holding Room            | General waste: 12 x 1100L MGBs<br>Recycling: 12 x 1100L MGBs<br>1 x bin tug                  | 70  | 70                                     |
|       | Central Bulky Goods Waste Storage Room  |  | 24  | 52                                     |

The waste room areas have been calculated based on equipment requirements and/or bin dimensions with an additional 70% of bin GFA factored in for manoeuvrability.

In addition, all doorways and passageways facilitating the movement of bins and/or bulky waste items must be at least 1800mm wide per Council's DCP. The following table provides further waste room requirements.

Table 14: Waste Room Requirements

| Waste Room Type   | Waste Room Requirements  |
|---|--|
| Chute Discharge Room                                    | <ul style="list-style-type: none"> <li>• Ceiling clearance height must be a minimum of 3000mm;</li> <li>• The chute penetration must have a minimum 500mm clearance of any service pipes or other overhead obstacles (subject to penetration location);</li> <li>• All waste discharge points should be caged off to ensure the safety of any personnel accessing the waste room;</li> <li>• 200mm clearance is required around compaction equipment;</li> <li>• Where a chute offset is required, the angle of the offset must not exceed 40 degrees (Subject to number of consecutive offset and/pr up to 1500mm);</li> <li>• Where two sets of volume management equipment are placed under the chutes, a 200mm clearance is required between the equipment;</li> <li>• Minimum 0.9-meter clearance around the linear track system;</li> <li>• 1.8m unobstructed clearance zone between equipment and doorway;</li> </ul> |
| Residential Bin Holding Room and/or Bin Collection Area | <ul style="list-style-type: none"> <li>• Bins must not be stacked in rows that are more than two bins deep;</li> <li>• 0.2m between bins to allow adequate space for manoeuvrability;</li> </ul>   |
| Bulky Goods Waste Storage Room                          | <ul style="list-style-type: none"> <li>• May be a dedicated room or screened area within another waste room;</li> <li>• Must be in close proximity to the collection area;</li> <li>• Area must also be allocated for the segregation of e-waste, gas bottles, cardboard, etc.</li> <li>• Doorway should be a minimum of 1500mm wide;</li> </ul>   |
| Retail Bin Room   | <ul style="list-style-type: none"> <li>• In order to ensure staff safety, all bins should be arranged so they can be accessed without moving another bin;</li> </ul>   |

## 12.0 BIN MOVING PATHS

The building manager is responsible for the transportation of bins as required from their designated operational locations to the bin holding room as required and returning them once emptied to resume operational use.

Transfer of bins should minimise manual handling where possible, as bins become heavy when full. The building manager must assess manual handling risks and provide any relevant documentation to key personal.

The routes along the bin moving path should;

- Allow for a continuous route that is wholly within the property boundary.
- Be free from obstruction and obstacles such as steps and kerbs.
- Be constructed of solid materials with a non-slip surface.
- Be A minimum of 300mm wider than the largest bin used onsite.
- If bins are moved manually, the route must not exceed a grade of 1:14.
- If a bin moving device is used, the route cannot exceed the maximum operating grade of the device. This is typically a grade of 1:4, however this will vary depending on the model of bin moving device acquired for the site.

As the distance of the bin moving paths exceeds 10m, a bin moving device is required to aid the movement of full bins. The developer is responsible for supplying all equipment required for moving bins this includes any bin lifters, bin moving devices and waste transfer bins. This equipment must be new and appropriate for the site. The developer should contact a bin-tug, trailer or tractor consultant to provide equipment recommendations.

Once the site is operational (and the developers is no longer involved) the building proprietors/strata/body corporate will be responsible for maintaining, repairing and replacing waste management equipment.

Bins may have to be fitted with hitches to enable the simultaneous transportation of multiple bins to the collection area. Council must be informed of any hitch attachments required to be installed on bins.

## 12.0 CONSTRUCTION REQUIREMENTS

Waste room construction must comply with the minimum standards as outlined in the *Penrith Development Control Plan 2014*, in order to minimise odours, deter vermin, protect surrounding areas, and make it a user-friendly and safe area.

The *NSW Better practice guide for resource recovery in residential developments (2019)* also states that better practice bin storage areas should achieve more than the minimum compliance requirements, which are as follows:

- Ensuring BCA compliance, including ventilation. Where required, ventilation system must comply with AS1668.4-2012 The use of ventilation and air conditioning in buildings.
- Ensuring storage areas are well lit (sensor lighting preferred) and have lighting available 24 hours a day.
- Provision of bin washing facilities, including taps for hot and cold water provided through a centralised mixing valve. The taps must be protected from bins and be located where they can be easily accessed even when the area is at bin capacity.
- Floor constructed of concrete at least 75mm thick.
- Floor graded so that any water is directed to a sewer authority approved drainage connection to ensure washing bins and/or waste storage areas do not discharge flow into the stormwater drain.
- Provision of smooth, cleanable and durable floor and wall surfaces that extend up the wall to a height equivalent to any bins held in the area.
- Ensuring ceilings are finished with a smooth-faced non-absorbent material capable of being cleaned.
- All surfaces (walls, ceiling and floors) finished in a light colour.

### 12.1 ADDITIONAL CONSIDERATIONS

- Waste room floor to be sealed with a two-pack epoxy;
- All corners coved and sealed 100mm up, this is to eliminate build-up of dirt;
- Tap height and light switch height of 1.6m;
- Storm water access preventatives (grate);
- All walls painted with light colour and washable paint;
- Equipment electric outlets to be installed 1700mm above finished floor level;
- Optional automatic odour and pest control system installed
- If 660L or 1100L bins are utilised, 2 x 820mm (minimum) double-doors must be used;
- All personnel doors are hinged, lockable and self-closing;
- Conform to the Building Code of Australia, Australian standards and local laws; and
- Childproofing and public/operator safety shall be assessed and ensured
- Waste and recycling rooms must have their own exhaust ventilation system either;
  - Mechanically - exhausting at a rate of 5L/m<sup>2</sup> floor area, with a minimum rate of 100L/s minimum. Mechanical exhaust systems shall comply with AS1668.4.2012 and not cause any inconvenience, noise or odour problem; or
  - Naturally - permanent, unobstructed, and opening direct to the external air, not less than one-twentieth (1/20) of the floor area.

## 13.0 USEFUL CONTACTS

EFC does not warrant or make representation for goods or services provided by suppliers.

---

### LOCAL COUNCIL

Penrith Council Customer Service    Ph: (02) 4732 7777    E: [council@penrith.city](mailto:council@penrith.city)

---

### PRIVATE WASTE COLLECTION PROVIDER

|                             |                  |   |
|-----------------------------|------------------|---|
| Capital City Waste Services | Ph: 02 9599 9999 | E: <a href="mailto:service@ccws.net.au">service@ccws.net.au</a>       |
| Remondis                    | Ph: 02 9032 7100 |   |
| Suez Environmental          | Ph: 13 13 35     |   |
| Wastewise NSW               | Ph: 1300 550 408 | E: <a href="mailto:admin@wastewise.com.au">admin@wastewise.com.au</a> |

---

### BIN MOVING DEVICE SUPPLIERS

|              |                  |   |
|--------------|------------------|---|
| Electrodrive | Ph: 1800 333 002 | E: <a href="mailto:sales@electrodrive.com.au">sales@electrodrive.com.au</a> |
| Sitecraft    | Ph: 1300 363 152 | E: <a href="mailto:sales@sitecraft.com.au">sales@sitecraft.com.au</a>       |
| Spacepac     | Ph: 1300 763 444 |   |

---

### ORGANIC DIGESTERS AND DEHYDRATORS

|              |                  |   |
|--------------|------------------|---|
| Closed Loop  | Ph: 1300 762 166 |   |
| Orca         |                  | E: <a href="mailto:contact.australia@feedtheorca.com">contact.australia@feedtheorca.com</a> |
| Soil Food    | Ph: 1300 556 628 |   |
| Waste Master | Ph: 1800 614 272 | E: <a href="mailto:hello@wastemasterpacific.com.au">hello@wastemasterpacific.com.au</a>     |

---

### COOKING OIL CONTAINERS AND DISPOSAL

|        |                  |   |
|--------|------------------|---|
| Auscol | Ph: 1800 629 476 | E: <a href="mailto:sales@auscol.com">sales@auscol.com</a> |
|--------|------------------|---|

---

### ODOUR CONTROL

|                |                  |   |
|----------------|------------------|---|
| EF Neutralizer | Ph: 1300 435 374 | E: <a href="mailto:info@elephantsfoot.com.au">info@elephantsfoot.com.au</a> |
|----------------|------------------|---|

---

### SOURCE SPERATION BINS

|                           |                  |   |
|---------------------------|------------------|---|
| Source Separation Systems | Ph: 1300 739 913 | E: <a href="mailto:info@sourceseparationsystems.com.au">info@sourceseparationsystems.com.au</a> |
|---------------------------|------------------|---|

---

### MOBILE GARBAGE BINS, BULK BINS AND BIN EQUIPMENT

|                |                  |   |
|----------------|------------------|---|
| SULO           | Ph: 1300 364 388 | E: <a href="mailto:sales@sulo.com.au">sales@sulo.com.au</a> |
| OTTO Australia | Ph: 02 9153 6999 |   |

---


### CHUTES, COMPACTORS AND EDIVERTER SYSTEMS

|                |                  |   |
|----------------|------------------|---|
| Elephants Foot | Ph: 1800 025 073 | E: <a href="mailto:info@elephantsfoot.com.au">info@elephantsfoot.com.au</a> |
|----------------|------------------|---|

## APPENDIX A: ARCHITECTURAL PLANS



# APPENDIX: A.1 BASEMENT 2 FLOOR PLAN – STAGE FOUR (BIN STORAGE ROOMS)




Source: Turner, Drawing no. DA-110-006, Revision 10, 20-02-2024.

APPENDIX: A.2 TYPICAL FLOOR PLAN – STAGE FOUR.



Source: Turner, Drawing no. DA-110-008, Revision 10, 20-02-2024.


# APPENDIX: A.3 TYPICAL FLOOR PLAN – STAGE TWO



Source: Turner, drawing no. DA-110-010, Revision 11, 20-02-2024.




APPENDIX: A.4 TYPICAL FLOOR PLAN – STAGE THREE



Source: Turner, drawing no. DA-110-020, Revision 11, 20-02-2024.



# APPENDIX: A.5 TYPICAL FLOOR PLAN – STAGE ONE



Source: Turner, drawing no. DA-110-020, Revision 11, 20-02-2024.


## APPENDIX B: INSTALLATION EQUIPMENT

## APPENDIX: B.1 TYPICAL DUAL CHUTE SHAFT & PENETRATION SET-OUT




### CHUTE SHAFT & PENETRATION SET-OUT


DUAL Ø610 STEEL




01 DUAL (610ø) GALV. STEEL CHUTE LAYOUT PENETRATION SET-OUT




02 DUAL (610ø) GALV. STEEL CHUTE LAYOUT




03 DUAL (610ø) GALV. STEEL CHUTE LAYOUT with ENCLOSURE CUPBOARD (\*)



04 DUAL (610ø) GALV. STEEL CHUTE LAYOUT WITH CIRCULAR PENETRATION SET-OUT



05 DUAL (610ø) GALV. STEEL CHUTE LAYOUT (w/ CIRCULAR PENETRATION)



06 DUAL (610ø) GALV. STEEL CHUTE LAYOUT with ENCLOSURE CUPBOARD (\*)

(\*) NOTE: ENCLOSURES ARE RECOMMENDED IF THE CHUTE OPENS DIRECTLY TO A CORRIDOR OR IS NOT LOCATED IN A WASTE ROOM. IF CHUTE ACCESS IS WITHIN A WASTE ROOM THEN THE CUPBOARD ENCLOSURES ARE NOT REQUIRED.

SCALE 1:25 @ A3

Chute Shaft & Penetration - Ver 1.2 April 26, 2022

Please note: This is an example only, please refer to the supplier's information and specification.



## APPENDIX: B.2 TYPICAL LINEAR TRACK SYSTEM FOR 1100L MGBS



ELEPHANTS FOOT RECYCLING SOLUTIONS  
44-46 GIBSON AVE, PADSTOW NSW 2211  
E: [info@elephantsfoot.com.au](mailto:info@elephantsfoot.com.au) W: [elephantsfoot.com.au](http://elephantsfoot.com.au)  
Free Call: 1300 4 ELEPHANT (1300 435 374)

# 1100 LITRE LINEAR TRACK SYSTEM

## PRODUCT INFORMATION

Elephants Foot 1100 Litre bin Linear Track System is a versatile waste handling solution for many types of multi-storey or multi-level developments. The Linear Track System collects waste or recycling being disposed from the floors above through the chute system, discharging the material via a hopper that feeds the bins. Electromechanically driven with automated operation, the system utilises linear motion to automatically change over full bins. Once all the bins are filled, an indicator light will illuminate signifying that the bins are ready for withdrawal and collection. Available with or without compaction unit, our standard 660 litre bin Linear Track System is available in the standard 2 bin option. Our 3 Bin option is available as a special order.



### SPECIFICATIONS

|                      |                        |
|----------------------|------------------------|
| System Control       | Electric PLC           |
| Power Supply         | 415 V AC / 10A / 5 PIN |
| Motor Size (kW)      | 1.1                    |
| Maximum bin load     | 440 kg                 |
| Noise (dBA)          | <85                    |
| Bin Size (L)         | 1100                   |
| Cycle time (sec)     | 60                     |
| Bin Quantity options | 2 or 3                 |

### OPTIONAL EXTRAS

- Compaction unit – Please refer to the bin compactor product information sheet for details and specifications
- Enhanced safety add on's – Interlocking barriers, occupancy sensors or safety light curtains (presence sensing light barriers)
- Full bin SMS and email notification
- CMMS and BMS integration
- Extend warranty – Terms and conditions apply

### STANDARD FEATURES & BENEFITS

- Simple operation with user friendly controls
- Increased waste servicing efficiency for the development.
- Automatic system control with manual override
- Robust unit construction for long performance life
- Low service and maintain costs
- Rotating flashing beacon (activated during operation)
- Quiet and efficient system operation
- Maximise safety for residents, caretakers and collectors
- Restrained design with minimal moving parts
- Can suit low ceiling clearances
- Floor contact components fully galvanised steel
- Retro fitting options to suit other chutes systems
- Compliant with relevant Building Codes and Standards
- Standard 12 month warranty







# 1,100 LITRE LINEAR TRACK SYSTEM



| No. of Bins | Reference (mm) |      |      |
|-------------|----------------|------|------|
|             | A              | B    | C    |
| 2           | 900            | 3700 | 5300 |
| 3           | 2100           | 5940 | 7550 |

Available with or without compaction unit, our standard 1100 litre bin Linear Track System is available in the standard 2 bin option. Our 3 Bin option is available as a special order.



## Notes:

Bins not provided by Elephants Foot

Drawings shown are for general information purposes only and provide minimum equipment spacial requirements for waste room design.

These drawings are not intended for site specific use or for construction. Each project is unique and will be designed to suit.

Additional equipment options, systems and configurations are available. For design assessment, information and advice, please contact an Elephants Foot design consultant on 1300 435 374

*Please Note: This is an example only – please refer to supplier's information and specification*

## APPENDIX C: PRIMARY WASTE MANAGEMENT PROVISIONS

## APPENDIX: C.1 TYPICAL BIN SPECIFICATIONS


### Mobile bins

Mobile bins come in a variety of sizes and are designed for lifting and emptying by purpose-built equipment.

Mobile bins with capacities of up to 1700L must comply with *AS4123.6-2006 Mobile waste containers* which specifies standard sizes and sets out the colour designations for the bodies and lids of mobile waste containers indicating the type of materials they are used to collect.

The most common bin sizes are provided below, although not all sizes are shown. The dimensions are a guide only and differ slightly between manufacturers. Some bins have flat or domed lids and are used with different lifting devices. Refer to *AS4123.6-2006* for further details.

**Table G1.1: Average dimension ranges for two-wheel mobile bins**




| Bin capacity                            | 80L  | 120L      | 140L      | 240L      | 360L      |
|---|------|-----------|-----------|-----------|-----------|
| Height (mm)                             | 870  | 940       | 1065      | 1080      | 1100      |
| Depth (mm)                              | 530  | 530       | 540       | 735       | 820       |
| Width (mm)                              | 450  | 485       | 500       | 580       | 600       |
| Approximate footprint (m <sup>2</sup> ) | 0.24 | 0.26–0.33 | 0.27–0.33 | 0.41–0.43 | 0.49      |
| Approximate weight (kg)                 | 8.5  | 9.5       | 10.4      | 15.5      | 23        |
| Approximate maximum load (kg)           | 32   | 48        | 56        | 96        | Not known |

**Wheelie bin**

Sources include Sulo, Single Waste, Cleanaway, SUEZ, just wheelie bins and Perth Waste for two-wheel mobile bins

**Table G1.2: Average dimension ranges for four-wheel bulk bins**



| Bin capacity                       | 660L      | 770L      | 1100L     | 1300L     | 1700L     |
|------------------------------------|-----------|-----------|-----------|-----------|-----------|
| Height (mm)                        | 1250      | 1425      | 1470      | 1480      | 1470      |
| Depth (mm)                         | 850       | 1100      | 1245      | 1250      | 1250      |
| Width (mm)                         | 1370      | 1370      | 1370      | 1770      | 1770      |
| Approx footprint (m <sup>2</sup> ) | 0.86–1.16 | 1.51      | 1.33–1.74 | 2.21      | 2.21      |
| Approx weight (kg)                 | 45        | Not known | 65        | Not known | Not known |
| Approx maximum load (kg)           | 310       | Not known | 440       | Not known | Not known |

**Dome or flat lid container**

Sources include Sulo, Signal Waste, Cleanaway, SUEZ, Just Wheelie Bins and Perth Waste

Source: *Better Practice Guide For Resource Recovery In Residential Developments 2019*, NSW Environmental Protection Authority

## APPENDIX: C.2 SIGNAGE FOR WASTE AND RECYCLING BINS

### Waste signs

Signs and educational materials perform several functions including:

- informing residents why it is important to recover resources and protect the environment
- providing clear instructions on how to use the bins and services provided
- alerting people to any dangers or hazards within the bin storage areas.

All waste, recycling and organic bins should be Australian Standard colours and clearly and correctly labelled, such as by a sticker on the lid and/or the body of the bin.

Communal bin storage areas should be clearly signposted with signs outlining how to correctly separate waste into the bins provided. The local council responsible for waste services may be a good source of signs and posters and can advise on what signs are suitable.

Information on who to contact to find out more about the recycling and/or other resource recovery services in the building should also be displayed in communal areas, such as on a noticeboard.

The Planet Ark website also has resources available free of charge for use by businesses and councils. These signs can be found at [businessrecycling.com.au/research/signage.cfm](http://businessrecycling.com.au/research/signage.cfm)

Figure I1.1: Examples of waste wall posters (EPA supplied)



Figure I1.2: Examples of bin lid stickers (EPA supplied)



Source: *Better Practice Guide For Resource Recovery In Residential Developments 2019*, NSW Environmental Protection Authority

## Problem waste signs

The EPA has also produced a range of images and signs that can be used for problem wastes, such as fluoro globes and tubes, household and car batteries, e-waste and smoke detectors. To access these resources, contact the NSW EPA. Some examples are shown below.

Figure I2.1: Problem waste signs



## Safety signs

The use of safety signs for waste resource recovery rooms must comply with *AS1319 Safety signs for occupational environments*. Safety signs must be used to regulate and control safety related to behaviour, warn of hazards and provide emergency information, including fire protection information. Suitable signs should be decided for each development as required.

Figure I3.1: Example safety signs



Source: *Better Practice Guide For Resource Recovery In Residential Developments 2019*, NSW Environmental Protection Authority

## APPENDIX: C.3 REAR LOAD WASTE COLLECTION VEHICLE (LOW ENTRY)


### 2.3 DESIGN SPECIFICATIONS REAR LOAD WASTE COLLECTION VEHICLES

The following dimensions are provided for a standard heavy rigid vehicle as identified in Australian Standard 2890.2:

#### 2.3.1 Low Entry Heavy Rigid Waste Collection Vehicle

| Vehicle Classifications       | Heavy Rigid Vehicle Dimensions |
|-------------------------------|--------------------------------|
| Overall Length (m)            | 9.7                            |
| Operational Length (m)        | 11.7                           |
| Design Width (m)              | 2.8                            |
| Design Height (m)             | 3.1                            |
| Swept Circle (m)              | 17.0                           |
| Clearance (travel height) (m) | 3.5                            |
| Roadway/ramp grade (max)      | 1:6.5 (15.4%)                  |
| Rate of change of grade (max) | 1:12 (8.3%) in 4.0m of travel  |
| Gross Weight (max tonnes)     | 28.0                           |
| Front Chassis Clearance       | 13°                            |
| Rear Chassis Clearance        | 16°                            |

**Table 1: Standard dimensions in accordance with AS 2890.2**



**Figure 1: 9.7m Heavy Rigid Rear Load Waste Collection Vehicle specifications**

Source: Penrith Development Control Plan: C5 (Waste Management Guidelines for Residential Flat Buildings)

## APPENDIX: C.4 TYPICAL BIN MOVERS

### Battery powered tug with a 1 or 2 tonne tow capacity



#### Features at a glance

One tonne (Evo 1T) or two tonne (Evo 2T) tow capacity

Auto latching hitch

Three speed motor with emergency stop

#### Typical applications

The Tug Evo is suitable for airports, factories, warehouses, apartment buildings or large facilities. This powered tug is also suitable for transporting medical carts around hospitals or moving heavy specialist equipment.

#### Features:

- 1 or 2 tonne tow capacity of inclines up to 6 degrees
- 500kg tow capacity if inclines up to 14 degrees
- CE Compliant
- 5 km/h max speed
- 2 x 12V 42Ah MK-gel batteries with 24V smart charger.
- Powerful transaxle

#### Safety Features:

- Intuitive control with standard automatic safety brake, forward and reverse drive.
- Emergency stop button.

Emergency back-off button

Source: <http://www.electrodrive.com.au/products/tugs/tug-evo.aspx>



## APPENDIX: C.5 TYPICAL SEATED BIN MOVERS

# SITECRAFT

MATERIALS HANDLING EQUIPMENT




17 Macquarie Drive, Thomastown, VIC 3074

Phone: 1300 363 152 Fax: 1300 722 383


E: sales@sitecraft.com.au ABN: 36 423 328 526

## SITECRAFT HEAVY DUTY ELECTRIC TOW TRACTOR

- > Towing capacities from 2000 kg to 6,000 kg
- > **Full AC electric system** has a brake-releasing function, making the unit easy and effortless to operate; The maintenance-free motor completely solves the issues of DC motor carbon brush.
- > Batteries located in the lowest part of frame ensures excellent stability
- > Quick open back service cover for easy maintenance and part replacement
- > CANbus technology reduces wiring complexity and increases reliability
- > H type axle design provides excellent stability
- > New high-range steering design; light steering and easy to maintain.
- > New large-screen instrument display provides information clearly and directly to the operator.



**12 MONTH  
WARRANTY**



| Model                         |               | ST-2000AC         | ST-3000AC         | ST-5000AC          | ST-6000AC          |
|-------------------------------|---------------|-------------------|-------------------|--------------------|--------------------|
| Towing Capacity               | Kg            | 2000              | 3000              | 5000               | 6000               |
| Drawbar Centre Height         | h1/h2/h3 mm   | 280/350/420       | 280/350/420       | 280/350/420        | 280/350/420        |
| Motor                         | Kw / V        | 3Kw / 36V         | 3Kw / 36V         | 5Kw / 48V          | 5Kw / 48V          |
| Total Size                    | L x B x H mm  | 1720 x 968 x 1270 | 1720 x 968 x 1270 | 1975 x 1100 x 1270 | 1975 x 1100 x 1270 |
| Total Weight (With Batteries) | Kg            | 740               | 780               | 1240               | 1280               |
| Wheel Size                    | Solid Rubber  | 15*4-8            | 15*4-8            | 15*4-8             | 15*4-8             |
| Wheelbase                     | L1 mm         | 1055              | 1055              | 1280               | 1280               |
| Rear Hanging Distance         | L2 mm         | 382               | 382               | 500                | 500                |
| Seat Height                   | h4 mm         | 910               | 910               | 910                | 910                |
| Ground Clearance              | X mm          | 90                | 90                | 90                 | 90                 |
| Turning Radius                | Wa mm         | 1500              | 1500              | 1650               | 1650               |
| Maximum Speed                 | Km/h          | 10                | 8                 | 14                 | 12                 |
| Battery                       | V/Ah          | 36/200            | 36/250            | 48/360             | 48/400             |
| Battery Weight                | Kg            | 200               | 250               | 610                | 650                |
| Charger                       | On-board V/Ah | 36/30             | 36/30             | 48/50              | 48/50              |



**SITECRAFT**  
MATERIALS HANDLING EQUIPMENT



17 Macquarie Drive, Thomastown, VIC 3074  
Phone: 1300 363 152 Fax: 1300 722 383  
E: sales@sitecraft.com.au ABN: 36 423 328 526


## SITECRAFT HEAVY DUTY ELECTRIC TOW TRACTOR



Sitecraft ST3000-AC tow tug moving 660 & 1100 litre bins



Sitecraft ST3000-AC tow tug moving 660 & 1100 litre bins



ST3000-AC tow tug complete with 6 x 250AH heavy duty batteries



Optional steel / aluminium trailers for moving waste bins, linen trolleys, food trolleys, delivery boxes, etc ...

Source: <https://www.sitecraft.net.au/materials-handling/tow-tugs-powered-vehicles/electric-tow-vehicles/>

## APPENDIX D: SECONDARY WASTE MANAGEMENT PROVISIONS

## APPENDIX: D.1 TYPICAL WORM FARM SPECIFICATIONS

### Worm farms



Worm farms or vermiculture systems transform food and other organic material into vermicast (worm compost) and vermi-liquid (liquid extraction from a worm farm). Seafood, seafood shells, meat or bones, and dairy products are not an acceptable part of the worms' diet and should not be applied to these systems. Worm farms can occupy a small footprint and be located on balconies or in gardens. The worm farm should be placed in a sheltered position to avoid getting too hot in summer.

Worm farms come in different sizes and designs and are sold through hardware stores and often at local government offices. Medium and large-scale worm farms can service many households and commercial activities. These larger systems need a management process to ensure they are properly maintained.

### Onsite composting



Compost tumblers and bins and compost bays transform food and other organic material into useful soil enhancer (compost). They are more versatile than worm farms as they can generally process a wider range of materials, including woody garden organics and can be placed in the sun. A variety of compost bins and tumblers are available from hardware stores or some local councils. There are also various online resources on how to construct them using recycling materials such as timber pallets. The footprint area requirement for a typical single household compost bin is about 1m x 1m x 1m.

Before setting up an onsite composter or worm-farm system, check with council for any local requirements such as setback distances from property boundaries.

Source: *Better Practice Guide For Resource Recovery In Residential Developments 2019*, NSW Environmental Protection Authority

## APPENDIX: D.2 EXAMPLE APARTMENT STYLE COMPOST BIN



Apartment Style Compost bin – available from hardware stores

Suitable for:

- Vegetables
- Coffee grounds and filters
- Tea and tea bags
- Crushed eggshells (but not eggs)
- Nutshells
- Houseplants
- Leaves
- Cardboard rolls, cereal
- Boxes, brown paper bags
- Clean paper
- Shredded newspaper
- Fireplace ashes
- Wood chips, sawdust,
- Toothpicks, burnt matches
- Cotton and wool rags
- Dryer and vacuum cleaner lint
- Hair and fur
- Hay and straw

## APPENDIX: D.3 TYPICAL COOKING OIL CONTAINERS



Drums 205L



Pour in Bulk Tank

[View Brochure](#)



Oil Kaddy System

[View Brochure](#)



Eco System 700L fixed

Eco System 310L mobile

Eco Systems



Direct-Connect to Fryer

Source: <http://www.auscol.com/services/collection-systems/>



## APPENDIX: D.4 TYPICAL SOURCE SEPARATION BINS



Source: <https://www.sourceseparationsystems.com.au/>