



Stake all trees with 2 No. 38 x 1800mm, chisel pointed hardwood stakes. The trees immediately after planting with flexible canvas or rubber ties in a figure 8. Secure tie to stakes by wrapping around stake and nailing with galvanised nails.

Ensure plants are placed so as to match crown of rootball with surrounding surface level. Gently tease outer root system avoiding major disturbance to plant. Construct soil ring berm (watering saucer), around immediate crown of rootball to hold at least 5 litres of water. Spread 75mm layer of pine bark mulch to saucer. Ensure excavated soil is removed offsite or spread on subgrade PRIOR to spreading of imported topsoil. Under no circumstances is subsoil to remain on surface.

Keep mulch and topsoil away from trunk base. Raised ring of soil to direct water into rootball - especially important if top of rootball is raised above grade.

Specified topsoil cultivated by mechanical means.

Apply Osmocote slow release fertiliser 50 gms to evergreen tree spread into backfill. Avoid direct root contact with fertiliser.

Pack backfill soil around base of rootball to stabilise and allow backfill to settle naturally, or tamp lightly.

Notes:

1. Width of planting hole is: 3 times rootball diameter in highly compacted soil
2. 2 times rootball diameter minimum in all other areas
3. Depth of planting hole is: approx. 150mm below the base of the rootball

All trees to be healthy well grown specimens free of pests and diseases. Trees to be watered while still in their pots, prior to planting.

**PLANTING SCHEDULE**  
SELECTED FROM LIST OF INDIGENOUS/ LOW WATER USE SPECIES OF HAWKESBURY CITY COUNCIL

ABBREV#	BOTANIC NAME	COMMON NAME	MATURE HEIGHT	MATURE SPREAD	FLOWERING
CT	Clerodendrum Tomentosum	Hairy Clerodendrum	2m	1.5m	October to January
LP	Leptospermum Polygallifolium	Lemon Scented Tea Tree	1-4m	1-3m	Spring
CC	Casuarina Cunninghamiana	River She Oak	20-25m	6m	February to March
AF	Acacia floribunda	White Salwood Wattle	2-4m	2-3m	Spring
AI	Acacia implexa	Hickory Wattle	5-12m	2-4m	Summer
BM	Banksia Myrtifolia	Grey Myrtle	3-6m	3m	Summer
BS	Banksia Spinulosa	Hairpin Banksia	1-3m	2m	April - July
PL	Pimelea Linifolia	Rice Flower	1.5 m	1m	Spring
TL	Tristania laurina	Water Gum	3-10m	3-5m	Spring
BV	Baeckea Virgata	Twiggy Heath Myrtle	0.5 m	0.5m	Late Spring
CG	Ceratopetalum Gummiferum	NSW Christmas Bush	2-4 m	1-3m	Spring
DR	Dianella Revoluta	Blueberry Flax-lily	0.5 m	0.5m	Spring

**LANDSCAPE CONCEPT PLAN**  
SCALE: 1:200

DRAWING <b>LANDSCAPE CONCEPT</b>		PROJECT <b>PROPOSED NEW MOTEL</b>		REV. A	REVISION DESCRIPTION AMENDED DA SUBMISSION	DATE AUG, 2018	REV. B	REVISION DESCRIPTION AMENDED DA SUBMISSION	DATE SEPT, 2018	NOTES FIGURED DIMENSIONS TO TAKE PRECEDENCE OVER SCALING. ANY DISCREPANCIES TO BE CHECKED WITH THE AUTHOR PRIOR TO COMMENCING WORK. ALL LOCAL GOVERNMENT REGULATIONS, BUILDING CODE OF AUSTRALIA AND OTHER CODES AND STANDARDS SHALL BE COMPLIED WITH IN THE WORKS. THESE DRAWINGS ARE PROTECTED BY COPYRIGHT.
DATE SEPT, 2018	DRAWN A.P.G.	AT <b>189 WINDSOR ROAD</b> [LOT 2 in 1164124] <b>VINEYARD NSW 2765</b>		FOR <b>SWANKIN PTY LIMITED</b>						
REF. .. VINEYARD_M\DAPLAN2A.DCS5										
DRAWING No. 39608	EX DA	YEAR 18	REV. B							

**HOMEPLAN**  
PROJECT DESIGN RESOURCES  
**ARCHITECTS**

UNIT 20, 22 HUDSON AVE, CASTLE HILL  
NSW 2154 AUSTRALIA  
PHONE: 02 8850 7688 FAX: 02 8850 7699  
EMAIL: INFO@HOMEPLAN-ARCHITECTS.COM  
JOHN G. BOURKE B.A.RCH (HONS), A.R.A.I.A.  
DIP. C.D. (HONS), A.S.T.C. (HONS), P.D.C., N.S.W. REG. #2426