



WASTE MANAGEMENT PLAN

Establishment of a Solar PV Power
Generation Plant
Broockmanns Road, Finley NSW 2713

KDC

This page has been left blank intentionally

Address: Lot 61 in DP1053533, Broockmanns Road, Finley NSW 2713

Proposal: Establishment of Solar PV Power Generation Plant.

OBJECTIVES FOR THE WASTE MANAGEMENT ON THIS SITE

- + To minimise resource requirements and construction waste through reuse and recycling; and the efficient selection and ordering of resources.
- + To ensure the waste management systems are compatible with the relevant waste collection services.

The management of waste is addressed in this WMP in the following sections, according to the stages of the development:

- + Site preparation and construction; and
- + Ongoing operation.

1 CONSTRUCTION STAGE

Construction waste will be separated on site by builder's contractors and builder's laborer's during the construction stage. The site needs to be checked on a regular basis to make sure no recyclable materials are mixed with non-recyclable materials; and to set aside on site an area to store the recyclable materials for transportation to local recycling plants.

The site manager will erect a sign on site for waste areas and will inform the builder's staff where material is to be collected for recycling. The site manager and/or builder will impose the execution of the waste separation policy on a regular basis and to have on-going checks.

Stockpiles shall be located and managed appropriately to prevent sediment runoff and ensure minimal environmental impact from the building site.

Suitable all-weather vehicular access points shall be provided for the construction phase, and all sediment and erosion control devices implemented on site prior to commencement of construction works.

Type of waste generated	Estimates Volume in m ³ or area m ² or weight in tonne (t)	Reuse and Recycling		Disposal
		On-Site	Off-Site	
Excavated Material	<10m ³	Possible reuse of soil onsite.	Unused excavated material to be disposed at local waste facility.	
Metal (Ferrous) E.g. Steel	3t		Sent to local metal recycler by contractor.	
Metal (Non-ferrous) E.g. Aluminium	<1t		Sent to local metal recycler by contractor.	
Packaging (Wood) E.g. Pallets, dunnage	39.5t		Reuse by logistics contactor. Broken directed to recycler.	
Packaging (Other) (Plastic, cardboard etc.)	4.8t		Cardboard/paper sent to recycler by contractor.	Disposed of at local waste facility by contractor
Green Waste	<8t		Directed for green waste reuse by local recycler.	
Other waste e.g. pvc plastics, paint, paper / cardboard	<2t	-		Disposed of at local waste facility by contractor

2 ONGOING OPERATION STAGE

Staff will separate general waste and recyclables within the individual waste storage / management area. In the service yard a minimum of two separate bulk bins will be located. Waste and recycling bins will be clearly labelled and identifiable. The bins and waste storages areas will be cleaned by staff with protective gloves.

Type of waste generated	Estimated Volume per week	Reuse and Recycling		Disposal
		On-Site	Off-Site	
Food and General Waste	20L			Disposed of at local landfill by waste contractor on an as needs basis
Recyclable Waste	20L			Disposed of at local recycle plant by waste contractor on an as needs basis
Green Waste	20L			Disposed of at local recycle plant by waste contractor on an as needs basis