

Toga Addison Pty Limited
Level 5, 45 Jones Street
ULTIMO NSW 2007

Project 85151.00 Rev0
16 December 2015
PMO

Attention: Mr Michael Calvi

Dear Sirs

**Report on Due Diligence Assessment – Geotechnical
Proposed Residential Development
137 – 151 Anzac Pde, Kensington**

1. Introduction

This report presents the results of a due diligence assessment of geotechnical conditions undertaken at 137 – 151 Anzac Parade, Kensington. The work was commissioned by Toga Addison Pty Limited, prospective developers of the site.

The due diligence assessment was undertaken to determine geotechnical conditions on the site. For the purposes of this assessment it is assumed that the development will include a multi-storey residential unit building with one or more basement levels.

The geotechnical assessment component included three cone penetration tests, the drilling of two boreholes, the installation of two groundwater wells and engineering interpretation. Details of the field work and comments relevant to geotechnical issues are provided in this report.

A due diligence assessment of contamination risks and a hazardous building materials assessment were undertaken at the same time as this geotechnical assessment and are reported separately.

2. Site Description

The development site is a near-rectangular shaped lot with average dimensions of approximately 90 m by 45 m. It is bounded by a 7-Eleven service station to the north, Anzac Parade to the east, and residential dwellings/units to the south and west. The ground surface is relatively level and in the order of RL 25 m relative to the Australian Height Datum (AHD). The western portion of the southernmost lot (i.e. 147 – 151 Anzac Parade) has been excavated to form a parking area and is about 1.5 m below the surrounding areas.

At the time of the assessment the site was occupied by numerous buildings including a four-storey residential unit building, single-storey dwelling/commercial premises, one and two-storey commercial buildings and a four-storey motel. None of the existing buildings are known to contain basement levels. The site is shown on Drawing 1 in Attachment B.

3. Regional Geology and Hydrogeology

The Sydney 1:100 000 Geological Series Sheet indicates that the site is underlain by transgressive dunes which comprise medium to fine-grained marine sands with podsols. An extract from the geological map is shown in Figure 1.



Figure 1: Extract from geological map

The groundwater table is likely to be relatively shallow and flow in a west to south-west direction towards Alexandra Canal and ultimately Botany Bay. A search of licenced groundwater wells indicates that several monitoring wells are located within the service station to the north of the site as well as within the northern-most lot (i.e. 137 Anzac Parade). The standing water level was recorded on the well installation records at between about 2.4 m and 2.9 m below the ground surface.

4. Field Work

4.1 Methods

Three cone penetration tests (CPTs 1 to 3) were undertaken to depths of between 16.1 m and 20.0 m. A CPT involves pushing a 35 mm diameter instrumented cone and friction sleeve into the ground using hydraulic thrust from a ballasted truck-mounted testing rig. Measurements of cone resistance and sleeve friction are made at 20 mm depth intervals and are stored on a portable computer for subsequent interpretation and analysis. Notes relating to CPT technology are attached.

Two boreholes (BH4 and BH5) were drilled to depths of 6.0 m and 7.0 m using a DT250 drilling rig fitted with sold flight augers. The bores were converted into temporary groundwater monitoring wells at the completion of drilling by placing Class 18 uPVC screen and casing into the holes, backfilling the screened section with gravel, constructing a bentonite plug and installing steel covers flush with the ground surface.

The test locations are shown on Drawing 1 in Attachment B. The ground surface levels at the test locations were measured to AHD using an automatic level.

4.2 Results

The subsurface conditions inferred from the CPTs and encountered in the boreholes are shown on the results sheets and logs included in Attachment C. Notes defining descriptive terms and classification methods are provided in Attachment A.

The conditions encountered in the CPTs and boreholes can be described as follows:

- PAVEMENT – 100 mm to 130 mm thick concrete slab;
- FILLING – sand filling with some coarse gravel to a depth of 0.4 m in BH4.
- SAND – very loose to loose sand/silty sand to depths of between 0.5 m and 5.5 m, underlain by medium dense to dense sand/clayey sand to depths of between 2.3 m to 6.4 m. A relatively thick layer of very dense sand was then encountered to depths of 13.0 m to 13.4 m, underlain by bands of loose to very dense sands and very stiff to hard clays.

Groundwater was measured at depths of between 1.2 m and 3.0 m (RL 21.9 m to RL 22.4 m AHD) at the time of the field work. The flow direction appears to be to the south/south-west.

5. Geotechnical Considerations for Redevelopment

The following comments are provided in relation to the geotechnical aspects of the proposed redevelopment project. The comments have been provided on the basis that the redevelopment will include a multi-storey building over one or more basement levels.

- Excavation for the basement will be required in filling and sands. This will be readily achievable using hydraulic excavators with bucket attachments. Rock excavation will not be required on the site.
- Shoring will be required to support the sides of the excavation. Excavation below the groundwater will probably require the use of impermeable shoring walls such as CSM walls, diaphragm walls or secant piles. If excavation is shallow then contiguous piles or steel sheet piles could be used. The dense and very dense sands may prevent the use of sheet piles below about 5 m depth due to issues associated with driving sheets in these materials.
- Temporary ground anchors will probably be required to support the shoring walls until the basement slabs have been constructed. Permission from neighbouring landowners will be required prior to installing anchors. Water-tightness issues associated with drilling anchors through an impermeable basement wall should be considered when developing the anchoring methodology.
- Groundwater currently appears to be at a depth of about 3 m below the level of Anzac Parade. The basement structure will need to be tanked to the surface (and possibly higher depending on Council flood design requirements) to prevent water ingress into the basement. Long-term pumping of groundwater from within a basement is generally not allowed in highly permeable sands.
- Dewatering will be required during construction if the excavation proceeds below the water table as expected. This will probably require spear points around the perimeter of the site and possibly some internal wells.
- Care will need to be taken to prevent groundwater drawdown on adjacent sites. This is achieved by using a properly designed dewatering system, ensuring that shoring walls are founded at an appropriate depth, and the monitoring of groundwater levels outside the site during pumping.
- Assuming two basement levels are proposed, the building could be supported by a raft slab founded in the very dense sands encountered on the site. If fewer basement levels are proposed then the building may have to be supported by piles founded in the very dense sand layer.

Additional geotechnical investigation is likely to be required on the site as part of the detailed design process. The type and amount of investigation will depend on the type of shoring/basement walls and piles/raft slab selected for the project.

6. Limitations

Douglas Partners (DP) has prepared this report for this project at 137 – 151 Anzac Parade, Kensington in accordance with DP's proposal dated 15 October 2015 and acceptance received from Toga Addison Pty Limited. This report is provided for the use of Toga Addison Developments Pty Limited for this project only and for the purposes as described in the report. It should not be relied upon for other projects or by a third party. In preparing this report DP has necessarily relied upon information provided by the client and/or their agents.

The results provided in the report are indicative of the sub-surface conditions on the site only at the specific sampling locations, only to the depths investigated and only at the time the work was carried out. Sub-surface conditions can change abruptly due to variable geological processes and also as a result of human influences. Such changes may occur after DP's field testing has been completed.

This report must be read in conjunction with all of the attached and should be kept in its entirety without separation of individual pages or sections. DP cannot be held responsible for interpretations or conclusions made by others unless they are supported by an expressed statement, interpretation, outcome or conclusion stated in this report.

Yours faithfully
Douglas Partners Pty Ltd



Peter Oitmaa
Senior Associate

Reviewed by



Michael J Thom
Principal

Attachments: A: Notes About this Report
 B: Drawing
 C: Field Work Results

Attachment A

Notes About this Report

About this Report

Douglas Partners



Introduction

These notes have been provided to amplify DP's report in regard to classification methods, field procedures and the comments section. Not all are necessarily relevant to all reports.

DP's reports are based on information gained from limited subsurface excavations and sampling, supplemented by knowledge of local geology and experience. For this reason, they must be regarded as interpretive rather than factual documents, limited to some extent by the scope of information on which they rely.

Copyright

This report is the property of Douglas Partners Pty Ltd. The report may only be used for the purpose for which it was commissioned and in accordance with the Conditions of Engagement for the commission supplied at the time of proposal. Unauthorised use of this report in any form whatsoever is prohibited.

Borehole and Test Pit Logs

The borehole and test pit logs presented in this report are an engineering and/or geological interpretation of the subsurface conditions, and their reliability will depend to some extent on frequency of sampling and the method of drilling or excavation. Ideally, continuous undisturbed sampling or core drilling will provide the most reliable assessment, but this is not always practicable or possible to justify on economic grounds. In any case the boreholes and test pits represent only a very small sample of the total subsurface profile.

Interpretation of the information and its application to design and construction should therefore take into account the spacing of boreholes or pits, the frequency of sampling, and the possibility of other than 'straight line' variations between the test locations.

Groundwater

Where groundwater levels are measured in boreholes there are several potential problems, namely:

- In low permeability soils groundwater may enter the hole very slowly or perhaps not at all during the time the hole is left open;

- A localised, perched water table may lead to an erroneous indication of the true water table;
- Water table levels will vary from time to time with seasons or recent weather changes. They may not be the same at the time of construction as are indicated in the report; and
- The use of water or mud as a drilling fluid will mask any groundwater inflow. Water has to be blown out of the hole and drilling mud must first be washed out of the hole if water measurements are to be made.

More reliable measurements can be made by installing standpipes which are read at intervals over several days, or perhaps weeks for low permeability soils. Piezometers, sealed in a particular stratum, may be advisable in low permeability soils or where there may be interference from a perched water table.

Reports

The report has been prepared by qualified personnel, is based on the information obtained from field and laboratory testing, and has been undertaken to current engineering standards of interpretation and analysis. Where the report has been prepared for a specific design proposal, the information and interpretation may not be relevant if the design proposal is changed. If this happens, DP will be pleased to review the report and the sufficiency of the investigation work.

Every care is taken with the report as it relates to interpretation of subsurface conditions, discussion of geotechnical and environmental aspects, and recommendations or suggestions for design and construction. However, DP cannot always anticipate or assume responsibility for:

- Unexpected variations in ground conditions. The potential for this will depend partly on borehole or pit spacing and sampling frequency;
- Changes in policy or interpretations of policy by statutory authorities; or
- The actions of contractors responding to commercial pressures.

If these occur, DP will be pleased to assist with investigations or advice to resolve the matter.

About this Report

Site Anomalies

In the event that conditions encountered on site during construction appear to vary from those which were expected from the information contained in the report, DP requests that it be immediately notified. Most problems are much more readily resolved when conditions are exposed rather than at some later stage, well after the event.

Information for Contractual Purposes

Where information obtained from this report is provided for tendering purposes, it is recommended that all information, including the written report and discussion, be made available. In circumstances where the discussion or comments section is not relevant to the contractual situation, it may be appropriate to prepare a specially edited document. DP would be pleased to assist in this regard and/or to make additional report copies available for contract purposes at a nominal charge.

Site Inspection

The company will always be pleased to provide engineering inspection services for geotechnical and environmental aspects of work to which this report is related. This could range from a site visit to confirm that conditions exposed are as expected, to full time engineering presence on site.



Sampling

Sampling is carried out during drilling or test pitting to allow engineering examination (and laboratory testing where required) of the soil or rock.

Disturbed samples taken during drilling provide information on colour, type, inclusions and, depending upon the degree of disturbance, some information on strength and structure.

Undisturbed samples are taken by pushing a thin-walled sample tube into the soil and withdrawing it to obtain a sample of the soil in a relatively undisturbed state. Such samples yield information on structure and strength, and are necessary for laboratory determination of shear strength and compressibility. Undisturbed sampling is generally effective only in cohesive soils.

Test Pits

Test pits are usually excavated with a backhoe or an excavator, allowing close examination of the in-situ soil if it is safe to enter into the pit. The depth of excavation is limited to about 3 m for a backhoe and up to 6 m for a large excavator. A potential disadvantage of this investigation method is the larger area of disturbance to the site.

Large Diameter Augers

Boreholes can be drilled using a rotating plate or short spiral auger, generally 300 mm or larger in diameter commonly mounted on a standard piling rig. The cuttings are returned to the surface at intervals (generally not more than 0.5 m) and are disturbed but usually unchanged in moisture content. Identification of soil strata is generally much more reliable than with continuous spiral flight augers, and is usually supplemented by occasional undisturbed tube samples.

Continuous Spiral Flight Augers

The borehole is advanced using 90-115 mm diameter continuous spiral flight augers which are withdrawn at intervals to allow sampling or in-situ testing. This is a relatively economical means of drilling in clays and sands above the water table. Samples are returned to the surface, or may be collected after withdrawal of the auger flights, but they are disturbed and may be mixed with soils from the sides of the hole. Information from the drilling (as distinct from specific sampling by SPTs or undisturbed samples) is of relatively low

reliability, due to the remoulding, possible mixing or softening of samples by groundwater.

Non-core Rotary Drilling

The borehole is advanced using a rotary bit, with water or drilling mud being pumped down the drill rods and returned up the annulus, carrying the drill cuttings. Only major changes in stratification can be determined from the cuttings, together with some information from the rate of penetration. Where drilling mud is used this can mask the cuttings and reliable identification is only possible from separate sampling such as SPTs.

Continuous Core Drilling

A continuous core sample can be obtained using a diamond tipped core barrel, usually with a 50 mm internal diameter. Provided full core recovery is achieved (which is not always possible in weak rocks and granular soils), this technique provides a very reliable method of investigation.

Standard Penetration Tests

Standard penetration tests (SPT) are used as a means of estimating the density or strength of soils and also of obtaining a relatively undisturbed sample. The test procedure is described in Australian Standard 1289, Methods of Testing Soils for Engineering Purposes - Test 6.3.1.

The test is carried out in a borehole by driving a 50 mm diameter split sample tube under the impact of a 63 kg hammer with a free fall of 760 mm. It is normal for the tube to be driven in three successive 150 mm increments and the 'N' value is taken as the number of blows for the last 300 mm. In dense sands, very hard clays or weak rock, the full 450 mm penetration may not be practicable and the test is discontinued.

The test results are reported in the following form.

- In the case where full penetration is obtained with successive blow counts for each 150 mm of, say, 4, 6 and 7 as:
4,6,7
N=13
- In the case where the test is discontinued before the full penetration depth, say after 15 blows for the first 150 mm and 30 blows for the next 40 mm as:
15, 30/40 mm

Sampling Methods

The results of the SPT tests can be related empirically to the engineering properties of the soils.

Dynamic Cone Penetrometer Tests / Perth Sand Penetrometer Tests

Dynamic penetrometer tests (DCP or PSP) are carried out by driving a steel rod into the ground using a standard weight of hammer falling a specified distance. As the rod penetrates the soil the number of blows required to penetrate each successive 150 mm depth are recorded. Normally there is a depth limitation of 1.2 m, but this may be extended in certain conditions by the use of extension rods. Two types of penetrometer are commonly used.

- Perth sand penetrometer - a 16 mm diameter flat ended rod is driven using a 9 kg hammer dropping 600 mm (AS 1289, Test 6.3.3). This test was developed for testing the density of sands and is mainly used in granular soils and filling.
- Cone penetrometer - a 16 mm diameter rod with a 20 mm diameter cone end is driven using a 9 kg hammer dropping 510 mm (AS 1289, Test 6.3.2). This test was developed initially for pavement subgrade investigations, and correlations of the test results with California Bearing Ratio have been published by various road authorities.



Description and Classification Methods

The methods of description and classification of soils and rocks used in this report are based on Australian Standard AS 1726, Geotechnical Site Investigations Code. In general, the descriptions include strength or density, colour, structure, soil or rock type and inclusions.

Soil Types

Soil types are described according to the predominant particle size, qualified by the grading of other particles present:

Type	Particle size (mm)
Boulder	>200
Cobble	63 - 200
Gravel	2.36 - 63
Sand	0.075 - 2.36
Silt	0.002 - 0.075
Clay	<0.002

The sand and gravel sizes can be further subdivided as follows:

Type	Particle size (mm)
Coarse gravel	20 - 63
Medium gravel	6 - 20
Fine gravel	2.36 - 6
Coarse sand	0.6 - 2.36
Medium sand	0.2 - 0.6
Fine sand	0.075 - 0.2

The proportions of secondary constituents of soils are described as:

Term	Proportion	Example
And	Specify	Clay (60%) and Sand (40%)
Adjective	20 - 35%	Sandy Clay
Slightly	12 - 20%	Slightly Sandy Clay
With some	5 - 12%	Clay with some sand
With a trace of	0 - 5%	Clay with a trace of sand

Definitions of grading terms used are:

- Well graded - a good representation of all particle sizes
- Poorly graded - an excess or deficiency of particular sizes within the specified range
- Uniformly graded - an excess of a particular particle size
- Gap graded - a deficiency of a particular particle size with the range

Cohesive Soils

Cohesive soils, such as clays, are classified on the basis of undrained shear strength. The strength may be measured by laboratory testing, or estimated by field tests or engineering examination. The strength terms are defined as follows:

Description	Abbreviation	Undrained shear strength (kPa)
Very soft	vs	<12
Soft	s	12 - 25
Firm	f	25 - 50
Stiff	st	50 - 100
Very stiff	vst	100 - 200
Hard	h	>200

Cohesionless Soils

Cohesionless soils, such as clean sands, are classified on the basis of relative density, generally from the results of standard penetration tests (SPT), cone penetration tests (CPT) or dynamic penetrometers (PSP). The relative density terms are given below:

Relative Density	Abbreviation	SPT N value	CPT qc value (MPa)
Very loose	vl	<4	<2
Loose	l	4 - 10	2 - 5
Medium dense	md	10 - 30	5 - 15
Dense	d	30 - 50	15 - 25
Very dense	vd	>50	>25

Soil Descriptions

Soil Origin

It is often difficult to accurately determine the origin of a soil. Soils can generally be classified as:

- Residual soil - derived from in-situ weathering of the underlying rock;
- Transported soils - formed somewhere else and transported by nature to the site; or
- Filling - moved by man.

Transported soils may be further subdivided into:

- Alluvium - river deposits
- Lacustrine - lake deposits
- Aeolian - wind deposits
- Littoral - beach deposits
- Estuarine - tidal river deposits
- Talus - scree or coarse colluvium
- Slopewash or Colluvium - transported downslope by gravity assisted by water. Often includes angular rock fragments and boulders.

Cone Penetration Tests Douglas Partners



Introduction

The Cone Penetration Test (CPT) is a sophisticated soil profiling test carried out in-situ. A special cone shaped probe is used which is connected to a digital data acquisition system. The cone and adjoining sleeve section contain a series of strain gauges and other transducers which continuously monitor and record various soil parameters as the cone penetrates the soils.

The soil parameters measured depend on the type of cone being used, however they always include the following basic measurements

- Cone tip resistance q_c
- Sleeve friction f_s
- Inclination (from vertical) i
- Depth below ground z




Figure 1: Cone Diagram

The inclinometer in the cone enables the verticality of the test to be confirmed and, if required, the vertical depth can be corrected.

The cone is thrust into the ground at a steady rate of about 20 mm/sec, usually using the hydraulic rams of a purpose built CPT rig, or a drilling rig. The testing is carried out in accordance with the Australian Standard AS1289 Test 6.5.1.



Figure 2: Purpose built CPT rig

The CPT can penetrate most soil types and is particularly suited to alluvial soils, being able to detect fine layering and strength variations. With sufficient thrust the cone can often penetrate a short distance into weathered rock. The cone will usually reach refusal in coarse filling, medium to coarse gravel and on very low strength or better rock. Tests have been successfully completed to more than 60 m.

Types of CPTs

Douglas Partners (and its subsidiary GroundTest) owns and operates the following types of CPT cones:

Type	Measures
Standard	Basic parameters (q_c , f_s , i & z)
Piezocone	Dynamic pore pressure (u) plus basic parameters. Dissipation tests estimate consolidation parameters
Conductivity	Bulk soil electrical conductivity (σ) plus basic parameters
Seismic	Shear wave velocity (V_s), compression wave velocity (V_p), plus basic parameters

Strata Interpretation

The CPT parameters can be used to infer the Soil Behaviour Type (SBT), based on normalised values of cone resistance (Q_t) and friction ratio (F_r). These are used in conjunction with soil classification charts, such as the one below (after Robertson 1990)

Cone Penetration Tests




Figure 3: Soil Classification Chart

DP's in-house CPT software provides computer aided interpretation of soil strata, generating soil descriptions and strengths for each layer. The software can also produce plots of estimated soil parameters, including modulus, friction angle, relative density, shear strength and over consolidation ratio.

DP's CPT software helps our engineers quickly evaluate the critical soil layers and then focus on developing practical solutions for the client's project.

Engineering Applications

There are many uses for CPT data. The main applications are briefly introduced below:

Settlement

CPT provides a continuous profile of soil type and strength, providing an excellent basis for settlement analysis. Soil compressibility can be estimated from cone derived moduli, or known consolidation parameters for the critical layers (eg. from laboratory testing). Further, if pore pressure dissipation tests are undertaken using a piezocone, in-situ consolidation coefficients can be estimated to aid analysis.

Pile Capacity

The cone is, in effect, a small scale pile and, therefore, ideal for direct estimation of pile capacity. DP's in-house program ConePile can analyse most pile types and produces pile capacity versus depth plots. The analysis methods are based on proven static theory and empirical studies, taking account of scale effects, pile materials and method of installation. The results are expressed in limit state format, consistent with the Piling Code AS2159.

Dynamic or Earthquake Analysis

CPT and, in particular, Seismic CPT are suitable for dynamic foundation studies and earthquake response analyses, by profiling the low strain shear modulus G_0 . Techniques have also been developed relating CPT results to the risk of soil liquefaction.

Other Applications

Other applications of CPT include ground improvement monitoring (testing before and after works), salinity and contaminant plume mapping (conductivity cone), preloading studies and verification of strength gain.




Figure 4: Sample Cone Plot

Attachment B

Drawing



- Cone Penetration Test
- Borehole/Groundwater Monitoring Well

- Existing Groundwater Monitoring Well



CLIENT: Toga Addison Pty Limited	
OFFICE: Sydney	DRAWN BY: PMO
SCALE: NTS	DATE: 16 Dec 2015

TITLE: **Locations of Tests**
137 - 155 Anzac Parade
KENSINGTON

PROJECT No:	85151.00
DRAWING No:	1
REVISION:	B

Attachment C

Field Work Results

CONE PENETRATION TEST

CLIENT: TOGA ADDISON DEVELOPMENTS PTY LIMITED

PROJECT: DUE DILIGENCE ASSESSMENT

LOCATION: 137-155 ANZAC PARADE, KENSINGTON

REDUCED LEVEL: 25.2


COORDINATES: 335713E 6246336N

CPT1

Page 1 of 1

DATE 20/10/2015

PROJECT No: 85151



REMARKS: CONCRETE SURFACE SLAB CORED TO 0.1 m DEPTH PRIOR TO TESTING.
GROUNDWATER OBSERVED AT 3.0 m DEPTH AFTER WITHDRAWAL OF RODS.

Water depth after test: 3.00m depth (assumed)

File: P:\85151.00 - KENSINGTON 137 - 155 Anzac Pde\4.0 Field Work\85151 KENSINGTON CPTs\CPT1.CP5
Cone ID: 120631 Type: I-CFYX-10

ConePlot Version 5.9.2
© 2003 Douglas Partners Pty Ltd

CONE PENETRATION TEST

CLIENT: TOGA ADDISON DEVELOPMENTS PTY LIMITED

PROJECT: DUE DILIGENCE ASSESSMENT

LOCATION: 137-155 ANZAC PARADE, KENSINGTON

REDUCED LEVEL: 24.9


COORDINATES: 335680E 6246298N

CPT2

Page 1 of 1

DATE 20/10/2015

PROJECT No: 85151



REMARKS: DUMMY CONE USED FROM 0.0 m TO 0.2 m DEPTH TO PENETRATE CONCRETE SURFACE SLAB PRIOR TO TESTING; HOLE DISCONTINUED DUE TO TRUCK LIFTING UNSAFELY. GROUNDWATER OBSERVED AT 3.0 m DEPTH AFTER WITHDRAWAL OF RODS.

Water depth after test: 3.00m depth (assumed)

File: P:85151.00 - KENSINGTON 137 - 155 Anzac Pde\4.0 Field Work\85151 KENSINGTON CPTs\CPT2.CP5

Cone ID: 120631 Type: I-CFXY-10

ConePlot Version 5.9.2

© 2003 Douglas Partners Pty Ltd

CONE PENETRATION TEST

CLIENT: TOGA ADDISON DEVELOPMENTS PTY LIMITED

PROJECT: DUE DILIGENCE ASSESSMENT

LOCATION: 137-155 ANZAC PARADE, KENSINGTON

REDUCED LEVEL: 23.5


COORDINATES: 335670E 6246262N

CPT3

Page 1 of 1

DATE 20/10/2015

PROJECT No: 85151



REMARKS: CONCRETE SURFACE SLAB CORED TO 0.13 m DEPTH PRIOR TO TESTING.
GROUNDWATER OBSERVED AT 1.2 m DEPTH AFTER WITHDRAWAL OF RODS.

Water depth after test: 1.20m depth (assumed)

File: P:185151.00 - KENSINGTON 137 - 155 Anzac Pde\4.0 Field Work\85151 KENSINGTON CPT3\CPT3.CP5
Cone ID: 120631 Type: I-CFXY-10

ConePlot Version 5.9.2
© 2003 Douglas Partners Pty Ltd

BOREHOLE LOG

CLIENT: Toga Addison Developments Pty Limited
PROJECT: Due Dilligence Assessment
LOCATION: 137-155 Anzac Parade, Kensington

SURFACE LEVEL: 25.3 AHD
EASTING: 335682
NORTHING: 6246339
DIP/AZIMUTH: 90°/--

BORE No: BH4
PROJECT No: 85151
DATE: 20/10/2015
SHEET 1 OF 1

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Well Construction Details	
				Type	Depth	Sample	Results & Comments			
25.3	0.1	CONCRETE SLAB - 0.1m thick	[Cross-hatched pattern]							
	0.4	FILLING - grey-brown sand with some coarse gravel, moist	[Dotted pattern]							
		SAND - yellow, fine to medium sand, moist	[Dotted pattern]	A/E	1.0					
			[Dotted pattern]	A/E	2.0					
	2.3	SILTY SAND - dark brown with grey mottling, fine to medium grained silty sand, wet (organic odour)	[Vertical dashed lines]	A/E	3.0			▼		
	3.2	SAND - yellow, fine to medium grained sand, saturated	[Dotted pattern]							
	3.5	SILTY SAND - brown, silty sand, saturated	[Vertical dashed lines]	A/E	4.0					
	4.4	SAND - yellow, fine to medium grained sand, saturated	[Dotted pattern]	A/E	5.0					
	6.0	Bore discontinued at 6.0m								

RIG: DT250

DRILLER: SY

LOGGED: CG

CASING: Uncased

TYPE OF BORING: Free groundwater observed at 2.9m during drilling

WATER OBSERVATIONS: Groundwater well installed to 5.9m (screened 0.4-5.9m)

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	>	Water seep
E	Environmental sample	≡	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test Is(50) (MPa)
		PL(D)	Point load diametral test Is(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)

BOREHOLE LOG

CLIENT: Toga Addison Developments Pty Limited
PROJECT: Due Dilligence Assessment
LOCATION: 137-155 Anzac Parade, Kensington

SURFACE LEVEL: 23.5 AHD
EASTING: 335670
NORTHING: 6246260
DIP/AZIMUTH: 90°/--

BORE No: BH5
PROJECT No: 85151
DATE: 20/10/2015
SHEET 1 OF 1

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Well Construction Details	
				Type	Depth	Sample	Results & Comments			
23.5	0.13	CONCRETE SLAB - 0.13m thick	▲							
23.0		SAND - grey, fine to medium grained sand, moist	●							
22.5		0.7m: brown mottling	●							
22.0	1.1	SAND - brown, fine to medium grained sand, moist	●	A/E	1.0			▼		
21.5		1.3m: becoming wet	●							
21.0		1.5m: becoming saturated	●							
20.5	2.0		●	A/E	2.0					
20.0	2.7	SAND - yellow-brown, fine to medium grained sand, saturated	●	A/E	3.0					
19.5	3.0		●							
19.0	4.0		●	A/E	4.0					
18.5	4.2	SAND - yellow, fine to medium grained sand, saturated	●							
18.0	5.0		●							
17.5	5.5		●	A/E/S	5.5		pp = 250 18,25/100mm refusal			
17.0	6.0		●							
16.5	7.0	Bore discontinued at 7.0m	●	A/E/S	7.0		pp = 230 27,25/80mm refusal			
16.0	8.0		●							
15.5	9.0		●							

RIG: DT250

DRILLER: SY

LOGGED: CG

CASING: Uncased

TYPE OF BORING: Free groundwater observed at 1.5m during drilling

WATER OBSERVATIONS: Groundwater well installed to 6.0m (screened 1.0-6.0m)

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	▷	Water seep
E	Environmental sample	≡	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test Is(50) (MPa)
		PL(D)	Point load diametral test Is(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)