

22 April 2024

Our Reference: 24-0142

Sydney Water Corporation
1 Smith Street
Parramatta NSW 2150


To whom it may concern,

RE: Feasibility Application for a Large Lot residential development in The Oaks CN 214636

This feasibility application is being lodged for the developer (Proficient Constructions (Aust) Pty Ltd) to receive guidance from Sydney Water regarding the potable water and wastewater servicing conditions for the proposed 9 large lot development of the following site:

- 80 Silverdale Road, The Oaks, Lot 3 DP1201486

The existing development is rural land. The proposed development is a large lot residential subdivision, see below (in Appendix A is a copy of the draft civil plans for the site):



The client is asking for the following to be addressed as part of the feasibility letter:

Wastewater Servicing

Can Sydney Water please advise on the following:

- Would SWC accept servicing the large lots with a combination of gravity and LPSS (majority LPSS pending levels), refer to Appendix B for markup

- If there are any issues with capacity in the receiving system, please state where and of what nature the capacity issues are


Potable Water Servicing

Can Sydney Water please advise on the following:

- The solution for PW servicing would be to extend a DN100 main along the proposed road (see markup in Appendix B), would that be acceptable to SWC?
- If there are any issues with capacity, please state where and of what nature the capacity issues are

If there are any questions or if any further information is required, please do not hesitate to contact the undersigned.

Yours faithfully



Orion Group

Technical Director - Water Servicing – Florian Jaehne


E: f.jaehne@theoriongroup.au

P: 0498 493 479

Appendix A – Draft Civil Design Plans

PROPOSED RESIDENTIAL SUBDIVISION
LOT 3 DP 1201486, 80 SILVERDALE ROAD, THE OAKS
DEVELOPMENT APPLICATION CIVIL PLANS
MR & MRS NOCERA C/-
PROFICIENT CONSTRUCTIONS (AUST) PTY LTD

Sheet List Table	
Sheet Number	Sheet Title
01	TITLE PAGE
02	CIVIL WORKS PLAN
03	BULK EARTHWORKS
04	ROAD LONG SECTIONS
05	INTERSECTION PLAN
06	ROAD TYPICAL SECTIONS
07	CATCHMENT PLAN
08	DRAINAGE CALCULATIONS
09	DRAINAGE LONG SECTIONS
10	MUSIC CATCHMENT PLAN
11	INTERSECTION SIGHT DISTANCE
12	INTERSECTION SWEEP PATHS
13	SOIL & WATER MANAGEMENT PLAN
14	SOIL & WATER MANAGEMENT DETAILS



LOCALITY SKETCH
1:2500 @ A1

LEGEND PROPOSED			LEGEND EXISTING		
	STORMWATER PIPE	+ 10.00		STORMWATER LINE	+10.00
	GRATED PIT		CONTOURS		EXISTING SPOT LEVEL
	JUNCTION PIT		CATCHMENT BOUNDARY		EXISTING CONTOURS
	KERB INLET PIT		EDGE STRIP		GAS LINE
	SEDIMENT FENCE		KERB & GUTTER		ELECTRICAL LINE
	SEDIMENT TRAP		RETAINING WALL		
	TEMPORARY CONSTRUCTION EXIT		SUBSOIL DRAINAGE		
	RAINWATER TANK		SWALE WITH INFILTRATION TRENCH		
			ROADSIDE GUARD RAIL		

SERVICES ARE SHOWN INDICATIVE ONLY. CONTRACTOR TO CONFIRM ALL SERVICE LOCATIONS PRIOR TO CONSTRUCTION

DIMENSIONS SHALL NOT BE OBTAINED BY SCALING FROM THIS SET OF PLANS

GENERAL NOTES

- G1. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH WOLLONDILLY SHIRE COUNCIL DEVELOPMENT CODE AND TO THE REQUIREMENTS OF COUNCIL'S AUTHORISED OFFICER.
- G2. INSPECTIONS BY THE AUTHORISED OFFICER SHALL BE CARRIED OUT AT THE FOLLOWING STAGES:
- (a) PRIOR TO INSTALLATION OF EROSION AND SEDIMENT CONTROL STRUCTURES
 - (b) PRIOR TO BACKFILLING PIPELINES, SUBSOIL DRAINS, TRENCH BEDDING AND DAMS
 - (c) PRIOR TO CASTING OF PITS AND OTHER CONCRETE STRUCTURES, INCLUDING KERB AND GUTTER
 - (d) PROOF-ROLLER TEST OF SUBGRADE AND SUB-BASE
 - (e) ROLLER TEST OF COMPLETED PAVEMENT PRIOR TO PLACEMENT OF WEARING COURSE
 - (f) FORMWORKS PRIOR TO POURING CONCRETE IN PARKING AREA FOR FOOTPATH CROSSING AND OTHER ASSOCIATED WORK
 - (g) PRIOR TO BACKFILLING PUBLIC UTILITY CROSSINGS IN ROAD RESERVES
 - (h) PRIOR TO PLACEMENT OF ASPHALTIC CONCRETE
 - (i) FINAL INSPECTION AFTER ALL WORKS ARE COMPLETED AND 'WORKS AS EXECUTED' PLANS HAVE BEEN SUBMITTED TO COUNCIL
- G3. NO TREES TO BE REMOVED UNLESS APPROVAL IS GRANTED BY COUNCIL.
- G4. MAKE SMOOTH JUNCTIONS WITH EXISTING WORKS.
- G5. NO WORK TO BE CARRIED OUT ON COUNCIL PROPERTY OR ADJOINING PROPERTIES WITHOUT THE WRITTEN PERMISSION FROM THE OWNER.
- G6. VEHICULAR ACCESS AND ALL SERVICES TO BE MAINTAINED AT ALL TIMES TO ADJOINING PROPERTIES AFFECTED BY CONSTRUCTION.
- G7. ALL RUBBISH, BUILDINGS, SHEDS AND FENCES TO BE REMOVED TO SATISFACTION OF COUNCIL'S ENGINEER AT COMPLETION OF WORKS.
- G8. A TRAFFIC CONTROL PLAN IS TO BE SUBMITTED TO COUNCIL WITH A SECTION 138 APPLICATION PRIOR TO COMMENCEMENT OF WORKS.
- G9. ALL FILL AREAS ARE TO BE INSPECTED BY A GEOTECHNICAL ENGINEER PRIOR TO STRIPPING AND ANY RECOMMENDATIONS REGARDING TREATMENT OF SALINE AFFECTATION ARE TO BE IMPLEMENTED.
- G10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE VERIFICATION OF THE LOCATION OF ANY EXISTING SERVICES AFFECTING THE WORKS AREA, ANY DAMAGED SERVICES SHALL BE REPAIRED AT THE CONTRACTORS COST.

EARTHWORKS NOTES

- E1. EARTHWORKS TO BE CARRIED OUT TO THE SATISFACTION OF THE PCA AND GEOTECHNICAL ENGINEER. UNSOUND MATERIALS ARE TO BE REMOVED FROM ROADS AND LOTS PRIOR TO FILLING. THE CONTRACTOR IS TO ARRANGE AND MAKE AVAILABLE COMPACTION CERTIFICATES WHERE REQUIRED.
- E2. WHERE THE SLOPE OF THE NATURAL SURFACE EXCEEDS ONE IN FOUR (1:4), BENCHES ARE TO BE CUT TO PREVENT SLIPPING OF THE PLACED FILL MATERIAL AS REQUIRED BY THE PCA AND GEOTECHNICAL ENGINEER.
- E3. ALL BATTERS ARE TO BE SCARIFIED TO ASSIST WITH ADHESION OF TOP SOIL TO BATTER FACE.
- E4. PROVIDE MINIMUM 150mm AND MAXIMUM 300mm TOPSOIL WITH GRASS SEEDING ON FOOTPATHS, FILLED AREAS AND ALL OTHER AREAS DISTURBED DURING CONSTRUCTION.
- E5. THE CONTROL TESTING OF EARTHWORKS SHALL BE IN ACCORDANCE WITH THE GUIDELINES IN AUSTRALIAN STANDARD 3798 - 2007. WHERE IT IS PROPOSED TO USE TEST METHOD AS1289 E8.1 OR AS1289 E8.2 TO DETERMINE THE FIELD DENSITY, A SAND REPLACEMENT METHOD SHALL BE USED TO CONFIRM THE RESULTS AS DIRECTED BY COUNCIL. THE GEOTECHNICAL TESTING AUTHORITY SHALL HAVE A LEVEL 1 RESPONSIBILITY FOR ALL FILLING AS DEFINED IN APPENDIX B AS 3798-2007, AND AT THE END OF THE WORKS SHALL CONFIRM THE EARTHWORKS COMPLY WITH THE REQUIREMENTS OF THE SPECIFICATION AND DRAWINGS.
- E6. THE CONTRACTOR SHALL CONTROL SEDIMENTATION, EROSION AND POLLUTION DURING CONSTRUCTION IN ACCORDANCE WITH MANAGING URBAN STORMWATER: SOILS AND CONSTRUCTION VOLUME 1 (LANDCOM 2004) AND MANAGING URBAN STORMWATER: SOILS AND CONSTRUCTION VOLUME 2 (DEPARTMENT OF ENVIRONMENT AND CLIMATE CHANGE 2007).

ROADWORKS NOTES

- R1. SUBGRADE, SUB-BASE, AND BASE TO BE COMPACTED IN ACCORDANCE WITH WOLLONDILLY SHIRE COUNCILS DEVELOPMENT CODE.
- R2. SUBSOIL DRAINS TO BE PROVIDED ON BOTH SIDES OF ROADS (EXCEPT WHERE THERE IS STORM WATER DRAINAGE).
- R3. 150 X 50 H.D. GALVANISED STEEL KERB OUTLETS TO BE PLACED IN LAYBACK KERB AND 90mm DIA. GALVANISED STEEL PIPE SECTION TO BE PLACED IN UPRIGHT KERB ON LOW SIDE OF LOTS. PROVIDE SUITABLE ADAPTOR TO ALLOW CONNECTION OF 90mm DIA. STORM WATER PIPE.
- R4. PERAMBULATOR CROSSINGS TO BE PROVIDED IN ALL KERB RETURNS OR WHERE REQUIRED BY COUNCIL.
- R5. SERVICE CONDUITS TO BE PLACED AS DIRECTED BY ENDEAVOUR ENERGY, TELECOMMUNICATIONS AND AS REQUIRED BY THE SYDNEY WATER.
- R6. PROPOSED SERVICES CROSSING EXISTING ROADS SHALL BE THRUST BORED UNDER THE ROAD SO AS NOT TO DAMAGE EXISTING SURFACE.
- R7. SIGNPOSTING AND LINEMARKING TO CONFORM WITH AS1742.2 RAISED RETRO- REFLECTIVE PAVEMENT MARKERS TO CONFORM WITH AS1906.
- R8. STREET SIGNS TO COMPLY WITH COUNCIL'S SPECIFICATION FOR STREET NAME SIGNS AND MUST BE INSTALLED BY THE DEVELOPER.
- R9. ALL LEVELS ARE TO BE SET OUT FROM ESTABLISHED STATE SURVEY MARKS.

STORMWATER NOTES



- S1. ALL PIPES TO BE SPIGOT AND SOCKET, RUBBER RING JOINTED. ALL PIPES IN ROAD RESERVES (OTHER THAN ROOF WATER AND SUBSOIL) ARE TO BE STEEL REINFORCED CONCRETE PIPES.
- S2. ALL LONGITUDINAL PIPELINES IN ROADS MUST BE LOCATED UNDER KERB AND GUTTER AND BE BACKFILLED WITH 7mm AGGREGATE WHERE 10-15% OF FINES IS ALLOWABLE UNLESS OTHERWISE INDICATED ON PLANS AND APPROVED BY COUNCIL.
- S3. DRAINAGE LINES MUST BE BACKFILLED AS PER WOLLONDILLY SHIRE COUNCILS DEVELOPMENT CODE. THREE (3) METRES OF AGLINE WRAPPED IN GEOTECH STOCKING MUST BE PROVIDED TO ALL DOWNSTREAM PITS.
- S4. ALL GULLY PITS TO COUNCIL'S STANDARD AND LINTELS CENTRALLY PLACED AT SAG PITS.
- S5. ALL PITS MUST BE BENCHED AND STREAMLINED. PROVIDE SL72 REINFORCEMENT AND STEP IRONS IN ALL PITS OVER 12M DEEP.
- S6. CONCRETE TO HAVE MINIMUM COMPRESSIVE STRENGTH OF 25 MPA AT 28 DAYS UNLESS SPECIFIED OTHERWISE BY COUNCIL ENGINEER.
- S7. ALL INTER ALLOTMENT DRAINAGE MUST HAVE A MINIMUM COVER OF 300mm TO THE TOP OF PIPE UNLESS OTHERWISE APPROVED BY THE COUNCIL ENGINEER.
- S8. CATCH DRAINS MUST BE CONSTRUCTED AS PER SWMP.
- S9. ALL COMMON DRAINAGE LINES MUST BE LAID CENTRALLY WITHIN 12m-30m EASEMENTS. CLEANING EYES MUST BE PROVIDED IMMEDIATELY DOWNSTREAM OF ALL SLOPE JUNCTIONS.
- S10. ONE HUNDRED (100) YEAR OVERLAND FLOW PATHS MUST BE FORMED AND SHOWN ON WORK AS EXECUTED DRAWINGS.
- S11. ADEQUATE PROVISION TO BE MADE FOR SCOURING AND SEDIMENTATION TO ALL DRAINAGE WORKS IN ACCORDANCE WITH WOLLONDILLY SHIRE COUNCILS DEVELOPMENT CODE.
- S12. COMMON DRAINAGE LINES MUST BE INSTALLED AFTER SEWERAGE LINES HAVE BEEN INSTALLED WHERE SEWER IS PROPOSED ADJACENT TO INTER ALLOTMENT

GEOTECHNICAL NOTES

- G1. THE CONTRACTOR SHALL IMPLEMENT EROSION AND SEDIMENT CONTROL MEASURES AS NECESSARY, AND TO THE SATISFACTION OF COUNCIL PRIOR TO THE COMMENCEMENT OF CONSTRUCTION AND DURING CONSTRUCTION SEE SWMP.
- G2. TESTS SHALL BE UNDERTAKEN ON ANY PROPOSED FILL MATERIALS TO ENSURE THAT THEY DO NOT HAVE A HIGH DISPERSION POTENTIAL AS DEFINED BY EMERSON CRUMB/DISPERSION TESTS (AS1289 (8-1980))
- G3. ALL FILLING AND PAVEMENT CONSTRUCTION MUST BE UNDERTAKEN TO THE REQUIREMENTS OF AS3798-2007 THE FOLLOWING COMPACTION LEVELS ARE RECOMMENDED:
- | | | |
|----------------|------|----------|
| LOT FILLING | 98% | STANDARD |
| ROAD SUB-GRADE | 100% | STANDARD |
| ROAD SUB-BASE | 95% | MODIFIED |
| ROAD BASE | 98% | MODIFIED |
- G4. ALL TESTING WORKS SHALL BE CONTROLLED AND CERTIFIED BY A N.A.T.A REGISTERED LABORATORY. A COLLATED COPY OF ALL TEST CERTIFICATES, ACCOMPANIED BY AN OVERALL SITE PLAN, CLEARLY INDICATING THE LOCATION OF EACH TEST AND FILL AREAS ETC, AND THE LABORATORY CERTIFICATE COVERING THE WHOLE OF THE AREA TESTED ARE TO BE FORWARDED TO COUNCIL UPON COMPLETION.
- G5. FINAL PAVEMENT THICKNESS TO BE DETERMINED AFTER BOXING OUT BY JOINT INSPECTION BY N.A.T.A REGISTERED LABORATORY AND COUNCIL'S ENGINEER. PAVEMENT REPORT TO BE AVAILABLE TO COUNCIL A MINIMUM OF TWO CLEAR DAYS PRIOR TO INSPECTION.

T:\Projects\23130_80_Silverdale Road_The Oaks\Drawg\DA\23130_Plans.dwg

REVISIONS	No.	DESCRIPTION	DRN	APP	DATE	 Site Plus Pty Ltd ABN 73 104 315 095 engineering landscape design flooding management				Height Datum	A.H.D	Client Title	MR & MRS NOCERA C/- PROFICIENT CONSTRUCTIONS (AUST)		Dwg Title	PROPOSED SUBDIVISION 80 SILVERDALE ROAD, THE OAKS			Ref & Dwg No	
	A	PRELIMINARY CLIENT ISSUE	I.B.	A.C.	14.03.24					Drawn	I.B.								23130.DA.C01	
	B	REVISED EARTHWORKS	I.B.	A.C.	05.04.24					Designed	A.C.								Sheet No	
	----	----	----	----	----					Checked	A.C.								Sheet 01 of 14	
	----	----	----	----	----					Approved	A.C.								Scale	
	----	----	----	----	----					Dwg Status		Local Authority		AS NOTED @ A1						
	----	----	----	----	----					DA		WOLLONDILLY		Date						
										05.04.24		Rev	B	A1						



T:\Projects\23130 80 Silverdale Road, The Oaks\Drawings\DA\23130_Plans.dwg

No.	DESCRIPTION	DRN	APP	DATE
A	PRELIMINARY CLIENT ISSUE	I.B.	A.C.	14.03.24
B	REVISED EARTHWORKS	I.B.	A.C.	05.04.24

Site Plus Pty Ltd ABN 73 104 315 095


WOLLONGONG - HEAD OFFICE
Shop 1, 18 Arrow Avenue
Figtree NSW 2525
PO Box 506
Figtree NSW 2525
T 61 2 4227 4233
F 61 2 4227 4133
E info@siteplus.com.au

engineering landscape design flooding management



Height Datum	A.H.D	Client Title MR & MRS NOCERA C/- PROFICIENT CONSTRUCTIONS (AUST)	
Drawn	I.B.		
Designed	A.C.		
Checked	A.C.		
Approved	A.C.		

Dwg Status		DA	Local Authority
			WOLLONDILLY

Dwg Title PROPOSED SUBDIVISION 80 SILVERDALE ROAD, THE OAKS		Ref & Dwg No 23130.DA.C02	
		Sheet No 02 of 14	
		Scale 1:750 @ A1	
Date 05.04.24	Rev B	A1	



BULK EARTHWORKS PLAN
SCALE 1:750



SURFACE ELEVATION DATA			
NUMBER	MINIMUM ELEVATION	MAXIMUM ELEVATION	COLOR
1	-3.09	-2.50	
2	-2.50	-2.00	
3	-2.00	-1.50	
4	-1.50	-1.00	
5	-1.00	-0.50	
6	-0.50	0.00	
7	0.00	0.50	
8	0.50	1.00	
9	1.00	1.50	
10	1.50	1.80	

CUT/FILL SUMMARY

- CUT/FILL SUMMARY ASSUMED 200mm TOP SOIL STRIPPING PRIOR TO EXCAVATION OF CUT OR PLACEMENT OF FILL.

- NO ALLOWANCE MADE FOR UNSUITABLE MATERIAL THAT MAY BE ENCOUNTERED ON SITE.

SUMMARY

CUT=	13,981	cu.m
FILL=	17,576	cu.m
EXCAVATION OF TRENCHES=	275	cu.m
EXCAVATION OF PAVEMENT=	1957	cu.m
TOTAL IMPORT OF MATERIAL TO SITE=		
	1363	cu.m

T:\Projects\23130 80 Silverdale Road, The Oaks\Drawings\23130_Plan.dwg

REVISIONS	No.	DESCRIPTION	DRN	APP	DATE	 Site Plus Pty Ltd ABN 73 104 315 095 engineering landscape design flooding management	WOLLONGONG - HEAD OFFICE Shop 1, 18 Arrow Avenue Figtree NSW 2555 PO Box 506 Figtree NSW 2525 T 61 2 4227 4233 F 61 2 4227 4133 E info@siteplus.com.au	Height Datum	A.H.D	Client Title	MR & MRS NOCERA C/- PROFICIENT CONSTRUCTIONS (AUST)	Dwg Title	PROPOSED SUBDIVISION 80 SILVERDALE ROAD, THE OAKS BULK EARTHWORKS	Ref & Dwg No 23130.DA.C03							
	A	PRELIMINARY CLIENT ISSUE	I.B.	A.C.	14.03.24			Drawn	I.B.						Sheet No	03 of 14	Date 05.04.24	Rev B	A1		
	B	REVISED EARTHWORKS	I.B.	A.C.	05.04.24			Designed	A.C.						Scale	1:750 @ A1					
	----	----	----	----	----			Checked	A.C.						Dwg Status	DA				Local Authority	WOLLONDILLY
	----	----	----	----	----			Approved	A.C.												

REVISIONS

No.	DESCRIPTION	DRN	APP	DATE
A	PRELIMINARY CLIENT ISSUE	I.B.	A.C.	14.03.24
B	REVISED EARTHWORKS	I.B.	A.C.	05.04.24
----	----	----	----	----
----	----	----	----	----
----	----	----	----	----



Site Plus Pty Ltd ABN 73 104 315 095



engineering

landscape

design

flooding



management


WOLLONGONG - HEAD OFFICE
Shop 1, 18 Arrow Avenue
Figtree NSW 2556
PO Box 506
Figtree NSW 2525
Tel 2 4227 4233
F 61 2 4227 4133
E info@siteplus.com.au

Height Datum	A.H.D
Drawn	I.B.
Designed	A.C.
Checked	A.C.
Approved	A.C.


Client Title		MR & MRS NOCERA C/- PROFICIENT CONSTRUCTIONS (AUST)	
Dwg Status		DA	Local Authority WOLLONDILLY

Dwg Title	PROPOSED SUBDIVISION			Ref & Dwg No	23130.DA.C04
	80 SILVERDALE ROAD, THE OAKS			Sheet No	
				Sheet	04 of 14
				Scale	AS NOTED @ A1
	ROAD LONG SECTIONS			Date	05.04.24
				Rev	B A1





KERB AND GUTTER (K&G)
SCALE 1:20




EXTEND SUB BASE
BELOW & PAST KERB

20




EDGE STRIP

SCALE 1:20





PROPOSED SUBDIVISION
0 SILVERDALE ROAD, THE OAKS
ROAD TYPICAL SECTIONS

Ref & Dwg No		
23130.DA.C06		
Sheet No		
Sheet	06	of 14
Scale		
AS NOTED @ A1		
Date	Rev	
05.04.24	B	A1



HEADWALL SCOUR PROTECTION DETAIL
SCALE 1:20



PIPE OUTLET SCOUR PROTECTION DETAIL
SCALE 1:20

T:\Projects\23130 80 Silverdale Road, The Oaks\Drawings\DA\23130_Drainage.dwg

REVISIONS	No.	DESCRIPTION	DRN	APP	DATE	siteplus Site Plus Pty Ltd ABN 73 104 315 095 engineering landscape design flooding management	WOLLONGONG - HEAD OFFICE Shop 1, 18 Arrow Avenue Figtree NSW 2555 PO Box 506 Figtree NSW 2555 T 61 2 4227 4233 F 61 2 4227 4133 E info@siteplus.com.au		Height Datum	A.H.D	Client Title MR & MRS NOCERA C/- PROFICIENT CONSTRUCTIONS (AUST)	Dwg Title PROPOSED SUBDIVISION 80 SILVERDALE ROAD, THE OAKS	Ref & Dwg No 23130.DA.C07						
	A	PRELIMINARY CLIENT ISSUE	I.B.	A.C.	14.03.24		Drawn	I.B.	Sheet No	07 of 14									
	B	REVISED EARTHWORKS	I.B.	A.C.	05.04.24		Designed	A.C.	Sheet	07 of 14									
	----	----	----	----	----		Checked	A.C.	Scale	1:750 @ A1									
	----	----	----	----	----		Approved	A.C.	Dwg Status	DA			Local Authority	WOLLONDILLY	Date	05.04.24	Rev	B	A1
	----	----	----	----	----									CATCHMENT PLAN					

T: \Projects\23130 80 Silverdale Road, The Oaks\Dwg\DA\23130_Drainage.dwg


Pit Schedule - Site Drainage												
Pit No.	Pit Type	Pit Width	Pit Length	Outlet Diameter	Outlet Invert RL	Inlet Diameter	Inlet Invert RL	Pit Depth	Pit Lid Level	Easting	Northing	Comment
		(mm)	(mm)	(mm)	(m)	(mm)	(m)	(m)	(m)	(m)	(m)	
A/6	HEADWALL					600	278.273	0.948	279.221	276224.52	6227521.223	
A/5	KIP 2.4m Lintel	600	900	600	278.339	600	278.339	1.282	279.621	276218.38	6227519.980	
A/4	KIP 1.2m Lintel	600	900	600	278.552	600	278.577	1.273	279.825	276205.52	6227503.018	
A/3	KIP 2.4m Lintel	600	900	600	278.720	600	278.750	1.332	280.052	276192.60	6227501.243	
						375	278.991					
A/2	KIP 2.4m Lintel	600	900	600	279.640	600	279.674	1.322	280.962	276171.64	6227504.853	
B/1	KIP 2.4m Lintel	600	900	375	278.990			1.010	280.000	276195.11	6227513.365	
A/1	EXISTING PIT			600	280.070			1.525	281.595	276160.29	6227501.904	
C/3	PIPE OUTLET					375	278.085	0.910	278.995	276235.21	6227547.159	
C/2	KIP 2.4m Lintel	600	900	375	278.383	375	278.413	1.010	279.393	276225.63	6227549.698	
C/1	GSIP 900x900	900	900	375	278.610			1.057	279.667	276221.97	6227552.953	
D/2	PIPE OUTLET					375	277.390	1.010	278.400	276249.98	6227587.177	
D/1	GSIP 900x900	900	900	375	277.982			1.010	278.992	276235.79	6227590.335	
E/2	PIPE OUTLET					375	276.836	1.010	277.846	276262.62	6227625.349	
E/1	GSIP 900x900	900	900	375	277.384			1.010	278.394	276248.57	6227628.687	
F/2	PIPE OUTLET					375	276.114	1.010	277.124	276261.47	6227685.740	
F/1	GSIP 900x900	900	900	375	276.553			1.031	277.584	276247.68	6227686.349	
G/2	PIPE OUTLET					375	275.488	1.010	276.498	276267.86	6227721.009	
G/1	GSIP 900x900	900	900	375	276.076			1.010	277.086	276253.52	6227723.119	
H/2	PIPE OUTLET					375	274.960	1.010	275.970	276281.21	6227754.942	
H/1	GSIP 900x900	900	900	375	275.587			1.010	276.597	276266.14	6227757.245	
I/2	PIPE OUTLET					375	274.419	1.010	275.429	276301.74	6227785.616	
I/1	GSIP 900x900	900	900	375	275.052			1.010	276.062	276286.25	6227789.604	
J/2	PIPE OUTLET					375	273.563	1.010	274.573	276264.62	6227878.544	
J/1	GSIP 900x900	900	900	375	274.145			1.010	275.155	276262.52	6227863.996	
K/2	PIPE OUTLET					375	274.006	1.010	275.016	276234.57	6227883.333	
K/1	GSIP 900x900	900	900	375	274.570			1.010	275.580	276232.73	6227868.984	
L/2	HEADWALL					375	275.927	1.030	276.957	276173.36	6227904.242	
L/1	HEADWALL			375	276.265			1.201	277.466	276167.17	6227871.048	

HGL Report - Site Drainage Return Period: 20%yrs Location: depths The Oaks-2016																								
Pipe Connecting Pits (Downstream Upstream)	Pipe Class	Pipe Diameter	Pipe Length	Pipe Design Flow	Mannings n	Pipe Velocity	Pipe Part Velocity	Pipe Velocity Head	HGL at Downstream Pit	Pipe Friction Slope	Pipe Friction Loss	HGL at Upstream Pit	Pit Loss Coefficient	Pipe Head Loss	Adopted Upstream Water Level	Pit Surcharge Level (Pit Inlet/Outlet Level)	Downstream Pipe Obvert	Upstream Pipe Obvert	Downstream Pipe Invert	Upstream Pipe Invert	Pipe Slope	Pipe Design Flow	Pipe HGL Capacity	Pipe Manning Capacity
		(mm)	(m)	(l/s)		(m/s)	(m/s)	(m)	(m)	(%)	(m)	(m)	Ku	(m)	(m)	(m)	(m)	(m)	(m)	(m)	(%)	(l/s)	(l/s)	(l/s)
A/2 A/1	Class 3 RCP	600	11.724	0.0	0.013	0.00	0.000	0.000	280.272	0.00	0.000	280.668	18.000	0.000	280.668	281.595	280.272	280.668	279.674	280.070	3.378	0.0	1540.6	0.0
A/3 A/2	Class 3 RCP	600	21.267	13.3	0.013	0.05	14.55	0.000	279.230	0.00	0.000	280.120	2.200	0.000	280.120	280.962	279.348	280.238	278.750	279.640	4.185	13.3	1717.9	1245.0
A/4 A/3	Class 3 RCP	600	13.046	27.0	0.013	0.10	1.126	0.000	279.085	0.00	0.000	279.228	2.650	0.001	279.230	280.052	279.175	279.318	278.577	278.720	1.098	27.0	867.6	637.7
A/5 A/4	Class 3 RCP	600	21.282	29.5	0.013	0.10	1.118	0.001	278.872	0.00	0.000	279.085	1.014	0.001	279.085	279.825	278.937	279.150	278.339	278.552	1.000	29.5	826.9	608.6
A/6 A/5	Class 3 RCP	600	6.267	31.9	0.013	0.11	1.168	0.001	278.871	0.00	0.000	278.871	1.000	0.001	278.872	279.621	278.871	278.937	278.273	278.339	1.052	31.9	848.7	624.2
A/3 B/1	Class 3 RCP	375	12.380	16.5	0.013	0.15	0.150	0.001	279.366	0.00	0.001	279.367	17.659	0.020	279.387	280.000	279.366	279.365	278.991	278.990	-0.008	16.5	18.9	16.1
C/2 C/1	Class 3 RCP	375	4.901	55.6	0.013	0.50	2.321	0.013	278.558	0.00	0.003	278.755	11.835	0.153	278.908	279.667	278.788	278.985	278.413	278.610	4.020	55.6	497.6	351.5
C/3 C/2	Class 3 RCP	375	9.914	83.3	0.013	0.75	2.348	0.029	278.460	0.00	0.013	278.518	14.06	0.041	278.558	279.393	278.460	278.758	278.085	278.383	3.011	83.3	429.3	304.2
D/2 D/1	Class 3 RCP	375	14.530	59.1	0.013	0.54	2.377	0.015	277.765	0.00	0.010	278.086	11.365	0.166	278.252	278.992	277.765	278.357	277.390	277.982	4.075	59.1	501.1	353.9
E/2 E/1	Class 3 RCP	375	14.433	64.1	0.013	0.58	2.370	0.017	277.211	0.00	0.011	277.494	10.823	0.186	277.680	278.394	277.211	277.759	276.836	277.384	3.795	64.1	483.2	341.6
F/2 F/1	Class 3 RCP	375	13.808	78.5	0.013	0.71	2.356	0.026	276.489	0.00	0.016	276.681	9.373	0.242	276.923	277.584	276.489	276.928	276.114	276.553	3.179	78.5	441.4	312.6
G/2 G/1	Class 3 RCP	375	14.498	65.6	0.013	0.59	2.446	0.018	275.863	0.00	0.012	276.186	10.661	0.192	276.377	277.086	275.863	276.451	275.488	276.076	4.058	65.6	500.0	353.2
H/2 H/1	Class 3 RCP	375	15.245	55.6	0.013	0.50	2.343	0.013	275.335	0.00	0.009	275.687	11.829	0.153	275.840	276.597	275.335	275.962	274.960	275.587	4.114	55.6	503.5	355.6
I/2 I/1	Class 3 RCP	375	16.002	59.6	0.013	0.54	2.359	0.015	274.794	0.00	0.011	275.157	11.308	0.168	275.325	276.062	274.794	275.427	274.419	275.052	3.959	59.6	493.8	348.8
I/2 I/1	Class 3 RCP	375	16.002	59.6	0.013	0.54	2.359	0.015	274.794	0.00	0.011	275.157	11.308	0.168	275.325	276.062	274.794	275.427	274.419	275.052	3.959	59.6	493.8	348.8
J/2 J/1	Class 3 RCP	375	14.699	66.9	0.013	0.61	2.439	0.019	273.938	0.00	0.013	274.256	10.519	0.197	274.453	275.155	273.938	274.520	273.563	274.145	3.959	66.9	493.7	348.8
K/2 K/1	Class 3 RCP	375	14.466	62.8	0.013	0.57	2.383	0.017	274.381	0.00	0.011	274.678	10.960	0.181	274.859	275.580	274.381	274.945	274.006	274.570	3.897	62.8	489.8	346.1
L/2 L/1	Class 3 RCP	375	33.767	60.2	0.013	0.55	14.41	0.015	276.302	0.00	0.024	276.416	11.235	0.170	276.587	277.466	276.302	276.640	275.927	276.265	1.000	60.2	243.5	175.3


REVISIONS				DESCRIPTION				DRN		APP		DATE		WOLLONGONG - HEAD OFFICE Shop 1, 18 Arrow Avenue Figtree NSW 2555 PO Box 506 Figtree NSW 2525 T 61 2 4227 4233 F 61 2 4227 4133 E info@siteplus.com.au				Height Datum		Client Title				Dwg Title		Ref & Dwg No			
No.	A	B		PRELIMINARY CLIENT ISSUE				I.B.	A.C.	A.C.		14.03.24						Drawn	I.B.	MR & MRS NOCERA C/-				PROPOSED SUBDIVISION		23130.DA.C08			
	----	----		REVISED EARTHWORKS				I.B.	A.C.	A.C.		05.04.24		Site Plus Pty Ltd ABN 73 104 315 095				Designed	A.C.	PROFICIENT CONSTRUCTIONS (AUST)				80 SILVERDALE ROAD, THE OAKS		Sheet No 08 of 14			
	----	----						----	----	----		----		Site Plus Pty Ltd ABN 73 104 315 095				Checked	A.C.	-----						Scale AS NOTED @ A1			
	----	----						----	----	----		----		Site Plus Pty Ltd ABN 73 104 315 095				Approved	A.C.	Dwg Status		Local Authority		DRAINAGE CALCULATIONS		Date		Rev	
	----	----						----	----	----		----		Site Plus Pty Ltd ABN 73 104 315 095						DA		WOLLONDILLY				05.04.24		B	
	----	----						----	----	----		----		Site Plus Pty Ltd ABN 73 104 315 095														A1	

Hydrologic Design Sheet - Site Drainage Return Period: 20% Location: depths The Oaks-2016															
Pit	Catchment Flow Length	Catchment Slope	Catchment Roughness	Catchment Flow Time	Gutter Flow Time	Total Time	Pit C Factor	Total Catchment Area	Aera Contributing	Rainfall Intensity	Total Catchment Flow	Pit Type	Gutter Pit Inflow	Gutter Slope	Total Upstream Catchment
	(m)	(%)	'n'	(min)	(min)	(min)		(ha)	(l/s)	(mm/hr)	(l/s)		(l/s)	(%)	(ha)
A/1									0.0	118.9		SITEPLUS			0.0
A/2				20.00		20	1.000	0.07	0.1	68.4	13.3	SITEPLUS	9.3		0.1
	93.45	5.3	0.012				1.000	0.05							
							0.000								
	93.45	5.3	0.300				1.000	0.02							
A/3				5.00		5	1.000	0.02	0.1	118.9	7.3	SITEPLUS	5.1		0.1
	30.55	4.5	0.012				1.000	0.02							
							0.000								
	4.85	4.0	0.300				1.000	0.01							
A/4				5.00		5	1.000	0.01	0.2	118.9	4.3	SITEPLUS	3.0		0.2
	20.63	3.1	0.012				1.000	0.01							
							0.000								
	9.22	4.0	0.300				1.000	0.00							
A/5				5.00		5	1.000	0.01	0.2	118.9	4.3	SITEPLUS	3.0		0.2
	26.69	1.8	0.012				1.000	0.01							
							0.000								
	1.99	9.3	0.300				1.000	0.00							
B/1				5.00		5	1.000	0.05	0.1	118.9	16.5	SITEPLUS	11.6		0.1
	56.03	3.0	0.012				1.000	0.04							
							0.000								
	4.78	7.8	0.300				1.000	0.02							
C/1				20.00		20	1.000	0.40	0.4	68.4	76.1	SITEPLUS	22.8		0.4
	109.38	3.9	0.012				1.000	0.12							
							0.000								
	109.38	3.9	0.300				1.000	0.28							
C/2				5.00		5	1.000	0.04	0.4	118.9	12.6	SITEPLUS	8.8		0.4
	57.14	1.9	0.012				1.000	0.03							
							0.000								
	4.23	6.1	0.300				1.000	0.01							
D/1				20.00		20	1.000	0.43	0.4	68.4	81.0	SITEPLUS	24.3		0.4
	112.45	3.5	0.012				1.000	0.13							
							0.000								
	112.45	3.5	0.300				1.000	0.30							
E/1				20.00		20	1.000	0.46	0.5	68.4	87.8	SITEPLUS	26.3		0.5
	121.66	3.0	0.012				1.000	0.14							
							0.000								
	121.66	3.0	0.300				1.000	0.32							
F/1				20.00		20	1.000	0.57	0.6	68.4	107.6	SITEPLUS	32.3		0.6
	116.70	3.0	0.012				1.000	0.17							
							0.000								
	116.70	3.0	0.300				1.000	0.40							
G/1				20.00		20	1.000	0.47	0.5	68.4	89.8	SITEPLUS	26.9		0.5
	116.04	3.0	0.012				1.000	0.14							
							0.000								
	116.04	3.0	0.300				1.000	0.33							
H/1				20.00		20	1.000	0.40	0.4	68.4	76.2	SITEPLUS	22.9		0.4
	235.82	3.0	0.012				1.000	0.12							
							0.000								
	235.82	3.0	0.300				1.000	0.28							
I/1				20.00		20	1.000	0.43	0.4	68.4	81.7	SITEPLUS	24.5		0.4
	129.77	2.6	0.012				1.000	0.13							
							0.000								
	129.77	2.6	0.300				1.000	0.30							
J/1				20.00		20	1.000	0.48	0.5	68.4	91.7	SITEPLUS	27.5		0.5
	73.99	2.8	0.012				1.000	0.14							
							0.000								
	73.99	2.8	0.300				1.000	0.34							
K/1				20.00		20	1.000	0.45	0.5	68.4	86.1	SITEPLUS	25.8		0.5
	93.04	3.0	0.012				1.000	0.14							
							0.000								
	93.04	3.0	0.300				1.000	0.32							
L/1				20.00		20	1.000	0.32	0.3	68.4	60.2	SITEPLUS	42.2		0.3
	357.76	8.6	0.012				1.000	0.22							
							0.000								
	357.76	8.6	0.300				1.000	0.10							


T:\Projects\23130_80_Silverdale Road, The Oaks\Drawings\DA\23130_Drainage.dwg




LINE G
SCALES: HORIZ 1:500 VERT 1:100




LINE H
SCALES: HORIZ 1:500 VERT 1:100




LINE I
SCALES: HORIZ 1:500 VERT 1:100




LINE J
SCALES: HORIZ 1:500 VERT 1:100




LINE K
SCALES: HORIZ 1:500 VERT 1:100




LINE L
SCALES: HORIZ 1:500 VERT 1:100




LINE A
SCALES: HORIZ 1:500 VERT 1:100




LINE B
SCALES: HORIZ 1:500 VERT 1:100




LINE C
SCALES: HORIZ 1:500 VERT 1:100



LINE D
SCALES: HORIZ 1:500 VERT 1:100



LINE E
SCALES: HORIZ 1:500 VERT 1:100




LINE F
SCALES: HORIZ 1:500 VERT 1:100

REVISIONS		DESCRIPTION				DRN		APP		DATE		Height Datum		Client Title		Dwg Title		Ref & Dwg No	
No.	A	PRELIMINARY CLIENT ISSUE				I.B.	A.C.	14.03.24				A.H.D		MR & MRS NOCERA C/-		PROPOSED SUBDIVISION		23130.DA.C09	
	B	REVISED EARTHWORKS				I.B.	A.C.	05.04.24				I.B.		PROFICIENT CONSTRUCTIONS (AUST)		80 SILVERDALE ROAD, THE OAKS		Sheet No 09 of 14	
												A.C.						Scale AS NOTED @ A1	
												A.C.		Dwg Status DA		Local Authority WOLLONDILLY		Date 05.04.24	
												A.C.				DRAINAGE LONG SECTIONS		Rev B	
																		A1	



WOLLONGONG - HEAD OFFICE
Shop 1, 18 Arrow Avenue
Figtree NSW 2525
PO Box 506
Figtree NSW 2525
T 61 2 4227 4233
F 61 2 4227 4133
E info@siteplus.com.au

engineering landscape design flooding management



WATER QUALITY MUSIC MODEL RESULTS
BASED ON THE WATER QUALITY MEASURES OUTLINED IN THE WOLLONDILLY WUSD GUIDELINE, THE FOLLOWING FLOW REDUCTION WAS ATTAINED:

FLOW 13.400 ML/yr

REFER TO SITEPLUS'S MUSIC MODEL FOR DETAILS. WOLLONDILLY WUSD GUIDELINES REQUIRES RESIDUAL FLOW RANGING BETWEEN 2.5-3.0 ML/yr/ha

SITE REQUIREMENT CALCULATION:

DEVELOPMENT AREA = 5.193 ha
RESIDUAL FLOW RANGE = 12.983 - 15.579 ML/yr




RAINWATER TANK AVERAGE DAILY DEMAND
RAINWATER REUSE WAS BASED ON THE METHODOLOGY OUTLINED IN THE WOLLONDILLY WUSD GUIDELINE:

SIZE OF ROOF = 450 m²
MIN SIZE OF RWT = 18,000 L
MIN AVG DAILY DEMAND = 2,700 L/day

LEGEND

- ROOF AREA 450m²
100% IMPERVIOUS
- LANDSCAPE AREA
30% IMPERVIOUS
- ROAD RESERVE AREA
47% IMPERVIOUS



MUSIC CATCHMENT PLAN
SCALE 1:750




MUSIC SCHEMATIC

Treatment Train Effectiveness - Receiving Node			
	Sources	Residual Load	% Reduction
Flow (ML/yr)	39.6	13.4	66.2
Total Suspended Solids (kg/yr)	5440	399	92.7
Total Phosphorus (kg/yr)	10.2	1.79	82.4
Total Nitrogen (kg/yr)	81.9	21.7	73.5
Gross Pollutants (kg/yr)	907	0	100

MUSIC RESULTS



REVISIONS	No.	DESCRIPTION	DRN	APP	DATE	siteplus Site Plus Pty Ltd ABN 73 104 315 095 engineering landscape design flooding management	WOLLONGONG - HEAD OFFICE Shop 1, 18 Arrow Avenue Figtree NSW 2525 PO Box 506 Figtree NSW 2525 T 61 2 4227 4233 F 61 2 4227 4133 E info@siteplus.com.au	Height Datum	A.H.D	Client Title	MR & MRS NOCERA C/- PROFICIENT CONSTRUCTIONS (AUST)	Dwg Title	PROPOSED SUBDIVISION 80 SILVERDALE ROAD, THE OAKS	Ref & Dwg No																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
	A	PRELIMINARY CLIENT ISSUE	I.B.	A.C.	14.03.24			23130.DA.C12																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
	B	REVISED EARTHWORKS	I.B.	A.C.	05.04.24			Sheet No																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
	----	----	----	----	----			12 of 14																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
	----	----	----	----	----			Scale																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
	----	----	----	----	----			1:200 @ A1																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
	----	----	----	----	----			Date																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					</





- STATEMENT OF SOIL MANAGEMENT
- 1 ALL TOPSOIL IS TO BE STOCKPILED IN AREAS DESIGNATED ON PLAN.
 - 2 ALL FORMED EMBANKMENTS (CUT & FILL) ARE TO BE SEEDED WITHIN 7 DAYS.
 - 3 ALL DISTURBED AREAS INCLUDING ANY CONTROLLED FILL ARE TO BE TOPSOILED & SEEDED PRIOR TO COMPLETION OF WORKS. ALL DISTURBED AREAS THAT WILL NOT BE STABILIZED WITHIN 2 MONTHS MUST BE TEMPORARILY REVEGETATED WITHIN 7 DAYS OF CLEARING AREAS THAT FAIL TO ESTABLISH MUST BE RESOWN IMMEDIATELY.
 - 4 ALL GULLY PITS ARE TO BE PROVIDED WITH SEDIMENT FILTER BARRIERS SUCH AS STRAW BAIL OR SANDBAGS
 - 5 PROVIDE TEMPORARY DIVERSION BANKS ON SITE AS DIRECTED
 - 6 AT THE TOP OF ALL FILL EMBANKMENTS, PROVIDE A BERM TO PREVENT WATER RUNNING DOWN EMBANKMENTS. BERM IS TO BE MAINTAINED AT ALL TIMES AS THE FILL EMBANKMENT PROGRESSES TO FINAL LEVEL
 - 7 ALL FORMED EMBANKMENTS (CUT & FILL) TO BE TOPSOILED & SEEDED/FERTILIZED ON FINAL TRIMMING
 - 8 FOR TEMPORARY REVEGETATION PURPOSES, THE REVEGETATION MIXTURE SHOULD BE TO COUNCIL SPECIFICATIONS
 - 9 TRENCHES FOR INTERLOT DRAINAGE LINES ARE TO BE REINSTATED WITH TOPSOIL FOLLOWING PIPE INSTALLATION & BACKFILLING & IMMEDIATELY SEEDED/FERTILIZED
 - 10 THE GROUND SHALL BE TYNED / SCARIFIED TO A MIN DEPTH 100mm PRIOR TO SEEDING
 - 11 CONTRACTOR SHOULD LIASE REGULARLY WITH ENGINEER TO DETERMINE AREAS WHICH CAN BE PROGRESSIVELY REVEGETATED
 - 12 TO ASSIST IN DUST CONTROL /WIND EROSION A TRACKIFIER SUCH AS CUROSOL SHOULD BE USED OR EQUIVALENT ENDORSED PRODUCT BY EPA, RATES AS PER MANUFACTURES SPECIFICATION
 - 13 DESIGNATED PLANT AND MACHINERY ACCESSWAYS TO BE DEFINED ONSITE BY THE INSTALLATION OF PARAWEBBING FENCING TO MINIMIZE UNNECESSARY SITE DISTURBANCE
 - 14 IT IS THE CONTRACTORS RESPONSIBILITY TO MAINTAIN SOIL EROSION CONTROL DEVICES AND CONTROL DUST.
 - 15 A LOG BOOK IS TO BE MAINTAINED ON SITE, MAKING ENTRIES AT LEAST WEEKLY, IMMEDIATELY BEFORE FORECAST RAIN AND AFTER RAINFALL. ENTRIES WILL INCLUDE:
 - (i) THE VOLUME AND INTENSITY OF ANY RAINFALL EVENTS;
 - (ii) THE CONDITION OF ANY SOIL AND WATER MANAGEMENT WORKS AND WETHER IT IS LIKELY TO BE EFFECTIVE UNTIL THE NEXT AUDIT;
 - (iii) INSTALLATION, REMOVAL & REPAIRS OF ANY EROSION CONTROLS;
 - (iv) THE CONDITION OF VEGETATION AND ANY NEED TO IRRIGATE;
 - (v) THE NEED FOR DUST PREVENTION STRATEGIES;
 - (vi) ANY REMEDIAL WORKS TO BE UNDERTAKEN;
 - (vii) INSTANCES RESULTING IN DAMAGE TO CONTROLS, ACCIDENTAL OR OTHERWISE;
 - (viii) TIME, DATE, VOLUME AND TYPE OF ANY FLOCCULANTS;
 - (ix) TIME, DATE, VOLUME AND TYPE OF SEDIMENT REMOVED FROM CONTROL STRUCTURES AND WHERE IT HAS BEEN DISPOSED;
- THE LOG BOOK IS TO BE KEPT ON-SITE AND MADE AVAILABLE ON SITE TO ANY ONE REQUIRING IT. IT SHOULD ALSO CONTAIN MAINTENANCE REQUIREMENTS AND PROCEDURES FOR ANY CONTROL REQUIRING IT.

- MAINTENANCE PROCEDURES DURING CONSTRUCTION
- 1 ALL EROSION CONTROL MEASURES ARE TO BE MAINTAINED AT ALL TIMES SO THAT THOSE MEASURES ARE FULLY FUNCTIONAL / OPERATIONAL DURING THE CURRENCY OR WORKS. ALL SUCH CONTROLS MUST ALSO BE FULLY FUNCTIONAL / OPERATIONAL SHOULD WORK OPERATIONS CEASE TEMPORARILY, (e.g WEEKENDS, ROSTERED DAYS OFF, etc) 2 RESPREAD MATERIAL GAINED DURING MAINTENANCE OPERATION OR ALTERNATIVELY PLACE ON STOCKPILES.

- GENERAL NOTES
- 1 REMOVE ALL SOIL & SPOIL MATERIAL FROM THE ROADWAY & GUTTER SYSTEM FOR THAT SECTION OF TRENCHING & / OR OTHER WORKS CARRIED OUT ON ANY ONE DAY. THIS IS TO BE UNDERTAKEN ON THE COMPLETION OF EACH DAY'S WORK.
 - 2 ABSTAIN FROM PLACING SPOIL / STOCKPILES ON OR IN THE IMMEDIATE VICINITY OF THE KERB & GUTTER SYSTEM. A MINIMUM SET BACK OF THREE (3) METRES WILL BE REQUIRED.
 - 3 STOCKPILES REFERED TO IN ITEM 2 ARE NOT TO BE PLACED WITHIN FIFTEEN (15) METRES EITHER SIDE OF KERB INLET PITS. THIS IS TO BE REGARDED AS A DESIGNATED EXCLUSION ZONE.
 - 4 WHERE ROCK IS ENCOUNTERED DURING THE TRENCHING OPERATIONS & THIS MATERIAL IS CONSIDERED TO BE UNSUITABLE AS BACKFILL, THEN ALL OVERSIZED ROCK WILL BE REQUIRED TO BE REMOVED FROM THE SITE & WILL NOT BE PERMITTED TO REMAIN ON THE SURFACE OF REGRADING & SURFACE PREPARATION PRIOR TO SEEDING DISTURBED AREAS.

SOIL AND WATER MANAGEMENT PLAN
SCALE 1:750



- LEGEND PROPOSED
- LEVEL SPREADER
 - STORMWATER PIPE
 - GRATED PIT
 - JUNCTION PIT
 - KERB INLET PIT
 - SEDIMENT FENCE
 - SEDIMENT TRAP
 - STABILISED CONSTRUCTION EXIT
 - DISTURBED AREA
 - DIVERSION BANK AND CHANNEL
 - BARRIER FENCE
 - DIVERSION BANK ONLY

NOTE: All erosion and sediment controls must be in accordance with Landcom's Managing Urban Stormwater, Soils and Construction, Volume 1, 4th Edition, March 2004

REVISIONS	No.	DESCRIPTION	DRN	APP	DATE		Site Plus Pty Ltd ABN 73 104 315 095	engineering	landscape	design	flooding	management	Height Datum A.H.D	Client Title MR & MRS NOCERA C/- PROFICIENT CONSTRUCTIONS (AUST)	Dwg Title PROPOSED SUBDIVISION 80 SILVERDALE ROAD, THE OAKS SOIL & WATER MANAGEMENT PLAN	Ref & Dwg No 23130.DA.C13
	A	PRELIMINARY CLIENT ISSUE	I.B.	A.C.	14.03.24											
	B	REVISED EARTHWORKS	I.B.	A.C.	05.04.24								Drawn I.B.	Dwg Status DA	Local Authority WOLLONDILLY	Date 05.04.24
													Designed A.C.			Rev B
													Checked A.C.			
													Approved A.C.			A1

Appendix B – Hydra Markup

