# STAGE 2 - DETAILED ENVIRONMENTAL SITE INVESTIGATION

**PROVIDED BY:**

## LRM GLOBAL PTY LTD

## LIABILITY & RISK MANAGEMENT CONSULTING




**FOR WORKS:**

## 266 LONGUEVILLE ROAD, LANE COVE

**FOR:**

## AUSTRALIAN UNITY LTD

## AUGUST 2018

**CONFIDENTIAL**

## TABLE OF CONTENTS


**ABBREVIATIONS** ..... 7

**1.0 INTRODUCTION** ..... 13

**2.0 ASSESSMENT OBJECTIVES AND SCOPE** ..... 14

**2.1 Assessment Objective** ..... 14

**2.2 Scope** ..... 14

**3.0 SITE IDENTIFICATION** ..... 16

**4.0 STAGE 1– PRELIMINARY ENVIRONMENTAL SITE ASSESSMENT** ..... 16

**4.1 Site and Regional Setting** ..... 16

*4.1.1 Land use Zoning* ..... 16
*4.1.2 Local Topography* ..... 17
*4.1.3 Nearby Sensitive Receptors* ..... 17
*4.1.4 Regional Geology* ..... 17
*4.1.5 Underground Utilities and UPSS* ..... 18
*4.1.6 Acid Sulphate Soils* ..... 18
*4.1.7 Local Hydrology and Nearby Groundwater Bores* ..... 18
*4.1.8 Aerial Photographs* ..... 18
*4.1.9 Historical Land Title Review* ..... 20
*4.1.10 Historic Plans* ..... 22
*4.1.11 Historic Business Listings* ..... 22
*4.1.12 Council Records Review* ..... 23

**5.0 ENVIRONMENTAL RECORDS REVIEW** ..... 24

**5.1 NSW EPA DECCW Contaminated Land Database (epa.nsw.gov.au)** ..... 24

**5.2 SafeWork Search** ..... 24

**5.3 Protection of Environment Operations Act 1997 Public Register** ..... 24

**5.4 Contaminated Land and Waste Management Facilities** ..... 25

**5.5 EPA PFAS Investigation Program** ..... 25

**5.6 Previous Site Geotechnical and Environmental Reports** ..... 26

**6.0 SITE RECONNAISSANCE** ..... 31

**7.0 CONCEPTUAL SITE MODEL** ..... 33

**7.1 Potential Sources of contamination** ..... 33

**7.2 Initial Data Gap Assessment** ..... 33

**7.3 Receptors** ..... 39

**8.0 STAGE 1 PESA CONCLUSIONS AND RECOMMENDATIONS** ..... 41

**9.0 STAGE 2 – DETAILED ENVIRONEMTNAL SITE INVESTIGATION** ..... 42

**9.1 DESI Objectives** ..... 42

**9.2 Development Application Conditions – Contamination** ..... 42

**10.0 DATA QUALITY OBJECTIVES** ..... 43

**10.1 Overview** ..... 43

*10.1.1 STEP 1: State the Problem* ..... 43
*10.1.2 STEP 2: Identification of the Assessment Decisions/ Goals* ..... 43
*10.1.3 STEP 3: Identification of Decision Inputs* ..... 44
*10.1.4 STEP 4: Definition of Study Boundaries* ..... 44

*10.1.5 STEP 5: Decision Rules ..... 44*
*10.1.6 STEP 6: Limits on Decision Errors ..... 44*
*10.1.7 STEP 7: Optimise the Design for Obtaining Data ..... 46*
**11.0 ASSESSMENT CRITERIA ..... 47**
**11.1 Soil Criteria ..... 47**
**11.2 Groundwater Criteria ..... 50**
**12.0 DATA QUALITY ASSESSMENT ..... 51**
**13.0 SOIL INVESTIGATION ..... 54**
**13.1 Field Soil Investigation Objectives ..... 54**
**14.0 SOIL RESULTS ..... 61**
**15.0 DISCUSSION – SOIL ..... 66**
***15.1.1 Human Health ..... 66***
***15.1.2 Soil Disposal Classification ..... 66***
*15.1.3 Ecological Risks ..... 68*
**16.0 SOIL VAPOUR ASSESSMENT ..... 68**
**17.0 GROUNDWATER ASSESSMENT ..... 68**
**17.1 Groundwater Assessment Objectives ..... 68**
**17.2 Groundwater Assessment Criteria ..... 68**
**17.3 Groundwater Monitoring Well Location Selection Criteria ..... 69**
**18.0 DATA QUALITY ASSESSMENT - GROUNDWATER ..... 70**
**19.0 GROUNDWATER WELL INSTALLATION ..... 73**
**19.1 Monitoring Well Construction Details ..... 73**
**19.2 Monitoring Well Development ..... 73**
**19.3 Groundwater Sampling Details ..... 74**
**19.4 Field Observations ..... 75**
**20.0 GROUNDWATER RESULTS ..... 75**
**21.0 GROUNDWATER DISCUSSION ..... 76**
**21.1 Sensitive receptors and Water Quality Objectives ..... 77**
**21.2 Site Dewatering and Discharge Licenses ..... 77**
**22.0 CONCEPTUAL SITE MODEL ..... 78**
**22.1 Sources ..... 78**
**22.2 Data Gaps ..... 78**
**22.3 Receptors ..... 80**
**23.0 STATEMENT OF LIMITATIONS ..... 84**
**24.0 REFERENCES ..... 85**

**TABLES IN TEXT**


| | |
|---|---|
| TABLE 1 | Site Identification Information |
| TABLE 2a | Historic Title Summaries (Lot 1 DP 1227921) |
| TABLE 2b | Historic Title Summaries (Lot 1 DP 321353) |
| TABLE 3 | UBD Business Listing Site Occupancy and Adjacent Significant Summary |
| TABLE 4 | List of NSW Contaminated Sites Notified to the EPA |
| TABLE 5 | Surrounding Sites Listed on the Protection of Environment Operations Act 1997 Public Register |
| TABLE 6 | Potential Sources and Contaminants of Concern |
| TABLE 7 | Data Gap Analyses and Sample Analysis Plan |
| TABLE 8 | Adopted Ecological Investigation Levels |
| TABLE 9 | QA/QC Samples Required vs. Collected |
| TABLE 10 | Initial Soil Sample Locations |
| TABLE 11 | Secondary Soil Sample Locations |
| TABLE 12 | Summarised Primary Soil Sample Analysis per Stratigraphy |
| TABLE 13 | Human Health Exceedance Summary (mg/kg) |
| TABLE 14 | Waste Disposal SCC without TCLP Exceedance Summary (mg/kg) |
| TABLE 15 | Groundwater Rounds Sampling Analytes |
| TABLE 16 | Groundwater Field Data Pre-Sampling and Stabilisation |
| TABLE 17 | Groundwater Results Exceedance Table |

## APPENDICES

**A Site Plans and Figures**

Figure 2 Site Location Plan
Figure 3 Site Features Plan
Figure 4 Sample Location Plan Soil and Groundwater
Figure 5 Soil Exceedances Plan - Waste Category
Figure 6 Soil Exceedances Plan – HILs / HSL / Management Limits
Figure 7 Groundwater GIL Exceedances
Figure 8a/b Groundwater SWL 29/05/2018 and 3/08/2018
Figure 9 Cross-Section
Figure 10 Proposed Development Plans

**B Historical Records and Documentation**

Figure 11 Land Reclassification Map
Figure 12 Land Zoning Map
Figure 13 Environmental Protection Land Map
Figure 14 LEP Planning Zones
Figure 15 Elevation Contours
Figure 16 Soil Landscapes
Figure 17 Dial Before You Dig
Figure 18 Geology 1:100,000 Plan
Figure 19 Historical Maps (1917, 1949, 1975)
Figure 20 Contaminated Land & Waste Management Facilities
Figure 21 Current EPA Licensed Activities
Figure 22 Delicensed & Former Licensed EPA Activities
Figure 23 Groundwater Borehole Proximity Plan
Figure 24 Historical Business Directory Records
Figure 25 Acid Sulfate Soils Map
Figure 26 Sensitive Zone Map
Section 10.7 Planning Certificates
Safework Search
Historical Aerial Photographs
Historical Titles

**C Field Sheets and Calibration Logs**

LRM Soil Bore and Monitoring Well Construction Logs
SMEC Soil Bore and Monitoring Well Construction Logs
LRM Groundwater Field Stabilisation Logs
EP Risk Groundwater Field Stabilisation Logs
Soil and Groundwater Sampling Procedures
Calibration Records
Rental Documents

**D** **Analytical Results Tables, Laboratory Results and COCs**

Table 18a: Analytical Soil Results – NEPM HILs
Table 18b: Analytical Soil Results – NEPM HSLs
Table 18c: Analytical Soil Results – NEPM Management Limits
Table 19: Analytical Soil Results – NEPM EILs
Table 20: Analytical Soil Results – NSW EPA 2008 Waste Criteria
Table 21: Analytical Groundwater Results – NEPM GILs
Table 22: QA/QC Soil RPDs
Table 23: QA/QC Groundwater RPDs
Table 24: QA/QC Soil Trip and Rinsate Blank Results
Table 25: QA/QC Groundwater Trip and Rinsate Results



**E** **Full Laboratory Results**

Soil Laboratory Results, SRAs and COCs
Groundwater Laboratory Results, SRA's and COCs

**F** **Historical Report Extracts and SAQP**

SMEC
Arcadia
Applied Ecology
LRM SAQPs

**AUTHORISED BY:**

| | | |
|---|---|---|
| LRM Global Pty Ltd<br>Liability & Risk Management | Written by:<br><br>Adam Campbell<br>Environmental Consultant<br>Date: 17/08/2018 | Authorised by:<br><br>Jon Lawson<br>Principal Consultant<br>Date: 17/08/2018 |

**DISTRIBUTION LIST:**

| No. of Copies | Status | Date | Prepared for: |
|---|---|---|---|
| Copy 1 | Final Draft | 17/08/2018 | Client – Australian Unity Ltd |
| Copy 2 | Final Draft | 17/08/2018 | Assessor – LRM Global Pty Ltd |
| Copy 3 | Final Draft | 17/08/2018 | Auditor – Brad May, Epic Environmental Pty Ltd |

## ABBREVIATIONS

| | |
|---|---|
| **AHD** | Australian Height Datum |
| **ANZECC** | Australian and New Zealand Environment and Conservation Council |
| **BTEX** | Benzene, Toluene, Ethylbenzene and Xylene |
| **CCME** | Canadian Council of Ministers of the Environment |
| **CHCs** | Chlorinated Hydrocarbons |
| **DESI** | Detailed Environmental Site Assessment |
| **EIL** | Ecological Investigation Levels |
| **EC** | Electrical conductivity |
| **EPA** | Environment Protection Authority |
| **HALVOL** | Halogenated Volatile Organics |
| **HIL** | Health Investigation Levels |
| **LRM** | LRM Global – Liability & Risk Management Consulting |
| **m BGL** | Metres below ground level |
| **MAHs** | Monocyclic Aromatic Hydrocarbons |
| **NATA** | National Association of Testing Authorities |
| **NEPC** | National Environment Protection Council |
| **NEPM** | National Environment Protection Measure |
| **NHMRC** | National Health and Medical Research Council |
| **OCPs** | Organochlorine Pesticides |
| **OPPs** | Organophosphorous Pesticides |
| **PAHs** | Polycyclic Aromatic Hydrocarbons |
| **PESA** | Preliminary Environmental Site Assessment |
| **PCBs** | Polychlorinated Biphenyls |
| **PESA** | Preliminary Environmental Site Assessment |
| **PID** | Photoionisation Detector |
| **QA/QC** | Quality Assurance / Quality Control |
| **RAP** | Remediation Action Plan |
| **SAQP** | Sample and Quality Analysis Plan |
| **SVCHCs** | Semi-volatile Chlorinated Hydrocarbons |
| **SVOCs** | Semi-volatile Organic Compounds |
| **TDS** | Total Dissolved Solids |
| **TCLP** | Total Concentration Leachability Potential |
| **TIT** | Triple Interceptor Trap |
| **TOC** | Total Organic Carbon |
| **TRHs** | Total Petroleum Hydrocarbons |
| **USEPA** | United States Environmental Protection Agency |
| **VHCs** | Volatile Halogenated Hydrocarbons |
| **VOCs** | Volatile Organic Compounds |

## Executive Summary

LRM Global Pty Ltd (LRM) was engaged by Australian Unity Ltd (the client) to complete a Preliminary Environmental Site Assessment (PESA) and subsequent Stage 2 – Detailed Environmental Site Investigation (DESI) of the property located at 266 Longueville Road, Lane Cove, NSW (the site) to document any potential environmental liabilities that are apparent from a comprehensive desktop study, soil and groundwater assessment as part of a development application for a proposed high density retirement village.

The planned development will consist of a seven level structure basement car park levels to a maximum depth of approximately 12 meters below ground level subject to the site slope. Ground level landscaped areas with accessible soils will remain in some isolated areas, however, all fill material will be excavated from site during initial civil works. The majority of planted species will be indigenous to the local area. The ground level of the proposed structure will consist of a loading bay and parking areas, general facilities and residents units due to the sloped nature of the site. Upper levels will consist of high density housing with communal rooftop garden areas on the uppermost level.

The objectives of this investigation are as follows:

- Characterise site soil and groundwater conditions;
- To inform and guide the Remediation Action Plan (RAP) to be enacted during the site redevelopment process;
- Provide all analytical data in summarised tables and provide all other relevant data in the form of a detailed environmental site assessment report for the environmental auditor to consider as part of their audit of the site;
- Council DA conditions for a Stage 2 Detailed Site Investigation Report (as per the NSW EPA's Guidelines for Consultants Reporting on Contaminated Sites);
- A single report detailing the location, type and level of contaminants, compiling all relevant information which details soil and groundwater sampling and testing to date;
- Identify the potential for migration of contaminants off site;
- Provide a statement that the site will be suitable upon remediation for the development proposed; and
- Comply with State Environmental Planning Policy 55 – Remediation of Land.

**Planning Objectives**

Draft Conditions of Consent: Revised 27June 2018
266 Longueville Road, Lane Cove

PART A – DEFERRED COMMENCEMENT CONSENT CONDITIONS:

The consent will not operate and it may not be acted upon until the Council or its delegate is satisfied as to the following matters:

(i) Deferred Commencement Condition – Contaminated Land

A Stage 2 Detailed Site Investigation Report (as per the NSW EPA's *Guidelines for Consultants Reporting on Contaminated Sites*) shall be submitted to Council for assessment. The report shall identify to Council's satisfaction the location, type and level of contaminants in a single

report compiling all relevant information which details soil sampling and testing to date. The report shall also identify the potential for migration of contaminants off site. The report must include a statement to the effect that the site, upon remediation, will be suitable for the development proposed.

Reason for condition: Compliance with *State Environmental Planning Policy 55 – Remediation of Land*

The key findings of the DESI field investigation are as follows:

## Preliminary Assessment

On the basis of the desktop historical review and visual inspection of the site, the following conclusions can be drawn:

- The desktop study indicates that the site is zoned *'R4 High Density Residential*'.
- Acid Sulphate Soils are not potentially present at the site.
- According to the aerial photographs, land titles, historic plans and business directories reviewed, the site was vacant until construction of the Bowling Green commenced in approximately 1961 and has been used as such till this assessment date.
- The surrounding area has undergone light commercial and residential development over time. A review of the historical aerial photographs and EPA records indicate that there have been no quarrying or landfilling activities in the area surrounding the site. As such, it is considered unlikely that there would be a landfill gas issue at this site. However on-site observations and the previous environmental report do indicate infilling has occurred to some extent, however with no evidence of putrescible wastes.
- A search of the NSW OEH Contaminated Land Database and Protection of Environment Operations Act 1997 Public Register found no records for the site.
- A Stage 2 Detailed Environmental Site Investigation is required to characterise the site soils and groundwater.

## Soil Investigation

On the basis of the visual aspects of the site, review of the site history and results of soil analysis, the following conclusions can be drawn:

- Soil impacts in the fill material include lead, mercury, PAHs and zinc exceeding adopted site criteria.
- No exceedances in the natural underlying material were reported.
- Asbestos containing materials were identified on the site surface and potentially deeper within fill material;
- Aesthetic issues are present in the form of concrete, brick, glass, general demolition wastes, discarded household goods and household type rubbish. The lateral extent of these materials within the fill profile will be further characterised during test pitting and site excavation works.
- A final site validation sampling assessment will compare soils against adopted NEPM HIL Criteria A for sensitive land use settings and EILs for accessible areas / gardens for the remaining soils after the completion of excavation and fill removal.

Given the development proposed of the site and the fact that all fill material at the site will be excavated and disposed off-site, the future risk the site soils pose to human health is considered low.

**Fill Material Waste Classification**

- TCLP conducted by SMEC reported only exceedances of criteria for lead.
- Both Nickel and BaP were non-detect or below criteria.
- Approximately 27,000 ton of fill material is required to be removed.
- Asbestos to be removed or abated as appropriate to bonded status and extent.

Soils were compared to the 2008 NSW EPA soil disposal criteria and also the criteria detailed with the NSW EPA excavated natural material order 2014 for offsite disposal purposes.

- The sample analysis results indicate that fill material across the site can generally be classified as "**General Solid Waste**".
- **Hazardous waste** was reported at 4 locations
- Exceedances of the CT1 and CT2 criteria detailed within Table 1 of the NSW EPA Waste Classification Guidelines – Part 1 were noted relating to lead in 21 locations only were reported as "**Restricted Waste**".
- These exceedances will be further delineated with greater accuracy and TCLP analysis during excavation test pitting when full access is available to those fill material domains.
- The fill material at site cannot be currently classified as ENM due to its imported and potentially contaminated nature.

**Natural Material Waste Classification**

- Currently the sample analysis results indicate that natural material beneath the fill layer across the site can be classified as "VENM" for offsite disposal purposes. No exceedances of the waste criteria were reported in this profile within the samples collected.
- Further characterisation can be completed once excavation has reached this depth and removed the contaminated fill layer above.

## Groundwater Investigation

- A groundwater monitoring network consisting of 3 wells was installed across the site.
- Concentrations of metals including aluminum, cadmium, copper, iron, lead, nickel and zinc were reported exceeding the drinking water, fresh water, Aesthetic and Recreational Primary and Secondary Criteria for the site during the two monitoring rounds. However, it should be noted that the concentration reported were minimal and consistent across the site indicating that these concentration are likely naturally occurring and not derived from historical uses at the site.
- Concentrations of Chlorinated hydrocarbons, halogenated benzenes, halogenated hydrocarbons, TPH, BTEX, PAHs, MAHs, OCPs, phenols, phthalates and PCBs were all reported below the laboratory limit of reporting.
- No volatile organic compounds were reported, indicating that the groundwater assessed is unlikely to pose a vapor risk to future site users.

It is considered, based on the results reported from groundwater samples obtained at the site, that the groundwater assessed is unlikely to pose a risk to the current or proposed future site use and is considered not to been polluted as a result of historic site activities.

## Conclusions

Based on the soil and groundwater data to date, the site is considered suitable for the proposed aged care facility development with no human health risk posed by the identified subsurface conditions following the proposed off-site disposal of all fill material at the site.

The potential off-site impacts of site sourced contaminates are not yet complete with further soil and groundwater works required, detailed below.

Future site workers potentially coming into contact with contaminated fill material will require contact personal protective equipment in the form of gloves, long sleeves and pants to protect against any dermal contact.

Current site gardeners not coming into contact with soils during maintenance work, e.g. lawn moving of greens would not require PPE. Any more significant works that involve soil disturbance PE as per site constructions works would be required.

Control measures should be implemented during the project test pitting and excavation works which is outlined in the site Remediation Action Plan (RAP). These would include but not limited to;

- Site security, signage, fencing;
- Storm water / surface waters management;
- Soil management plan;
- Noise control plan;
- Dust control plan;
- Odour control plan;
- Occupation health and safety plan;
- Unexpected finds plan;
- Final site validation.

This report satisfies the conditions as required to achieve compliance with State Environmental Planning Policy 55 – Remediation of Land.

### Final statement

The site at 266 Longueville Road Lane Cove will be suitable, upon remediation, for the proposed high density residential aged care facility.

- Based on the soil and groundwater data to date, the site is considered suitable for the proposed aged care facility development with no human health risk posed by the identified subsurface conditions following the proposed off-site disposal of all fill material at the site.
- Currently the site poses no risk to site users including gardeners who currently maintain the bowling greens.

- Constraints on the sites current users should include no sub-surface or access to site soils without appropriate PPE and reference to the site Remediation Action Plan. Site soils / fill material are contaminated.

**Further works**

Further works required to more accurately characterize the site for land use acceptability, waste disposal classification and potential off-site impacts are required. These further works are detailed and guided by the site Remediation Action Plan.

- Soil test pitting targeted locations for hot spot delineation vertically and laterally;
- Asbestos delineation;
- Aesthetic assessment;
- TCLP analysis for soil hot spots for waste classification;
- Further groundwater wells to the eastern boundary of the site to determine potential off-site impacts to Gore Creek;
- Surface water and sediment sampling of Gore Creek;
- Additional groundwater sampling with selected lower LOR as applicable;
- Soil sampling for EIL criteria calculations;
- Final sit validation following removal of fill material;
- Update the site RAP based on this final report.

# 1.0 INTRODUCTION

LRM Global Pty Ltd (LRM) was engaged by Australian Unity Ltd (the client) to complete a Preliminary Environmental Site Assessment (PESA, completed) and subsequent Stage 2 – Detailed Environmental Site Investigation (DESI, this report) of the property located at 266 Longueville Road, Lane Cove, NSW (the site) to document any potential environmental liabilities that are apparent from a comprehensive desktop study, soil and groundwater assessment as part of a development application for a proposed high density retirement village.

LRM understands that the site is proposed to be developed as high density retirement living with two level basement car parks below the building footprint with open spaced areas to the northern aspect as the building does not occupy the entire site lot. The open space areas consist of existing trees and landscaping planted on natural ground to the north east and north western corners and the central north section also some planted areas on concreted where above basement generator and equipment rooms. The western edge will have a retaining wall interface with the retained forested area outside of the development boundary and will be backfilled with imported clean material and landscaped. The building is seven levels in total with interspaced courtyards. Appendix A shows the site location and feature plans. The below is a figure detailing the boundaries of the site for the purposes of the investigation.

***Figure 1: Site Development & Assessment Boundary***



# 2.0 ASSESSMENT OBJECTIVES AND SCOPE

## 2.1 Assessment Objective

The objective of the preliminary investigation was to obtain and assess historical information pertaining to the site and its previous use, conduct a detailed site inspection to locate any potential sources of soil and groundwater contamination both on and off-site and present these findings in a report that meets council and audit process requirements.

The objectives of this investigation are as follows:

- Characterise site soil and groundwater conditions;
- Satisfy council DA conditions for a Stage 2 Detailed Site Investigation Report (as per the NSW EPA's Guidelines for Consultants Reporting on Contaminated Sites);
- A single report detailing the location, type and level of contaminants, compiling all relevant information which details soil and groundwater sampling and testing to date;
- Identify the potential for migration of contaminants off site;
- Provide a statement that the site will be suitable upon remediation for the development proposed;
- Comply with State Environmental Planning Policy 55 – Remediation of Land;
- Comparison of results against the adopted NEPM criteria;
- Compliance with NSW EPA guidance;
- To inform and guide the Remediation Action Plan (RAP) to be enacted during the site redevelopment process;
- Provide all analytical data in summarised tables and provide all other relevant data in the form of a detailed environmental site assessment report for the environmental auditor to consider as part of their audit of the site; and
- The development of an appropriate waste classification for excavated soils in accordance with NSW EPA Waste Classification Guidelines - Part 1: Classifying waste.

## 2.2 Scope

LRM Global was engaged by Australian Unity Ltd to complete a Preliminary Environmental Site Assessment (PESA) and subsequent Stage 2 – Detailed Environmental Site Investigation (DESI) of the property located at 266 Longueville Road, Lane Cove, NSW comprising of the following works:

**Stage 1 PESA Scope:**

- A review of available site records held by property representatives;
- A detailed review of available files, data and other records maintained by regulatory authorities (i.e. Local Council, trade waste authority and EPA);
- Inspection of historical aerial photography;
- Historical title search to first private ownership;
- Site reconnaissance by a qualified environmental consultant;
- Review of previous consultant reports prepared for the site;
- Comparison of results against the adopted NEPM criteria;

- Compliance with NSW EPA guidance;

**Stage 2 DESI Scope:**

- Conduct a supplementary soil and groundwater assessment to determine the contamination status of the sites subsurface;
- Determine if any soil or groundwater contaminants are at concentrations which pose an adverse human health or environmental threat to the existing and / or proposed land-use;
- Assess the data collected from the sampling and analysis program against policies, regulations, guidelines and standards currently adopted in the state of New South Wales. Data exceeding the appropriate requirements is evaluated in terms of the risks posed by the contamination and remedial measures to be undertaken to minimise those risks;
- Drilling and installation of 3 groundwater monitoring wells on-site;
- Soil sampling across the accessible areas of the site, target depth 12.5m;
- Collection of soil samples from fill and natural material encountered during drilling;
- Logging of monitoring well construction bores and soil bores;
- Surveying and development of monitoring wells prior to sampling works;
- Gauge, purge and collect groundwater samples from 3 groundwater monitoring wells;
- Engagement of NATA accredited laboratories for sample analysis;
- Completion of detailed environmental site assessment and soil disposal classification reports; and
- Inform the development of a RAP.

# 3.0 SITE IDENTIFICATION

The site is located at 266 Longueville Road, Lane Cove, NSW and is accessible from this street only.

***Table 1: Site Identification Information***

| | | |
|---|---|---|
| **Site address** | 266 Longueville Road, Lane Cove | |
| **Site Identification** | Bowling Club | |
| **Total site area** | Approximately 9,000 $m^2$ | |
| **Municipality** | Lane Cove Municipal Council | |
| **Development Application Number** | DA/117/2017 | |
| **Zoning** | High Density Residential R4 (Development area) Environmental Conversation E2 (eastern side), Riparian Land | |
| **Current Title** | Lot 1 | DP 1227921 |
| **Current owner** | Lane Cove Council | |
| **Current Title** | Lot 1 | DP 321353 |
| **Current owner** | Lane Cove Council | |

The site location plan is presented as Figure 2, Appendix A.

The proposed development plans are provided as Figures 10, Appendix A.

# 4.0 STAGE 1– PRELIMINARY ENVIRONMENTAL SITE ASSESSMENT

## 4.1 Site and Regional Setting

The following sections detail the site zoning, regional setting, and historical information.

### *4.1.1 Land use Zoning*

The Lane Cove Local Environmental Plan 2009 Land Zoning Maps indicated that the site is Zoned B4 High Density Residential. The immediate general surrounds are zoned R2 Low Density Residential and E2 Environmental Conservation to the east which is defined as Riparian land.

The three relevant Planning Certificates under Section 10.7 Environmental Planning and Assessment Act 1970 are included in Appendix B. These replace the former named Section 149 Certificates.

- The certificates note that the land is not subject to a management order within the definition of the Section 59(2) of the Contaminated Land Management Act 1997;

- The certificates note that loose fill asbestos was used in residential homes in the local government area;
- The certificates note that the land is subject to a Tree Preservation Order; and
- The land is currently under an overland flow study to determine exact locations subject to inundation.

The Lane Cove Local Environmental Plan (LEP) 2009 applies to the land, this includes following plans;

- Lane Cove LEP, Land Reclassification Map – Sheet RPL_004 (Figure 11)
- Lane Cove LEP, Land Zoning Map – Sheet LZN_004 (Figure 12)
- Lane Cove LEP, Env Protection and Riparian Land Map – Sheet CL1_004 (Figure13)

The area to the west of the site within the riparian zoning on the LEP plan and is outside of the development boundary. The regional Lane Cove zoning map is Figure 14 in Appendix B

The LEP zoning plan maps are presented in **Appendix B**.

### *4.1.2 Local Topography*

The site and surrounds slope significantly to the east as they fall away to the adjacent Gore Creek and golf course. The West side of the site is most elevated with the small partially bitumen covered car park, falling away slightly to the east to the first bowling green, with a significant drop west to the second bowling green and further dropping away to the north to the treed area.

A local topographic map is included as Figure 15 within **Appendix B** for reference.

### *4.1.3 Nearby Sensitive Receptors*

The site reconnaissance did not reveal evidence of water pooling or seepage. The nearest sensitive receptor to the site is judged to be predominantly via surface run-off directed towards off-site municipal storm water drains, Gore Creek and Tambourine Creek, Lane Cove River and Woodford Bay, Parramatta River and ultimately Sydney Harbour.

The primary receiving water body for groundwater and surface runoff from the site is Gore Creek which runs immediately along the eastern boundary of the site. Gore Creek Reserve is located downstream of the site and is a recreational reserve. Lane Cove Gore Creek walking track also generally follows the watercourse from near the Pacific Highway to Lane Cove River. Aquatic ecosystems and aesthetic considerations are of primary concern and potentially secondary contract recreation and primary contact recreation, although are no longer considered common practice in the area.

### *4.1.4 Regional Geology*

The Geological Survey of New South Wales, Sydney Map Sheet 1:100,000 (Sheet 9130) shows the site is underlain by the Middle Triassic Age ‘Hawkesbury Sandstone’ which comprises medium to coarse grained quartz sandstone with minor shale and laminate lenses. The regional geology map is presented as Figure 16 within **Appendix B.**

The soil landscapes are defined as being to the central and west of site as Lucas Heights, Residual and the eastern portion as Deep Creek Alluvial. The soil landscapes map is presented as Figure 18 within **Appendix B**.

### *4.1.5 Underground Utilities and UPSS*

At this stage no evidence of Underground Petrol Storage Systems (UPSS) have been identified on or associated with the site. Should any be discovered, the UPSS Regulation – Sensitive Zones Map for the Lane Cove Municipal Council indicates that the site and surrounding area is located north of and not within a 'Sensitive Zone'. The sensitive zone map is included as Figure 26 for reference should a UPSS be identinfied.

A 'Dial Before You Dig' search has been conducted to determine the presence of underground utilities which may act as a preferential pathway for any potential contamination migration both onsite and offsite. Plans will be included within the DESI Report currently underway.

Figure 17 includes the relevant DBYD search outputs for the site.

### *4.1.6 Acid Sulphate Soils*

The Lane Cove Environmental Plan 2009 Acid Sulphate Soils Map Sheet ASS_004 indicates that soils on the site and in the surrounding area not at risk of Potential Acid Sulphate Soils (PASS).

See attached Figure 25, **Appendix B.**

### *4.1.7 Local Hydrology and Nearby Groundwater Bores*

The hydrogeology maps of Australia indicate that aquifers on-site and surrounding are porous, extensive aquifers of low to moderate productivity.

The Bureau of Meteorology Australian Groundwater Explorer was used in an attempt to search for nearby hydrogeological records for registered groundwater wells in the area.

There are no identified historical groundwater bores on the site.

There were 5 groundwater wells identified during the search within a 500 m radius of the site. There are 4 monitoring wells located 142 – 153 m south of site clearly associated with the ongoing assessment of the service station. One irrigation/ monitoring bore was also identified 135 m south east of the site at a depth of 24 m, this is likely associated with the golf course. Refer to **Appendix B** Figure 23 for surrounding groundwater bore location plan.

### *4.1.8 Aerial Photographs*

As part of the desktop site history brief, aerial photographs of the site and surrounds from 1943, 1951, 1955, 1961, 1965, 1970, 1982, 1991, 2002, 2009, and 2014 were and reviewed. The findings of which are summarised below and copies are provided in **Appendix B.**

**1943**

The site appears to be vacant and vegetated to the central and east sides with trees. Some walking tracks are evident, as are residential dwellings immediately on the north boundary of the site and across Longueville Road.

**1951**
The site and surrounds remain relatively unchanged since the 1943 aerial photograph. One additional building has been constructed to the immediate southern boundary of the site and appears to be residential in nature.

**1955**
The site and surrounds remain relatively unchanged since the 1951 aerial photograph. Adjacent structures do not appear to have changed either.

**1961**
The first bowling green has been developed on the site to the western edge along with the car park, and the building that serves as the current club house has also been constructed on the southern boundary. The central and eastern portions of the site still remain vegetated.

**1965**
The majority of the vegetation has been cleared, the second Bowling Green to the east of the site has been constructed and evidence of the golf course development to the east is also present. The onsite building remains visually unchanged.

**1970**
The site and surrounds remain relatively unchanged since the 1965 aerial photograph. Onsite structures do not appear to have changed, however the apartment block to the south appears to be under or near completion.

**1982**
The site and surrounds remain relatively unchanged since the 1970 aerial photograph. Onsite structures do not appear to have changed however the apartment block to the south boundary is completed.

**1991**
The site and surrounds remain relatively unchanged since the 1982 aerial photograph.

**2002**
The site and surrounds remain relatively unchanged since the 1991 aerial photograph.

**2009**
The site and surrounds remain relatively unchanged since the 2002 aerial photograph.

**2014**
There is no significant change from the 2009 aerial photograph of the site.

***Aerial Photograph Summary***

The aerial photograph review revealed that the site has been used for a bowling green from as early as 1961 and was vacant before that.

The surrounding area has typically been residential, with a shopping strip and service stations to the south, also as early as the 1940s. Historical land titles, plans and business listings have been assessed in conjunction with aerial photographs to identify site occupants.

### *4.1.9 Historical Land Title Review*

A review of the historical land titles pertaining to the site was undertaken in order to determine all site owners, their occupations and the dates to which they occupied the site. A summary of the site occupants is presented below while copies of the full title search records are attached in **Appendix B**.

***Table 2A: Historic Title Summaries***

| Year | Proprietor |
|---|---|
| **(Lot 1 DP 1227921)** | |
| 2017 – current | Lane Cove Council |
| | **(Lot 322 DP 1102537)** |
| 2006 – 2017 | Lane Cove Council |
| | **(Part Portion 322 Parish Willoughby – Area 3 Acres 35 ¾ Perches – CTVol 4337 Folio 52)** |
| 1958 – 2006 | Council of the Municipality of Lane Cove |
| 1956 – 1958 | The Cumberland County Council |
| 1948 – 1956 | Dorothy Muriel Macdougall, spinster |
| 1929 – 1948 | Ettie Emma Jane Macdougall, spinster |
| | **(Part Portion 322 Parish Willoughby – Area 3 Acres 2 Roods 20 Perches – CTVol 3098 Folio 92)** |
| 1920 – 1929 | Ettie Emma Jane MacDougall, spinster |
| | **(Part Portion 322 Parish Willoughby – Area 3 Acres 2 Roods 20 Perches – CTVol 1928 Fol's 58, 60 & 62)** |
| 1908 – 1920 | Frank Winter, modeller<br>Leonard Winter, modeller<br>Louise Heckenberg, wife of Casper Heckenberg |

| | |
|---|---|
| | **(Part Portion 322 Parish Willoughby – Area 3 Acres 2 Roods 20 Perches – CTVol 1120 Folio 249)** |
| 1907 – 1908 | Leonard Winter, modeller<br>Thomas Good fellow |
| 1894 – 1907 | Leonard Winter, modeller |

**Title Tree**

Lot 1 DP 1227921

Folio Identifier 1/1227921

Folio Identifier 322/1102537

Certificate of Title Volume 4337 Folio 52

Certificate of Title Volume 3098 Folio 92

Certificate of Title Volume 1928 Folio's 58, 60 & 62

Certificate of Title Volume 1120 Folio 249

***Table 2B: Historic Title Summaries***

| Year | Proprietor |
|---|---|
| **(Lot 1 DP 321353)** | |
| 1988 – current | The Council of the Municipality of Lane Cove |
| | **(Lot 1 DP 321353 – Area 1 Rood 24 ¼ Perches – CTVol 4200 Fol 204)** |
| 1957 – 1988 | The Council of the Municipality of Lane Cove |
| 1928 – 1957 | The Commonwealth of Australia |
| | **(Part Portion 322 Parish Willoughby – Area 3 Acres 2 Roods 20 Perches – CTVol 3098 Folio 92)** |
| 1920 – 1928 | Ettie Emma Jane MacDougall, spinster |
| | **(Part Portion 322 Parish Willoughby – Area 3 Acres 2 Roods 20 Perches – CTVol 1928 Fol's 58, 60 & 62)** |

| | |
|---|---|
| 1908 – 1920 | Frank Winter, modeller<br>Leonard Winter, modeller<br>Louise Heckenberg, wife of Casper Heckenberg |
| | **(Part Portion 322 Parish Willoughby – Area 3 Acres 2 Roods 20 Perches – CTVol 1120 Folio 249)** |
| 1907 – 1908 | Leonard Winter, modeller<br>Thomas Goodfellow |
| 1894 – 1907 | Leonard Winter, modeller |

**Title Tree**

Lot 1 DP 321353

Folio Identifier 1/321353

Certificate of Title Volume 4200 Folio 204

Certificate of Title Volume 3098 Folio 92

Certificate of Title Volume 1928 Folio's 58, 60 & 62

Certificate of Title Volume 1120 Folio 249

According to the land titles search the site has been occupied from as early as 1894. Lot 1 DP 1227921 (the main part of the site) came under Lane Cover ownership in 1956, and prior to that was in private hands. Lot 1 DP 321353 (the North West corner) came under Lane Cove Council ownership in 1928, and was also in the same private ownership prior to that.The title search indicates site ownership but not necessarily site occupancy.

### *4.1.10 Historic Plans*

Three historical maps were reviewed, the 1917 Commonwealth 1:63360 Sheet 423 does not reveal any significant information for the site location. The 1949 update of this plan also does not reveal any significant data and shows road as per the UBD listings. The 1975 plan shows information as consistent with the aerial imagery and UBD listings.

Copies of the plans reviewed are presented within Figure 19 **Appendix B**.

### *4.1.11 Historic Business Listings*

A search of the Sydney UBD Business Listings for the site address was conducted on the listings produced in 1950, 1965, 1970, 1975, 1978, 1982, 1986 and 1991. The listings provide details relating to the business name, address and activities. Details of the business occupying the site address are listed within Table 3. The findings of the business directories are relatively consistent with the historic title search results indicating that the site throughout its history has been occupied by the Ladies Bowling Club from as early as 1965 and prior to that as unlisted. UBD listings are detailed in full in **Appendix B** and Figure 24.

*Table 3: UBD Business Listing Site Occupancy and Adjacent Significant Summary*

| Year | Business name and Address | Business Activity |
|---|---|---|
| 1991 | Caltex Northwood Service Station<br>10 Northwood Rd | Service Station<br>73m south |
| 1986 | Calico Northwood Service Station<br>10 Northwood Rd | Service Station<br>73m south |
| | **Lane Cove Women's Bowling & recreation Club<br>On-Site** | **Bowling Club** |
| 1982 | **Lane Cove Women's Bowling & recreation Club<br>On-Site** | **Bowling Club** |
| 1978 | Caltex Northwood Service Station<br>10 Northwood Rd | Service Station<br>73m south |
| | **Lane Cove Women's Bowling & recreation Club<br>On-Site** | **Bowling Club** |
| | BP Northwood Service Station<br>6 Kenneth Street Norwood | Service Station<br>117m south |
| 1975 | Pascate, L & M. Service Station<br>10 Northwood Rd | Service Station<br>73m south |
| | **Lane Cove Women's Bowling & recreation Club<br>On-Site** | **Bowling Club** |
| 1970 | Partners Service Station<br>10 Northwood Rd | Service Station<br>73m south |
| | **Lane Cove Women's Bowling & recreation Club<br>On-Site** | **Bowling Club** |
| 1965 | **Lane Cove Women's Bowling & recreation Club<br>On-Site** | **Bowling Club** |
| | Radke, W. H. & Co. Motor Garage<br>8 Kenneth Street | Service Station and Engineers<br>117m south |
| 1950 | Longueville Service Station<br>Cnr Norwood and Kenneth Streets | Service Station<br>88m south |
| | Floyd, A. L. Pleazing Products<br>5 Northwood Road | Furniture and Toy Manufactures<br>148m south |
| | Radke and Dennis<br>6 Kenneth Street | Service Station<br>117m south |

### *4.1.12 Council Records Review*

A request for information was submitted to the Lane Cove Council to retrieve any significant or relative records pertaining to the site. No significant information was available outside of the LEP records already obtained.

# 5.0 ENVIRONMENTAL RECORDS REVIEW

Figures 20 – 22 in Appendix B are present in relation to the following searches.

## 5.1 NSW EPA DECCW Contaminated Land Database (epa.nsw.gov.au)

A search of the NSW EPA DECCW Record of Contaminated Land Notices Database established under Part 3 of the Contaminated Land Management Act 1997 found no records for the site. Details for sites located within 500 m of the site are presented within Table 4 below:

A search of the NSW EPA DECCW List of NSW contaminated sites (current as of July 2017) notified to EPA under Section 60 of the Contaminated Land Management Act 1997 found no records for the site. Details for sites located within 500 m of the site are presented within Table 4 below:

A search of the public register established under Section 308 of the Protection of the Environment Operations Act 1997 found no records for the site. The surrounding sites listed on the register (disregarding surrendered or ceased licences) are summarised in the table below.

***Table 4: List of NSW Contaminated Sites Notified to the EPA***

| Address | Site Name | Contamination Activity Type | Management Class | Distance from site |
|---|---|---|---|---|
| 5 – 7 Northwood Road, Lane Cove | Caltex Service Station | Service Station | Under Assessment | 135 m south |

## 5.2 SafeWork Search

A safework search was conducted and the letter included in Appendix B. No records were identified.

## 5.3 Protection of Environment Operations Act 1997 Public Register

A search of the public register established under Section 308 of the Protection of the Environment Operations Act 1997 found no records for the site or on land within 500 m. The surrounding sites listed on the register within 500 m are limited to surrendered or ceased licences and are summarised in the table below.

***Table 5: Surrounding Sites Listed on the Protection of Environment Operations Act 1997 Public Register***

| Address/ Location | Organisation Name | Licenced Activity & Status | Distance from site |
|---|---|---|---|
| Waterways throughout NSW | Sydney Weed & Pest Management Pty Ltd | Surrendered: Other activities / Non Scheduled Activity – Application of Herbicides | 48 m east |

| | | | |
|---|---|---|---|
| Waterways throughout NSW | Luhrmann Environment Management Pty Ltd | Surrendered: Other activities / Non Scheduled Activity – Application of Herbicides | 48 m north |
| Waterways throughout NSW | Robert Orchard | Surrendered: Other activities / Non Scheduled Activity – Application of Herbicides | 48 m north |

## 5.4 Contaminated Land and Waste Management Facilities

There are no identified waste management facilities within 500 m of the site. One waste transfer station (Weir Minerals Australia Ltd, licensed activity under POEO Act) was identified approximately 1km away to the north east, too far away to be considered significant in the context of potential off-site impacts.

The NSW contaminated land lists on site 135 m to the south, a Caltex Service Station at 5-7 Longueville Road. This site is currently under assessment.

## 5.5 EPA PFAS Investigation Program

No records for this site or surrounds were identified. PFAS has been added as a potential contaminant of concern due to the unknown nature of the sites fill material.

## 5.6 Previous Site Geotechnical and Environmental Reports

An executive summary extract of the below reviewed reports and documents along with bore logs and cross sections is included within **Appendix F.** Full reports are available upon request.

**SMEC Australia Pty Ltd, *266 Longueville Road, Lane Cove, Geotechnical and Environmental Investigation Report,* December 2011**

A site report at 266 Longueville Road was conducted in December 2011, by SMEC Australia Pty Ltd (Consulting Geotechnical and Environmental Engineers) for the Lane Cove Municipal Council.

The purpose of the investigation was to provide advice on the sub-surface conditions of the land that may be relevant to future redevelopment and also to assess the potential for human health and environmental exposures at the property due to chemical contaminants in the soil. The scope of the environmental component of the investigation included a site inspection and a review of the land use history, as well as a preliminary soil sampling program.

The soil samples were collected from a total of 15 boreholes drilled at evenly spaced locations as access allowed across the site in November 2011. The soil sampling locations are shown on Figure 3 from SMEC's December 2011 report, which is attached to this report, and the soil profile logs providing a description of the fill encountered and soil samples collected is provided in Appendix F. The methodology by which the samples were collected is described in SMEC's December 2011 report.

The soil samples collected were initially analysed for a broad screen of potential chemical contaminants including heavy metals, polycyclic aromatic hydrocarbons (PAH), total petroleum hydrocarbons (TPH), monocyclic aromatic hydrocarbons (BTEX), polychlorinated biphenyls (PCB), organochlorine pesticides (OCP), organophosphorus pesticides (OPP), phenolic compounds, fluoride, cyanide and asbestos. However, in order to further classify the soil selected samples were subsequently tested for leachable lead, nickel and PAHs in January 2012.

**Site Geology**

The Geological Survey of NSW 1:100,000 Sydney Geological Map (Sheet 9130) shows that the site is underlain by the Middle Triassic Age 'Hawkesbury Sandstone' which comprises medium to coarse grained quartz sandstone with minor shale and laminate lenses. The natural soils encountered during the investigation comprised silty sand topsoil overlying silty and sandy clay subsoil, which are consistent with in-situ weathered soils derived from the Hawkesbury Sandstone formation. Sandstone bedrock was also encountered in each of the 15 boreholes at depths of between 0.2 m and 8.6 m below the ground surface, and depth to bedrock was greatest in the eastern portion of the site. A layer of fill material between 0.2 m and 8.6 m in thickness was also observed at each sample location. The fill is heterogeneous, comprising sands, gravels and clays, and fragments of anthropogenic wastes including bricks, ash, ceramics and glass were observed in the fill at a number of borehole locations.

**Site Hydrogeology**

A search of the Department of Natural Resources (DNR) groundwater database was performed to identify groundwater wells in the proximity of the site. The search identified a total of eight registered groundwater monitoring wells located within 2 km of the site. Out of the eight wells five are registered for 'monitoring' purposes, two are registered as irrigation bores and the last is registered for 'domestic' purposes.

The aquifer lithology is reported to be sandstone with the database information showing that multiple aquifers are likely to be present in the sandstone bedrock. Aquifer depths in the wells (where reported) are stated as being between 4 m and 144 m below the ground surface with the depth to groundwater in the closest bore to the site (150 m South-east) being approximately 16.8 m below ground level. Additionally, perched groundwater was encountered at the soil/rock interface in multiple boreholes drilled on the site between the depths of 2.0 m and 8.5 m.

**Results**

The results of the investigation showed that the concentrations of chemical contaminants measured in the soil samples retrieved from the site are generally low and below criteria that are protective of human-health for recreational and also standard and high-density residential land use settings. However, the fill in the east of the site below 1.5 m depth was found to be impacted with lead and polycyclic aromatic hydrocarbons (PAHs) at concentrations which exceed the relevant health-based criteria.

Bore logs and cross sections indicate clearly the increasing fill layer depth heading from west to east, and the level of the natural sandstone beneath.

Elevated concentrations of lead (640 mg/kg to 7 300 mg/kg), total PAH (27 mg/kg) and the PAH species benzo(a)pyrene (1.1 mg/kg to 3.2 mg/kg) were measured in several samples of fill material retrieved from the bowling green area in the east of the site. These concentrations are above the SIL (Column 1) criteria for these analytes. The lead and benzo(a)pyrene concentrations in several samples are also above their respective SIL (Column 3) criteria. Further, the lead concentrations in two samples exceed the SILs (Column 2) criteria. That is, the site could potentially present a risk to human-health for the existing recreational use and also for high and low density residential land use settings where exposure pathways exist.

The concentrations of lead (640 mg/kg to 7 300 mg/kg), mercury (1.2 mg/kg to 3.0 mg/kg) and zinc (220 mg/kg to 820 mg/kg) measured in the soil at a number of locations on the site are above the PILs for these metals of 600 mg/kg, 1 mg/kg and 200 mg/kg respectively. The PILs are criteria which are designed to be protective of plant health within an urban setting.

The sample locations plan, cross sections and bore logs have been included in Appendix F

The full report can be provided upon request.

**SMEC Pty Ltd, Soil Sampling and Classification Program, Land at 266Longueville Road, Lane Cove, January 2012.**

SMEC as part of a combined geotechnical and environmental investigation provided soil disposal advice for in-situ soils. This investigation showed that due to the presence of anthropogenic materials throughout the imported soils across the site, the imported soils had no prospect for off-site re-use as 'Clean Fill' and as such disposal to landfill was appropriate. The purpose of this report was to determine the waste category of the soils at 266 Longueville Road Lane Cove.

SMEC as part of their combined investigation drilled 15 boreholes across the site and took samples at strategic depths at each. Soil chemistry results were compared to NSW EPA Waste Classification Guidelines and exceedances noted. Lead, nickel and benzo(a)pyrene were noted as contaminants of concern. All samples exceeding the GSW threshold were analysed for TCLP to characterise the mobility of the contaminants of concern. Samples analysed using TCLP for benzo(a)pyrene were all below detection. Nickel and lead were detected in samples analysed using TCLP however only sample BH11_4.3-4.5 exceeded TCLP criteria.

As such SMEC determined the site was classified as General Solid Waste with the exception of a 'hotspot' BH13 which was classified as Restricted Solid Waste under the prevision of General Immobilisation Approval 2009/07. It was suggested that the extent of the hotspot was unknown and further investigation to delineate could determine this.

**Applied Ecology Pty Ltd, *Flora, Fauna & Fungi Impact Assessment for a proposed development site at 266 Longueville Road*, January 2012, for Lane Cove Municipal Council.**

The purpose of the investigation was to provide a flora, fauna & fungi impact assessment as part of the proposed development at 266 Longueville Road, Lane Cove, NSW. The development of an apartment is being considered for the western part of 266 Longueville Road. Development of the apartment will not extend down the wooded slopes and the golf course on the eastern part of the site. Council is investigating the possibility of a new walking track through the existing bushland to link this site with the Lane Cove Country Club. Prior to any development of the proposal, Council requires to understand the ecological attributes of the immediate area. The scope of the investigation included identification of flora, fauna & fungi species present on the subject/adjacent sites, conservation value of the species and communities identified, analysis of the likely significance of impacts of a future residential development and identification of specific design measures that may be incorporated into development to ameliorate impacts towards the native flora, fauna and fungi.

**Flora**

Searches conducted on the NSW Wildlife Atlas (www.bionet.nsw.gov.au), PlantNet (www.rbgsyd.nsw.gov.au), and EPBC Act database (www.environment.gov.aul) revealed a total of 10 different threatened flora species reported in the Lane Cove area or within 5km of the study site. A similar search was conducted for Endangered Ecological Communities which revealed three vegetation communities listed for the area. These communities included the Blue Gum High Forest, Coastal Saltmarsh and the Hygrocybeae community.

**Fauna**

Applied Ecology Pty Ltd opted for passive techniques that involved no handling of animals or traps which may be prone to tampering and theft in urbanised areas endangering both the animals and integrity of the investigation. Various methods were utilised to identify native fauna occupying the targeted/surrounding sites. The various methods included two searches conducted on NSW Wildlife Atlas and EPBC Act database, spotlighting survey, call playback, bat ultrasonic call recordings, diurnal bird census and a Herpetofauna search. The Atlas searches revealed a total of eight threatened fauna species reported for this area.

**Fungi**

Applied Ecology Pty Ltd conducted an Atlas search and field survey to identify various fungi species native to the site. The Atlas search revealed a total of nine threatened species of fungi reported in the area. One endangered fungi community, the Hygrocybeae community of Lane Cove Bushland Park was also recorded. The field survey was undertaken over a period of over 2 hours, totalling 10 hours of searching.

**Conclusion**

Based on these results Applied Ecology Pty Ltd provided identification of key threats for the threatened and endangered species of flora, fauna and fungi.

- Reduction in food resources for Powerful Owls by affecting numbers of ringtail possums, or reducing feeding, roosting and breeding habitat for ringtail possums and increasing predation by domestic cats in the area. This has been identified has a key threat for this species.
- Reduction in food resources for Grey-headed Flying Foxes by reducing the quality and/or extent of bushland in the area. This has been identified as a key threatening process for this species.
- Reduction in floristic diversity in Coastal Enriched Sandstone Moist Forest in the area by clearing or changing conditions in surrounding areas.
- Reduction in extent of good quality vegetation in CESMF through invasion of weed species.
- Reduction in condition of CESMF through runoff from proposed development site.
- Reduction in condition of CESMF through sediment deposition during building on proposed development site.

To assist in the mitigation of impacts of the development, Applied Ecology Pty Ltd provided specific measures to reduce and offset impacts. A list of these measure are dot pointed below.

- Choice of suitable plant species for landscaping clearly outlined as part of the development approval.
- Ongoing weed management as part of comprehensive bush regeneration plan for the E2 zone.
- Management of soil stability on slopes below the bowling green area by staged weed removal, stabilisation and revegetation as required.
- Staged removal of shrub layer weeds to retain habitat elements.
- Offset weeds that provide possum food by planting suitable native species.
- Provide supplementary nesting site (e.g. nest boxes) for possums to ensure ongoing food supplies for Powerful Owls.
- Plant native species that provide food resources for Grey-headed Flying Foxes.
- Manage access by developing formals path(s)

- Management of runoff from development site to reduce impacts from changed water quality and quantity.
- Supplementary fungi survey in autumn to confirm presence/absence of threatened fungal species
- Management of pedestrian access through the site and adjoining reserve area. Existing track alignments indicate current usage patterns (Figure 25), and provision of formal walking tracks should reflect these (Figures 22-24). Raised steps are recommended for steeper areas to reduce potential erosion impacts. Given the general lack of suitability of the habitat for *Hygrocybe* fungi, the remainder of the track route should be clearly delineated, but should remain a "natural" bush track.

The full list of identified species of flora, fauna and fungi can be found in full report which can be provided upon request.

**Arcadis Australia Pacific Pty Ltd, *266 Longueville Road, May 2017*, for Australian Unity Limited.**

The purpose of the investigation was to provide land restoration services on the sub-surface of the land as part of the development of 266 Longueville Road, Lane Cove, NSW. Historical third party environmental reports for the site indicated the presence of polyaromatic hydrocarbons (benzo-a-pyrene) and heavy metal (lead and nickel) contamination on the site associated with historic filling. The preliminary waste classifications of General Solid Waste (estimate 11,350 $m^3$) and Restricted Waste (estimate 6,000 $m^3$) were potentially resulting in particularly high disposal costs if not further assessed and managed. The proposed scope of the investigation included insitu waste assessment and reporting, remediation planning/supervision, review of sustainable soil waste disposal sites and site validation.

An indicative cost estimate was undertaken by Environmental Strategies Pty Ltd in collaboration with Arcadis Australia Pacific Pty Ltd. Environmental Strategies Pty Ltd had not undertaken any preceding investigations at the site therefore previous third party geotechnical and preliminary site investigation/insitu waste classification reports prepared by SMEC testing in 2011-2012 provided analytical data with respect to the presence of contamination and waste associated with the historic filling of the site.

**Statistical Analysis and Waste Assessment Review**

Statistical analysis and waste assessment review of the SMEC (2012) sample data was undertaken to assist with management and remediation estimates. Two statistical reviews were performed in accordance with the NEPM 1999 (2013) Assessment of Contamination Guidelines and NSW EPA (2014) Waste Classification Guidelines utilising the application of 95% UCL with the sample data set under two different scenarios – without removal of identified soil 'hotspots' and with removal of soil 'hotspots'.

Statistical review 1 calculated the 95% Chebychev (Mean, Sd) UCL targeting the lead, benzo(a)pyrene, and nickel in site fill without the removal of identified soil 'hotspots'. The results identified Fill soils were assessed to be General Solid Waste (GSW) at all boreholes with the exception of BH13 which was assessed to be either Restricted Solid Waste (RSW) or Hazardous Waste subject to a General Immobilisation Approval being granted by the EPA for the disposal of ash and/or slag material.

Statistical review 2 followed the same methodology but assumed remediation by physical removal of the hotspots identified at BH11, BH12, BH13 and BH15 in the eastern portion of the site. The results indicated that further delineation of the fill soils is required at BH11, BH12, BH13 and BH15 prior to undertaking localised excavation and offsite disposal of materials. Additionally, it confirmed that all remaining fill soil could be classified as Excavated Natural Material (ENM) in accordance with Protection of the Environment Operations (Waste) Regulation 2005 – General Exemption Under Part 6, Clause 51 and 51A "The excavated natural material exemption 2008."

**Conclusion**

In providing this advice, Environmental Strategies Pty Ltd concluded with two potential remediation strategies which were offsite disposal and onsite containment. Offsite disposal of excavated materials and waste offered Australian Unity long term certainty of outcome, no ongoing management of contamination and a reduced timeframe for remediation. The cost estimate was broken up into three scenarios based on the estimated volumes associated with the contaminant hotspots.

The onsite containment remediation strategy provided Australian Unity with a sustainable remediation alternative while still mitigating any human health and environmental risk to future occupants of the site. Environmental Strategies believed that the General Solid Waste and Restricted Solid Waste material could be safely encapsulated onsite ensuring removal of any exposure pathways to the contamination and a low likelihood of leachability. Installation of the on-site waste material encapsulation cell would be under the proposed car parking area and would be managed under an Environmental Management Plan (EMP).

# 6.0 SITE RECONNAISSANCE

Jon Lawson of LRM Global undertook an initial site visit and walk-through of the accessible areas of the property on 14th June 2017 along with Brad May (Environmental Auditor, Epic Environmental).

**General Site Condition and Surrounding Area**

The entirety of the site's surface could not be inspected due to access limitations relating to both vegetation and slope. No access was gained to the club house however it was not considered significant nor a source of potential contamination.

The surrounding area consisted of residential land use to the north and south, a strip of remnant forest, Gore Creek and golf course to the east. To the west is Longueville Road. A commercial area of shops exists to the north and south along Longueville Road.

- The site is fenced on the northern side with the adjacent residential properties and unfenced on all other boundaries.
- Soil stability is generally good as all surfaces are either grassed or heavily vegetated. Stability to the eastern and northern edge of the lower Bowling Green is less clear due to significant steep slope and vegetation and is likely to have potential for erosion and instability.
- No visible signs of plant stress were evident. Refer to Applied Ecology Report XXx

- No visible evidence of waste drums, fuel storage tanks of associated infrastructure was evident.
- No obvious odours were noted during walkovers and no visible signs of surface contamination, staining, discoloration, bare soil or stressed vegetation.
- The current site building is unused but remains in good condition and is still secured against unauthorised access.
- During site inspections and drilling / sampling works no visible surface waters were observed.
- There is no evidence of flood potential or historical flooding at the site.

**Past and Current Site Uses**

There is no evidence of any previous site use, buildings, structures or remnant infrastructure. The site is currently divided into two bowling greens, club house, car parking and landscaped areas. The previous in-filled nature and dumping on the site prior to its development is evident. Building and general demolition waste is observable on the battered slopes of the bowling greens and towards the north and east side forested areas.

**Potentially Contaminating Sources**

No other potential sources of contamination were evident onsite or nearby during the site walk over inspection of accessible parts of the site including gatics, triple interceptor traps or evidence of aboveground or underground storage tanks, chemical storage, bunded areas, septic systems, heating oil tanks, or industrial wastes.

Significant in-filling is evident across the site along with mixed household and demolition wastes. This was visually evident to the battered sides of the bowling greens beneath and intermixed with the sites vegetation. It also is observable spilled down to the eastern edge of the site and further into the riparian zone.

The nearest service station is located approximately 50m to the south, cross and down hydraulic gradient.

**Asbestos**

Suspect asbestos containing materials were noted during the site inspection and considering the in-filled nature of the site, asbestos is considered a contaminant of concern. The club house will undergo an asbestos audit prior to demolition and if required asbestos removal works and associated clearances will be conducted.

# 7.0 CONCEPTUAL SITE MODEL

The conceptual site model is derived from the findings of the preliminary site assessment report for the site completed by LRM which are incorporated into this report.

## 7.1 Potential Sources of contamination

Certain land uses such as commercial, industrial or agricultural etc. have the potential to lead to site contamination, the degree of which is highly variable from site to site. The Department of Urban Affairs and Planning, Environment Protection Authority 1998 Publication 'Managing Land Contamination, Planning Guidelines SEPP 55 – Remediation of Land' Appendix A lists specific land uses and their likely associated risks for contaminating land. The table below lists site land uses, the potential risk said uses and the potential contaminants of concern resulting from same.

***Table 6: Potential Sources and Contaminants of Concern***

| Source | Location | Contaminants of Concern | Media | Comments / Risk Potential |
|---|---|---|---|---|
| Imported Fill Material - Regional | Entire site (levelling) | Various (commonly PAHs and heavy metals), TRH, OPP/ OCP, asbestos, PFOS / PFAS | Soil/ Groundwater | High |
| Nearby Service Station | Offsite 75m property to south | TRH/BTEX, PAH, heavy metals | Soil/ Groundwater/ Soil vapour | Low<br>Cross and down gradient |
| Bowling greens | Entire Site | OCPs, methyl mercury, OPPs | Soil | High, most likely surface soils |

## 7.2 Initial Data Gap Assessment

The following table presents a summary of the initial sampling conducted and data gap analysis in order to guide the next round of soil sampling to be conducted both for locations and analysis. SMEC initial sampling is BH1 – BH15 and the green areas are supplementary LRM sampling borehole locations BH16 – BH42.

Portions of the site will remain inaccessible due to gradient and vegetation and require further assessment following demolition and during site excavation works. This additional data is also required to determine an offsite waste disposal classification under the VENM guidelines for the materials as per the planned basement excavation.

At this stage no groundwater investigation was planned until greater site access had been achieved to reach the eastern edges of the site.

There are no current plans to assess soil vapour at the site, however, the presence of an offsite former service station to the south may warrant such investigation in the future if soil and groundwater results from site investigation works highlight a potential risk.

***Table 7: Data Gap Analyses and Sample Analysis Plan***

| Area | Location | Total depth to sandstone/ termination | Sample Depth | Analytical Suite | Impacts | Gap |
|---|---|---|---|---|---|---|
| Car park | BH1 | 0.8 | 0.2 | Metals, OCP/OPP & Asbestos | | PAH TRH |
| | BH2 | 0.2 | 0.2 | BTEX & PAH | | Metals TRH |
| | BH16 LRM | 0.8 | 0.1 | Metals, PAH, TRH & Asbestos | | |
| | | | 0.8 | Metals, PAH & TRH | | |
| | BH17 LRM | 0.8 | 0.1 | Metals, PAH & TRH | | |
| | | | 0.7 | Metals, PAH & TRH | | |
| Bowling Green 1 | BH3 | 0.4 | 0.2 | Metals | | OCP/OPP |
| | BH4 | 1.0 | 0.2 | Metals, BTEX, TRH & PAH | | |
| | | | 0.7 | Metals | | PAH |
| | BH5 | 3.3 | 1.5 | Metals, BTEX, TRH, PAH, OCP/OPP, Phenolics & PCB | | |
| | | | 2.9 | Metals, BTEX, PAH & TRH | | |
| | BH6 | 0.3 | 0.2 | Metals | | OCP/OPP |
| | BH7 | 1.8 | 0.2 | OCP/OPP, Asbestos & PCB | | |
| | BH8 | 3.55 | 0.2 | Metals | | OCP/OPP |
| | | | 1.5 | Metals, BTEX, PAH & TRH | | |
| | BH18 LRM | 0.6 | 0.1 | Metals, OCP/OPP & pH | | |
| | | | 0.6 | Metals, PAH & Asbestos | | |
| | BH19 LRM | 0.55 | 0.1 | Metals & OCP/OPP | | |
| | | | 0.5 | Metals & PAH | | |
| | BH20 LRM | 1.9 | 0.1 | Metals, OCP/OPP & pH | | |
| | | | 1.0 | Metals & PAH | | |
| | | | 1.9 | Metals, PAH & PCB | | |

| Area | Location | Total depth to sandstone/ termination | Sample Depth | Analytical Suite | Impacts | Gap |
|---|---|---|---|---|---|---|
| | BH21 LRM | 4.1 | 0.1 | Metals & OCP/OPP | | |
| | | | 1.2 | Metals, PAH & Asbestos | | |
| | | | 3.0 | Metals, TRH & PCB | | |
| | | | 4.0 | Metals & PAH | | |
| | BH22 LRM | 1.75 | .01 | Metals, OCP/OPP & pH | | |
| | | | 1.0 | Metals, TRH & Asbestos | | |
| | BH23 LRM | 1.35 | 0.1 | Metals & OCP/OPP | | |
| | | | 0.6 | Metals & PAH | | |
| | BH24 LRM | 4.0 | 0.1 | Metals, OCP/OPP, pH & TRH | | |
| | | | 1.5 | Metals, PAH & Asbestos | | |
| | | | 2.8 | Metals, TRH & PCB | | |
| House and Garden Area | BH9 | 0.2 | 0.2 | Metals & Asbestos | | OCP/OPP |
| | BH31 LRM | 1.0 | 0.1 | Metals & OCP/OPP | | |
| | | | 1.0 | Metals & PAH | | |
| | BH25 LRM | | 0.2 | Metals & OCP/OPP | | |
| | BH26 LRM | 0.6 | 0.2 | Metals & OCP/OPP | | |
| | BH33 LRM | 1.7 | 0.2 | Metals & OCP/OPP | | |
| | | | 1.0 | Metals & PAH | | |
| Bowling Green 2 | BH10 | 2.6 | 0.2 | Metals, TRH, BTEX & PAH | Nickel | OCP/OPP |
| | | | 1.3 | Metals, TRH, PAH & BTEX | | |
| | BH11 | 9.0 | 1.5 | Metals, TRH, BTEX, PAH, OCP, PCB, Phenolics & Asbestos | | |
| | | | 4.5 | Metals, TRH, BTEX, PAH, OCP & Asbestos | Lead | |

| Area | Location | Total depth to sandstone/ termination | Sample Depth | Analytical Suite | Impacts | Gap |
|---|---|---|---|---|---|---|
| | | | 8.8 | Metals, TRH, BTEX, PAH, OPP, PCB & Asbestos | | |
| | BH12 | 4.9 | 0.3 | Metals & OCP | | OPP |
| | | | 1.5 | Metals, TRH, BTEX, PAH, PCB, Phenolics & Asbestos | Lead Benzo(a) | |
| | | | 4.5 | Metals, TRH, BTEX, PAH & OCP | Lead | |
| | BH13 | 8.7 | 1.5 | Metals, TRH, BTEX, PAH, OCP, PCB, Phenolics & Asbestos | Benzo(a) | |
| | | | 4.5 | Metals, TRH, BTEX, PAH, PCB, Phenolics & Asbestos | Lead | |
| | | | 7.5 | Metals, TRH, BTEX, PAH & Asbestos | Benzo(a) Lead | |
| | BH14 | 2.1 | 0.3 | Metals & OCP/OPP | | |
| | BH15 | | 0.3 | Metals, OCP & PCB | | OPP |
| | | | 1.5 | Metals, TRH, BTEX, PAH, OPP & Asbestos | Lead | |
| | | | 4.2 | Metals, TRH, BTEX, PAH, PCB, Phenolics & Asbestos | Lead Benzo(a) | |
| Bowling Green 2 | BH27 LRM | 1.2 On concrete? | 0.1 | Metals, OCP/OPP & pH | | |
| | | | 1.0 | Metals & PAH | | |
| | BH28 LRM | 4.5 | 0.1 | Metals& OCP/OPP | | |
| | | | 2.0 | Metals & Asbestos | | |
| | | | 3.0 | Metals & PAH | | |
| | | | 4.0 | Metals, PCB & TRH | | |

| Area | Location | Total depth to sandstone/ termination | Sample Depth | Analytical Suite | Impacts | Gap |
|---|---|---|---|---|---|---|
| | BH29 LRM | 8.0 | 0.1 | Metals, OCP/OPP & pH | | |
| | | | 1.0 | Metals & PAH | | |
| | | | 2.0 | Metals & Asbestos | | |
| | | | 3.0 | Metals & PAH | | |
| | | | 4.0 | Metals & PCB | | |
| | | | 5.0 | Metals & Asbestos | | |
| | | | 6.0 | Metals & PAH | | |
| | | | 7.0 | Metals | | |
| | | | 8.0 | Metals & TRH | | |
| | BH30 LRM | 7.45 | 0.1 | Metals & OCP/OPP | | |
| | | | 1.0 | Metals & PAH | | |
| | | | 2.0 | Metals & Asbestos | | |
| | | | 3.0 | Metals & TRH | | |
| | | | 4.0 | Metals & PAH | | |
| | | | 5.0 | Metals & Asbestos | | |
| | | | 6.0 | Metals & PCB | | |
| | | | 7.0 | Metals & TRH | | |
| | BH32 LRM | 3.0 | 0.1 | Metals, OCP/OPP & pH | | |
| | | | 1.0 | Metals & PAH | | |
| | | | 2.2 | Metals & PAH | | |
| | | | 3.0 | Metals | | |
| | | | 4.0 | Metals & TRH | | |
| Forested areas | BH34 LRM | 0.4 | 0.1 | Asbestos, Metals & PAH | | |
| | BH35 LRM | 0.4 | 0.1 | Asbestos & Metals | | |
| | BH36 LRM | 0.3 | 0.1 | Asbestos & Metals | | |
| | BH37 LRM | 0.3 | 0.1 | Asbestos, Metals & PAH | | |
| | BH38 LRM | 0.2 | 0.1 | Asbestos, Metals & PAH | | |
| | BH39 LRM | 0.5 | 0.1 | Asbestos, Metals & TRH | | |
| | BH40 LRM | 0.3 | 0.2 | Metals & PAH | | |
| | BH41 LRM | 0.5 | 0.3 | Metals & PAH | | |

| Area | Location | Total depth to sandstone/ termination | Sample Depth | Analytical Suite | Impacts | Gap |
|---|---|---|---|---|---|---|
| | BH42 LRM | 0.5 | 0.2 | Metals & OCP/OPP | | |
| QA/QC | Duplicate 1<br>Duplicate 2 – 4 | | | NEPM Suite Metals | | |
| | Split 1<br>Split 2 - 4 | | | NEPM Suite Metals | | |
| | Trip Blanks 1 | | | TRH C6-C9 | | |
| | Rinsates 1 | | | Metals | | |

## 7.3 Receptors

**Geology**

The main geological units encountered and or at the site, in order of stratigraphic sequence from youngest to oldest include:

- Fill material "*Manmade fill"* consisting of: clays, sands, demolition rubble and household waste.
- Natural – Middle Triassic Age 'Hawkesbury Sandstone' which comprises medium to coarse grained quartz sandstone with minor shale and laminate lenses.

The key transport mechanisms for soil contaminants include mobilisation via surface water flow and infiltration and to a lesser extent through windborne dust.

**Groundwater**

Groundwater provides a key transport mechanism for contaminants through horizontal and vertical migration of contaminated surface water/stormwater/groundwater through site soils (into the underlying aquifer), and then possible migration of the impact via advection and dispersion toward Gore Creek and eventually the bay. There is a high potential for vertical migration of contaminated surface water through the fill into groundwater and Gore Creek.

**Surface water**

Surface water drainage over the site is judged to be predominantly via surface run-off directed towards Gore Creek to the east. The majority of the site is currently unsealed. Surface water is considered likely to act as a potential transport mechanism at the site even considering the extent of vegetative coverage over the site. Surface water percolating into a perched water layer within the imported fill is expected to also drain towards Gore Creek and may present potential for contamination to this surface water body.

**Exposure Pathways**

Based on the identified receptors and the release, fate, and transport characteristics of the CoPC, pathways through which receptors may become exposed include inhalation, ingestion and dermal absorption. These are discussed briefly below in the context of the site setting:

- Inhalation Exposure Pathway: There is low potential for inhalation of fumes from potential soil and groundwater contamination associated with the historic site and offsite activities. There is the potential for creation of dust during disturbance of soils and infrastructure. Risk of potential inhalation of contaminated dusts during future site demolition and excavation works.
- Ingestion Exposure Pathway: Ingestion of contaminants by current and future site workers may occur through day-to-day activities and direct contact with contaminated soils or surface water. Future site layout has all soils excavated to within the natural profile removing this risk.
- Groundwater: A risk to human health exposure from groundwater in the area is associated domestic or irrigation purposes is considered unlikely due to the availability of a reticulated water supply and the only extractive bore identified is on the other side of Gore Creek for the Golf Course. A risk to ecological receptors is likely as groundwater will discharge to Gore Creek and ultimately to the Parramatta River and Sydney Harbour.
- Dermal Exposure Pathway: Exposure may occur via sorption through biological membranes such as skin. This pathway may be a concern whenever contaminated soil; surface water or groundwater comes into direct contact with a biological membrane. This pathway could also be a concern if contaminated surface water (runoff from the site) was to come into direct contact with benthic and aquatic flora and fauna within off-site surface water receiving environments.

The preliminary site investigation identified a number of potential human and environmental receptors of contamination provided an exposure pathway exists. The identified receptors are listed below:

**Human Health Receptors:**

- Current and future site workers including construction workers during site development and current and future commercial tenants;
- Future maintenance workers and landscapers / gardeners;
- Future site high density residents and staff;
- Offsite receptors including residents and workers on neighbouring properties and recreational users of nearby water courses.

**Environmental receptors:**

- Onsite flora and fauna;
- Offsite ecosystems including the adjacent remnant Coastal Enriched Sandstone Moist Forest vegetation., the down-gradient surface water environments including Gore Creek the Parramatta River and Sydney Harbour;
- Groundwater beneath the site.

# 8.0 STAGE 1 PESA CONCLUSIONS AND RECOMMENDATIONS

LRM Global Pty Ltd (LRM) was retained by the client to complete a PESA to document any potential environmental liabilities that are apparent from a comprehensive desktop study and soil and groundwater assessment as part of a Development Application for a proposed high density retirement living residential land use.

**Key Findings**

- The desktop study indicates that the site is zoned *'R4 High Density Residential*'.
- Acid Sulphate Soils are not likely to be present at the site.
- According to the aerial photographs, land titles, historic plans and business directories reviewed, the site was vacant until construction of the bowling green commenced in approximately 1961 and vacated in 1995. The surrounding area has undergone light commercial and residential development over time. A review of the historical aerial photographs and EPA records indicate that there have been no quarrying or landfilling activities in the area surrounding the site. As such, it is considered unlikely that there would be a landfill gas issue at this site.
- On-site observations and the previous environmental reports indicate significant infilling has occurred on the subject site. No evidence of green waste or putrescible waste was evident and most waste appears to be demolition and household goods related.
- A search of the NSW OEH Contaminated Land Database and Protection of Environment Operations Act 1997 Public Register found no records for the site.

**Conclusions**

Based on the findings of the Stage 1 historical assessment and reviews of previous reports it is considered that;

- The site has contaminated soils within the fill material;
- The site has the potential for the groundwater to be contaminated.

**Recommendations**

Based on the findings of the Preliminary Environmental Site Assessment it is recommended that;

- A Detailed Environmental Site Investigation of the soil and groundwater be undertaken to Australian Standards and in accordance with the National Environmental Protection Measure and applicable NSW regulations including the DECCW Waste Classification Guidelines Part 1: Classifying Waste and the Virgin Excavated Natural Material (VENM) for off-site disposal during basement works;
- Further delineation of soil impacts within the impacted fill material;
- Further investigation of the underlying natural material;
- Install groundwater wells to assess the impact of the site fill material on the groundwater;

# 9.0 STAGE 2 – DETAILED ENVIRONEMTNAL SITE INVESTIGATION

## 9.1 DESI Objectives

The objectives of the detailed environmental investigation are to implement the recommendations of the preliminary site investigation report and to satisfy the below DA conditions as required by Lance Cove Council.

## 9.2 Development Application Conditions – Contamination

The following conditions relating to contamination have been requested as a condition by the council.

A Stage 2 Detailed Environmental Site Investigation Report (as per the NSW EPA's Guidelines for Consultants Reporting on Contaminated Sites) shall be submitted to Council for assessment. The report shall identify to Councils satisfaction the location, type and level of contaminants in a single report compiling all relevant information which details soil sampling and testing to date. The report shall also identify the potential for migration of contaminants off site. The report must include a statement to the effect that the site, upon remediation, will be suitable for the development proposed.

Where the DESI states that the site requires remediation, a Remediation Action Plan is to be submitted, prepared by a suitably qualified and competent environmental consultant in accordance with the NSW Government Office of Environment and Heritage Guidelines for Consultants Reporting on Contaminated Sites and the Contaminated Land Management Act 1997.

# 10.0 DATA QUALITY OBJECTIVES

## 10.1 Overview

The Data Quality Objective (DQO) process will be applied to the investigations as described below, to ensure that data collection activities are appropriate and achieve the stated objectives.

A process for establishing data quality objectives for an investigation-site has been defined by the NSW DEC *Guidelines for the NSW Site Auditor Scheme (3rd edition, October* 2017). The DQO process will be applied to the validation program, as described below, to ensure that data collection activities are appropriate and achieve the project objectives. The DQO process involves seven steps as follows:

- Step 1: State the problem
- Step 2: Identification of the Assessment Decisions/ Goals
- Step 3: Identification of Decision Inputs
- Step 4: Definition of Study Boundaries
- Step 5: Decision Rules
- Step 6: Limits on Decision Errors
- Step 7: Optimise the design for obtaining data

The seven DQO steps for this project are defined as follows:

### *10.1.1 STEP 1: State the Problem*

The client wishes to develop the site for a high density, aged care facility with a three basement at the deepest point.

The site has historically been used for potentially contaminating activities including imported fill for levelling during its development and operation as a bowling green.

The problem is soil at the site has undergone limited assessment, however further assessment of both soil and groundwater is required to close out existing data gaps and to confirm the findings of the preliminary assessment to determine the sites suitability for the proposed use, the necessity for a remedial action plan, and an off-site soil disposal classification.

Further investigate the lead hotspot to the east of the lower Bowling Green and any impact to the sites groundwater. Further investigate contaminants of concern from the fill material in the sites groundwater.

### *10.1.2 STEP 2: Identification of the Assessment Decisions/ Goals*

Additional data is required to be collected to address the problem described in “Step 1”

- Is the site suitable for the proposed high density, aged care facility land use in respect to CoPC from historical use and filling?
- Is there any impact from potential adjoining off-site contamination that would pose a potential risk to on-site receptors?

- Does residual contamination on the site have the potential to cause unacceptable risks to off-site receptors in the future?
- What is the waste classification of soils that may require off-site disposal?
- Is further assessment (including further assessment of soils required following demolition of existing structures) or remediation/management/validation required?

### *10.1.3 STEP 3: Identification of Decision Inputs*

Data inputs to the decision making process will include:

- Existing data collected from the preliminary site assessment desktop and intrusive studies.
- Quantitative data gained through further soil and groundwater intrusive assessment works and laboratory analysis.
- Adopted Assessment Criteria as detailed in Section 5.0.

### *10.1.4 STEP 4: Definition of Study Boundaries*

The site boundary is depicted within attached Figure 1. The vertical boundaries of the study are as follows:

- Soil Investigation – where possible the soil investigation shall extend to the proposed project excavation depth of 12.5 mbgl.
- Groundwater Investigation – Three wells to be installed within the site title boundaries, to represent up-gradient, site derived and down-gradient groundwater conditions.

Temporal Boundaries – while no temporal boundaries exist as such, the client has expressed a wish that the works are executed promptly.

### *10.1.5 STEP 5: Decision Rules*

In order to decide whether the data obtained is precise, accurate, reliable and reproducible for the site at the time of the investigation, field and laboratory quality control and quality assurance (QA/QC) procedures will be utilised throughout the sampling programs and all sampling work will be carried out in accordance with LRM's Standard Field Operating Procedures, which are based on standard industry practices. QA/QC results will be compared to nominal acceptance limits.

Project analytical data will be compared to NSW EPA made or approved guidelines. The nominated site assessment criteria are presented in Section 5. On the basis of this initial comparison, a decision will be made as to whether or not the contamination may pose a potential risk (environmental or health based), warranting further assessment.

### *10.1.6 STEP 6: Limits on Decision Errors*

Two types of decision errors are possible:

- False Negative - The site (or areas of the site) may be considered 'uncontaminated' when in fact it is contaminated.
- False Positive - The site (or areas of the site) may be considered 'contaminated' when in fact it is not contaminated.

The implications of the first decision error are considered less acceptable than the second, as the first error could involve unacceptable risk to health and/or the environment, and potentially future costs including possible litigation if the site is found to be unsuitable in the future. The risks associated with the second error are primarily limited to unwarranted remediation costs. The limits on the first decision error are therefore addressed by use of conservative investigation criteria (which incorporate a factor of safety) and by analysing any data exceeding these criteria on the basis of the 95% upper confidence level (UCL) of the average concentrations. In accordance with the NEPM, secondary criteria apply as follows:

- The standard deviation of the results should be less than 50% of the relevant investigation or screening level.
- No single value should exceed 250% of the relevant investigation or screening level.

The risk of the second decision error occurring will be will minimised by minimising the potential for unrepresentative data which could arise from the following causes:

- Sampling errors which occur when the sampling program does not adequately detect the variability of a contaminant from point to point across the Site, (i.e. the samples collected are not representative of the Site conditions).
- Measurement errors which occur during sample collection, handling preparation, analysis and data reduction.

To minimise the potential for unrepresentative data, Data Quality Indicators (DQIs) will be evaluated. The DQIs for sampling techniques and laboratory analysis of collected samples will be based on those listed in Section 4.1 of the NSW EPA Auditor Guidelines (DEC October 2017). Step 5 and Step 6 of the data quality objectives will be assessed by reference to data quality indicators as follows:

**Completeness** – is a measure of the amount of useable data (expressed as %) from data collection activities. The completeness goal is set at there being sufficient valid data generated during the study. If there is insufficient valid data, then additional data are required to be collected. Completeness can be influenced by field issues such as access for sampling or by laboratory issues such as adherence to sample holding times.

**Comparability** – the confidence (expressed qualitatively) that data may be considered to be equivalent for each sampling and analytical event. Comparability is achieved through adopting consistent sampling techniques and ensuring laboratories use consistent analysis techniques.

**Representativeness** - expresses the degree to which sample data accurately represents each media present on the site. Representativeness is achieved by collecting samples in an appropriate pattern across the site, by using a sufficient number of sampling locations to characterise the site and by using consistent, repeatable and appropriate methodologies.

**Precision** - measures the reproducibility or variation of data. The precision of the data is assessed by calculating the Relative Percent Difference (RPD) between primary and duplicate/ inter-lab split samples

LRM adopt nominal acceptance criteria of 30% RPD for duplicates and splits for results >30 times the LOR, 50% for results between 10-30 times the LOR, and 100% for results <10 times

the LOR. It is noted that this will not always be achieved, particularly in heterogeneous media such as imported fill material or disturbed natural materials, or at low analyte concentrations.

**Accuracy (bias)** - measures quantitatively the closeness of the reported data to the true value. Bias can be introduced during sample collection through cross contamination from contaminated equipment, during sample preservation and transport and from laboratory sample handling, preparation and analysis techniques. Accuracy is assessed by reference to the analytical results of laboratory internal QA/QC samples including spikes, blanks and reference standards.

The nominal “acceptance limits” on laboratory control samples are defined as follows:

Laboratory spikes – 70-130% for metals/inorganics 60-140% for organics.
Laboratory duplicates - <30% for metals/inorganics, <50% for organics.
Laboratory blanks - <practical quantitation limit.

Accuracy of field works is assessed by examining the level of contamination detected in field and rinsate blanks. Blanks should return concentrations of all organic analytes as being less than the practical quantitation limit of the testing laboratory. The individual testing laboratories will conduct an assessment of the internal laboratory QA/QC program however the results will also be independently reviewed and assessed by LRM.

### *10.1.7 STEP 7: Optimise the Design for Obtaining Data*

The sampling program has been designed to provide sufficient information to allow a sound scientific and statistical evaluation of the questions set out in Step 2.

To optimise the design of the investigations, this SAQP has been prepared in consultation with the client, site occupants and the Site Auditor and giving consideration to previous investigations. The SAQP will be reviewed and refined as necessary during the assessment by evaluating field observations and analytical results.

All samples were submitted to a NATA accredited laboratory for analysis. The primary laboratory engaged for the assessment works was Envirolab Pty Ltd and ALS Pty Ltd were engaged as the secondary laboratory.

# 11.0 ASSESSMENT CRITERIA

## 11.1 Soil Criteria

In assessing any soil contamination present on this site, and considering the purpose of this assessment, the data will be evaluated against the levels that are given in the NEPM Schedule B (1) Guidelines on the Investigation Levels for Soil and Groundwater [National Environment Protection (Assessment of Site Contamination) Measure 2013].

The approach used by LRM in undertaking these investigation works is based on recognised guidelines for the assessment of potentially contaminated sites, published in but not limited to:

- AS 4482.1 – 2005 *Guide to investigation and sampling of potentially contaminated soil, Part 1: Non- Volatile and semi-volatile compounds;*
- AS 4482.2 – 1999 *Guide to sampling and investigation of potentially contaminated soil, Part 2: Volatile substances;*
- *The National Environment Protection (Assessment of Site Contamination) Measure 1999*, as amended 2013.
- NSW EPA Sampling and design Guidelines (September 1995);
- *Guidelines for consultants reporting on contaminated sites (August 2011);*
- NSW Environment, Climate Change and Water 2010, Vapour intrusion: Technical Note;
- *NSW DECC 2009, Waste Classification Guidelines – Part 1;Classifying Waste;*
- Acid Sulphate Soil Manual (August 1998);
- *NSW EPA Resource Recovery Order under Part 9, Clause 93 of the Protection of the Environment Operations (Waste) Regulation 2014 – The excavated natural material order 2014.*

The full reference list is detailed in Section 24.

**Human health risk**

Considering the current site and surrounding land use and the proposed site development, human health risk will be assessed for future and existing residents (high density), current and future construction and commercial workers and users of the recreational open spaces at the site.

Soil results will be compared to criteria for high density residential, recreational/ open space and commercial/ industrial land use settings as outlined in the following tables within the NEPM Schedule B1 Guideline on Investigation Levels for Soil and Groundwater, Appendix A:

- Table 1A(1) Health Investigation Levels for soil contaminants – Residential A, B, Recreational/Open space C, Commercial/Industrial D;
- Table 1A(3) Soil HSLs for vapour intrusion (mg/kg) – HSL A&B, HSL C & HSL D;
- Table 1B(7) Management Limits for TPH fractions F1-F4 in soil – “Residential, Parkland and Public Open Space” and “Commercial and industrial”.

**Ecological Protection**

Open space / landscaped areas and existing vegetated areas will be subjected to ecological protection criteria as per the NEPM.

Currently the site surface consists of imported impacted fill material scheduled for removal and as such is not appropriate for EILs to be applied to. Following remediation works and final setting of site RLs the final site surface soils remaining will be sampled for EIL analysis suites and site specific EILs will be calculated and applied.

Site specific EIL criteria will be calculated once final RLs are established and will be applied to all open space, landscaped, planted and existing / retained vegetated areas as applicable.

In the interim, the below adopted EILs can be used as a guideline;

***Table 8: Adopted Ecological Investigation Levels***

| Contaminant | Assumed Values | EIL (mg/kg) |
|---|---|---|
| Arsenic | Generic EIL | 100 |
| Chromium III | Derived EIL assumes 1% soil clay content for aged soils within a high traffic NSW suburb | 200 |
| Copper | Derived EIL assumes pH of 7, 1% soil clay content and 10% cation exchange capacity for aged soils within a high traffic NSW suburb | 220 |
| DDT | Generic EIL | 180 |
| Lead | Derived EIL assumes aged soils within a high traffic NSW suburb | 1100 |
| Naphthalene | Generic EIL | 170 |
| Nickel | Derived EIL assumes 10% cation exchange capacity for aged alluvial sandy soils within a high traffic NSW suburb | 170 |
| Zinc | Derived EIL assumes soil pH of 7, 10% cation exchange capacity for aged alluvial sandy soils within a high traffic NSW suburb | 520 |

**Note:** Cation exchange values are taken from the NSW DPI Agriculture website where published average values for North Coast soils indicate that light sandy alluvial soils have a CEC of 10-20%. The adopted figure of 10% takes a conservative approach towards the assessment.

**Waste Classification** - The criteria detailed within the NSW EPA Waste Classification Guidelines 2008 and the NSW EPA Resource Recovery Order under Part 9, Clause 93 of the Protection of the Environment Operations (Waste) Regulation 2014 – The excavated natural material order 2014 will be used to classify soils for future disposal off-site.

Soils will be classified using their specific chemical concentrations (SCC) with analysis being conducted for the sites contaminants of concern as identified in Table 2 previously. A separate waste disposal classification will be provided for each geological unit encountered.

The two measurable properties of chemical contaminants used to classify waste are:

- The SCC of any chemical contaminant in the waste, expressed as milligrams per kilogram (mg/kg); and
- The leachable concentration of any chemical contaminant using TCLP, expressed as milligrams per litre (mg/L).

Analysis results will initially be compared to CT1 values for General Solid Waste and CT2 values for restricted solid waste as detailed within Table 1 of the NSW EPA Waste classification guidelines – Part 1.

Where SCC levels exceed the CT1 values for general solid waste further TCLP analysis will be conducted with results compared to the CT1 values for General Solid Waste and CT2 values for restricted solid waste as detailed within Table 2 of the NSW EPA Waste Classification Guidelines – Part 1.

Where contaminant levels exceed the CT1 or CT2 values statistical analysis of sample data for that contaminant involving the calculation of 95% UCL values will be conducted with the aid of “Pro UCL” and results will be compared to values for SCC or TCLP values for that contaminant to ensure that the calculated values are appropriately classified.

Soils that meet the classification criteria for ‘General Solid Waste’ will be classed as VENM or ENM where possible. Further site investigation via test pitting will be required to first ascertain suitability for this application.

The Protection of the Environment Operations Act 1997 (POEO Act) defines virgin excavated natural material (VENM) as natural material (such as clay, gravel, sand, soil or rock fines):

(a) that has been excavated or quarried from areas that are not contaminated with manufactured chemicals, or with process residues, as a result of industrial, commercial, mining or agricultural activities, and

(b) that does not contain any sulfidic ores or soils or any other waste and includes excavated natural material that meets such criteria for virgin excavated natural material as may be approved for the time being pursuant to an EPA Gazettal notice.

Excavated natural material (ENM) is defined as: naturally occurring rock and soil (including but not limited to materials such as sandstone, shale, clay and soil) that has:

a) Been excavated from the ground, and

b) Contains at least 98% (by weight) natural material, and

c) Does not meet the definition of Virgin Excavated Natural Material in the Act.

Excavated natural material does not include material located in a hotspot; that has been processed; or that contains asbestos, Acid Sulphate Soils (ASS), Potential Acid Sulphate soils (PASS) or sulfidic ores.

**Aesthetic Considerations** – Considering the proposed change in land use from a commercial setting to a primarily residential setting with open recreational space, an aesthetic assessment of the material present on-site is considered necessary and will follow the guidelines outlined within Section 3.6.3 of the NEPM Schedule B(1) Investigation Levels for Soil & Groundwater.

Significant volumes of demolition and household waste have been observed in surface fill areas on the batters and adjacent to the greens. It is considered likely that this material extends in depth along with the imported fill material.

**Asbestos Materials** – Considering the site's historic use and the presence of imported near surface fill material, it is possible that asbestos containing materials are present within the site's soils. Asbestos materials have been identified in surface soils to the north east side of the site and is considered likely to be heterogeneously distributed within the fill material. Asbestos impacts shall be assessed as per guidelines detailed within Section 4 of the NEPM Schedule B(1) Investigation Levels for Soil & Groundwater. Should visual suspect material be identified during the works they will be assessed against the criteria detailed within Table 7 of the aforementioned NEPM document for residential, recreational and commercial/ industrial land use settings.

## 11.2 Groundwater Criteria

In assessing any groundwater contamination present on this site, and considering the purpose of this assessment, the data will be evaluated against the levels that are given in the NEPM Schedule B (1) Guidelines on the Investigation Levels for Soil and Groundwater [National Environment Protection (Assessment of Site Contamination) Measure 2013].

The approach used by LRM in undertaking these investigation works is based on recognised guidelines for the assessment of potentially contaminated sites, published in but not limited to:

- *Australian and New Zealand Guidelines for Fresh and Marine Water Quality*, ANZECC / ARMCANZ 2000.
- *The National Environment Protection (Assessment of Site Contamination) Measure 1999*, as amended 2013.
- *NEPM 2013 Table 1c GILs Drinking Water and Fresh Waters*
- Schedule B(6) Guideline on the Framework for Risk-Based Assessment of Groundwater Contamination NEPM, NEPC 2011
- PFAS National Environment Management Plan, January 2018, HEPA.
- Sydney Harbour and Parramatta River Water Quality Objectives

The full reference list is detailed in Section 24.

## 12.0 DATA QUALITY ASSESSMENT

To minimise the potential for unrepresentative Data Quality Indicators (DQIs) will be evaluated. The DQIs for sampling techniques and laboratory analysis of collected samples will be based on those listed in Section 4.1 of the NSW EPA Auditor Guidelines (DEC October 2017). Step 5 and Step 6 of the data quality objectives will be assessed by reference to data quality indicators.

**Field and Analytical QA/QC - Soils**

The control measures generated from the field sampling and analytical works program were as follows:

- Suitable records of field observations including bore logs with stratigraphy, visual and olfactory observations and PID readings (**Appendix C**);
- Sampling plan – density, media and location as per the attached SAQP (Appendix F);
- Use of approved and appropriate sampling methods as per the attached SAQP (**Appendix C**);
- Preservation and storage of samples post collection and during transit – refer laboratory SRA (sample receipt advice) regarding temperature of samples and attempt to cool observed upon receipt of samples at the laboratory (**Appendix E**);
- Completed chain of custody (COC) and laboratory sample receipt documentation (**Appendix E**);
- All Sample holding times were within acceptable limits – samples were delivered to the receiving laboratories on the day of sampling;
- All samples have been analysed by NATA accredited Laboratories namely Envirolab (Primary) and ALS Pty Ltd (secondary) using appropriate methods to allow for data comparison to adopted investigation levels;
- Laboratory quality control measures have been conducted in line with NEPM requirements. The laboratories followed internal quality control procedures, e.g. routine analysis of standard solutions, reference materials, reagent blanks, laboratory duplicates and spikes and surrogates. To assess the extent of matrix bias or interference on analyte recovery and sample to sample precision, numerous spike recovery appraisals were conducted by the laboratory. Recovery percentages for the soil spikes were generally between the LRM acceptable ranges of 70 – 130%, or 30 – 150% for phenols, indicating little negative or positive bias on reported analyte concentrations.
- Laboratory RPD acceptance criteria were exceeded at the following locations: BH34 for Split 1 for Copper, Lead, Manganese and Zinc. These soil samples represent fill material and the RPD exceedances are considered to be associated with the non-homogenous nature of the fill material.
- Field blanks and duplicate/ split samples were collected in accordance with Australian standards and are discussed further below.
- Laboratory Data has been reviewed for the occurrence of anomalous or unusual results which are inconsistent with field observations. The data was considered to be consistent

with field observations relating to the levels of contaminants reported within fill and natural materials.

**Relative Percent Difference Calculations**

LRM adopt nominal acceptance criteria of 30% RPD for duplicates and splits for results >30 times the LOR, 50% for results between 10-30 times the LOR, and 100% for results <10 times the LOR.

Duplicate and triplicate laboratory split samples taken during sampling were analysed for metals during the PESA. The majority of RPDs relating to the soil samples were within acceptable criteria, with the exception of levels of nickel, lead, copper, manganese and zinc.

These results can be attributed to the non-homogenous nature of the fill material at the site, however, as the majority (>99.00%) of RPDs are within the acceptable limits, the data retrieved is considered repeatable and highly reliable. Attached table for soils provide the RPDs that could be calculated with over >99% of results falling within acceptable criteria as per AS4482.1 2005.

Refer to Table 22 within **Appendix D** for Soil RPD calculation results.

**Field Blanks**

A trip blank was prepared in 40 mL glass vials with a Teflon septum lids and pre-prepared with hydrochloric acid. The trip blank accompanied the samples throughout the entire sampling procedure and during delivery to the receiving laboratory. A trip blank was taken during the soil and groundwater sampling program as they were conducted on the same day and were analysed for TRH $C_6$-$C_9$ to determine if samples were potentially exposed to any volatile contaminants via cross contamination during storage and transport.

A rinsate blank was taken from the third stage of the decontamination procedure (the first stage being a solution of tap water and 'Decon 90'; the second stage – tap water; and the third stage is deionized rinse water only) to ensure the decontamination procedure is effective and being appropriately undertaken. Rinsate samples taken during the soil and groundwater sampling program were analysed for metals. During sampling all equipment used was decontaminated in the abovementioned fashion.

Trip and rinsate blank sample analysis reported no analyte concentrations above the laboratory limit of reporting.

Refer to Table 24 in **Appendix D** for QA/QC soil field blank results.

**QA/QC Evaluation against Data Quality Indicators**

**Completeness** – is a measure of the amount of useable data (expressed as %) from data collection activities. The completeness goal is set at there being sufficient valid data generated during the study. If there is insufficient valid data, then additional data are required to be collected. Completeness can be influenced by field issues such as access for sampling or by laboratory issues such as adherence to sample holding times. No issues with refusal were noted at the site and hence, the assessment is 100% complete for the DESI soil assessment.

**Comparability** – the confidence (expressed qualitatively) that data may be considered to be equivalent for each sampling and analytical event. Comparability is achieved through adopting consistent sampling techniques and ensuring laboratories use consistent analysis techniques. All samples were collected using consistent and approved sampling techniques as detailed within the SAQP and were analysed at NATA accredited laboratories throughout all stages of the assessment works.

**Representativeness** - expresses the degree to which sample data accurately represents each media present on the site. Representativeness is achieved by collecting samples in an appropriate pattern across the site, by using a sufficient number of sampling locations to characterise the site and by using consistent, repeatable and appropriate methodologies. The sampling plan adhered to and exceeded the sampling density requirements as per Australian Standards and NEPM Publications sampling soils at 47 locations across the site during both PESA and DESI intrusive works. Soil sample depths targeted fill material and shallow and deep natural material and analysed them for the majority of identified COPCs. Accordingly the data is considered representative of the media and suitable for interpretative use.

**Precision** - measures the reproducibility or variation of data. The precision of the data is assessed by calculating the Relative Percent Difference (RPD) between primary and duplicate/ triplicate samples. Over 99% of calculated RPD results from 6 duplicate samples and 6 triplicate samples collected of the soil assessment were within acceptable criteria as per AS4482.1 2005.

**Accuracy (bias)** - measures quantitatively the closeness of the reported data to the true value. Bias can be introduced during sample collection through cross contamination from contaminated equipment, during sample preservation and transport and from laboratory sample handling, preparation and analysis techniques. Accuracy is assessed by reference to the analytical results of laboratory internal QA/QC samples including spikes, blanks and reference standards.

The nominal “acceptance limits” on laboratory control samples are defined as follows:

Laboratory spikes – 70-130% for metals/inorganics 60-140% for organics.
Laboratory duplicates - <30% for metals/inorganics, <50% for organics.
Laboratory blanks - <practical quantitation limit.

The majority laboratory spikes and blanks were reported within acceptable limits. Laboratory duplicates were exceeded for some levels of metals typically within samples of fill material however, the majority of results were reported within acceptable limits and as such the reported data is considered to be of a sufficiently accurate for interpretive purposes.

Accuracy of field works is assessed by examining the level of contamination detected in field and rinsate blanks. Blanks should return concentrations of all organic analytes as being less than the practical quantitation limit of the testing laboratory. All field blanks collected and analysed during both stages of the soil assessment reported results below the laboratory limit of reporting.

**QA/QC Tabulated Frequency Summary**

***Table 9: QA/QC Samples Required vs. Collected***

| Quality Control Samples | Minimum Number of QA/QC Samples Required | Total Project QA/QC | |
|---|---|---|---|
| | | Soil Required | Soil Collected |
| Dup Sample | 1 in 20 | 3 | 6 |
| Split Sample | 1 in 20 | 3 | 6 |
| Rinsate Blank | 1 /matrix / equipment / day | 2 | 2 |
| Trip Blank | 1/day/ eskie | 2 | 2 |
| **Quality Control Samples** | **Minimum Number of QA/QC Samples Required** | **GW Required** | **GW Collected** |
| Dup Sample | 1 in 20 | 2 | 2 |
| Split Sample | 1 in 20 | 2 | 2 |
| Rinsate Blank | 1 /matrix / equipment / day | 2 | 2 |
| Trip Blank | 1/day/ eskie | 2 | 2 |

**Overall QA/QC Adequacy**

It is concluded that the quality control procedures have confirmed that overall data supplied by the laboratories is adequate to arrive at the conclusions of this report.

# 13.0 SOIL INVESTIGATION

## 13.1 Field Soil Investigation Objectives

The objectives to achieve the outcomes of the field soil investigation were;

- Assess the data collected from the sampling and analysis program against policies, regulations, guidelines and standards currently adopted in the State of New South Wales. Data exceeding the appropriate requirements is evaluated in terms of the risks posed by the contamination and remedial measures to be undertaken to remove or minimise those risks;
- Determine if the subsurface has been contaminated as a result of historic activities at the site including infilling; and
- The development of an appropriate waste classification for excavated soils in accordance with NSW EPA Waste Classification Guidelines - Part 1: Classifying waste.

The sampling technique adopted in the assessment of soil was in accordance with the Australian Standard 4482:1 – 2005, Guide to the Sampling and Investigation of Potentially Contaminated Soil, Part 1: Non-Volatile and Semi volatile Compounds and Part 2: Volatile Compounds.

Refer to Appendix C for typical soil sampling procedures and also for the SAQP associated with the DESI stage of the works.

The sample regime was guided by the findings of the preliminary soil investigation works and also by the proposed site development. The number of sample locations is in excess of the sample density grid requirements for the site area of approximately 0.9 hectares as detailed within Australian standard AS4482.1-2005 and NEPM Guidelines for assessing contaminated sites. As an evenly spaced grid was not possible due to site elevation changes a detailed assessment of hot spot size identification is no feasible due to the inherent inaccuracies and bias due to the inaccessible areas to date.

Sample target depths aimed to classify and outline the extent of distinct geological units across the site including fill layers and natural soils to the planned excavation depth.

All soil locations were sampled in accordance with AS4482.1-1997(2005). Typically samples were taken within the surface fill material, generally at depths of between 0.1 and 0.5 m below ground level, and within the natural profile below at meter intervals or after geological interface points and at or below the depth of excavation or point of refusal. However, each location varied depending on field conditions encountered. A plan showing the soil bore / monitoring well locations is provided on Figure 4, **Appendix A**.

The analytical program detailed in Tables 10 & 11 below was considered suitable for the objectives of this investigation.

Field methodologies are described in detail in the following sections.

***Table 10: Initial Soil Sample Locations***

| Sample Location/Depth | Purpose | Stratigraphy | Analysis |
|---|---|---|---|
| **6/07/2017 – Initial LRM Soil Investigation Works** | | | |

| | | | |
|---|---|---|---|
| BH16 – 0.1 | Soil Investigation Bore | Fill | Metals, PAH, TRH |
| BH16 – 0.8 | Soil Investigation Bore | Natural | Metals, PAH, TRH |
| BH17 – 0.1 | Soil Investigation Bore | Fill | Metals, PAH, TRH |
| BH17 – 0.7 | Soil Investigation Bore | Natural | Metals, PAH, TRH |
| BH18 – 0.1 | Soil Investigation Bore | Fill | Metals, OCP/OPP, pH |
| BH18 – 0.6 | Soil Investigation Bore | Natural | Metals, PAH |
| BH19 – 0.1 | Soil Investigation Bore | Fill | Metals, OCP/OPP, pH |
| BH19 – 0.5 | Soil Investigation Bore | Natural | NEPM Basic Suite |
| BH20 – 0.1 | Soil Investigation Bore | Fill | Metals, OCP/OPP, pH |
| BH20 – 1.0 | Soil Investigation Bore | Natural | Metals, pH |
| BH20 – 1.9 | Soil Investigation Bore | Natural | Metals, PAH |
| BH21 – 0.1 | Soil Investigation Bore | Fill | Metals, OCP/OPP |
| BH21 – 1.2 | Soil Investigation Bore | Fill | Metals, PAH |
| BH21 – 3.0 | Soil Investigation Bore | Natural | Metals, TRH, PCB |
| BH21 – 4.0 | Soil Investigation Bore | Natural | Metals, PAH |
| BH22 – 0.1 | Soil Investigation Bore | Fill | Metals, OCP/OPP, pH |
| BH22 – 1.0 | Soil Investigation Bore | Natural | Metals, TRH |
| BH23 – 0.1 | Soil Investigation Bore | Fill | Metals, OCP/OPP |
| BH23 – 1.0 | Soil Investigation Bore | Natural | Metals, PAH |
| BH24 – 0.1 | Soil Investigation Bore | Fill | Metals, OCP/OPP, pH, TRH |
| BH24 – 1.5 | Soil Investigation Bore | Fill | Metals, PAH |
| BH24 – 2.8 | Soil Investigation Bore | Natural | Metals, TRH, PCB |

| | | | |
|---|---|---|---|
| BH25 – 0.2 | Soil Investigation Bore | Fill | Metals, OCP/OPP |
| BH26 – 0.2 | Soil Investigation Bore | Fill | Metals, OCP/OPP |
| BH27 – 0.1 | Soil Investigation Bore | Fill | Metals, OCP/OPP, pH |
| BH27 – 1.0 | Soil Investigation Bore | Natural | Metals, PAH |
| BH28 – 0.1 | Soil Investigation Bore | Fill | Metals, OCP/OPP |
| BH28 – 2.0 | Soil Investigation Bore | Natural | Metals |
| BH28 – 3.0 | Soil Investigation Bore | Natural | Metals, PAH |
| BH28 – 4.0 | Soil Investigation Bore | Natural | Metals, PCB, TRH |
| BH29 – 0.1 | Soil Investigation Bore | Fill | Metals, OCP/OPP, pH |
| BH29 – 1.0 | Soil Investigation Bore | Fill | Metals, PAH |
| BH29 – 2.0 | Soil Investigation Bore | Fill | Metals |
| BH29 – 3.0 | Soil Investigation Bore | Fill | Metals, PAH |
| BH29 – 4.0 | Soil Investigation Bore | Fill | Metals, PCB |
| BH29 – 5.0 | Soil Investigation Bore | Fill | Metals |
| BH29 – 6.0 | Soil Investigation Bore | Fill | Metals, PAH |
| BH29 – 7.0 | Soil Investigation Bore | Fill | Metals |
| BH29 – 8.0 | Soil Investigation Bore | Fill | Metals, TRH |
| BH30 – 0.1 | Soil Investigation Bore | Fill | Metals, OCP/OPP |
| BH30 – 1.0 | Soil Investigation Bore | Fill | NEPM Basic Suite |
| BH30 – 2.0 | Soil Investigation Bore | Fill | Metals |
| BH30 – 3.0 | Soil Investigation Bore | Fill | Metals, TRH |
| BH30 – 4.0 | Soil Investigation Bore | Fill | Metals, PAH |

| | | | |
|---|---|---|---|
| BH30 – 5.0 | Soil Investigation Bore | Fill | Metals |
| BH30 – 6.0 | Soil Investigation Bore | Fill | Metals, PCB |
| BH30 – 7.0 | Soil Investigation Bore | Natural | Metals, TRH |
| BH31 – 0.1 | Soil Investigation Bore | Fill | Metals, OCP/OPP |
| BH31 – 1.0 | Soil Investigation Bore | Natural | Metals, PAH |
| BH32 – 0.1 | Soil Investigation Bore | Fill | Metals, OCP/OPP, pH |
| BH32 – 1.0 | Soil Investigation Bore | Fill | Metals, PAH |
| BH32 – 2.2 | Soil Investigation Bore | Natural | Metals, PAH |
| BH32 – 3.0 | Soil Investigation Bore | Natural | Metals |
| BH32 – 4.0 | Soil Investigation Bore | Natural | Metals, TRH |
| BH33 – 0.2 | Soil Investigation Bore | Fill | Metals, OCP/OPP |
| BH33 – 1.0 | Soil Investigation Bore | Natural | Metals, PAH |
| BH34 – 0.1 | Soil Investigation Bore | Fill | NEPM Basic Suite |
| BH35 – 0.1 | Soil Investigation Bore | Fill | Metals |
| BH36 – 0.1 | Soil Investigation Bore | Fill | Metals |
| BH37 – 0.1 | Soil Investigation Bore | Fill | Metals, PAH |
| BH38 – 0.1 | Soil Investigation Bore | Fill | Metals, PAH |
| BH39 – 0.1 | Soil Investigation Bore | Fill | Metals, TRH |
| BH40 – 0.1 | Soil Investigation Bore | Fill | Metals |
| BH41 – 0.1 | Soil Investigation Bore | Fill | Metals |
| BH42 – 0.1 | Soil Investigation Bore | Fill | Metals, OCP/OPP |

***Table 11: Secondary Soil Sample Locations***

| Sample Location/Depth | Purpose | Stratigraphy | Analysis |
|---|---|---|---|
| **10/05/2018 – Additional Soil and Groundwater Investigation Works** | | | |
| BH43 – 5.0 | Groundwater Investigation Well | Natural | NSW Waste Disposal Screen |
| BH43 – 6.0 | Groundwater Investigation Well | Natural | Metals, TRH/BTEX, PAH |
| BH43 – 7.0 | Groundwater Investigation Well | Natural | Metals, TRH/BTEX, PAH |
| BH43 – 8.0 | Groundwater Investigation Well | Natural | Metals, TRH/BTEX, PAH |
| BH43 – 9.0 | Groundwater Investigation Well | Natural | NSW Waste Disposal Screen |
| BH44 – 5.0 | Groundwater Investigation Well | Natural | NSW Waste Disposal Screen |
| BH44 – 6.0 | Groundwater Investigation Well | Natural | Metals, TRH/BTEX, PAH |
| BH44 – 7.0 | Groundwater Investigation Well | Natural | Metals, TRH/BTEX, PAH |
| BH44 – 8.0 | Groundwater Investigation Well | Natural | Metals, TRH/BTEX, PAH |
| BH44 – 9.0 | Groundwater Investigation Well | Natural | NSW Waste Disposal Screen |
| BH45 – 7.0 | Groundwater Investigation Well | Natural | NSW Waste Disposal Screen |
| BH45 – 7.8 | Groundwater Investigation Well | Natural | Metals, TRH/BTEX, PAH |
| BH45 – 8.0 | Groundwater Investigation Well | Natural | NSW Waste Disposal Screen |
| BH46 – 0.2 | Soil Investigation Bore | Fill | NSW Waste Disposal Screen |
| BH46 – 0.5 | Soil Investigation Bore | Natural | Metals, TRH/BTEX, PAH |
| BH46 – 1.0 | Soil Investigation Bore | Natural | Metals, TRH/BTEX, PAH |
| BH46 – 2.0 | Soil Investigation Bore | Natural | Metals, TRH/BTEX, PAH |
| BH46 – 2.3 | Soil Investigation Bore | Natural | NSW Waste Disposal Screen |
| BH47 – 3.6 | Soil Investigation Bore | Fill | NSW Waste Disposal Screen |
| BH47 – 5.0 | Soil Investigation Bore | Natural | Metals, TRH/BTEX, PAH |

| | | | |
|---|---|---|---|
| BH47 – 6.0 | Soil Investigation Bore | Natural | Metals, TRH/BTEX, PAH |
| BH47 – 6.5 | Soil Investigation Bore | Natural | Metals, TRH/BTEX, PAH |
| BH47 – 7.0 | Soil Investigation Bore | Natural | NSW Waste Disposal Screen |

**NEPM Basic Suite –**
As, Be, B, Cd, Cr, Co, Cu, Pb, Mn, Hg (total), Ni, Se, Zn, Hexavalent Cr (VI), Cyanide - Free PAH's, Phenol, Pentachlorophenol, Cresols, DDT+DDE+DDD, Aldrin + Dieldrin, Chlordane, Endosulfan, Endrin, Heptachlor, HCB, Methoxychlor, Chlorpyrifos, PCB's (aroclors), Mirex, Toxaphene, Atrazine, Bifenthrin, TRH, BTEXs.

**NSW Waste disposal screen –**
11 Metals (As, Cd, Cu, Hg, Mo, Ni, Pb, Se, Ag, Sn, Zn), Hexavalent Cr, Cyanide – Total / free, Fluoride - Total by fusion, VOC/TRH (C6-C10), Acid Herbicides, SVOCs, Phthalates, 2,4-DNT & Nitrobenzene, OC/OP, Speciated Phenols, PAH (includes BaP), TRH (C6-C36)

***Table 12: Summarised Primary Soil Sample Analysis per Stratigraphy (LRM)***

| **Stratigraphy** | **Fill** | **Natural** |
|---|---|---|
| **Selected analysis** | **# Analysis conducted – primary samples** | |
| PCBs | 7 | 14 |
| PAHs | 18 | 35 |
| TRH/BTEX | 13 | 32 |
| Metals | 55 | 47 |
| OCP | 23 | 9 |
| OPP | 23 | 9 |
| pH | 14 | 9 |
| sVOC | 6 | 9 |
| VOC | 6 | 9 |
| Inorganics | 6 | 9 |
| MAH | 6 | 9 |

## 14.0 SOIL RESULTS

Preliminary field soil investigation works were completed on 6th July 2017. The DESI soil works were undertaken on 10th and 11th May 2018 and the DESI groundwater works were undertaken on 14th May 2018.

The main geological units encountered at the site, in order of stratigraphic sequence from youngest to oldest include:

- Fill material - generally clays, silts and sands containing in areas, anthropogenic materials including glass, brick cement ceramics, glass and other miscellaneous debris and occasional organic material including roots.

- Natural – Quaternary Holocene Sands, light brown, fine to medium grained, dry.

The geological observations during site investigation works are presented within the field bore-logs within **Appendix C**. Cross-sections included in **Appendix A** shows the extent of the excavation for the removal of soil at the site for the proposed development.

Soil samples were generally analysed for broad spectrum analytical suites or for general contaminants of concern considered appropriate for the site.

Refer to **Appendix E** for full laboratory data tables and NATA endorsed analysis certificates.

The following presents a summary of the key findings of the soil analytical assessment:

**Human Health**

Based on the proposed land use for this site (aged care facility), the results were compared against NEPM HIL A sensitive use residential criteria. As all proposed open garden areas of the development shall be planted in validated and/or imported materials, the more sensitive HIL C criteria (recreational/open space) has also been applied to soils to assess the potential for on-site re-use. Exceedances of the HIL A criteria for fill and natural soils are presented within Table 13 below:

*Table 13: Human Health Exceedance Summary (mg/kg)*

| # Sample Results | Analyte | Adopted HIL | Min Conc. | Max Conc. | Locations exceeding investigation levels |
|---|---|---|---|---|---|
| **Fill Material** | | | | | |
| 11 | Lead | 600 | 6 | 6,200 | **BH11**_4.3 (360)<br>**BH12**_4.5 (640)<br>**BH13**_4.3 (7,300)<br>**BH13**_7.3 (1,400)<br>**BH15**_4.0 (650)<br>**BH22**_1.0 (830)<br>**BH29**_4.0 (790)<br>**BH29**_5.0 (740)<br>**BH29**_8.0 (6,200)<br>**BH30**_6.0 (500)<br>**BH35**_0.1 (1,300) |
| 1 | B(a)P | 3 | <1 | 3.2 | **BH12**_4.3 (3.2) |
| **Natural Material** | | | | | |
| 47 | No Exceedances recorded for any analyte | | | | |

Accordingly, it is considered unnecessary to compare the data to less sensitive criteria for existing and proposed commercial / industrial land-uses.

Concentrations of lead and B(a)P were reported exceeding the human health criteria adopted for the site with soil samples as listed above. However, it should be noted at all the exceedances of human health criteria were reported in fill material and that all soil samples collected in natural soils reported concentrations below the human health criteria.

No further exceedances of the adopted human health criteria were noted for any other analyte in soil samples collected at the site.

A plan showing the areas of exceedances of the human health criteria is attached as Figure 6 in **Appendix A.**

**Asbestos in Soil**

Asbestos containing materials (bonded in nature) were observed to the northern side of the lower Bowling Green and scattered across the lower treed area in the north eastern corner of the site. The extent of heavy vegetation made more detailed investigation difficult. It is likely that further asbestos impacts exit within the site fill material. Following the removal of further vegetation, a test pitting program is required to further assess and delineate more accurately asbestos impacts. Push tube or augur drilling methods are not suitable for assessing asbestos

impacts as asbestos fragments tend to be pushed to the side and not captured within the sample therefore typically underestimating the extent.

### Aesthetics

Various anthropogenic materials including but not limited to glass, brick, concrete, bricks and metal were encountered within fill material across the site during investigation works. It is considered that the fill material is aesthetically unsuitable for use in landscaped or garden bed areas. Planned landscaped areas of site should have fill materials stripped during the site development works with chemically and aesthetically suitable material imported as per the landscaping requirements.

### Waste Disposal

Soils were compared to the 2008 NSW EPA soil disposal criteria and also the criteria detailed with the NSW EPA excavated natural material order 2014 for off-site disposal purposes. Table 9 below summarises specific contaminant concentration exceedances of the contaminant threshold values outlined in Table 1 of the NSW waste classification guidelines – Part 1 for fill and natural material encountered on-site. Where multiple values exist for the same sample due to laboratory internal duplicate/ triplicate analysis the most elevated value is considered for disposal classification purposes.

***Table 14: Waste Disposal SCC without TCLP Exceedance Summary (mg/kg)***

| # Sample Results* | Analyte | CT1 | CT2 | Min Conc. | Max Conc. | Sample Locations exceeding Contamination Threshold Concentrations |
|---|---|---|---|---|---|---|
| **Fill Material** | | | | | | |
| 55 | Lead | 100 | 400 | 6 | 6,200 | **BH21**_3.0 (120)<br>**BH22**_0.1 (230)<br>**BH22**_1.0 (830)<br>**BH27**_0.1 (130)<br>**BH28**_3.0 (130)<br>**BH28**_4.0 (150)<br>**BH29**_2.0 (220)<br>**BH29**_4.0 (790)<br>**BH29**_5.0 (740)<br>**BH29**_6.0 (260)<br>**BH29**_7.0 (540)<br>**BH29**_8.0 (6,200)<br>**BH30**_1.0 (150)<br>**BH30**_3.0 (130)<br>**BH30**_4.0 (210)<br>**BH30**_5.0 (130)<br>**BH30**_6.0 (500)<br>**BH35**_0.1 (1,300)<br>**BH38**_0.1 (150) |
| 55 | Mercury | 4 | 16 | <1 | 6.4 | **BH19**_0.1(6.4)<br>**BH20**_0.1(5.2)<br>**BH23**_0.1(4.2)<br>**BH28**_0.1(4.1)<br>**BH30**_0.1(4.4)<br>**BH40**_0.1(5.5)<br>**BH41**_0.1(4.1)<br>**BH42**_0.1(5.2) |

| | | | | | | |
|---|---|---|---|---|---|---|
| 55 | Nickel | 40 | 160 | 2 | 93 | **BH38**_0.1 (93) |
| 18 | Benzo(a)pyrene | 0.8 | 3.2 | <0.05 | 2.2 | **BH30**_1.0 (2.2) |
| **Natural Material** | | | | | | |
| 47 | No Exceedances recorded for any analyte | | | | | |

**TCLP Analysis**

No TCLP analysis was conducted on the samples from the DESI as it was beyond the scope of those works and laboratory holding times. During excavation / test pitting works TCLP testing will conducted on hot spots identified as restricted waste as required.

Initial TCLP analysis was conducted during the SMEC assessment and is detailed below.

**Fill Material Waste Classification**

The analysis results of sampling activities undertaken to date indicate that surficial fill material across the site can generally be classified as "General Solid Waste" with the following exceptions. Exceedances of the CT1 and CT2 criteria detailed within Table 1 of the NSW EPA Waste Classification Guidelines – Part 1 were noted as follows:

- **Restricted Waste** - fill materials in 12 locations are currently classified as "Restricted Waste" due to the reported concentrations exceeding the CT1 criteria for lead at four locations (BH21, BH27, BH28 and BH38), mercury at eight locations (BH19, BH20, BH23, BH28, BH30, BH40, BH41 and BH42), nickel at one location (BH38) and benzo(a)pyrene at one location (BH30). Mercury concentrations exceeding the CT1 criteria were all detected in shallow soils (0.1 mbgs) within the footprint of the former bowling greens and are anticipated to be associated with former green keeping activities.
- **Hazardous Waste** – fill materials in four locations (BH22, BH29, BH30 and BH35) are currently classified as "Hazardous Waste" due to the reported lead concentrations exceeding the CT2 criteria. These locations were within fill material at the eastern margin of both former bowling green where fill material is generally at its deepest. Lead impacts at each location are delineated on-site, except for BH35, adjacent to the northern site boundary.
- SMEC report: Lead, nickel and benzo(a)pyrene were noted as contaminants of concern. All samples exceeding the GSW threshold were analysed for TCLP to characterise the mobility of the contaminants of concern. Samples analysed using TCLP for benzo(a)pyrene were all below detection. Nickel and lead were detected in samples analysed using TCLP however only sample BH11_4.3-4.5 exceeded TCLP criteria.
- As such SMEC determined the site was classified as General Solid Waste with the exception of a 'hotspot' BH13 which was classified as Restricted Solid Waste under the prevision of General Immobilisation Approval 2009/07. It was suggested that the extent of the hotspot was unknown and further investigation to delineate could determine this.

It should be noted that these classifications are based on the conservative specific contaminant concentration (SCC) values applied by Table 1 of NSW EPA Waste Classification Guidelines – Part 1 in the absence of TCLP data. Following collection of additional data including TCLP

analysis, the SCC values applicable with TCLP results are considerably less conservative (assuming the TCLP values are not exceeding the criteria) and it is anticipated that the fill material classifications should change considerably, resulting in a much larger quantity of fill being classified as “General Solid Waste” with minimal material classified as “Hazardous Waste”.

These areas of fill will be further investigated, delineated with greater accuracy, resampled and submitted for TCLP analysis during excavation when full access is available to those fill material domains.

Any soils containing asbestos would also be classified as Special Waste - Asbestos Waste. In accordance with the NSW Waste Regulation 2014, waste soils must only be disposed to a waste facility that is appropriately licenced to receive the incoming waste.

The fill material at site cannot be classified as VENM/ENM due to its imported and contaminated nature.

It should be noted that whilst not all fill material falls within the basement excavation it wil be required to be excavated out as part of site works.

**Natural Material Waste Classification**

Currently the sample analysis results indicate that natural material across the site can be classified as “VENM” for off-site disposal purposes. No exceedances of the waste criteria were reported in the samples collected.

Cross-sections included in **Appendix A** show the extent of the excavation for the removal of soil at the site for the proposed development.

# 15.0 DISCUSSION – SOIL

Soil samples were collected on site in the initial SMEC soil assessment and on to subsequent assessments by LRM. The initial LRM assessment was additional grid and targeted soil assessment works and the second assessment was for the installation of three groundwater wells and two deeper soil bores, with soil samples taken in natural material in all five bores (including the three groundwater wells) to target the natural profile underlying the fill material.

The initial soil assessment primarily targeted the site fill material, the second assessment groundwater and natural material.

It is noted not all soil bores terminated in natural material or delineated deeper impacts of heavy metals or PAHSs. As the general profile of the sites natural material beneath the fill layer is relatively well understood and documented this is not considered significant to the conceptual model of the site.

Deeper hot spot targeting will be more appropriate during excavation works undertaken for fill material disposal were impacted materials may be segregated and treated independently from other site soils specifically where they may require treatment / stabilisation.

## 15.1.1 Human Health

The risk based investigation levels developed by the National Environmental Health Forum (NEHF) and incorporated under the NEPM 'Assessment of Site Contamination' for; Low-density Residential Scenario (A levels – used for workers), Medium to High-density Residential Scenario (B levels) are based on a relatively conservative assessment of the potential exposure of adults and children assuming 100% bioavailability of contaminants.

Given the development proposed of the site and the fact that all fill material at the site will be excavated and disposed off-site, the future risk the site soils pose to human health is considered low.

## 15.1.2 Soil Disposal Classification

Soils were compared to the 2008 NSW EPA soil disposal criteria and also the criteria detailed with the NSW EPA excavated natural material order 2014 for off-site disposal purposes.

**Fill Material Waste Classification**

These are conservative results without TCLP and will be further delineated with greater accuracy and TCLP analysis during excavation when full access is available to those fill material domains with results and classification expected to drop a level of classification in general.

The fill material at site cannot be classified as ENM due to its imported and contaminated nature.

SMEC and LRM borelogs were used in conjunction with the development plans to determine the approximate volumes of imported and natural materials that will be required to be excavated as part of the development of the site. Soil chemistry data was then used in conjunction with the estimated volumes of fill and natural materials to estimate the volumes of each soil disposal category.

The development plans show that an area of the site is to be dug to 42.40 m AHD for a four level basement. The area to be excavated is approximately 16,000 m3 however as the site's ground surface level varies greatly, the surface elevation across the site was used to more closely represent the volumes to be removed.

The majority (~80%) of the soil to be removed is natural in origin with the surface fill atop it also to be disposed of. The calculated approximate volumes of fill and natural materials to be excavated are shown below.

- Imported Material: 27,200 tons
- Natural Material: 100,150 tons

The natural materials are to be disposed of as Excavated Natural Material and the imported material is to be disposed of as General Solid Waste, Restricted Solid Waste and some Hazardous Solid Waste. It is assumed of the imported material the majority is Restricted Solid Waste (70%) with approximately 15% is Hazardous Solid Waste and 15% General Solid Waste however this is a preliminary estimation only and will change as further investigation occurs.

The calculated approximate volumes of General Solid Waste and Restricted Solid Waste of imported fill are shown below.

- General Solid Waste: 4,080 tons
- Restricted Solid Waste: 21,760 tons
- Hazardous Solid Waste: 4,080 tons

Figure 9 shows a cross section of the site, running from west to east, across the area of excavation. This cross section uses a vertical exaggeration of 4X to show the varied surface elevation and depths of soils across the area of excavation. The depth of excavation as per development plans is also shown in this cross section.

**Natural Material Waste Classification**

Currently the sample analysis results indicate that natural material across the site can be classified as "VENM" for offsite disposal purposes. No exceedances of the waste criteria were reported in the samples collected.

### 15.1.3 Ecological Risks

NEPM criteria and have been adopted for the ESLs as per Schedule B (1), Appendix A, Table A1, adopting Urban Residential/Public Open Space. Calculated site specific EILs will be conducted once final site levels are determined following fill material removal to assess any remaining ecological impacts.

## 16.0 SOIL VAPOUR ASSESSMENT

No direct soil vapour assessment has been conducted as part of this assessment; however results from the soil and groundwater assessment have been compared to adopted NEPM vapour risk criteria with results indicating that no vapour risk is considered likely to exist at the site. Additionally, during soil sampling headspace bag samples were collected and screened using a PID with no significant readings. PID readings are recorded on the field bore-logs within Appendix C. Readings below 10ppm are considered to be not significant due to potential for moisture interference. Bore logs have been updated with exact original PID readings.

## 17.0 GROUNDWATER ASSESSMENT

### 17.1 Groundwater Assessment Objectives

- Identify and intercept uppermost aquifer, determine aquifer flow direction, elevation, and likely point of discharge
- Assess the data collected from the sampling and analysis program against policies, regulations, guidelines and standards currently adopted in the State of New South Wales. Data exceeding the appropriate requirements is evaluated in terms of the risks posed by the contamination and remedial measures to be undertaken to remove or minimise those risks;
- Assess the impact of landfill material on groundwater conditions on and off-site; and
- Report findings in a format suitable for review by EPA appointed environmental auditor.

### 17.2 Groundwater Assessment Criteria

- *Contaminated Sites: Guidelines for the Assessment and Management of Groundwater Contamination, March 2007, NSW DEC.*
- *SEPP 55*
- *NEPM Schedule B(1) – Investigation Levels for Soil and Groundwater, 2013*
- *Schedule B(6) of the site contamination measure (NEPC 2013).*
- *Sydney Harbour and Parramatta RiverWater Quality Objectives*
- *NSW EPA, Waste Classification Guidelines November 2014*
- *NSW EPA, Designing Sampling Programs for Sites Potentially Contaminated by PFAS, November 2016*

- *HEPA, PFAS National Environmental Management Plan January 2018*

## 17.3 Groundwater Monitoring Well Location Selection Criteria

This report presents an assessment of the groundwater conditions at the site via the sampling and analysis of the three groundwater monitoring wells installed at the site, including field stabilisation measurements taken during groundwater purging prior to sampling. The purpose of the groundwater monitoring was to assess the groundwater quality beneath the site and any impacts on groundwater quality from the sites in-filled material and potential impacts on the adjacent surface waterway, Gore Creek to the east. Due to the aspect of the site adjacent the creek, drilling access was restricted down-hydraulic gradient of the site. This will be addressed within the future remediation action plan.

The current three groundwater wells have been installed as permissible by site access limitations. Figure 9 present the groundwater well locations against site features.

- GW01 is in an ideal location to represent up gradient inflowing groundwater to the site being in the upper north east car park area.
- GW02 is installed to the eastern side of the upper bowling green, representing groundwater in the upper third of the in-filled area of the site.
- GW03 is installed to the eastern central side of the lower green. Having met repeated refusal at the very eastern edge of the green, the well was installed at 9 m bgl within natural material. The maximum depth was reached and the well installed with a likely dry column. Groundwater eventually formed a water column within the well, however, it is not known at this stage whether this represents the upper aquifer or a thin perched layer migrating atop natural rock towards the creek. This will be addressed within the future remediation action plan.

At this stage, access does not allow the installation of any groundwater wells further to the east between the eastern extent of the in-filled area and Gore Creek. Further wells would be required in this area once access permits in order to more accurately assess any potential contaminants leaving the site, and their impact on Gore Creek.

It is likely surface water (and potentially sediment sampling) within Gore Creek, up and down gradient of the site, will be required to further characterise any potential impacts based on identified contaminants of concern exceeding groundwater criteria adopted for the site and for Gore Creek.

# 18.0 DATA QUALITY ASSESSMENT - GROUNDWATER

To minimise the potential for unrepresentative data, DQIs for the groundwater sampling program will be evaluated. The DQIs for sampling techniques and laboratory analysis of collected samples will be based on those listed in Section 4.1 of the NSW EPA Auditor Guidelines (DEC October 2017). Step 5 and Step 6 of the data quality objectives will be assessed by reference to data quality indicators.

**Field and analytical QA/QC**

The control measures generated from the field sampling and analytical works program were as follows:

- Suitable records of field observations including well installation logs, development records and groundwater field stabilization logs, including visual observations for turbidity, coloration, sheen and olfactory observations (Appendix C);
- Use of appropriate sampling methods as per the attached SAQP (Appendix C);
- Preservation and storage of samples post collection and during transit – refer laboratory SRA (sample receipt advice) regarding temperature of samples and attempt to cool observed upon receipt of samples at laboratory (Appendix E);
- Completed (COC) chain of custody and laboratory sample receipt documentation (Appendix E);
- All Sample holding times were within acceptable limits – samples were delivered to the receiving laboratories on the day of sampling;
- All samples have been analysed by NATA accredited Laboratories namely Envirolab using appropriate methods to allow for data comparison to adopted investigation levels;
- Laboratory quality control measures have been conducted in line with NEPM requirements. The laboratories followed internal quality control procedures, e.g. routine analysis of standard solutions, reference materials, reagent blanks, laboratory duplicates and spikes and surrogates. To assess the extent of matrix bias or interference on analyte recovery and sample to sample precision, numerous spike recovery appraisals were conducted by the laboratory. Recovery percentages for the soil spikes were generally between the LRM acceptable ranges of 70 – 130%, or 30 – 150% for phenols, indicating little negative or positive bias on reported analyte concentrations;
- Laboratory RPD acceptance criteria were exceeded at any stage during the assessment;
- Field blanks and duplicate/ split samples were collected in accordance with Australian standards and are discussed further below; and
- Laboratory Data has been reviewed for the occurrence of anomalous or unusual results which are inconsistent with field observations. The majority of the data was considered to be consistent with field observations relating to the levels of contaminants reported.

**Relative Percent Difference Calculations**

LRM adopt nominal acceptance criteria of 30% RPD for duplicates and splits for results >30 times the LOR, 50% for results between 10-30 times the LOR, and 100% for results <10 times the LOR.

Duplicate and Triplicate samples taken during sampling were analysed for the full analyte suite as undertaken for the primary sample (GW01) during the DESI. All RPDs relating to the groundwater samples were within acceptable criteria, with the exception of levels of copper.

The copper RPD exceedance can be attributed to the low concentrations reported. It was also noted that the concentrations reported in the duplicate and triplicate groundwater samples were consistent and below the concentration reported in the primary sample, hence the primary sample concentrations is more conservative.

As all the RPDs (with the exception of copper) are within the acceptable limits, the data retrieved is considered repeatable and highly reliable. Attached tables provide the RPDs that could be calculated with over 99.375% of results falling within acceptable criteria as per AS4482.1 2005.

Refer Table 23 within Appendix D for groundwater RPD calculation results.

**Field Blanks**

Trip blanks were prepared in 40 mL glass vials with a teflon septum lids and pre-prepared with hydrochloric acid. The trip blanks accompanied the samples throughout the entire sampling procedure and during delivery to the receiving laboratory. A trip blank was taken during the soil and groundwater sampling program as they were conducted on the same day and were analysed for TRH C6-C9 to determine if samples were potentially exposed to any volatile contaminants via cross contamination during storage and transport.

Rinsate blanks were taken from the third stage of the decontamination procedure (the first stage being a solution of tap water and 'Decon 90'; the second stage – tap water; and the third stage is deionized rinse water only) to ensure the decontamination procedure is effective and being appropriately undertaken. Rinsate samples taken during the soil and groundwater sampling program were analysed for metals. During sampling all equipment used was decontaminated in the abovementioned fashion.
Trip and rinsate blank sample analysis reported no analyte concentrations above the laboratory limit of reporting.

Refer to Table 25 in Appendix D for QA/QC field blank results.

**QA/QC Evaluation against Data Quality Indicators**

**Completeness** – is a measure of the amount of useable data (expressed as %) from data collection activities. The completeness goal is set at there being sufficient valid data generated during the study. If there is insufficient valid data, then additional data are required to be collected. Completeness can be influenced by field issues such as access for sampling or by laboratory issues such as adherence to sample holding times. Samples were collected and analysed from two of the three groundwater monitoring wells on-site and accordingly the data set is considered 66.6% complete. However, based on the location of the groundwater

monitoring wells and the reported concentrations of analytes reported in the sampled wells, the expected results from the third un-sampled monitoring well are considered unlikely vary.

**Comparability** – the confidence (expressed qualitatively) that data may be considered to be equivalent for each sampling and analytical event. Comparability is achieved through adopting consistent sampling techniques and ensuring laboratories use consistent analysis techniques. All samples were collected using consistent and approved sampling techniques as detailed within the SAQP and were analysed at NATA accredited laboratories throughout all stages of the assessment works.

**Representativeness** - expresses the degree to which sample data accurately represents each media present on the site. Representativeness is achieved by collecting samples in an appropriate pattern across the site, by using a sufficient number of sampling locations to characterise the site and by using consistent, repeatable and appropriate methodologies. The monitoring well locations targeted groundwater as it entered the site, at the centre of site and as it exited the site giving a representative data set of groundwater conditions across the site. Samples from all monitoring wells were analysed for all of the identified COPCs. Accordingly the data is considered representative of the media and suitable for interpretative use.

**Precision** - measures the reproducibility or variation of data. The precision of the data is assessed by calculating the Relative Percent Difference (RPD) between primary and duplicate/ inter-lab split samples. Over 99.375% of calculated RPD results from 1 duplicate sample and 1 triplicate sample collected over the DESI stage of the groundwater assessment were within acceptable criteria as per AS4482.1 2005.

**Accuracy (bias)** - measures quantitatively the closeness of the reported data to the true value. Bias can be introduced during sample collection through cross contamination from contaminated equipment, during sample preservation and transport and from laboratory sample handling, preparation and analysis techniques. Accuracy is assessed by reference to the analytical results of laboratory internal QA/QC samples including spikes, blanks and reference standards. The nominal “acceptance limits” on laboratory control samples are defined as follows:

Laboratory spikes – 70-130% for metals/inorganics 60-140% for organics.
Laboratory duplicates - <30% for metals/inorganics, <50% for organics.
Laboratory blanks - <practical quantitation limit.

All laboratory spikes, duplicates and blanks were reported within acceptable limits and as such the reported data is considered to be of a sufficiently accurate for interpretive purposes.

Accuracy of field works is assessed by examining the level of contamination detected in trip and rinsate blanks. Blanks should return concentrations of all organic analytes as being less than the practical quantitation limit of the testing laboratory. All blanks collected and analysed during both the assessment reported results below the laboratory limit of reporting.

**Overall QA/QC Adequacy**

It is concluded that the quality control procedures have confirmed that overall data supplied by the laboratories is adequate to arrive at the conclusions of this report.

# 19.0 GROUNDWATER WELL INSTALLATION

## 19.1 Monitoring Well Construction Details

Drilling was undertaken with the use of solid stem augers and or push-tubes for soil sampling purposes where appropriate.

The groundwater monitoring wells were installed by a licensed drilling contractor (Stratacore Pty Ltd). The bore construction methodology is detailed below.

The groundwater monitoring wells were constructed with 50 mm, Class 18, PVC casing and were completed with sealed screw joints. The wells were backfilled with graded and cleaned packing sands around the screen and to 0.5 m above, followed by a bentonite seal, and then grouted with a mix of concrete and bentonite to surface level and topped with a lockable cap and flush gatic cover which was sealed with concrete.

Well depths were selected based on the identified depth of the uppermost aquifer. Groundwater was identified by a marked increase in moisture, at which point GW01 for example was left to stand for approximately one hour at 7 m, 8 m and 9 m and then installed. The process was followed during the installation of GW02 and GW03 as appropriate. The steady rise of standing water level following cessation of drilling indicates a semi-confined aquifer beneath the site. Well depths are listed below:

- GW01: 9.19 m bTOC
- GW02: 11.10 m bTOC
- GW03: 8.80 m bTOC

The groundwater monitoring well bore construction logs are presented in Appendix C.

## 19.2 Monitoring Well Development

GW03 was found to be dry on the XXX and as such was not developed. GW01 and GW02 had made water and were developed in the following manner:

- SWLs and well depth from the north point of the top of casing were measured.
- The well holding volumes were calculated from the water column height, screen length, borehole, screen and standpipe diameter and sand porosity. Three times this volume was purged from each well using hand bailers. See below for a list of purge volumes:
    - GW01: Approx. 4 m post installation – 21.5 L/HV (70 L removed)
    - GW02: Approx. 4 m post installation – 26 L/HV (80 L removed)
    - GW03: Approx. 1.2 m prior to second monitoring round (purged dry)
- A new hand bailer and string was used for each well.
- Water purged was collected in the stored waste drums for analysis and disposal when full at a later stage (as further GME still required).

- Groundwater purged from the wells was noted to be clear with minor turbidity throughout development clearing with time.

### 19.3 Groundwater Sampling Details

The following describes the field procedures used during the groundwater monitoring.

Groundwater sampling was undertaken on 14th May 2018 of GW01 and GW02 (LRM Pty Ltd) and of GW01 – GW03 on the 3rd August 2018 (EP Risk Pty Ltd). The sample collection involved purging and sampling through a low flow sampling technique with new, disposable bladder and tubing being lowered slowly into the well and sampling was undertaken once field quality parameters stabilized. Field parameters were recorded by an ex-situ flow through cell. Samples were placed into laboratory prepared containers, and then placed into chilled and appropriately preserved containers for delivery to the laboratory.

The wells were stabilised with the aim of collecting samples that were representative of the groundwater present at the site. The samples were analysed for broad spectrum analytical suites, as per table 15 below.

On-site field measurements included temperature, water temperature, electrical conductivity, pH, redox, dissolved oxygen, standing water level and visual and olfactory observations. Groundwater monitoring field sheets are attached in Appendix C.

**Table 15: Groundwater Rounds Sampling Analytes**

| Well | Round | Analytes |
|---|---|---|
| ***GW01*** | 1 | NEPM HIL Screen, TDS, Cations & Anions, pH |
| | 2 | TRH/BTEX, VOCs, PAHs, Total Phenolics, Phthalates, OCPs, PCBs, TDS, pH, metals (Al, Ag, As, B, Ba, Be, Cd, Cr, Co, Cu, Fe, Pb, Mn, Hg, Mo, Ni, Se, Sb, Sn, Ti, V, Zn), cation/anions, ammonia, flouride, Hexavalent chromium, total cyanide, PFAS & PFOS |
| ***GW02*** | 1 | NEPM HIL Screen, TDS, Cations & Anions, pH |
| | 2 | TRH/BTEX, VOCs, PAHs, Total Phenolics, Phthalates, OCPs, PCBs, TDS, pH, metals (Al, Ag, As, B, Ba, Be, Cd, Cr, Co, Cu, Fe, Pb, Mn, Hg, Mo, Ni, Se, Sb, Sn, Ti, V, Zn), cation/anions, ammonia, flouride, Hexavalent chromium, total cyanide, PFAS & PFOS |
| ***GW03*** | 1 | Dry |
| | 2 | TRH/BTEX, VOCs, PAHs, Total Phenolics, Phthalates, OCPs, PCBs, TDS, pH, metals (Al, Ag, As, B, Ba, Be, Cd, Cr, Co, Cu, Fe, Pb, Mn, Hg, Mo, Ni, Se, Sb, Sn, Ti, V, Zn), cation/anions, ammonia, flouride, Hexavalent chromium, total cyanide, PFAS & PFOS |
| ***Dup & Split*** | 1 | NEPM HIL Screen, TDS, Cations & Anions, pH |
| | 2 | TRH/BTEX, VOCs, PAHs, Total Phenolics, Phthalates, OCPs, PCBs, TDS, pH, metals (Al, Ag, As, B, Ba, Be, Cd, Cr, Co, Cu, Fe, Pb, Mn, Hg, Mo, Ni, Se, Sb, Sn, Ti, V, Zn), cation/anions, ammonia, flouride, Hexavalent chromium, total cyanide, PFAS & PFOS |
| ***Trip Blank*** | 1 | TRH |
| | 2 | TRH C6-C9 |
| ***Rinsate Blank*** | 1 | N/A – Container smashed in transit, sample compromised |
| | 2 | TRH, PAH, Heavy Metals |

### 19.4 Field Observations

Field observations were taken including standing water level, visible phase separated hydrocarbon (PSH) product, temperature, pH, redox, dissolved oxygen and electrical conductivity. Refer to Table 16 below and Appendix C for full stabilisation details. No PSH product was detected at any point during field investigations.

Collected field data observations also included any visual and/or odours identified during sampling. No hydrocarbon odours or sheens indicative of obvious contamination were noted during purging or sampling.

***Table 16: Groundwater Field Data Pre-Sampling and Stabilisation***

| Monitoring Well | Date | Round Number | Temp (°C) | Electrical Conductivity (uS/cm) | pH (Units) | Redox (mV) | Dissolved Oxygen (mg/L) |
|---|---|---|---|---|---|---|---|
| *GW01* | 14/05/2018 | 1 | 19.6 | 277 | 4.61 | 214 | 5.76 |
| | 3/08/2018 | 2 | 14.9 | 685 | 4.09 | 11 | 1.97 |
| *GW02* | 14/05/2018 | 1 | 19.2 | 344 | 5.11 | 189 | 5.18 |
| | 3/08/2018 | 2 | 16.7 | 288 | 3.45 | 49 | 3.42 |
| *GW03* | 3/08/2018 | 2 | 19.3 | 664 | 6.50 | 115 | 4.19 |

## 20.0 GROUNDWATER RESULTS

**Table 17: Groundwater Criteria Exceedance summary table**

| Analyte (Conc.) | Criteria Exceeded | Sample Location(s) | Round |
|---|---|---|---|
| *Aluminium* | GIL Fresh Waters | GW01 & GW02 | 1 & 2 |
| *Cadmium* | GIL Fresh & Drinking Waters | GW02 | 1 |
| *Copper* | GIL Fresh Waters | GW01, GW02 & GW03 | 1 & 2 |
| *Iron* | ANZECC 2000 & ADWG 2015 | GW01, GW02 & (GW03 ANZECC 2000 only) | 1 & 2 |
| *Lead* | GIL Fresh Waters | GW02 | 2 |
| *Manganese* | ANZECC 2000 & ADWG 2015 | GW01 – ADWG for Round 2 only<br>GW02 – No Exceedances in Round 2<br>GW03 – ADWG Only | 1 & 2 |
| *Nickel* | GIL Fresh & Drinking Waters | GW01 (Round 1 GIL FW only), GW02 & GW03 | 1 & 2 |
| *Zinc* | GIL Fresh Waters & ANZECC 2000 | GW01, GW02 & GW03 | 1 & 2 |

Concentrations of Chlorinated hydrocarbons, halogenated benzenes, halogenated hydrocarbons, TPH, BTEX, PAHs, MAHs, OCPs, phenols, phthalates and PCBs were all reported below the laboratory limit of reporting (see detail below regarding LOR vs Criteria)

Refer to Figures 4 and 7 within Appendix A for groundwater well locations and criteria exceedances respectively.

The full laboratory results are presented in Tables 18a, 18b and 18c within Appendix D. Certificates and COCs of the groundwater analysis are presented in Appendix E. The following section outlines the results of the groundwater analytical results.

## 21.0 GROUNDWATER DISCUSSION

Concentrations of metals including aluminum, cadmium, copper, iron, lead, manganese, nickel and zinc were reported exceeding the drinking water, fresh water and marine water criteria for the site during the recent monitoring round. It should be noted that the concentration reported were minimal and consistent across the site including the up-gradient well GW01 indicating that these concentration are likely naturally occurring and not derived from historical uses at the site.

Also as no volatile organic compounds were reported this indicates that the sites groundwater assessed is unlikely to pose a vapor risk to current and future site users.

PFAS / PFOS compounds were added as contaminants of concern for the second round of groundwater sampling on all three wells. Low levels were reported at wells GW01 and GW02 and non-detects for all compounds al GW03 towards the sites eastern boundary. The highest levels reported were at the up-gradient well to the west, GW01, indicating there is currently no detectable impact on the site groundwater from PFAS / PFOS compounds emanating from the in-filled materials.

TDS was reported at between 180 – 470mg/L with levels at the up-gradient well GW01 being similar to the down gradient well GW03 indicating the site is not having a negative impact of the groundwater exiting towards Gore Creek.

Sydney Harbour and Parramatta Upper Estuary / Areas affected by Urban Development Water Quality Objectives, Aquatic ecosystems, visual amenity and secondary contact recreation criteria aimed at Maintaining or improving the ecological condition of water bodies and their riparian zones over the long term which applies to all natural water including Gore Creek, which will require background levels of listed indicator criteria to be established upstream and downstream of the site to determine if any site derived negative impacts have occurred.

Further investigation is required in the eastern section to further assess the final edge of the landfill material prior to Gore Creek and this is addressed in the RAP where access via significant excavation works is required to allow practical access for a drill rig into this eastern edge area of the site. This stage of works would coincide with surface water / sediment sampling in Gore Creek.

Compounds with criteria below detection. Listed next to the method type and applicable criteria. None of the below contaminants were identified in the site soil assessment as contaminants exceeding NEPM criteria. Only benzo(a)pyrene was identified in two locations exceeding general fill criteria. Analysis of TCLPs will be required prior to acceptance to landfill. As such the below list is not currently considered significant to the characterisation of the sites

groundwater. However the detection limits on these listed contaminants will be lowered for future groundwater sampling rounds:

- Metals, **Silver (Filtered),** ANZECC 2000 FW 95%, Aquatic Ecosystems
- Metals, **Chromium (hexavalent) (Filtered),** ANZECC 2000 FW 95%, Aquatic Ecosystems
- OCP in water, **DDT**, ANZECC 2000 FW 95%, Aquatic Ecosystems
- OCP in water, **Endrin**, ANZECC 2000 FW 95%, Aquatic Ecosystems
- OCP in water, **Heptachlor**, ANZECC 2000 FW 95%, Aquatic Ecosystems
- PAHs in Water, **Benzo(a) pyrene**, NEPM 2013 Table 1C GILs, Drinking Water
- PCBs in water, **Arochlor 1242**, ANZECC 2000 FW 95%, Aquatic Ecosystems
- PCBs in water, **Arochlor 1254**, ANZECC 2000 FW 95%, Aquatic Ecosystems
- Phthalates in water, **Bis(2-ethylhexyl) phthalate**, NEPM 2013 Table 1C GILs, Drinking Water
- Phthalates in water, **Di-n-butyl phthalate,** NEPM 2013 Table 1C GILs, Drinking Water
- VOCs, **1,1-dichloroethene**, Recreational water quality and aesthetics, Secondary Contact Recreation
- VOCs, **Bromomethane**, NEPM 2013 Table 1C GILs, Drinking Water
- VOCs, **Hexachlorobutadiene**, NEPM 2013 Table 1C GILs, Drinking Water
- VOCs, **Vinyl Chloride**, NEPM 2013 Table 1C GILs, Drinking Water

It is considered, based on the results reported from groundwater samples obtained to date at the site, that the groundwater assessed is unlikely to pose a risk to the current or proposed future site use and is considered not to been polluted as a result of historic site activities.

## 21.1 Sensitive receptors and Water Quality Objectives

The site reconnaissance did not reveal evidence of water pooling or seepage. The nearest sensitive receptor to the site is judged to be predominantly via surface run-off directed towards off-site municipal storm water drains, Gore Creek and Tambourine Creek, Lane Cove River and Woodford Bay, Parramatta River and ultimately Sydney Harbour.

Surveying and gauging of the on-site monitoring well network indicates that the groundwater is interpreted to flow generally south-easterly across the site, following the topography, toward Gore Creek. Refer to Figures 8a and 8b in Appendix A for groundwater monitoring well locations and flow directions.

## 21.2 Site Dewatering and Discharge Licenses

During construction, site dewatering will be required during the basement excavation works as the planned excavation extends to 12 m bgl and the sites groundwater will be intersected. Dewatering works will result in discharge of the water to the local storm-water drainage system operated by Sydney Water. Temporary extraction and discharge licenses will be required from DPI Water and Sydney Water respectively. Groundwater will likely require treatment prior to discharge from the site relating to pH adjustment and removal of suspended solids prior to release from site.

Any such requirements will likely be stipulated by the discharge license conditions from Sydney water.

Any geotechnical engineering recommendations to reduce the likely lowering of the water table should be adhered to.

# 22.0 CONCEPTUAL SITE MODEL

The revised conceptual site model is derived from the findings of the DESI program for both soil and groundwater in order to identify any potential and any actual risks under the current and future proposed uses of the site including whilst under construction.

## 22.1 Sources

- The historical fill material identified at the site with impacts from lead, mercury, zinc and PAHs.
- The application of Methyl mercury to the bowling greens for pest control
- Asbestos and building / demolition debris (aesthetic)
- Landfill leachate

The identified depth of fill across the site extended up to 9.0 mbgl at its deepest point. All fill material at the site will be removed prior to the proposed site development been undertaken and final site surface validation sampling round will be undertaken.

There is no requirement to assess soil vapour at the site at this stage based on the soil and groundwater assessment results.

Groundwater reported no concentrations exceeding the adopted human health criteria (with the exception of metals which were considered natural based on their reported concentrations and consistency across the site) and no volatile analytes were identified, therefore, groundwater is not considered to have been impacted by analyte concentrations reported within soil at the site at this stage of the assessment.

## 22.2 Data Gaps

Data gaps remain on site primarily due to access issues associated with the sites elevation changes and vegetation coverage.

Test pitting following demolition and vegetation removal works will reveal the full extent of the site surface, further delineation of impacts related to the fill material and groundwater, below details the current identified data gaps;

- Asbestos delineation sub-surface in the fill and beneath vegetation;
- Aesthetic issues in fill material;
- Further grid soil samples in areas of currently inaccessible gradient;
- TCLP analysis of hot spots for more accurate waste disposal classification;
- Hot spot delineation vertically and laterally for more accurate volume estimates;
- EIL sampling of remaining soils for specific criteria calculations;

- Further groundwater wells to the eastern side of site once access is viable to assess potential impacts to Gore Creek;
- Additional soil sampling into the riparian zone to determine impact and extent of intruding fill material;
- Surface water and sediment sampling within Gore Creek to assess impacts from site fill material and groundwater;
- Lower LOR or identified analytes where appropriate;
- Asbestos and hazardous materials survey of the building;

**Geology**

The main geological units encountered and or at the site, in order of stratigraphic sequence from youngest to oldest include:

- Fill material - generally clays, silts and sands containing in areas, anthropogenic materials including glass, brick cement ceramics, glass and other miscellaneous debris and occasional organic material including roots.
- Natural – Quaternary Holocene Sands, light brown, fine to medium grained, dry.

**Exposure Pathways**

Based on the identified receptors and the release, fate, and transport characteristics of the CoPC, pathways through which receptors may become exposed include inhalation, ingestion and dermal absorption. These are discussed briefly below in the context of the site setting:

**Current Site User Risks**

- Inhalation Exposure Pathway: There is currently low potential for creation of dust during disturbance of soils.
- Ingestion Exposure Pathway: There is a low risk of ingestion of contaminants by current site occupants through day-to-day activities and direct contact with contaminated soils or surface water.
- Groundwater: No identified risk to current site users is indicated. No identified risk to ecological receptors, though groundwater is likely to discharge to the Gore Creek and ultimately to Lane Cove River.
- Dermal Exposure Pathway: There is low likelihood of exposure that may occur via sorption through biological membranes such as skin. This pathway may be a concern whenever contaminated soil; surface water or groundwater comes into direct contact with a biological membrane. Current site gardeners should take basic personal protective measures by using gloves.

**Construction / Development Stages**

- Inhalation Exposure Pathway: There is the potential for inhalation of dusts from potential soil contamination associated with the historic site activities. There is also the potential for creation of dust during disturbance of soils and infrastructure. Risk of potential inhalation of contaminated dusts during future site works.
- Ingestion Exposure Pathway: Ingestion of contaminants by constructions workers may occur through day-to-day activities and direct contact with contaminated soils or surface water.

- Groundwater: Dewatering will be required during basement development works. No significant risk is posed to site workers from ingestion of the groundwater.
- Dermal Exposure Pathway: Exposure may occur via sorption through biological membranes such as skin. This pathway may be a concern whenever contaminated soil; surface water or groundwater comes into direct contact with a biological membrane. This pathway could also be a concern if contaminated surface water (runoff from the site) was to come into direct contact with benthic and aquatic flora and fauna within off-site surface water receiving environments. Site construction workers will also likely encounter fill materials during initial site works.

**Future Site Users**

- Inhalation Exposure Pathway: No future risk will remain as all contaminated fill will be removed from site during development works.
- Ingestion Exposure Pathway: No future risk will remain as all contaminated fill will be removed from site during development works.
- Groundwater: No future risk to human health is identified. A low risk to ecological receptors is identified via naturally slightly elevated heavy metals concentrations, should groundwater discharge to local waterways.
- Dermal Exposure Pathway: No future risk will remain as all contaminated fill will be removed from site during development works. Garden areas will utilise imported or certified re-used clean fill material.

### 22.3 Receptors

The preliminary site investigation identified a number of potential human and environmental receptors of contamination provided an exposure pathway exists. The identified receptors are listed below:

Human Health Receptors:

- Current and future site workers including construction workers during site development and current commercial tenants;
- Future site high-density aged care facility residents;
- Future landscape gardeners in the deep planting zone;
- Off-site receptors including residents and workers on neighbouring properties and recreational users of nearby water courses.

Environmental receptors:

- On-site flora and fauna;
- Off-site ecosystems including down-gradient surface water environments including Gore Creek and Lane Cove River;
- Groundwater beneath the site.

## Soil Investigation

On the basis of the visual aspects of the site, review of the site history and results of soil analysis, the following conclusions can be drawn:

Given the development proposed of the site and the fact that all fill material at the site will be excavated and disposed off-site, the future risk the site soils pose to human health is considered low. The risk to current users is low as the site remains effectively sealed beneath the vegetation and no volatile impacts were report. Gardening maintenance is generally limited to mowing and therefore not disturbing or accessing the underlying impacted soils.

Soils were compared to the 2008 NSW EPA soil disposal criteria and also the criteria detailed with the NSW EPA excavated natural material order 2014 for offsite disposal purposes. Further classification delineation will be conducted during the test pitting program guided by the site RAP.

All site fill material will be excavated during site works thereby removing all NEPM exceedances identified.

**Fill Material Waste Classification**

The sample analysis results indicate that surficial fill material across the site can generally be classified as "**General Solid Waste**". Exceedances of the CT1 and CT2 criteria detailed within Table 1 of the NSW EPA Waste Classification Guidelines – Part 1 were noted relating to lead, mercury and B(a)P in 21 locations reported as "**Restricted Waste**" (without TCLP). Lead was reported as "**Hazardous Waste"** in 4 locations only currently without TCLP analysis. These will be further delineated with greater accuracy and TCLP analysis during excavation when full access is available to those fill material domains.

SMEC as part of their combined investigation drilled 15 boreholes across the site and took samples at strategic depths at each. Soil chemistry results were compared to NSW EPA Waste Classification Guidelines and exceedances noted. Lead, nickel and benzo(a)pyrene were noted as contaminants of concern. All samples exceeding the GSW threshold were analysed for TCLP to characterise the mobility of the contaminants of concern. Samples analysed using TCLP for benzo(a)pyrene were all below detection. Nickel and lead were detected in samples analysed using TCLP however only sample BH11_4.3-4.5 exceeded TCLP criteria.

As such SMEC determined the site was classified as General Solid Waste with the exception of a 'hotspot' BH13 which was classified as Restricted Solid Waste under the prevision of General Immobilisation Approval 2009/07. It was suggested that the extent of the hotspot was unknown and further investigation to delineate could determine this.

The fill material at site cannot be classified as ENM due to its imported and contaminated nature at this stage.

**Natural Material Waste Classification**

Currently the sample analysis results indicate that natural material across the site can be classified as "VENM" for offsite disposal purposes. No exceedances of the waste criteria were reported in the samples collected within the natural material beneath the fill layer.

## Groundwater Investigation

A groundwater monitoring network consisting of 3 groundwater monitoring wells was installed across the site.

Concentrations of metals including aluminum, cadmium, copper, lead, nickel and zinc were reported exceeding the Australian drinking water guidelines 2015, NEPM GIL fresh and drinking waters, ANZECC 2000 criteria for the site during the recent monitoring round. However, it should be noted that the concentration reported were minimal and consistent across the site indicating that these concentration are likely naturally occurring and not derived from historical uses at the site.

Concentrations of Chlorinated hydrocarbons, halogenated benzenes, halogenated hydrocarbons, TPH, BTEX, PAHs, MAHs, OCPs, phenols, phthalates and PCBs were all reported below the laboratory limit of reporting.

No volatile organic compounds were reported, indicating that the groundwater assessed is unlikely to pose a vapor risk to current and future site users.

It is considered, based on the results reported from groundwater samples obtained at the site, that the groundwater assessed is unlikely to pose a risk to the current or proposed future site use and is considered not to been polluted as a result of historic site activities. Further investigation is required to adequately assess potential impacts to Gore Creek.

## Conclusions

- Site workers potentially coming into contact with contaminated fill material will require contact personal protective equipment in the form of gloves, long sleeves and pants to protect against any dermal contact.
- The fill material removal works will be subject to the implementation of control measures which will be detailed in the RAP.
- All site fill material will be excavated during site works thereby removing all NEPM exceedances identified.
- Surficial fill soils at the site can be classed in general as “General solid waste” and “Restricted waste” for offsite disposal purposes.
- Isolated areas of Hazardous wastes will be further investigated, delineated and classified by TCLP and test pitting.
- Underlying natural materials can currently be classified as natural material largely meeting the definition of virgin excavated natural material (VENM) as detailed in the Protection of the Environment Operations Act 1997 (POEO Act).

Further delineation investigation through additional sampling should be undertaken post demolition more accurately classify the natural soil profile beneath the upper layer of fill material.

**Final statement**

The site at 266 Longueville Road Lane Cove will be suitable, upon remediation, for the proposed high density residential aged care facility.

- Based on the soil and groundwater data to date, the site is considered suitable for the proposed aged care facility development with no human health risk posed by the identified subsurface conditions following the proposed off-site disposal of all fill material at the site.
- Currently the site poses no risk to site users including gardeners who currently maintain the bowling greens.
- Constraints on the sites current users should include no sub-surface or access to site soils without appropriate PPE and reference to the site Remediation Action Plan. Site soils / fill material are contaminated.

**Further works**

Further works required to more accurately characterize the site for land use acceptability, waste disposal classification and potential off-site impacts are required. These further works are detailed in the site Remediation Action Plan.

- Soil test pitting targeted locations for hot spot delineation vertically and laterally;
- Asbestos delineation;
- Aesthetic assessment;
- TCLP analysis for soil hot spots for waste classification;
- Further groundwater wells to the eastern boundary of the site to determine potential off-site impacts to Gore Creek;
- Surface water and sediment sampling of Gore Creek;
- Additional groundwater sampling with selected lower LOR as applicable;
- Soil sampling for EIL criteria calculations;
- Update the site RAP based on this final report.

## 23.0 STATEMENT OF LIMITATIONS

This report has been prepared for Australian Unity Ltd for the purpose set out herein. The services performed by LRM Global Pty Ltd have been conducted with the level of quality and expertise generally associated with activities of this nature by an environmental consulting practice.

Responsibility is disclaimed for any loss or damage other than to Australian Unity Ltd. LRM Global Pty Ltd does not accept any responsibility suffered by any other party whatsoever including, but not limited to, negligence on the part of LRM Global Pty Ltd.

This report is for the use of Australian Unity Ltd and its appointed New South Wales EPA approved environmental auditor and agents namely Brad May and Epic Environmental. LRM Global Pty Ltd does not intend that any other person accept or rely upon it. This report shall only be presented in full, except where written approval with comments is provided by LRM Global Pty Ltd.

The information contained in this report is considered to be accurate on the date of issue in accordance with the current conditions of the site. Whilst the report is accurate to the best of our knowledge and belief, LRM Global Pty Ltd cannot guarantee completeness or accuracy of any descriptions or conclusions based on supplied information, including but not limited to, information provided by previous site assessors and data arising from investigations by any other third party.

## 24.0 REFERENCES


AS 4482.1 – 2005 Guide to investigation and sampling of potentially contaminated soil, Part 1: Non- Volatile and semi-volatile compounds

AS 4482.2 – 2005 Guide to sampling and investigation of potentially contaminated soil, Part 2: Volatile substances

AS 2159 – 2009 Pilling Design and Installation

Australian and New Zealand Guidelines for Fresh and Marine Water Quality, ANZECC / ARMCANZ 1992.

Australian and New Zealand Guidelines for Fresh and Marine Water Quality, ANZECC / ARMCANZ 2000.

Australian Drinking Water Guidelines 6, NHMRC 2011 (updated 2017)

Technical Note, Investigation of Service Station Sites, NSW EPA April 2014

Guidelines for Groundwater Protection in Australia, ANZECC 1995.

NEPC Health Screening Levels – Groundwater HSL-A NEPC 2013

NHMRC/NRMC (2008) Guidelines for Managing Risks in Recreational Water (Health / Aesthetic)

NSW EPA Contaminated Sites Guidelines for Consultants Reporting on Contaminated sites, 1997 (updated 2011)

Schedule B(1) Guideline on Investigation levels for Soil and Groundwater NEPM, 2013 NEPC

Schedule B(2) Site Characterisation NEPM, 2011 NEPC

Schedule B(4) Guideline on Health Risk Assessment Methodology NEPM, NEPC 2011

Schedule B(5)b Guideline Methodology to Derive EIL's in Contaminated Soil NEPM, NEPC 2011

Schedule B(5)c Guideline for EIL's for Arsenic, Chromium III, Copper, DDT, Lead, Naphthalene, Nickel & Zinc NEPM, 2011 NEPC

Schedule B96) Guideline on the Framework for Risk-Based Assessment of Groundwater Contamination NEPM, NEPC 2011

CRC Care Technical Report no. 10: Health screening levels for petroleum hydrocarbons in soil and groundwater

NSW EPA Waste Classification Guidelines 2008

NSW EPA State Environmental Planning Policy No 55 – Remediation of Land – 1998 (July 2014)

NSW EPA Department of Urban Affairs and Planning, Managing Land Contamination, Planning Guidelines, SEPP 55 – Remediation of Land – 1998

NSW DEC Guidelines for the NSW Site Auditor Scheme (3rd Edition) October 2017

NSW EPA Contaminated Sites, Guidelines for the Assessment and Management of Groundwater Contamination, March 2007

www.qcc.nsw.gov.au

http://www.1100.com.au/

Geological Series Sheet 8726 (Edition 1) 1977 Geological Survey of NSW Department of Mines

NSW Natural Resource Atlas

NSW OEH Contaminated Land Database

*NSW DECC 2009, Waste Classification Guidelines – Part 1; Classifying Waste*

*Addendum to the Waste Classification Guidelines (2014) – Part 1: classifying waste October 2016*

*NSW DECC 2009, Waste Classification Guidelines – Part 4; Acid Sulphate Soils*

*NSW EPA Resource Recovery Order under Part 9, Clause 93 of the Protection of the Environment Operations (Waste) Regulation 2014 – The excavated natural material order 2014.*

*Resource Recovery Order under Part 9, Clause 93 of the Protection of the Environment Operations (Waste) Regulation, The excavated natural material order* 2014

**Consultant Reports**

SMEC Australia Pty Ltd, *266 Longueville Road, Lane Cove, Geotechnical and Environmental Investigation Report,* December 2011


SMEC Pty Ltd, Soil Sampling and Classification Program, Land at 266Longueville Road, Lane Cove, January 2012.

Applied Ecology Pty Ltd, *Flora, Fauna & Fungi Impact Assessment for a proposed development site at 266 Longueville Road*, January 2012, for Lane Cove Municipal Council.

Arcadis Australia Pacific Pty Ltd, *266 Longueville Road, May 2017*, for Australian Unity Limited.

# APPENDIX A

## SITE PLANS & FIGURES




Site Location

| Amemdmants | Site | 266 Longueville Road, Lane Cove NSW | | | N |
|---|---|---|---|---|---|
| | Title | Site Location Plan | | | |
| | Client | Australian Unity Limited | | | Figure 2 |
| | Date 07/03/2018 | Drawn DY | Checked JL | Scale | Job No: 27380 |

LRM GLOBAL
P.O. Box 1237
Carlton VIC 3053
Ph: (03) 9371 3400
www.lrmglobal.com.au
LRM GLOBAL PTY LTD
Liability and risk management




| | |
|---|---|
| Site | 266 Longueville Rd Lane Cove NSW |
| Title | Current Site Layout/Site Features Plan |
| Client | Australian Unity Pty Ltd |
| Date | 17/08/18 |
| Drawn | BP |
| Checked | JL |
| Scale | 1:20 (on A3) |

N

Figure 3

Job No. 27380

0m 3m 10m
1m 5m 20m

LRM GLOBAL
P.O. Box 1237
Carlton VIC 3053
Ph: (03) 9371 3400
www.lrmglobal.com.au
LRM GLOBAL PTY LTD
Liability and risk management




Assessment Boundary

GW03 Ground Water Monitoring Well

BH28 LRM Borehole Location

BH10 SMEC Borehole Location

| | | | |
|---|---|---|---|
| Site | 266 Longueville Rd Lane Cove NSW | | |
| Title | Sample Location Plan Soil and Groundwater | | |
| Client | Australian Unity Pty Ltd | | |
| Date 17/08/18 | Drawn DY | Checked JL | Scale 1:15 (on A3) |


N

Figure 4

Job No. 27380

0m 3m 10m
1m 5m

LRM GLOBAL
P.O. Box 1237
Carlingford 2065
T (02) 9871 0400
www.lrmglobal.com.au
LRM GLOBAL PTY LTD
Liability and risk management




| BH16 | Depth (mBGL) | 0.1 m |
|---|---|---|
| Lead | mg/kg | 110 |

| BH20 | Depth (mBGL) | 0.1 m |
|---|---|---|
| Mercury | mg/kg | 5.2 |

| BH21 | Depth (mBGL) | 3 m |
|---|---|---|
| Lead | mg/kg | 120 |

| BH35 | Depth (mBGL) | 0.1 m |
|---|---|---|
| Lead | mg/kg | 1,300 |

| BH38 | Depth (mBGL) | 0.1 m |
|---|---|---|
| Lead | mg/kg | 150 |
| Nickel | mg/kg | 93 |

| BH28 | Depth (mBGL) | 0.1 m | 3 m | 4 m |
|---|---|---|---|---|
| Lead | mg/kg | 10 | 130 | 150 |
| Mercury | mg/kg | 4.1 | 0.2 | <0.1 |

| BH19 | Depth (mBGL) | 0.1 m |
|---|---|---|
| Mercury | mg/kg | 6.4 |

| BH11 | Depth (mBGL) | 4.3-4.5 m |
|---|---|---|
| Lead | mg/kg | 360 |
| Mercury | mg/kg | 0.110 |
| Nickel | mg/kg | 1.40 |
| Benzo(a) pyrene | mg/kg | <0.5 |

| BH22 | Depth (mBGL) | 0.1 m | 1 m |
|---|---|---|---|
| Lead | mg/kg | 230 | 830 |

| BH27 | Depth (mBGL) | 0.1 m |
|---|---|---|
| Lead | mg/kg | 130 |

| BH23 | Depth (mBGL) | 0.1 m |
|---|---|---|
| Mercury | mg/kg | 4.2 |

| BH13 | Depth (mBGL) | 1.3-1.5 m | 4.3-4.5 m | 7.3-7.5 m |
|---|---|---|---|---|
| Lead | mg/kg | 42 | 7,300 | 1,400 |
| Leachable Lead | mg/L | - | 12 | 1 |
| Benzo(a) pyrene | mg/kg | 1 | 1 | 1 |

| BH10 | Depth (mBGL) | 0.0-0.2 m |
|---|---|---|
| Nickel | mg/kg | 46 |

| BH40 | Depth (mBGL) | 0.1 m |
|---|---|---|
| Mercury | mg/kg | 5.5 |

| BH42 | Depth (mBGL) | 0.1 m |
|---|---|---|
| Mercury | mg/kg | 5.2 |

| BH12 | Depth (mBGL) | 1.3-1.5 m | 4.3-4.5 m |
|---|---|---|---|
| Lead | mg/kg | 130 | 640 |
| Benzo(a) pyrene | mg/kg | 3 | 1 |

| BH41 | Depth (mBGL) | 0.1 m |
|---|---|---|
| Mercury | mg/kg | 4.1 |

| BH33 | Depth (mBGL) | 1 m |
|---|---|---|
| Benzo(a) pyrene | mg/kg | 2.2 |

| BH29 | Depth (mBGL) | 2 m | 3 m | 4 m | 5 m | 6 m | 7 m | 8 m |
|---|---|---|---|---|---|---|---|---|
| Lead | mg/kg | 220 | 49 | 790 | 740 | 260 | 540 | 6,200 |

| BH15 | Depth (mBGL) | 4.0-4.3 m |
|---|---|---|
| Lead | mg/kg | 650 |
| Benzo(a) pyrene | mg/kg | 2 |

| BH30 | Depth (mBGL) | 0.1 m | 1 m | 2 m | 3 m | 4 m | 5 m | 6 m |
|---|---|---|---|---|---|---|---|---|
| Lead | mg/kg | 10 | 150 | 53 | 130 | 210 | 130 | 500 |
| Mercury | mg/kg | 4.4 | <0.1 | 0.3 | 0.3 | 0.2 | <0.1 | 0.2 |
| Benzo(a) pyrene | mg/kg | - | 2.2 | - | - | 0.52 | - | - |

| NSW 2008 General Solid Waste SCC | NSW 2008 Restricted Solid Waste SCC and TCLP | NSW 2008 Restricted Solid Waste SCC | NSW 2008 Hazardous Solid Waste SCC |
|---|---|---|---|
| | | | |

Site: 266 Longueville Rd Lane Cove NSW
Title: Soil Exceedances plan - Waste Category
Client: Australian Unity Pty Ltd
Date: 17/08/18 | Drawn: DY | Checked: JL | Scale: 1:15 (on A3)
Figure: 5
Job No: 27380

Assessment Boundary
BH28 LRM Borehole Location
BH10 SMEC Borehole Location

0m 3m 10m
1m 5m

LRM GLOBAL
P.O. Box 1237
Carlton VIC 3053
Ph: (03) 9371 3400
www.lrmglobal.com.au
LRM GLOBAL PTY LTD
Liability and risk management




| BH35 | |
|---|---|
| Depth (mbgl) | 0.1 |
| Lead (mg/kg) | 1,300 |

| BH11 | |
|---|---|
| Depth (mbgl) | 4.3-4.5 |
| Lead (mg/kg) | 360 |

| BH29 | | | | |
|---|---|---|---|---|
| Depth (mbgl) | 4 | 5 | 7 | 8 |
| Lead (mg/kg) | 790 | 740 | 540 | 6,200 |

| BH13 | | |
|---|---|---|
| paste | 4.3-4.5 | 7.3-7.5 |
| Lead (mg/kg) | 7,300 | 1400 |

| BH30 | |
|---|---|
| Depth (mbgl) | 6 |
| Lead (mg/kg) | 500 |

| BH15 | |
|---|---|
| Depth (mbgl) | 4.0-4.2 |
| Lead (mg/kg) | 650 |

| BH22 | |
|---|---|
| Depth (mbgl) | 1 |
| Lead (mg/kg) | 830 |

| BH12 | | |
|---|---|---|
| Depth (mbgl) | 1.3-1.5 | 4.3-4.5 |
| Lead (mg/kg) | 130 | 640 |
| Carcinogenic PAHs (as BaP TEQ) | 3.2 | 0.5 |

| NEPM 2013 Table 1A(1) HILs Comm/Ind D Soil | NEPM 2013 Table 1A(1) HILs Rec C Soil | NEPM 2013 Table 1A(1) HILs Res A Soil | NEPM 2013 Table 1A(1) HILs Res B Soil |
|---|---|---|---|
| | | | |

Assessment Boundary

BH28 LRM Borehole Location

BH10 SMEC Borehole Location

| | |
|---|---|
| Site | 266 Longueville Rd Lane Cove NSW |
| Title | Soil Exceedances plan - HILs |
| Client | Australian Unity Pty Ltd |
| Date | 17/08/18 |
| Drawn | BP |
| Checked | JL |
| Scale | 1:15 (on A3) |
| Figure | 6 |
| Job No. | 27380 |

N

0m 3m 10m
1m 5m

LRM GLOBAL
P.O. Box 1237
Carlton VIC 3053
Ph: (03) 9371 3400
www.lrmglobal.com.au
LRM GLOBAL PTY LTD
Liability and risk management

| GW01 | | 14/05/2018 | 3/08/2018 |
|---|---|---|---|
| Aluminium (Filtered) | mg/L | 0.2* | 0.64* |
| Cadmium (Filtered) | mg/L | <0.0001 | <0.0001 |
| Copper (Filtered) | mg/L | 0.019 | 0.032* |
| Iron (Filtered) | mg/L | 2.3 | 2.9* |
| Lead (Filtered) | mg/L | 0.001 | 0.004* |
| Manganese (Filtered) | mg/L | **LNN** | **LMF** |
| Nickel (Filtered) | mg/L | 0.012 | 0.061* |
| Zinc (Filtered) | mg/L | 0.068 | 0.26* |

| GW02 | | 14/05/2018 | 3/08/2018 |
|---|---|---|---|
| Aluminium (Filtered) | mg/L | 0.12 | 1.7 |
| Cadmium (Filtered) | mg/L | 0.0003 | <0.0001 |
| Copper (Filtered) | mg/L | 0.012 | 0.018 |
| Iron (Filtered) | mg/L | 6.1 | 0.92 |
| Lead (Filtered) | mg/L | <0.001 | 0.005 |
| Manganese (Filtered) | mg/L | **LNT** | 0.036 |
| Nickel (Filtered) | mg/L | 0.037 | 0.063 |
| Zinc (Filtered) | mg/L | 0.12 | 0.23 |

| GW03 | | 3/08/2018 |
|---|---|---|
| Aluminium (Filtered) | mg/L | 0.01 |
| Cadmium (Filtered) | mg/L | <0.0001 |
| Copper (Filtered) | mg/L | 0.009 |
| Iron (Filtered) | mg/L | 0.24 |
| Lead (Filtered) | mg/L | 0.001 |
| Manganese (Filtered) | mg/L | **LMU** |
| Nickel (Filtered) | mg/L | 0.035 |
| Zinc (Filtered) | mg/L | 0.056 |

GW01

GW02

GW03

| ADWG 2015 Aesthetic | ANZECC 2000 FW 95%, Aquatic Ecosystems | NEPM 2013 Table 1C GILs, Drinking Water | Recreational water quality and aesthetics, Secondary Contact Recreation |
|---|---|---|---|
| | | | |

Assessment Boundary

GW03 Monitoring Well Location

Values with an asterisk are taken from either the Duplicate or the Split as these values were higher than their corresponding primary sample. Refer to GW Table.
Values in **bold** exceed multiple criteria.

| | |
|---|---|
| Site | 266 Longueville Rd Lane Cove NSW |
| Title | GW Exceedances Plan |
| Client | Australian Unity Pty Ltd |
| Figure | 7 |
| Date | 17/08/18 |
| Drawn | BP |
| Checked | JL |
| Scale | 1:15 (on A3) |
| Job No: | 27380 |

0m 3m 10m
1m 5m

LRM GLOBAL
P.O. Box 1237
Carlton VIC 3053
Ph: (03) 9371 3400
www.lrmglobal.com.au
LRM GLOBAL PTY LTD
Liability and risk management


GW01 | TOC (m AHD) | SWL (m BTOC) | SWL (m AHD)
29.05.2018 | 57.0540 | 4.4300 | 52.6240
GW02 | TOC (m AHD) | SWL (m BTOC) | SWL (m AHD)
29.05.2018 | 55.4850 | 6.7200 | 48.7650
GW03 | TOC (m AHD) | SWL (m BTOC) | SWL (m AHD)
29.05.2018 | 49.6560 | 8.3800 | 41.2760
GW01
GW02
GW03
Inferred GW Flow Direction
51
49
47
45
43
Assessment Boundary
Monitoring Well Location
SWL (intervals of 2 mAHD)
Site 266 Longueville Rd Lane Cove NSW
Title Standing Water Level 29/05/2018
Client Australian Unity Pty Ltd
Figure 8a
Job No: 27380
Date 9/08/18
Drawn BP
Checked JL
Scale 1:15 (on A3)
0m 3m 10m
1m 5m
LRM GLOBAL PTY LTD
Liability and risk management




| GW01 | TOC (m AHD) | SWL (m BTOC) | SWL (m AHD) |
|---|---|---|---|
| 3.08.2018 | 57.0540 | 4.3200 | 52.7340 |

| GW02 | TOC (m AHD) | SWL (m BTOC) | SWL (m AHD) |
|---|---|---|---|
| 3.08.2018 | 55.4850 | 6.7300 | 48.7550 |

| GW03 | TOC (m AHD) | SWL (m BTOC) | SWL (m AHD) |
|---|---|---|---|
| 3.08.2018 | 49.6560 | 7.2300 | 42.4260 |

Assessment Boundary


GW03 Monitoring Well Location

46 SWL (intervals of 2 mAHD)

| | |
|---|---|
| Site | 266 Longueville Rd Lane Cove NSW |
| Title | Standing Water Level 3/08/2018 |
| Client | Australian Unity Pty Ltd |
| Figure: | 8b |
| Job No: | 27380 |
| Date | 9/08/18 |
| Drawn | BP |
| Checked | JL |
| Scale | 1:15 (on A3) |

0m 3m 10m
1m 5m

LRM GLOBAL
P.O. Box 1217
Carlton VIC 3053
Ph: (03) 9371 3400
www.lrmglobal.com.au
LRM GLOBAL PTY LTD
Liability and risk management




Fill Material

Residual Soil

Sandstone

Area of Excavation

— SWL — Groundwater Standing Water Level

| | |
|---|---|
| Site | 266 Longueville Rd Lane Cove NSW |
| Title | F-F' Cross Section |
| Client | Australian Unity Pty Ltd |
| Figure | 9 |
| Job No | 27380 |


| Date | Drawn | Checked | Scale | Vertical Exaggeration |
|---|---|---|---|---|
| 7/08/18 | BP | JL | 1:10,000 (on A3) | 4X |

0m 3m 10m
1m 5m

N

LRM GLOBAL
P.O. Box 1237
Carlton VIC 3053
Ph: (03) 9371 3400
www.lrmglobal.com.au
LRM GLOBAL PTY LTD
Liability and risk management

# Figure 10 - Development Plans








1 AXONOMETRIC
1 : 75

0 1 2 3 5 10m

Australian Unity

**SENIORS LIVING VILLAGE PROJECT**

266 LONGUEVILLE RD
LANE COVE
NSW

© Copyright Thomson Adsett Pty Ltd.
ABN 76 105 314 654
Trading as ThomsonAdsett.

TA # 16.0161.12

Telephone +61 2 9003 9000
sydney@thomsonadsett.com
Suite 410, 50 Holt Street
Surry Hills
NSW 2010 Australia
thomsonadsett.com

thomson adsett

**PERSPECTIVES**

As indicated @ A1 | 21.09.2016

**A301** | **rev. A**







0 1 2 3 5 10m

Australian Unity

## SENIORS LIVING VILLAGE PROJECT

266 LONGUEVILLE RD
LANE COVE
NSW

© Copyright Thomson Adsett Pty Ltd.
ABN 76 105 314 654
Trading as ThomsonAdsett.

TA # 16.0161.12

Telephone +61 2 9003 9000
sydney@thomsonadsett.com
Suite 410, 50 Holt Street
Surry Hills
NSW 2010 Australia
thomsonadsett.com

thomson adsett

**PERSPECTIVES**

@ A1

21.09.2016

**A302**

**rev. G**




1 Northern Elevation
1 : 200




2 Southern Elevation
1 : 200

0 1 2 3 5 10m

Australian Unity

**SENIORS LIVING VILLAGE PROJECT**

266 LONGUEVILLE RD
LANE COVE
NSW

© Copyright Thomson Adsett Pty Ltd.
ABN 76 105 314 654
Trading as ThomsonAdsett.

TA # 16.0161.12

Telephone +61 2 9003 9000
sydney@thomsonadsett.com
Suite 410, 50 Holt Street
Surry Hills
NSW 2010 Australia
thomsonadsett.com

thomson adsett

**ELEVATIONS 1**

As indicated @ A1

21.09.2016

**A303**

**rev. G**




2 Western Elevation
1 : 200




1 Eastern Elevation
1 : 200

0 1 2 3 5 10m

Australian Unity

**SENIORS LIVING VILLAGE PROJECT**

266 LONGUEVILLE RD
LANE COVE
NSW

© Copyright Thomson Adsett Pty Ltd.
ABN 76 105 314 654
Trading as ThomsonAdsett.

TA # 16.0161.12

Telephone +61 2 9003 9000
sydney@thomsonadsett.com
Suite 410, 50 Holt Street
Surry Hills
NSW 2010 Australia
thomsonadsett.com

thomson adsett

**ELEVATIONS 2**


As indicated @ A1

21.09.2016

**A304**

**rev. G**















EXTERNAL PALETTE- MOOD BOARD


THE EXTERNAL MATERIALS WERE CHOSEN TO REDUCE THE VISUAL IMPACT ON THE LANDSCAPE; IN COLOURS THAT INTEGRATE WITH THE GREENERY FROM THE BUSHLAND AND SURROUNDINGS

THE BUILDING WOULD SIT ON A ROBUST SANDSTONE BASE, REMINISENCE OF THE SANDSTONE ROCK FOUND ON SITE. ATOP A LIGHT BUILDING WITH GENEROUS BALCONIES AND PRIVATE OPEN SPACES OVERLOOKING GENEROUS COURTYARDS, CREATING A WARM AND HOMELY FEELING.THE ASSYMETRIC BALCONIES CREATE THE IDEA OF EXCLUSIVITY AS EVERY APARTMENT HAS A DIFFERENT CONFIGURATION OF PLAN AND BALCONY.

THE AGED CARE FLOORS HAVE A VIEWING DECK, ENCLOSED IN GLASS ALLOWING VIEWS OF THE SURROUNDING GREENERY AND THE FAR DISTANT CITY VIEWS.

THE METAL MESH, SEMICOVERED ROOF ELEMENTS CREATE A LAYER OF PRIVACY AND SUN PROTECTION WHILE ADDING INTERESTING LIGHT AND SHADOW PATTERNS.

IMAGES ON THIS SHEET ARE FOR INDICATIVE REFERENCES ONLY AND DO NOT REPRESENT ANY THOMSON ADSETT PROJECT







0 1 2 3 5 10m

Australian Unity

**SENIORS LIVING VILLAGE PROJECT**

266 LONGUEVILLE RD
LANE COVE
NSW

© Copyright Thomson Adsett Pty Ltd.
ABN 76 105 314 654
Trading as ThomsonAdsett.

TA # 16.0161.12

Telephone +61 2 9003 9000
sydney@thomsonadsett.com
Suite 410, 50 Holt Street
Surry Hills
NSW 2010 Australia
thomsonadsett.com

thomson adsett

**MOOD AND MATERIALS BOARD - EXTERIOR**

1 : 1 @ A1

21.09.2016

**A350**

**rev. A**























ALL THE IMAGES ARE OF PROJECTS AND COPYRIGHT OF THOMSON ADSETT








INTERNAL PALETTE- MOOD BOARD

THE INTERIORS SHALL BE LUXURIOUS WITH CONTEMPORARY FINISHES, WHILST PROVIDING COZINESS MAKING THE APARTMENTS, AND RESIDENTIAL AGED CARE COMFORTABLE. THE SPACES SHALL HAVE FLEXIBILITY TO ALLOW FOR DIFFERENT FINISHES AND FURNITURE ACCORDING TO THE PREFERENCE OF THE RESIDENT

WAY FINDING IS PROPOSED TO BE DONE IN TWO OR MORE LANGUAGES TO EMBRACE THE DIFFERENT CULTURES OF LANE COVE RESIDENTS.

EACH SPACE IS DESIGNED TO PROVIDE A CALMING YET A RICH SENSORY EXPERIENCE TO THE RESIDENTS OF 266 LONGUEVILLE ROAD





0 1 2 3 5 10m

Australian Unity

**SENIORS LIVING VILLAGE PROJECT**

266 LONGUEVILLE RD
LANE COVE
NSW

© Copyright Thomson Adsett Pty Ltd.
ABN 76 105 314 654
Trading as ThomsonAdsett.

TA # 16.0161.12


Telephone +61 2 9003 9000
sydney@thomsonadsett.com
Suite 410, 50 Holt Street
Surry Hills
NSW 2010 Australia
thomsonadsett.com

thomson adsett

**MOOD AND MATERIALS BOARD - INTERIORS**

@ A1 21.09.2016

**A351** **rev. A**




0 1 2 3 5 10m

**SENIORS LIVING VILLAGE PROJECT**

266 LOUGUEVILLE RD
LANE COVE
NSW

Australian Unity

© Copyright Thomson Adsett Pty Ltd.
ABN 76 105 314 654
Trading as ThomsonAdsett.

TA # 16.0161.12


Telephone +61 2 9003 9000
sydney@thomsonadsett.com
Suite 410, 50 Holt Street
Surry Hills
NSW 2010 Australia
thomsonadsett.com

thomson adsett

**LEVEL 1 FLOOR PLAN (RL 42.400)**

1 : 200 @ A1 10.08.2016

**A201** **rev. B**




0 1 2 3 5 10m

# SENIORS LIVING VILLAGE PROJECT

266 LOUGUEVILLE RD
LANE COVE
NSW

Australian Unity

© Copyright Thomson Adsett Pty Ltd.
ABN 76 105 314 654
Trading as ThomsonAdsett.

TA # 16.0161.12


Telephone +61 2 9003 9000
sydney@thomsonadsett.com
Suite 410, 50 Holt Street
Surry Hills
NSW 2010 Australia
thomsonadsett.com

thomson adsett

## LEVEL 2 FLOOR PLAN (RL45.600)

1 : 200 @ A1 10.08.2016

**A202** **rev. B**




0 1 2 3 5 10m

## SENIORS LIVING VILLAGE PROJECT

266 LOUGUEVILLE RD
LANE COVE
NSW

Australian Unity

© Copyright Thomson Adsett Pty Ltd.
ABN 76 105 314 654
Trading as ThomsonAdsett.

TA # 16.0161.12


Telephone +61 2 9003 9000
sydney@thomsonadsett.com
Suite 410, 50 Holt Street
Surry Hills
NSW 2010 Australia
thomsonadsett.com

thomson adsett

## LEVEL 3 FLOOR PLAN (RL48.800)

1 : 200 @ A1 10.08.2016

**A203** **rev. B**




0 1 2 3 5 10m

## SENIORS LIVING VILLAGE PROJECT

266 LOUGUEVILLE RD
LANE COVE
NSW

Australian Unity

© Copyright Thomson Adsett Pty Ltd.
ABN 76 105 314 654
Trading as ThomsonAdsett.

TA # 16.0161.12


Telephone +61 2 9003 9000
sydney@thomsonadsett.com
Suite 410, 50 Holt Street
Surry Hills
NSW 2010 Australia
thomsonadsett.com

thomson adsett

## LEVEL 4 FLOOR PLAN (RL52.000)

1 : 200 @ A1 10.08.2016

**A204** **rev. B**




0 1 2 3 5 10m

**SENIORS LIVING VILLAGE PROJECT**

266 LOUGUEVILLE RD
LANE COVE
NSW

Australian Unity

© Copyright Thomson Adsett Pty Ltd.
ABN 76 105 314 654
Trading as ThomsonAdsett.

TA # 16.0161.12


Telephone +61 2 9003 9000
sydney@thomsonadsett.com
Suite 410, 50 Holt Street
Surry Hills
NSW 2010 Australia
thomsonadsett.com

thomson adsett

**LEVEL 5 FLOOR PLAN (RL 55.600)**

1 : 200 @ A1 10.08.2016

**A205** **rev. B**




0 1 2 3 5 10m

## SENIORS LIVING VILLAGE PROJECT

266 LOUGUEVILLE RD
LANE COVE
NSW

Australian Unity

© Copyright Thomson Adsett Pty Ltd.
ABN 76 105 314 654
Trading as ThomsonAdsett.

TA # 16.0161.12


Telephone +61 2 9003 9000
sydney@thomsonadsett.com
Suite 410, 50 Holt Street
Surry Hills
NSW 2010 Australia
thomsonadsett.com

thomson adsett

## LEVEL 6 FLOOR PLAN (RL 59.200)

1 : 200 @ A1 10.08.2016

**A206** **rev. B**




0 1 2 3 5 10m

**SENIORS LIVING VILLAGE PROJECT**

266 LOUGUEVILLE RD
LANE COVE
NSW

Australian Unity

© Copyright Thomson Adsett Pty Ltd.
ABN 76 105 314 654
Trading as ThomsonAdsett.

TA # 16.0161.12

Telephone +61 2 9003 9000
sydney@thomsonadsett.com
Suite 410, 50 Holt Street
Surry Hills
NSW 2010 Australia
thomsonadsett.com

thomson adsett

**LEVEL 7 FLOOR PLAN (RL 62.800)**
NON-CONFORMING

1 : 200 @ A1 10.08.2016

**A207** **rev. B**

# APPENDIX B

## HISTORIC RECORDS AND DOCUMENTATION

# Figure 11 - Land Reclassification Map

## Lane Cove Local Environmental Plan 2009


Land Reclassification (Part Lots) Map - Sheet RPL_004

**Land Reclassification (Part Lots)**

Operational Land

**Cadastre**

Cadastre 22/12/99 © Land & Property Information (LPI)
Addendum 11/07/14 © Lane Cove Council





N

0 200 400 Metres

Scale: 1:10,000 @ A3

Projection: GDA 1994
MGA Zone 56

Map identification number:
4700_COM_RPL_004_010_20140711



# Figure 12 - Land Zoning Map

## Lane Cove Local Environmental Plan 2009


Land Zoning Map - Sheet LZN_004

**Zone**

- B1 Neighbourhood Centre
- B2 Local Centre
- B3 Commercial Core
- B4 Mixed Use
- E2 Environmental Conservation
- E4 Environmental Living
- IN2 Light Industrial
- IN4 Working Waterfront
- R2 Low Density Residential
- R3 Medium Density Residential
- R4 High Density Residential
- RE1 Public Recreation
- SP2 Infrastructure
- UL Unzoned Land

**Cadastre**

Cadastre 22/12/99 © Land & Property Information (LPI)
Addendum 13/10/2017 © Lane Cove Council




N

0 200 400 Metres

Scale: 1:10,000 @ A3

Projection: GDA 1994
MGA Zone 56

Map identification number:
4700_COM_LZN_004_010_20171013

WILLOUGHBY LGA

SP2 - Classified Road


SP2 - Railway

SP2 - Health Services Facility

Sydney Harbour

NORTH SYDNEY LGA


# Figure 13 - Environmental Protection Land Map



# Figure 14 - LEP Planning Zones

## LEP Planning Zones


**266 Longueville Road, Lane Cove, NSW 2066**



# Figure 15 - Elevation Contours

## Elevation Contours (m AHD)

**266 Longueville Road, Lane Cove, NSW 2066**




**Legend**

- Site Centre
- Elevation Contour (m AHD)
- Site Boundary
- Report Buffer
- Property Boundary

Accuracy & Currency: This contour data can be up to 0.4 of the contour interval out in height and must therefore not be used for any design or engineering works, but only as a general guide to topography. Gaps may occur along contour lines due to vertical topography, obscured topography in the source photography such as buildings, dense vegetation or dead ground, or the fact that original buildings have been replaced in the intervening thirty years since the original contour capture.

Scale: 0 100 200 400 Meters

Data Sources: Property Boundaries & Topographic Data: © Land and Property Information (a division of the Department of Finance and Services) 2017


Coordinate System: GDA 1994 MGA Zone 56

Date: 20June 2017

# Figure 16 - Soil Landscapes

## Soil Landscapes

**266 Longueville Road, Lane Cove, NSW 2066**



# Soils

**266 Longueville Road, Lane Cove, NSW 2066**

## Soil Landscapes

What are the onsite Soil Landscapes?

| Soil Code | Name | Group | Process | Map Sheet | Scale |
|---|---|---|---|---|---|
| ALdc | DEEP CREEK | | ALLUVIAL | Sydney | 1:100,000 |
| RElh | LUCAS HEIGHTS | | RESIDUAL | Sydney | 1:100,000 |

What are the Soil Landscapes within the dataset buffer?

| Soil Code | Name | Group | Process | Map Sheet | Scale |
|---|---|---|---|---|---|
| ALdc | DEEP CREEK | | ALLUVIAL | Sydney | 1:100,000 |
| COha | HAWKESBURY | | COLLUVIAL | Sydney | 1:100,000 |
| COwp | WEST PENNANT HILLS | | COLLUVIAL | Sydney | 1:100,000 |
| DTxx | DISTURBED TERRAIN | | DISTURBED TERRAIN | Sydney | 1:100,000 |
| ERgn | GLENORIE | | EROSIONAL | Sydney | 1:100,000 |
| ERgy | GYMEA | | EROSIONAL | Sydney | 1:100,000 |
| ERla | LAMBERT | | EROSIONAL | Sydney | 1:100,000 |
| RElh | LUCAS HEIGHTS | | RESIDUAL | Sydney | 1:100,000 |
| WATER | WATER | | WATER | Sydney | 1:100,000 |

Soils Landscapes Data Source : NSW Office of Environment and Heritage
Creative Commons 3.0 © Commonwealth of Australia http://creativecommons.org/licenses/by/3.0/au/deed.en

# Figure 17 - Dial Before You Dig Plans

DIAL BEFORE YOU DIG www.1100.com.au

Job No 14698606


Phone: 1100
**www.1100.com.au**

## Caller Details

| | | | | | |
|---|---|---|---|---|---|
| **Contact:** | Mr Jon Lawson | **Caller Id:** | 956162 | **Phone:** | 0393713400 |
| **Company:** | LRM Global | **Mobile:** | 0411147722 | **Fax:** | 0393713499 |
| **Address:** | 65 Stubbs Street<br>Kensington VIC 3031 | **Email:** | jon.lawson@lrmglobal.com.au | | |

## Dig Site and Enquiry Details

**WARNING:** The map below only displays the location of the proposed dig site and does not display any asset owners' pipe or cables. The area highlighted has been used only to identify the participating asset owners, who will send information to you directly.




**User Reference:** Lane Cove
**Working on Behalf of:** Private

| Enquiry Date: | Start Date: | End Date: |
|---|---|---|
| 06/08/2018 | 31/08/2018 | 31/08/2018 |

**Address:**
266 Longueville Road
Lane Cove NSW 2066

**Job Purpose:** Design
**Onsite Activity:** Planning & Design
**Location of Workplace:** Private Property
**Location in Road:** Not Supplied

- Check the location of the dig site is correct. If not submit a new enquiry.
- If the scope of works change, or plan validity dates expire, resubmit your enquiry.
- Do NOT dig without plans. Safe excavation is your responsibility. If you do not understand the plans or how to proceed safely, please contact the relevant asset owners.

**Notes/Description of Works:**
Environmental Bores

## Your Responsibilities and Duty of Care

- If plans are not received within 2 working days, contact the asset owners directly & quote their Sequence No.
- ALWAYS perform an onsite inspection for the presence of assets. Should you require an onsite location, contact the asset owners directly. Please remember, plans do not detail the exact location of assets.
- Pothole to establish the exact location of all underground assets using a hand shovel, before using heavy machinery.
- Ensure you adhere to any State legislative requirements regarding Duty of Care and safe digging requirements.
- If you damage an underground asset you MUST advise the asset owner immediately.
- By using this service, you agree to Privacy Policy and the terms and disclaimers set out at **www.1100.com.au**
- **For more information on safe excavation practices, visit www.1100.com.au**

## Asset Owner Details

The assets owners listed below have been requested to contact you with information about their asset locations within 2 working days.
Additional time should be allowed for information issued by post. It is **your responsibility** to identify the presence of any underground assets in and around your proposed dig site. Please be aware, that not all asset owners are registered with the Dial Before You Dig service, so it is **your responsibility** to identify and contact any asset owners not listed here directly.
** Asset owners highlighted by asterisks ** require that you visit their offices to collect plans.
# Asset owners highlighted with a hash require that you call them to discuss your enquiry or to obtain plans.

| Seq. No. | Authority Name | Phone | Status |
|---|---|---|---|
| 74173084 | Ausgrid | 0249510899 | NOTIFIED |
| 74173086 | Jemena Gas North | 1300880906 | NOTIFIED |
| 74173088 | NBN Co, NswAct | 1800626762 | NOTIFIED |
| 74173083 | PIPE Networks, Nsw | 1800201100 | NOTIFIED |
| 74173087 | Sydney Water | 132092 | NOTIFIED |
| 74173085 | Telstra NSW, Central | 1800653935 | NOTIFIED |


END OF UTILITIES LIST




# Indicative Plans


| | |
|---|---|
| **Issue Date:** | 06/08/2018 |
| **Location:** | 266 Longueville Road,Lane Cove,NSW-2066 |

DIAL BEFORE YOU DIG www.1100.com.au





© 2015 nbn co limited | ABN 86 136 533 741




# GLADESVILLE 6C

SCALE 1:2000

50 0 50 100 150 200

THIS MAP UPDATED ON 04/07/2018
THIS PLAN IS DIAGRAMATIC ONLY. DISTANCES SCALED FROM THIS PLAN MAY NOT BE ACCURATE.

DATE ALTERED:..... BY:.....

| | | |
|---|---|---|
| G5B | G6A | G6B |
| G5D | G6C | G6D |
| G8B | G9A | G9B |

ADJOINING MAPS

| | |
|---|---|
| 331 / 432 / 334 | LANE COVE |
| NETWORK AREA | MUNICIPALITY AREA |

# Jemena

## KEY

MAX ALLOWABLE OPERATING PRESSURE

| | | |
|---|---|---|
| T | TRUNK PIPELINE | 7000 kPa |
| P | PRIMARY MAIN | 3500 kPa |
| S | SECONDARY MAIN | 1050 kPa |
| 400 | NETWORK MAIN | 400 kPa |
| | NETWORK MAIN | 300 kPa |
| | NETWORK MAIN | 210 kPa |
| 100 | NETWORK MAIN | 100 kPa |
| 30 | NETWORK MAIN | 30 kPa |
| | NETWORK MAIN | 7 kPa |
| | NETWORK MAIN | 2 kPa |
| | NETWORK MAIN WITH MAIN STUBS | |
| | PROPOSED MAINS | |
| PR 11-2 3 | STEEL MAIN PROJECT NUMBER | |
| P | PRESSURE MONITORING STATION | |
| | VALVE | |
| | SYSTEM PRESSURE REGULATOR | |
| S | SIPHON | |
| 123 | NETWORK NODE | |
| 123S | NETWORK VALVE NODE | |
| (298) | VALVE NUMBER | |
| 6NB | 6 INCH CAST IRON MAIN | |
| 150MM | 150MM STEEL MAIN | |
| 110MM PE/NY | 110MM POLYETHYLENE/NYLON MAIN | |
| (6)NB 50MM NY | 50MM NYLON INSERTED INTO 6NB MAIN CAST IRON MAIN | |
| 1.2MBL | DISTANCE IN METRES OF MAIN FROM BOUNDARY LINE | |
| 1957 | YEAR LAID | |
| | MUNICIPALITY BOUNDARY | |
| | NETWORK BOUNDARY | |
| 123 | HOUSE NUMBER | |

GLADESVILLE 6C

# Guide to reading Sydney Water DBYD Plans



February 2015

# Asset Information

## Legend

### Sewer

- Sewer Main (with flow arrow & size type text) — 225 PVC
- Disused Main
- Rising Main
- Maintenance Hole (with upstream depth to invert) — 1.7
- Sub-surface chamber
- Maintenance Hole with Overflow chamber
- Ventshalft EDUCT — VSE
- Ventshaft INDUCT — VS
- Property Connection Point (with chainage to downstream MH) — 10.5
- Concrete Encased Section — Concrete Encased
- Terminal Maintenance Shaft — TMS
- Maintenance Shaft — MS
- Rodding Point — RP
- Lamphole
- Vertical — VERT
- Pumping Station — SP0882
- Sewer Rehabilitation

### Pressure Sewer

- Pressure Sewer Main
- Pump Unit (Alarm, Electrical Cable, Pump Unit) — A
- Property Valve Boundary Assembly
- Stop Valve
- Reducer / Taper
- Flushing Point — FP

### Vacuum Sewer


- Pressure Sewer Main
- Division Valve
- Vacuum Chamber
- Clean Out Point

### Stormwater

- Stormwater Pipe
- Stormwater Channel
- Stormwater Gully
- Stormwater Maintenance Hole

### Property Details

- Boundary Line
- Easement Line
- House Number
- Lot Number
- Proposed Land




- Sydney Water Heritage Site (please call **132 092** and ask for the **Heritage Unit**)

### Water

- WaterMain - Potable (with size type text) — 200 PVC
- Disconnected Main - Potable
- Proposed Main - Potable
- Water Main - Recycled
- Special Supply Conditions - Potable
- Special Supply Conditions - Recycled
- Restrained Joints - Potable
- Restrained Joints - Recycled
- Hydrant
- Maintenance Hole
- Stop Valve
- Stop Vale with By-pass
- Stop Valve with Tapers
- Closed Stop Valve
- Air Valve
- Valve
- Scour
- Reducer / Taper
- Vertical Bends
- Reservoir
- Recycled Water is shown as per Potable above. Colour as indicated

### Private Mains

- Potable Water Main
- Recycled Water Main
- Sewer Main
- Symbols for Private Mains shown grey

# Asset Information

## Pipe Types


| | | | |
|---|---|---|---|
| **ABS** | Acrylonitrile Butadiene Styrene | **AC** | Asbestos Cement |
| **BRICK** | Brick | **CI** | Cast Iron |
| **CICL** | Cast Iron Cement Lined | **CONC** | Concrete |
| **COPPER** | Copper | **DI** | Ductile Iron |
| **DICL** | Ductile Iron Cement (mortar) Lined | **DIPL** | Ductile Iron Polymeric Lined |
| **EW** | Earthenware | **FIBG** | Fibreglass |
| **FL BAR** | Forged Locking Bar | **GI** | Galvanised Iron |
| **GRP** | Glass Reinforced Plastics | **HDPE** | High Density Polyethylene |
| **MS** | Mild Steel | **MSCL** | Mild Steel Cement Lined |
| **PE** | Polyethylene | **PC** | Polymer Concrete |
| **PP** | Polypropylene | **PVC** | Polyvinylchloride |
| **PVC - M** | Polyvinylchloride, Modified | **PVC - O** | Polyvinylchloride, Oriented |
| **PVC - U** | Polyvinylchloride, Unplasticised | **RC** | Reinforced Concrete |
| **RC-PL** | Reinforced Concrete Plastics Lined | **S** | Steel |
| **SCL** | Steel Cement (mortar) Lined | **SCL IBL** | Steel Cement Lined Internal Bitumen Lined |
| **SGW** | Salt Glazed Ware | **SPL** | Steel Polymeric Lined |
| **SS** | Stainless Steel | **STONE** | Stone |
| **VC** | Vitrified Clay | **WI** | Wrought Iron |
| **WS** | Woodstave | | |

## Further Information

Please consult the Dial Before You Dig enquiries page on the Sydney Water website

For general enquiries please call the Customer Contact Centre on **132 092**

**In an emergency, or to notify Sydney Water of damage or threats to its structures, call 13 20 90 (24 hours, 7 days)**




DBYD Address:
266 Longueville Road
Lane Cove NSW 2066

DBYD Job No: 14698606

DBYD Sequence No: 74173087

Copyright Reserved Sydney Water 2018

No warranty is given that the information shown is complete or accurate.

SYDNEY WATER CORPORATION

Scale: 1:1000

Date of Production: 06/08/2018

Plan 1 of 1

N

0m 5m 10m 15m 20m

# Reading Ausgrid Plans
COMN0119

## 1 Property Lines

**"property line" (PL),** sometimes referred to as **"building line" (BL),** is the standard dimensioning reference point on all Ausgrid plans and represents property boundaries.

Typically the PL is the boundary between private property and local council's footpath area or nature reserve. Most residential fences and office blocks are erected along the PL.

**"kerb line" (KL)** is less frequently referred to on Ausgrid plans, and where used will be identified clearly as KL.

Numbers listed within property boundaries should correspond to recognised "street numbers" (refer to figure 1).




**Figure 1**

## 2 Datum References

**"datum references"** identify distances (in metres) from significant features (such as corners of property boundaries) to reference points such as Ausgrid assets (eg: "conduits", "cables", "joints") (refer to figure 2).





**Figure 2**

## 3 Cross Sections

A "cross sections" displayed on Ausgrid plans detail information relating to the relative position (ie: distance from the **"property line",** and the depth of **"cover"**) of Ausgrid assets.

**"Cover"** is a term used to refer to the depth of cables underground.

A "cross section" leader line will be drawn indicating the location of the displayed **"cable"** or **"conduit"** information on Ausgrid plans.

The distance from **"property line"** (in metres) and depth of **"cover"** (in metres) references are displayed as; ie: 0.6 metres from PL and 0.5 metres underground.

Where distance and cover are not recorded, they will be clearly marked as **"NR".**

NOTE: Distance and cover where indicated may be different to the actual position of the cables (eg: fill may have been placed at site that has changed the ground level).

"PL" distance shown in cross sections is an indicative measure to the centre of the trench allocation from the adjacent property line.

On some plans the "cross sections" may also be shown with a specific number (eg: HR1). This number will match with a cross section detail found in the border of the plot or on a separate plot page (refer to figures 3 and 4).





**Figure 3**





**Figure 4**

## 4 Cable Joints and Joint Reports

**"cable joints"** (numbered individually) and **"joint reports"** (attached to Ausgrid plans) can provide information relating to the relative position of Ausgrid assets, distance from the "property line" (in metres), and the depth of "cover" (in metres) (refer to figures 5 and 6).





**Figure 5**





**Figure 6**

## 5 Cross Section Detail Boxes

**"cross section"** detail boxes on the sides of an Ausgrid plan are used when there is insufficient room to display **"cable"** and/or "conduit" information on the Ausgrid plan.

Ausgrid plans (refer to figure 7) are bordered by numeric identifiers along the top and bottom borders and alpha identifiers along the side borders.





**Figure 7**

**"Cross section"** leader line and annotation is drawn on the Ausgrid plan for a reference to **"cable"** and/or **"conduit"** information in the **"cross section"** detail boxes.

## 6 Pits

Underground **"pits"** are numbered on Ausgrid plans, positioned relative to the **"property line" (PL)**, and can be found on either the footpath (nature strip) or the road (refer figure 8).





**Figure 8**

## 7 Proposal Areas

There are areas where underground work may have been issued for construction by Ausgrid, but details are not yet completely displayed on Ausgrid plans. In such cases a shaded **"proposal area"** is displayed on the Ausgrid plan, indicating underground work may have commenced in the vicinity but is not yet complete.

In some instances cables and other assets within the shaded **"proposal area"** will be shown in a bright magenta colour, indicating that the proposed new work displayed within the shaded area is based on initial planning documentation (refer to figure 9).





**Figure 9**

In other instances the shaded **"proposal area"** itself may be shown as a blue colour, indicating that the new work displayed within the shaded area on the Ausgrid plan is yet to include details regarding final depths and dimensioning (refer to figure 10).





**Figure 10**

NOTE: In cases where these shaded **"proposal areas"** are displayed on Ausgrid plans.

"Ausgrid's design plans showing the proposed position of its underground cables, overhead lines and structures have been prepared solely for Ausgrid's own planning use. They show the proposed position of such underground cables, overhead lines and structures as proposed at the time of planning and have not necessarily been corrected to take into account any changes to road widths, road levels, fences and buildings subsequent to proposed installation.

Actual installations may vary from proposed installations as it may be necessary to take account of unforeseen above ground or subterranean constructions. Therefore, Ausgrid does not hold out that the design plans show more than the proposed presence or absence of its underground cables, overhead lines and structures in the street and will accept no liability for inaccuracies in the information shown on such design plans from any cause whatsoever."

Any further information regarding information displayed for "proposal areas" can be obtained by contacting the Ausgrid DBYD office at the number indicated on the response to your DBYD enquiry for further information.

## 8 Ausgrid (ISG) Map Grid

The pale grey line indicates the 1:1000 Ausgrid (ISG) map grid border. The pale grey annotation located in the corners of the Ausgrid plan window, indicates the 1:1000 Ausgrid (ISG) map grid reference.

The 1:1000 Ausgrid (ISG) map grid border and reference on Ausgrid plans should be used when reading the **"joint report"** (see part 4 of this document for more detail) to accurately locate underground cables.

The buffer area shown on the plan should relate to the area requested on the original Dial Before you Dig request.

The grid index box can be used for reference where necessary (located in the bottom right corner of the Ausgrid plans), and will also indicate the buffer area shown on the plan.

## 9 Ausgrid "Distribution" and "Transmission" Plans

The Ausgrid plans supplied may identify both **"distribution"** and **"transmission"** voltage assets for the area defined in the DBYD request (refer to figure 11).





**Figure 11**

In the Sydney region, the Ausgrid plans are separately labelled as "Distribution **– nnnnnnn"** and **"Transmission – nnnnnnn"**, where **"nnnnnnn"** refers to the DBYD sequence number quoted.

In the Hunter region, the Ausgrid plans show combined **"distribution"** and **"transmission"** voltage assets, and are clearly labelled as **"Distr + Trans –** nnnn**nnn"** where **"nnnnnnn"** refers to the DBYD sequence number.

In the Hunter region, some DBYD requests are covered by PENGUIN grid references. In such cases, the Ausgrid Plans show the grid quoted with a cross-reference to a corresponding Ausgrid (ISG) map grid (eg: PENGUIN 136B3 – DP711, where DP711 is the Ausgrid (ISG) grid) to optimise the legibility of plans due to PENGUIN grid scale.

Some Hunter plans may have transmission cables in the area, when these cables are present there will be a warning printed at the top of the plan supplied:

WARNING: If there is work in the vicinity of transmission cables, Ausgrid must be contacted at least two weeks before the work is due to commence.

## 10 "Shifting Land Base" on Ausgrid Distribution and Transmission Plans

In some instances, the plans supplied may indicate road or property outlines that appear to have shifted in relation to the Ausgrid assets displayed (refer to figure 12).





Figure 12

In such instances, always refer to the **"property line"** (in metres) and depth of **"cover"** (in metres) references displayed on the nearest relevant **"cross sections"** to obtain Ausgrid asset location information (see Reading Ausgrid Plans, clause 3, Cross Sections for more detail).

## 11 "Underground Earthing Infrastructure"

In some instances, the plans supplied may also indicate the presence of underground earthing infrastructure associated with underground and/or overhead Ausgrid assets.

The **"Earth Point"** symbol (refer to figure 13) will be shown on plans to minimize risk of disturbance or damage to any Ausgrid underground earthing infrastructure in the vicinity.



Figure 13

## 12 Aluminium Single Core Cables – Specific Excavation Hazard

Certain cables specifically illustrated in figures 14 and 15 below are susceptible to deterioration that may pose a risk of electric shock when working near them, particularly in damp ground.

For all work on or near Ausgrid's network (where workers have been trained in Ausgrid's "Work Near Underground Power Lines" course) the work practices outlined in NS199 "Safe Electrical Working on Low Voltage Assets" Section 7 for work near low voltage aluminium single core cable must be adhered to. Further information is also available to Accredited Service Providers in Safety Alert SA06_15 issued May 2015.

All other persons must contact Ausgrid before excavating near these cables to arrange for appropriate precautions to be applied.





Figure 14

The **"star"** symbols over the cable indicate that it is susceptible to this deterioration.

Cables that are in duct lines have this symbology covered so an at-risk cable is indicated only within a cross section by a **"#"** appended to its cable code as illustrated below.







Figure 15

GL632 - AR1




Ref: A4

GL632 - AS1




Ref: B3




JOINT DETAIL REPORT

| No.... | Ch Fit ..... | FtCvr ..... | Joint Location ..... |
|---|---|---|---|
| Map GL632 | | | |
| 7 | 1413.29 | 0.71/0.71 | 25.6 S OF RICHARDSON ST SPL |

**WARNING**

Ausgrid's plans show the position of assets at the time of installation and may not account for subsequent changes to road alignments, fences or buildings. The plans show no more than the presence or absence of Ausgrid assets in the area.

Persons working near electricity networks must exercise care and will be held responsible for any damage caused.

You must excavate by hand or use vacuum excavation to establish the location of Ausgrid underground cables and associated assets.

Underground: Working near a cable may result in electric shock even if no contact is made. Any work in the vicinity of any cable should only be performed using safe work methods developed in accordance with the recommendations included in WorkCover Code of Practice for Excavation and WorkCover Guide for Work Near Underground Assets,

as well as recommendations of Ausgrid's Network Standard NS156.

Overhead: Do not excavate near poles or towers until the stability of the foundation has been assessed by Ausgrid. Cables or earth conductors may be present in substations, poles or towers.

Workers must maintain safe approach distances and follow applicable WorkCover Codes of Practice.

NOTE: 1. You must keep Ausgrid plans on site during excavation works. If the people actually performing the excavation works do not know how to read and interpret Ausgrid's plans, then the work must be directed by a person who knows how to read and interpret the plans. 2. This information includes data from the NSW Digital Cadastral Database by Land and Property Information (c) 2016, used under Creative Commons licence version 4.0

| | | |
|---|---|---|
| GL63122 | GL63211 | GL63212 |
| GL63124 | GL63213 | GL63214 |
| GL63142 | GL63231 | GL63232 |

ISG GRID

| | | |
|---|---|---|
| 21924 | 21934 | 21944 |
| 21925 | 21935 | 21945 |
| 21926 | 21936 | 21946 |

GRID

**GMLA0**

**Distribution - 74173084**

INFORMATION ON THIS PLAN ONLY VALID FOR 30 DAYS FROM ISSUE DATE

**Page 1 of 1**

**6 Aug 2018**

N

**1:161**

0 — 10 metres

Ausgrid


A0 MOCS_std_plot

N_74173084_GMLA0_V1.mapd

# Figure 18 - Geology 1:100,000 Plan

## Geology 1:100,000

**266 Longueville Road, Lane Cove, NSW 2066**



# Geology

**266 Longueville Road, Lane Cove, NSW 2066**

## Geological Units

What are the Geological Units onsite?

| Symbol | Description | Unit Name | Group | Sub Group | Age | Dom Lith | Map Sheet | Dataset |
|---|---|---|---|---|---|---|---|---|
| Rh | Medium to coarse grained quartz sandstone, very minor shale and laminate lenses | | | | Triassic | | Sydney | 1:100,000 |

What are the Geological Units within the dataset buffer?

| Symbol | Description | Unit Name | Group | Sub Group | Age | Dom Lith | Map Sheet | Dataset |
|---|---|---|---|---|---|---|---|---|
| Qha | Silty to peaty quartz sand, silt, and clay. Ferruginous and humic cementation in places. Common shell layers | | | | Quaternary | | Sydney | 1:100,000 |
| Rh | Medium to coarse grained quartz sandstone, very minor shale and laminate lenses | | | | Triassic | | Sydney | 1:100,000 |
| Rwa | Black to dark grey shale and laminate | Ashfield Shale | Wianamatta Group | | Triassic | | Sydney | 1:100,000 |
| water | | | | | | | Sydney | 1:100,000 |

## Geological Structures

What are the Geological Structures onsite?

| Feature | Name | Description | Map Sheet | Dataset |
|---|---|---|---|---|
| No features | | | | 1:100,000 |

What are the Geological Structures within the dataset buffer?

| Feature | Name | Description | Map Sheet | Dataset |
|---|---|---|---|---|
| No features | | | | 1:100,000 |

Geological Data Source : NSW Department of Industry, Resources & Energy

© State of New South Wales through the NSW Department of Industry, Resources & Energy

# Figure 19 - Historical Maps (1917, 1949, 1975)

## Historical Map 1975

**266 Longueville Road, Lane Cove, NSW 2066**



# Historical Maps ca.1949

**266 Longueville Road, Lane Cove, NSW 2066**



# Historical Maps ca.1917

**266 Longueville Road, Lane Cove, NSW 2066**




Scale: 0 250 500 1,000 Meters

Data Sources: Australia 1:63360 Sheet 423
Sydney, New South Wales
Prepared by Commonwealth Section Imperial General Staff


Coordinate System:
GDA 1994 MGA Zone 56

Date: 20 June 2017

# Figure 20 - Contaminated Land & Waste Management Facilities

## Contaminated Land & Waste Management Facilities


**266 Longueville Road, Lane Cove, NSW 2066**



# Figure 21 - Current EPA Licensed Activites

## Current EPA Licensed Activities


**266 Longueville Road, Lane Cove, NSW 2066**



# Figure 22 - Delicensed & Former Licensed EPA Activities

## Delicensed & Former Licensed EPA Activities


**266 Longueville Road, Lane Cove, NSW 2066**



# Figure 23 - Groundwater Borehole Proximity Plan

## Groundwater Boreholes


**266 Longueville Road, Lane Cove, NSW 2066**



# Figure 24 - Historical Business Directory Records

## 1991 Historical Business Directory Records

**266 Longueville Road, Lane Cove, NSW 2066**



# Historical Business Directories

**266 Longueville Road, Lane Cove, NSW 2066**

## 1991 Business to Business Directory Records
## Premise or Road Intersection Matches

Records from the 1991 UBD Business to Business Directory, mapped to a premise or road intersection, within the dataset buffer:

| Business Activity | Organisation | Address | Ref No. | Location Confidence | Distance to Feature Point | Direction |
|---|---|---|---|---|---|---|
| Motor Garages & Service Stations | Caltex Northwood Service Station | 10 Northwood Rd., Northwood 2066 | 53640 | Premise Match | 73m | South |
| Swimming Pool Mfrs &/or Construction Contractors | Lane Cove Pool Shop | 16 Northwood Rd Northwood 2066 | 63786 | Premise Match | 105m | South |
| Property Management | Mackeddie Real Estate Pty. Ltd. | 3 Northwood Rd Longeville 2066 | 59647 | Premise Match | 136m | South |
| Real Estate Agents | Mackeddie Real Estate Pty. Ltd. | 3 Northwood Rd., Longueville 2066 | 60445 | Premise Match | 136m | South |

Business Directory Content Derived from Universal Business Directories (UBD) - Licensed from Hardie Grant

## 1991 Business to Business Directory Records
## Road or Area Matches


Records from the 1991 UBD Business to Business Directory, mapped to a road or an area, within the dataset buffer. Records are mapped to the road when a building number is not supplied, cannot be found, or the road has been renumbered since the directory was published:

| Business Activity | Organisation | Address | Ref No. | Location Confidence | Distance to Road Corridor |
|---|---|---|---|---|---|
| N/A | No records in buffer | | | | |

Business Directory Content Derived from Universal Business Directories (UBD) - Licensed from Hardie Grant

# 1986 Historical Business Directory Records

**266 Longueville Road, Lane Cove, NSW 2066**



# Historical Business Directories

**266 Longueville Road, Lane Cove, NSW 2066**

## 1986 Business to Business Directory Records
## Premise or Road Intersection Matches

Records from the 1986 UBD Business to Business Directory, mapped to a premise or road intersection, within the dataset buffer:

| Business Activity | Premise | Ref No. | Location Confidence | Distance to Feature Point | Direction |
|---|---|---|---|---|---|
| MOTOR GARAGES & SERVICE STATIONS. | Calico Northwood, 10 Northwood Rd., Northwood. | 64372 | Premise Match | 73m | South |
| BRICKLAYERS. | City Bricklaying Corp. Pty. Ltd., 49 Richardson St., Lane Cove. | 7698 | Premise Match | 80m | North |
| NEWSAGENTS. | Milowaters Newsagency, 12 Northwood Rd., Northwood. | 69522 | Premise Match | 89m | South |
| BUTCHERS-RETAIL. | Longueville Butchery, 14 Northwood Rd., Longueville. | 10205 | Premise Match | 97m | South |
| ENGINEERS – CONSULTING. | Engineering Partners, 16 Northwood Rd., Northwood. | 28842 | Premise Match | 105m | South |
| SWIMMING POOL &/OR EQUIPMENT MFRS. &/OR DISTS. | Lane Cove Pool Shop, 16 Northwood Rd., Northwood. | 90133 | Premise Match | 105m | South |
| TAKE-AWAY FOODS. | Shop One, I6A Northwood Rd., Northwood. | 91741 | Premise Match | 105m | South |
| CHEMISTS-PHARMACEUTICAL. | Foleys Pharmacy, 18B Northwood Rd., Northwood. | 14227 | Premise Match | 119m | South |
| VETERINARY SURGEONS. | Hopwood, Gregory, P., 18 Northwood Rd., Northwood. | 97350 | Premise Match | 119m | South |
| WINE &/OR SPIRIT MERCHANTS RETAIL. | Northwood Cellars, 1 Northwood Rd., Northwood. | 99486 | Premise Match | 127m | South |
| PROPERTY MANAGEMENT. | Mackeddie Real Estate Pty. Ltd., 3 Northwood Rd., Longueville. | 77766 | Premise Match | 136m | South |
| REAL ESTATE AGENTS. | Mackeddle Real Estate Pty. Ltd., 3 Northwood Rd„ Longueville. | 79837 | Premise Match | 136m | South |

Business Directory Content Derived from Universal Business Directories (UBD) - Licensed from Hardie Grant

## 1986 Business to Business Directory Records
## Road or Area Matches


Records from the 1986 UBD Business to Business Directory, mapped to a road or an area, within the dataset buffer. Records are mapped to the road when a building number is not supplied, cannot be found, or the road has been renumbered since the directory was published:

| Business Activity | Premise | Ref No. | Location Confidence | Distance to Road Corridor |
|---|---|---|---|---|
| TAKE-AWAY FOODS. | King of the Roasts, 84 Longueville Rd., Lane Cove. | 91147 | Road Match | 0m |
| CLUBS &/OR SPORTING BODIES. | Lane Cove Womens Bowling & Recreation Club, Longueville Rd., Lane Cove. | 18941 | Road Match | 0m |
| MEDICAL PRACTITIONERS. | Norris, J. C., 2 Kenneth St., Northwood. | 56741 | Road Match | 117m |

Business Directory Content Derived from Universal Business Directories (UBD) - Licensed from Hardie Grant

# 1982 Historical Business Directory Records

**266 Longueville Road, Lane Cove, NSW 2066**



# Historical Business Directories

**266 Longueville Road, Lane Cove, NSW 2066**

## 1982 Business Directory Records
## Premise or Road Intersection Matches

Records from the 1982 UBD Business Directory, mapped to a premise or road intersection, within the dataset buffer:

| Business Activity | Premise | Ref No. | Location Confidence | Distance to Feature Point | Direction |
|---|---|---|---|---|---|
| BRICKLAYERS. (B6260) | City Bricklaying Corp. Pty. Ltd., 49 Richardson St., Lane Cove.2066. | 8548 | Premise Match | 80m | North |
| NEWSAGENTS. (N0800) | Milowaters Newsagency, 12 Northwood Rd., Northwood. 2066. | 60681 | Premise Match | 89m | South |
| BUTCHERS - RETAIL. (B8040) | Longueville Butchery, 14 Northwood Rd., Longueville. 2066. | 11143 | Premise Match | 97m | South |
| ENGINEERS - CONSULTING. (E6600) | Engineering Partners, 16 Northwood Rd., Northwood. 2066. | 26991 | Premise Match | 105m | South |
| SWIMMING POOLS & EQUIPMENT.(S8370) | Lane Cove Pool Shop, 16 Northwood Rd., Northwood. 2066. | 77875 | Premise Match | 105m | South |
| CHEMISTS - PHARMACEUTICAL. (C4110) | Foleys Pharmacy, 18B Northwood Rd., Northwood. 2066. | 15027 | Premise Match | 119m | South |
| WINE &/OR SPIRIT MERCHANTS -. RETAIL. (W5960) | Northwood Cellars, 1 Northwood Rd., Northwood. 2066. | 84893 | Premise Match | 127m | South |
| REAL ESTATE AGENTS. (R2555) | Mackeddie Real Estate Pty. Ltd., 3 Northwood Rd Longueville.2066. | 69360 | Premise Match | 136m | South |
| PROPERTY MANAGEMENT. (P9060) | Mackeddie Real Estate Pty. Ltd., 3 Northwood Rd., Longueville.2066. | 67448 | Premise Match | 136m | South |

Business Directory Content Derived from Universal Business Directories (UBD) - Licensed from Hardie Grant

## 1982 Business Directory Records
## Road or Area Matches


Records from the 1982 UBD Business Directory, mapped to a road or an area, within the dataset buffer. Records are mapped to the road when a building number is not supplied, cannot be found, or the road has been renumbered since the directory was published:

| Business Activity | Premise | Ref No. | Location Confidence | Distance to Road Corridor |
|---|---|---|---|---|
| CLUBS &/OR SPORTING BODIES.(C5730) | Lane Cove Womens Bowling & Recreation Club, Longueville Rd., LaneCove. 2066. | 17270 | Road Match | 0m |
| MEDICAL PRACTITIONERS. (M2020) | Norris, J. C., 2 Kenneth St., Northwood. 2066. | 49621 | Road Match | 117m |
| MEDICAL PRACTITIONERS. (M2020) | Skinner, K., 2 Kenneth St., Northwood. 2066. | 50336 | Road Match | 117m |

Business Directory Content Derived from Universal Business Directories (UBD) - Licensed from Hardie Grant

# 1978 Historical Business Directory Records

**266 Longueville Road, Lane Cove, NSW 2066**



# Historical Business Directories

**266 Longueville Road, Lane Cove, NSW 2066**

## 1978 Business Directory Records
## Premise or Road Intersection Matches

Records from the 1978 UBD Business Directory, mapped to a premise or road intersection, within the dataset buffer:

| Business Activity | Premise | Ref No. | Location Confidence | Distance to Feature Point | Direction |
|---|---|---|---|---|---|
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. | Caltex Service Station, 10 Northwood Rd., Northwood. | 49727 | Premise Match | 73m | South |
| BUTCHERS-RETAIL. | Hummerston, P.N. & C.W., 14 Northwood Rd., Longueville. | 9343 | Premise Match | 97m | South |
| BUTCHERS-RETAIL. | Longueville Butchery, 14 Northwood Rd., Longueville. | 9478 | Premise Match | 97m | South |
| FRUITERERS &/OR GREENGROCERS. | Bettini, A.O., 18C Northwood Rd., Northwood. | 30302 | Premise Match | 119m | South |
| CHEMISTS-PHARMACEUTICAL. | Foleys Pharmacy, 18B Northwood Rd., Northwood. | 13212 | Premise Match | 119m | South |
| WINE &/OR SPIRIT MERCHANTS- RETAIL. | Northwood Cellars, 1 Northwood Rd., Northwood. | 74804 | Premise Match | 127m | South |
| PROPERTY MANAGEMENT. | Mackeddie Real Estate Pty. Ltd., 3 Northwood Rd., Longueville. | 60258 | Premise Match | 136m | South |
| REAL ESTATE AGENTS &/OR VALUERS. | Mackeddie Real Estate Pty. Ltd., 3 Northwood Rd., Longueville. | 61954 | Premise Match | 136m | South |

Business Directory Content Derived from Universal Business Directories (UBD) - Licensed from Hardie Grant

## 1978 Business Directory Records
## Road or Area Matches


Records from the 1978 UBD Business Directory, mapped to a road or an area, within the dataset buffer. Records are mapped to the road when a building number is not supplied, cannot be found, or the road has been renumbered since the directory was published:

| Business Activity | Premise | Ref No. | Location Confidence | Distance to Road Corridor |
|---|---|---|---|---|
| CLUBS &,/OR SPORTING BODIES. | lane Cove Womens Bowling & Recreation Chib. Longueville Rd., Lane Cove. | 15614 | Road Match | 0m |
| SCHOOLS-KINDERGARTEN, DAY NURSERY. | Kindergarten Union of N.S.W, (Inc.), Richardson Rd., Lane Cove. | 65011 | Road Match | 96m |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. | BP Northwood Service Station. 6 Kenneth St.. Northwood. | 49586 | Road Match | 117m |

Business Directory Content Derived from Universal Business Directories (UBD) - Licensed from Hardie Grant

# 1975 Historical Business Directory Records

**266 Longueville Road, Lane Cove, NSW 2066**



# Historical Business Directories

**266 Longueville Road, Lane Cove, NSW 2066**

## 1975 Business Directory Records
## Premise or Road Intersection Matches

Records from the 1975 UBD Business Directory, mapped to a premise or road intersection, within the dataset buffer:

| Business Activity | Premise | Ref No. | Location Confidence | Distance to Feature Point | Direction |
|---|---|---|---|---|---|
| MOTOR GARAGES &/OR ENGINEERS. | Pascate, L. & M., 10 Northwood Rd, Northwood. | 59374 | Premise Match | 73m | South |
| STATIONERS., RETAIL | Northwood Newsagency, 12 Northwood Rd., Northwood. | 80107 | Premise Match | 89m | South |
| NEWSAGENTS-GENERAL | Northwood Newsagency. 12 Northwood Rd., Northwood. | 63749 | Premise Match | 89m | South |
| BUTCHERS-RETAIL | Longueville Butchery, 14 Northwood Rd., Northwood. | 10724 | Premise Match | 97m | South |
| CHEMISTS-PHARMACEUTICAL | Foley's Pharmacy, 16B Northwood Rd., Northwood. | 15274 | Premise Match | 106m | South |
| DRY CLEANERS, PRESSERS&/OR DYERS. | Lawrence Dry Cleaners, 18A Northwood Rd., Northwood | 24129 | Premise Match | 121m | South |
| FRUITERERS &/OR GREENGROCERS. | Northwood Fruit & Vegetable Store, The, 18C Northwood Rd Northwood. | 35629 | Premise Match | 121m | South |
| REAL ESTATE AGENTS &/OR VALUERS. | MacKeddie Real Estate, 3 Northwood Pd., Longueville. | 72642 | Premise Match | 136m | South |
| PROPERTY MANAGEMENT. | MacKeddie Real Estate, 3 Northwood Rd., Longueville. | 70712 | Premise Match | 136m | South |

Business Directory Content Derived from Universal Business Directories (UBD) - Licensed from Hardie Grant

## 1975 Business Directory Records
## Road or Area Matches


Records from the 1975 UBD Business Directory, mapped to a road or an area, within the dataset buffer. Records are mapped to the road when a building number is not supplied, cannot be found, or the road has been renumbered since the directory was published:

| Business Activity | Premise | Ref No. | Location Confidence | Distance to Road Corridor |
|---|---|---|---|---|
| MEDICAL PRACTITIONERS. | Belfer, J. B., 461 Longueville Rd., Lane Cove. | 49700 | Road Match | 0m |
| LOCAL BODIES. | Lane Cove Council Chambers, Longueville Rd., Lane Cove. | 47821 | Road Match | 0m |
| CLUBS & /OR SPORTING BODIES | Lane Cove Womens Bowling & Recreation Club, Longueville Rd., Lane Cove. | 18080 | Road Match | 0m |

Business Directory Content Derived from Universal Business Directories (UBD) - Licensed from Hardie Grant

# 1970 Historical Business Directory Records

**266 Longueville Road, Lane Cove, NSW 2066**



# Historical Business Directories

**266 Longueville Road, Lane Cove, NSW 2066**

## 1970 Business Directory Records
## Premise or Road Intersection Matches

Records from the 1970 UBD Business Directory, mapped to a premise or road intersection, within the dataset buffer:

| Business Activity | Premise | Ref No. | Location Confidence | Distance to Feature Point | Direction |
|---|---|---|---|---|---|
| LAWN MOWER SALES/SERVICE (L310) | Partners Service Station (The),10 Northwood Rd.,Nrthwd | 322811 | Premise Match | 73m | South |
| MOTOR GARAGES & ENGINEERS(M6S6) | Partners Service Station (The),10 Northwood Rd.NORTHWOOD | 338395 | Premise Match | 73m | South |
| NEWSAGENTS (N100) | Northwood Newsagency,12 Northwood Rd.,Northwood | 343741 | Premise Match | 89m | South |
| STATIONERS-RETAIL (S516) | Northwood Newsagency,12 Northwood Rd.,Northwood | 364710 | Premise Match | 89m | South |
| BUTCHERS-RETAIL (B860) | Longueville Butchery, 14 Northwood Rd., Northwood | 273964 | Premise Match | 97m | South |
| POULTRY DEALERS-RETAIL (P692) | Longueville Butchery,14 Northwood Rd.,Northwood | 351254 | Premise Match | 97m | South |
| MOTOR BUS SERVICES (M516) | Longueville Motor Bus Co. Pty. Ltd.r 16 Northwood Rd.,Northwood | 335618 | Premise Match | 105m | South |
| CHEMISTS-PHARMACEUTICAL (C286) | Foley's Pharmacy, 18b Northwood Rd., Northwood | 280377 | Premise Match | 119m | South |
| CHEMISTS-PHARMACEUTICAL (C286) | Gieeson, Michael G., 18b Northwood Rd., Northwood | 280424 | Premise Match | 119m | South |
| FRUITERERS/GREENGROCERS (F640) | Northwood Fruit & Veg.Store (The),18c Northwood Rd.,Northwood . | 307653 | Premise Match | 119m | South |
| GROCERS-RETAIL (G655) | Northwood Self Service,1 Northwood Rd.,Northwood | 312826 | Premise Match | 127m | South |
| REAL ESTATE AGENTS/VALUERS(R205) | MacKeddie Real Estate,3 Northwood Rd.6LONGUEVILLE | 355671 | Premise Match | 136m | South |

Business Directory Content Derived from Universal Business Directories (UBD) - Licensed from Hardie Grant

## 1970 Business Directory Records
## Road or Area Matches

Records from the 1970 UBD Business Directory, mapped to a road or an area, within the dataset buffer. Records are mapped to the road when a building number is not supplied, cannot be found, or the road has been renumbered since the directory was published:


| Business Activity | Premise | Ref No. | Location Confidence | Distance to Road Corridor |
|---|---|---|---|---|
| BOOT & SHOE REPAIRERS (B580) | Crispe, AG., LonguevNIe Rd., Lane Cove | 268785 | Road Match | 0m |
| MUSIC TEACHERS (M780) | Harrison White Studio,9 Longueville Rd.,Lane Cove | 342957 | Road Match | 0m |
| LOCAL BODIES (L630) | Lane Cove Council Chambers,Longueville Rd.,Lane Cove | 323764 | Road Match | 0m |
| LIBRARIES-LENDING (L450) | Lane Cove Public Library,Longueville Rd.,Lane Cove | 323196 | Road Match | 0m |
| CLUBS & SPORTING BODIES (C487) | Lane Cove Women's Bowling & Recreation Club, LonguevilleRd., Lane Cove. | 284360 | Road Match | 0m |
| BEDDING MANUFACTURERS (B270) | Malba Products, 82 Longueville Rd., Lane Cove | 266851 | Road Match | 0m |
| CLUBS & SPORTING BODIES (C487) | Lane Cove Bowling & Recreation Club, Kenneth St., Longueville | 284351 | Road Match | 117m |
| CLUBS & SPORTING BODIES (C487) | Lane Cove Bowling Club., Kenneth St, Lane Cove | 284352 | Road Match | 117m |
| CLUBS & SPORTING BODIES (C487) | Lane Cove Tennis Club, Kenneth St., Lane Cove | 284358 | Road Match | 117m |
| CLUBS & SPORTING BODIES (C487) | Longueville Tennis Club, Kenneth St., Longueville | 284386 | Road Match | 117m |

| Business Activity | Premise | Ref No. | Location Confidence | Distance to Road Corridor |
|---|---|---|---|---|
| FRUITERERS/GREENGROCERS (F640) | Northwood,Kenneth Street Two,2 Kenneth St.,Northwood | 307654 | Road Match | 117m |

Business Directory Content Derived from Universal Business Directories (UBD) - Licensed from Hardie Grant

# 1965 Historical Business Directory Records

**266 Longueville Road, Lane Cove, NSW 2066**



# Historical Business Directories

**266 Longueville Road, Lane Cove, NSW 2066**

## 1965 Business Directory Records
## Premise or Road Intersection Matches

Records from the 1965 UBD Business Directory, mapped to a premise or road intersection, within the dataset buffer:

| Business Activity | Premise | Ref No. | Location Confidence | Distance to Feature Point | Direction |
|---|---|---|---|---|---|
| Grocers - Retail | Northwood Service Stores, , 4 Northwood Rd., Northwood | 96927 | Premise Match | 65m | South |
| STATIONERS—RETAIL | Northwood Newsagency , 12 Northwood Rd., Northwood | 147636 | Premise Match | 89m | South |
| Newsagents | Northwood Newsagency, 12 Northwood Rd., Northwood | 128363 | Premise Match | 89m | South |
| Butchers - Retail | Longueville Butchery , 14 Northwood Rd. Northwood | 58732 | Premise Match | 97m | South |
| Poultry Dealers - Retail | Longueville Butchery, , 14 Northwood Rd., Northwood | 135471 | Premise Match | 97m | South |
| Haberdashery - Retail | Eighteen-A (8-Teen-A) , 18a Northwood Rd., Northwood | 97534 | Premise Match | 121m | South |
| Butchers - Retail | Northwood Meat Service (Crawley), , 1a Northwood Rd , Northwood | 58986 | Premise Match | 127m | South |
| Grocers - Retail | Northwood Self Service, , 1 Northwood Rd., Northwood | 96926 | Premise Match | 127m | South |
| DELICATESSENS | McKinley, M. & W., 3 Northwood Rd., Northwood | 72404 | Premise Match | 137m | South |

Business Directory Content Derived from Universal Business Directories (UBD) - Licensed from Hardie Grant

## 1965 Business Directory Records
## Road or Area Matches


Records from the 1965 UBD Business Directory, mapped to a road or an area, within the dataset buffer. Records are mapped to the road when a building number is not supplied, cannot be found, or the road has been renumbered since the directory was published:

| Business Activity | Premise | Ref No. | Location Confidence | Distance to Road Corridor |
|---|---|---|---|---|
| BOOT & SHOE REPAIRERS | Ceisee, A. G., Longuevilte Rd., Lane Cove | 53201 | Road Match | 0m |
| Local Bodies | Lane Cove Council Chambers, Longueville Rd., Lane Cove | 108329 | Road Match | 0m |
| Clubs & Sporting Bodies | Lane Cove Women's Bowling & Recreation Club, Longueville Rd., Lane Cove | 69034 | Road Match | 0m |
| Schools/Colleges - Private/Public | Woodley Preparatory School, , Lonqueville Rd , Longueville | 143005 | Road Match | 0m |
| Clubs & Sporting Bodies | Lane Cove Bowling & Recreation Club, Kenneth St., Longueville | 69029 | Road Match | 117m |
| Fruiterers & Greengrocers | Northwood, Kenneth Street "Two", , 2 Kenneth St., Northwood | 91837 | Road Match | 117m |
| Motor Garages & Engineers - Longueville | Radke, W. H. & Co., 8 Kenneth St. | 122954 | Road Match | 117m |

Business Directory Content Derived from Universal Business Directories (UBD) - Licensed from Hardie Grant

# 1950 Historical Business Directory Records

**266 Longueville Road, Lane Cove, NSW 2066**



# Historical Business Directories

**266 Longueville Road, Lane Cove, NSW 2066**

## 1950 Business Directory Records
## Premise or Road Intersection Matches

Records from the 1950 UBD Business Directory, mapped to a premise or road intersection, within the dataset buffer:

| Business Activity | Premise | Ref No. | Location Confidence | Distance to Feature Point | Direction |
|---|---|---|---|---|---|
| GROCERS-RETAIL | Chalmers, J., 4 Northwood Rd., Northwood | 56816 | Premise Match | 65m | South |
| MOTOR SERVICE STATIONS-PETROL, Etc. | Longueville Service Station (Les. Smith), Cnr. Northwood Rd. and Kenneth St., Longueville | 86158 | Road Intersection | 88m | South |
| NEWSAGENTS | Isles, A. B., 12 Northwood Rd., Northwood | 88079 | Premise Match | 89m | South |
| BUTCHERS-RETAIL | Outfield, G. H., 14 Northwood Rd., Lane Cove | 14069 | Premise Match | 97m | South |
| FRUITERERS & GREENGROCERS | Cleary, D., 18 Northwood Rd., Lane Cove | 49828 | Premise Match | 119m | South |
| FRUITERERS & GREENGROCERS | Emmett, A., 18a Northwood Rd., Lane Cove | 50028 | Premise Match | 119m | South |
| MIXED BUSINESSES & GENERAL STORES | Pym, A. and J., 1 Northwood Rd., Northwood | 80826 | Premise Match | 127m | South |
| GROCERS-RETAIL | Pym, A., 1 Northwood Rd., Northwood | 58789 | Premise Match | 127m | South |
| DELICATESSENS & SMALLGOODS DEALERS | Pyrn, .A, 1 Northwood Rd., Northwood | 31068 | Premise Match | 127m | South |
| MILK BARS & CONFECTIONERS | ym, A., 1 Northwood Rd., Northwood | 77588 | Premise Match | 127m | South |
| GROCERS-RETAIL | Merkel, H. P., 3 Northwood Rd., Northwood | 58379 | Premise Match | 136m | South |
| DELICATESSENS & SMALLGOODS DEALERS | Merkell, N. P., 3 Northwood Rd., Northwood | 30889 | Premise Match | 136m | South |
| ELECTRICAL CONTRACTORS &/OR ELECTRICIANS | Alliance Electrical Co., 5 Northwood Rd., Northwood | 37338 | Premise Match | 148m | South |
| ELECTRICAL CONTRACTORS &/OR ELECTRICIANS | Alliance Electrical Co., 5 Northwood Rd., Northwood | 37337 | Premise Match | 148m | South |
| ELECTRICAL SUPPLIES & APPLIANCES RETAILERS | Alliance Electrical Co., 5 Northwood Rd., Northwood | 38349 | Premise Match | 148m | South |
| BEAUTY SALONS &/OR LADIES' HAIRDRESSERS | Dudgeon, Miss J., 5a Northwood Rd., Northwood | 7083 | Premise Match | 148m | South |
| FURNITURE MFRS.-FOLDING &/OR CANVAS | Floyd, A. L. Pleazing Products, 5 Northwood Rd., Northwood | 53134 | Premise Match | 148m | South |
| TOY MANUFACTURERS | Floyd, A. L. Pleazing Products, 5 Northwood Rd., Northwood | 109777 | Premise Match | 148m | South |
| BEAUTY SALONS &/OR LADIES' HAIRDRESSERS | Ralph, R., 5a Northwood Rd., Northwood | 7704 | Premise Match | 148m | South |

Business Directory Content Derived from Universal Business Directories (UBD) - Licensed from Hardie Grant

## 1950 Business Directory Records
## Road or Area Matches

Records from the 1950 UBD Business Directory, mapped to a road or an area, within the dataset buffer. Records are mapped to the road when a building number is not supplied, cannot be found, or the road has been renumbered since the directory was published:

| Business Activity | Premise | Ref No. | Location Confidence | Distance to Road Corridor |
|---|---|---|---|---|
| FUNERAL DIRECTORS | Andrews, T. J. Longueville Rd., Lane Cove | 51974 | Road Match | 0m |
| HALLS | Lane Cove Masonic, Longueville Rd., Lane Cove | 60366 | Road Match | 0m |

| Business Activity | Premise | Ref No. | Location Confidence | Distance to Road Corridor |
|---|---|---|---|---|
| HALLS | Lane Cove Town Hall, Longueville Rd., Lane Cove | 60367 | Road Match | 0m |
| MOTOR GARAGES &/OR ENGINEERS | Radke and Denniss, 6 Kenneth St., Longueville | 84252 | Road Match | 117m |
| WELDERS-ELECTRIC &/OR OXY | Radke and Denniss, 6 Kenneth St., Longueville | 113027 | Road Match | 117m |

Business Directory Content Derived from Universal Business Directories (UBD) - Licensed from Hardie Grant

# Historical Business Directories

**266 Longueville Road, Lane Cove, NSW 2066**

## Dry Cleaners, Motor Garages & Service Stations
## Premise or Road Intersection Matches

Dry Cleaners, Motor Garages & Service Stations from UBD Business Directories, mapped to a premise or road intersection, within the dataset buffer:

| Business Activity | Premise | Ref No. | Year | Location Confidence | Distance to Feature Point | Direction |
|---|---|---|---|---|---|---|
| Motor Garages & Service Stations | Caltex Northwood Service Station 10 Northwood Rd., Northwood 2066 | 53640 | 1991 | Premise Match | 73m | South |
| MOTOR GARAGES & SERVICE STATIONS. | Calico Northwood, 10 Northwood Rd., Northwood. | 64372 | 1986 | Premise Match | 73m | South |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. | Caltex Service Station, 10 Northwood Rd., Northwood. | 49727 | 1978 | Premise Match | 73m | South |
| MOTOR GARAGES &/OR ENGINEERS. | Pascate, L. & M., 10 Northwood Rd, Northwood. | 59374 | 1975 | Premise Match | 73m | South |
| MOTOR GARAGES & ENGINEERS(M6S6) | Partners Service Station (The),10 Northwood Rd.NORTHWOOD | 338395 | 1970 | Premise Match | 73m | South |
| MOTOR SERVICE STATIONS-PETROL, Etc. | Longueville Service Station (Les. Smith), Cnr. Northwood Rd. and Kenneth St., Longueville | 86158 | 1950 | Road Intersection | 88m | South |
| DRY CLEANERS, PRESSERS&/OR DYERS. | Lawrence Dry Cleaners, 18A Northwood Rd., Northwood | 24129 | 1975 | Premise Match | 121m | South |
| Motor Garages & Service Stations | Ampol Longueville ply. Ltd. 7 Northwood Rd., Longueville.-2066 | 53477 | 1991 | Premise Match | 161m | South |
| MOTOR GARAGES & SERVICE STATIONS. | Ampol Longueville Pty. Ltd., 7 Northwood Rd., Longueville. | 63931 | 1986 | Premise Match | 161m | South |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. (M6860) | Ampol Longueville Pty. Ltd., 7 Northwood Rd., Longueville. 2066. | 56013 | 1982 | Premise Match | 161m | South |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. | Longueville Service Station, 7 Northwood Rd., Longueville. | 50393 | 1978 | Premise Match | 161m | South |
| MOTOR GARAGES &/OR ENGINEERS. | Longueville Service Station. 7 Northwood Rd., Longueville. | 59165 | 1975 | Premise Match | 161m | South |
| MOTOR SERVICE STATIONS-PETROL,OIL,Etc. (M716) | Longueville Service Station,7 Northwood Rd.LONGUEVILLE | 341284 | 1970 | Premise Match | 161m | South |
| MOTOR SERVICE STATIONS-PETROL,OIL,Etc. (M716) | Longueville Service Station,7 Northwood Rd.NORTHWOOD | 341285 | 1970 | Premise Match | 161m | South |
| Motor Service Stations - Petrol, Oil, Etc. - Longueville | Longueville Service Station, 7 Northwood Ave. | 125870 | 1965 | Premise Match | 161m | South |
| Motor Garages & Engineers - Longueville | Longueville Service Station, 7 Northwood Rd. | 122953 | 1965 | Premise Match | 161m | South |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. (M6860) | BP Northwood Service Station, 9 Northwood Rd , Northwood. 2066. | 56268 | 1982 | Premise Match | 175m | South |
| MOTOR SERVICE STATIONS - PETROL, OIL | BP Northwood Service Station, 9 Northwood Rd., Northwood. | 61530 | 1975 | Premise Match | 175m | South |
| MOTOR GARAGES &/OR ENGINEERS | Bivens, D„ 35 Wangalla Rd., Lane Cove | 83458 | 1950 | Premise Match | 641m | West |
| DRY CLEANERS & PRESSERS. | Riverview Dry Cleaners, 59A Tambourine Bay Rd., Lane Cove. | 25495 | 1986 | Premise Match | 685m | West |
| DRY CLEANERS & PRESSERS. (D8500) | Riverview Dry Cleaners, 59A Tambourine Bay Rd., Lane Cove. 2066. | 24026 | 1982 | Premise Match | 685m | West |
| DRY CLEANERS, PRESSERS &/OR DYERS | Riverview Dry Cleaners, 59A Tambourine Bay Rd., Lane Cove. | 20937 | 1978 | Premise Match | 685m | West |
| DRY CLEANERS, PRESSERS&/OR DYERS. | Riverview Dry Cleaners. 59A Tambourine Bay Rd., Lane Cove. | 24311 | 1975 | Premise Match | 690m | West |
| DRY CLEANERS, PRESSERS & DYERS | Vicks Dry Cleaners,  150 Longueville Rd., Lane Cove | 35810 | 1950 | Premise Match | 806m | North |
| MOTOR GARAGES &/OR ENGINEERS. | Central Auto Port, 50 Burns Bay Rd., Lane Cove. | 58646 | 1975 | Premise Match | 828m | North West |
| DRY CLEANERS, PRESSERS&/OR DYERS. | Lawrence Dry Cleaners, 48 Bums Bay Rd., Lane Cove. | 24133 | 1975 | Premise Match | 833m | North West |
| Motor Service Stations - Petrol, Oil, Etc. - Lane Cove | Central Auto Port, 48 Burns Bay Rd. | 125834 | 1965 | Premise Match | 833m | North West |

| Business Activity | Premise | Ref No. | Year | Location Confidence | Distance to Feature Point | Direction |
|---|---|---|---|---|---|---|
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. | Central Auto Port, 50 Burns Bay Rd., Lane Cove. | 49778 | 1978 | Premise Match | 835m | North West |
| MOTOR GARAGES & ENGINEERS(M6S6) | Central Auto Port,50 Burns Bay Rd.LANE COVE | 337549 | 1970 | Premise Match | 835m | North West |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. (M6860) | Autostrada Pty. Ltd., Rear 373 Pacific H'way., Artarmon. 2064. | 56064 | 1982 | Premise Match | 853m | North East |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. | Autostrada Pty. Ltd., 373 Pacific H'way., Artarmon. | 49330 | 1978 | Premise Match | 853m | North East |
| MOTOR GARAGES & ENGINEERS(M6S6) | Lardner,Ted Motors,44 Burns Bay Rd.LANE COVE | 338145 | 1970 | Premise Match | 854m | North West |
| Motor Garages & Engineers - Lane Cove | Lardner, Tad Motors, 44 Burns Bay Rd. | 122879 | 1965 | Premise Match | 854m | North West |
| MOTOR GARAGES &/OR ENGINEERS | Bivens, Don C., 44 Burns Bay Rd., Lane Cove | 83459 | 1950 | Premise Match | 854m | North West |
| MOTOR GARAGES & ENGINEERS(M6S6) | White Nicfiolson,B.M.C.,387 Pacific Highway. ARTARMON | 338877 | 1970 | Premise Match | 858m | North East |
| DRY CLEANERS & PRESSERS. | Lawrence Dry Cleaners, 56 Burns Bay Rd., Lane Cove. | 25394 | 1986 | Premise Match | 861m | North West |
| DRY CLEANERS & PRESSERS. (D8500) | Lawrence Dry Cleaners, 56 Burns Bay Rd., Lane Cove, 2066. | 23905 | 1982 | Premise Match | 861m | North West |
| DRY CLEANERS, PRESSERS & DYERS | Tasman Dry Cleaners.  326 Pacific Hghway., Lane Cove | 35773 | 1950 | Premise Match | 875m | North East |
| MOTOR SERVICE STATIONS - PETROL, OIL | Golden Fleece Service Station, 395 Pacific H'way, Artarmon. | 61790 | 1975 | Premise Match | 882m | North East |
| Motor Service Stations - Petrol, Oil, Etc. - Artarmon | Golden Fleece Service Station, 395 Pacific Hghwy. | 125384 | 1965 | Premise Match | 882m | North East |
| Motor Garages & Engineers - Artarmon | Styles, R., 395 Pacific Hghwy. | 122120 | 1965 | Premise Match | 882m | North East |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. | Golden Fleece Service Station, 395 Pacific H'way, Artarmon. | 50164 | 1978 | Premise Match | 885m | North East |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. | Styles, R., 395 Pacific H'way., Artarmon. | 50886 | 1978 | Premise Match | 885m | North East |
| DRY CLEANERS & PRESSERS. | Escort Dry Cleaners. 120 Longueville Rd., Lane Cove. | 25296 | 1986 | Premise Match | 886m | North |
| DRY CLEANERS & PRESSERS. (D8500) | Escort Dry Cleaners, 120 Longueville Rd., Lane Cove. 2066. | 23826 | 1982 | Premise Match | 886m | North |
| DRY CLEANERS, PRESSERS &/OR DYERS | Escort Dry Cleaners, 120 Longueville Rd., Lane Cove. | 20762 | 1978 | Premise Match | 886m | North |
| DRY CLEANERS, PRESSERS&/OR DYERS. | Escort Dry Cleaners, 120 Longueville Rd., Lane Cove. | 24019 | 1975 | Premise Match | 886m | North |
| Motor Garages & Service Stations | Artarmon Self Serve Mobil 395 Pacific Hway, Chatswood 2067 | 53519 | 1991 | Premise Match | 886m | North East |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. (M6860) | Golden Fleece Artarmon Service Station, 395 Pacific H'way,Artarmon. 2064. | 56813 | 1982 | Premise Match | 886m | North East |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. (M6860) | Styles, Rex, 395 Pacific H'way., Artarmon. 2064. | 57635 | 1982 | Premise Match | 886m | North East |
| MOTOR SERVICE STATIONS-PETROL,OIL,Etc. (M716) | Golden Fleece Service Station,395 Pacific Highway.Artarmon | 341161 | 1970 | Premise Match | 886m | North East |
| MOTOR GARAGES & ENGINEERS(M6S6) | Styles,R.,395 Pacific Highway.ARTARMON | 338678 | 1970 | Premise Match | 886m | North East |
| MOTOR GARAGES & SERVICE STATIONS. | BP South Lane Cove, 64 Burns Bay Rd., Lane Cove. | 64231 | 1986 | Premise Match | 895m | North West |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. (M6860) | Amoco Lane Cove, 64 Burns Bay Rd., Lane Cove. 2066. | 55972 | 1982 | Premise Match | 895m | North West |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. | Amoco Lane Cove, 64 Burns Bay Rd.. Lane Cove. | 49236 | 1978 | Premise Match | 895m | North West |
| MOTOR GARAGES & SERVICE STATIONS. | Walker Begg, 96 Hotham Pde., Artarmon. | 65680 | 1986 | Premise Match | 896m | North East |
| MOTOR GARAGES & ENGINEERS(M6S6) | Lane Cove Service Centre,43-45 Burns Bay Rd.LANE COVE | 338138 | 1970 | Premise Match | 904m | North West |
| MOTOR SERVICE STATIONS-PETROL,OIL,Etc. (M716) | Lane Cove (Mobil) Service Centre,45 Burns Bay Rd.LANE COVE | 341266 | 1970 | Premise Match | 911m | North West |
| MOTOR GARAGES & SERVICE STATIONS. | Automotive Developmental Services Pty. Ltd., Rear 78 Whiting St., Artarmon. | 63990 | 1986 | Premise Match | 919m | North East |

| Business Activity | Premise | Ref No. | Year | Location Confidence | Distance to Feature Point | Direction |
|---|---|---|---|---|---|---|
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. (M6860) | Pope Automobile Developments, Rear 78 Whiting St., Artarmon.2064. | 57394 | 1982 | Premise Match | 919m | North East |
| Motor Service Stations - Petrol, Oil, Etc. - Lane Cove | Lane Cove (Mobil) Service Centre, 45-47 Burns Bay Rd. | 125840 | 1965 | Premise Match | 924m | North West |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. | Lane Cove Service Centre, 45 Burns Bay Rd., Lane Cove. | 50364 | 1978 | Premise Match | 925m | North West |
| MOTOR GARAGES &/OR ENGINEERS. | Lane Cove Service Centre, 43 Burns Bay Rd., Lane Cove. | 59140 | 1975 | Premise Match | 925m | North West |
| DRY CLEANERS, PRESSERS&/OR DYERS. | New Mayfair Dry Cleaning Pty. Ltd., 98 Longueville Rd., Lane Cove. | 24238 | 1975 | Premise Match | 927m | North |
| DRY CLEANERS & PRESSERS. | New Mayfair Dry Cleaning Pty. Ltd., 98 Longueville Rd., Lane Cove. | 25452 | 1986 | Premise Match | 928m | North |
| DRY CLEANERS & PRESSERS. (D8500) | New Mayfair Dry Cleaning Pty. Ltd., 98 Longueville Rd., Lane Cove.. 2066. | 23987 | 1982 | Premise Match | 928m | North |
| DRY CLEANERS, PRESSERS &/OR DYERS | New Mayfair Dry Cleaning Pty. Ltd., 98 Longueville Rd., Lane Cove. | 20890 | 1978 | Premise Match | 928m | North |
| DRY CLEANERS,PRESSERS/DYERS (D710) | New Mayfair Dry Cleaners Pty.Ltd.,98 Longueville Rd.,Lane Cove | 292418 | 1970 | Premise Match | 928m | North |
| Dry Cleaners, Pressers/Dyers | New Mayfair Dry Cleaners Pty. Ltd., 98 Longueville Rd., Lane Cove | 76260 | 1965 | Premise Match | 928m | North |
| MOTOR GARAGES &/OR ENGINEERS. | BP Artarmon Service Station, 327 Pacific H'way, Artarmon. | 58512 | 1975 | Premise Match | 930m | North East |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. | B. & W. Motor Engineers, 85 Longueville Rd., Lane Cove. | 49358 | 1978 | Premise Match | 956m | North |
| MOTOR GARAGES & ENGINEERS(M6S6) | B. & w. Motor Engineers,85 Longueville Rd.LANE COVE | 337230 | 1970 | Premise Match | 956m | North |
| Motor Garages & Engineers - Lane Cove | B. & W. Motor Engineers, 85 Longueville Rd. | 122875 | 1965 | Premise Match | 956m | North |
| MOTOR GARAGES &/OR ENGINEERS. | Lane Cove Auto Port. 374 Pacific Hwy, Lane Cove. | 59139 | 1975 | Premise Match | 964m | North |
| Motor Service Stations - Petrol, Oil, Etc. - Lane Cove | Lane Cove Auto Port, 374-378 Pacific Hghwy. | 125839 | 1965 | Premise Match | 964m | North |
| MOTOR GARAGES & ENGINEERS(M6S6) | Lane Cove Auto Port,374 Pacific Highway.LANE COVE | 338137 | 1970 | Premise Match | 967m | North East |
| Motor Garages & Service Stations | Shell Lane Cove Self Serve 374 Pacific H'way, Lane Cove | 53862 | 1991 | Road Intersection | 969m | North East |
| MOTOR GARAGES & SERVICE STATIONS. | Shell Lane Cove Self Serve, 374 Pacific H'way., Lane Cove. | 65430 | 1986 | Road Intersection | 969m | North East |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. | BP Artarmon Service Station, 327Pacific H'way, Artarmon. | 49493 | 1978 | Premise Match | 970m | North East |
| MOTOR GARAGES & ENGINEERS(M6S6) | BP Artarmon Service Station,327 Pacific Highway.ARTARMON | 337356 | 1970 | Premise Match | 970m | North East |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. (M6860) | Custom Clutches, 81 Dickson Ave., Artarmon. 2064. | 56602 | 1982 | Premise Match | 973m | North East |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. (M6860) | Lane Cove Auto Port, 374 Pacific H'way., Lane Cove. 2066. | 57078 | 1982 | Road Intersection | 976m | North East |
| MOTOR GARAGES & SERVICE STATIONS. | Alamain Service Centre, 73 Longueville Rd., Lane Cove. | 63868 | 1986 | Premise Match | 979m | North |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. (M6860) | Alamain Service Centre, 73 Longueville Rd., Lane Cove. 2066. | 55938 | 1982 | Premise Match | 979m | North |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. | Lane Cove Terminus Motors, 73 Longueville Rd., Lane Cove. | 50365 | 1978 | Premise Match | 979m | North |
| MOTOR SERVICE STATIONS-PETROL,OIL,Etc. (M716) | Ampol Service Station,73 Longueville Rd.LANE COVE | 340771 | 1970 | Premise Match | 979m | North |
| MOTOR GARAGES & ENGINEERS(M6S6) | Lane Cove Terminus Motors,73 Longueville Rd.LANE COVE | 338139 | 1970 | Premise Match | 979m | North |
| Motor Garages & Engineers - Lane Cove | Ampol Garage, 73 Longueville Rd. | 122874 | 1965 | Premise Match | 979m | North |
| MOTOR GARAGES &/OR ENGINEERS | Belsey, F. S., 73 Longueville Rd., Lane Cove | 83446 | 1950 | Premise Match | 979m | North |
| MOTOR SERVICE STATIONS-PETROL, Etc. | Lane Cove Terminus Motors, 73 Longueville Rd., Lane Cove | 86123 | 1950 | Premise Match | 979m | North |
| MOTOR GARAGES &/OR ENGINEERS | Lane Cove Terminus Motors, 73 Longuevlle Rd., Lane Cove | 83976 | 1950 | Premise Match | 979m | North |
| Engineers - Laundry & Dry Cleaning | Cooper, Grimm & Turner Engineering Pty. Ltd. , 78 Hotham Pde., Artarmon | 83321 | 1965 | Premise Match | 980m | North East |

| Business Activity | Premise | Ref No. | Year | Location Confidence | Distance to Feature Point | Direction |
|---|---|---|---|---|---|---|
| Dry Cleaning Machinery & Supplies - Mfrs. &/or Dists. | Cooper, Grimm & Turner Engineering Pty. Ltd., 78 Hotham Pde., Artarmon | 76398 | 1965 | Premise Match | 980m | North East |
| MOTOR GARAGES &/OR ENGINEERS. | Lane Cove Terminus Motors. 73 Longueville Rd., Lane Cove. | 59141 | 1975 | Premise Match | 981m | North |
| MOTOR GARAGES & SERVICE STATIONS. | Esso Lane Cove Service Station, 382 Pacific H'way, Lane Cove. | 64636 | 1986 | Premise Match | 986m | North |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. (M6860) | Esso Lane Cove Service Station, 382 Pacific H'way, Lane Cove.2066. | 56705 | 1982 | Premise Match | 986m | North |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. | Esso Servicenter, 382 Pacific H'way, Lane Cove. | 49993 | 1978 | Premise Match | 986m | North |
| MOTOR GARAGES & ENGINEERS(M6S6) | Red Carpet Service Station Pty. Ltd.,382 Pacific Highway.LANE COVE | 338487 | 1970 | Premise Match | 986m | North |
| MOTOR GARAGES &/OR ENGINEERS. | Esso Servicenter 382 Pacific H'way, Lane Cove. | 58830 | 1975 | Premise Match | 987m | North |
| Motor Garages & Service Stations | Ampol Artarmon 301 Pacific H'way., Artarmon. 2064 | 53458 | 1991 | Premise Match | 988m | North East |
| MOTOR GARAGES & SERVICE STATIONS. | Pit Stop Performance Centre Pty. Ltd., 301 Pacific H'way. Artarmon. | 65271 | 1986 | Premise Match | 988m | North East |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. (M6860) | Pit Stop Performance Centre, 301 Pacific H'way., Artarmon. 2064. | 57389 | 1982 | Premise Match | 988m | North East |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. | Total Artarmon Service Station, 301 Pacific H'way, Artarmon. | 50958 | 1978 | Premise Match | 988m | North East |
| MOTOR SERVICE STATIONS - PETROL, OIL | Total Artarmon Service Station, 301 Pacific H'way, Artarmon. | 61987 | 1975 | Premise Match | 988m | North East |
| MOTOR SERVICE STATIONS-PETROL,OIL,Etc. (M716) | Total Artarmon Service Station,301 Pacific Highway.Artarmon | 341547 | 1970 | Premise Match | 988m | North East |
| Motor Service Stations - Petrol, Oil, Etc. - Artarmon | Total Artarmon Service Station, 301 Pacific Hghwy. | 125388 | 1965 | Premise Match | 988m | North East |
| Motor Garages & Engineers - Artarmon | Castlereagh Tuning Centre, 403 Pacific Hghwy. | 122115 | 1965 | Premise Match | 997m | North East |

Business Directory Content Derived from Universal Business Directories (UBD) - Licensed from Hardie Grant

# Historical Business Directories

**266 Longueville Road, Lane Cove, NSW 2066**

## Dry Cleaners, Motor Garages & Service Stations Road or Area Matches

Dry Cleaners, Motor Garages & Service Stations from UBD Business Directories, mapped to a road or an area, within the dataset buffer. Records are mapped to the road when a building number is not supplied, cannot be found, or the road has been renumbered since the directory was published:

| Business Activity | Premise | Ref No. | Year | Location Confidence | Distance to Road Corridor |
|---|---|---|---|---|---|
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. | BP Northwood Service Station. 6 Kenneth St.. Northwood. | 49586 | 1978 | Road Match | 117m |
| MOTOR GARAGES &/OR ENGINEERS | Radke and Denniss, 6 Kenneth St., Longueville | 84252 | 1950 | Road Match | 117m |
| Motor Garages & Engineers - Longueville | Radke, W. H. & Co., 8 Kenneth St. | 122954 | 1965 | Road Match | 117m |
| MOTOR SERVICE STATIONS-PETROL,OIL,Etc. (M716) | Embassy Services of Auburn Pty. Ltd.,Northwood Rd.NORTHWOOD | 341027 | 1970 | Road Match | 379m |
| MOTOR GARAGES &/OR ENGINEERS. | Alto Ford (Artarmon) Pty. Ltd., 387 Pacific H'way., Artarmon. | 58323 | 1975 | Road Match | 803m |
| MOTOR SERVICE STATIONS - PETROL, OIL | BP Hanthom Service Station, 422 Pacific H'way, Artarmon. | 61413 | 1975 | Road Match | 803m |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. | BP Hanthorn Service Station, 422 Pacific H'way, Artarmon, | 49350 | 1978 | Road Match | 803m |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. | Lane Cove Auto Port, Pacific H'way., Lane Cove. | 50362 | 1978 | Road Match | 803m |
| MOTOR GARAGES & SERVICE STATIONS. | Pacific Tyrepower Automotive, 341 Pacific H'way., Artarmon. | 65224 | 1986 | Road Match | 803m |
| MOTOR GARAGES & SERVICE STATIONS. | Shell Artarmon Auto Port, 247 Pacific H'way., ArtarmOn. | 65405 | 1986 | Road Match | 803m |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. | T.V. Auto Port, 247 Pacific H'way, Artarmon. | 50930 | 1978 | Road Match | 803m |
| MOTOR GARAGES &/OR ENGINEERS &/OR SERVICE STATIONS. (M6860) | T.V. Auto Port, 247 Pacific H'way, Artarmon. 2064. | 57676 | 1982 | Road Match | 803m |
| Motor Service Stations - Petrol, Oil, Etc. - Artarmon | Hanthorn, R. G. & Co., 420 Pacific Hghwy. | 125386 | 1965 | Road Match | 818m |
| Motor Service Stations - Petrol, Oil, Etc. - Artarmon | Schmitz, P. B., Pacific Hghwy. | 125387 | 1965 | Road Match | 818m |
| MOTOR GARAGES &/OR ENGINEERS | Bennet'5 Corner Garage, Burns Bay Rd., Lane Cove | 83448 | 1950 | Road Match | 825m |
| MOTOR GARAGES &/OR ENGINEERS. | Bruce's B. Service Station, 66 Bums Bay Rd., Lane Cove. | 58492 | 1975 | Road Match | 825m |
| MOTOR GARAGES &/OR ENGINEERS. | Burns Bay Auto Port, 250 Bums Bay Rd., Lane Cove. | 58504 | 1975 | Road Match | 825m |
| MOTOR GARAGES &/OR ENGINEERS | Felton's Service Station, Burns Bay, Rd,, Lane Cove | 83738 | 1950 | Road Match | 825m |
| MOTOR SERVICE STATIONS-PETROL, Etc. | Feltons Service Station, Burns Bay Rd., Lane Cove | 85954 | 1950 | Road Match | 825m |
| MOTOR GARAGES &/OR ENGINEERS | Hutchison, S. J., Burns Bay Rd., Lane Cove | 83901 | 1950 | Road Match | 825m |

Business Directory Content Derived from Universal Business Directories (UBD) - Licensed from Hardie Grant

# Figure 25 - Acid Sulfate Soils Map

**Lane Cove Local Environmental Plan 2009**

Acid Sulfate Soils Map -


Sheet ASS_004

**Acid Sulfate Soils**

- 2 — Class 2
- 3 — Class 3
- 5 — Class 5

**Cadastre**

- Cadastre 30/04/09 © Lane Cove Council




N
W
E
S


0 metres 500

Projection GDA 1994
Zone 56

Scale: 1:10000 @ A3

Map identification number:
4700_COM_ASS_004_010_20090430

# Figure 26 - Sensitive Zone Map




## UPSS Regulation - Sensitive Zones Map

### LANE COVE MUNICIPAL COUNCIL

**Legend**

- Council Area
- Road
- Railway
- Sensitive Zone

Copyright Department of Environment, Climate Change and Water (NSW)
This map is not guaranteed to be free from error or omission
The Department of Environment, Climate Change and Water (NSW) and its employees disclaim liability for any act done on the information in the map and any consequences of such acts or omissions

Datum/Projection: GCS GDA 1994

Jan 12, 2010

0 0.4
Kilometres

Department of Environment, Climate Change and Water NSW

Scale at A3

1 cm equals 0.20 km

N

Lane Cove Council
48 Longueville Road, Lane Cove NSW 2066 Tel: 9911 3555 Fax: 9911 3600

# PLANNING CERTIFICATE

*Under Section10.7 Environmental Planning and Assessment Act, 1979*

**Applicant:**
Jon Lawson
65 Stubbs Streey
Kensington VIC 3031

| | |
|---|---|
| Date of Issue: | 15/08/2018 |
| Council Reference: | 133596 |
| Applicant Reference: | Lane Cove |
| Certificate No: | 1076 |

**Owner(s):** **Lane Cove Council**
**Property address:** **266 Longueville Road LANE COVE NSW 2066**
**Description:** **LOT: 1 DP: 321353**
**Property Reference:** **13319**

## INFORMATION PROVIDED PURSUANT TO SECTION 10.7(2) & (5) OF THE ACT

**The planning information contained in this certificate applies specifically to the land.**

**Table of Contents**


| Description | Section No. |
|---|---|
| **Part 2: Information for Section 10.7 (2)** | |
| Names of relevant planning instruments and DCP | 1 |
| Zoning, Heritage, Conservation | 2 |
| Zoning & land use under SEPP (Sydney Region Growth Centres) 2006 | 2A |
| Complying Development | 3 |
| Coastal protection | 4 |
| Certain information relating to beaches and coasts | 4A |
| Annual charges: Local Government Act – coastal protection | 4B |
| Mine Subsidence | 5 |
| Road Widening and road realignment | 6 |
| Council and other public hazard risk restriction | 7 |
| Flood related development controls | 7A |
| Land reserved for acquisition | 8 |
| Contributions plans | 9 |
| Biodiversity certified land | 9A |
| Biobanking agreements | 10 |
| Bushfire prone land | 11 |
| Property Vegetation Plans | 12 |
| Orders under Trees (disputes between neighbours) act | 13 |
| Directions under part 3A | 14 |
| Site compatibility certificates and conditions for seniors housing | 15 |
| Site compatibility certificates for infrastructure | 16 |
| Site compatibility certificates and conditions for affordable rental housing | 17 |
| Contaminated Land Management Act 1997s.59(2) | Note |
| | |
| **Part 5:** Additional information for Section 10.7 (5) | Part 5 |




PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

## PART 2:

## Sec: 1 Names of relevant planning instruments and DCP

1) The name of each environmental planning instrument that applies to the carrying out of development on the land.
**Lane Cove Local Environmental Plan 2009 - gazetted on 19 February 2010**

**State Environmental Planning Policy No.19: Bushland in Urban Areas - gazetted 24 October 1986**

**State Environmental Planning Policy No.32: Urban Consolidation (Redevelopment of Urban Land) - gazetted 15 November 1991**

**State Environmental Planning Policy No.55: Remediation of Land - gazetted 28 August 1998**

**State Environmental Planning Policy No.64: Advertising and Signage - gazetted 16 March 2001**

**State Environmental Planning Policy (BASIX) 2004 - gazetted 25 June 2004**

**State Environmental Planning Policy (Housing for seniors or people with a disability) 2004 Amendment No.2 - gazetted 31 March 2004 effective 12 October 2007**

**State Environmental Planning Policy (Temporary Structures and Places of Public Entertainment) - gazetted 28 September 2007**

**State Environmental Planning Policy (Major Projects) 2005 - gazetted 1 August 2005**

**State Environmental Planning Policy (Infrastructure) 2007 - gazetted 21 December 2007; commenced 1 January 2008**

**State Environmental Planning Policy (Exempt & Complying Development Codes) - gazetted 12 December 2008**

2) The name of each proposed environmental planning instrument that will apply to the carrying out of development on the land and that is or has been the subject of community consultations or on public exhibition under the Act (unless the Director-General has notified the council that the making of the proposed instrument has been deferred indefinitely or has not been approved)
**N/A**

3) The name of each development control plan that applies to the carrying out of development on the land.
**Lane Cove Development Control Plan, effective 22 February 2010**

4) In this clause, proposed environmental planning instrument includes a planning proposal for a LEP or draft environmental planning instrument.

## Sec: 2 Zoning and land use under relevant LEPs



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

## The land is zoned: High Density Residential R4

1) **Objectives of zone**
   - To provide for the housing needs of the community within a high density residential environment.
   - To provide a variety of housing types within a high density residential environment.
   - To enable other land uses that provide facilities or services to meet the day to day needs of residents.
   - To provide for a high concentration of housing with good access to transport, services and facilities.
   - To ensure that the existing amenity of residences in the neighbourhood is respected.
   - To avoid the isolation of sites resulting from site amalgamation.
   - To ensure that landscaping is maintained and enhanced as a major element in the residential environment.

2) **Permitted without consent**

   Nil

3) **Permitted with consent**

   Bed and breakfast accommodation; Boarding houses; Child care centres; Community facilities; Exhibition homes; Group homes; Home businesses; Home industries; Hotel or motel accommodation; Multi dwelling housing; Neighbourhood shops; Places of public worship; Residential flat buildings; Respite day care centres; Restaurants or cafes; Roads; Shop top housing; Signage.

4) **Prohibited**

   Any development not specified in item 2 or 3.

5) Whether any development standards applying to the land fix minimum land dimensions for the erection of a dwelling-house on the land and, if so, the minimum land dimensions so fixed:
   **Not Applicable**

6) Whether the land includes or comprises critical habitat:
   **NO**

7) Whether the land is in a conservation area (however described):
   **NO**

8) Whether an item of environmental heritage (however described) is situated on the land:
   **NO**

## Sec: 2A Zoning and land use under State Environmental Planning Policy (Sydney Region Growth Centres) 2006



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

**Not applicable.**

## Sec: 3 Complying development

1) The extent to which the land is on which complying development may be carried out under each of the codes for complying development because of the provisions of clauses 1.17A (1) (c) to (e), (2), (3) and (4) and 1.19 of State Environmental Planning Policy (Exempt and Complying Development Codes) 2008.

2) The extent to which complying development may not be carried out on that land because of the provisions of clauses 1.17A (1)(c) to (e), (2), (3) and (4) and 1.19 of that Policy and the reasons why it may not be carried out under those clauses.

3) If the council does not have sufficient information to ascertain the extent to which complying development may or may not be carried out on the land, a statement that a restriction applies to the land, but it may not apply to all of the land, and that council does not have sufficient information to ascertain the extent to which complying development may or may not be carried out on the land.

**(1) Complying development may be carried out on the land as a whole under the SEPP in accordance with the following Codes (unless the land is excluded elsewhere in this Section):- General Housing Code, Housing Alterations Code, General Development Code, Subdivision Code, Demolition Code and/or Fire Safety Code.**

**(2) Not applicable.**
**PLEASE NOTE: All of the provisions of the Low Rise Medium Density Housing Code have been deferred from the Lane Cove Local Government Area**

**(3) Not applicable**

## Sec: 4 Coastal Protection

Whether or not the land is affected by the operation of section 38 or 39 of the Coastal Protection Act 1979, but only to the extent that the council has been so notified by the Department of Services, Technology and Administration.

**NO**

## Sec: 4A Certain information relating to beaches and coasts

**Not applicable.**

## Sec: 4B Annual charges under Local Government Act 1993 for coastal protection services that relate to existing coastal protection works

**Not applicable.**

## Sec: 5 Mine subsidence



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

Whether or not the land is proclaimed to be a mine subsidence district within the meaning of section 15 of the *Mine Subsidence Compensation Act 1961*:
**NO**

## Sec: 6 Road widening and road realignment

Whether or not the land is affected by any road widening or road realignment under:

a) Division 2 of Part 3 of the *Roads Act 1993*:
**Not affected by road widening**

b) Any environmental planning instrument:
**NO**

c) Any resolution of the council:
**NO**

## Sec: 7 Council and other public authority policies on hazard risk restrictions

Whether or not the land is affected by a policy:
a) Adopted by the council, or
b) Adopted by any other public authority and notified to the council for the express purpose of its adoption by that authority being referred to in planning certificates issued by the council, that restricts the development of the land because of the likelihood of :-

Land slip:
**NO**

Bushfire:
**See Section 11.**

Tidal inundation:
**NO**

Subsidence:
**NO**

Acid Sulphate soils:
**NO**

## Sec: 7A Flood related development controls information

1) Whether or not development on that land or part of the land for the purposes of swelling houses, dual occupancies, multi dwelling housing or residential flat buildings (not including development for the purposes of group homes or seniors housing) is subject to flood related development controls.
**The Lane Cove Development Control Plan - effective 22 February 2010 - applies**



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

2) Whether or not development on that land or part of the land for any other purpose is subject to flood related development controls.
**The Lane Cove Development Control Plan - effective 22 February 2010 - applies**

**Overland Flow**
**A study is currently being undertaken to determine exact locations subject to overland flow in the Municipality of Lane Cove. Until such time as Council has completed this work, property owners should conduct their own investigations to be satisfied that this property is not affected by overland flow.**

Words and expressions in this clause have the same meanings as in the standard instrument set out in the *Standard Instrument (Local Environmental Plans) Order 2006*.

## Sec: 8 Land reserved for acquisition

Whether or not any environmental planning instrument or proposed environmental planning instrument referred to in clause 1 makes provision in relation to the acquisition of the land by a public authority, as referred to in section 27 of the Act.
**NO**

## Sec: 9 Contributions plans

**Lane Cove Section 94 Contributions Plan.**

## Sec: 9A Biodiversity certified land

**Not applicable.**

## Sec: 10 Biobanking agreements

**Not applicable.**

## Sec: 11 Bushfire prone land

**The land is not identified on the Lane Cove Bushfire Prone Land Map dated 27 May 2016.**

## Sec: 12 Property vegetation plans

**Not applicable.**

## Sec: 13 Orders under Trees (disputes Between Neighbours) Act 2006

Whether an order has been made under the *Trees (Disputes Between Neighbours) Act 2006* to carry out work in relation to a tree on the land (but only if the council has been notified of the order).
**NONE**



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

## Sec: 14 Directions under Part 3A

If there is a direction by the Minister in force under section 75P (2) (c1) of the Act that a provision of an environmental planning instrument prohibiting or restricting the carrying out of a project or a stage of a project on the land under Part 4 of the Act does not have effect, a statement to that effect identifying the provision that does not have effect.
**NONE**

## Sec: 15 Site compatibility certificates and conditions for seniors housing

If the land to which *State Environmental Planning Policy (Housing for Seniors or People with a Disability) 2004* applies:
**A Site Compatibility Certificate for Seniors Housing was issued on 6 July 2017 (and is valid for 24 months from this date) with respect to this land. A copy of the Site Compatibility Certificate can be obtained from the Head Offices of NSW Planning and Environment by contacting 1300 305 695.**

## Sec: 16 Site compatibility certificates for infrastructure

Whether there is a valid site compatibility certificate (infrastructure), of which the council is aware, in respect of proposed development on the land.
**NO**

## Sec: 17 Site compatibility certificates and conditions for affordable rental housing

Whether there is a current site compatibility certificate (affordable rental housing), of which the council is aware, in respect of proposed development on the land:
**NO**

## Sec: 18 Paper Subdivision Information

1) The name of any development plan adopted by a relevant authority that applies to the land or that is proposed to be subject to a consent ballot.
**Not applicable**

2) The date of an subdivision order that applies to the land.
**Not applicable**

3) Words and expressions used in this clause have the same meaning as they have in Part 16C of this Regulation.

## Sec: 19 Site verification certificates

**Not applicable**



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

## Sec: 20 Loose-fill asbestos insulation

If the land includes any residential premises (within the meaning of Division 1A of Part 8 of the Home Building Act 1989) that are listed on the register that is required to be maintained under that Division, a statement to that effect.

- **Some residential homes located in the Local Government Area have been identified as containing Loose Fill Asbestos Insulation (LFAI) , for example in the roof space**
- **NSW Fair Trading maintains a Register of these homes that are affected by Loose Fill Asbestos Insulation. This register can be found on NSW Fair Trading's website -** http://www.fairtrading.nsw.gov.au/ftw/Tenants_and_home_owners/Loose_fill_asbestos_insulation.page

**You should make your own enquiries as to the age of the buildings on the land to which this certificate relates to confirm the status of the property.**

## Sec: 21 Affected building notices and building product rectification orders

1) A statement of whether there is any affected building notice of which the council is aware that is in force in respect of the land.
**NO**

2) A statement of:
(a) whether there is any building product rectification order of which the council is aware that is in force in respect of the land and has not been fully complied with, and
**NO**

(b) whether any notice of intention to make a building product rectification order of which the council is aware has been given in respect of the land and is outstanding.

**NO**

3) In this clause:
affected building notice has the same meaning as in Part 4 of the Building Products (Safety) Act 2017.
building product rectification order has the same meaning as in the Building Products (Safety) Act 2017.

## Note. The following matters are prescribed by section 59 (2) of the Contaminated Land Management Act 1997 as additional matters to be specified in a planning certificate:

a) That the land to which the certificate relates is significantly contaminated land within the meaning of that Act – if the land (or part of the land) is significantly contaminated land at the date when the certificate is issued,
**NO**

b) That the land to which the certificate relates is subject to a management order within the meaning of that Act – if it is subject to such an order at the date when the certificate is issued,
**NO**



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

c) That the land to which the certificate relates is subject of an approved voluntary management proposal within the meaning of that Act – if it is the subject of such an approved proposal at the date when the certificate is issued,
**NO**

d) That the land to which the certificate relates is subject to an ongoing maintenance order within the meaning of that Act – if it is subject to such an order at the date when the certificate is issued,
**NO**

e) That the land to which the certificate relates is the subject of a site audit statement within the meaning of that Act – if a copy of such a statement has been provided at any time to the local authority issuing the certificate.
**NO**

**Council records do not have sufficient information about the uses (including previous uses) of the land which is the subject of this Section 10.7 certificate. To confirm that the land hasn't been used for a purpose which would be likely to have contaminated the land, parties should make their own enquiries as to whether the land may be contaminated.**

**For further information, please contact the Strategic Planning Department on 9911 3612.**



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

Lane Cove Council
48 Longueville Road, Lane Cove NSW 2066 Tel: 9911 3555 Fax: 9911 3600

## Part 5:
## ADDITIONAL INFORMATION PROVIDED UNDER SECTION 10.7(5) OF THE ACT

The instruments and the plans should be examined in relation to the specific restrictions which may apply to any development which may be proposed.

The land is subject to a Tree Preservation Order, details of which are available at Council's Customer Service Centre.

The Register of Consents may be examined at Council's Customer Service Centre for particulars relating to development consents which may have been issued for the use or development of the land.

Enquiries regarding Arterial Road Reservations and Regional Open Space should be directed to the Roads and Traffic Authority and Department of Planning respectively.

The information provided concerning the Coastal Protection Act, 1979 is only to the extent that the Council has been notified by the Department of Public Works and Services.

**For more information, please contact the Strategic Planning Department on 9911 3555**



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

Lane Cove Council
48 Longueville Road, Lane Cove NSW 2066 Tel: 9911 3555 Fax: 9911 3600

# PLANNING CERTIFICATE

*Under Section10.7 Environmental Planning and Assessment Act, 1979*

**Applicant:**
Jon Lawson
65 Stubbs Streey
Kensington VIC 3031

| | |
|---|---|
| Date of Issue: | 15/08/2018 |
| Council Reference: | 133596 |
| Applicant Reference: | Lane Cove |
| Certificate No: | 1077 |

**Owner(s):** **Lane Cove Council**
**Property address:** **266 Longueville Road LANE COVE NSW 2066**
**Description:** **LOT: 1 DP: 1227921**
**Property Reference:** **21426**

## INFORMATION PROVIDED PURSUANT TO SECTION 10.7(2) & (5) OF THE ACT

**The planning information contained in this certificate applies specifically to the land.**

**Table of Contents**


| Description | Section No. |
|---|---|
| **Part 2: Information for Section 10.7 (2)** | |
| Names of relevant planning instruments and DCP | 1 |
| Zoning, Heritage, Conservation | 2 |
| Zoning & land use under SEPP (Sydney Region Growth Centres) 2006 | 2A |
| Complying Development | 3 |
| Coastal protection | 4 |
| Certain information relating to beaches and coasts | 4A |
| Annual charges: Local Government Act – coastal protection | 4B |
| Mine Subsidence | 5 |
| Road Widening and road realignment | 6 |
| Council and other public hazard risk restriction | 7 |
| Flood related development controls | 7A |
| Land reserved for acquisition | 8 |
| Contributions plans | 9 |
| Biodiversity certified land | 9A |
| Biobanking agreements | 10 |
| Bushfire prone land | 11 |
| Property Vegetation Plans | 12 |
| Orders under Trees (disputes between neighbours) act | 13 |
| Directions under part 3A | 14 |
| Site compatibility certificates and conditions for seniors housing | 15 |
| Site compatibility certificates for infrastructure | 16 |
| Site compatibility certificates and conditions for affordable rental housing | 17 |
| Contaminated Land Management Act 1997s.59(2) | Note |
| | |
| **Part 5:** Additional information for Section 10.7 (5) | Part 5 |




PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

## PART 2:

## Sec: 1 Names of relevant planning instruments and DCP

1) The name of each environmental planning instrument that applies to the carrying out of development on the land.
**Lane Cove Local Environmental Plan 2009 - gazetted on 19 February 2010**

**State Environmental Planning Policy No.19: Bushland in Urban Areas - gazetted 24 October 1986**

**State Environmental Planning Policy No.32: Urban Consolidation (Redevelopment of Urban Land) - gazetted 15 November 1991**

**State Environmental Planning Policy No.55: Remediation of Land - gazetted 28 August 1998**

**State Environmental Planning Policy No.64: Advertising and Signage - gazetted 16 March 2001**

**State Environmental Planning Policy (BASIX) 2004 - gazetted 25 June 2004**

**State Environmental Planning Policy (Housing for seniors or people with a disability) 2004 Amendment No.2 - gazetted 31 March 2004 effective 12 October 2007**

**State Environmental Planning Policy (Temporary Structures and Places of Public Entertainment) - gazetted 28 September 2007**

**State Environmental Planning Policy (Major Projects) 2005 - gazetted 1 August 2005**

**State Environmental Planning Policy (Infrastructure) 2007 - gazetted 21 December 2007; commenced 1 January 2008**

**State Environmental Planning Policy (Exempt & Complying Development Codes) - gazetted 12 December 2008**

2) The name of each proposed environmental planning instrument that will apply to the carrying out of development on the land and that is or has been the subject of community consultations or on public exhibition under the Act (unless the Director-General has notified the council that the making of the proposed instrument has been deferred indefinitely or has not been approved)
**N/A**

3) The name of each development control plan that applies to the carrying out of development on the land.
**Lane Cove Development Control Plan, effective 22 February 2010**

4) In this clause, proposed environmental planning instrument includes a planning proposal for a LEP or draft environmental planning instrument.

## Sec: 2 Zoning and land use under relevant LEPs



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

## The land is zoned: High Density Residential R4

1) **Objectives of zone**
   - To provide for the housing needs of the community within a high density residential environment.
   - To provide a variety of housing types within a high density residential environment.
   - To enable other land uses that provide facilities or services to meet the day to day needs of residents.
   - To provide for a high concentration of housing with good access to transport, services and facilities.
   - To ensure that the existing amenity of residences in the neighbourhood is respected.
   - To avoid the isolation of sites resulting from site amalgamation.
   - To ensure that landscaping is maintained and enhanced as a major element in the residential environment.

2) **Permitted without consent**

   Nil

3) **Permitted with consent**

   Bed and breakfast accommodation; Boarding houses; Child care centres; Community facilities; Exhibition homes; Group homes; Home businesses; Home industries; Hotel or motel accommodation; Multi dwelling housing; Neighbourhood shops; Places of public worship; Residential flat buildings; Respite day care centres; Restaurants or cafes; Roads; Shop top housing; Signage.

4) **Prohibited**

   Any development not specified in item 2 or 3.

5) Whether any development standards applying to the land fix minimum land dimensions for the erection of a dwelling-house on the land and, if so, the minimum land dimensions so fixed:
   **Not Applicable**

6) Whether the land includes or comprises critical habitat:
   **NO**

7) Whether the land is in a conservation area (however described):
   **NO**

8) Whether an item of environmental heritage (however described) is situated on the land:
   **NO**

## Sec: 2A Zoning and land use under State Environmental Planning Policy (Sydney Region Growth Centres) 2006



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

**Not applicable.**

## Sec: 3 Complying development

1) The extent to which the land is on which complying development may be carried out under each of the codes for complying development because of the provisions of clauses 1.17A (1) (c) to (e), (2), (3) and (4) and 1.19 of State Environmental Planning Policy (Exempt and Complying Development Codes) 2008.

2) The extent to which complying development may not be carried out on that land because of the provisions of clauses 1.17A (1)(c) to (e), (2), (3) and (4) and 1.19 of that Policy and the reasons why it may not be carried out under those clauses.

3) If the council does not have sufficient information to ascertain the extent to which complying development may or may not be carried out on the land, a statement that a restriction applies to the land, but it may not apply to all of the land, and that council does not have sufficient information to ascertain the extent to which complying development may or may not be carried out on the land.

**(1) Complying development may not be carried out under the SEPP's General Housing Code on the part of the land indicated in(2). Complying development may be carried out on the land elsewhere under the following Codes (unless the land is excluded elsewhere in this Section 3): Housing Alterations Code, General Development Code, Subdivision Code, Demolition Code and/or Fire Safety Code.**
**(2) Complying development may not be carried out under the SEPP's General Housing Code on the part of the land mapped as within an Environmental Protection area under the LEP. Reason:Envmtl Prtn LEP**

**(3) Not applicable**

## Sec: 4 Coastal Protection

Whether or not the land is affected by the operation of section 38 or 39 of the Coastal Protection Act 1979, but only to the extent that the council has been so notified by the Department of Services, Technology and Administration.

**NO**

## Sec: 4A Certain information relating to beaches and coasts

**Not applicable.**

## Sec: 4B Annual charges under Local Government Act 1993 for coastal protection services that relate to existing coastal protection works

**Not applicable.**

## Sec: 5 Mine subsidence



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

Whether or not the land is proclaimed to be a mine subsidence district within the meaning of section 15 of the *Mine Subsidence Compensation Act 1961*:
**NO**

## Sec: 6 Road widening and road realignment

Whether or not the land is affected by any road widening or road realignment under:

a) Division 2 of Part 3 of the *Roads Act 1993*:
**Not affected by road widening**

b) Any environmental planning instrument:
**NO**

c) Any resolution of the council:
**NO**

## Sec: 7 Council and other public authority policies on hazard risk restrictions

Whether or not the land is affected by a policy:
a) Adopted by the council, or
b) Adopted by any other public authority and notified to the council for the express purpose of its adoption by that authority being referred to in planning certificates issued by the council, that restricts the development of the land because of the likelihood of :-

Land slip:
**NO**

Bushfire:
**See Section 11.**

Tidal inundation:
**NO**

Subsidence:
**NO**

Acid Sulphate soils:
**NO**

## Sec: 7A Flood related development controls information

1) Whether or not development on that land or part of the land for the purposes of swelling houses, dual occupancies, multi dwelling housing or residential flat buildings (not including development for the purposes of group homes or seniors housing) is subject to flood related development controls.
**The Lane Cove Development Control Plan - effective 22 February 2010 - applies**



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

2) Whether or not development on that land or part of the land for any other purpose is subject to flood related development controls.
**The Lane Cove Development Control Plan - effective 22 February 2010 - applies**

**Overland Flow**
**A study is currently being undertaken to determine exact locations subject to overland flow in the Municipality of Lane Cove. Until such time as Council has completed this work, property owners should conduct their own investigations to be satisfied that this property is not affected by overland flow.**

Words and expressions in this clause have the same meanings as in the standard instrument set out in the *Standard Instrument (Local Environmental Plans) Order 2006*.

## Sec: 8 Land reserved for acquisition

Whether or not any environmental planning instrument or proposed environmental planning instrument referred to in clause 1 makes provision in relation to the acquisition of the land by a public authority, as referred to in section 27 of the Act.
**NO**

## Sec: 9 Contributions plans

**Lane Cove Section 94 Contributions Plan.**

## Sec: 9A Biodiversity certified land

**Not applicable.**

## Sec: 10 Biobanking agreements

**Not applicable.**

## Sec: 11 Bushfire prone land

**The land is not identified on the Lane Cove Bushfire Prone Land Map dated 27 May 2016.**

## Sec: 12 Property vegetation plans

**Not applicable.**

## Sec: 13 Orders under Trees (disputes Between Neighbours) Act 2006

Whether an order has been made under the *Trees (Disputes Between Neighbours) Act 2006* to carry out work in relation to a tree on the land (but only if the council has been notified of the order).
**NONE**



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

## Sec: 14 Directions under Part 3A

If there is a direction by the Minister in force under section 75P (2) (c1) of the Act that a provision of an environmental planning instrument prohibiting or restricting the carrying out of a project or a stage of a project on the land under Part 4 of the Act does not have effect, a statement to that effect identifying the provision that does not have effect.
**NONE**

## Sec: 15 Site compatibility certificates and conditions for seniors housing

If the land to which *State Environmental Planning Policy (Housing for Seniors or People with a Disability) 2004* applies:
**A Site Compatibility Certificate for Seniors Housing was issued on 6 July 2017 (and is valid for 24 months from this date) with respect to this land. A copy of the Site Compatibility Certificate can be obtained from the Head Offices of NSW Planning and Environment by contacting 1300 305 695.**

## Sec: 16 Site compatibility certificates for infrastructure

Whether there is a valid site compatibility certificate (infrastructure), of which the council is aware, in respect of proposed development on the land.
**NO**

## Sec: 17 Site compatibility certificates and conditions for affordable rental housing

Whether there is a current site compatibility certificate (affordable rental housing), of which the council is aware, in respect of proposed development on the land:
**NO**

## Sec: 18 Paper Subdivision Information

1) The name of any development plan adopted by a relevant authority that applies to the land or that is proposed to be subject to a consent ballot.
**Not applicable**

2) The date of an subdivision order that applies to the land.
**Not applicable**

3) Words and expressions used in this clause have the same meaning as they have in Part 16C of this Regulation.

## Sec: 19 Site verification certificates

**Not applicable**



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

## Sec: 20 Loose-fill asbestos insulation

If the land includes any residential premises (within the meaning of Division 1A of Part 8 of the Home Building Act 1989) that are listed on the register that is required to be maintained under that Division, a statement to that effect.

- **Some residential homes located in the Local Government Area have been identified as containing Loose Fill Asbestos Insulation (LFAI) , for example in the roof space**
- **NSW Fair Trading maintains a Register of these homes that are affected by Loose Fill Asbestos Insulation. This register can be found on NSW Fair Trading's website -** http://www.fairtrading.nsw.gov.au/ftw/Tenants_and_home_owners/Loose_fill_asbestos_insulation.page

**You should make your own enquiries as to the age of the buildings on the land to which this certificate relates to confirm the status of the property.**

## Sec: 21 Affected building notices and building product rectification orders

1) A statement of whether there is any affected building notice of which the council is aware that is in force in respect of the land.
**NO**

2) A statement of:
(a) whether there is any building product rectification order of which the council is aware that is in force in respect of the land and has not been fully complied with, and
**NO**

(b) whether any notice of intention to make a building product rectification order of which the council is aware has been given in respect of the land and is outstanding.

**NO**

3) In this clause:
affected building notice has the same meaning as in Part 4 of the Building Products (Safety) Act 2017.
building product rectification order has the same meaning as in the Building Products (Safety) Act 2017.

## Note. The following matters are prescribed by section 59 (2) of the Contaminated Land Management Act 1997 as additional matters to be specified in a planning certificate:

a) That the land to which the certificate relates is significantly contaminated land within the meaning of that Act – if the land (or part of the land) is significantly contaminated land at the date when the certificate is issued,
**NO**

b) That the land to which the certificate relates is subject to a management order within the meaning of that Act – if it is subject to such an order at the date when the certificate is issued,
**NO**



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

c) That the land to which the certificate relates is subject of an approved voluntary management proposal within the meaning of that Act – if it is the subject of such an approved proposal at the date when the certificate is issued,
**NO**

d) That the land to which the certificate relates is subject to an ongoing maintenance order within the meaning of that Act – if it is subject to such an order at the date when the certificate is issued,
**NO**

e) That the land to which the certificate relates is the subject of a site audit statement within the meaning of that Act – if a copy of such a statement has been provided at any time to the local authority issuing the certificate.
**NO**

**Council records do not have sufficient information about the uses (including previous uses) of the land which is the subject of this Section 10.7 certificate. To confirm that the land hasn't been used for a purpose which would be likely to have contaminated the land, parties should make their own enquiries as to whether the land may be contaminated.**

**For further information, please contact the Strategic Planning Department on 9911 3612.**



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

Lane Cove Council
48 Longueville Road Lane Cove NSW 2066 Tel: 9911 3555 Fax: 9911 3600

## Part 5:
## ADDITIONAL INFORMATION PROVIDED UNDER SECTION 10.7(5) OF THE ACT

The instruments and the plans should be examined in relation to the specific restrictions which may apply to any development which may be proposed.

The land is subject to a Tree Preservation Order, details of which are available at Council's Customer Service Centre.

The Register of Consents may be examined at Council's Customer Service Centre for particulars relating to development consents which may have been issued for the use or development of the land.

Enquiries regarding Arterial Road Reservations and Regional Open Space should be directed to the Roads and Traffic Authority and Department of Planning respectively.

The information provided concerning the Coastal Protection Act, 1979 is only to the extent that the Council has been notified by the Department of Public Works and Services.

**For more information, please contact the Strategic Planning Department on 9911 3555**



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

Lane Cove Council
48 Longueville Road Lane Cove NSW 2066 Tel: 9911 3555 Fax: 9911 3600

# PLANNING CERTIFICATE

*Under Section10.7 Environmental Planning and Assessment Act, 1979*

**Applicant:**
Jon Lawson
65 Stubbs Streey
Kensington VIC 3031

| | |
|---|---|
| Date of Issue: | 15/08/2018 |
| Council Reference: | 133596 |
| Applicant Reference: | Lane Cove |
| Certificate No: | 1078 |

**Owner(s):** **Lane Cove Council**
**Property address:** **266 Longueville Road LANE COVE NSW 2066**
**Description:** **LOT: 2 DP: 1227921**
**Property Reference:** **21427**

**INFORMATION PROVIDED PURSUANT TO SECTION 10.7(2) & (5) OF THE ACT**

**The planning information contained in this certificate applies specifically to the land.**

**Table of Contents**


| Description | Section No. |
|---|---|
| **Part 2: Information for Section 10.7 (2)** | |
| Names of relevant planning instruments and DCP | 1 |
| Zoning, Heritage, Conservation | 2 |
| Zoning & land use under SEPP (Sydney Region Growth Centres) 2006 | 2A |
| Complying Development | 3 |
| Coastal protection | 4 |
| Certain information relating to beaches and coasts | 4A |
| Annual charges: Local Government Act – coastal protection | 4B |
| Mine Subsidence | 5 |
| Road Widening and road realignment | 6 |
| Council and other public hazard risk restriction | 7 |
| Flood related development controls | 7A |
| Land reserved for acquisition | 8 |
| Contributions plans | 9 |
| Biodiversity certified land | 9A |
| Biobanking agreements | 10 |
| Bushfire prone land | 11 |
| Property Vegetation Plans | 12 |
| Orders under Trees (disputes between neighbours) act | 13 |
| Directions under part 3A | 14 |
| Site compatibility certificates and conditions for seniors housing | 15 |
| Site compatibility certificates for infrastructure | 16 |
| Site compatibility certificates and conditions for affordable rental housing | 17 |
| Contaminated Land Management Act 1997s.59(2) | Note |
| | |
| **Part 5:** Additional information for Section 10.7 (5) | Part 5 |




PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

## PART 2:

## Sec: 1 Names of relevant planning instruments and DCP

1) The name of each environmental planning instrument that applies to the carrying out of development on the land.
**Lane Cove Local Environmental Plan 2009 - gazetted on 19 February 2010**

**State Environmental Planning Policy No.19: Bushland in Urban Areas - gazetted 24 October 1986**

**State Environmental Planning Policy No.32: Urban Consolidation (Redevelopment of Urban Land) - gazetted 15 November 1991**

**State Environmental Planning Policy No.55: Remediation of Land - gazetted 28 August 1998**

**State Environmental Planning Policy No.64: Advertising and Signage - gazetted 16 March 2001**

**State Environmental Planning Policy (BASIX) 2004 - gazetted 25 June 2004**

**State Environmental Planning Policy (Housing for seniors or people with a disability) 2004 Amendment No.2 - gazetted 31 March 2004 effective 12 October 2007**

**State Environmental Planning Policy (Temporary Structures and Places of Public Entertainment) - gazetted 28 September 2007**

**State Environmental Planning Policy (Major Projects) 2005 - gazetted 1 August 2005**

**State Environmental Planning Policy (Infrastructure) 2007 - gazetted 21 December 2007; commenced 1 January 2008**

**State Environmental Planning Policy (Exempt & Complying Development Codes) - gazetted 12 December 2008**

2) The name of each proposed environmental planning instrument that will apply to the carrying out of development on the land and that is or has been the subject of community consultations or on public exhibition under the Act (unless the Director-General has notified the council that the making of the proposed instrument has been deferred indefinitely or has not been approved)
**N/A**

3) The name of each development control plan that applies to the carrying out of development on the land.
**Lane Cove Development Control Plan, effective 22 February 2010**

4) In this clause, proposed environmental planning instrument includes a planning proposal for a LEP or draft environmental planning instrument.

## Sec: 2 Zoning and land use under relevant LEPs



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

## The land is zoned: High Density Residential R4

1) **Objectives of zone**
   - To provide for the housing needs of the community within a high density residential environment.
   - To provide a variety of housing types within a high density residential environment.
   - To enable other land uses that provide facilities or services to meet the day to day needs of residents.
   - To provide for a high concentration of housing with good access to transport, services and facilities.
   - To ensure that the existing amenity of residences in the neighbourhood is respected.
   - To avoid the isolation of sites resulting from site amalgamation.
   - To ensure that landscaping is maintained and enhanced as a major element in the residential environment.

2) **Permitted without consent**

   Nil

3) **Permitted with consent**

   Bed and breakfast accommodation; Boarding houses; Child care centres; Community facilities; Exhibition homes; Group homes; Home businesses; Home industries; Hotel or motel accommodation; Multi dwelling housing; Neighbourhood shops; Places of public worship; Residential flat buildings; Respite day care centres; Restaurants or cafes; Roads; Shop top housing; Signage.

4) **Prohibited**

   Any development not specified in item 2 or 3.

5) Whether any development standards applying to the land fix minimum land dimensions for the erection of a dwelling-house on the land and, if so, the minimum land dimensions so fixed:
   **Not Applicable**

6) Whether the land includes or comprises critical habitat:
   **NO**

7) Whether the land is in a conservation area (however described):
   **NO**

8) Whether an item of environmental heritage (however described) is situated on the land:
   **NO**

## Sec: 2A Zoning and land use under State Environmental Planning Policy (Sydney Region Growth Centres) 2006



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

**Not applicable.**

## Sec: 3 Complying development

1) The extent to which the land is on which complying development may be carried out under each of the codes for complying development because of the provisions of clauses 1.17A (1) (c) to (e), (2), (3) and (4) and 1.19 of State Environmental Planning Policy (Exempt and Complying Development Codes) 2008.

2) The extent to which complying development may not be carried out on that land because of the provisions of clauses 1.17A (1)(c) to (e), (2), (3) and (4) and 1.19 of that Policy and the reasons why it may not be carried out under those clauses.

3) If the council does not have sufficient information to ascertain the extent to which complying development may or may not be carried out on the land, a statement that a restriction applies to the land, but it may not apply to all of the land, and that council does not have sufficient information to ascertain the extent to which complying development may or may not be carried out on the land.

**(1) Complying development may be carried out on the land as a whole under the SEPP in accordance with the following Codes (unless the land is excluded elsewhere in this Section):- General Housing Code, Housing Alterations Code, General Development Code, Subdivision Code, Demolition Code and/or Fire Safety Code.**

**(2) Not applicable.**
**PLEASE NOTE: All of the provisions of the Low Rise Medium Density Housing Code have been deferred from the Lane Cove Local Government Area**

**(3) Not applicable**

## Sec: 4 Coastal Protection

Whether or not the land is affected by the operation of section 38 or 39 of the Coastal Protection Act 1979, but only to the extent that the council has been so notified by the Department of Services, Technology and Administration.

**NO**

## Sec: 4A Certain information relating to beaches and coasts

**Not applicable.**

## Sec: 4B Annual charges under Local Government Act 1993 for coastal protection services that relate to existing coastal protection works

**Not applicable.**

## Sec: 5 Mine subsidence



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

Whether or not the land is proclaimed to be a mine subsidence district within the meaning of section 15 of the *Mine Subsidence Compensation Act 1961*:
**NO**

## Sec: 6 Road widening and road realignment

Whether or not the land is affected by any road widening or road realignment under:

a) Division 2 of Part 3 of the *Roads Act 1993*:
**Not affected by road widening**

b) Any environmental planning instrument:
**NO**

c) Any resolution of the council:
**NO**

## Sec: 7 Council and other public authority policies on hazard risk restrictions

Whether or not the land is affected by a policy:
a) Adopted by the council, or
b) Adopted by any other public authority and notified to the council for the express purpose of its adoption by that authority being referred to in planning certificates issued by the council, that restricts the development of the land because of the likelihood of :-

Land slip:
**NO**

Bushfire:
**See Section 11.**

Tidal inundation:
**NO**

Subsidence:
**NO**

Acid Sulphate soils:
**NO**

## Sec: 7A Flood related development controls information

1) Whether or not development on that land or part of the land for the purposes of swelling houses, dual occupancies, multi dwelling housing or residential flat buildings (not including development for the purposes of group homes or seniors housing) is subject to flood related development controls.
**The Lane Cove Development Control Plan - effective 22 February 2010 - applies**



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

2) Whether or not development on that land or part of the land for any other purpose is subject to flood related development controls.
**The Lane Cove Development Control Plan - effective 22 February 2010 - applies**

**Overland Flow**
**A study is currently being undertaken to determine exact locations subject to overland flow in the Municipality of Lane Cove. Until such time as Council has completed this work, property owners should conduct their own investigations to be satisfied that this property is not affected by overland flow.**

Words and expressions in this clause have the same meanings as in the standard instrument set out in the *Standard Instrument (Local Environmental Plans) Order 2006*.

## Sec: 8 Land reserved for acquisition

Whether or not any environmental planning instrument or proposed environmental planning instrument referred to in clause 1 makes provision in relation to the acquisition of the land by a public authority, as referred to in section 27 of the Act.
**NO**

## Sec: 9 Contributions plans

**Lane Cove Section 94 Contributions Plan.**

## Sec: 9A Biodiversity certified land

**Not applicable.**

## Sec: 10 Biobanking agreements

**Not applicable.**

## Sec: 11 Bushfire prone land

**The land is not identified on the Lane Cove Bushfire Prone Land Map dated 27 May 2016.**

## Sec: 12 Property vegetation plans

**Not applicable.**

## Sec: 13 Orders under Trees (disputes Between Neighbours) Act 2006

Whether an order has been made under the *Trees (Disputes Between Neighbours) Act 2006* to carry out work in relation to a tree on the land (but only if the council has been notified of the order).
**NONE**



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

## Sec: 14 Directions under Part 3A

If there is a direction by the Minister in force under section 75P (2) (c1) of the Act that a provision of an environmental planning instrument prohibiting or restricting the carrying out of a project or a stage of a project on the land under Part 4 of the Act does not have effect, a statement to that effect identifying the provision that does not have effect.
**NONE**

## Sec: 15 Site compatibility certificates and conditions for seniors housing

If the land to which *State Environmental Planning Policy (Housing for Seniors or People with a Disability) 2004* applies:
**A Site Compatibility Certificate for Seniors Housing was issued on 6 July 2017 (and is valid for 24 months from this date) with respect to this land. A copy of the Site Compatibility Certificate can be obtained from the Head Offices of NSW Planning and Environment by contacting 1300 305 695.**

## Sec: 16 Site compatibility certificates for infrastructure

Whether there is a valid site compatibility certificate (infrastructure), of which the council is aware, in respect of proposed development on the land.
**NO**

## Sec: 17 Site compatibility certificates and conditions for affordable rental housing

Whether there is a current site compatibility certificate (affordable rental housing), of which the council is aware, in respect of proposed development on the land:
**NO**

## Sec: 18 Paper Subdivision Information

1) The name of any development plan adopted by a relevant authority that applies to the land or that is proposed to be subject to a consent ballot.
**Not applicable**

2) The date of an subdivision order that applies to the land.
**Not applicable**

3) Words and expressions used in this clause have the same meaning as they have in Part 16C of this Regulation.

## Sec: 19 Site verification certificates

**Not applicable**



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

## Sec: 20 Loose-fill asbestos insulation

If the land includes any residential premises (within the meaning of Division 1A of Part 8 of the Home Building Act 1989) that are listed on the register that is required to be maintained under that Division, a statement to that effect.

- **Some residential homes located in the Local Government Area have been identified as containing Loose Fill Asbestos Insulation (LFAI) , for example in the roof space**
- **NSW Fair Trading maintains a Register of these homes that are affected by Loose Fill Asbestos Insulation. This register can be found on NSW Fair Trading's website -** http://www.fairtrading.nsw.gov.au/ftw/Tenants_and_home_owners/Loose_fill_asbestos_insulation.page

**You should make your own enquiries as to the age of the buildings on the land to which this certificate relates to confirm the status of the property.**

## Sec: 21 Affected building notices and building product rectification orders

1) A statement of whether there is any affected building notice of which the council is aware that is in force in respect of the land.
**NO**

2) A statement of:
(a) whether there is any building product rectification order of which the council is aware that is in force in respect of the land and has not been fully complied with, and
**NO**

(b) whether any notice of intention to make a building product rectification order of which the council is aware has been given in respect of the land and is outstanding.

**NO**

3) In this clause:
affected building notice has the same meaning as in Part 4 of the Building Products (Safety) Act 2017.
building product rectification order has the same meaning as in the Building Products (Safety) Act 2017.

## Note. The following matters are prescribed by section 59 (2) of the Contaminated Land Management Act 1997 as additional matters to be specified in a planning certificate:

a) That the land to which the certificate relates is significantly contaminated land within the meaning of that Act – if the land (or part of the land) is significantly contaminated land at the date when the certificate is issued,
**NO**

b) That the land to which the certificate relates is subject to a management order within the meaning of that Act – if it is subject to such an order at the date when the certificate is issued,
**NO**



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

c) That the land to which the certificate relates is subject of an approved voluntary management proposal within the meaning of that Act – if it is the subject of such an approved proposal at the date when the certificate is issued,
**NO**

d) That the land to which the certificate relates is subject to an ongoing maintenance order within the meaning of that Act – if it is subject to such an order at the date when the certificate is issued,
**NO**

e) That the land to which the certificate relates is the subject of a site audit statement within the meaning of that Act – if a copy of such a statement has been provided at any time to the local authority issuing the certificate.
**NO**

**Council records do not have sufficient information about the uses (including previous uses) of the land which is the subject of this Section 10.7 certificate. To confirm that the land hasn't been used for a purpose which would be likely to have contaminated the land, parties should make their own enquiries as to whether the land may be contaminated.**

**For further information, please contact the Strategic Planning Department on 9911 3612.**



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

## Part 5:
## ADDITIONAL INFORMATION PROVIDED UNDER SECTION 10.7(5) OF THE ACT

The instruments and the plans should be examined in relation to the specific restrictions which may apply to any development which may be proposed.

The land is subject to a Tree Preservation Order, details of which are available at Council's Customer Service Centre.

The Register of Consents may be examined at Council's Customer Service Centre for particulars relating to development consents which may have been issued for the use or development of the land.

Enquiries regarding Arterial Road Reservations and Regional Open Space should be directed to the Roads and Traffic Authority and Department of Planning respectively.

The information provided concerning the Coastal Protection Act, 1979 is only to the extent that the Council has been notified by the Department of Public Works and Services.

**For more information, please contact the Strategic Planning Department on 9911 3555**



PO Box 20 Lane Cove NSW 1595, Lane Cove
Email - service@lanecove.nsw.gov.au • Website - www.lanecove.nsw.gov.au • ABN 42 062 211 626

WorkCover NSW
92-100 Donnison Street, Gosford, NSW 2250
Locked Bag 2906, Lisarow, NSW 2252
T 02 4321 5000 F 02 4325 4145
WorkCover Assistance Service 13 10 50
DX 731 Sydney workcover.nsw.gov.au

Our Ref: D11/147592
Your Ref: David Yonge

23 November 2011

Attention: David Yonge
SMEC Testing Services Pty Ltd
PO BOX 6989
Wetherill Park NSW 2164

Dear Mr Yonge,

**RE SITE: 266 Longueville Rd Lane Cove NSW 2066**

I refer to your site search request received by WorkCover NSW on 21November 2011 requesting information on licences to keep dangerous goods for the above site.

A search of the Stored Chemical Information Database (SCID) and the microfiche records held by WorkCover NSW has not located any records pertaining to the above mentioned premises.

If you have any further queries please contact the Dangerous Goods Licensing Team on (02) 4321 5500.

Yours Sincerely

Brent Jones
Senior Licensing Officer
Dangerous Goods Team

# Aerial Imagery 2014

**266 Longueville Road, Lane Cove, NSW 2066**




| Scale: 0 25 50 100 Meters | Data Sources:Aerial Imagery © Land and Property Information (a division of the Department of Finance and Services) | Coordinate System: GDA 1994 MGA Zone 56 | Date: 20June 2017 |
|---|---|---|---|

# Aerial Imagery 2009

**266 Longueville Road, Lane Cove, NSW 2066**




Scale:
0 25 50 100
Meters

Data Sources: Aerial Imagery © 2017 Google Inc, used with permission. Google and the Google logo are registered trademarks of Google Inc.

Coordinate System:
GDA 1994 MGA Zone 56

Date: 15 June 2017

# Aerial Imagery 2002

**266 Longueville Road, Lane Cove, NSW 2066**





Data Sources: Aerial Imagery © 2017 Google Inc, used with permission. Google and the Google logo are registered trademarks of Google Inc.

Coordinate System: GDA 1994 MGA Zone 56

Date: 15 June 2017

# Aerial Imagery 1991

**266 Longueville Road, Lane Cove, NSW 2066**





Data Sources: Historical Aerials: © Land and Property Information (a division of the Department of Finance and Services)

Coordinate System: GDA 1994 MGA Zone 56

Date: 15 June, 2017


# Aerial Imagery 1982

**266 Longueville Road, Lane Cove, NSW 2066**



# Aerial Imagery 1970

**266 Longueville Road, Lane Cove, NSW 2066**





Data Sources: Historical Aerials: © Land and Property Information (a division of the Department of Finance and Services)

Coordinate System: GDA 1994 MGA Zone 56

Date: 15 June, 2017

# Aerial Imagery 1965

**266 Longueville Road, Lane Cove, NSW 2066**




Data Sources: Historical Aerials: © Land and Property Information (a division of the Department of Finance and Services)

Coordinate System: GDA 1994 MGA Zone 56

Date: 15 June, 2017

# Aerial Imagery 1961

**266 Longueville Road, Lane Cove, NSW 2066**





Data Sources: Historical Aerials: © Land and Property Information (a division of the Department of Finance and Services)

Coordinate System: GDA 1994 MGA Zone 56

Date: 15 June, 2017

# Aerial Imagery 1955

**266 Longueville Road, Lane Cove, NSW 2066**



# Aerial Imagery 1951

**266 Longueville Road, Lane Cove, NSW 2066**





Data Sources: Historical Aerials: © Land and Property Information (a division of the Department of Finance and Services)

Coordinate System: GDA 1994 MGA Zone 56

Date: 15 June, 2017

# Aerial Imagery 1943

**266 Longueville Road, Lane Cove, NSW 2066**




Scale: 0 25 50 100 Meters

Data Sources:Aerial Imagery © Land and Property Information (a division of the Department of Finance and Services)

Coordinate System: GDA 1994 MGA Zone 56

Date: 20June 2017


Land & Property Information

# Cadastral Records Enquiry Report

**Ref :** lotsearch - longueville

**Requested Parcel :** Lot 1 DP 1227921 **Identified Parcel :** Lot 1 DP 1227921

**Locality :** LANE COVE **LGA :** LANE COVE **Parish :** WILLOUGHBY **County :** CUMBERLAND






Copyright © Land and Property Information ABN: 23 519 493 925

**This information is provided as a searching aid only. While every endeavour is made to ensure the current cadastral pattern is accurately reflected, the Registrar General cannot guarantee the information provided. For all ACTIVITY PRIOR to SEPT 2002 you must refer to the RGs Charting and Reference Maps.**

| | Status | Surv/Comp | Purpose |
|---|---|---|---|
| DP321048 | | | |
| Lot(s): 4 | | | |
| DP1064002 | REGISTERED | SURVEY | SURVEY INFORMATION ONLY |
| DP1017134 | | | |
| Lot(s): 1, 2 | | | |
| DP380914 | HISTORICAL | SURVEY | UNRESEARCHED |
| DP1127778 | | | |
| Lot(s): 100 | | | |
| DP450210 | HISTORICAL | SURVEY | UNRESEARCHED |
| DP1227921 | | | |
| Lot(s): 1, 3 | | | |
| DP1102537 | HISTORICAL | COMPILATION | DEPARTMENTAL |
| Lot(s): 2, 3 | | | |
| DP91655 | HISTORICAL | COMPILATION | UNRESEARCHED |
| SP63447 | | | |
| DP1017844 | HISTORICAL | SURVEY | REDEFINITION |
| SP64478 | | | |
| DP4373 | HISTORICAL | SURVEY | UNRESEARCHED |
| DP174177 | HISTORICAL | COMPILATION | UNRESEARCHED |
| DP397152 | HISTORICAL | SURVEY | UNRESEARCHED |
| DP1021521 | REGISTERED | SURVEY | CONSOLIDATION |
| Road | | | |
| Polygon Id(s): 105004805 | | | |
| NSW GAZ. 07-09-2012 DEDICATED PUBLIC ROAD | | | Folio : 3930 |


Copyright © Land and Property Information ABN: 23 519 493 925

**Requested Parcel :** Lot 1 DP 1227921 **Identified Parcel :** Lot 1 DP 1227921

**Locality :** LANE COVE **LGA :** LANE COVE **Parish :** WILLOUGHBY **County :** CUMBERLAND

| Plan | Surv/Comp | Purpose |
|---|---|---|
| DP4373 | SURVEY | UNRESEARCHED |
| DP4454 | SURVEY | UNRESEARCHED |
| DP5817 | SURVEY | UNRESEARCHED |
| DP8423 | SURVEY | UNRESEARCHED |
| DP9728 | SURVEY | UNRESEARCHED |
| DP9870 | SURVEY | UNRESEARCHED |
| DP10679 | SURVEY | UNRESEARCHED |
| DP13276 | SURVEY | UNRESEARCHED |
| DP20884 | SURVEY | UNRESEARCHED |
| DP100900 | COMPILATION | UNRESEARCHED |
| DP105994 | SURVEY | UNRESEARCHED |
| DP115668 | COMPILATION | DEPARTMENTAL |
| DP165253 | COMPILATION | UNRESEARCHED |
| DP172784 | SURVEY | UNRESEARCHED |
| DP184281 | COMPILATION | UNRESEARCHED |
| DP224455 | SURVEY | SUBDIVISION |
| DP302498 | COMPILATION | UNRESEARCHED |
| DP307899 | SURVEY | UNRESEARCHED |
| DP316446 | COMPILATION | UNRESEARCHED |
| DP321048 | SURVEY | UNRESEARCHED |
| DP321353 | SURVEY | UNRESEARCHED |
| DP346706 | COMPILATION | UNRESEARCHED |
| DP354660 | COMPILATION | UNRESEARCHED |
| DP363547 | COMPILATION | UNRESEARCHED |
| DP363548 | COMPILATION | UNRESEARCHED |
| DP380914 | SURVEY | UNRESEARCHED |
| DP445348 | COMPILATION | UNRESEARCHED |
| DP517993 | SURVEY | SUBDIVISION |
| DP555414 | SURVEY | SUBDIVISION |
| DP663462 | COMPILATION | DEPARTMENTAL |
| DP668028 | COMPILATION | DEPARTMENTAL |
| DP816151 | SURVEY | CONSOLIDATION |
| DP857133 | SURVEY | SUBDIVISION |
| DP907301 | COMPILATION | UNRESEARCHED |
| DP917402 | COMPILATION | UNRESEARCHED |
| DP917813 | COMPILATION | UNRESEARCHED |
| DP942108 | SURVEY | UNRESEARCHED |
| DP948555 | COMPILATION | UNRESEARCHED |
| DP948556 | COMPILATION | UNRESEARCHED |
| DP1017134 | SURVEY | SUBDIVISION |
| DP1111781 | COMPILATION | DEPARTMENTAL |
| DP1127778 | SURVEY | REDEFINITION |
| DP1227921 | SURVEY | SUBDIVISION |
| DP1227921 | UNRESEARCHED | SUBDIVISION |
| SP5383 | COMPILATION | STRATA PLAN |
| SP7419 | COMPILATION | STRATA PLAN |
| SP52592 | COMPILATION | STRATA PLAN |
| SP63447 | COMPILATION | STRATA PLAN |
| SP64478 | COMPILATION | STRATA PLAN |


Copyright © Land and Property Information ABN: 23 519 493 925

Req:R009743 /Doc:DP 0321353 P /Rev:31-Oct-2000 /Sts:OK.OK /Pgs:ALL /Prt:12-Jul-2017 12:25 /Seq:1 of 1
Ref:als /Src:T

B719892

F.P.321353 (E)

Plan Form No 6 (for transfers leases etc)

Municipality of Lane Cove.
Shire of

M. M.

# PLAN

of survey of part of land comprised in C.T. Vol, 3098 Folio, 92.

*Parish of Willoughby County of Cumberland*


Scale 100 Feet to an Inch.

CONVERSION TABLE ADDED IN DEPARTMENT OF LANDS

DP 321353

| FEET | INCHES | METRES |
|---|---|---|
| 6 | 7 1/4 | 2.013 |
| 10 | - | 3.048 |
| 56 | 7 1/4 | 17.253 |
| 66 | - | 20.117 |
| 67 | 7 1/2 | 20.612 |
| 67 | 9 1/2 | 20.663 |
| 68 | 2 | 20.777 |
| 70 | 7 1/2 | 21.527 |
| 90 | 3 1/4 | 27.515 |
| 90 | 9 1/4 | 27.667 |
| 97 | 0 1/2 | 29.578 |
| 100 | - | 30.480 |
| 100 | 9 | 30.709 |
| 117 | 10 | 35.916 |
| 126 | - | 38.405 |
| 150 | - | 45.720 |
| 237 | 11 | 72.517 |

| AC | RD | P | SQ M |
|---|---|---|---|
| - | 1 | 24.3 | 1626 |




Appl^n 8509.

M P S (R.P.) 21353

There are no easements created in favour of the purchaser of the lot shown and there are no restrictions affecting the user of the said land stipulated for by the vendor.

E. J. Maidenpall

Transferor

No 416 of 12-7-28

J. Mc Lister

◎ G.I. Pipes inserted on boundary lines 10 links from corners.

I, Robert James Rain of Sydney

Licensed Surveyor specially licensed under the Real Property Act, 1900, do hereby solemnly and sincerely declare (a) that all boundaries and measurements shown on this plan are correct, (b) that all survey marks found and relevant physical objects on or adjacent to the boundaries are correctly represented, (c) that all physical objects indicated actually exist in the positions shown, (d) that the whole of the material facts in relation to the land are correctly represented, (e) that the survey has been made * by me , and I make this solemn declaration conscientiously believing the same to be true, and by virtue of the provisions of the Oaths Act, 1900.

Subscribed and declared before me at Sydney this 12th day of April A.D. 1928

Field Book 4476 f

Datum line of Azimuth A.B.

H K Drummond J.P.

R.J. Rain Licensed Surveyor

Date of Survey April 1928.

* Here add by me or under my immediate supervision as the case may be

19/9/28


This is the plan marked "" referred to in Memorandum of Transfer

Dated 26th June 1928

E. J. Maidenpall Transferor

Signatures of parties to be made in this margin.

Solicitor General for Transferee




Req:R009738 /Doc:DP 1227921 P /Rev:23-Mar-2017 /Sts:SC.OK /Pgs:ALL /Prt:12-Jul-2017 12:25 /Seq:1 of 3
Ref:als /Src:E
DP1227921
CAD REF Z:\257-11\CR_P_LANS257-11G SU [08] - K S - D.S.

PLAN FORM 6 (2013) WARNING: Creasing or folding will lead to rejection ePlan

# DEPOSITED PLAN ADMINISTRATION SHEET

Sheet 1 of 2 sheet(s)

Office Use Only

Registered: 21.3.2017

Title System: TORRENS

Purpose: SUBDIVISION

Office Use Only

# DP1227921

PLAN OF
SUBDIVISION OF LOT 322 D.P.1102537 &
LOT 1 D.P.91655

LGA: LANE COVE

Locality: LANE COVE

Parish: WILLOUGHBY

County: CUMBERLAND

## Crown Lands NSW/Western Lands Office Approval

I, ..... (Authorised Officer) in approving this plan certify that all necessary approvals in regard to the allocation of the land shown herein have been given.

Signature: .....

Date: .....

File Number: .....

Office: .....

## Subdivision Certificate

I, Michael Mason

*Authorised Person/~~*General Manager~~/~~*Accredited Certifier~~, certify that the provisions of s.109J of the *Environmental Planning and Assessment Act 1979* have been satisfied in relation to the proposed subdivision, new road or reserve set out herein.

Signature: .....

Accreditation number: –

Consent Authority: Lane Cove Council

Date of endorsement: 19/12/2016

Subdivision Certificate number: 3093

File number: –

*Strike through inapplicable parts.

## Survey Certificate

I, MATTHEW JAMES COOPER

of CRAIG & RHODES PTY LTD

a surveyor registered under the *Surveying and Spatial Information Act 2002*, certify that:

*(a) The land shown in the plan was surveyed in accordance with the *Surveying and Spatial Information Regulation 2012*, is accurate and the survey was completed on 16 DECEMBER 2016

~~*(b) The part of the land shown in the plan(*being/*excluding ^.....~~
~~.....)~~
~~was surveyed in accordance with the *Surveying and Spatial Information Regulation 2012*, is accurate and the survey was completed on, ..... the part not surveyed was compiled in accordance with that regulation.~~

~~*(c) The land shown in the plan was compiled in accordance with the *Surveying and Spatial Information Regulation 2012*.~~

Signature ..... Dated: 19/12/16

Surveyor ID: 8834

Datum Line: 'X' - 'Y'

Type: *Urban/~~*Rural~~

The Terrain is ~~*Level-Undulating~~/ *Steep-Mountainous

*Strike through if inapplicable.
^Specify the land actually surveyed or specify and land shown in the plan that is not the subject of the survey.

Statements of intention to dedicate public roads create public reserves and drainage reserves, acquire/resume land.

It is intended to dedicate Lot 3 as a public reserve

Plans used in the preparation of survey/~~compilation~~

| | | |
|---|---|---|
| D.P.2380 | D.P.307899 | D.P.1017134 |
| D.P.3886 | D.P.321048 | D.P.1021521 |
| D.P.4454 | D.P.321353 | D.P.1102537 |
| D.P.8423 | D.P.370042 | D.P.1127778 |
| D.P.9728 | D.P.380914 | C.P.14-2005 |
| D.P.13276 | D.P.397152 | |
| D.P.20884 | D.P.534692 | |
| D.P.58509 | D.P.539383 | |
| D.P.91655 | D.P.816151 | |
| D.P.224455 | D.P.857133 | |

If space is insufficient continue on PLAN FORM 6A

Signatures, Seals and Section 88B Statements should appear on PLAN FORM 6A

Surveyor's Reference: 257-11

CAD REF: Z:\257-11\CR_PLANS\257-11G S01 [04] - K.S. - D.S.

PLAN FORM 6A (2012) WARNING: **Creasing or folding will lead to rejection** ePlan

# DEPOSITED PLAN ADMINISTRATION SHEET

Sheet 2 of 2 sheet(s)

Office Use Only

Registered: 21.3.2017

Office Use Only

# DP1227921

PLAN OF
SUBDIVISION OF LOT 322 D.P.1102537 &
LOT 1 D.P.91655

This sheet is for the provision of the following information as required:

- A schedule of lots and addresses - See 60(c) *SSI Regulation 2012*
- Statements of intention to create and release affecting interests in accordance with section 88B *Conveyancing Act 1919*
- Signatures and seals - see 195D *Conveyancing Act 1919*
- Any information which cannot fit in the appropriate panel of sheet 1 of the administration sheets.

Subdivision Certificate number: 3093

Date of Endorsement: 19/12/2016

| SURVEYING & SPATIAL INFORMATION REGULATION 2012 CLAUSE 60(c) | | | | |
|---|---|---|---|---|
| SCHEDULE OF LOTS & ADDRESSES | | | | |
| LOT | STREET No. | STREET NAME | STREET TYPE | LOCALITY |
| 1 | 266 | LONGUEVILLE | ROAD | LANE COVE |
| 2 | 266 | LONGUEVILLE | ROAD | LANE COVE |
| 3 | 0 | MCMAHONS | ROAD | LANE COVE |

LANE COVE COUNCIL, BY ITS DELEGATE PURSUANT TO S.377 LOCAL GOVERNMENT ACT 1919

.....
SIGNATURE OF DELEGATE

Michael Mason
NAME OF DELEGATE

I CERTIFY THAT I AM AN ELIGIBLE WITNESS & THAT THE DELEGATE SIGNED IN MY PRESENCE

A Panich
SIGNATURE OF WITNESS

ANGELA PANICH
NAME OF WITNESS

**Angela Elizabeth Panich**
**Justice of the Peace**
**NSW Reg. No. 216459**

4/77-81 BURNS BAY RD, LANE COVE
ADDRESS OF WITNESS

If space is insufficient use additional annexure sheet

Surveyor's Reference: 257-11

CAD REF: Z:\257-11\CR_PLANS\257-11G S01 (04) - K.S. - D.S.

Advance Legal Searchers

**Advance Legal Searchers Pty Ltd hereby certifies that the information contained in this document has been provided electronically by the Registrar General in accordance with Section 96B(2) of the Real Property Act.**

Information provided through Tri-Search an approved LPI*NSW* Information Broker

LAND AND PROPERTY INFORMATION NEW SOUTH WALES - TITLE SEARCH

---

FOLIO: 1/321353

---

| SEARCH DATE | TIME | EDITION NO | DATE |
|---|---|---|---|
| 12/7/2017 | 12:27 PM | 1 | 22/3/2017 |

LAND

---

LOT 1 IN DEPOSITED PLAN 321353
LOCAL GOVERNMENT AREA LANE COVE
PARISH OF WILLOUGHBY COUNTY OF CUMBERLAND
TITLE DIAGRAM DP321353

FIRST SCHEDULE

---

THE COUNCIL OF THE MUNICIPALITY OF LANE COVE (T G835734)

SECOND SCHEDULE (2 NOTIFICATIONS)

---

1 RESERVATIONS AND CONDITIONS IN THE CROWN GRANT(S)
2 AM241830 THIS EDITION ISSUED PURSUANT TO S.111 REAL PROPERTY ACT, 1900

NOTATIONS

---

UNREGISTERED DEALINGS: NIL

*** END OF SEARCH ***



***ANY ENTRIES PRECEDED BY AN ASTERISK DO NOT APPEAR ON THE CURRENT EDITION OF THE CERTIFICATE OF TITLE. WARNING: THE INFORMATION APPEARING UNDER NOTATIONS HAS NOT BEEN FORMALLY RECORDED IN THE REGISTER.***

Advance Legal Searchers

**Advance Legal Searchers Pty Ltd hereby certifies that the information contained in this document has been provided electronically by the Registrar General in accordance with Section 96B(2) of the Real Property Act.**

Information provided through Tri-Search an approved LPI*NSW* Information Broker

LAND AND PROPERTY INFORMATION NEW SOUTH WALES - TITLE SEARCH

---

FOLIO: 1/1227921

---

| SEARCH DATE | TIME | EDITION NO | DATE |
|---|---|---|---|
| 12/7/2017 | 12:26 PM | 1 | 22/3/2017 |

LAND

---

LOT 1 IN DEPOSITED PLAN 1227921
AT LANE COVE
LOCAL GOVERNMENT AREA LANE COVE
PARISH OF WILLOUGHBY COUNTY OF CUMBERLAND
TITLE DIAGRAM DP1227921

FIRST SCHEDULE

---

LANE COVE COUNCIL

SECOND SCHEDULE (1 NOTIFICATION)

---

1 RESERVATIONS AND CONDITIONS IN THE CROWN GRANT(S)

NOTATIONS

---

UNREGISTERED DEALINGS: NIL

*** END OF SEARCH ***



***ANY ENTRIES PRECEDED BY AN ASTERISK DO NOT APPEAR ON THE CURRENT EDITION OF THE CERTIFICATE OF TITLE. WARNING: THE INFORMATION APPEARING UNDER NOTATIONS HAS NOT BEEN FORMALLY RECORDED IN THE REGISTER.***

# APPENDIX C

## FIELD SHEETS & CALIBRATION LOGS

# LRM Borehole Logs (BH16 - BH47)

## BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH16 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** SS | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 0.8 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| **Depth (m)** | **Lithological Symbol** | **SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour)** | **Sample ID** | **PID (ppm)** | **Other Comments** |
| | | Ground Surface | | | |
| 0.0 | | Fill Material: Sandy silt, low plasticity, brown, no odour, dry. | 0.1 | 0.2 | |
| 0.5 | | Natural: Clayey sand, fine to medium grained, orange, no odour, dry. | | | |
| | | Termination @ 0.8m | 0.8 | 0.1 | |
| 1.0 | | End of Investigation | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH17 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** SS | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 0.8 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | Fill Material: Sandy gravel, medium to coarse grained, grey brown, no odou, dry. | 0.1 | 0.2 | |
| 0.5 | | Natural: Sandstone, fine to medium grained, grey orange, no odour, dry. | 0.7 | 0.1 | |
| | | Termination @ 0.8m | | | |
| 1.0 | | End of Investigation | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH18 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** SS | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 0.6 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| **Depth (m)** | **Lithological Symbol** | **SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour)** | **Sample ID** | **PID (ppm)** | **Other Comments** |
| | | Ground Surface | | | |
| 0.0 | | Fill Material:<br>Silty sand, fine to medium grained, brown, with gravels, no odour, dry. | 0.1 | 0.1 | |
| 0.5 | | Natural:<br>Sandstone, fine to medium grained, orange, no odour.<br>Refusal @ 0.6 m | 0.6 | 0.3 | |
| 1.0 | | End of Investigation | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH19 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** SS | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 0.55 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| **Depth (m)** | **Lithological Symbol** | **SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour)** | **Sample ID** | **PID (ppm)** | **Other Comments** |
| | | Ground Surface | | | |
| 0.0 | | Fill Material: Silty sand, fine to medium grained, brown, with gravels, no odour, dry. | 0.1 | 0.4 | |
| | | Natural: Sandstone, fine to medium grained, grey orange, no odour, dry. | | | |
| 0.5 | | Refusal @ 0.55m | 0.5 | 0.0 | |
| | | End of Investigation | | | |
| 1.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH20 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** SS | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 1.9 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | Fill Material: Silty sand, fine to medium grained, brown, with gravels, no odour, dry. | 0.1 | 0.0 | |
| 0.5 | | Fill Material: Gravel, course grained, sub-angular, dark grey, some sand, dry. | | | |
| 1.0 | | Natural: Sandstone, fine to medium grained, grey orange, no odour, dry. | 1.0 | 0.3 | |
| 1.5 | | Termination @ 1.9 m | | | |
| | | End of Investigation | 1.9 | 0.2 | |
| 2.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH21 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** SS | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 4.1 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | Fill Material: Silty sand, fine to medium grained, brown, with gravels, no odour, dry. | 0.1 | 0.2 | |
| 0.5 | | Fill Material: Gravelly sandy Clay, medium plasticity, sub-angular gravels, brown. dry. | | | |
| 1.0 | | | 1.2 | 0.1 | |
| 1.5 | | | | | |
| 2.0 | | | | | |
| 2.5 | | | | | |
| 3.0 | | Residual Soil: sandy Clay, low plasticity, orange brown, with occasional ironstone gravels, becoming grey mottled red. moist | 3.0 | 0.3 | |
| 3.5 | | Natural: Sandstone, fine to medium grained, grey orange, no odour, moist | | | |
| 4.0 | | Refusal @ 4.1 | 4.0 | 0.0 | |
| | | End of Investigation | | | |
| 4.5 | | | | | |
| 5.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH22 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** SS | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 1.0 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| **Depth (m)** | **Lithological Symbol** | **SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour)** | **Sample ID** | **PID (ppm)** | **Other Comments** |
| | | Ground Surface | | | |
| 0.0 | | Fill Material: Silty sand, fine to medium grained, brown, with gravels, no odour, dry. | 0.1 | 0.5 | |
| 0.5 | | Fill Material: Gravelly sandy Clay, medium plasticity, sub-angular gravels, brown. dry. | | | |
| 1.0 | | End of Investigation | 1.0 | 0.2 | |
| 1.5 | | | | | |
| 2.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH23 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** SS | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 1.35 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | Fill Material: Silty sand, fine to medium grained, brown, with gravels, no odour. | 0.1 | 0.5 | |
| 0.5 | | Natural: Sandstone, fine to medium grained, orange, no odour. | | | |
| 1.0 | | Refusal @ 1.35m | 1.0 | 0.2 | |
| | | End of Investigation | | | |
| 1.5 | | | | | |
| 2.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH24 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** SS | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 4.1 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | Fill Material: Silty sand, fine to medium grained, brown, with gravels, no odour. | 0.1 | 0.4 | |
| 0.5 | | Fill Material: Sandy silty Clay, low-medium plasticity, orange brown, no odours. | | | |
| 1.0 | | | | | |
| 1.5 | | | 1.5 | 0.9 | |
| 2.0 | | Residual Soil: Silty Clay, medium-high plasticity, brown, no odour. | | | |
| 2.5 | | | | | |
| | | | 2.8 | 0.4 | |
| 3.0 | | | | | |
| 3.5 | | Natural: Sandstone, fine to medium grained, orange brown, no odour. | | | |
| 4.0 | | Refusal @ 4.0 m | | | |
| | | End of Investigation | | | |
| 4.5 | | | | | |
| 5.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH25 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** HA | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 0.2 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| **Depth (m)** | **Lithological Symbol** | **SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour)** | **Sample ID** | **PID (ppm)** | **Other Comments** |
| | | Ground Surface | | | |
| 0.0 | | Fill Material:<br>Sandy silt, low plasticity, brown, no odour, dry | | | |
| | | End of Investigation | 0.2 | 0.4 | |
| 0.5 | | | | | |
| 1.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH26 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** HA | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 0.6 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| **Depth (m)** | **Lithological Symbol** | **SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour)** | **Sample ID** | **PID (ppm)** | **Other Comments** |
| | | Ground Surface | | | |
| 0.0 | | Fill Material:<br>Sandy silt,fine grained, brown, no odour, dry<br><br>Refusal @ 0.6m | 0.2 | 0.7 | |
| 0.5 | | | | | |
| | | End of Investigation | | | |
| 1.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH27 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** SS | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 1.0 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | Fill Material: Sandy silt, low plasticity, brown, no odour, dry | 0.1 | 0.3 | |
| | | Fill Material: Clayey sand, fine to medium grained, orange, no odour, dry | | | |
| 0.5 | | | | | |
| 1.0 | | End of Investigation | 1.0 | 0.6 | |
| 1.5 | | | | | |
| 2.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH28 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** SS | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 4.5 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | Fill Material: Silty sand, fine to medium grained, brown, with gravels, no odour, dry. | 0.1 | 0.1 | |
| 0.5 | | Fill Material: Silty sandy, fine to medium grained, grey brown, fragments of gravel, dry, no odour, dry. | | | |
| 1.0 | | | 1.0 | 0.8 | |
| 1.5 | | | | | |
| 2.0 | | Residual Soil: Clayey sand, fine to medium grained, orange brown, moist, no odour, moist. | 2.0 | 0.5 | |
| 2.5 | | | | | |
| | | Natural: Sandstone, fine to medium grained, pale grey, wet, no odour. | | | |
| 3.0 | | | 3.0 | 0.4 | |
| 3.5 | | | | | |
| 4.0 | | | 4.0 | 0.8 | |
| 4.5 | | End of Investigation | | | |
| 5.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH29 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** SS | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 8.0 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | Fill Material: Silty sand, fine to medium grained, brown, with gravels, no odour. | 0.1 | 0.0 | |
| 0.5 | | Fill Material: Gravelly clayey Sand, fine to coarse grained,orange brown, with high plasticity clay bands, no odour. | | | |
| 1.0 | | | 1.0 | 0.5 | |
| 1.5 | | Fill Material: Gravelly sandy Clay, medium - high plasticity, grey brown, with brick fragments, ash, porcelain and glass, no odour. | | | |
| 2.0 | | | 2.0 | 0.2 | |
| 2.5 | | Fill Material Silty sandy Gravel, fine to course grained, orange brown, with brick fragments and angular sandstone gravel, no odour. | | | |
| 3.0 | | | 3.0 | 0.3 | |
| 3.5 | | | | | |
| 4.0 | | | 4.0 | 0.2 | |
| 4.5 | | | | | |
| 5.0 | | | 5.0 | 0.0 | |
| 5.5 | | | | | |
| 6.0 | | | 6.0 | 0.7 | |
| 6.5 | | | | | |
| 7.0 | | | 7.0 | 0.4 | |
| 7.5 | | | | | |
| 8.0 | | End of Investigation | 8.0 | 0.6 | |
| 8.5 | | | | | |
| 9.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH30 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** SS | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 7.45 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | Fill Material: silty sand, fine to medium grained, brown, with gravels, no odour, dry | 0.1 | 0.1 | |
| 0.5 | | Fill Material: gravelly silty Sand, fine to coarse grained, pale brown, with high plasticity clay bands and brickfragments, no odour, dry | | | |
| 1.0 | | | 1.0 | 0.4 | |
| 1.5 | | Fill Material: sandy silty Clay, medium plasticity, brown, with occasional medium to coarse grained gravels, dry | | | |
| 2.0 | | | 2.0 | 0.6 | |
| 2.5 | | | | | |
| 3.0 | | | 3.0 | 0.8 | |
| 3.5 | | Fill Material: Gravelly clayey Sand, fine to course grained, grey to orange brown, with brick fragments, ash, porcelain and glass, no odour, dry | | | |
| 4.0 | | | 4.0 | 1.1 | |
| 4.5 | | | | | |
| 5.0 | | | 5.0 | 0.3 | |
| 5.5 | | | | | |
| 6.0 | | | 6.0 | 0.8 | |
| 6.5 | | | | | |
| 7.0 | | Natural: Sandstone, fine to medium grained, orange grey, estimate very low to low strength becoming to low medium strength and pale grey, moist | 7.0 | 0.7 | |
| 7.5 | | End of Investigation | | | |
| 8.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH31 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** SS | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 1.5 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | Fill Material: Sandy silt, low plasticity, brown, no odour, dry. | 0.1 | 0.2 | |
| | | Natural: Sandstone, fine to medium grained, orange grey, no odour, dry. | | | |
| 0.5 | | | | | |
| 1.0 | | | 1.0 | 0.5 | |
| 1.5 | | End of Investigation | | | |
| 2.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH32 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** SS | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 4.0 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | Fill Material: Silty sand, fine to medium grained, brown, with gravels, no odour, dry. | 0.1 | 0.2 | |
| 0.5 | | Fill Material: Silty sandy, fine to medium grained, grey brown, fragments of gravel, dry, no odour, dry. | | | |
| 1.0 | | | 1.0 | 0.5 | |
| 1.5 | | | | | |
| 2.0 | | Residual Soil: Clayey sand, fine to medium grained, orange brown, moist, no odour, moist. | 2.2 | 0.4 | |
| 2.5 | | | | | |
| | | Natural: Sandstone, fine to medium grained, pale grey, wet, no odour. | | | |
| 3.0 | | | 3.0 | 0.0 | |
| 3.5 | | | | | |
| 4.0 | | | 4.0 | 010 | |
| | | End of Investigation | | | |
| 4.5 | | | | | |
| 5.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH33 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** HA | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 1.7 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | Fill Material: Sandy silt, low plasticity, brown, no odour, dry. | 0.2 | 0.2 | |
| 0.5 | | Natural: Sandstone, fine to medium grained, pale grey, dry. | | | |
| 1.0 | | | 1.0 | 0.9 | |
| 1.5 | | Termination @ 1.7m | | | |
| 2.0 | | End of Investigation | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH34 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** HA | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 0.4 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | Fill Material:<br>Sandstone, fine to medium grained, dark red grading to pale, no odour, dry. | | | |
| | | | 0.1 | 0.3 | DUP1, SPLIT1 |
| | | Refusal @ 0.4m | | | |
| | | End of Investigation | | | |
| 0.5 | | | | | |
| 1.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH35 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** HA | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 0.4 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | Fill Material:<br>Sandy silt,fine grained, debris, tile fragments, brown, no odour, dry.<br><br>Refusal @ 0.4m | 0.1 | 0.5 | DUP2, SPLIT2 |
| 0.5 | | End of Investigation | | | |
| 1.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH36 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** HA | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 0.3 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | Fill Material:<br>Sandy silt,fine grained, brown, no odour, dry.<br><br>Refusal @ 0.3m | 0.1 | 0.0 | DUP3, SPLIT3 |
| 0.5 | | End of Investigation | | | |
| 1.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH37 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** HA | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 0.3 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | Fill Material:<br>Sandy silt,fine grained, brown, no odour, dry.<br><br>Refusal @ 0.3m | 0.1 | 0.1 | DUP4, SPLIT4 |
| 0.5 | | End of Investigation | | | |
| 1.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH38 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** HA | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 0.5 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| **Depth (m)** | **Lithological Symbol** | **SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour)** | **Sample ID** | **PID (ppm)** | **Other Comments** |
| | | Ground Surface | | | |
| 0.0 | | Fill Material:<br>Sandy silt,fine grained, brown, no odour, rubbish, glass, brick fragments, dry. | | | |
| | | | 0.1 | 0.7 | |
| 0.5 | | Refusal @ 0.5m | | | |
| | | End of Investigation | | | |
| 1.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH39 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** HA | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 0.5 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | Fill Material:<br>Sandy silt,fine grained, brown, no odour, dry.<br><br>Refusal @ 0.5m | 0.1 | 0.3 | |
| 0.5 | | End of Investigation | | | |
| 1.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH40 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** HA | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 0.2 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | Fill Material:<br>Sandy silt,fine grained, brown, no odour, dry. | 0.1 | 0.4 | |
| 0.5 | | End of Investigation | | | |
| 1.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH41 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** HA | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 0.2 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| **Depth (m)** | **Lithological Symbol** | **SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour)** | **Sample ID** | **PID (ppm)** | **Other Comments** |
| | | Ground Surface | | | |
| 0.0 | | Fill Material:<br>Sandy silt,fine grained, brown, no odour, dry. | 0.1 | 0.6 | |
| 0.5 | | End of Investigation | | | |
| 1.0 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH42 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** | ***Easting:*** 0 |
| ***Project Name:*** Lane Cove NSW | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** SS | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 0.2 | ***Checked By:*** |
| ***Date Drilled:*** 10/7/2017 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| **Depth (m)** | **Lithological Symbol** | **SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour)** | **Sample ID** | **PID (ppm)** | **Other Comments** |
| | | Ground Surface | | | |
| 0.0 | | Fill Material: Sandy silt,fine grained, brown, no odour, dry. | 0.1 | 0.8 | |
| 0.5 | | End of Investigation | | | |
| 1.0 | | | | | |

**NOTES:**

# Monitoring Well: GW01/ BH43

***Project Ref. No:*** 27380 | ***Project Name:*** Longueville Rd Lane Cove | ***Completion Date:*** 10/05/2018

***BCL No:*** | ***Drilling Contractor:*** Stratacore Drilling | ***Page Number:*** 1 of 1


***Drilling Method:*** SA | ***Drillers Licence No:*** | ***Logged By:*** JL

***Well Diameter (mm):*** 50 | ***Well Depth (m):*** 10.0 | ***Checked By:*** JL

***Casing Stickup (m):*** 0.0 | ***Well Material:*** PVC | ***Easting:*** 0

***Location Description:*** | ***Northing:*** 0

| Geological Description | Graphic Symbol | Depth | Sample Type | Sample ID | PID (ppm) | Well Construction Details | Additional Observations |
|---|---|---|---|---|---|---|---|
| Ground Surface | | 0.0 | | | | | |
| 0.0-0.1 Fill: Silty Sand<br>Moderately moist, brown to dark grey with some organic content. No stains or odours. | | | | | | | |
| 0.10-10.0 Natural: Sand<br>Fine to medium grained, dry. Becoming stiff with depth. No odours or staining. | | 1.0 | | | | | |
| | | 2.0 | | | | | |
| | | 3.0 | | | | | |
| | | 4.0 | | | | | |
| | | 5.0 | | BH43_5.0, Dup5, Split 5 | 0.3 | | |
| | | 6.0 | | BH43_6.0 | 0.4 | | |
| | | 7.0 | | BH43_7.0 | 0.2 | | |
| Becomes moist @ 7.7 mbgl. | | 8.0 | | BH43_8.0 | 0.7 | | |
| | | 9.0 | | BH43_9.0 | 0.0 | | |
| Bore terminated @ 10.0 mbgl | | 10.0 | | | | | |
| End of Log | | | | | | | |




**Groundwater Observations -**

**Depth Water Encountered During Drilling (mbNS):** 7.7 **Post Install Water Level (mbNS):** 4.36

**Sample Type -**

- **Hand Auger**
- **Solid Stem Auger**
- **Push Tube**
- **Split Spoon**
- **R.A.B**

**Monitoring Well Construction Key -**

- **Screen** 7.0-10.0 **Backfill** 0.5-6.0
- **Bentonite** 6.0-6.5
- **Filter Pack** 6.5-10.0
- **Grout** 0.0-0.5

# Monitoring Well: GW02/ BH44

***Project Ref. No:*** 27380 | ***Project Name:*** Longueville Rd Lane Cove | ***Completion Date:*** 10/05/2018

***BCL No:*** | ***Drilling Contractor:*** Stratacore Drilling | ***Page Number:*** 1 of 1


***Drilling Method:*** SA | ***Drillers Licence No:*** | ***Logged By:*** JL

***Well Diameter (mm):*** 50 | ***Well Depth (m):*** 10.0 | ***Checked By:*** JL

***Casing Stickup (m):*** 0.0 | ***Well Material:*** PVC | ***Easting:*** 0

***Location Description:*** | ***Northing:*** 0

| Geological Description | Graphic Symbol | Depth | Sample Type | Sample ID | PID (ppm) | Well Construction Details | Additional Observations |
|---|---|---|---|---|---|---|---|
| Ground Surface | | 0.0 | | | | | |
| 0.0-0.1 Fill: Silty Sand<br>Dry, brown to dark grey with some organic content. No stains or odours. | | | | | | | |
| 0.1-1.5 Fill: Silty Sand<br>Dry, brown to dark grey. No stains or odours. | | 1.0 | | | | | |
| 1.5-10.0 Natural: Sand<br>Fine to medium grained. Orange and dry, no odours or staining. | | 2.0 | | | | | |
| | | 3.0 | | | | | |
| | | 4.0 | | | | | |
| Becomes light brown @ 5.0 mbgl. | | 5.0 | | BH44_5.0 | 0.9 | | |
| | | 6.0 | | BH44_6.0 | 0.6 | | |
| Becomes moist @ 6.2 mbgl. | | | | | | | |
| Becomes dark brown @ 7.0 mbgl. | | 7.0 | | BH44_7.0 | 0.7 | | |
| | | 8.0 | | BH44_8.0 | 0.1 | | |
| | | 9.0 | | BH44_9.0 | 0.2 | | |
| Bore terminated @ 10.0 mbgl | | 10.0 | | | | | |
| End of Log | | | | | | | |




**Groundwater Observations -**

**Depth Water Encountered During Drilling (mbNS):** 10.0 **Post Install Water Level (mbNS):** 6.62

**Sample Type -**

- **Hand Auger**
- **Solid Stem Auger**
- **Push Tube**
- **Split Spoon**
- **R.A.B**


**Monitoring Well Construction Key -**

- **Screen** 7.0-10.0 **Backfill** 0.5-6.0
- **Bentonite** 6.0-6.5
- **Filter Pack** 6.5-10.0
- **Grout** 0.0-0.5

# Monitoring Well: GW03/BH45

***Project Ref. No:*** 27380
***Project Name:*** Longueville Rd Lane Cove
***Completion Date:*** 10/05/2018
***BCL No:***
***Drilling Contractor:*** Stratacore Drilling
***Page Number:*** 1 of 1
***Drilling Method:*** SA
***Drillers Licence No:***
***Logged By:*** JL
***Well Diameter (mm):*** 50
***Well Depth (m):*** 10.0
***Checked By:*** JL
***Casing Stickup (m):*** 0.0
***Well Material:*** PVC
***Easting:*** 0
***Location Description:***
***Northing:*** 0

| Geological Description | Graphic Symbol | Depth | Sample Type | Sample ID | PID (ppm) | Well Construction Details | Additional Observations |
|---|---|---|---|---|---|---|---|
| Ground Surface | | 0.0 | | | | | |
| 0.0-0.1 Fill: Silty Sand<br>Dry, brown to dark grey with some organic content. No stains or odours. | | | | | | | |
| 0.1-7.30 Fill: Silty Sand<br>Dry, brown to dark grey. No stains or odours. | | 1.0<br>2.0<br>3.0<br>4.0<br>5.0<br>6.0 | | | | | |
| | | 7.0 | | BH45_7.0 | 0.2 | | |
| 7.3-8.7 Natural: Sand<br>Brown. Fine to medium grained, dry. Stiff. No odours or staining. | | | | BH45_7.8<br>BH45_8.0 | 0.4<br>0.7 | | |
| | | 8.0 | | | | | |
| Hard reufusal, bore terminated @ 8.7 mbgl on sandstone. | | 9.0 | | | | | |
| End of Log | | 10.0 | | | | | |




**Groundwater Observations -**

**Depth Water Encountered During Drilling (mbNS):** 7.7
**Post Install Water Level (mbNS):** 4.36

**Sample Type -**

- **Hand Auger**
- **Solid Stem Auger**
- **Push Tube**
- **Split Spoon**
- **R.A.B**

**Monitoring Well Construction Key -**

- **Screen** 7.0-10.0 **Backfill** 0.5-6.0
- **Bentonite** 6.0-6.5
- **Filter Pack** 6.5-10.0
- **Grout** 0.0-0.5

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH46 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** Stratacore Drilling | ***Easting:*** 0 |
| ***Project Name:*** Longvueville Rd lane Cove | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** SS | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 7 | ***Checked By:*** |
| ***Date Drilled:*** 11/05/2018 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | 0.00-0.05 Fill: Silty Sand<br>Dry, Brown to dark grey with some organics. No stains or odours. | BH46_0.2 | 0.2 | |
| 0.5 | | 0.05-2.54 Natural: Sand<br>Light brown. Fine to medium grained, moist. Becoming Stiff with depth. No odours or satining. | BH46_0.5 | 0.4 | |
| 1.0 | | | BH46_1.0 | 0.3 | |
| 1.5 | | | | | |
| 2.0 | | | BH46_2.0, Dup06, Split06 | 0.2 | |
| 2.5 | | Hard refusal, bore terminated @ 2.5 mbgl on sandstone. | BH46_2.3 | 0.0 | |
| | | End of Investigation | | | |
| 3.0 | | | | | |
| 3.5 | | | | | |
| 4.0 | | | | | |
| 4.5 | | | | | |
| 5.0 | | | | | |
| 5.5 | | | | | |
| 6.0 | | | | | |
| 6.5 | | | | | |
| 7.0 | | | | | |
| 7.5 | | | | | |

**NOTES:**

# BOREHOLE LOG

| | |
|---|---|
| ***Borehole No:*** BH47 | |
| ***Page Number:*** 1 of 1 | |

| | | |
|---|---|---|
| ***Client:*** Australian Unity Limited | ***Drilling Contractor:*** Stratacore Drilling | ***Easting:*** 0 |
| ***Project Name:*** Longvueville Rd lane Cove | ***Driller:*** | ***Northing:*** 0 |
| ***Project Ref. No:*** 27380 | ***Drilling Method:*** SS | ***Logged By:*** JL |
| ***Location:*** Lane Cove NSW | ***Total Depth (m):*** 7 | ***Checked By:*** |
| ***Date Drilled:*** 11/05/2018 | ***Diameter (mm):*** | |

| DRILLING | | | | | |
|---|---|---|---|---|---|
| Depth (m) | Lithological Symbol | SOIL DESCRIPTION (Soil type, density/plasticity, moitsure, odour) | Sample ID | PID (ppm) | Other Comments |
| | | Ground Surface | | | |
| 0.0 | | 0.00-0.1 Fill: Silty Sand<br>Dry, Brown to dark grey with some organics. No stains or odours. | | | |
| 0.5 | | 0.1-3.7Fill: Silty Sand<br>Dry, Brown to dark grey. No stains or odours. | | | |
| 1.0 | | | | | |
| 1.5 | | | | | |
| 2.0 | | | | | |
| 2.5 | | | | | |
| 3.0 | | | | | |
| 3.5 | | | BH47_3.6 | 0.2 | |
| | | 3.7-7.0 Natural: Sand<br>Light brown. Fine to medium grained, moist. Becoming Stiff with depth. No odours or satining. | | | |
| 4.0 | | | | | |
| 4.5 | | | | | |
| 5.0 | | | BH47_5.0 | 0.7 | |
| 5.5 | | | | | |
| 6.0 | | | BH47_6.0 | 0.5 | |
| 6.5 | | | BH47_6.5 | 0.2 | |
| | | | BH47_7.0 | 0.3 | |
| | | Hard refusal, bore terminated @ 7.0 mbgl on sandstone. | | | |
| 7.0 | | End of Investigation | | | |
| 7.5 | | | | | |

**NOTES:**

# SMEC Borehole Logs (BH1 - BH15)

## NON-CORE DRILL HOLE - GEOLOGICAL LOG

**HOLE NO : BH1**

PROJECT : 266 Longueville Road, Lane Cove GI
LOCATION : Car Park
CLIENT : Lane Cove Council
FEATURE : Car Park
FILE / JOB NO : 30011131
SHEET : 1 OF 1

POSITION : E: 330825.006, N: 6256063.811 (56 MGA94) SURFACE ELEVATION : 56.000 (AHD) ANGLE FROM HORIZONTAL : 90°

RIG TYPE : Edson 3000 MOUNTING : Truck CONTRACTOR : BHC Drilling DRILLER : C.W

DATE STARTED : 10/11/11 DATE COMPLETED : 10/11/11 DATE LOGGED : 10/11/11 LOGGED BY : A.G CHECKED BY : M.G

| DRILLING | | | | | | | MATERIAL | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| PROGRESS: DRILLING & CASING | PROGRESS: WATER | DRILLING PENETRATION | GROUND WATER LEVELS | SAMPLES & FIELD TESTS | ELEVATION (RL) | DEPTH (m) | GRAPHIC LOG | CLASSIFICATION SYMBOL | MATERIAL DESCRIPTION<br>Soil Type, Plasticity or Particle Characteristic, Colour, Secondary and Minor Components | MOISTURE CONDITION | CONSISTENCY RELATIVE DENSITY | STRUCTURE & Other Observations |
| ADT | | E | | ES 0.20m | 56.0 | 0.0 | | ML | Sandy SILT<br>low plasticity, brown, with minor rootlets in the top 100mm | D | D | FILL |
| | | | | 0.60m ES 0.80m | | 0.30m | | SC | Clayey SAND<br>fine to medium grained, orange | | | RESIDUAL SOIL |
| | | M | | | 55.0 | 1.0 | | | SANDSTONE<br>fine to medium grained, pale grey, estimate very low to low strength becoming low to medium strength at 1.3m | | | WEATHERED ROCK<br>0.80: Low TC Bit Resistance |
| | | H | | | | 1.50m | | | BOREHOLE BH1 TERMINATED AT 1.50 m<br>Target depth | | | 1.30: Medium TC Bit Resistance |
| | | | | | 54.0 | 2.0 | | | | | | |
| | | | | | 53.0 | 3.0 | | | | | | |
| | | | | | 52.0 | 4.0 | | | | | | |
| | | | | | 51.0 | 5.0 | | | | | | |
| | | | | | 50.0 | 6.0 | | | | | | |
| | | | | | 49.0 | 7.0 | | | | | | |
| | | | | | 48.0 | 8.0 | | | | | | |

See Explanatory Notes for details of abbreviations & basis of descriptions.

SMEC AUSTRALIA

UPDATED SMEC LIBRARY_AGS 3_1 RTA 1_1 LIB 08_WITH FENCE TOOL_AND_CAD COLOUR.GLB Log SMEC NON-CORE DRILL HOLE LANE COVE.GPJ <<DrawingFile>> 01/12/2011 08:32 8.2.904

# NON-CORE DRILL HOLE - GEOLOGICAL LOG

**HOLE NO : BH2**

PROJECT : 266 Longueville Road, Lane Cove GI
LOCATION : Car Park
CLIENT : Lane Cove Council
FEATURE : Bowling Green
FILE / JOB NO : 30011131
SHEET : 1 OF 1

POSITION : E: 330825.156, N: 6256047.893 (56 MGA94) SURFACE ELEVATION : 56.000 (AHD) ANGLE FROM HORIZONTAL : 90°

RIG TYPE : Edson 3000 MOUNTING : Truck CONTRACTOR : BHC Drilling DRILLER : C.W

DATE STARTED : 10/11/11 DATE COMPLETED : 10/11/11 DATE LOGGED : 10/11/11 LOGGED BY : A.G CHECKED BY : M.G

| DRILLING | | | | | | | MATERIAL | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| PROGRESS: DRILLING & CASING | PROGRESS: WATER | DRILLING PENETRATION | GROUND WATER LEVELS | SAMPLES & FIELD TESTS | ELEVATION (RL) | DEPTH (m) | GRAPHIC LOG | CLASSIFICATION SYMBOL | MATERIAL DESCRIPTION<br>Soil Type, Plasticity or Particle Characteristic, Colour, Secondary and Minor Components | MOISTURE CONDITION | CONSISTENCY RELATIVE DENSITY | STRUCTURE & Other Observations |
| AD/T | | E | | ES 0.20m | 56.0 | 0.0 | | | 0.20m Sandy GRAVEL<br>medium to coarse grained, grey brown, (Roadbase) | D | | FILL |
| | | M | | 0.50m<br>ES 0.70m | | | | | SANDSTONE<br>fine to medium grained, grey orange, estimate very low to low strength becoming low to medium strength at 0.7m | | | WEATHERED ROCK<br>0.20: Very Low TC Bit Resistance<br>0.70: Moderate TC Bit Resistance |
| | | H | | | 55.0 | 1.0 | | | 1.50m | | | |
| | | | | | 54.0 | 2.0 | | | BOREHOLE BH2 TERMINATED AT 1.50 m<br>Target depth | | | |
| | | | | | 53.0 | 3.0 | | | | | | |
| | | | | | 52.0 | 4.0 | | | | | | |
| | | | | | 51.0 | 5.0 | | | | | | |
| | | | | | 50.0 | 6.0 | | | | | | |
| | | | | | 49.0 | 7.0 | | | | | | |
| | | | | | 48.0 | 8.0 | | | | | | |

See Explanatory Notes for details of abbreviations & basis of descriptions.

SMEC AUSTRALIA

UPDATED SMEC LIBRARY_AGS 3_1 RTA 1_1 LIB 08_WITH FENCE TOOL_AND_CAD COLOUR.GLB Log SMEC NON-CORE DRILL HOLE LANE COVE.GPJ <<DrawingFile>> 01/12/2011 08:34 8.2.904

# NON-CORE DRILL HOLE - GEOLOGICAL LOG

**HOLE NO : BH3**

PROJECT : 266 Longueville Road, Lane Cove GI
LOCATION : Upper
CLIENT : Lane Cove Council
FEATURE : Bowling Green
FILE / JOB NO : 30011131
SHEET : 1 OF 1

POSITION : E: 330842.726, N: 6256055.884 (56 MGA94) SURFACE ELEVATION : 55.200 (AHD) ANGLE FROM HORIZONTAL : 90°

RIG TYPE : Edson 3000 MOUNTING : Truck CONTRACTOR : BHC Drilling DRILLER : C.W

DATE STARTED : 11/11/11 DATE COMPLETED : 11/11/11 DATE LOGGED : 11/11/11 LOGGED BY : A.G CHECKED BY : M.G

| DRILLING | | | | | | MATERIAL | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| PROGRESS: DRILLING & CASING | PROGRESS: WATER | DRILLING PENETRATION | GROUND WATER LEVELS | SAMPLES & FIELD TESTS | ELEVATION (RL) / DEPTH (m) | GRAPHIC LOG | CLASSIFICATION SYMBOL | MATERIAL DESCRIPTION<br>Soil Type, Plasticity or Particle Characteristic, Colour, Secondary and Minor Components | MOISTURE CONDITION | CONSISTENCY RELATIVE DENSITY | STRUCTURE & Other Observations |
| AD/T | | E | | ES 0.20m | 55.0 / 0.0 | | | Silty SAND<br>fine to medium grained, brown, with gravels from 0.2-0.4m | D | | TOPSOIL |
| | | | | 0.50m ES 0.70m | | | | 0.40m<br>SANDSTONE<br>fine to medium grained, grey orange, estimate very low to low strength | | | WEATHERED ROCK<br>0.40: Very Low TC Bit Resistance |
| | | M | | | 54.0 / 1.0 | | | 1.50m<br>BOREHOLE BH3 TERMINATED AT 1.50 m<br>Target depth | | | |
| | | | | | 53.0 / 2.0 | | | | | | |
| | | | | | 52.0 / 3.0 | | | | | | |
| | | | | | 51.0 / 4.0 | | | | | | |
| | | | | | 50.0 / 5.0 | | | | | | |
| | | | | | 49.0 / 6.0 | | | | | | |
| | | | | | 48.0 / 7.0 | | | | | | |
| | | | | | 8.0 | | | | | | |

See Explanatory Notes for details of abbreviations & basis of descriptions.

SMEC AUSTRALIA



UPDATED SMEC LIBRARY_AGS 3_1.RTA 1_1 LIB 08_WITH FENCE TOOL_AND_CAD COLOUR.GLB Log SMEC NON-CORE DRILL HOLE LANE COVE.GPJ <<DrawingFile>> 01/12/2011 08:34 8.2.904

# NON-CORE DRILL HOLE - GEOLOGICAL LOG

**HOLE NO : BH4**

PROJECT : 266 Longueville Road, Lane Cove GI
LOCATION : Upper
CLIENT : Lane Cove Council
FEATURE : Bowling Green
FILE / JOB NO : 30011131
SHEET : 1 OF 1

POSITION : E: 330856.029, N: 6256037.214 (56 MGA94) SURFACE ELEVATION : 55.200 (AHD) ANGLE FROM HORIZONTAL : 90°

RIG TYPE : Edson 3000 MOUNTING : Truck CONTRACTOR : BHC Drilling DRILLER : C.W

DATE STARTED : 11/11/11 DATE COMPLETED : 11/11/11 DATE LOGGED : 11/11/11 LOGGED BY : A.G CHECKED BY : M.G

| DRILLING | | | | | | | MATERIAL | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| PROGRESS: DRILLING & CASING | PROGRESS: WATER | DRILLING PENETRATION | GROUND WATER LEVELS | SAMPLES & FIELD TESTS | ELEVATION (RL) | DEPTH (m) | GRAPHIC LOG | CLASSIFICATION SYMBOL | MATERIAL DESCRIPTION<br>Soil Type, Plasticity or Particle Characteristic, Colour, Secondary and Minor Components | MOISTURE CONDITION | CONSISTENCY RELATIVE DENSITY | STRUCTURE & Other Observations |
| AT | | E | | ES 0.20m | 55.0 | 0.0 | | SM | Silty SAND<br>fine to medium grained, brown, with rootlets in the top 100mm | D | | TOPSOIL<br>0.20: Triplicate ES Taken |
| | | | | | | 0.30m | | | | | | FILL |
| | | | | 0.50m ES 0.70m | | | | GW | GRAVEL<br>coarse grained, to 30 mm, sub-angular, dark grey, with some sand | | | |
| | | | | | | 1.00m | | | | | | |
| | | M | | 1.10m ES 1.30m | 54.0 | 1.0 | | | SANDSTONE<br>fine to medium grained, grey orange, estimate very low to low strength becoming low to medium strength at 1.7m | | | WEATHERED ROCK<br>1.00: Very Low TC Bit Resistance |
| | | H | | | | | | | | | | 1.70: Medium TC Bit Resistance |
| | | | | | | 2.00m | | | | | | |
| | | | | | 53.0 | 2.0 | | | BOREHOLE BH4 TERMINATED AT 2.00 m<br>Target depth | | | |
| | | | | | 52.0 | 3.0 | | | | | | |
| | | | | | 51.0 | 4.0 | | | | | | |
| | | | | | 50.0 | 5.0 | | | | | | |
| | | | | | 49.0 | 6.0 | | | | | | |
| | | | | | 48.0 | 7.0 | | | | | | |
| | | | | | | 8.0 | | | | | | |

See Explanatory Notes for details of abbreviations & basis of descriptions.

SMEC AUSTRALIA

UPDATED SMEC LIBRARY_AGS 3_1.RTA 1_1 LIB 08_WITH FENCE TOOL_AND_CAD COLOUR.GLB Log SMEC NON-CORE DRILL HOLE LANE COVE.GPJ <<DrawingFile>> 01/12/2011 08:34 8.2.904

# NON-CORE DRILL HOLE - GEOLOGICAL LOG

**HOLE NO : BH5**

PROJECT : 266 Longueville Road, Lane Cove GI
LOCATION : Upper
CLIENT : Lane Cove Council
FEATURE : Bowling Green
FILE / JOB NO : 30011131
SHEET : 1 OF 1

POSITION : E: 330874.040, N: 6256048.627 (56 MGA94) SURFACE ELEVATION : 55.200 (AHD) ANGLE FROM HORIZONTAL : 90°

RIG TYPE : Edson 3000 MOUNTING : Truck CONTRACTOR : BHC Drilling DRILLER : C.W

DATE STARTED : 11/11/11 DATE COMPLETED : 11/11/11 DATE LOGGED : 11/11/11 LOGGED BY : A.G CHECKED BY : M.G

| DRILLING | | | | | | | MATERIAL | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| PROGRESS: DRILLING & CASING | PROGRESS: WATER | DRILLING PENETRATION | GROUND WATER LEVELS | SAMPLES & FIELD TESTS | ELEVATION (RL) | DEPTH (m) | GRAPHIC LOG | CLASSIFICATION SYMBOL | MATERIAL DESCRIPTION<br>Soil Type, Plasticity or Particle Characteristic, Colour, Secondary and Minor Components | MOISTURE CONDITION | CONSISTENCY RELATIVE DENSITY | STRUCTURE & Other Observations |
| ADT | | | | ES<br>0.20m | 55.0 | 0.0 | | SM | Silty SAND<br>fine to medium grained, brown, with rootlets in the top 100mm<br>0.40m | | | TOPSOIL |
| | | | | 1.30m<br>ES<br>**1.50m** | 54.0 | 1.0 | | | Gravelly Sandy CLAY<br>medium plasticity, brown, with sub angular gravels | | | FILL |
| | | E-H | | SPT<br>3,2,3<br>N=5<br>1.95m | | 1.50m | | CL | 1.50: As above but grey brown | D | S - F | 1.50: PID = 2ppm |
| | | | | 3.00m | 53.0 | 2.0 | | | | | | 2.70: Duplicate ES Taken |
| | | E | | SPT<br>6,15,25/100mm<br>N=>40 | 52.0 | 3.0 | | CL | Sandy CLAY<br>low plasticity, orange brown, with occasional ironstone gravels, becoming grey mottled red<br>3.30m | M | St | RESIDUAL SOIL<br>3.20: Minor seepage at soil/rock interface |
| | | M | | 3.40m<br>3.70m | | | | | SANDSTONE<br>fine to medium grained, grey orange, estimate very low to low strength becoming low to medium strength at 3.7m | | | WEATHERED ROCK<br>3.30: Very Low TC Bit Resistance<br>3.70: High TC Bit Resistance |
| | | H | | ES<br>3.90m | | 4.00m | | | | | | |
| | | | | | 51.0 | | | | BOREHOLE BH5 TERMINATED AT 4.00 m<br>Target depth | | | |
| | | | | | 50.0 | 5.0 | | | | | | |
| | | | | | 49.0 | 6.0 | | | | | | |
| | | | | | 48.0 | 7.0 | | | | | | |
| | | | | | | 8.0 | | | | | | |

See Explanatory Notes for details of abbreviations & basis of descriptions.

SMEC AUSTRALIA



UPDATED SMEC LIBRARY_AGS 3_1.RTA 1_1 LIB 08_WITH FENCE TOOL_AND_CAD COLOUR.GLB Log SMEC NON-CORE DRILL HOLE LANE COVE.GPJ <<DrawingFile>> 01/12/2011 08:34 8.2.904

# NON-CORE DRILL HOLE - GEOLOGICAL LOG

**HOLE NO : BH6**

PROJECT : 266 Longueville Road, Lane Cove GI
LOCATION : Upper
CLIENT : Lane Cove Council
FEATURE : Bowling Green
FILE / JOB NO : 30011131
SHEET : 1 OF 1

POSITION : E: 330842.730, N: 6256025.009 (56 MGA94) SURFACE ELEVATION : 55.200 (AHD) ANGLE FROM HORIZONTAL : 90°

RIG TYPE : Edson 3000 MOUNTING : Truck CONTRACTOR : BHC Drilling DRILLER : C.W

DATE STARTED : 11/11/11 DATE COMPLETED : 11/11/11 DATE LOGGED : 11/11/11 LOGGED BY : A.G CHECKED BY : M.G

| DRILLING | | | | | | | MATERIAL | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| PROGRESS: DRILLING & CASING | PROGRESS: WATER | DRILLING PENETRATION | GROUND WATER LEVELS | SAMPLES & FIELD TESTS | ELEVATION (RL) | DEPTH (m) | GRAPHIC LOG | CLASSIFICATION SYMBOL | MATERIAL DESCRIPTION<br>Soil Type, Plasticity or Particle Characteristic, Colour, Secondary and Minor Components | MOISTURE CONDITION | CONSISTENCY RELATIVE DENSITY | STRUCTURE & Other Observations |
| ADT | | E | | ES<br>0.20m | 55.0 | 0.0 | | SM | Silty SAND<br>fine to medium grained, brown, with rootlets in the top 100mm | D | | TOPSOIL |
| | | | | | | 0.30m | | | | | | |
| | | M | | 0.50m<br>0.50m<br>ES | | | | | SANDSTONE<br>fine to medium grained, orange, estimate very low to low strength<br>becoming low to medium strength and pale grey at 1.0m | | | WEATHERED ROCK<br>0.30: Very Low TC Bit Resistance |
| | | H | | | 54.0 | 1.0 | | | | | | 1.00: Medium TC Bit Resistance |
| | | | | | | 1.50m | | | 1.50: As above becoming pale grey, low to medium plasticity | | | |
| | | | | | 53.0 | 2.0 | | | | | | |
| | | | | | | 3.00m | | | 3.00: As above becoming grey and low strength | | | |
| | | | | | 52.0 | 3.0 | | | | | | |
| | | | | | | 4.00 | | | | | | |
| | | | | | 51.0 | 4.0 | | | | | | |
| | | | | | | 4.50m | | | 4.50: As above becoming low to medium strength | | | |
| | | | | | 50.0 | 5.0 | | | | | | |
| | | | | | | 6.00m | | | 4.50: As above becoming medium strength<br>BOREHOLE BH6 TERMINATED AT 1.50 m<br>Target depth | | | |
| | | | | | 49.0 | 6.0 | | | | | | |
| | | | | | | 7.00 | | | | | | |
| | | | | | 48.0 | 8.0 | | | | | | |

See Explanatory Notes for details of abbreviations & basis of descriptions.

SMEC AUSTRALIA



UPDATED SMEC LIBRARY_AGS 3_1.RTA 1_1 LIB 08_WITH FENCE TOOL_AND_CAD COLOUR.GLB Log SMEC NON-CORE DRILL HOLE LANE COVE.GPJ <<DrawingFile>> 01/12/2011 08:34 8.2.904

# NON-CORE DRILL HOLE - GEOLOGICAL LOG

**HOLE NO : BH7**

PROJECT : 266 Longueville Road, Lane Cove GI
LOCATION : Upper
CLIENT : Lane Cove Council
FEATURE : Bowling Green
FILE / JOB NO : 30011131
SHEET : 1 OF 1

POSITION : E: 330870.600, N: 6256040.032 (56 MGA94) SURFACE ELEVATION : 55.200 (AHD) ANGLE FROM HORIZONTAL : 90°

RIG TYPE : Edson 3000 MOUNTING : Truck CONTRACTOR : BHC Drilling DRILLER : C.W

DATE STARTED : 11/11/11 DATE COMPLETED : 11/11/11 DATE LOGGED : 11/11/11 LOGGED BY : A.G CHECKED BY : M.G

| DRILLING | | | | | | MATERIAL | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| PROGRESS: DRILLING & CASING | PROGRESS: WATER | DRILLING PENETRATION | GROUND WATER LEVELS | SAMPLES & FIELD TESTS | ELEVATION (RL) / DEPTH (m) | GRAPHIC LOG | CLASSIFICATION SYMBOL | MATERIAL DESCRIPTION<br>Soil Type, Plasticity or Particle Characteristic, Colour, Secondary and Minor Components | MOISTURE CONDITION | CONSISTENCY RELATIVE DENSITY | STRUCTURE & Other Observations |
| ADT | | E | | ES<br>0.20m | 55.0 / 0.0 | | SM | Silty SAND<br>fine to medium grained, brown, with rootlets in the top 100mm<br>0.30m | D | | TOPSOIL |
| | | | | | | | CL | Gravelly Sandy CLAY<br>low plasticity, brown, gravels are sub-angular<br>1.10m | | | FILL |
| | | | | 1.30m<br>ES<br>**1.50m**<br>SPT<br>3, 3, 7<br>N=10 | 54.0 / 1.0 | | CH | Sandy Silty CLAY<br>medium to high plasticity, grey mottled orange, with ironstone gravels<br>1.80m | M | St | RESIDUAL SOIL<br>1.50: PID = 1.5ppm<br>1.60: P.P = 200kPa<br>1.70: Minor seepage at soil/rock interface |
| | | M | | 1.95m | 53.0 / 2.0 | | | SANDSTONE<br>fine to medium grained, orange brown, estimate very low to low strength becoming low to medium strength and pale grey at 2.7m | | | WEATHERED ROCK<br>1.80: Low TC Bit Resistance |
| | | | | 2.70m | | | | | | | 2.70: Medium TC Bit Resistance |
| | | H | | ES<br>2.90m | | | | 3.00m | | | |
| | | | | | 52.0 / 3.0 | | | BOREHOLE BH7 TERMINATED AT 3.00 m<br>Target depth | | | |
| | | | | | 51.0 / 4.0 | | | | | | |
| | | | | | 50.0 / 5.0 | | | | | | |
| | | | | | 49.0 / 6.0 | | | | | | |
| | | | | | 48.0 / 7.0 | | | | | | |
| | | | | | 8.0 | | | | | | |

See Explanatory Notes for details of abbreviations & basis of descriptions.

SMEC AUSTRALIA



UPDATED SMEC LIBRARY_AGS 3_1.RTA 1_1 LIB 08_WITH FENCE TOOL_AND_CAD COLOUR.GLB Log SMEC NON-CORE DRILL HOLE LANE COVE.GPJ <<DrawingFile>> 01/12/2011 08:34 8.2.904

# NON-CORE DRILL HOLE - GEOLOGICAL LOG

**HOLE NO : BH8**

PROJECT : 266 Longueville Road, Lane Cove GI
LOCATION : Upper
CLIENT : Lane Cove Council
FEATURE : Bowling Green
FILE / JOB NO : 30011131
SHEET : 1 OF 1

POSITION : E: 330866.718, N: 6256022.623 (56 MGA94) SURFACE ELEVATION : 55.200 (AHD) ANGLE FROM HORIZONTAL : 90°

RIG TYPE : Edson 3000 MOUNTING : Truck CONTRACTOR : BHC Drilling DRILLER : C.W

DATE STARTED : 11/11/11 DATE COMPLETED : 11/11/11 DATE LOGGED : 11/11/11 LOGGED BY : A.G CHECKED BY : M.G

| DRILLING | | | | | | | MATERIAL | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| PROGRESS: DRILLING & CASING | PROGRESS: WATER | DRILLING PENETRATION | GROUND WATER LEVELS | SAMPLES & FIELD TESTS | ELEVATION (RL) | DEPTH (m) | GRAPHIC LOG | CLASSIFICATION SYMBOL | MATERIAL DESCRIPTION<br>Soil Type, Plasticity or Particle Characteristic, Colour, Secondary and Minor Components | MOISTURE CONDITION | CONSISTENCY RELATIVE DENSITY | STRUCTURE & Other Observations |
| ADT | | E | | ES 0.20m | 55.0 | 0.0 | | SM | Silty SAND<br>fine to medium grained, brown, with rootlets in the top 100mm | D | | TOPSOIL |
| | | | | | | 0.30m | | | | | | |
| | | | | 1.50m<br>SPT 1, 2, 1 N=3 | 54.0 | 1.0 | | CL | Sandy Silty CLAY<br>low to medium plasticity, orange brown | M | S | FILL<br>1.50: PID = 1.5ppm<br>1.60: P.P = 25kPa |
| | | | | 1.95m | | 2.0 | | | | | | |
| | | | | 2.70m<br>ES 2.90m | 53.0 | | | CH | Silty CLAY<br>medium to high plasticity, brown | M to W | St | RESIDUAL SOIL<br>3.00: PID = 2.2ppm<br>3.10: P.P = 150kPa |
| | | | | 3.00m<br>SPT 3, 16, 14 N=30 | | 3.0 | | | | | | |
| | | | | 3.45m | 52.0 | 3.35m | | | SANDSTONE<br>fine to medium grained, orange brown, estimate very low to low strength becoming low to medium strength and pale grey at 4.3m | | | WEATHERED ROCK<br>3.35: Seepage at soil/rock interface<br>3.40: Low TC Bit Resistance |
| | | M | | 4.20m<br>ES 4.40m | 51.0 | 4.0 | | | | | | 4.30: Medium TC Bit Resistance |
| | | H | | | | 4.50m | | | BOREHOLE BH8 TERMINATED AT 4.50 m<br>Target depth | | | |
| | | | | | 50.0 | 5.0 | | | | | | |
| | | | | | 49.0 | 6.0 | | | | | | |
| | | | | | 48.0 | 7.0 | | | | | | |
| | | | | | | 8.0 | | | | | | |

See Explanatory Notes for details of abbreviations & basis of descriptions.

SMEC AUSTRALIA



UPDATED SMEC LIBRARY_AGS 3_1.RTA 1_1 LIB 08_WITH FENCE TOOL_AND_CAD COLOUR.GLB Log SMEC NON-CORE DRILL HOLE LANE COVE.GPJ <<DrawingFile>> 01/12/2011 08:34 8.2.904

# NON-CORE DRILL HOLE - GEOLOGICAL LOG

**HOLE NO : BH9**

PROJECT : 266 Longueville Road, Lane Cove GI
LOCATION : Upper
CLIENT : Lane Cove Council
FEATURE : Bowling Green
FILE / JOB NO : 30011131
SHEET : 1 OF 1

POSITION : E: 330848.230, N: 6256008.151 (56 MGA94) SURFACE ELEVATION : 55.500 (AHD) ANGLE FROM HORIZONTAL : 90°

RIG TYPE : Edson 3000 MOUNTING : Truck CONTRACTOR : BHC Drilling DRILLER : C.W

DATE STARTED : 11/11/11 DATE COMPLETED : 11/11/11 DATE LOGGED : 11/11/11 LOGGED BY : A.G CHECKED BY : M.G

| DRILLING | | | | | | | MATERIAL | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| PROGRESS: DRILLING & CASING | PROGRESS: WATER | DRILLING PENETRATION | GROUND WATER LEVELS | SAMPLES & FIELD TESTS | ELEVATION (RL) | DEPTH (m) | GRAPHIC LOG | CLASSIFICATION SYMBOL | MATERIAL DESCRIPTION<br>Soil Type, Plasticity or Particle Characteristic, Colour, Secondary and Minor Components | MOISTURE CONDITION | CONSISTENCY RELATIVE DENSITY | STRUCTURE & Other Observations |
| ADT | | E | | ES 0.20m | 55.0 | 0.0 | | SM | 0.20m Silty SAND<br>fine to medium grained, brown, with rootlets in the top 100mm | D | | TOPSOIL |
| | | M | | 0.50m | | | | | SANDSTONE<br>fine to medium grained, orange grey, estimate very low to low strength becoming low to medium strength and pale grey at 0.5m | | | WEATHERED ROCK<br>0.20: Very Low TC Bit Resistance<br>0.50: Medium TC Bit Resistance |
| | | H | | ES 0.70m | | 1.0 | | | | | | |
| | | | | | 54.0 | 1.50m | | | BOREHOLE BH9 TERMINATED AT 1.50 m<br>Target depth | | | |
| | | | | | 53.0 | 2.0 | | | | | | |
| | | | | | 52.0 | 3.0 | | | | | | |
| | | | | | 51.0 | 4.0 | | | | | | |
| | | | | | 50.0 | 5.0 | | | | | | |
| | | | | | 49.0 | 6.0 | | | | | | |
| | | | | | 48.0 | 7.0 | | | | | | |
| | | | | | | 8.0 | | | | | | |

See Explanatory Notes for details of abbreviations & basis of descriptions.

SMEC AUSTRALIA



UPDATED SMEC LIBRARY_AGS 3_1.RTA 1_1 LIB 08_WITH FENCE TOOL_AND_CAD COLOUR.GLB Log SMEC NON-CORE DRILL HOLE LANE COVE.GPJ <<DrawingFile>> 01/12/2011 08:34 8.2.904

# NON-CORE DRILL HOLE - GEOLOGICAL LOG

**HOLE NO : BH10**

PROJECT : 266 Longueville Road, Lane Cove GI
LOCATION : Lower
CLIENT : Lane Cove Council
FEATURE : Car Park
FILE / JOB NO : 30011131
SHEET : 1 OF 1

POSITION : E: 330887.837, N: 6256015.200 (56 MGA94) SURFACE ELEVATION : 49.500 (AHD) ANGLE FROM HORIZONTAL : 90°

RIG TYPE : Edson 3000 MOUNTING : Truck CONTRACTOR : BHC Drilling DRILLER : C.W

DATE STARTED : 10/11/11 DATE COMPLETED : 10/11/11 DATE LOGGED : 10/11/11 LOGGED BY : A.G CHECKED BY : M.G

| DRILLING | | | | | | | MATERIAL | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| PROGRESS: DRILLING & CASING | PROGRESS: WATER | DRILLING PENETRATION | GROUND WATER LEVELS | SAMPLES & FIELD TESTS | ELEVATION (RL) / DEPTH (m) | GRAPHIC LOG | CLASSIFICATION SYMBOL | MATERIAL DESCRIPTION<br>Soil Type, Plasticity or Particle Characteristic, Colour, Secondary and Minor Components | MOISTURE CONDITION | CONSISTENCY RELATIVE DENSITY | STRUCTURE & Other Observations |
| AD/T | | E | | | 49.0 / 0.0 | | SM | Silty SAND<br>fine to medium grained, brown, with rootlets in the top 100mm<br>0.30m | | | TOPSOIL<br>0.10: Triplicate ES Taken |
| | | | | | | | SM | Silty SAND<br>fine to medium grained, grey brown, with occasional angular gravels | D | VL to L | FILL |
| | | | | 1.50m<br>SPT<br>2, 1, 2<br>N=3<br>1.95m | 48.0 / 1.0 | | | 1.90m | | | 1.50: PID = 3.2ppm |
| | | | | | 47.0 / 2.0 | | SC | Clayey SAND<br>fine to medium grained, orange brown<br>2.60m | M to W | MD | RESIDUAL SOIL |
| | | M | | 2.70m<br>ES<br>2.90m | 46.0 / 3.0 | | | SANDSTONE<br>fine to medium grained, pale grey, estimate very low to low strength becoming low to medium strength at 3.3m<br>3.50m | | | 2.55: Seepage at soil/rock interface<br>WEATHERED ROCK<br>2.60: Low TC Bit Resistance<br>3.30: Medium TC Bit Resistance |
| | | H | | | 45.0 / 4.0 | | | BOREHOLE BH10 TERMINATED AT 3.50 m<br>Target depth | | | |
| | | | | | 44.0 / 5.0 | | | | | | |
| | | | | | 43.0 / 6.0 | | | | | | |
| | | | | | 42.0 / 7.0 | | | | | | |
| | | | | | 8.0 | | | | | | |

See Explanatory Notes for details of abbreviations & basis of descriptions.

SMEC AUSTRALIA



UPDATED SMEC LIBRARY_AGS 3_1.RTA 1_1 LIB 08_WITH FENCE TOOL_AND_CAD COLOUR.GLB Log SMEC NON-CORE DRILL HOLE LANE COVE.GPJ <<DrawingFile>> 01/12/2011 08:33 8.2.904

# NON-CORE DRILL HOLE - GEOLOGICAL LOG

**HOLE NO : BH11**

PROJECT : 266 Longueville Road, Lane Cove GI
LOCATION : Lower
CLIENT : Lane Cove Council
FEATURE : Bowling Green
FILE / JOB NO : 30011131
SHEET : 1 OF 2

POSITION : E: 330916.180, N: 6256014.449 (56 MGA94) SURFACE ELEVATION : 49.500 (AHD) ANGLE FROM HORIZONTAL : 90°

RIG TYPE : Edson 3000 MOUNTING : Truck CONTRACTOR : BHC Drilling DRILLER : C.W

DATE STARTED : 10/11/11 DATE COMPLETED : 10/11/11 DATE LOGGED : 10/11/11 LOGGED BY : A.G CHECKED BY : M.G

| DRILLING | | | | | | | | MATERIAL | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| PROGRESS: DRILLING & CASING | PROGRESS: WATER | DRILLING PENETRATION | GROUND WATER LEVELS | SAMPLES & FIELD TESTS | ELEVATION (RL) | DEPTH (m) | GRAPHIC LOG | CLASSIFICATION SYMBOL | MATERIAL DESCRIPTION<br>Soil Type, Plasticity or Particle Characteristic, Colour, Secondary and Minor Components | MOISTURE CONDITION | CONSISTENCY RELATIVE DENSITY | STRUCTURE & Other Observations |
| AD/T | | E | | ES<br>0.20m | 49.0 | 0.0 | | SM | Silty SAND<br>fine to medium grained, brown, with rootlets in the top 100mm<br>0.40m | D | | TOPSOIL<br>0.20: PID = 1.1ppm |
| | | | | | | | | SW | Gravelly Clayey SAND<br>fine to coarse grained, orange brown, with high plasticity clay bands<br>1.00m | D to M | L | FILL |
| | | | | 1.30m<br>ES<br>**1.50m**<br>SPT<br>2, 2, 1<br>N=3<br>1.95m | 48.0 | 1.0<br>2.0 | | CH | Gravelly Sandy CLAY<br>medium to high plasticity, grey brown, with brick fragments, ash, porcelain and glass<br>2.50m | M | S | 1.00: Mixed penetration with cobbles and boulders in fill<br>1.50: PID = 1.7ppm |
| | | | | 3.00m<br>SPT<br>8, 8, 8<br>N=16<br>3.45m | 47.0<br>46.0 | 3.0 | | | Silty Sandy GRAVEL<br>fine to coarse grained, orange brown, with brick fragments and angular sandstone gravel<br>4.00: Clay Lenses | | | 3.00: PID = 2.2ppm<br>3.10: P.P = 150kPa |
| | | E-H | | 4.30m<br>ES<br>**4.50m**<br>SPT<br>6, 10, 6<br>N=16<br>4.95m | 45.0 | 4.0<br>5.0 | | GW | | D | MD | 4.50: PID = 10.5ppm |
| | | | | 5.70m<br>ES<br>5.90m<br>6.00m<br>SPT<br>7, 7, 6<br>N=13<br>6.45m | 44.0<br>43.0 | 6.0<br>7.0 | | | | | | 6.00: PID = 1.6ppm<br>7.50: PID = 1.2ppm |
| | | | | | 42.0 | 8.0 | | | | | | |

See Explanatory Notes for details of abbreviations & basis of descriptions.

SMEC AUSTRALIA



UPDATED SMEC LIBRARY_AGS 3_1 RTA 1_1 LIB 08_WITH FENCE TOOL_AND_CAD COLOUR.GLB Log SMEC NON-CORE DRILL HOLE LANE COVE.GPJ <<DrawingFile>> 01/12/2011 08:33 8.2.904

# NON-CORE DRILL HOLE - GEOLOGICAL LOG

**HOLE NO : BH11**

PROJECT : 266 Longueville Road, Lane Cove GI
LOCATION : Lower
CLIENT : Lane Cove Council
FEATURE : Bowling Green
FILE / JOB NO : 30011131
SHEET : 2 OF 2

POSITION : E: 330916.180, N: 6256014.449 (56 MGA94) SURFACE ELEVATION : 49.500 (AHD) ANGLE FROM HORIZONTAL : 90°

RIG TYPE : Edson 3000 MOUNTING : Truck CONTRACTOR : BHC Drilling DRILLER : C.W

DATE STARTED : 10/11/11 DATE COMPLETED : 10/11/11 DATE LOGGED : 10/11/11 LOGGED BY : A.G CHECKED BY : M.G

| DRILLING | | | | | | MATERIAL | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| PROGRESS: DRILLING & CASING | PROGRESS: WATER | DRILLING PENETRATION | GROUND WATER LEVELS | SAMPLES & FIELD TESTS | ELEVATION (RL) / DEPTH (m) | GRAPHIC LOG | CLASSIFICATION SYMBOL | MATERIAL DESCRIPTION<br>Soil Type, Plasticity or Particle Characteristic, Colour, Secondary and Minor Components | MOISTURE CONDITION | CONSISTENCY RELATIVE DENSITY | STRUCTURE & Other Observations |
| AD/T | | E-H | | | 8.0 | | GW | Silty Sandy GRAVEL<br>fine to coarse grained, orange brown, with brick fragments and angular sandstone gravel *(continued)* | D | MD | |
| | | | | 8.60m | | | | | | | 8.55: Seepage at soil/rock interface |
| | | M | | ES<br>8.80m | 41.0 | | | SANDSTONE<br>fine to medium grained, orange brown, estimate very low to low strength becoming low to medium strength and pale grey at 9.0m | | | WEATHERED ROCK<br>8.60: Low TC Bit Resistance |
| | | H | | | 9.0 | | | | | | 9.00: Medium TC Bit Resistance |
| | | | | | 9.40m | | | BOREHOLE BH11 TERMINATED AT 9.40 m<br>Target depth | | | |
| | | | | | 40.0 | | | | | | |
| | | | | | 10.0 | | | | | | |
| | | | | | 39.0 | | | | | | |
| | | | | | 11.0 | | | | | | |
| | | | | | 38.0 | | | | | | |
| | | | | | 12.0 | | | | | | |
| | | | | | 37.0 | | | | | | |
| | | | | | 13.0 | | | | | | |
| | | | | | 36.0 | | | | | | |
| | | | | | 14.0 | | | | | | |
| | | | | | 35.0 | | | | | | |
| | | | | | 15.0 | | | | | | |
| | | | | | 34.0 | | | | | | |
| | | | | | 16.0 | | | | | | |

See Explanatory Notes for details of abbreviations & basis of descriptions.

SMEC AUSTRALIA

UPDATED SMEC LIBRARY_AGS 3_1 RTA 1_1 LIB 08_WITH FENCE TOOL_AND_CAD COLOUR.GLB Log SMEC NON-CORE DRILL HOLE LANE COVE.GPJ <<DrawingFile>> 01/12/2011 08:33 8.2.904

# NON-CORE DRILL HOLE - GEOLOGICAL LOG

**HOLE NO : BH12**

PROJECT : 266 Longueville Road, Lane Cove GI
LOCATION : Lower
CLIENT : Lane Cove Council
FEATURE : Bowling Green
FILE / JOB NO : 30011131
SHEET : 1 OF 1

POSITION : E: 330900.328, N: 6256004.913 (56 MGA94) SURFACE ELEVATION : 49.500 (AHD) ANGLE FROM HORIZONTAL : 90°

RIG TYPE : Edson 3000 MOUNTING : Truck CONTRACTOR : BHC Drilling DRILLER : C.W

DATE STARTED : 10/11/11 DATE COMPLETED : 10/11/11 DATE LOGGED : 10/11/11 LOGGED BY : A.G CHECKED BY : M.G

| DRILLING | | | | | | | MATERIAL | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| PROGRESS: DRILLING & CASING | PROGRESS: WATER | DRILLING PENETRATION | GROUND WATER LEVELS | SAMPLES & FIELD TESTS | ELEVATION (RL) / DEPTH (m) | GRAPHIC LOG | CLASSIFICATION SYMBOL | MATERIAL DESCRIPTION<br>Soil Type, Plasticity or Particle Characteristic, Colour, Secondary and Minor Components | MOISTURE CONDITION | CONSISTENCY RELATIVE DENSITY | STRUCTURE & Other Observations |
| AD/T | | E | | ES<br>0.20m | 49.0 / 0.0 | | SM | Silty SAND<br>fine to medium grained, brown, with rootlets in the top 100mm<br>0.40m | D | S | TOPSOIL |
| | | | | 1.30m<br>ES<br>**1.50m**<br>SPT<br>3, 1, 2 N=3<br>1.95m | 48.0 / 1.0 | | CL | Sandy Silty CLAY<br>medium plasticity, brown, with angular gravels, brick fragments, ash and glass sand | | | FILL<br>1.50: PID = 1.5ppm<br>1.60: P.P = 40kPa |
| | | | | 3.00m<br>SPT<br>3, 7, 8<br>N=15<br>3.45m | 47.0 / 3.0 | | | | | | 3.00: PID = 2.7ppm<br>3.10: P.P = 25kPa |
| | | | | 4.30m<br>ES<br>**4.50m**<br>SPT<br>2, 3, 3 N=6<br>4.95m | 46.0 / 4.0 | | GC | Clayey Sandy GRAVEL<br>medium to coarse grained, sub-angular, grey brown<br>4.90m | M to W | MD / L | 4.50: PID = 3ppm 0 Slight Odour<br>4.80: Seepage at soil/rock interface |
| | | M | | 5.70m | 45.0 / 5.0 | | | SANDSTONE<br>fine to medium grained, grey brown, estimate very low to low strength becoming low to medium strength and pale grey at 5.7m | | | WEATHERED ROCK<br>4.90: Low TC Bit Resistance |
| | | H | | ES<br>5.90m | 44.0 / 6.0 | | | 6.00m | | | 5.70: Medium TC Bit Resistance |
| | | | | | 43.0 / 7.0 | | | BOREHOLE BH12 TERMINATED AT 6.00 m<br>Target depth | | | |
| | | | | | 42.0 / 8.0 | | | | | | |

See Explanatory Notes for details of abbreviations & basis of descriptions.

SMEC AUSTRALIA



UPDATED SMEC LIBRARY_AGS 3_1.RTA 1_1 LIB 08_WITH FENCE TOOL_AND_CAD COLOUR.GLB Log SMEC NON-CORE DRILL HOLE LANE COVE.GPJ <<DrawingFile>> 01/12/2011 08:34 8.2.904

# NON-CORE DRILL HOLE - GEOLOGICAL LOG

**HOLE NO : BH13**

PROJECT : 266 Longueville Road, Lane Cove GI
LOCATION : Lower
CLIENT : Lane Cove Council
FEATURE : Bowling Green
FILE / JOB NO : 30011131
SHEET : 1 OF 2

POSITION : E: 330915.675, N: 6256004.801 (56 MGA94) SURFACE ELEVATION : 49.500 (AHD) ANGLE FROM HORIZONTAL : 90°

RIG TYPE : Edson 3000 MOUNTING : Truck CONTRACTOR : BHC Drilling DRILLER : C.W

DATE STARTED : 10/11/11 DATE COMPLETED : 10/11/11 DATE LOGGED : 10/11/11 LOGGED BY : A.G CHECKED BY : M.G

| DRILLING | | | | | | | MATERIAL | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| PROGRESS: DRILLING & CASING | PROGRESS: WATER | DRILLING PENETRATION | GROUND WATER LEVELS | SAMPLES & FIELD TESTS | ELEVATION (RL) | DEPTH (m) | GRAPHIC LOG | CLASSIFICATION SYMBOL | MATERIAL DESCRIPTION<br>Soil Type, Plasticity or Particle Characteristic, Colour, Secondary and Minor Components | MOISTURE CONDITION | CONSISTENCY RELATIVE DENSITY | STRUCTURE & Other Observations |
| AD/T | | E | | ES<br>0.20m | 49.0 | 0.0 | | SM | Silty SAND<br>fine to medium grained, brown, with rootlets in the top 100mm<br>0.40m | D | | TOPSOIL<br>0.20: PID = 1.1ppm |
| | | | | 1.30m<br>ES<br>**1.50m**<br>SPT<br>3, 2, 3<br>N=5<br>1.95m | 48.0 | 1.0<br>2.0 | | CL | Gravelly Silty CLAY<br>low to medium plasticity, pale brown to grey, with angular gravels, brick fragments, ash and glass gravel<br>2.50m | | S to F | FILL<br>1.50: PID = 1.7ppm |
| | | E-H | | 2.70m<br>ES<br>2.90m<br>3.00m<br>SPT<br>3, 11, 7<br>N=18<br>3.45m | 47.0<br>46.0 | 3.0 | | SW | Silty Gravelly SAND<br>fine to coarse grained, grey, with brick fragments, ash, porcelain and glass silt | | D | 3.00: PID = 1.9ppm<br>3.50: Mixed penetration with cobbles and boulders in fill |
| | | | | 4.30m<br>ES<br>**4.50m**<br>SPT<br>11, 11, 12<br>N=23<br>4.95m | 45.0 | 4.0<br>5.0 | | | | | | 4.50: PID = 11ppm |
| | | | | 5.80m<br>ES<br>**6.00m**<br>SPT<br>2, 5, 3<br>N=8<br>6.45m | 44.0<br>43.0 | 6.0 | | | 6.40 - 7.00: Medium plasticity clay band | | L - MD | 6.00: PID = 1.6ppm |
| | | | | 7.30m<br>ES<br>**7.50m**<br>SPT<br>2, 1, 0<br>N=1<br>7.95m | 42.0 | 7.0<br>8.0 | | | | | VL | 7.30: Duplicate sample taken<br>7.50: PID = 1ppm |

See Explanatory Notes for details of abbreviations & basis of descriptions.

SMEC AUSTRALIA



UPDATED SMEC LIBRARY_AGS 3_1 RTA 1_1 LIB 08_WITH FENCE TOOL_AND_CAD COLOUR.GLB Log SMEC NON-CORE DRILL HOLE LANE COVE.GPJ <<DrawingFile>> 01/12/2011 08:34 8.2.904

# NON-CORE DRILL HOLE - GEOLOGICAL LOG

**HOLE NO : BH13**

PROJECT : 266 Longueville Road, Lane Cove GI
LOCATION : Lower
CLIENT : Lane Cove Council
FEATURE : Bowling Green
FILE / JOB NO : 30011131
SHEET : 2 OF 2

POSITION : E: 330915.675, N: 6256004.801 (56 MGA94) SURFACE ELEVATION : 49.500 (AHD) ANGLE FROM HORIZONTAL : 90°

RIG TYPE : Edson 3000 MOUNTING : Truck CONTRACTOR : BHC Drilling DRILLER : C.W

DATE STARTED : 10/11/11 DATE COMPLETED : 10/11/11 DATE LOGGED : 10/11/11 LOGGED BY : A.G CHECKED BY : M.G

| DRILLING | | | | | | MATERIAL | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| PROGRESS: DRILLING & CASING | PROGRESS: WATER | DRILLING PENETRATION | GROUND WATER LEVELS | SAMPLES & FIELD TESTS | ELEVATION (RL) / DEPTH (m) | GRAPHIC LOG | CLASSIFICATION SYMBOL | MATERIAL DESCRIPTION<br>Soil Type, Plasticity or Particle Characteristic, Colour, Secondary and Minor Components | MOISTURE CONDITION | CONSISTENCY RELATIVE DENSITY | STRUCTURE & Other Observations |
| | | E-H | | | 8.0 | | SW | 8.10m | W | VL | 8.00: Seepage at soil/rock interface |
| AD/T | | M | | | | | | SANDSTONE<br>fine to medium grained, orange brown, estimate very low to low strength becoming low to medium strength and pale grey at 8.5m | | | WEATHERED ROCK<br>8.10: Low TC Bit Resistance |
| | | H | | | 41.0 | | | 8.70m | | | 8.50: Medium TC Bit Resistance |
| | | | | | | | | BOREHOLE BH13 TERMINATED AT 8.70 m<br>Target depth | | | |
| | | | | | 9.0 | | | | | | |
| | | | | | 40.0 | | | | | | |
| | | | | | 10.0 | | | | | | |
| | | | | | 39.0 | | | | | | |
| | | | | | 11.0 | | | | | | |
| | | | | | 38.0 | | | | | | |
| | | | | | 12.0 | | | | | | |
| | | | | | 37.0 | | | | | | |
| | | | | | 13.0 | | | | | | |
| | | | | | 36.0 | | | | | | |
| | | | | | 14.0 | | | | | | |
| | | | | | 35.0 | | | | | | |
| | | | | | 15.0 | | | | | | |
| | | | | | 34.0 | | | | | | |
| | | | | | 16.0 | | | | | | |

See Explanatory Notes for details of abbreviations & basis of descriptions.

SMEC AUSTRALIA



UPDATED SMEC LIBRARY_AGS 3_1.RTA 1_1 LIB 08_WITH FENCE TOOL_AND_CAD COLOUR.GLB Log SMEC NON-CORE DRILL HOLE LANE COVE.GPJ <<DrawingFile>> 01/12/2011 08:34 8.2.904

# NON-CORE DRILL HOLE - GEOLOGICAL LOG

**HOLE NO : BH14**

PROJECT : 266 Longueville Road, Lane Cove GI
LOCATION : Lower
CLIENT : Lane Cove Council
FEATURE : Bowling Green
FILE / JOB NO : 30011131
SHEET : 1 OF 1

POSITION : E: 330881.749, N: 6255997.518 (56 MGA94) SURFACE ELEVATION : 49.500 (AHD) ANGLE FROM HORIZONTAL : 90°

RIG TYPE : Edson 3000 MOUNTING : Truck CONTRACTOR : BHC Drilling DRILLER : C.W

DATE STARTED : 10/11/11 DATE COMPLETED : 10/11/11 DATE LOGGED : 10/11/11 LOGGED BY : A.G CHECKED BY : M.G

| DRILLING | | | | | | | MATERIAL | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| PROGRESS: DRILLING & CASING | PROGRESS: WATER | DRILLING PENETRATION | GROUND WATER LEVELS | SAMPLES & FIELD TESTS | ELEVATION (RL) / DEPTH (m) | GRAPHIC LOG | CLASSIFICATION SYMBOL | MATERIAL DESCRIPTION<br>Soil Type, Plasticity or Particle Characteristic, Colour, Secondary and Minor Components | MOISTURE CONDITION | CONSISTENCY RELATIVE DENSITY | STRUCTURE & Other Observations |
| AD/T | | E | | 1.30m<br>ES<br>**1.50m**<br>SPT<br>1, 1, 2<br>N=3<br>1.95m | 49.0 / 0.0 | | SM | Silty SILT<br>fine to medium, brown, with rootlets in the top 100mm | D | S | TOPSOIL<br>0.20: PID = 2.2ppm |
| | | | | | 48.0 / 1.0 | | CH | Sandy Silty CLAY<br>high plasticity, grey orange brown | | | RESIDUAL SOIL<br>1.50: PID = 2.7ppm |
| | | M | | | 47.0 / 2.0 | | | SANDSTONE<br>fine to medium grained, orange, estimate very low to low strength becoming low to medium strength and pale grey at 3.0m | M to W | | 2.00: Seepage at soil/rock interface<br>WEATHERED ROCK<br>2.10: Low TC Bit Resistance |
| | | H | | | 46.0 / 3.0 | | | | | | 3.00: Medium TC Bit Resistance |
| | | | | | 45.0 / 4.0 | | | BOREHOLE BH14 TERMINATED AT 3.50 m<br>Target depth | | | |
| | | | | | 44.0 / 5.0 | | | | | | |
| | | | | | 43.0 / 6.0 | | | | | | |
| | | | | | 42.0 / 7.0 | | | | | | |
| | | | | | 8.0 | | | | | | |

0.60m
2.10m
3.50m

See Explanatory Notes for details of abbreviations & basis of descriptions.

SMEC AUSTRALIA



UPDATED SMEC LIBRARY_AGS 3_1 RTA 1_1 LIB 08_WITH FENCE TOOL_AND_CAD COLOUR.GLB Log SMEC NON-CORE DRILL HOLE LANE COVE.GPJ <<DrawingFile>> 01/12/2011 08:34 8.2.904

# NON-CORE DRILL HOLE - GEOLOGICAL LOG

**HOLE NO : BH15**

PROJECT : 266 Longueville Road, Lane Cove GI
LOCATION : Lower
CLIENT : Lane Cove Council
FEATURE : Bowling Green
FILE / JOB NO : 30011131
SHEET : 1 OF 1

POSITION : E: 330912.721, N: 6255990.120 (56 MGA94) SURFACE ELEVATION : 49.500 (AHD) ANGLE FROM HORIZONTAL : 90°

RIG TYPE : Edson 3000 MOUNTING : Truck CONTRACTOR : BHC Drilling DRILLER : C.W

DATE STARTED : 10/11/11 DATE COMPLETED : 10/11/11 DATE LOGGED : 10/11/11 LOGGED BY : A.G CHECKED BY : M.G

| DRILLING | | | | | | | MATERIAL | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| PROGRESS: DRILLING & CASING | PROGRESS: WATER | DRILLING PENETRATION | GROUND WATER LEVELS | SAMPLES & FIELD TESTS | ELEVATION (RL) / DEPTH (m) | GRAPHIC LOG | CLASSIFICATION SYMBOL | MATERIAL DESCRIPTION<br>Soil Type, Plasticity or Particle Characteristic, Colour, Secondary and Minor Components | MOISTURE CONDITION | CONSISTENCY RELATIVE DENSITY | STRUCTURE & Other Observations |
| AD/T | | E | | 0.10m<br>ES<br>0.30m | 49.0 / 0.0 | | SM | Silty SAND<br>fine to medium grained, brown, with rootlets in the top 100mm | | | TOPSOIL<br>0.20: PID = 1.3ppm |
| | | | | | | | | 0.40m | | | |
| | | | | | | | SW | Gravelly Silty SAND<br>fine to coarse grained, pale brown, with brick fragments and clay layers | | L | FILL |
| | | | | 1.30m | 1.0 | | | 1.30m | | | |
| | | E-H | | ES<br>1.50m<br>1.70m<br>SPT<br>3, 1, 3<br>N=4<br>2.15m | 48.0 / 2.0 | | CL | Sandy Silty CLAY<br>medium plasticity, brown, with occasional medium to coarse grained gravels | | F | 1.30: Mixed penetration with cobbles and boulders in fill<br>1.50: PID = 0.9ppm |
| | | | | 2.70m<br>ES<br>2.90m<br>3.00m<br>SPT<br>6, 16, 13<br>N=29<br>3.45m | 47.0 / 3.0 | | | | | | 3.00: PID = 1.4ppm |
| | | | | | | | | 3.20m | | | |
| | | | | | 46.0 / 4.0 | | | Gravelly Clayey SAND<br>fine to coarse grained, grey to orange brown, with brick fragments, ash, porcelain and glass | D | | |
| | | | | 4.20m<br>ES<br>4.40m<br>4.50m<br>SPT<br>12, 16, 12<br>N=28<br>4.95m | 45.0 / 5.0 | | SW | 4.70 - 6.80 - Becoming grey gravelly sand | | D - VD | 4.50: PID = 1.3ppm |
| | | | | 5.70m<br>ES<br>5.90m<br>6.00m<br>SPT<br>18, 13,<br>>25100mm<br>N=>38<br>6.45m | 44.0 / 6.0 | | | | | | 6.00: PID = 3.3ppm |
| | | | | | 43.0 / 7.0 | | | | W to M | | 6.70: Seepage at soil/rock interface |
| | | | | | | | | 6.80m | | | |
| | | M | | | | | | SANDSTONE<br>fine to medium grained, orange grey, estimate very low to low strength becoming low to medium strength and pale grey at 7.2m | | | WEATHERED ROCK<br>6.80: Low TC Bit Resistance |
| | | H | | | | | | | | | 7.20: Medium TC Bit Resistance |
| | | | | | | | | 7.40m | | | |
| | | | | | 42.0 / 8.0 | | | BOREHOLE BH15 TERMINATED AT 7.40 m<br>Target depth | | | |

See Explanatory Notes for details of abbreviations & basis of descriptions.

SMEC AUSTRALIA



UPDATED SMEC LIBRARY_AGS 3_1 RTA 1_1 LIB 08_WITH FENCE TOOL_AND_CAD COLOUR.GLB Log SMEC NON-CORE DRILL HOLE LANE COVE.GPJ <<DrawingFile>> 01/12/2011 08:34 8.2.904

# LRM Groundwater Fieldsheets

LRM GLOBAL

## GENERAL INFORMATION

Client: O2 Unity — Site: Lane Cove

Bore ID: Cw02 — Date: 14/5/18

Bore Condition: Good

Well Cap Secure: Yes

Bore Locked: No — Locking Type:

**Weather Conditions:** Sunny and clear.

Wind Speed: — Wind Direction:

Weather Conditions (Preceding days):

Air Temp °C: — Atm. Pressure:

**Bore GPS Location:** (MAP Datum - AUS GEOD '66) S: E:

## PURGING & SAMPLE COLLECTION INFORMATION

Field Meter Used:

Flow Through Cell Used:

Depth Tape Used: ✓

Decontamination Procedure Carried Out: ✓

Sampled By: TW

Time sample taken:

Metals Sample Field Filtered: ✓

Filter Type:

Samples placed on ice for transport: ✓

Sampling Device:

| | |
|---|---|
| 1. Stainless Steel Bailer | |
| 2. Downhole Submersible Pump | |
| 3. QED Well Wizard Bladder Pump | |
| 4. Syphon Tube with Non Return Valve | |
| 5. Sample Pro Micro Purge Pump | X |
| 6. Other | |

## Field Measurements and Stabilisation Record

| Time | Purge Rate (L/min) | Volume Purged (L) | Temp (°C) | Electrical Cond. (uS/cm) | pH (Units) | Redox (mV) | Dissolved Oxygen (mg/L) | SWL (mbTOC) | Appearance (colour, turbidity, odour, gas) |
|---|---|---|---|---|---|---|---|---|---|
| Stabilisation Criteria | | | +/-0.5 | +/-3% | +/-0.05 | +/-10 | +/-10% | < 0.50m | |
| 0845 | 0.2 | 1.2 | 18.86 | 357 | 5.00 | 185 | 6.20 | | Slightly turbid, no odour. |
| 0850 | 0.2 | 1.2 | 19.2 | 346 | 5.00 | 188 | 5.39 | | |
| 0855 | 0.2 | 1.4 | 19.1 | 344 | 5.12 | 188 | 4.99 | | |
| 0900 | 0.2 | 1.6 | 19.2 | 344 | 5.11 | 189 | 5.18 | | |
| Total vol purged (L): | | | | | | Sample Appearance - | | | |

Field Meter Calibration reference sheet:

## GAUGING INFORMATION

Pre-purging SWL (m bTOC) - PVC north side: 6.70

Ground Level to TOC (m) - PVC north side: Flush

Pre-purging SWL (m bGL):

Total Depth of Bore (m bTOC) - PVC north side: 11.1

Pump inlet placement (m bTOC) - PVC north side: 7.0 ~

Post Sampling SWL (m bTOC) - PVC north side:

## Sample Containers Used

| | Preservative | Sample Container |
|---|---|---|
| Nil | | |
| HNO3(Metals) | | |
| H2SO4 | | |
| HCl(VOC) | | |
| Other | | |

No of Sample Containers:

Volume of sample collected (L): 1.6L.

General Comments:

Inner Well Casing Diameter

50mm: ✓ 100mm:

Other:

| | |
|---|---|
| Lab No. : | |
| Report No. : | |

LRM GLOBAL

## GENERAL INFORMATION

Client: Oz Unity  Site: Lorne Love

Bore ID: GW01  Date: 14/5/18

Bore Condition: Good

Well Cap Secure: Yes

Bore Locked: No  Locking Type: _____

**Weather Conditions:** Sunny Clear.

Wind Speed: _____  Wind Direction: _____

Weather Conditions (Preceding days): _____

Air Temp °C: _____  Atm. Pressure: _____

**Bore GPS Location:** (MAP Datum - AUS GEOD' 66)  S: _____  E: _____

## PURGING & SAMPLE COLLECTION INFORMATION

Field Meter Used: _____

Flow Through Cell Used: _____

Depth Tape Used: ✓

Decontamination Procedure Carried Out: ✓

Sampled By: SK

Time sample taken: ✓

Metals Sample Field Filtered: ✓

Filter Type: ✓

Samples placed on ice for transport: ✓

Sampling Device:

| | |
|---|---|
| 1. Stainless Steel Bailer | |
| 2. Downhole Submersible Pump | |
| 3. QED Well Wizard Bladder Pump | |
| 4. Syphon Tube with Non Return Valve | |
| 5. Sample Pro Micro Purge Pump | X |
| 6. Other _____ | |

## Field Measurements and Stabilisation Record

| Time | Purge Rate (L/min) | Volume Purged (L) | Temp (°C) | Electrical Cond. (uS/cm) | pH (Units) | Redox (mV) | Dissolved Oxygen (mg/L) | SWL (mbTOC) | Appearance (colour, turbidity, odour, gas) |
|---|---|---|---|---|---|---|---|---|---|
| Stabilisation Criteria | | | +/-0.5 | +/-3% | +/-0.05 | +/-10 | +/-10% | < 0.50m | |
| 0735 | 0.2 | 1.2 | 18.4 | 260 | 4.51 | 200 | 6.31 | | Clear, No odour |
| 0740 | 0.3 | 1.3 | 19.4 | 294 | 4.53 | 211 | 6.21 | | |
| 0745 | 0.3 | 1.6 | 19.5 | 272 | 4.58 | 212 | 6.00 | | |
| 0750 | 0.3 | 1.9 | 19.6 | 277 | 4.61 | 214 | 5.76 | | |
| Total vol purged (L): | | | | | | Sample Appearance - | | | |

Dup 01 + Split 01 collected.

Field Meter Calibration reference sheet: _____

## GAUGING INFORMATION

Pre-purging SWL (m bTOC) - PVC north side: 4.45

Ground Level to TOC (m) - PVC north side: 0.00

Pre-purging SWL (m bGL): _____

Total Depth of Bore (m bTOC) - PVC north side: 9.2

Pump inlet placement (m bTOC) - PVC north side: 7.5 m

Post Sampling SWL (m bTOC) - PVC north side: _____

General Comments: Dup 01 + Split 01

## Sample Containers Used

| | Preservative | Sample Container |
|---|---|---|
| Nil | | |
| HNO3(Metals) | | |
| H2SO4 | | |
| HCl(VOC) | | |
| Other | | |

No of Sample Containers: _____

Volume of sample collected (L): 1.6 L.

**Inner Well Casing Diameter**

| 50mm: ✓ | 100mm: |
|---|---|
| Other: | |

| | |
|---|---|
| Lab No. : | |
| Report No. : | |

# EP Risk Groundwater Fieldsheets

EP RISK

## Groundwater Sampling Field Parameter Form

| | |
|---|---|
| **Job Number:** 27380 | **Date:** 3/8/18 |
| **Project:** Lane Cove GME | **Well Number:** GW01 |
| **Location:** 266 Longueville Rd, Lane Cove | **Sampler(s):** NM |

### Field Measurements

| | | | |
|---|---|---|---|
| Organic vapours in well: | 0.1 | ppm | Measurement device: PID |
| Depth to Groundwater: | 4.32 | mBTOC | Measurement Device: IP Probe |
| Depth to Immiscible Layer: | — | mBTOC | Measurement Device: |
| Thickness to Immiscible Layer: | — | m | |
| Well Depth: | 9.19 | mBTOC | Source: IP Probe |
| Thickness of Groundwater Column: | ~~4.87~~ | m | |

### Well Purging

Purge Method: Low flow - Micro Purge

Volume in Casing: L

Purge Volume: L

Start Purge: ~~9:25~~ 9:25

End Purge: 9:50

| TIME | TEMP (°C) | ELEC, COND. (+/- 3%) | DO | | REDOX (+/- 10mv) | pH (+/- 0.05) | SALINITY | Turbidity/TSS (+/- 10%) | PURGE RATE | PUMP INTAKE DEPTH (mBTOC) | Litres removed | Comments (appearance, odour, etc) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | mg/L | Sat % | | | | | | | | |
| 9:30 | 14.3 | 723 µS | 4.46 | | 10 mV | 4.11 | | 382 ppm | 10/2 | 5.3 | 0.2 | clear, colourless |
| 9:35 | 14.9 | 683 µS | 2.26 | | 7 mV | 4.12 | | 381 ppm | 10/2 | 5.3 | 0.2 | " " |
| 9:40 | 14.8 | 688 µS | 2.01 | | 9 mV | 4.10 | | 382 ppm | 10/2 | 5.3 | 0.2 | " " |
| 9:45 | 14.8 | 686 µS | 1.95 | | 12 mV | 4.10 | | 384 ppm | 10/2 | 5.3 | 0.2 | " " |
| 9:50 | 14.9 | 685 µS | 1.97 | | 11 mV | 4.09 | | 384 ppm | 10/2 | 5.3 | 0.2 | " " |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |

Sampled from 11:25 to 12:05

# Groundwater Sampling Field Parameter Form

| | | | |
|---|---|---|---|
| **Job Number:** | 27380 | **Date:** | 3/8/18 |
| **Project:** | Lane Cove GME | **Well Number:** | GW02 |
| **Location:** | 266 Longueville Rd, Lane Cove | **Sampler(s):** | NM |

## Field Measurements

| | | | | |
|---|---|---|---|---|
| Organic vapours in well: | 0.0 | ppm | Measurement device: | PID |
| Depth to Groundwater: | 6.73 | mBTOC | Measurement Device: | IP Probe |
| Depth to Immiscible Layer: | — | mBTOC | Measurement Device: | |
| Thickness to Immiscible Layer: | — | m | | |
| Well Depth: | 11.13 | mBTOC | Source: | IP Probe |
| Thickness of Groundwater Column: | 4.4 | m | | |

## Well Purging

Purge Method: Low flow - MicroPurge

| | | | |
|---|---|---|---|
| Volume in Casing: | L | Purge Volume: | L |
| Start Purge: | 10:50 | End Purge: | 11:20 |

| TIME | TEMP (°C) | ELEC, COND. (+/- 3%) | DO | | REDOX (+/- 10mv) | pH (+/- 0.05) | SALINITY | Turbidity/TSS (+/- 10%) | PURGE RATE | PUMP INTAKE DEPTH (mBTOC) | Litres removed | Comments (appearance, odour, etc) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | mg/L | Sat % | | | | | | | | |
| 10:55 | 16.5 | 304 µS | 4.63 | | 64 mV | 4.44 | | 158 PPm | 10/5 | ~~8~~ 7.7 | 0.4 | clear, odour/ess |
| 11:00 | 17.1 | 277 µS | 4.58 | | 66 mV | 4.26 | | 153 PPm | 10/5 | 7.7 | 0.4 | " " |
| 11:05 | 17.0 | 286 µS | ~~5.45~~ * | | 70 mV | ~~3.85~~ | | 152 PPm | 10/5 | 7.9 ** | 0.2 | " " |
| 11:10 | 16.8 | 287 µS | 3.47 | | 54 mV | 3.36 | | 154 PPm | 10/5 | 7.9 | 0.2 | " " |
| 11:15 | 16.7 | 289 µS | 3.26 | | 49 mV | 3.43 | | 154 PPm | 10/5 | 7.9 | 0.2 | " " |
| 11:20 | 16.7 | 288 µS | 3.42 | | 49 mV | 3.45 | | 153 PPm | 10/5 | 7.9 | 0.2 | " " |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |

* 4.68 #

** moved 0.2 m below due to drawdown, reduced ~~purge~~ rate.

# SOIL SAMPLING PROCEDURES

## Planning

Prior to soil sampling at a site, detailed planning is undertaken to review relevant site documentation, environmental standards, regulations and policies, as well as consultation with project stockholders directly interested or involved in the soil sampling works.

The planning phase of soil sampling works, details to the field scientist the proposed excavation method, the likely number and location of soil samples to be collected, the required analysis of the soil samples, the volume of soil samples to be collected and the appropriate sampling containers required.

Excavation is carried out with consideration to the following;

- Depth of assessment required;
- Likely encountered geology, including fill and natural material;
- Ease of access;
- Acceptable site disturbance; and
- Required analysis.

The volumes of soil samples collected and the sample containers used are determined, in consultation with the elected NATA accredited laboratory and vary based on the intended analysis required for soil samples at the project site.

## Cleaning Procedures

All sampling equipment is thoroughly cleaned before use and between the collection of soil samples to minimise the risk of cross contamination. This included all hand augers, trowels, scoops etc. and any other applicable equipment that was used. The cleaning procedure for all sampling equipment involved:

- Removal of all soil adhering to the sampling equipment with the use of a brush and washing in tap water;
- Wash the sampling equipment in a bucket with DECON 90 solution (or similar phosphate-free laboratory detergent);
- Rinse the sampling equipment in a second bucket with tap water; and
- Rinse the sampling equipment in a third bucket with de-ionised water.

As part of quality assurance and control of the sampling process, a ‘Rinsate Blank’ sample is taken using de-ionised water off the sampling equipment after the cleaning procedure has been completed. This ‘Rinsate Blank’ sample is analysed and the results used to indicate the effectiveness and integrity of the cleaning procedure.

## Sample Collection

The field scientist wore new, clean, nitrile gloves when handling all soil samples and cleaning soil sampling equipment. Soil samples were collected from consolidated material and placed into pre-

washed glass jars with tight fitting screw top lids provided by the laboratory to prevent the loss of volatile contaminants.

Each sample jar was labelled with the following information:

- LRM Global Job Number;
- Project Name;
- Date of Sampling; and
- Sample Name/Number (including depth of sample), all samples were given a unique name/number.

As per Australian Standards AS 4482.2 1999, using the zero headspace procedures, care is taken to disturb the soil as little as possible before being placed into the single-use jars and the sample 'exactly fits,' giving zero headspace.

A duplicate of all soil samples is collected in a PID bag, where screening of the head space with the PID to detect volatile organic compounds in soil gases is undertaken. The PID is 'zeroed' and then calibrated using a 100 ppm standard gas solution of Isobutylene as field works initiate and annually as specified by the manufacturer calibrated and serviced by an appropriately qualified technician.

## Sample Transportation and Documentation

Chain-of-custody documentation is completed for all soil samples collected at the project site. The COC includes the information listed above and the chemical analyses required for each sample.

All samples were cooled upon collection prior to analysis. This includes transportation and on-site storage. Samples were stored on-site and during transport in a laboratory chiller box with adequate ice bricks. Samples were transported by the field scientist who also completed the chain-of-custody documentation upon delivery to the receiving NATA accredited laboratories.

The COC, as per AS44821.1 2005, included the following information:

- Names and details of:
    - Person transferring samples.
    - Receiving Laboratory.
    - Client.
- Time and date of;
    - Samples being collected.
    - Samples received by the laboratory.
- Analysis required and turn-around-time.
- Samples with expected high contaminant levels.

## Setup and SWL Gauging Procedure

- Prior to departure to the site, field meters (DO, Temp, EC, Redox, pH) are calibrated and data recorded on a Field Meter Calibration Sheet - MGT DOC-FLDCAL.
- Prior to works commencing, review and complete the mgt Groundwater / Leachate/ Surface Water Sampling Job Safety Analysis Sheet. Work should not commence unless all activities can be complied with safely and the JSA is signed off.
- If historical records of the analysis results are available, determine the order of sampling from the least contaminated well to the most contaminated. If historical records are not available, ask the client to determine an order of sampling.
- At each borehole, take air temperature, GPS coordinates and barometric pressure – record on Groundwater Field Log Sheet - MGT DOC-GW2.
- Put a plastic sheet next to the well for placement of all sampling equipment.
- Open bore hole casing – use keys to unlock the casing where required – if the lock is jammed due to weather or dirt, clean it .

- Remove the borehole end cap and clear the top of the bore of dirt and other foreign material, taking care that no material enters the bore.
- Place the end cap in an area that will not receive any contamination from other material.
- If the borehole has any external or internal damage, or there is any source of possible contamination or future damage or contamination, record on the field sheet and take a photograph for future reference.
- Decontaminate the level sensor as per the decontamination procedure detailed below.

**GAUGING STANDING WATER LEVEL (SWL)**

- Lower the level sensor into the borehole until an audible electronic beep is heard – read the depth measurement from the tape against the top of the PVC pipe on the northern side (or nominated AHD reference point / client reference point) and record on the field log sheet as SWL (m bTOC). Lower the depth tape to the bottom of the bore and read the depth measurement from the tape against the top of the PVC pipe on the northern side (or nominated AHD reference point / client reference point) and record on the field log sheet as Total Depth of Bore (m bTOC).
- Carefully remove the depth tape from the bore, wiping tape dry with paper towel as it is withdrawn from the bore.
- Measure the distance from ground level to the top of the PVC pipe on the northern side (or nominated AHD reference point / client reference point) and record on the field log sheet.
- Compare recorded depths against previous depths on the historical spreadsheet and repeat gauging if possible inconsistencies are noted.

## Well Purging Procedures.

**LOW FLOW METHOD**

- Decontaminate the sampling equipment as per the decontamination procedure detailed below.
- Slowly lower the appropriate sampling equipment into the borehole taking care to minimise disturbance of the groundwater. If the client has a designated pump intake depth, set at that designated level.
- If a client has not designated an inlet depth the following guidelines should be used:
  - Standard landfill analysis –If well construction details are known, the pump intake should be located in the middle or slightly above the middle of the screened interval. If construction details are not known, place inlet at least ¾ of the way down the water column, but no further than 3.0m above the bottom of the bore.
  - Targeting LNAPL's – place inlet at the top of the water column, approximately 0.20m below the SWL (Placement of the pump at the top of the water column for sampling is only recommended in unconfined aquifers, screened across the water table, where this is the desired sampling point).
  - Targeting DNAPL'S – Place inlet at the bottom of the water column – client should be contacted in regards to specific sampling method and pump inlet placement.

- Other / unknown - If well construction details are known, the pump intake should be located in the middle or slightly above the middle of the screened interval. If construction details are not known, place inlet at least ¾ of the way down the water column, but no further than 3.0m above the bottom of the bore

- After installation of the sampling equipment, allow the SWL to stabilise – record the stabilised level on the field log sheet.
- Set the pump purge rate to approximately 0.1L/min and begin purging.
- Monitor Groundwater depth and purge rate and adjust the purge rate to minimise drawdown in the well. The purge rate can be increased up to 0.5L/min as long as drawdown in the well does not exceed 0.5m.
- During purging, run all purged water from the bore through the in-situ probe container where the pH, Temperature, Dissolved Oxygen, Redox Potential, Conductivity, SWL and Purge Water Appearance are measured every 3-5 min and recorded on the field sheet (purge water should be disposed of as re the method below).
- Purge the groundwater and note field parameters until three consecutive readings (see below) have been recorded.

| | |
|---|---|
| Temperature | +/- 0.5oC |
| Dissolved Oxygen | +/- 10% |
| pH | +/- 0.1 |
| Redox potential | +/- 10mV |
| Conductivity | +/- 3% |
| Sample Appearance | Consistent colour and turbidity |

- Record on the field sheet the Temperature, Conductivity, Dissolved Oxygen, pH, Redox, Sample Appearance, Sample Odour, and post purge SWL at the time of sampling.

## Sampling Procedure

- Prior to sampling, label each of the sample containers with the sample ID, Bore ID, Site and Date.
- The sampling rate should be the same or at a lower rate than the purge rate.
- Disconnect the sample discharge line from the flow through cell and use to fill up the sample containers. Place the sample volumes required in appropriately preserved containers, if necessary filter the groundwater in-situ prior to preserving for metals (refer to the above documents for suitable sample containers and preservatives). Containers should be filled in the following order:

  - vials for VOC's
  - bottle for organics
  - bottle for TOC
  - bottle for nutrient analysis
  - bottles with no preservative
  - bottle for metals analysis

- Take care to minimize disturbance and aeration of the sample whilst filling the containers. Place samples in an esky on ice and keep below 4°C during sampling and transport to the laboratory. Samples that are believed to be highly contaminated should be placed in a separate esky to uncontaminated / slightly contaminated samples.
- Record the SWL at the completion of the sampling on the field sheet against the top of the PVC pipe on the northern side (or nominated AHD reference point / client reference point) and record on the field log sheet.
- Remove the sampling equipment from the bore – if Syphon tubing or bladder pump systems are being used, these may remain dedicated to the bore. If dedicated tubing is being used at the bore, remove the sample and/or air line from the pump fittings and place back into well.
- Replace bore cap and lock borehole casing prior to leaving site.

## On-Site Sampling Equipment Decontamination Procedures.

Between bores the following decontamination procedures of all sampling equipment is to be followed to ensure that cross contamination of the samples does not occur:

- Wiping of excess dirt from the equipment using paper towel.
- Washing of all sampling equipment with tap water and Phosphate free detergent
- Rinsing all equipment with distilled water.
- Inspection of equipment to determine cleanliness.
- Rinse with distilled water.
- The equipment is then allowed to dry or dried with paper towel.
- When using a submersible pump – run the pump in the above detergent, rinsing water and distilled water as well as cleaning the outside surfaces as shown above.
- When using the bladder pump system break the bladder pump down and wash each section as described above.

ThermoFisher SCIENTIFIC

The world leader in serving science

# RENTALS

## Equipment Certification Report – TPS 90FLT Water Quality Meter

This Water Quality Meter has been performance checked and calibrated as follows:

| Sensor | Concentration | Span 1 | Span 2 | Traceability Lot # | Pass? |
|---|---|---|---|---|---|
| pH | 7.00pH/ 4.00pH | 7.00 pH | 4.00 pH | 321063/318962 | ☑ |
| Conductivity | 12.88mS/cm | 0.00 mS/cm | 12.88 mS/cm | 316592 | ☑ |
| TDS | 36.0ppk | 0 ppk | 36 ppk | 318987 | ☑ |
| Dissolved Oxygen | Sodium Sulphite / Air | 0.00 ppm in Sodium Sulphite | 9.39 ppm Saturation in Air | 5928(SS) 306207 (DI) | ☑ |
| Turbidity | 360 NTU | 0 NTU | 360 NTU | 316002 | ☑ |
| Redox (ORP)**240mV | ☑ | Electrode operability test 240mV +/- 10%. Actual: 250 mV | | 316292(A) 317541 (B) | |

☑ Battery Status ____7.1_____(min 7.2V)
☑ Electrical Safety Tag attached (AS/NZS 3760)

☐ Temperature _____21.0_____°C
☐ Electrodes Cleaned and checked

Tag No: _000256_____

Valid to: ___15/09/2018_____

Date: 27/07/2018

Signed: _____

Please check that the following items are received and that all items are cleaned and decontaminated before return. A minimum $30 cleaning / service / repair charge may be applied to any unclean or damaged items. Items not returned will be billed for at the full replacement cost.

| Sent | Returned | Item |
|---|---|---|
| ☑ | ☐ | 90FLMV Unit. Ops check/Battery status: ____8.0_____ |
| ☑ | ☐ | pH sensor with wetting cap, 5m |
| ☑ | ☐ | Conductivity/TDS/Temperature K=10 sensor, 5m |
| ☑ | ☐ | Dissolved oxygen YSI5739 sensor with wetting cap, 5m |
| ☑ | ☐ | Turbidity sensor, 5m |
| ☑ | ☐ | Power supply 240V to 12V DC 200mA |
| ☑ | ☐ | Instruction Manual |
| ☑ | ☐ | Quick Guide |
| ☑ | ☐ | Storage solution for pH and ORP sensors |
| ☑ | ☐ | Carry Case |
| ☑ | ☐ | Check to confirm electrical safety (tag must be valid) |

Date: 27/07/2018

Signed: _____

| | | | |
|---|---|---|---|
| TFS Reference | CS009276 | Return Date: | / / |
| Customer Reference | | Return Time: | |
| Equipment ID | 90FLTSG | Condition on return: | |
| Equipment Serial No. | U4343 | | |

Thermo Fisher Scientific Australia Pty Ltd

ABN 52 058 390 917
Unit 5, 4 Talavera Road North Ryde NSW 2113
Ph: 02 8817 4253 Email: RentalsAU@thermofisher.com

# Rental Contract

BILL TO

LRM Global Pty Ltd
PO Box 1237
CARLTON VIC 3053

SHIP TO

LRM Global Pty Ltd
Site Contact Name: Jon Lawson
c/o QT Sydney 49 Market St
SYDNEY NSW 2000
Telephone No:

CONTRACT NO: CS008821

Delivery Date: 09-May-2018
Rental Contact:
Customer No: 391876
CustomerPO: TBC
Terms: 30 Days from Statement

Special Instructions:
- Send with consumables (3 x bailers)

| QTY | PRODUCT # | DESCRIPTION | START DATE | END DATE | DAY | WK | MTH |
|---|---|---|---|---|---|---|---|
| 1 | MPKITC | Micropurge Low Flow Sampling Kit C | 10/05/18 | 10/05/18 | $255.00 | $760.00 | $1,590.00 |
| 1 | EEP25 | - MP15 Controller | 10/05/18 | 10/05/18 | $0.00 | $0.00 | $0.00 |
| 1 | EEP65 | - Sample Pro Pump | 10/05/18 | 10/05/18 | $0.00 | $0.00 | $0.00 |
| 1 | EEW35 | - EFC WQM - Flow Cell | 10/05/18 | 10/05/18 | $0.00 | $0.00 | $0.00 |
| 1 | EEW45 | - 90FLMV WQM | 10/05/18 | 10/05/18 | $0.00 | $0.00 | $0.00 |
| 1 | EEI20 | - Solinst Interface Meter | 10/05/18 | 10/05/18 | $0.00 | $0.00 | $0.00 |
| 1 | FL | Freight - Local | 10/05/18 | 10/05/18 | $39.00 | $0.00 | $0.00 |

| | |
|---|---|
| Subtotal: | $294.00 |
| GST: | $29.40 |
| TOTAL: | $323.40 |

Please note that this contract is subject to the Terms & Condition of Hire.

# RENTING FROM THERMO FISHER SCIENTIFIC

Renting from Thermo Fisher Scientific Australia Pty Ltd (Thermo Fisher Scientific) is subject to the following:

## 1. Rental Period

The rental period commences on the date show on the Rental Order Confirmation Report and terminates at 12:00pm on the first business day after the period nominated on the Rental Order Confirmation Report. For locations with no overnight courier service, up to one free return travel day is available, if pre-arranged with Thermo Fisher Scientific. No charge for weekend or public holiday use, unless specified. Minimum rental period is one day. Extending the rental period is permitted only with prior approval from Thermo Fisher Scientific. Equipment rented for a period of more than one month will be invoiced on a monthly basis (at end of calendar month). Extending the rental period is permitted with prior written approval from Thermo Fisher Scientific with 24 hours notice prior to the end of the original rental period. Any goods not returned to Thermo Fisher Scientific within the agreed rental period or the agreed/approved extended rental period, will be charged at the standard rates until all equipment and accessories have been returned, regardless of the goods being used or not.

## 2. Contact ability & Changes

Thermo Fisher Scientific may sometimes need to contact the Renter when previously agreed shipping dates cannot be met. The Renter should ensure that they or an appointed person is contactable by telephone or by other means on the day of shipping. At least 24hrs notice is required prior to the start of the rental agreement for cancellations/changes to delivery sites/date changes/etc. Late changes and cancellations may result in all of the subsequent freight and handling charges being imposed.

## 3. Freight Charges

Delivery to the Renter:

Unless otherwise notified, Thermo Fisher Scientific will use its own freight service. The Renter will be invoiced for the freight/handling costs incurred. Rental charges associated with extended transit times are at the discretion of Thermo Fisher Scientific.

Returning Equipment to Thermo Fisher Scientific:

Organising the delivery and associated charges of return freight is the responsibility of the Renter, unless prior arrangement is made with Thermo Fisher Scientific. This does not remove the obligation under Item 4.

## 4. Instrument Maintenance & Calibration

TFS shall at its expense, when deemed necessary, perform maintenance and calibration of equipment. Reports of such calibration are included with the instrument. Much of TFS's equipment will require regular field calibration and it is the responsibility of the Customer to perform such calibrations.

## 5. Damage or Loss

Damage or loss to equipment during possession or during freight from the Renter to Thermo Fisher Scientific is the responsibility of the Renter. The Renter assumes all financial liability for loss and damage of equipment due to misuse, abuse or accident. Thermo Fisher Scientific is not responsible for any loss of data as collected on Thermo Fisher Scientific rental equipment. Transit insurance charges to cover the value of equipment replacement can be included if desired by the Renter. The Renter must notify Thermo Fisher Scientific immediately if any equipment is lost or damaged or if any problem develops with the rented equipment.

## 6. Damage, Missing Components & Decontamination

- Additional charges will apply if the Rental equipment is returned incomplete, damaged or if Customer fails to decontaminate and clean equipment.
- When Rental Equipment is returned in damaged conditions, the Customer will be notified immediately that they are liable for all repair costs. After the repair has been completed, Customer will be issued a Repair invoice which must be paid within 30 days from date of Repair invoice.
- When equipment is returned with missing accessories and components, the Customer will be notified immediately. Until all accessories and components, are returned, the Rental period will continue at the applicable rental rate. The Customer will be liable for the full replacement cost of any missing or lost equipment, accessories or components.
- All Rental Equipment must be returned clean and free of any hazardous or non hazardous contamination. A Decontamination & Cleaning Fee will be applied to any Rental Equipment which Customer returns in a contaminated condition. The current Decontamination & Cleaning Fee is $90.00 per hour, exclusive of GST, and the fee will be based upon how long the equipment takes to be cleaned, with a minimum charge of $30.00 exclusive of GST.

## 7. Instrument Failure

In the event of an instrument failure, Thermo Fisher Scientific must be notified immediately. Please note standard rental charges will continue to apply until Thermo Fisher receives such notification. Thermo Fisher Scientific will in the first instance attempt to guide the customer to rectify the fault, however if the fault cannot be rectified promptly, then Thermo Fisher will ship a replacement equipment. If the reason for equipment failure is determined to be Thermo Fisher Scientific's fault or the equipment has failed for unknown reasons, the costs of issuing a replacement product will be at Thermo Fisher Scientific's expense. No rental charge will be applied for the time the Customer does not have a working instrument when it is determined that the failure was not the Customer's fault. If the failure is determined to be due to the Customer, applicable courier delivery charges will apply for the replacement equipment and the Rental period will continue at the standard rental rates.

## 8. Liability

Thermo Fisher Scientific is not liable for any loss or damage of any kind whatsoever and howsoever arising (including but not limited to loss arising by reason of delay, non-delivery, defective materials or workmanship) out of or in connection with the supply of goods or services, including (without limitation) any indirect or consequential loss (including without limitation loss of profit, loss of revenue, loss of contract, loss of use of goods, loss on resale, loss of goodwill or increased cost of workings), even if due to the negligence of the Seller or any of its employees or agents.

## 9. Standard Terms and Conditions of Business

This transaction is subject to our Terms & Conditions of Business which are available on our website www.thermofisher.com.au or by contacting this office.

10. Debit Authority

When the customer has given a credit car or account debit authority, Thermo Fisher Scientific are hereby authorised to debit all fees, charges, additional costs and expenses applicable to the rental from the Customers credit card or account.

11. Rent-2-Buy Program

The Rent to Buy (R2B) Program is only applicable for Customers using Thermo Fisher Scientific Rentals service. It is only applicable for products currently within the rental fleet in Australia. Other products may be considered upon negotiation, so please talk to your local sales representative in the first instance or the Rentals Manager.

- There is no minimum rental period to activate the R2B Program discount.
- The discount applies only to the last rental from Thermo Fisher Scientific. Discounts can't be accumulated with multiple rentals.
- The discount is off the standard list price at the time of purchase.
- The maximum discount for RTB is 50% of one month's rental.
- The applicable rental fees must be paid in full in order to proceed with the R2B Program offer of purchasing a new unit at the discounted rate.
- Notification in writing (e.g. Email) of intent to purchase the rented unit at the R2B Program discount is required within two (2) weeks post return of the rental equipment in order for the R2B Program to be activated. There is no obligation on the renter to purchase a unit even if an intention to purchase is stated.
- Normal warranty terms apply per any equipment purchased.
- The R2B Terms and Conditions can be altered at any time at the discretion of Thermo Fisher Scientific. The Rent to Buy (R2B) program can be withdrawn at any time at the discretion of Thermo Fisher Scientific.
- All standard Rental Terms & Conditions apply to all rentals. These can be found at www.thermofisher.com.au within the rentals section. Similarly, all standard Thermo Fisher Scientific Terms and Conditions apply.
- Thermo Fisher Scientific does not accept any liability for any loss or damages to property, commercial operations or persons for equipment used whilst under the R2B Program.

12. Other Charges

Where applicable, the customer shall be responsible for the payment of all costs, taxes, customs duties or tariffs, imposts and expenses which arise or are incurred from this rental.

13. Payments and Defaults

If the Customer does not have an approved account with Thermo Fisher Scientific, Customer must pay for the full Rental period before the Rental starts. Customers with an approved trading account must provide a PO or reference number and remit payment within 30 days from the date of invoice. Thermo Fisher Scientific does not accept credit card numbers via email or fax. If you wish to pay via credit card, please call Customer Service (1300 735 295).
Should the Customer fail to pay any rental payments when required and immediate action is not taken by the Customer to rectify this situation, the equipment will be removed by Thermo Fisher Scientific and charges applied for due Rental fees and recovery costs.

14. Rental Agreement

- The Equipment is rented to Customer only and ownership of the Equipment shall remain at all times with Thermo Fisher. The Equipment will be physically identified as Thermo Fisher property, and Customer shall not remove or deface these markings on the Equipment.
- Customer must permit Thermo Fisher Scientific employees or agents appointed by Thermo Fisher Scientific to enter the premises where the equipment is located in order to inspect the equipment or to carry repairs at times which are deemed to be necessary by Thermo Fisher.
- The equipment will be kept at the delivery address specified in the Rental Order Confirmation Report unless prior written permission has been obtained to relocate the equipment.
- Customer agrees to keep the equipment free from all liens and encumbrances or other adverse claims of title. Customer shall, at ThermoFisher's request, provide Thermo Fisher with all reasonable assistance (including executing any documents or taking any administrative steps) necessary to perfect ThermoFisher's ownership interest in the Equipment.
- In the event that this agreement terminates for any reason, Thermo Fisher shall be immediately entitled to recover the Equipment from the Customer's premises and Customer hereby grants Thermo Fisher permission to enter onto its premises in order to recover the Equipment in such circumstances.

15. Warranty

Thermo Fisher Scientific warrants that each item of equipment hired is of merchantable quality and reasonably fit for the purpose for which it was designed. The Customer acknowledges that it has not relied upon any statement by Thermo Fisher Scientific in respect to Customer's purpose for utilisation of the equipment and that Thermo Fisher Scientific is not responsible or liable for any failure or unsuitability of equipment to perform the purpose required by the customer.

16. Early Cessation

Thermo Fisher Scientific expressly reserves itself the right of early cessation, which may be exercised on demand and at the absolute discretion of Thermo Fisher Scientific. The applicable rental shall be adjusted and payable on a pro-rata basis.

17. Consumables

Thermo Fisher reserves the right to separately charge for all consumables required for the operation of the equipment.

EP RISK

# EP Risk Management Pty Ltd

## Photo-ionisation Detector (PID) Calibration Certificate

| Project Details | | |
|---|---|---|
| Date: 3/8/18 | Project No.: EP0909 | Project Manager: Rachel Condon |
| Time: 8:00 am | Location: Lane Cove | |
| Weather: Fine | | |

| PID Information | | | | |
|---|---|---|---|---|
| **Calibration** | **Actual Value** | **Reading** | **Pass** | |
| Zero - Fresh Air | 0.0 ppm | 0.0 ppm | ✓ | |
| Span - Isobutylene | 100.0ppm | 99.6 ppm | ✓ | |
| Set Alarm Limits to | High | 100 ppm | Low | 50 ppm |

| Operations Check | | | | | |
|---|---|---|---|---|---|
| ✓ | Performance Check (pump, lamp, sensor and battery voltage check) | | | | |
| ✓ | Battery Charge | ✓ | Filters Check | ✓ | Spare battery voltage (5.5 V min) 5.8V |
| ✓ | Bump Test | Date: 3/8/18 | | | |

Date: 3/8/18 Check By: NM

Signed: N. McGuinness

# APPENDIX D

# ANALTICAL RESULTS TABLES

# Table 18a: Soil Results Compared Against NEPM HILs

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

LRM GLOBAL

# Table 18a: Soil Results Compared Against NEPM HILs

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | **Sampled Date** | 6/07/2017 | 6/07/2017 | 6/07/2017 

# Table 18a: Soil Results Compared Against NEPM HILs

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

# Table 18a: Soil Results Compared Against NEPM HILs

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

LRM GLOBAL

# Table 18a: Soil Results Compared Against NEPM HILs

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

LRM GLOBAL

# Table 18a: Soil Results Compared Against NEPM HILs

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

**Table 18b: Soil Results Compared Against NEPM HSLs**

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

**Table 18b: Soil Results Compared Against NEPM HSLs**

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

**Table 18b: Soil Results Compared Against NEPM HSLs**

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

# Table 18b: Soil Results Compared Against NEPM HSLs

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

LRM GLOBAL

# Table 18b: Soil Results Compared Against NEPM HSLs

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

# Table 18b: Soil Results Compared Against NEPM HSLs

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

# Table 18c: Soil Results Compared Against TRH Management Limits

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

# Table 18c: Soil Results Compared Against TRH Management Limits

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

# Table 18c: Soil Results Compared Against TRH Management Limits

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

LRM GLOBAL

# Table 18c: Soil Results Compared Against TRH Management Limits

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

LRM GLOBAL

# Table 18c: Soil Results Compared Against TRH Management Limits

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

# Table 18c: Soil Results Compared Against TRH Management Limits

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

# Table 19: Soil Results Compared Against Adopted EILs

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | **Sampled Date** | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| | | | | **Sample Name** | BH16 | BH16 | BH17 | BH17 | BH18 | BH18 | BH19 | BH19 | BH20 | BH20 | BH20 | BH21 | BH21 | BH21 | BH21 | BH22 | BH22 | BH23 | BH23 | BH24 | BH24 | BH24 | BH25 | BH26 | | |
| | | | | **SampleDepth** | 0.1 | 0.8 | 0.1 | 0.7 | 0.1 | 0.6 | 0.1 | 0.5 | 0.1 | 1 | 1.9 | 0.1 | 1.2 | 3 | 4 | 0.1 | 1 | 0.1 | 1 | 0.1 | 1.5 | 2.8 | 0.2 | 0.2 | | |
| **Chemical Group** | **Chemical Name** | **Units** | **EQL** | Adopted Ecological Investigation Levels | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 3/4-Methylphenol (m/p-cresol) | mg/kg | 0.4 | | - | - | - | - | - | - | - | <0.4 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Benzo(a)pyrene TEQ (LOR) | mg/kg | 0.5 | | 0.9 | <0.5 | <0.5 | <0.5 | - | <0.5 | - | <0.5 | - | <0.5 | <0.5 | - | <0.5 | - | <0.5 | - | - | - | <0.5 | - | <0.5 | - | - | - | - | - |
| | Benzo(b+j+k)fluoranthene | mg/kg | 0.2 | | 1 | <0.2 | <0.2 | <0.2 | - | <0.2 | - | <0.2 | - | <0.2 | <0.2 | - | <0.2 | - | <0.2 | - | - | - | <0.2 | - | <0.2 | - | - | - | - | - |
| | DCPA (Chlorthal) Diacid | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Plasticiser Compounds | mg/kg | 5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Scheduled chemicals (NSW Waste 2008) | mg/kg | 1.3 | | - | - | - | - | <1.3 | - | <1.3 | <2.5 | <1.3 | - | - | <1.3 | - | - | - | <1.3 | - | <1.3 | - | <1.3 | - | - | - | <1.3 | <1.3 | <1.3 |
| | Total Positive PAHs | mg/kg | 0.05 | | 7.1 | <0.05 | 0.4 | <0.05 | - | 0.3 | - | <0.05 | - | <0.05 | <0.05 | - | 0.06 | - | <0.05 | - | - | - | <0.05 | - | 0.4 | - | - | - | - | - |
| | Benzo(a)pyrene TEQ calc (Half) | mg/kg | 0.5 | | 0.9 | <0.5 | <0.5 | <0.5 | - | <0.5 | - | <0.5 | - | <0.5 | <0.5 | - | <0.5 | - | <0.5 | - | - | - | <0.5 | - | <0.5 | - | - | - | - | - |
| | Benzo(a)pyrene TEQ calc (Zero) | mg/kg | 0.5 | | 0.9 | <0.5 | <0.5 | <0.5 | - | <0.5 | - | <0.5 | - | <0.5 | <0.5 | - | <0.5 | - | <0.5 | - | - | - | <0.5 | - | <0.5 | - | - | - | - | - |
| | Metribuzin | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Acid Herbicides | 2,6-D | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Triazine Herb | Irgarol | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Benzene | mg/kg | 0.2 | | - | - | - | - | - | - | - | <0.2 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Ethylbenzene | mg/kg | 0.5 | | - | - | - | - | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Toluene | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| BTEX | Xylene (m & p) | mg/kg | 1 | | - | - | - | - | - | - | - | <2 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Xylene (o) | mg/kg | 0.5 | | - | - | - | - | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Xylene Total | mg/kg | 1 | | - | - | - | - | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | C6-C10 less BTEX (F1) | mg/kg | 25 | | - | - | - | - | - | - | - | <25 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,1,1,2-tetrachloroethane | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,1,1-trichloroethane | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,1,2,2-tetrachloroethane | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,1,2-trichloroethane | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,1-dichloroethane | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,1-dichloroethene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,1-dichloropropene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,2,3-trichloropropane | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,2-dibromo-3-chloropropane | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,2-dichloroethane | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,2-dichloropropane | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,3-dichloropropane | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,2-dichloropropane | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Bromochloromethane | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Chlorinated Hydrocarbons | Bromodichloromethane | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Bromoform | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Carbon tetrachloride | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Chlorodibromomethane | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Chloroethane | mg/kg | 1 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Chloroform | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Chloromethane | mg/kg | 1 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | cis-1,2-dichloroethene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | cis-1,3-dichloropropene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Dibromomethane | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Hexachlorobutadiene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Trichloroethene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Tetrachloroethene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | trans-1,2-dichloroethene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | trans-1,3-dichloropropene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Vinyl chloride | mg/kg | 1 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Explosives | Nitrobenzene | mg/kg | 0.1 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,2,3-trichlorobenzene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,2,4-trichlorobenzene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,2-dichlorobenzene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,3-dichlorobenzene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Halogenated Benzenes | 1,4-dichlorobenzene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2-chlorotoluene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 4-chlorotoluene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Bromobenzene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Chlorobenzene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Hexachlorobenzene | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | - | <0.1 | <0.1 | <0.1 |
| | 1,2-dibromoethane | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Halogenated Hydrocarbons | Bromomethane | mg/kg | 1 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Dichlorodifluoromethane | mg/kg | 1 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Trichlorofluoromethane | mg/kg | 1 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,3,4,6-tetrachlorophenol | mg/kg | 0.2 | | - | - | - | - | - | - | - | <0.2 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4,5-trichlorophenol | mg/kg | 0.2 | | - | - | - | - | - | - | - | <0.2 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4,6-trichlorophenol | mg/kg | 0.2 | | - | - | - | - | - | - | - | <0.2 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Halogenated Phenols | 2,4-dichlorophenol | mg/kg | 0.2 | | - | - | - | - | - | - | - | <0.2 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,6-dichlorophenol | mg/kg | 0.2 | | - | - | - | - | - | - | - | <0.2 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2-chlorophenol | mg/kg | 0.2 | | - | - | - | - | - | - | - | <0.2 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Pentachlorophenol | mg/kg | 1 | | - | - | - | - | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4,5-Trichlorophenoxy Acetic Acid | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4,5-TP (Silvex) | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4-dichlorophenoxybutanoic acid | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Hedonal | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4-Dichlorprop | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4,6-Trichlorophenoxy-acetic acid | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2-Chlorophenoxyacetic acid | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 4-Chlorophenoxy acetic acid | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Ametryn | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Acifluorfen | mg/kg | 2 | | - | - | - | - | - | - | - | <2 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Atrazine | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Bromoxynil | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Herbicides | Clopyralid | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Cyanazine | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Dicamba | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Dinoseb | mg/kg | 1 | | - | - | - | - | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Hexazinone | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2-Methyl-4-chlorophenoxyacetic acid | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2-Methyl-4-Chlorophenoxy Butanoic Acid | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Mecoprop | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Prometryn | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Propazine | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Simazine | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Terbutryn | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Triclopyr | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Inorganics | Cyanide (Free) | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Cyanide Total | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Fluoride | mg/kg | 50 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,2,4-trimethylbenzene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,3,5-trimethylbenzene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Isopropylbenzene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | n-butylbenzene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| MAH | n-propylbenzene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | p-isopropyltoluene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | sec-butylbenzene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Styrene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | tert-butylbenzene | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Arsenic | mg/kg | 4 | 100 | 8 | 9 | 5 | 16 | <4 | <4 | 5 | <4 | <4 | <4 | <4 | <4 | <4 | 9 | <4 | <4 | <4 | <4 | <4 | <4 | <4 | <4 | 22 | <4 | | |
| | Beryllium | mg/kg | 1 | | - | - | - | - | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | | |
| | Boron | mg/kg | 3 | | - | - | - | - | - | - | - | <3 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | | |
| | Cadmium | mg/kg | 0.4 | | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | 1 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | | |
| | Chromium (hexavalent) | mg/kg | 1 | | - | - | - | - | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | | |
| | Chromium (III+VI) | mg/kg | 1 | 200 | 12 | 9 | 14 | 7 | 9 | 6 | 9 | 8 | 9 | 14 | 3 | 14 | 12 | 23 | 5 | 5 | 8 | 7 | 5 | 9 | 9 | 14 | 16 | 4 | | |
| | Cobalt | mg/kg | 1 | | - | - | - | - | - | - | - | 1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | | |
| | Copper | mg/kg | 1 | 220 | 21 | <1 | 5 | 4 | 8 | 1 | 8 | 2 | 8 | <1 | <1 | 9 | 3 | 12 | <1 | 72 | 16 | 7 | <1 | 7 | 3 | 1 | 15 | <1 | | |
| Metals | Lead | mg/kg | 1 | 1,100 | 89 | 11 | 11 | 13 | 13 | 10 | 13 | 17 | 14 | 8 | 8 | 12 | 23 | 120 | 6 | 230 | 830 | 12 | 4 | 11 | 18 | 15 | 87 | 6 | | |
| | Manganese | mg/kg | 1 | | - | - | - | - | - | - | - | 20 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | | |
| | Mercury | mg/kg | 0.1 | | 0.2 | <0.1 | <0.1 | <0.1 | 3.7 | <0.1 | 6.4 | <0.1 | 5.2 | <0.1 | <0.1 | 2.7 | <0.1 | <0.1 | <0.1 | 0.2 | 0.2 | 4.2 | <0.1 | 2.7 | <0.1 | <0.1 | 0.2 | <0.1 | | |
| | Molybdenum | mg/kg | 1 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | | |
| | Nickel | mg/kg | 1 | 170 | 9 | <1 | 1 | <1 | 3 | <1 | 2 | <1 | 3 | 2 | <1 | 4 | 3 | 5 | <1 | 17 | 4 | 3 | <1 | 2 | 1 | <1 | 3 | <1 | | |
| | Selenium | mg/kg | 2 | | - | - | - | - | - | - | - | <2 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | | |
| | Silver | mg/kg | 1 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | | |
| | Tin | mg/kg | 1 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | | |
| | Zinc | mg/kg | 1 | 520 | 84 | <1 | 6 | 2 | 18 | 7 | 14 | 5 | 17 | 50 | 1 | 19 | 89 | 640 | <1 | 110 | 260 | 18 | <1 | 17 | 14 | 8 | 66 | 2 | | |
| Organic | Terbutylazine | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | | |

# Table 19: Soil Results Compared Against Adopted EILs

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | **Sampled Date** | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| | | | | | **Sample Name** | BH16 | BH16 | BH17 | BH17 | BH18 | BH18 | BH19 | BH19 | BH20 | BH20 | BH20 | BH21 | BH21 | BH21 | BH21 | BH22 | BH22 | BH23 | BH23 | BH24 | BH24 | BH24 | BH25 | BH26 |
| | | | | | **SampleDepth** | 0.1 | 0.8 | 0.1 | 0.7 | 0.1 | 0.6 | 0.1 | 0.5 | 0.1 | 1 | 1.9 | 0.1 | 1.2 | 3 | 4 | 0.1 | 1 | 0.1 | 1 | 0.1 | 1.5 | 2.8 | 0.2 | 0.2 |
| **Chemical Group** | **Chemical Name** | **Units** | **EQL** | Adopted Ecological Investigation Levels | | | | | | | | | | | | | | | | | | | | | | | | | |
| Organochlorine Pesticides | 4,4-DDE | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | 0.1 | - | - | <0.1 | <0.1 |
| | a-BHC | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Aldrin | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | b-BHC | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Chlordane (cis) | mg/kg | 0.1 | | - | - | - | - | 0.2 | - | 0.1 | <0.1 | 0.1 | - | - | 0.2 | - | - | - | <0.1 | - | 0.3 | - | 0.1 | - | - | <0.1 | <0.1 |
| | Chlordane (trans) | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | 0.1 | - | - | - | <0.1 | - | 0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | d-BHC | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | DDD | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | DDT | mg/kg | 0.1 | 180 | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | DDT+DDE+DDD | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | 0.1 | - | - | <0.1 | <0.1 |
| | Dieldrin | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Endosulfan I | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Endosulfan II | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Endosulfan sulphate | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Endrin | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Endrin aldehyde | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | g-BHC (Lindane) | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Heptachlor | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Heptachlor epoxide | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Methoxychlor | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Toxaphene | mg/kg | 2 | | - | - | - | - | - | - | - | <2 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Organophosphorous Pesticides | Azinophos methyl | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Bromophos-ethyl | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Chlorpyrifos | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Chlorpyrifos-methyl | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Diazinon | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Dichlorvos | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Dimethoate | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Ethion | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Fenitrothion | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Malathion | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| | Ronnel | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| Other | 3,5-Dichlorobenzoic acid | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Actril (loxynil) | mg/kg | 1 | | - | - | - | - | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| PAH/Phenols | PAH (total, NSW Waste 2008) | mg/kg | | | 6.27 | <1.35 | 0.83 | <1.35 | - | 0.8 | - | <1.35 | - | <1.35 | <1.35 | - | 0.71 | - | <1.35 | - | - | - | <1.35 | - | 1.03 | - | - | - |
| | 2,4-dimethylphenol | mg/kg | 0.2 | | - | - | - | - | - | - | - | <0.2 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4-dinitrophenol | mg/kg | 2 | | - | - | - | - | - | - | - | <4 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2-methylphenol | mg/kg | 0.2 | | - | - | - | - | - | - | - | <0.2 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2-nitrophenol | mg/kg | 0.2 | | - | - | - | - | - | - | - | <0.2 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 4,6-Dinitro-2-methylphenol | mg/kg | 2 | | - | - | - | - | - | - | - | <2 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 4-chloro-3-methylphenol | mg/kg | 1 | | - | - | - | - | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 4-methylphenol | mg/kg | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 4-nitrophenol | mg/kg | 4 | | - | - | - | - | - | - | - | <4 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Acenaphthene | mg/kg | 0.1 | | <0.1 | <0.1 | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | - | - |
| | Acenaphthylene | mg/kg | 0.1 | | <0.1 | <0.1 | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | - | - |
| | Anthracene | mg/kg | 0.1 | | <0.1 | <0.1 | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | - | - |
| | Benz(a)anthracene | mg/kg | 0.1 | | 0.6 | <0.1 | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | - | - |
| | Benzo(a) pyrene | mg/kg | 0.05 | | 0.67 | <0.05 | 0.08 | <0.05 | - | 0.05 | - | <0.05 | - | <0.05 | <0.05 | - | 0.06 | - | <0.05 | - | - | - | <0.05 | - | 0.08 | - | - | - |
| | Benzo(b+k)fluoranthene | mg/kg | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Benzo(g,h,i)perylene | mg/kg | 0.1 | | 0.6 | <0.1 | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | - | - |
| | Chrysene | mg/kg | 0.1 | | 0.6 | <0.1 | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | - | - |
| | Cresol Total | mg/kg | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Dibenz(a,h)anthracene | mg/kg | 0.1 | | <0.1 | <0.1 | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | - | - |
| | Fluoranthene | mg/kg | 0.1 | | 1.3 | <0.1 | 0.1 | <0.1 | - | 0.1 | - | <0.1 | - | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | - | - | <0.1 | - | 0.2 | - | - | - |
| | Fluorene | mg/kg | 0.1 | | <0.1 | <0.1 | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | - | - |
| | Indeno(1,2,3-c,d)pyrene | mg/kg | 0.1 | | 0.5 | <0.1 | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | - | - |
| | Naphthalene | mg/kg | 0.1 | 170 | <0.1 | <0.1 | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | - | - |
| | PAHs (Sum of total) | mg/kg | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Phenanthrene | mg/kg | 0.1 | | 0.5 | <0.1 | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | - | - |
| | Phenol | mg/kg | 0.2 | | - | - | - | - | - | - | - | <0.2 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Phenolics Total | mg/kg | 0.2 | | - | - | - | - | - | - | - | <5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Picloram | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Pyrene | mg/kg | 0.1 | | 1.2 | <0.1 | 0.1 | <0.1 | - | 0.1 | - | <0.1 | - | <0.1 | <0.1 | - | <0.1 | - | <0.1 | - | - | - | <0.1 | - | 0.2 | - | - | - |
| Pesticides | Pesticides (total, NSW Waste 2008) | mg/kg | | | - | - | - | - | <0.6 | - | <0.6 | <3.6 | <0.6 | - | - | <0.6 | - | - | - | <0.6 | - | <0.6 | - | <0.6 | - | - | <0.6 | <0.6 |
| | Bifenthrin | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Mirex | mg/kg | 0.5 | | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Parathion | mg/kg | 0.1 | | - | - | - | - | <0.1 | - | <0.1 | <0.1 | <0.1 | - | - | <0.1 | - | - | - | <0.1 | - | <0.1 | - | <0.1 | - | - | <0.1 | <0.1 |
| Phthalates | Bis(2-ethylhexyl) phthalate | mg/kg | 5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Butyl benzyl phthalate | mg/kg | 1 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Diethylphthalate | mg/kg | 1 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Dimethyl phthalate | mg/kg | 1 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Di-n-butyl phthalate | mg/kg | 5 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Di-n-octyl phthalate | mg/kg | 1 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Polychlorinated Biphenyls | Arochlor 1016 | mg/kg | 0.1 | | - | - | - | - | - | - | - | <0.1 | - | - | - | <0.1 | - | - | <0.1 | - | - | - | - | - | - | - | <0.1 | - | - |
| | Arochlor 1221 | mg/kg | 0.1 | | - | - | - | - | - | - | - | <0.1 | - | - | - | <0.1 | - | - | <0.1 | - | - | - | - | - | - | - | <0.1 | - | - |
| | Arochlor 1232 | mg/kg | 0.1 | | - | - | - | - | - | - | - | <0.1 | - | - | - | <0.1 | - | - | <0.1 | - | - | - | - | - | - | - | <0.1 | - | - |
| | Arochlor 1242 | mg/kg | 0.1 | | - | - | - | - | - | - | - | <0.1 | - | - | - | <0.1 | - | - | <0.1 | - | - | - | - | - | - | - | <0.1 | - | - |
| | Arochlor 1248 | mg/kg | 0.1 | | - | - | - | - | - | - | - | <0.1 | - | - | - | <0.1 | - | - | <0.1 | - | - | - | - | - | - | - | <0.1 | - | - |
| | Arochlor 1254 | mg/kg | 0.1 | | - | - | - | - | - | - | - | <0.1 | - | - | - | <0.1 | - | - | <0.1 | - | - | - | - | - | - | - | <0.1 | - | - |
| | Arochlor 1260 | mg/kg | 0.1 | | - | - | - | - | - | - | - | <0.1 | - | - | - | <0.1 | - | - | <0.1 | - | - | - | - | - | - | - | <0.1 | - | - |
| | PCBs (Sum of total) | mg/kg | 0.1 | | - | - | - | - | - | - | - | <0.1 | - | - | - | <0.1 | - | - | <0.1 | - | - | - | - | - | - | - | <0.1 | - | - |
| Solvents | Cyclohexane | mg/kg | 1 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| TRH | C10-C16 | mg/kg | 50 | | <50 | <50 | <50 | <50 | - | - | - | <50 | - | - | - | - | - | <50 | - | - | <50 | - | - | <50 | - | <50 | - | - |
| | C16-C34 | mg/kg | 100 | | <100 | <100 | <100 | <100 | - | - | - | <100 | - | - | - | - | - | <100 | - | - | <100 | - | - | <100 | - | <100 | - | - |
| | C34-C40 | mg/kg | 100 | | <100 | <100 | <100 | <100 | - | - | - | <100 | - | - | - | - | - | <100 | - | - | <100 | - | - | <100 | - | <100 | - | - |
| | F2-NAPHTHALENE | mg/kg | 50 | | <50 | <50 | <50 | <50 | - | - | - | <50 | - | - | - | - | - | <50 | - | - | <50 | - | - | <50 | - | <50 | - | - |
| | C6 - C9 | mg/kg | 25 | | <25 | <25 | <25 | <25 | - | - | - | <25 | - | - | - | - | - | <25 | - | - | <25 | - | - | <25 | - | <25 | - | - |
| | C10 - C14 | mg/kg | 50 | | <50 | <50 | <50 | <50 | - | - | - | <50 | - | - | - | - | - | <50 | - | - | <50 | - | - | <50 | - | <50 | - | - |
| | C15 - C28 | mg/kg | 100 | | <100 | <100 | <100 | <100 | - | - | - | <100 | - | - | - | - | - | <100 | - | - | <100 | - | - | <100 | - | <100 | - | - |
| | C29-C36 | mg/kg | 100 | | <100 | <100 | <100 | <100 | - | - | - | <100 | - | - | - | - | - | <100 | - | - | <100 | - | - | <100 | - | <100 | - | - |
| | +C10 - C36 (Sum of total) | mg/kg | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | C10 - C40 (Sum of total) | mg/kg | 50 | | <50 | <50 | <50 | <50 | - | - | - | <50 | - | - | - | - | - | <50 | - | - | <50 | - | - | <50 | - | <50 | - | - |
| | C6-C10 | mg/kg | 25 | | <25 | <25 | <25 | <25 | - | - | - | <25 | - | - | - | - | - | <25 | - | - | <25 | - | - | <25 | - | <25 | - | - |

# Table 19: Soil Results Compared Against Adopted EILs

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

# Table 19: Soil Results Compared Against Adopted EILs

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

# Table 19: Soil Results Compared Against Adopted EILs

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

LRM GLOBAL

# Table 19: Soil Results Compared Against Adopted EILs

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | |

# Table 19: Soil Results Compared Against Adopted EILs

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | **Sampled Date** | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 10/05/2018 | 11/05/2018 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 11/05/2018 | 11/05/2018 |
| | | | | **Sample Name** | Dup1 | Dup2 | Dup3 | Dup4 | Dup 5 | Dup 6 | Split 1 | Split 2 | Split 3 | Split 4 | Split 5 | Spilt 6 |
| | | | | **SampleDepth** | 0.1 | 0.1 | 0.1 | 0.1 | | | | | | | 5 | 6 |
| **Chemical Group** | **Chemical Name** | **Units** | **EQL** | Adopted Ecological Investigation Levels | | | | | | | | | | | | |
| | 3/4-Methylphenol (m/p-cresol) | mg/kg | 0.4 | | <0.4 | - | - | - | - | - | - | - | - | - | - | - |
| | Benzo(a)pyrene TEQ (LOR) | mg/kg | 0.5 | | <0.5 | - | - | - | <0.5 | <0.5 | <0.5 | - | - | - | - | - |
| | Benzo(b+j+k)fluoranthene | mg/kg | 0.2 | | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | - | - | - |
| | DCPA (Chlorthal) Diacid | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Plasticiser Compounds | mg/kg | 5 | | - | - | - | - | - | - | - | - | - | - | - | - |
| | Scheduled chemicals (NSW Waste 2008) | mg/kg | 1.3 | | <2.5 | - | - | - | - | - | <3 | - | - | - | - | - |
| | Total Positive PAHs | mg/kg | 0.05 | | <0.05 | - | - | - | <0.05 | <0.05 | - | - | - | - | - | - |
| | Benzo(a)pyrene TEQ calc (Half) | mg/kg | 0.5 | | <0.5 | - | - | - | <0.5 | <0.5 | <0.5 | - | - | - | - | - |
| | Benzo(a)pyrene TEQ calc (Zero) | mg/kg | 0.5 | | <0.5 | - | - | - | <0.5 | <0.5 | <0.5 | - | - | - | - | - |
| | Metribuzin | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | - | - | - | - | - | - |
| Acid Herbicides | 2,6-D | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| Triazine Herb | Irgarol | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | - | - | - | - | - | - |
| BTEX | Benzene | mg/kg | 0.2 | | <0.2 | - | - | - | <0.2 | <0.2 | <0.2 | - | - | - | - | - |
| | Ethylbenzene | mg/kg | 0.5 | | <1 | - | - | - | <1 | <1 | <0.5 | - | - | - | - | - |
| | Toluene | mg/kg | 0.5 | | <0.5 | - | - | - | <0.5 | <0.5 | <0.5 | - | - | - | - | - |
| | Xylene (m & p) | mg/kg | 1 | | <2 | - | - | - | <2 | <2 | <1 | - | - | - | - | - |
| | Xylene (o) | mg/kg | 0.5 | | <1 | - | - | - | <1 | <1 | <0.5 | - | - | - | - | - |
| | Xylene Total | mg/kg | 1 | | <1 | - | - | - | <1 | <1 | <1 | - | - | - | - | - |
| | C6-C10 less BTEX (F1) | mg/kg | 25 | | <25 | - | - | - | <25 | <25 | <25 | - | - | - | - | - |
| Chlorinated Hydrocarbons | 1,1,1,2-tetrachloroethane | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 1,1,1-trichloroethane | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 1,1,2,2-tetrachloroethane | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 1,1,2-trichloroethane | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 1,1-dichloroethane | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 1,1-dichloroethene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 1,1-dichloropropene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 1,2,3-trichloropropane | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 1,2-dibromo-3-chloropropane | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 1,2-dichloroethane | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 1,2-dichloropropane | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 1,3-dichloropropane | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 2,2-dichloropropane | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Bromochloromethane | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Bromodichloromethane | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Bromoform | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Carbon tetrachloride | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Chlorodibromomethane | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Chloroethane | mg/kg | 1 | | - | - | - | - | - | - | <1 | - | - | - | - | - |
| | Chloroform | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Chloromethane | mg/kg | 1 | | - | - | - | - | - | - | <1 | - | - | - | - | - |
| | cis-1,2-dichloroethene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | cis-1,3-dichloropropene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Dibromomethane | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Hexachlorobutadiene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Trichloroethene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Tetrachloroethene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | trans-1,2-dichloroethene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | trans-1,3-dichloropropene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Vinyl chloride | mg/kg | 1 | | - | - | - | - | - | - | <1 | - | - | - | - | - |
| Explosives | Nitrobenzene | mg/kg | 0.1 | | - | - | - | - | - | - | - | - | - | - | - | - |
| Halogenated Benzenes | 1,2,3-trichlorobenzene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 1,2,4-trichlorobenzene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 1,2-dichlorobenzene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 1,3-dichlorobenzene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 1,4-dichlorobenzene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 2-chlorotoluene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 4-chlorotoluene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Bromobenzene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Chlorobenzene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Hexachlorobenzene | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| Halogenated Hydrocarbons | 1,2-dibromoethane | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Bromomethane | mg/kg | 1 | | - | - | - | - | - | - | <1 | - | - | - | - | - |
| | Dichlorodifluoromethane | mg/kg | 1 | | - | - | - | - | - | - | <1 | - | - | - | - | - |
| | Trichlorofluoromethane | mg/kg | 1 | | - | - | - | - | - | - | <1 | - | - | - | - | - |
| Halogenated Phenols | 2,3,4,6-tetrachlorophenol | mg/kg | 0.2 | | <0.2 | - | - | - | - | - | <0.2 | - | - | - | - | - |
| | 2,4,5-trichlorophenol | mg/kg | 0.2 | | <0.2 | - | - | - | - | - | <0.2 | - | - | - | - | - |
| | 2,4,6-trichlorophenol | mg/kg | 0.2 | | <0.2 | - | - | - | - | - | <0.2 | - | - | - | - | - |
| | 2,4-dichlorophenol | mg/kg | 0.2 | | <0.2 | - | - | - | - | - | <0.2 | - | - | - | - | - |
| | 2,6-dichlorophenol | mg/kg | 0.2 | | <0.2 | - | - | - | - | - | <0.2 | - | - | - | - | - |
| | 2-chlorophenol | mg/kg | 0.2 | | <0.2 | - | - | - | - | - | <0.2 | - | - | - | - | - |
| | Pentachlorophenol | mg/kg | 1 | | <1 | - | - | - | - | - | <1 | - | - | - | - | - |
| Herbicides | 2,4,5-Trichlorophenoxy Acetic Acid | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 2,4,5-TP (Silvex) | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 2,4-dichlorophenoxybutanoic acid | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Hedonal | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 2,4-Dichlorprop | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 2,4,6-Trichlorophenoxy-acetic acid | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 2-Chlorophenoxyacetic acid | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 4-Chlorophenoxy acetic acid | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Ametryn | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | - | - | - | - | - | - |
| | Acifluorfen | mg/kg | 2 | | <2 | - | - | - | - | - | <2 | - | - | - | - | - |
| | Atrazine | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Bromoxynil | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Clopyralid | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Cyanazine | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | - | - | - | - | - | - |
| | Dicamba | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Dinoseb | mg/kg | 1 | | <1 | - | - | - | - | - | <1 | - | - | - | - | - |
| | Hexazinone | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | - | - | - | - | - | - |
| | 2-Methyl-4-chlorophenoxyacetic acid | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 2-Methyl-4-Chlorophenoxy Butanoic Acid | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Mecoprop | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Prometryn | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | - | - | - | - | - | - |
| | Propazine | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | - | - | - | - | - | - |
| | Simazine | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | - | - | - | - | - | - |
| | Terbutryn | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | - | - | - | - | - | - |
| | Triclopyr | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| Inorganics | Cyanide (Free) | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Cyanide Total | mg/kg | 0.5 | | - | - | - | - | - | - | - | - | - | - | - | - |
| | Fluoride | mg/kg | 50 | | - | - | - | - | - | - | - | - | - | - | - | - |
| MAH | 1,2,4-trimethylbenzene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | 1,3,5-trimethylbenzene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Isopropylbenzene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | n-butylbenzene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | n-propylbenzene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | p-isopropyltoluene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | sec-butylbenzene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Styrene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | tert-butylbenzene | mg/kg | 0.5 | | - | - | - | - | - | - | <0.5 | - | - | - | - | - |
| Metals | Arsenic | mg/kg | 4 | 100 | <4 | 5 | 14 | <4 | <4 | <4 | 4 | 4 | 8 | <4 | <4 | <4 |
| | Beryllium | mg/kg | 1 | | <1 | - | - | - | - | - | <1 | - | - | - | - | - |
| | Boron | mg/kg | 3 | | <3 | - | - | - | - | - | <3 | - | - | - | - | - |
| | Cadmium | mg/kg | 0.4 | | <0.4 | 6 | 0.6 | <0.4 | <0.4 | <0.4 | <0.4 | 8.2 | <0.4 | <0.4 | <0.4 | <0.4 |
| | Chromium (hexavalent) | mg/kg | 1 | | <1 | - | - | - | - | - | <1 | - | - | - | - | - |
| | Chromium (III+VI) | mg/kg | 1 | 200 | 4 | 18 | 13 | 8 | 6 | 10 | 5 | 18 | 14 | 7 | 6 | 9 |
| | Cobalt | mg/kg | 1 | | <1 | - | - | - | - | - | <1 | - | - | - | - | - |
| | Copper | mg/kg | 1 | 220 | 2 | 230 | 47 | 8 | 5 | <1 | 7 | 240 | 30 | 7 | 5 | <1 |
| | Lead | mg/kg | 1 | 1,100 | 7 | 1,100 | 91 | 53 | 5 | 6 | 25 | 1,200 | 60 | 49 | 4 | 6 |
| | Manganese | mg/kg | 1 | | 2 | - | - | - | - | - | 7 | - | - | - | - | - |
| | Mercury | mg/kg | 0.1 | | <0.1 | 0.2 | 0.1 | 0.1 | <0.1 | <0.1 | <0.1 | 0.2 | <0.1 | 0.1 | <0.1 | <0.1 |
| | Molybdenum | mg/kg | 1 | | - | - | - | - | <1 | 1 | - | - | - | - | <1 | 2 |
| | Nickel | mg/kg | 1 | 170 | <1 | 11 | 9 | 2 | 2 | <1 | <1 | 13 | 3 | 2 | 2 | <1 |
| | Selenium | mg/kg | 2 | | <2 | - | - | - | <2 | <2 | <2 | - | - | - | <2 | <2 |
| | Silver | mg/kg | 1 | | - | - | - | - | <1 | <1 | - | - | - | - | <1 | <1 |
| | Tin | mg/kg | 1 | | - | - | - | - | <1 | <1 | - | - | - | - | <1 | <1 |
| | Zinc | mg/kg | 1 | 520 | 10 | 650 | 230 | 82 | - | - | 32 | 730 | 170 | 71 | - | - |
| Organic | Terbutylazine | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | - | - | - | - | - | - |

**Table 19: Soil Results Compared Against Adopted EILs**

**Australian Unity Limited**
**266 Longueville Road**
**Lane Cove**

| | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | **Sampled Date** | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 10/05/2018 | 11/05/2018 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 11/05/2018 | 11/05/2018 |
| | | | | **Sample Name** | Dup1 | Dup2 | Dup3 | Dup4 | Dup 5 | Dup 6 | Split 1 | Split 2 | Split 3 | Split 4 | Split 5 | Spilt 6 |
| | | | | **SampleDepth** | 0.1 | 0.1 | 0.1 | 0.1 | | | | | | | 5 | 6 |
| **Chemical Group** | **Chemical Name** | **Units** | **EQL** | Adopted Ecological Investigation Levels | | | | | | | | | | | | |
| Organochlorine Pesticides | 4,4-DDE | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | a-BHC | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Aldrin | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | b-BHC | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Chlordane (cis) | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Chlordane (trans) | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | d-BHC | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | DDD | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | DDT | mg/kg | 0.1 | 180 | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | DDT+DDE+DDD | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Dieldrin | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Endosulfan I | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Endosulfan II | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Endosulfan sulphate | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Endrin | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Endrin aldehyde | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | g-BHC (Lindane) | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Heptachlor | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Heptachlor epoxide | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Methoxychlor | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Toxaphene | mg/kg | 2 | | <2 | - | - | - | - | - | <2 | - | - | - | - | - |
| Organophosphorous Pesticides | Azinophos methyl | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | - | - | - | - | - | - |
| | Bromophos-ethyl | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | - | - | - | - | - | - |
| | Chlorpyrifos | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Chlorpyrifos-methyl | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | - | - | - | - | - | - |
| | Diazinon | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | - | - | - | - | - | - |
| | Dichlorvos | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | - | - | - | - | - | - |
| | Dimethoate | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | - | - | - | - | - | - |
| | Ethion | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | - | - | - | - | - | - |
| | Fenitrothion | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | - | - | - | - | - | - |
| | Malathion | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | - | - | - | - | - | - |
| | Ronnel | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | - | - | - | - | - | - |
| Other | 3,5-Dichlorobenzoic acid | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Actril (loxynil) | mg/kg | 1 | | <1 | - | - | - | - | - | <1 | - | - | - | - | - |
| PAH/Phenols | PAH (total, NSW Waste 2008) | mg/kg | | | <1.35 | - | - | - | <1.35 | <1.35 | 0.73 | - | - | - | - | - |
| | 2,4-dimethylphenol | mg/kg | 0.2 | | <0.2 | - | - | - | - | - | <0.2 | - | - | - | - | - |
| | 2,4-dinitrophenol | mg/kg | 2 | | <4 | - | - | - | - | - | <2 | - | - | - | - | - |
| | 2-methylphenol | mg/kg | 0.2 | | <0.2 | - | - | - | - | - | <0.2 | - | - | - | - | - |
| | 2-nitrophenol | mg/kg | 0.2 | | <0.2 | - | - | - | - | - | <0.2 | - | - | - | - | - |
| | 4,6-Dinitro-2-methylphenol | mg/kg | 2 | | <2 | - | - | - | - | - | - | - | - | - | - | - |
| | 4-chloro-3-methylphenol | mg/kg | 1 | | <1 | - | - | - | - | - | <2 | - | - | - | - | - |
| | 4-methylphenol | mg/kg | | | - | - | - | - | - | - | <0.4 | - | - | - | - | - |
| | 4-nitrophenol | mg/kg | 4 | | <4 | - | - | - | - | - | <4 | - | - | - | - | - |
| | Acenaphthene | mg/kg | 0.1 | | <0.1 | - | - | - | <0.1 | <0.1 | <0.1 | - | - | - | - | - |
| | Acenaphthylene | mg/kg | 0.1 | | <0.1 | - | - | - | <0.1 | <0.1 | <0.1 | - | - | - | - | - |
| | Anthracene | mg/kg | 0.1 | | <0.1 | - | - | - | <0.1 | <0.1 | <0.1 | - | - | - | - | - |
| | Benz(a)anthracene | mg/kg | 0.1 | | <0.1 | - | - | - | <0.1 | <0.1 | <0.1 | - | - | - | - | - |
| | Benzo(a) pyrene | mg/kg | 0.05 | | <0.05 | - | - | - | <0.05 | <0.05 | 0.08 | - | - | - | - | - |
| | Benzo(b+k)fluoranthene | mg/kg | | | - | - | - | - | - | - | <0.2 | - | - | - | - | - |
| | Benzo(g,h,i)perylene | mg/kg | 0.1 | | <0.1 | - | - | - | <0.1 | <0.1 | <0.1 | - | - | - | - | - |
| | Chrysene | mg/kg | 0.1 | | <0.1 | - | - | - | <0.1 | <0.1 | <0.1 | - | - | - | - | - |
| | Cresol Total | mg/kg | | | - | - | - | - | - | - | <0.2 | - | - | - | - | - |
| | Dibenz(a,h)anthracene | mg/kg | 0.1 | | <0.1 | - | - | - | <0.1 | <0.1 | <0.1 | - | - | - | - | - |
| | Fluoranthene | mg/kg | 0.1 | | <0.1 | - | - | - | <0.1 | <0.1 | <0.1 | - | - | - | - | - |
| | Fluorene | mg/kg | 0.1 | | <0.1 | - | - | - | <0.1 | <0.1 | <0.1 | - | - | - | - | - |
| | Indeno(1,2,3-c,d)pyrene | mg/kg | 0.1 | | <0.1 | - | - | - | <0.1 | <0.1 | <0.1 | - | - | - | - | - |
| | Naphthalene | mg/kg | 0.1 | 170 | <0.1 | - | - | - | <0.1 | <0.1 | <0.1 | - | - | - | - | - |
| | PAHs (Sum of total) | mg/kg | | | - | - | - | - | - | - | 0.08 | - | - | - | - | - |
| | Phenanthrene | mg/kg | 0.1 | | <0.1 | - | - | - | <0.1 | <0.1 | <0.1 | - | - | - | - | - |
| | Phenol | mg/kg | 0.2 | | <0.2 | - | - | - | - | - | <0.2 | - | - | - | - | - |
| | Phenolics Total | mg/kg | 0.2 | | <5 | - | - | - | - | - | <0.2 | - | - | - | - | - |
| | Picloram | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Pyrene | mg/kg | 0.1 | | <0.1 | - | - | - | <0.1 | <0.1 | <0.1 | - | - | - | - | - |
| Pesticides | Pesticides (total, NSW Waste 2008) | mg/kg | | | <3.6 | - | - | - | - | - | <3 | - | - | - | - | - |
| | Bifenthrin | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Mirex | mg/kg | 0.5 | | <0.5 | - | - | - | - | - | <0.5 | - | - | - | - | - |
| | Parathion | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | - | - | - | - | - | - |
| Phthalates | Bis(2-ethylhexyl) phthalate | mg/kg | 5 | | - | - | - | - | - | - | - | - | - | - | - | - |
| | Butyl benzyl phthalate | mg/kg | 1 | | - | - | - | - | - | - | - | - | - | - | - | - |
| | Diethylphthalate | mg/kg | 1 | | - | - | - | - | - | - | - | - | - | - | - | - |
| | Dimethyl phthalate | mg/kg | 1 | | - | - | - | - | - | - | - | - | - | - | - | - |
| | Di-n-butyl phthalate | mg/kg | 5 | | - | - | - | - | - | - | - | - | - | - | - | - |
| | Di-n-octyl phthalate | mg/kg | 1 | | - | - | - | - | - | - | - | - | - | - | - | - |
| Polychlorinated Biphenyls | Arochlor 1016 | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Arochlor 1221 | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Arochlor 1232 | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Arochlor 1242 | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Arochlor 1248 | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Arochlor 1254 | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | Arochlor 1260 | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| | PCBs (Sum of total) | mg/kg | 0.1 | | <0.1 | - | - | - | - | - | <0.1 | - | - | - | - | - |
| Solvents | Cyclohexane | mg/kg | 1 | | - | - | - | - | - | - | <1 | - | - | - | - | - |
| TRH | C10-C16 | mg/kg | 50 | | <50 | - | - | - | <50 | <50 | <50 | - | - | - | - | - |
| | C16-C34 | mg/kg | 100 | | <100 | - | - | - | <100 | <100 | <100 | - | - | - | - | - |
| | C34-C40 | mg/kg | 100 | | <100 | - | - | - | <100 | <100 | <100 | - | - | - | - | - |
| | F2-NAPHTHALENE | mg/kg | 50 | | <50 | - | - | - | <50 | <50 | <50 | - | - | - | - | - |
| | C6 - C9 | mg/kg | 25 | | <25 | - | - | - | <25 | <25 | <25 | - | - | - | - | - |
| | C10 - C14 | mg/kg | 50 | | <50 | - | - | - | <50 | <50 | <50 | - | - | - | - | - |
| | C15 - C28 | mg/kg | 100 | | <100 | - | - | - | <100 | <100 | <100 | - | - | - | - | - |
| | C29-C36 | mg/kg | 100 | | <100 | - | - | - | <100 | <100 | <100 | - | - | - | - | - |
| | +C10 - C36 (Sum of total) | mg/kg | | | - | - | - | - | - | - | <50 | - | - | - | - | - |
| | C10 - C40 (Sum of total) | mg/kg | 50 | | <50 | - | - | - | <50 | <50 | <50 | - | - | - | - | - |
| | C6-C10 | mg/kg | 25 | | <25 | - | - | - | <25 | <25 | <25 | - | - | - | - | - |

# Table 20: Soil Results Compared Against NSW EPA 2008 Waste Criteria

**Australian Unity Limited**
**266 Langueville Road**
**Lane Cove, NSW**

| | | |

# Table 20: Soil Results Compared Against NSW EPA 2008 Waste Criteria

**Australian Unity Limited**
**266 Langueville Road**
**Lane Cove, NSW**

| | | |

LRM GLOBAL

# Table 20: Soil Results Compared Against NSW EPA 2008 Waste Criteria

**Australian Unity Limited**
**266 Langueville Road**
**Lane Cove, NSW**

| | | |

# Table 20: Soil Results Compared Against NSW EPA 2008 Waste Criteria

**Australian Unity Limited**
**266 Langueville Road**
**Lane Cove, NSW**

| | | |

**Table 20: Soil Results Compared Against NSW EPA 2008 Waste Criteria**

**Australian Unity Limited**
**266 Langueville Road**
**Lane Cove, NSW**

| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | **Sampled Date** | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 10/05/2018 | 11/05/2018 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| | | | | | **Sample Loc.** | BH43_5.0 | BH43_6.0 | BH43_7.0 | BH43_8.0 | BH43_9.0 | BH44_5.0 | BH44_6.0 | BH44_7.0 | BH44_8.0 | BH44_9.0 | BH45_7.0 | BH45_7.8 | BH45_8.0 | BH46_0.2 | BH46_0.5 | BH46_1.0 | BH46_2.0 | BH46_2.3 | BH47_3.6 | BH47_5.0 | BH47_6.0 | BH47_6.5 | BH47_7.0 | Dup1 | Dup2 | Dup3 | Dup4 | Dup 5 | Dup 6 | BH16 - [SPLIT] | BH29 - [SPLIT] | BH30 - [SPLIT] |
| | | | | | **Sample Depth** | 5 | 6 | 7 | 8 | 9 | 5 | 6 | 7 | 8 | 9 | 7 | 7.8 | 8 | 0.2 | 0.5 | 1 | 2 | 2.3 | 3.6 | 5 | 6 | 6.5 | 7 | 0.1 | 0.1 | 0.1 | 0.1 | | | 0.1 | 8 | 6 |
| | | | | NSW 2008 Restricted Waste | NSW 2008 Hazardous Waste | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| **Chemical Group** | **Chemical Name** | **Units** | **EQL** | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 3/4-Methylphenol (m/p-cresol) | mg/kg | 0.4 | | | <0.4 | - | - | - | <0.4 | <0.4 | - | - | - | <0.4 | <0.4 | - | <0.4 | <0.4 | - | - | - | <0.4 | <0.4 | - | - | - | <0.4 | <0.4 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Benzo(a)pyrene TEQ (LOR) | mg/kg | 0.5 | | | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | - | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - |
| | Benzo(b+j+k)fluoranthene | mg/kg | 0.2 | | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | 0.4 | 0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | - | - | - | - | <0.2 | <0.2 | - | - | - | - | - | - | - |
| | DCPA (Chlorthal) Diacid | mg/kg | 0.5 | | | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Plasticiser Compounds | mg/kg | 5 | 20 | 80 | <5 | - | - | - | <5 | <5 | - | - | - | <5 | <5 | - | <5 | <5 | - | - | - | <5 | <5 | - | - | - | <5 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Scheduled chemicals (NSW Waste 2008) | mg/kg | 7.5 | | | <7.5 | - | - | - | <7.5 | <7.5 | - | - | - | <7.5 | <7.5 | - | <7.5 | <7.5 | - | - | - | <7.5 | <7.5 | - | - | - | <7.5 | <2.5 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Total Positive PAHs | mg/kg | 0.05 | | | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | 0.65 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | 2.4 | 1.1 | <0.05 | <0.05 | 0.3 | <0.05 | - | - | - | - | <0.05 | <0.05 | - | - | - | - | - | - | - |
| | Benzo(a)pyrene TEQ calc (Half) | mg/kg | 0.5 | | | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | - | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - |
| | Benzo(a)pyrene TEQ calc (Zero) | mg/kg | 0.5 | | | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | - | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - |
| | Metribuzin | mg/kg | 0.5 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Acid Herbicides in Soil | 2,6-D | mg/kg | 0.5 | | | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Triazine Herb Soil | Irgarol | mg/kg | 0.5 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| BTEX | Benzene | mg/kg | 0.2 | 10 | 40 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | - | - | - | - | <0.2 | <0.2 | - | - | - | - | - | - | - |
| | Ethylbenzene | mg/kg | 1 | 600 | 2400 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | - | - | - | - | <1 | <1 | - | - | - | - | - | - | - |
| | Toluene | mg/kg | 0.5 | 288 | 1152 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | - | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - |
| | Xylene (m & p) | mg/kg | 2 | | | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | - | - | - | - | <2 | <2 | - | - | - | - | - | - | - |
| | Xylene (o) | mg/kg | 1 | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | - | - | - | - | <1 | <1 | - | - | - | - | - | - | - |
| | Xylene Total | mg/kg | 1 | 1000 | 4000 | - | <1 | <1 | <1 | - | - | <1 | <1 | <1 | - | - | <1 | - | - | <1 | <1 | <1 | - | - | <1 | <1 | <1 | - | <1 | <1 | - | - | - | - | <1 | <1 | - | - | - | - | - | - | - |
| | C6-C10 less BTEX (F1) | mg/kg | 25 | | | - | <25 | <25 | <25 | - | - | <25 | <25 | <25 | - | - | <25 | - | - | <25 | <25 | <25 | - | - | <25 | <25 | <25 | - | <25 | <25 | - | - | - | - | <25 | <25 | - | - | - | - | - | - | - |
| Chlorinated Hydrocarbons | 1,1,1,2-tetrachloroethane | mg/kg | 1 | 200 | 800 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,1,1-trichloroethane | mg/kg | 1 | 600 | 2400 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,1,2,2-tetrachloroethane | mg/kg | 1 | 26 | 104 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,1,2-trichloroethane | mg/kg | 1 | 24 | 96 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,1-dichloroethane | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,1-dichloroethene | mg/kg | 1 | 14 | 56 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,1-dichloropropene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,2,3-trichloropropane | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,2-dibromo-3-chloropropane | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,2-dichloroethane | mg/kg | 1 | 10 | 40 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,2-dichloropropane | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,3-dichloropropane | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,2-dichloropropane | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Bromochloromethane | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Bromodichloromethane | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Bromoform | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Carbon tetrachloride | mg/kg | 1 | 10 | 40 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Chlorodibromomethane | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Chloroethane | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Chloroform | mg/kg | 1 | 120 | 480 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Chloromethane | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | cis-1,2-dichloroethene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | cis-1,3-dichloropropene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Dibromomethane | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Hexachlorobutadiene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Trichloroethene | mg/kg | 1 | 10 | 40 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Tetrachloroethene | mg/kg | 1 | 14 | 56 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | trans-1,2-dichloroethene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | trans-1,3-dichloropropene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Vinyl chloride | mg/kg | 1 | 4 | 16 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Explosives | Nitrobenzene | mg/kg | 0.1 | 40 | 160 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Halogenated Benzenes | 1,2,3-trichlorobenzene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,2,4-trichlorobenzene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,2-dichlorobenzene | mg/kg | 1 | 86 | 344 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,3-dichlorobenzene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 1,4-dichlorobenzene | mg/kg | 1 | 150 | 600 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2-chlorotoluene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 4-chlorotoluene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Bromobenzene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Chlorobenzene | mg/kg | 1 | 2000 | 8000 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Hexachlorobenzene | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Halogenated Hydrocarbons | 1,2-dibromoethane | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Bromomethane | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Dichlorodifluoromethane | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Trichlorofluoromethane | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Halogenated Phenols | 2,3,4,6-tetrachlorophenol | mg/kg | 0.2 | | | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4,5-trichlorophenol | mg/kg | 0.2 | 8000 | 32000 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4,6-trichlorophenol | mg/kg | 0.2 | 40 | 160 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4-dichlorophenol | mg/kg | 0.2 | | | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,6-dichlorophenol | mg/kg | 0.2 | | | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2-chlorophenol | mg/kg | 0.2 | | | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Pentachlorophenol | mg/kg | 1 | | | <5 | - | - | - | <5 | <5 | - | - | - | <5 | <5 | - | <5 | <5 | - | - | - | <5 | <5 | - | - | - | <5 | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Herbicides | 2,4,5-Trichlorophenoxy Acetic Acid | mg/kg | 0.5 | | | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4,5-TP (Silvex) | mg/kg | 0.5 | | | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4-dichlorophenoxybutanoic acid | mg/kg | 0.5 | | | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Hedonal | mg/kg | 0.5 | 200 | 800 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4-Dichlorprop | mg/kg | 0.5 | | | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4,6-Trichlorophenoxy-acetic acid | mg/kg | 0.5 | | | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2-Chlorophenoxyacetic acid | mg/kg | 0.5 | | | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 4-Chlorophenoxy acetic acid | mg/kg | 0.5 | | | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Ametryn | mg/kg | 0.5 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Acifluorfen | mg/kg | 2 | | | <2 | - | - | - | <2 | <2 | - | - | - | <2 | <2 | - | <2 | <2 | - | - | - | <2 | <2 | - | - | - | <2 | <2 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Atrazine | mg/kg | 0.5 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Bromoxynil | mg/kg | 0.5 | | | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Clopyralid | mg/kg | 0.5 | | | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Cyanazine | mg/kg | 0.5 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Dicamba | mg/kg | 0.5 | | | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Dinoseb | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Hexazinone | mg/kg | 0.5 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2-Methyl-4-chlorophenoxyacetic acid | mg/kg | 0.5 | | | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2-Methyl-4-Chlorophenoxy Butanoic Acid | mg/kg | 0.5 | | | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Mecoprop | mg/kg | 0.5 | | | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Prometryn | mg/kg | 0.5 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Propazine | mg/kg | 0.5 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Simazine | mg/kg | 0.5 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Terbutryn | mg/kg | 0.5 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Triclopyr | mg/kg | 0.5 | 40 | 160 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - |

LRM GLOBAL

# Table 20: Soil Results Compared Against NSW EPA 2008 Waste Criteria

**Australian Unity Limited**
**266 Langueville Road**
**Lane Cove, NSW**

| | | | | | Sampled Date | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 10/05/2018 | 11/05/2018 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | Sample Loc. | BH43_5.0 | BH43_6.0 | BH43_7.0 | BH43_8.0 | BH43_9.0 | BH44_5.0 | BH44_6.0 | BH44_7.0 | BH44_8.0 | BH44_9.0 | BH45_7.0 | BH45_7.8 | BH45_8.0 | BH46_0.2 | BH46_0.5 | BH46_1.0 | BH46_2.0 | BH46_2.3 | BH47_3.6 | BH47_5.0 | BH47_6.0 | BH47_6.5 | BH47_7.0 | Dup1 | Dup2 | Dup3 | Dup4 | Dup 5 | Dup 6 | BH16 - [SPLIT] | BH29 - [SPLIT] | BH30 - [SPLIT] |
| | | | | | Sample Depth | 5 | 6 | 7 | 8 | 9 | 5 | 6 | 7 | 8 | 9 | 7 | 7.8 | 8 | 0.2 | 0.5 | 1 | 2 | 2.3 | 3.6 | 5 | 6 | 6.5 | 7 | 0.1 | 0.1 | 0.1 | 0.1 | | | 0.1 | 8 | 6 |
| | | | | NSW 2008 Restricted Waste | NSW 2008 Hazardous Waste | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| **Chemical Group** | **Chemical Name** | **Units** | **EQL** | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Inorganics | Cyanide (Free) | mg/kg | 0.5 | | | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - | - |
| | Cyanide Total | mg/kg | 0.5 | 320 | 1280 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - |
| | Fluoride | mg/kg | 50 | 3000 | 12000 | <50 | - | - | - | <50 | <50 | - | - | - | <50 | <50 | - | <50 | <50 | - | - | - | <50 | <50 | - | - | - | <50 | - | - | - | - | - | - | - | - | - |
| MAH | 1,2,4-trimethylbenzene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - |
| | 1,3,5-trimethylbenzene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - |
| | Isopropylbenzene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - |
| | n-butylbenzene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - |
| | n-propylbenzene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - |
| | p-isopropyltoluene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - |
| | sec-butylbenzene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - |
| | Styrene | mg/kg | 1 | 60 | 240 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - |
| | tert-butylbenzene | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - | - | - |
| Metals | Arsenic | mg/kg | 4 | 100 | 400 | <4 | <4 | <4 | <4 | <4 | <4 | 8 | <4 | <4 | <4 | <4 | <4 | <4 | <4 | <4 | <4 | <4 | <4 | 4 | <4 | 4 | <4 | <4 | 5 | 14 | <4 | <4 | <4 | 8 | <4 | <4 |
| | Beryllium | mg/kg | 1 | 20 | 80 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <1 | - | - | - | - | - | <1 | - | - |
| | Boron | mg/kg | 3 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <3 | - | - | - | - | - | <3 | - | - |
| | Cadmium | mg/kg | 0.4 | 20 | 80 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | 6 | 0.6 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 |
| | Chromium (hexavalent) | mg/kg | 1 | 100 | 400 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | - | - | - | - | - | - |
| | Chromium (III+VI) | mg/kg | 1 | | | 5 | 7 | 7 | 7 | 7 | 4 | 15 | 12 | 16 | 13 | 9 | 9 | 12 | 5 | 5 | 3 | 9 | 10 | 9 | 9 | 10 | 9 | 6 | 4 | 18 | 13 | 8 | 6 | 10 | 16 | 8 | 17 |
| | Cobalt | mg/kg | 1 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <1 | - | - | - | - | - | 4 | - | - |
| | Copper | mg/kg | 1 | | | 4 | 6 | 5 | 5 | 4 | 1 | 3 | 4 | 5 | 3 | 4 | 2 | 6 | <1 | <1 | <1 | <1 | <1 | 4 | 3 | 6 | 5 | 2 | 2 | 230 | 47 | 8 | 5 | <1 | 30 | 6 | 19 |
| | Lead | mg/kg | 1 | 100 | 400 | 5 | 7 | 6 | 5 | 4 | 4 | 12 | 4 | 3 | 4 | 10 | 16 | 19 | 6 | 7 | 7 | 6 | 5 | 25 | 14 | 14 | 13 | 8 | 7 | 1,100 | 91 | 53 | 5 | 6 | 110 | 3,700 | 490 |
| | Manganese | mg/kg | 1 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 2 | - | - | - | - | - | 190 | - | - |
| | Mercury | mg/kg | 0.1 | 4 | 16 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | 0.2 | 0.1 | 0.1 | <0.1 | <0.1 | 0.2 | <0.1 | 0.1 |
| | Molybdenum | mg/kg | 1 | 100 | 400 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | 1 | 1 | <1 | <1 | <1 | 1 | <1 | - | - | - | - | <1 | 1 | - | - | - |
| | Nickel | mg/kg | 1 | 40 | 160 | 2 | 2 | 3 | 2 | 2 | <1 | 1 | 2 | 5 | 3 | 3 | 1 | 3 | <1 | <1 | <1 | <1 | 2 | 3 | 1 | 1 | 1 | <1 | 11 | 9 | 2 | 2 | <1 | 12 | 3 | 11 |
| | Selenium | mg/kg | 2 | 20 | 80 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | - | - | - | <2 | <2 | <2 | - | - |
| | Silver | mg/kg | 1 | 100 | 400 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | - | - | - | - | <1 | <1 | - | - | - |
| | Tin | mg/kg | 1 | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | - | - | - | - | <1 | <1 | - | - | - |
| | Zinc | mg/kg | 1 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 10 | 650 | 230 | 82 | - | - | 130 | 79 | 370 |
| Organic | Terbutylazine | mg/kg | 0.5 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - |
| Organochlorine Pesticides | 4,4-DDE | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | a-BHC | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Aldrin | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | b-BHC | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Chlordane (cis) | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Chlordane (trans) | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | d-BHC | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | DDD | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | DDT | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | DDT+DDE+DDD | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Dieldrin | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Endosulfan I | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Endosulfan II | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Endosulfan sulphate | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Endrin | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Endrin aldehyde | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | g-BHC (Lindane) | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Heptachlor | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Heptachlor epoxide | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Methoxychlor | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Toxaphene | mg/kg | 2 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <2 | - | - | - | - | - | - | - | - |
| Organophosphorous Pesticides | Azinophos methyl | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Bromophos-ethyl | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Chlorpyrifos | mg/kg | 0.1 | 4 | 16 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Chlorpyrifos-methyl | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Diazinon | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Dichlorvos | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Dimethoate | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Ethion | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Fenitrothion | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Malathion | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| | Ronnel | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| Other | 3,5-Dichlorobenzoic acid | mg/kg | 0.5 | | | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - |
| | Actril (loxynil) | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | - | - | - | - | - |
| PAH/Phenols | PAH (total, NSW Waste 2008) | mg/kg | | | | <1.35 | <1.35 | <1.35 | <1.35 | <1.35 | <1.35 | 1.09 | <1.35 | <1.35 | <1.35 | <1.35 | <1.35 | <1.35 | <1.35 | <1.35 | <1.35 | <1.35 | 2.3 | 1.25 | <1.35 | <1.35 | 0.81 | <1.35 | - | - | - | <1.35 | <1.35 | - | - | - |
| | 2,4-dimethylphenol | mg/kg | 0.2 | | | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | - | - | - | - | - |
| | 2,4-dinitrophenol | mg/kg | 4 | | | <4 | - | - | - | <4 | <4 | - | - | - | <4 | <4 | - | <4 | <4 | - | - | - | <4 | <4 | - | - | - | <4 | <4 | - | - | - | - | - | - | - | - |
| | 2-methylphenol | mg/kg | 0.2 | 4000 | 16000 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | - | - | - | - | - |
| | 2-nitrophenol | mg/kg | 0.2 | | | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | - | - | - | - | - |
| | 4,6-Dinitro-2-methylphenol | mg/kg | 2 | | | <10 | - | - | - | <10 | <10 | - | - | - | <10 | <10 | - | <10 | <10 | - | - | - | <10 | <10 | - | - | - | <10 | <2 | - | - | - | - | - | - | - | - |
| | 4-chloro-3-methylphenol | mg/kg | 1 | | | <5 | - | - | - | <5 | <5 | - | - | - | <5 | <5 | - | <5 | <5 | - | - | - | <5 | <5 | - | - | - | <5 | <1 | - | - | - | - | - | - | - | - |
| | 4-nitrophenol | mg/kg | 4 | | | <4 | - | - | - | <4 | <4 | - | - | - | <4 | <4 | - | <4 | <4 | - | - | - | <4 | <4 | - | - | - | <4 | <4 | - | - | - | - | - | - | - | - |
| | Acenaphthene | mg/kg | 0.1 | | | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - |
| | Acenaphthylene | mg/kg | 0.1 | | | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - |
| | Anthracene | mg/kg | 0.1 | | | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - |
| | Benz(a)anthracene | mg/kg | 0.1 | | | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | 0.2 | 0.1 | <0.1 | <0.1 | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - |
| | Benzo(a) pyrene | mg/kg | 0.05 | 0.8 | 3.2 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | 0.09 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | 0.2 | 0.1 | <0.05 | <0.05 | 0.06 | <0.05 | - | - | - | <0.05 | <0.05 | - | - | - |
| | Benzo(g,h,i)perylene | mg/kg | 0.1 | | | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | 0.2 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - |
| | Chrysene | mg/kg | 0.1 | | | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | 0.2 | 0.1 | <0.1 | <0.1 | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - |
| | Dibenz(a,h)anthracene | mg/kg | 0.1 | | | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - |
| | Fluoranthene | mg/kg | 0.1 | | | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | 0.2 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | 0.4 | 0.2 | <0.1 | <0.1 | 0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - |
| | Fluorene | mg/kg | 0.1 | | | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - |
| | Indeno(1,2,3-c,d)pyrene | mg/kg | 0.1 | | | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | 0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - |
| | Naphthalene | mg/kg | 0.1 | | | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - |
| | Phenanthrene | mg/kg | 0.1 | | | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | 0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | 0.2 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - |
| | Phenol | mg/kg | 0.2 | | | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | <0.2 | <0.2 | - | - | - | - | - | - | - | - |
| | Phenolics Total | mg/kg | 5 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <5 | - | - | - | - | - | - | - | - |
| | Picloram | mg/kg | 0.5 | 60 | 240 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | <0.5 | <0.5 | - | - | - | - | - | - | - | - |
| | Pyrene | mg/kg | 0.1 | | | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | 0.2 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | 0.5 | 0.3 | <0.1 | <0.1 | 0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - |
| Pesticides | Pesticides (total, NSW Waste 2008) | mg/kg | | | | <5.6 | - | - | - | <5.6 | <5.6 | - | - | - | <5.6 | <5.6 | - | <5.6 | <5.6 | - | - | - | <5.6 | <5.6 | - | - | - | <5.6 | <3.6 | - | - | - | - | - | - | - | - |
| | Bifenthrin | mg/kg | 0.5 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - |
| | Mirex | mg/kg | 0.5 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - |
| | Parathion | mg/kg | 0.1 | | | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | <0.1 | <0.1 | - | - | - | - | - | - | - | - |
| Phthalates | Bis(2-ethylhexyl) phthalate | mg/kg | 5 | | | <5 | - | - | - | <5 | <5 | - | - | - | <5 | <5 | - | <5 | <5 | - | - | - | <5 | <5 | - | - | - | <5 | - | - | - | - | - | - | - | - |
| | Butyl benzyl phthalate | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - |
| | Diethylphthalate | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - |
| | Dimethyl phthalate | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - |
| | Di-n-butyl phthalate | mg/kg | 5 | | | <5 | - | - | - | <5 | <5 | - | - | - | <5 | <5 | - | <5 | <5 | - | - | - | <5 | <5 | - | - | - | <5 | - | - | - | - | - | - | - | - |
| | Di-n-octyl phthalate | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - |
| Polychlorinated Biphenyls | Arochlor 1016 | mg/kg | 0.1 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.1 | - | - | - | - | - | - | - | - |
| | Arochlor 1221 | mg/kg | 0.1 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.1 | - | - | - | - | - | - | - | - |
| | Arochlor 1232 | mg/kg | 0.1 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.1 | - | - | - | - | - | - | - | - |
| | Arochlor 1242 | mg/kg | 0.1 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.1 | - | - | - | - | - | - | - | - |
| | Arochlor 1248 | mg/kg | 0.1 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.1 | - | - | - | - | - | - | - | - |
| | Arochlor 1254 | mg/kg | 0.1 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.1 | - | - | - | - | - | - | - | - |
| | Arochlor 1260 | mg/kg | 0.1 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.1 | - | - | - | - | - | - | - | - |
| | PCBs (Sum of total) | mg/kg | 0.1 | | | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.1 | - | - | - | - | - | - | - | - |
| Solvents | Cyclohexane | mg/kg | 1 | | | <1 | - | - | - | <1 | <1 | - | - | - | <1 | <1 | - | <1 | <1 | - | - | - | <1 | <1 | - | - | - | <1 | - | - | - | - | - | - | - | - |
| TPH | C10-C16 | mg/kg | 50 | | | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 | - | - | - | <50 | <50 | - | - | - |
| | C16-C34 | mg/kg | 100 | | | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | - | - | - | <100 | <100 | - | - | - |
| | C34-C40 | mg/kg | 100 | | | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | <100 | - | - | - | <100 | <100 | - | - | - |
| | F2-NAPHTHALENE | mg/kg | 50 | | | - | <50 | <50 | <50 | - | - | <50 | <50 | <50 | - | - | <50 | - | - | <50 | <50 | <50 | - | - | <50 | <50 | <50 | - | <50 | - | - | - | <50 | <50 | - | - | - |
| | C6 - C9 | mg/kg | 25 | 650 | 2,600 | <25 | <25

# Table 21: Groundwater Results

**Australian Unity Ltd**
**266 Longueville Road,**
**Lane Cove**

| | | | | | | | | | Round 1 | | Round 2 | | Round 1 | QA/QC | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | Field ID | GW01 | GW01 | GW02 | GW02 | GW03 | Dup 1 | DUP/03/08/18 | Split 1 | SPLIT/03/08/18 |
| | | | | | | | | Sampled Date | 14/05/2018 | 3/08/2018 | 14/05/2018 | 3/08/2018 | 3/08/2018 | 14/05/2018 | 3/08/2018 | 14/05/2018 | 3/08/2018 |
| Method Type | Chemical Name | Units | EQL | ADWG 2015 Aesthetic | ANZECC/ARMCANZ (2000) Fresh and Marine Water Quality. Irrigation | NEPM 2013 Table 1C GILs, Drinking Water | NEPM 2013 Table 1C GILs, Fresh Waters | | | | | | | | | | |
| Heavy Metals | Aluminium (Filtered) | mg/L | 0.01 | | 5 | | **0.055** | | **0.19** | **0.5** | **0.12** | **1.7** | 0.01 | **0.2** | **0.41** | **0.18** | **0.64** |
| | Antimony (Filtered) | mg/L | 0.001 | | | 0.003 | | | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| | Arsenic (Filtered) | mg/L | 0.001 | | 0.1 | 0.01 | | | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| | Barium (Filtered) | mg/L | 0.001 | | | 2 | | | 0.036 | 0.021 | 0.056 | 0.059 | 0.094 | 0.033 | 0.022 | 0.032 | 0.025 |
| | Beryllium (Filtered) | mg/L | 0.0005 | | 0.1 | 0.06 | | | 0.0005 | 0.0008 | <0.0005 | <0.0005 | <0.0005 | <0.0005 | 0.0007 | <0.0005 | 0.0009 |
| | Boron (Filtered) | mg/L | 0.02 | | 0.5 | 4 | **0.37** | | 0.09 | 0.06 | 0.1 | 0.04 | 0.1 | 0.09 | 0.06 | 0.09 | 0.08 |
| | Cadmium (Filtered) | mg/L | 0.0001 | | 0.01 | 0.002 | **0.0002** | | <0.0001 | <0.0001 | **0.0003** | <0.0001 | <0.0001 | <0.0001 | <0.0001 | <0.0001 | <0.0001 |
| | Chromium (III+VI) (Filtered) | mg/L | 0.001 | | 0.1 | | | | <0.001 | 0.001 | <0.001 | 0.002 | 0.001 | <0.001 | <0.001 | <0.001 | 0.001 |
| | Cobalt (Filtered) | mg/L | 0.001 | | 0.05 | | | | 0.011 | 0.004 | 0.018 | 0.001 | 0.005 | 0.011 | 0.004 | 0.011 | 0.005 |
| | Copper (Filtered) | mg/L | 0.001 | 1 | 0.2 | 2 | **0.0014** | | **0.019** | **0.006** | **0.012** | **0.018** | **0.009** | **0.007** | **0.032** | **0.007** | **0.007** |
| | Iron (Filtered) | mg/L | 0.01 | 0.3 | 0.2 | | | | 2.3 | 2.4 | 6.1 | 0.92 | 0.24 | 2.3 | 2 | 2.2 | 2.9 |
| | Lead (Filtered) | mg/L | 0.001 | | 2 | 0.01 | **0.0034** | | 0.001 | 0.002 | <0.001 | **0.005** | 0.001 | 0.001 | **0.004** | 0.001 | 0.003 |
| | Manganese (Filtered) | mg/L | 0.005 | 0.1 | 0.2 | 0.5 | **1.9** | | 0.22 | 0.16 | 0.27 | 0.036 | 0.18 | 0.22 | 0.15 | 0.21 | 0.19 |
| | Mercury (Filtered) | mg/L | 0.00005 | | 0.002 | 0.001 | **0.00006** | | <0.00005 | <0.00005 | <0.00005 | <0.00005 | 0.00005 | <0.00005 | <0.00005 | <0.00005 | <0.00005 |
| | Molybdenum (Filtered) | mg/L | 0.001 | | 0.01 | 0.05 | | | <0.001 | <0.001 | <0.001 | <0.001 | 0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| | Nickel (Filtered) | mg/L | 0.001 | | 1 | 0.02 | **0.011** | | **0.012** | **0.052** | **0.037** | **0.063** | **0.035** | 0.01 | **0.054** | 0.009 | **0.061** |
| | Selenium (Filtered) | mg/L | 0.001 | | 0.02 | 0.01 | **0.005** | | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| | Silver (Filtered) | mg/L | 0.001 | | | 0.1 | **0.00005** | | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| | Thallium (Filtered) | mg/L | 0.001 | | | | | | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| | Tin (Filtered) | mg/L | 0.001 | | | | | | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | 0.001 |
| | Vanadium (Filtered) | mg/L | 0.001 | | 0.1 | | | | <0.001 | <0.001 | <0.001 | <0.001 | 0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| | Zinc (Filtered) | mg/L | 0.001 | 3 | 0.02 | | **0.008** | | **0.068** | **0.22** | **0.12** | **0.23** | **0.056** | **0.062** | **0.2** | **0.061** | **0.26** |
| Inorganics | Alkalinity (Bicarbonate as CaCO3) | mg/L | 5 | | | | | | 8 | <5 | 7 | <5 | 230 | 7 | <5 | 7 | <5 |
| | Alkalinity (Carbonate) | mg/L | 5 | | | | | | <5 | <5 | <5 | <5 | <5 | <5 | <5 | <5 | - |
| | Alkalinity (Hydroxide) as CaCO3 | µg/L | 5000 | | | | | | <5000 | <5000 | <5000 | <5000 | <5000 | <5000 | <5000 | <5000 | - |
| | Alkalinity (total) as CaCO3 | mg/L | 5 | | | | | | 8 | <5 | 7 | <5 | 230 | 7 | <5 | 7 | <5 |
| | Calcium (Filtered) | mg/L | 0.5 | | | | | | 4.8 | 0.9 | 11 | 2 | 100 | 4.8 | 0.9 | 4.8 | 0.8 |
| | Carbonate as CaCO3 | mg/L | 5 | | | | | | - | - | - | - | - | - | - | - | <5 |
| | Chloride | mg/L | 1 | 250 | | | | | 93 | 110 | 39 | 48 | 30 | 89 | 110 | 88 | 110 |
| | Hydroxide | µg/L | 5000 | | | | | | - | - | - | - | - | - | - | - | <5000 |
| | Magnesium (Filtered) | mg/L | 0.5 | | | | | | 5.2 | 4.8 | 5.7 | 6.3 | 9.3 | 4.9 | 4.5 | 4.7 | 4.5 |
| | Potassium (Filtered) | mg/L | 0.5 | | | | | | 2.1 | 1.1 | 8.3 | 1 | 9.3 | 2 | 1.1 | 2 | 0.9 |
| | Sodium (Filtered) | mg/L | 0.5 | 180 | | | | | 140 | 140 | 32 | 33 | 16 | 130 | 140 | 130 | 110 |
| | Sulphate (Filtered) | mg/L | 1 | 250 | 1000 | 500 | | | 110 | 120 | 59 | 47 | 98 | 110 | 120 | 100 | 150 |
| | Ammonia | mg/L | 0.005 | 0.5 | | | **0.9** | | - | <0.005 | - | 0.041 | 0.34 | - | <0.005 | - | 0.007 |
| | Chromium (hexavalent) (Filtered) | mg/L | 0.005 | | | 0.05 | **0.001** | | <0.005 | <0.005 | <0.005 | <0.005 | <0.005 | <0.005 | <0.005 | <0.005 | - |
| | Cyanide Total | mg/L | 0.004 | | | 0.08 | **0.007** | | <0.004 | <0.004 | <0.004 | <0.004 | <0.004 | <0.004 | <0.004 | <0.004 | - |
| | Fluoride | mg/L | 0.1 | | 1 | 1.5 | | | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| | pH (Lab) | pH_Units | 0.1 | | | | | | 5 | 4.4 | 5.1 | 4.2 | 6.8 | 4.9 | 4.4 | 4.9 | 4.2 |
| | TDS | mg/L | 5 | 600 | | | | | 440 | 440 | 230 | 180 | 470 | 420 | 430 | 430 | 370 |
| OCP | 4,4-DDE | µg/L | 0.2 | | | | | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| | a-BHC | µg/L | 0.2 | | | | | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| | Aldrin | µg/L | 0.2 | | | | | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| | b-BHC | µg/L | 0.2 | | | | | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| | Chlordane (cis) | µg/L | 0.2 | | | | | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| | Chlordane (trans) | µg/L | 0.2 | | | | | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| | d-BHC | µg/L | 0.2 | | | | | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| | DDD | µg/L | 0.2 | | | | | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| | DDT | µg/L | 0.2 | | | 9 | **0.006** | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| | Dieldrin | µg/L | 0.2 | | | | | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| | Endosulfan I | µg/L | 0.2 | | | | | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| | Endosulfan II | µg/L | 0.2 | | | | | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| | Endosulfan sulphate | µg/L | 0.2 | | | | | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| | Endrin | µg/L | 0.2 | | | | **0.01** | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| | Endrin aldehyde | µg/L | 0.2 | | | | | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| | g-BHC (Lindane) | µg/L | 0.2 | | | 10 | **0.2** | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| | Heptachlor | µg/L | 0.2 | | | | **0.01** | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| | Heptachlor epoxide | µg/L | 0.2 | | | 0.3 | | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| | Hexachlorobenzene | µg/L | 0.2 | | | | | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| | Methoxychlor | µg/L | 0.2 | | | | | | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| PAHs | Acenaphthene | µg/L | 1 | | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Acenaphthylene | µg/L | 1 | | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Anthracene | µg/L | 1 | | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Benz(a)anthracene | µg/L | 1 | | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Benzo(a) pyrene | µg/L | 1 | | | 0.01 | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Benzo(b+k)fluoranthene | µg/L | | | | | | | - | - | - | - | - | - | - | - | <2 |
| | Benzo(g,h,i)perylene | µg/L | 1 | | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Chrysene | µg/L | 1 | | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Dibenz(a,h)anthracene | µg/L | 1 | | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Fluoranthene | µg/L | 1 | | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Fluorene | µg/L | 1 | | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Indeno(1,2,3-c,d)pyrene | µg/L | 1 | | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Naphthalene | µg/L | 1 | | | | **16** | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | PAHs (Sum of total) | µg/L | 1 | | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Phenanthrene | µg/L | 1 | | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Pyrene | µg/L | 1 | | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| PCBs | Arochlor 1016 | µg/L | 2 | | | | | | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 |
| | Arochlor 1221 | µg/L | 2 | | | | | | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 |
| | Arochlor 1232 | µg/L | 2 | | | | | | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 |
| | Arochlor 1242 | µg/L | 2 | | | | **0.3** | | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 |
| | Arochlor 1248 | µg/L | 2 | | | | | | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 |
| | Arochlor 1254 | µg/L | 2 | | | | **0.01** | | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 |
| | Arochlor 1260 | µg/L | 2 | | | | | | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 |
| PFAS Short | Total Positive PFAS | µg/L | 0.01 | | | | | | - | 0.02 | - | 0.01 | <0.01 | - | 0.03 | - | - |
| | Total Positive PFHxS & PFOS | µg/L | 0.01 | | | 0.07* | **0.7*** | | - | 0.02 | - | 0.01 | <0.01 | - | 0.03 | - | - |
| | Total Positive PFOA & PFOS | µg/L | 0.01 | | | | | | - | <0.01 | - | <0.01 | <0.01 | - | <0.01 | - | - |
| | 8:2 FTS | µg/L | 0.01 | | | | | | - | <0.01 | - | <0.01 | <0.01 | - | <0.01 | - | - |
| | Extracted ISTD 13C2 6:2FTS | % | | | | | | | - | 87 | - | 94 | 87 | - | 86 | - | - |
| | Extracted ISTD 13C2 8:2FTS | % | | | | | | | - | 68 | - | 67 | 75 | - | 61 | - | - |
| | Extracted ISTD 13C4 PFOA | % | | | | | | | - | 110 | - | 103 | 110 | - | 105 | - | - |
| | Extracted ISTD 13C4 PFOS | % | | | | | | | - | 82 | - | 89 | 77 | - | 82 | - | - |
| | Extracted ISTD 18O2 PFHxS | % | | | | | | | - | 86 | - | 81 | 75 | - | 72 | - | - |
| | 6:2 Fluorotelomer Sulfonate (6:2 FtS) | mg/L | 0.00001 | | | | | | - | <0.00001 | - | <0.00001 | <0.00001 | - | <0.00001 | - | - |
| | Perfluorohexanesulfonic acid - PFHxS | µg/L | 0.01 | | | | | | - | 0.02 | - | 0.01 | <0.01 | - | 0.03 | - | - |
| | Perfluorooctanesulfonic acid PFOS | µg/L | 0.01 | | 0.13* | | **0.13*** | | - | <0.01 | - | <0.01 | <0.01 | - | <0.01 | - | - |
| | Perfluorooctanoate PFOA | mg/L | 0.00001 | | 0.22* | 0.56* | **5.6*** | | - | <0.00001 | - | <0.00001 | <0.00001 | - | <0.00001 | - | - |

# Table 21: Groundwater Results

**Australian Unity Ltd**
**266 Longueville Road,**
**Lane Cove**

| | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | **Field ID** | GW01 | GW01 | GW02 | GW02 | GW03 | Dup 1 | DUP/03/08/18 | Split 1 | SPLIT/03/08/18 |
| | | | | | | | **Sampled Date** | 14/05/2018 | 3/08/2018 | 14/05/2018 | 3/08/2018 | 3/08/2018 | 14/05/2018 | 3/08/2018 | 14/05/2018 | 3/08/2018 |
| | | | | ADWG 2015 Aesthetic | ANZECC/ARMCANZ (2000) Fresh and Marine Water Quality. Irrigation | NEPM 2013 Table 1C GILs, Drinking Water | NEPM 2013 Table 1C GILs, Fresh Waters | | | | | | | | | |
| **Method Type** | **Chemical Name** | **Units** | **EQL** | | | | | | | | | | | | | |
| Phenols | Phenolics Total | µg/L | 50 | | | | | <50 | - | <50 | - | - | <50 | - | <50 | - |
| Phthalates | Bis(2-ethylhexyl) phthalate | µg/L | 50 | | | 10 | | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 |
| | Butyl benzyl phthalate | µg/L | 10 | | | | | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 |
| | Diethylphthalate | µg/L | 10 | | | | **1000** | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 |
| | Dimethyl phthalate | µg/L | 10 | | | | **3700** | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 |
| | Di-n-butyl phthalate | µg/L | 50 | | | | **10** | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 | <50 |
| | Di-n-octyl phthalate | µg/L | 10 | | | | | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 |
| svTRH (C10-C40) | C10-C16 | mg/L | 0.05 | | | | | - | <0.05 | - | <0.05 | <0.05 | - | <0.05 | - | - |
| | C16-C34 | mg/L | 0.1 | | | | | - | <0.1 | - | <0.1 | <0.1 | - | <0.1 | - | - |
| | C34-C40 | mg/L | 0.1 | | | | | - | <0.1 | - | <0.1 | <0.1 | - | <0.1 | - | - |
| | F2-NAPHTHALENE | mg/L | 0.05 | | | | | - | <0.05 | - | <0.05 | <0.05 | - | <0.05 | - | - |
| | C10 - C14 | µg/L | 50 | | | | | - | <50 | - | <50 | <50 | - | <50 | - | - |
| | C15 - C28 | µg/L | 100 | | | | | - | <100 | - | <100 | <100 | - | <100 | - | - |
| | C29-C36 | µg/L | 100 | | | | | - | <100 | - | <100 | <100 | - | <100 | - | - |
| Total Phenolics | Phenolics Total | µg/L | 50 | | | | | - | <50 | - | <50 | <50 | - | <50 | - | - |
| TRH Water(C10-C40) | C10-C16 | mg/L | 0.05 | | | | | <0.05 | - | <0.05 | - | - | <0.05 | - | <0.05 | <0.05 |
| | C16-C34 | mg/L | 0.1 | | | | | <0.1 | - | <0.1 | - | - | <0.1 | - | <0.1 | <0.1 |
| | C34-C40 | mg/L | 0.1 | | | | | <0.1 | - | <0.1 | - | - | <0.1 | - | <0.1 | <0.1 |
| | F2-NAPHTHALENE | mg/L | 0.05 | | | | | <0.05 | - | <0.05 | - | - | <0.05 | - | <0.05 | <0.05 |
| | C10 - C14 | µg/L | 50 | | | | | <50 | - | <50 | - | - | <50 | - | <50 | <50 |
| | C15 - C28 | µg/L | 100 | | | | | <100 | - | <100 | - | - | <100 | - | <100 | <100 |
| | C29-C36 | µg/L | 100 | | | | | <100 | - | <100 | - | - | <100 | - | <100 | <100 |
| VOCs | 1,1,1,2-tetrachloroethane | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 1,1,1-trichloroethane | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 1,1,2,2-tetrachloroethane | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 1,1,2-trichloroethane | µg/L | 1 | | | | **6500** | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 1,1-dichloroethane | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 1,1-dichloroethene | µg/L | 1 | | | 30 | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 1,1-dichloropropene | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 1,2,3-trichlorobenzene | µg/L | 1 | | | 30 | **3** | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 1,2,3-trichloropropane | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 1,2,4-trichlorobenzene | µg/L | 1 | | | 30 | **85** | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 1,2,4-trimethylbenzene | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 1,2-dibromo-3-chloropropane | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 1,2-dibromoethane | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 1,2-dichlorobenzene | µg/L | 1 | 1 | | 1500 | **160** | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 1,2-dichloroethane | µg/L | 1 | | | 3 | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 1,2-dichloropropane | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 1,3,5-trimethylbenzene | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 1,3-dichlorobenzene | µg/L | 1 | 20 | | | **260** | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 1,3-dichloropropane | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 1,4-dichlorobenzene | µg/L | 1 | 0.3 | | 40 | **60** | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 2,2-dichloropropane | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 2-chlorotoluene | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | 4-chlorotoluene | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Benzene | µg/L | 1 | | | 1 | **950** | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Bromobenzene | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Bromochloromethane | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Bromodichloromethane | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Bromoform | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Bromomethane | µg/L | 10 | | | 1 | | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 |
| | Carbon tetrachloride | µg/L | 1 | | | 3 | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Chlorobenzene | µg/L | 1 | 10 | | 300 | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Chlorodibromomethane | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Chloroethane | µg/L | 10 | | | | | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 |
| | Chloroform | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Chloromethane | µg/L | 10 | | | | | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 |
| | cis-1,2-dichloroethene | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | cis-1,3-dichloropropene | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Cyclohexane | mg/L | 0.001 | | | | | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| | Dibromomethane | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Dichlorodifluoromethane | µg/L | 10 | | | | | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 |
| | Ethylbenzene | µg/L | 1 | 3 | | 300 | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Hexachlorobutadiene | µg/L | 1 | | | 0.7 | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Isopropylbenzene | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | n-butylbenzene | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | n-propylbenzene | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | p-isopropyltoluene | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | sec-butylbenzene | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Styrene | µg/L | 1 | 4 | | 30 | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Trichloroethene | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | tert-butylbenzene | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Tetrachloroethene | µg/L | 1 | | | 50 | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Toluene | µg/L | 1 | 25 | | 800 | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | trans-1,2-dichloroethene | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | trans-1,3-dichloropropene | µg/L | 1 | | | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| | Trichlorofluoromethane | µg/L | 10 | | | | | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 |
| | Vinyl chloride | µg/L | 10 | | | 0.3 | | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 | <10 |
| | Xylene (m & p) | µg/L | 2 | | | | | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 | <2 |
| | Xylene (o) | µg/L | 1 | | | | **350** | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| vTRH & BTEXN | Benzene | µg/L | 1 | | | 1 | **950** | <1 | - | <1 | - | - | <1 | - | <1 | - |
| | Ethylbenzene | µg/L | 1 | 3 | | 300 | | <1 | - | <1 | - | - | <1 | - | <1 | - |
| | Naphthalene | µg/L | 1 | | | | **16** | <1 | - | <1 | - | - | <1 | - | <1 | - |
| | Toluene | µg/L | 1 | 25 | | 800 | | <1 | - | <1 | - | - | <1 | - | <1 | - |
| | C6 - C9 | µg/L | 10 | | | | | <10 | - | <10 | - | - | <10 | - | <10 | - |
| | Xylene (m & p) | µg/L | 2 | | | | | <2 | - | <2 | - | - | <2 | - | <2 | - |
| | Xylene (o) | µg/L | 1 | | | | **350** | <1 | - | <1 | - | - | <1 | - | <1 | - |
| | C6-C10 less BTEX (F1) | mg/L | 0.01 | | | | | <0.01 | - | <0.01 | - | - | <0.01 | - | <0.01 | - |
| | C6-C10 | mg/L | 0.01 | | | | | <0.01 | - | <0.01 | - | - | <0.01 | - | <0.01 | - |
| vTRH(C6-C10)/BTEXN | Benzene | µg/L | 1 | | | 1 | **950** | - | <1 | - | <1 | <1 | - | <1 | - | <1 |
| | Ethylbenzene | µg/L | 1 | 3 | | 300 | | - | <1 | - | <1 | <1 | - | <1 | - | <1 |
| | Naphthalene | µg/L | 1 | | | | **16** | - | <1 | - | <1 | <1 | - | <1 | - | <1 |
| | Toluene | µg/L | 1 | 25 | | 800 | | - | <1 | - | <1 | <1 | - | <1 | - | <1 |
| | C6 - C9 | µg/L | 10 | | | | | - | <10 | - | <10 | <10 | - | <10 | - | <10 |
| | Xylene (m & p) | µg/L | 2 | | | | | - | <2 | - | <2 | <2 | - | <2 | - | <2 |
| | Xylene (o) | µg/L | 1 | | | | **350** | - | <1 | - | <1 | <1 | - | <1 | - | <1 |
| | C6-C10 less BTEX (F1) | mg/L | 0.01 | | | | | - | <0.01 | - | <0.01 | <0.01 | - | <0.01 | - | <0.01 |
| | C6-C10 | mg/L | 0.01 | | | | | - | <0.01 | - | <0.01 | <0.01 | - | <0.01 | - | <0.01 |

# Table 22: Soil RPDs

**Australian Unity Ltd**
**266 Longueville Road**
**Lane Cove**

| Method Type | Chemical Name | Units | EQL | Lab Report Number | 170939 | 170939 | | 170939 | 170939 | | 170939 | 170939 | | 170939 | 170939 | | 191466 | 191466 | | 191466 | 191466 | | 170939 | 11218 | | 170939 | 11218 | | 170939 | 11218 | | 170939 | 11218 | | 191466 | 191466 | | 191466 | 191466 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | Field ID | BH34 | Dup1 | RPD | BH35 | Dup2 | RPD | BH36 | Dup3 | RPD | BH37 | Dup4 | RPD | BH43_5.0 | Dup 5 | RPD | BH46_2.0 | Dup 6 | RPD | BH34 | Split 1 | RPD | BH35 | Split 2 | RPD | BH36 | Split 3 | RPD | BH37 | Split 4 | RPD | BH43_5.0 | Split 5 | RPD | BH46_2.0 | Spilt 6 | RPD |
| | | | | Sampled Date | 6/07/2017 | 6/07/2017 | | 6/07/2017 | 6/07/2017 | | 6/07/2017 | 6/07/2017 | | 6/07/2017 | 6/07/2017 | | 10/05/2018 | 10/05/2018 | | 11/05/2018 | 11/05/2018 | | 6/07/2017 | 6/07/2017 | | 6/07/2017 | 6/07/2017 | | 6/07/2017 | 6/07/2017 | | 6/07/2017 | 6/07/2017 | | 10/05/2018 | 10/05/2018 | | 11/05/2018 | 11/05/2018 | |
| BTEX | Benzene | mg/kg | 0.2 | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | <0.2 | - | - |
| | Ethylbenzene | mg/kg | 1 (Primary): 0.5 (Interlab) | <1.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | <1.0 | <1.0 | 0 | <1.0 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | <1.0 | - | - |
| | Toluene | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - |
| | Xylene (m & p) | mg/kg | 2 (Primary): 1 (Interlab) | <2.0 | <2.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | <2.0 | <2.0 | 0 | <2.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | <2.0 | - | - |
| | Xylene (o) | mg/kg | 1 (Primary): 0.5 (Interlab) | <1.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | <1.0 | <1.0 | 0 | <1.0 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | <1.0 | - | - |
| | Xylene Total | mg/kg | 1 | <1.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | <1.0 | - | - |
| | C6-C10 less BTEX (F1) | mg/kg | 25 | <25.0 | <25.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | <25.0 | <25.0 | 0 | <25.0 | <25.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | <25.0 | - | - |
| Speciated Phenols | 2,3,4,6-tetrachlorophenol | mg/kg | 0.2 | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4,5-trichlorophenol | mg/kg | 0.2 | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4,6-trichlorophenol | mg/kg | 0.2 | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4-dichlorophenol | mg/kg | 0.2 | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,6-dichlorophenol | mg/kg | 0.2 | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2-chlorophenol | mg/kg | 0.2 | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Pentachlorophenol | mg/kg | 1 | <1.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <1.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 3/4-Methylphenol (m/p-cresol) | mg/kg | 0.4 | <0.4 | <0.4 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.4 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4-dimethylphenol | mg/kg | 0.2 | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4-dinitrophenol | mg/kg | 4 (Primary): 2 (Interlab) | <4.0 | <4.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <4.0 | <2.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2-methylphenol | mg/kg | 0.2 | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2-nitrophenol | mg/kg | 0.2 | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 4,6-Dinitro-2-methylphenol | mg/kg | 2 | <2.0 | <2.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <2.0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 4-chloro-3-methylphenol | mg/kg | 1 (Primary): 2 (Interlab) | <1.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <1.0 | <2.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 4-nitrophenol | mg/kg | 4 | <4.0 | <4.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <4.0 | <4.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Phenol | mg/kg | 0.2 | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.2 | <0.2 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Herbicides | 2,4,5-Trichlorophenoxy Acetic Acid | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4,5-TP (Silvex) | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4-dichlorophenoxybutanoic acid | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Hedonal | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4-Dichlorprop | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,4,6-Trichlorophenoxy-acetic acid | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2-Chlorophenoxyacetic acid | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 4-Chlorophenoxy acetic acid | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Acifluorfen | mg/kg | 2 | <2.0 | <2.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <2.0 | <2.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Bromoxynil | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Clopyralid | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Dicamba | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Dinoseb | mg/kg | 1 | <1.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <1.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2-Methyl-4-chlorophenoxyacetic acid | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2-Methyl-4-Chlorophenoxy Butanoic Acid | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Mecoprop | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Triclopyr | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | DCPA (Chlorthal) Diacid | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 2,6-D | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Metribuzin | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Irgarol | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Ametryn | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Atrazine | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Cyanazine | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Hexazinone | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Prometryn | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Propazine | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Simazine | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Terbutryn | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | 3,5-Dichlorobenzoic acid | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Actril (loxynil) | mg/kg | 1 | <1.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <1.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Picloram | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Cyanide | Cyanide (Free) | mg/kg | 0.5 | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <0.5 | <0.5 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Heavy Metals | Arsenic | mg/kg | 4 | <4.0 | <4.0 | 0 | 6.0 | 5.0 | 18 | 7.0 | 14.0 | 67 | <4.0 | <4.0 | 0 | <4.0 | <4.0 | 0 | <4.0 | <4.0 | 0 | <4.0 | 4.0 | 0 | 6.0 | 4.0 | 40 | 7.0 | 8.0 | 13 | <4.0 | <4.0 | 0 | <4.0 | <4.0 | 0 | <4.0 | <4.0 | 0 |
| | Beryllium | mg/kg | 1 | <1.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <1.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Boron | mg/kg | 3 | <3.0 | <3.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <3.0 | <3.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Cadmium | mg/kg | 0.4 | <0.4 | <0.4 | 0 | 10.0 | 6.0 | 50 | 0.5 | 0.6 | 18 | <0.4 | <0.4 | 0 | <0.4 | <0.4 | 0 | <0.4 | <0.4 | 0 | <0.4 | <0.4 | 0 | 10.0 | 8.2 | 20 | 0.5 | <0.4 | 22 | <0.4 | <0.4 | 0 | <0.4 | <0.4 | 0 | <0.4 | <0.4 | 0 |
| | Chromium (III+VI) | mg/kg | 1 | 4.0 | 4.0 | 0 | 22.0 | 18.0 | 20 | 12.0 | 13.0 | 8 | 8.0 | 8.0 | 0 | 5.0 | 6.0 | 18 | 9.0 | 10.0 | 11 | 4.0 | 5.0 | 22 | 22.0 | 18.0 | 20 | 12.0 | 14.0 | 15 | 8.0 | 7.0 | 13 | 5.0 | 6.0 | 18 | 9.0 | 9.0 | 0 |
| | Chromium (hexavalent) | mg/kg | 1 | <1.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <1.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Cobalt | mg/kg | 1 | <1.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | <1.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Copper | mg/kg | 1 | 2.0 | 2.0 | 0 | 270.0 | 230.0 | 16 | 37.0 | 47.0 | 24 | 8.0 | 8.0 | 0 | 4.0 | 5.0 | 22 | <1.0 | <1.0 | 0 | **2.0** | **7.0** | **111** | 270.0 | 240.0 | 12 | 37.0 | 30.0 | 21 | 8.0 | 7.0 | 13 | 4.0 | 5.0 | 22 | <1.0 | <1.0 | 0 |
| | Lead | mg/kg | 1 | 9.0 | 7.0 | 25 | 1300.0 | 1100.0 | 17 | 79.0 | 91.0 | 14 | 49.0 | 53.0 | 8 | 5.0 | 5.0 | 0 | 6.0 | 6.0 | 0 | **9.0** | **25.0** | **94** | 1300.0 | 1200.0 | 8 | 79.0 | 60.0 | 27 | 49.0 | 49.0 | 0 | 5.0 | 4.0 | 22 | 6.0 | 6.0 | 0 |
| | Manganese | mg/kg | 1 | 2.0 | 2.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | **2.0** | **7.0** | **111** | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| | Mercury | mg/kg | 0.1 | <0.1 | <0.1 | 0 | 0.3 | 0.2 | 40 | 0.1 | 0.1 | 0 | 0.1 | 0.1 | 0 | <0.1 | <0.1 | 0 | <0.1 | <0.1 | 0 | <0.1 | <0.1 | 0 | 0.3 | 0.2 | 40 | 0.1 | <0.1 | 0 | 0.1 | 0.1 | 0 | <0.1 | <0.1 | 0 | <0.1 | <0.1 | 0 |
| | Molybdenum | mg/kg | 1 | - | - | - | - | - | - | - | - | - | - | - | - | <1.0 | <1.0 | 0 | 1.0 | 1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | <1.0 | <1.0 | 0 | 1.0 | 2.0 | 67 |
| | Nickel | mg/kg | 1 | <1.0 | <1.0 | 0 | 16.0 | 11.0 | 37 | 3.0 | 9.0 | 100 | 2.0 | 2.0 | 0 | 2.0 | 2.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | 16.0 | 13.0 | 21 | 3.0 | 3.0 | 0 | 2.0 | 2.0 | 0 | 2.0 | 2.0 | 0 | <1.0 | <1.0 | 0 |
| | Silver | mg/kg | 1 | - | - | - | - | - | - | - | - | - | - | - | - | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 |
| | Selenium | mg/kg | 2 | <2.0 | <2.0 | 0 | - | - | - | - | - | - | - | - | - | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | - | - | - | - | - | - | - | - | - | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 |
| | Tin | mg/kg | 1 | - | - | - | - | - | - | - | - | - | - | - | - | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | - | - | - | - | - | - | - | - | - | - | - | - | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 |
| | Zinc | mg/kg | 1 | 11.0 | 10.0 | 10 | 730.0 | 650.0 | 12 | 230.0 | 230.0 | 0 | 90.0 | 82.0 | 9 | - | - | - | - | - | - | **11.0** | **32.0** | **98** | 730.0 | 730.0 | 0 | 230.0 | 170.0 | 30 | 90.0 | 71.0 | 24 | - | - | - | - | - | - |

# Table 22: Soil RPDs

**Australian Unity Ltd**
**266 Longueville Road**
**Lane Cove**

| | | |

# Table 23: Groundwater RPDs

**Australian Unity Ltd**
**266 Longueville Road**
**Lane Cove**

| | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Lab Report #** | | | | 191604 | 191604 | | 191604 | 191604 | | 197675 | 197675 | | 197675 | 14401 | | 191604 | ES1814906 | |
| **Field ID** | | | | GW01 | Dup 1 | **RPD** | GW01 | Split 1 | **RPD** | GW01 | DUP/03/08/18 | **RPD** | GW01 | SPLIT/03/08/18 | **RPD** | GW01 | Split 1 | **RPD** |
| **Sampled Date** | | | | 14/05/2018 | 14/05/2018 | | 14/05/2018 | 14/05/2018 | | 3/08/2018 | 3/08/2018 | | 3/08/2018 | 3/08/2018 | | 14/05/2018 | 14/05/2018 | |
| **Method Type** | **Chemical Name** | **Units** | **EQL** | | | | | | | | | | | | | | | |
| PFAS | Total Positive PFAS | µg/L | 0.01 | - | - | - | - | - | - | 0.02 | 0.03 | 40 | 0.02 | - | - | - | - | - |
| | Total Positive PFHxS & PFOS | µg/L | 0.01 | - | - | - | - | - | - | 0.02 | 0.03 | 40 | 0.02 | - | - | - | - | - |
| | Total Positive PFOA & PFOS | µg/L | 0.01 | - | - | - | - | - | - | <0.01 | <0.01 | 0 | <0.01 | - | - | - | - | - |
| | 8:2 FTS | µg/L | 0.01 | - | - | - | - | - | - | <0.01 | <0.01 | 0 | <0.01 | - | - | - | - | - |
| | Extracted ISTD 13C2 6:2FTS | % | | - | - | - | - | - | - | 87.0 | 86.0 | 1 | 87.0 | - | - | - | - | - |
| | Extracted ISTD 13C2 8:2FTS | % | | - | - | - | - | - | - | 68.0 | 61.0 | 11 | 68.0 | - | - | - | - | - |
| | Extracted ISTD 13C4 PFOA | % | | - | - | - | - | - | - | 110.0 | 105.0 | 5 | 110.0 | - | - | - | - | - |
| | Extracted ISTD 13C4 PFOS | % | | - | - | - | - | - | - | 82.0 | 82.0 | 0 | 82.0 | - | - | - | - | - |
| | Extracted ISTD 18O2 PFHxS | % | | - | - | - | - | - | - | 86.0 | 72.0 | 18 | 86.0 | - | - | - | - | - |
| | Perfluorohexanesulfonic acid - PFHxS | µg/L | 0.01 | - | - | - | - | - | - | 0.02 | 0.03 | 40 | 0.02 | - | - | - | - | - |
| | Perfluorooctanesulfonic acid PFOS | µg/L | 0.01 | - | - | - | - | - | - | <0.01 | <0.01 | 0 | <0.01 | - | - | - | - | - |
| | Perfluorooctanoate | mg/l | 0.00001 | - | - | - | - | - | - | <0.0 | <0.0 | 0 | <0.0 | - | - | - | - | - |
| | 6:2 Fluorotelomer Sulfonate (6:2 FtS) | mg/l | 0.00001 | - | - | - | - | - | - | <0.0 | <0.0 | 0 | <0.0 | - | - | - | - | - |
| | | | | | | | | | | | | | | | | | | |
| vTRH & BTEXN | Benzene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Ethylbenzene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Toluene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Xylene (m & p) | µg/L | 2 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | - | - |
| | Xylene (o) | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | C6-C10 less BTEX (F1) | mg/l | 0.01 | <0.01 | <0.01 | 0 | <0.01 | <0.01 | 0 | <0.01 | <0.01 | 0 | <0.01 | <0.01 | 0 | <0.01 | - | - |
| | | | | | | | | | | | | | | | | | | |
| VOCs | 1,1,1,2-tetrachloroethane | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 1,1,1-trichloroethane | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 1,1,2,2-tetrachloroethane | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 1,1,2-trichloroethane | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 1,1-dichloroethane | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 1,1-dichloroethene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 1,1-dichloropropene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 1,2,3-trichloropropane | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 1,2-dibromo-3-chloropropane | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 1,2-dichloroethane | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 1,2-dichloropropane | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 1,3-dichloropropane | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 2,2-dichloropropane | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Bromochloromethane | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Bromodichloromethane | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Bromoform | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Carbon tetrachloride | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Chlorodibromomethane | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Chloroethane | µg/L | 10 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | - | - |
| | Chloroform | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Chloromethane | µg/L | 10 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | - | - |
| | cis-1,2-dichloroethene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | cis-1,3-dichloropropene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Dibromomethane | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Hexachlorobutadiene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Trichloroethene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Tetrachloroethene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | trans-1,2-dichloroethene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | trans-1,3-dichloropropene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Vinyl chloride | µg/L | 10 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | - | - |
| | 1,2,3-trichlorobenzene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 1,2,4-trichlorobenzene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 1,2-dichlorobenzene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 1,3-dichlorobenzene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 1,4-dichlorobenzene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 2-chlorotoluene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 4-chlorotoluene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Bromobenzene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Chlorobenzene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 1,2-dibromoethane | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Bromomethane | µg/L | 10 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | - | - |
| | Dichlorodifluoromethane | µg/L | 10 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | - | - |
| | Trichlorofluoromethane | µg/L | 10 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | - | - |
| | 1,2,4-trimethylbenzene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | 1,3,5-trimethylbenzene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Isopropylbenzene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | n-butylbenzene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | n-propylbenzene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | p-isopropyltoluene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | sec-butylbenzene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Styrene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | tert-butylbenzene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Benzene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Ethylbenzene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Toluene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Xylene (m & p) | µg/L | 2 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | - | - |
| | Xylene (o) | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Cyclohexane | mg/l | 0.001 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | - | - |
| | | | | | | | | | | | | | | | | | | |
| Miscellaneous Inorganics | Alkalinity (Bicarbonate as CaCO3) | mg/l | 5 | 8.0 | 7.0 | 13 | 8.0 | 7.0 | 13 | <5.0 | <5.0 | 0 | <5.0 | <5.0 | 0 | 8.0 | - | - |
| | Alkalinity (Hydroxide) as CaCO3 | µg/l | 5000 | <5000.0 | <5000.0 | 0 | <5000.0 | <5000.0 | 0 | <5000.0 | <5000.0 | 0 | <5000.0 | - | - | <5000.0 | - | - |
| | Alkalinity (total) as CaCO3 | mg/l | 5 | 8.0 | 7.0 | 13 | 8.0 | 7.0 | 13 | <5.0 | <5.0 | 0 | <5.0 | - | - | 8.0 | - | - |
| | Chloride | mg/l | 1 | 93.0 | 89.0 | 4 | 93.0 | 88.0 | 6 | 110.0 | 110.0 | 0 | 110.0 | 110.0 | 0 | 93.0 | - | - |
| | Sodium (Filtered) | mg/l | 0.5 | 140.0 | 130.0 | 7 | 140.0 | 130.0 | 7 | 140.0 | 140.0 | 0 | 140.0 | - | - | 140.0 | - | - |
| | Sulphate | mg/l | 1 | 110.0 | 110.0 | 0 | 110.0 | 100.0 | 10 | 120.0 | 120.0 | 0 | 120.0 | - | - | 110.0 | - | - |
| | Cyanide Total | mg/l | 0.004 | <0.004 | <0.004 | 0 | <0.004 | <0.004 | 0 | <0.004 | <0.004 | 0 | <0.004 | - | - | <0.004 | - | - |
| | Fluoride | mg/l | 0.1 | <0.1 | <0.1 | 0 | <0.1 | <0.1 | 0 | <0.1 | <0.1 | 0 | <0.1 | <0.1 | 0 | <0.1 | - | - |
| | pH (Lab) | pH_Units | | 5.0 | 4.9 | 2 | 5.0 | 4.9 | 2 | 4.4 | 4.4 | 0 | 4.4 | 4.2 | 5 | 5.0 | - | - |
| | TDS | mg/l | 5 | 440.0 | 420.0 | 5 | 440.0 | 430.0 | 2 | 440.0 | 430.0 | 2 | 440.0 | 370.0 | 17 | 440.0 | - | - |
| | Ammonia | mg/l | 0.005 | | | | | | | <0.005 | <0.005 | 0 | <0.005 | - | - | - | - | - |
| | Calcium (Filtered) | mg/l | 0.5 | 4.8 | 4.8 | 0 | 4.8 | 4.8 | 0 | 0.9 | 0.9 | 0 | 0.9 | - | - | 4.8 | - | - |
| | Magnesium (Filtered) | mg/l | 0.5 | 5.2 | 4.9 | 6 | 5.2 | 4.7 | 10 | 4.8 | 4.5 | 6 | 4.8 | - | - | 5.2 | - | - |
| | Potassium (Filtered) | mg/l | 0.5 | 2.1 | 2.0 | 5 | 2.1 | 2.0 | 5 | 1.1 | 1.1 | 0 | 1.1 | - | - | 2.1 | - | - |
| | Chromium (hexavalent) (Filtered) | mg/l | 0.005 | <0.005 | <0.005 | 0 | <0.005 | <0.005 | 0 | <0.005 | <0.005 | 0 | <0.005 | - | - | <0.005 | - | - |
| | Alkalinity (Carbonate) | mg/l | 5 | <5.0 | <5.0 | 0 | <5.0 | <5.0 | 0 | <5.0 | <5.0 | 0 | <5.0 | - | - | <5.0 | - | - |

# Table 23: Groundwater RPDs

**Australian Unity Ltd**
**266 Longueville Road**
**Lane Cove**

| | | | | **Lab Report #** | 191604 | 191604 | | 191604 | 191604 | | 197675 | 197675 | | 197675 | 14401 | | 191604 | ES1814906 | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | **Field ID** | GW01 | Dup 1 | **RPD** | GW01 | Split 1 | **RPD** | GW01 | DUP/03/08/18 | **RPD** | GW01 | SPLIT/03/08/18 | **RPD** | GW01 | Split 1 | **RPD** |
| | | | | **Sampled Date** | 14/05/2018 | 14/05/2018 | | 14/05/2018 | 14/05/2018 | | 3/08/2018 | 3/08/2018 | | 3/08/2018 | 3/08/2018 | | 14/05/2018 | 14/05/2018 | |
| Heavy Metals | Aluminium (Filtered) | mg/l | 0.01 | 0.19 | 0.2 | 5 | 0.19 | 0.18 | 5 | 0.5 | 0.41 | 20 | 0.5 | 0.64 | 25 | 0.19 | - | - |
| | Antimony (Filtered) | mg/l | 0.001 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | - | - |
| | Arsenic (Filtered) | mg/l | 0.001 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | - | - |
| | Barium (Filtered) | mg/l | 0.001 | 0.036 | 0.033 | 9 | 0.036 | 0.032 | 12 | 0.021 | 0.022 | 5 | 0.021 | 0.025 | 17 | 0.036 | - | - |
| | Beryllium (Filtered) | mg/l | 0.0005 | 0.0005 | <0.0005 | 0 | 0.0005 | <0.0005 | 0 | 0.0008 | 0.0007 | 13 | 0.0008 | 0.0009 | 12 | 0.0005 | - | - |
| | Boron (Filtered) | mg/l | 0.02 | 0.09 | 0.09 | 0 | 0.09 | 0.09 | 0 | 0.06 | 0.06 | 0 | 0.06 | 0.08 | 29 | 0.09 | - | - |
| | Cadmium (Filtered) | mg/l | 0.0001 | <0.0001 | <0.0001 | 0 | <0.0001 | <0.0001 | 0 | <0.0001 | <0.0001 | 0 | <0.0001 | <0.0001 | 0 | <0.0001 | - | - |
| | Chromium (III+VI) (Filtered) | mg/l | 0.001 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | 0.001 | <0.001 | 0 | 0.001 | 0.001 | 0 | <0.001 | - | - |
| | Cobalt (Filtered) | mg/l | 0.001 | 0.011 | 0.011 | 0 | 0.011 | 0.011 | 0 | 0.004 | 0.004 | 0 | 0.004 | 0.005 | 22 | 0.011 | - | - |
| | Copper (Filtered) | mg/l | 0.001 | **0.019** | **0.007** | **92** | **0.019** | **0.007** | **92** | **0.006** | **0.032** | **137** | 0.006 | 0.007 | 15 | 0.019 | - | - |
| | Iron (Filtered) | mg/l | 0.01 | 2.3 | 2.3 | 0 | 2.3 | 2.2 | 4 | 2.4 | 2.0 | 18 | 2.4 | 2.9 | 19 | 2.3 | - | - |
| | Lead (Filtered) | mg/l | 0.001 | 0.001 | 0.001 | 0 | 0.001 | 0.001 | 0 | 0.002 | 0.004 | 67 | 0.002 | 0.003 | 40 | 0.001 | - | - |
| | Manganese (Filtered) | mg/l | 0.005 | 0.22 | 0.22 | 0 | 0.22 | 0.21 | 5 | 0.16 | 0.15 | 6 | 0.16 | 0.19 | 17 | 0.22 | - | - |
| | Mercury (Filtered) | mg/l | 0.00005 | <0.0001 | <0.0001 | 0 | <0.0001 | <0.0001 | 0 | <0.0001 | <0.0001 | 0 | <0.0001 | <0.0001 | 0 | <0.0001 | - | - |
| | Molybdenum (Filtered) | mg/l | 0.001 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | - | - |
| | Nickel (Filtered) | mg/l | 0.001 | 0.012 | 0.01 | 18 | 0.012 | 0.009 | 29 | 0.052 | 0.054 | 4 | 0.052 | 0.061 | 16 | 0.012 | - | - |
| | Selenium (Filtered) | mg/l | 0.001 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | - | - |
| | Silver (Filtered) | mg/l | 0.001 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | - | - |
| | Thallium (Filtered) | mg/l | 0.001 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | - | - |
| | Tin (Filtered) | mg/l | 0.001 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | 0.001 | 0 | <0.001 | - | - |
| | Vanadium (Filtered) | mg/l | 0.001 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | <0.001 | 0 | <0.001 | - | - |
| | Zinc (Filtered) | mg/l | 0.001 | 0.068 | 0.062 | 9 | 0.068 | 0.061 | 11 | 0.22 | 0.2 | 10 | 0.22 | 0.26 | 17 | 0.068 | - | - |
| | | | | | | | | | | | | | | | | | | | |
| OCP | 4,4-DDE | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | a-BHC | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | Aldrin | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | b-BHC | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | Chlordane (cis) | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | Chlordane (trans) | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | d-BHC | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | DDD | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | DDT | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | Dieldrin | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | Endosulfan I | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | Endosulfan II | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | Endosulfan sulphate | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | Endrin | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | Endrin aldehyde | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | g-BHC (Lindane) | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | Heptachlor | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | Heptachlor epoxide | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | Methoxychlor | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | Hexachlorobenzene | µg/L | 0.2 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | <0.2 | 0 | <0.2 | - | - |
| | | | | | | | | | | | | | | | | | | | |
| PAHs | Acenaphthene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Acenaphthylene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Anthracene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Benz(a)anthracene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Benzo(a) pyrene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Benzo(g,h,i)perylene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Chrysene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Dibenz(a,h)anthracene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Fluoranthene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Fluorene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Indeno(1,2,3-c,d)pyrene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Naphthalene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Naphthalene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Phenanthrene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | Pyrene | µg/L | 1 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | <1.0 | 0 | <1.0 | - | - |
| | | | | | | | | | | | | | | | | | | | |
| Phenols | Phenolics Total | µg/l | 50 | <50.0 | <50.0 | 0 | <50.0 | <50.0 | 0 | <50.0 | <50.0 | 0 | <50.0 | - | - | <50.0 | - | - |
| | | | | | | | | | | | | | | | | | | | |
| Phthalates | Bis(2-ethylhexyl) phthalate | µg/L | 50 | <50.0 | <50.0 | 0 | <50.0 | <50.0 | 0 | <50.0 | <50.0 | 0 | <50.0 | <50.0 | 0 | <50.0 | - | - |
| | Butyl benzyl phthalate | µg/L | 10 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | - | - |
| | Diethylphthalate | µg/L | 10 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | - | - |
| | Dimethyl phthalate | µg/L | 10 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | - | - |
| | Di-n-butyl phthalate | µg/L | 50 | <50.0 | <50.0 | 0 | <50.0 | <50.0 | 0 | <50.0 | <50.0 | 0 | <50.0 | <50.0 | 0 | <50.0 | - | - |
| | Di-n-octyl phthalate | µg/L | 10 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | - | - |
| | | | | | | | | | | | | | | | | | | | |
| PCBs | Arochlor 1016 | µg/L | 2 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | - | - |
| | Arochlor 1221 | µg/L | 2 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | - | - |
| | Arochlor 1232 | µg/L | 2 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | - | - |
| | Arochlor 1242 | µg/L | 2 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | - | - |
| | Arochlor 1248 | µg/L | 2 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | - | - |
| | Arochlor 1254 | µg/L | 2 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | - | - |
| | Arochlor 1260 | µg/L | 2 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | <2.0 | 0 | <2.0 | - | - |
| | | | | | | | | | | | | | | | | | | | |
| TRHs | C6 - C9 | µg/L | 10 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | <10.0 | 0 | <10.0 | - | - |
| | C6-C10 | mg/l | 0.01 | <0.01 | <0.01 | 0 | <0.01 | <0.01 | 0 | <0.01 | <0.01 | 0 | <0.01 | <0.01 | 0 | <0.01 | - | - |
| | C10-C16 | mg/l | 0.05 | <0.05 | <0.05 | 0 | <0.05 | <0.05 | 0 | <0.05 | <0.05 | 0 | <0.05 | <0.05 | 0 | <0.05 | - | - |
| | C16-C34 | mg/l | 0.1 | <0.1 | <0.1 | 0 | <0.1 | <0.1 | 0 | <0.1 | <0.1 | 0 | <0.1 | <0.1 | 0 | <0.1 | - | - |
| | C34-C40 | mg/l | 0.1 | <0.1 | <0.1 | 0 | <0.1 | <0.1 | 0 | <0.1 | <0.1 | 0 | <0.1 | <0.1 | 0 | <0.1 | - | - |
| | F2-NAPHTHALENE | mg/l | 0.05 | <0.05 | <0.05 | 0 | <0.05 | <0.05 | 0 | <0.05 | <0.05 | 0 | <0.05 | <0.05 | 0 | <0.05 | - | - |
| | C10 - C14 | µg/L | 50 | <50.0 | <50.0 | 0 | <50.0 | <50.0 | 0 | <50.0 | <50.0 | 0 | <50.0 | <50.0 | 0 | <50.0 | - | - |
| | C15 - C28 | µg/L | 100 | <100.0 | <100.0 | 0 | <100.0 | <100.0 | 0 | <100.0 | <100.0 | 0 | <100.0 | <100.0 | 0 | <100.0 | - | - |
| | C29-C36 | µg/L | 100 | <100.0 | <100.0 | 0 | <100.0 | <100.0 | 0 | <100.0 | <100.0 | 0 | <100.0 | <100.0 | 0 | <100.0 | - | - |

*RPDs have only been considered where a concentration is greater than 1 times the EQL.
**High RPDs are in bold (Acceptable RPDs for each EQL multiplier range are: 100 (1-10 x EQL); 50 (10-30 x EQL); 30 ( > 30 x EQL))
***Interlab Duplicates are matched on a per compound basis as methods vary between laboratories. Any methods in the row header relate to those used in the primary laboratory

# Table 24: Soil Field Blanks

**Australian Unity Ltd**
**266 Longueville Road**
**Lane Cove**

| | | | | | | |
|---|---|---|---|---|---|---|
| **Lab Report #** | 170939 | 197675 | 170939 | 191466 | 197675 | |
| **Field ID** | Rinsate | RB/03/08/18 | Trip | Trip 1 | TB/03/08/18 | |
| **Sampled_Date** | 6/07/2017 | 3/08/2018 | 6/07/2017 | 10/05/2018 | 3/08/2018 | |
| **Sample Type** | Rinsate | Rinsate | Trip_B | Trip_B | Trip_B | |

| Method Type | Chemical Name | Units | EQL | | | | | |
|---|---|---|---|---|---|---|---|---|
| Heavy Metals | Aluminium (Filtered) | mg/l | 0.01 | - | <0.01 | - | - | - |
| | Antimony (Filtered) | mg/l | 0.001 | - | <0.001 | - | - | - |
| | Arsenic (Filtered) | mg/l | 0.001 | <0.05 | <0.001 | - | - | - |
| | Barium (Filtered) | mg/l | 0.001 | - | <0.001 | - | - | - |
| | Beryllium (Filtered) | mg/l | 0.0005 | - | <0.0005 | - | - | - |
| | Boron (Filtered) | mg/l | 0.02 | - | <0.02 | - | - | - |
| | Cadmium (Filtered) | mg/l | 0.0001 | <0.01 | <0.0001 | - | - | - |
| | Chromium (III+VI) (Filtered) | mg/l | 0.001 | <0.01 | <0.001 | - | - | - |
| | Cobalt (Filtered) | mg/l | 0.001 | - | <0.001 | - | - | - |
| | Copper (Filtered) | mg/l | 0.001 | <0.01 | <0.001 | - | - | - |
| | Iron (Filtered) | mg/l | 0.01 | - | <0.01 | - | - | - |
| | Lead (Filtered) | mg/l | 0.001 | <0.03 | <0.001 | - | - | - |
| | Manganese (Filtered) | mg/l | 0.005 | - | <0.005 | - | - | - |
| | Mercury (Filtered) | mg/l | 0.00005 | <0.0005 | <0.00005 | - | - | - |
| | Molybdenum (Filtered) | mg/l | 0.001 | - | <0.001 | - | - | - |
| | Nickel (Filtered) | mg/l | 0.001 | <0.02 | <0.001 | - | - | - |
| | Selenium (Filtered) | mg/l | 0.001 | - | <0.001 | - | - | - |
| | Silver (Filtered) | mg/l | 0.001 | - | <0.001 | - | - | - |
| | Tin (Filtered) | mg/l | 0.001 | - | <0.001 | - | - | - |
| | Titanium (Filtered) | mg/l | 0.001 | - | <0.001 | - | - | - |
| | Vanadium (Filtered) | mg/l | 0.001 | - | <0.001 | - | - | - |
| | Zinc (Filtered) | mg/l | 0.001 | <0.02 | <0.001 | - | - | - |
| | | | | | | | | |
| PAHs | Acenaphthene | µg/L | 1 | - | <1 | - | - | - |
| | Acenaphthylene | µg/L | 1 | - | <1 | - | - | - |
| | Anthracene | µg/L | 1 | - | <1 | - | - | - |
| | Benz(a)anthracene | µg/L | 1 | - | <1 | - | - | - |
| | Benzo(a) pyrene | µg/L | 1 | - | <1 | - | - | - |
| | Benzo(g,h,i)perylene | µg/L | 1 | - | <1 | - | - | - |
| | Chrysene | µg/L | 1 | - | <1 | - | - | - |
| | Dibenz(a,h)anthracene | µg/L | 1 | - | <1 | - | - | - |
| | Fluoranthene | µg/L | 1 | - | <1 | - | - | - |
| | Fluorene | µg/L | 1 | - | <1 | - | - | - |
| | Indeno(1,2,3-c,d)pyrene | µg/L | 1 | - | <1 | - | - | - |
| | Naphthalene | µg/L | 1 | - | <1 | - | - | - |
| | Phenanthrene | µg/L | 1 | - | <1 | - | - | - |
| | Pyrene | µg/L | 1 | - | <1 | - | - | - |
| | | | | | | | | |
| TRH | C6 - C9 | µg/L | 10 | - | <10 | <10 | <10 | <10 |
| | C6-C10 | mg/l | 0.01 | - | <0.01 | <0.01 | <0.01 | <0.01 |
| | C10-C16 | mg/l | 0.05 | - | <0.05 | - | <0.05 | - |
| | C16-C34 | mg/l | 0.1 | - | <0.1 | - | <0.1 | - |
| | C34-C40 | mg/l | 0.1 | - | <0.1 | - | <0.1 | - |
| | C10 - C14 | µg/L | 50 | - | <50 | - | <50 | - |
| | C15 - C28 | µg/L | 100 | - | <100 | - | <100 | - |
| | C29-C36 | µg/L | 100 | - | <100 | - | <100 | - |

# Table 25: Groundwater Field Blanks

**Australian Unity Ltd**
**266 Longueville Road**
**Lane Cove**

| | | | |
|---|---|---|---|
| **Lab Report #** | 197675 | 191466 | 197675 |
| **Field ID** | RB/03/08/18 | Trip 1 | TB/03/08/18 |
| **Sampled_Date** | 3/08/2018 | 10/05/2018 | 3/08/2018 |
| **Sample Type** | Rinsate | Trip_B | Trip_B |

| Method Type | Chemical Name | Units | EQL | | | |
|---|---|---|---|---|---|---|
| Heavy Metals | Aluminium (Filtered) | mg/l | 0.01 | <0.01 | - | - |
| | Antimony (Filtered) | mg/l | 0.001 | <0.001 | - | - |
| | Arsenic (Filtered) | mg/l | 0.001 | <0.001 | - | - |
| | Barium (Filtered) | mg/l | 0.001 | <0.001 | - | - |
| | Beryllium (Filtered) | mg/l | 0.0005 | <0.0005 | - | - |
| | Boron (Filtered) | mg/l | 0.02 | <0.02 | - | - |
| | Cadmium (Filtered) | mg/l | 0.0001 | <0.0001 | - | - |
| | Chromium (III+VI) (Filtered) | mg/l | 0.001 | <0.001 | - | - |
| | Cobalt (Filtered) | mg/l | 0.001 | <0.001 | - | - |
| | Copper (Filtered) | mg/l | 0.001 | <0.001 | - | - |
| | Iron (Filtered) | mg/l | 0.01 | <0.01 | - | - |
| | Lead (Filtered) | mg/l | 0.001 | <0.001 | - | - |
| | Manganese (Filtered) | mg/l | 0.005 | <0.005 | - | - |
| | Mercury (Filtered) | mg/l | 0.00005 | <0.00005 | - | - |
| | Molybdenum (Filtered) | mg/l | 0.001 | <0.001 | - | - |
| | Nickel (Filtered) | mg/l | 0.001 | <0.001 | - | - |
| | Selenium (Filtered) | mg/l | 0.001 | <0.001 | - | - |
| | Silver (Filtered) | mg/l | 0.001 | <0.001 | - | - |
| | Tin (Filtered) | mg/l | 0.001 | <0.001 | - | - |
| | Titanium (Filtered) | mg/l | 0.001 | <0.001 | - | - |
| | Vanadium (Filtered) | mg/l | 0.001 | <0.001 | - | - |
| | Zinc (Filtered) | mg/l | 0.001 | <0.001 | - | - |
| | | | | | | |
| PAHs | Acenaphthene | µg/L | 1 | <1 | - | - |
| | Acenaphthylene | µg/L | 1 | <1 | - | - |
| | Anthracene | µg/L | 1 | <1 | - | - |
| | Benz(a)anthracene | µg/L | 1 | <1 | - | - |
| | Benzo(a) pyrene | µg/L | 1 | <1 | - | - |
| | Benzo(g,h,i)perylene | µg/L | 1 | <1 | - | - |
| | Chrysene | µg/L | 1 | <1 | - | - |
| | Dibenz(a,h)anthracene | µg/L | 1 | <1 | - | - |
| | Fluoranthene | µg/L | 1 | <1 | - | - |
| | Fluorene | µg/L | 1 | <1 | - | - |
| | Indeno(1,2,3-c,d)pyrene | µg/L | 1 | <1 | - | - |
| | Naphthalene | µg/L | 1 | <1 | - | - |
| | Phenanthrene | µg/L | 1 | <1 | - | - |
| | Pyrene | µg/L | 1 | <1 | - | - |
| | | | | | | |
| TRHs | C6 - C9 | µg/L | 10 | <10 | <10 | <10 |
| | C6-C10 | mg/l | 0.01 | <0.01 | <0.01 | <0.01 |
| | C10-C16 | mg/l | 0.05 | <0.05 | <0.05 | - |
| | C16-C34 | mg/l | 0.1 | <0.1 | <0.1 | - |
| | C34-C40 | mg/l | 0.1 | <0.1 | <0.1 | - |
| | C10 - C14 | µg/L | 50 | <50 | <50 | - |
| | C15 - C28 | µg/L | 100 | <100 | <100 | - |
| | C29-C36 | µg/L | 100 | <100 | <100 | - |

# APPENDIX E

## LABORATORY RESULTS, SRAs AND COC'S

P.O. Box 1237
Carlton VIC 3053
enquiries@lrmglobal.com.au

# CHAIN OF CUSTODY

**Job Number:** 27380

**ATTENTION**

**CLIENT**

**CLIENT NUMBER**

**LOCATION** Longueville Road Lane Cove

Sheet 1 of 1

| Sample Number | Sample Date | Sample Type | Analysis Required | No. of Containers | Turn-around Time Required |
|---|---|---|---|---|---|
| 1 Split 1 | 6/07/2017 | Soil | NEPM Suite | 1 | 5 day |
| 2 Split 2 | 6/07/2017 | Soil | Metals | 1 | 5 day |
| 3 Split 3 | 6/07/2017 | Soil | Metals | 1 | 5 day |
| 4 Split 4 | 6/07/2017 | Soil | Metals | 1 | 5 day |

ENVIROLAB
Envirolab Services
12 Ashley Street
Chatswood NSW 2067
Ph: (02) 9910 6200

Job No: 11218
Date Received: 11/7/17
Time Received: 10:35
Received by: MS
Temp: Cool/Ambient 16.5°C
Cooling: Ice/Icepack
Security: Intact/Broken/None

**Total number of containers** 4

**Additional information::**

**Email Results To**

| | Tick |
|---|---|
| jon.lawson@lrmglobal.com.au | Yep |
| kevin.b@lrmglobal.com.au | |
| ajacob@lrmglobal.com.au | |
| acampbell@lrmglobal.com.au | |
| b.paule@lrmglobal.com.au | |

Sampled by: JL

Checked by: JL

**Additional Comments**

170939

Chain of custody must be signed and dated by LRM, courier, and laboratory.

| RELINQUISHED BY (Signature) | ORGANISATION | DATE / TIME | RECEIVED BY (Signature) | ORGANISATION | DATE / TIME |
|---|---|---|---|---|---|
| | LRM | 7/07/2017 | M. Sayed | ENS | 11/7/17 10:35 |
| RELINQUISHED BY (Signature) | ORGANISATION | DATE / TIME | RECEIVED BY (Signature) | RECEIVED FOR LABORATORY BY (Signature) | |
| | ENS | 10/7/17 | | | |

1 Dalmore Drive, Scoresby, Victoria 3179
tel: +61 3 9763 2500

email: melbourne@envirolab.com.au
envirolab.com.au

Envirolab Services Pty Ltd - Melbourne | ABN 37 112 535 645 - 002

# CERTIFICATE OF ANALYSIS 11218

**Client:**
**LRM Global**
65 Stubbs Street
Kensington
VIC 3031

**Attention:** Jon Lawson

**Sample log in details:**

| | |
|---|---|
| Your Reference: | **27380 - Longueville Road Lane Cove** |
| No. of samples: | 4 Soils |
| Date samples received / completed instructions received | 11/07/2017 / 11/07/2017 |

**Analysis Details:**
Please refer to the following pages for results, methodology summary and quality control data.
Samples were analysed as received from the client. Results relate specifically to the samples as received.
Results are reported on a dry weight basis for solids and on an as received basis for other matrices.
***Please refer to the last page of this report for any comments relating to the results.***

**Report Details:**

| | |
|---|---|
| Date results requested by: / Issue Date: | 18/07/17 / 18/07/17 |
| Date of Preliminary Report: | Not Issued |

NATA accreditation number 2901. This document shall not be reproduced except in full.
Accredited for compliance with ISO/IEC 17025 - Testing **Tests not covered by NATA are denoted with *.**

**Results Approved By:**

Pamela Adams
Laboratory Manager



ACCREDITED FOR TECHNICAL COMPETENCE

| VOCs in soil<br>Our Reference:<br>Your Reference<br>Date Sampled<br>Type of sample | UNITS<br>----------<br>---------- | 11218-1<br>Split 1<br>06/07/2017<br>Soil |
|---|---|---|
| Date extracted | - | 12/07/2017 |
| Date analysed | - | 13/07/2017 |
| Dichlorodifluoromethane | mg/kg | <1 |
| Chloromethane | mg/kg | <1 |
| Vinyl Chloride | mg/kg | <1 |
| Bromomethane | mg/kg | <1 |
| Chloroethane | mg/kg | <1 |
| Trichlorofluoromethane | mg/kg | <1 |
| 1,1-Dichloroethene | mg/kg | <0.5 |
| trans-1,2-dichloroethene | mg/kg | <0.5 |
| 1,1-dichloroethane | mg/kg | <0.5 |
| cis-1,2-dichloroethene | mg/kg | <0.5 |
| bromochloromethane | mg/kg | <0.5 |
| chloroform | mg/kg | <0.5 |
| 2,2-dichloropropane | mg/kg | <0.5 |
| 1,2-dichloroethane | mg/kg | <0.5 |
| 1,1,1-trichloroethane | mg/kg | <0.5 |
| 1,1-dichloropropene | mg/kg | <0.5 |
| Cyclohexane | mg/kg | <1 |
| carbon tetrachloride | mg/kg | <0.5 |
| Benzene | mg/kg | <0.2 |
| dibromomethane | mg/kg | <0.5 |
| 1,2-dichloropropane | mg/kg | <0.5 |
| trichloroethene | mg/kg | <0.5 |
| bromodichloromethane | mg/kg | <0.5 |
| trans-1,3-dichloropropene | mg/kg | <0.5 |
| cis-1,3-dichloropropene | mg/kg | <0.5 |
| 1,1,2-trichloroethane | mg/kg | <0.5 |
| Toluene | mg/kg | <0.5 |
| 1,3-dichloropropane | mg/kg | <0.5 |
| dibromochloromethane | mg/kg | <0.5 |
| 1,2-dibromoethane | mg/kg | <0.5 |
| Tetrachloroethene | mg/kg | <0.5 |
| 1,1,1,2-tetrachloroethane | mg/kg | <0.5 |
| chlorobenzene | mg/kg | <0.5 |
| Ethylbenzene | mg/kg | <0.5 |
| bromoform | mg/kg | <0.5 |
| m+p-xylene | mg/kg | <1 |
| styrene | mg/kg | <0.5 |
| 1,1,2,2-tetrachloroethane | mg/kg | <0.5 |



NATA
ACCREDITED FOR
TECHNICAL
COMPETENCE

| VOCs in soil<br>Our Reference:<br>Your Reference<br>Date Sampled<br>Type of sample | UNITS<br>----------<br>----------<br> | 11218-1<br>Split 1<br>06/07/2017<br>Soil |
|---|---|---|
| o-Xylene | mg/kg | <0.5 |
| 1,2,3-trichloropropane | mg/kg | <0.5 |
| isopropylbenzene | mg/kg | <0.5 |
| bromobenzene | mg/kg | <0.5 |
| n-propyl benzene | mg/kg | <0.5 |
| 2-chlorotoluene | mg/kg | <0.5 |
| 4-chlorotoluene | mg/kg | <0.5 |
| 1,3,5-trimethyl benzene | mg/kg | <0.5 |
| tert-butyl benzene | mg/kg | <0.5 |
| 1,2,4-trimethyl benzene | mg/kg | <0.5 |
| 1,3-dichlorobenzene | mg/kg | <0.5 |
| sec-butyl benzene | mg/kg | <0.5 |
| 1,4-dichlorobenzene | mg/kg | <0.5 |
| 4-isopropyl toluene | mg/kg | <0.5 |
| 1,2-dichlorobenzene | mg/kg | <0.5 |
| n-butyl benzene | mg/kg | <0.5 |
| 1,2-dibromo-3-chloropropane | mg/kg | <0.5 |
| 1,2,4-trichlorobenzene | mg/kg | <0.5 |
| hexachlorobutadiene | mg/kg | <0.5 |
| 1,2,3-trichlorobenzene | mg/kg | <0.5 |
| Surrogate Dibromofluoromethane | % | 70 |
| *Surrogate* aaa-Trifluorotoluene | % | 89 |
| *Surrogate* Toluene-$d_8$ | % | 99 |
| *Surrogate* 4-Bromofluorobenzene | % | 96 |



NATA
ACCREDITED FOR
TECHNICAL
COMPETENCE

| vTRH(C6-C10)/BTEXN in Soil | | |
|---|---|---|
| Our Reference: | UNITS | 11218-1 |
| Your Reference | ---------- | Split 1 |
| Date Sampled | ---------- | 06/07/2017 |
| Type of sample | | Soil |
| Date extracted | - | 12/07/2017 |
| Date analysed | - | 13/07/2017 |
| vTRH $C_6$ - $C_9$ | mg/kg | <25 |
| vTRH $C_6$ - $C_{10}$ | mg/kg | <25 |
| TRH $C_6$ - $C_{10}$ less BTEX (F1) | mg/kg | <25 |
| Benzene | mg/kg | <0.2 |
| Toluene | mg/kg | <0.5 |
| Ethylbenzene | mg/kg | <1 |
| m+p-xylene | mg/kg | <2 |
| o-Xylene | mg/kg | <1 |
| Naphthalene | mg/kg | <1 |
| Total +ve Xylenes | mg/kg | <1 |
| *Surrogate* aaa-Trifluorotoluene | % | 89 |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| TRH Soil C10-C40 NEPM | | |
|---|---|---|
| Our Reference: | UNITS | 11218-1 |
| Your Reference | ---------- | Split 1 |
| Date Sampled | ---------- | 06/07/2017 |
| Type of sample | | Soil |
| Date extracted | - | 12/07/2017 |
| Date analysed | - | 13/07/2017 |
| TRHC$_{10}$ - C$_{14}$ | mg/kg | <50 |
| TRHC$_{15}$ - C$_{28}$ | mg/kg | <100 |
| TRHC$_{29}$ - C$_{36}$ | mg/kg | <100 |
| Total +ve TRH (C10-C36) | mg/kg | <50 |
| TRH>C$_{10}$-C$_{16}$ | mg/kg | <50 |
| TRH>C$_{10}$ - C$_{16}$ less Naphthalene (F2) | mg/kg | <50 |
| TRH>C$_{16}$-C$_{34}$ | mg/kg | <100 |
| TRH>C$_{34}$-C$_{40}$ | mg/kg | <100 |
| Total +ve TRH (>C10-C40) | mg/kg | <50 |
| *Surrogate* o-Terphenyl | % | 95 |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| PAHs in Soil | | |
|---|---|---|
| Our Reference: | UNITS | 11218-1 |
| Your Reference | ---------- | Split 1 |
| Date Sampled | ---------- | 06/07/2017 |
| Type of sample | | Soil |
| Date extracted | - | 12/07/2017 |
| Date analysed | - | 15/07/2017 |
| Naphthalene | mg/kg | <0.1 |
| Acenaphthylene | mg/kg | <0.1 |
| Acenaphthene | mg/kg | <0.1 |
| Fluorene | mg/kg | <0.1 |
| Phenanthrene | mg/kg | <0.1 |
| Anthracene | mg/kg | <0.1 |
| Fluoranthene | mg/kg | <0.1 |
| Pyrene | mg/kg | <0.1 |
| Benzo(a)anthracene | mg/kg | <0.1 |
| Chrysene | mg/kg | <0.1 |
| Benzo(b,j&k)fluoranthene | mg/kg | <0.2 |
| Benzo(a)pyrene | mg/kg | 0.08 |
| Indeno(1,2,3-c,d)pyrene | mg/kg | <0.1 |
| Dibenzo(a,h)anthracene | mg/kg | <0.1 |
| Benzo(g,h,i)perylene | mg/kg | <0.1 |
| Total +ve PAH's | mg/kg | 0.08 |
| Benzo(a)pyrene TEQ calc (Zero) | mg/kg | <0.5 |
| Benzo(a)pyrene TEQ calc (Half) | mg/kg | <0.5 |
| Benzo(a)pyrene TEQ calc (PQL) | mg/kg | <0.5 |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | 98 |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| Speciated Phenols in Soil | | |
|---|---|---|
| Our Reference: | UNITS | 11218-1 |
| Your Reference | ---------- | Split 1 |
| Date Sampled | ---------- | 06/07/2017 |
| Type of sample | | Soil |
| Date extracted | - | 12/07/2017 |
| Date analysed | - | 15/07/2017 |
| Phenol | mg/kg | <0.2 |
| 2-Chlorophenol | mg/kg | <0.2 |
| 2-Methylphenol | mg/kg | <0.2 |
| 3/4-Methylphenol | mg/kg | <0.4 |
| 2-Nitrophenol | mg/kg | <0.2 |
| 2,4-Dimethylphenol | mg/kg | <0.2 |
| 2,4-Dichlorophenol | mg/kg | <0.2 |
| 2,6-Dichlorophenol | mg/kg | <0.2 |
| 2,4,5-Trichlorophenol | mg/kg | <0.2 |
| 2,4,6-Trichlorophenol | mg/kg | <0.2 |
| 2,4-Dinitrophenol | mg/kg | <2 |
| 4-Nitrophenol | mg/kg | <4 |
| 2,3,4,6-Tetrachlorophenol | mg/kg | <0.2 |
| Pentachlorophenol | mg/kg | <1 |
| 4-Chloro-3-Methylphenol | mg/kg | <2 |
| Total +ve Cresols | mg/kg | <0.2 |
| Total +ve Phenols | mg/kg | <0.2 |
| *Surrogate* Phenol-$d_6$ | % | 82 |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| OCP in Soil - NEPM | | |
|---|---|---|
| Our Reference: | UNITS | 11218-1 |
| Your Reference | ---------- | Split 1 |
| Date Sampled | ---------- | 06/07/2017 |
| Type of sample | | Soil |
| Date extracted | - | 12/07/2017 |
| Date analysed | - | 15/07/2017 |
| alpha-BHC | mg/kg | <0.1 |
| Hexachlorobenzene | mg/kg | <0.1 |
| beta-BHC | mg/kg | <0.1 |
| gamma-BHC | mg/kg | <0.1 |
| Heptachlor | mg/kg | <0.1 |
| delta-BHC | mg/kg | <0.1 |
| Aldrin | mg/kg | <0.1 |
| Heptachlor Epoxide | mg/kg | <0.1 |
| gamma-Chlordane | mg/kg | <0.1 |
| alpha-chlordane | mg/kg | <0.1 |
| Endosulfan I | mg/kg | <0.1 |
| pp-DDE | mg/kg | <0.1 |
| Dieldrin | mg/kg | <0.1 |
| Endrin | mg/kg | <0.1 |
| Endosulfan II | mg/kg | <0.1 |
| pp-DDD | mg/kg | <0.1 |
| Endrin Aldehyde | mg/kg | <0.1 |
| pp-DDT | mg/kg | <0.1 |
| Endosulfan Sulphate | mg/kg | <0.1 |
| Methoxychlor | mg/kg | <0.1 |
| Total +ve reported Aldrin + Dieldrin | mg/kg | <0.1 |
| Total +ve reported DDT+DDD+DDE | mg/kg | <0.1 |
| Mirex | mg/kg | <0.5 |
| Toxaphene | mg/kg | <2 |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | 98 |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| OP in Soil - NEPM | | |
|---|---|---|
| Our Reference: | UNITS | 11218-1 |
| Your Reference | ---------- | Split 1 |
| Date Sampled | ---------- | 06/07/2017 |
| Type of sample | | Soil |
| Date extracted | - | 12/07/2017 |
| Date analysed | - | 15/07/2017 |
| Chlorpyrifos | mg/kg | <0.1 |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | 98 |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| PCBs in Soil | | |
|---|---|---|
| Our Reference: | UNITS | 11218-1 |
| Your Reference | ---------- | Split 1 |
| Date Sampled | ---------- | 06/07/2017 |
| Type of sample | | Soil |
| Date extracted | - | 12/07/2017 |
| Date analysed | - | 15/07/2017 |
| Aroclor 1016 | mg/kg | <0.1 |
| Aroclor 1221 | mg/kg | <0.1 |
| Aroclor 1232 | mg/kg | <0.1 |
| Aroclor 1242 | mg/kg | <0.1 |
| Aroclor 1248 | mg/kg | <0.1 |
| Aroclor 1254 | mg/kg | <0.1 |
| Aroclor 1260 | mg/kg | <0.1 |
| Total +ve PCBs (1016-1260) | mg/kg | <0.1 |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | 98 |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| Synthetic Pyrethroids - NEPM | | |
|---|---|---|
| Our Reference: | UNITS | 11218-1 |
| Your Reference | ---------- | Split 1 |
| Date Sampled | ---------- | 06/07/2017 |
| Type of sample | | Soil |
| Date extracted | - | 12/07/2017 |
| Date analysed | - | 15/07/2017 |
| Bifenthrin | mg/kg | <0.5 |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| Triazine Herbicides in Soil | | |
|---|---|---|
| Our Reference: | UNITS | 11218-1 |
| Your Reference | ---------- | Split 1 |
| Date Sampled | ---------- | 06/07/2017 |
| Type of sample | | Soil |
| Date extracted | - | 12/07/2017 |
| Date analysed | - | 15/07/2017 |
| Atrazine | mg/kg | <0.5 |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| Phenoxy Acid Herbicides in Soil | | |
|---|---|---|
| Our Reference: | UNITS | 11218-1 |
| Your Reference | ---------- | Split 1 |
| Date Sampled | ---------- | 06/07/2017 |
| Type of sample | | Soil |
| Date Extracted | - | 14/07/2017 |
| Date analysed | - | 14/07/2017 |
| Clopyralid | mg/kg | <0.5 |
| 3,5-Dichlorobenzoic acid | mg/kg | <0.5 |
| o-Chlorophenoxy acetic acid | mg/kg | <0.5 |
| 4-CPA | mg/kg | <0.5 |
| Dicamba | mg/kg | <0.5 |
| Mecoprop | mg/kg | <0.5 |
| MCPA | mg/kg | <0.5 |
| Dichloroprop | mg/kg | <0.5 |
| 2,4-D | mg/kg | <0.5 |
| Bromoxynil | mg/kg | <0.5 |
| Triclopyr | mg/kg | <0.5 |
| 2,4,5-TP (Silvex) | mg/kg | <0.5 |
| 2,4,5-T | mg/kg | <0.5 |
| MCPB | mg/kg | <0.5 |
| 2.4-DB | mg/kg | <0.5 |
| Dinoseb | mg/kg | <1.0 |
| Ioxynil | mg/kg | <1.0 |
| Picloram | mg/kg | <0.5 |
| DCPA (Chlorthal) Diacid | mg/kg | <0.5 |
| Acifluorfen | mg/kg | <2.0 |
| 2,4,6-T | mg/kg | <0.5 |
| 2,6-D | mg/kg | <0.5 |
| Surrogate: 2,4-DCPA | % | 104 |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| NEPM screen metals in soil<br>Our Reference:<br>Your Reference<br>Date Sampled<br>Type of sample | UNITS<br>----------<br>---------- | 11218-1<br>Split 1<br>06/07/2017<br>Soil | 11218-2<br>Split 2<br>06/07/2017<br>Soil | 11218-3<br>Split 3<br>06/07/2017<br>Soil | 11218-4<br>Split 4<br>06/07/2017<br>Soil |
|---|---|---|---|---|---|
| Date digested | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Arsenic | mg/kg | 4 | 4 | 8 | <4 |
| Beryllium | mg/kg | <1 | [NA] | [NA] | [NA] |
| Boron | mg/kg | <3 | [NA] | [NA] | [NA] |
| Cadmium | mg/kg | <0.4 | 8.2 | <0.4 | <0.4 |
| Cobalt | mg/kg | <1 | [NA] | [NA] | [NA] |
| Chromium | mg/kg | 5 | 18 | 14 | 7 |
| Copper | mg/kg | 7 | 240 | 30 | 7 |
| Lead | mg/kg | 25 | 1,200 | 60 | 49 |
| Mercury | mg/kg | <0.1 | 0.2 | <0.1 | 0.1 |
| Manganese | mg/kg | 7 | [NA] | [NA] | [NA] |
| Nickel | mg/kg | <1 | 13 | 3 | 2 |
| Selenium | mg/kg | <2 | [NA] | [NA] | [NA] |
| Zinc | mg/kg | 32 | 730 | 170 | 71 |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| Misc Inorg - soil NEPM | | |
|---|---|---|
| Our Reference: | UNITS | 11218-1 |
| Your Reference | ---------- | Split 1 |
| Date Sampled | ---------- | 06/07/2017 |
| Type of sample | | Soil |
| Date prepared | - | 13/07/2017 |
| Date analysed | - | 14/07/2017 |
| Free Cyanide in soil | mg/kg | <0.5 |
| Hexavalent Chromium, $Cr^{6+}$ | mg/kg | <1 |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| Moisture<br>Our Reference:<br>Your Reference<br>Date Sampled<br>Type of sample | UNITS<br>----------<br>---------- | 11218-1<br>Split 1<br>06/07/2017<br>Soil | 11218-2<br>Split 2<br>06/07/2017<br>Soil | 11218-3<br>Split 3<br>06/07/2017<br>Soil | 11218-4<br>Split 4<br>06/07/2017<br>Soil |
|---|---|---|---|---|---|
| Date prepared | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Moisture | % | 11 | 13 | 22 | 16 |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| Method ID | Methodology Summary |
|---|---|
| Org-014 | Soil samples are extracted with methanol and spiked into water prior to analysing by purge and trap GC-MS. |
| Org-016 | Soil samples are extracted with methanol and spiked into water prior to analysing by purge and trap GC-MS. Water samples are analysed directly by purge and trap GC-MS. F1 = (C6-C10)-BTEX as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater.<br>Note, the Total +ve Xylene PQL is reflective of the lowest individual PQL and is therefore "Total +ve Xylenes" is simply a sum of the positive individual Xylenes. |
| Org-003 | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-FID.<br><br>F2 = (>C10-C16)-Naphthalene as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater (HSLs Tables 1A (3, 4)). Note Naphthalene is determined from the VOC analysis.<br><br>Note, the Total +ve TRH PQL is reflective of the lowest individual PQL and is therefore "Total +ve TRH" is simply a sum of the positive individual TRH fractions (>C10-C40). |
| Org-012 | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS. Benzo(a)pyrene TEQ as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater - 2013.<br><br>For soil results:-<br><br>1. 'TEQ PQL' values are assuming all contributing PAHs reported as <PQL are actually at the PQL. This is the most conservative approach and can give false positive TEQs given that PAHs that contribute to the TEQ calculation may not be present.<br>2. 'TEQ zero' values are assuming all contributing PAHs reported as <PQL are zero. This is the least conservative approach and is more susceptible to false negative TEQs when PAHs that contribute to the TEQ calculation are present but below PQL.<br>3. 'TEQ half PQL' values are assuming all contributing PAHs reported as <PQL are half the stipulated PQL. Hence a mid-point between the most and least conservative approaches above.<br>Note, the Total +ve PAHs PQL is reflective of the lowest individual PQL and is therefore" Total +ve PAHs" is simply a sum of the positive individual PAHs. |
| Org-012 | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS.<br>Note, the Total +ve Cresols or Phenols PQL is reflective of the lowest individual PQL and is therefore" Total +ve Cresols or Phenols" is simply a sum of the positive individual Cresols or Phenols. |
| Org-012 | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS. |
| Org-012 | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS.<br><br>Note, For OCs the Total +ve reported DDD+DDE+DDT PQL is reflective of the lowest individual PQL and is therefore simply a sum of the positive individually report DDD+DDE+DDT. |
| Org-012 | Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC-ECD or GC-MS.<br>Note, the Total +ve PCBs PQL is reflective of the lowest individual PQL and is therefore" Total +ve PCBs" is simply a sum of the positive individual PCBs. |
| Org-012 | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS. |
| ORG-031 | Acid herbicides and speciated phenols in soil by DCM:Acetone extraction with derivatisation and determination by GC-MS. |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| Method ID | Methodology Summary |
|---|---|
| | Haloacetic acids in waters are derivatised and analysed by GC-ECD.<br>Acid herbicides, speciated phenols, carbamates and ureas in water by DCM extraction with derivatisation and determination by GC-MS.<br>Analysed by MPL, NATA accrediation 2901. |
| Metals-020 ICP-AES | Determination of various metals by ICP-AES. |
| Metals-021 CV-AAS | Determination of Mercury by Cold Vapour AAS. |
| Inorg-013 | Cyanide - total determined colourimetrically after distillation, based on APHA latest edition, 4500-CN_C,E. Free cyanide determined colourimetrically after filtration and confirmed by diffusion.<br>Solids are extracted in a caustic media prior to distillation and analysis. |
| Inorg-024 | Hexavalent Chromium (Cr6+) - determined colourimetrically by discrete analyser. |
| Inorg-008 | Moisture content determined by heating at 105 deg C for a minimum of 12 hours. |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| QUALITY CONTROL<br>VOCs in soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br>Base II Duplicate II %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| Date extracted | - | | | 12/07/2017 | 11218-1 | 12/07/2017 \|\| 12/07/2017 | LCS-1 | 12/07/2017 |
| Date analysed | - | | | 12/07/2017 | 11218-1 | 13/07/2017 \|\| 14/07/2017 | LCS-1 | 12/07/2017 |
| Dichlorodifluoromethane | mg/kg | 1 | Org-014 | <1 | 11218-1 | <1 \|\| <1 | [NR] | [NR] |
| Chloromethane | mg/kg | 1 | Org-014 | <1 | 11218-1 | <1 \|\| <1 | [NR] | [NR] |
| Vinyl Chloride | mg/kg | 1 | Org-014 | <1 | 11218-1 | <1 \|\| <1 | [NR] | [NR] |
| Bromomethane | mg/kg | 1 | Org-014 | <1 | 11218-1 | <1 \|\| <1 | [NR] | [NR] |
| Chloroethane | mg/kg | 1 | Org-014 | <1 | 11218-1 | <1 \|\| <1 | [NR] | [NR] |
| Trichlorofluoromethane | mg/kg | 1 | Org-014 | <1 | 11218-1 | <1 \|\| <1 | [NR] | [NR] |
| 1,1-Dichloroethene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| trans-1,2-dichloroethene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| 1,1-dichloroethane | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | LCS-1 | 73% |
| cis-1,2-dichloroethene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| bromochloromethane | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| chloroform | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | LCS-1 | 74% |
| 2,2-dichloropropane | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| 1,2-dichloroethane | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | LCS-1 | 76% |
| 1,1,1-trichloroethane | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | LCS-1 | 76% |
| 1,1-dichloropropene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| Cyclohexane | mg/kg | 1 | Org-014 | <1 | 11218-1 | <1 \|\| <1 | [NR] | [NR] |
| carbon tetrachloride | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| Benzene | mg/kg | 0.2 | Org-014 | <0.2 | 11218-1 | <0.2 \|\| <0.2 | [NR] | [NR] |
| dibromomethane | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| 1,2-dichloropropane | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| trichloroethene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | LCS-1 | 79% |
| bromodichloromethane | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | LCS-1 | 78% |
| trans-1,3-dichloropropene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| cis-1,3-dichloropropene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| 1,1,2-trichloroethane | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| Toluene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| 1,3-dichloropropane | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| dibromochloromethane | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | LCS-1 | 82% |
| 1,2-dibromoethane | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| Tetrachloroethene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | LCS-1 | 78% |
| 1,1,1,2-tetrachloroethane | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| chlorobenzene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| Ethylbenzene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| bromoform | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| m+p-xylene | mg/kg | 1 | Org-014 | <1 | 11218-1 | <1 \|\| <1 | [NR] | [NR] |
| styrene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| 1,1,2,2-tetrachloroethane | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| QUALITY CONTROL<br><br>VOCs in soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br><br>Base ll Duplicate ll %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| o-Xylene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| 1,2,3-trichloropropane | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| isopropylbenzene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| bromobenzene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| n-propyl benzene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| 2-chlorotoluene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| 4-chlorotoluene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| 1,3,5-trimethyl benzene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| tert-butyl benzene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| 1,2,4-trimethyl benzene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| 1,3-dichlorobenzene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| sec-butyl benzene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| 1,4-dichlorobenzene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| 4-isopropyl toluene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| 1,2-dichlorobenzene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| n-butyl benzene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| 1,2-dibromo-3-chloropropane | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| 1,2,4-trichlorobenzene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| hexachlorobutadiene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| 1,2,3-trichlorobenzene | mg/kg | 0.5 | Org-014 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| Surrogate Dibromofluoromethane | % | | Org-014 | 90 | 11218-1 | 70 \|\| 68 \|\| RPD: 3 | LCS-1 | 91% |
| *Surrogate* aaa-Trifluorotoluene | % | | Org-014 | 90 | 11218-1 | 89 \|\| 87 \|\| RPD: 2 | LCS-1 | 92% |
| *Surrogate* Toluene-$d_8$ | % | | Org-014 | 100 | 11218-1 | 99 \|\| 100 \|\| RPD: 1 | LCS-1 | 100% |
| *Surrogate* 4-Bromofluorobenzene | % | | Org-014 | 97 | 11218-1 | 96 \|\| 97 \|\| RPD: 1 | LCS-1 | 99% |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| QUALITY CONTROL<br>vTRH(C6-C10)/BTEXN in Soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br>Base \|\| Duplicate \|\| %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| Date extracted | - | | | 12/07/2017 | 11218-1 | 12/07/2017 \|\| 12/07/2017 | LCS-1 | 12/07/2017 |
| Date analysed | - | | | 13/07/2017 | 11218-1 | 13/07/2017 \|\| 14/07/2017 | LCS-1 | 13/07/2017 |
| vTRH $C_6$ - $C_9$ | mg/kg | 25 | Org-016 | <25 | 11218-1 | <25 \|\| <25 | LCS-1 | 93% |
| vTRH $C_6$ - $C_{10}$ | mg/kg | 25 | Org-016 | <25 | 11218-1 | <25 \|\| <25 | LCS-1 | 93% |
| Benzene | mg/kg | 0.2 | Org-016 | <0.2 | 11218-1 | <0.2 \|\| <0.2 | LCS-1 | 90% |
| Toluene | mg/kg | 0.5 | Org-016 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | LCS-1 | 92% |
| Ethylbenzene | mg/kg | 1 | Org-016 | <1 | 11218-1 | <1 \|\| <1 | LCS-1 | 96% |
| m+p-xylene | mg/kg | 2 | Org-016 | <2 | 11218-1 | <2 \|\| <2 | LCS-1 | 94% |
| o-Xylene | mg/kg | 1 | Org-016 | <1 | 11218-1 | <1 \|\| <1 | LCS-1 | 94% |
| Naphthalene | mg/kg | 1 | Org-014 | <1 | 11218-1 | <1 \|\| <1 | [NR] | [NR] |
| *Surrogate* aaa-Trifluorotoluene | % | | Org-016 | 101 | 11218-1 | 89 \|\| 89 \|\| RPD: 0 | LCS-1 | 96% |

| QUALITY CONTROL<br>TRH Soil C10-C40 NEPM | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br>Base \|\| Duplicate \|\| %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| Date extracted | - | | | 12/07/2017 | 11218-1 | 12/07/2017 \|\| 12/07/2017 | LCS-1 | 12/07/2017 |
| Date analysed | - | | | 13/07/2017 | 11218-1 | 13/07/2017 \|\| 13/07/2017 | LCS-1 | 13/07/2017 |
| TRH $C_{10}$ - $C_{14}$ | mg/kg | 50 | Org-003 | <50 | 11218-1 | <50 \|\| <50 | LCS-1 | 91% |
| TRH $C_{15}$ - $C_{28}$ | mg/kg | 100 | Org-003 | <100 | 11218-1 | <100 \|\| <100 | LCS-1 | 94% |
| TRH $C_{29}$ - $C_{36}$ | mg/kg | 100 | Org-003 | <100 | 11218-1 | <100 \|\| <100 | LCS-1 | 93% |
| TRH >$C_{10}$-$C_{16}$ | mg/kg | 50 | Org-003 | <50 | 11218-1 | <50 \|\| <50 | LCS-1 | 91% |
| TRH >$C_{16}$-$C_{34}$ | mg/kg | 100 | Org-003 | <100 | 11218-1 | <100 \|\| <100 | LCS-1 | 94% |
| TRH >$C_{34}$-$C_{40}$ | mg/kg | 100 | Org-003 | <100 | 11218-1 | <100 \|\| <100 | LCS-1 | 93% |
| *Surrogate* o-Terphenyl | % | | Org-003 | 85 | 11218-1 | 95 \|\| 90 \|\| RPD: 5 | LCS-1 | 84% |

| QUALITY CONTROL<br>PAHs in Soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br>Base \|\| Duplicate \|\| %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| Date extracted | - | | | 12/07/2017 | 11218-1 | 12/07/2017 \|\| 12/07/2017 | LCS-1 | 12/07/2017 |
| Date analysed | - | | | 15/07/2017 | 11218-1 | 15/07/2017 \|\| 15/07/2017 | LCS-1 | 15/07/2017 |
| Naphthalene | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | LCS-1 | 84% |
| Acenaphthylene | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | LCS-1 | 88% |
| Acenaphthene | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| Fluorene | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | LCS-1 | 84% |
| Phenanthrene | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | LCS-1 | 84% |
| Anthracene | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| Fluoranthene | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | LCS-1 | 84% |
| Pyrene | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | LCS-1 | 88% |
| Benzo(a)anthracene | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| Chrysene | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | LCS-1 | 102% |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| QUALITY CONTROL<br>PAHs in Soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br>Base II Duplicate II %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| Benzo (b,j&k)fluoranthene | mg/kg | 0.2 | Org-012 | <0.2 | 11218-1 | <0.2 \|\| <0.2 | [NR] | [NR] |
| Benzo(a)pyrene | mg/kg | 0.05 | Org-012 | <0.05 | 11218-1 | 0.08 \|\| 0.09 \|\| RPD: 12 | LCS-1 | 88% |
| Indeno(1,2,3-c,d)pyrene | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| Dibenzo(a,h)anthracene | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| Benzo(g,h,i)perylene | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | | Org-012 | 98 | 11218-1 | 98 \|\| 98 \|\| RPD: 0 | LCS-1 | 90% |
| QUALITY CONTROL<br>Speciated Phenols in Soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br>Base II Duplicate II %RPD | Spike Sm# | Spike % Recovery |
| Date extracted | - | | Org-012 | 12/07/2017 | 11218-1 | 12/07/2017 \|\| 12/07/2017 | LCS-1 | 12/07/2017 |
| Date analysed | - | | Org-012 | 15/07/2017 | 11218-1 | 15/07/2017 \|\| 15/07/2017 | LCS-1 | 15/07/2017 |
| Phenol | mg/kg | 0.2 | Org-012 | <0.2 | 11218-1 | <0.2 \|\| <0.2 | LCS-1 | 96% |
| 2-Chlorophenol | mg/kg | 0.2 | Org-012 | <0.2 | 11218-1 | <0.2 \|\| <0.2 | LCS-1 | 92% |
| 2-Methylphenol | mg/kg | 0.2 | Org-012 | <0.2 | 11218-1 | <0.2 \|\| <0.2 | LCS-1 | 86% |
| 3/4-Methylphenol | mg/kg | 0.4 | Org-012 | <0.4 | 11218-1 | <0.4 \|\| <0.4 | [NR] | [NR] |
| 2-Nitrophenol | mg/kg | 0.2 | Org-012 | <0.2 | 11218-1 | <0.2 \|\| <0.2 | [NR] | [NR] |
| 2,4-Dimethylphenol | mg/kg | 0.2 | Org-012 | <0.2 | 11218-1 | <0.2 \|\| <0.2 | [NR] | [NR] |
| 2,4-Dichlorophenol | mg/kg | 0.2 | Org-012 | <0.2 | 11218-1 | <0.2 \|\| <0.2 | [NR] | [NR] |
| 2,6-Dichlorophenol | mg/kg | 0.2 | Org-012 | <0.2 | 11218-1 | <0.2 \|\| <0.2 | LCS-1 | 94% |
| 2,4,5-Trichlorophenol | mg/kg | 0.2 | Org-012 | <0.2 | 11218-1 | <0.2 \|\| <0.2 | [NR] | [NR] |
| 2,4,6-Trichlorophenol | mg/kg | 0.2 | Org-012 | <0.2 | 11218-1 | <0.2 \|\| <0.2 | [NR] | [NR] |
| 2,4-Dinitrophenol | mg/kg | 2 | Org-012 | <2 | 11218-1 | <2 \|\| <2 | [NR] | [NR] |
| 4-Nitrophenol | mg/kg | 4 | Org-012 | <4 | 11218-1 | <4 \|\| <4 | [NR] | [NR] |
| 2,3,4,6-Tetrachlorophenol | mg/kg | 0.2 | Org-012 | <0.2 | 11218-1 | <0.2 \|\| <0.2 | [NR] | [NR] |
| Pentachlorophenol | mg/kg | 1 | Org-012 | <1 | 11218-1 | <1 \|\| <1 | LCS-1 | 62% |
| 4-Chloro-3-Methylphenol | mg/kg | 2 | Org-012 | <2 | 11218-1 | <2 \|\| <2 | [NR] | [NR] |
| *Surrogate* Phenol-$d_6$ | % | | Org-012 | 94 | 11218-1 | 82 \|\| 80 \|\| RPD: 2 | LCS-1 | 94% |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| QUALITY CONTROL<br><br>OCP in Soil - NEPM | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br><br>Base ll Duplicate ll %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| Date extracted | - | | | 12/07/2017 | 11218-1 | 12/07/2017 \|\| 12/07/2017 | LCS-1 | 12/07/2017 |
| Date analysed | - | | | 15/07/2017 | 11218-1 | 15/07/2017 \|\| 15/07/2017 | LCS-1 | 15/07/2017 |
| alpha-BHC | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | LCS-1 | 82% |
| Hexachlorobenzene | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| beta-BHC | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | LCS-1 | 82% |
| gamma-BHC | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| Heptachlor | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | LCS-1 | 86% |
| delta-BHC | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| Aldrin | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | LCS-1 | 82% |
| Heptachlor Epoxide | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | LCS-1 | 86% |
| gamma-Chlordane | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | LCS-1 | 82% |
| alpha-chlordane | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| Endosulfan I | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| pp-DDE | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | LCS-1 | 82% |
| Dieldrin | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | LCS-1 | 84% |
| Endrin | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| Endosulfan II | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| pp-DDD | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | LCS-1 | 94% |
| Endrin Aldehyde | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| pp-DDT | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| Endosulfan Sulphate | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | LCS-1 | 86% |
| Methoxychlor | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| Mirex | mg/kg | 0.5 | Org-012 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | [NR] | [NR] |
| Toxaphene | mg/kg | 2 | Org-012 | <2 | 11218-1 | <2 \|\| <2 | [NR] | [NR] |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | | Org-012 | 98 | 11218-1 | 98 \|\| 98 \|\| RPD: 0 | LCS-1 | 90% |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| QUALITY CONTROL<br>OP in Soil - NEPM | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br>Base ll Duplicate ll %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| Date extracted | - | | | 12/07/2017 | 11218-1 | 12/07/2017 \|\| 12/07/2017 | LCS-1 | 12/07/2017 |
| Date analysed | - | | | 15/07/2017 | 11218-1 | 15/07/2017 \|\| 15/07/2017 | LCS-1 | 15/07/2017 |
| Chlorpyrifos | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | LCS-1 | 92% |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | | Org-012 | 98 | 11218-1 | 98 \|\| 98 \|\| RPD: 0 | LCS-1 | 90% |
| QUALITY CONTROL<br>PCBs in Soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br>Base ll Duplicate ll %RPD | Spike Sm# | Spike % Recovery |
| Date extracted | - | | | 12/07/2017 | 11218-1 | 12/07/2017 \|\| 12/07/2017 | LCS-1 | 12/07/2017 |
| Date analysed | - | | | 15/07/2017 | 11218-1 | 15/07/2017 \|\| 15/07/2017 | LCS-1 | 15/07/2017 |
| Aroclor 1016 | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| Aroclor 1221 | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| Aroclor 1232 | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| Aroclor 1242 | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| Aroclor 1248 | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| Aroclor 1254 | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | LCS-1 | 90% |
| Aroclor 1260 | mg/kg | 0.1 | Org-012 | <0.1 | 11218-1 | <0.1 \|\| <0.1 | [NR] | [NR] |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | | Org-012 | 98 | 11218-1 | 98 \|\| 98 \|\| RPD: 0 | LCS-1 | 90% |
| QUALITY CONTROL<br>Synthetic Pyrethroids - NEPM | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br>Base ll Duplicate ll %RPD | Spike Sm# | Spike % Recovery |
| Date extracted | - | | | 12/07/2017 | 11218-1 | 12/07/2017 \|\| 12/07/2017 | LCS-1 | 12/07/2017 |
| Date analysed | - | | | 15/07/2017 | 11218-1 | 15/07/2017 \|\| 15/07/2017 | LCS-1 | 15/07/2017 |
| Bifenthrin | mg/kg | 0.5 | Org-012 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | LCS-1 | 102% |
| QUALITY CONTROL<br>Triazine Herbicides in Soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br>Base ll Duplicate ll %RPD | Spike Sm# | Spike % Recovery |
| Date extracted | - | | | 12/07/2017 | 11218-1 | 12/07/2017 \|\| 12/07/2017 | LCS-1 | 12/07/2017 |
| Date analysed | - | | | 15/07/2017 | 11218-1 | 15/07/2017 \|\| 15/07/2017 | LCS-1 | 15/07/2017 |
| Atrazine | mg/kg | 0.5 | Org-012 | <0.5 | 11218-1 | <0.5 \|\| <0.5 | LCS-1 | 86% |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| QUALITY CONTROL<br><br>Phenoxy Acid Herbicides in Soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br><br>Base II Duplicate II %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| Clopyralid | mg/kg | 0.5 | ORG-031 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| 3,5-Dichlorobenzoic acid | mg/kg | 0.5 | ORG-031 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| o-Chlorophenoxy acetic acid | mg/kg | 0.5 | ORG-031 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| 4-CPA | mg/kg | 0.5 | ORG-031 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| Dicamba | mg/kg | 0.5 | ORG-031 | <0.5 | [NT] | [NT] | LCS-1 | 88% |
| Mecoprop | mg/kg | 0.5 | ORG-031 | <0.5 | [NT] | [NT] | LCS-1 | 86% |
| MCPA | mg/kg | 0.5 | ORG-031 | <0.5 | [NT] | [NT] | LCS-1 | 84% |
| Dichloroprop | mg/kg | 0.5 | ORG-031 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| 2,4-D | mg/kg | 0.5 | ORG-031 | <0.5 | [NT] | [NT] | LCS-1 | 84% |
| Bromoxynil | mg/kg | 0.5 | ORG-031 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| Triclopyr | mg/kg | 0.5 | ORG-031 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| 2,4,5-TP (Silvex) | mg/kg | 0.5 | ORG-031 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| 2,4,5-T | mg/kg | 0.5 | ORG-031 | <0.5 | [NT] | [NT] | LCS-1 | 81% |
| MCPB | mg/kg | 0.5 | ORG-031 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| 2.4-DB | mg/kg | 0.5 | ORG-031 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| Dinoseb | mg/kg | 1 | ORG-031 | <1.0 | [NT] | [NT] | [NR] | [NR] |
| Ioxynil | mg/kg | 1 | ORG-031 | <1.0 | [NT] | [NT] | [NR] | [NR] |
| Picloram | mg/kg | 0.5 | ORG-031 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| DCPA (Chlorthal) Diacid | mg/kg | 0.5 | ORG-031 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| Acifluorfen | mg/kg | 2 | ORG-031 | <2.0 | [NT] | [NT] | [NR] | [NR] |
| 2,4,6-T | mg/kg | 0.5 | ORG-031 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| 2,6-D | mg/kg | 0.5 | ORG-031 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| Surrogate: 2,4-DCPA | % | | ORG-031 | 102 | [NT] | [NT] | LCS-1 | 106% |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| QUALITY CONTROL<br><br>NEPM screen metals in soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br><br>Base II Duplicate II %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| Date digested | - | | | 13/07/2017 | [NT] | [NT] | LCS-1 | 13/07/2017 |
| Date analysed | - | | | 13/07/2017 | [NT] | [NT] | LCS-1 | 13/07/2017 |
| Arsenic | mg/kg | 4 | Metals-020 ICP-AES | <4 | [NT] | [NT] | LCS-1 | 103% |
| Beryllium | mg/kg | 1 | Metals-020 ICP-AES | <1 | [NT] | [NT] | LCS-1 | 118% |
| Boron | mg/kg | 3 | Metals-020 ICP-AES | <3 | [NT] | [NT] | LCS-1 | 105% |
| Cadmium | mg/kg | 0.4 | Metals-020 ICP-AES | <0.4 | [NT] | [NT] | LCS-1 | 109% |
| Cobalt | mg/kg | 1 | Metals-020 ICP-AES | <1 | [NT] | [NT] | LCS-1 | 102% |
| Chromium | mg/kg | 1 | Metals-020 ICP-AES | <1 | [NT] | [NT] | LCS-1 | 108% |
| Copper | mg/kg | 1 | Metals-020 ICP-AES | <1 | [NT] | [NT] | LCS-1 | 107% |
| Lead | mg/kg | 1 | Metals-020 ICP-AES | <1 | [NT] | [NT] | LCS-1 | 105% |
| Mercury | mg/kg | 0.1 | Metals-021 CV-AAS | <0.1 | [NT] | [NT] | LCS-1 | 112% |
| Manganese | mg/kg | 1 | Metals-020 ICP-AES | <1 | [NT] | [NT] | LCS-1 | 109% |
| Nickel | mg/kg | 1 | Metals-020 ICP-AES | <1 | [NT] | [NT] | LCS-1 | 105% |
| Selenium | mg/kg | 2 | Metals-020 ICP-AES | <2 | [NT] | [NT] | LCS-1 | 97% |
| Zinc | mg/kg | 1 | Metals-020 ICP-AES | <1 | [NT] | [NT] | LCS-1 | 105% |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| QUALITY CONTROL<br>Misc Inorg - soil NEPM | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br>Base II Duplicate II %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| Date prepared | - | | | 13/07/2017 | [NT] | [NT] | LCS-1 | 13/07/2017 |
| Date analysed | - | | | 14/07/2017 | [NT] | [NT] | LCS-1 | 14/07/2017 |
| Free Cyanide in soil | mg/kg | 0.5 | Inorg-013 | <0.5 | [NT] | [NT] | LCS-1 | 84% |
| Hexavalent Chromium, $Cr^{6+}$ | mg/kg | 1 | Inorg-024 | <1 | [NT] | [NT] | LCS-1 | 88% |

| QUALITY CONTROL<br>Moisture | UNITS | PQL | METHOD | Blank |
|---|---|---|---|---|
| Date prepared | - | | | [NT] |
| Date analysed | - | | | [NT] |
| Moisture | % | 0.1 | Inorg-008 | [NT] |

| QUALITY CONTROL<br>PAHs in Soil | UNITS | Dup. Sm# | Duplicate<br>Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Date extracted | - | [NT] | [NT] | 11218-1 | 12/07/2017 |
| Date analysed | - | [NT] | [NT] | 11218-1 | 15/07/2017 |
| Naphthalene | mg/kg | [NT] | [NT] | 11218-1 | 91% |
| Acenaphthylene | mg/kg | [NT] | [NT] | 11218-1 | 90% |
| Acenaphthene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Fluorene | mg/kg | [NT] | [NT] | 11218-1 | 93% |
| Phenanthrene | mg/kg | [NT] | [NT] | 11218-1 | 98% |
| Anthracene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Fluoranthene | mg/kg | [NT] | [NT] | 11218-1 | 97% |
| Pyrene | mg/kg | [NT] | [NT] | 11218-1 | 104% |
| Benzo(a)anthracene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Chrysene | mg/kg | [NT] | [NT] | 11218-1 | 110% |
| Benzo(b,j&k)fluoranthene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Benzo(a)pyrene | mg/kg | [NT] | [NT] | 11218-1 | 97% |
| Indeno(1,2,3-c,d)pyrene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Dibenzo(a,h)anthracene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Benzo(g,h,i)perylene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | [NT] | [NT] | 11218-1 | 102% |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| QUALITY CONTROL Speciated Phenols in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Date extracted | - | [NT] | [NT] | 11218-1 | 12/07/2017 |
| Date analysed | - | [NT] | [NT] | 11218-1 | 15/07/2017 |
| Phenol | mg/kg | [NT] | [NT] | 11218-1 | 86% |
| 2-Chlorophenol | mg/kg | [NT] | [NT] | 11218-1 | 86% |
| 2-Methylphenol | mg/kg | [NT] | [NT] | 11218-1 | 86% |
| 3/4-Methylphenol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2-Nitrophenol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2,4-Dimethylphenol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2,4-Dichlorophenol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2,6-Dichlorophenol | mg/kg | [NT] | [NT] | 11218-1 | 94% |
| 2,4,5-Trichlorophenol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2,4,6-Trichlorophenol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2,4-Dinitrophenol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 4-Nitrophenol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2,3,4,6-Tetrachlorophenol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Pentachlorophenol | mg/kg | [NT] | [NT] | 11218-1 | 64% |
| 4-Chloro-3-Methylphenol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| *Surrogate* Phenol-$d_6$ | % | [NT] | [NT] | 11218-1 | 92% |

| QUALITY CONTROL OCP in Soil - NEPM | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Date extracted | - | [NT] | [NT] | 11218-1 | 12/07/2017 |
| Date analysed | - | [NT] | [NT] | 11218-1 | 15/07/2017 |
| alpha-BHC | mg/kg | [NT] | [NT] | 11218-1 | 88% |
| Hexachlorobenzene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| beta-BHC | mg/kg | [NT] | [NT] | 11218-1 | 88% |
| gamma-BHC | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Heptachlor | mg/kg | [NT] | [NT] | 11218-1 | 89% |
| delta-BHC | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Aldrin | mg/kg | [NT] | [NT] | 11218-1 | 89% |
| Heptachlor Epoxide | mg/kg | [NT] | [NT] | 11218-1 | 98% |
| gamma-Chlordane | mg/kg | [NT] | [NT] | 11218-1 | 89% |
| alpha-chlordane | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Endosulfan I | mg/kg | [NT] | [NT] | [NR] | [NR] |
| pp-DDE | mg/kg | [NT] | [NT] | 11218-1 | 89% |
| Dieldrin | mg/kg | [NT] | [NT] | 11218-1 | 91% |
| Endrin | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Endosulfan II | mg/kg | [NT] | [NT] | [NR] | [NR] |
| pp-DDD | mg/kg | [NT] | [NT] | 11218-1 | 107% |
| Endrin Aldehyde | mg/kg | [NT] | [NT] | [NR] | [NR] |
| pp-DDT | mg/kg | [NT] | [NT] | [NR] | [NR] |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

| QUALITY CONTROL OCP in Soil - NEPM | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Endosulfan Sulphate | mg/kg | [NT] | [NT] | 11218-1 | 94% |
| Methoxychlor | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Mirex | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Toxaphene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | [NT] | [NT] | 11218-1 | 102% |
| QUALITY CONTROL OP in Soil - NEPM | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
| Date extracted | - | [NT] | [NT] | 11218-1 | 12/07/2017 |
| Date analysed | - | [NT] | [NT] | 11218-1 | 15/07/2017 |
| Chlorpyrifos | mg/kg | [NT] | [NT] | 11218-1 | 101% |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | [NT] | [NT] | 11218-1 | 102% |
| QUALITY CONTROL PCBs in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
| Date extracted | - | [NT] | [NT] | 11218-1 | 12/07/2017 |
| Date analysed | - | [NT] | [NT] | 11218-1 | 15/07/2017 |
| Aroclor 1016 | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1221 | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1232 | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1242 | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1248 | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1254 | mg/kg | [NT] | [NT] | 11218-1 | 98% |
| Aroclor 1260 | mg/kg | [NT] | [NT] | [NR] | [NR] |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | [NT] | [NT] | 11218-1 | 102% |
| QUALITY CONTROL Synthetic Pyrethroids - NEPM | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
| Date extracted | - | [NT] | [NT] | 11218-1 | 12/07/2017 |
| Date analysed | - | [NT] | [NT] | 11218-1 | 15/07/2017 |
| Bifenthrin | mg/kg | [NT] | [NT] | 11218-1 | 117% |
| QUALITY CONTROL Triazine Herbicides in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
| Date extracted | - | [NT] | [NT] | 11218-1 | 12/07/2017 |
| Date analysed | - | [NT] | [NT] | 11218-1 | 15/07/2017 |
| Atrazine | mg/kg | [NT] | [NT] | 11218-1 | 91% |



NATA
ACCREDITED FOR TECHNICAL COMPETENCE

**Report Comments:**

Acid Herbicides analysed by MPL. Report number 198166.

| | |
|---|---|
| Asbestos ID was analysed by Approved Identifier: | Not applicable for this job |
| Asbestos ID was authorised by Approved Signatory: | Not applicable for this job |

| | | |
|---|---|---|
| INS: Insufficient sample for this test | PQL: Practical Quantitation Limit | NT: Not tested |
| NR: Test not required | RPD: Relative Percent Difference | NA: Test not required |
| <: Less than | >: Greater than | LCS: Laboratory Control Sample |

## Quality Control Definitions

**Blank**: This is the component of the analytical signal which is not derived from the sample but from reagents, glassware etc, can be determined by processing solvents and reagents in exactly the same manner as for samples.

**Duplicate**: This is the complete duplicate analysis of a sample from the process batch. If possible, the sample selected should be one where the analyte concentration is easily measurable.

**Matrix Spike** : A portion of the sample is spiked with a known concentration of target analyte. The purpose of the matrix spike is to monitor the performance of the analytical method used and to determine whether matrix interferences exist.

**LCS (Laboratory Control Sample)** : This comprises either a standard reference material or a control matrix (such as a blank sand or water) fortified with analytes representative of the analyte class. It is simply a check sample.

**Surrogate Spike:** Surrogates are known additions to each sample, blank, matrix spike and LCS in a batch, of compounds which are similar to the analyte of interest, however are not expected to be found in real samples.

## Laboratory Acceptance Criteria

Duplicate sample and matrix spike recoveries may not be reported on smaller jobs, however, were analysed at a frequency to meet or exceed NEPM requirements. All samples are tested in batched of 20. The duplicate sample RPD and matrix spike recoveries for the batch were within the laboratory acceptance criteria.
Filters, swabs, wipes, tubes and badges will not have duplicate data as the whole sample is generally extracted during sample extraction.
Spikes for Physical and Aggregate Tests are not applicable.
For VOCs in water samples, three vials are required for duplicate or spike analysis.

Duplicates: <5xPQL - any RPD is acceptable; >5xPQL - 0-50% RPD is acceptable.
Matrix Spikes, LCS and Surrogate recoveries: Generally 70-130% for inorganics/metals; 60-140% for organics (+/-50% surrogates) and 10-140% for labile SVOCs (including labile surrogates), ultra trace organics and speciated phenols is acceptable.

In circumstances where no duplicate and/or sample spike has been reported at 1 in 10 and/or 1 in 20 samples respectively, the sample volume submitted was insufficient in order to satisfy laboratory QA/QC protocols.

When samples are received where certain analytes are outside of recommended technical holding times (THTs), the analysis has proceeded. Where analytes are on the verge of breaching THTs, every effort will be made to analyse within the THT or as soon as practicable.

Where sampling dates are not provided, Envirolab are not in a position to comment on the validity of the analysis where recommended technical holding times may have been breached.

Measurement Uncertainty estimates are available for most tests upon request.

LRM GLOBAL

P.O. Box 1237
Carlton VIC 3053
enquiries@lrmglobal.com.au

# CHAIN OF CUSTODY

**Job Number:** 27380

Sheet 1 of 1

| | |
|---|---|
| **ATTENTION** | Envirolab |
| **CLIENT** | Australian Unity Limited |
| **LOCATION** | 266 Longueville Rd, Lane Cove |

| | Sample Number | Sample Date | Sample Type | Analysis Required | No. of Containers | Turn-around Time Required |
|---|---|---|---|---|---|---|
| 1 | GW01 | 3/08/2018 | Water | TRH/BTEX, VOCs, PAHs, Total Phenolics, Phthalates, OCPs, PCBs, TDS, pH, metals (Al, Ag, As, B, Ba, Be, Cd, Cr, Co, Cu, Fe, Pb, Mn, Hg, Mo, Ni, Se, Sb, Sn, Ti, V, Zn), cation/anions, ammonia, flouride, Hexavalent chromium, total cyanide, PFAS & PFOS | 9 | Standard |
| 2 | GW02 | 3/08/2018 | Water | TRH/BTEX, VOCs, PAHs, Total Phenolics, Phthalates, OCPs, PCBs, TDS, pH, metals (Al, Ag, As, B, Ba, Be, Cd, Cr, Co, Cu, Fe, Pb, Mn, Hg, Mo, Ni, Se, Sb, Sn, Ti, V, Zn), cation/anions, ammonia, flouride, Hexavalent chromium, total cyanide, PFAS & PFOS | 9 | Standard |
| 3 | GW03 | 3/08/2018 | Water | TRH/BTEX, VOCs, PAHs, Total Phenolics, Phthalates, OCPs, PCBs, TDS, pH, metals (Al, Ag, As, B, Ba, Be, Cd, Cr, Co, Cu, Fe, Pb, Mn, Hg, Mo, Ni, Se, Sb, Sn, Ti, V, Zn), cation/anions, ammonia, flouride, Hexavalent chromium, total cyanide, PFAS & PFOS | 9 | Standard |
| 4 | DUP/03/08/18 | 3/08/2018 | Water | TRH/BTEX, VOCs, PAHs, Total Phenolics, Phthalates, OCPs, PCBs, TDS, pH, metals (Al, Ag, As, B, Ba, Be, Cd, Cr, Co, Cu, Fe, Pb, Mn, Hg, Mo, Ni, Se, Sb, Sn, Ti, V, Zn), cation/anions, ammonia, flouride, Hexavalent chromium, total cyanide, PFAS & PFOS | 9 | Standard |
| 1 | SPLIT/03/08/18 | 3/08/2018 | Water | TRH/BTEX, VOCs, PAHs, Total Phenolics, Phthalates, OCPs, PCBs, TDS, pH, metals (Al, Ag, As, B, Ba, Be, Cd, Cr, Co, Cu, Fe, Pb, Mn, Hg, Mo, Ni, Se, Sb, Sn, Ti, V, Zn), cation/anions, ammonia, flouride, Hexavalent chromium, total cyanide, PFAS & PFOS | 9 | Standard |
| 5 | RB/03/08/18 | 3/08/2018 | Water | TPH, PAHs, Metals | 4 | Standard |
| 6 | TB/03/08/18 | 3/08/2018 | Water | TPH C6-C9 | 2 | Standard |

ENVIROLAB

*Envirolab Services*
*12 Ashley St*
*Chatswood NSW 2067*
*Ph: (02) 9910 6200*

Job No: 197675
Date Received: 3/8/18
Time Received: 1423
Received By: MT
Temp: Cool/Ambient 6.9
Cooling: Ice/Icepack
Security: Intact/Broken/None

**Total number of containers** 51

ENVIROLAB

Job No: 14401
Date Received: 7/8/18
Time Received: 13:24
Received by: [illegible]
Temp: Cool/Ambient
Cooling: Ice/Icepack
Security: Intact/Broken/None

10.3

**Additional information::**

| Email Results To | Tick |
|---|---|
| jon.lawson@lrmglobal.com.au | √ |
| acampbell@lrmglobal.com.au | √ |
| ajacob@lrmglobal.com.au | |
| dyeoh@lrmglobal.com.au | |
| bpaule@lrmglobal.com.au | |

Chain of custody must be signed and dated by LRM, courier, and laboratory.

Sampled by: NM (EP Risk)

Checked by: AJC (LRM)

**Additional Comments**

Splits to Envirolab (Melb)

| RELINQUISHED BY (Signature) | ORGANISATION | DATE / TIME | RECEIVED BY (Signature) | ORGANISATION | DATE / TIME |
|---|---|---|---|---|---|
| N-M Ebourne | EP Risk | 3/8/18 | MT | ELS | 3/8/18 1423 |
| RELINQUISHED BY (Signature) | ORGANISATION | DATE / TIME | RECEIVED BY (Signature) | RECEIVED FOR LABORATORY BY (Signature) | |
| JE. | ELS | 6/8/18 12:45 | | | |

**Envirolab Services Pty Ltd**
ABN 37 112 535 645 - 002
25 Research Drive Croydon South VIC 3136
ph 03 9763 2500 fax 03 9763 2633
melbourne@envirolab.com.au
www.envirolab.com.au

# CERTIFICATE OF ANALYSIS 14401

## Client Details

| | |
|---|---|
| **Client** | LRM Global |
| **Attention** | Adam Campbell |
| **Address** | 65 Stubbs Street, Kensington, VIC, 3031 |

## Sample Details

| | |
|---|---|
| **Your Reference** | **27380 - 266 Longueville Rd, Lane Cove** |
| **Number of Samples** | 1 Water |
| **Date samples received** | 07/08/2018 |
| **Date completed instructions received** | 07/08/2018 |

## Analysis Details

Please refer to the following pages for results, methodology summary and quality control data.

Samples were analysed as received from the client. Results relate specifically to the samples as received.

Results are reported on a dry weight basis for solids and on an as received basis for other matrices.

## Report Details

| | |
|---|---|
| **Date results requested by** | 14/08/2018 |
| **Date of Issue** | 14/08/2018 |

NATA Accreditation Number 2901. This document shall not be reproduced except in full.

Accredited for compliance with ISO/IEC 17025 - Testing. **Tests not covered by NATA are denoted with ***

**Results Approved By**
Chris De Luca, Senior Chemist

**Authorised By**



Pamela Adams, Laboratory Manager

| VOCs in water | | |
|---|---|---|
| Our Reference | | 14401-1 |
| Your Reference | UNITS | SPLIT/03/08/18 |
| Date Sampled | | 03/08/2018 |
| Type of sample | | Water |
| Date extracted | - | 08/08/2018 |
| Date analysed | - | 08/08/2018 |
| Dichlorodifluoromethane | µg/L | <10 |
| Chloromethane | µg/L | <10 |
| Vinyl Chloride | µg/L | <10 |
| Bromomethane | µg/L | <10 |
| Chloroethane | µg/L | <10 |
| Trichlorofluoromethane | µg/L | <10 |
| 1,1-Dichloroethene | µg/L | <1 |
| Trans-1,2-dichloroethene | µg/L | <1 |
| 1,1-dichloroethane | µg/L | <1 |
| Cis-1,2-dichloroethene | µg/L | <1 |
| Bromochloromethane | µg/L | <1 |
| Chloroform | µg/L | <1 |
| 2,2-dichloropropane | µg/L | <1 |
| 1,2-dichloroethane | µg/L | <1 |
| 1,1,1-trichloroethane | µg/L | <1 |
| 1,1-dichloropropene | µg/L | <1 |
| Cyclohexane | µg/L | <1 |
| Carbon tetrachloride | µg/L | <1 |
| Benzene | µg/L | <1 |
| Dibromomethane | µg/L | <1 |
| 1,2-dichloropropane | µg/L | <1 |
| Trichloroethene | µg/L | <1 |
| Bromodichloromethane | µg/L | <1 |
| trans-1,3-dichloropropene | µg/L | <1 |
| cis-1,3-dichloropropene | µg/L | <1 |
| 1,1,2-trichloroethane | µg/L | <1 |
| Toluene | µg/L | <1 |
| 1,3-dichloropropane | µg/L | <1 |
| Dibromochloromethane | µg/L | <1 |
| 1,2-dibromoethane | µg/L | <1 |
| Tetrachloroethene | µg/L | <1 |
| 1,1,1,2-tetrachloroethane | µg/L | <1 |
| Chlorobenzene | µg/L | <1 |
| Ethylbenzene | µg/L | <1 |
| Bromoform | µg/L | <1 |

| VOCs in water | | |
|---|---|---|
| Our Reference | | 14401-1 |
| Your Reference | UNITS | SPLIT/03/08/18 |
| Date Sampled | | 03/08/2018 |
| Type of sample | | Water |
| m+p-xylene | µg/L | <2 |
| Styrene | µg/L | <1 |
| 1,1,2,2-tetrachloroethane | µg/L | <1 |
| o-xylene | µg/L | <1 |
| 1,2,3-trichloropropane | µg/L | <1 |
| Isopropylbenzene | µg/L | <1 |
| Bromobenzene | µg/L | <1 |
| n-propyl benzene | µg/L | <1 |
| 2-chlorotoluene | µg/L | <1 |
| 4-chlorotoluene | µg/L | <1 |
| 1,3,5-trimethyl benzene | µg/L | <1 |
| Tert-butyl benzene | µg/L | <1 |
| 1,2,4-trimethyl benzene | µg/L | <1 |
| 1,3-dichlorobenzene | µg/L | <1 |
| Sec-butyl benzene | µg/L | <1 |
| 1,4-dichlorobenzene | µg/L | <1 |
| 4-isopropyl toluene | µg/L | <1 |
| 1,2-dichlorobenzene | µg/L | <1 |
| n-butyl benzene | µg/L | <1 |
| 1,2-dibromo-3-chloropropane | µg/L | <1 |
| 1,2,4-trichlorobenzene | µg/L | <1 |
| Hexachlorobutadiene | µg/L | <1 |
| 1,2,3-trichlorobenzene | µg/L | <1 |
| *Surrogate* Dibromofluoromethane | % | 93 |
| *Surrogate* toluene-d8 | % | 88 |
| *Surrogate* 4-BFB | % | 96 |

| vTRH(C6-C10)/BTEXN in Water | | |
|---|---|---|
| Our Reference | | 14401-1 |
| Your Reference | UNITS | SPLIT/03/08/18 |
| Date Sampled | | 03/08/2018 |
| Type of sample | | Water |
| Date extracted | - | 08/08/2018 |
| Date analysed | - | 08/08/2018 |
| TRH $C_6$ - $C_9$ | µg/L | <10 |
| TRH $C_6$ - $C_{10}$ | µg/L | <10 |
| TRH $C_6$ - $C_{10}$ less BTEX (F1) | µg/L | <10 |
| Benzene | µg/L | <1 |
| Toluene | µg/L | <1 |
| Ethylbenzene | µg/L | <1 |
| m+p-xylene | µg/L | <2 |
| o-xylene | µg/L | <1 |
| Naphthalene | µg/L | <1 |
| *Surrogate* Dibromofluoromethane | % | 111 |
| *Surrogate* toluene-d8 | % | 98 |
| *Surrogate* 4-BFB | % | 98 |

| TRH Water(C10-C40) NEPM | | |
|---|---|---|
| Our Reference | | 14401-1 |
| Your Reference | UNITS | SPLIT/03/08/18 |
| Date Sampled | | 03/08/2018 |
| Type of sample | | Water |
| Date extracted | - | 08/08/2018 |
| Date analysed | - | 08/08/2018 |
| TRH $C_{10}$ - $C_{14}$ | µg/L | <50 |
| TRH $C_{15}$ - $C_{28}$ | µg/L | <100 |
| TRH $C_{29}$ - $C_{36}$ | µg/L | <100 |
| TRH >$C_{10}$ - $C_{16}$ | µg/L | <50 |
| TRH >$C_{10}$ - $C_{16}$ less Naphthalene (F2) | µg/L | <50 |
| TRH >$C_{16}$ - $C_{34}$ | µg/L | <100 |
| TRH >$C_{34}$ - $C_{40}$ | µg/L | <100 |
| *Surrogate* o-Terphenyl | % | 86 |

| PAHs in Water | | |
|---|---|---|
| Our Reference | | 14401-1 |
| Your Reference | UNITS | SPLIT/03/08/18 |
| Date Sampled | | 03/08/2018 |
| Type of sample | | Water |
| Date extracted | - | 08/08/2018 |
| Date analysed | - | 08/08/2018 |
| Naphthalene | µg/L | <1 |
| Acenaphthylene | µg/L | <1 |
| Acenaphthene | µg/L | <1 |
| Fluorene | µg/L | <1 |
| Phenanthrene | µg/L | <1 |
| Anthracene | µg/L | <1 |
| Fluoranthene | µg/L | <1 |
| Pyrene | µg/L | <1 |
| Benzo(a)anthracene | µg/L | <1 |
| Chrysene | µg/L | <1 |
| Benzo(b,j&k)fluoranthene | µg/L | <2 |
| Benzo(a)pyrene | µg/L | <1 |
| Indeno(1,2,3-c,d)pyrene | µg/L | <1 |
| Dibenzo(a,h)anthracene | µg/L | <1 |
| Benzo(g,h,i)perylene | µg/L | <1 |
| Total +ve PAH's | µg/L | <1 |
| Benzo(a)pyrene TEQ | µg/L | <5 |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | 84 |

| Phthalates in water | | |
|---|---|---|
| Our Reference | | 14401-1 |
| Your Reference | UNITS | SPLIT/03/08/18 |
| Date Sampled | | 03/08/2018 |
| Type of sample | | Water |
| Date extracted | - | 08/08/2018 |
| Date analysed | - | 14/08/2018 |
| Dimethyl phthalate | µg/L | <10 |
| Diethylphthalate | µg/L | <10 |
| Di-n-butylphthalate | µg/L | <50 |
| Butylbenzylphthalate | µg/L | <10 |
| Bis(2-ethylhexyl) phthalate | µg/L | <50 |
| Di-n-octylphthalate | µg/L | <10 |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | 78 |

| OCP in water | | |
|---|---|---|
| Our Reference | | 14401-1 |
| Your Reference | UNITS | SPLIT/03/08/18 |
| Date Sampled | | 03/08/2018 |
| Type of sample | | Water |
| Date extracted | - | 08/08/2018 |
| Date analysed | - | 14/08/2018 |
| HCB | µg/L | <0.2 |
| alpha-BHC | µg/L | <0.2 |
| gamma-BHC | µg/L | <0.2 |
| beta-BHC | µg/L | <0.2 |
| Heptachlor | µg/L | <0.2 |
| delta-BHC | µg/L | <0.2 |
| Aldrin | µg/L | <0.2 |
| Heptachlor Epoxide | µg/L | <0.2 |
| gamma-Chlordane | µg/L | <0.2 |
| alpha-Chlordane | µg/L | <0.2 |
| Endosulfan I | µg/L | <0.2 |
| pp-DDE | µg/L | <0.2 |
| Dieldrin | µg/L | <0.2 |
| Endrin | µg/L | <0.2 |
| pp-DDD | µg/L | <0.2 |
| Endosulfan II | µg/L | <0.2 |
| pp-DDT | µg/L | <0.2 |
| Endrin Aldehyde | µg/L | <0.2 |
| Endosulfan Sulphate | µg/L | <0.2 |
| Methoxychlor | µg/L | <0.2 |
| *Surrogate p*-Terphenyl | % | 78 |

| PCBs in Water | | |
|---|---|---|
| Our Reference | | 14401-1 |
| Your Reference | UNITS | SPLIT/03/08/18 |
| Date Sampled | | 03/08/2018 |
| Type of sample | | Water |
| Date extracted | - | 08/08/2018 |
| Date analysed | - | 14/08/2018 |
| Aroclor 1016 | µg/L | <2 |
| Aroclor 1221 | µg/L | <2 |
| Aroclor 1232 | µg/L | <2 |
| Aroclor 1242 | µg/L | <2 |
| Aroclor 1248 | µg/L | <2 |
| Aroclor 1254 | µg/L | <2 |
| Aroclor 1260 | µg/L | <2 |
| *Surrogate p*-Terphenyl | % | 78 |

| All metals in water-dissolved | | |
|---|---|---|
| Our Reference | | 14401-1 |
| Your Reference | UNITS | SPLIT/03/08/18 |
| Date Sampled | | 03/08/2018 |
| Type of sample | | Water |
| Date prepared | - | 08/08/2018 |
| Date analysed | - | 08/08/2018 |
| Aluminium-Dissolved | µg/L | 640 |
| Silver-Dissolved | µg/L | <1 |
| Arsenic-Dissolved | µg/L | <1 |
| Boron-Dissolved | µg/L | 80 |
| Barium-Dissolved | µg/L | 25 |
| Beryllium-Dissolved | µg/L | 0.9 |
| Cadmium-Dissolved | µg/L | <0.1 |
| Chromium-Dissolved | µg/L | 1 |
| Cobalt-Dissolved | µg/L | 5 |
| Copper-Dissolved | µg/L | 7 |
| Iron-Dissolved | µg/L | 2,900 |
| Lead-Dissolved | µg/L | 3 |
| Manganese-Dissolved | µg/L | 190 |
| Mercury-Dissolved | µg/L | <0.05 |
| Molybdenum-Dissolved | µg/L | <1 |
| Nickel-Dissolved | µg/L | 61 |
| Selenium-Dissolved | µg/L | <1 |
| Antimony-Dissolved | µg/L | <1 |
| Tin-Dissolved | µg/L | <1 |
| Titanium-Dissolved | µg/L | 1 |
| Vanadium-Dissolved | µg/L | <1 |
| Zinc-Dissolved | µg/L | 260 |

| Ion Balance | | |
|---|---|---|
| Our Reference | | 14401-1 |
| Your Reference | UNITS | SPLIT/03/08/18 |
| Date Sampled | | 03/08/2018 |
| Type of sample | | Water |
| Date prepared | - | 09/08/2018 |
| Date analysed | - | 09/08/2018 |
| Calcium - Dissolved | mg/L | 0.8 |
| Potassium - Dissolved | mg/L | 0.9 |
| Sodium - Dissolved | mg/L | 110 |
| Magnesium - Dissolved | mg/L | 4.5 |
| Hydroxide Alkalinity ($OH^-$) as $CaCO_3$ | mg/L | <5 |
| Bicarbonate Alkalinity as $CaCO_3$ | mg/L | <5 |
| Carbonate Alkalinity as $CaCO_3$ | mg/L | <5 |
| Total Alkalinity as $CaCO_3$ | mg/L | <5 |
| Sulphate, SO4 | mg/L | 150 |
| Chloride, Cl | mg/L | 110 |
| Hardness | mgCaCO 3 /L | 21 |
| Ionic Balance | % | -8.1 |

| Miscellaneous Inorganics | | |
|---|---|---|
| Our Reference | | 14401-1 |
| Your Reference | UNITS | SPLIT/03/08/18 |
| Date Sampled | | 03/08/2018 |
| Type of sample | | Water |
| Date prepared | - | 07/08/2018 |
| Date analysed | - | 08/08/2018 |
| Ammonia as N in water | mg/L | 0.007 |
| Fluoride, F | mg/L | <0.1 |
| Total Dissolved Solids (grav) | mg/L | 370 |
| pH | pH Units | 4.2 |

| Method ID | Methodology Summary |
|---|---|
| **Inorg-001** | pH - Measured using pH meter and electrode in accordance with APHA latest edition, 4500-H+. Please note that the results for water analyses are indicative only as analysis outside of the APHA storage times. |
| **Inorg-006** | Alkalinity - determined titrimetrically in accordance with APHA latest edition, 2320-B. |
| **Inorg-018** | Total Dissolved Solids - determined gravimetrically. The solids are dried at 180+/-10oC. |
| **Inorg-026** | Fluoride determined by ion selective electrode (ISE) in accordance with APHA latest edition, 4500-F-C. |
| **Inorg-040** | The concentrations of the major ions (mg/L) are converted to milliequivalents and summed. The ionic balance should be within +/- 10% ie total anions = total cations +/-10%. |
| **Inorg-057** | Ammonia - determined colourimetrically based on EPA350.1 and APHA latest edition 4500-NH3 F, Soils are analysed following a KCl extraction. |
| **Inorg-081** | Anions - a range of Anions are determined by Ion Chromatography, in accordance with APHA 22nd ED, 4110-B. Alternatively determined by colourimetry/turbidity using Discrete Analyer. |
| **Metals-020 ICP-AES** | Determination of various metals by ICP-AES. |
| **Metals-021 CV-AAS** | Determination of Mercury by Cold Vapour AAS. |
| **Metals-022 ICP-MS** | Determination of various metals by ICP-MS. |
| **Org-003** | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-FID.<br><br>F2 = (>C10-C16)-Naphthalene as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater (HSLs Tables 1A (3, 4)). Note Naphthalene is determined from the VOC analysis.<br><br>Note, the Total +ve TRH PQL is reflective of the lowest individual PQL and is therefore "Total +ve TRH" is simply a sum of the positive individual TRH fractions (>C10-C40). |
| **Org-005** | Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC with dual ECD's. |
| **Org-006** | Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC-ECD. |
| **Org-012** | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS. |
| **Org-012** | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS. Benzo(a)pyrene TEQ as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater 2013. |
| **Org-013** | Water samples are analysed directly by purge and trap GC-MS. |
| **Org-016** | Soil samples are extracted with methanol and spiked into water prior to analysing by purge and trap GC-MS. Water samples are analysed directly by purge and trap GC-MS. F1 = (C6-C10)-BTEX as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater.<br>Note, the Total +ve Xylene PQL is reflective of the lowest individual PQL and is therefore "Total +ve Xylenes" is simply a sum of the positive individual Xylenes. |

| QUALITY CONTROL: VOCs in water | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-1 | [NT] |
| Date extracted | - | | | 08/08/2018 | [NT] | [NT] | [NT] | [NT] | 08/08/2018 | [NT] |
| Date analysed | - | | | 08/08/2018 | [NT] | [NT] | [NT] | [NT] | 08/08/2018 | [NT] |
| Dichlorodifluoromethane | µg/L | 10 | Org-013 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Chloromethane | µg/L | 10 | Org-013 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Vinyl Chloride | µg/L | 10 | Org-013 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Bromomethane | µg/L | 10 | Org-013 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Chloroethane | µg/L | 10 | Org-013 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Trichlorofluoromethane | µg/L | 10 | Org-013 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,1-Dichloroethene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Trans-1,2-dichloroethene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,1-dichloroethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 85 | [NT] |
| Cis-1,2-dichloroethene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Bromochloromethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Chloroform | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 90 | [NT] |
| 2,2-dichloropropane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2-dichloroethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 98 | [NT] |
| 1,1,1-trichloroethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 90 | [NT] |
| 1,1-dichloropropene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Cyclohexane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Carbon tetrachloride | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Dibromomethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2-dichloropropane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Trichloroethene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 99 | [NT] |
| Bromodichloromethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 93 | [NT] |
| trans-1,3-dichloropropene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| cis-1,3-dichloropropene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,1,2-trichloroethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Toluene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,3-dichloropropane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Dibromochloromethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 93 | [NT] |
| 1,2-dibromoethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Tetrachloroethene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 91 | [NT] |
| 1,1,1,2-tetrachloroethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Chlorobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Ethylbenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Bromoform | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| m+p-xylene | µg/L | 2 | Org-013 | <2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Styrene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,1,2,2-tetrachloroethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| o-xylene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |

| QUALITY CONTROL: VOCs in water | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-1 | [NT] |
| 1,2,3-trichloropropane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Isopropylbenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Bromobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| n-propyl benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 2-chlorotoluene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 4-chlorotoluene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,3,5-trimethyl benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Tert-butyl benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2,4-trimethyl benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,3-dichlorobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Sec-butyl benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,4-dichlorobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 4-isopropyl toluene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2-dichlorobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| n-butyl benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2-dibromo-3-chloropropane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2,4-trichlorobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Hexachlorobutadiene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2,3-trichlorobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| *Surrogate* Dibromofluoromethane | % | | Org-013 | 107 | [NT] | [NT] | [NT] | [NT] | 93 | [NT] |
| *Surrogate* toluene-d8 | % | | Org-013 | 92 | [NT] | [NT] | [NT] | [NT] | 102 | [NT] |
| *Surrogate* 4-BFB | % | | Org-013 | 99 | [NT] | [NT] | [NT] | [NT] | 99 | [NT] |

| QUALITY CONTROL: vTRH(C6-C10)/BTEXN in Water | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-1 | [NT] |
| Date extracted | - | | | 08/08/2018 | [NT] | [NT] | [NT] | [NT] | 08/08/2018 | [NT] |
| Date analysed | - | | | 08/08/2018 | [NT] | [NT] | [NT] | [NT] | 08/08/2018 | [NT] |
| TRH $C_6$ - $C_9$ | µg/L | 10 | Org-016 | <10 | [NT] | [NT] | [NT] | [NT] | 105 | [NT] |
| TRH $C_6$ - $C_{10}$ | µg/L | 10 | Org-016 | <10 | [NT] | [NT] | [NT] | [NT] | 105 | [NT] |
| Benzene | µg/L | 1 | Org-016 | <1 | [NT] | [NT] | [NT] | [NT] | 115 | [NT] |
| Toluene | µg/L | 1 | Org-016 | <1 | [NT] | [NT] | [NT] | [NT] | 108 | [NT] |
| Ethylbenzene | µg/L | 1 | Org-016 | <1 | [NT] | [NT] | [NT] | [NT] | 96 | [NT] |
| m+p-xylene | µg/L | 2 | Org-016 | <2 | [NT] | [NT] | [NT] | [NT] | 102 | [NT] |
| o-xylene | µg/L | 1 | Org-016 | <1 | [NT] | [NT] | [NT] | [NT] | 101 | [NT] |
| Naphthalene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 118 | [NT] |
| *Surrogate* Dibromofluoromethane | % | | Org-016 | 121 | [NT] | [NT] | [NT] | [NT] | 107 | [NT] |
| *Surrogate* toluene-d8 | % | | Org-016 | 98 | [NT] | [NT] | [NT] | [NT] | 102 | [NT] |
| *Surrogate* 4-BFB | % | | Org-016 | 101 | [NT] | [NT] | [NT] | [NT] | 106 | [NT] |

| QUALITY CONTROL: TRH Water(C10-C40) NEPM | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-1 | [NT] |
| Date extracted | - | | | 08/08/2018 | [NT] | [NT] | [NT] | [NT] | 09/08/2018 | [NT] |
| Date analysed | - | | | 08/08/2018 | [NT] | [NT] | [NT] | [NT] | 09/08/2018 | [NT] |
| TRH $C_{10}$ - $C_{14}$ | µg/L | 50 | Org-003 | <50 | [NT] | [NT] | [NT] | [NT] | 84 | [NT] |
| TRH $C_{15}$ - $C_{28}$ | µg/L | 100 | Org-003 | <100 | [NT] | [NT] | [NT] | [NT] | 95 | [NT] |
| TRH $C_{29}$ - $C_{36}$ | µg/L | 100 | Org-003 | <100 | [NT] | [NT] | [NT] | [NT] | 107 | [NT] |
| TRH >$C_{10}$ - $C_{16}$ | µg/L | 50 | Org-003 | <50 | [NT] | [NT] | [NT] | [NT] | 84 | [NT] |
| TRH >$C_{16}$ - $C_{34}$ | µg/L | 100 | Org-003 | <100 | [NT] | [NT] | [NT] | [NT] | 95 | [NT] |
| TRH >$C_{34}$ - $C_{40}$ | µg/L | 100 | Org-003 | <100 | [NT] | [NT] | [NT] | [NT] | 107 | [NT] |
| *Surrogate* o-Terphenyl | % | | Org-003 | 102 | [NT] | [NT] | [NT] | [NT] | 89 | [NT] |

| QUALITY CONTROL: PAHs in Water | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-1 | [NT] |
| Date extracted | - | | | 08/08/2018 | [NT] | [NT] | [NT] | [NT] | 08/08/2018 | [NT] |
| Date analysed | - | | | 08/08/2018 | [NT] | [NT] | [NT] | [NT] | 08/08/2018 | [NT] |
| Naphthalene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | 84 | [NT] |
| Acenaphthylene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | 88 | [NT] |
| Acenaphthene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Fluorene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | 88 | [NT] |
| Phenanthrene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | 100 | [NT] |
| Anthracene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Fluoranthene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | 88 | [NT] |
| Pyrene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | 96 | [NT] |
| Benzo(a)anthracene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Chrysene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | 100 | [NT] |
| Benzo(b,j&k)fluoranthene | µg/L | 2 | Org-012 | <2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Benzo(a)pyrene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | 92 | [NT] |
| Indeno(1,2,3-c,d)pyrene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Dibenzo(a,h)anthracene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Benzo(g,h,i)perylene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | | Org-012 | 108 | [NT] | [NT] | [NT] | [NT] | 104 | [NT] |

| QUALITY CONTROL: Phthalates in water | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-1 | [NT] |
| Date extracted | - | | | 08/08/2018 | [NT] | [NT] | [NT] | [NT] | 08/08/2018 | [NT] |
| Date analysed | - | | | 14/08/2018 | [NT] | [NT] | [NT] | [NT] | 14/08/2018 | [NT] |
| Dimethyl phthalate | µg/L | 10 | Org-012 | <10 | [NT] | [NT] | [NT] | [NT] | 107 | [NT] |
| Diethylphthalate | µg/L | 10 | Org-012 | <10 | [NT] | [NT] | [NT] | [NT] | 115 | [NT] |
| Di-n-butylphthalate | µg/L | 50 | Org-012 | <50 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Butylbenzylphthalate | µg/L | 10 | Org-012 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Bis(2-ethylhexyl) phthalate | µg/L | 50 | Org-012 | <50 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Di-n-octylphthalate | µg/L | 10 | Org-012 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | | Org-012 | 96 | [NT] | [NT] | [NT] | [NT] | 92 | [NT] |

| QUALITY CONTROL: OCP in water | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-1 | [NT] |
| Date extracted | - | | | 08/08/2018 | [NT] | [NT] | [NT] | [NT] | 08/08/2018 | [NT] |
| Date analysed | - | | | 14/08/2018 | [NT] | [NT] | [NT] | [NT] | 14/08/2018 | [NT] |
| HCB | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| alpha-BHC | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 76 | [NT] |
| gamma-BHC | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| beta-BHC | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 84 | [NT] |
| Heptachlor | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 100 | [NT] |
| delta-BHC | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Aldrin | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 112 | [NT] |
| Heptachlor Epoxide | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 68 | [NT] |
| gamma-Chlordane | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 72 | [NT] |
| alpha-Chlordane | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Endosulfan I | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| pp-DDE | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 84 | [NT] |
| Dieldrin | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 72 | [NT] |
| Endrin | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| pp-DDD | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 88 | [NT] |
| Endosulfan II | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| pp-DDT | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Endrin Aldehyde | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Endosulfan Sulphate | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 88 | [NT] |
| Methoxychlor | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| *Surrogate p*-Terphenyl | % | | Org-005 | 96 | [NT] | [NT] | [NT] | [NT] | 92 | [NT] |

| QUALITY CONTROL: PCBs in Water | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-1 | [NT] |
| Date extracted | - | | | 08/08/2018 | [NT] | [NT] | [NT] | [NT] | 08/08/2018 | [NT] |
| Date analysed | - | | | 14/08/2018 | [NT] | [NT] | [NT] | [NT] | 14/08/2018 | [NT] |
| Aroclor 1016 | µg/L | 2 | Org-006 | <2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Aroclor 1221 | µg/L | 2 | Org-006 | <2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Aroclor 1232 | µg/L | 2 | Org-006 | <2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Aroclor 1242 | µg/L | 2 | Org-006 | <2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Aroclor 1248 | µg/L | 2 | Org-006 | <2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Aroclor 1254 | µg/L | 2 | Org-006 | <2 | [NT] | [NT] | [NT] | [NT] | 65 | [NT] |
| Aroclor 1260 | µg/L | 2 | Org-006 | <2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| *Surrogate p*-Terphenyl | % | | Org-006 | 96 | [NT] | [NT] | [NT] | [NT] | 92 | [NT] |

| QUALITY CONTROL: All metals in water-dissolved | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-1 | [NT] |
| Date prepared | - | | | 08/08/2018 | [NT] | [NT] | [NT] | [NT] | 08/08/2018 | [NT] |
| Date analysed | - | | | 08/08/2018 | [NT] | [NT] | [NT] | [NT] | 08/08/2018 | [NT] |
| Aluminium-Dissolved | µg/L | 10 | Metals-022 ICP-MS | <10 | [NT] | [NT] | [NT] | [NT] | 119 | [NT] |
| Silver-Dissolved | µg/L | 1 | Metals-022 ICP-MS | <1 | [NT] | [NT] | [NT] | [NT] | 96 | [NT] |
| Arsenic-Dissolved | µg/L | 1 | Metals-022 ICP-MS | <1 | [NT] | [NT] | [NT] | [NT] | 111 | [NT] |
| Boron-Dissolved | µg/L | 20 | Metals-022 ICP-MS | <20 | [NT] | [NT] | [NT] | [NT] | 122 | [NT] |
| Barium-Dissolved | µg/L | 1 | Metals-022 ICP-MS | <1 | [NT] | [NT] | [NT] | [NT] | 114 | [NT] |
| Beryllium-Dissolved | µg/L | 0.5 | Metals-022 ICP-MS | <0.5 | [NT] | [NT] | [NT] | [NT] | 112 | [NT] |
| Cadmium-Dissolved | µg/L | 0.1 | Metals-022 ICP-MS | <0.1 | [NT] | [NT] | [NT] | [NT] | 106 | [NT] |
| Chromium-Dissolved | µg/L | 1 | Metals-022 ICP-MS | <1 | [NT] | [NT] | [NT] | [NT] | 109 | [NT] |
| Cobalt-Dissolved | µg/L | 1 | Metals-022 ICP-MS | <1 | [NT] | [NT] | [NT] | [NT] | 104 | [NT] |
| Copper-Dissolved | µg/L | 1 | Metals-022 ICP-MS | <1 | [NT] | [NT] | [NT] | [NT] | 106 | [NT] |
| Iron-Dissolved | µg/L | 10 | Metals-022 ICP-MS | <10 | [NT] | [NT] | [NT] | [NT] | 112 | [NT] |
| Lead-Dissolved | µg/L | 1 | Metals-022 ICP-MS | <1 | [NT] | [NT] | [NT] | [NT] | 102 | [NT] |
| Manganese-Dissolved | µg/L | 5 | Metals-022 ICP-MS | <5 | [NT] | [NT] | [NT] | [NT] | 111 | [NT] |
| Mercury-Dissolved | µg/L | 0.05 | Metals-021 CV-AAS | <0.05 | [NT] | [NT] | [NT] | [NT] | 103 | [NT] |
| Molybdenum-Dissolved | µg/L | 1 | Metals-022 ICP-MS | <1 | [NT] | [NT] | [NT] | [NT] | 109 | [NT] |
| Nickel-Dissolved | µg/L | 1 | Metals-022 ICP-MS | <1 | [NT] | [NT] | [NT] | [NT] | 106 | [NT] |
| Selenium-Dissolved | µg/L | 1 | Metals-022 ICP-MS | <1 | [NT] | [NT] | [NT] | [NT] | 101 | [NT] |
| Antimony-Dissolved | µg/L | 1 | Metals-022 ICP-MS | <1 | [NT] | [NT] | [NT] | [NT] | 125 | [NT] |
| Tin-Dissolved | µg/L | 1 | Metals-022 ICP-MS | <1 | [NT] | [NT] | [NT] | [NT] | 104 | [NT] |
| Titanium-Dissolved | µg/L | 1 | Metals-022 ICP-MS | <1 | [NT] | [NT] | [NT] | [NT] | 115 | [NT] |

| QUALITY CONTROL: All metals in water-dissolved | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-1 | [NT] |
| Vanadium-Dissolved | µg/L | 1 | Metals-022 ICP-MS | <1 | [NT] | [NT] | [NT] | [NT] | 110 | [NT] |
| Zinc-Dissolved | µg/L | 1 | Metals-022 ICP-MS | <1 | [NT] | [NT] | [NT] | [NT] | 117 | [NT] |

| QUALITY CONTROL: Ion Balance | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-1 | [NT] |
| Date prepared | - | | | 09/08/2018 | [NT] | [NT] | [NT] | [NT] | 09/08/2018 | [NT] |
| Date analysed | - | | | 09/08/2018 | [NT] | [NT] | [NT] | [NT] | 09/08/2018 | [NT] |
| Calcium - Dissolved | mg/L | 0.5 | Metals-020 ICP-AES | <0.5 | [NT] | [NT] | [NT] | [NT] | 98 | [NT] |
| Potassium - Dissolved | mg/L | 0.5 | Metals-020 ICP-AES | <0.5 | [NT] | [NT] | [NT] | [NT] | 98 | [NT] |
| Sodium - Dissolved | mg/L | 0.5 | Metals-020 ICP-AES | <0.5 | [NT] | [NT] | [NT] | [NT] | 96 | [NT] |
| Magnesium - Dissolved | mg/L | 0.5 | Metals-020 ICP-AES | <0.5 | [NT] | [NT] | [NT] | [NT] | 98 | [NT] |
| Hydroxide Alkalinity ($OH^-$) as $CaCO_3$ | mg/L | 5 | Inorg-006 | <5 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Bicarbonate Alkalinity as $CaCO_3$ | mg/L | 5 | Inorg-006 | <5 | [NT] | [NT] | [NT] | [NT] | 118 | [NT] |
| Carbonate Alkalinity as $CaCO_3$ | mg/L | 5 | Inorg-006 | <5 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Total Alkalinity as $CaCO_3$ | mg/L | 5 | Inorg-006 | <5 | [NT] | [NT] | [NT] | [NT] | 118 | [NT] |
| Sulphate, SO4 | mg/L | 1 | Inorg-081 | <1 | [NT] | [NT] | [NT] | [NT] | 123 | [NT] |
| Chloride, Cl | mg/L | 1 | Inorg-081 | <1 | [NT] | [NT] | [NT] | [NT] | 123 | [NT] |
| Hardness | mgCaCO 3 /L | 3 | | <3 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |

| QUALITY CONTROL: Miscellaneous Inorganics | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-1 | [NT] |
| Date prepared | - | | | 07/08/2018 | [NT] | [NT] | [NT] | [NT] | 07/08/2018 | [NT] |
| Date analysed | - | | | 08/08/2018 | [NT] | [NT] | [NT] | [NT] | 08/08/2018 | [NT] |
| Ammonia as N in water | mg/L | 0.005 | Inorg-057 | <0.005 | [NT] | [NT] | [NT] | [NT] | 101 | [NT] |
| Fluoride, F | mg/L | 0.1 | Inorg-026 | <0.1 | [NT] | [NT] | [NT] | [NT] | 92 | [NT] |
| Total Dissolved Solids (grav) | mg/L | 5 | Inorg-018 | <5 | [NT] | [NT] | [NT] | [NT] | 94 | [NT] |
| pH | pH Units | | Inorg-001 | [NT] | [NT] | [NT] | [NT] | [NT] | 99 | [NT] |

## Result Definitions

| | |
|---|---|
| **NT** | Not tested |
| **NA** | Test not required |
| **INS** | Insufficient sample for this test |
| **PQL** | Practical Quantitation Limit |
| **<** | Less than |
| **>** | Greater than |
| **RPD** | Relative Percent Difference |
| **LCS** | Laboratory Control Sample |
| **NS** | Not specified |
| **NEPM** | National Environmental Protection Measure |
| **NR** | Not Reported |

## Quality Control Definitions

| | |
|---|---|
| **Blank** | This is the component of the analytical signal which is not derived from the sample but from reagents, glassware etc, can be determined by processing solvents and reagents in exactly the same manner as for samples. |
| **Duplicate** | This is the complete duplicate analysis of a sample from the process batch. If possible, the sample selected should be one where the analyte concentration is easily measurable. |
| **Matrix Spike** | A portion of the sample is spiked with a known concentration of target analyte. The purpose of the matrix spike is to monitor the performance of the analytical method used and to determine whether matrix interferences exist. |
| **LCS (Laboratory Control Sample)** | This comprises either a standard reference material or a control matrix (such as a blank sand or water) fortified with analytes representative of the analyte class. It is simply a check sample. |
| **Surrogate Spike** | Surrogates are known additions to each sample, blank, matrix spike and LCS in a batch, of compounds which are similar to the analyte of interest, however are not expected to be found in real samples. |

Australian Drinking Water Guidelines recommend that Thermotolerant Coliform, Faecal Enterococci, & E.Coli levels are less than 1cfu/100mL. The recommended maximums are taken from "Australian Drinking Water Guidelines", published by NHMRC & ARMC 2011.

## Laboratory Acceptance Criteria

Duplicate sample and matrix spike recoveries may not be reported on smaller jobs, however, were analysed at a frequency to meet or exceed NEPM requirements. All samples are tested in batches of 20. The duplicate sample RPD and matrix spike recoveries for the batch were within the laboratory acceptance criteria.

Filters, swabs, wipes, tubes and badges will not have duplicate data as the whole sample is generally extracted during sample extraction.

Spikes for Physical and Aggregate Tests are not applicable.

For VOCs in water samples, three vials are required for duplicate or spike analysis.

Duplicates: <5xPQL - any RPD is acceptable; >5xPQL - 0-50% RPD is acceptable.

Matrix Spikes, LCS and Surrogate recoveries: Generally 70-130% for inorganics/metals; 60-140% for organics (+/-50% surrogates) and 10-140% for labile SVOCs (including labile surrogates), ultra trace organics and speciated phenols is acceptable.

In circumstances where no duplicate and/or sample spike has been reported at 1 in 10 and/or 1 in 20 samples respectively, the sample volume submitted was insufficient in order to satisfy laboratory QA/QC protocols.

When samples are received where certain analytes are outside of recommended technical holding times (THTs), the analysis has proceeded. Where analytes are on the verge of breaching THTs, every effort will be made to analyse within the THT or as soon as practicable.

Where sampling dates are not provided, Envirolab are not in a position to comment on the validity of the analysis where recommended technical holding times may have been breached.

Measurement Uncertainty estimates are available for most tests upon request.

P.O. Box 1237
Carlton VIC 3053
enquiries@lrmglobal.com.au

# CHAIN OF CUSTODY

**Job Number:** 27380

**ATTENTION**

**CLIENT**

**CLIENT NUMBER**

**LOCATION** 266 Longueville Road Lane Cove

Sheet 1 of

**Additional information::**

| Email Results To | Tick |
|---|---|
| jon.lawson@lrmglobal.com.au | Yep |
| kevin.b@lrmglobal.com.au | |
| ajacob@lrmglobal.com.au | |
| acampbell@lrmglobal.com.au | |
| l.main@lrmglobal.com.au | |

Chain of custody must be signed and dated by LRM, courier, and laboratory.

**Total number of containers** 74

Sampled by: JL

Checked by: JL

**Comments**

| RELINQUISHED BY (Signature) | ORGANISATION | DATE / TIME | RECEIVED BY (Signature) | ORGANISATION | DATE / TIME |
|---|---|---|---|---|---|
| | LRM | 10/07/2017 | | | |

| Sample Number | Sample Date | Sample Type | Analysis Required | No. of Containers | Turn-around Time Required |
|---|---|---|---|---|---|
| BH16 - 0.1 1 | 1 6/07/2017 | Soil | Metals, PAH, TRH | 1 | 5 day |
| BH16 - 0.8 2 | 2 6/07/2017 | Soil | Metals, PAH, TRH | 1 | 5 day |
| BH17 - 0.1 3 | 3 6/07/2017 | Soil | Metals, PAH, TRH | 1 | 5 day |
| BH17 - 0.7 4 | 4 6/07/2017 | Soil | Metals, PAH, TRH | 1 | 5 day |
| BH18 - 0.1 5 | 5 6/07/2017 | Soil | Metals, OCP/OPP, pH | 1 | 5 day |
| BH18 - 0.6 6 | 6 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH19 - 0.1 7 | 7 6/07/2017 | Soil | Metals, OCP/OPP, pH | 1 | 5 day |
| * BH19 - 0.5 66 | 66 6/07/2017 | Soil | NEPM Suite Basic | 1 | 5 day |
| BH20 - 0.1 8 | 8 6/07/2017 | Soil | Metals, OCP/OPP, pH | 1 | 5 day |
| BH20 - 1.0 9 | 9 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH20 - 1.9 10 | 10 6/07/2017 | Soil | Metals, PAH, PCB | 1 | 5 day |
| BH21 - 0.1 11 | 11 6/07/2017 | Soil | Metals, OCP/OPP | 1 | 5 day |
| BH21 - 1.2 12 | 12 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH21 - 3.0 13 | 13 6/07/2017 | Soil | Metals, TRH, PCB | 1 | 5 day |
| * BH21 - 4.0 67 | 67 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH22 - 0.1 14 | 14 6/07/2017 | Soil | Metals, OCP, OPP, pH | 1 | 5 day |
| BH22 - 1.0 15 | 15 6/07/2017 | Soil | Metals, TRH | 1 | 5 day |
| BH23 - 0.1 16 | 16 6/07/2017 | Soil | Metals, OCP, OPP | 1 | 5 day |
| BH23 - 1.0 17 | 17 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |

ENVIROLAB

Envirolab Services
12 Ashley St
Chatswood NSW 2067
Ph: (02) 9910 6200

Job No: 170939

Date Received: 7/7/2017

Time Received: 10.00

Received by: AR

Temp: Cool/Ambient 10.5

Cooling: Ice/Icepack

Security: Intact/Broken/None

P.O. Box 1237
Carlton VIC 3053
enquiries@lrmglobal.com.au

# CHAIN OF CUSTODY

**Job Number:** 27380

Sheet 1 of

**ATTENTION**

**CLIENT**

**CLIENT NUMBER**

**LOCATION** 266 Longueville Road Lane Cove

**Additional information::**

| Email Results To | Tick |
|---|---|
| jon.lawson@lrmglobal.com.au | Yep |
| kevin.b@lrmglobal.com.au | |
| ajacob@lrmglobal.com.au | |
| acampbell@lrmglobal.com.au | |
| l.main@lrmglobal.com.au | |

Chain of custody must be signed and dated by LRM, courier, and laboratory.

**Total number of containers** 74

Sampled by: JL

Checked by: JL

**Comments**

| RELINQUISHED BY (Signature) | ORGANISATION | DATE / TIME | RECEIVED BY (Signature) | ORGANISATION | DATE / TIME |
|---|---|---|---|---|---|
| | LRM | 10/07/2017 | | | |

| Sample Number | Sample Date | Sample Type | Analysis Required | No. of Containers | Turn-around Time Required |
|---|---|---|---|---|---|
| BH24 - 0.1 18 | 18 6/07/2017 | Soil | Metals, OCP, OPP, pH, TRH | 1 | 5 day |
| BH24 - 1.5 19 | 19 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH24 - 2.8 20 | 20 6/07/2017 | Soil | Metals, TRH, PCB | 1 | 5 day |
| BH25 - 0.2 21 | 21 6/07/2017 | Soil | Metals. OCP, OPP | 1 | 5 day |
| BH26 - 0.2 22 | 22 6/07/2017 | Soil | Metals, OCP, OPP | 1 | 5 day |
| BH27 - 0.1 23 | 23 6/07/2017 | Soil | Metals, OCP, OPP, pH | 1 | 5 day |
| BH27 - 1.0 24 | 24 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH28 - 0.1 25 | 25 6/07/2017 | Soil | Metals, OCP, OPP | 1 | 5 day |
| BH28 - 2.0 26 | 26 6/07/2017 | Soil | Metals | 1 | 5 day |
| BH28 - 3.0 27 | 27 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH28 - 4.0 28 | 28 6/07/2017 | Soil | Metals, PCB, TRH | 1 | 5 day |
| BH29 - 0.1 29 | 29 6/07/2017 | Soil | Metals, OCP, OPP, pH | 1 | 5 day |
| BH29 - 1.0 30 | 30 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH29 - 2.0 31 | 31 6/07/2017 | Soil | Metals | 1 | 5 day |
| BH29 - 3.0 32 | 32 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH29 - 4.0 33 | 33 6/07/2017 | Soil | Metals, PCB | 1 | 5 day |
| BH29 - 5.0 34 | 34 6/07/2017 | Soil | Metals | 1 | 5 day |
| * BH29 - 6.0 ] 63 | 63 6/07/2017 | Soil | Metals, PAH | | |
| * BH29 - 7.0 ] 65 | 65 6/07/2017 | Soil | Metals | 1 | 5 day |

170939

P.O. Box 1237
Carlton VIC 3053
enquiries@lrmglobal.com.au

# CHAIN OF CUSTODY

**Job Number:** 27380

**ATTENTION**

**CLIENT**

**CLIENT NUMBER**

**LOCATION** 266 Longueville Road Lane Cove

Sheet 1 of

**Additional information::**

| Email Results To | Tick |
|---|---|
| jon.lawson@lrmglobal.com.au | Yep |
| kevin.b@lrmglobal.com.au | |
| ajacob@lrmglobal.com.au | |
| acampbell@lrmglobal.com.au | |
| l.main@lrmglobal.com.au | |

Chain of custody must be signed and dated by LRM, courier, and laboratory.

**Total number of containers** 74

Sampled by: JL

Checked by: JL

**Comments**

| RELINQUISHED BY (Signature) | ORGANISATION | DATE / TIME | RECEIVED BY (Signature) | ORGANISATION | DATE / TIME |
|---|---|---|---|---|---|
| | LRM | 10/07/2017 | | | |

| Sample Number | Sample Date | Sample Type | Analysis Required | No. of Containers | Turn-around Time Required |
|---|---|---|---|---|---|
| * BH29 - 8.0 - 64 | 64 6/07/2017 | Soil | Metals, TRH | | |
| BH30 - 0.1 35 | 35 6/07/2017 | Soil | Metals, OCP, OPP | 1 | 5 day |
| BH30 - 1.0 36 | 36 6/07/2017 | Soil | NEPM Suite Basic | 1 | 5 day |
| BH30 - 2.0 37 | 37 6/07/2017 | Soil | Metals | 1 | 5 day |
| BH30 - 3.0 38 | 38 6/07/2017 | Soil | Metals, TRH | 1 | 5 day |
| BH30 - 4.0 39 | 39 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH30 - 5.0 40 | 40 6/07/2017 | Soil | Metals | 1 | 5 day |
| BH30 - 6.0 41 | 41 6/07/2017 | Soil | Metals, PCB | 1 | 5 day |
| BH30 - 7.0 42 | 42 6/07/2017 | Soil | Metals, TRH | 1 | 5 day |
| BH31 - 0.1 43 | 43 6/07/2017 | Soil | Metals, OCP, OPP | 1 | 5 day |
| * BH31 - 1.0 - 71 | 71 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH32 - 0.1 44 | 44 6/07/2017 | Soil | Metals, OCP, OPP, pH | 1 | 5 day |
| BH32 - 1.0 45 | 45 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH32 - 2.2 46 | 46 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH32 - 3.0 47 | 47 6/07/2017 | Soil | Metals | 1 | 5 day |
| BH32 - 4.0 48 | 48 6/07/2017 | Soil | Metals, TRH | 1 | 5 day |
| BH33 - 0.2 49 | 49 6/07/2017 | Soil | Metals, OCP. OPP | 1 | 5 day |
| BH33 - 1.0 50 | 50 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH34 - 0.1 51 | 51 6/07/2017 | Soil | NEPM Suite Basic | 1 | 5 day |

ID2939

P.O. Box 1237
Carlton VIC 3053
enquiries@lrmglobal.com.au

# CHAIN OF CUSTODY

**Job Number:** 27380

**ATTENTION**

**CLIENT**

**CLIENT NUMBER**

**LOCATION** 266 Longueville Road Lane Cove

Sheet 1 of

**Additional information::**

| Email Results To | Tick |
|---|---|
| jon.lawson@lrmglobal.com.au | Yep |
| kevin.b@lrmglobal.com.au | |
| ajacob@lrmglobal.com.au | |
| acampbell@lrmglobal.com.au | |
| l.main@lrmglobal.com.au | |

Chain of custody must be signed and dated by LRM, courier, and laboratory.

**Total number of containers** 74

Sampled by: JL

Checked by: JL

**Comments**

| RELINQUISHED BY (Signature) | ORGANISATION | DATE / TIME | RECEIVED BY (Signature) | ORGANISATION | DATE / TIME |
|---|---|---|---|---|---|
| | LRM | 10/07/2017 | | | |

| Sample Number | Sample Date | Sample Type | Analysis Required | No. of Containers | Turn-around Time Required |
|---|---|---|---|---|---|
| BH35 - 0.1 52 | 52 6/07/2017 | Soil | Metals, | 1 | 5 day |
| BH36 - 0.1 53 | 53 6/07/2017 | Soil | Metals | 1 | 5 day |
| BH37 - 0.1 54 | 54 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH38 - 0.1 55 | 55 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH39 - 0.1 56 | 56 6/07/2017 | Soil | Metals, TRH | 1 | 5 day |
| BH40 - 0.1 68 | 68 6/07/2017 | Soil | Metals | 1 | 5 day |
| BH41 - 0.1 69 | 69 6/07/2017 | Soil | Metals | 1 | 5 day |
| BH42 - 0.1 70 | 70 6/07/2017 | Soil | Metals, OCP, OPP | 1 | 5 day |
| Dup 1 57 | 57 6/07/2017 | Soil | NEPM Suite Basic | 1 | 5 day |
| Dup 2 58 | 58 6/07/2017 | Soil | Metals | 1 | 5 day |
| Dup 3 59 | 59 6/07/2017 | Soil | Metals | 1 | 5 day |
| Dup 4 60 | 60 6/07/2017 | Soil | Metals | 1 | 5 day |
| Split 1 | - 6/07/2017 | Soil | NEPM Suite Basic | 1 | 5 day |
| Split 2 MELB | - 6/07/2017 | Soil | Metals | 1 | 5 day |
| Split 3 | - 6/07/2017 | Soil | Metals | 1 | 5 day |
| Split 4 | - 6/07/2017 | Soil | Metals | 1 | 5 day |
| Trip 61 | 61 6/07/2017 | Water | C6-9 | 2 | 5 day |
| Rinsate 62 | 62 6/07/2017 | Water | Metals | 1 | 5 day |

170939

12 Ashley Street, Chatswood, NSW 2067
tel: +61 2 9910 6200

email: sydney@envirolab.com.au
envirolab.com.au

Envirolab Services Pty Ltd - Sydney | ABN 37 112 535 645

# CERTIFICATE OF ANALYSIS 170939

**Client:**
**LRM Global**
PO Box 1237
Carlton
VIC 3053

**Attention:** Jon Lawson

**Sample log in details:**

| | |
|---|---|
| Your Reference: | **27380, Lane Cove** |
| No. of samples: | 69 Soils, 2 Waters |
| Date samples received / completed instructions received | 07/07/17 / 10/07/17 |

**Analysis Details:**
Please refer to the following pages for results, methodology summary and quality control data.
Samples were analysed as received from the client. Results relate specifically to the samples as received.
Results are reported on a dry weight basis for solids and on an as received basis for other matrices.
***Please refer to the last page of this report for any comments relating to the results.***

**Report Details:**

| | |
|---|---|
| Date results requested by: / Issue Date: | 18/07/17 / 18/07/17 |
| Date of Preliminary Report: | Not Issued |

NATA accreditation number 2901. This document shall not be reproduced except in full.
Accredited for compliance with ISO/IEC 17025 - Testing **Tests not covered by NATA are denoted with *.**

**Results Approved By:**

David Springer
General Manager

| vTRH(C6-C10)/BTEXN in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-1 | 170939-2 | 170939-3 | 170939-4 | 170939-13 |
| Your Reference | ---------- - | BH16 | BH16 | BH17 | BH17 | BH21 |
| Depth | ---------- | 0.1 | 0.8 | 0.1 | 0.7 | 3.0 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| TRHC$_6$ - C$_9$ | mg/kg | <25 | <25 | <25 | <25 | <25 |
| TRHC$_6$ - C$_{10}$ | mg/kg | <25 | <25 | <25 | <25 | <25 |
| *Surrogate* aaa-Trifluorotoluene | % | 98 | 97 | 96 | 88 | 95 |

| vTRH(C6-C10)/BTEXN in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-15 | 170939-18 | 170939-20 | 170939-28 | 170939-36 |
| Your Reference | ---------- - | BH22 | BH24 | BH24 | BH28 | BH30 |
| Depth | ---------- | 1.0 | 0.1 | 2.8 | 4.0 | 1.0 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| TRHC$_6$ - C$_9$ | mg/kg | <25 | <25 | <25 | <25 | <25 |
| TRHC$_6$ - C$_{10}$ | mg/kg | <25 | <25 | <25 | <25 | <25 |
| vTPHC$_6$ - C$_{10}$ less BTEX (F1) | mg/kg | [NA] | [NA] | [NA] | [NA] | <25 |
| Benzene | mg/kg | [NA] | [NA] | [NA] | [NA] | <0.2 |
| Toluene | mg/kg | [NA] | [NA] | [NA] | [NA] | <0.5 |
| Ethylbenzene | mg/kg | [NA] | [NA] | [NA] | [NA] | <1 |
| m+p-xylene | mg/kg | [NA] | [NA] | [NA] | [NA] | <2 |
| o-Xylene | mg/kg | [NA] | [NA] | [NA] | [NA] | <1 |
| Total +ve Xylenes | mg/kg | [NA] | [NA] | [NA] | [NA] | <1 |
| naphthalene | mg/kg | [NA] | [NA] | [NA] | [NA] | <1 |
| *Surrogate* aaa-Trifluorotoluene | % | 97 | 97 | 91 | 95 | 96 |

| vTRH(C6-C10)/BTEXN in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-38 | 170939-42 | 170939-48 | 170939-51 | 170939-56 |
| Your Reference | ---------- - | BH30 | BH30 | BH32 | BH34 | BH39 |
| Depth | ---------- | 3.0 | 7.0 | 4.0 | 0.1 | 0.1 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| TRHC$_6$ - C$_9$ | mg/kg | <25 | <25 | <25 | <25 | <25 |
| TRHC$_6$ - C$_{10}$ | mg/kg | <25 | <25 | <25 | <25 | <25 |
| vTPHC$_6$ - C$_{10}$ less BTEX (F1) | mg/kg | [NA] | [NA] | [NA] | <25 | [NA] |
| Benzene | mg/kg | [NA] | [NA] | [NA] | <0.2 | [NA] |
| Toluene | mg/kg | [NA] | [NA] | [NA] | <0.5 | [NA] |
| Ethylbenzene | mg/kg | [NA] | [NA] | [NA] | <1 | [NA] |
| m+p-xylene | mg/kg | [NA] | [NA] | [NA] | <2 | [NA] |
| o-Xylene | mg/kg | [NA] | [NA] | [NA] | <1 | [NA] |
| Total +ve Xylenes | mg/kg | [NA] | [NA] | [NA] | <1 | [NA] |
| naphthalene | mg/kg | [NA] | [NA] | [NA] | <1 | [NA] |
| *Surrogate* aaa-Trifluorotoluene | % | 90 | 83 | 103 | 91 | 89 |

| vTRH(C6-C10)/BTEXN in Soil | | | | |
|---|---|---|---|---|
| Our Reference: | UNITS | 170939-57 | 170939-64 | 170939-66 |
| Your Reference | ---------- - | Dup1 | BH29 | BH19 |
| Depth | ---------- | - | 8.0 | 0.5 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| TRHC$_6$ - C$_9$ | mg/kg | <25 | <25 | <25 |
| TRHC$_6$ - C$_{10}$ | mg/kg | <25 | <25 | <25 |
| vTPHC$_6$ - C$_{10}$ less BTEX (F1) | mg/kg | <25 | [NA] | <25 |
| Benzene | mg/kg | <0.2 | [NA] | <0.2 |
| Toluene | mg/kg | <0.5 | [NA] | <0.5 |
| Ethylbenzene | mg/kg | <1 | [NA] | <1 |
| m+p-xylene | mg/kg | <2 | [NA] | <2 |
| o-Xylene | mg/kg | <1 | [NA] | <1 |
| Total +ve Xylenes | mg/kg | <1 | [NA] | <1 |
| naphthalene | mg/kg | <1 | [NA] | <1 |
| *Surrogate* aaa-Trifluorotoluene | % | 101 | 91 | 102 |

| svTRH (C10-C40) in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-1 | 170939-2 | 170939-3 | 170939-4 | 170939-13 |
| Your Reference | ---------- - | BH16 | BH16 | BH17 | BH17 | BH21 |
| Depth | ---------- | 0.1 | 0.8 | 0.1 | 0.7 | 3.0 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| TRHC$_{10}$ - C$_{14}$ | mg/kg | <50 | <50 | <50 | <50 | <50 |
| TRHC$_{15}$ - C$_{28}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRHC$_{29}$ - C$_{36}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRH>C$_{10}$-C$_{16}$ | mg/kg | <50 | <50 | <50 | <50 | <50 |
| TRH>C$_{10}$ - C$_{16}$ less Naphthalene (F2) | mg/kg | <50 | <50 | <50 | <50 | <50 |
| TRH>C$_{16}$-C$_{34}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRH>C$_{34}$-C$_{40}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| Total +ve TRH (>C10-C40) | mg/kg | <50 | <50 | <50 | <50 | <50 |
| *Surrogate* o-Terphenyl | % | 110 | 91 | 92 | 91 | 100 |

| svTRH (C10-C40) in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-15 | 170939-18 | 170939-20 | 170939-28 | 170939-36 |
| Your Reference | ---------- - | BH22 | BH24 | BH24 | BH28 | BH30 |
| Depth | ---------- | 1.0 | 0.1 | 2.8 | 4.0 | 1.0 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| TRHC$_{10}$ - C$_{14}$ | mg/kg | <50 | <50 | <50 | <50 | <50 |
| TRHC$_{15}$ - C$_{28}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRHC$_{29}$ - C$_{36}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRH>C$_{10}$-C$_{16}$ | mg/kg | <50 | <50 | <50 | <50 | <50 |
| TRH>C$_{10}$ - C$_{16}$ less Naphthalene (F2) | mg/kg | <50 | <50 | <50 | <50 | <50 |
| TRH>C$_{16}$-C$_{34}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRH>C$_{34}$-C$_{40}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| Total +ve TRH (>C10-C40) | mg/kg | <50 | <50 | <50 | <50 | <50 |
| *Surrogate* o-Terphenyl | % | 89 | 89 | 89 | 91 | 89 |

| svTRH (C10-C40) in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-38 | 170939-42 | 170939-48 | 170939-51 | 170939-56 |
| Your Reference | ---------- - | BH30 | BH30 | BH32 | BH34 | BH39 |
| Depth | ---------- | 3.0 | 7.0 | 4.0 | 0.1 | 0.1 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| TRHC$_{10}$ - C$_{14}$ | mg/kg | <50 | <50 | <50 | <50 | <50 |
| TRHC$_{15}$ - C$_{28}$ | mg/kg | <100 | <100 | <100 | <100 | 360 |
| TRHC$_{29}$ - C$_{36}$ | mg/kg | <100 | <100 | <100 | <100 | 480 |
| TRH>C$_{10}$-C$_{16}$ | mg/kg | <50 | <50 | <50 | <50 | 68 |
| TRH>C$_{10}$ - C$_{16}$ less Naphthalene (F2) | mg/kg | <50 | <50 | <50 | <50 | [NT] |
| TRH>C$_{16}$-C$_{34}$ | mg/kg | <100 | <100 | <100 | <100 | 640 |
| TRH>C$_{34}$-C$_{40}$ | mg/kg | <100 | <100 | <100 | <100 | 370 |
| Total +ve TRH (>C10-C40) | mg/kg | <50 | <50 | <50 | <50 | 1,100 |
| *Surrogate* o-Terphenyl | % | 88 | 88 | 93 | 94 | 103 |

| svTRH (C10-C40) in Soil | | | | |
|---|---|---|---|---|
| Our Reference: | UNITS | 170939-57 | 170939-64 | 170939-66 |
| Your Reference | ---------- - | Dup1 | BH29 | BH19 |
| Depth | ---------- | - | 8.0 | 0.5 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| TRHC$_{10}$ - C$_{14}$ | mg/kg | <50 | <50 | <50 |
| TRHC$_{15}$ - C$_{28}$ | mg/kg | <100 | <100 | <100 |
| TRHC$_{29}$ - C$_{36}$ | mg/kg | <100 | <100 | <100 |
| TRH>C$_{10}$-C$_{16}$ | mg/kg | <50 | <50 | <50 |
| TRH>C$_{10}$ - C$_{16}$ less Naphthalene (F2) | mg/kg | <50 | <50 | <50 |
| TRH>C$_{16}$-C$_{34}$ | mg/kg | <100 | <100 | <100 |
| TRH>C$_{34}$-C$_{40}$ | mg/kg | <100 | <100 | <100 |
| Total +ve TRH (>C10-C40) | mg/kg | <50 | <50 | <50 |
| *Surrogate* o-Terphenyl | % | 91 | 106 | 91 |

| PAHs in Soil<br>Our Reference:<br>Your Reference<br><br>Depth<br>Date Sampled<br>Type of sample | UNITS<br>----------<br>-<br>----------<br><br><br> | 170939-1<br>BH16<br><br>0.1<br>6/07/2017<br>Soil | 170939-2<br>BH16<br><br>0.8<br>6/07/2017<br>Soil | 170939-3<br>BH17<br><br>0.1<br>6/07/2017<br>Soil | 170939-4<br>BH17<br><br>0.7<br>6/07/2017<br>Soil | 170939-6<br>BH18<br><br>0.6<br>6/07/2017<br>Soil |
|---|---|---|---|---|---|---|
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Naphthalene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Acenaphthylene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Acenaphthene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fluorene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Phenanthrene | mg/kg | 0.5 | <0.1 | <0.1 | <0.1 | <0.1 |
| Anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fluoranthene | mg/kg | 1.3 | <0.1 | 0.1 | <0.1 | 0.1 |
| Pyrene | mg/kg | 1.2 | <0.1 | 0.1 | <0.1 | 0.1 |
| Benzo(a)anthracene | mg/kg | 0.6 | <0.1 | <0.1 | <0.1 | <0.1 |
| Chrysene | mg/kg | 0.6 | <0.1 | <0.1 | <0.1 | <0.1 |
| Benzo(b,j+k)fluoranthene | mg/kg | 1 | <0.2 | <0.2 | <0.2 | <0.2 |
| Benzo(a)pyrene | mg/kg | 0.67 | <0.05 | 0.08 | <0.05 | 0.05 |
| Indeno(1,2,3-c,d)pyrene | mg/kg | 0.5 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dibenzo(a,h)anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Benzo(g,h,i)perylene | mg/kg | 0.6 | <0.1 | <0.1 | <0.1 | <0.1 |
| Benzo(a)pyrene TEQ calc (zero) | mg/kg | 0.9 | <0.5 | <0.5 | <0.5 | <0.5 |
| Benzo(a)pyrene TEQ calc(half) | mg/kg | 0.9 | <0.5 | <0.5 | <0.5 | <0.5 |
| Benzo(a)pyrene TEQ calc(PQL) | mg/kg | 0.9 | <0.5 | <0.5 | <0.5 | <0.5 |
| Total +ve PAH's | mg/kg | 7.1 | <0.05 | 0.4 | <0.05 | 0.3 |
| *Surrogate p*-Terphenyl-d14 | % | 91 | 93 | 91 | 89 | 88 |

| PAHs in Soil<br>Our Reference:<br>Your Reference | UNITS<br>---------- | 170939-9<br>BH20 | 170939-10<br>BH20 | 170939-12<br>BH21 | 170939-17<br>BH23 | 170939-19<br>BH24 |
|---|---|---|---|---|---|---|
| Depth | ---------- | 1.0 | 1.9 | 1.2 | 1.0 | 1.5 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Naphthalene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Acenaphthylene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Acenaphthene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fluorene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Phenanthrene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fluoranthene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | 0.2 |
| Pyrene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | 0.2 |
| Benzo(a)anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Chrysene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Benzo(b,j+k)fluoranthene | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| Benzo(a)pyrene | mg/kg | <0.05 | <0.05 | 0.06 | <0.05 | 0.08 |
| Indeno(1,2,3-c,d)pyrene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dibenzo(a,h)anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Benzo(g,h,i)perylene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Benzo(a)pyrene TEQ calc (zero) | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Benzo(a)pyrene TEQ calc(half) | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Benzo(a)pyrene TEQ calc(PQL) | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Total +ve PAH's | mg/kg | <0.05 | <0.05 | 0.06 | <0.05 | 0.4 |
| *Surrogate p*-Terphenyl-d14 | % | 84 | 89 | 88 | 88 | 90 |

| PAHs in Soil<br>Our Reference:<br>Your Reference | UNITS<br>---------- | 170939-24<br>BH27 | 170939-27<br>BH28 | 170939-30<br>BH29 | 170939-32<br>BH29 | 170939-36<br>BH30 |
|---|---|---|---|---|---|---|
| Depth | ---------- | 1.0 | 3.0 | 1.0 | 3.0 | 1.0 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Naphthalene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Acenaphthylene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | 0.4 |
| Acenaphthene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fluorene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Phenanthrene | mg/kg | <0.1 | 0.2 | <0.1 | <0.1 | 0.9 |
| Anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | 0.4 |
| Fluoranthene | mg/kg | <0.1 | 0.6 | 0.2 | 0.4 | 3.5 |
| Pyrene | mg/kg | <0.1 | 0.7 | 0.2 | 0.4 | 3.9 |
| Benzo(a)anthracene | mg/kg | <0.1 | 0.4 | 0.1 | 0.2 | 2.0 |
| Chrysene | mg/kg | <0.1 | 0.4 | 0.1 | 0.2 | 2.1 |
| Benzo(b,j+k)fluoranthene | mg/kg | <0.2 | 0.7 | 0.2 | 0.3 | 3.4 |
| Benzo(a)pyrene | mg/kg | <0.05 | 0.4 | 0.1 | 0.2 | 2.2 |
| Indeno(1,2,3-c,d)pyrene | mg/kg | <0.1 | 0.3 | <0.1 | 0.1 | 1.2 |
| Dibenzo(a,h)anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | 0.3 |
| Benzo(g,h,i)perylene | mg/kg | <0.1 | 0.3 | 0.1 | 0.2 | 1.6 |
| Benzo(a)pyrene TEQ calc (zero) | mg/kg | <0.5 | 0.6 | <0.5 | <0.5 | 3.2 |
| Benzo(a)pyrene TEQ calc(half) | mg/kg | <0.5 | 0.6 | <0.5 | <0.5 | 3.2 |
| Benzo(a)pyrene TEQ calc(PQL) | mg/kg | <0.5 | 0.6 | <0.5 | <0.5 | 3.2 |
| Total +ve PAH's | mg/kg | <0.05 | 4.2 | 0.97 | 2.1 | 22 |
| *Surrogate p*-Terphenyl-d14 | % | 90 | 93 | 95 | 94 | 81 |

| PAHs in Soil<br>Our Reference:<br>Your Reference | UNITS<br>---------- | 170939-39<br>BH30 | 170939-45<br>BH32 | 170939-46<br>BH32 | 170939-50<br>BH33 | 170939-51<br>BH34 |
|---|---|---|---|---|---|---|
| Depth | ---------- | 4.0 | 1.0 | 2.2 | 1.0 | 0.1 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Naphthalene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Acenaphthylene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Acenaphthene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fluorene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Phenanthrene | mg/kg | 0.2 | <0.1 | 0.1 | 0.8 | <0.1 |
| Anthracene | mg/kg | <0.1 | <0.1 | <0.1 | 0.2 | <0.1 |
| Fluoranthene | mg/kg | 0.9 | <0.1 | 0.2 | 1.5 | <0.1 |
| Pyrene | mg/kg | 1 | <0.1 | 0.2 | 1.5 | <0.1 |
| Benzo(a)anthracene | mg/kg | 0.5 | <0.1 | <0.1 | 0.8 | <0.1 |
| Chrysene | mg/kg | 0.5 | <0.1 | <0.1 | 0.9 | <0.1 |
| Benzo(b,j+k)fluoranthene | mg/kg | 0.8 | <0.2 | <0.2 | 3.1 | <0.2 |
| Benzo(a)pyrene | mg/kg | 0.52 | <0.05 | 0.08 | 2.2 | <0.05 |
| Indeno(1,2,3-c,d)pyrene | mg/kg | 0.3 | <0.1 | <0.1 | 1.8 | <0.1 |
| Dibenzo(a,h)anthracene | mg/kg | <0.1 | <0.1 | <0.1 | 0.4 | <0.1 |
| Benzo(g,h,i)perylene | mg/kg | 0.3 | <0.1 | <0.1 | 2.5 | <0.1 |
| Benzo(a)pyrene TEQ calc (zero) | mg/kg | 0.7 | <0.5 | <0.5 | 3.2 | <0.5 |
| Benzo(a)pyrene TEQ calc(half) | mg/kg | 0.7 | <0.5 | <0.5 | 3.2 | <0.5 |
| Benzo(a)pyrene TEQ calc(PQL) | mg/kg | 0.7 | <0.5 | <0.5 | 3.2 | <0.5 |
| Total +ve PAH's | mg/kg | 5.1 | <0.05 | 0.51 | 16 | <0.05 |
| *Surrogate p*-Terphenyl-d14 | % | 95 | 91 | 91 | 93 | 81 |

| PAHs in Soil<br>Our Reference:<br>Your Reference | UNITS<br>---------- | 170939-54<br>BH37 | 170939-55<br>BH38 | 170939-57<br>Dup1 | 170939-63<br>BH29 | 170939-66<br>BH19 |
|---|---|---|---|---|---|---|
| Depth | ---------- | 0.1 | 0.1 | - | 6.0 | 0.5 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Naphthalene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Acenaphthylene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Acenaphthene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fluorene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Phenanthrene | mg/kg | 0.1 | 0.1 | <0.1 | 0.2 | <0.1 |
| Anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fluoranthene | mg/kg | 0.3 | 0.4 | <0.1 | 0.5 | <0.1 |
| Pyrene | mg/kg | 0.3 | 0.3 | <0.1 | 0.6 | <0.1 |
| Benzo(a)anthracene | mg/kg | 0.1 | 0.2 | <0.1 | 0.4 | <0.1 |
| Chrysene | mg/kg | 0.1 | 0.2 | <0.1 | 0.4 | <0.1 |
| Benzo(b,j+k)fluoranthene | mg/kg | 0.3 | 0.4 | <0.2 | 0.7 | <0.2 |
| Benzo(a)pyrene | mg/kg | 0.2 | 0.2 | <0.05 | 0.5 | <0.05 |
| Indeno(1,2,3-c,d)pyrene | mg/kg | 0.1 | 0.1 | <0.1 | 0.3 | <0.1 |
| Dibenzo(a,h)anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Benzo(g,h,i)perylene | mg/kg | 0.1 | 0.2 | <0.1 | 0.3 | <0.1 |
| Benzo(a)pyrene TEQ calc (zero) | mg/kg | <0.5 | <0.5 | <0.5 | 0.6 | <0.5 |
| Benzo(a)pyrene TEQ calc(half) | mg/kg | <0.5 | <0.5 | <0.5 | 0.6 | <0.5 |
| Benzo(a)pyrene TEQ calc(PQL) | mg/kg | <0.5 | <0.5 | <0.5 | 0.6 | <0.5 |
| Total +ve PAH's | mg/kg | 1.7 | 2.1 | <0.05 | 3.9 | <0.05 |
| *Surrogate p*-Terphenyl-d14 | % | 91 | 98 | 81 | 94 | 81 |

| PAHs in Soil<br>Our Reference:<br>Your Reference<br><br>Depth<br>Date Sampled<br>Type of sample | UNITS<br>----------<br>-<br>----------<br><br><br> | 170939-67<br>BH21<br><br>4.0<br>6/07/2017<br>Soil | 170939-71<br>BH31<br><br>1.0<br>6/07/2017<br>Soil |
|---|---|---|---|
| Date extracted | - | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 |
| Naphthalene | mg/kg | <0.1 | <0.1 |
| Acenaphthylene | mg/kg | <0.1 | <0.1 |
| Acenaphthene | mg/kg | <0.1 | <0.1 |
| Fluorene | mg/kg | <0.1 | <0.1 |
| Phenanthrene | mg/kg | <0.1 | <0.1 |
| Anthracene | mg/kg | <0.1 | <0.1 |
| Fluoranthene | mg/kg | <0.1 | <0.1 |
| Pyrene | mg/kg | <0.1 | <0.1 |
| Benzo(a)anthracene | mg/kg | <0.1 | <0.1 |
| Chrysene | mg/kg | <0.1 | <0.1 |
| Benzo(b,j+k)fluoranthene | mg/kg | <0.2 | <0.2 |
| Benzo(a)pyrene | mg/kg | <0.05 | <0.05 |
| Indeno(1,2,3-c,d)pyrene | mg/kg | <0.1 | <0.1 |
| Dibenzo(a,h)anthracene | mg/kg | <0.1 | <0.1 |
| Benzo(g,h,i)perylene | mg/kg | <0.1 | <0.1 |
| Benzo(a)pyrene TEQ calc (zero) | mg/kg | <0.5 | <0.5 |
| Benzo(a)pyrene TEQ calc(half) | mg/kg | <0.5 | <0.5 |
| Benzo(a)pyrene TEQ calc(PQL) | mg/kg | <0.5 | <0.5 |
| Total +ve PAH's | mg/kg | <0.05 | <0.05 |
| *Surrogate p*-Terphenyl-d14 | % | 97 | 99 |

| Acid Extractractable metals in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-1 | 170939-2 | 170939-3 | 170939-4 | 170939-5 |
| Your Reference | ---------- | BH16 | BH16 | BH17 | BH17 | BH18 |
| | - | | | | | |
| Depth | ---------- | 0.1 | 0.8 | 0.1 | 0.7 | 0.1 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Arsenic | mg/kg | 8 | 9 | 5 | 16 | <4 |
| Cadmium | mg/kg | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 |
| Chromium | mg/kg | 12 | 9 | 14 | 7 | 9 |
| Copper | mg/kg | 21 | <1 | 5 | 4 | 8 |
| Lead | mg/kg | 89 | 11 | 11 | 13 | 13 |
| Mercury | mg/kg | 0.2 | <0.1 | <0.1 | <0.1 | 3.7 |
| Nickel | mg/kg | 9 | <1 | 1 | <1 | 3 |
| Zinc | mg/kg | 84 | <1 | 6 | 2 | 18 |

| Acid Extractractable metals in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-6 | 170939-7 | 170939-8 | 170939-9 | 170939-10 |
| Your Reference | ---------- | BH18 | BH19 | BH20 | BH20 | BH20 |
| | - | | | | | |
| Depth | ---------- | 0.6 | 0.1 | 0.1 | 1.0 | 1.9 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Arsenic | mg/kg | <4 | 5 | <4 | <4 | <4 |
| Cadmium | mg/kg | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 |
| Chromium | mg/kg | 6 | 9 | 9 | 14 | 3 |
| Copper | mg/kg | 1 | 8 | 8 | <1 | <1 |
| Lead | mg/kg | 10 | 13 | 14 | 8 | 8 |
| Mercury | mg/kg | <0.1 | 6.4 | 5.2 | <0.1 | <0.1 |
| Nickel | mg/kg | <1 | 2 | 3 | 2 | <1 |
| Zinc | mg/kg | 7 | 14 | 17 | 50 | 1 |

| Acid Extractractable metals in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-11 | 170939-12 | 170939-13 | 170939-14 | 170939-15 |
| Your Reference | ---------- - | BH21 | BH21 | BH21 | BH22 | BH22 |
| Depth | ---------- | 0.1 | 1.2 | 3.0 | 0.1 | 1.0 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Arsenic | mg/kg | <4 | <4 | 9 | <4 | <4 |
| Cadmium | mg/kg | <0.4 | <0.4 | 1 | <0.4 | <0.4 |
| Chromium | mg/kg | 14 | 12 | 23 | 5 | 8 |
| Copper | mg/kg | 9 | 3 | 12 | 72 | 16 |
| Lead | mg/kg | 12 | 23 | 120 | 230 | 830 |
| Mercury | mg/kg | 2.7 | <0.1 | <0.1 | 0.2 | 0.2 |
| Nickel | mg/kg | 4 | 3 | 5 | 17 | 4 |
| Zinc | mg/kg | 19 | 89 | 640 | 110 | 260 |

| Acid Extractractable metals in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-16 | 170939-17 | 170939-18 | 170939-19 | 170939-20 |
| Your Reference | ---------- - | BH23 | BH23 | BH24 | BH24 | BH24 |
| Depth | ---------- | 0.1 | 1.0 | 0.1 | 1.5 | 2.8 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Arsenic | mg/kg | <4 | <4 | <4 | <4 | <4 |
| Cadmium | mg/kg | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 |
| Chromium | mg/kg | 7 | 5 | 9 | 9 | 14 |
| Copper | mg/kg | 7 | <1 | 7 | 3 | 1 |
| Lead | mg/kg | 12 | 4 | 11 | 18 | 15 |
| Mercury | mg/kg | 4.2 | <0.1 | 2.7 | <0.1 | <0.1 |
| Nickel | mg/kg | 3 | <1 | 2 | 1 | <1 |
| Zinc | mg/kg | 18 | <1 | 17 | 14 | 8 |

| Acid Extractractable metals in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-21 | 170939-22 | 170939-23 | 170939-24 | 170939-25 |
| Your Reference | ---------- - | BH25 | BH26 | BH27 | BH27 | BH28 |
| Depth | ---------- | 0.2 | 0.2 | 0.1 | 1.0 | 0.1 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Arsenic | mg/kg | 22 | <4 | 8 | <4 | <4 |
| Cadmium | mg/kg | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 |
| Chromium | mg/kg | 16 | 4 | 12 | 12 | 7 |
| Copper | mg/kg | 15 | <1 | 17 | 3 | 7 |
| Lead | mg/kg | 87 | 6 | 130 | 34 | 10 |
| Mercury | mg/kg | 0.2 | <0.1 | 0.2 | <0.1 | 4.1 |
| Nickel | mg/kg | 3 | <1 | 5 | <1 | 3 |
| Zinc | mg/kg | 66 | 2 | 140 | 12 | 17 |

| Acid Extractractable metals in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-26 | 170939-27 | 170939-28 | 170939-29 | 170939-30 |
| Your Reference | ---------- - | BH28 | BH28 | BH28 | BH29 | BH29 |
| Depth | ---------- | 2.0 | 3.0 | 4.0 | 0.1 | 1.0 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Arsenic | mg/kg | <4 | 5 | 7 | <4 | 6 |
| Cadmium | mg/kg | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 |
| Chromium | mg/kg | 11 | 27 | 14 | 8 | 46 |
| Copper | mg/kg | 4 | 21 | 57 | 7 | 6 |
| Lead | mg/kg | 52 | 130 | 150 | 9 | 66 |
| Mercury | mg/kg | <0.1 | 0.2 | <0.1 | 3.2 | 0.1 |
| Nickel | mg/kg | 1 | 5 | 17 | 3 | 3 |
| Zinc | mg/kg | 28 | 120 | 4,600 | 16 | 56 |

| Acid Extractractable metals in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-31 | 170939-32 | 170939-33 | 170939-34 | 170939-35 |
| Your Reference | ---------- - | BH29 | BH29 | BH29 | BH29 | BH30 |
| Depth | ---------- | 2.0 | 3.0 | 4.0 | 5.0 | 0.1 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Arsenic | mg/kg | 5 | <4 | <4 | <4 | <4 |
| Cadmium | mg/kg | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 |
| Chromium | mg/kg | 21 | 4 | 14 | 7 | 6 |
| Copper | mg/kg | 21 | 2 | 17 | 16 | 6 |
| Lead | mg/kg | 220 | 49 | 790 | 740 | 10 |
| Mercury | mg/kg | 0.2 | <0.1 | 0.1 | 0.6 | 4.4 |
| Nickel | mg/kg | 5 | <1 | 11 | 4 | 2 |
| Zinc | mg/kg | 110 | 17 | 170 | 230 | 9 |

| Acid Extractractable metals in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-36 | 170939-37 | 170939-38 | 170939-39 | 170939-40 |
| Your Reference | ---------- - | BH30 | BH30 | BH30 | BH30 | BH30 |
| Depth | ---------- | 1.0 | 2.0 | 3.0 | 4.0 | 5.0 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Arsenic | mg/kg | 5 | 6 | 6 | <4 | <4 |
| Beryllium | mg/kg | <1 | [NA] | [NA] | [NA] | [NA] |
| Boron | mg/kg | <3 | [NA] | [NA] | [NA] | [NA] |
| Cadmium | mg/kg | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 |
| Chromium | mg/kg | 19 | 17 | 37 | 11 | 6 |
| Cobalt | mg/kg | <1 | [NA] | [NA] | [NA] | [NA] |
| Copper | mg/kg | 14 | 15 | 14 | 36 | 3 |
| Lead | mg/kg | 150 | 53 | 130 | 210 | 130 |
| Manganese | mg/kg | 26 | [NA] | [NA] | [NA] | [NA] |
| Mercury | mg/kg | <0.1 | 0.3 | 0.3 | 0.2 | <0.1 |
| Nickel | mg/kg | 2 | 6 | 3 | 26 | 4 |
| Selenium | mg/kg | <2 | [NA] | [NA] | [NA] | [NA] |
| Zinc | mg/kg | 140 | 66 | 110 | 94 | 89 |

| Acid Extractractable metals in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-41 | 170939-42 | 170939-43 | 170939-44 | 170939-45 |
| Your Reference | ---------- - | BH30 | BH30 | BH31 | BH32 | BH32 |
| Depth | ---------- | 6.0 | 7.0 | 0.1 | 0.1 | 1.0 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Arsenic | mg/kg | <4 | <4 | 32 | <4 | 8 |
| Cadmium | mg/kg | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 |
| Chromium | mg/kg | 79 | 7 | 10 | 4 | 10 |
| Copper | mg/kg | 58 | <1 | 14 | 36 | 15 |
| Lead | mg/kg | 500 | 3 | 55 | 4 | 18 |
| Mercury | mg/kg | 0.2 | <0.1 | 0.5 | 0.2 | <0.1 |
| Nickel | mg/kg | 23 | <1 | 3 | 34 | 1 |
| Zinc | mg/kg | 180 | 4 | 54 | 27 | 9 |

| Acid Extractractable metals in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-46 | 170939-47 | 170939-48 | 170939-49 | 170939-50 |
| Your Reference | ---------- - | BH32 | BH32 | BH32 | BH33 | BH33 |
| Depth | ---------- | 2.2 | 3.0 | 4.0 | 0.2 | 1.0 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Arsenic | mg/kg | <4 | 8 | <4 | <4 | <4 |
| Cadmium | mg/kg | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 |
| Chromium | mg/kg | 7 | 9 | 14 | 20 | 15 |
| Copper | mg/kg | 4 | 11 | <1 | <1 | 21 |
| Lead | mg/kg | 15 | 19 | 6 | 7 | 48 |
| Mercury | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Nickel | mg/kg | 1 | 2 | <1 | <1 | 2 |
| Zinc | mg/kg | 10 | 9 | <1 | <1 | 63 |

| Acid Extractractable metals in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-51 | 170939-52 | 170939-53 | 170939-54 | 170939-55 |
| Your Reference | ---------- - | BH34 | BH35 | BH36 | BH37 | BH38 |
| Depth | ---------- | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Arsenic | mg/kg | <4 | 6 | 7 | <4 | 7 |
| Beryllium | mg/kg | <1 | [NA] | [NA] | [NA] | [NA] |
| Boron | mg/kg | <3 | [NA] | [NA] | [NA] | [NA] |
| Cadmium | mg/kg | <0.4 | 10 | 0.5 | <0.4 | 2 |
| Chromium | mg/kg | 4 | 22 | 12 | 8 | 180 |
| Cobalt | mg/kg | <1 | [NA] | [NA] | [NA] | [NA] |
| Copper | mg/kg | 2 | 270 | 37 | 8 | 140 |
| Lead | mg/kg | 9 | 1,300 | 79 | 49 | 150 |
| Manganese | mg/kg | 2 | [NA] | [NA] | [NA] | [NA] |
| Mercury | mg/kg | <0.1 | 0.3 | 0.1 | 0.1 | 1.3 |
| Nickel | mg/kg | <1 | 16 | 3 | 2 | 93 |
| Selenium | mg/kg | <2 | [NA] | [NA] | [NA] | [NA] |
| Zinc | mg/kg | 11 | 730 | 230 | 90 | 680 |

| Acid Extractractable metals in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-56 | 170939-57 | 170939-58 | 170939-59 | 170939-60 |
| Your Reference | ---------- - | BH39 | Dup1 | Dup2 | Dup3 | Dup4 |
| Depth | ---------- | 0.1 | - | - | - | - |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Arsenic | mg/kg | <4 | <4 | 5 | 14 | <4 |
| Beryllium | mg/kg | [NA] | <1 | [NA] | [NA] | [NA] |
| Boron | mg/kg | [NA] | <3 | [NA] | [NA] | [NA] |
| Cadmium | mg/kg | 0.7 | <0.4 | 6.0 | 0.6 | <0.4 |
| Chromium | mg/kg | 6 | 4 | 18 | 13 | 8 |
| Cobalt | mg/kg | [NA] | <1 | [NA] | [NA] | [NA] |
| Copper | mg/kg | 30 | 2 | 230 | 47 | 8 |
| Lead | mg/kg | 76 | 7 | 1,100 | 91 | 53 |
| Manganese | mg/kg | [NA] | 2 | [NA] | [NA] | [NA] |
| Mercury | mg/kg | 0.2 | <0.1 | 0.2 | 0.1 | 0.1 |
| Nickel | mg/kg | 6 | <1 | 11 | 9 | 2 |
| Selenium | mg/kg | [NA] | <2 | [NA] | [NA] | [NA] |
| Zinc | mg/kg | 210 | 10 | 650 | 230 | 82 |

| Acid Extractractable metals in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-63 | 170939-64 | 170939-65 | 170939-66 | 170939-67 |
| Your Reference | ---------- - | BH29 | BH29 | BH29 | BH19 | BH21 |
| Depth | ---------- | 6.0 | 8.0 | 7.0 | 0.5 | 4.0 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Arsenic | mg/kg | <4 | 4 | <4 | <4 | <4 |
| Beryllium | mg/kg | [NA] | [NA] | [NA] | <1 | [NA] |
| Boron | mg/kg | [NA] | [NA] | [NA] | <3 | [NA] |
| Cadmium | mg/kg | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 |
| Chromium | mg/kg | 12 | 10 | 4 | 8 | 5 |
| Cobalt | mg/kg | [NA] | [NA] | [NA] | 1 | [NA] |
| Copper | mg/kg | 11 | 8 | 5 | 2 | <1 |
| Lead | mg/kg | 260 | 6,200 | 540 | 17 | 6 |
| Manganese | mg/kg | [NA] | [NA] | [NA] | 20 | [NA] |
| Mercury | mg/kg | 0.3 | <0.1 | <0.1 | <0.1 | <0.1 |
| Nickel | mg/kg | 7 | 5 | 2 | <1 | <1 |
| Selenium | mg/kg | [NA] | [NA] | [NA] | <2 | [NA] |
| Zinc | mg/kg | 90 | 94 | 190 | 5 | <1 |

| Acid Extractractable metals in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-68 | 170939-69 | 170939-70 | 170939-71 | 170939-72 |
| Your Reference | ---------- - | BH40 | BH41 | BH42 | BH31 | BH16 - [TRIPLICATE] |
| Depth | ---------- | 0.1 | 0.1 | 0.1 | 1.0 | 0.1 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 06/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Arsenic | mg/kg | <4 | <4 | <4 | <4 | 8 |
| Beryllium | mg/kg | [NA] | [NA] | [NA] | [NA] | <1 |
| Boron | mg/kg | [NA] | [NA] | [NA] | [NA] | <3 |
| Cadmium | mg/kg | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 |
| Chromium | mg/kg | 7 | 6 | 12 | 4 | 16 |
| Cobalt | mg/kg | [NA] | [NA] | [NA] | [NA] | 4 |
| Copper | mg/kg | 10 | 11 | 9 | <1 | 30 |
| Lead | mg/kg | 12 | 53 | 11 | 5 | 110 |
| Manganese | mg/kg | [NA] | [NA] | [NA] | [NA] | 190 |
| Mercury | mg/kg | 5.5 | 4.1 | 5.2 | <0.1 | 0.2 |
| Nickel | mg/kg | 2 | 2 | 3 | <1 | 12 |
| Selenium | mg/kg | [NA] | [NA] | [NA] | [NA] | <2 |
| Zinc | mg/kg | 14 | 71 | 15 | <1 | 130 |

| Acid Extractractable metals in soil | | | |
|---|---|---|---|
| Our Reference: | UNITS | 170939-73 | 170939-74 |
| Your Reference | ---------- | BH30 - [TRIPLICATE] | BH29 - [TRIPLICATE] |
| | - | | |
| Depth | ---------- | 6.0 | 8.0 |
| Date Sampled | | 06/07/2017 | 06/07/2017 |
| Type of sample | | Soil | Soil |
| Date prepared | - | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 |
| Arsenic | mg/kg | <4 | <4 |
| Cadmium | mg/kg | <0.4 | <0.4 |
| Chromium | mg/kg | 17 | 8 |
| Copper | mg/kg | 19 | 6 |
| Lead | mg/kg | 490 | 3,700 |
| Mercury | mg/kg | 0.1 | <0.1 |
| Nickel | mg/kg | 11 | 3 |
| Zinc | mg/kg | 370 | 79 |

| Moisture | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-1 | 170939-2 | 170939-3 | 170939-4 | 170939-5 |
| Your Reference | ---------- - | BH16 | BH16 | BH17 | BH17 | BH18 |
| Depth | ---------- | 0.1 | 0.8 | 0.1 | 0.7 | 0.1 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Moisture | % | 11 | 14 | 11 | 9.4 | 8.5 |

| Moisture | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-6 | 170939-7 | 170939-8 | 170939-9 | 170939-10 |
| Your Reference | ---------- - | BH18 | BH19 | BH20 | BH20 | BH20 |
| Depth | ---------- | 0.6 | 0.1 | 0.1 | 1.0 | 1.9 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Moisture | % | 7.7 | 11 | 11 | 17 | 12 |

| Moisture | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-11 | 170939-12 | 170939-13 | 170939-14 | 170939-15 |
| Your Reference | ---------- - | BH21 | BH21 | BH21 | BH22 | BH22 |
| Depth | ---------- | 0.1 | 1.2 | 3.0 | 0.1 | 1.0 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Moisture | % | 9.8 | 14 | 19 | 9.2 | 12 |

| Moisture | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-16 | 170939-17 | 170939-18 | 170939-19 | 170939-20 |
| Your Reference | ---------- - | BH23 | BH23 | BH24 | BH24 | BH24 |
| Depth | ---------- | 0.1 | 1.0 | 0.1 | 1.5 | 2.8 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Moisture | % | 12 | 9.9 | 8.4 | 5.7 | 16 |

| Moisture | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-21 | 170939-22 | 170939-23 | 170939-24 | 170939-25 |
| Your Reference | ---------- | BH25 | BH26 | BH27 | BH27 | BH28 |
| | - | | | | | |
| Depth | ---------- | 0.2 | 0.2 | 0.1 | 1.0 | 0.1 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Moisture | % | 13 | 14 | 17 | 7.6 | 13 |

| Moisture | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-26 | 170939-27 | 170939-28 | 170939-29 | 170939-30 |
| Your Reference | ---------- | BH28 | BH28 | BH28 | BH29 | BH29 |
| | - | | | | | |
| Depth | ---------- | 2.0 | 3.0 | 4.0 | 0.1 | 1.0 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Moisture | % | 15 | 16 | 11 | 9.7 | 21 |

| Moisture | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-31 | 170939-32 | 170939-33 | 170939-34 | 170939-35 |
| Your Reference | ---------- | BH29 | BH29 | BH29 | BH29 | BH30 |
| | - | | | | | |
| Depth | ---------- | 2.0 | 3.0 | 4.0 | 5.0 | 0.1 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Moisture | % | 13 | 9.7 | 9.8 | 12 | 10 |

| Moisture | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-36 | 170939-37 | 170939-38 | 170939-39 | 170939-40 |
| Your Reference | ---------- | BH30 | BH30 | BH30 | BH30 | BH30 |
| | - | | | | | |
| Depth | ---------- | 1.0 | 2.0 | 3.0 | 4.0 | 5.0 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Moisture | % | 8.6 | 9.4 | 16 | 6.4 | 6.9 |

| Moisture | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-41 | 170939-42 | 170939-43 | 170939-44 | 170939-45 |
| Your Reference | ---------- | BH30 | BH30 | BH31 | BH32 | BH32 |
| | - | | | | | |
| Depth | ---------- | 6.0 | 7.0 | 0.1 | 0.1 | 1.0 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Moisture | % | 7.7 | 15 | 16 | 6.4 | 15 |

| Moisture | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-46 | 170939-47 | 170939-48 | 170939-49 | 170939-50 |
| Your Reference | ---------- | BH32 | BH32 | BH32 | BH33 | BH33 |
| | - | | | | | |
| Depth | ---------- | 2.2 | 3.0 | 4.0 | 0.2 | 1.0 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Moisture | % | 9.8 | 17 | 13 | 14 | 13 |

| Moisture | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-51 | 170939-52 | 170939-53 | 170939-54 | 170939-55 |
| Your Reference | ---------- | BH34 | BH35 | BH36 | BH37 | BH38 |
| | - | | | | | |
| Depth | ---------- | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Moisture | % | 12 | 15 | 25 | 14 | 25 |

| Moisture | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-56 | 170939-57 | 170939-58 | 170939-59 | 170939-60 |
| Your Reference | ---------- | BH39 | Dup1 | Dup2 | Dup3 | Dup4 |
| | - | | | | | |
| Depth | ---------- | 0.1 | - | - | - | - |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Moisture | % | 27 | 12 | 13 | 25 | 16 |

| Moisture | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-63 | 170939-64 | 170939-65 | 170939-66 | 170939-67 |
| Your Reference | ---------- - | BH29 | BH29 | BH29 | BH19 | BH21 |
| Depth | ---------- | 6.0 | 8.0 | 7.0 | 0.5 | 4.0 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Moisture | % | 5.5 | 19 | 11 | 12 | 14 |

| Moisture | | | | | |
|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-68 | 170939-69 | 170939-70 | 170939-71 |
| Your Reference | ---------- - | BH40 | BH41 | BH42 | BH31 |
| Depth | ---------- | 0.1 | 0.1 | 0.1 | 1.0 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil |
| Date prepared | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Moisture | % | 7.6 | 19 | 10 | 9.1 |

| Organochlorine Pesticides in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-5 | 170939-7 | 170939-8 | 170939-11 | 170939-14 |
| Your Reference | ---------- - | BH18 | BH19 | BH20 | BH21 | BH22 |
| Depth | ---------- | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| HCB | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| alpha-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| gamma-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| beta-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Heptachlor | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| delta-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Aldrin | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Heptachlor Epoxide | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| gamma-Chlordane | mg/kg | <0.1 | <0.1 | <0.1 | 0.1 | <0.1 |
| alpha-chlordane | mg/kg | 0.2 | 0.1 | 0.1 | 0.2 | <0.1 |
| Endosulfan I | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| pp-DDE | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dieldrin | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endrin | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| pp-DDD | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endosulfan II | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| pp-DDT | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endrin Aldehyde | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endosulfan Sulphate | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Methoxychlor | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Total +ve DDT+DDD+DDE | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| *Surrogate* TCMX | % | 89 | 89 | 90 | 89 | 89 |

| Organochlorine Pesticides in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-16 | 170939-18 | 170939-21 | 170939-22 | 170939-23 |
| Your Reference | ---------- - | BH23 | BH24 | BH25 | BH26 | BH27 |
| Depth | ---------- | 0.1 | 0.1 | 0.2 | 0.2 | 0.1 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| HCB | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| alpha-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| gamma-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| beta-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Heptachlor | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| delta-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Aldrin | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Heptachlor Epoxide | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| gamma-Chlordane | mg/kg | 0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| alpha-chlordane | mg/kg | 0.3 | 0.1 | <0.1 | <0.1 | <0.1 |
| Endosulfan I | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| pp-DDE | mg/kg | <0.1 | 0.1 | <0.1 | <0.1 | <0.1 |
| Dieldrin | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endrin | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| pp-DDD | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endosulfan II | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| pp-DDT | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endrin Aldehyde | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endosulfan Sulphate | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Methoxychlor | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Total +ve DDT+DDD+DDE | mg/kg | <0.1 | 0.1 | <0.1 | <0.1 | <0.1 |
| *Surrogate* TCMX | % | 91 | 91 | 95 | 94 | 95 |

| Organochlorine Pesticides in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-25 | 170939-29 | 170939-35 | 170939-36 | 170939-43 |
| Your Reference | ---------- - | BH28 | BH29 | BH30 | BH30 | BH31 |
| Depth | ---------- | 0.1 | 0.1 | 0.1 | 1.0 | 0.1 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| HCB | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| alpha-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| gamma-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| beta-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Heptachlor | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| delta-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Aldrin | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Heptachlor Epoxide | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| gamma-Chlordane | mg/kg | <0.1 | <0.1 | 0.1 | <0.1 | <0.1 |
| alpha-chlordane | mg/kg | <0.1 | <0.1 | 0.1 | <0.1 | <0.1 |
| Endosulfan I | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| pp-DDE | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dieldrin | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endrin | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| pp-DDD | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endosulfan II | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| pp-DDT | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endrin Aldehyde | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endosulfan Sulphate | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Methoxychlor | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Total +ve DDT+DDD+DDE | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| *Surrogate* TCMX | % | 93 | 93 | 99 | 102 | 99 |

| Organochlorine Pesticides in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-44 | 170939-49 | 170939-51 | 170939-57 | 170939-66 |
| Your Reference | ---------- - | BH32 | BH33 | BH34 | Dup1 | BH19 |
| Depth | ---------- | 0.1 | 0.2 | 0.1 | - | 0.5 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 14/07/2017 | 14/07/2017 |
| HCB | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| alpha-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| gamma-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| beta-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Heptachlor | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| delta-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Aldrin | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Heptachlor Epoxide | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| gamma-Chlordane | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| alpha-chlordane | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endosulfan I | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| pp-DDE | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dieldrin | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endrin | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| pp-DDD | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endosulfan II | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| pp-DDT | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endrin Aldehyde | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endosulfan Sulphate | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Methoxychlor | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Total +ve DDT+DDD+DDE | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| *Surrogate* TCMX | % | 97 | 103 | 106 | 94 | 95 |

| Organochlorine Pesticides in soil | | |
|---|---|---|
| Our Reference: | UNITS | 170939-70 |
| Your Reference | ---------- | BH42 |
| | - | |
| Depth | ---------- | 0.1 |
| Date Sampled | | 6/07/2017 |
| Type of sample | | Soil |
| Date extracted | - | 11/07/2017 |
| Date analysed | - | 14/07/2017 |
| HCB | mg/kg | <0.1 |
| alpha-BHC | mg/kg | <0.1 |
| gamma-BHC | mg/kg | <0.1 |
| beta-BHC | mg/kg | <0.1 |
| Heptachlor | mg/kg | <0.1 |
| delta-BHC | mg/kg | <0.1 |
| Aldrin | mg/kg | <0.1 |
| Heptachlor Epoxide | mg/kg | <0.1 |
| gamma-Chlordane | mg/kg | <0.1 |
| alpha-chlordane | mg/kg | 0.1 |
| Endosulfan I | mg/kg | <0.1 |
| pp-DDE | mg/kg | <0.1 |
| Dieldrin | mg/kg | <0.1 |
| Endrin | mg/kg | <0.1 |
| pp-DDD | mg/kg | <0.1 |
| Endosulfan II | mg/kg | <0.1 |
| pp-DDT | mg/kg | <0.1 |
| Endrin Aldehyde | mg/kg | <0.1 |
| Endosulfan Sulphate | mg/kg | <0.1 |
| Methoxychlor | mg/kg | <0.1 |
| Total +ve DDT+DDD+DDE | mg/kg | <0.1 |
| *Surrogate* TCMX | % | 93 |

| Organophosphorus Pesticides | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-5 | 170939-7 | 170939-8 | 170939-11 | 170939-14 |
| Your Reference | ---------- - | BH18 | BH19 | BH20 | BH21 | BH22 |
| Depth | ---------- | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Azinphos-methyl (Guthion) | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Bromophos-ethyl | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Chlorpyriphos | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Chlorpyriphos-methyl | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Diazinon | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dichlorvos | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dimethoate | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Ethion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fenitrothion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Malathion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Parathion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Ronnel | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| *Surrogate* TCMX | % | 89 | 89 | 90 | 89 | 89 |

| Organophosphorus Pesticides | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-16 | 170939-18 | 170939-21 | 170939-22 | 170939-23 |
| Your Reference | ---------- - | BH23 | BH24 | BH25 | BH26 | BH27 |
| Depth | ---------- | 0.1 | 0.1 | 0.2 | 0.2 | 0.1 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Azinphos-methyl (Guthion) | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Bromophos-ethyl | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Chlorpyriphos | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Chlorpyriphos-methyl | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Diazinon | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dichlorvos | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dimethoate | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Ethion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fenitrothion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Malathion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Parathion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Ronnel | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| *Surrogate* TCMX | % | 91 | 91 | 95 | 94 | 95 |

| Organophosphorus Pesticides<br>Our Reference:<br>Your Reference<br><br>Depth<br>Date Sampled<br>Type of sample | UNITS<br>----------<br>-<br>----------<br><br><br> | 170939-25<br>BH28<br><br>0.1<br>6/07/2017<br>Soil | 170939-29<br>BH29<br><br>0.1<br>6/07/2017<br>Soil | 170939-35<br>BH30<br><br>0.1<br>6/07/2017<br>Soil | 170939-36<br>BH30<br><br>1.0<br>6/07/2017<br>Soil | 170939-43<br>BH31<br><br>0.1<br>6/07/2017<br>Soil |
|---|---|---|---|---|---|---|
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Azinphos-methyl (Guthion) | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Bromophos-ethyl | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Chlorpyriphos | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Chlorpyriphos-methyl | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Diazinon | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dichlorvos | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dimethoate | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Ethion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fenitrothion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Malathion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Parathion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Ronnel | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| *Surrogate* TCMX | % | 93 | 93 | 99 | 102 | 99 |

| Organophosphorus Pesticides<br>Our Reference:<br>Your Reference<br><br>Depth<br>Date Sampled<br>Type of sample | UNITS<br>----------<br>-<br>----------<br><br><br> | 170939-44<br>BH32<br><br>0.1<br>6/07/2017<br>Soil | 170939-49<br>BH33<br><br>0.2<br>6/07/2017<br>Soil | 170939-51<br>BH34<br><br>0.1<br>6/07/2017<br>Soil | 170939-57<br>Dup1<br><br>-<br>6/07/2017<br>Soil | 170939-66<br>BH19<br><br>0.5<br>6/07/2017<br>Soil |
|---|---|---|---|---|---|---|
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 14/07/2017 | 14/07/2017 |
| Azinphos-methyl (Guthion) | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Bromophos-ethyl | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Chlorpyriphos | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Chlorpyriphos-methyl | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Diazinon | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dichlorvos | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dimethoate | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Ethion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fenitrothion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Malathion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Parathion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Ronnel | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| *Surrogate* TCMX | % | 97 | 103 | 106 | 94 | 95 |

| Organophosphorus Pesticides | | |
|---|---|---|
| Our Reference: | UNITS | 170939-70 |
| Your Reference | ---------- | BH42 |
| | - | |
| Depth | ---------- | 0.1 |
| Date Sampled | | 6/07/2017 |
| Type of sample | | Soil |
| Date extracted | - | 11/07/2017 |
| Date analysed | - | 14/07/2017 |
| Azinphos-methyl (Guthion) | mg/kg | <0.1 |
| Bromophos-ethyl | mg/kg | <0.1 |
| Chlorpyriphos | mg/kg | <0.1 |
| Chlorpyriphos-methyl | mg/kg | <0.1 |
| Diazinon | mg/kg | <0.1 |
| Dichlorvos | mg/kg | <0.1 |
| Dimethoate | mg/kg | <0.1 |
| Ethion | mg/kg | <0.1 |
| Fenitrothion | mg/kg | <0.1 |
| Malathion | mg/kg | <0.1 |
| Parathion | mg/kg | <0.1 |
| Ronnel | mg/kg | <0.1 |
| *Surrogate* TCMX | % | 93 |

| PCBs in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-10 | 170939-13 | 170939-20 | 170939-28 | 170939-33 |
| Your Reference | ---------- | BH20 | BH21 | BH24 | BH28 | BH29 |
| | - | | | | | |
| Depth | ---------- | 1.9 | 3.0 | 2.8 | 4.0 | 4.0 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Aroclor 1016 | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Aroclor 1221 | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Aroclor 1232 | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Aroclor 1242 | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Aroclor 1248 | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Aroclor 1254 | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Aroclor 1260 | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Total +ve PCBs (1016-1260) | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| *Surrogate* TCLMX | % | 89 | 91 | 112 | 108 | 100 |

| PCBs in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-36 | 170939-41 | 170939-51 | 170939-57 | 170939-66 |
| Your Reference | ---------- | BH30 | BH30 | BH34 | Dup1 | BH19 |
| | - | | | | | |
| Depth | ---------- | 1.0 | 6.0 | 0.1 | - | 0.5 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 14/07/2017 | 14/07/2017 |
| Aroclor 1016 | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Aroclor 1221 | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Aroclor 1232 | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Aroclor 1242 | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Aroclor 1248 | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Aroclor 1254 | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Aroclor 1260 | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Total +ve PCBs (1016-1260) | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| *Surrogate* TCLMX | % | 102 | 97 | 106 | 94 | 95 |

| Triazine Herbicides in Soil | | | | | |
|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-36 | 170939-51 | 170939-57 | 170939-66 |
| Your Reference | ---------- | BH30 | BH34 | Dup1 | BH19 |
| Depth | ---------- | 1.0 | 0.1 | - | 0.5 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil |
| Date prepared | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Atrazine | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| Ametryn | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| Cyanazine | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| Hexazinone | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| Irgarol | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| Metribuzin | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| Prometryn | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| Propazine | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| Simazine | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| Terbutryn | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| Terbuthylazine | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | 93 | 92 | 101 | 96 |

| Speciated Phenols in Soil | | | | | |
|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-36 | 170939-51 | 170939-57 | 170939-66 |
| Your Reference | ---------- | BH30 | BH34 | Dup1 | BH19 |
| Depth | - ---------- | 1.0 | 0.1 | - | 0.5 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil |
| Date extracted | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 12/07/2017 | 12/07/2017 | 12/07/2017 | 12/07/2017 |
| Phenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 |
| 2-Chlorophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 |
| 4-Chloro-3-methylphenol | mg/kg | <1 | <1 | <1 | <1 |
| 2-Methylphenol (o-cresol) | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 |
| 3/4-Methylphenol (m/p-cresol) | mg/kg | <0.4 | <0.4 | <0.4 | <0.4 |
| 2-Nitrophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 |
| 2,4 -Dimethylphenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 |
| 2,4-Dichlorophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 |
| 2,6-Dichlorophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 |
| 2,4,5-Trichlorophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 |
| 2,4,6-Trichlorophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 |
| 2,4-Dinitrophenol | mg/kg | <4 | <4 | <4 | <4 |
| 4-Nitrophenol | mg/kg | <4 | <4 | <4 | <4 |
| 2346-Tetrachlorophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 |
| 2-methyl-4,6-Dinitrophenol | mg/kg | <2 | <2 | <2 | <2 |
| Pentachlorophenol | mg/kg | <1 | <1 | <1 | <1 |
| *Surrogate* 2-fluorophenol | % | 88 | 97 | 96 | 47 |
| *Surrogate* Phenol-$d_6$ | % | 83 | 88 | 88 | 87 |
| *Surrogate 2,4,6-Tribromophenol* | % | 91 | 118 | 125 | 112 |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | 93 | 95 | 97 | 94 |

| Misc Inorg - Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-5 | 170939-7 | 170939-8 | 170939-14 | 170939-18 |
| Your Reference | ---------- - | BH18 | BH19 | BH20 | BH22 | BH24 |
| Depth | ---------- | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| pH 1:5 soil:water | pH Units | 5.8 | 5.6 | 5.8 | 8.4 | 6.0 |

| Misc Inorg - Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-23 | 170939-29 | 170939-36 | 170939-44 | 170939-51 |
| Your Reference | ---------- - | BH27 | BH29 | BH30 | BH32 | BH34 |
| Depth | ---------- | 0.1 | 0.1 | 1.0 | 0.1 | 0.1 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| pH 1:5 soil:water | pH Units | 7.9 | 6.1 | 8.6 | 8.0 | 5.2 |

| Misc Inorg - Soil | | | |
|---|---|---|---|
| Our Reference: | UNITS | 170939-57 | 170939-66 |
| Your Reference | ---------- - | Dup1 | BH19 |
| Depth | ---------- | - | 0.5 |
| Date Sampled | | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil |
| Date prepared | - | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 13/07/2017 | 13/07/2017 |
| pH 1:5 soil:water | pH Units | 5.5 | 5.3 |

| Misc Soil - Inorg | | | | | |
|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-36 | 170939-51 | 170939-57 | 170939-66 |
| Your Reference | ---------- | BH30 | BH34 | Dup1 | BH19 |
| Depth | - ---------- | 1.0 | 0.1 | - | 0.5 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil |
| Date prepared | - | 14/07/2017 | 14/07/2017 | 14/07/2017 | 14/07/2017 |
| Date analysed | - | 14/07/2017 | 14/07/2017 | 14/07/2017 | 14/07/2017 |
| Hexavalent Chromium, $Cr^{6+}$ | mg/kg | <1 | <1 | <1 | <1 |

| Misc Soil - Inorg | | | | | |
|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-36 | 170939-51 | 170939-57 | 170939-66 |
| Your Reference | ---------- | BH30 | BH34 | Dup1 | BH19 |
| Depth | - ---------- | 1.0 | 0.1 | - | 0.5 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil |
| Date prepared | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Date analysed | - | 11/07/2017 | 11/07/2017 | 11/07/2017 | 11/07/2017 |
| Total Phenolics (as Phenol) | mg/kg | <5 | <5 | <5 | <5 |
| Free Cyanide in soil | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |

| Phenoxy Acid Herbicides in Soil | | | | | |
|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-36 | 170939-51 | 170939-57 | 170939-66 |
| Your Reference | ---------- - | BH30 | BH34 | Dup1 | BH19 |
| Depth | ---------- | 1.0 | 0.1 | - | 0.5 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil |
| Date extracted | - | 14/07/2017 | 14/07/2017 | 14/07/2017 | 14/07/2017 |
| Date analysed | - | 14/07/2017 | 14/07/2017 | 14/07/2017 | 14/07/2017 |
| Clopyralid | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| 3,5-Dichlorobenzoic acid | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| o-chlorophenoxy acetic acid | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| 4-CPA | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| Dicamba | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| MCPP | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| MCPA | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| Dichlorprop | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| 2,4-D | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| Bromoxynil | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| Triclopyr | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| 2,4,5-TP | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| 2,4,5-T | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| MCPB | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| Dinoseb | mg/kg | <1 | <1 | <1 | <1 |
| 2,4-DB | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| Ioxynil | mg/kg | <1 | <1 | <1 | <1 |
| Picloram | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| DCPA (Chlorthal) Diacid | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| Acifluorfen | mg/kg | <2 | <2 | <2 | <2 |
| 2,4,6-T | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| 2,6-D | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| Surrogate 2.4- DCPA | % | 96 | 98 | 102 | 102 |

| Synthetic Pyrethroids in soil | | | | | |
|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-36 | 170939-51 | 170939-57 | 170939-66 |
| Your Reference | ---------- - | BH30 | BH34 | Dup1 | BH19 |
| Depth | ---------- | 1.0 | 0.1 | - | 0.5 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil |
| Date extracted | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 14/07/2017 | 14/07/2017 | 14/07/2017 | 14/07/2017 |
| Bifenthrin | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | 114 | 116 | 116 | 112 |

| SVOCs in Soil | | | | | |
|---|---|---|---|---|---|
| Our Reference: | UNITS | 170939-36 | 170939-51 | 170939-57 | 170939-66 |
| Your Reference | ---------- | BH30 | BH34 | Dup1 | BH19 |
| Depth | - ---------- | 1.0 | 0.1 | - | 0.5 |
| Date Sampled | | 6/07/2017 | 6/07/2017 | 6/07/2017 | 6/07/2017 |
| Type of sample | | Soil | Soil | Soil | Soil |
| Date extracted | - | 13/07/2017 | 13/07/2017 | 13/07/2017 | 13/07/2017 |
| Date analysed | - | 14/07/2017 | 14/07/2017 | 14/07/2017 | 14/07/2017 |
| Toxaphene* | mg/kg | <2.0 | <2.0 | <2.0 | <2.0 |
| Mirex | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 |

| vTRH in Water (C6-C9) NEPM | | |
|---|---|---|
| Our Reference: | UNITS | 170939-61 |
| Your Reference | ---------- | Trip |
| | - | |
| Depth | ---------- | - |
| Date Sampled | | 6/07/2017 |
| Type of sample | | Water |
| Date extracted | - | 11/07/2017 |
| Date analysed | - | 12/07/2017 |
| TRHC$_{6}$ - C$_{9}$ | µg/L | <10 |
| TRHC$_{6}$ - C$_{10}$ | µg/L | <10 |
| *Surrogate* Dibromofluoromethane | % | 99 |
| *Surrogate* toluene-d8 | % | 90 |
| *Surrogate* 4-BFB | % | 92 |

| Metals in Water - Dissolved | | |
|---|---|---|
| Our Reference: | UNITS | 170939-62 |
| Your Reference | ---------- - | Rinsate |
| Depth | ---------- | - |
| Date Sampled | | 6/07/2017 |
| Type of sample | | Water |
| Date digested | - | 11/07/2017 |
| Date analysed | - | 11/07/2017 |
| Arsenic - Dissolved | mg/L | <0.05 |
| Cadmium - Dissolved | mg/L | <0.01 |
| Chromium - Dissolved | mg/L | <0.01 |
| Copper - Dissolved | mg/L | <0.01 |
| Lead - Dissolved | mg/L | <0.03 |
| Mercury - Dissolved | mg/L | <0.0005 |
| Nickel - Dissolved | mg/L | <0.02 |
| Zinc - Dissolved | mg/L | <0.02 |

| Method ID | Methodology Summary |
|---|---|
| Org-016 | Soil samples are extracted with methanol and spiked into water prior to analysing by purge and trap GC-MS. Water samples are analysed directly by purge and trap GC-MS. F1 = (C6-C10)-BTEX as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater. |
| Org-016 | Soil samples are extracted with methanol and spiked into water prior to analysing by purge and trap GC-MS. Water samples are analysed directly by purge and trap GC-MS. F1 = (C6-C10)-BTEX as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater.<br>Note, the Total +ve Xylene PQL is reflective of the lowest individual PQL and is therefore "Total +ve Xylenes" is simply a sum of the positive individual Xylenes. |
| Org-014 | Soil samples are extracted with methanol and spiked into water prior to analysing by purge and trap GC-MS. |
| Org-003 | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-FID.<br>F2 = (>C10-C16)-Naphthalene as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater (HSLs Tables 1A (3, 4)). Note Naphthalene is determined from the VOC analysis. |
| Org-003 | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-FID.<br><br>F2 = (>C10-C16)-Naphthalene as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater (HSLs Tables 1A (3, 4)). Note Naphthalene is determined from the VOC analysis.<br><br>Note, the Total +ve TRH PQL is reflective of the lowest individual PQL and is therefore "Total +ve TRH" is simply a sum of the positive individual TRH fractions (>C10-C40). |
| Org-012 | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS. Benzo(a)pyrene TEQ as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater - 2013.<br>For soil results:-<br>1. 'TEQ PQL' values are assuming all contributing PAHs reported as <PQL are actually at the PQL. This is the most conservative approach and can give false positive TEQs given that PAHs that contribute to the TEQ calculation may not be present.<br>2. 'TEQ zero' values are assuming all contributing PAHs reported as <PQL are zero. This is the least conservative approach and is more susceptible to false negative TEQs when PAHs that contribute to the TEQ calculation are present but below PQL.<br>3. 'TEQ half PQL' values are assuming all contributing PAHs reported as <PQL are half the stipulated PQL. Hence a mid-point between the most and least conservative approaches above.<br>Note, the Total +ve PAHs PQL is reflective of the lowest individual PQL and is therefore "Total +ve PAHs" is simply a sum of the positive individual PAHs. |
| Metals-020 | Determination of various metals by ICP-AES. |
| Metals-021 | Determination of Mercury by Cold Vapour AAS. |
| Inorg-008 | Moisture content determined by heating at 105+/-5 °C for a minimum of 12 hours. |
| Org-005 | Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC with dual ECD's. |
| Org-005 | Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC with dual ECD's.<br>Note, the Total +ve reported DDD+DDE+DDT PQL is reflective of the lowest individual PQL and is therefore simply a sum of the positive individually report DDD+DDE+DDT. |
| Org-008 | Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC with dual ECD's. |
| Org-006 | Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC-ECD. |

| Method ID | Methodology Summary |
|---|---|
| Org-006 | Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC-ECD.<br>Note, the Total +ve PCBs PQL is reflective of the lowest individual PQL and is therefore" Total +ve PCBs" is simply a sum of the positive individual PCBs. |
| Org-012 | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS. |
| Inorg-001 | pH - Measured using pH meter and electrode in accordance with APHA latest edition, 4500-H+. Please note that the results for water analyses are indicative only, as analysis outside of the APHA storage times. |
| Inorg-024 | Hexavalent Chromium (Cr6+) - determined colourimetrically. |
| Inorg-031 | Total Phenolics by segmented flow analyser (in line distillation with colourimetric finish).<br>Solids are extracted in a caustic media prior to analysis. |
| Inorg-014 | Cyanide - free, total, weak acid dissociable by segmented flow analyser (in line dialysis with colourimetric finish).<br>Solids are extracted in a caustic media prior to analysis. |
| Ext-054 | Analysed by MPL Envirolab |
| Org-012VIC | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS. Samples analysed at Envirolab Melbourne, NATA site accreditation no. 21192. |
| External data | Field data provided by client |

| QUALITY CONTROL<br>vTRH(C6-C10)/BTEXN in Soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br>Base ll Duplicate ll %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| Date extracted | - | | | 11/07/2017 | [NT] | [NT] | LCS-6 | 11/07/2017 |
| Date analysed | - | | | 12/07/2017 | [NT] | [NT] | LCS-6 | 12/07/2017 |
| TRHC$_6$ - C$_9$ | mg/kg | 25 | Org-016 | <25 | [NT] | [NT] | LCS-6 | 113% |
| TRHC$_6$ - C$_{10}$ | mg/kg | 25 | Org-016 | <25 | [NT] | [NT] | LCS-6 | 113% |
| Benzene | mg/kg | 0.2 | Org-016 | <0.2 | [NT] | [NT] | LCS-6 | 112% |
| Toluene | mg/kg | 0.5 | Org-016 | <0.5 | [NT] | [NT] | LCS-6 | 111% |
| Ethylbenzene | mg/kg | 1 | Org-016 | <1 | [NT] | [NT] | LCS-6 | 112% |
| m+p-xylene | mg/kg | 2 | Org-016 | <2 | [NT] | [NT] | LCS-6 | 116% |
| o-Xylene | mg/kg | 1 | Org-016 | <1 | [NT] | [NT] | LCS-6 | 115% |
| naphthalene | mg/kg | 1 | Org-014 | <1 | [NT] | [NT] | [NR] | [NR] |
| *Surrogate* aaa-Trifluorotoluene | % | | Org-016 | 97 | [NT] | [NT] | LCS-6 | 100% |

| QUALITY CONTROL<br>svTRH (C10-C40) in Soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br>Base ll Duplicate ll %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| Date extracted | - | | | 11/07/2017 | [NT] | [NT] | LCS-6 | 11/07/2017 |
| Date analysed | - | | | 12/07/2017 | [NT] | [NT] | LCS-6 | 12/07/2017 |
| TRHC$_{10}$ - C$_{14}$ | mg/kg | 50 | Org-003 | <50 | [NT] | [NT] | LCS-6 | 114% |
| TRHC$_{15}$ - C$_{28}$ | mg/kg | 100 | Org-003 | <100 | [NT] | [NT] | LCS-6 | 112% |
| TRHC$_{29}$ - C$_{36}$ | mg/kg | 100 | Org-003 | <100 | [NT] | [NT] | LCS-6 | 106% |
| TRH>C$_{10}$-C$_{16}$ | mg/kg | 50 | Org-003 | <50 | [NT] | [NT] | LCS-6 | 114% |
| TRH>C$_{16}$-C$_{34}$ | mg/kg | 100 | Org-003 | <100 | [NT] | [NT] | LCS-6 | 112% |
| TRH>C$_{34}$-C$_{40}$ | mg/kg | 100 | Org-003 | <100 | [NT] | [NT] | LCS-6 | 106% |
| *Surrogate* o-Terphenyl | % | | Org-003 | 91 | [NT] | [NT] | LCS-6 | 119% |

| QUALITY CONTROL<br>PAHs in Soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br>Base ll Duplicate ll %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| Date extracted | - | | | 11/07/2017 | [NT] | [NT] | LCS-6 | 11/07/2017 |
| Date analysed | - | | | 12/07/2017 | [NT] | [NT] | LCS-6 | 12/07/2017 |
| Naphthalene | mg/kg | 0.1 | Org-012 | <0.1 | [NT] | [NT] | LCS-6 | 112% |
| Acenaphthylene | mg/kg | 0.1 | Org-012 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Acenaphthene | mg/kg | 0.1 | Org-012 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Fluorene | mg/kg | 0.1 | Org-012 | <0.1 | [NT] | [NT] | LCS-6 | 100% |
| Phenanthrene | mg/kg | 0.1 | Org-012 | <0.1 | [NT] | [NT] | LCS-6 | 106% |
| Anthracene | mg/kg | 0.1 | Org-012 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Fluoranthene | mg/kg | 0.1 | Org-012 | <0.1 | [NT] | [NT] | LCS-6 | 103% |
| Pyrene | mg/kg | 0.1 | Org-012 | <0.1 | [NT] | [NT] | LCS-6 | 102% |
| Benzo(a)anthracene | mg/kg | 0.1 | Org-012 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Chrysene | mg/kg | 0.1 | Org-012 | <0.1 | [NT] | [NT] | LCS-6 | 123% |
| Benzo(b,j+k) fluoranthene | mg/kg | 0.2 | Org-012 | <0.2 | [NT] | [NT] | [NR] | [NR] |

| QUALITY CONTROL<br><br>PAHs in Soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br><br>Base ll Duplicate ll %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| Benzo(a)pyrene | mg/kg | 0.05 | Org-012 | <0.05 | [NT] | [NT] | LCS-6 | 100% |
| Indeno(1,2,3-c,d)pyrene | mg/kg | 0.1 | Org-012 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Dibenzo(a,h)anthracene | mg/kg | 0.1 | Org-012 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Benzo(g,h,i)perylene | mg/kg | 0.1 | Org-012 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| *Surrogate p*-Terphenyl-d14 | % | | Org-012 | 84 | [NT] | [NT] | LCS-6 | 118% |
| QUALITY CONTROL<br><br>Acid Extractractable metals in soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br><br>Base ll Duplicate ll %RPD | Spike Sm# | Spike % Recovery |
| Date prepared | - | | | 13/07/2017 | 170939-1 | 13/07/2017 \|\| 13/07/2017 | LCS-6 | 13/07/2017 |
| Date analysed | - | | | 13/07/2017 | 170939-1 | 13/07/2017 \|\| 13/07/2017 | LCS-6 | 13/07/2017 |
| Arsenic | mg/kg | 4 | Metals-020 | <4 | 170939-1 | 8 \|\| 11 \|\| RPD: 32 | LCS-6 | 106% |
| Beryllium | mg/kg | 1 | Metals-020 | <1 | [NT] | [NT] | LCS-6 | 94% |
| Boron | mg/kg | 3 | Metals-020 | <3 | [NT] | [NT] | LCS-6 | 101% |
| Cadmium | mg/kg | 0.4 | Metals-020 | <0.4 | 170939-1 | <0.4 \|\| <0.4 | LCS-6 | 101% |
| Chromium | mg/kg | 1 | Metals-020 | <1 | 170939-1 | 12 \|\| 16 \|\| RPD: 29 | LCS-6 | 105% |
| Cobalt | mg/kg | 1 | Metals-020 | <1 | [NT] | [NT] | LCS-6 | 99% |
| Copper | mg/kg | 1 | Metals-020 | <1 | 170939-1 | 21 \|\| 36 \|\| RPD: 53 | LCS-6 | 105% |
| Lead | mg/kg | 1 | Metals-020 | <1 | 170939-1 | 89 \|\| 170 \|\| RPD: 63 | LCS-6 | 100% |
| Manganese | mg/kg | 1 | Metals-020 | <1 | [NT] | [NT] | LCS-6 | 125% |
| Mercury | mg/kg | 0.1 | Metals-021 | <0.1 | 170939-1 | 0.2 \|\| 0.2 \|\| RPD: 0 | LCS-6 | 107% |
| Nickel | mg/kg | 1 | Metals-020 | <1 | 170939-1 | 9 \|\| 15 \|\| RPD: 50 | LCS-6 | 99% |
| Selenium | mg/kg | 2 | Metals-020 | <2 | [NT] | [NT] | LCS-6 | 98% |
| Zinc | mg/kg | 1 | Metals-020 | <1 | 170939-1 | 84 \|\| 110 \|\| RPD: 27 | LCS-6 | 101% |

| QUALITY CONTROL<br><br>Organochlorine Pesticides in soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br><br>Base II Duplicate II %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| Date extracted | - | | | 11/07/2017 | [NT] | [NT] | LCS-6 | 11/07/2017 |
| Date analysed | - | | | 11/07/2017 | [NT] | [NT] | LCS-6 | 11/07/2017 |
| HCB | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| alpha-BHC | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | LCS-6 | 70% |
| gamma-BHC | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| beta-BHC | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | LCS-6 | 103% |
| Heptachlor | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | LCS-6 | 105% |
| delta-BHC | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Aldrin | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | LCS-6 | 102% |
| Heptachlor Epoxide | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | LCS-6 | 105% |
| gamma-Chlordane | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| alpha-chlordane | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Endosulfan I | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| pp-DDE | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | LCS-6 | 112% |
| Dieldrin | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | LCS-6 | 114% |
| Endrin | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | LCS-6 | 101% |
| pp-DDD | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | LCS-6 | 108% |
| Endosulfan II | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| pp-DDT | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Endrin Aldehyde | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Endosulfan Sulphate | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Methoxychlor | mg/kg | 0.1 | Org-005 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| *Surrogate* TCMX | % | | Org-005 | 101 | [NT] | [NT] | LCS-6 | 117% |

| QUALITY CONTROL<br><br>Organophosphorus Pesticides | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br><br>Base ll Duplicate ll %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| Date extracted | - | | | 11/07/2017 | [NT] | [NT] | LCS-6 | 11/07/2017 |
| Date analysed | - | | | 11/07/2017 | [NT] | [NT] | LCS-6 | 11/07/2017 |
| Azinphos-methyl (Guthion) | mg/kg | 0.1 | Org-008 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Bromophos-ethyl | mg/kg | 0.1 | Org-008 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Chlorpyriphos | mg/kg | 0.1 | Org-008 | <0.1 | [NT] | [NT] | LCS-6 | 87% |
| Chlorpyriphos-methyl | mg/kg | 0.1 | Org-008 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Diazinon | mg/kg | 0.1 | Org-008 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Dichlorvos | mg/kg | 0.1 | Org-008 | <0.1 | [NT] | [NT] | LCS-6 | 80% |
| Dimethoate | mg/kg | 0.1 | Org-008 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Ethion | mg/kg | 0.1 | Org-008 | <0.1 | [NT] | [NT] | LCS-6 | 107% |
| Fenitrothion | mg/kg | 0.1 | Org-008 | <0.1 | [NT] | [NT] | LCS-6 | 83% |
| Malathion | mg/kg | 0.1 | Org-008 | <0.1 | [NT] | [NT] | LCS-6 | 72% |
| Parathion | mg/kg | 0.1 | Org-008 | <0.1 | [NT] | [NT] | LCS-6 | 84% |
| Ronnel | mg/kg | 0.1 | Org-008 | <0.1 | [NT] | [NT] | LCS-6 | 98% |
| *Surrogate* TCMX | % | | Org-008 | 101 | [NT] | [NT] | LCS-6 | 95% |

| QUALITY CONTROL<br><br>PCBs in Soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br><br>Base ll Duplicate ll %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| Date extracted | - | | | 11/07/2017 | [NT] | [NT] | LCS-6 | 11/07/2017 |
| Date analysed | - | | | 11/07/2017 | [NT] | [NT] | LCS-6 | 11/07/2017 |
| Aroclor 1016 | mg/kg | 0.1 | Org-006 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1221 | mg/kg | 0.1 | Org-006 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1232 | mg/kg | 0.1 | Org-006 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1242 | mg/kg | 0.1 | Org-006 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1248 | mg/kg | 0.1 | Org-006 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1254 | mg/kg | 0.1 | Org-006 | <0.1 | [NT] | [NT] | LCS-6 | 105% |
| Aroclor 1260 | mg/kg | 0.1 | Org-006 | <0.1 | [NT] | [NT] | [NR] | [NR] |
| *Surrogate* TCLMX | % | | Org-006 | 101 | [NT] | [NT] | LCS-6 | 95% |

| QUALITY CONTROL<br><br>Triazine Herbicides in Soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br><br>Base II Duplicate II %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| Date prepared | - | | | 11/07/2017 | [NT] | [NT] | LCS-6 | 11/07/2017 |
| Date analysed | - | | | 11/07/2017 | [NT] | [NT] | LCS-6 | 11/07/2017 |
| Atrazine | mg/kg | 0.5 | Org-012 | <0.5 | [NT] | [NT] | LCS-6 | 92% |
| Ametryn | mg/kg | 0.5 | Org-012 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| Cyanazine | mg/kg | 0.5 | Org-012 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| Hexazinone | mg/kg | 0.5 | Org-012 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| Irgarol | mg/kg | 0.5 | Org-012 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| Metribuzin | mg/kg | 0.5 | Org-012 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| Prometryn | mg/kg | 0.5 | Org-012 | <0.5 | [NT] | [NT] | LCS-6 | 96% |
| Propazine | mg/kg | 0.5 | Org-012 | <0.5 | [NT] | [NT] | LCS-6 | 98% |
| Simazine | mg/kg | 0.5 | Org-012 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| Terbutryn | mg/kg | 0.5 | Org-012 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| Terbuthylazine | mg/kg | 0.5 | Org-012 | <0.5 | [NT] | [NT] | [NR] | [NR] |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | | Org-012 | 95 | [NT] | [NT] | LCS-6 | 93% |

| QUALITY CONTROL<br><br>Speciated Phenols in Soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br><br>Base II Duplicate II %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| Date extracted | - | | | 11/07/2017 | [NT] | [NT] | LCS-6 | 11/07/2017 |
| Date analysed | - | | | 12/07/2017 | [NT] | [NT] | LCS-6 | 12/07/2017 |
| Phenol | mg/kg | 0.2 | Org-012 | <0.2 | [NT] | [NT] | LCS-6 | 72% |
| 2-Chlorophenol | mg/kg | 0.2 | Org-012 | <0.2 | [NT] | [NT] | LCS-6 | 86% |
| 4-Chloro-3-methylphenol | mg/kg | 1 | Org-012 | <1 | [NT] | [NT] | [NR] | [NR] |
| 2-Methylphenol (o-cresol) | mg/kg | 0.2 | Org-012 | <0.2 | [NT] | [NT] | LCS-6 | 102% |
| 3/4-Methylphenol (m/p-cresol) | mg/kg | 0.4 | Org-012 | <0.4 | [NT] | [NT] | [NR] | [NR] |
| 2-Nitrophenol | mg/kg | 0.2 | Org-012 | <0.2 | [NT] | [NT] | [NR] | [NR] |
| 2,4-Dimethylphenol | mg/kg | 0.2 | Org-012 | <0.2 | [NT] | [NT] | [NR] | [NR] |
| 2,4-Dichlorophenol | mg/kg | 0.2 | Org-012 | <0.2 | [NT] | [NT] | [NR] | [NR] |
| 2,6-Dichlorophenol | mg/kg | 0.2 | Org-012 | <0.2 | [NT] | [NT] | LCS-6 | 98% |
| 2,4,5-Trichlorophenol | mg/kg | 0.2 | Org-012 | <0.2 | [NT] | [NT] | [NR] | [NR] |
| 2,4,6-Trichlorophenol | mg/kg | 0.2 | Org-012 | <0.2 | [NT] | [NT] | [NR] | [NR] |
| 2,4-Dinitrophenol | mg/kg | 4 | Org-012 | <4 | [NT] | [NT] | [NR] | [NR] |
| 4-Nitrophenol | mg/kg | 4 | Org-012 | <4 | [NT] | [NT] | LCS-6 | 100% |
| 2346-Tetrachlorophenol | mg/kg | 0.2 | Org-012 | <0.2 | [NT] | [NT] | [NR] | [NR] |
| 2-methyl-4,6-Dinitrophenol | mg/kg | 2 | Org-012 | <2 | [NT] | [NT] | [NR] | [NR] |
| Pentachlorophenol | mg/kg | 1 | Org-012 | <1 | [NT] | [NT] | LCS-6 | 114% |
| *Surrogate* 2-fluorophenol | % | | Org-012 | 87 | [NT] | [NT] | LCS-6 | 99% |
| *Surrogate* Phenol-$d_6$ | % | | Org-012 | 79 | [NT] | [NT] | LCS-6 | 112% |
| *Surrogate 2,4,6*-Tribromophenol | % | | Org-012 | 108 | [NT] | [NT] | LCS-6 | 128% |

| QUALITY CONTROL<br>Speciated Phenols in Soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br>Base ll Duplicate ll %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|---|---|---|
| *Surrogate p*-Terphenyl-$d_{14}$ | % | | Org-012 | 87 | [NT] | [NT] | LCS-6 | 100% |
| QUALITY CONTROL<br>Misc Inorg - Soil | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br>Base ll Duplicate ll %RPD | Spike Sm# | Spike % Recovery |
| Date prepared | - | | | 13/07/2017 | [NT] | [NT] | LCS-6 | 13/07/2017 |
| Date analysed | - | | | 13/07/2017 | [NT] | [NT] | LCS-6 | 13/07/2017 |
| pH 1:5 soil:water | pH Units | | Inorg-001 | [NT] | [NT] | [NT] | LCS-6 | 101% |
| QUALITY CONTROL<br>Misc Soil - Inorg | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br>Base ll Duplicate ll %RPD | Spike Sm# | Spike % Recovery |
| Date prepared | - | | | 14/07/2017 | [NT] | [NT] | LCS-6 | 14/07/2017 |
| Date analysed | - | | | 14/07/2017 | [NT] | [NT] | LCS-6 | 14/07/2017 |
| Hexavalent Chromium, $Cr^{6+}$ | mg/kg | 1 | Inorg-024 | <1 | [NT] | [NT] | LCS-6 | 86% |
| QUALITY CONTROL<br>Misc Soil - Inorg | UNITS | PQL | METHOD | Blank | Duplicate Sm# | Duplicate results<br>Base ll Duplicate ll %RPD | Spike Sm# | Spike % Recovery |
| Date prepared | - | | | 11/07/2017 | [NT] | [NT] | LCS-6 | 11/07/2017 |
| Date analysed | - | | | 11/07/2017 | [NT] | [NT] | LCS-6 | 11/07/2017 |
| Total Phenolics (as Phenol) | mg/kg | 5 | Inorg-031 | <5 | [NT] | [NT] | LCS-6 | 97% |
| Free Cyanide in soil | mg/kg | 0.5 | Inorg-014 | <0.5 | [NT] | [NT] | LCS-6 | 102% |

| QUALITY CONTROL<br>Phenoxy Acid Herbicides in Soil | UNITS | PQL | METHOD | Blank |
|---|---|---|---|---|
| Date extracted | - | | | 14/07/2017 |
| Date analysed | - | | | 14/07/2017 |
| Clopyralid | mg/kg | 0.5 | Ext-054 | <0.5 |
| 3,5-Dichlorobenzoic acid | mg/kg | 0.5 | Ext-054 | <0.5 |
| o-chlorophenoxy acetic acid | mg/kg | 0.5 | Ext-054 | <0.5 |
| 4-CPA | mg/kg | 0.5 | Ext-054 | <0.5 |
| Dicamba | mg/kg | 0.5 | Ext-054 | <0.5 |
| MCPP | mg/kg | 0.5 | Ext-054 | <0.5 |
| MCPA | mg/kg | 0.5 | Ext-054 | <0.5 |
| Dichlorprop | mg/kg | 0.5 | Ext-054 | <0.5 |
| 2,4-D | mg/kg | 0.5 | Ext-054 | <0.5 |
| Bromoxynil | mg/kg | 0.5 | Ext-054 | <0.5 |
| Triclopyr | mg/kg | 0.5 | Ext-054 | <0.5 |
| 2,4,5-TP | mg/kg | 0.5 | Ext-054 | <0.5 |

| QUALITY CONTROL Phenoxy Acid Herbicides in Soil | UNITS | PQL | METHOD | Blank |
|---|---|---|---|---|
| 2,4,5-T | mg/kg | 0.5 | Ext-054 | <0.5 |
| MCPB | mg/kg | 0.5 | Ext-054 | <0.5 |
| Dinoseb | mg/kg | 1 | Ext-054 | <1 |
| 2,4-DB | mg/kg | 0.5 | Ext-054 | <0.5 |
| Ioxynil | mg/kg | 1 | Ext-054 | <1 |
| Picloram | mg/kg | 0.5 | Ext-054 | <0.5 |
| DCPA (Chlorthal) Diacid | mg/kg | 0.5 | Ext-054 | <0.5 |
| Acifluorfen | mg/kg | 2 | Ext-054 | <2 |
| 2,4,6-T | mg/kg | 0.5 | Ext-054 | <0.5 |
| 2,6-D | mg/kg | 0.5 | Ext-054 | <0.5 |
| Surrogate 2.4- DCPA | % | | Ext-054 | 102 |
| QUALITY CONTROL Synthetic Pyrethroids in soil | UNITS | PQL | METHOD | Blank |
| Date extracted | - | | Org-012VIC | 13/07/2017 |
| Date analysed | - | | Org-012VIC | 14/07/2017 |
| Bifenthrin | mg/kg | 0.5 | Org-012VIC | <0.5 |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | | Org-012 | 108 |
| QUALITY CONTROL SVOCs in Soil | UNITS | PQL | METHOD | Blank |
| Date extracted | - | | | 13/07/2017 |
| Date analysed | - | | | 14/07/2017 |
| Toxaphene* | mg/kg | 2 | External data | <2.0 |
| Mirex | mg/kg | 0.5 | External data | <0.5 |
| QUALITY CONTROL vTRH in Water (C6-C9) NEPM | UNITS | PQL | METHOD | Blank |
| Date extracted | - | | | 11/07/2017 |
| Date analysed | - | | | 12/07/2017 |
| $TRHC_6$ - $C_9$ | µg/L | 10 | Org-016 | <10 |
| $TRHC_6$ - $C_{10}$ | µg/L | 10 | Org-016 | <10 |
| *Surrogate* Dibromofluoromethane | % | | Org-016 | 97 |
| *Surrogate* toluene-d8 | % | | Org-016 | 91 |
| *Surrogate* 4-BFB | % | | Org-016 | 94 |

| QUALITY CONTROL Metals in Water - Dissolved | UNITS | PQL | METHOD | Blank |
|---|---|---|---|---|
| Date digested | - | | | 11/07/2017 |
| Date analysed | - | | | 11/07/2017 |
| Arsenic - Dissolved | mg/L | 0.05 | Metals-020 | <0.05 |
| Cadmium - Dissolved | mg/L | 0.01 | Metals-020 | <0.01 |
| Chromium - Dissolved | mg/L | 0.01 | Metals-020 | <0.01 |
| Copper - Dissolved | mg/L | 0.01 | Metals-020 | <0.01 |
| Lead - Dissolved | mg/L | 0.03 | Metals-020 | <0.03 |
| Mercury - Dissolved | mg/L | 0.0005 | Metals-021 | <0.0005 |
| Nickel - Dissolved | mg/L | 0.02 | Metals-020 | <0.02 |
| Zinc - Dissolved | mg/L | 0.02 | Metals-020 | <0.02 |

| QUALITY CONTROL PAHs in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Date extracted | - | [NT] | [NT] | LCS-7 | 11/07/2017 |
| Date analysed | - | [NT] | [NT] | LCS-7 | 12/07/2017 |
| Naphthalene | mg/kg | [NT] | [NT] | LCS-7 | 112% |
| Acenaphthylene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Acenaphthene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Fluorene | mg/kg | [NT] | [NT] | LCS-7 | 100% |
| Phenanthrene | mg/kg | [NT] | [NT] | LCS-7 | 107% |
| Anthracene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Fluoranthene | mg/kg | [NT] | [NT] | LCS-7 | 105% |
| Pyrene | mg/kg | [NT] | [NT] | LCS-7 | 103% |
| Benzo(a)anthracene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Chrysene | mg/kg | [NT] | [NT] | LCS-7 | 122% |
| Benzo(b,j+k)fluoranthene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Benzo(a)pyrene | mg/kg | [NT] | [NT] | LCS-7 | 99% |
| Indeno(1,2,3-c,d)pyrene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Dibenzo(a,h)anthracene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Benzo(g,h,i)perylene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| *Surrogate p*-Terphenyl-d14 | % | [NT] | [NT] | LCS-7 | 120% |

| QUALITY CONTROL Acid Extractractable metals in soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Date prepared | - | 170939-11 | 13/07/2017 \|\| 13/07/2017 | LCS-7 | 13/07/2017 |
| Date analysed | - | 170939-11 | 13/07/2017 \|\| 13/07/2017 | LCS-7 | 13/07/2017 |
| Arsenic | mg/kg | 170939-11 | <4 \|\| <4 | LCS-7 | 104% |
| Beryllium | mg/kg | [NT] | [NT] | LCS-7 | 93% |
| Boron | mg/kg | [NT] | [NT] | LCS-7 | 99% |
| Cadmium | mg/kg | 170939-11 | <0.4 \|\| <0.4 | LCS-7 | 101% |
| Chromium | mg/kg | 170939-11 | 14 \|\| 10 \|\| RPD: 33 | LCS-7 | 104% |
| Cobalt | mg/kg | [NT] | [NT] | LCS-7 | 98% |
| Copper | mg/kg | 170939-11 | 9 \|\| 9 \|\| RPD: 0 | LCS-7 | 104% |
| Lead | mg/kg | 170939-11 | 12 \|\| 10 \|\| RPD: 18 | LCS-7 | 100% |
| Manganese | mg/kg | [NT] | [NT] | LCS-7 | 119% |
| Mercury | mg/kg | 170939-11 | 2.7 \|\| 2.4 \|\| RPD: 12 | LCS-7 | 105% |
| Nickel | mg/kg | 170939-11 | 4 \|\| 3 \|\| RPD: 29 | LCS-7 | 99% |
| Selenium | mg/kg | [NT] | [NT] | LCS-7 | 97% |
| Zinc | mg/kg | 170939-11 | 19 \|\| 14 \|\| RPD: 30 | LCS-7 | 100% |

| QUALITY CONTROL Organochlorine Pesticides in soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Date extracted | - | [NT] | [NT] | LCS-7 | 11/07/2017 |
| Date analysed | - | [NT] | [NT] | LCS-7 | 11/07/2017 |
| HCB | mg/kg | [NT] | [NT] | [NR] | [NR] |
| alpha-BHC | mg/kg | [NT] | [NT] | LCS-7 | 82% |
| gamma-BHC | mg/kg | [NT] | [NT] | [NR] | [NR] |
| beta-BHC | mg/kg | [NT] | [NT] | LCS-7 | 108% |
| Heptachlor | mg/kg | [NT] | [NT] | LCS-7 | 114% |
| delta-BHC | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Aldrin | mg/kg | [NT] | [NT] | LCS-7 | 105% |
| Heptachlor Epoxide | mg/kg | [NT] | [NT] | LCS-7 | 107% |
| gamma-Chlordane | mg/kg | [NT] | [NT] | [NR] | [NR] |
| alpha-chlordane | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Endosulfan I | mg/kg | [NT] | [NT] | [NR] | [NR] |
| pp-DDE | mg/kg | [NT] | [NT] | LCS-7 | 109% |
| Dieldrin | mg/kg | [NT] | [NT] | LCS-7 | 118% |
| Endrin | mg/kg | [NT] | [NT] | LCS-7 | 108% |
| pp-DDD | mg/kg | [NT] | [NT] | LCS-7 | 119% |
| Endosulfan II | mg/kg | [NT] | [NT] | [NR] | [NR] |
| pp-DDT | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Endrin Aldehyde | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Endosulfan Sulphate | mg/kg | [NT] | [NT] | LCS-7 | 100% |
| Methoxychlor | mg/kg | [NT] | [NT] | [NR] | [NR] |
| *Surrogate* TCMX | % | [NT] | [NT] | LCS-7 | 118% |

| QUALITY CONTROL Organophosphorus Pesticides | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Date extracted | - | [NT] | [NT] | LCS-7 | 11/07/2017 |
| Date analysed | - | [NT] | [NT] | LCS-7 | 11/07/2017 |
| Azinphos-methyl (Guthion) | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Bromophos-ethyl | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Chlorpyriphos | mg/kg | [NT] | [NT] | LCS-7 | 99% |
| Chlorpyriphos-methyl | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Diazinon | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Dichlorvos | mg/kg | [NT] | [NT] | LCS-7 | 88% |
| Dimethoate | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Ethion | mg/kg | [NT] | [NT] | LCS-7 | 102% |
| Fenitrothion | mg/kg | [NT] | [NT] | LCS-7 | 96% |
| Malathion | mg/kg | [NT] | [NT] | LCS-7 | 74% |
| Parathion | mg/kg | [NT] | [NT] | LCS-7 | 108% |
| Ronnel | mg/kg | [NT] | [NT] | LCS-7 | 106% |
| *Surrogate* TCMX | % | [NT] | [NT] | LCS-7 | 102% |
| QUALITY CONTROL PCBs in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
| Date extracted | - | [NT] | [NT] | LCS-7 | 11/07/2017 |
| Date analysed | - | [NT] | [NT] | LCS-7 | 11/07/2017 |
| Aroclor 1016 | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1221 | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1232 | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1242 | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1248 | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1254 | mg/kg | [NT] | [NT] | LCS-7 | 101% |
| Aroclor 1260 | mg/kg | [NT] | [NT] | [NR] | [NR] |
| *Surrogate* TCLMX | % | [NT] | [NT] | LCS-7 | 102% |
| QUALITY CONTROL Acid Extractractable metals in soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
| Date prepared | - | 170939-21 | 13/07/2017 \|\| 13/07/2017 | LCS-8 | 13/07/2017 |
| Date analysed | - | 170939-21 | 13/07/2017 \|\| 13/07/2017 | LCS-8 | 13/07/2017 |
| Arsenic | mg/kg | 170939-21 | 22 \|\| 15 \|\| RPD: 38 | LCS-8 | 110% |
| Beryllium | mg/kg | [NT] | [NT] | LCS-8 | 96% |
| Boron | mg/kg | [NT] | [NT] | LCS-8 | 104% |
| Cadmium | mg/kg | 170939-21 | <0.4 \|\| <0.4 | LCS-8 | 105% |
| Chromium | mg/kg | 170939-21 | 16 \|\| 12 \|\| RPD: 29 | LCS-8 | 110% |
| Cobalt | mg/kg | [NT] | [NT] | LCS-8 | 105% |
| Copper | mg/kg | 170939-21 | 15 \|\| 13 \|\| RPD: 14 | LCS-8 | 109% |
| Lead | mg/kg | 170939-21 | 87 \|\| 61 \|\| RPD: 35 | LCS-8 | 104% |
| Manganese | mg/kg | [NT] | [NT] | LCS-8 | 124% |

| QUALITY CONTROL Acid Extractractable metals in soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Mercury | mg/kg | 170939-21 | 0.2 \|\| 0.2 \|\| RPD: 0 | LCS-8 | 105% |
| Nickel | mg/kg | 170939-21 | 3 \|\| 2 \|\| RPD: 40 | LCS-8 | 103% |
| Selenium | mg/kg | [NT] | [NT] | LCS-8 | 102% |
| Zinc | mg/kg | 170939-21 | 66 \|\| 61 \|\| RPD: 8 | LCS-8 | 105% |
| QUALITY CONTROL Acid Extractractable metals in soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
| Date prepared | - | 170939-31 | 13/07/2017 \|\| 13/07/2017 | LCS-9 | 13/07/2017 |
| Date analysed | - | 170939-31 | 13/07/2017 \|\| 13/07/2017 | LCS-9 | 13/07/2017 |
| Arsenic | mg/kg | 170939-31 | 5 \|\| 4 \|\| RPD: 22 | LCS-9 | 108% |
| Beryllium | mg/kg | [NT] | [NT] | LCS-9 | 93% |
| Boron | mg/kg | [NT] | [NT] | LCS-9 | 102% |
| Cadmium | mg/kg | 170939-31 | <0.4 \|\| <0.4 | LCS-9 | 104% |
| Chromium | mg/kg | 170939-31 | 21 \|\| 17 \|\| RPD: 21 | LCS-9 | 107% |
| Cobalt | mg/kg | [NT] | [NT] | LCS-9 | 102% |
| Copper | mg/kg | 170939-31 | 21 \|\| 23 \|\| RPD: 9 | LCS-9 | 107% |
| Lead | mg/kg | 170939-31 | 220 \|\| 200 \|\| RPD: 10 | LCS-9 | 103% |
| Manganese | mg/kg | [NT] | [NT] | LCS-9 | 125% |
| Mercury | mg/kg | 170939-31 | 0.2 \|\| 0.2 \|\| RPD: 0 | LCS-9 | 118% |
| Nickel | mg/kg | 170939-31 | 5 \|\| 7 \|\| RPD: 33 | LCS-9 | 102% |
| Selenium | mg/kg | [NT] | [NT] | LCS-9 | 100% |
| Zinc | mg/kg | 170939-31 | 110 \|\| 130 \|\| RPD: 17 | LCS-9 | 103% |

| QUALITY CONTROL vTRH(C6-C10)/BTEXN in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD |
|---|---|---|---|
| Date extracted | - | 170939-36 | 11/07/2017 \|\| 11/07/2017 |
| Date analysed | - | 170939-36 | 12/07/2017 \|\| 12/07/2017 |
| TRHC$_6$ - C$_9$ | mg/kg | 170939-36 | <25 \|\| <25 |
| TRHC$_6$ - C$_{10}$ | mg/kg | 170939-36 | <25 \|\| <25 |
| Benzene | mg/kg | 170939-36 | <0.2 \|\| <0.2 |
| Toluene | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| Ethylbenzene | mg/kg | 170939-36 | <1 \|\| <1 |
| m+p-xylene | mg/kg | 170939-36 | <2 \|\| <2 |
| o-Xylene | mg/kg | 170939-36 | <1 \|\| <1 |
| naphthalene | mg/kg | 170939-36 | <1 \|\| <1 |
| *Surrogate* aaa-Trifluorotoluene | % | 170939-36 | 96 \|\| 84 \|\| RPD: 13 |

| QUALITY CONTROL svTRH (C10-C40) in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD |
|---|---|---|---|
| Date extracted | - | 170939-36 | 11/07/2017 \|\| 11/07/2017 |
| Date analysed | - | 170939-36 | 12/07/2017 \|\| 12/07/2017 |
| TRHC$_{10}$ - C$_{14}$ | mg/kg | 170939-36 | <50 \|\| <50 |
| TRHC$_{15}$ - C$_{28}$ | mg/kg | 170939-36 | <100 \|\| <100 |
| TRHC$_{29}$ - C$_{36}$ | mg/kg | 170939-36 | <100 \|\| <100 |
| TRH>C$_{10}$-C$_{16}$ | mg/kg | 170939-36 | <50 \|\| <50 |
| TRH>C$_{16}$-C$_{34}$ | mg/kg | 170939-36 | <100 \|\| <100 |
| TRH>C$_{34}$-C$_{40}$ | mg/kg | 170939-36 | <100 \|\| <100 |
| *Surrogate* o-Terphenyl | % | 170939-36 | 89 \|\| 88 \|\| RPD: 1 |

| QUALITY CONTROL PAHs in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Date extracted | - | 170939-36 | 11/07/2017 \|\| 11/07/2017 | 170939-2 | 11/07/2017 |
| Date analysed | - | 170939-36 | 12/07/2017 \|\| 12/07/2017 | 170939-2 | 12/07/2017 |
| Naphthalene | mg/kg | 170939-36 | <0.1 \|\| <0.1 | 170939-2 | 100% |
| Acenaphthylene | mg/kg | 170939-36 | 0.4 \|\| 0.1 \|\| RPD: 120 | [NR] | [NR] |
| Acenaphthene | mg/kg | 170939-36 | <0.1 \|\| <0.1 | [NR] | [NR] |
| Fluorene | mg/kg | 170939-36 | <0.1 \|\| <0.1 | 170939-2 | 91% |
| Phenanthrene | mg/kg | 170939-36 | 0.9 \|\| 0.8 \|\| RPD: 12 | 170939-2 | 108% |
| Anthracene | mg/kg | 170939-36 | 0.4 \|\| 0.3 \|\| RPD: 29 | [NR] | [NR] |
| Fluoranthene | mg/kg | 170939-36 | 3.5 \|\| 3.4 \|\| RPD: 3 | 170939-2 | 109% |
| Pyrene | mg/kg | 170939-36 | 3.9 \|\| 3.9 \|\| RPD: 0 | 170939-2 | 111% |
| Benzo(a)anthracene | mg/kg | 170939-36 | 2.0 \|\| 2.3 \|\| RPD: 14 | [NR] | [NR] |
| Chrysene | mg/kg | 170939-36 | 2.1 \|\| 2.1 \|\| RPD: 0 | 170939-2 | 119% |
| Benzo(b,j+k)fluoranthene | mg/kg | 170939-36 | 3.4 \|\| 3.7 \|\| RPD: 8 | [NR] | [NR] |
| Benzo(a)pyrene | mg/kg | 170939-36 | 2.2 \|\| 2.4 \|\| RPD: 9 | 170939-2 | 105% |
| Indeno(1,2,3-c,d)pyrene | mg/kg | 170939-36 | 1.2 \|\| 1.4 \|\| RPD: 15 | [NR] | [NR] |
| Dibenzo(a,h)anthracene | mg/kg | 170939-36 | 0.3 \|\| 0.4 \|\| RPD: 29 | [NR] | [NR] |
| Benzo(g,h,i)perylene | mg/kg | 170939-36 | 1.6 \|\| 1.9 \|\| RPD: 17 | [NR] | [NR] |
| *Surrogate p*-Terphenyl-d14 | % | 170939-36 | 81 \|\| 82 \|\| RPD: 1 | 170939-2 | 103% |

| QUALITY CONTROL Acid Extractractable metals in soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Date prepared | - | [NT] | [NT] | 170939-2 | 13/07/2017 |
| Date analysed | - | [NT] | [NT] | 170939-2 | 13/07/2017 |
| Arsenic | mg/kg | [NT] | [NT] | 170939-2 | 80% |
| Beryllium | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Boron | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Cadmium | mg/kg | [NT] | [NT] | 170939-2 | 97% |
| Chromium | mg/kg | [NT] | [NT] | 170939-2 | 101% |
| Cobalt | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Copper | mg/kg | [NT] | [NT] | 170939-2 | 102% |
| Lead | mg/kg | [NT] | [NT] | 170939-2 | 98% |
| Manganese | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Mercury | mg/kg | [NT] | [NT] | 170939-2 | 117% |
| Nickel | mg/kg | [NT] | [NT] | 170939-2 | 95% |
| Selenium | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Zinc | mg/kg | [NT] | [NT] | 170939-2 | 96% |

| QUALITY CONTROL Organochlorine Pesticides in soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD |
|---|---|---|---|
| Date extracted | - | 170939-36 | 11/07/2017 \|\| 11/07/2017 |
| Date analysed | - | 170939-36 | 11/07/2017 \|\| 11/07/2017 |
| HCB | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| alpha-BHC | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| gamma-BHC | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| beta-BHC | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Heptachlor | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| delta-BHC | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Aldrin | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Heptachlor Epoxide | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| gamma-Chlordane | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| alpha-chlordane | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Endosulfan I | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| pp-DDE | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Dieldrin | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Endrin | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| pp-DDD | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Endosulfan II | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| pp-DDT | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Endrin Aldehyde | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Endosulfan Sulphate | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Methoxychlor | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| *Surrogate* TCMX | % | 170939-36 | 102 \|\| 97 \|\| RPD: 5 |

| QUALITY CONTROL Organophosphorus Pesticides | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD |
|---|---|---|---|
| Date extracted | - | 170939-36 | 11/07/2017 \|\| 11/07/2017 |
| Date analysed | - | 170939-36 | 11/07/2017 \|\| 11/07/2017 |
| Azinphos-methyl (Guthion) | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Bromophos-ethyl | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Chlorpyriphos | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Chlorpyriphos-methyl | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Diazinon | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Dichlorvos | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Dimethoate | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Ethion | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Fenitrothion | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Malathion | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Parathion | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Ronnel | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| *Surrogate* TCMX | % | 170939-36 | 102 \|\| 97 \|\| RPD: 5 |
| QUALITY CONTROL PCBs in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD |
| Date extracted | - | 170939-36 | 11/07/2017 \|\| 11/07/2017 |
| Date analysed | - | 170939-36 | 11/07/2017 \|\| 11/07/2017 |
| Aroclor 1016 | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Aroclor 1221 | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Aroclor 1232 | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Aroclor 1242 | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Aroclor 1248 | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Aroclor 1254 | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| Aroclor 1260 | mg/kg | 170939-36 | <0.1 \|\| <0.1 |
| *Surrogate* TCLMX | % | 170939-36 | 102 \|\| 97 \|\| RPD: 5 |
| QUALITY CONTROL Triazine Herbicides in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD |
| Date prepared | - | 170939-36 | 11/07/2017 \|\| 11/07/2017 |
| Date analysed | - | 170939-36 | 11/07/2017 \|\| 11/07/2017 |
| Atrazine | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| Ametryn | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| Cyanazine | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| Hexazinone | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| Irgarol | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| Metribuzin | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| Prometryn | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| Propazine | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| Simazine | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| Terbutryn | mg/kg | 170939-36 | <0.5 \|\| <0.5 |

| QUALITY CONTROL Triazine Herbicides in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD |
|---|---|---|---|
| Terbuthylazine | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | 170939-36 | 93 \|\| 93 \|\| RPD: 0 |
| **QUALITY CONTROL Speciated Phenols in Soil** | **UNITS** | **Dup. Sm#** | **Duplicate Base + Duplicate + %RPD** |
| Date extracted | - | 170939-36 | 11/07/2017 \|\| 11/07/2017 |
| Date analysed | - | 170939-36 | 12/07/2017 \|\| 12/07/2017 |
| Phenol | mg/kg | 170939-36 | <0.2 \|\| <0.2 |
| 2-Chlorophenol | mg/kg | 170939-36 | <0.2 \|\| <0.2 |
| 4-Chloro-3-methylphenol | mg/kg | 170939-36 | <1 \|\| <1 |
| 2-Methylphenol (o-cresol) | mg/kg | 170939-36 | <0.2 \|\| <0.2 |
| 3/4-Methylphenol (m/p-cresol) | mg/kg | 170939-36 | <0.4 \|\| <0.4 |
| 2-Nitrophenol | mg/kg | 170939-36 | <0.2 \|\| <0.2 |
| 2,4-Dimethylphenol | mg/kg | 170939-36 | <0.2 \|\| <0.2 |
| 2,4-Dichlorophenol | mg/kg | 170939-36 | <0.2 \|\| <0.2 |
| 2,6-Dichlorophenol | mg/kg | 170939-36 | <0.2 \|\| <0.2 |
| 2,4,5-Trichlorophenol | mg/kg | 170939-36 | <0.2 \|\| <0.2 |
| 2,4,6-Trichlorophenol | mg/kg | 170939-36 | <0.2 \|\| <0.2 |
| 2,4-Dinitrophenol | mg/kg | 170939-36 | <4 \|\| <4 |
| 4-Nitrophenol | mg/kg | 170939-36 | <4 \|\| <4 |
| 2346-Tetrachlorophenol | mg/kg | 170939-36 | <0.2 \|\| <0.2 |
| 2-methyl-4,6-Dinitrophenol | mg/kg | 170939-36 | <2 \|\| <2 |
| Pentachlorophenol | mg/kg | 170939-36 | <1 \|\| <1 |
| *Surrogate* 2-fluorophenol | % | 170939-36 | 88 \|\| 90 \|\| RPD: 2 |
| *Surrogate* Phenol-$d_6$ | % | 170939-36 | 83 \|\| 86 \|\| RPD: 4 |
| *Surrogate 2,4,6*-Tribromophenol | % | 170939-36 | 91 \|\| 96 \|\| RPD: 5 |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | 170939-36 | 93 \|\| 90 \|\| RPD: 3 |

| QUALITY CONTROL<br>Phenoxy Acid Herbicides in Soil | UNITS | Dup. Sm# | Duplicate<br>Base + Duplicate + %RPD |
|---|---|---|---|
| Date extracted | - | 170939-36 | 14/07/2017 \|\| 14/07/2017 |
| Date analysed | - | 170939-36 | 14/07/2017 \|\| 14/07/2017 |
| Clopyralid | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| 3,5-Dichlorobenzoic acid | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| o-chlorophenoxy acetic acid | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| 4-CPA | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| Dicamba | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| MCPP | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| MCPA | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| Dichlorprop | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| 2,4-D | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| Bromoxynil | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| Triclopyr | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| 2,4,5-TP | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| 2,4,5-T | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| MCPB | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| Dinoseb | mg/kg | 170939-36 | <1 \|\| <1 |
| 2,4-DB | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| Ioxynil | mg/kg | 170939-36 | <1 \|\| <1 |
| Picloram | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| DCPA (Chlorthal) Diacid | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| Acifluorfen | mg/kg | 170939-36 | <2 \|\| <2 |
| 2,4,6-T | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| 2,6-D | mg/kg | 170939-36 | <0.5 \|\| <0.5 |
| Surrogate 2.4- DCPA | % | 170939-36 | 96 \|\| 100 \|\| RPD: 4 |

| QUALITY CONTROL Acid Extractractable metals in soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Date prepared | - | 170939-41 | 13/07/2017 \|\| 13/07/2017 | 170939-22 | 13/07/2017 |
| Date analysed | - | 170939-41 | 13/07/2017 \|\| 13/07/2017 | 170939-22 | 13/07/2017 |
| Arsenic | mg/kg | 170939-41 | <4 \|\| <4 | 170939-22 | 97% |
| Beryllium | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Boron | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Cadmium | mg/kg | 170939-41 | <0.4 \|\| <0.4 | 170939-22 | 108% |
| Chromium | mg/kg | 170939-41 | 79 \|\| 67 \|\| RPD: 16 | 170939-22 | 107% |
| Cobalt | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Copper | mg/kg | 170939-41 | 58 \|\| 33 \|\| RPD: 55 | 170939-22 | 110% |
| Lead | mg/kg | 170939-41 | 500 \|\| 480 \|\| RPD: 4 | 170939-22 | 106% |
| Manganese | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Mercury | mg/kg | 170939-41 | 0.2 \|\| 0.2 \|\| RPD: 0 | 170939-22 | 106% |
| Nickel | mg/kg | 170939-41 | 23 \|\| 18 \|\| RPD: 24 | 170939-22 | 103% |
| Selenium | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Zinc | mg/kg | 170939-41 | 180 \|\| 350 \|\| RPD: 64 | 170939-22 | 102% |

| QUALITY CONTROL vTRH(C6-C10)/BTEXN in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD |
|---|---|---|---|
| Date extracted | - | 170939-51 | 11/07/2017 \|\| 11/07/2017 |
| Date analysed | - | 170939-51 | 12/07/2017 \|\| 12/07/2017 |
| TRH $C_6$ - $C_9$ | mg/kg | 170939-51 | <25 \|\| <25 |
| TRH $C_6$ - $C_{10}$ | mg/kg | 170939-51 | <25 \|\| <25 |
| Benzene | mg/kg | 170939-51 | <0.2 \|\| <0.2 |
| Toluene | mg/kg | 170939-51 | <0.5 \|\| <0.5 |
| Ethylbenzene | mg/kg | 170939-51 | <1 \|\| <1 |
| m+p-xylene | mg/kg | 170939-51 | <2 \|\| <2 |
| o-Xylene | mg/kg | 170939-51 | <1 \|\| <1 |
| naphthalene | mg/kg | 170939-51 | <1 \|\| <1 |
| *Surrogate* aaa-Trifluorotoluene | % | 170939-51 | 91 \|\| 84 \|\| RPD: 8 |

| QUALITY CONTROL svTRH (C10-C40) in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD |
|---|---|---|---|
| Date extracted | - | 170939-51 | 11/07/2017 \|\| 11/07/2017 |
| Date analysed | - | 170939-51 | 12/07/2017 \|\| 12/07/2017 |
| TRHC$_{10}$ - C$_{14}$ | mg/kg | 170939-51 | <50 \|\| <50 |
| TRHC$_{15}$ - C$_{28}$ | mg/kg | 170939-51 | <100 \|\| <100 |
| TRHC$_{29}$ - C$_{36}$ | mg/kg | 170939-51 | <100 \|\| <100 |
| TRH>C$_{10}$-C$_{16}$ | mg/kg | 170939-51 | <50 \|\| <50 |
| TRH>C$_{16}$-C$_{34}$ | mg/kg | 170939-51 | <100 \|\| <100 |
| TRH>C$_{34}$-C$_{40}$ | mg/kg | 170939-51 | <100 \|\| <100 |
| *Surrogate* o-Terphenyl | % | 170939-51 | 94 \|\| 95 \|\| RPD: 1 |

| QUALITY CONTROL PAHs in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD |
|---|---|---|---|
| Date extracted | - | 170939-51 | 11/07/2017 \|\| 11/07/2017 |
| Date analysed | - | 170939-51 | 12/07/2017 \|\| 12/07/2017 |
| Naphthalene | mg/kg | 170939-51 | <0.1 \|\| <0.1 |
| Acenaphthylene | mg/kg | 170939-51 | <0.1 \|\| <0.1 |
| Acenaphthene | mg/kg | 170939-51 | <0.1 \|\| <0.1 |
| Fluorene | mg/kg | 170939-51 | <0.1 \|\| <0.1 |
| Phenanthrene | mg/kg | 170939-51 | <0.1 \|\| <0.1 |
| Anthracene | mg/kg | 170939-51 | <0.1 \|\| <0.1 |
| Fluoranthene | mg/kg | 170939-51 | <0.1 \|\| <0.1 |
| Pyrene | mg/kg | 170939-51 | <0.1 \|\| <0.1 |
| Benzo(a)anthracene | mg/kg | 170939-51 | <0.1 \|\| <0.1 |
| Chrysene | mg/kg | 170939-51 | <0.1 \|\| <0.1 |
| Benzo(b,j+k)fluoranthene | mg/kg | 170939-51 | <0.2 \|\| <0.2 |
| Benzo(a)pyrene | mg/kg | 170939-51 | <0.05 \|\| <0.05 |
| Indeno(1,2,3-c,d)pyrene | mg/kg | 170939-51 | <0.1 \|\| <0.1 |
| Dibenzo(a,h)anthracene | mg/kg | 170939-51 | <0.1 \|\| <0.1 |
| Benzo(g,h,i)perylene | mg/kg | 170939-51 | <0.1 \|\| <0.1 |
| *Surrogate p*-Terphenyl-d14 | % | 170939-51 | 81 \|\| 79 \|\| RPD: 2 |

| QUALITY CONTROL<br>Acid Extractractable metals in soil | UNITS | Dup. Sm# | Duplicate<br>Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Date prepared | - | 170939-51 | 13/07/2017 \|\| 13/07/2017 | 170939-42 | 13/07/2017 |
| Date analysed | - | 170939-51 | 13/07/2017 \|\| 13/07/2017 | 170939-42 | 13/07/2017 |
| Arsenic | mg/kg | 170939-51 | <4 \|\| <4 | 170939-42 | 91% |
| Beryllium | mg/kg | 170939-51 | <1 \|\| <1 | [NR] | [NR] |
| Boron | mg/kg | 170939-51 | <3 \|\| <3 | [NR] | [NR] |
| Cadmium | mg/kg | 170939-51 | <0.4 \|\| <0.4 | 170939-42 | 104% |
| Chromium | mg/kg | 170939-51 | 4 \|\| 4 \|\| RPD: 0 | 170939-42 | 107% |
| Cobalt | mg/kg | 170939-51 | <1 \|\| <1 | [NR] | [NR] |
| Copper | mg/kg | 170939-51 | 2 \|\| 2 \|\| RPD: 0 | 170939-42 | 109% |
| Lead | mg/kg | 170939-51 | 9 \|\| 9 \|\| RPD: 0 | 170939-42 | 103% |
| Manganese | mg/kg | 170939-51 | 2 \|\| 3 \|\| RPD: 40 | [NR] | [NR] |
| Mercury | mg/kg | 170939-51 | <0.1 \|\| <0.1 | 170939-42 | 98% |
| Nickel | mg/kg | 170939-51 | <1 \|\| <1 | 170939-42 | 102% |
| Selenium | mg/kg | 170939-51 | <2 \|\| <2 | [NR] | [NR] |
| Zinc | mg/kg | 170939-51 | 11 \|\| 12 \|\| RPD: 9 | 170939-42 | 100% |
| QUALITY CONTROL<br>vTRH(C6-C10)/BTEXN in Soil | UNITS | Dup. Sm# | Duplicate<br>Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
| Date extracted | - | [NT] | [NT] | 170939-57 | 11/07/2017 |
| Date analysed | - | [NT] | [NT] | 170939-57 | 12/07/2017 |
| $TRHC_6$ - $C_9$ | mg/kg | [NT] | [NT] | 170939-57 | 118% |
| $TRHC_6$ - $C_{10}$ | mg/kg | [NT] | [NT] | 170939-57 | 118% |
| Benzene | mg/kg | [NT] | [NT] | 170939-57 | 116% |
| Toluene | mg/kg | [NT] | [NT] | 170939-57 | 117% |
| Ethylbenzene | mg/kg | [NT] | [NT] | 170939-57 | 117% |
| m+p-xylene | mg/kg | [NT] | [NT] | 170939-57 | 121% |
| o-Xylene | mg/kg | [NT] | [NT] | 170939-57 | 121% |
| naphthalene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| *Surrogate* aaa-Trifluorotoluene | % | [NT] | [NT] | 170939-57 | 101% |

| QUALITY CONTROL svTRH (C10-C40) in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Date extracted | - | [NT] | [NT] | 170939-57 | 11/07/2017 |
| Date analysed | - | [NT] | [NT] | 170939-57 | 12/07/2017 |
| TRHC$_{10}$ - C$_{14}$ | mg/kg | [NT] | [NT] | 170939-57 | 110% |
| TRHC$_{15}$ - C$_{28}$ | mg/kg | [NT] | [NT] | 170939-57 | 115% |
| TRHC$_{29}$ - C$_{36}$ | mg/kg | [NT] | [NT] | 170939-57 | 89% |
| TRH>C$_{10}$-C$_{16}$ | mg/kg | [NT] | [NT] | 170939-57 | 110% |
| TRH>C$_{16}$-C$_{34}$ | mg/kg | [NT] | [NT] | 170939-57 | 115% |
| TRH>C$_{34}$-C$_{40}$ | mg/kg | [NT] | [NT] | 170939-57 | 89% |
| *Surrogate* o-Terphenyl | % | [NT] | [NT] | 170939-57 | 91% |
| QUALITY CONTROL PAHs in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
| Date extracted | - | [NT] | [NT] | 170939-57 | 11/07/2017 |
| Date analysed | - | [NT] | [NT] | 170939-57 | 12/07/2017 |
| Naphthalene | mg/kg | [NT] | [NT] | 170939-57 | 112% |
| Acenaphthylene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Acenaphthene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Fluorene | mg/kg | [NT] | [NT] | 170939-57 | 100% |
| Phenanthrene | mg/kg | [NT] | [NT] | 170939-57 | 101% |
| Anthracene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Fluoranthene | mg/kg | [NT] | [NT] | 170939-57 | 96% |
| Pyrene | mg/kg | [NT] | [NT] | 170939-57 | 102% |
| Benzo(a)anthracene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Chrysene | mg/kg | [NT] | [NT] | 170939-57 | 120% |
| Benzo(b,j+k)fluoranthene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Benzo(a)pyrene | mg/kg | [NT] | [NT] | 170939-57 | 110% |
| Indeno(1,2,3-c,d)pyrene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Dibenzo(a,h)anthracene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Benzo(g,h,i)perylene | mg/kg | [NT] | [NT] | [NR] | [NR] |
| *Surrogate p*-Terphenyl-d14 | % | [NT] | [NT] | 170939-57 | 117% |

| QUALITY CONTROL Acid Extractractable metals in soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD |
|---|---|---|---|
| Date prepared | - | 170939-60 | 13/07/2017 \|\| 13/07/2017 |
| Date analysed | - | 170939-60 | 13/07/2017 \|\| 13/07/2017 |
| Arsenic | mg/kg | 170939-60 | <4 \|\| <4 |
| Beryllium | mg/kg | [NT] | [NT] |
| Boron | mg/kg | [NT] | [NT] |
| Cadmium | mg/kg | 170939-60 | <0.4 \|\| <0.4 |
| Chromium | mg/kg | 170939-60 | 8 \|\| 8 \|\| RPD: 0 |
| Cobalt | mg/kg | [NT] | [NT] |
| Copper | mg/kg | 170939-60 | 8 \|\| 8 \|\| RPD: 0 |
| Lead | mg/kg | 170939-60 | 53 \|\| 49 \|\| RPD: 8 |
| Manganese | mg/kg | [NT] | [NT] |
| Mercury | mg/kg | 170939-60 | 0.1 \|\| 0.1 \|\| RPD: 0 |
| Nickel | mg/kg | 170939-60 | 2 \|\| 2 \|\| RPD: 0 |
| Selenium | mg/kg | [NT] | [NT] |
| Zinc | mg/kg | 170939-60 | 82 \|\| 84 \|\| RPD: 2 |

| QUALITY CONTROL Organochlorine Pesticides in soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Date extracted | - | [NT] | [NT] | 170939-57 | 11/07/2017 |
| Date analysed | - | [NT] | [NT] | 170939-57 | 14/07/2017 |
| HCB | mg/kg | [NT] | [NT] | [NR] | [NR] |
| alpha-BHC | mg/kg | [NT] | [NT] | 170939-57 | 85% |
| gamma-BHC | mg/kg | [NT] | [NT] | [NR] | [NR] |
| beta-BHC | mg/kg | [NT] | [NT] | 170939-57 | 101% |
| Heptachlor | mg/kg | [NT] | [NT] | 170939-57 | 107% |
| delta-BHC | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Aldrin | mg/kg | [NT] | [NT] | 170939-57 | 98% |
| Heptachlor Epoxide | mg/kg | [NT] | [NT] | 170939-57 | 100% |
| gamma-Chlordane | mg/kg | [NT] | [NT] | [NR] | [NR] |
| alpha-chlordane | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Endosulfan I | mg/kg | [NT] | [NT] | [NR] | [NR] |
| pp-DDE | mg/kg | [NT] | [NT] | 170939-57 | 100% |
| Dieldrin | mg/kg | [NT] | [NT] | 170939-57 | 110% |
| Endrin | mg/kg | [NT] | [NT] | 170939-57 | 103% |
| pp-DDD | mg/kg | [NT] | [NT] | 170939-57 | 109% |
| Endosulfan II | mg/kg | [NT] | [NT] | [NR] | [NR] |
| pp-DDT | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Endrin Aldehyde | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Endosulfan Sulphate | mg/kg | [NT] | [NT] | 170939-57 | 102% |
| Methoxychlor | mg/kg | [NT] | [NT] | [NR] | [NR] |
| *Surrogate* TCMX | % | [NT] | [NT] | 170939-57 | 115% |

| QUALITY CONTROL Organophosphorus Pesticides | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Date extracted | - | [NT] | [NT] | 170939-57 | 11/07/2017 |
| Date analysed | - | [NT] | [NT] | 170939-57 | 14/07/2017 |
| Azinphos-methyl (Guthion) | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Bromophos-ethyl | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Chlorpyriphos | mg/kg | [NT] | [NT] | 170939-57 | 95% |
| Chlorpyriphos-methyl | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Diazinon | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Dichlorvos | mg/kg | [NT] | [NT] | 170939-57 | 88% |
| Dimethoate | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Ethion | mg/kg | [NT] | [NT] | 170939-57 | 107% |
| Fenitrothion | mg/kg | [NT] | [NT] | 170939-57 | 112% |
| Malathion | mg/kg | [NT] | [NT] | 170939-57 | 81% |
| Parathion | mg/kg | [NT] | [NT] | 170939-57 | 104% |
| Ronnel | mg/kg | [NT] | [NT] | 170939-57 | 103% |
| *Surrogate* TCMX | % | [NT] | [NT] | 170939-57 | 92% |
| QUALITY CONTROL PCBs in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
| Date extracted | - | [NT] | [NT] | 170939-57 | 11/07/2017 |
| Date analysed | - | [NT] | [NT] | 170939-57 | 14/07/2017 |
| Aroclor 1016 | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1221 | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1232 | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1242 | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1248 | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Aroclor 1254 | mg/kg | [NT] | [NT] | 170939-57 | 100% |
| Aroclor 1260 | mg/kg | [NT] | [NT] | [NR] | [NR] |
| *Surrogate* TCLMX | % | [NT] | [NT] | 170939-57 | 92% |
| QUALITY CONTROL Triazine Herbicides in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
| Date prepared | - | [NT] | [NT] | 170939-57 | 11/07/2017 |
| Date analysed | - | [NT] | [NT] | 170939-57 | 11/07/2017 |
| Atrazine | mg/kg | [NT] | [NT] | 170939-57 | 94% |
| Ametryn | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Cyanazine | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Hexazinone | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Irgarol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Metribuzin | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Prometryn | mg/kg | [NT] | [NT] | 170939-57 | 99% |
| Propazine | mg/kg | [NT] | [NT] | 170939-57 | 106% |
| Simazine | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Terbutryn | mg/kg | [NT] | [NT] | [NR] | [NR] |

| QUALITY CONTROL Triazine Herbicides in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Terbuthylazine | mg/kg | [NT] | [NT] | [NR] | [NR] |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | [NT] | [NT] | 170939-57 | 81% |
| QUALITY CONTROL Speciated Phenols in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
| Date extracted | - | [NT] | [NT] | 170939-57 | 11/07/2017 |
| Date analysed | - | [NT] | [NT] | 170939-57 | 12/07/2017 |
| Phenol | mg/kg | [NT] | [NT] | 170939-57 | 66% |
| 2-Chlorophenol | mg/kg | [NT] | [NT] | 170939-57 | 70% |
| 4-Chloro-3-methylphenol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2-Methylphenol (o-cresol) | mg/kg | [NT] | [NT] | 170939-57 | 72% |
| 3/4-Methylphenol (m/p-cresol) | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2-Nitrophenol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2,4-Dimethylphenol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2,4-Dichlorophenol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2,6-Dichlorophenol | mg/kg | [NT] | [NT] | 170939-57 | 94% |
| 2,4,5-Trichlorophenol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2,4,6-Trichlorophenol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2,4-Dinitrophenol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 4-Nitrophenol | mg/kg | [NT] | [NT] | 170939-57 | 52% |
| 2346-Tetrachlorophenol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2-methyl-4,6-Dinitrophenol | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Pentachlorophenol | mg/kg | [NT] | [NT] | 170939-57 | 98% |
| *Surrogate* 2-fluorophenol | % | [NT] | [NT] | 170939-57 | 100% |
| *Surrogate* Phenol-$d_6$ | % | [NT] | [NT] | 170939-57 | 104% |
| *Surrogate 2,4,6*-Tribromophenol | % | [NT] | [NT] | 170939-57 | 117% |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | [NT] | [NT] | 170939-57 | 91% |

| QUALITY CONTROL svTRH (C10-C40) in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD |
|---|---|---|---|
| Date extracted | - | 170939-66 | 11/07/2017 \|\| 11/07/2017 |
| Date analysed | - | 170939-66 | 12/07/2017 \|\| 12/07/2017 |
| TRHC$_{10}$ - C$_{14}$ | mg/kg | 170939-66 | <50 \|\| <50 |
| TRHC$_{15}$ - C$_{28}$ | mg/kg | 170939-66 | <100 \|\| <100 |
| TRHC$_{29}$ - C$_{36}$ | mg/kg | 170939-66 | <100 \|\| <100 |
| TRH>C$_{10}$-C$_{16}$ | mg/kg | 170939-66 | <50 \|\| <50 |
| TRH>C$_{16}$-C$_{34}$ | mg/kg | 170939-66 | <100 \|\| <100 |
| TRH>C$_{34}$-C$_{40}$ | mg/kg | 170939-66 | <100 \|\| <100 |
| *Surrogate* o-Terphenyl | % | 170939-66 | 91 \|\| 91 \|\| RPD: 0 |

| QUALITY CONTROL PAHs in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD |
|---|---|---|---|
| Date extracted | - | 170939-66 | 11/07/2017 \|\| 11/07/2017 |
| Date analysed | - | 170939-66 | 12/07/2017 \|\| 12/07/2017 |
| Naphthalene | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Acenaphthylene | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Acenaphthene | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Fluorene | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Phenanthrene | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Anthracene | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Fluoranthene | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Pyrene | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Benzo(a)anthracene | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Chrysene | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Benzo(b,j+k)fluoranthene | mg/kg | 170939-66 | <0.2 \|\| <0.2 |
| Benzo(a)pyrene | mg/kg | 170939-66 | <0.05 \|\| <0.05 |
| Indeno(1,2,3-c,d)pyrene | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Dibenzo(a,h)anthracene | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Benzo(g,h,i)perylene | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| *Surrogate p*-Terphenyl-d14 | % | 170939-66 | 81 \|\| 81 \|\| RPD: 0 |

| QUALITY CONTROL Acid Extractractable metals in soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Date prepared | - | [NT] | [NT] | 170939-63 | 13/07/2017 |
| Date analysed | - | [NT] | [NT] | 170939-63 | 13/07/2017 |
| Arsenic | mg/kg | [NT] | [NT] | 170939-63 | 98% |
| Beryllium | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Boron | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Cadmium | mg/kg | [NT] | [NT] | 170939-63 | 95% |
| Chromium | mg/kg | [NT] | [NT] | 170939-63 | 113% |
| Cobalt | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Copper | mg/kg | [NT] | [NT] | 170939-63 | 111% |
| Lead | mg/kg | [NT] | [NT] | 170939-63 | # |
| Manganese | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Mercury | mg/kg | [NT] | [NT] | 170939-63 | 97% |
| Nickel | mg/kg | [NT] | [NT] | 170939-63 | 86% |
| Selenium | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Zinc | mg/kg | [NT] | [NT] | 170939-63 | 123% |

| QUALITY CONTROL Organochlorine Pesticides in soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD |
|---|---|---|---|
| Date extracted | - | 170939-66 | 11/07/2017 \|\| 11/07/2017 |
| Date analysed | - | 170939-66 | 14/07/2017 \|\| 14/07/2017 |
| HCB | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| alpha-BHC | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| gamma-BHC | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| beta-BHC | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Heptachlor | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| delta-BHC | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Aldrin | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Heptachlor Epoxide | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| gamma-Chlordane | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| alpha-chlordane | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Endosulfan I | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| pp-DDE | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Dieldrin | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Endrin | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| pp-DDD | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Endosulfan II | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| pp-DDT | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Endrin Aldehyde | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Endosulfan Sulphate | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Methoxychlor | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| *Surrogate* TCMX | % | 170939-66 | 95 \|\| 91 \|\| RPD: 4 |

| QUALITY CONTROL Organophosphorus Pesticides | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD |
|---|---|---|---|
| Date extracted | - | 170939-66 | 11/07/2017 \|\| 11/07/2017 |
| Date analysed | - | 170939-66 | 14/07/2017 \|\| 14/07/2017 |
| Azinphos-methyl (Guthion) | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Bromophos-ethyl | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Chlorpyriphos | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Chlorpyriphos-methyl | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Diazinon | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Dichlorvos | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Dimethoate | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Ethion | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Fenitrothion | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Malathion | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Parathion | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Ronnel | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| *Surrogate* TCMX | % | 170939-66 | 95 \|\| 91 \|\| RPD: 4 |
| QUALITY CONTROL PCBs in Soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD |
| Date extracted | - | 170939-66 | 11/07/2017 \|\| 11/07/2017 |
| Date analysed | - | 170939-66 | 14/07/2017 \|\| 14/07/2017 |
| Aroclor 1016 | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Aroclor 1221 | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Aroclor 1232 | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Aroclor 1242 | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Aroclor 1248 | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Aroclor 1254 | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| Aroclor 1260 | mg/kg | 170939-66 | <0.1 \|\| <0.1 |
| *Surrogate* TCLMX | % | 170939-66 | 95 \|\| 91 \|\| RPD: 4 |
| QUALITY CONTROL Acid Extractractable metals in soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD |
| Date prepared | - | 170939-71 | 13/07/2017 \|\| 13/07/2017 |
| Date analysed | - | 170939-71 | 13/07/2017 \|\| 13/07/2017 |
| Arsenic | mg/kg | 170939-71 | <4 \|\| <4 |
| Beryllium | mg/kg | [NT] | [NT] |
| Boron | mg/kg | [NT] | [NT] |
| Cadmium | mg/kg | 170939-71 | <0.4 \|\| <0.4 |
| Chromium | mg/kg | 170939-71 | 4 \|\| 3 \|\| RPD: 29 |
| Cobalt | mg/kg | [NT] | [NT] |
| Copper | mg/kg | 170939-71 | <1 \|\| <1 |
| Lead | mg/kg | 170939-71 | 5 \|\| 6 \|\| RPD: 18 |
| Manganese | mg/kg | [NT] | [NT] |

| QUALITY CONTROL<br>Acid Extractractable metals in soil | UNITS | Dup. Sm# | Duplicate<br>Base + Duplicate + %RPD |
|---|---|---|---|
| Mercury | mg/kg | 170939-71 | <0.1 \|\| <0.1 |
| Nickel | mg/kg | 170939-71 | <1 \|\| <1 |
| Selenium | mg/kg | [NT] | [NT] |
| Zinc | mg/kg | 170939-71 | <1 \|\| <1 |

| QUALITY CONTROL<br>vTRH in Water (C6-C9) NEPM | UNITS | Dup. Sm# | Duplicate<br>Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Date extracted | - | [NT] | [NT] | LCS-W2 | 11/07/2017 |
| Date analysed | - | [NT] | [NT] | LCS-W2 | 12/07/2017 |
| TRHC$_6$ - C$_9$ | µg/L | [NT] | [NT] | LCS-W2 | 124% |
| TRHC$_6$ - C$_{10}$ | µg/L | [NT] | [NT] | LCS-W2 | 124% |
| *Surrogate* Dibromofluoromethane | % | [NT] | [NT] | LCS-W2 | 94% |
| *Surrogate* toluene-d8 | % | [NT] | [NT] | LCS-W2 | 96% |
| *Surrogate* 4-BFB | % | [NT] | [NT] | LCS-W2 | 110% |

| QUALITY CONTROL<br>Misc Inorg - Soil | UNITS | Dup. Sm# | Duplicate<br>Base + Duplicate + %RPD |
|---|---|---|---|
| Date prepared | - | 170939-5 | 13/07/2017 \|\| 13/07/2017 |
| Date analysed | - | 170939-5 | 13/07/2017 \|\| 13/07/2017 |
| pH 1:5 soil:water | pH Units | 170939-5 | 5.8 \|\| 5.8 \|\| RPD: 0 |

| QUALITY CONTROL<br>Metals in Water - Dissolved | UNITS | Dup. Sm# | Duplicate<br>Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Date digested | - | [NT] | [NT] | LCS-W1 | 11/07/2017 |
| Date analysed | - | [NT] | [NT] | LCS-W1 | 11/07/2017 |
| Arsenic - Dissolved | mg/L | [NT] | [NT] | LCS-W1 | 101% |
| Cadmium - Dissolved | mg/L | [NT] | [NT] | LCS-W1 | 106% |
| Chromium - Dissolved | mg/L | [NT] | [NT] | LCS-W1 | 104% |
| Copper - Dissolved | mg/L | [NT] | [NT] | LCS-W1 | 104% |
| Lead - Dissolved | mg/L | [NT] | [NT] | LCS-W1 | 102% |
| Mercury - Dissolved | mg/L | [NT] | [NT] | LCS-W1 | 96% |
| Nickel - Dissolved | mg/L | [NT] | [NT] | LCS-W1 | 102% |
| Zinc - Dissolved | mg/L | [NT] | [NT] | LCS-W1 | 103% |

| QUALITY CONTROL<br>Misc Inorg - Soil | UNITS | Dup. Sm# | Duplicate<br>Base + Duplicate + %RPD |
|---|---|---|---|
| Date prepared | - | 170939-57 | 13/07/2017 \|\| 13/07/2017 |
| Date analysed | - | 170939-57 | 13/07/2017 \|\| 13/07/2017 |
| pH 1:5 soil:water | pH Units | 170939-57 | 5.5 \|\| 5.3 \|\| RPD: 4 |

| QUALITY CONTROL<br>Phenoxy Acid Herbicides in Soil | UNITS | Dup. Sm# | Duplicate<br>Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Date extracted | - | [NT] | [NT] | LCS-1 | 14/07/2017 |
| Date analysed | - | [NT] | [NT] | LCS-1 | 14/07/2017 |
| Clopyralid | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 3,5-Dichlorobenzoic acid | mg/kg | [NT] | [NT] | [NR] | [NR] |
| o-chlorophenoxy acetic acid | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 4-CPA | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Dicamba | mg/kg | [NT] | [NT] | LCS-1 | 88% |
| MCPP | mg/kg | [NT] | [NT] | LCS-1 | 86% |
| MCPA | mg/kg | [NT] | [NT] | LCS-1 | 84% |
| Dichlorprop | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2,4-D | mg/kg | [NT] | [NT] | LCS-1 | 84% |
| Bromoxynil | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Triclopyr | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2,4,5-TP | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2,4,5-T | mg/kg | [NT] | [NT] | LCS-1 | 81% |
| MCPB | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Dinoseb | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2,4-DB | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Ioxynil | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Picloram | mg/kg | [NT] | [NT] | [NR] | [NR] |
| DCPA (Chlorthal) Diacid | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Acifluorfen | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2,4,6-T | mg/kg | [NT] | [NT] | [NR] | [NR] |
| 2,6-D | mg/kg | [NT] | [NT] | [NR] | [NR] |
| Surrogate 2.4- DCPA | % | [NT] | [NT] | LCS-1 | 106% |

| QUALITY CONTROL Synthetic Pyrethroids in soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD | Spike Sm# | Spike % Recovery |
|---|---|---|---|---|---|
| Date extracted | - | [NT] | [NT] | LCS-1 | 13/07/2017 |
| Date analysed | - | [NT] | [NT] | LCS-1 | 14/07/2017 |
| Bifenthrin | mg/kg | [NT] | [NT] | LCS-1 | 83% |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | [NT] | [NT] | LCS-1 | 106% |

| QUALITY CONTROL Acid Extractractable metals in soil | UNITS | Dup. Sm# | Duplicate Base + Duplicate + %RPD |
|---|---|---|---|
| Date prepared | - | 170939-64 | 13/07/2017 \|\| 13/07/2017 |
| Date analysed | - | 170939-64 | 13/07/2017 \|\| 13/07/2017 |
| Arsenic | mg/kg | 170939-64 | 4 \|\| <4 |
| Beryllium | mg/kg | [NT] | [NT] |
| Boron | mg/kg | [NT] | [NT] |
| Cadmium | mg/kg | 170939-64 | <0.4 \|\| <0.4 |
| Chromium | mg/kg | 170939-64 | 10 \|\| 8 \|\| RPD: 22 |
| Cobalt | mg/kg | [NT] | [NT] |
| Copper | mg/kg | 170939-64 | 8 \|\| 5 \|\| RPD: 46 |
| Lead | mg/kg | 170939-64 | 6200 \|\| 2200 \|\| RPD: 95 |
| Manganese | mg/kg | [NT] | [NT] |
| Mercury | mg/kg | 170939-64 | <0.1 \|\| <0.1 |
| Nickel | mg/kg | 170939-64 | 5 \|\| 5 \|\| RPD: 0 |
| Selenium | mg/kg | [NT] | [NT] |
| Zinc | mg/kg | 170939-64 | 94 \|\| 58 \|\| RPD: 47 |

**Report Comments:**

Acid Extractable Metals in Soil: The laboratory RPD acceptance criteria has been exceeded for 170939-1 for Cu, Pb, and Ni. Therefore a triplicate result has been issued as laboratory sample number 170939-72.

Acid Extractable Metals in Soil: The laboratory RPD acceptance criteria has been exceeded for 170939-41 for Cu and Zn. Therefore a triplicate result has been issued as laboratory sample number 170939-73.

Acid Extractable Metals in Soil:
# Percent recovery is not possible to report due to the high concentration of the element/s in the sample/s. However an acceptable recovery was obtained for the LCS.

PCBs in soil:
It was noted that PCBs were detected in sample 14.

Acid Extractable Metals in Soil: The laboratory RPD acceptance criteria has been exceeded for 170939-64 for Pb. Therefore a triplicate result has been issued as laboratory sample number 170939-74.

Herbicides, Synthetic Pyrethroids, Toxaphene & Mirex analysed by MPL Laboratories. Report No.198096.

| | |
|---|---|
| Asbestos ID was analysed by Approved Identifier: | Not applicable for this job |
| Asbestos ID was authorised by Approved Signatory: | Not applicable for this job |

| | | |
|---|---|---|
| INS: Insufficient sample for this test | PQL: Practical Quantitation Limit | NT: Not tested |
| NR: Test not required | RPD: Relative Percent Difference | NA: Test not required |
| <: Less than | >: Greater than | LCS: Laboratory Control Sample |

## Quality Control Definitions

**Blank**: This is the component of the analytical signal which is not derived from the sample but from reagents, glassware etc, can be determined by processing solvents and reagents in exactly the same manner as for samples.

**Duplicate**: This is the complete duplicate analysis of a sample from the process batch. If possible, the sample selected should be one where the analyte concentration is easily measurable.

**Matrix Spike** : A portion of the sample is spiked with a known concentration of target analyte. The purpose of the matrix spike is to monitor the performance of the analytical method used and to determine whether matrix interferences exist.

**LCS (Laboratory Control Sample)** : This comprises either a standard reference material or a control matrix (such as a blank sand or water) fortified with analytes representative of the analyte class. It is simply a check sample.

**Surrogate Spike:** Surrogates are known additions to each sample, blank, matrix spike and LCS in a batch, of compounds which are similar to the analyte of interest, however are not expected to be found in real samples.

## Laboratory Acceptance Criteria

Duplicate sample and matrix spike recoveries may not be reported on smaller jobs, however, were analysed at a frequency to meet or exceed NEPM requirements. All samples are tested in batches of 20. The duplicate sample RPD and matrix spike recoveries for the batch were within the laboratory acceptance criteria.
Filters, swabs, wipes, tubes and badges will not have duplicate data as the whole sample is generally extracted during sample extraction.
Spikes for Physical and Aggregate Tests are not applicable.
For VOCs in water samples, three vials are required for duplicate or spike analysis.

Duplicates: <5xPQL - any RPD is acceptable; >5xPQL - 0-50% RPD is acceptable.
Matrix Spikes, LCS and Surrogate recoveries: Generally 70-130% for inorganics/metals; 60-140% for organics (+/-50% surrogates) and 10-140% for labile SVOCs (including labile surrogates), ultra trace organics and speciated phenols is acceptable.

In circumstances where no duplicate and/or sample spike has been reported at 1 in 10 and/or 1 in 20 samples respectively, the sample volume submitted was insufficient in order to satisfy laboratory QA/QC protocols.

When samples are received where certain analytes are outside of recommended technical holding times (THTs), the analysis has proceeded. Where analytes are on the verge of breaching THTs, every effort will be made to analyse within the THT or as soon as practicable.

Where sampling dates are not provided, Envirolab are not in a position to comment on the validity of the analysis where recommended technical holding times may have been breached.

Measurement Uncertainty estimates are available for most tests upon request.

# CHAIN OF CUSTODY - Client

## ENVIROLAB GROUP - National phone number 1300 424 344


Sydney Lab - Envirolab Services
12 Ashley St, Chatswood, NSW 2067
Ph: 02 9910 6200 / sydney@envirolab.com.au

Perth Lab - MPL Laboratories
16-18 Hayden Crt Myaree, WA 6154
Ph: 08 9317 2505 / lab@mpl.com.au

Melbourne Lab - Envirolab Services
1A Dalmore Drive Scoresby VIC 3179
Ph: 03 9763 2500 / melbourne@envirolab.com.au

Adelaide Office - Envirolab Services
7a The Parade, Norwood, SA 5067
Ph: 08 7087 6800 / adelaide@envirolab.com.au

Brisbane Office - Envirolab Services
20a, 10-20 Depot St, Banyo, QLD 4014
Ph: 07 3266 9532 / brisbane@envirolab.com.au

Darwin Office - Envirolab Services
Unit 7, 17 Willes Rd, Berrimah, NT 0820
Ph: 08 8967 1201 / darwin@envirolab.com.au


| | |
|---|---|
| Client: LRM | Client Project Name / Number / Site etc (ie report title): |
| Contact Person: | |
| Project Mgr: | PO No.: |
| Sampler: | Envirolab Quote No. : |
| Address: Lane Cove. | Date results required: Or choose: standard / same day / 1 day / 2 day / 3 day *Note: Inform lab in advance if urgent turnaround is required - surcharges apply* |
| Phone: Mob: 0411477722 | Additional report format: esdat / equis / |
| Email: jon.lawson@lrmglobal.com.au | Lab Comments: |

| Envirolab Sample ID | Client Sample ID or information | Depth | Date sampled | Type of sample | Metals | TRH | BTEX | PAH | NSW Waste Disposal Screen | | | | | | | | | | Comments |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | BH43 - 1.0 | | 10/5 | Soil | | | | | ✓ | | | | | | | | | | |
| 2 | BH43 - 6.0 | | | | ✓ | ✓ | ✓ | ✓ | | | | | | | | | | | |
| 3 | BH43 - 7.0 | | | | ✓ | ✓ | ✓ | ✓ | | | | | | | | | | | |
| 4 | BH43 - 8.0 | | | | ✓ | ✓ | ✓ | ✓ | | | | | | | | | | | |
| 5 | BH43 - 9.0 | | | | | | | | ✓ | | | | | | | | | | |
| 6 | BH44 - 5.0 | | | | | | | | ✓ | | | | | | | | | | |
| 7 | BH44 - 6.0 | | | | ✓ | ✓ | ✓ | ✓ | | | | | | | | | | | |
| 8 | BH44 - 7.0 | | | | ✓ | ✓ | ✓ | ✓ | | | | | | | | | | | |
| 9 | BH44 - 8.0 | | | | ✓ | ✓ | ✓ | ✓ | | | | | | | | | | | |
| 10 | BH44 - 9.0 | | | | | | | | ✓ | | | | | | | | | | |
| 11 | BH45 - 7.0 | | | | | | | | ✓ | | | | | | | | | | |
| 12 | BH45 - 7.8 | | | | ✓ | ✓ | ✓ | ✓ | | | | | | | | | | | |
| 13 | BH45 - 8.0 | | ↓ | ↓ | | | | | ✓ | | | | | | | | | | |

| | | | |
|---|---|---|---|
| Relinquished by (Company): | Received by (Company): ELS | Lab Use Only | |
| Print Name: | Print Name: Rebecca | Job number: 191466 | Cooling: Ice / Ice pack / None |
| Date & Time: | Date & Time: 11/5/18 16:00 | Temperature: | Security seal: Intact / Broken / None |
| Signature: | Signature: | TAT Req - SAME day / 1 / 2 / 3 / 4 / STD | |

# CHAIN OF CUSTODY - Client

## ENVIROLAB GROUP - National phone number 1300 424 344


Sydney Lab - Envirolab Services
12 Ashley St, Chatswood, NSW 2067
Ph: 02 9910 6200 / sydney@envirolab.com.au

Perth Lab - MPL Laboratories
16-18 Hayden Crt Myaree, WA 6154
Ph: 08 9317 2505 / lab@mpl.com.au

Melbourne Lab - Envirolab Services
1A Dalmore Drive Scoresby VIC 3179
Ph: 03 9763 2500 / melbourne@envirolab.com.au

Adelaide Office - Envirolab Services
7a The Parade, Norwood, SA 5067
Ph: 08 7087 6800 / adelaide@envirolab.com.au

Brisbane Office - Envirolab Services
20a, 10-20 Depot St, Banyo, QLD 4014
Ph: 07 3266 9532 / brisbane@envirolab.com.au

Darwin Office - Envirolab Services
Unit 7, 17 Willes Rd, Berrimah, NT 0820
Ph: 08 8967 1201 / darwin@envirolab.com.au


| | |
|---|---|
| Client: Arcon | Client Project Name / Number / Site etc (ie report title): |
| Contact Person: | |
| Project Mgr: | PO No.: |
| Sampler: | Envirolab Quote No. : |
| Address: Lane Cove | Date results required: Or choose: standard / same day / 1 day / 2 day / 3 day *Note: Inform lab in advance if urgent turnaround is required - surcharges apply* |
| Phone: Mob: 0411497122 | Additional report format: esdat / equis / |
| Email: | Lab Comments: |

| Envirolab Sample ID | Client Sample ID or information | Depth | Date sampled | Type of sample | TRH | BTEX | PAH | Metals | NSW Waste (Liquid) Screen | | | | | | | | | | Comments |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 14 | BH46 - 0.2 | 11/5 | | S | | | | | ✓ | | | | | | | | | | |
| 15 | BH46 - 0.5 | ↓ | | | ✓ | ✓ | ✓ | ✓ | | | | | | | | | | | |
| 16 | BH46 - 1.0 | | | | ✓ | ✓ | ✓ | ✓ | | | | | | | | | | | |
| 17 | BH46 - 2.0 | | | | ✓ | ✓ | ✓ | ✓ | | | | | | | | | | | |
| 18 | BH46 - 2.3 | | | | | | | | ✓ | | | | | | | | | | |
| 19 | BH47 - 3.6 | | | | | | | | ✓ | | | | | | | | | | |
| 20 | BH47 - 5.0 | | | | ✓ | ✓ | ✓ | ✓ | | | | | | | | | | | |
| 21 | BH47 - 6.0 | | | | ✓ | ✓ | ✓ | ✓ | | | | | | | | | | | |
| 22 | BH47 - 6.5 | | | | ✓ | ✓ | ✓ | ✓ | | | | | | | | | | | |
| 23 | BH47 - 7.0 | ↓ | | | | | | | ✓ | | | | | | | | | | |
| 24 | Dup 6 | 10/5 | | ↓ | ✓ | ✓ | ✓ | ✓ | | | | | | | | | | | |
| 25 | Dup 7 | 11/5 | | | ✓ | ✓ | ✓ | ✓ | | | | | | | | | | | |
| 26 | Trip B | labelled | | Water | ✓ | | | | | | | | | | | | | | |

labelled
Dup 5
Dup 6

| | | | |
|---|---|---|---|
| Relinquished by (Company): | Received by (Company): | Lab Use Only | |
| Print Name: | Print Name: | Job number: 191406 | Cooling: Ice / Ice pack / None |
| Date & Time: | Date & Time: 11/5/18 | Temperature: | Security seal: Intact / Broken /None |
| Signature: | Signature: | TAT Req - SAME day / 1 / 2 / 3 / 4 / STD | |

# CHAIN OF CUSTODY - Client

## ENVIROLAB GROUP - National phone number 1300 424 344

| | |
|---|---|
| Client: UNK | Client Project Name / Number / Site etc (ie report title): |
| Contact Person: | |
| Project Mgr: | PO No.: |
| Sampler: | Envirolab Quote No. : |
| Address: Lane Cove | Date results required: |
| | Or choose: standard / same day / 1 day / 2 day / 3 day<br>*Note: Inform lab in advance if urgent turnaround is required - surcharges apply* |
| Phone: Mob: 0411477725 | Additional report format: esdat / equis / |
| Email: | Lab Comments: |


Sydney Lab - Envirolab Services
12 Ashley St, Chatswood, NSW 2067
Ph: 02 9910 6200 / sydney@envirolab.com.au

Perth Lab - MPL Laboratories
16-18 Hayden Crt Myaree, WA 6154
Ph: 08 9317 2505 / lab@mpl.com.au

Melbourne Lab - Envirolab Services
1A Dalmore Drive Scoresby VIC 3179
Ph: 03 9763 2500 / melbourne@envirolab.com.au

Adelaide Office - Envirolab Services
7a The Parade, Norwood, SA 5067
Ph: 08 7087 6800 / adelaide@envirolab.com.au

Brisbane Office - Envirolab Services
20a, 10-20 Depot St, Banyo, QLD 4014
Ph: 07 3266 9532 / brisbane@envirolab.com.au

Darwin Office - Envirolab Services
Unit 7, 17 Willes Rd, Berrimah, NT 0820
Ph: 08 8967 1201 / darwin@envirolab.com.au


| Sample Information | | | | | Tests Required | | | | | | | | | | | | | | | Comments |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Envirolab Sample ID | Client Sample ID or information | Depth | Date sampled | Type of sample | Metals | | | | | | | | | | | | | | | Provide as much information about the sample as you can |
| 27 | Split 5 | 1V5 | | Sal | ✓ | | | | | | | | | | | | | | | |
| 28 | Split 6. | 1V5 | | 11 | ✓ | | | | | | | | | | | | | | | |

| | | | |
|---|---|---|---|
| Relinquished by (Company): | Received by (Company): | Lab Use Only | |
| Print Name: | Print Name: | Job number: 191466 | Cooling: Ice / Ice pack / None |
| Date & Time: | Date & Time: RW 11/5/18 | Temperature: | Security seal: Intact / Broken /None |
| Signature: | Signature: | TAT Req - SAME day / 1 / 2 / 3 / 4 / STD | |

**Envirolab Services Pty Ltd**
ABN 37 112 535 645
12 Ashley St Chatswood NSW 2067
ph 02 9910 6200 fax 02 9910 6201
customerservice@envirolab.com.au
www.envirolab.com.au

# CERTIFICATE OF ANALYSIS 191466

## Client Details

| | |
|---|---|
| **Client** | LRM Global |
| **Attention** | Jon Lawson |
| **Address** | PO Box 1237, Carlton, VIC, 3053 |

## Sample Details

| | |
|---|---|
| **Your Reference** | **Soil & Water Analysis** |
| **Number of Samples** | 27 Soil, 1 Water |
| **Date samples received** | 11/05/2018 |
| **Date completed instructions received** | 11/05/2018 |

## Analysis Details

Please refer to the following pages for results, methodology summary and quality control data.

Samples were analysed as received from the client. Results relate specifically to the samples as received.

Results are reported on a dry weight basis for solids and on an as received basis for other matrices.

**Please refer to the last page of this report for any comments relating to the results.**

## Report Details

| | |
|---|---|
| **Date results requested by** | 18/05/2018 |
| **Date of Issue** | 23/05/2018 |

NATA Accreditation Number 2901. This document shall not be reproduced except in full.

Accredited for compliance with ISO/IEC 17025 - Testing. **Tests not covered by NATA are denoted with ***

**Results Approved By**
Dragana Tomas, Senior Chemist
Giovanni Agosti, Group Technical Manager
Nancy Zhang, Assistant Lab Manager
Nick Sarlamis, Inorganics Supervisor
Steven Luong, Senior Chemist

**Authorised By**



Jacinta Hurst, Laboratory Manager

| VOCs in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-1 | 191466-5 | 191466-6 | 191466-10 | 191466-11 |
| Your Reference | UNITS | BH43_5.0 | BH43_9.0 | BH44_5.0 | BH44_9.0 | BH45_7.0 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Dichlorodifluoromethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Chloromethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Vinyl Chloride | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Bromomethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Chloroethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Trichlorofluoromethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| trans-1,2-dichloroethene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,1-dichloroethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| cis-1,2-dichloroethene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| bromochloromethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| chloroform | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 2,2-dichloropropane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,2-dichloroethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,1,1-trichloroethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,1-dichloropropene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Cyclohexane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| carbon tetrachloride | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Benzene | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| dibromomethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,2-dichloropropane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| trichloroethene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| bromodichloromethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| trans-1,3-dichloropropene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| cis-1,3-dichloropropene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,1,2-trichloroethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Toluene | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| 1,3-dichloropropane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| dibromochloromethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,2-dibromoethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| tetrachloroethene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,1,1,2-tetrachloroethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| chlorobenzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Ethylbenzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| bromoform | mg/kg | <1 | <1 | <1 | <1 | <1 |

| VOCs in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-1 | 191466-5 | 191466-6 | 191466-10 | 191466-11 |
| Your Reference | UNITS | BH43_5.0 | BH43_9.0 | BH44_5.0 | BH44_9.0 | BH45_7.0 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| m+p-xylene | mg/kg | <2 | <2 | <2 | <2 | <2 |
| styrene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,1,2,2-tetrachloroethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| o-Xylene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,2,3-trichloropropane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| isopropylbenzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| bromobenzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| n-propyl benzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 2-chlorotoluene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 4-chlorotoluene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,3,5-trimethyl benzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| tert-butyl benzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,2,4-trimethyl benzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,3-dichlorobenzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| sec-butyl benzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,4-dichlorobenzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 4-isopropyl toluene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,2-dichlorobenzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| n-butyl benzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,2-dibromo-3-chloropropane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,2,4-trichlorobenzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| hexachlorobutadiene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,2,3-trichlorobenzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| *Surrogate* Dibromofluorometha | % | 99 | 100 | 69 | 100 | 101 |
| *Surrogate* aaa-Trifluorotoluene | % | 85 | 89 | 95 | 84 | 88 |
| *Surrogate* Toluene-$d_8$ | % | 99 | 100 | 100 | 99 | 100 |
| *Surrogate* 4-Bromofluorobenzene | % | 97 | 96 | 93 | 96 | 98 |

| VOCs in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-13 | 191466-14 | 191466-18 | 191466-19 | 191466-23 |
| Your Reference | UNITS | BH45_8.0 | BH46_0.2 | BH46_2.3 | BH47_3.6 | BH47_7.0 |
| Date Sampled | | 10/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 16/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 17/05/2018 |
| Dichlorodifluoromethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Chloromethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Vinyl Chloride | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Bromomethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Chloroethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Trichlorofluoromethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| trans-1,2-dichloroethene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,1-dichloroethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| cis-1,2-dichloroethene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| bromochloromethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| chloroform | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 2,2-dichloropropane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,2-dichloroethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,1,1-trichloroethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,1-dichloropropene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Cyclohexane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| carbon tetrachloride | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Benzene | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| dibromomethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,2-dichloropropane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| trichloroethene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| bromodichloromethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| trans-1,3-dichloropropene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| cis-1,3-dichloropropene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,1,2-trichloroethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Toluene | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| 1,3-dichloropropane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| dibromochloromethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,2-dibromoethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| tetrachloroethene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,1,1,2-tetrachloroethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| chlorobenzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Ethylbenzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| bromoform | mg/kg | <1 | <1 | <1 | <1 | <1 |

| VOCs in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-13 | 191466-14 | 191466-18 | 191466-19 | 191466-23 |
| Your Reference | UNITS | BH45_8.0 | BH46_0.2 | BH46_2.3 | BH47_3.6 | BH47_7.0 |
| Date Sampled | | 10/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| m+p-xylene | mg/kg | <2 | <2 | <2 | <2 | <2 |
| styrene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,1,2,2-tetrachloroethane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| o-Xylene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,2,3-trichloropropane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| isopropylbenzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| bromobenzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| n-propyl benzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 2-chlorotoluene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 4-chlorotoluene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,3,5-trimethyl benzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| tert-butyl benzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,2,4-trimethyl benzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,3-dichlorobenzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| sec-butyl benzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,4-dichlorobenzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 4-isopropyl toluene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,2-dichlorobenzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| n-butyl benzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,2-dibromo-3-chloropropane | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,2,4-trichlorobenzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| hexachlorobutadiene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 1,2,3-trichlorobenzene | mg/kg | <1 | <1 | <1 | <1 | <1 |
| *Surrogate* Dibromofluorometha | % | 100 | 101 | 100 | 103 | 101 |
| *Surrogate* aaa-Trifluorotoluene | % | 96 | 88 | 89 | 90 | 91 |
| *Surrogate* Toluene-$d_8$ | % | 98 | 99 | 98 | 100 | 98 |
| *Surrogate* 4-Bromofluorobenzene | % | 97 | 96 | 95 | 94 | 94 |

| vTRH(C6-C10)/BTEXN in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-1 | 191466-2 | 191466-3 | 191466-4 | 191466-5 |
| Your Reference | UNITS | BH43_5.0 | BH43_6.0 | BH43_7.0 | BH43_8.0 | BH43_9.0 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 16/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 17/05/2018 | 16/05/2018 |
| TRH $C_6$ - $C_9$ | mg/kg | <25 | <25 | <25 | <25 | <25 |
| TRH $C_6$ - $C_{10}$ | mg/kg | <25 | <25 | <25 | <25 | <25 |
| vTPH $C_6$ - $C_{10}$ less BTEX (F1) | mg/kg | [NA] | <25 | <25 | <25 | [NA] |
| Benzene | mg/kg | [NA] | <0.2 | <0.2 | <0.2 | [NA] |
| Toluene | mg/kg | [NA] | <0.5 | <0.5 | <0.5 | [NA] |
| Ethylbenzene | mg/kg | [NA] | <1 | <1 | <1 | [NA] |
| m+p-xylene | mg/kg | [NA] | <2 | <2 | <2 | [NA] |
| o-Xylene | mg/kg | [NA] | <1 | <1 | <1 | [NA] |
| naphthalene | mg/kg | [NA] | <1 | <1 | <1 | [NA] |
| Total +ve Xylenes | mg/kg | [NA] | <1 | <1 | <1 | [NA] |
| *Surrogate* aaa-Trifluorotoluene | % | 76 | 85 | 85 | 92 | 80 |

| vTRH(C6-C10)/BTEXN in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-6 | 191466-7 | 191466-8 | 191466-9 | 191466-10 |
| Your Reference | UNITS | BH44_5.0 | BH44_6.0 | BH44_7.0 | BH44_8.0 | BH44_9.0 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 15/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 17/05/2018 | 17/05/2018 | 17/05/2018 | 16/05/2018 |
| TRH $C_6$ - $C_9$ | mg/kg | <25 | <25 | <25 | <25 | <25 |
| TRH $C_6$ - $C_{10}$ | mg/kg | <25 | <25 | <25 | <25 | <25 |
| vTPH $C_6$ - $C_{10}$ less BTEX (F1) | mg/kg | [NA] | <25 | <25 | <25 | [NA] |
| Benzene | mg/kg | [NA] | <0.2 | <0.2 | <0.2 | [NA] |
| Toluene | mg/kg | [NA] | <0.5 | <0.5 | <0.5 | [NA] |
| Ethylbenzene | mg/kg | [NA] | <1 | <1 | <1 | [NA] |
| m+p-xylene | mg/kg | [NA] | <2 | <2 | <2 | [NA] |
| o-Xylene | mg/kg | [NA] | <1 | <1 | <1 | [NA] |
| naphthalene | mg/kg | [NA] | <1 | <1 | <1 | [NA] |
| Total +ve Xylenes | mg/kg | [NA] | <1 | <1 | <1 | [NA] |
| *Surrogate* aaa-Trifluorotoluene | % | 84 | 95 | 92 | 92 | 75 |

| vTRH(C6-C10)/BTEXN in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-11 | 191466-12 | 191466-13 | 191466-14 | 191466-15 |
| Your Reference | UNITS | BH45_7.0 | BH45_7.8 | BH45_8.0 | BH46_0.2 | BH46_0.5 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 15/05/2018 | 16/05/2018 | 15/05/2018 | 15/05/2018 | 16/05/2018 |
| Date analysed | - | 16/05/2018 | 17/05/2018 | 16/05/2018 | 16/05/2018 | 17/05/2018 |
| TRH $C_6$ - $C_9$ | mg/kg | <25 | <25 | <25 | <25 | <25 |
| TRH $C_6$ - $C_{10}$ | mg/kg | <25 | <25 | <25 | <25 | <25 |
| vTPH $C_6$ - $C_{10}$ less BTEX (F1) | mg/kg | [NA] | <25 | [NA] | [NA] | <25 |
| Benzene | mg/kg | [NA] | <0.2 | [NA] | [NA] | <0.2 |
| Toluene | mg/kg | [NA] | <0.5 | [NA] | [NA] | <0.5 |
| Ethylbenzene | mg/kg | [NA] | <1 | [NA] | [NA] | <1 |
| m+p-xylene | mg/kg | [NA] | <2 | [NA] | [NA] | <2 |
| o-Xylene | mg/kg | [NA] | <1 | [NA] | [NA] | <1 |
| naphthalene | mg/kg | [NA] | <1 | [NA] | [NA] | <1 |
| Total +ve Xylenes | mg/kg | [NA] | <1 | [NA] | [NA] | <1 |
| *Surrogate* aaa-Trifluorotoluene | % | 78 | 91 | 85 | 79 | 92 |

| vTRH(C6-C10)/BTEXN in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-16 | 191466-17 | 191466-18 | 191466-19 | 191466-20 |
| Your Reference | UNITS | BH46_1.0 | BH46_2.0 | BH46_2.3 | BH47_3.6 | BH47_5.0 |
| Date Sampled | | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 16/05/2018 | 16/05/2018 | 15/05/2018 | 15/05/2018 | 16/05/2018 |
| Date analysed | - | 17/05/2018 | 17/05/2018 | 16/05/2018 | 16/05/2018 | 17/05/2018 |
| TRH $C_6$ - $C_9$ | mg/kg | <25 | <25 | <25 | <25 | <25 |
| TRH $C_6$ - $C_{10}$ | mg/kg | <25 | <25 | <25 | <25 | <25 |
| vTPH $C_6$ - $C_{10}$ less BTEX (F1) | mg/kg | <25 | <25 | [NA] | [NA] | <25 |
| Benzene | mg/kg | <0.2 | <0.2 | [NA] | [NA] | <0.2 |
| Toluene | mg/kg | <0.5 | <0.5 | [NA] | [NA] | <0.5 |
| Ethylbenzene | mg/kg | <1 | <1 | [NA] | [NA] | <1 |
| m+p-xylene | mg/kg | <2 | <2 | [NA] | [NA] | <2 |
| o-Xylene | mg/kg | <1 | <1 | [NA] | [NA] | <1 |
| naphthalene | mg/kg | <1 | <1 | [NA] | [NA] | <1 |
| Total +ve Xylenes | mg/kg | <1 | <1 | [NA] | [NA] | <1 |
| *Surrogate* aaa-Trifluorotoluene | % | 92 | 92 | 79 | 80 | 95 |

| vTRH(C6-C10)/BTEXN in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-21 | 191466-22 | 191466-23 | 191466-24 | 191466-25 |
| Your Reference | UNITS | BH47_6.0 | BH47_6.5 | BH47_7.0 | Dup 6 | Dup 7 |
| Date Sampled | | 11/05/2018 | 11/05/2018 | 11/05/2018 | 10/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Date analysed | - | 17/05/2018 | 17/05/2018 | 17/05/2018 | 17/05/2018 | 17/05/2018 |
| TRH $C_6$ - $C_9$ | mg/kg | <25 | <25 | <25 | <25 | <25 |
| TRH $C_6$ - $C_{10}$ | mg/kg | <25 | <25 | <25 | <25 | <25 |
| vTPH $C_6$ - $C_{10}$ less BTEX (F1) | mg/kg | <25 | <25 | [NA] | <25 | <25 |
| Benzene | mg/kg | <0.2 | <0.2 | [NA] | <0.2 | <0.2 |
| Toluene | mg/kg | <0.5 | <0.5 | [NA] | <0.5 | <0.5 |
| Ethylbenzene | mg/kg | <1 | <1 | [NA] | <1 | <1 |
| m+p-xylene | mg/kg | <2 | <2 | [NA] | <2 | <2 |
| o-Xylene | mg/kg | <1 | <1 | [NA] | <1 | <1 |
| naphthalene | mg/kg | <1 | <1 | [NA] | <1 | <1 |
| Total +ve Xylenes | mg/kg | <1 | <1 | [NA] | <1 | <1 |
| *Surrogate* aaa-Trifluorotoluene | % | 94 | 86 | 81 | 90 | 94 |

| svTRH (C10-C40) in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-1 | 191466-2 | 191466-3 | 191466-4 | 191466-5 |
| Your Reference | UNITS | BH43_5.0 | BH43_6.0 | BH43_7.0 | BH43_8.0 | BH43_9.0 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 16/05/2018 |
| TRH $C_{10}$ - $C_{14}$ | mg/kg | <50 | <50 | <50 | <50 | <50 |
| TRH $C_{15}$ - $C_{28}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRH $C_{29}$ - $C_{36}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRH >$C_{10}$ -$C_{16}$ | mg/kg | <50 | <50 | <50 | <50 | <50 |
| TRH >$C_{10}$ - $C_{16}$ less Naphthalene (F2) | mg/kg | [NA] | <50 | <50 | <50 | [NA] |
| TRH >$C_{16}$ -$C_{34}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRH >$C_{34}$ -$C_{40}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| Total +ve TRH (>C10-C40) | mg/kg | <50 | <50 | <50 | <50 | <50 |
| *Surrogate* o-Terphenyl | % | 71 | 71 | 72 | 71 | 70 |

| svTRH (C10-C40) in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-6 | 191466-7 | 191466-8 | 191466-9 | 191466-10 |
| Your Reference | UNITS | BH44_5.0 | BH44_6.0 | BH44_7.0 | BH44_8.0 | BH44_9.0 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| TRH $C_{10}$ - $C_{14}$ | mg/kg | <50 | <50 | <50 | <50 | <50 |
| TRH $C_{15}$ - $C_{28}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRH $C_{29}$ - $C_{36}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRH >$C_{10}$ -$C_{16}$ | mg/kg | <50 | <50 | <50 | <50 | <50 |
| TRH >$C_{10}$ - $C_{16}$ less Naphthalene (F2) | mg/kg | [NA] | <50 | <50 | <50 | [NA] |
| TRH >$C_{16}$ -$C_{34}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRH >$C_{34}$ -$C_{40}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| Total +ve TRH (>C10-C40) | mg/kg | <50 | <50 | <50 | <50 | <50 |
| *Surrogate* o-Terphenyl | % | 70 | 71 | 70 | 70 | 69 |

| svTRH (C10-C40) in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-11 | 191466-12 | 191466-13 | 191466-14 | 191466-15 |
| Your Reference | UNITS | BH45_7.0 | BH45_7.8 | BH45_8.0 | BH46_0.2 | BH46_0.5 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| TRH $C_{10}$ - $C_{14}$ | mg/kg | <50 | <50 | <50 | <50 | <50 |
| TRH $C_{15}$ - $C_{28}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRH $C_{29}$ - $C_{36}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRH >$C_{10}$ -$C_{16}$ | mg/kg | <50 | <50 | <50 | <50 | <50 |
| TRH >$C_{10}$ - $C_{16}$ less Naphthalene (F2) | mg/kg | [NA] | <50 | [NA] | [NA] | <50 |
| TRH >$C_{16}$ -$C_{34}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRH >$C_{34}$ -$C_{40}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| Total +ve TRH (>C10-C40) | mg/kg | <50 | <50 | <50 | <50 | <50 |
| *Surrogate* o-Terphenyl | % | 70 | 67 | 69 | 70 | 70 |

| svTRH (C10-C40) in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-16 | 191466-17 | 191466-18 | 191466-19 | 191466-20 |
| Your Reference | UNITS | BH46_1.0 | BH46_2.0 | BH46_2.3 | BH47_3.6 | BH47_5.0 |
| Date Sampled | | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| TRH $C_{10}$ - $C_{14}$ | mg/kg | <50 | <50 | <50 | <50 | <50 |
| TRH $C_{15}$ - $C_{28}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRH $C_{29}$ - $C_{36}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRH >$C_{10}$ -$C_{16}$ | mg/kg | <50 | <50 | <50 | <50 | <50 |
| TRH >$C_{10}$ - $C_{16}$ less Naphthalene (F2) | mg/kg | <50 | <50 | [NA] | [NA] | <50 |
| TRH >$C_{16}$ -$C_{34}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRH >$C_{34}$ -$C_{40}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| Total +ve TRH (>C10-C40) | mg/kg | <50 | <50 | <50 | <50 | <50 |
| *Surrogate* o-Terphenyl | % | 70 | 70 | 70 | 69 | 69 |

| svTRH (C10-C40) in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-21 | 191466-22 | 191466-23 | 191466-24 | 191466-25 |
| Your Reference | UNITS | BH47_6.0 | BH47_6.5 | BH47_7.0 | Dup 6 | Dup 7 |
| Date Sampled | | 11/05/2018 | 11/05/2018 | 11/05/2018 | 10/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| TRH $C_{10}$ - $C_{14}$ | mg/kg | <50 | <50 | <50 | <50 | <50 |
| TRH $C_{15}$ - $C_{28}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRH $C_{29}$ - $C_{36}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRH >$C_{10}$ -$C_{16}$ | mg/kg | <50 | <50 | <50 | <50 | <50 |
| TRH >$C_{10}$ - $C_{16}$ less Naphthalene (F2) | mg/kg | <50 | <50 | [NA] | <50 | <50 |
| TRH >$C_{16}$ -$C_{34}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| TRH >$C_{34}$ -$C_{40}$ | mg/kg | <100 | <100 | <100 | <100 | <100 |
| Total +ve TRH (>C10-C40) | mg/kg | <50 | <50 | <50 | <50 | <50 |
| *Surrogate* o-Terphenyl | % | 95 | 95 | 97 | 99 | 96 |

| PAHs in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-1 | 191466-2 | 191466-3 | 191466-4 | 191466-5 |
| Your Reference | UNITS | BH43_5.0 | BH43_6.0 | BH43_7.0 | BH43_8.0 | BH43_9.0 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Naphthalene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Acenaphthylene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Acenaphthene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fluorene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Phenanthrene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fluoranthene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Pyrene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Benzo(a)anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Chrysene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Benzo(b,j+k)fluoranthene | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| Benzo(a)pyrene | mg/kg | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 |
| Indeno(1,2,3-c,d)pyrene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dibenzo(a,h)anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Benzo(g,h,i)perylene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Total +ve PAH's | mg/kg | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 |
| Benzo(a)pyrene TEQ calc (zero) | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Benzo(a)pyrene TEQ calc(half) | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Benzo(a)pyrene TEQ calc(PQL) | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| *Surrogate p*-Terphenyl-d14 | % | 97 | 94 | 95 | 99 | 97 |

| PAHs in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-6 | 191466-7 | 191466-8 | 191466-9 | 191466-10 |
| Your Reference | UNITS | BH44_5.0 | BH44_6.0 | BH44_7.0 | BH44_8.0 | BH44_9.0 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Naphthalene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Acenaphthylene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Acenaphthene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fluorene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Phenanthrene | mg/kg | <0.1 | 0.1 | <0.1 | <0.1 | <0.1 |
| Anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fluoranthene | mg/kg | <0.1 | 0.2 | <0.1 | <0.1 | <0.1 |
| Pyrene | mg/kg | <0.1 | 0.2 | <0.1 | <0.1 | <0.1 |
| Benzo(a)anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Chrysene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Benzo(b,j+k)fluoranthene | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| Benzo(a)pyrene | mg/kg | <0.05 | 0.09 | <0.05 | <0.05 | <0.05 |
| Indeno(1,2,3-c,d)pyrene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dibenzo(a,h)anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Benzo(g,h,i)perylene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Total +ve PAH's | mg/kg | <0.05 | 0.65 | <0.05 | <0.05 | <0.05 |
| Benzo(a)pyrene TEQ calc (zero) | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Benzo(a)pyrene TEQ calc(half) | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Benzo(a)pyrene TEQ calc(PQL) | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| *Surrogate p*-Terphenyl-d14 | % | 98 | 97 | 100 | 100 | 100 |

| PAHs in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-11 | 191466-12 | 191466-13 | 191466-14 | 191466-15 |
| Your Reference | UNITS | BH45_7.0 | BH45_7.8 | BH45_8.0 | BH46_0.2 | BH46_0.5 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Naphthalene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Acenaphthylene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Acenaphthene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fluorene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Phenanthrene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fluoranthene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Pyrene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Benzo(a)anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Chrysene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Benzo(b,j+k)fluoranthene | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| Benzo(a)pyrene | mg/kg | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 |
| Indeno(1,2,3-c,d)pyrene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dibenzo(a,h)anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Benzo(g,h,i)perylene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Total +ve PAH's | mg/kg | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 |
| Benzo(a)pyrene TEQ calc (zero) | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Benzo(a)pyrene TEQ calc(half) | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Benzo(a)pyrene TEQ calc(PQL) | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| *Surrogate p*-Terphenyl-d14 | % | 96 | 97 | 96 | 98 | 97 |

| PAHs in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-16 | 191466-17 | 191466-18 | 191466-19 | 191466-20 |
| Your Reference | UNITS | BH46_1.0 | BH46_2.0 | BH46_2.3 | BH47_3.6 | BH47_5.0 |
| Date Sampled | | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Naphthalene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Acenaphthylene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Acenaphthene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fluorene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Phenanthrene | mg/kg | <0.1 | <0.1 | <0.1 | 0.2 | <0.1 |
| Anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fluoranthene | mg/kg | <0.1 | <0.1 | <0.1 | 0.4 | 0.2 |
| Pyrene | mg/kg | <0.1 | <0.1 | <0.1 | 0.5 | 0.3 |
| Benzo(a)anthracene | mg/kg | <0.1 | <0.1 | <0.1 | 0.2 | 0.1 |
| Chrysene | mg/kg | <0.1 | <0.1 | <0.1 | 0.2 | 0.1 |
| Benzo(b,j+k)fluoranthene | mg/kg | <0.2 | <0.2 | <0.2 | 0.4 | 0.2 |
| Benzo(a)pyrene | mg/kg | <0.05 | <0.05 | <0.05 | 0.2 | 0.1 |
| Indeno(1,2,3-c,d)pyrene | mg/kg | <0.1 | <0.1 | <0.1 | 0.1 | <0.1 |
| Dibenzo(a,h)anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Benzo(g,h,i)perylene | mg/kg | <0.1 | <0.1 | <0.1 | 0.2 | <0.1 |
| Total +ve PAH's | mg/kg | <0.05 | <0.05 | <0.05 | 2.4 | 1.1 |
| Benzo(a)pyrene TEQ calc (zero) | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Benzo(a)pyrene TEQ calc(half) | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Benzo(a)pyrene TEQ calc(PQL) | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| *Surrogate p*-Terphenyl-d14 | % | 96 | 100 | 99 | 97 | 98 |

| PAHs in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-21 | 191466-22 | 191466-23 | 191466-24 | 191466-25 |
| Your Reference | UNITS | BH47_6.0 | BH47_6.5 | BH47_7.0 | Dup 6 | Dup 7 |
| Date Sampled | | 11/05/2018 | 11/05/2018 | 11/05/2018 | 10/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Naphthalene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Acenaphthylene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Acenaphthene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fluorene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Phenanthrene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fluoranthene | mg/kg | <0.1 | <0.1 | 0.1 | <0.1 | <0.1 |
| Pyrene | mg/kg | <0.1 | <0.1 | 0.1 | <0.1 | <0.1 |
| Benzo(a)anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Chrysene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Benzo(b,j+k)fluoranthene | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| Benzo(a)pyrene | mg/kg | <0.05 | <0.05 | 0.06 | <0.05 | <0.05 |
| Indeno(1,2,3-c,d)pyrene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dibenzo(a,h)anthracene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Benzo(g,h,i)perylene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Total +ve PAH's | mg/kg | <0.05 | <0.05 | 0.3 | <0.05 | <0.05 |
| Benzo(a)pyrene TEQ calc (zero) | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Benzo(a)pyrene TEQ calc(half) | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Benzo(a)pyrene TEQ calc(PQL) | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| *Surrogate p*-Terphenyl-d14 | % | 95 | 97 | 97 | 96 | 98 |

| Organochlorine Pesticides in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-1 | 191466-5 | 191466-6 | 191466-10 | 191466-11 |
| Your Reference | UNITS | BH43_5.0 | BH43_9.0 | BH44_5.0 | BH44_9.0 | BH45_7.0 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| HCB | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| alpha-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| gamma-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| beta-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Heptachlor | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| delta-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Aldrin | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Heptachlor Epoxide | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| gamma-Chlordane | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| alpha-chlordane | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endosulfan I | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| pp-DDE | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dieldrin | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endrin | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| pp-DDD | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endosulfan II | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| pp-DDT | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endrin Aldehyde | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endosulfan Sulphate | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Methoxychlor | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Total +ve DDT+DDD+DDE | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| *Surrogate* TCMX | % | 103 | 102 | 102 | 102 | 101 |

| Organochlorine Pesticides in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-13 | 191466-14 | 191466-18 | 191466-19 | 191466-23 |
| Your Reference | UNITS | BH45_8.0 | BH46_0.2 | BH46_2.3 | BH47_3.6 | BH47_7.0 |
| Date Sampled | | 10/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| HCB | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| alpha-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| gamma-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| beta-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Heptachlor | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| delta-BHC | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Aldrin | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Heptachlor Epoxide | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| gamma-Chlordane | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| alpha-chlordane | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endosulfan I | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| pp-DDE | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dieldrin | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endrin | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| pp-DDD | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endosulfan II | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| pp-DDT | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endrin Aldehyde | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Endosulfan Sulphate | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Methoxychlor | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Total +ve DDT+DDD+DDE | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| *Surrogate* TCMX | % | 101 | 106 | 103 | 99 | 98 |

| Organophosphorus Pesticides | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-1 | 191466-5 | 191466-6 | 191466-10 | 191466-11 |
| Your Reference | UNITS | BH43_5.0 | BH43_9.0 | BH44_5.0 | BH44_9.0 | BH45_7.0 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Azinphos-methyl (Guthion) | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Bromophos-ethyl | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Chlorpyriphos | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Chlorpyriphos-methyl | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Diazinon | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dichlorvos | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dimethoate | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Ethion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fenitrothion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Malathion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Parathion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Ronnel | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| *Surrogate* TCMX | % | 103 | 102 | 102 | 102 | 101 |

| Organophosphorus Pesticides | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-13 | 191466-14 | 191466-18 | 191466-19 | 191466-23 |
| Your Reference | UNITS | BH45_8.0 | BH46_0.2 | BH46_2.3 | BH47_3.6 | BH47_7.0 |
| Date Sampled | | 10/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Azinphos-methyl (Guthion) | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Bromophos-ethyl | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Chlorpyriphos | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Chlorpyriphos-methyl | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Diazinon | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dichlorvos | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Dimethoate | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Ethion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Fenitrothion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Malathion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Parathion | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Ronnel | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| *Surrogate* TCMX | % | 101 | 106 | 103 | 99 | 98 |

| Acid Extractable metals in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-1 | 191466-2 | 191466-3 | 191466-4 | 191466-5 |
| Your Reference | UNITS | BH43_5.0 | BH43_6.0 | BH43_7.0 | BH43_8.0 | BH43_9.0 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Arsenic | mg/kg | <4 | <4 | <4 | <4 | <4 |
| Cadmium | mg/kg | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 |
| Copper | mg/kg | 4 | 6 | 5 | 5 | 4 |
| Mercury | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Molybdenum | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Nickel | mg/kg | 2 | 2 | 3 | 2 | 2 |
| Lead | mg/kg | 5 | 7 | 6 | 5 | 4 |
| Selenium | mg/kg | <2 | <2 | <2 | <2 | <2 |
| Silver | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Tin | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Chromium | mg/kg | 5 | 7 | 7 | 7 | 7 |

| Acid Extractable metals in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-6 | 191466-7 | 191466-8 | 191466-9 | 191466-10 |
| Your Reference | UNITS | BH44_5.0 | BH44_6.0 | BH44_7.0 | BH44_8.0 | BH44_9.0 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Arsenic | mg/kg | <4 | 8 | <4 | <4 | <4 |
| Cadmium | mg/kg | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 |
| Copper | mg/kg | 1 | 3 | 4 | 5 | 3 |
| Mercury | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Molybdenum | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Nickel | mg/kg | <1 | 1 | 2 | 5 | 3 |
| Lead | mg/kg | 4 | 12 | 4 | 3 | 4 |
| Selenium | mg/kg | <2 | <2 | <2 | <2 | <2 |
| Silver | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Tin | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Chromium | mg/kg | 4 | 15 | 12 | 16 | 13 |

| Acid Extractable metals in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-11 | 191466-12 | 191466-13 | 191466-14 | 191466-15 |
| Your Reference | UNITS | BH45_7.0 | BH45_7.8 | BH45_8.0 | BH46_0.2 | BH46_0.5 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Arsenic | mg/kg | <4 | <4 | <4 | <4 | <4 |
| Cadmium | mg/kg | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 |
| Copper | mg/kg | 4 | 2 | 6 | <1 | <1 |
| Mercury | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Molybdenum | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Nickel | mg/kg | 3 | 1 | 3 | <1 | <1 |
| Lead | mg/kg | 10 | 16 | 19 | 6 | 7 |
| Selenium | mg/kg | <2 | <2 | <2 | <2 | <2 |
| Silver | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Tin | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Chromium | mg/kg | 9 | 9 | 12 | 5 | 5 |

| Acid Extractable metals in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-16 | 191466-17 | 191466-18 | 191466-19 | 191466-20 |
| Your Reference | UNITS | BH46_1.0 | BH46_2.0 | BH46_2.3 | BH47_3.6 | BH47_5.0 |
| Date Sampled | | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Arsenic | mg/kg | <4 | <4 | <4 | 4 | <4 |
| Cadmium | mg/kg | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 |
| Copper | mg/kg | <1 | <1 | <1 | 4 | 3 |
| Mercury | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Molybdenum | mg/kg | <1 | 1 | 1 | <1 | <1 |
| Nickel | mg/kg | <1 | <1 | <1 | 2 | 3 |
| Lead | mg/kg | 7 | 6 | 5 | 25 | 14 |
| Selenium | mg/kg | <2 | <2 | <2 | <2 | <2 |
| Silver | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Tin | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Chromium | mg/kg | 3 | 9 | 10 | 9 | 9 |

| Acid Extractable metals in soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-21 | 191466-22 | 191466-23 | 191466-24 | 191466-25 |
| Your Reference | UNITS | BH47_6.0 | BH47_6.5 | BH47_7.0 | Dup 6 | Dup 7 |
| Date Sampled | | 11/05/2018 | 11/05/2018 | 11/05/2018 | 10/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Arsenic | mg/kg | 4 | <4 | <4 | <4 | <4 |
| Cadmium | mg/kg | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 |
| Copper | mg/kg | 6 | 5 | 2 | 5 | <1 |
| Mercury | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Molybdenum | mg/kg | <1 | 1 | <1 | <1 | 1 |
| Nickel | mg/kg | 1 | 1 | 1 | 2 | <1 |
| Lead | mg/kg | 14 | 13 | 8 | 5 | 6 |
| Selenium | mg/kg | <2 | <2 | <2 | <2 | <2 |
| Silver | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Tin | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Chromium | mg/kg | 10 | 9 | 6 | 6 | 10 |

| Acid Extractable metals in soil | | | |
|---|---|---|---|
| Our Reference | | 191466-27 | 191466-28 |
| Your Reference | UNITS | Split 5 | Spilt 6 |
| Date Sampled | | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil |
| Date prepared | - | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 15/05/2018 | 15/05/2018 |
| Arsenic | mg/kg | <4 | <4 |
| Cadmium | mg/kg | <0.4 | <0.4 |
| Copper | mg/kg | 5 | <1 |
| Mercury | mg/kg | <0.1 | <0.1 |
| Molybdenum | mg/kg | <1 | 2 |
| Nickel | mg/kg | 2 | <1 |
| Lead | mg/kg | 4 | 6 |
| Selenium | mg/kg | <2 | <2 |
| Silver | mg/kg | <1 | <1 |
| Tin | mg/kg | <1 | <1 |
| Chromium | mg/kg | 6 | 9 |

| Misc Inorg - Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-1 | 191466-5 | 191466-6 | 191466-10 | 191466-11 |
| Your Reference | UNITS | BH43_5.0 | BH43_9.0 | BH44_5.0 | BH44_9.0 | BH45_7.0 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Free Cyanide in soil | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Total Cyanide | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Hexavalent Chromium, $Cr^{6+}$ | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Total Fluoride | mg/kg | <50 | <50 | <50 | <50 | <50 |

| Misc Inorg - Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-13 | 191466-14 | 191466-18 | 191466-19 | 191466-23 |
| Your Reference | UNITS | BH45_8.0 | BH46_0.2 | BH46_2.3 | BH47_3.6 | BH47_7.0 |
| Date Sampled | | 10/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Free Cyanide in soil | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Total Cyanide | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Hexavalent Chromium, $Cr^{6+}$ | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Total Fluoride | mg/kg | <50 | <50 | <50 | <50 | <50 |

| Moisture | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-1 | 191466-2 | 191466-3 | 191466-4 | 191466-5 |
| Your Reference | UNITS | BH43_5.0 | BH43_6.0 | BH43_7.0 | BH43_8.0 | BH43_9.0 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Moisture | % | 8.5 | 10 | 16 | 13 | 11 |

| Moisture | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-6 | 191466-7 | 191466-8 | 191466-9 | 191466-10 |
| Your Reference | UNITS | BH44_5.0 | BH44_6.0 | BH44_7.0 | BH44_8.0 | BH44_9.0 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Moisture | % | 5.1 | 6.8 | 6.5 | 6.3 | 7.2 |

| Moisture | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-11 | 191466-12 | 191466-13 | 191466-14 | 191466-15 |
| Your Reference | UNITS | BH45_7.0 | BH45_7.8 | BH45_8.0 | BH46_0.2 | BH46_0.5 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Moisture | % | 7.1 | 6.3 | 7.4 | 3.8 | 4.5 |

| Moisture | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-16 | 191466-17 | 191466-18 | 191466-19 | 191466-20 |
| Your Reference | UNITS | BH46_1.0 | BH46_2.0 | BH46_2.3 | BH47_3.6 | BH47_5.0 |
| Date Sampled | | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Moisture | % | 4.3 | 4.2 | 3.9 | 11 | 11 |

| Moisture | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-21 | 191466-22 | 191466-23 | 191466-24 | 191466-25 |
| Your Reference | UNITS | BH47_6.0 | BH47_6.5 | BH47_7.0 | Dup 6 | Dup 7 |
| Date Sampled | | 11/05/2018 | 11/05/2018 | 11/05/2018 | 10/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date prepared | - | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Moisture | % | 6.9 | 17 | 15 | 8.5 | 4.5 |

| Moisture | | | |
|---|---|---|---|
| Our Reference | | 191466-27 | 191466-28 |
| Your Reference | UNITS | Split 5 | Spilt 6 |
| Date Sampled | | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil |
| Date prepared | - | 15/05/2018 | 15/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 |
| Moisture | % | 8.3 | 4.3 |

| SVOCs in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-1 | 191466-5 | 191466-6 | 191466-10 | 191466-11 |
| Your Reference | UNITS | BH43_5.0 | BH43_9.0 | BH44_5.0 | BH44_9.0 | BH45_7.0 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 |
| Date analysed | - | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 |
| Nitrobenzene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| 2,4-Dintrotoluene | mg/kg | <1 | <1 | <1 | <1 | <1 |

| SVOCs in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-13 | 191466-14 | 191466-18 | 191466-19 | 191466-23 |
| Your Reference | UNITS | BH45_8.0 | BH46_0.2 | BH46_2.3 | BH47_3.6 | BH47_7.0 |
| Date Sampled | | 10/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 |
| Date analysed | - | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 |
| Nitrobenzene | mg/kg | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| 2,4-Dintrotoluene | mg/kg | <1 | <1 | <1 | <1 | <1 |

| Speciated Phenols in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-1 | 191466-5 | 191466-6 | 191466-10 | 191466-11 |
| Your Reference | UNITS | BH43_5.0 | BH43_9.0 | BH44_5.0 | BH44_9.0 | BH45_7.0 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 |
| Date analysed | - | 19/05/2018 | 19/05/2018 | 19/05/2018 | 19/05/2018 | 19/05/2018 |
| Phenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 2-Chlorophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 4-Chloro-3-methylphenol | mg/kg | <5 | <5 | <5 | <5 | <5 |
| 2-Methylphenol (o-cresol) | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 3/4-Methylphenol (m/p-cresol) | mg/kg | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 |
| 2-Nitrophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 2,4 -Dimethylphenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 2,4-Dichlorophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 2,6-Dichlorophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 2,4,5-Trichlorophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 2,4,6-Trichlorophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 2,4-Dinitrophenol | mg/kg | <4 | <4 | <4 | <4 | <4 |
| 4-Nitrophenol | mg/kg | <4 | <4 | <4 | <4 | <4 |
| 2346-Tetrachlorophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 2-methyl-4,6-Dinitrophenol | mg/kg | <10 | <10 | <10 | <10 | <10 |
| Pentachlorophenol | mg/kg | <5 | <5 | <5 | <5 | <5 |
| *Surrogate* Phenol-$d_6$ | % | 94 | 96 | 94 | 96 | 96 |

| Speciated Phenols in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-13 | 191466-14 | 191466-18 | 191466-19 | 191466-23 |
| Your Reference | UNITS | BH45_8.0 | BH46_0.2 | BH46_2.3 | BH47_3.6 | BH47_7.0 |
| Date Sampled | | 10/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 |
| Date analysed | - | 19/05/2018 | 19/05/2018 | 19/05/2018 | 19/05/2018 | 19/05/2018 |
| Phenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 2-Chlorophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 4-Chloro-3-methylphenol | mg/kg | <5 | <5 | <5 | <5 | <5 |
| 2-Methylphenol (o-cresol) | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 3/4-Methylphenol (m/p-cresol) | mg/kg | <0.4 | <0.4 | <0.4 | <0.4 | <0.4 |
| 2-Nitrophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 2,4 -Dimethylphenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 2,4-Dichlorophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 2,6-Dichlorophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 2,4,5-Trichlorophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 2,4,6-Trichlorophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 2,4-Dinitrophenol | mg/kg | <4 | <4 | <4 | <4 | <4 |
| 4-Nitrophenol | mg/kg | <4 | <4 | <4 | <4 | <4 |
| 2346-Tetrachlorophenol | mg/kg | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 |
| 2-methyl-4,6-Dinitrophenol | mg/kg | <10 | <10 | <10 | <10 | <10 |
| Pentachlorophenol | mg/kg | <5 | <5 | <5 | <5 | <5 |
| *Surrogate* Phenol-$d_6$ | % | 95 | 95 | 95 | 95 | 96 |

| Phenoxy Acid Herbicides in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-1 | 191466-5 | 191466-6 | 191466-10 | 191466-11 |
| Your Reference | UNITS | BH43_5.0 | BH43_9.0 | BH44_5.0 | BH44_9.0 | BH45_7.0 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 22/05/2018 | 22/05/2018 | 22/05/2018 | 22/05/2018 | 22/05/2018 |
| Date analysed | - | 22/05/2018 | 22/05/2018 | 22/05/2018 | 22/05/2018 | 22/05/2018 |
| Clopyralid | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| 3,5-Dichlorobenzoic acid | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| o-chlorophenoxy acetic acid | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| 4-CPA | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Dicamba | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| MCPP | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| MCPA | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Dichlorprop | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| 2,4-D | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Bromoxynil | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Triclopyr | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| 2,4,5-TP | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| 2,4,5-T | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| MCPB | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Dinoseb | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 2,4-DB | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Ioxynil | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Picloram | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| DCPA (Chlorthal) Diacid | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Acifluorfen | mg/kg | <2 | <2 | <2 | <2 | <2 |
| 2,4,6-T | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| 2,6-D | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Surrogate 2.4- DCPA | % | 100 | 87 | 95 | 93 | 88 |

| Phenoxy Acid Herbicides in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-13 | 191466-14 | 191466-18 | 191466-19 | 191466-23 |
| Your Reference | UNITS | BH45_8.0 | BH46_0.2 | BH46_2.3 | BH47_3.6 | BH47_7.0 |
| Date Sampled | | 10/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 22/05/2018 | 22/05/2018 | 22/05/2018 | 22/05/2018 | 22/05/2018 |
| Date analysed | - | 22/05/2018 | 22/05/2018 | 22/05/2018 | 22/05/2018 | 22/05/2018 |
| Clopyralid | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| 3,5-Dichlorobenzoic acid | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| o-chlorophenoxy acetic acid | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| 4-CPA | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Dicamba | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| MCPP | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| MCPA | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Dichlorprop | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| 2,4-D | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Bromoxynil | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Triclopyr | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| 2,4,5-TP | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| 2,4,5-T | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| MCPB | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Dinoseb | mg/kg | <1 | <1 | <1 | <1 | <1 |
| 2,4-DB | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Ioxynil | mg/kg | <1 | <1 | <1 | <1 | <1 |
| Picloram | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| DCPA (Chlorthal) Diacid | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Acifluorfen | mg/kg | <2 | <2 | <2 | <2 | <2 |
| 2,4,6-T | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| 2,6-D | mg/kg | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| Surrogate 2.4- DCPA | % | 95 | 95 | 95 | 95 | 96 |

| Phthalates in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-1 | 191466-5 | 191466-6 | 191466-10 | 191466-11 |
| Your Reference | UNITS | BH43_5.0 | BH43_9.0 | BH44_5.0 | BH44_9.0 | BH45_7.0 |
| Date Sampled | | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 | 10/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 |
| Date analysed | - | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 |
| Dimethylphthalate | mg/kg | <1 | <1 | <1 | <1 | <1 |
| diethylphthalate | mg/kg | <1 | <1 | <1 | <1 | <1 |
| di-n-butylphthalate | mg/kg | <5 | <5 | <5 | <5 | <5 |
| butylbenzylphthalate | mg/kg | <1 | <1 | <1 | <1 | <1 |
| bis(2-ethylhexyl)phthalate | mg/kg | <5 | <5 | <5 | <5 | <5 |
| di-n-octylphthalate | mg/kg | <1 | <1 | <1 | <1 | <1 |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | 93 | 92 | 95 | 89 | 99 |

| Phthalates in Soil | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 191466-13 | 191466-14 | 191466-18 | 191466-19 | 191466-23 |
| Your Reference | UNITS | BH45_8.0 | BH46_0.2 | BH46_2.3 | BH47_3.6 | BH47_7.0 |
| Date Sampled | | 10/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 | 11/05/2018 |
| Type of sample | | Soil | Soil | Soil | Soil | Soil |
| Date extracted | - | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 |
| Date analysed | - | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 |
| Dimethylphthalate | mg/kg | <1 | <1 | <1 | <1 | <1 |
| diethylphthalate | mg/kg | <1 | <1 | <1 | <1 | <1 |
| di-n-butylphthalate | mg/kg | <5 | <5 | <5 | <5 | <5 |
| butylbenzylphthalate | mg/kg | <1 | <1 | <1 | <1 | <1 |
| bis(2-ethylhexyl)phthalate | mg/kg | <5 | <5 | <5 | <5 | <5 |
| di-n-octylphthalate | mg/kg | <1 | <1 | <1 | <1 | <1 |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | 92 | 93 | 94 | 96 | 94 |

| vTRH in Water (C6-C9) NEPM | | |
|---|---|---|
| Our Reference | | 191466-26 |
| Your Reference | UNITS | Trip 1 |
| Date Sampled | | 10/05/2018 |
| Type of sample | | Water |
| Date extracted | - | 15/05/2018 |
| Date analysed | - | 16/05/2018 |
| TRH $C_6$ - $C_9$ | µg/L | <10 |
| TRH $C_6$ - $C_{10}$ | µg/L | <10 |
| *Surrogate* Dibromofluoromethane | % | 100 |
| *Surrogate* toluene-d8 | % | 98 |
| *Surrogate* 4-BFB | % | 99 |

| svTRH (C10-C40) in Water | | |
|---|---|---|
| Our Reference | | 191466-26 |
| Your Reference | UNITS | Trip 1 |
| Date Sampled | | 10/05/2018 |
| Type of sample | | Water |
| Date extracted | - | 15/05/2018 |
| Date analysed | - | 15/05/2018 |
| TRH $C_{10}$ - $C_{14}$ | µg/L | <50 |
| TRH $C_{15}$ - $C_{28}$ | µg/L | <100 |
| TRH $C_{29}$ - $C_{36}$ | µg/L | <100 |
| TRH >$C_{10}$ - $C_{16}$ | µg/L | <50 |
| TRH >$C_{16}$ - $C_{34}$ | µg/L | <100 |
| TRH >$C_{34}$ - $C_{40}$ | µg/L | <100 |
| *Surrogate* o-Terphenyl | % | 81 |

| Method ID | Methodology Summary |
|---|---|
| **Ext-054** | Analysed by MPL Envirolab |
| **Inorg-008** | Moisture content determined by heating at 105+/-5 °C for a minimum of 12 hours. |
| **Inorg-014** | Cyanide - free, total, weak acid dissociable by segmented flow analyser (in line dialysis with colourimetric finish).<br>Solids are extracted in a caustic media prior to analysis. |
| **Inorg-024** | Hexavalent Chromium (Cr6+) - determined colourimetrically. |
| **Inorg-026/53** | Fluoride by caustic fusion and determined by ion selective electrode (ISE) analysis. |
| **Metals-020** | Determination of various metals by ICP-AES. |
| **Metals-021** | Determination of Mercury by Cold Vapour AAS. |
| **Org-003** | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-FID.<br>F2 = (>C10-C16)-Naphthalene as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater (HSLs Tables 1A (3, 4)). Note Naphthalene is determined from the VOC analysis. |
| **Org-003** | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-FID.<br><br>F2 = (>C10-C16)-Naphthalene as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater (HSLs Tables 1A (3, 4)). Note Naphthalene is determined from the VOC analysis.<br><br>Note, the Total +ve TRH PQL is reflective of the lowest individual PQL and is therefore "Total +ve TRH" is simply a sum of the positive individual TRH fractions (>C10-C40). |
| **Org-005** | Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC with dual ECD's. |
| **Org-005** | Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC with dual ECD's.<br>Note, the Total +ve reported DDD+DDE+DDT PQL is reflective of the lowest individual PQL and is therefore simply a sum of the positive individually report DDD+DDE+DDT. |
| **Org-008** | Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC with dual ECD's. |
| **Org-012** | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS. |

| Method ID | Methodology Summary |
|---|---|
| **Org-012** | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS. Benzo(a)pyrene TEQ as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater - 2013.<br>For soil results:-<br>1. 'EQ PQL'values are assuming all contributing PAHs reported as <PQL are actually at the PQL. This is the most conservative approach and can give false positive TEQs given that PAHs that contribute to the TEQ calculation may not be present.<br>2. 'EQ zero'values are assuming all contributing PAHs reported as <PQL are zero. This is the least conservative approach and is more susceptible to false negative TEQs when PAHs that contribute to the TEQ calculation are present but below PQL.<br>3. 'EQ half PQL'values are assuming all contributing PAHs reported as <PQL are half the stipulated PQL. Hence a mid-point between the most and least conservative approaches above.<br>Note, the Total +ve PAHs PQL is reflective of the lowest individual PQL and is therefore "Total +ve PAHs" is simply a sum of the positive individual PAHs. |
| **Org-014** | Soil samples are extracted with methanol and spiked into water prior to analysing by purge and trap GC-MS. |
| **Org-016** | Soil samples are extracted with methanol and spiked into water prior to analysing by purge and trap GC-MS. Water samples are analysed directly by purge and trap GC-MS. F1 = (C6-C10)-BTEX as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater. |
| **Org-016** | Soil samples are extracted with methanol and spiked into water prior to analysing by purge and trap GC-MS. Water samples are analysed directly by purge and trap GC-MS. F1 = (C6-C10)-BTEX as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater.<br>Note, the Total +ve Xylene PQL is reflective of the lowest individual PQL and is therefore "Total +ve Xylenes" is simply a sum of the positive individual Xylenes. |

| QUALITY CONTROL: VOCs in soil | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-3 | 191466-5 |
| Date extracted | - | | | 16/05/2018 | 1 | 15/05/2018 | 15/05/2018 | | 15/05/2018 | 15/05/2018 |
| Date analysed | - | | | 17/05/2018 | 1 | 16/05/2018 | 16/05/2018 | | 16/05/2018 | 16/05/2018 |
| Dichlorodifluoromethane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| Chloromethane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| Vinyl Chloride | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| Bromomethane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| Chloroethane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| Trichlorofluoromethane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| 1,1-Dichloroethene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| trans-1,2-dichloroethene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| 1,1-dichloroethane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | 81 | 86 |
| cis-1,2-dichloroethene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| bromochloromethane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| chloroform | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | 81 | 85 |
| 2,2-dichloropropane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| 1,2-dichloroethane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | 73 | 78 |
| 1,1,1-trichloroethane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | 80 | 85 |
| 1,1-dichloropropene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| Cyclohexane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| carbon tetrachloride | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| Benzene | mg/kg | 0.2 | Org-014 | <0.2 | 1 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| dibromomethane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| 1,2-dichloropropane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| trichloroethene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | 77 | 82 |
| bromodichloromethane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | 80 | 85 |
| trans-1,3-dichloropropene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| cis-1,3-dichloropropene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| 1,1,2-trichloroethane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| Toluene | mg/kg | 0.5 | Org-014 | <0.5 | 1 | <0.5 | <0.5 | 0 | [NT] | [NT] |
| 1,3-dichloropropane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| dibromochloromethane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | 99 | 105 |
| 1,2-dibromoethane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| tetrachloroethene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | 81 | 85 |
| 1,1,1,2-tetrachloroethane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| chlorobenzene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| Ethylbenzene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| bromoform | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| m+p-xylene | mg/kg | 2 | Org-014 | <2 | 1 | <2 | <2 | 0 | [NT] | [NT] |
| styrene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| 1,1,2,2-tetrachloroethane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| o-Xylene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |

| QUALITY CONTROL: VOCs in soil | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-3 | 191466-5 |
| 1,2,3-trichloropropane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| isopropylbenzene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| bromobenzene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| n-propyl benzene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| 2-chlorotoluene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| 4-chlorotoluene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| 1,3,5-trimethyl benzene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| tert-butyl benzene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| 1,2,4-trimethyl benzene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| 1,3-dichlorobenzene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| sec-butyl benzene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| 1,4-dichlorobenzene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| 4-isopropyl toluene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| 1,2-dichlorobenzene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| n-butyl benzene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| 1,2-dibromo-3-chloropropane | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| 1,2,4-trichlorobenzene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| hexachlorobutadiene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| 1,2,3-trichlorobenzene | mg/kg | 1 | Org-014 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| *Surrogate* Dibromofluorometha | % | | Org-014 | 99 | 1 | 99 | 100 | 1 | 100 | 101 |
| *Surrogate* aaa-Trifluorotoluene | % | | Org-014 | 86 | 1 | 85 | 82 | 4 | 88 | 89 |
| *Surrogate* Toluene-$d_8$ | % | | Org-014 | 100 | 1 | 99 | 101 | 2 | 102 | 101 |
| *Surrogate* 4-Bromofluorobenzene | % | | Org-014 | 97 | 1 | 97 | 95 | 2 | 99 | 97 |

| QUALITY CONTROL: VOCs in soil | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | [NT] | [NT] |
| Date extracted | - | | | [NT] | 11 | 15/05/2018 | 15/05/2018 | | [NT] | [NT] |
| Date analysed | - | | | [NT] | 11 | 16/05/2018 | 16/05/2018 | | [NT] | [NT] |
| Dichlorodifluoromethane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| Chloromethane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| Vinyl Chloride | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| Bromomethane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| Chloroethane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| Trichlorofluoromethane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 1,1-Dichloroethene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| trans-1,2-dichloroethene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 1,1-dichloroethane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| cis-1,2-dichloroethene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| bromochloromethane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| chloroform | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 2,2-dichloropropane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 1,2-dichloroethane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 1,1,1-trichloroethane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 1,1-dichloropropene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| Cyclohexane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| carbon tetrachloride | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| Benzene | mg/kg | 0.2 | Org-014 | [NT] | 11 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| dibromomethane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 1,2-dichloropropane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| trichloroethene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| bromodichloromethane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| trans-1,3-dichloropropene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| cis-1,3-dichloropropene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 1,1,2-trichloroethane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| Toluene | mg/kg | 0.5 | Org-014 | [NT] | 11 | <0.5 | <0.5 | 0 | [NT] | [NT] |
| 1,3-dichloropropane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| dibromochloromethane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 1,2-dibromoethane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| tetrachloroethene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 1,1,1,2-tetrachloroethane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| chlorobenzene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| Ethylbenzene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| bromoform | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| m+p-xylene | mg/kg | 2 | Org-014 | [NT] | 11 | <2 | <2 | 0 | [NT] | [NT] |
| styrene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 1,1,2,2-tetrachloroethane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| o-Xylene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |

| QUALITY CONTROL: VOCs in soil | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | [NT] | [NT] |
| 1,2,3-trichloropropane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| isopropylbenzene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| bromobenzene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| n-propyl benzene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 2-chlorotoluene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 4-chlorotoluene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 1,3,5-trimethyl benzene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| tert-butyl benzene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 1,2,4-trimethyl benzene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 1,3-dichlorobenzene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| sec-butyl benzene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 1,4-dichlorobenzene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 4-isopropyl toluene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 1,2-dichlorobenzene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| n-butyl benzene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 1,2-dibromo-3-chloropropane | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 1,2,4-trichlorobenzene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| hexachlorobutadiene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| 1,2,3-trichlorobenzene | mg/kg | 1 | Org-014 | [NT] | 11 | <1 | <1 | 0 | [NT] | [NT] |
| *Surrogate* Dibromofluorometha | % | | Org-014 | [NT] | 11 | 101 | 101 | 0 | [NT] | [NT] |
| *Surrogate* aaa-Trifluorotoluene | % | | Org-014 | [NT] | 11 | 88 | 90 | 2 | [NT] | [NT] |
| *Surrogate* Toluene-$d_8$ | % | | Org-014 | [NT] | 11 | 100 | 98 | 2 | [NT] | [NT] |
| *Surrogate* 4-Bromofluorobenzene | % | | Org-014 | [NT] | 11 | 98 | 94 | 4 | [NT] | [NT] |

| QUALITY CONTROL: vTRH(C6-C10)/BTEXN in Soil | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-3 | 191466-5 |
| Date extracted | - | | | 16/05/2018 | 1 | 15/05/2018 | 15/05/2018 | | 15/05/2018 | 15/05/2018 |
| Date analysed | - | | | 17/05/2018 | 1 | 16/05/2018 | 16/05/2018 | | 16/05/2018 | 16/05/2018 |
| TRH $C_6$ - $C_9$ | mg/kg | 25 | Org-016 | <25 | 1 | <25 | <25 | 0 | 88 | 85 |
| TRH $C_6$ - $C_{10}$ | mg/kg | 25 | Org-016 | <25 | 1 | <25 | <25 | 0 | 88 | 85 |
| Benzene | mg/kg | 0.2 | Org-016 | <0.2 | 21 | <0.2 | <0.2 | 0 | 84 | 83 |
| Toluene | mg/kg | 0.5 | Org-016 | <0.5 | 21 | <0.5 | <0.5 | 0 | 93 | 85 |
| Ethylbenzene | mg/kg | 1 | Org-016 | <1 | 21 | <1 | <1 | 0 | 90 | 86 |
| m+p-xylene | mg/kg | 2 | Org-016 | <2 | 21 | <2 | <2 | 0 | 87 | 85 |
| o-Xylene | mg/kg | 1 | Org-016 | <1 | 21 | <1 | <1 | 0 | 85 | 87 |
| naphthalene | mg/kg | 1 | Org-014 | <1 | 21 | <1 | <1 | 0 | [NT] | [NT] |
| *Surrogate* aaa-Trifluorotoluene | % | | Org-016 | 100 | 1 | 76 | 73 | 4 | 86 | 79 |

| QUALITY CONTROL: vTRH(C6-C10)/BTEXN in Soil | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | [NT] | [NT] |
| Date extracted | - | | | [NT] | 11 | 15/05/2018 | 15/05/2018 | | [NT] | [NT] |
| Date analysed | - | | | [NT] | 11 | 16/05/2018 | 16/05/2018 | | [NT] | [NT] |
| TRH $C_6$ - $C_9$ | mg/kg | 25 | Org-016 | [NT] | 11 | <25 | <25 | 0 | [NT] | [NT] |
| TRH $C_6$ - $C_{10}$ | mg/kg | 25 | Org-016 | [NT] | 11 | <25 | <25 | 0 | [NT] | [NT] |
| *Surrogate* aaa-Trifluorotoluene | % | | Org-016 | [NT] | 11 | 78 | 80 | 3 | [NT] | [NT] |

| QUALITY CONTROL: vTRH(C6-C10)/BTEXN in Soil | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | [NT] | [NT] |
| Date extracted | - | | | [NT] | 21 | 16/05/2018 | 16/05/2018 | | [NT] | [NT] |
| Date analysed | - | | | [NT] | 21 | 17/05/2018 | 17/05/2018 | | [NT] | [NT] |
| TRH $C_6$ - $C_9$ | mg/kg | 25 | Org-016 | [NT] | 21 | <25 | <25 | 0 | [NT] | [NT] |
| TRH $C_6$ - $C_{10}$ | mg/kg | 25 | Org-016 | [NT] | 21 | <25 | <25 | 0 | [NT] | [NT] |
| *Surrogate* aaa-Trifluorotoluene | % | | Org-016 | [NT] | 21 | 94 | 99 | 5 | [NT] | [NT] |

| QUALITY CONTROL: svTRH (C10-C40) in Soil | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-3 | 191466-5 |
| Date extracted | - | | | 15/05/2018 | 1 | 15/05/2018 | 15/05/2018 | | 15/05/2018 | 15/05/2018 |
| Date analysed | - | | | 16/05/2018 | 1 | 15/05/2018 | 15/05/2018 | | 15/05/2018 | 16/05/2018 |
| TRH $C_{10}$ - $C_{14}$ | mg/kg | 50 | Org-003 | <50 | 1 | <50 | <50 | 0 | 92 | 94 |
| TRH $C_{15}$ - $C_{28}$ | mg/kg | 100 | Org-003 | <100 | 1 | <100 | <100 | 0 | 83 | 83 |
| TRH $C_{29}$ - $C_{36}$ | mg/kg | 100 | Org-003 | <100 | 1 | <100 | <100 | 0 | 77 | 71 |
| TRH >$C_{10}$ -$C_{16}$ | mg/kg | 50 | Org-003 | <50 | 1 | <50 | <50 | 0 | 92 | 94 |
| TRH >$C_{16}$ -$C_{34}$ | mg/kg | 100 | Org-003 | <100 | 1 | <100 | <100 | 0 | 83 | 83 |
| TRH >$C_{34}$ -$C_{40}$ | mg/kg | 100 | Org-003 | <100 | 1 | <100 | <100 | 0 | 77 | 71 |
| *Surrogate* o-Terphenyl | % | | Org-003 | 99 | 1 | 71 | 72 | 1 | 81 | 70 |

| QUALITY CONTROL: svTRH (C10-C40) in Soil | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-4 | 191466-22 |
| Date extracted | - | | | [NT] | 11 | 15/05/2018 | 15/05/2018 | | 15/05/2018 | 15/05/2018 |
| Date analysed | - | | | [NT] | 11 | 16/05/2018 | 16/05/2018 | | 16/05/2018 | 16/05/2018 |
| TRH $C_{10}$ - $C_{14}$ | mg/kg | 50 | Org-003 | [NT] | 11 | <50 | <50 | 0 | 100 | 104 |
| TRH $C_{15}$ - $C_{28}$ | mg/kg | 100 | Org-003 | [NT] | 11 | <100 | <100 | 0 | 80 | 81 |
| TRH $C_{29}$ - $C_{36}$ | mg/kg | 100 | Org-003 | [NT] | 11 | <100 | <100 | 0 | 77 | 71 |
| TRH >$C_{10}$ -$C_{16}$ | mg/kg | 50 | Org-003 | [NT] | 11 | <50 | <50 | 0 | 100 | 104 |
| TRH >$C_{16}$ -$C_{34}$ | mg/kg | 100 | Org-003 | [NT] | 11 | <100 | <100 | 0 | 80 | 81 |
| TRH >$C_{34}$ -$C_{40}$ | mg/kg | 100 | Org-003 | [NT] | 11 | <100 | <100 | 0 | 77 | 71 |
| *Surrogate* o-Terphenyl | % | | Org-003 | [NT] | 11 | 70 | 70 | 0 | 81 | 95 |

| QUALITY CONTROL: PAHs in Soil | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-3 | 191466-5 |
| Date extracted | - | | | 15/05/2018 | 1 | 15/05/2018 | 15/05/2018 | | 15/05/2018 | 15/05/2018 |
| Date analysed | - | | | 16/05/2018 | 1 | 16/05/2018 | 16/05/2018 | | 16/05/2018 | 16/05/2018 |
| Naphthalene | mg/kg | 0.1 | Org-012 | <0.1 | 1 | <0.1 | <0.1 | 0 | 89 | 84 |
| Acenaphthylene | mg/kg | 0.1 | Org-012 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Acenaphthene | mg/kg | 0.1 | Org-012 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Fluorene | mg/kg | 0.1 | Org-012 | <0.1 | 1 | <0.1 | <0.1 | 0 | 93 | 89 |
| Phenanthrene | mg/kg | 0.1 | Org-012 | <0.1 | 1 | <0.1 | <0.1 | 0 | 94 | 91 |
| Anthracene | mg/kg | 0.1 | Org-012 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Fluoranthene | mg/kg | 0.1 | Org-012 | <0.1 | 1 | <0.1 | <0.1 | 0 | 97 | 96 |
| Pyrene | mg/kg | 0.1 | Org-012 | <0.1 | 1 | <0.1 | <0.1 | 0 | 93 | 94 |
| Benzo(a)anthracene | mg/kg | 0.1 | Org-012 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Chrysene | mg/kg | 0.1 | Org-012 | <0.1 | 1 | <0.1 | <0.1 | 0 | 88 | 83 |
| Benzo(b,j+k)fluoranthene | mg/kg | 0.2 | Org-012 | <0.2 | 1 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| Benzo(a)pyrene | mg/kg | 0.05 | Org-012 | <0.05 | 1 | <0.05 | <0.05 | 0 | 87 | 79 |
| Indeno(1,2,3-c,d)pyrene | mg/kg | 0.1 | Org-012 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Dibenzo(a,h)anthracene | mg/kg | 0.1 | Org-012 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Benzo(g,h,i)perylene | mg/kg | 0.1 | Org-012 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| *Surrogate p*-Terphenyl-d14 | % | | Org-012 | 105 | 1 | 97 | 97 | 0 | 120 | 124 |

| QUALITY CONTROL: PAHs in Soil | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-4 | 191466-22 |
| Date extracted | - | | | [NT] | 11 | 15/05/2018 | 15/05/2018 | | 15/05/2018 | 15/05/2018 |
| Date analysed | - | | | [NT] | 11 | 16/05/2018 | 16/05/2018 | | 16/05/2018 | 16/05/2018 |
| Naphthalene | mg/kg | 0.1 | Org-012 | [NT] | 11 | <0.1 | <0.1 | 0 | 89 | 89 |
| Acenaphthylene | mg/kg | 0.1 | Org-012 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Acenaphthene | mg/kg | 0.1 | Org-012 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Fluorene | mg/kg | 0.1 | Org-012 | [NT] | 11 | <0.1 | <0.1 | 0 | 93 | 92 |
| Phenanthrene | mg/kg | 0.1 | Org-012 | [NT] | 11 | <0.1 | <0.1 | 0 | 95 | 92 |
| Anthracene | mg/kg | 0.1 | Org-012 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Fluoranthene | mg/kg | 0.1 | Org-012 | [NT] | 11 | <0.1 | <0.1 | 0 | 97 | 96 |
| Pyrene | mg/kg | 0.1 | Org-012 | [NT] | 11 | <0.1 | <0.1 | 0 | 94 | 92 |
| Benzo(a)anthracene | mg/kg | 0.1 | Org-012 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Chrysene | mg/kg | 0.1 | Org-012 | [NT] | 11 | <0.1 | <0.1 | 0 | 88 | 87 |
| Benzo(b,j+k)fluoranthene | mg/kg | 0.2 | Org-012 | [NT] | 11 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| Benzo(a)pyrene | mg/kg | 0.05 | Org-012 | [NT] | 11 | <0.05 | <0.05 | 0 | 87 | 82 |
| Indeno(1,2,3-c,d)pyrene | mg/kg | 0.1 | Org-012 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Dibenzo(a,h)anthracene | mg/kg | 0.1 | Org-012 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Benzo(g,h,i)perylene | mg/kg | 0.1 | Org-012 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| *Surrogate p*-Terphenyl-d14 | % | | Org-012 | [NT] | 11 | 96 | 96 | 0 | 120 | 117 |

| QUALITY CONTROL: PAHs in Soil | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | [NT] | [NT] |
| Date extracted | - | | | [NT] | 21 | 15/05/2018 | 15/05/2018 | | [NT] | [NT] |
| Date analysed | - | | | [NT] | 21 | 16/05/2018 | 16/05/2018 | | [NT] | [NT] |
| Naphthalene | mg/kg | 0.1 | Org-012 | [NT] | 21 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Acenaphthylene | mg/kg | 0.1 | Org-012 | [NT] | 21 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Acenaphthene | mg/kg | 0.1 | Org-012 | [NT] | 21 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Fluorene | mg/kg | 0.1 | Org-012 | [NT] | 21 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Phenanthrene | mg/kg | 0.1 | Org-012 | [NT] | 21 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Anthracene | mg/kg | 0.1 | Org-012 | [NT] | 21 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Fluoranthene | mg/kg | 0.1 | Org-012 | [NT] | 21 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Pyrene | mg/kg | 0.1 | Org-012 | [NT] | 21 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Benzo(a)anthracene | mg/kg | 0.1 | Org-012 | [NT] | 21 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Chrysene | mg/kg | 0.1 | Org-012 | [NT] | 21 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Benzo(b,j+k)fluoranthene | mg/kg | 0.2 | Org-012 | [NT] | 21 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| Benzo(a)pyrene | mg/kg | 0.05 | Org-012 | [NT] | 21 | <0.05 | <0.05 | 0 | [NT] | [NT] |
| Indeno(1,2,3-c,d)pyrene | mg/kg | 0.1 | Org-012 | [NT] | 21 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Dibenzo(a,h)anthracene | mg/kg | 0.1 | Org-012 | [NT] | 21 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Benzo(g,h,i)perylene | mg/kg | 0.1 | Org-012 | [NT] | 21 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| *Surrogate p*-Terphenyl-d14 | % | | Org-012 | [NT] | 21 | 95 | 97 | 2 | [NT] | [NT] |

| QUALITY CONTROL: Organochlorine Pesticides in soil | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-3 | 191466-5 |
| Date extracted | - | | | 15/05/2018 | 1 | 15/05/2018 | 15/05/2018 | | 15/05/2018 | 15/05/2018 |
| Date analysed | - | | | 16/05/2018 | 1 | 16/05/2018 | 16/05/2018 | | 16/05/2018 | 16/05/2018 |
| HCB | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| alpha-BHC | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | 101 | 104 |
| gamma-BHC | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| beta-BHC | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | 90 | 92 |
| Heptachlor | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | 95 | 95 |
| delta-BHC | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Aldrin | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | 98 | 100 |
| Heptachlor Epoxide | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | 92 | 94 |
| gamma-Chlordane | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| alpha-chlordane | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Endosulfan I | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| pp-DDE | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | 101 | 103 |
| Dieldrin | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | 105 | 107 |
| Endrin | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | 92 | 93 |
| pp-DDD | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | 100 | 102 |
| Endosulfan II | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| pp-DDT | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Endrin Aldehyde | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Endosulfan Sulphate | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | 83 | 90 |
| Methoxychlor | mg/kg | 0.1 | Org-005 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| *Surrogate* TCMX | % | | Org-005 | 102 | 1 | 103 | 106 | 3 | 123 | 123 |

| QUALITY CONTROL: Organochlorine Pesticides in soil | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | [NT] | [NT] |
| Date extracted | - | | | [NT] | 11 | 15/05/2018 | 15/05/2018 | | [NT] | [NT] |
| Date analysed | - | | | [NT] | 11 | 16/05/2018 | 16/05/2018 | | [NT] | [NT] |
| HCB | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| alpha-BHC | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| gamma-BHC | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| beta-BHC | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Heptachlor | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| delta-BHC | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Aldrin | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Heptachlor Epoxide | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| gamma-Chlordane | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| alpha-chlordane | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Endosulfan I | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| pp-DDE | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Dieldrin | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Endrin | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| pp-DDD | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Endosulfan II | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| pp-DDT | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Endrin Aldehyde | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Endosulfan Sulphate | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Methoxychlor | mg/kg | 0.1 | Org-005 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| *Surrogate* TCMX | % | | Org-005 | [NT] | 11 | 101 | 103 | 2 | [NT] | [NT] |

| QUALITY CONTROL: Organophosphorus Pesticides | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-3 | 191466-5 |
| Date extracted | - | | | 15/05/2018 | 1 | 15/05/2018 | 15/05/2018 | | 15/05/2018 | 15/05/2018 |
| Date analysed | - | | | 16/05/2018 | 1 | 16/05/2018 | 16/05/2018 | | 16/05/2018 | 16/05/2018 |
| Azinphos-methyl (Guthion) | mg/kg | 0.1 | Org-008 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Bromophos-ethyl | mg/kg | 0.1 | Org-008 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Chlorpyriphos | mg/kg | 0.1 | Org-008 | <0.1 | 1 | <0.1 | <0.1 | 0 | 99 | 100 |
| Chlorpyriphos-methyl | mg/kg | 0.1 | Org-008 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Diazinon | mg/kg | 0.1 | Org-008 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Dichlorvos | mg/kg | 0.1 | Org-008 | <0.1 | 1 | <0.1 | <0.1 | 0 | 101 | 103 |
| Dimethoate | mg/kg | 0.1 | Org-008 | <0.1 | 1 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Ethion | mg/kg | 0.1 | Org-008 | <0.1 | 1 | <0.1 | <0.1 | 0 | 95 | 95 |
| Fenitrothion | mg/kg | 0.1 | Org-008 | <0.1 | 1 | <0.1 | <0.1 | 0 | 99 | 97 |
| Malathion | mg/kg | 0.1 | Org-008 | <0.1 | 1 | <0.1 | <0.1 | 0 | 103 | 104 |
| Parathion | mg/kg | 0.1 | Org-008 | <0.1 | 1 | <0.1 | <0.1 | 0 | 118 | 116 |
| Ronnel | mg/kg | 0.1 | Org-008 | <0.1 | 1 | <0.1 | <0.1 | 0 | 104 | 105 |
| *Surrogate* TCMX | % | | Org-008 | 102 | 1 | 103 | 106 | 3 | 102 | 100 |

| QUALITY CONTROL: Organophosphorus Pesticides | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | [NT] | [NT] |
| Date extracted | - | | | [NT] | 11 | 15/05/2018 | 15/05/2018 | | [NT] | [NT] |
| Date analysed | - | | | [NT] | 11 | 16/05/2018 | 16/05/2018 | | [NT] | [NT] |
| Azinphos-methyl (Guthion) | mg/kg | 0.1 | Org-008 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Bromophos-ethyl | mg/kg | 0.1 | Org-008 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Chlorpyriphos | mg/kg | 0.1 | Org-008 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Chlorpyriphos-methyl | mg/kg | 0.1 | Org-008 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Diazinon | mg/kg | 0.1 | Org-008 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Dichlorvos | mg/kg | 0.1 | Org-008 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Dimethoate | mg/kg | 0.1 | Org-008 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Ethion | mg/kg | 0.1 | Org-008 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Fenitrothion | mg/kg | 0.1 | Org-008 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Malathion | mg/kg | 0.1 | Org-008 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Parathion | mg/kg | 0.1 | Org-008 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Ronnel | mg/kg | 0.1 | Org-008 | [NT] | 11 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| *Surrogate* TCMX | % | | Org-008 | [NT] | 11 | 101 | 103 | 2 | [NT] | [NT] |

| QUALITY CONTROL: Acid Extractable metals in soil | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-3 | 191466-5 |
| Date prepared | - | | | 15/05/2018 | 1 | 15/05/2018 | 15/05/2018 | | 15/05/2018 | 15/05/2018 |
| Date analysed | - | | | 15/05/2018 | 1 | 15/05/2018 | 15/05/2018 | | 15/05/2018 | 15/05/2018 |
| Arsenic | mg/kg | 4 | Metals-020 | <4 | 1 | <4 | <4 | 0 | 116 | 98 |
| Cadmium | mg/kg | 0.4 | Metals-020 | <0.4 | 1 | <0.4 | <0.4 | 0 | 106 | 103 |
| Copper | mg/kg | 1 | Metals-020 | <1 | 1 | 4 | 4 | 0 | 111 | 103 |
| Mercury | mg/kg | 0.1 | Metals-021 | <0.1 | 1 | <0.1 | <0.1 | 0 | 106 | 122 |
| Molybdenum | mg/kg | 1 | Metals-020 | <1 | 1 | <1 | <1 | 0 | 107 | 107 |
| Nickel | mg/kg | 1 | Metals-020 | <1 | 1 | 2 | 2 | 0 | 104 | 100 |
| Lead | mg/kg | 1 | Metals-020 | <1 | 1 | 5 | 5 | 0 | 104 | 100 |
| Selenium | mg/kg | 2 | Metals-020 | <2 | 1 | <2 | <2 | 0 | 107 | 98 |
| Silver | mg/kg | 1 | Metals-020 | <1 | 1 | <1 | <1 | 0 | 105 | 98 |
| Tin | mg/kg | 1 | Metals-020 | <1 | 1 | <1 | <1 | 0 | 103 | 104 |
| Chromium | mg/kg | 1 | Metals-020 | <1 | 1 | 5 | 5 | 0 | 111 | 101 |

| QUALITY CONTROL: Acid Extractable metals in soil | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-4 | 191466-22 |
| Date prepared | - | | | [NT] | 11 | 15/05/2018 | 15/05/2018 | | 15/05/2018 | 15/05/2018 |
| Date analysed | - | | | [NT] | 11 | 15/05/2018 | 15/05/2018 | | 15/05/2018 | 15/05/2018 |
| Arsenic | mg/kg | 4 | Metals-020 | [NT] | 11 | <4 | <4 | 0 | 110 | 96 |
| Cadmium | mg/kg | 0.4 | Metals-020 | [NT] | 11 | <0.4 | <0.4 | 0 | 102 | 98 |
| Copper | mg/kg | 1 | Metals-020 | [NT] | 11 | 4 | 4 | 0 | 106 | 101 |
| Mercury | mg/kg | 0.1 | Metals-021 | [NT] | 11 | <0.1 | <0.1 | 0 | 116 | 114 |
| Molybdenum | mg/kg | 1 | Metals-020 | [NT] | 11 | <1 | <1 | 0 | 103 | 105 |
| Nickel | mg/kg | 1 | Metals-020 | [NT] | 11 | 3 | 2 | 40 | 100 | 96 |
| Lead | mg/kg | 1 | Metals-020 | [NT] | 11 | 10 | 12 | 18 | 99 | 96 |
| Selenium | mg/kg | 2 | Metals-020 | [NT] | 11 | <2 | <2 | 0 | 102 | 93 |
| Silver | mg/kg | 1 | Metals-020 | [NT] | 11 | <1 | <1 | 0 | 101 | 99 |
| Tin | mg/kg | 1 | Metals-020 | [NT] | 11 | <1 | <1 | 0 | 98 | 101 |
| Chromium | mg/kg | 1 | Metals-020 | [NT] | 11 | 9 | 9 | 0 | 106 | 99 |

| QUALITY CONTROL: Acid Extractable metals in soil | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | [NT] | [NT] |
| Date prepared | - | | | [NT] | 21 | 15/05/2018 | 15/05/2018 | | [NT] | [NT] |
| Date analysed | - | | | [NT] | 21 | 15/05/2018 | 15/05/2018 | | [NT] | [NT] |
| Arsenic | mg/kg | 4 | Metals-020 | [NT] | 21 | 4 | 6 | 40 | [NT] | [NT] |
| Cadmium | mg/kg | 0.4 | Metals-020 | [NT] | 21 | <0.4 | <0.4 | 0 | [NT] | [NT] |
| Copper | mg/kg | 1 | Metals-020 | [NT] | 21 | 6 | 6 | 0 | [NT] | [NT] |
| Mercury | mg/kg | 0.1 | Metals-021 | [NT] | 21 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| Molybdenum | mg/kg | 1 | Metals-020 | [NT] | 21 | <1 | <1 | 0 | [NT] | [NT] |
| Nickel | mg/kg | 1 | Metals-020 | [NT] | 21 | 1 | 1 | 0 | [NT] | [NT] |
| Lead | mg/kg | 1 | Metals-020 | [NT] | 21 | 14 | 16 | 13 | [NT] | [NT] |
| Selenium | mg/kg | 2 | Metals-020 | [NT] | 21 | <2 | <2 | 0 | [NT] | [NT] |
| Silver | mg/kg | 1 | Metals-020 | [NT] | 21 | <1 | <1 | 0 | [NT] | [NT] |
| Tin | mg/kg | 1 | Metals-020 | [NT] | 21 | <1 | <1 | 0 | [NT] | [NT] |
| Chromium | mg/kg | 1 | Metals-020 | [NT] | 21 | 10 | 10 | 0 | [NT] | [NT] |

| QUALITY CONTROL: Misc Inorg - Soil | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-1 | 191466-5 |
| Date prepared | - | | | 16/05/2018 | 1 | 16/05/2018 | 16/05/2018 | | 16/05/2018 | 16/05/2018 |
| Date analysed | - | | | 16/05/2018 | 1 | 16/05/2018 | 16/05/2018 | | 16/05/2018 | 16/05/2018 |
| Free Cyanide in soil | mg/kg | 0.5 | Inorg-014 | <0.5 | 1 | <0.5 | <0.5 | 0 | 105 | 96 |
| Total Cyanide | mg/kg | 0.5 | Inorg-014 | <0.5 | 1 | <0.5 | <0.5 | 0 | 92 | 95 |
| Hexavalent Chromium, $Cr^{6+}$ | mg/kg | 1 | Inorg-024 | <1 | 1 | <1 | <1 | 0 | 102 | 104 |
| Total Fluoride | mg/kg | 50 | Inorg-026/53 | <50 | 1 | <50 | <50 | 0 | 82 | 77 |

| QUALITY CONTROL: SVOCs in Soil | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | [NT] | [NT] |
| Date extracted | - | | | 18/05/2018 | 13 | 18/05/2018 | 18/05/2018 | | [NT] | [NT] |
| Date analysed | - | | | 18/05/2018 | 13 | 18/05/2018 | 18/05/2018 | | [NT] | [NT] |
| Nitrobenzene | mg/kg | 0.1 | Org-012 | <0.1 | 13 | <0.1 | <0.1 | 0 | [NT] | [NT] |
| 2,4-Dintrotoluene | mg/kg | 1 | Org-012 | <1 | 13 | <1 | <1 | 0 | [NT] | [NT] |

| QUALITY CONTROL: Speciated Phenols in Soil | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-1 | [NT] |
| Date extracted | - | | | 18/05/2018 | 13 | 18/05/2018 | 18/05/2018 | | 18/05/2018 | [NT] |
| Date analysed | - | | | 19/05/2018 | 13 | 19/05/2018 | 19/05/2018 | | 19/05/2018 | [NT] |
| Phenol | mg/kg | 0.2 | Org-012 | <0.2 | 13 | <0.2 | <0.2 | 0 | 106 | [NT] |
| 2-Chlorophenol | mg/kg | 0.2 | Org-012 | <0.2 | 13 | <0.2 | <0.2 | 0 | 101 | [NT] |
| 4-Chloro-3-methylphenol | mg/kg | 5 | Org-012 | <5 | 13 | <5 | <5 | 0 | [NT] | [NT] |
| 2-Methylphenol (o-cresol) | mg/kg | 0.2 | Org-012 | <0.2 | 13 | <0.2 | <0.2 | 0 | 98 | [NT] |
| 3/4-Methylphenol (m/p-cresol) | mg/kg | 0.4 | Org-012 | <0.4 | 13 | <0.4 | <0.4 | 0 | [NT] | [NT] |
| 2-Nitrophenol | mg/kg | 0.2 | Org-012 | <0.2 | 13 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| 2,4 -Dimethylphenol | mg/kg | 0.2 | Org-012 | <0.2 | 13 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| 2,4-Dichlorophenol | mg/kg | 0.2 | Org-012 | <0.2 | 13 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| 2,6-Dichlorophenol | mg/kg | 0.2 | Org-012 | <0.2 | 13 | <0.2 | <0.2 | 0 | 102 | [NT] |
| 2,4,5-Trichlorophenol | mg/kg | 0.2 | Org-012 | <0.2 | 13 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| 2,4,6-Trichlorophenol | mg/kg | 0.2 | Org-012 | <0.2 | 13 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| 2,4-Dinitrophenol | mg/kg | 4 | Org-012 | <4 | 13 | <4 | <4 | 0 | [NT] | [NT] |
| 4-Nitrophenol | mg/kg | 4 | Org-012 | <4 | 13 | <4 | <4 | 0 | [NT] | [NT] |
| 2346-Tetrachlorophenol | mg/kg | 0.2 | Org-012 | <0.2 | 13 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| 2-methyl-4,6-Dinitrophenol | mg/kg | 10 | Org-012 | <10 | 13 | <10 | <10 | 0 | [NT] | [NT] |
| Pentachlorophenol | mg/kg | 5 | Org-012 | <5 | 13 | <5 | <5 | 0 | [NT] | [NT] |
| *Surrogate* Phenol-$d_6$ | % | | Org-012 | 99 | 13 | 95 | 96 | 1 | 93 | [NT] |

| QUALITY CONTROL: Phenoxy Acid Herbicides in Soil | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-1 | [NT] |
| Date extracted | - | | | 22/05/2018 | 6 | 22/05/2018 | 22/05/2018 | | 22/05/2018 | [NT] |
| Date analysed | - | | | 22/05/2018 | 6 | 22/05/2018 | 22/05/2018 | | 22/05/2018 | [NT] |
| Clopyralid | mg/kg | 0.5 | Ext-054 | <0.5 | 6 | <0.5 | <0.5 | 0 | [NT] | [NT] |
| 3,5-Dichlorobenzoic acid | mg/kg | 0.5 | Ext-054 | <0.5 | 6 | <0.5 | <0.5 | 0 | [NT] | [NT] |
| o-chlorophenoxy acetic acid | mg/kg | 0.5 | Ext-054 | <0.5 | 6 | <0.5 | <0.5 | 0 | [NT] | [NT] |
| 4-CPA | mg/kg | 0.5 | Ext-054 | <0.5 | 6 | <0.5 | <0.5 | 0 | [NT] | [NT] |
| Dicamba | mg/kg | 0.5 | Ext-054 | <0.5 | 6 | <0.5 | <0.5 | 0 | 97 | [NT] |
| MCPP | mg/kg | 0.5 | Ext-054 | <0.5 | 6 | <0.5 | <0.5 | 0 | 99 | [NT] |
| MCPA | mg/kg | 0.5 | Ext-054 | <0.5 | 6 | <0.5 | <0.5 | 0 | 99 | [NT] |
| Dichlorprop | mg/kg | 0.5 | Ext-054 | <0.5 | 6 | <0.5 | <0.5 | 0 | [NT] | [NT] |
| 2,4-D | mg/kg | 0.5 | Ext-054 | <0.5 | 6 | <0.5 | <0.5 | 0 | 94 | [NT] |
| Bromoxynil | mg/kg | 0.5 | Ext-054 | <0.5 | 6 | <0.5 | <0.5 | 0 | [NT] | [NT] |
| Triclopyr | mg/kg | 0.5 | Ext-054 | <0.5 | 6 | <0.5 | <0.5 | 0 | [NT] | [NT] |
| 2,4,5-TP | mg/kg | 0.5 | Ext-054 | <0.5 | 6 | <0.5 | <0.5 | 0 | [NT] | [NT] |
| 2,4,5-T | mg/kg | 0.5 | Ext-054 | <0.5 | 6 | <0.5 | <0.5 | 0 | 90 | [NT] |
| MCPB | mg/kg | 0.5 | Ext-054 | <0.5 | 6 | <0.5 | <0.5 | 0 | [NT] | [NT] |
| Dinoseb | mg/kg | 1 | Ext-054 | <1 | 6 | <1 | <1 | 0 | [NT] | [NT] |
| 2,4-DB | mg/kg | 0.5 | Ext-054 | <0.5 | 6 | <0.5 | <0.5 | 0 | [NT] | [NT] |
| Ioxynil | mg/kg | 1 | Ext-054 | <1 | 6 | <1 | <1 | 0 | [NT] | [NT] |
| Picloram | mg/kg | 0.5 | Ext-054 | <0.5 | 6 | <0.5 | <0.5 | 0 | [NT] | [NT] |
| DCPA (Chlorthal) Diacid | mg/kg | 0.5 | Ext-054 | <0.5 | 6 | <0.5 | <0.5 | 0 | [NT] | [NT] |
| Acifluorfen | mg/kg | 2 | Ext-054 | <2 | 6 | <2 | <2 | 0 | [NT] | [NT] |
| 2,4,6-T | mg/kg | 0.5 | Ext-054 | <0.5 | 6 | <0.5 | <0.5 | 0 | [NT] | [NT] |
| 2,6-D | mg/kg | 0.5 | Ext-054 | <0.5 | 6 | <0.5 | <0.5 | 0 | [NT] | [NT] |
| Surrogate 2.4- DCPA | % | | Ext-054 | [NT] | 6 | 95 | 86 | 10 | 98 | [NT] |

| QUALITY CONTROL: Phthalates in Soil | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-1 | [NT] |
| Date extracted | - | | | 18/05/2018 | 13 | 18/05/2018 | 18/05/2018 | | 18/05/2018 | [NT] |
| Date analysed | - | | | 18/05/2018 | 13 | 18/05/2018 | 18/05/2018 | | 18/05/2018 | [NT] |
| Dimethylphthalate | mg/kg | 1 | Org-012 | <1 | 13 | <1 | <1 | 0 | 92 | [NT] |
| diethylphthalate | mg/kg | 1 | Org-012 | <1 | 13 | <1 | <1 | 0 | [NT] | [NT] |
| di-n-butylphthalate | mg/kg | 5 | Org-012 | <5 | 13 | <5 | <5 | 0 | 94 | [NT] |
| butylbenzylphthalate | mg/kg | 1 | Org-012 | <1 | 13 | <1 | <1 | 0 | [NT] | [NT] |
| bis(2-ethylhexyl)phthalate | mg/kg | 5 | Org-012 | <5 | 13 | <5 | <5 | 0 | [NT] | [NT] |
| di-n-octylphthalate | mg/kg | 1 | Org-012 | <1 | 13 | <1 | <1 | 0 | [NT] | [NT] |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | | Org-012 | 93 | 13 | 92 | 95 | 3 | 99 | [NT] |

| QUALITY CONTROL: vTRH in Water (C6-C9) NEPM | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W1 | [NT] |
| Date extracted | - | | | 15/05/2018 | [NT] | [NT] | [NT] | [NT] | 15/05/2018 | [NT] |
| Date analysed | - | | | 16/05/2018 | [NT] | [NT] | [NT] | [NT] | 16/05/2018 | [NT] |
| TRH $C_6$ - $C_9$ | µg/L | 10 | Org-016 | <10 | [NT] | [NT] | [NT] | [NT] | 108 | [NT] |
| TRH $C_6$ - $C_{10}$ | µg/L | 10 | Org-016 | <10 | [NT] | [NT] | [NT] | [NT] | 108 | [NT] |
| *Surrogate* Dibromofluoromethane | % | | Org-016 | 105 | [NT] | [NT] | [NT] | [NT] | 104 | [NT] |
| *Surrogate* toluene-d8 | % | | Org-016 | 97 | [NT] | [NT] | [NT] | [NT] | 99 | [NT] |
| *Surrogate* 4-BFB | % | | Org-016 | 95 | [NT] | [NT] | [NT] | [NT] | 101 | [NT] |

| QUALITY CONTROL: svTRH (C10-C40) in Water | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W1 | [NT] |
| Date extracted | - | | | 15/05/2018 | [NT] | [NT] | [NT] | [NT] | 15/05/2018 | [NT] |
| Date analysed | - | | | 15/05/2018 | [NT] | [NT] | [NT] | [NT] | 15/05/2018 | [NT] |
| TRH $C_{10}$ - $C_{14}$ | µg/L | 50 | Org-003 | <50 | [NT] | [NT] | [NT] | [NT] | 106 | [NT] |
| TRH $C_{15}$ - $C_{28}$ | µg/L | 100 | Org-003 | <100 | [NT] | [NT] | [NT] | [NT] | 105 | [NT] |
| TRH $C_{29}$ - $C_{36}$ | µg/L | 100 | Org-003 | <100 | [NT] | [NT] | [NT] | [NT] | 110 | [NT] |
| TRH >$C_{10}$ - $C_{16}$ | µg/L | 50 | Org-003 | <50 | [NT] | [NT] | [NT] | [NT] | 106 | [NT] |
| TRH >$C_{16}$ - $C_{34}$ | µg/L | 100 | Org-003 | <100 | [NT] | [NT] | [NT] | [NT] | 105 | [NT] |
| TRH >$C_{34}$ - $C_{40}$ | µg/L | 100 | Org-003 | <100 | [NT] | [NT] | [NT] | [NT] | 110 | [NT] |
| *Surrogate* o-Terphenyl | % | | Org-003 | 84 | [NT] | [NT] | [NT] | [NT] | 97 | [NT] |

## Result Definitions

| | |
|---|---|
| **NT** | Not tested |
| **NA** | Test not required |
| **INS** | Insufficient sample for this test |
| **PQL** | Practical Quantitation Limit |
| **<** | Less than |
| **>** | Greater than |
| **RPD** | Relative Percent Difference |
| **LCS** | Laboratory Control Sample |
| **NS** | Not specified |
| **NEPM** | National Environmental Protection Measure |
| **NR** | Not Reported |

## Quality Control Definitions

| | |
|---|---|
| **Blank** | This is the component of the analytical signal which is not derived from the sample but from reagents, glassware etc, can be determined by processing solvents and reagents in exactly the same manner as for samples. |
| **Duplicate** | This is the complete duplicate analysis of a sample from the process batch. If possible, the sample selected should be one where the analyte concentration is easily measurable. |
| **Matrix Spike** | A portion of the sample is spiked with a known concentration of target analyte. The purpose of the matrix spike is to monitor the performance of the analytical method used and to determine whether matrix interferences exist. |
| **LCS (Laboratory Control Sample)** | This comprises either a standard reference material or a control matrix (such as a blank sand or water) fortified with analytes representative of the analyte class. It is simply a check sample. |
| **Surrogate Spike** | Surrogates are known additions to each sample, blank, matrix spike and LCS in a batch, of compounds which are similar to the analyte of interest, however are not expected to be found in real samples. |

Australian Drinking Water Guidelines recommend that Thermotolerant Coliform, Faecal Enterococci, & E.Coli levels are less than 1cfu/100mL. The recommended maximums are taken from "Australian Drinking Water Guidelines", published by NHMRC & ARMC 2011.

## Laboratory Acceptance Criteria

Duplicate sample and matrix spike recoveries may not be reported on smaller jobs, however, were analysed at a frequency to meet or exceed NEPM requirements. All samples are tested in batches of 20. The duplicate sample RPD and matrix spike recoveries for the batch were within the laboratory acceptance criteria.

Filters, swabs, wipes, tubes and badges will not have duplicate data as the whole sample is generally extracted during sample extraction.

Spikes for Physical and Aggregate Tests are not applicable.

For VOCs in water samples, three vials are required for duplicate or spike analysis.

Duplicates: <5xPQL - any RPD is acceptable; >5xPQL - 0-50% RPD is acceptable.

Matrix Spikes, LCS and Surrogate recoveries: Generally 70-130% for inorganics/metals; 60-140% for organics (+/-50% surrogates) and 10-140% for labile SVOCs (including labile surrogates), ultra trace organics and speciated phenols is acceptable.

In circumstances where no duplicate and/or sample spike has been reported at 1 in 10 and/or 1 in 20 samples respectively, the sample volume submitted was insufficient in order to satisfy laboratory QA/QC protocols.

When samples are received where certain analytes are outside of recommended technical holding times (THTs), the analysis has proceeded. Where analytes are on the verge of breaching THTs, every effort will be made to analyse within the THT or as soon as practicable.

Where sampling dates are not provided, Envirolab are not in a position to comment on the validity of the analysis where recommended technical holding times may have been breached.

Measurement Uncertainty estimates are available for most tests upon request.

## Report Comments

vTRH in Water (C6-C9) NEPM - Subsampled from plastic bottle.

Nitrobenzene, 2,4-Dinitrotoluene, Speciated Phenols, Phthalates & Herbicides in soil analysed by MPL Laboratories. Report No.210781.

COC received at 18:50.

P.O. Box 1237
Carlton VIC 3053
enquiries@lrmglobal.com.au

# CHAIN OF CUSTODY

**Job Number:** 27380

**ATTENTION**

**CLIENT**

**CLIENT NUMBER**

**LOCATION** 266 Longueville Road Lane Cove

Sheet 1 of 1

ENVIROLAB
*Envirolab Services*
*12 Ashley St*
*Chatswood NSW 2067*
*Ph: (02) 9910 6200*

**Total number of containers** 20

Job No: 191604

**Additional information::**

| Email Results To | Tick |
|---|---|
| jon.lawson@lrmglobal.com.au | Yep |
| kevin.b@lrmglobal.com.au | |
| ajacob@lrmglobal.com.au | |
| acampbell@lrmglobal.com.au | |
| l.main@lrmglobal.com.au | |

Sampled by: JL

Checked by: JL

Date Received: 14/5/18
Time Received: 14:00
Received By: JB
Temp: Cool/Ambient
Cooling: Ice/Icepack
Security: Intact/Broken/None

**Comments**

Chain of custody must be signed and dated by LRM, courier, and laboratory.

| RELINQUISHED BY (Signature) | ORGANISATION | DATE / TIME | RECEIVED BY (Signature) | ORGANISATION | DATE / TIME |
|---|---|---|---|---|---|
| | LRM | 14/05/2018 | | | |

| | Sample Number | Sample Date | Sample Type | Analysis Required | No. of Containers | Turn-around Time Required |
|---|---|---|---|---|---|---|
| 1 | GW01 | 14/05/2018 | Water | NEPM HIL Screen, TDS, Cations / Anions, pH | 5 | Standard |
| 2 | GW02 | 14/05/2018 | Water | NEPM HIL Screen, TDS, Cations / Anions, pH | 5 | Standard |
| 3 | Dup 1 | 14/05/2018 | Water | NEPM HIL Screen, TDS, Cations / Anions, pH | 5 | Standard |
| 4 | Split 1 | 14/05/2018 | Water | NEPM HIL Screen, TDS, Cations / Anions, pH | 5 | Standard |

5. TB (Tox(ic) kein)

**Envirolab Services Pty Ltd**
ABN 37 112 535 645
12 Ashley St Chatswood NSW 2067
ph 02 9910 6200 fax 02 9910 6201
customerservice@envirolab.com.au
www.envirolab.com.au

# CERTIFICATE OF ANALYSIS 191604

## Client Details

| | |
|---|---|
| **Client** | LRM Global |
| **Attention** | Jon Lawson |
| **Address** | PO Box 1237, Carlton, VIC, 3053 |

## Sample Details

| | |
|---|---|
| **Your Reference** | **27380** |
| **Number of Samples** | 4 Water, 1 Soil |
| **Date samples received** | 14/05/2018 |
| **Date completed instructions received** | 14/05/2018 |

## Analysis Details

Please refer to the following pages for results, methodology summary and quality control data.

Samples were analysed as received from the client. Results relate specifically to the samples as received.

Results are reported on a dry weight basis for solids and on an as received basis for other matrices.

**Please refer to the last page of this report for any comments relating to the results.**

## Report Details

| | |
|---|---|
| **Date results requested by** | 21/05/2018 |
| **Date of Issue** | 21/05/2018 |

NATA Accreditation Number 2901. This document shall not be reproduced except in full.

Accredited for compliance with ISO/IEC 17025 - Testing. **Tests not covered by NATA are denoted with ***

**Results Approved By**
Alexander Mitchell Maclean, Senior Chemist
Jeremy Faircloth, Organics Supervisor
Nancy Zhang, Assistant Lab Manager
Nick Sarlamis, Inorganics Supervisor
Priya Samarawickrama, Senior Chemist
Steven Luong, Senior Chemist

**Authorised By**



Jacinta Hurst, Laboratory Manager

| VOCs in water | | | | | |
|---|---|---|---|---|---|
| Our Reference | | 191604-1 | 191604-2 | 191604-3 | 191604-4 |
| Your Reference | UNITS | GW01 | GW02 | Dup 1 | Split 1 |
| Date Sampled | | 14/05/2018 | 14/05/2018 | 14/05/2018 | 14/05/2018 |
| Type of sample | | Water | Water | Water | Water |
| Date extracted | - | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 |
| Date analysed | - | 21/05/2018 | 21/05/2018 | 21/05/2018 | 21/05/2018 |
| Dichlorodifluoromethane | µg/L | <10 | <10 | <10 | <10 |
| Chloromethane | µg/L | <10 | <10 | <10 | <10 |
| Vinyl Chloride | µg/L | <10 | <10 | <10 | <10 |
| Bromomethane | µg/L | <10 | <10 | <10 | <10 |
| Chloroethane | µg/L | <10 | <10 | <10 | <10 |
| Trichlorofluoromethane | µg/L | <10 | <10 | <10 | <10 |
| 1,1-Dichloroethene | µg/L | <1 | <1 | <1 | <1 |
| Trans-1,2-dichloroethene | µg/L | <1 | <1 | <1 | <1 |
| 1,1-dichloroethane | µg/L | <1 | <1 | <1 | <1 |
| Cis-1,2-dichloroethene | µg/L | <1 | <1 | <1 | <1 |
| Bromochloromethane | µg/L | <1 | <1 | <1 | <1 |
| Chloroform | µg/L | <1 | <1 | <1 | <1 |
| 2,2-dichloropropane | µg/L | <1 | <1 | <1 | <1 |
| 1,2-dichloroethane | µg/L | <1 | <1 | <1 | <1 |
| 1,1,1-trichloroethane | µg/L | <1 | <1 | <1 | <1 |
| 1,1-dichloropropene | µg/L | <1 | <1 | <1 | <1 |
| Cyclohexane | µg/L | <1 | <1 | <1 | <1 |
| Carbon tetrachloride | µg/L | <1 | <1 | <1 | <1 |
| Benzene | µg/L | <1 | <1 | <1 | <1 |
| Dibromomethane | µg/L | <1 | <1 | <1 | <1 |
| 1,2-dichloropropane | µg/L | <1 | <1 | <1 | <1 |
| Trichloroethene | µg/L | <1 | <1 | <1 | <1 |
| Bromodichloromethane | µg/L | <1 | <1 | <1 | <1 |
| trans-1,3-dichloropropene | µg/L | <1 | <1 | <1 | <1 |
| cis-1,3-dichloropropene | µg/L | <1 | <1 | <1 | <1 |
| 1,1,2-trichloroethane | µg/L | <1 | <1 | <1 | <1 |
| Toluene | µg/L | <1 | <1 | <1 | <1 |
| 1,3-dichloropropane | µg/L | <1 | <1 | <1 | <1 |
| Dibromochloromethane | µg/L | <1 | <1 | <1 | <1 |
| 1,2-dibromoethane | µg/L | <1 | <1 | <1 | <1 |
| Tetrachloroethene | µg/L | <1 | <1 | <1 | <1 |
| 1,1,1,2-tetrachloroethane | µg/L | <1 | <1 | <1 | <1 |
| Chlorobenzene | µg/L | <1 | <1 | <1 | <1 |
| Ethylbenzene | µg/L | <1 | <1 | <1 | <1 |
| Bromoform | µg/L | <1 | <1 | <1 | <1 |

| VOCs in water | | | | | |
|---|---|---|---|---|---|
| Our Reference | | 191604-1 | 191604-2 | 191604-3 | 191604-4 |
| Your Reference | UNITS | GW01 | GW02 | Dup 1 | Split 1 |
| Date Sampled | | 14/05/2018 | 14/05/2018 | 14/05/2018 | 14/05/2018 |
| Type of sample | | Water | Water | Water | Water |
| m+p-xylene | µg/L | <2 | <2 | <2 | <2 |
| Styrene | µg/L | <1 | <1 | <1 | <1 |
| 1,1,2,2-tetrachloroethane | µg/L | <1 | <1 | <1 | <1 |
| o-xylene | µg/L | <1 | <1 | <1 | <1 |
| 1,2,3-trichloropropane | µg/L | <1 | <1 | <1 | <1 |
| Isopropylbenzene | µg/L | <1 | <1 | <1 | <1 |
| Bromobenzene | µg/L | <1 | <1 | <1 | <1 |
| n-propyl benzene | µg/L | <1 | <1 | <1 | <1 |
| 2-chlorotoluene | µg/L | <1 | <1 | <1 | <1 |
| 4-chlorotoluene | µg/L | <1 | <1 | <1 | <1 |
| 1,3,5-trimethyl benzene | µg/L | <1 | <1 | <1 | <1 |
| Tert-butyl benzene | µg/L | <1 | <1 | <1 | <1 |
| 1,2,4-trimethyl benzene | µg/L | <1 | <1 | <1 | <1 |
| 1,3-dichlorobenzene | µg/L | <1 | <1 | <1 | <1 |
| Sec-butyl benzene | µg/L | <1 | <1 | <1 | <1 |
| 1,4-dichlorobenzene | µg/L | <1 | <1 | <1 | <1 |
| 4-isopropyl toluene | µg/L | <1 | <1 | <1 | <1 |
| 1,2-dichlorobenzene | µg/L | <1 | <1 | <1 | <1 |
| n-butyl benzene | µg/L | <1 | <1 | <1 | <1 |
| 1,2-dibromo-3-chloropropane | µg/L | <1 | <1 | <1 | <1 |
| 1,2,4-trichlorobenzene | µg/L | <1 | <1 | <1 | <1 |
| Hexachlorobutadiene | µg/L | <1 | <1 | <1 | <1 |
| 1,2,3-trichlorobenzene | µg/L | <1 | <1 | <1 | <1 |
| *Surrogate* Dibromofluoromethane | % | 97 | 95 | 96 | 98 |
| *Surrogate* toluene-d8 | % | 100 | 99 | 100 | 99 |
| *Surrogate* 4-BFB | % | 96 | 95 | 94 | 96 |

| vTRH(C6-C10)/BTEXN in Water | | | | | |
|---|---|---|---|---|---|
| Our Reference | UNITS | 191604-1 | 191604-2 | 191604-3 | 191604-4 |
| Your Reference | | GW01 | GW02 | Dup 1 | Split 1 |
| Date Sampled | | 14/05/2018 | 14/05/2018 | 14/05/2018 | 14/05/2018 |
| Type of sample | | Water | Water | Water | Water |
| Date extracted | - | 18/05/2018 | 18/05/2018 | 18/05/2018 | 18/05/2018 |
| Date analysed | - | 21/05/2018 | 21/05/2018 | 21/05/2018 | 21/05/2018 |
| TRH $C_6$ - $C_9$ | µg/L | <10 | <10 | <10 | <10 |
| TRH $C_6$ - $C_{10}$ | µg/L | <10 | <10 | <10 | <10 |
| TRH $C_6$ - $C_{10}$ less BTEX (F1) | µg/L | <10 | <10 | <10 | <10 |
| Benzene | µg/L | <1 | <1 | <1 | <1 |
| Toluene | µg/L | <1 | <1 | <1 | <1 |
| Ethylbenzene | µg/L | <1 | <1 | <1 | <1 |
| m+p-xylene | µg/L | <2 | <2 | <2 | <2 |
| o-xylene | µg/L | <1 | <1 | <1 | <1 |
| Naphthalene | µg/L | <1 | <1 | <1 | <1 |
| *Surrogate* Dibromofluoromethane | % | 97 | 95 | 96 | 98 |
| *Surrogate* toluene-d8 | % | 100 | 99 | 100 | 99 |
| *Surrogate* 4-BFB | % | 96 | 95 | 94 | 96 |

| svTRH (C10-C40) in Water | | | | | |
|---|---|---|---|---|---|
| Our Reference | | 191604-1 | 191604-2 | 191604-3 | 191604-4 |
| Your Reference | UNITS | GW01 | GW02 | Dup 1 | Split 1 |
| Date Sampled | | 14/05/2018 | 14/05/2018 | 14/05/2018 | 14/05/2018 |
| Type of sample | | Water | Water | Water | Water |
| Date extracted | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Date analysed | - | 16/05/2018 | 17/05/2018 | 17/05/2018 | 17/05/2018 |
| TRH $C_{10}$ - $C_{14}$ | µg/L | <50 | <50 | <50 | <50 |
| TRH $C_{15}$ - $C_{28}$ | µg/L | <100 | <100 | <100 | <100 |
| TRH $C_{29}$ - $C_{36}$ | µg/L | <100 | <100 | <100 | <100 |
| TRH >$C_{10}$ - $C_{16}$ | µg/L | <50 | <50 | <50 | <50 |
| TRH >$C_{10}$ - $C_{16}$ less Naphthalene (F2) | µg/L | <50 | <50 | <50 | <50 |
| TRH >$C_{16}$ - $C_{34}$ | µg/L | <100 | <100 | <100 | <100 |
| TRH >$C_{34}$ - $C_{40}$ | µg/L | <100 | <100 | <100 | <100 |
| *Surrogate* o-Terphenyl | % | 91 | 106 | 78 | 105 |

| PAHs in Water | | | | | |
|---|---|---|---|---|---|
| Our Reference | | 191604-1 | 191604-2 | 191604-3 | 191604-4 |
| Your Reference | UNITS | GW01 | GW02 | Dup 1 | Split 1 |
| Date Sampled | | 14/05/2018 | 14/05/2018 | 14/05/2018 | 14/05/2018 |
| Type of sample | | Water | Water | Water | Water |
| Date extracted | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Date analysed | - | 17/05/2018 | 17/05/2018 | 17/05/2018 | 17/05/2018 |
| Naphthalene | µg/L | <1 | <1 | <1 | <1 |
| Acenaphthylene | µg/L | <1 | <1 | <1 | <1 |
| Acenaphthene | µg/L | <1 | <1 | <1 | <1 |
| Fluorene | µg/L | <1 | <1 | <1 | <1 |
| Phenanthrene | µg/L | <1 | <1 | <1 | <1 |
| Anthracene | µg/L | <1 | <1 | <1 | <1 |
| Fluoranthene | µg/L | <1 | <1 | <1 | <1 |
| Pyrene | µg/L | <1 | <1 | <1 | <1 |
| Benzo(a)anthracene | µg/L | <1 | <1 | <1 | <1 |
| Chrysene | µg/L | <1 | <1 | <1 | <1 |
| Benzo(b,j+k)fluoranthene | µg/L | <2 | <2 | <2 | <2 |
| Benzo(a)pyrene | µg/L | <1 | <1 | <1 | <1 |
| Indeno(1,2,3-c,d)pyrene | µg/L | <1 | <1 | <1 | <1 |
| Dibenzo(a,h)anthracene | µg/L | <1 | <1 | <1 | <1 |
| Benzo(g,h,i)perylene | µg/L | <1 | <1 | <1 | <1 |
| Benzo(a)pyrene TEQ | µg/L | <5 | <5 | <5 | <5 |
| Total +ve PAH's | µg/L | NIL (+)VE | NIL (+)VE | NIL (+)VE | NIL (+)VE |
| *Surrogate p*-Terphenyl-d14 | % | 106 | 120 | 89 | 118 |

| Total Phenolics in Water | | | | | |
|---|---|---|---|---|---|
| Our Reference | | 191604-1 | 191604-2 | 191604-3 | 191604-4 |
| Your Reference | UNITS | GW01 | GW02 | Dup 1 | Split 1 |
| Date Sampled | | 14/05/2018 | 14/05/2018 | 14/05/2018 | 14/05/2018 |
| Type of sample | | Water | Water | Water | Water |
| Date extracted | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Total Phenolics (as Phenol) | mg/L | <0.05 | <0.05 | <0.05 | <0.05 |

| OCP in water | | | | | |
|---|---|---|---|---|---|
| Our Reference | UNITS | 191604-1 | 191604-2 | 191604-3 | 191604-4 |
| Your Reference | | GW01 | GW02 | Dup 1 | Split 1 |
| Date Sampled | | 14/05/2018 | 14/05/2018 | 14/05/2018 | 14/05/2018 |
| Type of sample | | Water | Water | Water | Water |
| Date extracted | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Date analysed | - | 17/05/2018 | 17/05/2018 | 17/05/2018 | 17/05/2018 |
| HCB | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| alpha-BHC | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| gamma-BHC | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| beta-BHC | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Heptachlor | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| delta-BHC | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Aldrin | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Heptachlor Epoxide | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| gamma-Chlordane | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| alpha-Chlordane | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Endosulfan I | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| pp-DDE | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Dieldrin | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Endrin | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| pp-DDD | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Endosulfan II | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| pp-DDT | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Endrin Aldehyde | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Endosulfan Sulphate | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Methoxychlor | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| *Surrogate* TCMX | % | 113 | 127 | 87 | 125 |

| PCBs in Water | | | | | |
|---|---|---|---|---|---|
| Our Reference | | 191604-1 | 191604-2 | 191604-3 | 191604-4 |
| Your Reference | UNITS | GW01 | GW02 | Dup 1 | Split 1 |
| Date Sampled | | 14/05/2018 | 14/05/2018 | 14/05/2018 | 14/05/2018 |
| Type of sample | | Water | Water | Water | Water |
| Date extracted | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Date analysed | - | 17/05/2018 | 17/05/2018 | 17/05/2018 | 17/05/2018 |
| Aroclor 1016 | µg/L | <2 | <2 | <2 | <2 |
| Aroclor 1221 | µg/L | <2 | <2 | <2 | <2 |
| Aroclor 1232 | µg/L | <2 | <2 | <2 | <2 |
| Aroclor 1242 | µg/L | <2 | <2 | <2 | <2 |
| Aroclor 1248 | µg/L | <2 | <2 | <2 | <2 |
| Aroclor 1254 | µg/L | <2 | <2 | <2 | <2 |
| Aroclor 1260 | µg/L | <2 | <2 | <2 | <2 |
| *Surrogate* TCLMX | % | 113 | 127 | 87 | 125 |

| Phthalates in water | | | | | |
|---|---|---|---|---|---|
| Our Reference | | 191604-1 | 191604-2 | 191604-3 | 191604-4 |
| Your Reference | UNITS | GW01 | GW02 | Dup 1 | Split 1 |
| Date Sampled | | 14/05/2018 | 14/05/2018 | 14/05/2018 | 14/05/2018 |
| Type of sample | | Water | Water | Water | Water |
| Date extracted | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Date analysed | - | 17/05/2018 | 17/05/2018 | 17/05/2018 | 17/05/2018 |
| Bis(2-ethylhexyl) phthalate | µg/L | <50 | <50 | <50 | <50 |
| Butylbenzylphthalate | µg/L | <10 | <10 | <10 | <10 |
| Diethylphthalate | µg/L | <10 | <10 | <10 | <10 |
| Dimethyl phthalate | µg/L | <10 | <10 | <10 | <10 |
| Di-n-butylphthalate | µg/L | <50 | <50 | <50 | <50 |
| Di-n-octylphthalate | µg/L | <10 | <10 | <10 | <10 |
| *Surrogate* Nitrobenzene-$d_5$ | % | 64 | 84 | 71 | 78 |
| *Surrogate* 2-fluorobiphenyl | % | 59 | 75 | 61 | 70 |
| *Surrogate* 2,4,6-Tribromophenol | % | 40 | 54 | 44 | 52 |
| *Surrogate* *p*-Terphenyl-$d_{14}$ | % | 112 | 129 | 99 | 130 |

| HM in water - dissolved | | | | | |
|---|---|---|---|---|---|
| Our Reference | UNITS | 191604-1 | 191604-2 | 191604-3 | 191604-4 |
| Your Reference | | GW01 | GW02 | Dup 1 | Split 1 |
| Date Sampled | | 14/05/2018 | 14/05/2018 | 14/05/2018 | 14/05/2018 |
| Type of sample | | Water | Water | Water | Water |
| Date prepared | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Date analysed | - | 16/05/2018 | 16/05/2018 | 16/05/2018 | 16/05/2018 |
| Aluminium-Dissolved | µg/L | 190 | 120 | 200 | 180 |
| Silver-Dissolved | µg/L | <1 | <1 | <1 | <1 |
| Arsenic-Dissolved | µg/L | <1 | <1 | <1 | <1 |
| Boron-Dissolved | µg/L | 90 | 100 | 90 | 90 |
| Barium-Dissolved | µg/L | 36 | 56 | 33 | 32 |
| Beryllium-Dissolved | µg/L | 0.5 | <0.5 | <0.5 | <0.5 |
| Cadmium-Dissolved | µg/L | <0.1 | 0.3 | <0.1 | <0.1 |
| Chromium-Dissolved | µg/L | <1 | <1 | <1 | <1 |
| Cobalt-Dissolved | µg/L | 11 | 18 | 11 | 11 |
| Copper-Dissolved | µg/L | 19 | 12 | 7 | 7 |
| Iron-Dissolved | µg/L | 2,300 | 6,100 | 2,300 | 2,200 |
| Lead-Dissolved | µg/L | 1 | <1 | 1 | 1 |
| Manganese-Dissolved | µg/L | 220 | 270 | 220 | 210 |
| Mercury-Dissolved | µg/L | <0.05 | <0.05 | <0.05 | <0.05 |
| Molybdenum-Dissolved | µg/L | <1 | <1 | <1 | <1 |
| Nickel-Dissolved | µg/L | 12 | 37 | 10 | 9 |
| Selenium-Dissolved | µg/L | <1 | <1 | <1 | <1 |
| Antimony-Dissolved | µg/L | <1 | <1 | <1 | <1 |
| Tin-Dissolved | µg/L | <1 | <1 | <1 | <1 |
| Thallium-Dissolved | µg/L | <1 | <1 | <1 | <1 |
| Vanadium-Dissolved | µg/L | <1 | <1 | <1 | <1 |
| Zinc-Dissolved | µg/L | 68 | 120 | 62 | 61 |

| Miscellaneous Inorganics | | | | | |
|---|---|---|---|---|---|
| Our Reference | | 191604-1 | 191604-2 | 191604-3 | 191604-4 |
| Your Reference | UNITS | GW01 | GW02 | Dup 1 | Split 1 |
| Date Sampled | | 14/05/2018 | 14/05/2018 | 14/05/2018 | 14/05/2018 |
| Type of sample | | Water | Water | Water | Water |
| Date prepared | - | 14/05/2018 | 14/05/2018 | 14/05/2018 | 14/05/2018 |
| Date analysed | - | 14/05/2018 | 14/05/2018 | 14/05/2018 | 14/05/2018 |
| pH | pH Units | 5.0 | 5.1 | 4.9 | 4.9 |
| Total Cyanide | mg/L | <0.004 | <0.004 | <0.004 | <0.004 |
| Hexavalent Chromium, $Cr^{6+}$ | mg/L | <0.005 | <0.005 | <0.005 | <0.005 |
| Fluoride, F | mg/L | <0.1 | <0.1 | <0.1 | <0.1 |
| Total Dissolved Solids (grav) | mg/L | 440 | 230 | 420 | 430 |

| Ion Balance | | | | | |
|---|---|---|---|---|---|
| Our Reference | | 191604-1 | 191604-2 | 191604-3 | 191604-4 |
| Your Reference | UNITS | GW01 | GW02 | Dup 1 | Split 1 |
| Date Sampled | | 14/05/2018 | 14/05/2018 | 14/05/2018 | 14/05/2018 |
| Type of sample | | Water | Water | Water | Water |
| Date prepared | - | 14/05/2018 | 14/05/2018 | 14/05/2018 | 14/05/2018 |
| Date analysed | - | 14/05/2018 | 14/05/2018 | 14/05/2018 | 14/05/2018 |
| Calcium - Dissolved | mg/L | 4.8 | 11 | 4.8 | 4.8 |
| Potassium - Dissolved | mg/L | 2.1 | 8.3 | 2.0 | 2.0 |
| Sodium - Dissolved | mg/L | 140 | 32 | 130 | 130 |
| Magnesium - Dissolved | mg/L | 5.2 | 5.7 | 4.9 | 4.7 |
| Hydroxide Alkalinity ($OH^-$) as $CaCO_3$ | mg/L | <5 | <5 | <5 | <5 |
| Bicarbonate Alkalinity as $CaCO_3$ | mg/L | 8 | 7 | 7 | 7 |
| Carbonate Alkalinity as $CaCO_3$ | mg/L | <5 | <5 | <5 | <5 |
| Total Alkalinity as $CaCO_3$ | mg/L | 8 | 7 | 7 | 7 |
| Sulphate, SO4 | mg/L | 110 | 59 | 110 | 100 |
| Chloride, Cl | mg/L | 93 | 39 | 89 | 88 |
| Ionic Balance | % | 13 | 4.0 | 13 | 13 |

| Method ID | Methodology Summary |
|---|---|
| **Inorg-001** | pH - Measured using pH meter and electrode in accordance with APHA latest edition, 4500-H+. Please note that the results for water analyses are indicative only, as analysis outside of the APHA storage times. |
| **Inorg-006** | Alkalinity - determined titrimetrically in accordance with APHA latest edition, 2320-B. |
| **Inorg-014** | Cyanide - free, total, weak acid dissociable by segmented flow analyser (in line dialysis with colourimetric finish). Solids are extracted in a caustic media prior to analysis. |
| **Inorg-018** | Total Dissolved Solids - determined gravimetrically. The solids are dried at 180+/-10°C. |
| **Inorg-024** | Hexavalent Chromium (Cr6+) - determined colourimetrically. |
| **Inorg-026** | Fluoride determined by ion selective electrode (ISE) in accordance with APHA latest edition, 4500-F-C. |
| **Inorg-031** | Total Phenolics by segmented flow analyser (in line distillation with colourimetric finish). Solids are extracted in a caustic media prior to analysis. |
| **Inorg-040** | The concentrations of the major ions (mg/L) are converted to milliequivalents and summed. The ionic balance should be within +/- 10% ie total anions = total cations +/-10%. |
| **Inorg-081** | Anions - a range of Anions are determined by Ion Chromatography, in accordance with APHA latest edition, 4110-B. Alternatively determined by colourimetry/turbidity using Discrete Analyer. |
| **Metals-020** | Determination of various metals by ICP-AES. |
| **Metals-021** | Determination of Mercury by Cold Vapour AAS. |
| **Metals-022** | Determination of various metals by ICP-MS. |
| **Org-003** | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-FID. F2 = (>C10-C16)-Naphthalene as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater (HSLs Tables 1A (3, 4)). Note Naphthalene is determined from the VOC analysis. |
| **Org-005** | Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC with dual ECD's. |
| **Org-006** | Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC-ECD. |
| **Org-012** | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS. |
| **Org-012** | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS. Benzo(a)pyrene TEQ as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater - 2013. |
| **Org-013** | Water samples are analysed directly by purge and trap GC-MS. |
| **Org-016** | Soil samples are extracted with methanol and spiked into water prior to analysing by purge and trap GC-MS. Water samples are analysed directly by purge and trap GC-MS. F1 = (C6-C10)-BTEX as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater. |

| QUALITY CONTROL: VOCs in water | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W1 | [NT] |
| Date extracted | - | | | 18/05/2018 | [NT] | [NT] | [NT] | [NT] | 18/05/2018 | [NT] |
| Date analysed | - | | | 21/05/2018 | [NT] | [NT] | [NT] | [NT] | 21/05/2018 | [NT] |
| Dichlorodifluoromethane | µg/L | 10 | Org-013 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Chloromethane | µg/L | 10 | Org-013 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Vinyl Chloride | µg/L | 10 | Org-013 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Bromomethane | µg/L | 10 | Org-013 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Chloroethane | µg/L | 10 | Org-013 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Trichlorofluoromethane | µg/L | 10 | Org-013 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,1-Dichloroethene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Trans-1,2-dichloroethene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,1-dichloroethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 105 | [NT] |
| Cis-1,2-dichloroethene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Bromochloromethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Chloroform | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 107 | [NT] |
| 2,2-dichloropropane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2-dichloroethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 114 | [NT] |
| 1,1,1-trichloroethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 108 | [NT] |
| 1,1-dichloropropene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Cyclohexane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Carbon tetrachloride | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Dibromomethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2-dichloropropane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Trichloroethene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 108 | [NT] |
| Bromodichloromethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 109 | [NT] |
| trans-1,3-dichloropropene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| cis-1,3-dichloropropene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,1,2-trichloroethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Toluene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,3-dichloropropane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Dibromochloromethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 107 | [NT] |
| 1,2-dibromoethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Tetrachloroethene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 98 | [NT] |
| 1,1,1,2-tetrachloroethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Chlorobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Ethylbenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Bromoform | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| m+p-xylene | µg/L | 2 | Org-013 | <2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Styrene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,1,2,2-tetrachloroethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| o-xylene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |

| QUALITY CONTROL: VOCs in water | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W1 | [NT] |
| 1,2,3-trichloropropane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Isopropylbenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Bromobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| n-propyl benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 2-chlorotoluene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 4-chlorotoluene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,3,5-trimethyl benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Tert-butyl benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2,4-trimethyl benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,3-dichlorobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Sec-butyl benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,4-dichlorobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 4-isopropyl toluene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2-dichlorobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| n-butyl benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2-dibromo-3-chloropropane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2,4-trichlorobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Hexachlorobutadiene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2,3-trichlorobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| *Surrogate* Dibromofluoromethane | % | | Org-013 | 107 | [NT] | [NT] | [NT] | [NT] | 103 | [NT] |
| *Surrogate* toluene-d8 | % | | Org-013 | 99 | [NT] | [NT] | [NT] | [NT] | 99 | [NT] |
| *Surrogate* 4-BFB | % | | Org-013 | 91 | [NT] | [NT] | [NT] | [NT] | 99 | [NT] |

| QUALITY CONTROL: vTRH(C6-C10)/BTEXN in Water | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W1 | [NT] |
| Date extracted | - | | | 18/05/2018 | [NT] | [NT] | [NT] | [NT] | 18/05/2018 | [NT] |
| Date analysed | - | | | 21/05/2018 | [NT] | [NT] | [NT] | [NT] | 21/05/2018 | [NT] |
| TRH $C_6$ - $C_9$ | µg/L | 10 | Org-016 | <10 | [NT] | [NT] | [NT] | [NT] | 116 | [NT] |
| TRH $C_6$ - $C_{10}$ | µg/L | 10 | Org-016 | <10 | [NT] | [NT] | [NT] | [NT] | 116 | [NT] |
| Benzene | µg/L | 1 | Org-016 | <1 | [NT] | [NT] | [NT] | [NT] | 115 | [NT] |
| Toluene | µg/L | 1 | Org-016 | <1 | [NT] | [NT] | [NT] | [NT] | 115 | [NT] |
| Ethylbenzene | µg/L | 1 | Org-016 | <1 | [NT] | [NT] | [NT] | [NT] | 118 | [NT] |
| m+p-xylene | µg/L | 2 | Org-016 | <2 | [NT] | [NT] | [NT] | [NT] | 117 | [NT] |
| o-xylene | µg/L | 1 | Org-016 | <1 | [NT] | [NT] | [NT] | [NT] | 117 | [NT] |
| Naphthalene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| *Surrogate* Dibromofluoromethane | % | | Org-016 | 107 | [NT] | [NT] | [NT] | [NT] | 103 | [NT] |
| *Surrogate* toluene-d8 | % | | Org-016 | 97 | [NT] | [NT] | [NT] | [NT] | 102 | [NT] |
| *Surrogate* 4-BFB | % | | Org-016 | 95 | [NT] | [NT] | [NT] | [NT] | 100 | [NT] |

| QUALITY CONTROL: svTRH (C10-C40) in Water | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W2 | [NT] |
| Date extracted | - | | | 16/05/2018 | 1 | 16/05/2018 | 16/05/2018 | | 16/05/2018 | [NT] |
| Date analysed | - | | | 17/05/2018 | 1 | 16/05/2018 | 17/05/2018 | | 17/05/2018 | [NT] |
| TRH $C_{10}$ - $C_{14}$ | µg/L | 50 | Org-003 | <50 | 1 | <50 | <50 | 0 | 104 | [NT] |
| TRH $C_{15}$ - $C_{28}$ | µg/L | 100 | Org-003 | <100 | 1 | <100 | <100 | 0 | 99 | [NT] |
| TRH $C_{29}$ - $C_{36}$ | µg/L | 100 | Org-003 | <100 | 1 | <100 | <100 | 0 | 120 | [NT] |
| TRH >$C_{10}$ - $C_{16}$ | µg/L | 50 | Org-003 | <50 | 1 | <50 | <50 | 0 | 104 | [NT] |
| TRH >$C_{16}$ - $C_{34}$ | µg/L | 100 | Org-003 | <100 | 1 | <100 | <100 | 0 | 99 | [NT] |
| TRH >$C_{34}$ - $C_{40}$ | µg/L | 100 | Org-003 | <100 | 1 | <100 | <100 | 0 | 120 | [NT] |
| *Surrogate* o-Terphenyl | % | | Org-003 | 111 | 1 | 91 | 85 | 7 | 114 | [NT] |

| QUALITY CONTROL: PAHs in Water | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W2 | [NT] |
| Date extracted | - | | | 16/05/2018 | 1 | 16/05/2018 | 16/05/2018 | | 16/05/2018 | [NT] |
| Date analysed | - | | | 17/05/2018 | 1 | 17/05/2018 | 17/05/2018 | | 17/05/2018 | [NT] |
| Naphthalene | µg/L | 1 | Org-012 | <1 | 1 | <1 | <1 | 0 | 70 | [NT] |
| Acenaphthylene | µg/L | 1 | Org-012 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| Acenaphthene | µg/L | 1 | Org-012 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| Fluorene | µg/L | 1 | Org-012 | <1 | 1 | <1 | <1 | 0 | 76 | [NT] |
| Phenanthrene | µg/L | 1 | Org-012 | <1 | 1 | <1 | <1 | 0 | 88 | [NT] |
| Anthracene | µg/L | 1 | Org-012 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| Fluoranthene | µg/L | 1 | Org-012 | <1 | 1 | <1 | <1 | 0 | 81 | [NT] |
| Pyrene | µg/L | 1 | Org-012 | <1 | 1 | <1 | <1 | 0 | 79 | [NT] |
| Benzo(a)anthracene | µg/L | 1 | Org-012 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| Chrysene | µg/L | 1 | Org-012 | <1 | 1 | <1 | <1 | 0 | 71 | [NT] |
| Benzo(b,j+k)fluoranthene | µg/L | 2 | Org-012 | <2 | 1 | <2 | <2 | 0 | [NT] | [NT] |
| Benzo(a)pyrene | µg/L | 1 | Org-012 | <1 | 1 | <1 | <1 | 0 | 76 | [NT] |
| Indeno(1,2,3-c,d)pyrene | µg/L | 1 | Org-012 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| Dibenzo(a,h)anthracene | µg/L | 1 | Org-012 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| Benzo(g,h,i)perylene | µg/L | 1 | Org-012 | <1 | 1 | <1 | <1 | 0 | [NT] | [NT] |
| *Surrogate p*-Terphenyl-d14 | % | | Org-012 | 100 | 1 | 106 | 108 | 2 | 86 | [NT] |

| QUALITY CONTROL: Total Phenolics in Water | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W2 | [NT] |
| Date extracted | - | | | 16/05/2018 | 1 | 16/05/2018 | 16/05/2018 | | 16/05/2018 | [NT] |
| Date analysed | - | | | 16/05/2018 | 1 | 16/05/2018 | 16/05/2018 | | 16/05/2018 | [NT] |
| Total Phenolics (as Phenol) | mg/L | 0.05 | Inorg-031 | <0.05 | 1 | <0.05 | <0.05 | 0 | 100 | [NT] |

| QUALITY CONTROL: OCP in water | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W1 | [NT] |
| Date extracted | - | | | 16/05/2018 | 1 | 16/05/2018 | 16/05/2018 | | 16/05/2018 | [NT] |
| Date analysed | - | | | 17/05/2018 | 1 | 17/05/2018 | 17/05/2018 | | 17/05/2018 | [NT] |
| HCB | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| alpha-BHC | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | 110 | [NT] |
| gamma-BHC | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| beta-BHC | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | 99 | [NT] |
| Heptachlor | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | 108 | [NT] |
| delta-BHC | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| Aldrin | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | 108 | [NT] |
| Heptachlor Epoxide | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | 101 | [NT] |
| gamma-Chlordane | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| alpha-Chlordane | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| Endosulfan I | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| pp-DDE | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | 112 | [NT] |
| Dieldrin | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | 116 | [NT] |
| Endrin | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | 105 | [NT] |
| pp-DDD | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | 111 | [NT] |
| Endosulfan II | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| pp-DDT | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| Endrin Aldehyde | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| Endosulfan Sulphate | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | 110 | [NT] |
| Methoxychlor | µg/L | 0.2 | Org-005 | <0.2 | 1 | <0.2 | <0.2 | 0 | [NT] | [NT] |
| *Surrogate* TCMX | % | | Org-005 | 118 | 1 | 113 | 103 | 9 | 115 | [NT] |

| QUALITY CONTROL: PCBs in Water | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W1 | [NT] |
| Date extracted | - | | | 16/05/2018 | 1 | 16/05/2018 | 16/05/2018 | | 16/05/2018 | [NT] |
| Date analysed | - | | | 17/05/2018 | 1 | 17/05/2018 | 17/05/2018 | | 17/05/2018 | [NT] |
| Aroclor 1016 | µg/L | 2 | Org-006 | <2 | 1 | <2 | <2 | 0 | [NT] | [NT] |
| Aroclor 1221 | µg/L | 2 | Org-006 | <2 | 1 | <2 | <2 | 0 | [NT] | [NT] |
| Aroclor 1232 | µg/L | 2 | Org-006 | <2 | 1 | <2 | <2 | 0 | [NT] | [NT] |
| Aroclor 1242 | µg/L | 2 | Org-006 | <2 | 1 | <2 | <2 | 0 | [NT] | [NT] |
| Aroclor 1248 | µg/L | 2 | Org-006 | <2 | 1 | <2 | <2 | 0 | [NT] | [NT] |
| Aroclor 1254 | µg/L | 2 | Org-006 | <2 | 1 | <2 | <2 | 0 | 99 | [NT] |
| Aroclor 1260 | µg/L | 2 | Org-006 | <2 | 1 | <2 | <2 | 0 | [NT] | [NT] |
| *Surrogate* TCLMX | % | | Org-006 | 118 | 1 | 113 | 103 | 9 | 119 | [NT] |

| QUALITY CONTROL: Phthalates in water | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W2 | [NT] |
| Date extracted | - | | | 16/05/2018 | 1 | 16/05/2018 | 16/05/2018 | | 16/05/2018 | [NT] |
| Date analysed | - | | | 17/05/2018 | 1 | 17/05/2018 | 17/05/2018 | | 17/05/2018 | [NT] |
| Bis(2-ethylhexyl) phthalate | µg/L | 50 | Org-012 | <50 | 1 | <50 | <50 | 0 | [NT] | [NT] |
| Butylbenzylphthalate | µg/L | 10 | Org-012 | <10 | 1 | <10 | <10 | 0 | [NT] | [NT] |
| Diethylphthalate | µg/L | 10 | Org-012 | <10 | 1 | <10 | <10 | 0 | 71 | [NT] |
| Dimethyl phthalate | µg/L | 10 | Org-012 | <10 | 1 | <10 | <10 | 0 | 76 | [NT] |
| Di-n-butylphthalate | µg/L | 50 | Org-012 | <50 | 1 | <50 | <50 | 0 | [NT] | [NT] |
| Di-n-octylphthalate | µg/L | 10 | Org-012 | <10 | 1 | <10 | <10 | 0 | [NT] | [NT] |
| *Surrogate* Nitrobenzene-$d_5$ | % | | Org-012 | 87 | 1 | 64 | 81 | 23 | 69 | [NT] |
| *Surrogate* 2-fluorobiphenyl | % | | Org-012 | 71 | 1 | 59 | 69 | 16 | 59 | [NT] |
| *Surrogate* 2,4,6-Tribromophenol | % | | Org-012 | 51 | 1 | 40 | 52 | 26 | 66 | [NT] |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | | Org-012 | 102 | 1 | 112 | 110 | 2 | 81 | [NT] |

| QUALITY CONTROL: HM in water - dissolved | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W2 | 191604-2 |
| Date prepared | - | | | 16/05/2018 | 1 | 16/05/2018 | 16/05/2018 | | 16/05/2018 | 16/05/2018 |
| Date analysed | - | | | 16/05/2018 | 1 | 16/05/2018 | 16/05/2018 | | 16/05/2018 | 16/05/2018 |
| Aluminium-Dissolved | µg/L | 10 | Metals-022 | <10 | 1 | 190 | 180 | 5 | 103 | 97 |
| Silver-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | <1 | <1 | 0 | 105 | 104 |
| Arsenic-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | <1 | <1 | 0 | 103 | 100 |
| Boron-Dissolved | µg/L | 20 | Metals-022 | <20 | 1 | 90 | 80 | 12 | 109 | 106 |
| Barium-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | 36 | 35 | 3 | 94 | 102 |
| Beryllium-Dissolved | µg/L | 0.5 | Metals-022 | <0.5 | 1 | 0.5 | 0.5 | 0 | 101 | 98 |
| Cadmium-Dissolved | µg/L | 0.1 | Metals-022 | <0.1 | 1 | <0.1 | <0.1 | 0 | 101 | 103 |
| Chromium-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | <1 | <1 | 0 | 95 | 89 |
| Cobalt-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | 11 | 11 | 0 | 105 | 100 |
| Copper-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | 19 | 18 | 5 | 100 | 96 |
| Iron-Dissolved | µg/L | 10 | Metals-022 | <10 | 1 | 2300 | 2300 | 0 | 102 | # |
| Lead-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | 1 | 1 | 0 | 100 | 99 |
| Manganese-Dissolved | µg/L | 5 | Metals-022 | <5 | 1 | 220 | 220 | 0 | 102 | 92 |
| Mercury-Dissolved | µg/L | 0.05 | Metals-021 | <0.05 | 1 | <0.05 | [NT] | | 99 | [NT] |
| Molybdenum-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | <1 | <1 | 0 | 94 | 99 |
| Nickel-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | 12 | 12 | 0 | 101 | 95 |
| Selenium-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | <1 | <1 | 0 | 98 | 102 |
| Antimony-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | <1 | <1 | 0 | 104 | 107 |
| Tin-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | <1 | <1 | 0 | 111 | 117 |
| Thallium-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | <1 | <1 | 0 | 101 | 97 |
| Vanadium-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | <1 | <1 | 0 | 97 | 91 |
| Zinc-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | 68 | 67 | 1 | 101 | 98 |

| QUALITY CONTROL: Miscellaneous Inorganics | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W2 | [NT] |
| Date prepared | - | | | 14/05/2018 | 1 | 14/05/2018 | 14/05/2018 | | 14/05/2018 | [NT] |
| Date analysed | - | | | 14/05/2018 | 1 | 14/05/2018 | 14/05/2018 | | 14/05/2018 | [NT] |
| pH | pH Units | | Inorg-001 | [NT] | 1 | 5.0 | [NT] | | 102 | [NT] |
| Total Cyanide | mg/L | 0.004 | Inorg-014 | <0.004 | 1 | <0.004 | <0.004 | 0 | 95 | [NT] |
| Hexavalent Chromium, $Cr^{6+}$ | mg/L | 0.005 | Inorg-024 | <0.005 | 1 | <0.005 | [NT] | | 91 | [NT] |
| Fluoride, F | mg/L | 0.1 | Inorg-026 | <0.1 | 1 | <0.1 | [NT] | | 98 | [NT] |
| Total Dissolved Solids (grav) | mg/L | 5 | Inorg-018 | <5 | 1 | 440 | [NT] | | 103 | [NT] |

| QUALITY CONTROL: Ion Balance | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W1 | [NT] |
| Date prepared | - | | | 14/05/2018 | [NT] | [NT] | [NT] | [NT] | 14/05/2018 | [NT] |
| Date analysed | - | | | 14/05/2018 | [NT] | [NT] | [NT] | [NT] | 14/05/2018 | [NT] |
| Calcium - Dissolved | mg/L | 0.5 | Metals-020 | <0.5 | [NT] | [NT] | [NT] | [NT] | 106 | [NT] |
| Potassium - Dissolved | mg/L | 0.5 | Metals-020 | <0.5 | [NT] | [NT] | [NT] | [NT] | 118 | [NT] |
| Sodium - Dissolved | mg/L | 0.5 | Metals-020 | <0.5 | [NT] | [NT] | [NT] | [NT] | 106 | [NT] |
| Magnesium - Dissolved | mg/L | 0.5 | Metals-020 | <0.5 | [NT] | [NT] | [NT] | [NT] | 106 | [NT] |
| Hydroxide Alkalinity ($OH^-$) as $CaCO_3$ | mg/L | 5 | Inorg-006 | <5 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Bicarbonate Alkalinity as $CaCO_3$ | mg/L | 5 | Inorg-006 | <5 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Carbonate Alkalinity as $CaCO_3$ | mg/L | 5 | Inorg-006 | <5 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Total Alkalinity as $CaCO_3$ | mg/L | 5 | Inorg-006 | <5 | [NT] | [NT] | [NT] | [NT] | 97 | [NT] |
| Sulphate, SO4 | mg/L | 1 | Inorg-081 | <1 | [NT] | [NT] | [NT] | [NT] | 88 | [NT] |
| Chloride, Cl | mg/L | 1 | Inorg-081 | <1 | [NT] | [NT] | [NT] | [NT] | 118 | [NT] |

## Result Definitions

| | |
|---|---|
| **NT** | Not tested |
| **NA** | Test not required |
| **INS** | Insufficient sample for this test |
| **PQL** | Practical Quantitation Limit |
| **<** | Less than |
| **>** | Greater than |
| **RPD** | Relative Percent Difference |
| **LCS** | Laboratory Control Sample |
| **NS** | Not specified |
| **NEPM** | National Environmental Protection Measure |
| **NR** | Not Reported |

## Quality Control Definitions

| | |
|---|---|
| **Blank** | This is the component of the analytical signal which is not derived from the sample but from reagents, glassware etc, can be determined by processing solvents and reagents in exactly the same manner as for samples. |
| **Duplicate** | This is the complete duplicate analysis of a sample from the process batch. If possible, the sample selected should be one where the analyte concentration is easily measurable. |
| **Matrix Spike** | A portion of the sample is spiked with a known concentration of target analyte. The purpose of the matrix spike is to monitor the performance of the analytical method used and to determine whether matrix interferences exist. |
| **LCS (Laboratory Control Sample)** | This comprises either a standard reference material or a control matrix (such as a blank sand or water) fortified with analytes representative of the analyte class. It is simply a check sample. |
| **Surrogate Spike** | Surrogates are known additions to each sample, blank, matrix spike and LCS in a batch, of compounds which are similar to the analyte of interest, however are not expected to be found in real samples. |

Australian Drinking Water Guidelines recommend that Thermotolerant Coliform, Faecal Enterococci, & E.Coli levels are less than 1cfu/100mL. The recommended maximums are taken from "Australian Drinking Water Guidelines", published by NHMRC & ARMC 2011.

## Laboratory Acceptance Criteria

Duplicate sample and matrix spike recoveries may not be reported on smaller jobs, however, were analysed at a frequency to meet or exceed NEPM requirements. All samples are tested in batches of 20. The duplicate sample RPD and matrix spike recoveries for the batch were within the laboratory acceptance criteria.

Filters, swabs, wipes, tubes and badges will not have duplicate data as the whole sample is generally extracted during sample extraction.

Spikes for Physical and Aggregate Tests are not applicable.

For VOCs in water samples, three vials are required for duplicate or spike analysis.

Duplicates: <5xPQL - any RPD is acceptable; >5xPQL - 0-50% RPD is acceptable.

Matrix Spikes, LCS and Surrogate recoveries: Generally 70-130% for inorganics/metals; 60-140% for organics (+/-50% surrogates) and 10-140% for labile SVOCs (including labile surrogates), ultra trace organics and speciated phenols is acceptable.

In circumstances where no duplicate and/or sample spike has been reported at 1 in 10 and/or 1 in 20 samples respectively, the sample volume submitted was insufficient in order to satisfy laboratory QA/QC protocols.

When samples are received where certain analytes are outside of recommended technical holding times (THTs), the analysis has proceeded. Where analytes are on the verge of breaching THTs, every effort will be made to analyse within the THT or as soon as practicable.

Where sampling dates are not provided, Envirolab are not in a position to comment on the validity of the analysis where recommended technical holding times may have been breached.

Measurement Uncertainty estimates are available for most tests upon request.

## Report Comments

Dissolved Metals: The preserved sample provided was not identified as either total or dissolved, therefore the unpreserved sample was filtered through 0.45 µm filter at the lab.
Note: there is a possibility some elements may be underestimated.

HM in water - dissolved - # Percent recovery is not possible to report due to the high concentration of the element/s in the sample/s. However an acceptable recovery was obtained for the LCS.

LRM GLOBAL

P.O. Box 1237
Carlton VIC 3053
enquiries@lrmglobal.com.au

# CHAIN OF CUSTODY

**Job Number:** 27380

| | |
|---|---|
| **ATTENTION** | Envirolab |
| **CLIENT** | Australian Unity Limited |
| **LOCATION** | 266 Longueville Rd, Lane Cove |

Sheet 1 of 1

| | Sample Number | Sample Date | Sample Type | Analysis Required | No. of Containers | Turn-around Time Required |
|---|---|---|---|---|---|---|
| 1 | GW01 | 3/08/2018 | Water | TRH/BTEX, VOCs, PAHs, Total Phenolics, Phthalates, OCPs, PCBs, TDS, pH, metals (Al, Ag, As, B, Ba, Be, Cd, Cr, Co, Cu, Fe, Pb, Mn, Hg, Mo, Ni, Se, Sb, Sn, Tl, V, Zn), cation/anions, ammonia, flouride, Hexavalent chromium, total cyanide, PFAS & PFOS | 9 | Standard |
| 2 | GW02 | 3/08/2018 | Water | TRH/BTEX, VOCs, PAHs, Total Phenolics, Phthalates, OCPs, PCBs, TDS, pH, metals (Al, Ag, As, B, Ba, Be, Cd, Cr, Co, Cu, Fe, Pb, Mn, Hg, Mo, Ni, Se, Sb, Sn, Tl, V, Zn), cation/anions, ammonia, flouride, Hexavalent chromium, total cyanide, PFAS & PFOS | 9 | Standard |
| 3 | GW03 | 3/08/2018 | Water | TRH/BTEX, VOCs, PAHs, Total Phenolics, Phthalates, OCPs, PCBs, TDS, pH, metals (Al, Ag, As, B, Ba, Be, Cd, Cr, Co, Cu, Fe, Pb, Mn, Hg, Mo, Ni, Se, Sb, Sn, Tl, V, Zn), cation/anions, ammonia, flouride, Hexavalent chromium, total cyanide, PFAS & PFOS | 9 | Standard |
| 4 | DUP/03/08/18 | 3/08/2018 | Water | TRH/BTEX, VOCs, PAHs, Total Phenolics, Phthalates, OCPs, PCBs, TDS, pH, metals (Al, Ag, As, B, Ba, Be, Cd, Cr, Co, Cu, Fe, Pb, Mn, Hg, Mo, Ni, Se, Sb, Sn, Tl, V, Zn), cation/anions, ammonia, flouride, Hexavalent chromium, total cyanide, PFAS & PFOS | 9 | Standard |
| | SPLIT/03/08/18 | 3/08/2018 | Water | TRH/BTEX, VOCs, PAHs, Total Phenolics, Phthalates, OCPs, PCBs, TDS, pH, metals (Al, Ag, As, B, Ba, Be, Cd, Cr, Co, Cu, Fe, Pb, Mn, Hg, Mo, Ni, Se, Sb, Sn, Tl, V, Zn), cation/anions, ammonia, flouride, Hexavalent chromium, total cyanide, PFAS & PFOS | 9 | Standard |
| 5 | RB/03/08/18 | 3/08/2018 | Water | TPH, PAHs, Metals | 4 | Standard |
| 6 | TB/03/08/18 | 3/08/2018 | Water | TPH C6-C9 | 2 | Standard |
| | | | | | | - |
| | | | | | | - |
| | | | | | | - |
| | | | | | | - |
| | | | | | | - |
| | | | | | | - |
| | | | | | | - |

ENVIROLAB

*Envirolab Services*
*12 Ashley St*
*Chatswood NSW 2067*
*Ph: (02) 9910 6200*

Job No: 197675
Date Received: 3/8/18
Time Received: 1430
Received By: MT
Temp: Cool/Ambient 6.9
Cooling: Ice/Pack
Security: Intact/Broken/None

**Total number of containers** 51

**Additional Information::**

| Email Results To | Tick |
|---|---|
| jon.lawson@lrmglobal.com.au | √ |
| acampbell@lrmglobal.com.au | √ |
| ajacob@lrmglobal.com.au | |
| dyeoh@lrmglobal.com.au | |
| bpaule@lrmglobal.com.au | |

Chain of custody must be signed and dated by LRM, courier, and laboratory.

Sampled by: NM (EP Risk)

Checked by: AJC (LRM)

**Additional Comments**

Splits to Envirolab (Melb)

| RELINQUISHED BY (Signature) | ORGANISATION | DATE / TIME | RECEIVED BY (Signature) | ORGANISATION | DATE / TIME |
|---|---|---|---|---|---|
| N-M Ubsoud | EP Risk | 3/8/18 | MT | EL | 3/8/18 1430 |
| RELINQUISHED BY (Signature) | ORGANISATION | DATE / TIME | RECEIVED BY (Signature) | RECEIVED FOR LABORATORY BY (Signature) | |
| | | | | | |

**Envirolab Services Pty Ltd**
ABN 37 112 535 645
12 Ashley St Chatswood NSW 2067
ph 02 9910 6200 fax 02 9910 6201
customerservice@envirolab.com.au
www.envirolab.com.au

# SAMPLE RECEIPT ADVICE

## Client Details

| | |
|---|---|
| **Client** | LRM Global |
| **Attention** | Adam Campbell, Jon Lawson |

## Sample Login Details

| | |
|---|---|
| **Your reference** | 27380, 266 Longueville Rd, Lane Cove |
| **Envirolab Reference** | 197675 |
| **Date Sample Received** | 03/08/2018 |
| **Date Instructions Received** | 03/08/2018 |
| **Date Results Expected to be Reported** | 10/08/2018 |

## Sample Condition

| | |
|---|---|
| **Samples received in appropriate condition for analysis** | YES |
| **No. of Samples Provided** | 6 Water |
| **Turnaround Time Requested** | Standard |
| **Temperature on Receipt (°C)** | 6.9 |
| **Cooling Method** | Ice |
| **Sampling Date Provided** | YES |

## Comments

Nil

Please direct any queries to:

| Aileen Hie | Jacinta Hurst |
|---|---|
| **Phone: 02 9910 6200** | **Phone: 02 9910 6200** |
| **Fax: 02 9910 6201** | **Fax: 02 9910 6201** |
| **Email: ahie@envirolab.com.au** | **Email: jhurst@envirolab.com.au** |

*Analysis Underway, details on the following page:*

**Envirolab Services Pty Ltd**
ABN 37 112 535 645
12 Ashley St Chatswood NSW 2067
ph 02 9910 6200 fax 02 9910 6201
customerservice@envirolab.com.au
www.envirolab.com.au

| Sample ID | VOCs in water | vTRH(C6-C10)/BTEXN in Water | svTRH (C10-C40) in Water | PAHsin Water | OCP in water | PCBs in Water | All metals in water-dissolved | Total Phenolicsin Water | Phthalates in water | Total Dissolved Solids(grav) | pH | Ammonia as N in water | Fluoride, F | Hexavalent Chromium, Cr6+ | Total Cyanide | Calcium - Dissolved | Potassium - Dissolved | Sodium - Dissolved | Magnesium - Dissolved | Hydroxide Alkalinity (OH-) as CaCO3 | Bicarbonate Alkalinity as CaCO3 | Carbonate Alkalinity as CaCO3 | Total Alkalinity as CaCO3 | Sulphate, SO4 | Chloride, Cl | Ionic Balance | PFAS in Waters Short |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **GW01** | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ |
| **GW02** | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ |
| **GW03** | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ |
| **DUP/03/08/18** | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ |
| **RB/03/08/18** | | ✓ | ✓ | ✓ | | | ✓ | | | | | | | | | | | | | | | | | | | |
| **TB/03/08/18** | | ✓ | | | | | | | | | | | | | | | | | | | | | | | | |

The '✓' indicates the testing you have requested. **THIS IS NOT A REPORT OF THE RESULTS.**

## Additional Info

Sample storage - Waters are routinely disposed of approximately 1 month and soils approximately 2 months from receipt.

Requests for longer term sample storage must be received in writing.

**Envirolab Services Pty Ltd**
ABN 37 112 535 645
12 Ashley St Chatswood NSW 2067
ph 02 9910 6200 fax 02 9910 6201
customerservice@envirolab.com.au
www.envirolab.com.au

# CERTIFICATE OF ANALYSIS 197675

## Client Details

| | |
|---|---|
| **Client** | LRM Global |
| **Attention** | Adam Campbell, Jon Lawson |
| **Address** | PO Box 1237, Carlton, VIC, 3053 |

## Sample Details

| | |
|---|---|
| **Your Reference** | **27380, 266 Longueville Rd, Lane Cove** |
| **Number of Samples** | 6 Water |
| **Date samples received** | 03/08/2018 |
| **Date completed instructions received** | 03/08/2018 |

## Analysis Details

Please refer to the following pages for results, methodology summary and quality control data.

Samples were analysed as received from the client. Results relate specifically to the samples as received.

Results are reported on a dry weight basis for solids and on an as received basis for other matrices.

**Please refer to the last page of this report for any comments relating to the results.**

## Report Details

| | |
|---|---|
| **Date results requested by** | 10/08/2018 |
| **Date of Issue** | 10/08/2018 |

NATA Accreditation Number 2901. This document shall not be reproduced except in full.

Accredited for compliance with ISO/IEC 17025 - Testing. **Tests not covered by NATA are denoted with ***

**Results Approved By**
Jeremy Faircloth, Organics Supervisor
Nick Sarlamis, Inorganics Supervisor
Phalak Inthakesone, Organics Development Manager, Sydney
Simon Mills, Group R&D Manager
Steven Luong, Senior Chemist

**Authorised By**



Jacinta Hurst, Laboratory Manager

| VOCs in water | | | | | |
|---|---|---|---|---|---|
| Our Reference | | 197675-1 | 197675-2 | 197675-3 | 197675-4 |
| Your Reference | UNITS | GW01 | GW02 | GW03 | DUP/03/08/18 |
| Date Sampled | | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 |
| Type of sample | | Water | Water | Water | Water |
| Date extracted | - | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 |
| Date analysed | - | 06/08/2018 | 06/08/2018 | 06/08/2018 | 06/08/2018 |
| Dichlorodifluoromethane | µg/L | <10 | <10 | <10 | <10 |
| Chloromethane | µg/L | <10 | <10 | <10 | <10 |
| Vinyl Chloride | µg/L | <10 | <10 | <10 | <10 |
| Bromomethane | µg/L | <10 | <10 | <10 | <10 |
| Chloroethane | µg/L | <10 | <10 | <10 | <10 |
| Trichlorofluoromethane | µg/L | <10 | <10 | <10 | <10 |
| 1,1-Dichloroethene | µg/L | <1 | <1 | <1 | <1 |
| Trans-1,2-dichloroethene | µg/L | <1 | <1 | <1 | <1 |
| 1,1-dichloroethane | µg/L | <1 | <1 | <1 | <1 |
| Cis-1,2-dichloroethene | µg/L | <1 | <1 | <1 | <1 |
| Bromochloromethane | µg/L | <1 | <1 | <1 | <1 |
| Chloroform | µg/L | <1 | <1 | <1 | <1 |
| 2,2-dichloropropane | µg/L | <1 | <1 | <1 | <1 |
| 1,2-dichloroethane | µg/L | <1 | <1 | <1 | <1 |
| 1,1,1-trichloroethane | µg/L | <1 | <1 | <1 | <1 |
| 1,1-dichloropropene | µg/L | <1 | <1 | <1 | <1 |
| Cyclohexane | µg/L | <1 | <1 | <1 | <1 |
| Carbon tetrachloride | µg/L | <1 | <1 | <1 | <1 |
| Benzene | µg/L | <1 | <1 | <1 | <1 |
| Dibromomethane | µg/L | <1 | <1 | <1 | <1 |
| 1,2-dichloropropane | µg/L | <1 | <1 | <1 | <1 |
| Trichloroethene | µg/L | <1 | <1 | <1 | <1 |
| Bromodichloromethane | µg/L | <1 | <1 | <1 | <1 |
| trans-1,3-dichloropropene | µg/L | <1 | <1 | <1 | <1 |
| cis-1,3-dichloropropene | µg/L | <1 | <1 | <1 | <1 |
| 1,1,2-trichloroethane | µg/L | <1 | <1 | <1 | <1 |
| Toluene | µg/L | <1 | <1 | <1 | <1 |
| 1,3-dichloropropane | µg/L | <1 | <1 | <1 | <1 |
| Dibromochloromethane | µg/L | <1 | <1 | <1 | <1 |
| 1,2-dibromoethane | µg/L | <1 | <1 | <1 | <1 |
| Tetrachloroethene | µg/L | <1 | <1 | <1 | <1 |
| 1,1,1,2-tetrachloroethane | µg/L | <1 | <1 | <1 | <1 |
| Chlorobenzene | µg/L | <1 | <1 | <1 | <1 |
| Ethylbenzene | µg/L | <1 | <1 | <1 | <1 |
| Bromoform | µg/L | <1 | <1 | <1 | <1 |

| VOCs in water | | | | | |
|---|---|---|---|---|---|
| Our Reference | | 197675-1 | 197675-2 | 197675-3 | 197675-4 |
| Your Reference | UNITS | GW01 | GW02 | GW03 | DUP/03/08/18 |
| Date Sampled | | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 |
| Type of sample | | Water | Water | Water | Water |
| m+p-xylene | µg/L | <2 | <2 | <2 | <2 |
| Styrene | µg/L | <1 | <1 | <1 | <1 |
| 1,1,2,2-tetrachloroethane | µg/L | <1 | <1 | <1 | <1 |
| o-xylene | µg/L | <1 | <1 | <1 | <1 |
| 1,2,3-trichloropropane | µg/L | <1 | <1 | <1 | <1 |
| Isopropylbenzene | µg/L | <1 | <1 | <1 | <1 |
| Bromobenzene | µg/L | <1 | <1 | <1 | <1 |
| n-propyl benzene | µg/L | <1 | <1 | <1 | <1 |
| 2-chlorotoluene | µg/L | <1 | <1 | <1 | <1 |
| 4-chlorotoluene | µg/L | <1 | <1 | <1 | <1 |
| 1,3,5-trimethyl benzene | µg/L | <1 | <1 | <1 | <1 |
| Tert-butyl benzene | µg/L | <1 | <1 | <1 | <1 |
| 1,2,4-trimethyl benzene | µg/L | <1 | <1 | <1 | <1 |
| 1,3-dichlorobenzene | µg/L | <1 | <1 | <1 | <1 |
| Sec-butyl benzene | µg/L | <1 | <1 | <1 | <1 |
| 1,4-dichlorobenzene | µg/L | <1 | <1 | <1 | <1 |
| 4-isopropyl toluene | µg/L | <1 | <1 | <1 | <1 |
| 1,2-dichlorobenzene | µg/L | <1 | <1 | <1 | <1 |
| n-butyl benzene | µg/L | <1 | <1 | <1 | <1 |
| 1,2-dibromo-3-chloropropane | µg/L | <1 | <1 | <1 | <1 |
| 1,2,4-trichlorobenzene | µg/L | <1 | <1 | <1 | <1 |
| Hexachlorobutadiene | µg/L | <1 | <1 | <1 | <1 |
| 1,2,3-trichlorobenzene | µg/L | <1 | <1 | <1 | <1 |
| *Surrogate* Dibromofluoromethane | % | 85 | 90 | 88 | 88 |
| *Surrogate* toluene-d8 | % | 80 | 81 | 80 | 79 |
| *Surrogate* 4-BFB | % | 94 | 94 | 95 | 95 |

| vTRH(C6-C10)/BTEXN in Water | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 197675-1 | 197675-2 | 197675-3 | 197675-4 | 197675-5 |
| Your Reference | UNITS | GW01 | GW02 | GW03 | DUP/03/08/18 | RB/03/08/18 |
| Date Sampled | | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 |
| Type of sample | | Water | Water | Water | Water | Water |
| Date extracted | - | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 |
| Date analysed | - | 06/08/2018 | 06/08/2018 | 06/08/2018 | 06/08/2018 | 06/08/2018 |
| TRH $C_6$ - $C_9$ | µg/L | <10 | <10 | <10 | <10 | <10 |
| TRH $C_6$ - $C_{10}$ | µg/L | <10 | <10 | <10 | <10 | <10 |
| TRH $C_6$ - $C_{10}$ less BTEX (F1) | µg/L | <10 | <10 | <10 | <10 | [NA] |
| Benzene | µg/L | <1 | <1 | <1 | <1 | [NA] |
| Toluene | µg/L | <1 | <1 | <1 | <1 | [NA] |
| Ethylbenzene | µg/L | <1 | <1 | <1 | <1 | [NA] |
| m+p-xylene | µg/L | <2 | <2 | <2 | <2 | [NA] |
| o-xylene | µg/L | <1 | <1 | <1 | <1 | [NA] |
| Naphthalene | µg/L | <1 | <1 | <1 | <1 | [NA] |
| *Surrogate* Dibromofluoromethane | % | 85 | 90 | 88 | 88 | 108 |
| *Surrogate* toluene-d8 | % | 80 | 81 | 80 | 79 | 96 |
| *Surrogate* 4-BFB | % | 94 | 94 | 95 | 95 | 101 |

| vTRH(C6-C10)/BTEXN in Water | | |
|---|---|---|
| Our Reference | | 197675-6 |
| Your Reference | UNITS | TB/03/08/18 |
| Date Sampled | | 03/08/2018 |
| Type of sample | | Water |
| Date extracted | - | 03/08/2018 |
| Date analysed | - | 06/08/2018 |
| TRH $C_6$ - $C_9$ | µg/L | <10 |
| TRH $C_6$ - $C_{10}$ | µg/L | <10 |
| *Surrogate* Dibromofluoromethane | % | 104 |
| *Surrogate* toluene-d8 | % | 96 |
| *Surrogate* 4-BFB | % | 100 |

| svTRH (C10-C40) in Water | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 197675-1 | 197675-2 | 197675-3 | 197675-4 | 197675-5 |
| Your Reference | UNITS | GW01 | GW02 | GW03 | DUP/03/08/18 | RB/03/08/18 |
| Date Sampled | | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 |
| Type of sample | | Water | Water | Water | Water | Water |
| Date extracted | - | 08/08/2018 | 08/08/2018 | 08/08/2018 | 08/08/2018 | 08/08/2018 |
| Date analysed | - | 09/08/2018 | 08/08/2018 | 09/08/2018 | 09/08/2018 | 09/08/2018 |
| TRH $C_{10}$ - $C_{14}$ | µg/L | <50 | <50 | <50 | <50 | <50 |
| TRH $C_{15}$ - $C_{28}$ | µg/L | <100 | <100 | <100 | <100 | <100 |
| TRH $C_{29}$ - $C_{36}$ | µg/L | <100 | <100 | <100 | <100 | <100 |
| TRH >$C_{10}$ - $C_{16}$ | µg/L | <50 | <50 | <50 | <50 | <50 |
| TRH >$C_{10}$ - $C_{16}$ less Naphthalene (F2) | µg/L | <50 | <50 | <50 | <50 | [NT] |
| TRH >$C_{16}$ - $C_{34}$ | µg/L | <100 | <100 | <100 | <100 | <100 |
| TRH >$C_{34}$ - $C_{40}$ | µg/L | <100 | <100 | <100 | <100 | <100 |
| *Surrogate* o-Terphenyl | % | 112 | 114 | 135 | 115 | 115 |

| PAHs in Water | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | UNITS | 197675-1 | 197675-2 | 197675-3 | 197675-4 | 197675-5 |
| Your Reference | | GW01 | GW02 | GW03 | DUP/03/08/18 | RB/03/08/18 |
| Date Sampled | | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 |
| Type of sample | | Water | Water | Water | Water | Water |
| Date extracted | - | 08/08/2018 | 08/08/2018 | 09/08/2018 | 09/08/2018 | 09/08/2018 |
| Date analysed | - | 09/08/2018 | 09/08/2018 | 10/08/2018 | 10/08/2018 | 10/08/2018 |
| Naphthalene | µg/L | <1 | <1 | <1 | <1 | <1 |
| Acenaphthylene | µg/L | <1 | <1 | <1 | <1 | <1 |
| Acenaphthene | µg/L | <1 | <1 | <1 | <1 | <1 |
| Fluorene | µg/L | <1 | <1 | <1 | <1 | <1 |
| Phenanthrene | µg/L | <1 | <1 | <1 | <1 | <1 |
| Anthracene | µg/L | <1 | <1 | <1 | <1 | <1 |
| Fluoranthene | µg/L | <1 | <1 | <1 | <1 | <1 |
| Pyrene | µg/L | <1 | <1 | <1 | <1 | <1 |
| Benzo(a)anthracene | µg/L | <1 | <1 | <1 | <1 | <1 |
| Chrysene | µg/L | <1 | <1 | <1 | <1 | <1 |
| Benzo(b,j+k)fluoranthene | µg/L | <2 | <2 | <2 | <2 | <2 |
| Benzo(a)pyrene | µg/L | <1 | <1 | <1 | <1 | <1 |
| Indeno(1,2,3-c,d)pyrene | µg/L | <1 | <1 | <1 | <1 | <1 |
| Dibenzo(a,h)anthracene | µg/L | <1 | <1 | <1 | <1 | <1 |
| Benzo(g,h,i)perylene | µg/L | <1 | <1 | <1 | <1 | <1 |
| Benzo(a)pyrene TEQ | µg/L | <5 | <5 | <5 | <5 | <5 |
| Total +ve PAH's | µg/L | NIL (+)VE | NIL (+)VE | NIL (+)VE | NIL (+)VE | NIL (+)VE |
| *Surrogate p*-Terphenyl-d14 | % | 129 | 130 | 124 | 123 | 122 |

| OCP in water | | | | | |
|---|---|---|---|---|---|
| Our Reference | UNITS | 197675-1 | 197675-2 | 197675-3 | 197675-4 |
| Your Reference | | GW01 | GW02 | GW03 | DUP/03/08/18 |
| Date Sampled | | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 |
| Type of sample | | Water | Water | Water | Water |
| Date extracted | - | 08/08/2018 | 08/08/2018 | 08/08/2018 | 08/08/2018 |
| Date analysed | - | 08/08/2018 | 08/08/2018 | 09/08/2018 | 09/08/2018 |
| HCB | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| alpha-BHC | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| gamma-BHC | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| beta-BHC | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Heptachlor | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| delta-BHC | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Aldrin | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Heptachlor Epoxide | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| gamma-Chlordane | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| alpha-Chlordane | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Endosulfan I | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| pp-DDE | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Dieldrin | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Endrin | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| pp-DDD | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Endosulfan II | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| pp-DDT | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Endrin Aldehyde | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Endosulfan Sulphate | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| Methoxychlor | µg/L | <0.2 | <0.2 | <0.2 | <0.2 |
| *Surrogate* TCMX | % | 110 | 108 | 108 | 102 |

| PCBs in Water | | | | | |
|---|---|---|---|---|---|
| Our Reference | | 197675-1 | 197675-2 | 197675-3 | 197675-4 |
| Your Reference | UNITS | GW01 | GW02 | GW03 | DUP/03/08/18 |
| Date Sampled | | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 |
| Type of sample | | Water | Water | Water | Water |
| Date extracted | - | 08/08/2018 | 08/08/2018 | 08/08/2018 | 08/08/2018 |
| Date analysed | - | 08/08/2018 | 08/08/2018 | 09/08/2018 | 09/08/2018 |
| Aroclor 1016 | µg/L | <2 | <2 | <2 | <2 |
| Aroclor 1221 | µg/L | <2 | <2 | <2 | <2 |
| Aroclor 1232 | µg/L | <2 | <2 | <2 | <2 |
| Aroclor 1242 | µg/L | <2 | <2 | <2 | <2 |
| Aroclor 1248 | µg/L | <2 | <2 | <2 | <2 |
| Aroclor 1254 | µg/L | <2 | <2 | <2 | <2 |
| Aroclor 1260 | µg/L | <2 | <2 | <2 | <2 |
| *Surrogate* TCLMX | % | 110 | 108 | 108 | 102 |

| All metals in water-dissolved | | | | | | |
|---|---|---|---|---|---|---|
| Our Reference | | 197675-1 | 197675-2 | 197675-3 | 197675-4 | 197675-5 |
| Your Reference | UNITS | GW01 | GW02 | GW03 | DUP/03/08/18 | RB/03/08/18 |
| Date Sampled | | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 |
| Type of sample | | Water | Water | Water | Water | Water |
| Date prepared | - | 06/08/2018 | 06/08/2018 | 06/08/2018 | 06/08/2018 | 06/08/2018 |
| Date analysed | - | 06/08/2018 | 06/08/2018 | 06/08/2018 | 06/08/2018 | 06/08/2018 |
| Aluminium-Dissolved | µg/L | 500 | 1,700 | 10 | 410 | <10 |
| Silver-Dissolved | µg/L | <1 | <1 | <1 | <1 | <1 |
| Arsenic-Dissolved | µg/L | <1 | <1 | <1 | <1 | <1 |
| Boron-Dissolved | µg/L | 60 | 40 | 100 | 60 | <20 |
| Barium-Dissolved | µg/L | 21 | 59 | 94 | 22 | <1 |
| Beryllium-Dissolved | µg/L | 0.8 | <0.5 | <0.5 | 0.7 | <0.5 |
| Cadmium-Dissolved | µg/L | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Chromium-Dissolved | µg/L | 1 | 2 | 1 | <1 | <1 |
| Cobalt-Dissolved | µg/L | 4 | 1 | 5 | 4 | <1 |
| Copper-Dissolved | µg/L | 6 | 18 | 9 | 32 | <1 |
| Iron-Dissolved | µg/L | 2,400 | 920 | 240 | 2,000 | <10 |
| Lead-Dissolved | µg/L | 2 | 5 | 1 | 4 | <1 |
| Manganese-Dissolved | µg/L | 160 | 36 | 180 | 150 | <5 |
| Mercury-Dissolved | µg/L | <0.05 | <0.05 | 0.05 | <0.05 | <0.05 |
| Molybdenum-Dissolved | µg/L | <1 | <1 | 1 | <1 | <1 |
| Nickel-Dissolved | µg/L | 52 | 63 | 35 | 54 | <1 |
| Selenium-Dissolved | µg/L | <1 | <1 | <1 | <1 | <1 |
| Antimony-Dissolved | µg/L | <1 | <1 | <1 | <1 | <1 |
| Tin-Dissolved | µg/L | <1 | <1 | <1 | <1 | <1 |
| Titanium-Dissolved | µg/L | <1 | <1 | <1 | <1 | <1 |
| Vanadium-Dissolved | µg/L | <1 | <1 | 1 | <1 | <1 |
| Zinc-Dissolved | µg/L | 220 | 230 | 56 | 200 | <1 |

| Total Phenolics in Water | | | | | |
|---|---|---|---|---|---|
| Our Reference | | 197675-1 | 197675-2 | 197675-3 | 197675-4 |
| Your Reference | UNITS | GW01 | GW02 | GW03 | DUP/03/08/18 |
| Date Sampled | | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 |
| Type of sample | | Water | Water | Water | Water |
| Date extracted | - | 06/08/2018 | 06/08/2018 | 06/08/2018 | 06/08/2018 |
| Date analysed | - | 06/08/2018 | 06/08/2018 | 06/08/2018 | 06/08/2018 |
| Total Phenolics (as Phenol) | mg/L | <0.05 | <0.05 | <0.05 | <0.05 |

| Phthalates in water | | | | | |
|---|---|---|---|---|---|
| Our Reference | UNITS | 197675-1 | 197675-2 | 197675-3 | 197675-4 |
| Your Reference | | GW01 | GW02 | GW03 | DUP/03/08/18 |
| Date Sampled | | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 |
| Type of sample | | Water | Water | Water | Water |
| Date extracted | - | 09/08/2018 | 09/08/2018 | 09/08/2018 | 09/08/2018 |
| Date analysed | - | 09/08/2018 | 09/08/2018 | 09/08/2018 | 09/08/2018 |
| Bis(2-ethylhexyl) phthalate | µg/L | <50 | <50 | <50 | <50 |
| Butylbenzylphthalate | µg/L | <10 | <10 | <10 | <10 |
| Diethylphthalate | µg/L | <10 | <10 | <10 | <10 |
| Dimethyl phthalate | µg/L | <10 | <10 | <10 | <10 |
| Di-n-butylphthalate | µg/L | <50 | <50 | <50 | <50 |
| Di-n-octylphthalate | µg/L | <10 | <10 | <10 | <10 |
| *Surrogate* Nitrobenzene-$d_5$ | % | 86 | 87 | 104 | 89 |
| *Surrogate* 2-fluorobiphenyl | % | 89 | 94 | 106 | 89 |
| *Surrogate* 2,4,6-Tribromophenol | % | 79 | 85 | 92 | 80 |
| *Surrogate* *p*-Terphenyl-$d_{14}$ | % | 79 | 90 | 120 | 83 |

| Miscellaneous Inorganics | | | | | |
|---|---|---|---|---|---|
| Our Reference | UNITS | 197675-1 | 197675-2 | 197675-3 | 197675-4 |
| Your Reference | | GW01 | GW02 | GW03 | DUP/03/08/18 |
| Date Sampled | | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 |
| Type of sample | | Water | Water | Water | Water |
| Date prepared | - | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 |
| Date analysed | - | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 |
| Total Dissolved Solids (grav) | mg/L | 440 | 180 | 470 | 430 |
| pH | pH Units | 4.4 | 4.2 | 6.8 | 4.4 |
| Ammonia as N in water | mg/L | <0.005 | 0.041 | 0.34 | <0.005 |
| Fluoride, F | mg/L | <0.1 | <0.1 | <0.1 | <0.1 |
| Hexavalent Chromium, $Cr^{6+}$ | mg/L | <0.005 | <0.005 | <0.005 | <0.005 |
| Total Cyanide | mg/L | <0.004 | <0.004 | <0.004 | <0.004 |

| Ion Balance | | | | | |
|---|---|---|---|---|---|
| Our Reference | | 197675-1 | 197675-2 | 197675-3 | 197675-4 |
| Your Reference | UNITS | GW01 | GW02 | GW03 | DUP/03/08/18 |
| Date Sampled | | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 |
| Type of sample | | Water | Water | Water | Water |
| Date prepared | - | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 |
| Date analysed | - | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 |
| Calcium - Dissolved | mg/L | 0.9 | 2.0 | 100 | 0.9 |
| Potassium - Dissolved | mg/L | 1.1 | 1 | 9.3 | 1.1 |
| Sodium - Dissolved | mg/L | 140 | 33 | 16 | 140 |
| Magnesium - Dissolved | mg/L | 4.8 | 6.3 | 9.3 | 4.5 |
| Hydroxide Alkalinity ($OH^-$) as $CaCO_3$ | mg/L | <5 | <5 | <5 | <5 |
| Bicarbonate Alkalinity as $CaCO_3$ | mg/L | <5 | <5 | 230 | <5 |
| Carbonate Alkalinity as $CaCO_3$ | mg/L | <5 | <5 | <5 | <5 |
| Total Alkalinity as $CaCO_3$ | mg/L | <5 | <5 | 230 | <5 |
| Sulphate, SO4 | mg/L | 120 | 47 | 98 | 120 |
| Chloride, Cl | mg/L | 110 | 48 | 30 | 110 |
| Ionic Balance | % | 9.0 | -6.0 | -4.0 | 8.0 |

| PFAS in Waters Short | | | | | |
|---|---|---|---|---|---|
| Our Reference | | 197675-1 | 197675-2 | 197675-3 | 197675-4 |
| Your Reference | UNITS | GW01 | GW02 | GW03 | DUP/03/08/18 |
| Date Sampled | | 03/08/2018 | 03/08/2018 | 03/08/2018 | 03/08/2018 |
| Type of sample | | Water | Water | Water | Water |
| Date prepared | - | 06/08/2018 | 06/08/2018 | 06/08/2018 | 06/08/2018 |
| Date analysed | - | 06/08/2018 | 06/08/2018 | 06/08/2018 | 06/08/2018 |
| Perfluorohexanesulfonic acid - PFHxS | µg/L | 0.02 | 0.01 | <0.01 | 0.03 |
| Perfluorooctanesulfonic acid PFOS | µg/L | <0.01 | <0.01 | <0.01 | <0.01 |
| Perfluorooctanoic acid PFOA | µg/L | <0.01 | <0.01 | <0.01 | <0.01 |
| 6:2 FTS | µg/L | <0.01 | <0.01 | <0.01 | <0.01 |
| 8:2 FTS | µg/L | <0.01 | <0.01 | <0.01 | <0.01 |
| *Surrogate* $^{13}C_8$ *PFOS* | % | 91 | 79 | 111 | 89 |
| *Surrogate* $^{13}C_2$ *PFOA* | % | 96 | 104 | 101 | 100 |
| *Extracted ISTD* $^{18}O_2$ *PFHxS* | % | 86 | 81 | 75 | 72 |
| *Extracted ISTD* $^{13}C_4$ *PFOS* | % | 82 | 89 | 77 | 82 |
| *Extracted ISTD* $^{13}C_4$ *PFOA* | % | 110 | 103 | 110 | 105 |
| *Extracted ISTD* $^{13}C_2$ *6:2FTS* | % | 87 | 94 | 87 | 86 |
| *Extracted ISTD* $^{13}C_2$ *8:2FTS* | % | 68 | 67 | 75 | 61 |
| Total Positive PFHxS & PFOS | µg/L | 0.02 | 0.01 | <0.01 | 0.03 |
| Total Positive PFOA & PFOS | µg/L | <0.01 | <0.01 | <0.01 | <0.01 |
| Total Positive PFAS | µg/L | 0.02 | 0.01 | <0.01 | 0.03 |

| Method ID | Methodology Summary |
|---|---|
| **Inorg-001** | pH - Measured using pH meter and electrode in accordance with APHA latest edition, 4500-H+. Please note that the results for water analyses are indicative only, as analysis outside of the APHA storage times. |
| **Inorg-006** | Alkalinity - determined titrimetrically in accordance with APHA latest edition, 2320-B. |
| **Inorg-014** | Cyanide - free, total, weak acid dissociable by segmented flow analyser (in line dialysis with colourimetric finish). Solids are extracted in a caustic media prior to analysis. |
| **Inorg-018** | Total Dissolved Solids - determined gravimetrically. The solids are dried at 180+/-10°C. |
| **Inorg-024** | Hexavalent Chromium (Cr6+) - determined colourimetrically. |
| **Inorg-026** | Fluoride determined by ion selective electrode (ISE) in accordance with APHA latest edition, 4500-F-C. |
| **Inorg-031** | Total Phenolics by segmented flow analyser (in line distillation with colourimetric finish). Solids are extracted in a caustic media prior to analysis. |
| **Inorg-040** | The concentrations of the major ions (mg/L) are converted to milliequivalents and summed. The ionic balance should be within +/- 10% ie total anions = total cations +/-10%. |
| **Inorg-057** | Ammonia - determined colourimetrically, based on APHA latest edition 4500-NH3 F. Soils are analysed following a KCl extraction. |
| **Inorg-081** | Anions - a range of Anions are determined by Ion Chromatography, in accordance with APHA latest edition, 4110-B. Alternatively determined by colourimetry/turbidity using Discrete Analyer. |
| **Metals-020** | Determination of various metals by ICP-AES. |
| **Metals-021** | Determination of Mercury by Cold Vapour AAS. |
| **Metals-022** | Determination of various metals by ICP-MS. |
| **Org-003** | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-FID. F2 = (>C10-C16)-Naphthalene as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater (HSLs Tables 1A (3, 4)). Note Naphthalene is determined from the VOC analysis. |
| **Org-005** | Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC with dual ECD's. |
| **Org-006** | Soil samples are extracted with dichloromethane/acetone and waters with dichloromethane and analysed by GC-ECD. |
| **Org-012** | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS. |
| **Org-012** | Soil samples are extracted with Dichloromethane/Acetone and waters with Dichloromethane and analysed by GC-MS. Benzo(a)pyrene TEQ as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater - 2013. |
| **Org-013** | Water samples are analysed directly by purge and trap GC-MS. |
| **Org-016** | Soil samples are extracted with methanol and spiked into water prior to analysing by purge and trap GC-MS. Water samples are analysed directly by purge and trap GC-MS. F1 = (C6-C10)-BTEX as per NEPM B1 Guideline on Investigation Levels for Soil and Groundwater. |

| Method ID | Methodology Summary |
|---|---|
| **Org-035** | Soil samples are extracted with basified Methanol. Waters and soil extracts are directly injected and/or concentrated/extracted using SPE. Analysis is undertaken with LC-MS/MS.<br><br>PFAS results include the sum of branched and linear isomers where applicable.<br><br>Please note that PFAS results are corrected for Extracted Internal Standards (QSM 5.1 Table B-15 terminology), which are mass labelled analytes added prior to sample preparation to assess matrix effects and verify processing of the sample. PFAS analytes without a commercially available mass labelled analogue are corrected vs a closely eluting mass labelled PFAS compound. Surrogates are also reported, in this context they are mass labelled PFAS compounds added prior to extraction but are used as monitoring compounds only (not used for result correction). Envicarb (or similar) is used discretionally to remove interfering matrix components.<br><br>Please contact the laboratory if estimates of Measurement Uncertainty are required as per WA DER. |
| **Org-035E** | Soil samples are extracted with basified Methanol. Waters and soil extracts are directly injected and/or concentrated/extracted using SPE. Analysis is undertaken with LC-MS/MS.<br><br>PFAS results include the sum of branched and linear isomers where applicable.<br><br>Please note that PFAS results are corrected for Extracted Internal Standards (QSM 5.1 Table B-15 terminology), which are mass labelled analytes added prior to sample preparation to assess matrix effects and verify processing of the sample. PFAS analytes without a commercially available mass labelled analogue are corrected vs a closely eluting mass labelled PFAS compound. Surrogates are also reported, in this context they are mass labelled PFAS compounds added prior to extraction but are used as monitoring compounds only (not used for result correction). Envicarb (or similar) is used discretionally to remove interfering matrix components.<br>Please contact the laboratory if estimates of Measurement Uncertainty are required as per WA DER. |
| **Org-035E_2** | Soil samples are extracted with basified Methanol. Waters and soil extracts are directly injected and/or concentrated/extracted using SPE. Analysis is undertaken with LC-MS/MS.<br><br>PFAS results include the sum of branched and linear isomers where applicable.<br><br>Please note that PFAS results are corrected for Extracted Internal Standards (QSM 5.1 Table B-15 terminology), which are mass labelled analytes added prior to sample preparation to assess matrix effects and verify processing of the sample. PFAS analytes without a commercially available mass labelled analogue are corrected vs a closely eluting mass labelled PFAS compound. Surrogates are also reported, in this context they are mass labelled PFAS compounds added prior to extraction but are used as monitoring compounds only (not used for result correction). Envicarb (or similar) is used discretionally to remove interfering matrix components.<br><br>Please contact the laboratory if estimates of Measurement Uncertainty are required as per WA DER. |

| QUALITY CONTROL: VOCs in water | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W2 | [NT] |
| Date extracted | - | | | 03/08/2018 | [NT] | [NT] | [NT] | [NT] | 03/08/2018 | [NT] |
| Date analysed | - | | | 06/08/2018 | [NT] | [NT] | [NT] | [NT] | 06/08/2018 | [NT] |
| Dichlorodifluoromethane | µg/L | 10 | Org-013 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Chloromethane | µg/L | 10 | Org-013 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Vinyl Chloride | µg/L | 10 | Org-013 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Bromomethane | µg/L | 10 | Org-013 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Chloroethane | µg/L | 10 | Org-013 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Trichlorofluoromethane | µg/L | 10 | Org-013 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,1-Dichloroethene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Trans-1,2-dichloroethene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,1-dichloroethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 79 | [NT] |
| Cis-1,2-dichloroethene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Bromochloromethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Chloroform | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 87 | [NT] |
| 2,2-dichloropropane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2-dichloroethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 90 | [NT] |
| 1,1,1-trichloroethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 92 | [NT] |
| 1,1-dichloropropene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Cyclohexane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Carbon tetrachloride | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Dibromomethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2-dichloropropane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Trichloroethene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 92 | [NT] |
| Bromodichloromethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 88 | [NT] |
| trans-1,3-dichloropropene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| cis-1,3-dichloropropene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,1,2-trichloroethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Toluene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,3-dichloropropane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Dibromochloromethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 91 | [NT] |
| 1,2-dibromoethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Tetrachloroethene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | 100 | [NT] |
| 1,1,1,2-tetrachloroethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Chlorobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Ethylbenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Bromoform | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| m+p-xylene | µg/L | 2 | Org-013 | <2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Styrene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,1,2,2-tetrachloroethane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| o-xylene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |

| QUALITY CONTROL: VOCs in water | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W2 | [NT] |
| 1,2,3-trichloropropane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Isopropylbenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Bromobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| n-propyl benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 2-chlorotoluene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 4-chlorotoluene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,3,5-trimethyl benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Tert-butyl benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2,4-trimethyl benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,3-dichlorobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Sec-butyl benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,4-dichlorobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 4-isopropyl toluene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2-dichlorobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| n-butyl benzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2-dibromo-3-chloropropane | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2,4-trichlorobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Hexachlorobutadiene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| 1,2,3-trichlorobenzene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| *Surrogate* Dibromofluoromethane | % | | Org-013 | 118 | [NT] | [NT] | [NT] | [NT] | 101 | [NT] |
| *Surrogate* toluene-d8 | % | | Org-013 | 89 | [NT] | [NT] | [NT] | [NT] | 97 | [NT] |
| *Surrogate* 4-BFB | % | | Org-013 | 99 | [NT] | [NT] | [NT] | [NT] | 107 | [NT] |

| QUALITY CONTROL: vTRH(C6-C10)/BTEXN in Water | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W2 | [NT] |
| Date extracted | - | | | 03/08/2018 | [NT] | [NT] | [NT] | [NT] | 03/08/2018 | [NT] |
| Date analysed | - | | | 06/08/2018 | [NT] | [NT] | [NT] | [NT] | 06/08/2018 | [NT] |
| TRH $C_6$ - $C_9$ | µg/L | 10 | Org-016 | <10 | [NT] | [NT] | [NT] | [NT] | 90 | [NT] |
| TRH $C_6$ - $C_{10}$ | µg/L | 10 | Org-016 | <10 | [NT] | [NT] | [NT] | [NT] | 90 | [NT] |
| Benzene | µg/L | 1 | Org-016 | <1 | [NT] | [NT] | [NT] | [NT] | 100 | [NT] |
| Toluene | µg/L | 1 | Org-016 | <1 | [NT] | [NT] | [NT] | [NT] | 97 | [NT] |
| Ethylbenzene | µg/L | 1 | Org-016 | <1 | [NT] | [NT] | [NT] | [NT] | 92 | [NT] |
| m+p-xylene | µg/L | 2 | Org-016 | <2 | [NT] | [NT] | [NT] | [NT] | 94 | [NT] |
| o-xylene | µg/L | 1 | Org-016 | <1 | [NT] | [NT] | [NT] | [NT] | 96 | [NT] |
| Naphthalene | µg/L | 1 | Org-013 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| *Surrogate* Dibromofluoromethane | % | | Org-016 | 118 | [NT] | [NT] | [NT] | [NT] | 102 | [NT] |
| *Surrogate* toluene-d8 | % | | Org-016 | 89 | [NT] | [NT] | [NT] | [NT] | 97 | [NT] |
| *Surrogate* 4-BFB | % | | Org-016 | 99 | [NT] | [NT] | [NT] | [NT] | 107 | [NT] |

| QUALITY CONTROL: svTRH (C10-C40) in Water | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W2 | [NT] |
| Date extracted | - | | | 09/08/2018 | [NT] | [NT] | [NT] | [NT] | 09/08/2018 | [NT] |
| Date analysed | - | | | 09/08/2018 | [NT] | [NT] | [NT] | [NT] | 09/08/2018 | [NT] |
| TRH $C_{10}$ - $C_{14}$ | µg/L | 50 | Org-003 | <50 | [NT] | [NT] | [NT] | [NT] | 130 | [NT] |
| TRH $C_{15}$ - $C_{28}$ | µg/L | 100 | Org-003 | <100 | [NT] | [NT] | [NT] | [NT] | 130 | [NT] |
| TRH $C_{29}$ - $C_{36}$ | µg/L | 100 | Org-003 | <100 | [NT] | [NT] | [NT] | [NT] | 100 | [NT] |
| TRH >$C_{10}$ - $C_{16}$ | µg/L | 50 | Org-003 | <50 | [NT] | [NT] | [NT] | [NT] | 130 | [NT] |
| TRH >$C_{16}$ - $C_{34}$ | µg/L | 100 | Org-003 | <100 | [NT] | [NT] | [NT] | [NT] | 130 | [NT] |
| TRH >$C_{34}$ - $C_{40}$ | µg/L | 100 | Org-003 | <100 | [NT] | [NT] | [NT] | [NT] | 100 | [NT] |
| *Surrogate* o-Terphenyl | % | | Org-003 | 116 | [NT] | [NT] | [NT] | [NT] | 126 | [NT] |

| QUALITY CONTROL: PAHs in Water | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W2 | [NT] |
| Date extracted | - | | | 09/08/2018 | [NT] | [NT] | [NT] | [NT] | 09/08/2018 | [NT] |
| Date analysed | - | | | 10/08/2018 | [NT] | [NT] | [NT] | [NT] | 10/08/2018 | [NT] |
| Naphthalene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | 86 | [NT] |
| Acenaphthylene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Acenaphthene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Fluorene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | 92 | [NT] |
| Phenanthrene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | 86 | [NT] |
| Anthracene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Fluoranthene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | 85 | [NT] |
| Pyrene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | 86 | [NT] |
| Benzo(a)anthracene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Chrysene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | 85 | [NT] |
| Benzo(b,j+k)fluoranthene | µg/L | 2 | Org-012 | <2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Benzo(a)pyrene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | 89 | [NT] |
| Indeno(1,2,3-c,d)pyrene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Dibenzo(a,h)anthracene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Benzo(g,h,i)perylene | µg/L | 1 | Org-012 | <1 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| *Surrogate p*-Terphenyl-d14 | % | | Org-012 | 102 | [NT] | [NT] | [NT] | [NT] | 88 | [NT] |

| QUALITY CONTROL: OCP in water | | | | | Duplicate | | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W1 | [NT] |
| Date extracted | - | | | 08/08/2018 | [NT] | [NT] | [NT] | [NT] | 08/08/2018 | [NT] |
| Date analysed | - | | | 08/08/2018 | [NT] | [NT] | [NT] | [NT] | 08/08/2018 | [NT] |
| HCB | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| alpha-BHC | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 95 | [NT] |
| gamma-BHC | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| beta-BHC | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 82 | [NT] |
| Heptachlor | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 85 | [NT] |
| delta-BHC | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Aldrin | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 83 | [NT] |
| Heptachlor Epoxide | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 86 | [NT] |
| gamma-Chlordane | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| alpha-Chlordane | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Endosulfan I | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| pp-DDE | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 94 | [NT] |
| Dieldrin | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 100 | [NT] |
| Endrin | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 98 | [NT] |
| pp-DDD | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 88 | [NT] |
| Endosulfan II | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| pp-DDT | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Endrin Aldehyde | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Endosulfan Sulphate | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | 93 | [NT] |
| Methoxychlor | µg/L | 0.2 | Org-005 | <0.2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| *Surrogate* TCMX | % | | Org-005 | 87 | [NT] | [NT] | [NT] | [NT] | 96 | [NT] |

| QUALITY CONTROL: PCBs in Water | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W1 | [NT] |
| Date extracted | - | | | 08/08/2018 | [NT] | [NT] | [NT] | [NT] | 08/08/2018 | [NT] |
| Date analysed | - | | | 08/08/2018 | [NT] | [NT] | [NT] | [NT] | 08/08/2018 | [NT] |
| Aroclor 1016 | µg/L | 2 | Org-006 | <2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Aroclor 1221 | µg/L | 2 | Org-006 | <2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Aroclor 1232 | µg/L | 2 | Org-006 | <2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Aroclor 1242 | µg/L | 2 | Org-006 | <2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Aroclor 1248 | µg/L | 2 | Org-006 | <2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Aroclor 1254 | µg/L | 2 | Org-006 | <2 | [NT] | [NT] | [NT] | [NT] | 83 | [NT] |
| Aroclor 1260 | µg/L | 2 | Org-006 | <2 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| *Surrogate* TCLMX | % | | Org-006 | 87 | [NT] | [NT] | [NT] | [NT] | 99 | [NT] |

| QUALITY CONTROL: All metals in water-dissolved | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W1 | 197675-2 |
| Date prepared | - | | | 06/08/2018 | 1 | 06/08/2018 | 06/08/2018 | | 06/08/2018 | 06/08/2018 |
| Date analysed | - | | | 06/08/2018 | 1 | 06/08/2018 | 06/08/2018 | | 06/08/2018 | 06/08/2018 |
| Aluminium-Dissolved | µg/L | 10 | Metals-022 | <10 | 1 | 500 | [NT] | | 117 | [NT] |
| Silver-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | <1 | [NT] | | 106 | [NT] |
| Arsenic-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | <1 | [NT] | | 105 | [NT] |
| Boron-Dissolved | µg/L | 20 | Metals-022 | <20 | 1 | 60 | [NT] | | 109 | [NT] |
| Barium-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | 21 | [NT] | | 109 | [NT] |
| Beryllium-Dissolved | µg/L | 0.5 | Metals-022 | <0.5 | 1 | 0.8 | [NT] | | 114 | [NT] |
| Cadmium-Dissolved | µg/L | 0.1 | Metals-022 | <0.1 | 1 | <0.1 | [NT] | | 105 | [NT] |
| Chromium-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | 1 | [NT] | | 120 | [NT] |
| Cobalt-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | 4 | [NT] | | 118 | [NT] |
| Copper-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | 6 | [NT] | | 104 | [NT] |
| Iron-Dissolved | µg/L | 10 | Metals-022 | <10 | 1 | 2400 | [NT] | | 111 | [NT] |
| Lead-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | 2 | [NT] | | 105 | [NT] |
| Manganese-Dissolved | µg/L | 5 | Metals-022 | <5 | 1 | 160 | [NT] | | 105 | [NT] |
| Mercury-Dissolved | µg/L | 0.05 | Metals-021 | <0.05 | 1 | <0.05 | <0.05 | 0 | 98 | 103 |
| Molybdenum-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | <1 | [NT] | | 106 | [NT] |
| Nickel-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | 52 | [NT] | | 105 | [NT] |
| Selenium-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | <1 | [NT] | | 103 | [NT] |
| Antimony-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | <1 | [NT] | | 112 | [NT] |
| Tin-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | <1 | [NT] | | 99 | [NT] |
| Titanium-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | <1 | [NT] | | 104 | [NT] |
| Vanadium-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | <1 | [NT] | | 114 | [NT] |
| Zinc-Dissolved | µg/L | 1 | Metals-022 | <1 | 1 | 220 | [NT] | | 101 | [NT] |

| QUALITY CONTROL: Total Phenolics in Water | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W1 | 197675-2 |
| Date extracted | - | | | 06/08/2018 | 1 | 06/08/2018 | 06/08/2018 | | 06/08/2018 | 06/08/2018 |
| Date analysed | - | | | 06/08/2018 | 1 | 06/08/2018 | 06/08/2018 | | 06/08/2018 | 06/08/2018 |
| Total Phenolics (as Phenol) | mg/L | 0.05 | Inorg-031 | <0.05 | 1 | <0.05 | <0.05 | 0 | 101 | 92 |

| QUALITY CONTROL: Phthalates in water | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W1 | [NT] |
| Date extracted | - | | | 09/08/2018 | [NT] | [NT] | [NT] | [NT] | 09/08/2018 | [NT] |
| Date analysed | - | | | 09/08/2018 | [NT] | [NT] | [NT] | [NT] | 09/08/2018 | [NT] |
| Bis(2-ethylhexyl) phthalate | µg/L | 50 | Org-012 | <50 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Butylbenzylphthalate | µg/L | 10 | Org-012 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Diethylphthalate | µg/L | 10 | Org-012 | <10 | [NT] | [NT] | [NT] | [NT] | 94 | [NT] |
| Dimethyl phthalate | µg/L | 10 | Org-012 | <10 | [NT] | [NT] | [NT] | [NT] | 91 | [NT] |
| Di-n-butylphthalate | µg/L | 50 | Org-012 | <50 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Di-n-octylphthalate | µg/L | 10 | Org-012 | <10 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| *Surrogate* Nitrobenzene-$d_5$ | % | | Org-012 | 65 | [NT] | [NT] | [NT] | [NT] | 82 | [NT] |
| *Surrogate* 2-fluorobiphenyl | % | | Org-012 | 77 | [NT] | [NT] | [NT] | [NT] | 76 | [NT] |
| *Surrogate* 2,4,6-Tribromophenol | % | | Org-012 | 61 | [NT] | [NT] | [NT] | [NT] | 76 | [NT] |
| *Surrogate p*-Terphenyl-$d_{14}$ | % | | Org-012 | 127 | [NT] | [NT] | [NT] | [NT] | 86 | [NT] |

| QUALITY CONTROL: Miscellaneous Inorganics | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W1 | 197675-2 |
| Date prepared | - | | | 03/08/2018 | 1 | 03/08/2018 | 03/08/2018 | | 03/08/2018 | 03/08/2018 |
| Date analysed | - | | | 03/08/2018 | 1 | 03/08/2018 | 03/08/2018 | | 03/08/2018 | 03/08/2018 |
| Total Dissolved Solids (grav) | mg/L | 5 | Inorg-018 | <5 | 1 | 440 | [NT] | | 91 | [NT] |
| pH | pH Units | | Inorg-001 | [NT] | 1 | 4.4 | [NT] | | 101 | [NT] |
| Ammonia as N in water | mg/L | 0.005 | Inorg-057 | <0.005 | 1 | <0.005 | [NT] | | 94 | [NT] |
| Fluoride, F | mg/L | 0.1 | Inorg-026 | <0.1 | 1 | <0.1 | [NT] | | 98 | 85 |
| Hexavalent Chromium, $Cr^{6+}$ | mg/L | 0.005 | Inorg-024 | <0.005 | 1 | <0.005 | [NT] | | 90 | [NT] |
| Total Cyanide | mg/L | 0.004 | Inorg-014 | <0.004 | 1 | <0.004 | <0.004 | 0 | 112 | 95 |

| QUALITY CONTROL: Ion Balance | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W2 | [NT] |
| Date prepared | - | | | 03/08/2018 | [NT] | [NT] | [NT] | [NT] | 03/08/2018 | [NT] |
| Date analysed | - | | | 03/08/2018 | [NT] | [NT] | [NT] | [NT] | 03/08/2018 | [NT] |
| Calcium - Dissolved | mg/L | 0.5 | Metals-020 | <0.5 | [NT] | [NT] | [NT] | [NT] | 97 | [NT] |
| Potassium - Dissolved | mg/L | 0.5 | Metals-020 | <0.5 | [NT] | [NT] | [NT] | [NT] | 116 | [NT] |
| Sodium - Dissolved | mg/L | 0.5 | Metals-020 | <0.5 | [NT] | [NT] | [NT] | [NT] | 120 | [NT] |
| Magnesium - Dissolved | mg/L | 0.5 | Metals-020 | <0.5 | [NT] | [NT] | [NT] | [NT] | 96 | [NT] |
| Hydroxide Alkalinity ($OH^-$) as $CaCO_3$ | mg/L | 5 | Inorg-006 | <5 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Bicarbonate Alkalinity as $CaCO_3$ | mg/L | 5 | Inorg-006 | <5 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Carbonate Alkalinity as $CaCO_3$ | mg/L | 5 | Inorg-006 | <5 | [NT] | [NT] | [NT] | [NT] | [NT] | [NT] |
| Total Alkalinity as $CaCO_3$ | mg/L | 5 | Inorg-006 | <5 | [NT] | [NT] | [NT] | [NT] | 102 | [NT] |
| Sulphate, SO4 | mg/L | 1 | Inorg-081 | <1 | [NT] | [NT] | [NT] | [NT] | 95 | [NT] |
| Chloride, Cl | mg/L | 1 | Inorg-081 | <1 | [NT] | [NT] | [NT] | [NT] | 95 | [NT] |

| QUALITY CONTROL: PFAS in Waters Short | | | | | | Duplicate | | | Spike Recovery % | |
|---|---|---|---|---|---|---|---|---|---|---|
| Test Description | Units | PQL | Method | Blank | # | Base | Dup. | RPD | LCS-W1 | 197675-2 |
| Date prepared | - | | | 06/08/2018 | 1 | 06/08/2018 | 06/08/2018 | | 06/08/2018 | 06/08/2018 |
| Date analysed | - | | | 06/08/2018 | 1 | 06/08/2018 | 06/08/2018 | | 06/08/2018 | 06/08/2018 |
| Perfluorohexanesulfonic acid - PFHxS | µg/L | 0.01 | Org-035E | <0.01 | 1 | 0.02 | 0.02 | 0 | 103 | 92 |
| Perfluorooctanesulfonic acid PFOS | µg/L | 0.01 | Org-035E | <0.01 | 1 | <0.01 | <0.01 | 0 | 98 | 102 |
| Perfluorooctanoic acid PFOA | µg/L | 0.01 | Org-035E | <0.01 | 1 | <0.01 | <0.01 | 0 | 89 | 81 |
| 6:2 FTS | µg/L | 0.01 | Org-035E | <0.01 | 1 | <0.01 | <0.01 | 0 | 91 | 86 |
| 8:2 FTS | µg/L | 0.01 | Org-035E | <0.01 | 1 | <0.01 | <0.01 | 0 | 107 | 102 |
| *Surrogate* $^{13}C_8$ *PFOS* | % | | Org-035E | 104 | 1 | 91 | 91 | 0 | 99 | 87 |
| *Surrogate* $^{13}C_2$ *PFOA* | % | | Org-035E_2 | 97 | 1 | 96 | 106 | 10 | 101 | 99 |
| *Extracted ISTD* $^{18}O_2$ *PFHxS* | % | | Org-035 | 90 | 1 | 86 | 80 | 7 | 96 | 84 |
| *Extracted ISTD* $^{13}C_4$ *PFOS* | % | | Org-035 | 100 | 1 | 82 | 93 | 13 | 104 | 80 |
| *Extracted ISTD* $^{13}C_4$ *PFOA* | % | | Org-035 | 115 | 1 | 110 | 103 | 7 | 113 | 104 |
| *Extracted ISTD* $^{13}C_2$ *6:2FTS* | % | | Org-035 | 104 | 1 | 87 | 85 | 2 | 106 | 91 |
| *Extracted ISTD* $^{13}C_2$ *8:2FTS* | % | | Org-035 | 97 | 1 | 68 | 68 | 0 | 87 | 72 |

## Result Definitions

| | |
|---|---|
| **NT** | Not tested |
| **NA** | Test not required |
| **INS** | Insufficient sample for this test |
| **PQL** | Practical Quantitation Limit |
| **<** | Less than |
| **>** | Greater than |
| **RPD** | Relative Percent Difference |
| **LCS** | Laboratory Control Sample |
| **NS** | Not specified |
| **NEPM** | National Environmental Protection Measure |
| **NR** | Not Reported |

## Quality Control Definitions

| | |
|---|---|
| **Blank** | This is the component of the analytical signal which is not derived from the sample but from reagents, glassware etc, can be determined by processing solvents and reagents in exactly the same manner as for samples. |
| **Duplicate** | This is the complete duplicate analysis of a sample from the process batch. If possible, the sample selected should be one where the analyte concentration is easily measurable. |
| **Matrix Spike** | A portion of the sample is spiked with a known concentration of target analyte. The purpose of the matrix spike is to monitor the performance of the analytical method used and to determine whether matrix interferences exist. |
| **LCS (Laboratory Control Sample)** | This comprises either a standard reference material or a control matrix (such as a blank sand or water) fortified with analytes representative of the analyte class. It is simply a check sample. |
| **Surrogate Spike** | Surrogates are known additions to each sample, blank, matrix spike and LCS in a batch, of compounds which are similar to the analyte of interest, however are not expected to be found in real samples. |

Australian Drinking Water Guidelines recommend that Thermotolerant Coliform, Faecal Enterococci, & E.Coli levels are less than 1cfu/100mL. The recommended maximums are taken from "Australian Drinking Water Guidelines", published by NHMRC & ARMC 2011.

## Laboratory Acceptance Criteria

Duplicate sample and matrix spike recoveries may not be reported on smaller jobs, however, were analysed at a frequency to meet or exceed NEPM requirements. All samples are tested in batches of 20. The duplicate sample RPD and matrix spike recoveries for the batch were within the laboratory acceptance criteria.

Filters, swabs, wipes, tubes and badges will not have duplicate data as the whole sample is generally extracted during sample extraction.

Spikes for Physical and Aggregate Tests are not applicable.

For VOCs in water samples, three vials are required for duplicate or spike analysis.

Duplicates: <5xPQL - any RPD is acceptable; >5xPQL - 0-50% RPD is acceptable.

Matrix Spikes, LCS and Surrogate recoveries: Generally 70-130% for inorganics/metals; 60-140% for organics (+/-50% surrogates) and 10-140% for labile SVOCs (including labile surrogates), ultra trace organics and speciated phenols is acceptable.

In circumstances where no duplicate and/or sample spike has been reported at 1 in 10 and/or 1 in 20 samples respectively, the sample volume submitted was insufficient in order to satisfy laboratory QA/QC protocols.

When samples are received where certain analytes are outside of recommended technical holding times (THTs), the analysis has proceeded. Where analytes are on the verge of breaching THTs, every effort will be made to analyse within the THT or as soon as practicable.

Where sampling dates are not provided, Envirolab are not in a position to comment on the validity of the analysis where recommended technical holding times may have been breached.

Measurement Uncertainty estimates are available for most tests upon request.

## Report Comments

TRH Water(C10-C40) NEPM - (3-5 SURROGATE)# Percent recovery is not possible to report as the high concentration of analytes in the sample/s
have caused interference.

Sample data for Metals has been confirmed for samples 1 and 4.

P.O. Box 1237
Carlton VIC 3053
enquiries@lrmglobal.com.au

# CHAIN OF CUSTODY

**Job Number:** 27380

**ATTENTION**

Sheet 1 of

**CLIENT**

**CLIENT NUMBER**

**LOCATION** 266 Longueville Road Lane Cove

**Additional information::**

**Total number of containers** 74

| Email Results To | Tick |
|---|---|
| jon.lawson@lrmglobal.com.au | Yep |
| kevin.b@lrmglobal.com.au | |
| ajacob@lrmglobal.com.au | |
| acampbell@lrmglobal.com.au | |
| l.main@lrmglobal.com.au | |

Sampled by: JL

Checked by: JL

**Comments**

Chain of custody must be signed and dated by LRM, courier, and laboratory.

| RELINQUISHED BY (Signature) | ORGANISATION | DATE / TIME | RECEIVED BY (Signature) | ORGANISATION | DATE / TIME |
|---|---|---|---|---|---|
| | LRM | 10/07/2017 | | | |

| Sample Number | Sample Date | Sample Type | Analysis Required | No. of Containers | Turn-around Time Required |
|---|---|---|---|---|---|
| BH16 - 0.1 | 6/07/2017 | Soil | Metals, PAH, TRH | 1 | 5 day |
| BH16 - 0.8 | 6/07/2017 | Soil | Metals, PAH, TRH | 1 | 5 day |
| BH17 - 0.1 | 6/07/2017 | Soil | Metals, PAH, TRH | 1 | 5 day |
| BH17 - 0.7 | 6/07/2017 | Soil | Metals, PAH, TRH | 1 | 5 day |
| BH18 - 0.1 | 6/07/2017 | Soil | Metals, OCP/OPP, pH | 1 | 5 day |
| BH18 - 0.6 | 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH19 - 0.1 | 6/07/2017 | Soil | Metals, OCP/OPP, pH | 1 | 5 day |
| BH19 - 0.5 | 6/07/2017 | Soil | NEPM Suite Basic | 1 | 5 day |
| BH20 - 0.1 | 6/07/2017 | Soil | Metals, OCP/OPP, pH | 1 | 5 day |
| BH20 - 1.0 | 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH20 - 1.9 | 6/07/2017 | Soil | Metals, PAH, PCB | 1 | 5 day |
| BH21 - 0.1 | 6/07/2017 | Soil | Metals, OCP/OPP | 1 | 5 day |
| BH21 - 1.2 | 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH21 - 3.0 | 6/07/2017 | Soil | Metals, TRH, PCB | 1 | 5 day |
| BH21 - 4.0 | 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH22 - 0.1 | 6/07/2017 | Soil | Metals, OCP, OPP, pH | 1 | 5 day |
| BH22 - 1.0 | 6/07/2017 | Soil | Metals, TRH | 1 | 5 day |
| BH23 - 0.1 | 6/07/2017 | Soil | Metals, OCP, OPP | 1 | 5 day |
| BH23 - 1.0 | 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |

P.O. Box 1237
Carlton VIC 3053
enquiries@lrmglobal.com.au

# CHAIN OF CUSTODY

**Job Number:** 27380

**ATTENTION**

**CLIENT**

**CLIENT NUMBER**

**LOCATION** 266 Longueville Road Lane Cove

Sheet 1 of

**Additional information::**

| Email Results To | Tick |
|---|---|
| jon.lawson@lrmglobal.com.au | Yep |
| kevin.b@lrmglobal.com.au | |
| ajacob@lrmglobal.com.au | |
| acampbell@lrmglobal.com.au | |
| l.main@lrmglobal.com.au | |

Chain of custody must be signed and dated by LRM, courier, and laboratory.

**Total number of containers** 74

Sampled by: JL

Checked by: JL

**Comments**

| RELINQUISHED BY (Signature) | ORGANISATION | DATE / TIME | RECEIVED BY (Signature) | ORGANISATION | DATE / TIME |
|---|---|---|---|---|---|
| | LRM | 10/07/2017 | | | |

| Sample Number | Sample Date | Sample Type | Analysis Required | No. of Containers | Turn-around Time Required |
|---|---|---|---|---|---|
| BH24 - 0.1 | 6/07/2017 | Soil | Metals, OCP, OPP, pH, TRH | 1 | 5 day |
| BH24 - 1.5 | 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH24 - 2.8 | 6/07/2017 | Soil | Metals, TRH, PCB | 1 | 5 day |
| BH25 - 0.2 | 6/07/2017 | Soil | Metals. OCP, OPP | 1 | 5 day |
| BH26 - 0.2 | 6/07/2017 | Soil | Metals, OCP, OPP | 1 | 5 day |
| BH27 - 0.1 | 6/07/2017 | Soil | Metals, OCP, OPP, pH | 1 | 5 day |
| BH27 - 1.0 | 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH28 - 0.1 | 6/07/2017 | Soil | Metals, OCP, OPP | 1 | 5 day |
| BH28 - 2.0 | 6/07/2017 | Soil | Metals | 1 | 5 day |
| BH28 - 3.0 | 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH28 - 4.0 | 6/07/2017 | Soil | Metals, PCB, TRH | 1 | 5 day |
| BH29 - 0.1 | 6/07/2017 | Soil | Metals, OCP, OPP, pH | 1 | 5 day |
| BH29 - 1.0 | 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH29 - 2.0 | 6/07/2017 | Soil | Metals | 1 | 5 day |
| BH29 - 3.0 | 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH29 - 4.0 | 6/07/2017 | Soil | Metals, PCB | 1 | 5 day |
| BH29 - 5.0 | 6/07/2017 | Soil | Metals | 1 | 5 day |
| BH29 - 6.0 | 6/07/2017 | Soil | Metals, PAH | | |
| BH29 - 7.0 | 6/07/2017 | Soil | Metals | 1 | 5 day |

P.O. Box 1237
Carlton VIC 3053
enquiries@lrmglobal.com.au

# CHAIN OF CUSTODY

**Job Number:** 27380

**ATTENTION**

Sheet 1 of

**CLIENT**

**CLIENT NUMBER**

**LOCATION** 266 Longueville Road Lane Cove

**Additional information::**

| Email Results To | Tick |
|---|---|
| jon.lawson@lrmglobal.com.au | Yep |
| kevin.b@lrmglobal.com.au | |
| ajacob@lrmglobal.com.au | |
| acampbell@lrmglobal.com.au | |
| l.main@lrmglobal.com.au | |

Chain of custody must be signed and dated by LRM, courier, and laboratory.

**Total number of containers** 74

Sampled by: JL

Checked by: JL

**Comments**

| RELINQUISHED BY (Signature) | ORGANISATION | DATE / TIME | RECEIVED BY (Signature) | ORGANISATION | DATE / TIME |
|---|---|---|---|---|---|
| | LRM | 10/07/2017 | | | |

| Sample Number | Sample Date | Sample Type | Analysis Required | No. of Containers | Turn-around Time Required |
|---|---|---|---|---|---|
| BH29 - 8.0 | 6/07/2017 | Soil | Metals, TRH | | |
| BH30 - 0.1 | 6/07/2017 | Soil | Metals, OCP, OPP | 1 | 5 day |
| BH30 - 1.0 | 6/07/2017 | Soil | NEPM Suite Basic | 1 | 5 day |
| BH30 - 2.0 | 6/07/2017 | Soil | Metals | 1 | 5 day |
| BH30 - 3.0 | 6/07/2017 | Soil | Metals, TRH | 1 | 5 day |
| BH30 - 4.0 | 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH30 - 5.0 | 6/07/2017 | Soil | Metals | 1 | 5 day |
| BH30 - 6.0 | 6/07/2017 | Soil | Metals, PCB | 1 | 5 day |
| BH30 - 7.0 | 6/07/2017 | Soil | Metals, TRH | 1 | 5 day |
| BH31 - 0.1 | 6/07/2017 | Soil | Metals, OCP, OPP | 1 | 5 day |
| BH31 - 1.0 | 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH32 - 0.1 | 6/07/2017 | Soil | Metals, OCP, OPP, pH | 1 | 5 day |
| BH32 - 1.0 | 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH32 - 2.2 | 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH32 - 3.0 | 6/07/2017 | Soil | Metals | 1 | 5 day |
| BH32 - 4.0 | 6/07/2017 | Soil | Metals, TRH | 1 | 5 day |
| BH33 - 0.2 | 6/07/2017 | Soil | Metals, OCP. OPP | 1 | 5 day |
| BH33 - 1.0 | 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH34 - 0.1 | 6/07/2017 | Soil | NEPM Suite Basic | 1 | 5 day |

P.O. Box 1237
Carlton VIC 3053
enquiries@lrmglobal.com.au

# CHAIN OF CUSTODY

**Job Number:** 27380

**ATTENTION**

Sheet 1 of

**CLIENT**

**CLIENT NUMBER**

**LOCATION** 266 Longueville Road Lane Cove

**Additional information::**

**Total number of containers** 74

| Email Results To | Tick |
|---|---|
| jon.lawson@lrmglobal.com.au | Yep |
| kevin.b@lrmglobal.com.au | |
| ajacob@lrmglobal.com.au | |
| acampbell@lrmglobal.com.au | |
| l.main@lrmglobal.com.au | |

Sampled by: JL

Checked by: JL

**Comments**

Chain of custody must be signed and dated by LRM, courier, and laboratory.

| RELINQUISHED BY (Signature) | ORGANISATION | DATE / TIME | RECEIVED BY (Signature) | ORGANISATION | DATE / TIME |
|---|---|---|---|---|---|
| | LRM | 10/07/2017 | | | |

| Sample Number | Sample Date | Sample Type | Analysis Required | No. of Containers | Turn-around Time Required |
|---|---|---|---|---|---|
| BH35 - 0.1 | 6/07/2017 | Soil | Metals, | 1 | 5 day |
| BH36 - 0.1 | 6/07/2017 | Soil | Metals | 1 | 5 day |
| BH37 - 0.1 | 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH38 - 0.1 | 6/07/2017 | Soil | Metals, PAH | 1 | 5 day |
| BH39 - 0.1 | 6/07/2017 | Soil | Metals, TRH | 1 | 5 day |
| BH40 - 0.1 | 6/07/2017 | Soil | Metals | 1 | 5 day |
| BH41 - 0.1 | 6/07/2017 | Soil | Metals | 1 | 5 day |
| BH42 - 0.1 | 6/07/2017 | Soil | Metals, OCP, OPP | 1 | 5 day |
| Dup 1 | 6/07/2017 | Soil | NEPM Suite Basic | 1 | 5 day |
| Dup 2 | 6/07/2017 | Soil | Metals | 1 | 5 day |
| Dup 3 | 6/07/2017 | Soil | Metals | 1 | 5 day |
| Dup 4 | 6/07/2017 | Soil | Metals | 1 | 5 day |
| Split 1 | 6/07/2017 | Soil | NEPM Suite Basic | 1 | 5 day |
| Split 2 | 6/07/2017 | Soil | Metals | 1 | 5 day |
| Split 3 | 6/07/2017 | Soil | Metals | 1 | 5 day |
| Split 4 | 6/07/2017 | Soil | Metals | 1 | 5 day |
| Trip | 6/07/2017 | Water | C6-9 | 2 | 5 day |
| Rinsate | 6/07/2017 | Water | Metals | 1 | 5 day |

COC received at 1845.

Environmental Division
Sydney
Work Order Reference
ES1814906

P.O. Box 1237
Carlton VIC 3053
enquiries@lrmglobal.com.au
Telephone : +61-2-8784 8555

# CHAIN OF CUSTODY

Job Number: 27380

Sheet 1 of 1

ATTENTION

CLIENT

CLIENT NUMBER

LOCATION 266 Longueville Road Lane Cove

Additional information::

Envirolab Services
12 Ashley St
Chatswood NSW 2067
Ph: (02) 9910 6200

Total number of containers: 20

Job No: 191604

Sampled by: JL

Checked by: JL

Date Received: 14/5/18
Time Received: 14:00
Received By: [illegible]
Temp: Cool/Ambient
Cooling: Ice/Icepack
Security: Intact/Broken/None

| Email Results To | Tick |
|---|---|
| jon.lawson@lrmglobal.com.au | Yep |
| kevin.b@lrmglobal.com.au | |
| ajacob@lrmglobal.com.au | |
| acampbell@lrmglobal.com.au | |
| l.main@lrmglobal.com.au | |

Comments

Chain of custody must be signed and dated by LRM, courier, and laboratory.

| RELINQUISHED BY (Signature) | ORGANISATION | DATE / TIME | RECEIVED BY (Signature) | ORGANISATION | DATE / TIME |
|---|---|---|---|---|---|
| | LRM | 14/05/2018 | | | |

| | Sample Number | Sample Date | Sample Type | Analysis Required | No. of Containers | Turn-around Time Required |
|---|---|---|---|---|---|---|
| 1 | GW01 | 14/05/2018 | Water | NEPM HIL Screen, TDS, Cations / Anions, pH | 5 | Standard |
| 2 | GW02 | 14/05/2018 | Water | NEPM HIL Screen, TDS, Cations / Anions, pH | 5 | Standard |
| 3 | Dup 1 | 14/05/2018 | Water | NEPM HIL Screen, TDS, Cations / Anions, pH | 5 | Standard |
| 4 | Split 1 | 14/05/2018 | Water | NEPM HIL Screen, ~~TDS, Cations / Anions, pH~~ | 5 | Standard |

5. TB (Tox(ic) bein)

See attached for testing

Relin: ELS JACK EMBLEN
22/5/18 1320

Rec: [signature]
22/5/18 1737 SYD

ES1814906

## Nancy Zhang

**From:** Jon Lawson <jon.lawson@lrmglobal.com.au>
**Sent:** Tuesday, 22 May 2018 9:17 AM
**To:** Nancy Zhang
**Subject:** SPlit
**Attachments:** 191604-[R00].pdf

Hi, also was there enough remaining sample from the Split to be able to send to say ALS for a metals screen? Cheers.

**Jon Lawson**
Principal Consultant
LRM Global Pty Ltd
T: (03) 9371 3400
M: 04111 477 22

www.lrmglobal.com.au

**LRM Global Pty Ltd**
65 Stubbs Street
Kensington VIC 3031
PO Box 1237
Carlton VIC 3053

Please consider the environment before printing this email

Al
Ag
As
B
Ba
Be
Cd
Cr
Co
Cu
Fe
Pb
Mn
Hg
Mo
Ni
Se
Sb
Sn
Tl

Relin: ELS JACK EMBLEN
22/5/18 13:20

ALS Environmental

# CERTIFICATE OF ANALYSIS

| | | | |
|---|---|---|---|
| **Work Order** | : **ES1814906** | Page | : 1 of 3 |
| Client | : **LRM GLOBAL** | Laboratory | : Environmental Division Sydney |
| Contact | : MR JON LAWSON | Contact | : Larissa Burns |
| Address | : P.BOX.1237<br>CARLTON VIC 3053 | Address | : 277-289 Woodpark Road Smithfield NSW Australia 2164 |
| Telephone | : ---- | Telephone | : +61-2-8784 8555 |
| Project | : ---- | Date Samples Received | : 22-May-2018 17:37 |
| Order number | : | Date Analysis Commenced | : 24-May-2018 |
| C-O-C number | : ---- | Issue Date | : 28-May-2018 15:54 |
| Sampler | : ---- | | |
| Site | : ---- | | |
| Quote number | : MEBQ/251/17 Primaary Work Only | | |
| No. of samples received | : 1 | | |
| No. of samples analysed | : 1 | | |

ilac-MRA NATA
Accreditation No. 825
Accredited for compliance with
ISO/IEC 17025 - Testing

This report supersedes any previous report(s) with this reference. Results apply to the sample(s) as submitted. This document shall not be reproduced, except in full.

This Certificate of Analysis contains the following information:

- General Comments
- Analytical Results

**Additional information pertinent to this report will be found in the following separate attachments: Quality Control Report, QA/QC Compliance Assessment to assist with Quality Review and Sample Receipt Notification.**

## *Signatories*

This document has been electronically signed by the authorized signatories below. Electronic signing is carried out in compliance with procedures specified in 21 CFR Part 11.

| *Signatories* | *Position* | *Accreditation Category* |
|---|---|---|
| Ivan Taylor | Analyst | Sydney Inorganics, Smithfield, NSW |

## General Comments

The analytical procedures used by the Environmental Division have been developed from established internationally recognized procedures such as those published by the USEPA, APHA, AS and NEPM. In house developed procedures are employed in the absence of documented standards or by client request.

Where moisture determination has been performed, results are reported on a dry weight basis.

Where a reported less than (<) result is higher than the LOR, this may be due to primary sample extract/digestate dilution and/or insufficient sample for analysis.

Where the LOR of a reported result differs from standard LOR, this may be due to high moisture content, insufficient sample (reduced weight employed) or matrix interference.

When sampling time information is not provided by the client, sampling dates are shown without a time component. In these instances, the time component has been assumed by the laboratory for processing purposes.

Where a result is required to meet compliance limits the associated uncertainty must be considered. Refer to the ALS Contact for details.

Key : CAS Number = CAS registry number from database maintained by Chemical Abstracts Services. The Chemical Abstracts Service is a division of the American Chemical Society.
LOR = Limit of reporting
^ = This result is computed from individual analyte detections at or above the level of reporting
ø = ALS is not NATA accredited for these tests.
~ = Indicates an estimated value.

## Analytical Results

| Sub-Matrix: WATER (Matrix: WATER) | | | | Client sample ID | Split 1 | ---- | ---- | ---- | ---- |
|---|---|---|---|---|---|---|---|---|---|
| | | | | Client sampling date / time | 14-May-2018 00:00 | ---- | ---- | ---- | ---- |
| Compound | CAS Number | LOR | Unit | | ES1814906-001 | -------- | -------- | -------- | -------- |
| | | | | | Result | ---- | ---- | ---- | ---- |
| **EG020T: Total Metals by ICP-MS** | | | | | | | | | |
| **Aluminium** | 7429-90-5 | 0.01 | mg/L | | **1.09** | ---- | ---- | ---- | ---- |
| **Antimony** | 7440-36-0 | 0.001 | mg/L | | <0.001 | ---- | ---- | ---- | ---- |
| **Arsenic** | 7440-38-2 | 0.001 | mg/L | | <0.001 | ---- | ---- | ---- | ---- |
| **Beryllium** | 7440-41-7 | 0.001 | mg/L | | <0.001 | ---- | ---- | ---- | ---- |
| **Barium** | 7440-39-3 | 0.001 | mg/L | | **0.041** | ---- | ---- | ---- | ---- |
| **Cadmium** | 7440-43-9 | 0.0001 | mg/L | | <0.0001 | ---- | ---- | ---- | ---- |
| **Chromium** | 7440-47-3 | 0.001 | mg/L | | **0.002** | ---- | ---- | ---- | ---- |
| **Cobalt** | 7440-48-4 | 0.001 | mg/L | | **0.011** | ---- | ---- | ---- | ---- |
| **Copper** | 7440-50-8 | 0.001 | mg/L | | **0.035** | ---- | ---- | ---- | ---- |
| **Lead** | 7439-92-1 | 0.001 | mg/L | | **0.002** | ---- | ---- | ---- | ---- |
| **Manganese** | 7439-96-5 | 0.001 | mg/L | | **0.210** | ---- | ---- | ---- | ---- |
| **Molybdenum** | 7439-98-7 | 0.001 | mg/L | | <0.001 | ---- | ---- | ---- | ---- |
| **Nickel** | 7440-02-0 | 0.001 | mg/L | | **0.014** | ---- | ---- | ---- | ---- |
| **Selenium** | 7782-49-2 | 0.01 | mg/L | | <0.01 | ---- | ---- | ---- | ---- |
| **Silver** | 7440-22-4 | 0.001 | mg/L | | <0.001 | ---- | ---- | ---- | ---- |
| **Thallium** | 7440-28-0 | 0.001 | mg/L | | <0.001 | ---- | ---- | ---- | ---- |
| **Tin** | 7440-31-5 | 0.001 | mg/L | | <0.001 | ---- | ---- | ---- | ---- |
| **Boron** | 7440-42-8 | 0.05 | mg/L | | **0.08** | ---- | ---- | ---- | ---- |
| **Iron** | 7439-89-6 | 0.05 | mg/L | | **2.61** | ---- | ---- | ---- | ---- |
| **EG035T: Total Recoverable Mercury by FIMS** | | | | | | | | | |
| **Mercury** | 7439-97-6 | 0.0001 | mg/L | | <0.0001 | ---- | ---- | ---- | ---- |

ALS Environmental

# QUALITY CONTROL REPORT

| | | | |
|---|---|---|---|
| **Work Order** | : **ES1814906** | Page | : 1 of 5 |
| Client | : **LRM GLOBAL** | Laboratory | : Environmental Division Sydney |
| Contact | : MR JON LAWSON | Contact | : Larissa Burns |
| Address | : P.BOX.1237<br>CARLTON VIC 3053 | Address | : 277-289 Woodpark Road Smithfield NSW Australia 2164 |
| Telephone | : ---- | Telephone | : +61-2-8784 8555 |
| Project | : ---- | Date Samples Received | : 22-May-2018 |
| Order number | : | Date Analysis Commenced | : 24-May-2018 |
| C-O-C number | : ---- | Issue Date | : 28-May-2018 |
| Sampler | : ---- | | |
| Site | : ---- | | |
| Quote number | : MEBQ/251/17 Primaary Work Only | | |
| No. of samples received | : 1 | | |
| No. of samples analysed | : 1 | | |

Accreditation No. 825
Accredited for compliance with
ISO/IEC 17025 - Testing

This report supersedes any previous report(s) with this reference. Results apply to the sample(s) as submitted. This document shall not be reproduced, except in full.

This Quality Control Report contains the following information:

- Laboratory Duplicate (DUP) Report; Relative Percentage Difference (RPD) and Acceptance Limits
- Method Blank (MB) and Laboratory Control Spike (LCS) Report; Recovery and Acceptance Limits
- Matrix Spike (MS) Report; Recovery and Acceptance Limits

## *Signatories*

This document has been electronically signed by the authorized signatories below. Electronic signing is carried out in compliance with procedures specified in 21 CFR Part 11.

| *Signatories* | *Position* | *Accreditation Category* |
|---|---|---|
| Ivan Taylor | Analyst | Sydney Inorganics, Smithfield, NSW |

## General Comments

The analytical procedures used by the Environmental Division have been developed from established internationally recognized procedures such as those published by the USEPA, APHA, AS and NEPM. In house developed procedures are employed in the absence of documented standards or by client request.

Where moisture determination has been performed, results are reported on a dry weight basis.

Where a reported less than (<) result is higher than the LOR, this may be due to primary sample extract/digestate dilution and/or insufficient sample for analysis. Where the LOR of a reported result differs from standard LOR, this may be due to high

Key : Anonymous = Refers to samples which are not specifically part of this work order but formed part of the QC process lot
CAS Number = CAS registry number from database maintained by Chemical Abstracts Services. The Chemical Abstracts Service is a division of the American Chemical Society.
LOR = Limit of reporting
RPD = Relative Percentage Difference
# = Indicates failed QC

## Laboratory Duplicate (DUP) Report

The quality control term Laboratory Duplicate refers to a randomly selected intralaboratory split. Laboratory duplicates provide information regarding method precision and sample heterogeneity. The permitted ranges for the Relative Percent Deviation (RPD) of Laboratory Duplicates are specified in ALS Method QWI-EN/38 and are dependent on the magnitude of results in comparison to the level of reporting: Result < 10 times LOR: No Limit; Result between 10 and 20 times LOR: 0% - 50%; Result > 20 times LOR: 0% - 20%.

Sub-Matrix: **WATER**

| | | | | Laboratory Duplicate (DUP) Report | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| *Laboratory sample ID* | *Client sample ID* | *Method: Compound* | *CAS Number* | *LOR* | *Unit* | *Original Result* | *Duplicate Result* | *RPD (%)* | *Recovery Limits (%)* |
| **EG020T: Total Metals by ICP-MS (QC Lot: 1672027)** | | | | | | | | | |
| ES1814273-001 | Anonymous | EG020B-T: Silver | 7440-22-4 | 0.001 | mg/L | <0.001 | <0.001 | 0.00 | No Limit |
| ES1814906-001 | Split 1 | EG020B-T: Silver | 7440-22-4 | 0.001 | mg/L | <0.001 | <0.001 | 0.00 | No Limit |
| **EG020T: Total Metals by ICP-MS (QC Lot: 1672029)** | | | | | | | | | |
| ES1814906-001 | Split 1 | EG020A-T: Copper | 7440-50-8 | 0.001 | mg/L | 0.035 | 0.035 | 0.00 | 0% - 20% |
| EW1802118-004 | Anonymous | EG020A-T: Cadmium | 7440-43-9 | 0.0001 | mg/L | <0.0001 | <0.0001 | 0.00 | No Limit |
| | | EG020A-T: Antimony | 7440-36-0 | 0.001 | mg/L | <0.001 | <0.001 | 0.00 | No Limit |
| | | EG020A-T: Arsenic | 7440-38-2 | 0.001 | mg/L | <0.001 | <0.001 | 0.00 | No Limit |
| | | EG020A-T: Beryllium | 7440-41-7 | 0.001 | mg/L | <0.001 | <0.001 | 0.00 | No Limit |
| | | EG020A-T: Barium | 7440-39-3 | 0.001 | mg/L | 0.036 | 0.035 | 2.85 | 0% - 20% |
| | | EG020A-T: Chromium | 7440-47-3 | 0.001 | mg/L | <0.001 | <0.001 | 0.00 | No Limit |
| | | EG020A-T: Cobalt | 7440-48-4 | 0.001 | mg/L | <0.001 | <0.001 | 0.00 | No Limit |
| | | EG020A-T: Copper | 7440-50-8 | 0.001 | mg/L | <0.001 | <0.001 | 0.00 | No Limit |
| | | EG020A-T: Lead | 7439-92-1 | 0.001 | mg/L | <0.001 | <0.001 | 0.00 | No Limit |
| | | EG020A-T: Manganese | 7439-96-5 | 0.001 | mg/L | 0.115 | 0.113 | 2.11 | 0% - 20% |
| | | EG020A-T: Molybdenum | 7439-98-7 | 0.001 | mg/L | <0.001 | <0.001 | 0.00 | No Limit |
| | | EG020A-T: Nickel | 7440-02-0 | 0.001 | mg/L | <0.001 | <0.001 | 0.00 | No Limit |
| | | EG020A-T: Thallium | 7440-28-0 | 0.001 | mg/L | <0.001 | <0.001 | 0.00 | No Limit |
| | | EG020A-T: Tin | 7440-31-5 | 0.001 | mg/L | <0.001 | <0.001 | 0.00 | No Limit |
| | | EG020A-T: Aluminium | 7429-90-5 | 0.01 | mg/L | 0.04 | 0.03 | 0.00 | No Limit |
| | | EG020A-T: Selenium | 7782-49-2 | 0.01 | mg/L | <0.01 | <0.01 | 0.00 | No Limit |
| | | EG020A-T: Boron | 7440-42-8 | 0.05 | mg/L | <0.05 | <0.05 | 0.00 | No Limit |
| | | EG020A-T: Iron | 7439-89-6 | 0.05 | mg/L | 0.77 | 0.76 | 2.27 | 0% - 50% |
| ES1814906-001 | Split 1 | EG020A-T: Cadmium | 7440-43-9 | 0.0001 | mg/L | <0.0001 | <0.0001 | 0.00 | No Limit |
| | | EG020A-T: Antimony | 7440-36-0 | 0.001 | mg/L | <0.001 | <0.001 | 0.00 | No Limit |
| | | EG020A-T: Arsenic | 7440-38-2 | 0.001 | mg/L | <0.001 | <0.001 | 0.00 | No Limit |

Sub-Matrix: **WATER**

| | | | | Laboratory Duplicate (DUP) Report | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| *Laboratory sample ID* | *Client sample ID* | *Method: Compound* | *CAS Number* | *LOR* | *Unit* | *Original Result* | *Duplicate Result* | *RPD (%)* | *Recovery Limits (%)* |
| **EG020T: Total Metals by ICP-MS (QC Lot: 1672029) - continued** | | | | | | | | | |
| ES1814906-001 | Split 1 | EG020A-T: Beryllium | 7440-41-7 | 0.001 | mg/L | <0.001 | <0.001 | 0.00 | No Limit |
| | | EG020A-T: Barium | 7440-39-3 | 0.001 | mg/L | 0.041 | 0.042 | 0.00 | 0% - 20% |
| | | EG020A-T: Chromium | 7440-47-3 | 0.001 | mg/L | 0.002 | 0.002 | 0.00 | No Limit |
| | | EG020A-T: Cobalt | 7440-48-4 | 0.001 | mg/L | 0.011 | 0.011 | 0.00 | 0% - 50% |
| | | EG020A-T: Lead | 7439-92-1 | 0.001 | mg/L | 0.002 | 0.004 | 47.0 | No Limit |
| | | EG020A-T: Manganese | 7439-96-5 | 0.001 | mg/L | 0.210 | 0.211 | 0.00 | 0% - 20% |
| | | EG020A-T: Molybdenum | 7439-98-7 | 0.001 | mg/L | <0.001 | <0.001 | 0.00 | No Limit |
| | | EG020A-T: Nickel | 7440-02-0 | 0.001 | mg/L | 0.014 | 0.015 | 0.00 | 0% - 50% |
| | | EG020A-T: Thallium | 7440-28-0 | 0.001 | mg/L | <0.001 | <0.001 | 0.00 | No Limit |
| | | EG020A-T: Tin | 7440-31-5 | 0.001 | mg/L | <0.001 | <0.001 | 0.00 | No Limit |
| | | EG020A-T: Aluminium | 7429-90-5 | 0.01 | mg/L | 1.09 | 1.18 | 7.70 | 0% - 20% |
| | | EG020A-T: Selenium | 7782-49-2 | 0.01 | mg/L | <0.01 | <0.01 | 0.00 | No Limit |
| | | EG020A-T: Boron | 7440-42-8 | 0.05 | mg/L | 0.08 | 0.08 | 0.00 | No Limit |
| | | EG020A-T: Iron | 7439-89-6 | 0.05 | mg/L | 2.61 | 2.66 | 1.82 | 0% - 20% |
| **EG035T: Total Recoverable Mercury by FIMS (QC Lot: 1672988)** | | | | | | | | | |
| EP1806290-014 | Anonymous | EG035T: Mercury | 7439-97-6 | 0.0001 | mg/L | <0.0001 | <0.0001 | 0.00 | No Limit |
| ES1814871-002 | Anonymous | EG035T: Mercury | 7439-97-6 | 0.0001 | mg/L | <0.0001 | <0.0001 | 0.00 | No Limit |

## Method Blank (MB) and Laboratory Control Spike (LCS) Report

The quality control term Method / Laboratory Blank refers to an analyte free matrix to which all reagents are added in the same volumes or proportions as used in standard sample preparation. The purpose of this QC parameter is to monitor potential laboratory contamination. The quality control term Laboratory Control Spike (LCS) refers to a certified reference material, or a known interference free matrix spiked with target analytes. The purpose of this QC parameter is to monitor method precision and accuracy independent of sample matrix. Dynamic Recovery Limits are based on statistical evaluation of processed LCS.

Sub-Matrix: **WATER**

| | | | | Method Blank (MB) Report | Laboratory Control Spike (LCS) Report | | | |
|---|---|---|---|---|---|---|---|---|
| | | | | | Spike | Spike Recovery (%) | Recovery Limits (%) | |
| Method: Compound | CAS Number | LOR | Unit | Result | Concentration | LCS | Low | High |
| **EG020T: Total Metals by ICP-MS (QCLot: 1672027)** | | | | | | | | |
| EG020B-T: Silver | 7440-22-4 | 0.001 | mg/L | <0.001 | ---- | ---- | ---- | ---- |
| **EG020T: Total Metals by ICP-MS (QCLot: 1672029)** | | | | | | | | |
| EG020A-T: Aluminium | 7429-90-5 | 0.01 | mg/L | <0.01 | 0.5 mg/L | 94.3 | 82 | 120 |
| EG020A-T: Antimony | 7440-36-0 | 0.001 | mg/L | <0.001 | ---- | ---- | ---- | ---- |
| EG020A-T: Arsenic | 7440-38-2 | 0.001 | mg/L | <0.001 | 0.1 mg/L | 90.1 | 82 | 114 |
| EG020A-T: Beryllium | 7440-41-7 | 0.001 | mg/L | <0.001 | 0.1 mg/L | 94.7 | 79 | 119 |
| EG020A-T: Barium | 7440-39-3 | 0.001 | mg/L | <0.001 | 0.1 mg/L | 90.4 | 84 | 116 |
| EG020A-T: Cadmium | 7440-43-9 | 0.0001 | mg/L | <0.0001 | 0.1 mg/L | 90.8 | 84 | 112 |
| EG020A-T: Chromium | 7440-47-3 | 0.001 | mg/L | <0.001 | 0.1 mg/L | 94.2 | 86 | 116 |
| EG020A-T: Cobalt | 7440-48-4 | 0.001 | mg/L | <0.001 | 0.1 mg/L | 90.5 | 84 | 116 |
| EG020A-T: Copper | 7440-50-8 | 0.001 | mg/L | <0.001 | 0.1 mg/L | 90.7 | 83 | 118 |
| EG020A-T: Lead | 7439-92-1 | 0.001 | mg/L | <0.001 | 0.1 mg/L | 91.4 | 85 | 115 |
| EG020A-T: Manganese | 7439-96-5 | 0.001 | mg/L | <0.001 | 0.1 mg/L | 95.4 | 85 | 113 |
| EG020A-T: Molybdenum | 7439-98-7 | 0.001 | mg/L | <0.001 | 0.1 mg/L | 95.5 | 83 | 121 |
| EG020A-T: Nickel | 7440-02-0 | 0.001 | mg/L | <0.001 | 0.1 mg/L | 90.2 | 84 | 116 |
| EG020A-T: Selenium | 7782-49-2 | 0.01 | mg/L | <0.01 | 0.1 mg/L | 91.4 | 68 | 126 |
| EG020A-T: Thallium | 7440-28-0 | 0.001 | mg/L | <0.001 | 0.1 mg/L | 91.6 | 87 | 117 |
| EG020A-T: Tin | 7440-31-5 | 0.001 | mg/L | <0.001 | 0.1 mg/L | 94.0 | 83 | 123 |
| EG020A-T: Boron | 7440-42-8 | 0.05 | mg/L | <0.05 | 0.5 mg/L | 103 | 75 | 129 |
| EG020A-T: Iron | 7439-89-6 | 0.05 | mg/L | <0.05 | 0.5 mg/L | 93.3 | 85 | 117 |
| **EG035T: Total Recoverable Mercury by FIMS (QCLot: 1672988)** | | | | | | | | |
| EG035T: Mercury | 7439-97-6 | 0.0001 | mg/L | <0.0001 | 0.01 mg/L | 91.4 | 77 | 111 |

## Matrix Spike (MS) Report

The quality control term Matrix Spike (MS) refers to an intralaboratory split sample spiked with a representative set of target analytes. The purpose of this QC parameter is to monitor potential matrix effects on analyte recoveries. Static Recovery Limits as per laboratory Data Quality Objectives (DQOs). Ideal recovery ranges stated may be waived in the event of sample matrix interference.

Sub-Matrix: **WATER**

| | | | | Matrix Spike (MS) Report | | | |
|---|---|---|---|---|---|---|---|
| | | | | Spike | SpikeRecovery(%) | Recovery Limits (%) | |
| Laboratory sample ID | Client sample ID | Method: Compound | CAS Number | Concentration | MS | Low | High |
| **EG020T: Total Metals by ICP-MS (QCLot: 1672029)** | | | | | | | |
| ES1814912-001 | Anonymous | EG020A-T: Arsenic | 7440-38-2 | 1 mg/L | 94.9 | 70 | 130 |
| | | EG020A-T: Beryllium | 7440-41-7 | 1 mg/L | 96.6 | 70 | 130 |
| | | EG020A-T: Barium | 7440-39-3 | 1 mg/L | 93.9 | 70 | 130 |

Sub-Matrix: **WATER**

| | | | | Matrix Spike (MS) Report | | | |
|---|---|---|---|---|---|---|---|
| | | | | Spike | SpikeRecovery(%) | Recovery Limits (%) | |
| *Laboratory sample ID* | *Client sample ID* | *Method: Compound* | *CAS Number* | *Concentration* | *MS* | *Low* | *High* |
| **EG020T: Total Metals by ICP-MS (QCLot: 1672029) - continued** | | | | | | | |
| ES1814912-001 | Anonymous | EG020A-T: Cadmium | 7440-43-9 | 0.25 mg/L | 94.7 | 70 | 130 |
| | | EG020A-T: Chromium | 7440-47-3 | 1 mg/L | 94.1 | 70 | 130 |
| | | EG020A-T: Cobalt | 7440-48-4 | 1 mg/L | 94.6 | 70 | 130 |
| | | EG020A-T: Copper | 7440-50-8 | 1 mg/L | 94.4 | 70 | 130 |
| | | EG020A-T: Lead | 7439-92-1 | 1 mg/L | 95.4 | 70 | 130 |
| | | EG020A-T: Manganese | 7439-96-5 | 1 mg/L | 92.1 | 70 | 130 |
| | | EG020A-T: Nickel | 7440-02-0 | 1 mg/L | 95.8 | 70 | 130 |
| **EG035T: Total Recoverable Mercury by FIMS (QCLot: 1672988)** | | | | | | | |
| ES1814675-001 | Anonymous | EG035T: Mercury | 7439-97-6 | 0.01 mg/L | 96.0 | 70 | 130 |

ALS Environmental

# QA/QC Compliance Assessment to assist with Quality Review

| | | | |
|---|---|---|---|
| **Work Order** | : **ES1814906** | Page | : 1 of 4 |
| Client | : **LRM GLOBAL** | Laboratory | : Environmental Division Sydney |
| Contact | : MR JON LAWSON | Telephone | : +61-2-8784 8555 |
| Project | : ---- | Date Samples Received | : 22-May-2018 |
| Site | : ---- | Issue Date | : 28-May-2018 |
| Sampler | : ---- | No. of samples received | : 1 |
| Order number | : | No. of samples analysed | : 1 |

**This report is automatically generated by the ALS LIMS through interpretation of the ALS Quality Control Report and several Quality Assurance parameters measured by ALS. This automated reporting highlights any non-conformances, facilitates faster and more accurate data validation and is designed to assist internal expert and external Auditor review. Many components of this report contribute to the overall DQO assessment and reporting for guideline compliance.**

Brief method summaries and references are also provided to assist in traceability.

## Summary of Outliers

### Outliers : Quality Control Samples

This report highlights outliers flagged in the Quality Control (QC) Report.

- **NO Method Blank value outliers occur.**
- **NO Duplicate outliers occur.**
- **NO Laboratory Control outliers occur.**
- **NO Matrix Spike outliers occur.**
- **For all regular sample matrices, NO surrogate recovery outliers occur.**

### Outliers : Analysis Holding Time Compliance

- **NO Analysis Holding Time Outliers exist.**

### Outliers : Frequency of Quality Control Samples

- **Quality Control Sample Frequency Outliers exist - please see following pages for full details.**

### Outliers : Frequency of Quality Control Samples

Matrix: **WATER**

| Quality Control Sample Type | Count | | Rate (%) | | Quality Control Specification |
|---|---|---|---|---|---|
| Method | QC | Regular | Actual | Expected | |
| Laboratory Control Samples (LCS) | | | | | |
| Total Metals by ICP-MS - Suite B | 0 | 8 | 0.00 | 5.00 | NEPM 2013 B3 & ALS QC Standard |

## Analysis Holding Time Compliance

If samples are identified below as having been analysed or extracted outside of recommended holding times, this should be taken into consideration when interpreting results.

This report summarizes extraction / preparation and analysis times and compares each with ALS recommended holding times (referencing USEPA SW 846, APHA, AS and NEPM) based on the sample container provided. Dates reported represent first date of extraction or analysis and preclude subsequent dilutions and reruns. A listing of breaches (if any) is provided herein.

Holding time for leachate methods (e.g. TCLP) vary according to the analytes reported. Assessment compares the leach date with the shortest analyte holding time for the equivalent soil method. These are: organics 14 days, mercury 28 days & other metals 180 days. A recorded breach does not guarantee a breach for all non-volatile parameters.

Holding times for ***VOC in soils*** vary according to analytes of interest. Vinyl Chloride and Styrene holding time is 7 days; others 14 days. A recorded breach does not guarantee a breach for all VOC analytes and should be verified in case the reported breach is a false positive or Vinyl Chloride and Styrene are not key analytes of interest/concern.

Matrix: **WATER**

Evaluation: × = Holding time breach ; ✓ = Within holding time.

| *Method* / *Container* / Client Sample ID(s) | *Sample Date* | *Extraction / Preparation* | | | *Analysis* | | |
|---|---|---|---|---|---|---|---|
| | | *Date extracted* | *Due for extraction* | *Evaluation* | *Date analysed* | *Due for analysis* | *Evaluation* |
| **EG020T: Total Metals by ICP-MS** | | | | | | | |
| **Clear Plastic Bottle - Nitric Acid; Unspecified (EG020B-T)** | | | | | | | |
| Split 1 | **14-May-2018** | **24-May-2018** | 10-Nov-2018 | ✓ | **24-May-2018** | 10-Nov-2018 | ✓ |
| **EG035T: Total Recoverable Mercury by FIMS** | | | | | | | |
| **Clear Plastic Bottle - Nitric Acid; Unspecified (EG035T)** | | | | | | | |
| Split 1 | **14-May-2018** | **----** | ---- | ---- | **24-May-2018** | 11-Jun-2018 | ✓ |

# Quality Control Parameter Frequency Compliance

The following report summarises the frequency of laboratory QC samples analysed within the analytical lot(s) in which the submitted sample(s) was(were) processed. Actual rate should be greater than or equal to the expected rate. A listing of breaches is provided in the Summary of Outliers.

Matrix: **WATER**

Evaluation: × = Quality Control frequency not within specification ; ✓ = Quality Control frequency within specification.

| Quality Control Sample Type | | Count | | Rate (%) | | | Quality Control Specification |
|---|---|---|---|---|---|---|---|
| *Analytical Methods* | *Method* | *QC* | *Regular* | ***Actual*** | ***Expected*** | *Evaluation* | |
| Laboratory Duplicates (DUP) | | | | | | | |
| Total Mercury by FIMS | EG035T | 2 | 20 | **10.00** | **10.00** | ✓ | NEPM 2013 B3 & ALS QC Standard |
| Total Metals by ICP-MS - Suite A | EG020A-T | 3 | 14 | **21.43** | **10.00** | ✓ | NEPM 2013 B3 & ALS QC Standard |
| Total Metals by ICP-MS - Suite B | EG020B-T | 2 | 8 | **25.00** | **10.00** | ✓ | NEPM 2013 B3 & ALS QC Standard |
| Laboratory Control Samples (LCS) | | | | | | | |
| Total Mercury by FIMS | EG035T | 1 | 20 | **5.00** | **5.00** | ✓ | NEPM 2013 B3 & ALS QC Standard |
| Total Metals by ICP-MS - Suite A | EG020A-T | 1 | 14 | **7.14** | **5.00** | ✓ | NEPM 2013 B3 & ALS QC Standard |
| Total Metals by ICP-MS - Suite B | EG020B-T | 0 | 8 | **0.00** | **5.00** | × | NEPM 2013 B3 & ALS QC Standard |
| Method Blanks (MB) | | | | | | | |
| Total Mercury by FIMS | EG035T | 1 | 20 | **5.00** | **5.00** | ✓ | NEPM 2013 B3 & ALS QC Standard |
| Total Metals by ICP-MS - Suite A | EG020A-T | 1 | 14 | **7.14** | **5.00** | ✓ | NEPM 2013 B3 & ALS QC Standard |
| Total Metals by ICP-MS - Suite B | EG020B-T | 1 | 8 | **12.50** | **5.00** | ✓ | NEPM 2013 B3 & ALS QC Standard |
| Matrix Spikes (MS) | | | | | | | |
| Total Mercury by FIMS | EG035T | 1 | 20 | **5.00** | **5.00** | ✓ | NEPM 2013 B3 & ALS QC Standard |
| Total Metals by ICP-MS - Suite A | EG020A-T | 1 | 14 | **7.14** | **5.00** | ✓ | NEPM 2013 B3 & ALS QC Standard |

## Brief Method Summaries

The analytical procedures used by the Environmental Division have been developed from established internationally recognized procedures such as those published by the US EPA, APHA, AS and NEPM. In house developed procedures are employed in the absence of documented standards or by client request. The following report provides brief descriptions of the analytical procedures employed for results reported in the Certificate of Analysis. Sources from which ALS methods have been developed are provided within the Method Descriptions.

| Analytical Methods | Method | Matrix | Method Descriptions |
|---|---|---|---|
| Total Metals by ICP-MS - Suite A | EG020A-T | WATER | In house: Referenced to APHA 3125; USEPA SW846 - 6020, ALS QWI-EN/EG020. The ICPMS technique utilizes a highly efficient argon plasma to ionize selected elements. Ions are then passed into a high vacuum mass spectrometer, which separates the analytes based on their distinct mass to charge ratios prior to their measurement by a discrete dynode ion detector. |
| Total Metals by ICP-MS - Suite B | EG020B-T | WATER | In house: Referenced to APHA 3125; USEPA SW846 - 6020, ALS QWI-EN/EG020. The ICPMS technique utilizes a highly efficient argon plasma to ionize selected elements. Ions are then passed into a high vacuum mass spectrometer, which separates the analytes based on their distinct mass to charge ratios prior to their measurement by a discrete dynode ion detector. |
| Total Mercury by FIMS | EG035T | WATER | In house: Referenced to AS 3550, APHA 3112 Hg - B (Flow-injection (SnCl2)(Cold Vapour generation) AAS) FIM-AAS is an automated flameless atomic absorption technique. A bromate/bromide reagent is used to oxidise any organic mercury compounds in the unfiltered sample. The ionic mercury is reduced online to atomic mercury vapour by SnCl2 which is then purged into a heated quartz cell. Quantification is by comparing absorbance against a calibration curve. This method is compliant with NEPM (2013) Schedule B(3) |

| Preparation Methods | Method | Matrix | Method Descriptions |
|---|---|---|---|
| Digestion for Total Recoverable Metals | EN25 | WATER | In house: Referenced to USEPA SW846-3005. Method 3005 is a Nitric/Hydrochloric acid digestion procedure used to prepare surface and ground water samples for analysis by ICPAES or ICPMS. This method is compliant with NEPM (2013) Schedule B(3) |

# APPENDIX F

## HISTORICAL REPORT EXTRACTS AND SAQPs

SMEC Testing Services Pty Ltd
ACN 101 164 702 ABN 22 101 164 702
CONSULTING GEOTECHNICAL & ENVIRONMENTAL ENGINEERS
Unit 14
1 Cowpasture Place
WETHERILL PARK
NSW 2164
Phone: (02) 9756 2166 Fax: (02) 9756 1137
Email: enquiries@smectesting.com.au
PO BOX 6909
Wetherill Park
NSW 2164

January 31, 2012
Project No. 18435/1177C
Report No. 12/0113
DWY

Mr Simon Fenton
Lane Cove Council
48 Longueville Road
LANE COVE NSW 2066

**SUBJECT: SOIL SAMPLING AND CLASSIFICATION PROGRAM, LAND AT 266 LONGUEVILLE ROAD, LANE COVE, NEW SOUTH WALES**

Dear Simon,

***Introduction and Background***

In December 2011 SMEC Australia Pty Ltd (SMEC) completed a combined environmental and geotechnical investigation of the property at 266 Longueville Road, Lane Cove, NSW (the 'site'). The purpose of the investigation was to provide advice on the sub-surface conditions of the land that may be relevant to future redevelopment and also to assess the potential for human-health and environmental exposures at the property due to chemical contaminants in the soil. The scope of the environmental component of the investigation included a site inspection and a review of the land use history, as well as a preliminary soil sampling program.

The results of the investigation showed that the concentrations of chemical contaminants measured in the soil samples retrieved from the site are generally low and below criteria that are protective of human-health for recreational and also standard and high-density residential land use settings. However, the fill in the east of the site below 1.5 m depth was found to be impacted with lead and polycyclic aromatic hydrocarbons (PAHs) at concentrations which exceed the relevant health-based criteria. That is, the site could present a potential risk to human-health for these land use settings where exposure pathways exist.

As the contaminated soil is located at a depth which would render it generally inaccessible to site users, the site would not present an unacceptable risk to human-health provided that the existing land surface levels are retained and that an Environmental Management Plan (EMP) is also prepared to ensure that the lead and PAH remains appropriately contained in the long term. Alternatively, the risks posed by the lead and PAH contamination would need to be negated by undertaking active remedial works to remove the chemically impacted fill from the site. We understand that this approach is favoured by Council, as the site may need to be completely stripped of fill during future redevelopment.

Given that the fill on the site is impacted with elevated levels of chemical contaminants and was also observed to contain appreciable quantities of anthropogenic wastes, the fill could not be beneficially reused as clean fill. That is, if fill was required to be removed from the site it would need to be classified as a waste in accordance with the Office of Environment and Heritage (OEH) *Waste Classification Guidelines, Part 1, Classifying Waste, April 2008* (Waste Guidelines) and disposed of to landfill. This report documents the results of the waste classification of the fill based on the results of the December 2011 investigation and the additional analysis of soil samples which was performed in January 2012 specifically for the purposes of the waste classification.

***Scope of Works***

The scope of work was as follows:

- Appraisal of the results of the December 2011 investigation with regard to criteria outlined in the Waste Guidelines;
- Additional leachability testing on selected samples retrieved during the 2011 investigation;
- Appraisal of site geology;
- Assessment of the quality of the soils on the site, and classification of the soil in accordance with OEH guidelines; and
- Preparation of a report to Lane Cove Council detailing the findings of the soil sampling and classification program.

***Sampling Procedures***

The soil samples were collected from a total of 15 boreholes drilled at evenly spaced locations across the site in November 2011. The soil sampling locations are shown on Figure 3 from SMEC's December 2001 report, which is attached to this report, and the soil profile logs providing a description of the fill encountered and soil samples collected is provided in Appendix A. The methodology by which the samples were collected is described in SMEC's December 2011 report.

The soil samples collected were initially analysed for a broad screen of potential chemical contaminants including heavy metals, polycyclic aromatic hydrocarbons (PAH), total petroleum hydrocarbons (TPH), monocyclic aromatic hydrocarbons (BTEX), polychlorinated biphenyls (PCB), organochlorine pesticides (OCP), organophosphorus pesticides (OPP), phenolic compounds, fluoride, cyanide and asbestos. However, in order to appropriately classify the soil selected samples were subsequently tested for leachable lead, nickel and PAHs in January 2012.

The analytical program for the soil samples is outlined in the COC documentation, which is provided in Appendix B. Labmark was selected as the primary laboratory to undertake the analyses, and ALS Sydney was selected as the secondary laboratory for the implementation of the field quality control program. Both Labmark and ALS are NATA accredited for the analyses performed.

***Site Geology***

The Geological Survey of NSW 1:100,000 Sydney Geological Map (Sheet 9130) shows that the site is underlain by the Middle Triassic Age 'Hawkesbury Sandstone' which comprises medium to coarse grained quartz sandstone with minor shale and laminate lenses.

The natural soils encountered during the investigation comprised silty sand topsoil overlying silty and sandy clay subsoil, which are consistent with in-situ weathered soils derived from the Hawkesbury Sandstone formation. Sandstone bedrock was also encountered in each of the 15 boreholes at depths of between 0.2 m and 8.6 m below the ground surface, and depth to bedrock was greatest in the eastern portion of the site.

A layer of fill material between 0.2 m and 8.6 m in thickness was also observed at each sample location. The fill is heterogeneous, comprising sands, gravels and clays, and fragments of anthropogenic wastes including bricks, ash, ceramics and glass were observed in the fill at a number of borehole locations.

Our review of the Acid Sulfate Soil (ASS) risk maps provided on the OEH NSW Natural Resource Atlas (NR Atlas) also shows that the site is located on land that is not expected to be affected by ASSs. This is supported by the geology and geomorphology of the site.

***Assessment Criteria***

In order to classify the soil, the relevant sampling results have been compared to the threshold values for the classification of non-liquid wastes presented in OEH's Waste Guidelines. The results for the soil samples have been compared with the contaminated threshold (CT) values only, with the exception of lead, nickel and PAH species benzo(a)pyrene in selected samples which are compared with the combined total concentration (SCC) and leachable concentration (TCLP) criteria.

***Results***

The results of the soil sample analyses are compared to the above criteria in Table A, and the analytical laboratory reports for the testing performed are provided in Appendix C.

The results show that the concentrations of chemical contaminants in the fill are below the CT1 values for General Solid Waste, with the exception of lead, nickel and benzo(a)pyrene. However, leachability testing subsequently performed on the samples has shown that the concentrations of these contaminants are below the maximum threshold values for General Solid Waste (SCC1 and TCLP values) when used together, although the concentration of both total and leachable lead in one sample retrieved from a depth of approximately 4.5 m in borehole BH13 positioned in the east of the site exceeded its criteria for General Solid Waste.

Further, whilst the concentration of leachable lead in this sample is below the maximum allowable TCLP criterion for Restricted Solid Waste, the total lead concentration is above the SCC1 threshold for Restricted Solid Waste. Therefore, the soils across the majority of the site are classified as General Solid Waste for the purposes of landfill disposal, whilst the discrete 'hotspot' of soil in the vicinity of location BH13 is classed as Hazardous Waste based on the Waste Guidelines criteria.

However, given that the elevated levels of lead in the soil at BH13 are expected to be due to metallurgical furnace residues (ash and slag), the soil would satisfy the conditions of General Immobilisation Approval 2009/07 under the provisions of the *Protection of the Environment Operations (Waste) Regulation 1996*. Under this approval soil which is impacted with chemical contaminants (including lead) that are the result of metallurgical residues can be classified based on their leachable concentrations alone. Therefore, the soil in the vicinity of BH13 could be classified as Restricted Solid Waste by invoking the abovementioned General Immobilisation Approval.

Q***uality Assurance/Quality Control Program***

As part of the 2011 investigation, a quality assurance program was implemented in order to confirm the accuracy and precision of the analytical data, and included the collection and analysis of one intra-laboratory and one inter-laboratory field duplicate sample. The results of the duplicate sample analyses are provided in Table B.

The results of the field intra and inter-laboratory duplicate sample analyses are compared to those of the corresponding primary samples in Table B. The results show that the variations between the primary and duplicate sample results are below the allowable Relative Percentage Difference (RPD) criteria of 50% for inorganic species and 70% for organic analytes in all but four of the 67 comparable data sets, which is an acceptable rate of correlation.

The discrepancies encountered are expected to be due to the heterogeneous distribution of the contaminants within fill material. Further, the contaminant concentrations in both the primary and duplicate samples have been used in the data set from which our conclusions have been made. Therefore, the RPD discrepancies do not affect the outcome of the assessment.

Further, our review of the laboratory's internal QC program has shown that the majority of internal duplicate samples, spike recoveries, surrogate standards and laboratory blanks were within the laboratories' recommended range for acceptable reproducibility. Therefore, STS considers the laboratory data obtained in the sampling program to be of acceptable precision, accuracy and reliability and representative of the site conditions encountered.

***Conclusions and Recommendations***

Based on the results of the soil sampling and analyses performed, the soil on the site at 266 Longueville Road, Lane Cove, is classified as General Solid Waste with the exception of a small 'hotspot' area of soil in the east of the site which would be classed a Restricted Solid Waste under the provisions of General Immobilisation Approval 2009/07.

Preliminary 'worst case' estimates suggest that up to approximately 6 000 $m^3$ of fill in the east of the site may be classed as Restricted Solid Waste, however, further soil sampling to delineate the extent of the 'hotspot' area could be undertaken to provide a more accurate estimate of Restricted Solid Waste volumes. Should bulk removal of the fill from the site be proposed, we would recommend that the 'hotspot' of lead impacted soil be excavated and disposed of initially. Following validation sampling to confirm that all soil classed as Restricted Solid Waste has been removed, the larger soil mass could then be disposed of to landfill as General Solid Waste. This would be the most cost effective approach to removing the fill from the site.

***Limitations***

SMEC Testing Services Pty Limited has performed its services for this project in accordance with its current professional standards. Laboratory analyses were undertaken as part of this investigation by ALS which is NATA accredited for the analyses performed.

When assessing the extent of contamination from a soil sampling program there is the possibility that variations may occur between sample locations. The actual presence of contaminated material at the site may differ from this inferred herein, since no sampling program, no matter how comprehensive, can reveal all anomalies and hot spots that may be present.

Regulatory evaluation criteria are constantly changing and as a consequence, the concentrations of contaminants in the soil subject to this sampling program may fall under different regulatory standards that could alter the soil classification.

Opinions and judgements expressed herein, which are based on our understanding and interpretation of current regulatory standards, should not be construed as legal opinions.

This document and the information herein have been prepared solely for the use of Lane Cove Council for the purposes nominated in this report. No person or organisation other than Lane Cove Council is entitled to rely on any part of the report without the prior written consent of STS. Any third party relying on this report shall have no legal recourse against STS or its parent organisations or subsidiaries and shall indemnify and defend them from all an against all claims arising out of, or in conjunctions with such use or reliance.



David Yonge (BSc, MSc)
Environmental Manager,
SMEC Testing Services Pty Limited

Mr Karlis Kambala
Development Manager
Australian Unity Limited
114 Albert Rd, South Melbourne,
VIC 3205
Reference: P16503_L01_R2

29/05/2017

**Proposal for Land Restoration Services at 266 Longueville Rd, Lane Cove, NSW**

Dear Karlis,

## Introduction

Arcadis Australia Pacific Pty Ltd (Arcadis) is pleased to provide this proposal to undertake environmental site assessment, waste management and land restoration services as part of the development of 266 Longueville Rd, Lane Cove, NSW (the Site) on behalf of Australian Unity Limited. Arcadis is a global specialist in site assessment, decommissioning and land restoration.

Arcadis (previously Environmental Strategies Pty Ltd) has previously undertaken a review of available site data and provided continued land restoration advice to Australian Unity with respect to developing the Site since project inception in 2016.

As part of a program of works for the Site, Arcadis has attended numerous (6 plus) project planning meetings, prepared remedial planning and estimation scenarios and ecologically sustainable development (ES) advice. This led to Australian Unity being awarded tender by Lane Cove Council to develop the Site as a retirement village (i.e. medium density residential with car parking. The advice provided is also relevant to the current Development Application (DA) process.

Previous Arcadis correspondence relevant to this proposal and project that has been prepared for Australian Unity is listed below and is presented again in **Attachment B**:

- *Indicative Remedial Cost Scenarios, 266 Longueville Rd, Lane Cove dated 18 August 2016*
- *CLM Advice - Ecologically Sustainable Development (ESD) Tender Schedule Input - Australian Unity, 266 Longueville Rd, Lane Cove NSW dated 30 August 2016*
- *Proposal for Land Restoration Services at 266 Longueville Rd, Lane Cove, NSW P16503_L01_R1 dated 19 December 2016*. **(Superseded by this proposal.)**

Our advice has been primarily based on our understanding of Site details documented in the following reports:

- *SMEC Holdings Geotechnical and Environmental Investigation Report' dated 22 December 2011 (Ref: 30011131) and;*

- *SMEC Testing Services 'Soil Sampling and Classification Program' dated 31 January 2012 (Ref 18435/1177C/Report No. 12/0113)*
- *Calibre Consulting Draft Preliminary Bulk Excavation Plan dated 12 August 2016*
- *Calibre Consulting Preliminary Earthworks Volume Estimates in email dated 12 August 2016*
- *Thomson Adsett Preliminary Architectural Drawings Rev B dated 10 August 2016*
- *Lane Cove Council Development Application Consent Conditions*
- *Minutes of previous project meetings*

This proposal outlines a staged process to meet Lane Cove Council's DA conditions of consent as provided to Arcadis by Australian Unity.

Council's requirements specifically include provision of:

- *A detailed environmental site assessment report (Phase 2 ESA); and a*
- *Remedial Action Plan (RAP)*
- *Review of all site works by an accredited NSW EPA Site Auditor. A Site Audit Statement and Site Audit Report will be required to determine the suitability of the site for its intended use in accordance with the NSW DEC (2006) Auditor Guidelines*.

These documents are to be prepared by a suitably qualified person in accordance with NSW EPA endorsed contaminated land guidelines.

In accordance with Australian Unity's current development proposal, the Site assessment must allow for insitu classification of waste materials to allow for expedited offsite disposal and/or beneficial reuse of materials in accordance with the NSW EPA waste management and minimisation hierarchy. In addition, an ecologically sustainable site remediation and validation program is required in accordance with the original ESD tender submission, this should include early determination of appropriately licensed fill sites that have authority and sufficient capacity to receive any Excavated Natural Material (ENM) and Virgin Excavated Natural Material (VENM) generated from the Site.

## 1.1 Background

An historical third party environmental report (2012) for the Site has indicated the presence of polyaromatic hydrocarbons (benzo-a-pyrene) and heavy metal (lead and nickel) contamination on the Site associated with historic filling that has a reported preliminary waste classifications of General Solid Waste (estimate 11,350m$^3$) and Restricted Waste (estimate 6000m$^3$) which could potentially result in very high material disposal costs if not further assessed and managed.

Arcadis (incorporating Environmental Strategies) has presented a technical approach in consultation with Australian Unity to achieve project objectives. The technical approach supporting this proposal has been summarised in detail in Environmental Strategies letter dated 18 August 2016 (Reference 16171_L01) in accordance with the tender proposal.

This proposal outlines the environmental services required to achieve the key goals of assessing and managing soil waste generation during construction and ultimately making the Site suitable for its intended use in accordance with Land Cove Council development application conditions. The services Arcadis consider will be required on this project are listed below:

Prior to Development Application (DA) submission:

- Environmental site investigation of fill materials on the Site to determine material handling, management and disposal requirements prior to excavation;
- Preparation of a Remedial Action Plan (RAP) to clearly document the Site remediation, waste management and validation strategy for the site.

Further to DA consent from Lane Cove Council:

- Review of suitable material receiving locations prior to the transport and disposal of excavated materials by Australian Unity;
- Supervision by a suitably qualified Arcadis environmental scientist during site excavation to oversee and control the excavation and separation of waste and natural material streams marked for offsite disposal; and
- Site validation reporting (required in accordance with the RAP.)

A Site Audit Statement (SAS) will required by Council from a NSW EPA Accredited Site Auditor. A separate proposal should therefore be sought from a preferred Auditor by Australian Unity. Please refer to our advice in the Audit advice section below.

## Background

A summary of the property is provided as follows

*Table 1: Background*

| Site Address | Area and notes |
|---|---|
| 266 Longueville Rd, Lane Cove, NSW | An approximate 9000m$^2$ site with two disused bowling greens and one site building. There is currently historic fill material present on the Site representing an insitu volume of approximately 17,350m$^2$ which requires waste classification prior to offsite disposal or potential onsite containment in accordance with the NSW EPA Waste Guidelines.<br><br>Previous preliminary sample data (SMEC Testing, 2012) indicated the presence of lead, nickel and PAH species B(a)P in site fill. A preliminary waste assessment of the Site fill material was undertaken indicating the presence of General Solid Waste with up to 6000m$^3$ of Restricted Solid Waste in the east of the site.<br><br>Without conducting an additional waste assessment at the site, offsite waste disposal costs using the current (2012) preliminary waste classification data have been estimated to be in excess of $7.2M based on current landfill levies.<br><br>The two former bowling greens have been historically infilled with material comprising sands, gravels and clays, and fragments of anthropogenic wastes including bricks, ash, ceramics and glass at increasing depth from west to east across the site. Arcadis as summarised the site geology from 15 boreholes that were advanced to the top of the bedrock on the site by SMEC (2011 and 2012) as follows:<br><br>Topsoil – Silty sand at depth 0 to 0.2mBGL (brown) |

| Site Address | Area and notes |
|---|---|
| | Fill –Comprising sands, gravels and clays, and fragments of anthropogenic wastes encountered at depth 0.2 m and 8.6 m below ground surface (brown, pale brown to grey)<br><br>Natural/Residual Soils - Comprising silty and sandy clay subsoil approximately 0.4 to 1.4m thick above the bedrock encountered at depths 0.6 to 3.4mBGL (grey or orange brown)<br><br>Bedrock - 'Hawkesbury Sandstone' which comprised medium to coarse grained quartz sandstone with minor shale and laminate lenses encountered between 0.2 m and 8.6 mBGL. Depth to bedrock was greatest in the eastern portion of the site. |

## Objectives

Arcadis has identified the following objectives that will be relevant to achieving successful outcomes on this project:

- Undertaking a site contamination investigation to assess the condition of soil on the Site including the nature and anticipated volume of wastes and materials to be generated prior to their proposed excavation and expedited disposal
- Development of a suitable remediation strategy, environmental management and planning in accordance with Council requirements and the ESD principles submitted as part of the tender.
- Supervision of remediation activities by a suitably qualified person on the Site
- Disposal of all wastes to suitably licensed facilities in a cost-effective manner
- Reporting of site remediation and validation activities to document the site's suitability for its intended use.
- Liaison with a NSW EPA Accredited Site Auditor in a manner that e

## Scope of Works

Arcadis propose to undertake the following scope of work to achieve the project objectives.

Prior to Development Application (DA) submission:

1. **Field Work**

   To estimate waste volumes on the Site and expedite offsite disposa during planned excavation, a targeted environmental site investigation (ESI) will be undertaken, it will include:

   - Site inspection, marking of sample locations, field preparation and works scheduling
   - Underground services clearance at each sample location (proposed borehole plan to be provided) prior to drilling
   - On site drilling of 15 soil bores (2 days total on site) to natural ground using a ute mounted rig to delineate impacts to the Site fill in the vicinity of hotspot locations (BH11, BH12, BH13 and BH15) situated on the historic bowling

greens, also adjacent to the existing site building and on the access road in sandy clay with ash fill;

- Collection of approximately 45 primary soil samples, and 7 Quality Control samples i.e. inter and intra laboratory samples (at a rate of 1 in 20 samples) and rinsate samples (2);
- Submission of soil samples to a NATA accredited laboratory for analysis (total 52 samples) - heavy metals (M8), EC, pH, PAH, BTEX, TPH $C_{10}$-$C_{36}$ and 15 samples for leachability testing (TCLP.)

**2. Insitu Waste Assessment and Reporting**

- Undertake a waste assessment of insitu fill sample results in accordance with the *NSW EPA 2014 Waste Guidelines* and *NSW EPA Resource Recovery Order under Part 9, Clause 93 of the POEO (Waste) Regulation 2014 The Excavated Natural Material Order 2014* to identify the extent of Virgin Excavated Natural Material (VENM), Excavated Natural Material (ENM), Exempted Materials under General Immobilisation Approvals 1999/05 and 2009/07, General Solid Waste (GSW), Restricted Waste (RW) and/or Hazardous Waste (HW) in fill on the Site prior to excavation.
- Preparation of an ESI report that summarises the results of the insitu waste assessment in general accordance with *NSW EPA 2011 Guidelines for Consultants Reporting on Contaminated Sites*. The report will include waste or material classification certificates for each waste stream identified and an insitu volume estimation prior to excavation for expedited disposal.

**3. Remediation Planning**

- Preparation of a Remedial Action Plan (RAP) in accordance with the *NSW EPA 2011 Guidelines for Consultants Reporting on Contaminated Sites*. The RAP will outline the remedial strategy, excavation staging, waste handling and management process and proposed validation program for the Site and inform the Construction Environmental Management Plan (CEMP) where required.

Further to DA consent from Lane Cove Council:

**4. Review of Suitable Soil Waste Disposal Sites**

- The ESI report will also include the results of a review that will identify available waste disposal locations in Sydney (i.e. licensed material receiving sites) to ensure that soil materials are transported and disposed offsite cost effectively. Data to be reviewed will include current locations, current owners, primary access routes, status of approvals, hours of operation, current quantities required by the sites, competing spoil transporters and approximate timing of material transport on the Lane Cove Project. This task allows for a maximum of 25 hours of review time for the Arcadis Project Manager.

**5. Remediation Supervision**

- Supervision of remedial excavations for a maximum of 3 working days on site for one suitably qualified Arcadis field scientist to remove soil contamination previously identified at BH11, BH12, BH13 and BH15 in the east of the Site (an approximate best case 350$m^2$ area).

**6. Site Validation**

- Preparation of a validation report that summarises remediation activities, the process of waste removal to assess site suitability in accordance with *NSW EPA 2011 Guidelines for Consultants Reporting on Contaminated Sites*.

Allowance has also been made for one day on site to visually inspect the bedrock interface after bulk excavation and limited soil sampling and analysis (a total of 5 primary samples) of remaining fill using a hand auger above the bedrock in the eastern portion of the site.

## Optional works (outside scope)

Optional works relevant to the project which have been excluded from our current scope are outlined below. Arcadis would prepare a proposal and seek authorisation from Australian Unity before proceeding with any additional or optional works.

1. **Management of the remediation works contract**
   - The project requires demolition of above ground structures (building, slabs, old services) and removal of identified soil waste from the site. Arcadis has strong capability in remediation of similar sites and would be happy to prepare a separate proposal for this component upon request.
2. **Disposal of Waste at rates**
   - Environmental Strategies has previously provided Australian Unity with a best-case disposal cost estimate (excluding transport) based on insitu volume estimates of 1500m$^3$ and 400m$^3$ of GSW and RSW respectively (Environmental Strategies, 18 August 2016 Ref 16171_L01). Arcadis would need to confirm the volume of waste materials before confirming the costs for disposal, however we can offer very competitive rates.
3. **Track and report the transport and disposal of excavated material**
   - Arcadis would be happy to oversee the process of waste material volume tracking during remediation and collect waste disposal dockets from the waste contractor or licensed receiving sites upon request and in accordance with the proposed bulk excavation plan presented by Calibre (August 2016) and the Arcadis ESI report.
4. **Additional assessment** of waste materials where they are stockpiled on site prior to offsite disposal;
5. **Assessment of imported soil materials or additional advice** for proposed reuse or management of fill onsite.

## Audit advice

Arcadis has previously worked with numerous NSW EPA Accredited Auditors. We also have two in house Senior Auditors for future audit work required by Australian Unity.

Based on our understanding, Australian Unity require an independent Auditor on this project and we know of the following external Auditors with current availability:

**Mrs Julie Evans**
Ramboll Environ Pty Ltd
Level 3, 100 Pacific Hwy
North Sydney NSW 2060
Phone (02) 9954 8100
Email jevans@ramboll.com

The costs for a statutory audit (includes Site Audit Statement and Site Audit Report) typically range from approximately $15,000 for a simple audit to approximately $25,000.

## Budget Estimate

Arcadis proposes to complete the scope of works for the cost estimate outlined below.

*Table 2: Budget Estimate Breakdown*

| Item | Item Description | Cost (ex GST) |
|---|---|---|
| Required for DA Submission (August 2017) | | |
| 1 | ESI Field Work (2 days on site) – assumes completion of field work in June as per scope to meet Council condition | $25, 100 |
| 2 | Preparation of Insitu Waste Assessment and ESI Report - as per scope to meet Council condition | $9, 900 |
| 3 | Preparation of Remediation Action Plan (RAP) – to meet Council condition | $9, 900 |
| **Sub Total** | | **$44,900** |
| Further to DA consent – during construction | | |
| 4 | Review of Suitable Waste Disposal Sites (Arcadis is aware of multiple Sydney receiving sites that are potentially available – we recommend checking availability, licenses and scheduling prior to construction.) | $4, 750 |
| 5 | On site Remediation Supervision<br>(assumes a total of three (3) days on site for one suitably qualified environmental scientist to supervise excavation and stockpiling of impacted material, visual inspection of exposed bedrock. No allowance for additional sampling.) | $7, 800 |
| 6 | Site Validation reporting (as per RAP) to meet Council condition | $9, 900 |
| 7 | Project Management Meetings<br>(assumes attendance at (3) two hour meetings for Ben Munro ($270/hr), travel and preparation.) | $3, 500 |
| **Sub Total** | | **$25, 950** |
| **Total (ex GST)** | | **$70, 850** |

## Project Timing

We can commence work in the week commencing 5 June, 2017 assuming receipt of a signed 'Authorisation to Proceed' form prior to this date. An Authorisation to Proceed form accompanies this proposal (Attachment B).

The ESI and RAP reports can be prepared within approximately three to four (3-4) weeks of receipt of the laboratory reports. Assuming authorisation to proceed is received from Australian Unity as a matter of priority, Arcadis will resource the project to meet a proposed report submission deadline of end July.

Australian Unity will have an opportunity to review and provide one round of comments on the report. Once comments are received the report can be finalised within three days.

## Assumptions and Allowances

The above cost estimate in Table 2 is based on the following assumptions and allowances:

- All costs presented in this proposal are exclusive of GST.
- Any additional works outside the scope of work presented in Section 1 would be charged based on our standard schedule of rates with your prior authorisation.
- Arcadis has applied a mark-up of 15% on all sub-contractor costs and consumables.
- Arcadis has assumed that access to the Site will be unimpeded and that all areas targeted for investigation will be accessible at the time of drilling.
- Arcadis has assumed use of a versatile track mounted rig with push tube and split spoon facility for advancement of 50mm soil boreholes. Based on site information, Arcadis has not allowed for groundwater or surface water investigation.
- Arcadis has not allowed for additional validation sampling given that the current design plan assumes bulk excavation of all fill material to bedrock. Site Validation – includes visual inspection of bedrock with an additional allowance for XRF hire (a hand held metal analyser) to be charged on a weekly basis to minimise the total cost of sampling and analysis required to validate remedial excavations. ES propose to obtain Auditor approval to apply this method when preparing the RAP.
- All laboratory analysis will have a standard turnaround of 7 working days. Faster turnaround times will incur additional surcharges (1 day – 50%, 2 day – 25%, 3 day – 12.5%).
- Arcadis has assumed that an electronic copy of the report will be provided to the client and allowed for one round of revisions only.
- Arcadis has allowed for only one revision of key deliverable reports following review by a third party Auditor. Any additional reviews will be considered a variation to the scope.
- Although it is unlikely, if a change in the number of boreholes and/or depth is required, drilling technique or additional time or additional mobilisation is required to complete the works, then Arcadis will consider this a variation to the budget estimate and charge the client a variation to complete the works;
- Costs have been prepared based on the remedial strategy and data review presented in Sections 2.2 and 3 and as per the statistical outputs shown in Attachment 1 of Environmental Strategies letter dated 18 August 2016 16171-L01-Rev2.

- All works are proposed to be undertaken under our standard terms of trade (Attachment A).

## Invoicing and Limitations

Invoices will be issued at the end of each month. Our payment terms are strictly 30 days. This proposal is valid for 60 days from date of submission to the Client.

The findings of the report will be based on the Scope of Work outlined above. Arcadis will perform services in a manner consistent with the normal level of care and expertise exercised by members of the environmental assessment profession. No warranties express or implied, are made.

Subject to the Scope of Work, Arcadis' assessment will be limited strictly to identifying typical environmental conditions associated with the subject property area and does not include evaluation of any other issues.

The absence of any identified hazardous or toxic materials on the subject property should not be interpreted as a guarantee that such materials do not exist on the site. Arcadis will not investigate any waste materials from the property that may have been disposed of off the site, nor related waste management practices.

The results of this assessment will be based upon the Site inspection and the sampling specified above conducted by Arcadis personnel and information from the Client, regulatory agencies and Council. All conclusions and recommendations regarding the property area will be the professional opinions of the Arcadis personnel involved with the project, subject to the qualifications made above.

While normal assessments of data reliability will be made, Arcadis will not assume responsibility or liability for errors in any data obtained from regulatory agencies, statements from sources outside of Arcadis, or developments resulting from situations outside the scope of this project.


## Insurance

Arcadis maintains up to $10 million of Professional Indemnity and $20 million of Public Liability and maintains all requisite insurances.

## Conclusion

Arcadis has the capacity and capability to commence the job in early June 2017 subject to authorisation. I trust that this proposal meets your immediate requirements and we look forward to working with you on this project. Should you have any questions regarding this proposal, please contact me on 0419 283 941.

Yours sincerely



Ben Munro
Principal Environmental Consultant, Arcadis
M 0419 283 941





















# FLORA, FAUNA & FUNGI IMPACT ASSESSMENT

**for a proposed development site at**

## 266 Longueville Road, Lane Cove

**Prepared for Lane Cove Council**

**By Applied Ecology Pty Ltd**

**09/01/2012**

appliedecology

appliedecology.com.au

Applied Ecology Pty Limited reserves all legal rights and remedies in relation to any infringement of its rights in respect of its confidential information.

DOCUMENT VERIFICATION

| | |
|---|---|
| Project Title | FLORA, FAUNA & FUNGI IMPACT ASSESSMENT for a proposed development site at 266 Longueville Road, Lane Cove |
| Document Title | As above |
| Client | Lane Cove Council |
| Client contact | Simon Fenton |

| Revision | Prepared by | Reviewed by | Date |
|---|---|---|---|
| Draft (D) | MB | AC | January 2011 |
| | | | |
| | | | |

DISCLAIMER

This report is prepared by APPLIED ECOLOGY Pty Limited for its clients' purposes only. The contents of this report are provided expressly for the named client for its own use. No responsibility is accepted for the use of or reliance upon this report in whole or in part by any third party. This report is prepared with information supplied by the client and possibly other stakeholders. While care is taken to ensure the veracity of information sources, no responsibility is accepted for information that is withheld, incorrect or that is inaccurate. This report has been compiled at the level of detail specified in the report and no responsibility is accepted for interpretations made at more detailed levels than so indicated.

ACKNOWLEDGMENTS

APPLIED ECOLOGY Pty Limited wishes to thank all representing organisations and individuals who assisted with fieldwork and contributed to the production or commented on the content of this report, including:

| | |
|---|---|
| Ray Kearney | Sydney Fungal Studies Group |
| Elma Kearney | Sydney Fungal Studies Groupc |
| Simon Fenton | Lane Cove Council |
| Kerry Heatley | Lane Cove Council |

## CONTENTS


DOCUMENT VERIFICATION ..... 1
LADIES BOWLING GREEN REDEVELOPMENT SITE: FLORA, FAUNA & FUNGI SURVEYS AND ECOLOGICAL ASSESSMENT ..... 4
PROJECT BACKGROUND & SITE CONTEXT ..... 4
PROJECT OBJECTIVES ..... 7
FLORA SURVEYS ..... 8
METHODS ..... 8
ATLAS SEARCH RESULTS ..... 9
FIELD SURVEY RESULTS ..... 9
FAUNA SURVEYS ..... 25
METHODS ..... 25
ATLAS SEARCHES ..... 26
FIELD SURVEY RESULTS ..... 26
FUNGI Survey ..... 28
METHODS ..... 28
ATLAS SEARCHES ..... 29
FIELD SURVEY RESULTS ..... 29
ASSESSMENT OF CONDITION ..... 34
ASSESSMENT OF VEGETATION CONDITION ..... 34
Zones 1-3: Roadside and Bowling Greens ..... 34
Zones 4-5: Bushland below Bowling Greens ..... 37
Zones 6-7: Bushland below Adjoining Properties ..... 39
ASSESSMENT OF HABITAT AND CONSERVATION VALUE ..... 40
FLORA/VEGETATION ..... 40
FAUNA ..... 42
FUNGI ..... 43
MITIGATION OF IMPACTS ..... 44
IDENTIFICATION OF THREATS ..... 44
SPECIFIC MEASURES TO REDUCE AND OFFSET IMPACTS ..... 45
REFERENCES ..... 47


TABLES


Table 1. Threatened flora species recorded within 5km of 266 Longueville Rd, Lane Cove. ..... 9
Table 2. Endangered Ecological Communities recorded within 5km of 266 Longueville Rd, Lane Cove ..... 9
Table 3. Native flora species recorded during surveys in December, 2011 in zones 1-3, 266 Longueville Rd, Lane Cove. ..... 11
Table 4. Exotic flora species recorded during surveys in December, 2011 in zones 1-3, 266 Longueville Rd, Lane Cove. ..... 11
Table 5. Native flora species recorded during surveys in December, 2011 in zones 4-5, 266 Longueville Rd, Lane Cove. ..... 15
Table 6. Exotic flora species recorded during surveys in December, 2011 in zones 4-5, 266 Longueville Rd, Lane Cove. ..... 17
Table 7. Native flora species recorded during surveys in December, 2011 in zones 6-7, 266 Longueville Rd, Lane Cove. ..... 19
Table 8. Exotic flora species recorded during surveys in December, 2011 in zones 6-7, 266 Longueville Rd, Lane Cove. ..... 22
Table 9. Threatened fauna species recorded within 5km of 266 Longueville Rd, Lane Cove. ..... 26
Table 10. Fauna species recorded during surveys in December, 2011 around 266 Longueville Rd, Lane Cove. ..... 26

Table 11. Threatened fungi species recorded within 5km of 266 Longueville Rd, Lane Cove. 29
Table 12 Species observed 31
Table 13. Percentage cover of native and exotic flora in vegetation layers for each of Zones 1-3. 35
Table 14. Percentage cover of native and exotic flora in vegetation layers for each of Zones 4-5. 38
Table 15. Percentage cover of native and exotic flora in vegetation layers for each of Zones 6-7. 40

FIGURES

Figure 1. The development site location overview (red outline). 4
Figure 2. The development site 5
Figure 3 Zoning 6
Figure 4 Recreation of Council's Bush Fire Prone Land - Rural Fires and Environmental Assessment Legislation Amendment Act 2002 map. 7
Figure 5. Location of vegetation zones for survey site at 266 Longueville Rd, Lane Cove and adjoining properties. 10
Figure 6. Ringtail possums were plentiful during night surveys. 28
Figure 7. A Blue Tongue Lizard was seen soaking up the early summer sunshine. 28
Figure 8. Grey Butcherbirds raise their young in nearby canopy. 28
Figure 9. Elma and Ray Kearney assisted Applied Ecology's staff (Meredith Brainwood in photo) with collection and identification of fungi at 266 Longueville Rd, Lane Cove. 30
Figure 10. Fungi collection ready for identification 30
Figure 11 Zones 1, 2 &3 34
Figure 12 Vegetation along the roadside edge (Zone 1) at 266 Longueville Rd, Lane Cove. 35
Figure 13 Vegetation associated with the disused middle green (Zone 3) at 266 Longueville Rd, Lane Cove. 36
Figure 14 Vegetation associated with the disused top green (Zone 2) at 266 Longueville Rd, Lane Cove. 36
Figure 15 Zones 4 & 5 37
Figure 17 Mature eucalypts provide canopy over weeds in the midstorey and groundlayers in Zone 4. 38
Figure 16 . Native canopy shelters a mixed understorey of native and exotic species in bushland in Zone 5. 38
Figure 18 Zones 6 & 7 39
Figure 19 Diversity of native flora is greatest in the bushland below adjoining properties (Zone 6). 40
Figure 20 Most of the vegetation on the survey site has been mapped as Coastal Enriched Sandstone Moist Forest (SMCMA draft vegetation mapping, DECCW 2009). 41
Figure 21. Location of good quality CESMF and poor quality CESMF based on current mapped extent of this community. 44
Figure 24. "Natural" walking tracks should be clearly defined by logs or other edging. 45
Figure 22. Formal footpath along McMahons Rd easement. 45
Figure 23. Informal extension to road easement pathway. 45
Figure 25. Location of existing paths through the subject site and adjoining reserve. Note that these routes may need to change following development of the bowling green site. 46

## PROJECT BACKGROUND & SITE CONTEXT

The site of the former Ladies Bowling Greens at 266 Longueville Road, Lane Cove are being considered for redevelopment by Lane Cove City Council. The proposed development site covers an area of approximately 1.5 hectares and is bounded by Longueville Road, to the north by adjacent private properties fronting Richardson Street West, to the east by McMahons Road easement which is part of the Lane Cove Country Club, and to the south by a strata property as well as bushland owned by Lane Cove Council.

The old bowling greens are located on the east of the site with easy access from Longueville Road. The site is forested on the lower slopes to the east, leading down to golf greens and fairways associated with the Lane Cove Country Club that are part. To the immediate east and southeast of the development site is land owned by Council and is part of the Lane Cove Country Club. These sites also contain remnant Coastal Enriched Sandstone Moist Forest vegetation.

Figure 1. The development site location overview (red outline).



Figure 2. The development site



An apartment development is being considered for the western part of 266 Longueville Road (Figure 2). No apartment development will extend down the wooded slopes and the golf course on the eastern part of the site. As part of any development, Council is investigating a new walking track through existing bushland (Figure 2) to link this site with the Lane Cove Country Club. Prior to development of the proposl, Council needs to understand the ecological attributes of the immediate area.


The subject site is currently zoned RE1- Public Recreation and E2 - Environmental Conservation under the Lane Cove Local Environment Plan 2009 (LCC LEP). R4 - High Density Residential abuts the subject site on the southern and north east boundary with R2 Low Density Residential along the northern boundary. The eastern portion of the subject site and adjacent areas are also zoned RE1 and form part of the Golf course.

The proposed development would occur in the portion of the lot zoned RE1. From the LCC LEP the objectives of this zoning are:

- To enable land to be used for public open space or recreational purposes.
- To provide a range of recreational settings and activities and compatible land uses.
- To protect and enhance the natural environment for recreational purposes.
- To make provision for rights of public access to more foreshore land and to link existing open space areas.

Environmental protection works are permitted without consent and Child care centres; Community facilities; Environmental facilities; Kiosks; Marinas; Mooring pens; Recreation areas; Recreation facilities (indoor); Recreation facilities (outdoor); Respite day care centres; Restaurants or cafes; Roads; Signage; Take away food and drink premises are permiteed with consent. Any other development is prohibited.

Figure 3 Zoning




The subject site would require rezoning for the proposal to proceed.

The remnant forest is mapped as Coastal Enriched Sandstone Moist Forest (SMCMA/DECCW 2009) and forms part of a larger 4 hectare patch of this community on adjoining lots (see Figure 20). This community forms a patchy yet contiguous canopy with Coastal Shale Sandstone forest along the southern boundary of the golf course to provide linkages to Land Cove Bushland Park to the east. The Coastal Enriched Sandstone Moist Forest presents a low fire risk according to Council's Bush Fire Prone Land mapping (2010).

Figure 4 Recreation of Council's Bush Fire Prone Land - Rural Fires and Environmental Assessment Legislation Amendment Act 2002 map.




## PROJECT OBJECTIVES

The key outputs of the flora, fauna and fungi assessment include:

- A review of any existing literature and information available for the development site and the general locality to determine issues for consideration
- A flora survey to identify species and vegetation communities present on the development site and, as a minimum extent, any present on the adjacent sites.
- A fauna survey to identify species present on the subject site and, as a minimum extent, any present on the adjacent sites.
- A fungi survey to identify species present on the subject site and, as a minimum extent, any present on the adjacent sites.
- An assessment of the conservation value of the species and communities recorded or identified with potential to occur on the subject site. This includes assessment of the condition of vegetation communities and the value of the subject site as fauna habitat.
- An analysis of the likely significance of the impacts of a future residential development in accordance with Commonwealth and State legislation requirements and local guidelines.
- The identification of specific measures that may be incorporated into the design of any future development to ameliorate any likely impacts upon the native flora and fauna on in the immediate area.

LRM Global Pty Ltd
GPO Box 1237
Melbourne VIC 3053
Email: jon.lawson@lrmglobal.com.au
Web: www.lrmglobal.com.au
Phone : (03) 9371 3400
Mobile: 04111 477 22

31st May 2017

Karlis Kambala
Australian Unity Ltd
114 Albert Road
South Melbourne VIC 3205

**Re: Detailed Environmental Site Audit Assessment Works at 266 Longueville Road, Lane Cove NSW.**

Please find attached our proposal for the Detailed Environmental Site Assessment works for Audit assessment report and soil classification for Australian Unity Limited at 266 Longueville Road, Lane Cove, NSW.

If any further information is required or if you have any queries regarding this information please do not hesitate to contact us on 04111 477 22.

Yours faithfully,
**LRM GLOBAL PTY LTD**



**Jon Lawson**
Environmental Consultant

# DETAILED ENVIRONAMENTAL SITE ASSESSMENT PROPOSAL

**PROVIDED BY:**

## LRM GLOBAL PTY LTD

## LIABILITY & RISK MANAGEMENT CONSULTING

**FOR WORKS:**

## 266 Longueville Road, Lane Cove, NSW




**FOR:**

## AUSTRALIAN UNITY LIMITED

## MAY 2017

**CONFIDENTIAL**

# TABLE OF CONTENTS


**1.0 INTRODUCTION ..... 4**

**2.0 OBJECTIVES ..... 4**

**3.0 SCOPE OF WORK ..... 4**

**4.0 CONCEPTUAL SITE MODEL ..... 5**

4.1 SOURCES ..... 5
4.2 DATA GAP ASSESSMENT ..... 5
4.3 PATHWAYS ..... 6
4.3 PATHWAYS ..... 7

**5.0 DATA QUALITY OBJECTIVES ..... 8**

5.1 OVERVIEW ..... 8
5.2 STEP 1: STATE THE PROBLEM ..... 8
5.2 STEP 2: IDENTIFICATION OF THE ASSESSMENT DECISIONS/ GOALS ..... 8
5.3 STEP 3: IDENTIFICATION OF DECISION INPUTS ..... 9
5.4 STEP 4: DEFINITION OF STUDY BOUNDARIES ..... 9
5.5 STEP 5: DECISION RULES ..... 9
5.6 STEP 6: LIMITS ON DECISION ERRORS ..... 9
5.7 STEP 7: OPTIMISE THE DESIGN FOR OBTAINING DATA ..... 11

**6.0 METHODOLOGY AND APPROACH ..... 12**

6.1 SOIL INVESTIGATION ..... 12
6.2 GROUNDWATER INVESTIGATION ..... 14
6.3 LABORATORY SELECTION ..... 15
6.3 ASSESSMENT CRITERIA ..... 15

**7.0 QUALITY ASSURANCE / QUALITY CONTROL AND DATA VALIDATION ..... 17**

**9.0 CLOSURE ..... 18**


Attachments: Proposed Sample Locations

# 1.0 INTRODUCTION

Australian Unity Ltd has invited LRM Global Pty Ltd to undertake a Detailed Environmental Site Assessment (ESA) for Audit at 266 Longueville Road, Lane Cove.

The current scope of work proposed outlines LRM's suggested approach to the work and tasks involved.

We acknowledge that given the potential for uncontrolled landfilling to have occurred that drill locations and samples analysis suites may significantly change based on site observations and the potential for drilling refusal.

# 2.0 OBJECTIVES

The objectives of these works are to characterize site subsurface conditions. The eventual aim is to satisfy the requirements so that an environmental audit for the site can be completed so that a Site Audit Statement can be issued for the site, allowing for site development for an aged care facility with a single underground basement (high density residential land use). It is understood that the basement excavation will extend vertically to a maximum depth of approximately 9.0 meters below ground level and will cover the majority of the site. Open paved/ landscaped areas are planned for portions of the site - refer to the attached extracts of the development plans.

The objectives of this investigation are as follows:

- Characterise site soil and groundwater conditions and flow direction;
- Provide all analytical data in groundwater tables and provide all other relevant data in the form of a detailed environmental site assessment report for the environmental auditor to consider as part of their audit of the site.
- The development of an appropriate waste classification for excavated soils in accordance with NSW EPA Waste Classification Guidelines -Part 1: Classifying waste.

# 3.0 SCOPE OF WORK

A summary of the scope of work to be undertaken by LRM to achieve the objectives listed above would include the following components:

- Site service location and clearance;
- Drilling and installation of 3 monitoring wells on-site – at a later stage following excavation
- Soil sampling at 23 locations to bring in line with the sample density requirements for the development site area of approximately 1.0 hectare as detailed within Australian standard AS4482.1-2005 and NEPM Guidelines for assessing contaminated sites;
- Collection of soil samples from fill and natural material encountered during drilling;
- Logging of soil bores;
- All samples will be couriered, on ice and under COC documentation to NATA accredited laboratories for analysis.
- Completion of detailed environmental site assessment and soil disposal classification reports.

# 4.0 CONCEPTUAL SITE MODEL

The conceptual site model is derived from the findings of the preliminary site assessment report for the site completed by SMEC dated December 2011 which should be read in conjunction with this SAQP.

## *4.1 SOURCES*

Potential sources of contamination and COPC's (contaminants of potential concern) identified at the site by the preliminary site assessment are detailed in the following table:

***Table 6: Potential Sources and Contaminants of Concern***

| Source | Location | Contaminants of Concern | Media | Comments / Risk Potential |
|---|---|---|---|---|
| Imported Fill Material – 1950 – 1970 | Entire site (levelling) | Various (commonly PAHs and heavy metals), TRH, OPP/ OCP | Soil/ Groundwater | High – Based on PSI soil assessment works. |
| Former bowling green 1950 – 1970 onward | Entire site | OCPs, OPPs Methyl-mercury | Soil/Groundwater | High - near surface soils |
| Service Station | South 50m | TRH, BTEX, SVOC, VOC, Lead | Groundwater | Low Down/cross gradient |

## *4.2 DATA GAP ASSESSMENT*

Soils at the site are currently characterized by 15 soil sample locations from the preliminary site assessment. Not all samples have been analysed for all identified COPC's. The identified depth of fill across the site extends from 0.3 to 8+ mbgl increasing in thickness toward the south east of site. Further sampling and analysis of the sites soils and representative geologies to project RL depth of 3.0 mbgl is required to determine if the site subsurface has been contaminated as a result of historic activities at the site and from surrounds and to determine the depth and extent of fill material across the previously inaccessible areas of the site. Additional data is also required to determine an offsite waste disposal classification for the materials as per the planned basement excavation.

Groundwater at the site has yet to be characterized. The proposed monitoring well network is required to determine the groundwater flow direction, elevation and to assess the quality of groundwater as it enters and leaves the site to determine if historic site or offsite activities have resulted in groundwater pollution or pose a health risk to future site occupants.

There are no current plans to assess soil vapor at the site given that significant excavation will occur removing the imported fill layer.

## *4.3 PATHWAYS*

### Geology

The main geological units encountered at the site, in order of stratigraphic sequence from youngest to oldest include:

- Fill material (entire site) generally silty sands or sandy clays sometimes containing gravel, glass fragments, ash and organic material including roots – expected to be permeable.
- Natural – residual sandy soil overlying medium to coarse grained quartz sandstone.

The key transport mechanisms for soil contaminants include mobilisation via surface water flow and infiltration and to a lesser extent through windborne dust.

### Groundwater

Groundwater provides a key transport mechanism for contaminants through horizontal and vertical migration of contaminated surface water/stormwater/groundwater through site soils (into the underlying aquifer), and then possible migration of the impact via advection and dispersion toward the canal/ bay. There is a high potential for vertical migration of contaminated groundwater beyond the fill as subsurface materials are predominantly sands, which generally have high permeability.

### Surface water

Surface water drainage over the site is judged to be predominantly via surface run-off directed towards offsite municipal storm water drains, Gore Creek and Tambourine Creek, Lane Cove River and Woodford Bay, Parramatta River and ultimately Botany Bay. The majority of the site is unsealed and grassed and most surface water is expected to drain into the municipal storm water drainage system. Surface water is considered unlikely to act as a potential transport mechanism at the site considering the extent of hardstand and grass coverage over the site.

### Exposure Pathways

Based on the identified receptors and the release, fate, and transport characteristics of the CoPC, pathways through which receptors may become exposed include inhalation, ingestion and dermal absorption. These are discussed briefly below in the context of the site setting:

- Inhalation Exposure Pathway: There is low potential for inhalation of fumes from potential soil and groundwater contamination as no volatile substances have been identified as COPC or from previous testing. There is also the potential for creation of dust during disturbance of soils and infrastructure. Risk of potential inhalation of contaminated dusts during future site works.
- Ingestion Exposure Pathway: Ingestion of contaminants by current and future site occupants may occur through day-to-day activities and direct contact with contaminated soils or surface water.
- Groundwater: A risk to human health exposure from groundwater in the area is associated domestic purposes are considered unlikely due to the availability of a reticulated water supply. A risk from irrigation activities is possible due to the presence of the golf course to the south east of site. A risk to ecological receptors as groundwater is likely to discharge to Gore Creek and subsequently to the Lane cove river.
- Dermal Exposure Pathway: Exposure may occur via sorption through biological membranes such as skin. This pathway may be a concern whenever contaminated soil; surface water or groundwater comes into direct contact with a biological membrane. This pathway could also be a concern if contaminated surface water (runoff from the site) was to come into direct

contact with benthic and aquatic flora and fauna within off-site surface water receiving environments.

## *4.3 PATHWAYS*

The preliminary site investigation identified a number of potential human and environmental receptors of contamination provided an exposure pathway exists. The identified receptors are listed below:

Human Health Receptors:

- Current and future site workers including construction workers during site development and current and future tenants;
- Future aged care residents and workers;
- Offsite receptors including residents and workers on neighboring properties and recreational users of nearby water courses.

Environmental receptors:

- Onsite flora and fauna;
- Offsite ecosystems including down-gradient surface water environments including Gore Creek to the east and Woodford Bay/ Lane Cove River to the south;
- Groundwater beneath the site.

# 5.0 DATA QUALITY OBJECTIVES

## *5.1 OVERVIEW*

The Data Quality Objective (DQO) process will be applied to the investigations as described below, to ensure that data collection activities are appropriate and achieve the stated objectives.

A process for establishing data quality objectives for an investigation-site has been defined by the NSW DEC *Guidelines for the NSW Site Auditor Scheme (2nd edition,* 2006). The Data Quality Objective (DQO) process will be applied to the validation program, as described below, to ensure that data collection activities are appropriate and achieve the project objectives. The DQO process involves seven steps as follows:

- Step 1: State the problem
- Step 2: Identification of the Assessment Decisions/ Goals
- Step 3: Identification of Decision Inputs
- Step 4: Definition of Study Boundaries
- Step 5: Decision Rules
- Step 6: Limits on Decision Errors
- Step 7: Optimise the design for obtaining data

The seven DQO steps for this project are defined as follows:

## *5.2 STEP 1: State the Problem*

The client wishes to develop the site for an aged care facility with a single basement level extending to a depth of 9 meters below ground level.

The site has historically been used for potentially contaminating activities including imported fill for levelling during its development and operation as a bowling green.

The site and surrounds have been subjected to historical infilling of potentially contaminated material.

The problem is soil at the site has undergone limited assessment in 2011 as part of the preliminary site assessment however further assessment of both soil and groundwater is required to close out existing data gaps and to confirm the findings of the preliminary assessment to determine the sites suitability for the proposed use, the necessity for a remedial action plan, and an offsite soil disposal classification.

## *5.2 STEP 2: Identification of the Assessment Decisions/ Goals*

Additional data is required to be collected to address the problem described in “Step 1”

- Is the site suitable for the proposed aged care facility/ high density residential land use in respect to CoPC from historical use and filling?
- Is there any impact from potential adjoining off-site contamination that would pose a potential risk to on-site receptors?

- Does residual contamination on the site have the potential to cause unacceptable risks to off-site receptors in the future?
- What is the waste classification of soils that may require off-site disposal?
- Is further assessment (including further assessment of soils required following demolition of existing structures) or remediation/management/validation required?

### *5.3 STEP 3: Identification of Decision Inputs*

Data inputs to the decision making process will include:

- Existing data collected from the preliminary site assessment desktop and intrusive studies.
- Quantitative data gained through further soil and groundwater intrusive assessment works and laboratory analysis.
- Adopted Assessment Criteria as detailed in section 6

### *5.4 STEP 4: Definition of Study Boundaries*

The site boundary is depicted within attached Figures 1 and 2. The vertical boundaries of the study are as follows:

- Soil Investigation – where possible the soil investigation shall extend to the proposed project excavation depth of 9.0 mbgl.

Temporal Boundaries – while no temporal boundaries exist as such the client has expressed a wish that the works are executed promptly.

### *5.5 STEP 5: Decision Rules*

In order to decide whether the data obtained is precise, accurate, reliable and reproducible for the site at the time of the investigation, field and laboratory quality control and quality assurance (QA/QC) procedures will be utilised throughout the sampling programs and all sampling work will be carried out in accordance with LRM's Standard Field Operating Procedures, which are based on standard industry practices. QA/QC results will be compared to nominal acceptance limits (as outlined in Section 7).

Project analytical data will be compared to NSW EPA made or approved guidelines. The nominated site assessment criteria are presented in Section 6. On the basis of this initial comparison, a decision will be made as to whether or not the contamination may pose a potential risk (environmental or health based), warranting further assessment.

### *5.6 STEP 6: Limits on Decision Errors*

Two types of decision errors are possible:

- False Negative - The site (or areas of the site) may be considered 'uncontaminated' when in fact it is contaminated.
- False Positive - The site (or areas of the site) may be considered 'contaminated' when in fact it is not contaminated.

The implications of the first decision error are considered less acceptable than the second, as the first error could involve unacceptable risk to health and/or the environment, and potentially future costs including possible litigation if the site is found to be unsuitable in the future. The

risks associated with the second error are primarily limited to unwarranted remediation costs. The limits on the first decision error are therefore addressed by use of conservative investigation criteria (which incorporate a factor of safety) and by analysing any data exceeding these criteria on the basis of the 95% upper confidence level (UCL) of the average concentrations. In accordance with the NEPM, secondary criteria apply as follows:

- The standard deviation of the results should be less than 50% of the relevant investigation or screening level.
- No single value should exceed 250% of the relevant investigation or screening level.

The risk of the second decision error occurring will be will minimised by minimising the potential for unrepresentative data which could arise from the following causes:

- Sampling errors which occur when the sampling program does not adequately detect the variability of a contaminant from point to point across the Site, (i.e. the samples collected are not representative of the Site conditions).
- Measurement errors which occur during sample collection, handling preparation, analysis and data reduction.

To minimise the potential for unrepresentative data Data Quality Indicators (DQIs) will be evaluated. The DQIs for sampling techniques and laboratory analysis of collected samples will be based on those listed in Appendix V of the NSW EPA Auditor Guidelines (DEC 2006). Step 5 and Step 6 of the data quality objectives will be assessed by reference to data quality indicators as follows:

**Completeness** – is a measure of the amount of useable data (expressed as %) from data collection activities. The completeness goal is set at there being sufficient valid data generated during the study. If there is insufficient valid data, then additional data are required to be collected. Completeness can be influenced by field issues such as access for sampling or by laboratory issues such as adherence to sample holding times.

**Comparability** – the confidence (expressed qualitatively) that data may be considered to be equivalent for each sampling and analytical event. Comparability is achieved through adopting consistent sampling techniques and ensuring laboratories use consistent analysis techniques.

**Representativeness** - expresses the degree to which sample data accurately represents each media present on the site. Representativeness is achieved by collecting samples in an appropriate pattern across the site, by using a sufficient number of sampling locations to characterise the site and by using consistent, repeatable and appropriate methodologies.

**Precision** - measures the reproducibility or variation of data. The precision of the data is assessed by calculating the Relative Percent Difference (RPD) between primary and duplicate/ inter-lab split samples

LRM will adopt nominal acceptance criteria of 30% RPD for duplicates and splits for inorganics, and nominal acceptance criteria of 50% RPD for field duplicates and splits for organic compounds. It is noted that this will not always be achieved, particularly in heterogeneous media such as imported fill material or disturbed natural materials, or at low analyte concentrations.

**Accuracy (bias)** - measures quantitatively the closeness of the reported data to the true value. Bias can be introduced during sample collection through cross contamination from contaminated equipment, during sample preservation and transport and from laboratory sample handling, preparation and analysis techniques. Accuracy is assessed by reference to the analytical results of laboratory internal QA/QC samples including spikes, blanks and reference standards.

The nominal “acceptance limits” on laboratory control samples are defined as follows:

Laboratory spikes – 70-130% for metals/inorganics 60-140% for organics.
Laboratory duplicates - <30% for metals/inorganics, <50% for organics.
Laboratory blanks - <practical quantitation limit.

Accuracy of field works is assessed by examining the level of contamination detected in field and rinsate blanks. Blanks should return concentrations of all organic analytes as being less than the practical quantitation limit of the testing laboratory. The individual testing laboratories will conduct an assessment of the internal laboratory QA/QC program however the results will also be independently reviewed and assessed by LRM

## *5.7 STEP 7: Optimise the Design for Obtaining Data*

The sampling program has been designed to provide sufficient information to allow a sound scientific and statistical evaluation of the questions set out in Step 2.

To optimise the design of the investigations, this SAQP has been prepared in consultation with the client, site occupants and the Site Auditor and giving consideration to previous investigations. The SAQP will be reviewed and refined as necessary during the assessment by evaluating field observations and analytical results.

# 6.0 METHODOLOGY AND APPROACH

The approach used by LRM in undertaking these investigation works is based on recognised guidelines for the assessment of potentially contaminated sites, published in:

- AS 4482.1 – 2005 *Guide to investigation and sampling of potentially contaminated soil, Part 1: Non- Volatile and semi-volatile compounds;*
- AS 4482.2 – 1999 *Guide to sampling and investigation of potentially contaminated soil, Part 2: Volatile substances;*
- *The National Environment Protection (Assessment of Site Contamination) Measure 1999*, as ammended 2013.
- *Australian and New Zealand Guidelines for Fresh and Marine Water Quality*, ANZECC / ARMCANZ 1992.
- *Australian and New Zealand Guidelines for Fresh and Marine Water Quality*, ANZECC / ARMCANZ 2000.
- NSW EPA Sampling and design Guidelines (September 1995);
- *Guidelines for consultants reporting on contaminated sites (August 2011);*
- *Guideline for the Assessment and management of Groundwater (March 2007);*
- *AS/NZS 5667.11 1998, Water Quality – Sampling – Guidance on sampling groundwaters;*
- NSW Environment, Climate Change and Water 2010, Vapour intrusion: Technical Note;
- *NSW DECC 2009, Waste Classification Guidelines – Part 1;Classifying Waste;*
- *NSW EPA The Excavated Natural Material Order, 2014.*

The works need to be completed so that the Auditor can successfully complete the assessment in accordance with the Environmental Auditor (Contaminated Land) Guidelines for Issue of an Environmental Audit Statement.

## *6.1 Soil Investigation*

Our methodology for the Soil Assessment is described as follows:

1. Field personnel will be suitably experienced and qualified to undertake and document the assessment tasks.
2. Field observations will be logged in accordance with Australian Standard 1726 and the Unified Soil Classification system. Notes will include the location and extent of fill and features such as seepage, moisture, water bearing zones, depth of groundwater tables, discolouration, staining, odours and other indications of contamination. This information will be recorded on the field borehole log and photographed.
3. Soil samples will be collected during monitoring well installation. Where possible, this will be via push-tube methodology prior to the use of solid stem augurs or hammering.
4. Sampling equipment shall be subjected to a three stage decontamination process using Decon 90/tap water, tap water and DI water prior to sampling at each location. Rinsate blanks shall be collected from the third stage.
5. All samples will be collected in clean, lab supplied, sample jars and placed immediately in a sample chest with ice or similar to attempt to reduce sample temperature.
6. Initially, three samples (one from the fill, one from the natural interface and one from the project basement excavation level) from each location shall be tested with the other (intervening samples) held pending initial results review.
7. Sample locations are indicated on the attached plan.
8. Soil sampling will be undertaken at 23 locations (15 drilled and 8 hand auger) to bring in line with the sample density requirements for the development site area of approximately 1.0

hectare as detailed within Australian standard AS4482.1-2005 and NEPM Guidelines for assessing contaminated sites;

9. Sample depths will be subject to local geological conditions, i.e. depth of any fill and natural soil. The sample depths are likely to represent fill or disturbed soil at the surface, soil profile interface point and natural soil at depth with an event total of 23 samples of fill material analysed, 10 samples of surface for herbicides and pesticides and 15 samples of natural material excluding QA/QC samples.
10. Should site observations reveal different layers of fill, or should fill extend further than envisaged, or where other evidence of contamination (such as discoloration or odour) is observed, there may be a need to collect further samples at the consultants' discretion.
11. Should adverse conditions be encountered onsite such as shallow refusal or where hand auguring is required due to access restrictions samples will be collected as outlined above however the deepest natural sample collected above the point of refusal will be analysed in lieu of the project RL sample. Should shallow refusal be encountered the location will be slightly repositioned and given an A/B designation.
12. Soil samples collected will be tested on-site for volatile hydrocarbons with a photoionization detector (PID) every meter or change in soil type or upon olfactory or visual detection of contamination.
13. Observations of the presence or absence of asbestos will be undertaken during field works and included within bore-logs and the DESI report.
14. The laboratory will be instructed via chain of custody documentation to analyse all samples on a normal 5-day turn-around time.
15. Samples will be collected from both the fill and natural soil profiles and will be analysed for contaminants of concern for the site, as identified in the preliminary site assessment as per Table 1 below.
16. Leachability analysis may also be undertaken pending receipt and review of initial soil sample results for off-site disposal classification purposes.
17. An allowance for quality control/ quality assurance (QA/QC) samples has been made in the current works plan in accordance with AS4482.1-2005. The QA/QC samples will comprise of blind replicate samples, inter-laboratory split samples and trip and rinsate blanks. The frequency of QA/QC field samples is presented within Table 3 below. Other samples such as field blanks may also be collected at the discretion of the environmental assessor.
18. All samples will be collected in clean, lab supplied, sample jars and placed immediately in a sample chest with ice or similar to attempt to reduce sample temperature.

The proposed sampling plan reflects the requirements of Table A - NSW EPA 1995 which describes the minimum sampling points for site characterisation, assuming circular hotspots, The adopted sampling pattern is based on the site history and associated data gaps relating to the location of contaminating site activities. The proposed sampling density allows for the detection with 95% confidence of circular contamination hotspots of up to 25.7 meters in diameter indicating that residual hotspots of a lesser diameter may remain undetected.

***Table 1: Proposed Soil Analytical Suite***

| Sample Location | Sample Target/ Expected Depth | # Samples Analysed/ Collected | Analyte |
|---|---|---|---|
| 10 Locations - Surface Fill on bowling greens | 0.1-0.2 | 10/10 | OCP/OPP, methyl-mercury |
| 23 Locations – Fill | 0.5 – 8m within fill material | 23/23 | Metals, PAHs (polycyclic aromatic hydrocarbons), TRHs (Total recoverable hydrocarbons) & BTEX, OCP/OPP |
| 15 Locations Deeper natural project depth - Natural | Excavation RL (1.0 - 9.0 mbgl) varying with site cut | 15/15 | Metals, PAHs (polycyclic aromatic hydrocarbons), TRHs (Total recoverable hydrocarbons) & BTEX, or on hold pending initial data review |

## *6.2 Groundwater Investigation*

**Stage 2 following excavation works.**

Our methodology for the further groundwater sampling is proposed as the following:

1. Installation of three groundwater monitoring wells;
2. Development of monitoring wells by removal of between 3 and 5 well volumes from each newly installed monitoring well a minimum of 1 day after installation in line with the minimum requirements as described within the NEPM schedule B2 section 8.2.3.5 to allow for bentonite seals to fully hydrate and for grout to cure.
3. Surveying of all monitoring wells by a licensed surveyor.
4. Field personnel will be suitably experienced and qualified to undertake and document the assessment tasks.
5. All groundwater monitoring wells will be gauged prior to purging and sampling a minimum of 1 day following development in line with the minimum requirements as described within the NEPM schedule B2 section 8.2.3.5 and considering the highly permeable nature of the subject aquifer allowing for a total of 2 days for the wells to equilibrate following installation.
6. Groundwater samples will be collected using Low-Flow MicroPurge sampling technique or similar, while monitoring field stabilization criteria and minimizing drawdown to ensure that representative groundwater samples are collected.
7. Field notes to be recorded and stabilisation criteria are detailed on the attached sample field sheets.
8. Groundwater sampling equipment shall be subjected to a three stage decontamination process using Decon 90/tap water, tap water and DI water prior to sampling at each location. Rinsate blanks shall be collected from the third stage.
9. All samples will be collected in clean, lab supplied, sample jars and placed immediately in a sample chest with ice or similar to attempt to reduce sample temperature.
10. Table 2 below details the groundwater samples to be collected for the investigation at the site.
11. The laboratory will be instructed via chain of custody documentation to analyse all samples on a normal 5-day turn-around time.

***Table 2: Proposed Groundwater Analytical Suite***

| Sample Location | Analyte |
|---|---|
| All Locations | NEPM HIL Screens |

The QA/QC program for the groundwater monitoring will consist of an inter-laboratory and intra-laboratory duplicate samples as well as rinsate and trip blanks (as detailed in Table 3 below).

## *6.3 Laboratory Selection*

Envirolab Sydney will serve as the primary laboratory for the purposes of this assessment and Eurofins-MGT will serve as the secondary laboratory for the analyses of inter-laboratory split samples.

The Laboratory Limits of Reporting will be below relevant site criteria.

## *6.3 Assessment Criteria*

***Site Soil Investigation:***

In assessing any soil contamination present on this site, and considering the purpose of this assessment, the data will be evaluated against the levels that are given in the NEPM Schedule B (1) Guidelines on the Investigation Levels for Soil and Groundwater [National Environment Protection (Assessment of Site Contamination) Measure 2013].

Human health risk - Given the proposed use of this site, as an 'Aged care facility' development with no opportunities for soil access, the NEPM HIL/HSL Setting B criteria will be the primary assessment tools for analytical results comparison. Results will also be compared against HIL A and HIL C criteria levels.

Ecological risk - The data will also be compared with the NEPM Ecological Investigation/Screening Levels (EIL's/ESLs) criteria as per Schedule B(1), Appendix A, adopting Urban Residential/ Public Open Space.

Waste Classification - The criteria detailed within the NSW EPA Waste Classification Guidelines 2008 will be used to classify soils for future disposal off-site.

***Site Groundwater Investigation:***

In assessing any groundwater contamination present on this site, and considering the purpose of this assessment, the data will be evaluated against the levels that are given in the NEPM Schedule B (1) Guidelines on the Investigation Levels for Soil and Groundwater [National Environment Protection (Assessment of Site Contamination) Measure 2013].

The Groundwater Investigation Levels (GILs) from the NEPM are based on the Australian Water Quality Guidelines 2000 (AWQG), the Australian Drinking Water Guidelines (ADWG), and the Guidelines for Managing Risk in Recreational Waters 2008 (GMRRW). The GILs are adopted in the NEPM as investigation levels in the context of the framework for risk-based assessment of groundwater contamination i.e. levels above which further assessment is required. Trigger

values for slightly to moderately disturbed marine ecosystems (95% level of protection) have been adopted based on the likely discharge point of groundwater at the site to Gore Creek and subsequently Lane Cove River.

The AWQG provide tabulated values based on percentage species protection for various aquatic environments and water uses. The appropriate settings for current and potential uses of groundwater need to be identified for the aquifer undergoing assessment. The guideline documents should be consulted for appropriate interpretation of guideline values, in consultation with relevant regulatory authorities if necessary.

The GILs define acceptable water quality for various contaminants at the point of use and provide frequently used values for drinking water and protection of fresh water ecosystems. The GMRRW recommend applying a multiplication factor of 10 to 20 to the ADWG for assessment of the acceptability of recreational water quality. GILs for other receptors should be obtained directly from the 'primary industries' section of the AWQG where relevant. Note that the recreational and aesthetics sections of the AWQG have been superseded by the GMRRW.

## 7.0 Quality Assurance / Quality Control and Data Validation

The objective of the QA/QC will be to undertake methods and procedures of sample collection and analysis to be used to ensure quality, accuracy, precision and completeness of data generated. The primary focus is on the acquisition of environmental data that is scientifically sound and defensible and can be used to fulfill the overall project objectives. The following will be undertaken:

- The number of quality control samples to be collected and analysed is presented in Table 3 below. This is in accordance with the requirements of the Australian Standard AS4482.1.
- All samples will be analysed by NATA-accredited laboratories namely Eurofins and Envirolab. Each laboratory will follow internal quality control procedures, e.g. routine analysis of standard solutions / reference materials, reagent blanks, laboratory duplicates and spiked samples.
- The quality control program will consist of LRM submitting field duplicates and inter-lab split samples to a primary and secondary laboratory for analysis. The quality assurance program will also consisted of LRM submitting equipment rinsate and Trip blanks for analysis. These results will be used to gauge the potential for cross contamination during sampling and transportation.
- Relative Percent Differences will be calculated from Primary and Duplicate/Split samples to confirm repeatability of sample results.

***Table 3: QA/QC – Frequency of QA/QC Requirements***

| Quality Control Samples | Minimum Number of QA/QC Samples Required | Actual No. Required – LRM Assessment works | | Analytical suite |
|---|---|---|---|---|
| | | Soil | Groundwater | |
| Duplicate Sample | 1 in 20 | 3 | 1 | Metals, PAH(Soil), |
| Split Sample | 1 in 20 | 3 | 1 | Metals, PAH(Soil) |
| Rinsate Blank | 1 / equipment / day | 1 | 1 | TRH/BTEX |
| Trip Blank | 1/day/ eskie | 1 | 1 | BTEX |

Following completion of the field programs, all of the information collected will be checked, data will be collated, calculations completed and results summarised in tabular form.

## 9.0 CLOSURE


I trust this Sample Analysis Plan is in line with your expectations. If you have any suggestions or inclusions that are required as part of these fieldworks, please do not hesitate to contact me on 042 418 2787.

Yours faithfully,
**LRM GLOBAL PTY LTD**



**Jon Lawson**
**Environmental Consultant**

# FIGURES:




| | | | |
|---|---|---|---|
| DATE 01/12/2011 | 0 5 10 20 1:750 Meters | PAGE SIZE A4 | COORDINATE SYSTEM GDA 94 MGA 56 |
| FIG NO. 3 | FIGURE TITLE Borehole Plan | | |
| PROJECT NO. 30011131 | PROJECT TITLE 266 Longueville Road GI | | |
| CREATED BY PR11334 | SOURCES Vector Backdrop - Roadnet © Map Data Services 2011. Aerial Imagery © Bing 2011. | | |

SMEC

© SMEC Australia Pty Ltd 2011. All Rights Reserved

Disclaimer: While all reasonable care has been taken to ensure the information contained on this map is up to date and accurate, this map contains data from a number of sources - no warranty is given that the information contained on this map is free from error or omission. Any reliance placed on such information shall be at the sole risk of the user. Please verify the accuracy of all information prior to using it. This map is not a design document.

Location: I:\projects\30011131 - 266 Longueville Road GI\008 DATA\GIS\Figure3_Longueville_Road_Boreholes.mxd

LRM Global Pty Ltd
GPO Box 1237
Melbourne VIC 3053
Email: jon.lawson@lrmglobal.com.au
Web: www.lrmglobal.com.au
Phone : (03) 9371 3400
Mobile: 04111 477 22

27th February 20178


Tm Miller
Australian Unity Ltd
114 Albert Road
South Melbourne VIC 3205

**Re: Initial Groundwater Assessment Works at 266 Longueville Road, Lane Cove NSW.**

Please find attached our proposal for initial Groundwater Assessment works for Audit assessment report for Australian Unity Limited at 266 Longueville Road, Lane Cove, NSW.

If any further information is required or if you have any queries regarding this information please do not hesitate to contact us on 04111 477 22.

Yours faithfully,
**LRM GLOBAL PTY LTD**



**JON LAWSON**
Environmental Consultant

# INITIAL GROUNDWATER ASSESSMENT AND SUPPLIMENTARY SOILS PROPOSAL

**PROVIDED BY:**

## LRM GLOBAL PTY LTD

## LIABILITY & RISK MANAGEMENT CONSULTING

**FOR WORKS:**

## 266 Longueville Road, Lane Cove, NSW




**FOR:**

## AUSTRALIAN UNITY LIMITED

## FEBRUARY 2018

**CONFIDENTIAL**

# TABLE OF CONTENTS


**1.0 INTRODUCTION ..... 4**

**2.0 OBJECTIVES ..... 4**

**3.0 SCOPE OF WORK ..... 4**

**5.0 DATA QUALITY OBJECTIVES ..... 5**

5.1 OVERVIEW ..... 5
5.2 STEP 1: STATE THE PROBLEM ..... 5
5.2 STEP 2: IDENTIFICATION OF THE ASSESSMENT DECISIONS/ GOALS ..... 5
5.3 STEP 3: IDENTIFICATION OF DECISION INPUTS ..... 6
5.4 STEP 4: DEFINITION OF STUDY BOUNDARIES ..... 6
5.5 STEP 5: DECISION RULES ..... 6
5.6 STEP 6: LIMITS ON DECISION ERRORS ..... 6
5.7 STEP 7: OPTIMISE THE DESIGN FOR OBTAINING DATA ..... 8

**6.0 METHODOLOGY AND APPROACH ..... 9**

6.1 SOIL INVESTIGATION ..... 9
6.2 GROUNDWATER INVESTIGATION ..... 10
6.3 LABORATORY SELECTION ..... 11
6.3 ASSESSMENT CRITERIA ..... 11

**7.0 QUALITY ASSURANCE / QUALITY CONTROL AND DATA VALIDATION ..... 13**

**9.0 CLOSURE AND COSTINGS ..... 14**


Attachments: Proposed Sample Locations

## 1.0 INTRODUCTION

Australian Unity Ltd has invited LRM Global Pty Ltd to undertake an initial Groundwater Assessment (ESA) and supplementary soil delineation at depth for Audit at 266 Longueville Road, Lane Cove.

The current scope of work proposed outlines LRM's suggested approach to the work and tasks involved.

## 2.0 OBJECTIVES

The objectives of these works are to further characterize site subsurface conditions. The eventual aim is to satisfy the requirements so that an environmental audit for the site can be completed so that a Site Audit Statement can be issued for the site, allowing for site development for an aged care facility with a single underground basement (high density residential land use). It is understood that the basement excavation will extend vertically to a maximum depth of approximately 12.0 meters below ground level and will cover the majority of the site. Open paved/ landscaped areas are planned for portions of the site - refer to the attached extracts of the development plans.

The objectives of this investigation are as follows:

- Characterise site groundwater conditions and flow direction;
- Provide all analytical data in groundwater tables and provide all other relevant data in the form of a detailed environmental site assessment report for the environmental auditor to consider as part of their audit of the site.
- The development of a more accurate waste classification for excavated soils in accordance with NSW EPA Waste Classification Guidelines -Part 1: Classifying waste.

## 3.0 SCOPE OF WORK

A summary of the scope of work to be undertaken by LRM to achieve the objectives listed above would include the following components:

- Site service location and clearance;
- Drilling and installation of 3 monitoring wells on-site;
- Soil sampling at 5 locations, target depth 12.5m (3 converted to wells);
- Collection of soil samples from fill and natural material encountered during drilling;
- Logging of soil and groundwater construction bores;
- All samples will be couriered, on ice and under COC documentation to NATA accredited laboratories for analysis;
- Completion of detailed environmental site assessment;

# 5.0 DATA QUALITY OBJECTIVES

## *5.1 OVERVIEW*

The Data Quality Objective (DQO) process will be applied to the investigations as described below, to ensure that data collection activities are appropriate and achieve the stated objectives.

A process for establishing data quality objectives for an investigation-site has been defined by the NSW DEC *Guidelines for the NSW Site Auditor Scheme (2nd edition,* 2006). The Data Quality Objective (DQO) process will be applied to the validation program, as described below, to ensure that data collection activities are appropriate and achieve the project objectives. The DQO process involves seven steps as follows:

- Step 1: State the problem
- Step 2: Identification of the Assessment Decisions/ Goals
- Step 3: Identification of Decision Inputs
- Step 4: Definition of Study Boundaries
- Step 5: Decision Rules
- Step 6: Limits on Decision Errors
- Step 7: Optimise the design for obtaining data

The seven DQO steps for this project are defined as follows:

## *5.2 STEP 1: State the Problem*

The client wishes to develop the site for an aged care facility with basement levels extending to a depth of 12 meters below ground level.

The site has historically been used for potentially contaminating activities including imported fill for levelling during its development and operation as a bowling green.

The site and surrounds have been subjected to historical infilling of potentially contaminated material.

The problem is soil at the site has undergone limited assessment in 2011 and again in 2017 as part of the preliminary site assessment however further assessment of both soil and groundwater is required to close out existing data gaps and to confirm the findings of the preliminary assessment to determine the sites suitability for the proposed use, the necessity for a remedial action plan, and an offsite soil disposal classification.

## *5.2 STEP 2: Identification of the Assessment Decisions/ Goals*

Additional data is required to be collected to address the problem described in “Step 1”

- Is the site suitable for the proposed aged care facility/ high density residential land use in respect to CoPC from historical use and filling?
- Is there any impact from potential adjoining off-site contamination that would pose a potential risk to on-site receptors?

- Does residual contamination on the site have the potential to cause unacceptable risks to off-site receptors in the future?
- What is the waste classification of soils that may require off-site disposal?
- Is further assessment (including further assessment of soils required following demolition of existing structures) or remediation/management/validation required?

## *5.3 STEP 3: Identification of Decision Inputs*

Data inputs to the decision making process will include:

- Existing data collected from the preliminary site assessment desktop and intrusive studies.
- Quantitative data gained through further soil and groundwater intrusive assessment works and laboratory analysis.
- Adopted Assessment Criteria as detailed in section 6

## *5.4 STEP 4: Definition of Study Boundaries*

The site boundary is depicted within attached Figure 1. The vertical boundaries of the study are as follows:

- Soil Investigation – where possible the soil investigation shall extend to the proposed project excavation depth of 12.5 mbgl.
- Groundwater Investigation – Three wells to be installed within the site title boundaries, to represent up-gradient, site derived and down-gradient groundwater conditions.

Temporal Boundaries – while no temporal boundaries exist as such the client has expressed a wish that the works are executed promptly.

## *5.5 STEP 5: Decision Rules*

In order to decide whether the data obtained is precise, accurate, reliable and reproducible for the site at the time of the investigation, field and laboratory quality control and quality assurance (QA/QC) procedures will be utilised throughout the sampling programs and all sampling work will be carried out in accordance with LRM's Standard Field Operating Procedures, which are based on standard industry practices. QA/QC results will be compared to nominal acceptance limits (as outlined in Section 7).

Project analytical data will be compared to NSW EPA made or approved guidelines. The nominated site assessment criteria are presented in Section 6. On the basis of this initial comparison, a decision will be made as to whether or not the contamination may pose a potential risk (environmental or health based), warranting further assessment.

## *5.6 STEP 6: Limits on Decision Errors*

Two types of decision errors are possible:

- False Negative - The site (or areas of the site) may be considered 'uncontaminated' when in fact it is contaminated.
- False Positive - The site (or areas of the site) may be considered 'contaminated' when in fact it is not contaminated.

The implications of the first decision error are considered less acceptable than the second, as the first error could involve unacceptable risk to health and/or the environment, and potentially future costs including possible litigation if the site is found to be unsuitable in the future. The risks associated with the second error are primarily limited to unwarranted remediation costs. The limits on the first decision error are therefore addressed by use of conservative investigation criteria (which incorporate a factor of safety) and by analysing any data exceeding these criteria on the basis of the 95% upper confidence level (UCL) of the average concentrations. In accordance with the NEPM, secondary criteria apply as follows:

- The standard deviation of the results should be less than 50% of the relevant investigation or screening level.
- No single value should exceed 250% of the relevant investigation or screening level.

The risk of the second decision error occurring will be will minimised by minimising the potential for unrepresentative data which could arise from the following causes:

- Sampling errors which occur when the sampling program does not adequately detect the variability of a contaminant from point to point across the Site, (i.e. the samples collected are not representative of the Site conditions).
- Measurement errors which occur during sample collection, handling preparation, analysis and data reduction.

To minimise the potential for unrepresentative data Data Quality Indicators (DQIs) will be evaluated. The DQIs for sampling techniques and laboratory analysis of collected samples will be based on those listed in Appendix V of the NSW EPA Auditor Guidelines (DEC 2006). Step 5 and Step 6 of the data quality objectives will be assessed by reference to data quality indicators as follows:

**Completeness** – is a measure of the amount of useable data (expressed as %) from data collection activities. The completeness goal is set at there being sufficient valid data generated during the study. If there is insufficient valid data, then additional data are required to be collected. Completeness can be influenced by field issues such as access for sampling or by laboratory issues such as adherence to sample holding times.

**Comparability** – the confidence (expressed qualitatively) that data may be considered to be equivalent for each sampling and analytical event. Comparability is achieved through adopting consistent sampling techniques and ensuring laboratories use consistent analysis techniques.

**Representativeness** - expresses the degree to which sample data accurately represents each media present on the site. Representativeness is achieved by collecting samples in an appropriate pattern across the site, by using a sufficient number of sampling locations to characterise the site and by using consistent, repeatable and appropriate methodologies.

**Precision** - measures the reproducibility or variation of data. The precision of the data is assessed by calculating the Relative Percent Difference (RPD) between primary and duplicate/ inter-lab split samples

LRM will adopt nominal acceptance criteria of 30% RPD for duplicates and splits for inorganics, and nominal acceptance criteria of 50% RPD for field duplicates and splits for organic compounds. It is noted that this will not always be achieved, particularly in heterogeneous media such as imported fill material or disturbed natural materials, or at low analyte concentrations.

**Accuracy (bias)** - measures quantitatively the closeness of the reported data to the true value. Bias can be introduced during sample collection through cross contamination from contaminated equipment, during sample preservation and transport and from laboratory sample

handling, preparation and analysis techniques. Accuracy is assessed by reference to the analytical results of laboratory internal QA/QC samples including spikes, blanks and reference standards.

The nominal “acceptance limits” on laboratory control samples are defined as follows:

Laboratory spikes – 70-130% for metals/inorganics 60-140% for organics.
Laboratory duplicates - <30% for metals/inorganics, <50% for organics.
Laboratory blanks - <practical quantitation limit.

Accuracy of field works is assessed by examining the level of contamination detected in field and rinsate blanks. Blanks should return concentrations of all organic analytes as being less than the practical quantitation limit of the testing laboratory. The individual testing laboratories will conduct an assessment of the internal laboratory QA/QC program however the results will also be independently reviewed and assessed by LRM

## *5.7 STEP 7: Optimise the Design for Obtaining Data*

The sampling program has been designed to provide sufficient information to allow a sound scientific and statistical evaluation of the questions set out in Step 2.

To optimise the design of the investigations, this SAQP has been prepared in consultation with the client, site occupants and the Site Auditor and giving consideration to previous investigations. The SAQP will be reviewed and refined as necessary during the assessment by evaluating field observations and analytical results.

# 6.0 METHODOLOGY AND APPROACH

The approach used by LRM in undertaking these investigation works is based on recognised guidelines for the assessment of potentially contaminated sites, published in:

- AS 4482.1 – 2005 *Guide to investigation and sampling of potentially contaminated soil, Part 1: Non- Volatile and semi-volatile compounds;*
- AS 4482.2 – 1999 *Guide to sampling and investigation of potentially contaminated soil, Part 2: Volatile substances;*
- *The National Environment Protection (Assessment of Site Contamination) Measure 1999*, as ammended 2013.
- *Australian and New Zealand Guidelines for Fresh and Marine Water Quality*, ANZECC / ARMCANZ 1992.
- *Australian and New Zealand Guidelines for Fresh and Marine Water Quality*, ANZECC / ARMCANZ 2000.
- NSW EPA Sampling and design Guidelines (September 1995);
- *Guidelines for consultants reporting on contaminated sites (August 2011);*
- *Guideline for the Assessment and management of Groundwater (March 2007);*
- *AS/NZS 5667.11 1998, Water Quality – Sampling – Guidance on sampling groundwaters;*
- NSW Environment, Climate Change and Water 2010, Vapour intrusion: Technical Note;
- *NSW DECC 2009, Waste Classification Guidelines – Part 1;Classifying Waste;*
- *NSW EPA The Excavated Natural Material Order, 2014.*

The works need to be completed so that the Auditor can successfully rely upon the data to assist with completing the assessment in accordance with the Environmental Auditor (Contaminated Land) Guidelines for Issue of an Environmental Audit Statement.

## *6.1 Soil Investigation*

Our methodology for the Soil Assessment is described as follows:

1. Field personnel will be suitably experienced and qualified to undertake and document the assessment tasks.
2. Field observations will be logged in accordance with Australian Standard 1726 and the Unified Soil Classification system. Notes will include the location and extent of fill and features such as seepage, moisture, water bearing zones, depth of groundwater tables, discolouration, staining, odours and other indications of contamination. This information will be recorded on the field borehole log and photographed.
3. Soil samples will be collected during monitoring well installation. Note that this will be by solid stem augurs;
4. Sampling equipment shall be subjected to a three stage decontamination process using Decon 90/tap water, tap water and DI water prior to sampling at each location. Rinsate blanks shall be collected from the third stage.
5. All samples will be collected in clean, lab supplied, sample jars and placed immediately in a sample chest with ice or similar to attempt to reduce sample temperature.
6. Initially, three samples (one from the fill, one from the natural interface and one from the project basement excavation level) from each location shall be tested with the other (intervening samples) held pending initial results review.
7. Sample locations are indicated on the attached plan.
8. Soil sampling will be undertaken at 5 locations;

9. Sample depths will be subject to local geological conditions, i.e. depth of any fill and natural soil. The sample depths are likely to represent fill or disturbed soil at the surface, soil profile interface point and natural soil (current targeted profile) at depth with an event total of 25 samples of fill material analysed excluding QA/QC samples.
10. Should site observations reveal different layers of fill, or should fill extend further than envisaged, or where other evidence of contamination (such as discoloration or odour) is observed, there may be a need to collect further samples at the consultants' discretion.
11. Soil samples collected will be tested on-site for volatile hydrocarbons with a photoionization detector (PID) every meter or change in soil type or upon olfactory or visual detection of contamination.
12. Observations of the presence or absence of asbestos will be undertaken during field works and included within bore-logs and the DESI report.
13. The laboratory will be instructed via chain of custody documentation to analyse all samples on a normal 5-day turn-around time.
14. Samples will be collected from both the fill and natural soil profiles and will be analysed for contaminants of concern for the site, as identified in the preliminary site assessment as per Table 1 below.
15. Leachability analysis may also be undertaken pending receipt and review of initial soil sample results for off-site disposal classification purposes.
16. An allowance for quality control/ quality assurance (QA/QC) samples has been made in the current works plan in accordance with AS4482.1-2005. The QA/QC samples will comprise of blind replicate samples, inter-laboratory split samples and trip and rinsate blanks. The frequency of QA/QC field samples is presented within Table 3 below. Other samples such as field blanks may also be collected at the discretion of the environmental assessor.
17. All samples will be collected in clean, lab supplied, sample jars and placed immediately in a sample chest with ice or similar to attempt to reduce sample temperature.

The proposed sampling plan reflects the requirements of Table A - NSW EPA 1995 which describes the minimum sampling points for site characterisation, assuming circular hotspots, The adopted sampling pattern is based on the site history and associated data gaps relating to the location of contaminating site activities. The proposed sampling density allows for the detection with 95% confidence of circular contamination hotspots of up to 25.7 meters in diameter indicating that residual hotspots of a lesser diameter may remain undetected.

***Table 1: Proposed Soil Analytical Suite***

| Sample Location | Sample Target/ Expected Depth | # Samples Analysed/ Collected | Analyte |
|---|---|---|---|
| 5 Locations Deeper natural project depth - Natural | Excavation RL (12 mbgl) varying with site cut | 25/25 | NSW Waste Disposal Screen x 10<br>TRH, BTEX, PAH, Metals x 25 |

## *6.2 Groundwater Investigation*

Our methodology for the further groundwater sampling is proposed as the following:

1. Installation of three groundwater monitoring wells;
2. Development of monitoring wells by removal of between 3 and 5 well volumes from each newly installed monitoring well a minimum of 1 day after installation in line with the minimum requirements as described within the NEPM schedule B2 section 8.2.3.5 to allow for bentonite seals to fully hydrate and for grout to cure.
3. Surveying of all monitoring wells by a licensed surveyor.
4. Field personnel will be suitably experienced and qualified to undertake and document the assessment tasks.

5. All groundwater monitoring wells will be gauged prior to purging and sampling a minimum of 1 day following development in line with the minimum requirements as described within the NEPM schedule B2 section 8.2.3.5 and considering the highly permeable nature of the subject aquifer allowing for a total of 3 days for the wells to equilibrate following installation.
6. Groundwater samples will be collected using Low-Flow MicroPurge sampling technique or similar, while monitoring field stabilization criteria and minimizing drawdown to ensure that representative groundwater samples are collected.
7. Field notes to be recorded and stabilisation criteria are detailed on the attached sample field sheets.
8. Groundwater sampling equipment shall be subjected to a three stage decontamination process using Decon 90/tap water, tap water and DI water prior to sampling at each location. Rinsate blanks shall be collected from the third stage.
9. All samples will be collected in clean, lab supplied, sample jars and placed immediately in a sample chest with ice or similar to attempt to reduce sample temperature.
10. Table 2 below details the groundwater samples to be collected for the investigation at the site.
11. The laboratory will be instructed via chain of custody documentation to analyse all samples on a normal 5-day turn-around time.

***Table 2: Proposed Groundwater Analytical Suite***

| Sample Location | Analyte |
|---|---|
| All Locations | NEPM HIL Screens, TDS, pH, Cations, Anions<br>(Any additional analytes impacts identified from soil will be added) |

The QA/QC program for the groundwater monitoring will consist of an inter-laboratory and intra-laboratory duplicate samples as well as rinsate and trip blanks (as detailed in Table 3 below).

## *6.3 Laboratory Selection*

Envirolab Sydney will serve as the primary laboratory for the purposes of this assessment and Eurofins-MGT will serve as the secondary laboratory for the analyses of inter-laboratory split samples.

The Laboratory Limits of Reporting will be below relevant site criteria.

## *6.3 Assessment Criteria*

***Site Soil Investigation:***

In assessing any soil contamination present on this site, and considering the purpose of this assessment, the data will be evaluated against the levels that are given in the NEPM Schedule B (1) Guidelines on the Investigation Levels for Soil and Groundwater [National Environment Protection (Assessment of Site Contamination) Measure 2013].

Human health risk - Given the proposed use of this site, as an 'Aged care facility' development with no opportunities for soil access, the NEPM HIL/HSL Setting B criteria will be the primary assessment tools for analytical results comparison. Results will also be compared against HIL A and HIL C criteria levels.

Ecological risk - The data will also be compared with the NEPM Ecological Investigation/Screening Levels (EIL's/ESLs) criteria as per Schedule B(1), Appendix A, adopting Urban Residential/ Public Open Space.

Waste Classification - The criteria detailed within the NSW EPA Waste Classification Guidelines 2008 will be used to classify soils for future disposal off-site.

***Site Groundwater Investigation:***

In assessing any groundwater contamination present on this site, and considering the purpose of this assessment, the data will be evaluated against the levels that are given in the NEPM Schedule B (1) Guidelines on the Investigation Levels for Soil and Groundwater [National Environment Protection (Assessment of Site Contamination) Measure 2013].

The Groundwater Investigation Levels (GILs) from the NEPM are based on the Australian Water Quality Guidelines 2000 (AWQG), the Australian Drinking Water Guidelines (ADWG), and the Guidelines for Managing Risk in Recreational Waters 2008 (GMRRW). The GILs are adopted in the NEPM as investigation levels in the context of the framework for risk-based assessment of groundwater contamination i.e. levels above which further assessment is required. Trigger values for slightly to moderately disturbed marine ecosystems (95% level of protection) have been adopted based on the likely discharge point of groundwater at the site to Gore Creek and subsequently Lane Cove River.

The AWQG provide tabulated values based on percentage species protection for various aquatic environments and water uses. The appropriate settings for current and potential uses of groundwater need to be identified for the aquifer undergoing assessment. The guideline documents should be consulted for appropriate interpretation of guideline values, in consultation with relevant regulatory authorities if necessary.

The GILs define acceptable water quality for various contaminants at the point of use and provide frequently used values for drinking water and protection of fresh water ecosystems. The GMRRW recommend applying a multiplication factor of 10 to 20 to the ADWG for assessment of the acceptability of recreational water quality. GILs for other receptors should be obtained directly from the 'primary industries' section of the AWQG where relevant. Note that the recreational and aesthetics sections of the AWQG have been superseded by the GMRRW.

## 7.0 Quality Assurance / Quality Control and Data Validation

The objective of the QA/QC will be to undertake methods and procedures of sample collection and analysis to be used to ensure quality, accuracy, precision and completeness of data generated. The primary focus is on the acquisition of environmental data that is scientifically sound and defensible and can be used to fulfill the overall project objectives. The following will be undertaken:

- The number of quality control samples to be collected and analysed is presented in Table 3 below. This is in accordance with the requirements of the Australian Standard AS4482.1.
- All samples will be analysed by NATA-accredited laboratories namely Eurofins and Envirolab. Each laboratory will follow internal quality control procedures, e.g. routine analysis of standard solutions / reference materials, reagent blanks, laboratory duplicates and spiked samples.
- The quality control program will consist of LRM submitting field duplicates and inter-lab split samples to a primary and secondary laboratory for analysis. The quality assurance program will also consisted of LRM submitting equipment rinsate and Trip blanks for analysis. These results will be used to gauge the potential for cross contamination during sampling and transportation.
- Relative Percent Differences will be calculated from Primary and Duplicate/Split samples to confirm repeatability of sample results.

***Table 3: QA/QC – Frequency of QA/QC Requirements***

| Quality Control Samples | Minimum Number of QA/QC Samples Required | Actual No. Required – LRM Assessment works | | Analytical suite |
|---|---|---|---|---|
| | | Soil | Groundwater | |
| Duplicate Sample | 1 in 20 | 2 | 1 | Metals, PAH(Soil), |
| Split Sample | 1 in 20 | 2 | 1 | Metals, PAH(Soil) |
| Rinsate Blank | 1 / equipment / day | 2 | 1 | TRH/BTEX |
| Trip Blank | 1/day/ eskie | 2 | 1 | BTEX |

Following completion of the field programs, all of the information collected will be checked, data will be collated, calculations completed and results summarised in tabular form.

## 9.0 CLOSURE AND COSTINGS

All works inclusive of service scanning, surveying, drilling, groundwater well installation, soil sampling, well development, groundwater sampling, NATA laboratory analysis, data tabulation, figures and reporting for auditor review.

I trust this Sample Analysis Plan is in line with your expectations. If you have any suggestions or inclusions that are required as part of these fieldworks, please do not hesitate to contact me on 04111 477 22.

Yours faithfully,
**LRM GLOBAL PTY LTD**



**Jon Lawson**
**Environmental Consultant**

# FIGURES:




| | | | | |
|---|---|---|---|---|
| **Preliminary Environmental Site Assessment** | | **Address:** 266 Longueville Road Lane Cove | | |
| Prepared for:<br>**Australian Unity Limited P/L** | Prepared by**:**<br>**LRM Global Pty Ltd** | **Figure 1 – Proposed GW Locations** | Date: **19/02/2018** | Source: NearMap |